


U. S.
OFFICIAL GAZETTE
UNITED STATES
PATENT OFFICE

VOL 886

MAY

1971

MICRO PHOTO DIVISION



BELL & HOWELL

J

OFFICIAL GAZETTE of the UNITED STATES PATENT OFFICE

May 4, 1971

Volume 886

Number 1

CONTENTS

Issue of May 4, 1971	1
Patent Notices	
Certificates of Correction for the Week of May 4, 1971	2
Service by Publication	2
Patents Available for Licensing or Sale	2
Condition of Patent Applications	3
Defensive Publications	4
Patents Granted	
Electrical	7
Chemical	75
General and Mechanical	132
Design Patents Granted	198
Index of Patentees	PI 1
Indices of Applicants of Defensive Publications and Designs	PI 28
Classification of	
Patents	PI 31
Designs and Defensive Publications	PI 32
Geographical Index of Residence of Inventors	
Patents	PI 33
Designs and Applicants of Defensive Publications	PI 34

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENTS SECTION), issued weekly, subscription \$89.00 per annum, foreign mailing \$22.25 additional; single copies \$2.00 each.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$17.00 per annum, foreign mailing \$4.25 additional; single copies 40 cents each.

CIRCULARS OF GENERAL INFORMATION concerning PATENTS or TRADEMARKS, price 15 cents each.

PRINTED COPIES OF PATENTS are furnished by the Patent Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS and DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents, Washington, D.C., 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S. Code P.O.

PATENT OFFICE NOTICES

Certificates of Correction for the Week of May 4, 1971

Re. 26,749	3,531,885	3,544,966	3,551,425
Re. 27,016	3,532,756	3,545,520	3,551,835
D. 219,319	3,532,972	3,546,018	3,551,848
3,333,484	3,533,286	3,546,184	3,552,468
3,375,187	3,533,959	3,546,736	3,552,910
3,417,084	3,534,265	3,546,913	3,553,126
3,443,219	3,535,936	3,547,534	3,553,546
3,472,038	3,535,965	3,547,815	3,553,671
3,472,225	3,537,834	3,548,348	3,554,794
3,476,605	3,539,123	3,548,382	3,554,989
3,477,432	3,539,465	3,548,780	3,555,020
3,496,241	3,539,739	3,548,823	3,555,078
3,496,243	3,539,776	3,549,534	3,555,530
3,499,382	3,541,040	3,549,546	3,556,305
3,505,287	3,541,887	3,549,638	3,557,012
3,510,516	3,541,906	3,549,851	3,557,111
3,510,635	3,542,117	3,550,583	3,557,611
3,512,484	3,542,756	3,551,087	3,558,291
3,516,375	3,543,943	3,551,186	3,558,563
3,520,398	3,544,439	3,551,263	3,558,572
3,521,543	3,544,495	3,551,380	3,559,654
3,527,704	3,544,530	3,551,407	3,560,209
3,531,326	3,544,690	3,551,409	3,560,309

Service by Publication

Elmer J. Knize

In accordance with Rule 47 of the Rules of Practice of the United States Patent Office in Patent Cases, Notice is hereby given of the filing on June 16, 1969, of an application for patent entitled "Dispenser With Cup Supporting Bristles," on behalf of Elmer J. Knize, whose last known address is 4049 West 31st Street, Chicago, Illinois. The application was made in compliance with Rule 47(a) and 35 U.S.C. 116 by Howard W. Johnson and Giacinto C. D'Ercole without execution by the said Elmer J. Knize.

Any action to be taken by the said Elmer J. Knize in connection with the said application must be taken within thirty days of the publication of this notice.

RICHARD A. WAHL,
Assistant Commissioner of Patents.

Patents Available for Licensing or Sale

3,191,513. FOLDING BELLOWS WITH INTERLOCKING CORNERS FOR PHOTOGRAPHIC DEVICES. Correspondence to: Central Trust Company Rochester N.Y., 44 Exchange St., Rochester, N.Y., 14614. Attn.: William K. Sjea, asst. vice pres.

3,389,561. METHOD OF AND APPARATUS FOR PROVIDING ANCHORS IN EARTH AND/OR ROCK FORMATIONS. Kenneth R. Taylor, P.O. Box 2185, Renton, Wash., 98055.

3,462,008. STORAGE AND HANDLING OF CHEMICAL SUBSTANCES. FEB, Limited, Manchester, England. Correspondence to: Michael S. Striker, 360 Lexington Ave., New York, N.Y., 10017.

3,519,250. STORAGE AND HANDLING OF CHEMICAL SUBSTANCES. FEB, Ltd., Manchester, England. Correspondence to: Michael S. Striker, 360 Lexington Ave., New York, N.Y., 10017.

3,535,667. ELECTRICAL SAFETY DEVICE. Henry C. Harnish, Jr., and Anthony J. Osello, Elcock Ave., Boonton, N.J. 07005.

3,549,035. FORK ASSIST. Donald W. Soper, Cross St., Orland, Maine, 04472.

3,552,388. BABY PATTING MACHINE. Thomas N. Zelenka, 205 S. Lemoore Ave., Lemoore, Calif., 93245.

3,557,999. PUSH-BUTTON SELF-OPENER CAN. Pedro Chagoyen, 81—07 25th Ave., Jackson Heights, N.Y., 11370.

3,559,305. GRADE AVERAGING DEVICE. Clyde S. Mundell, R.D. 1, Box 107, Carmichaels, Pa.

3,559,565. BARBEQUE GRILL. Clarence A. Getz, P.O. 316, Davenport, Wash., 99122.

3,559,339. COLLAPSIBLE PLANT STAKE ASSEMBLY. Robert W. Worley, 426 S. Clifton, Wichita, Kans., 67218.

3,560,015. COMBINED WHEEL AND PACK CARRIER. Lee J. Tracy, 629 8th St., Ogden, Utah, 84404.

3,560,047. FOLDABLE PORTABLE CHAIR WITH LIQUID DISPENSER. John Davis, 1200 La Cruz, El Paso, Tex., 79902.

3,563,159. ROTISSERIE. Martha Johnson, Huntington, W. Va. Correspondence to: Sherman Levy, Suite 602, Victor Bldg., 724 9th St. NW., Washington, D.C., 20001.

3,564,309. DATA STORAGE AND QUICK RETRIEVAL UNIT. Correspondence to: Sherman Levy, Suite 602 Victor Bldg., 724 9th St. NW., Washington, D.C., 20001.

The following 3 patents are offered by: John W. Barnd, 32 Gollybrook Road, Paramus, N.J.

3,351,128. MULTI-ZONE TEMPERATURE CONTROL.

3,496,991. FLUID TEMPERATURE REGULATING METHOD AND APPARATUS.

3,515,345. MULTI-ZONE TEMPERATURE CONTROL.

The following 4 patents are offered by: Joseph A. Vriend, P.O. Box 505, Squamish, British Columbia, Canada.

3,205,487. PORTABLE VISUAL SIGNAL DEVICE FOR GIVING VISUAL MORSE CODE SIGNALS.

3,361,487. PULSATING BRAKE.

3,415,334. HYDRAULIC DRIVE FOR MOTOR VEHICLES.

3,574,293. ANTI-KNOCK BEARING DEVICE.

General Electric Company is prepared to grant non-exclusive licenses under the following 10 patents upon reasonable terms to domestic manufacturers.

Applications for license under the following patent may be addressed to: Patent Counsel, General Electric Company, Bldg. 1, Electronics Park, Syracuse, N.Y., 13201.

3,122,610. CIRCUITRY FOR MULTIPLEX TRANSMISSION OF FM STEREO SIGNALS WITH PILOT SIGNAL.

Applications for license under the following patent may be addressed to: Patent Counsel, Telecommunication Products Dept., General Electric Company, Lynchburg, Va., 24502.

3,197,167. MOUNTING CLIP FOR POT CORE.

Applications for license under the following 2 patents may be addressed to: Division Patent Counsel, Power Transmission Division, General Electric Company, 6901 Elmwood Ave., Philadelphia, Pa., 19142.

3,546,407. VACUUM-TYPE CIRCUIT INTERRUPTER.

3,553,354. ALTERNATING CURRENT CIRCUIT BREAKER HAVING A CONTROL FOR TIMING OPENING RELATIVE TO THE CURRENT WAVE.

Applications for license under the following 3 patents may be addressed to the Patent Counsel, Communication and Control Device Products Dept. General Electric Co., Waynesboro, Va., 22980.

3,346,874. POWER CONTROL CIRCUITS.

3,553,612. MINIATURE RELAY WITH DOUBLE AIR GAP MAGNETIC CIRCUIT.

3,554,338. TWO-DIRECTIONAL ROTATION CLUTCH ASSEMBLY.

Applications for license under the following 3 patents may be addressed to the Division Patent Counsel, General Electric Co., Space Division, P.O. Box 8555, Philadelphia, Pa., 19101.

3,549,436. LAYERED PROPELLANT COMPOSITION CONSISTING OF AN ELECTRICAL CONDUCTOR AND AN INSULATOR.

3,551,111. REACTION-EXTRACTION AND ANALYSIS CHAMBER AND RELATED EQUIPMENT.

3,554,669. ELECTRICFLUID ENERGY CONVERTER.

PATENT EXAMINING CORPS

R. A. WAHL, Assistant Commissioner
F. H. BRONAUGH, Deputy Assistant Commissioner

CONDITION OF PATENT APPLICATIONS AS OF APRIL 20, 1971

PATENT EXAMINING GROUPS

	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—M. STERMAN, Director.....	12-01-69
Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	
GENERAL ORGANIC CHEMISTRY, GROUP 120—I. MARCUS, Director.....	8-22-69
Heterocyclic; Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—L. J. BERCOVITZ, Director.....	2-04-70
Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Natural Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g.: Coating; Molding; Ink; Adhesive and Abrading Compositions; Molding, Shaping, and Treating Processes.	
COATING AND LAMINATING, BLEACHING, DYEING AND PHOTOGRAPHY, GROUP 160—A. P. KENT, Director.....	1-26-70
Coating; Processes and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; Bleaching; Dyeing and Photography.	
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—W. B. KNIGHT, Director.....	10-03-69
Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS AND RELATED ELEMENTS, GROUP 210—N. ANSHER, Director.....	8-17-70
Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Miscellaneous.	
SECURITY, GROUP 220—R. L. CAMPBELL, Director.....	12-01-69
Ordnance, Firearms and Ammunition; Radar, Underwater Signalling, Directional Radio, Torpedoes, Seismic Exploring, Radio-Active Batteries; Nuclear Reactors, Powder Metallurgy, Rocket Fuels; Radio-Active Material.	
INFORMATION TRANSMISSION, STORAGE AND RETRIEVAL, GROUP 230—J. F. COUCH, Director.....	3-02-70
Communications; Multiplexing Techniques; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—W. L. CARLSON, Director.....	3-03-70
Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	
PHYSICS, GROUP 280—R. L. EVANS, Director.....	1-05-70
Photography; Sound and Lighting; Indicators and Optics; Measuring and Testing; Geometrical Instruments.	
DESIGNS, GROUP 290—R. L. CAMPBELL, Director.....	6-03-70
Industrial Arts; Household, Personal and Fine Arts.	
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—A. BERLIN, Director.....	1-23-70
Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet and Web Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Railways and Railway Equipment; Brakes; Rigid Flexible and Special Receptacles and Packages.	
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—D. J. STOCKING, Director.....	12-10-69
Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion—Bonding, Metal Founding; Metallurgical Apparatus; Plastics Working Apparatus; Plastic Block and Earthenware Apparatus; Machine Tools for Shaping or Dividing; Work and Tool Holders Woodworking; Tools; Cutlery; Jacks.	
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—A. RUEGG, Director.....	1-02-70
Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Butchering; Earth Working and Excavating; Fishing, etc.; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Trolley; Printing; Typewriters; Stationery; Information Dissemination.	
HEAT, POWER AND FLUID ENGINEERING, GROUP 340—C. F. GAREAU, Director.....	5-07-70
Power Plants; Combustion Engines; Fluid Motors; Pumps; Turbines; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Vaporizing; Temperature and Humidity Regulation; Machine Elements; Power Transmission; Fluid Handling; Lubrication; Joint Packing.	
CONSTRUCTIONS, SUPPORTS, TEXTILES, CLEANING, GROUP 350—T. J. HICKEY, Director.....	1-06-70
Joints; Fasteners; Rod, Pipe and Electrical Connectors; Miscellaneous Hardware; Locks; Building Structures; Closure Operators; Bridges; Closures; Earth Engineering; Drilling; Mining; Furniture; Receptacles; Supports; Cabinet Structures; Centrifugal Separations; Cleaning; Coating; Pressing; Agitating; Foods; Textiles; Apparel and Shoes; Sewing Machines; Winding and Reeling.	

Expiration of patents: The patents within the range of numbers indicated below expire during May 1971, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 70th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents..... Numbers 2,677,129 to 2,679,644, inclusive
Plant Patents..... Numbers 1,274 to 1,281, inclusive

DEFENSIVE PUBLICATIONS

PUBLISHED MAY 4, 1971

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O.G. 687. The abstracts of Defensive Publication applications are identified by distinctly numbered series and are arranged chronologically. The heading of each abstract indicates the number of pages of specification, including claims and sheets of drawings contained in the application as originally filed. The files of these applications are available to the public for inspection and reproduction may be purchased for 30 cents a sheet.

Defensive Publication applications have not been examined as to the merits of alleged invention. The Patent Office makes no assertion as to the novelty of the disclosed subject matter.

T886,001


HYDROKINETIC POWER TRANSMISSION SYSTEM WITH A SUBSTANTIALLY IDEAL FUNCTIONAL RELATIONSHIP BETWEEN OUTPUT SPEED AND TRACTIVE EFFORT

Martin G. Gabriel, Dearborn, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Continuation-in-part of application Ser. No. 518,853, Jan. 5, 1966. This application May 20, 1968, Ser. No. 738,368

Int. Cl. F16h 47/00
U.S. Cl. 74-732

4 Sheets Drawing, 13 Pages Specification



This specification describes a hydrokinetic torque converter transmission having an increased low speed torque ratio in geared portions of the mechanism and having a bladed stator of variable geometry in the torque converter portion of the mechanism. The individual stator blades are mounted on rotatable stator blade shafts which can be rotated to effect angular adjustment of the stator blades by means of a rack-and-pinion servo. An increased degree of deflection of the toroidal fluid flow in the stator region of the circuit is obtained as the converter speed ratio increases thereby providing an overall torque ratio characteristic that approaches a theoretical, ideal performance.

T886,002

PREPARATION OF ORIENTED FOAM LAMINAR STRUCTURES

Leon Edward Wolinski, Buffalo, N.Y., and Roland G. Harris, Chadds Ford, Pa., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

Continuation-in-part of application Ser. No. 848,206, Aug. 7, 1969. This application Sept. 26, 1969, Ser. No. 861,467

Int. Cl. C09j 5/00
U.S. Cl. 156-311

No Drawing, 8 Pages Specification

Process for the preparation of film-foam laminar structures substantially free from warp which comprises maintaining the laminar structure in a flat configuration after lamination while cooling the structure below the distortion temperature of the foam. In a preferred embodiment the foam sheet is an oriented closed cell foam consisting essentially of styrene polymer. The preferred films are of polyvinyl chloride and polypropylene.

T886,003

GAUGE CONTROL OF FOAM STRUCTURES

Leon Edward Wolinski, Buffalo, N.Y., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed Sept. 26, 1969, Ser. No. 861,477
Int. Cl. B29d 27/00; B32b 5/18; C08f 7/04

U.S. Cl. 264-51

No Drawing, 12 Pages Specification

Process for the treatment of thermoplastic closed cell foam structures by:

- Heating the structure to at least the second order transition temperature of the foam and below the temperature at which the foam undergoes cellular collapse,
- Compressing the foam structure to a thickness less than the nominal thickness of the foam structure and greater than the thickness determined according to the formula:

$$T = AB/C$$

wherein T is the desired minimum thickness, A is the density of the foam prior to treatment, B is initial nominal thickness of the foam, and C is the density of the unfused polymer, and

- Expanding the foam structure substantially free from restraint until the temperature of the foam structure is below the second order transition temperature.

T886,004

PURIFICATION OF DIPOTASSIUM TEREPHTHALATE

Erdem M. Atadan, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed Dec. 4, 1969, Ser. No. 882,281
Int. Cl. C07c 51/42

U.S. Cl. 260-525

No Drawing, 7 Pages Specification

Purified dipotassium terephthalate is recovered from crude aqueous dipotassium terephthalate solution containing potassium para-toluic acid as an impurity by crystallizing dipotassium terephthalate in an amount such that the weight ratio of potassium para-toluic acid to dipotassium terephthalate remaining in the aqueous solution does not exceed the potassium para-toluic acid to dipotassium terephthalate weight ratio at which potassium para-toluic acid will begin to crystallize, followed by separating the dipotassium terephthalate crystals from the aqueous solution, preferably by filtration. The crude aqueous solution of dipotassium terephthalate can be prepared either by dissolving crude terephthalic acid in a potassium alkaline aqueous solution, e.g., aqueous potassium hydroxide, or directly from the oxidation of para-xylene or para-toluic acid in a potassium alkaline aqueous medium. The crystallization is conducted at about from 0° to 160° C., preferably about from 10 to 140° C., and at about from 0.1 to 10, preferably about from 0.5 to 4, atmospheres of total pressure. The dipotassium terephthalate can then be washed with any solvent which is chemically inert with respect to the dipotassium terephthalate, preferably a nearly saturated aqueous solution of dipotassium

MAY 4, 1971

U. S. PATENT OFFICE

5

terephthalate, to displace any remaining mother liquor. Purified terephthalic acid can then be recovered by acidifying an aqueous solution of the purified dipotassium terephthalate.

T886,005

PRINTING INKS

Leon Edward Wolinski, Buffalo, N.Y., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed Dec. 17, 1969, Ser. No. 886,032
Int. Cl. C08h 9/00; C09d 3/26, 11/06

U.S. Cl. 106-27

No Drawing, 6 Pages Specification

A fast-drying printing ink useful in commercial lithographic printing and particularly useful in printing folded cartons and the like.

The ink comprises:

- a pigment;
- about 5-33 percent of an organic acid having from 8-20 carbon atoms and at least one set of conjugated double bonds such as an α or β form of oleostearic acid or a mixture of organic acids such as China oil;
- about 1.5-20 percent of a drying composition such as a solution of cobalt salts of aliphatic acids having from 4-40 carbon atoms, preferably C_8-C_{10} for an optimum balance of properties and particularly preferred is a 12 percent solution of a cobalt salt complex of a branched C_{10} aliphatic acid; and
- up to about 30 percent plasticizer such as an ether phthalate selected from bis(2-ethoxyethyl) phthalate, bis(2-methoxyethyl) phthalate, butyl benzyl phthalate.

T886,006

LINEAR FOUR-QUADRANT MULTIPLIER


Daniel R. Nichols, 302 John Ave.,
Linthicum Heights, Md. 21090

Filed Apr. 15, 1970, Ser. No. 28,679

Int. Cl. G06g 7/12

U.S. Cl. 307-229

2 Sheets Drawing, 16 Pages Specification



A circuit for multiplying two voltages together. The output is a voltage which is proportional to the product of the two voltages and whose sign is directly related to the signs of each of the input voltages. Even though non-linear elements are used, such as transistors, the final output voltage varies linearly with each of the input voltages. An AC voltage (2) is an input to a high gain amplifier (1). A DC voltage (70) is an input to a high gain operational amplifier (68). The two amplifiers are interconnected by a DC bridge and an AC bridge. Initially, both bridges are balanced. A change in the DC voltage momentarily unbalances the output of the DC bridge. The high gain of the operational amplifier (68) provides a degenerative feedback voltage to control the multiplying ampli-

T886,007

APPARATUS FOR DETECTING OVERSIZE DEFECTS IN YARN


John Vipond Harvey, 36 Campbell Crescent; Bruce Alexander Robinson, 3 Holland Crescent; and John William Stassen, 155 Division St., all of Kingston, Ontario, Canada

Filed May 4, 1970, Ser. No. 34,167

Int. Cl. G01n 19/08

U.S. Cl. 73-160

2 Sheets Drawing, 6 Pages Specification



A device for detecting oversize defects in yarns or filaments comprising a slotted flexible guide 12 having a strain gauge 19 mounted thereon. The yarns or filaments 10 are passed through the slot 11 and a defect in the yarns or filaments causes the guide to deflect a distance according to the size of the defect. The deflection produces a signal from the strain gauge which is fed to a discriminator that compares the magnitude of the signal with a preset level and eliminates signals from small defects. The device is particularly adaptable in solvent spinning of synthetic fibers for detecting oversize filaments, and polymer drips.

T886,008

DRAWING BOARD

James E. McConkey, 901 Elmgrove Road,
Rochester, N.Y. 14624

Filed June 8, 1970, Ser. No. 44,462

Int. Cl. A47b 27/00, 63/04

U.S. Cl. 312-23

1 Sheet Drawing, 6 Pages Specification



A drawing board is provided with a workface, an underface and a tray for holding drawing utensils or the like. The tray is arranged with respect to the workface so that a sheet of drawing paper supported on such workface, when overlapping an edge of the drawing board, will be partially disposed in such tray. A slot in the tray is of dimensions suitable for passage therethrough of the supported drawing sheet and communicates with a chamber located on the underface of the drawing board. Accordingly, a draftsman may remain seated at the drawing board and work on all areas of the supported sheet by feeding such sheet through the tray slot and into and out of the chamber.

T886,009

TRANSMISSION CABLES

David E. Hoiness, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
 Filed July 15, 1970, Ser. No. 55,030


Int. Cl. H01b 9/06

U.S. Cl. 174—25

1 Sheet Drawing. 10 Pages Specification

A cable for the high voltage transmission of electrical power which is composed of a conductive wire wrapped with several layers of insulative and shielding materials. One such insulative material in an oil impregnated paper in which the oil is a cable oil and the paper is composed of a mixture of aromatic polyamide fibrils and fibers

(e.g., fibrils and fibers of a wholly aromatic polyamide such as poly(meta-phenylene isophthalamide). The cables



have low electrical loss properties due to the low dissipation loss factor and the good dielectric strength of the above-identified paper.

PATENTS

GRANTED MAY 4, 1971

ELECTRICAL

3,576,936

ASSEMBLY KIT

Artur Fischer, Grunmetterstr 133, Tumligen, Germany

Filed Jan. 16, 1969, Ser. No. 791,748


Claims priority, application Germany, Jan. 24, 1968, P16 78

334.9


Int. Cl. G09b 23/18

U.S. Cl. 35—19A

7 Claims



the compression forces which occur when the two parts are bolted together, squeeze the gaskets together to force them



to expand and fill all of the available space within the housing parts and around the cables.

ERRATUM

For Class 174—128 sec:
 Patent No. 3,577,151

3,576,938

ELECTRICAL INSULATOR WITH POLYMER-CONTAINING JOINT BETWEEN THE PORCELAIN AND THE HARDWARE


Frank A. Capotosto, Newtown Square, Pa., and Robert V. Klint, Woodstown, N.J., assignors to General Electric Company

Filed Nov. 7, 1969, Ser. No. 874,853

Int. Cl. H01b 17/14, 17/38

U.S. Cl. 174—196

6 Claims



3,576,937
 UNDERGROUND RIGID CONNECTOR HOUSING SEAL
 Raymond W. Eldridge, Jr., St. Louis, Mo., assignor to International Telephone & Telegraph Corporation, New York, N.Y.

Filed Dec. 26, 1968, Ser. No. 787,098

Int. Cl. H02g 15/08

U.S. Cl. 174—92

4 Claims

An underground connector housing for large diameter power lines is enclosed within a split housing comprised of upper and lower Fiberglas reinforced plastic shells. These shells have entrance and exit ports for receiving the power cables which are connected together inside the housing. Gaskets seal the housing by following the contours of the mating surfaces on each shell of the Fiberglas housing. At the ports, the gaskets are increased slightly in thickness. Hence,

Discloses an electrical insulator that comprises an improved joint for attaching the insulator hardware to the porcelain body of the insulator. The porcelain has a roughened surface, and the joint comprises a thin release coating of

solid polymeric material on the roughened surface, a thicker coating of a polymer filled with a dry lubricant overlying the release coating but unbonded thereto, and a filled polymer in the space between the hardware and thicker coating that is bonded to both the thicker coating and the hardware. The release coating prevents the thicker coating from adhering to the roughened surface of the porcelain but is so thin that the thicker coating is still able to mechanically interlock with the roughened surface.


3,576,939

ELECTRICAL CABLES AND METHOD OF MAKING SAME

Gerhard Karl Ziemek, Hannover, Germany, assignor to Kabel-und Metallwerke Gutehoffnungshutte Aktiengesellschaft, Hannover, Germany
Filed Oct. 9, 1969, Ser. No. 864,984
Int. Cl. H01b 7/18

U.S. Cl. 174-107

10 Claims



Electrical cables having an outer shielding element of thin metal tape; the tape being shaped into tubular form about the cable core and having a longitudinal seam; the seam having marginal tab portions integral with the tape and in face-to-face contact, the outer edges of the tab portions being metallically integrated to provide electrical conductivity continuously about the circumference thereof and to form a fluid-imperious envelope for the core which is resistant to mechanical stresses.


3,576,940

FLAME-RETARDANT WIRE AND CABLE

John G. Stone, North Haven; George S. Buettner, and Christian A. Alm, Cheshire, Conn., assignors to Cerro Corporation, New York, N.Y.
Filed Dec. 3, 1968, Ser. No. 780,644
Int. Cl. H01b 7/28

U.S. Cl. 174-113

19 Claims



An electrical conductor or cable, capable of maintaining electrical integrity when exposed to open flame temperatures of 1000° F. without propagating a fire or resulting in falling burning particles or generating large volumes of smoke. The conductor or cable of this invention is comprised of a metallic conductor or plurality of conductors covered by a layer of primary insulation. Such conductors are then covered by a layer of silicone rubber which is, in turn, covered by a layer of glass fiber. The layer of glass fiber may then be covered by

another layer of silicone rubber which is, in turn, covered by a layer of braided asbestos impregnated with an intumescent material. In the alternative, the second layer of silicone rubber may be covered by an asbestos tape which is then covered by a layer of elastomeric material having fire-retardant properties.


3,576,941

FLAT POWER-DISTRIBUTION CABLE

Donald F. Colglazier, Rochester, Minn., assignor to International Business Machines Corporation, Armonk, N.Y.
Continuation-in-part of application Ser. No. 696,595, Jan. 9, 1968, now abandoned. This application Aug. 6, 1969, Ser. No. 847,937
Int. Cl. H01b 7/08

U.S. Cl. 174-117

15 Claims



A flat cable for distributing electrical power between hingeable or demountable pieces of electrical apparatus is made up of thin, flat conductors nonrigidly mounted one on top of the other. The nonrigid mounting of the conductors relative to each other permits one to slip or slide relative to the other and thereby improve flexure of the cable and also increase the number of flexures the cable can be cycled through before it fails. Nonrigid mounting can be achieved by several different configurations. First, each flat conductor can be provided with its separate insulating layer and then the two insulated conductors may be held one over the other loosely so that they may slide or slip relative to each other. Second, a flat insulating cable may have a partition across its width so that one flat conductor may be placed in one partitioned section and the other flat conductor may be placed under the other conductor in the second partitioned section. Third, separately insulated conductors may be taped together at spaced locations so as to allow each conductor to slide within its own insulation and to allow relative movement of the conductors between the spaced locations.

3,576,942

ELECTRIC INSULATORS WITH SPIGOTING ELEMENTS


Thomas Caldor, Saint-Yorre, Allier, France, assignor to Societe Sediver, Societe Europeenne d'Isolateurs en Verre, Paris, France
Filed May 20, 1969, Ser. No. 826,244
Claims priority, application France, May 22, 1968, 152,792
Int. Cl. H01b 17/14, 17/66, 19/00

U.S. Cl. 174-210

6 Claims

A method and apparatus for developing a column, which column comprises a plurality of substantially conical elements supporting one another in a spigoting arrangement, one seated in the other. The elements are connected to one another by a substance such as mortar. The walls of the elements are shaped such that when mortar is introduced in a

controlled manner into one of the elements, there is a controlled discharge of the temporarily fluidized mortar along horizontal and vertical field-of-view of the instrument. A detector produces a video signal which can be displayed on an



the ducts of prescribed contour constituted by the opposing wall surfaces of an adjacent interfitted element.


3,576,943

COLOR TELEVISION MIXING ARRANGEMENT

Hans-Dieter Schneider, Gross-Gerau, Germany, assignor to Fernseh G.m.b.H., Darmstadt, Germany
Filed Aug. 30, 1968, Ser. No. 756,671
Claims priority, application Germany, Aug. 31, 1967, P 15 37 117.2
Int. Cl. H04n 9/32

U.S. Cl. 178-5.4

8 Claims



An arrangement in the transmission of color television. Color component signals are applied to amplifiers which, in turn, provide outputs mixed with the luminance signal component. The mixing is performed in a network of summing resistors. Each of the color component signals is mixed with a luminance signal component such that the latter has an amplitude which varies inversely with the amplitude of the luminance signal.

3,576,944


SCANNING RADIOMETER WITH PLURAL REFERENCE SOURCES

Kenneth B. LaBaw, China Lake, Calif., assignor to the United States of America as represented by the Secretary of the Navy
Filed Jan. 28, 1969, Ser. No. 794,512
Int. Cl. G01j 5/52; H04n 3/08, 7/18

U.S. Cl. 178-6.8

10 Claims

A scanning radiometer for producing long wave length infrared photographs and radiometric measurements. The instrument provides a raster type area scan by varying the



oscilloscope and recorded with a camera to produce an area scanned picture.


3,576,945

APPARATUS FOR OPTICALLY INSETTING ONE IMAGE INTO ANOTHER IMAGE

William C. Ebeling, Binghamton, N.Y., assignor to Singer-General Precision, Inc., Binghamton, N.Y.
Filed Mar. 24, 1969, Ser. No. 809,732
Int. Cl. H04n 1/38, 5/24

U.S. Cl. 178-6.8

7 Claims



Apparatus is provided for inseting one image optically into a portion of another image. The apparatus includes two separate image generation and projection systems. A beam splitter combines the two images for projection onto a single viewing screen. One image projection system includes a field lens having one surface comprising an electroplastic film. A cathode ray is caused to sweep those portions of the film which represent the portion to be insetted by the other image. A TV camera system controls the generation of the cathode beam in response to an image projected through the beam splitter onto the TV camera. The portions of the film struck by the beam effectively occult corresponding portions of one image. The other image occupies the occulted portion.

ERRATUM

For Class 178-7.1 see:
Patent No. 3,577,200

3,576,946

POWER SUPPLY PROTECTION CIRCUIT UTILIZING A SILICON CONTROLLED RECTIFIER


Kenneth Frizane, Elmwood Park, Ill., assignor to Zenith Radio Corporation, Chicago, Ill.

Filed Jan. 3, 1969, Ser. No. 788,858

Int. Cl. H04n 5/44

U.S. Cl. 178-7.3

4 Claims



A control circuit for preventing the application of accelerating potential in excess of a predetermined maximum value to the cathode-ray picture tube of a television receiver. Positive polarity pulses amplitude-related to the applied accelerating potential are derived from the receiver horizontal deflection system and impressed across the emitter-base junction of a transistor. The base of this transistor is biased at a DC level such that the impressed pulses will exceed the breakdown potential of the junction when the accelerating potential exceeds its maximum value. When this occurs a control voltage is applied by the transistor to the control electrode of a silicon controlled rectifier (SCR) which has principal electrodes connected between the screen of the horizontal deflection system output tube and ground. This causes the SCR to conduct, substantially reducing the screen current applied to the output tube and hence the energy available for powering the receiver's sweep-excited high voltage power supply, and preventing further generation of excessive accelerating potential. To prevent the receiver from being rendered inoperative by a transient overload condition, a capacitor couples pulses from the output circuit of the receiver vertical deflection system to the screen of the horizontal output tube to periodically reduce the quiescent current through the principal electrodes following an over-voltage condition to a value below the minimum holding current required to sustain conduction, thereby restoring the SCR to a nonconductive state and the high voltage power supply to an operative state. During a sustained overvoltage condition the control circuit causes the receiver to alternate between operative and nonoperative states, which "blinking" action on the receiver viewing screen effectively indicates a malfunction.

3,576,947

RAPID FRAME SYNCHRONISM OF SERIAL BINARY DATA

Lawrence W. Kruger, Newbury Park, Calif., assignor to the United States of America as represented by the Secretary of the Navy

Filed Jan. 16, 1969, Ser. No. 791,685


Int. Cl. H04n 1/32

U.S. Cl. 178-69.5

7 Claims

A circuit means of detecting the synchronizing word in not more than two frames of serial binary information data having the serial data clocked through a shift register sync window and alternate gates for the sync word and its complement to a pair of frame bit shift registers to store the serial data for comparing consecutive frames for the sync word and

its complement to produce an output signal after two consecutive frames of input data, any miss of sync word detection in two frames causing circuit switching to reset the circuit means for subsequent detection of the sync word.



tion in two frames causing circuit switching to reset the circuit means for subsequent detection of the sync word.

ERRATUM

For Class 179-2 see:
Patent No. 3,577,201

3,576,948

SYSTEM FOR RECORDING HIGH FREQUENCY SIGNALS ON A RECORDER HAVING A LOWER FREQUENCY RESPONSE


Norman L. Stauffer, Englewood, Colo., assignor to Honeywell, Inc., Minneapolis, Minn.

Filed June 10, 1968, Ser. No. 735,723

Int. Cl. H04b 1/66

U.S. Cl. 179-15.55

6 Claims



A device is disclosed for recording high frequency signals on a lower frequency recorder. In accomplishing this, the high frequency signals are amplified and periodically stored in maximum and minimum storage devices. The stored maximum and minimum values of the high frequency signal are then sequentially applied through read amplifying circuitry to the lower frequency recorder which displays the signal retaining the amplitude thereof.

ERRATUM

For Class 179-15 see:
Patent No. 3,577,202

3,576,949

MULTISTAGE SWITCHING NETWORK EMPLOYING CASCADED THREE-TERMINAL CROSSPOINTS

Frans Corneel Leo DeWit, Mortsel, Belgium, and Hans Helmut Adelaar, Kapellenbos, Belgium, assignors to International Standard Electric Corporation, New York, N.Y.


Filed Jan. 18, 1968, Ser. No. 698,796

Claims priority, application Netherlands, Jan. 23, 1967, 6,701,051

Int. Cl. H04q 3/48

U.S. Cl. 179-18

7 Claims



A multistage relay crosspoint network is disclosed in which a connection is held operated through the windings of the relays, each in series with its make contact. In a four-stage connection the hold contacts of the 1st and 2nd as well as those of the 3rd and 4th stages are serially connected and such hold connections replace similar parallel ones involving marking contacts. The invention substantially reduces the number of marking relays needed to establish connections by having the windings of the 1st and 2nd as well as those of the 3rd and 4th stages on the same side and by selecting, through access relay contacts, the desired crosspoints in the 1st and 3rd stages while marking rectifiers are used in the 2nd and 4th to enable bundles of marking wires to be selected in these stages in order to operate the desired crosspoints in these stages also.

3,576,950

SELF-SEEKING ELECTRONIC SWITCHING NETWORK


Nikola Ljotic Jovic, Chicago, Ill., assignor to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Oct. 29, 1968, Ser. No. 771,453

Int. Cl. H04q 3/50

U.S. Cl. 179-18

10 Claims



Primarily, this electronic switching network is used to enable the construction and operation of truly large scale networks without sacrificing the desirable aspects of self-seeking principles. In greater detail, a self-seeking current controlled network of PNP diodes (or similar devices) is divided, by general purpose diodes, into a plurality of electrically isolated sections. The isolation sets inherent limits on offensive fan-out currents and crosstalk, and it enables self-imposed node point priming. This is done by firing crosspoints at naturally occurring oscillation frequencies which inherently speedup as the self-selection process approaches the successful completion of a latched path. Initially the oscillation is at the naturally occurring cyclic firing frequencies of the end-marked diodes at either ends of the paths. At speedup, the oscillation becomes the entire path leaping back and forth between the end-marked points. Finally, the path selection process is completed when current flows over a completed path.

3,576,951

CALLING SUBSCRIBER IDENTIFICATION SYSTEM

Tomomi Uchida; Takeshi Kondo, Tokyo-to; Hiroshi Takada, Kawasaki-shi; Hiroaki Eguchi, Tokyo, and Kenichi Hasegawa, Yokohama-shi, Japan, assignors to Nippon Electric Company, Limited, Tokyo-to, Japan and Futsu Limited, Kawasaki, Japan, fractional part interest to each


Filed Dec. 4, 1968, Ser. No. 781,048

Claims priority, application Japan, Dec. 9, 1967, 42/78280

Int. Cl. H04m 3/42

U.S. Cl. 179-18

2 Claims



A calling subscriber identification system in an automatic telephone exchange system determines the telephone number of a calling subscriber upon the calling subscriber making a telephone call to a called subscriber. The telephone number of the called subscriber is determined. Subscriber-determining apparatus determines if the called subscriber is a specific subscriber in accordance with the telephone number of the called subscriber. A recorder records the telephone number of the calling subscriber when the subscriber determining means determines that a telephone connection is made between the calling subscriber and the specific subscriber as the called subscriber. Calling subscriber identifying apparatus determines and indicates from the recorder the telephone number of the calling subscriber upon a command signal from the called subscriber. The command signal is produced and transmitted to the calling subscriber identifying apparatus under the control of the called subscriber.

3,576,952

FORWARD ERROR CORRECTING CODE TELECOMMUNICATING SYSTEM

Hendrik Cornelis Anthony Van Duuren, Wassenaar, Voorburg, Netherlands, assignor to and De Staat Der Nederlanden, Ten Deze Vergegenwoordigd Door De Directeur, The Hague, Netherlands


Filed Jan. 6, 1969, Ser. No. 789,340

Claims priority, application Netherlands, Jan. 19, 1968, 6800871

Int. Cl. H04l 1/10

U.S. Cl. 178-23.1

11 Claims



A multielement code telecommunication system comprising first converting each code signal into a constant ratio 1-bit/0-bit signal, storing a predetermined successive number of such converted code signals in shift registers to form a group.

and forming a test signal by modulo 2 adding the bits in said group of signals which test signal is transmitted with and after each said group to form a block of signals; receiving and storing in shift registers each signal in said group, testing each signal as it is received and if one and only one signal in said group is found mutilated or erroneous, clearing the shift register in which that erroneous signal is stored and reconstructing therein the correct signal from said test signal and the other correctly received signals in that group; and lastly reconvert said correct group of signals and transferring them from printing registers successively to a printer.

3,576,953


MAGNETIC TAPE INFORMATION STORAGE DEVICE
Werner Hauer, Sayre, Pa., assignor to Neo Dynamics, Inc.,
Irvington, N.J.

Filed July 3, 1968, Ser. No. 742,226

Int. Cl. G11b 5/76, 25/02

U.S. Cl. 179-100.2

7 Claims



An information storage device includes a rotatable drum having an anchoring element spaced from the periphery thereof. A magnetic recording tape extends around the periphery of the drum and has a tail engaging the anchoring element to provide a free path between the tape and the drum periphery for the reception of a spring biased member which urges the tape into sliding engagement with the opposing face of a magnetic transducer. In one form the drum is provided with a separable end plate provided with a pair of closely peripherally spaced longitudinal legs, and the tape is in the form of an endless ring looped about the leading and trailing edges of respective legs.

3,576,954

**METHOD OF LOW POWER BIAS, LOW DISTORTION
MAGNETIC RECORDING**


Edward C. Sand, Willoughby, Ohio, assignor to Clevite Corporation

Filed Sept. 16, 1968, Ser. No. 759,842

Int. Cl. G11b 5/02, 5/44

U.S. Cl. 179-100.2

5 Claims



A method of magnetic recording is provided which utilizes an AC signal flux recorded in conjunction with DC bias flux which biases the magnetic tape to the knee portion of the remanent magnetization characteristic of the magnetic

record medium. By using two tracks in the same medium and suitable distribution of signals, the method provides low distortion overall although each individual track is severely distorted.

3,576,955

**ARMATURE ASSEMBLY FOR MAGNETIC-TYPE
PHONOGRAPH PICKUP**

Shuichi Obata, Kyoto, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Oaza Kadoma, Kadoma-shi, Osaka, Japan


Filed Aug. 16, 1968, Ser. No. 753,236

Claims priority, application Japan, Aug. 22, 1967, 42/72682; 42/72683

Int. Cl. H04r 1/112

U.S. Cl. 179-100.41M

3 Claims



An armature assembly for a magnetic-type phonograph pickup having a cord or wire which supports a stylus arm with a magnet mounted thereon, the armature, being supported by the aid of the bending of the cord or wire at one stable point to vibrate uniformly in every direction at that point; and a bearing member of elastic material the compression of which can be adjusted so that at the peak the resonant frequency of the output voltage can be damped, such that the frequency response characteristic of the output voltage can be flattened.

3,576,956

STEREOPHONIC PHONOGRAPH TRANSDUCER

Cornelis Lanooy, and Herbert Mensen, Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed May 20, 1959, Ser. No. 814,556

Claims priority, application Netherlands, June 20, 1958, 228,905

Int. Cl. H04r 1/112, 19/10

U.S. Cl. 179-100.41

6 Claims



A phonograph pickup, particularly for stereophonic recording and reproduction in which a body for converting movements of a stylus is suspended within a housing to be tiltable in all directions.

3,576,957

PANTOGRAPHS

Arnold Tustin, Tring, England, assignor to British Railways Board, London, England

Filed Feb. 6, 1969, Ser. No. 797,028

Int. Cl. B601 5/08


U.S. Cl. 191-60.3

11 Claims

This invention provides an arrangement for the supply of electric current to vehicles, which includes a servosystem providing compensation for inertial forces so as to maintain a

contact member in electrically conductive connection with a conductor extending along the length of a track along which a vehicle runs. The servosystem includes a slug whose inertia is utilized to effect variation of the pressure of a fluid acting

pressurizing piston. The float itself responds to the fluid level and an upper float travel limit is established in accordance with the piston position.



3,576,960

**FLANGE FASTENING MEANS FOR A CONTACT
BUTTON FOR A VACUUM-TYPE CIRCUIT
INTERRUPTER**


Donald R. Kurtz, Malvern, Pa., assignor to General Electric Company

Filed Mar. 8, 1968, Ser. No. 711,759

Int. Cl. H01h 33/66

U.S. Cl. 200-144

4 Claims



on a piston in a cylinder so as to cause the pressure of such fluid on said piston to vary in a manner which includes a component proportional to upward and downward accelerations of the contact member and in the same sense.

3,576,958

**SWITCHING DEVICE WITH IMPROVED TABLET
ACTUATOR MEANS**

Junji Ohno, Hamamatsu-shi, Japan, assignor to Nippon Gakki Seizo Kabushiki Kaisha, Hamamatsu-shi, Japan


Filed Feb. 27, 1969, Ser. No. 802,368

Claims priority, application Japan, Apr. 13, 1968, Apr. 17, 1968, Apr. 19, 1968, 43/29886; 43/30983; 43/31689

Int. Cl. H01h 9/00

U.S. Cl. 200-1

9 Claims



The switching device of a tablet type comprises a plurality of tablets each having bosses formed integrally on the surfaces of its sidewalls coaxially with bores formed in the tablets to receive an axis. The tablets are arranged on a base by passing the axis through said bores in such a manner that the bosses formed on two adjacent tablets face each other.

Contact structure for a vacuum-type circuit interrupter comprising a contact containing an annular groove surrounding an integral central boss. An annular contact-making button is fitted in the groove and is secured in place by deforming the outer periphery of the boss to define an integral lip extending radially outwardly from the boss, overlapping a radially inwardly projecting shoulder on the button, and tightly sandwiching the shoulder against the bottom of the groove.

3,576,961

**VACUUM SWITCH WITH OPERATING MEANS FOR
ARRESTING CONTACT IN AN INTERMEDIATE
POSITION BEFORE COMPLETE OPENING**


John L. Turner, East St. Louis, Ill., assignor to Turner Electric Corporation, East St. Louis, Ill.

Filed Aug. 2, 1968, Ser. No. 749,719

Int. Cl. H01h 33/66, 3/52

U.S. Cl. 200-144

11 Claims



3,576,959

BRAKE WARNING SWITCH


John P. Bogosoff, Battle Creek, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Nov. 4, 1969, Ser. No. 873,843

Int. Cl. H01h 35/18

U.S. Cl. 200-84

8 Claims



A vehicle brake system master cylinder assembly is provided with a switch assembly employing a float to monitor both fluid level in a reservoir and excessive travel of a fluid-

Mechanism for operating a load interrupter switch responsive to opening and closing movements of an air break switch or a plurality of the latter. The load interrupter switch contacts are enclosed in a vacuum bottle preferably, one contact being fixed and the other movable axially away therefrom to

open position and toward the fixed contact to closed position. The movable contact is biased toward open position and is normally held in closed position by a lever pivoted at one end and extending transversely of the direction of movement of the contact. The lever is normally maintained in the contact-closed position by a rotatable cam. A latch member extending transversely of the lever normally overlies one end of the lever and when the cam is rotated to permit initial movement of the lever the end of the latch becomes engaged with the end of the lever, permitting a slight initial opening movement of the lever and the associated contact for a period of two to three cycles. Further movement of the cam causes another projection on it to engage the latch, keeping it clear of the end of the lever and permitting the lever to move freely, thus freeing the contact to move under spring pressure to its full open position. This sequential opening of the contact permits harmless arcing to occur across the contacts within the vacuum bottles during initial opening of the contacts until the current reaches its zero value, thus avoiding interruption of the current at other than zero values and the consequent occurrence of high transient voltages.

ERRATUM

For Class 200—151 see:
Patent No. 3,576,967

3,576,962

PUSH CONTACT DEVICE

Jean-Pierre Edmond Nicolas, Nice, France, assignor to Legrand, Limoges, France


Filed Dec. 5, 1968, Ser. No. 781,408

Claims priority, application France, Dec. 13, 1967, 132,124

Int. Cl. H01h 9/18; 3/12

U.S. Cl. 200—167

9 Claims



A push contact device having a small control travel intended for controlling electrical apparatus by current impulses. An operating pushrod projects freely from the center of a concave baseplate by a deformable operating plate against which the said pushrod is supported.

3,576,963

WELDING METHOD


Freeman M. Vowels, Louisville, Ky., assignor to American Air Filter Company, Inc., Louisville, Ky.

Filed Sept. 3, 1968, Ser. No. 757,169

Int. Cl. B23k 1/10

U.S. Cl. 219—92

4 Claims



A method of resistance welding electrically conductive bodies together wherein projection means and sealing means are positioned between overlapped portions of such bodies, the bodies then being subjected to pressure and current to seal and weld the bodies together.

3,576,964

WELDED JOINT


Alvin R. Williams, Northfield, Ohio, assignor to United States Steel Corporation

Filed May 27, 1969, Ser. No. 828,296

Int. Cl. B23k 1/10

U.S. Cl. 219—92

7 Claims



A welded joint is disclosed having an S-shaped metal connector provided with a first laminate cavity and a second laminate cavity, a first adhesively bonded laminate disposed in the first laminate cavity, and a second adhesively bonded laminate disposed in the second laminate cavity. The first adhesively bonded laminate and the second adhesively bonded laminate, each has a first metal member, a second metal member and an electrically insulating adhesive between the first metal member and the second metal member. The first adhesively bonded laminate and the second adhesively bonded laminate are disposed in the first laminate cavity and the second laminate cavity respectively so that the first metal members and the second metal members are in contact with the metal connector and are welded together.

3,576,965

METHOD AND DEVICE FOR BORING WORKPIECES, PARTICULARLY WATCH JEWELS BY MEANS OF LASER PULSES

Gottfried Gugger, Steffisburg, Switzerland, assignor to Laser Technique SA., Bern, Switzerland

Filed Sept. 13, 1968, Ser. No. 759,664


Claims priority, application Switzerland, Sept. 25, 1967,

13357/67

Int. Cl. B23k 9/00

U.S. Cl. 219—121

26 Claims



A method and device for producing bores of substantially circular cross section in workpieces, particularly in watch jewels, by means of laser pulses, wherein a number of laser pulses successively produced by a laser source are directed into an optical deflecting system wherein the laser beam is deflected from its axis of incidence, successive laser pulses being thereby distributed by said rotating deflecting system on a path round the axis of the bore to be produced.

3,576,966

ARC-WELDING IN NARROW GAP


Cornelius J. Sullivan, Berkeley Heights, N.J., assignor to Air Reduction Company, Incorporated, New York, N.Y.

Filed Mar. 27, 1967, Ser. No. 626,026

Int. Cl. B23k 9/12

U.S. Cl. 219—137

2 Claims



A welding wire of serpentine form is fed into an electric arc in a narrow gap between workpieces to be joined, the wire passing through a contact tube which is sheathed in electrical insulation to avoid short-circuiting to the workpieces, the serpentine form of the wire serving to direct the arc toward one side of the gap or the other in periodic oscillations as the electrode is moved lengthwise of the gap from one end to the other, and the seam is built up layer by layer in repeated passes of the electrode. Means are shown for bending the wire to the desired form.

3,576,967

SWITCH CONSTRUCTION WITH LOAD BREAK DEVICE HAVING ONE OR MORE MOVABLE SLATS WITH HEAT SPACERS


James E. Jeffries, Chicago, Ill., assignor to S & C Electric Company, Chicago, Ill.

Filed Apr. 4, 1969, Ser. No. 813,541

Int. Cl. H01h 33/06

U.S. Cl. 200—151

6 Claims



A rotatable switch blade engages and disengages stationary contact assembly through a slot in a generally sector-shaped insulating housing enclosing the contact assembly and formed by either a pair of stationary plates or by a single molded piece of plastic arc extinguishing material. The housing has one or more generally radially extending slats of plastic arc extinguishing material which are located in a groove or grooves on one side of the slot and are biased transversely into a registering groove or grooves on the other

side of the slot. The distal end of the switch blade successively engages the outer ends of the slats and displaces them transversely of the slot as the switch blade rotates toward the switch closed position. The reverse procedure occurs when the switch blade rotates toward the switch open position accompanied by arc confining and extinguishing action of the slat or slats and the housing.

3,576,968

ELECTRODE HEATING SYSTEM


Robert L. Collie, Orange County (2707 Catalina Drive) Orlando, Fla.

Filed May 19, 1969, Ser. No. 825,556

Int. Cl. H05b 3/60; F28d 15/00

U.S. Cl. 219—284

10 Claims



An electrode heating apparatus for controlling the heat output in an electric heating system by varying the level of an electrolyte solution in a heating chamber having electrodes therein. A heat exchanger is connected to the heating chamber for utilizing heat generated in the electrolyte solution and provision is made for a quick heat up of the electrolyte solution. Thermostatic valves control the flow of the electrolyte solution into and out of the heating chamber and thus the level of the electrolyte in the chamber which in turn determines the rate of heating of the electrolyte solution by the area of the electrodes covered by the electrolyte solution.

3,576,969

SOLDER REFLOW DEVICE


Rohinton J. Surty, Redwood City, Calif., and Conrad Trollmann, Baden Wurttemberg, Germany, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sept. 2, 1969, Ser. No. 854,396

Int. Cl. B23k 3/02; H05b 3/10

U.S. Cl. 219—221

1 Claim



Disclosed is a device for simultaneously soldering numerous integrated circuit chip leads to a circuit board. The

device is characterized by having a heating tip made of refractory, electrically insulative, thermally conductive, material. Fused to this tip is a coat of penetrating metallic paste. The paste is disposed on the tip in an electrically continuous path. Heating is accomplished by passing current through this metallic paste path.

3,576,970 QUICK HEAT AND ELECTRICAL POWER-PRODUCING SYSTEM


James R. Cherry, Barrington, Ill., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Oct. 1, 1969, Ser. No. 862,785

Int. Cl. F27d 11/00

U.S. Cl. 219-279

6 Claims



A system for producing either quick heat or electrical power, or both, for automobiles comprises a conventional alternator, an auxiliary alternator and a control system therefor. In the quick-heat mode the control system connects the field winding of the auxiliary alternator to load the output of the conventional alternator thereby avoiding the generation of voltage transients. If quick heat is not desired, the conventional alternator provides only electrical power and the auxiliary alternator has no output.

3,576,971 FLUID-ACTUATED TRANSLATING APPARATUS


Richard E. Norwood, Boulder, Colo., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed June 8, 1967, Ser. No. 644,584

Int. Cl. G06k 7/02

U.S. Cl. 235-61.11

6 Claims



Punched card interpreter using fluid jets for sensing the presence of holes and controlling diaphragm valves and fluid pressure to decode the hole arrangement and operate a recording device.

3,576,972 DOCUMENT CARRIER

Daniel J. Wood, 510 Sage Valley Drive, Richardson, Tex., and Harold E. Wood, 329 S. Prospect Ave., Park Ridge, Ill.

Filed Sept. 12, 1969, Ser. No. 857,410


Int. Cl. G06k 19/02

U.S. Cl. 235-61.12R

2 Claims

A document carrier envelope for processing checks through automatic magnetic character recognition sorting

equipment. The document carrier includes generally rectangular back and front sheets of approximately the same size. The front sheet is formed of relatively translucent material so that a check carried by the document carrier can be read, photographed or microfilmed and the front sheet is adhesive-



ly secured to the back sheet along one of the shorter side edges and along a line spaced from one of the longer side edges of the sheets. An elongated magnetic indicia-receiving strip is secured to the front sheet adjacent the adhesively secured longer side edges.

ERRATUM

For Class 235-61-114 see:
Patent No. 3,577,203

3,576,973 BINARY REGISTER


Wilburn D. Draper, Thousand Oaks, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 30, 1969, Ser. No. 820,400

Int. Cl. G06m 3/14; H03k 21/06

U.S. Cl. 235-92

16 Claims



A versatile binary register which has control means for selectively setting the register to the one's and two's complements in response to first and second control signals, respectively. In addition, alternate application of the first and second control signals causes the register to function as a counter which operates in the forward mode if the first and second control signals are applied in a given sequence and/or operates in the reverse mode if the signals are applied in an opposite sequence.

3,576,974 ADD AND SUBTRACT COUNTER

Francis P. Knox, Bloomfield, Conn., assignor to Redington Counters, Inc., Windsor, Conn.

Filed Sept. 26, 1969, Ser. No. 869,996


Int. Cl. G06m 3/14, 1/10

U.S. Cl. 235-92C

13 Claims

A counter has a novel drive assembly including a pinion cooperating both with a number wheel and also with an oscillatable ratchet to permit selective adding and subtracting. The pinion member has two adjacent axial portions with each portion having teeth spaced about the circumference. The number wheel is in meshing engagement with a first portion of the pinion member and the ratchet is mounted for oscillation adjacent the second portion thereof. Biasing means is provided to urge a tooth of the pinion member into engage-

ment with suitable means on the ratchet when the ratchet is in either of two positions spaced from a neutral point therebetween, so that return of the ratchet to its neutral point from one of those positions causes rotation of the



pinion in a direction opposite to the direction of oscillation of the ratchet. The biasing means also prevents engagement of a tooth with the ratchet at a wrong point during the cycle to avoid spurious action.

3,576,975 REVERSIBLE COUNTER WITH READOUT


Joachim A. Maass, 3212 Querns Road, Belmar, N.J.

Filed June 14, 1968, Ser. No. 737,130

Int. Cl. G06m 3/14

U.S. Cl. 235-92

2 Claims



The invention describes apparatus for counting a sequence of events and for displaying the final count of that sequence. A number of magnetic cores are energized and deenergized sequentially to produce a changing magnetic field. Ferromagnetic plates on a rotatable cylinder are arranged such that the changing magnetic field exerts a force on the plates which results in rotation of the cylinder to place any of a series of characters imprinted on the periphery of the cylinder at a viewing panel. The cylinder may be rotated in either direction of changing the order of energization of the cores to correspond to either addition or subtraction.

3,576,976 NONLINEAR OPTIMIZING COMPUTER FOR PROCESS CONTROL

Frank A. Russo, Royal Oak, and Robert J. Valek, Farmington, Mich., assignors to The Bendix Corporation

Filed Oct. 19, 1967, Ser. No. 676,586


Int. Cl. G05b 13/02; G06k 9/06

U.S. Cl. 235-150.1

7 Claims

An apparatus for converting an input signal representing a set of measured process parameters such as temperature, vibration or torque into an output signal representing a set of nonmeasurable process performance parameters such as tool wear, surface finish or production costs having a pattern

recognition circuit for classifying the measurable parameters into one of a plurality of classes and a linear regression net-



work for each class being selectable in accordance with the classification to calculate the performance parameters.

3,576,977 SYSTEM AND METHOD FOR CONTROLLING THE POSITIONING SYSTEM OF A PIPELAYING VESSEL


Robert H. Kolb, Cypress, Tex., assignor to Shell Oil Company, New York, N.Y.

Filed Aug. 26, 1968, Ser. No. 755,304

Int. Cl. G06g 7/70; B63b 35/04

U.S. Cl. 235-150.27

4 Claims



A system and method for controlling the movement, position and orientation of a pipelaying vessel in a manner designed to permit moving the vessel along a desired route while maintaining a desired tension in the pipe and while minimizing the bending forces in the pipe and pipe support structure which result from crosscurrents or misalignment of the vessel. Vessel movement along the route may be at a selected steady rate or may be intermittent and synchronized with the pipeline assembly process being conducted onboard.

3,576,978 SYSTEM FOR ACCOMODATING VARIOUS MACHINE TOOL RESOLUTIONS FROM A STANDARD PROGRAM

Jack Rosenberg, Pacific Palisades, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed May 13, 1968, Ser. No. 728,685


Int. Cl. B23g 21/00; G06f 15/46

U.S. Cl. 235-151.11

10 Claims

A system for providing the correct number of pulses to drive any machine tool having a resolution of less than 0.001 inch from a standard program written for control of a machine tool having a resolution of 0.001 inch. Command words containing control bits for control of the various axes of a machine tool are stored in a computer memory and gated out under control of pulses provided by an oscillator. If a command word from the buffer of the computer memory is gated out each millisecond and the standard program is written for a machine tool having a 0.001 inch resolution, a maximum vector feedrate of 60 inches per minute can be provided. If the machine tool which is to be controlled has a resolution of u inches and $m=0.001/u$ is an integer, which is

the usual case, the frequency of the pulses as well as the number of pulses in the pulse train must be modified. An oscillator which produces 1,000 m pulses per second is used to pulse a preset counter which is preset to m and therefore, sends 1,000 demand pulses per second to cause a new command word to be read from the computer memory every millisecond into an output buffer. The pulses from the oscillator are also fed directly to a transmission control device which



gates the command word in the output buffer to the machine tool. The result is that each command word is gated m times to the machine tool. To position the machine tool cutter at the end of a cut with the actual resolution built into the machine tool, the preset counter is set to 1 when the distance from the end of the line segment being cut is less than 0.001 inch so that each of the command words is sampled only once.

3,576,979

MOTION MONITOR SYSTEM


Amiel J. McCall, South Euclid; Ronald D. Elms, Mayfield Heights, and Larry D. Rice, Novelty, Ohio, assignors to Allen-Bradley Company, Milwaukee, Wis.

Filed Sept. 24, 1968, Ser. No. 762,097

Int. Cl. G06f 15/46; G05b 19/18

U.S. Cl. 235-151.11

7 Claims




A system for monitoring the motion of a numerically controlled machine tool to avoid costly errors. The motion command data that is normally supplied to the machine tool is also supplied to the monitoring system. Additionally, data from the machine tool slide transducers representative of the actual machine tool motion are fed back to the monitoring system. Tolerance data are also supplied to the monitoring system. On the basis of the data supplied thereto, the monitoring system continually determines whether or not a sufficient error exists to shut down the machine tool.

3,576,980 AUTOMATIC CORNER RECOGNITION SYSTEM

Harold W. Doyle, Newport Beach, Calif., assignor to California Computer Products, Inc., Anaheim, Calif.
Filed Mar. 28, 1968, Ser. No. 716,918
Int. Cl. G06f 7/38

U.S. Cl. 235-152

6 Claims



The angular change between successive line segments connecting consecutive data points defining a sample shape may be used to determine corners for controlling automatic pattern grading. When the segments are represented in vector notation the angular evaluation may be conveniently determined from the dot and cross product of the angle-forming vectors. Where long vectors are separated by short vectors, a corner reconstruction technique can be employed to locate a vertex approximately representative of the original sample shape.

3,576,981


DIGITAL INTERPOLATOR WITH A CORRECTIVE DISTRIBUTION COMMAND DEVICE

Kiyokazu Okamoto, and Masayuki Miyazaki, Tokyo, Japan, assignors to Nippon Electric Company, Limited, Tokyo, Japan

Filed Mar. 28, 1968, Ser. No. 716,954

Claims priority, application Japan, Mar. 31, 1967, 42/20527
U.S. Cl. 235-152

16 Claims




A corrective digital interpolator providing sequential steps in X and Y coordinates for tracing new curves from a prototype curve and for minimizing deviations of the new curve from the prototype curve, comprising translating coordinate signals and distribution signals representing, for example, a direction (vertical) other than the direction (horizontal) corresponding to a maximum component (horizontal) of a vector at different followup points, translating the other signals into corrective signals in such manner that the latter signals have a ratio of 3 to 2 relative to the other signals, and translating distribution command rate signals and corrective signals into corrected command rate signals for minimizing the deviations of the new curves from the prototype curve, the latter signals comprising logic sums of the distribution command rate signals and the corrective signals.

3,576,982 ERROR TOLERANT READ-ONLY STORAGE SYSTEM

Keith A. Duke, Wappingers Falls, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Dec. 16, 1968, Ser. No. 783,925
Int. Cl. G11c 29/00; G06f 11/00

U.S. Cl. 235-153

9 Claims U.S. Cl. 235-176



A read-only storage system wherein each data word is stored twice, once in its true form and once in its complementary form. Said two data words are further stored at complementary addresses and means are provided upon readout of any data word for detecting a system error. Said means being further operative to automatically access an address complementary to the one currently being utilized for reading out the same data word in the complementary form at said complementary address.

3,576,983

DIGITAL CALCULATOR SYSTEM FOR COMPUTING SQUARE ROOTS


David S. Cochran, Palo Alto, Calif., assignor to Hewlett-Packard Company, Palo Alto, Calif.

Filed Oct. 2, 1968, Ser. No. 764,436

Int. Cl. G06f 7/48

U.S. Cl. 235-158

6 Claims




In a data processing system, a control unit is provided for controlling the functions and operational sequence of a memory unit and an arithmetic unit so as to derive the square root of any given number. The control system includes two iterative control loops, the first of which initially subtracts a predetermined subtrahend term from one-half of the given number. Thereafter this control loop successively subtracts an incrementally advanced subtrahend term from the difference formed by the immediately preceding subtraction operation. The second iterative control loop reduces the degree of significance of the subtrahend digits when the difference formed by a subtraction operation is negative. The number of positive differences formed by the first control loop are counted and these counts represent the square root of the given number.

3,576,984 MULTI-FUNCTION LOGIC NETWORK

Roland S. Gregg, Jr., Canoga Park, Calif., assignor to The Bunker-Ramo Corporation, Canoga Park, Calif.
Filed Aug. 9, 1968, Ser. No. 751,607
Int. Cl. G06f 7/385, 7/38

13 Claims



A multifunction logic network is provided to perform a selected one of a plurality of operations, each a function of one, two or three variables and five control signals. A first plurality of gates provide all possible AND functions of two variables A and D, each in response to a separate control signal. A fifth gate then provides all possible inverted functions of a third variable C when true and one or more of the other variables A and D in response to a separate control signal. All possible AND functions of two variables are then combined by a sixth gate with the output of the fifth gate. A seventh gate provides all possible inverted functions of the third variable C when false and the other variables A and D in response to the output of the fifth gate and the fifth control signal. An eighth gate effectively OR's the complements of the sixth and seventh gates to provide all of 30 possible functions of one or more of the variables A, D and C. The remaining two operations consist of selectively transmitting one of two possible binary constants.

3,576,985

METHOD OF AND MEANS FOR TREATING GRAVITY PROFILES

Philip L. Lawrence, Riverside, Conn., assignor to Mobil Oil Corporation

Continuation of application Ser. No. 214,973, Aug. 6, 1962, now abandoned. This application Sept. 20, 1967, Ser. No. 669,314


Int. Cl. G06g 7/19; G01v 7/36

U.S. Cl. 235-181

16 Claims

A gravity profile containing gravitational anomalies is utilized and treated to provide information as to depths of the sources of the anomalies. The initial measurements of gravity potential along the line of exploration making up the gravity profile are corrected for change in elevation and a plurality of averaged gravity profiles are generated. The generated

profiles are subtracted from one another to generate difference profiles in which the several anomalies appear in turn and in greatly enhanced form.



ference profiles in which the several anomalies appear in turn and in greatly enhanced form.

3,576,986


ANALOG/DIGITAL DIFFERENTIAL APPARATUS FOR COMPARING RESOLVER OUTPUT DATA WITH A DIGITAL SIGNAL

David R. Brickner, and Billy K. Swift, Phoenix, Ariz., assignors to Sperry Rand Corporation
Filed Jan. 14, 1969, Ser. No. 790,987

Int. Cl. G06g 7/22; G06j 1/00

U.S. Cl. 235-189

13 Claims



Apparatus for comparing an analog input signal with a digital input signal and providing an analog output signal proportional to the difference therebetween, said apparatus comprising an analog/digital differential controller including digital-to-analog converters responsive to the more significant bits of the digital signal and operating in combination with multiplier and subtractor devices for establishing a coarse relationship between the analog and digital input signals and supplying an accurate reference voltage to a fine resolution digital-to-analog converter which is responsive to the less significant bits of the digital signal to produce fine data for summing with the coarse data and thereby form the output signal.

3,576,987

CHEMICAL LIGHTING DEVICE TO STORE, INITIATE AND DISPLAY CHEMICAL LIGHT

Heinz Kurt Walter Voight, Ridgefield, and Robert Lee Myers, Darien, Conn., assignors to American Cyanamid Company, Stamford, Conn.

Continuation-in-part of application Ser. No. 674,296, Oct. 10, 1967, now abandoned. This application Nov. 7, 1968, Ser. No. 777,987

Int. Cl. F21k 2/00

U.S. Cl. 240-2.25

6 Claims

A device for providing chemiluminescent light from a chemical reaction of suitable compounds in the presence of a fluorescent compound, the device being a self-contained light

unit, the device comprising an outer flexible, cylindrical, light transmitting container for one reactive composition, and an inner, rigid container for another reactive composition. Flex-



ing the outer container breaks the inner container, allowing the reactive compositions to mix and produce a reaction providing chemiluminescent light which is visible through the outer light transmitting container.

3,576,988

ADJUSTABLE STOP FOR SWINGABLE FLOODLIGHTS


Donald S. Henning, Thiensville, Wis., assignor to Phoenix Products Company, Inc., Milwaukee, Wis.

Filed June 6, 1968, Ser. No. 735,027

Int. Cl. F21p 1/00

U.S. Cl. 240-3

7 Claims



An arm structure that mounts a floodlight swings back and forth over a stop plate and collides with an abutment thereon that defines the operative position of the floodlight. The abutment is adjustable to different arm stopping positions along a curved edge of the plate.

3,576,989

PURSE-SIZE FACE-ILLUMINATING FLASHLIGHT AND MIRROR


Sidney Schwartz, Manhattan, N.Y. (375 West End Ave., New York, N.Y. 10024)

Filed Oct. 14, 1968, Ser. No. 767,362

Int. Cl. F21v 33/00

U.S. Cl. 240-4.2

3 Claims



A lady's handbag-size mirror is mounted in a molded plastic frame formed with a cavity extending diametrically

behind the mirror containing a dry cell battery. A lightbulb extends from one end of the cavity beyond the periphery of the mirror and is adapted to project light beams to the face of a user looking into the mirror. A removable depressible button extends from the other end of the cavity for actuating a normally open switch to light the bulb and permits access to the cavity for changing the battery and bulb. The frame is formed in mating halves which meet substantially in a plane parallel to that of the mirror.

3,576,990

LIGHTING SYSTEM


Wallace F. Johnson, 1287 W. Shaw, and William H. Tilson, 7560-A North Charles, Fresno, Calif.

Filed Sept. 27, 1968, Ser. No. 763,148

Int. Cl. F21p 1/00

U.S. Cl. 240-10

7 Claims



A versatile lighting system particularly characterized by a multiplicity of supporting bases, each conforming to a candlelike, truncated, frustoconical configuration surmounted by an interchangeable translucent, flame-shaped tip and including therein a miniature lamp disposed within a universal female receiver of a type particularly adapted to receive miniature lamp bases without regard to their configuration. The system electrically is connected in parallel with a portable source of electrical energy through a universal male connector seated in a receiver so that a plurality of radiating candlelike structures may be readily assembled for use as an ornamental lighting system in decorative schemes, including wall arrangements, centerpieces, floral arrays, and the like.

3,576,991

TRACK CIRCUIT PICKUP UNIT


Harlan J. Wilson, Sunnyside, Canada, assignor to Marquardt Industrial Products Co., Cucamonga, Calif.

Filed Jan. 23, 1969, Ser. No. 793,447

Int. Cl. B61l 21/00

U.S. Cl. 246-40

5 Claims



Apparatus is described which detects the presence of a train within a given area. The apparatus includes a sensing unit which comprises an iron core transformer vertically positioned between the rails of a railroad track. A single-loop primary winding is coupled across the track. A secondary winding of the transformer is coupled to a receiver. At least

one transmitter is coupled to the track at a predetermined distance from the sensing unit. The receiver detects secondary voltage induced by the track voltage applied to the primary winding. The wheel and axle of the train, when approaching the given area between the selected transmitter and the receiver, from the receiver end causes current to flow in the rails past the sensing unit, which through magnetic flux coupling to the sensing device adds in polarity to the magnetic flux in the core due to the primary winding, thereby increasing the signal induced into the secondary winding. This signal is detected by the receiver. When the train is within the given area between the selected transmitter and the receiver, the wheels and axle act as a shunt to short out any signals from the desired transmitter to the pickup unit.

3,576,992

TIME OF FLIGHT MASS SPECTROMETER HAVING BOTH LINEAR AND CURVED DRIFT REGIONS WHOSE ENERGY DISPERSIONS WITH TIME ARE MUTUALLY COMPENSATORY


Charles J. Moorman, and John Q. Parmater, Cincinnati, Ohio, assignors to The Bendix Corporation

Filed Sept. 13, 1968, Ser. No. 759,645

Int. Cl. H01j 39/36

U.S. Cl. 250-41.9

9 Claims



A mass spectrometer is disclosed which is based on the linear time-of-flight principle. Initial ion energies are compensated for by combining a curved drift region with a linear drift region so that ions of the same mass but differing energies reach the collector at the same time.

3,576,993

X-RAY CAMERA FOR X-RAY DIFFRACTION ANALYSIS ACCORDING TO GUINIER

Gunnar Hagg, Uppsala, Sweden, assignor to Incentive Research & Development AB, Bromma, Sweden

Filed Jan. 16, 1969, Ser. No. 791,731

Claims priority, application Sweden, Jan. 25, 1968, 1021/1968


Int. Cl. G01n 23/20

U.S. Cl. 250-51.5

11 Claims

An X-ray camera for X-ray diffraction analysis of powdered material according to the Guinier method, which camera comprises an airtight and evacuable casing having a radiation entrance window for X-ray radiation, in which casing all the components of the camera, as a crystal holder for a monochromator crystal, a specimen holder for the specimen to be analyzed and a film holder, are mounted. The crystal holder is preferably removably mounted on a support plate which is rotatable about an axis perpendicular to the direction of the X-ray radiation incident through the entrance window of the casing. A support and guide rail can be mounted or positioned in anyone of a number of different positions in the casing radially extending from the axis of rotation of the support plate for the crystal holder. Two carriages are movably supported on the support and guide rail and lockable relative thereto in desired positions. One of the carriages carries the specimen holder, whereas the other car-

riage can be mechanically coupled or connected to the film holder so as to determine the position of the film holder. The



principal advantage of this X-ray camera is that it can easily and rapidly be adjusted for different wavelengths of the X-ray radiation used for the diffraction analysis.

ERRATA

For Classes 250—83.1 and 250—65 see:
Patent Nos. 3,577,199 and 3,577,204

3,576,994

NEUTRON RADIOGRAPHY OF DEUTERATED TISSUE
Paul B. Parks, Aiken, S.C., and Mark Brown, Augusta, Ga., assignors to The United States of America as represented by the United States Atomic Energy Commission.

Filed July 14, 1969, Ser. No. 841,573
Int. Cl. G01t 3/00

U.S. Cl. 250—83.1

5 Claims

An improved method of preparing a neutron radiograph of biological media by first contacting the media with a fluid containing deuterium such as deuterium oxide. The protium in the nonfatty tissue is replaced with deuterium to substantially reduce the neutron capture and scatter within the deuterated tissue. Consequently, the radiolucency of the nonfatty tissue is greatly increased. Deuterium does not significantly replace the protium in the fatty tissue which therefore remains radiopaque in contrast to the radiolucent nonfatty tissue.

3,576,995


RADIATION SURVEY METER COUNTING LOSS COMPENSATION CIRCUIT

Joseph C. Nirschl, West Long Branch, and G. Edgar Mooney, Jr., Pt. Pleasant, N.J.

Filed Dec. 2, 1968, Ser. No. 780,505
Int. Cl. G01t 1/16

U.S. Cl. 250—83.3

3 Claims



A radiation survey meter including a radiation detector, an operational amplifier and a current meter in the output cir-

cuit thereof wherein the counting loss error of the detector, which causes a reduction in current at high dose rate levels, is compensated for by means of a Zener diode connected in circuit with a resistive network in the output circuit of the operational amplifier. For higher radiation dose levels, the output voltage of the operational amplifier exceeds the voltage at which the Zener diode starts conducting. The resulting impedance change in the output circuit causes additional current flow in the current meter. By proper selection of a Zener diode and the resistance network associated therewith, the dead time effect of the radiation detector can be adequately compensated for.

3,576,996


INSTRUMENT FOR MEASURING THE NET FLUX OF RADIANT ENERGY THROUGH A PLANE

Donald W. Stevens, West Concord, Mass., assignors to The United States of America as represented by the Secretary of the Air Force.

Filed Apr. 14, 1969, Ser. No. 815,761
Int. Cl. G01t 1/16

U.S. Cl. 250—83.3

1 Claim



A pair of solar radiation-absorbing surfaces mounted on opposite sides of a probe utilize the Seebeck and Peltier effects to maintain equal surface temperatures thereby avoiding errors due to wind. The current produced by the effects is a measure of the net radiation.

3,576,997

PARTICLE ACCELERATOR EMPLOYING A REVOLVING ELECTRIC FIELD FOR GENERATING X-RAYS


Peter E. Slavin, Cambridge, Mass., assignor to Intelligent Instruments, Inc., Woburn, Mass.

Division of Ser. No. 469,505, July 6, 1965, Pat. No. 3,432,657, filed Sept. 24, 1968, Ser. No. 762,051

Int. Cl. G03b 41/16

U.S. Cl. 250—90

6 Claims



A stereoscopic image is obtained from an X-ray scanning instrument in which the patient is moved along the axis of a rotating X-ray source with an X-ray receiver located oppositely the source and rotating with it to generate a helical scanning motion with respect to the patient. The X-ray receiver generates electrical signals which are recorded on magnetic tape and the tape is employed to operate a stereo

video system. A compact particle accelerator employing a revolving electrical field is provided for producing highly directional and monochromatic X-ray beams.

3,576,998

SELF CONTAINED, CLOSED SYSTEM AND METHOD FOR GENERATING AND COLLECTING A SHORT LIVED DAUGHTER RADIONUCLIDE FROM A LONG LIVED PARENT RADIONUCLIDE


Marshall E. Deutsch, Sudbury; Louis W. Mead, Lexington, and Zoltan Nagy, Quincy, Mass., assignors to Nen-Picker Radiopharmaceuticals, Inc., Boston, Mass.

Filed Nov. 16, 1966, Ser. No. 594,713

Int. Cl. G21g 5/00

U.S. Cl. 250—106

47 Claims



A sterile, pyrogen free, self-contained closed radionuclide generator system in which the eluant for extracting the daughter from the generator column, containing the parent and daughter on a supporting substrate, is prepackaged and stored in a predetermined amount in a sealed, flexible, collapsible plastic bag. The bag is sealably connected to the generator column by a conduit. The eluant is drawn from the bag through the generator column and is automatically withdrawn from the column and collected as an eluate of the daughter in the eluant by impaling a pierceable wall of a sealed evacuated eluate collecting tube on a cannula which is sealably connected to the generator to thereby apply a vacuum to the eluant in the bag to draw it through the generator and cannula into the evacuated eluate collecting tube.

3,576,999

METHOD AND APPARATUS FOR DETERMINING THE ORIENTATION OF AN OBJECT RELATIVE TO AN ELLIPTIC OBJECT


Richard Blythe; Gerald C. Scott; Edgar A. Work, Jr.; Donald S. Lowe, and Philip G. Hasell, Jr., Ann Arbor, Mich., assignors to The Bendix Corporation

Filed Jan. 16, 1965, Ser. No. 609,520

Int. Cl. G01j 1/20

U.S. Cl. 250—203

14 Claims



Method and apparatus for maintaining the orientation of an object, such as a satellite or spacecraft, with respect to a

ERRATUM

For Class 250—113 see:
Patent No. 3,577,205

3,577,000

SYNCHRORESOLVER WITH OPTICAL FEEDBACK LOOP


David A. Warner, Cambridge, Mass., assignor to the United States of America as represented by the Secretary of the Air Force.

Filed Aug. 21, 1969, Ser. No. 851,981

Int. Cl. G01d 5/30, 5/34

U.S. Cl. 250—230

13 Claims



A synchroresolver having a reflective means, a radiant source, a lens and a pair of energy sensors for determining the angular displacement of a rotating body. The reflective means may constitute a reflective prism, a plurality of convex cylindrical reflectors, or the combination of both. The radiant source reflects its radiant energy off the reflective means and onto the pair of energy sensors. The voltage output of the energy sensors is then utilized in making the desired angular determinations.

3,577,001


ELECTRIC CRANKING MOTOR AUTOMATIC DISCONNECT AND LOCKOUT CIRCUIT
Donald L. Cummins, Anderson, Ind., assignor to General Motors Corporation, Detroit, Mich.

Filed Oct. 31, 1969, Ser. No. 872,939

Int. Cl. F02n 1/108

U.S. Cl. 290—38

2 Claims



An electric cranking motor automatic disconnect and lockout circuit. The normally open contacts of an electric cranking motor-solenoid-operated switch, having the operating coil thereof connected across a source of DC potential through the normally open contacts of an electric relay, are connected in series with the electric cranking motor across the source of DC potential. Upon the closure of an electric

switch, an energizing circuit is established for the operating coil of the electric relay across the source of DC potential to close the associated normally open contacts thereof which establish an energizing circuit for the operating coil of the solenoid operated switch. At least a portion of the output potential of an electric generator driven by the cranked engine is transformer coupled across the gate-cathode electrodes of a silicon controlled rectifier, the anode-cathode electrodes of which are connected in parallel with the operating coil of the electric relay. When the generator output potential is of sufficient magnitude to produce gate-cathode current through the silicon controlled rectifier, the resulting anode-cathode current flow therethrough short circuits or shunts sufficient current around the operating coil of the electric relay to substantially deenergize and disenable the operating coil, consequently, the associated normally open contacts open to interrupt the energizing circuit for the operating coil of the cranking-motor-solenoid-operated switch. The silicon-controlled rectifier is maintained conductive while the engine is in the running mode, consequently, the operating coil of the electric relay is maintained disenabled thereby, a condition which prevents the reengagement of the cranking motor while the engine is in the running mode.

3,577,002

MOTOR-GENERATOR COMBINATION

Samuel S. Hall; Robert A. Miller, and Philip R. H. Riley, Ilford, Essex, England, assignors to The Plessey Company Limited, Ilford, England


Filed Apr. 16, 1969, Ser. No. 816,710

Claims priority, application Great Britain, Apr. 19, 1968, 18692/68

Int. Cl. F02n 11/04

U.S. Cl. 290-46

7 Claims



A compact unit for supplying an aircraft with both DC and AC electric power under normal running conditions and to provide also electric starting facilities, and which can be attached to a single engine pad of an aircraft turbine, is obtained by energizing the rotor field windings of an alternator with DC power via a rectifier system participating in its rotation from the armature windings of a coaxially arranged starter motor, which for the purpose has a second multiterminal field winding, the starter motor having also automatic brush-lifting gear; the DC power output is obtained from a second stator winding of the alternator via a built-in rectifier set.

3,577,003

AUTOMATIC BATTERY-SWITCHING DEVICE

Byron C. Behr, Norwalk, Conn.; Gunars Sprogis, Cleveland, Ohio, and Frederick E. Booth, Weston, Conn., assignors to Union Carbide Corporation, New York, N.Y.

Filed Mar. 11, 1969, Ser. No. 806,215


Int. Cl. H02j 7/00

U.S. Cl. 307-66

3 Claims

An apparatus for automatically switching off a working battery and switching on a standby battery when the working battery falls below a predetermined working voltage. The device utilizes at least one switching element such as a transistor associated with the working battery and at least

one switching element such as a transistor associated with the standby battery, with the transistor associated with the working battery being connected so as to back bias the transistor



associated with the standby battery. When the working battery wears down to a predetermined voltage its back bias is reduced to a sufficient point so as to turn on the standby transistor and thereby switch on the standby battery.

3,577,004

PROGRAMMED TIMER


Demetrios T. Tsotsas, Berwyn, Ill. (315 W. Stimpson, Linden, New Jersey, 07036)

Filed Sept. 23, 1968, Ser. No. 784,971

Int. Cl. H01h 7/00

U.S. Cl. 307-141

8 Claims



A programmed clock timer is described in which operation of an alarm and an appliance on an adjustable 24 hour sequence is supplemented with selectively programmed 24 hour and 7-day timing sequences whereby one or more appliances may be operated according to a predetermined program consisting of programmed time interval sequences. The program is visibly presented on a control panel with individual incremental time segments being programmed by an array of manually operated push-pull switches. A manual override feature separately controls a selected appliance.

3,577,005

TRANSISTOR INVERTER CIRCUIT

Alton O. Christensen, Houston, Tex., assignor to Shell Oil Company, New York, N.Y.

Continuation-in-part of application Ser. No. 787,067, now Patent No. 3,502,908, which is a continuation-in-part of application Ser. No. 761,450, Sept. 23, 1968. This application Nov. 24, 1969, Ser. No. 879,221


Int. Cl. H03k 19/08

U.S. Cl. 307-205

3 Claims

A ratioless MOSFET inverter for capacitive outputs consists basically of a pair of MOSFET's with their sources and drains tied together. The clock input is applied to the com-

mon drain connection and to the gate of one of the MOSFET's and the output is connected to the common source connection. In an alternative construction, the MOSFET whose gate is connected to the clock is replaced by



a Schottky diode connected between the source and drain terminals of the data input MOSFET. The clock is connected to the drain terminal of the data input MOSFET, and the output is connected to the source of the data input MOSFET.

3,577,006

FAIL-SAFE PULSED LOGIC AND GATE


Leo A. Tyrrell, Marion; Daniel E. Castleberry, Cedar Rapids, and Charles A. Weber, Marion, Iowa, assignors to Collins Radio Company, Cedar Rapids, Iowa

Filed Mar. 10, 1969, Ser. No. 805,497

Int. Cl. H03k 19/08, 19/22

U.S. Cl. 307-218

3 Claims



A DC logic handling fail-safe pulsed logic AND gate circuit capable of warning the user whenever substantially any single catastrophic component failure occurs inhibiting any of the functions a DC logic circuit is required to perform. It is a multiple input AND gate circuit with the inputs repeatedly pulsed to develop a resulting pulsed output when no input signals are inhibited and there are no circuit disorders within the gate circuit. Biasing circuits within the gate circuit are so subject to bias voltage variation with a signal input inhibit or internal circuit disorder as to inhibit the pulse signal output and thereby warn.

3,577,007

CONSTANT AMPLITUDE VARIABLE FREQUENCY SWEEP GENERATOR

Anthony L. Cross, Arcadia, Calif., assignor to Bell & Howell Company, Chicago, Ill.

Filed Jan. 21, 1969, Ser. No. 792,371


Int. Cl. H03k 4/08

U.S. Cl. 307-228

9 Claims

A sweep generator for an oscilloscope or the like is described for providing a sawtooth output voltage in synchronism with a periodic input signal having a variable repetition rate. A sweep capacitor is discharged in response to the occurrence of each input signal and then charged by a controllable current source to establish a ramp voltage across the capacitor with a selected slope. The voltage across the capacitor is compared with a reference voltage by means of a comparator circuit during a brief time interval at the end of

each charging cycle. The comparator circuit controls the



magnitude of the current supplied to the sweep capacitor to maintain the peak output voltage substantially constant.

3,577,008

AUTOMATIC FREQUENCY CONTROL APPARATUS


Jack Craft, Somerville, N.J., assignor to RCA Corporation

Filed Jan. 22, 1969, Ser. No. 792,983

Int. Cl. H03k 5/20

U.S. Cl. 307-233

6 Claims



Automatic frequency control apparatus including a differential amplifier-detector biased so as to be responsive only to signals exceeding a predetermined amplitude value established to effectively reduce undesired pull-in of adjacent signal frequencies.

3,577,009

QUADRATURE REJECTION AND FREQUENCY CONVERSION CIRCUIT

Laurence C. Hofmeister, Fort Lauderdale, Fla., assignor to The Bendix Corporation

Filed Feb. 17, 1969, Ser. No. 799,772

Int. Cl. H03b 3/04

U.S. Cl. 307-233

10 Claims

A circuit for eliminating quadrature components from a sinusoidal input signal is described. The circuit also divides

3,577,017

RECTANGULAR PULSE MODULATOR


Jimmy R. Duke, and Walter E. Miller, Jr., Huntsville, Ala., assignors to the United States of America as represented by the Secretary of the Army

Filed Dec. 17, 1968, Ser. No. 784,443

Int. Cl. H03k 3/35

U.S. Cl. 307—284

2 Claims



Discharge of a RLC network is controlled with a silicon-controlled rectifier to provide a rectangular pulse for pulsing GaAs lasers.

3,577,018

HIGH-SPEED LOGIC DEVICE EMPLOYING A GUNN-EFFECT ELEMENT AND A SEMICONDUCTOR LASER ELEMENT

Toshio Wada; Yasuo Matsukura, and Kuniichi Ohta, Tokyo, Japan, assignors to Nippon Electric Company, Limited, Tokyo, Japan


Filed Mar. 13, 1969, Ser. No. 806,830

Claims priority, application Japan, Mar. 15, 1968, 43/17141

Int. Cl. H01l 19/00

U.S. Cl. 307—299

12 Claims



A semiconductor device is described wherein a Gunn effect element is placed in series with the PN junction of a semiconductor laser. A bias potential is applied across the series connection to forwardly bias the PN junction and normally produce lasing action from the laser element. The bias potential is further selected so that current reductions produced by high electric field layers traveling within the Gunn element effectively suppress lasing actions. Several embodiments are shown.

3,577,019

INSULATED GATE FIELD EFFECT TRANSISTOR USED AS A VOLTAGE-CONTROLLED LINEAR RESISTOR


Herbert F. Storm, Delmar, N.Y., assignor to General Electric Company

Filed Sept. 24, 1968, Ser. No. 762,091

Int. Cl. H03k 3/26

U.S. Cl. 307—304

4 Claims



The channel resistance of a metal-oxide-semiconductor field-effect transistor, or other insulated gate field effect

transistor, is linearized by applying to the gate electrode, in addition to the gate voltage for controlling the conductivity, an external feedback voltage having a value of one-half the supply voltage to nullify the effect of the internal feedback due to the supply voltage. In some cases the base electrode is disconnected, but spurious effects caused thereby can be avoided. The voltage-controlled linear resistor can be employed in DC and AC circuits in applications such as an AC phase shift circuit.

3,577,020

ACCELERATION INSENSITIVE TRANSDUCER


Elmer Victor Carlson, Prospect Heights; Floyd Warren Cross, Wheaton, and Mead Clifford Killian, Elk Grove Village, Ill., assignors to Industrial Research Products, Inc., Elk Grove Village, Ill.

Continuation of application Ser. No. 550829, May 17, 1966, now abandoned. This application June 17, 1969, Ser. No. 835,304

Int. Cl. H04r 17/00

U.S. Cl. 310—8.2

10 Claims



A transducer which includes a conductive case and an apertured cover mounted on the case. A baffle plate is mounted adjacent to the aperture. A diaphragm is mounted on the case. A piezoelectric element is mounted within the case and is held in position by a resilient conductive clip which is stressed beyond its elastic limit. A lever attached to a fixed pivot connects the piezoelectric element with the diaphragm and has balanced effective moments due to inertia on opposite sides of the pivot.

3,577,021

PIEZOELECTRIC TRANSDUCER MOUNTING APPARATUS


Irvin F. Gerks, Winslow, Wash., assignor to Honeywell, Inc., Minneapolis, Minn.

Filed Jan. 29, 1969, Ser. No. 795,016

Int. Cl. H01v 7/00

U.S. Cl. 310—8.7

3 Claims



A method of and apparatus for mounting a ceramic transducer to substantially reduce stresses produced therein as a result of its operation or external forces. The improvement comprises cylindrical rings which, while having high axial stiffness, have relatively low radial stiffness and therefore allow the transducer to flex or expand radially with respect to the mounting means while being axially held in place.

3,577,022

THERMOBALLISTIC GENERATOR


Siegfried H. Hasinger, Dayton, Ohio, assignor to the United States of America as represented by the Secretary of the Air Force

Filed Jan. 6, 1970, Ser. No. 001,005

Int. Cl. H02n 3/00

U.S. Cl. 310—10

7 Claims



Jets of high energy supercritical steam in a disintegrated state containing a small percentage of conductive colloidal particles are inductively electrically charged, then evaporated, in a fillgas mixture of steam and hydrogen transferring electrical charge to the colloids. After the evaporation the hydrogen and water vapor carrying the charged colloids are accelerated to a supersonic speed in expansion nozzles such that a wet vapor condition occurs and condensation takes place with the charged colloids acting as condensation nuclei. The condensation nuclei are kept from contacting the expansion nozzle walls by a sheath composed of the fillgas. The charged condensation droplets at constant or with slightly increased environmental pressure then traverse a conversion space of suddenly increased cross section of determined size, from a ground potential plane to a plurality of collector electrode plates converting an essential part of their kinetic energy into electrical energy. They deposit their electrical charge thereon raising the collector to a high potential. Recirculation of hydrogen and steam through the conversion region assists in the conversion process as a cooling and transport medium. Electrical power at relatively high voltages and low currents between the collector electrode and ground potential is generated for utilization.

3,577,023

MOVING COIL ACTUATOR

Lewis W. Bleiman, Northridge, Calif., assignor to Advanced Peripherals, Inc., Van Nuys, Calif.

Filed Dec. 4, 1969, Ser. No. 882,108


Int. Cl. H02k 41/02

U.S. Cl. 310—13

15 Claims

A moving-coil actuator having a carriage with an upright supporting post and an elongated undercarriage extending in one direction along a track for supporting the carriage. An electrical coil mounted on one side of the post projects in the same direction as the undercarriage into an annular air gap in a permanent magnet assembly, the undercarriage projecting into the assembly through a slot therein, and a plurality of head-supporting arms project in the opposite direction from the post into a stack of memory discs. Roller bearings adjacent the opposite ends of the undercarriage ride on inclined ways on the track, and a holddown bearing assembly is spring

urged upwardly to ride along overlying ways. One element of an optical position-determining device is rigidly mounted on



the undercarriage to coact with fixed elements on the actuator to determine the position of the carriage.

3,577,024

LIQUID-COOLED DYNAMOELECTRIC MACHINES

Junpei Inagaki; Moriyoshi Sakamoto, Yokohama-shi; Tsuneo Nakaita, Kawasaki-shi, and Hiroyuki Kitamura, Yokohama-shi, Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki-shi, Japan


Filed Sept. 29, 1969, Ser. No. 861,602

Claims priority, application Japan, Oct. 1, 1968, 43/70872

Int. Cl. H02k 9/19

U.S. Cl. 310—54

1 Claim



In a liquid-cooled dynamoelectric machine comprising a stator, a rotor, and means to spray cooling liquid directly upon heated portions of the stator, the peripheral surface of the rotor is provided with a pair of oppositely directed helical grooves or a pair of oppositely inclined surfaces to create components of force which act to prevent the cooling liquid from entering into the airgap between the stator and the rotor.

3,577,025

CLIP FOR CARBON BRUSHES


Archie R. Kingsbury, Taylors, S.C., assignor to Union Carbide Corporation

Filed June 7, 1968, Ser. No. 735,348

Int. Cl. H02k 13/00

U.S. Cl. 310—239

11 Claims



A clip for use with carbon brushes to form an assembly suitable to operate in electric equipment, the clip having at

least two members, one of the members being provided with a resilient protruding segment. This segment moves to a position flush with the surface of the member to which it is secured while the clip is sliding into a groove in the carbon brush, and snaps back to its normal position when it engages a recess in the groove. With this construction, the clip is permanently secured to the brush.

3,577,026

METHOD FOR PRODUCING IONS UTILIZING A CHARGE-TRANSFER COLLISION


Willy Haerberli, Madison, Wis., assignor to the United States of America as represented by the United States Atomic Energy Commission

Filed June 24, 1969, Ser. No. 836,088

Int. Cl. H01j 27/00

U.S. Cl. 313-63

12 Claims



Ionization of a first beam of polarized neutral atoms is accomplished by a charge-transfer collision with a second beam of atoms.

3,577,027

LOW NOISE IMAGE INTENSIFIER


Constantin S. Szegho, Chicago, Ill., assignor to Zenith Radio Corporation

Filed Aug. 30, 1968, Ser. No. 756,443

Int. Cl. H01j 39/00, 1/52

U.S. Cl. 313-101

8 Claims



An image intensifier of otherwise conventional construction is improved by an inwardly directed extension of the envelope, projecting from one edge of the focus electrode and extending toward the anode. The focus electrode is a conductive coating on the internal surface of the envelope and is, in effect, extended by a conductive coating applied to the inwardly facing surface of the envelope extension. That extension terminates in a metal ring. With the structure, the surface separation or leakage path between the metal ring termination of the focus electrode and the anode is substantially greater than that otherwise existing between those electrodes. The increased separation of these electrode elements along the surface of the envelope minimizes the tendency toward field emission and its contribution to background noise. A high resistance coating or an electron shield protects the shoulder of the envelope from electron bombardment and eliminates that source of background noise.

3,577,028 CHLORINE-OXYGEN TRANSMIT-RECEIVED STAGE TO OPERATE AT SHORT PULSE WIDTHS, LOW PULSE REPETITION FREQUENCIES, AND WIDE DUTY CYCLES


Harry Goldie, Randallstown, Md., assignor to the United States of America as represented by the Secretary of the Air Force

Filed Sept. 30, 1969, Ser. No. 862,203

Int. Cl. H01j 17/20

U.S. Cl. 313-223

1 Claim



The invention consists of a mixture of chlorine gas, (Cl_2), and oxygen gas, (O_2), to be used in place of pure Cl_2 gas in transmit-receive stages for stable operation at shorter radio frequency pulse widths, lower pulse repetition frequencies and wider duty cycles than was previously possible with Cl_2 gas alone. The mixture reduces the power necessary for ionization of the gas in the stage which decreases the random amplitude modulation on the leakage envelope and reduces the total spike energy output to the receiver making it possible to use more sensitive receivers without danger of their being damaged by spike leakage. The invention also provides a much faster recovery time than is possible with a mixture of Cl_2 gas and noble gas which yields the same leakage as that of the invention.

3,577,029

HIGH-PRESSURE ELECTRIC DISCHARGE DEVICE CONTAINING MERCURY, HALOGEN, SCANDIUM AND SAMARIUM


Frederic Koury, Lexington, and John F. Waymouth, Marblehead, Mass., assignors to Sylvania Electric Products, Inc.

Filed Nov. 29, 1968, Ser. No. 780,117

Int. Cl. H01j 61/18

U.S. Cl. 313-229

6 Claims



A metal arc lamp, which emits all visible colors in the spectrum and has good red rendition, contains a fill including mercury, halogen, scandium and samarium. The lamp is an efficient producer of white light.

3,577,030

INDUCTIVE ENERGIZING CIRCUIT FOR ARC PLASMA GENERATOR


Richard T. Cusick, Laurel, and Edgar A. Bunt, Kensington, Md., assignors to the United States of America as represented by the Secretary of the Navy

Filed Oct. 30, 1967, Ser. No. 678,973

Int. Cl. H01j 7/24

U.S. Cl. 315-111

6 Claims



The present invention generally relates to a method and apparatus for controlling the running, as well as the starting and shut-down operations, of a shutdown arc plasma generator or the like whose spaced-apart electrodes are energized from a circuit including an inductor which is connected in series with the electrodes and their energizing voltage source and which functions to damp out current pulsations, particularly those occurring at high mass flow rates within the arc plasma generator. Moreover, by maintaining the electrode arc discharge current constant, the arc rotation rate is also more uniform. Due to the fact that the series inductor causes current buildup in the electrode energizing circuit to be a function of time, suitable means are provided for delaying the establishment of the electrode arc discharge until such time as the circuit current has been built up sufficiently to insure that the arc discharge will be sustained. Moreover, means are also provided for decoupling the inductor from the remainder of the electrode energizing circuit, prior to the time when the electrode energizing circuit is open-circuited, so as to prevent arcing at the switch or circuit breaker means utilized to open the electrode energizing circuit.

3,577,031

MULTICOLOR OSCILLOSCOPE


Neil R. Welsh, and Richard E. McCormick, Dana Point, Calif., assignors to Telonic Industries, Inc., Laguna Beach, Calif.

Filed July 7, 1969, Ser. No. 839,240

Int. Cl. H01j 29/50, 29/52, 29/72

U.S. Cl. 315-13

23 Claims



An oscilloscope employing a multibeam, multicolor cathode-ray tube in which each of several input signals are displayed in a different color on the cathode-ray tube screen. The electron beams are rapidly scanned along the vertical axis to produce a vertical raster. Plural horizontal reference lines are displayed in discrete colors simultaneously with the signal traces by displaying the reference lines and input

signals as colored dots by individually intensity modulating the plural electron beams during their alternate up and down scans. Plural vertical reference lines are displayed in discrete colors simultaneously with the signal traces and the horizontal reference lines by energizing each of the beams for a single vertical trace at a predetermined position along the horizontal screen axis. Convergence circuits correct for both vertical and horizontal convergence, the horizontal convergence circuit being adapted to correct for convergence for differing horizontal drive waveforms. A vertical scan oscillator including a resonant circuit incorporating the vertical deflection coil provides a high frequency, high voltage scan without requiring large voltages across the amplification stage.

3,577,032

SERIES GAP LIGHTNING ARRESTER WITH ARC EXTINGUISHING CHAMBERS


Darrel D. McStrack, New Berlin, and Lawrence M. Barrage, South Milwaukee, Wis., assignors to McGraw-Edison Company, Milwaukee, Wis.

Filed Nov. 22, 1968, Ser. No. 778,060

Int. Cl. H01t 1/04, 5/02; H02h 1/04

U.S. Cl. 315-36

25 Claims



This disclosure relates to an overvoltage spark gap protective apparatus having a series of arc gaps each within a spark gap chamber in combination with an outer coil to elongate the arcs. Each chamber houses a pair of spaced electrodes disposed nonsymmetrically therein to define an arc extension or elongating chamber to the one side of the electrodes. The walls of the confining chamber are formed of a semiconductor with a rough surface and are contoured to define a decreasing cross section with terminates in a narrow sidewall in the outer edge of the arc-elongating chamber. The outer end portion of the confining chamber, and particularly at the narrow sidewall, is connected by suitable vent passageway means to the exterior of the apparatus. The electrodes are mounted within an arcuate wall and secured thereto by an anchor lug along which the arc root moves from the electrode. A single wire magnetic coil is wound concentrically about the spark gap chamber and is connected in series with the protective arc gap electrodes. The coil serves to elongate the arc into the confining chamber and outwardly to the narrow sidewall.

ERRATUM

For Class 315-39 see:
Patent No. 3,577,207

3,577,033

MAGNETRON DEVICE WITH COOLING FLUID FLOW IN LONGITUDINAL DIRECTION OF MAGNETRON TUBE

Ichiro Aoki, Kenji Iwasaki, Yokohama-shi; Tamaji Yoshihashi, Fukaya-shi; Tokujin Koinuma, Kawasaki-shi; Masao Kato, and Akihiro Fukatsu, Yokohama-shi, Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki-shi, Japan

Filed Mar. 13, 1969, Ser. No. 806,975

Claims priority, application Japan, Mar. 18, 1968, Nov. 20, 1968, 43/20768; 43/100759


Int. Cl. H01j 7/26, 25/50

U.S. Cl. 315-39.71

5 Claims

In a magnetron device including a magnetron tube and a

permanent magnet, cooling means is provided for cooling the magnetron tube and magnet, the cooling means defining



cooling fluid flow paths in a direction substantially in parallel with the longitudinal axis of the magnetron tube.

ERRATUM

For Class 317—2 see:
Patent No. 3,577,208


3,577,034

POWER INTERRUPTION CONTROL SYSTEM

George D. Bernhard, Lincoln Park, and Olek Schwarz, Plainfield, N.J., assignors to Anaconda Wire and Cable Company
Filed Sept. 29, 1969, Ser. No. 861,882
Int. Cl. H01h 47/18

U.S. Cl. 317—22

4 Claims



Where a plurality of processing operations are powered from a common electrical supply, shutdown of the operations by momentary interruptions of power is prevented by timing a main circuit relay not to open unless the interruption has a preselected time duration, shorting individual switches that have opened due to the interruptions, and breaking such shorts soon after the power has resumed.

3,577,035


POWER TRANSISTOR PROTECTION CIRCUIT

James M. Constable, Flushing, N.Y., assignor to Del Electronics Corp., Mount Vernon, N.Y.
Filed June 11, 1968, Ser. No. 736,231
Int. Cl. H02h 3/08, 3/20

U.S. Cl. 317—31

12 Claims

A protection circuit is operatively connected to a power transistor in a power supply control circuit. Means are provided to derive signals representative of the current flow through the power transistor and to the voltage across that



transistor, and to sum those signals. At excessive, unsafe current and voltage levels in the power transistor, that sum will

exceed a predetermined value, and will be effective to decrease the current flowing through the power transistor.

ERRATUM

For Class 317—98 see:
Patent No. 3,577,209

3,577,036

METHOD AND MEANS FOR INTERCONNECTING CONDUCTORS ON DIFFERENT METALIZATION PATTERN LEVELS ON MONOLITHICALLY FABRICATED INTEGRATED CIRCUIT CHIPS BY ALLOYING AN INTERCONNECTION PORTION OF EACH CONDUCTOR TO CONTIGUOUS PORTIONS OF ONE LOW RESISTIVITY REGION OF THE CHIP


John J. Curtis, Endwell, N.Y., and Carl E. Ruoff, Boston, Mass., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed May 5, 1969, Ser. No. 821,592

Int. Cl. H01l 19/00

U.S. Cl. 317—101

8 Claims



Minimum connection area and maximum reliability over long periods of use are achieved with the improved technique for interconnecting two-level metalization patterns overlying monolithic integrated circuit chips. A pair of metal conductors from each of two levels are joined to each other and are further separately joined to contiguous portions of an isolated low resistivity region in the chip. It has been found that each connection between metalization patterns of two different levels can be effected in an area as small as approximately two-tenths mil by five-tenths mil.

3,577,037

DIFFUSED ELECTRICAL CONNECTOR APPARATUS AND METHOD OF MAKING SAME

Americo R. Di Pietro, Katonah, N.Y., and Rudolf E. Thun, Carlisle, Mass., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed July 5, 1968, Ser. No. 742,886


Int. Cl. H01l 19/00

U.S. Cl. 317—101

1 Claim

An electrical connector having first and second metallization conductive patterns disposed on two faces, respectively, of a semiconductor substrate and one or more diffused interconnections within the substrate for connecting the conductive patterns in a predetermined manner. Circuit apparatus

having at least two semiconductor substrates, each of which has a plurality of integrated circuits of the monolithic type,



and each of which is mounted on a mutually exclusive face of the aforementioned diffused electrical connector.

3,577,038

SEMICONDUCTOR DEVICES

Charles R. Cook, Jr., North Palm Beach, Fla., assignor to Texas Instruments Incorporated, Dallas, Tex.


Division of Ser. No. 595,532, Nov. 18, abandoned, which is a continuation of Ser. No. 221,409, Aug. 31, 1962, abandoned.

Sept. 4, 1968, Ser. No. 757,438

Int. Cl. H01l 19/00

U.S. Cl. 317—101

9 Claims



A large number of different types of circuits made from a single semiconductor wafer configuration by varying the manner in which connections and leads are provided to the various regions of the wafer. A plurality of different circuit elements such as transistors, diodes, resistors and capacitors, are formed in a wafer semiconductor material, preferably by diffusion into the surface of a major wafer. These elements are arranged in a pattern adjacent the major face, with each region or electrode of each element coming to the surface at this face so that electrical connection may be made thereto. An insulating coating is provided on the major face of the wafer, with holes being formed in the coating where contacts are to be made, and conductive material is preferably deposited first over the entire face of the wafer and is later removed in a selected pattern to create the interconnections between components necessary for the selected circuit.

3,577,039

OPTICAL APPARATUS FOR FLAW DETECTION

Norman R. Sanford, Dayton, Ohio, and Heinrich J. Wieg, New Burlington, Ohio, assignors to The Bendix Corporation

Filed Jan. 28, 1969, Ser. No. 794,526


Int. Cl. H01h 47/24

U.S. Cl. 317—127

7 Claims

There is disclosed an optical apparatus for flaw detection in which a traveling line of light is reflected from the surface

of an object to an array of photocells. The outputs of the photocells are combined in a summing amplifier and changes in the output of the summing amplifier exceeding some predetermined amount above or below a normal value are



3,577,040

SOLENOID CONTROL CIRCUIT


Richard H. Campbell, Jr., Gifford, N.H., assignor to Pneumo Dynamics Corporation, Cleveland, Ohio

Filed Sept. 26, 1968, Ser. No. 762,723

Int. Cl. H02m 7/44; H01h 47/32

U.S. Cl. 317—148.5

3 Claims



An electronic circuit for actuating a solenoid load from an AC power source in a two-step sequence wherein a high DC voltage is initially applied to "pull-in" the solenoid armature and a lower voltage maintains the armature in a "hold" condition. Silicon-controlled rectifiers (SCR's) provide an electronic switching and rectification of the voltage for operating power. The circuit is controlled by an electrical signal which conditions the SCR's to provide operating voltage during alternate half cycles of the power source and a time delay circuit allows conduction of the "pull-in" SCR for only a few cycles of the power source.

3,577,041

OVERCURRENT RELAY CIRCUIT

Arne Kring, and Arne Johansson, Vasteras, Sweden, assignors to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden

Filed Mar. 10, 1969, Ser. No. 805,758


Int. Cl. H01h 47/32

U.S. Cl. 317—148.5

3 Claims

An overcurrent relay circuit, the pickup value of which is substantially independent of the DC-component in an asymmetrical alternating current, has an input transformer, the magnetic circuit of which is provided with air gaps while the secondary load of this transformer is high-resistive. To the

secondary winding of the transformer is connected a rectifier with a smoothing device connected to level-sensing circuit



and an output magnetic relay in the output circuit of the level-sensing circuit.


3,577,042

GATE CONNECTION FOR CONTROLLED RECTIFIERS
Thomas J. Roach, Palos Verdes Estates, Calif., assignor to International Rectifier Corporation, El Segundo, Calif.
Filed June 19, 1967, Ser. No. 647,038

Int. Cl. H011 1/14, 1/10

U.S. Cl. 317—235

6 Claims



A gate lead wire is connected to the third layer of a four-layer semiconductor wafer at a plurality of spaced regions. The wire is received in a slot in the upper expansion plate and extends from the center of the wafer and outwardly.

3,577,043


MOSFET WITH IMPROVED VOLTAGE BREAKDOWN CHARACTERISTICS

Robert C. Cook, Worcester Township, Pa., assignor to United Aircraft Corporation, East Hartford, Conn.
Filed Dec. 7, 1967, Ser. No. 688,766

Int. Cl. H011 1/14, 19/00

U.S. Cl. 317—235R

1 Claim



A low resistivity impurity barrier prevents inversion layer conduction between a MOSFET protection diode and the

source (or drain). Adjusting the spacing and impurity gradient between the impurity barrier and the protection diode results in control over reverse bias breakdown between the diode impurity and the low resistivity barrier, rather than with the substrate, whereby a lower, controlled breakdown voltage may be achieved.

3,577,044

INTEGRATED SEMICONDUCTOR DEVICES AND FABRICATION METHODS THEREFOR

William J. Armstrong; Albert M. Healy, Essex Junction, Vt., and Michael C. Duffy, Poughkeepsie, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Division of Ser. No. 532,754, Mar. 8, 1966, Pat. No. 3,476,224, Dec. 17, 1968, Ser. No. 758,166

Int. Cl. H011 19/00

U.S. Cl. 317—235

6 Claims



This invention is directed generally to integrated semiconductor devices including fabrication methods therefor and, more particularly, to insulator encapsulated, dielectrically isolated, integrated semiconductor devices including fabrication methods therefor.

3,577,045


HIGH EMITTER EFFICIENCY SEMICONDUCTOR DEVICE WITH LOW BASE RESISTANCE AND BY SELECTIVE DIFFUSION OF BASE IMPURITIES

William E. Engeler, Scotia, and Marvin Garfinkel, Schenectady, N.Y., assignors to General Electric Company
Filed Sept. 18, 1968, Ser. No. 760,526

Int. Cl. H011 3/00

U.S. Cl. 317—235

14 Claims



A transistor, such as NPN type, for example, is fabricated by first diffusing a heavily doped P-type base contact region into an N-type semiconductor layer epitaxially grown on a heavily doped N-type semiconductor wafer. Holes are etched through the base contact region into the N-type layer and strongly N-type semiconductor material containing both N-type impurities and faster diffusing P-type impurities is epitaxially grown so as to fill the holes. The wafer is then heated to diffuse the P-type impurities so as to form a base region of controlled thickness, simultaneously forming emitter-base and base-collector junctions. Emitter contact is made by contacting the material epitaxially grown in the holes. Other type semiconductor devices, such as semiconductor controlled rectifiers, may also be fabricated in this manner.

3,577,046

MONOLITHIC COMPOUND THYRISTOR WITH A PILOT PORTION HAVING A METALLIC ELECTRODE WITH FINGER PORTIONS FORMED THEREON

Joseph Moyson, Union Springs, N.Y., assignor to General Electric Company

Continuation-in-part of application Ser. No. 741,675, July 1, 1968, now abandoned. This application Mar. 21, 1969, Ser. No. 809,076


Int. Cl. H011 1/00, 15/00

U.S. Cl. 317—235R

3 Claims

A silicon-controlled rectifier or thyristor is provided having a control signal responsive pilot portion functionally

separated from, though structurally monolithic with, a main current carrying portion. Turning on of the pilot portion is controlled by a gate or control signal and the resulting pilot current through the pilot portion provides a high energy turn-on signal for the main portion, thereby enabling optimum



turn-on efficiency to be designed into the pilot portion while preserving high current carrying capacity in the main portion, with resulting high di/dt and dv/dt . The turn-on signal from the pilot thyristor may be distributed over a wide area of the main thyristor.

3,577,047

FIELD EFFECT DEVICE


George Cheroff, Hopewell Junction, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 15, 1969, Ser. No. 791,254

Int. Cl. H011 1/14

U.S. Cl. 317—235

5 Claims



A field-effect device is provided which comprises a field effect transistor of the insulated gate type. The device is capable of being used as a photodetector with a gain greater than unity. To this end, the transistor is biased in the "off" state by a substrate potential (source-to-substrate) resulting from the provision of an external voltage supply in the source-to-substrate loop. Upon the radiation of the source and drain junctions in the transistor, a current is caused to flow between the source and drain electrodes which result in a current gain in excess of unity.

ERRATUM

For Class 317—235 see:
Patent No. 3,577,210

3,577,048

PLURAL MOTOR ANTISLIP DRIVE CONTROL
Tore Nordin, Vasteras, Sweden, assignor to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden

Filed Dec. 26, 1968, Ser. No. 787,182


Claims priority, application Sweden, Dec. 27, 1967, 17793/67
Int. Cl. B61c 15/08

U.S. Cl. 318—52

2 Claims

A driving system for an electric locomotive has a plurality of parallel-connected direct current motors each connected

to a pair of wheels and connected by their armature windings to a variable alternating current source by a rectifier. Each motor has a field winding connected to a control current source to receive signals from the source to reduce the field. Each armature circuit feeds to a selection device a mag-



nitude proportional to the armature current. The selection device selects the greatest of these magnitudes, which is compared with each of the magnitudes proportional to the armature current, which signal is then fed to the field winding. The control signal is maintained below a certain maximum value.

3,577,049



SELF-COMMUTATED ELECTROMOTIVE DEVICE
Joseph P. Madurski, Royal Oak; Rex W. Presley, Livonia, and Ralph W. Rothfus, Southfield, Mich., assignors to The Bendix Corporation

Filed Sept. 26, 1967, Ser. No. 670,726

Int. Cl. H02k 29/00

U.S. Cl. 318—138

15 Claims



An electromotive device including a stator provided with electromagnets, an eccentric armature mounted for move-

ment by the electromagnets, and an output member which is concentric with the stator and is driven by the armature movement. A light-actuated electromagnet commutation system is disclosed. The armature of the electromotive device has epicyclic movement relative to both the stator and the output member with the two epicyclic movements cooperating to provide an integrated motor transmission unit.

3,577,050

VEHICLE DRIVEN BY SYNCHRONOUS MOTORS


William L. Ringland, Greendale; Manfred E. Neumann, New Berlin; Ernst K. Kaeser, West Allis; Thomas P. Gilmore, Wauwatosa, and Alois F. Geiersbach, Milwaukee, Wis., assignors to Allis-Chalmers Manufacturing Company, Milwaukee, Wis.

Filed Aug. 27, 1969, Ser. No. 853,462

Int. Cl. H02p 5/22

U.S. Cl. 318-146

58 Claims




The wheels of a vehicle are driven by inductor type synchronous motors having solid rotors without windings and commutators. A diesel on the vehicle drives a pair of high frequency rotating generators each of which supplies power to a pair of the synchronous motors. Power pedal means actuated by the operator derive a power signal proportional to the desired tractive effort for the vehicle. A separate electric drive for each motor includes means for deriving a control signal modulated at motor speed, a cycloconverter between each motor and its generator regulated by the control signal, tachometer means for deriving a speed signal which is a function of motor speed, and control means responsive to both the power signal and speed signal for regulating the magnitude and phase of the control signal so that the motor output power is constant over the speed range at a level in accordance with the power pedal setting.

Brake means actuated by the operator derive a brake signal, and the vehicle has means for shifting the phase of the control signals for all the motors to regeneratively brake them when the brake signal exceeds the power signal. The vehicle has travel direction selector means for shifting the phase of all the control signals to reverse the direction of motor rotation and thus propel the vehicle backward. The vehicle has manually operated means for setting a speed limit for the vehicle and means for deriving a speed limit signal which is additive to the brake signal to regeneratively brake the motors when vehicle speed exceeds the set speed limit. Turn compensation means increase the power supplied to the motors of the wheels on the outside of a turn and decrease the power supplied to the motors of the wheels on the inside of the turn as a function of the degree of turn and the magnitude of the power signal.

3,577,051
MOTOR SPEED CONTROL CIRCUIT HAVING
VARIABLE REACTIVE IMPEDANCE MEANS
Herbert R. Montague, Binghamton, N.Y., assignor to Power Concepts Corporation, Hallstead, Pa.
Filed May 19, 1969, Ser. No. 825,617
Int. Cl. H02p 3/24

U.S. Cl. 318-212

5 Claims




A speed control circuit for induction motors, such as the shaded-pole type, in which a pair of oppositely poled, parallel-connected diodes are connected between an alternating current source and the motor. There is a variable resistor in series with one of the diodes to vary the direct current component supplied to the motor and control the motor speed. A saturable reactor is included in series with the diodes to also vary the circuit impedance and thereby reduce the energy dissipation required at low motor speeds.

3,577,052
AC MOTOR CONTROL SYSTEM WITH SYNCHRONOUS
SPEED CHANGE
David Elvis Bauer, 1800 W. Gromerby #21, Anaheim, Calif.
Filed Oct. 17, 1968, Ser. No. 768,295
Int. Cl. H02p 5/28, 5/40

U.S. Cl. 318-230

32 Claims



A variable DC power source supplies a DC voltage to a static inverter which provides a three-phase alternating voltage output to drive an AC motor. A ring counter which is cycled by a voltage controlled oscillator generates three-phase timing signals to control the frequency of the inverter output. An input control signal is coupled to the voltage controlled oscillator through a rate control means. The rate control means generates a voltage output to the voltage controlled oscillator which is proportional to the input control signal and follows and adjustment of the input control signal from one level to another at a predetermined rate. The output generated by the rate control means also controls the magnitude of the DC voltage output of the DC power source. An adjustment of the input control signal results in a proportional change in the magnitude and the frequency of the inverter output.


3,577,053
BRUSHLESS DC MOTOR INCLUDING A VARIABLE
ATTENUATOR FED COMMUTATOR
Joe H. McGee, Charlottesville, Va., assignor to Sperry Rand Corporation
Filed Feb. 17, 1969, Ser. No. 799,851
Int. Cl. H02k 29/02

U.S. Cl. 318-254

3 Claims

A brushless DC motor includes a cylindrical reflecting member on the rotor. The cylindrical surface of the reflect-

ing member is divided into arcuate sections equal in number to the number of stator coils in the motor, and each having a different level of reflectivity. Light from a stationary source illuminates the adjacent arcuate section and is reflected onto a stationary sensing element. The input to the sensing ele-




ment is dependent upon the level of reflectivity of the section that happens to be adjacent the light source. A logic circuit directs the output of the sensing element to the particular stator coils corresponding to the intensity of light reaching the sensor at that time.

3,577,054
REVERSIBLE FAIL-SAFE WHEELCHAIR DRIVE
CONTROL CIRCUIT
Roger W. Banks, Costa Mesa, Calif., assignor to Everest & Jennings, Inc.
Filed Jan. 24, 1969, Ser. No. 793,747
Int. Cl. H02p 1/22

U.S. Cl. 318-257

7 Claims



A drive control circuit for a motorized wheelchair whereby the wheelchair occupant can select both the direction and the rate of motion of the chair by means of a joystick. In both directions the same motor control circuit is used. To prevent a runaway motor condition which might be caused by a component breakdown in the drive control circuit, means are provided to deenergize the wheelchair motor rapidly.


3,577,055
MEANS FOR REGENERATIVE BRAKING OF AN
IMPULSE-CONTROLLED DIRECT CURRENT SERIES
MOTOR
Fredrik Hermansson, deceased late of Sweden, by Ingrid Hermansson, Administrator, Vasteras, Sweden, assignors to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden
Filed June 3, 1968, Ser. No. 734,062
Claims priority, application Sweden, June 9, 1967, 8096/67
Int. Cl. H02p 5/04

U.S. Cl. 318-302

1 Claim

An arrangement for regenerative braking of a thyristor-controlled DC series motor used as driving motor for street cars. During braking possible excess energy is consumed by a

resistor connected in parallel with the motor. The resistor is connected in series with a switching means for connecting




and disconnecting the resistor at an upper and lower voltage level, respectively.

3,577,056
DC MOTOR SERVOSYSTEM
Kazunobu Tsujikawa, Tokyo, Japan, assignor to Sony Corporation, Shinagawa-ku, Tokyo, Japan
Filed Mar. 12, 1969, Ser. No. 806,352
Claims priority, application Japan, Mar. 13, 1968, 43/16283
Int. Cl. H02p 5/16

U.S. Cl. 318-314

6 Claims



In order to control the phase and speed of a DC motor, particularly employed for driving the rotary magnetic heads of a video tape recorder, the output of a signal generator having a frequency corresponding to the rotational speed of the motor is fed through a demodulation circuit to a clamping circuit, and the rotational speed of the motor is controlled in accordance with variations in an output level resulting from the slicing of the output of the clamping circuit at a reference level. Simultaneously, the rotational position of the DC motor is detected and compared with an external reference signal, for example, the synchronizing signal of a television signal, and the clamp level of the clamping circuit is controlled by the output resulting from the comparison, thereby to drive the motor in synchronism with the external reference signal.


3,577,057
SYSTEM FOR CONTROLLING THE SPEED OF A
MOTOR UTILIZING PULSE WIDTH MODULATION
George A. Dyer, Santa Ana, and Emil Kohler, Anaheim, Calif., assignor to North American Rockwell Corporation
Filed Sept. 26, 1969, Ser. No. 861,397
Int. Cl. H02p 7/14

U.S. Cl. 318-328

8 Claims

An input voltage is summed with a voltage picked off from a polyphase motor for driving a voltage-controlled oscillator. The frequency of the output signal from the oscillator is dependent on the magnitude of the summed voltage. The pulse width is modified within a predetermined range as a function of the frequency and is converted into three phase signals

which are summed and applied to the stator windings of a motor. The signal across the windings has an optimum voltage for deriving a negative feedback signal that dominates the



age and frequency ratio which is varied when the speed of the motor is changed.

3,577,058

SELF-SYNCHRONOUS MOTOR CONTROL INCLUDING AN AC TRANSMITTER, A DC RECEIVER, AND A UNIQUE AMPLIFIER-DEMODULATOR


Richard L. Cohen, Old Bridge, N.J., assignor to The Bendix Corporation

Filed Dec. 19, 1968, Ser. No. 785,133

Int. Cl. G05b 1/12

U.S. Cl. 318-691

5 Claims



An indicating system including AC synchro transmitters providing AC signals corresponding to a condition. The AC signals are demodulated by phase-sensitive demodulators and the rectified signals are applied to DC synchro receivers operating an indicator for indicating the condition.

3,577,059

ELECTRIC POWER APPARATUS COMPRISING CONVERTER, FILTER, REGULATOR, AND MEANS FOR DYNAMICALLY STABILIZING THE FILTER

Fred W. Kelley, Jr., Media, Pa., assignor to General Electric Company

Filed Mar. 17, 1969, Ser. No. 807,867

Int. Cl. H02m 1/14, 7/12

U.S. Cl. 321-10

6 Claims

In electric power apparatus including a voltage-regulated converter and a filter supplying a load circuit with relatively smooth unipolarity voltage of desired magnitude, the filter is

dynamic response of the regulator to source or load disturbances.

3,577,060

ALTERNATING CURRENT POWER SUPPLY EMPLOYING PROGRAMMED TURN-ON AND TURN-OFF


William E. Richeson, Jr., Fort Wayne, Ind., assignor to The Magnavox Company, Fort Wayne, Ind.

Filed Mar. 10, 1969, Ser. No. 805,729

Int. Cl. H02m 1/18; H02h 7/14; H02m 5/44

U.S. Cl. 321-11

6 Claims



A reliability of a high-power alternating power supply wherein a low-power alternating current is used to convert a high-power direct current to said high-power alternating current is improved, when driven by sources and when driving loads that are inductive or inductively coupled, by the use of a programmed turn-on and turnoff procedure wherein the energy supplied to a reactive load is gradually increased and diminished respectively.

3,577,061

CONTROL APPARATUS FOR ELECTRIC ALTERNATORS

Peter J. Wyles, Stamford, England, assignor to Newage Lyon Limited, Stamford, England

Filed July 19, 1968, Ser. No. 746,108

Claims priority, application Great Britain, July 19, 1967,

34274/67


Int. Cl. H02p 9/08, 9/14

U.S. Cl. 322-27

1 Claim

In automatic regulating apparatus for an electric alternator a main thyristor is connected in series with an excitation winding across the alternator terminals and is controlled by a sensing circuit to which a signal corresponding to the alternator output voltage is passed. A saturable current transformer

has a primary winding in the load circuit of the alternator and a secondary winding connected through a rectifier to the



excitation coil to build up the excitation when the alternator has to start up under a permanently connected load, without interfering with control once the voltage has built up.

3,577,062

ZENER DIODE REFERENCE CIRCUIT INDEPENDENT OF INPUT VOLTAGE CHANGES


Eric J. Hoffman, Baltimore, Md.

Filed Feb. 19, 1969, Ser. No. 800,917

Int. Cl. G05f 1/44

U.S. Cl. 323-8

6 Claims



A Zener diode voltage reference circuit whose output is maintained at exactly the Zener voltage irrespective of changes in the input voltage. More particularly, since the voltage appearing across a Zener diode fluctuates slightly with changes in the Zener current, exact regulation is accomplished by maintaining the current flowing through the diode at a constant value; furthermore, the Zener current is held constant by adding to the circuit a second Zener diode which serves to extract from the first Zener diode all the current which would cause a voltage fluctuation.

3,577,063

VOLTAGE REGULATOR WITH INSIGNIFICANT CURRENT DRAIN

Edward T. E. Hurd, III, Willingboro, N.J., assignor to Honeywell Inc., Minneapolis, Minn.


Filed Feb. 3, 1969, Ser. No. 795,886

Int. Cl. G05f 3/08

U.S. Cl. 323-16

5 Claims

A voltage-regulating buffer, designed for use with a two-wire current signal transmitter, for limiting the line voltage which may be applied to the transmitter without adversely affecting the current signal from the transmitter. The buffer in-



cuit includes a series connected constant current unit and constant voltage unit.

3,577,064

AUTOMATIC ERROR DETECTION AND INDICATION IN A REMOTELY PROGRAMMABLE REGULATED POWER SUPPLY


Sarkis Nercessian, Long Island City, N.Y., assignor to Forbro Design Corp., New York, N.Y.

Filed Mar. 12, 1969, Ser. No. 806,385

Int. Cl. G05f 1/58

U.S. Cl. 323-20

12 Claims



A programmable regulated power supply includes internal control circuits for determining the output voltage and digital visual read-out indicators showing the output voltage called for by the control circuits. In the operation of this power supply there are a number of predetermined circuit conditions which may result in the actual output voltage being different from the called for voltage. These conditions are detected and indicated individually and collectively. Certain of these conditions when detected serve to also extinguish the visual indicators.

3,577,065

SWITCHING REGULATOR HAVING A DIODE CONNECTED TO AN INTERMEDIATE TAP OF A CHOKE

Franz Ludwig Putzrath, and Charles Allan Michel, Haddonfield, N.J., assignors to RCA Corporation

Filed Nov. 21, 1968, Ser. No. 777,654


Int. Cl. G05f 1/56

U.S. Cl. 323-22

9 Claims

A switching regulator having a switching device, a choke and a load connected in series with a pair of input terminals. The regulator further includes a diode tapped back on the choke to prevent current spikes at the output. By tapping the diode back on the choke, a voltage is induced in the tapped

portion at the time the switch becomes short circuited and this voltage limits the current flowing through the switch dur-



ing the time necessary for the diode to become reversed biased.


3,577,066

ELECTRICAL CONTROL SYSTEM

Harold A. McIntosh, South Pasadena, Calif., assignor to Robertshaw Controls Company, Richmond, Va.
Filed Mar. 7, 1969, Ser. No. 805,138
Int. Cl. G05f 3/02; G01r 17/02

U.S. Cl. 323-69

6 Claims



An electrical control system for controlling a function and comprising a flexible, variable resistor formed to provide a plurality of adjacent portions in heat exchange relationship with one another and adapted to move toward or away from one another, depending upon the direction of flexing of the resistor. The variable resistor is flexible axially to adjust the spacing between the adjacent portions to thereby vary the mutual heat transfer therebetween. This moves the electrical resistance of the flexible resistor to effect changes in the rate of current flow therethrough. A control means in circuit with the resistor is operative in response to said current changes to control the function.

3,577,067

PERSISTENT MODE SUPERCONDUCTIVE ORTHOGONAL GRADIENT CANCELLING COILS

Harry E. Weaver, Jr., Portola Valley, Calif., assignor to Varian Associates, Palo Alto, Calif.

Filed May 11, 1966, Ser. No. 549,353

Int. Cl. G01n 27/28


U.S. Cl. 324-0.5

5 Claims

A superconductive magnet is disclosed together with superconductive gradient cancelling coils for homogenizing the magnetic field produced by the magnet. A gyromagnetic spectrometer is also disclosed which employs the magnetic field produced by the superconductive magnet. The gradient cancelling coils include a plurality of turns of a superconductor arranged adjacent the region of the magnetic field to be corrected, such magnetic field having certain residual magnetic field gradients therein to be cancelled.

Means are provided for energizing the gradient cancelling coils with electrical currents in such a configuration as to define orthogonal superconductive gradient cancelling coils.

A superconductive connection is formed across the ends of the coil structure for closing the superconductive circuit across the ends of the coil to form a closed superconductive circuit, whereby the superconductive gradient cancelling coils may be operated in a persistent mode for enhanced sta-



bility and reduced power consumption. In one embodiment, a DC transformer is provided which has a primary winding coupled to the main magnetic field of the magnet and a secondary winding which serves to energize the gradient cancelling coils. In this manner, the gradient cancelling field components change their intensity in proportion to changes in intensity of the main magnetic field to maintain a corrected field.

3,577,068

OPTICALLY PUMPED MAGNETIC GRADIOMETER


Richard C. La Force, Grosse Point, Mich., assignor to Atlantic Richfield Company

Filed Aug. 27, 1968, Ser. No. 755,599

Int. Cl. G01r 33/08

U.S. Cl. 324-0.5

7 Claims



Apparatus for determining the gradient of the earth's magnetic field over a zone. The absorption magnetometer is encircled by a coil of wire coupled to a low frequency oscillator. The turns of the coil are unevenly spaced along the length of the cell and are canted with respect to the cell so that the magnetic field caused by current in the coil is inhomogeneous and offsets the gradient in the earth's magnetic field. The magnetometer's radio frequency output signal is amplitude modulated by a signal having the frequency of the oscillator output and having an amplitude proportional to the gradient of the earth's magnetic field. This modulation signal is amplitude detected and then phase detected using the oscillator output as a reference. The phase detector output is a signal indicative of the earth's magnetic field gradient.

3,577,069

OPTICAL RESONANCE CELLS CONTAINING AN ALLOY OF AN ALKALI METAL WITH ANOTHER METAL

Leon Malnar, and Henri Brun, Paris, France, assignors to CSF Compagnie Generale De Telegraphie Sans Fil

Filed Feb. 3, 1969, Ser. No. 796,355

Claims priority, application France, Feb. 5, 1968, 138,698


Int. Cl. G01r 33/08

U.S. Cl. 324-0.5

11 Claims

An optical resonance cell containing an alkali vapor to be optically pumped and comprising a bulb communicating with

the cell. An alloy of the alkali metal with another metal is placed in the bulb. This metal is so selected that the atoms of



its vapor produce a disturbance as small as possible of the spin function of the alkali atoms, by spin exchange collisions.

3,577,070

METHODS OF AND SYSTEMS FOR PERFORMING TESTING OF CONDUCTORS FOR DEFECTIVE INSULATION AND CONTINUITY


Howard C. Whitekettle, Jr., Towson, Md., assignor to Western Electric Company Incorporated, New York, N.Y.

Filed Apr. 8, 1969, Ser. No. 814,341

Int. Cl. G01r 31/02

U.S. Cl. 324-51

10 Claims



Methods of and systems for applying a voltage difference between at least two adjacent insulated conductors, testing for electrical characteristics of the insulated conductors as a result of the application of the voltage difference therebetween which are indicative of defective insulation and detecting for an electrostatic field adjacent to an end of a particular one of the conductors to determine if the one conductor is continuous.

3,577,071

MICROWAVE MATERIAL TESTER


Jack T. Collins, Boulder, Colo., assignor to Automation Industries, Inc., Century City, Calif.

Continuation of application Ser. No. 573,252, Aug. 18, 1966, now abandoned. This application Jan. 6, 1969, Ser. No. 789,203

Int. Cl. G01r 27/04

U.S. Cl. 324-58.5

2 Claims



A nondestructive testing device is described wherein a workpiece is coupled to a microwave resonant cavity. In addition to the sampling cavity, a tuneable reference resonant cavity may be employed. A modulated tuneable klystron

energizes both resonant cavities. A first phase-sensitive amplifier, responsive to the test cavity, controls a servosystem tuning the reference resonant cavity while a second phase-sensitive amplifier responsive to the reference resonant cavity tunes the klystron so that both cavities and the klystron are tuned alike after coupling of the workpiece. A digital readout is provided to indicate the tuning of the reference cavity. Alternatively, a single resonant cavity is coupled to a swept frequency klystron, with a filamentary workpiece passed through the cavity. The resultant Q of the cavity, and changes in resonant frequency thereof are indicated by an oscilloscope display.

3,577,072

BRIDGE CIRCUIT FOR DIFFERENTIALLY MEASURING CAPACITANCE


Arthur Miller, Chestnut Hill, Mass., assignor to Hewlett-Packard Company, Palo Alto, Calif.

Filed Nov. 19, 1968, Ser. No. 777,033

Int. Cl. G01r 27/26, 27/00

U.S. Cl. 324-60C

6 Claims



An AC bridge includes two variable capacitors and two complementary conductivity transistors. The two transistors conduct during opposite one-half cycles of the AC bridge excitation voltage to alternately couple the two capacitors in circuit with a load resistor. When either one of the capacitors is not coupled to the load, it is clamped to a source of reference potential by a diode. The output across the load is proportional to the difference in value between the two capacitors.

3,577,073

APPARATUS FOR AUTOMATED COMPUTER MAINTENANCE COMPRISING MEANS FOR VARYING THE INPUT SIGNAL SWITCHING THRESHOLD VOLTAGE FOR ANY OF A PLURALITY OF ELECTRONIC CIRCUITS


Seymour R. Cray, Chippewa Falls, Wis., assignor to Control Data Corporation, Minneapolis, Minn.

Filed Feb. 18, 1969, Ser. No. 800,105

Int. Cl. G01r 15/12

U.S. Cl. 324-73

7 Claims



An apparatus for providing the automated maintenance checkout of large-scale computers by selectively stressing the

operating voltage margins of any of the plurality of electronic logic modules comprising the computer is disclosed. The selective stressing is accomplished under the control of an auxiliary data processing system.

3,577,074

BRIDGE MEASURING CIRCUIT


Julius Praglin, Beachwood, Ohio, assignor to Keithley Instruments, Inc., Solon, Ohio

Filed Oct. 15, 1968, Ser. No. 767,745

Int. Cl. G01r 17/02, 27/02

U.S. Cl. 324-98

2 Claims



A measuring circuit is disclosed having a bridge with the input terminals connected to the positive and negative output terminals of a regulated power supply. The difference in potential between the output terminals of the bridge is adapted to be sensed by a null detector having a ground reference terminal provided by the power supply. In the null detector an indicator is connected to the bridge output terminals through an RC coupling network and MOS field-effect devices which are alternately rendered conductive by an oscillator. The polarizing voltage provided by the power supply for the bridge has a common ground with the null detector.

3,577,075

DIGITAL SERVO INDICATOR


Algirdas J. Krygeris, Richmond Heights, Ohio, assignor to Gilmore Industries, Inc., Cleveland, Ohio

Filed Nov. 14, 1968, Ser. No. 775,664

Int. Cl. G01r 17/06, 1/02

U.S. Cl. 324-99

4 Claims



An automatic, null-balance potentiometric device having a digital readout in which the rate of balance is proportional to the magnitude of the error and balance is approached asymptotically on an exponential curve, such device providing improved damping characteristics and noise reduction whereby accurate resolution to a hundredth of a microvolt is obtained.

3,577,076

AUTOMATIC RANGE SCALE SELECTION APPARATUS FOR A MEASURING DEVICE


James E. Frushour, Endwell; Earnest H. Millham, Apalachin, and James E. Ortloff, Harpursville, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sept. 5, 1968, Ser. No. 757,715

Int. Cl. G01r 15/08; G04f 9/00

U.S. Cl. 324-115

5 Claims



Apparatus for automatically selecting the proper scale in a measuring instrument wherein a transducer or sensor is provided for each required scale and all respond concurrently by producing an electrical analog output signal at various rates proportional to the input condition or property. A selection circuit compares the output levels with sensor limits and thereafter connects the output signal of the highest nonsaturated sensor with an analog-to-digital converter or indicating means.

3,577,077

APPARATUS FOR MEASURING THE AMOUNT OF MODULATION RESPONSE TO A DIFFERENTIAL INPUT SIGNAL


Sylvan A. Walliser, and Claire F. Asquith, Huntsville, Ala., assignors to the United States of America as represented by the Secretary of the Army

Filed Dec. 13, 1968, Ser. No. 783,645

Int. Cl. G01r 7/00

U.S. Cl. 324-140

7 Claims



A modulation meter for comparing the amount of flow in one output port of a gas amplifier with the flow in another output port of the amplifier. An input signal is fed from the output ports by way of a differential pressure transducer to the meter where a high impedance buffer stage responds to the signal to activate a high gain stage. The input signal response is coupled through the gain stage and an impedance matching or buffer stage to a differential amplifier. The differential amplifier responds to signal changes by varying the current controlled to a load meter that indicates the gas flow. All stages are transistorized and the differential amplifier has an emitter follower output circuit that prevents loading of the differential amplifier by the meter.

3,577,078

ELECTRICAL MEASURING OR INDICATING INSTRUMENT

Willy Kisselmann, Grunwald; Fritz Rumpelein, Munich; Paul Kopf, Unterhaching, and Franz Landbrecht, Unterhaching, Germany, assignors to Agfa-Gevaert Aktiengesellschaft, Leverkusen, Germany

Filed Apr. 1, 1969, Ser. No. 811,739


Claims priority, application Germany, Apr. 3, 1968,

P 17 66 101.7

Int. Cl. G01r 1/00

U.S. Cl. 324-154

9 Claims



A moving-coil instrument wherein the end positions of the pointer which shares oscillatory movements of the coil are determined by two elastic paper strips. The strips have inner portions which are received in slots provided therefor in a support which constitutes or includes the instrument housing, and outer portions having transversely extending edges which abut against the pointer when the latter assumes the corresponding end position. The strips are adjustable with reference to the support to facilitate calibration of the instrument and are thereupon bonded to the support.

3,577,079

WATCHMAN'S RADIO LOCATION INDICATING SYSTEM

Kenneth John Horstmann, 14 Park Lane, Bath, Somerset, and Colin Grahame Douglas, "Stoneybroke" Watergate, Colerne, Wiltshire, England

Filed May 31, 1968, Ser. No. 733,675


Claims priority, application England, May 31, 1967,

25198/67

Int. Cl. H04b 1/02

U.S. Cl. 325-53

4 Claims



In a location system a radio transmitter carried by a security guard or watchman has a modulator and an oscillator, but without the frequency determining components. At various points which the guard is required to visit are sets of frequency determining components carried in wall boxes, each set of components providing a different modulating frequency. The guard plugs in a lead from the transmitter at each point and the modulated carrier from the transmitter is received at a remote location, demodulated, and the point at which the modulating frequency was generated is identified.

ERRATUM

For Class 325-73 see:
Patent No. 3,577,073

3,577,080

REMOTE CONTROL SYSTEM FOR OPERATION OVER SAME AUDIOCHANNEL PROVIDING VOICE SIGNALS BETWEEN REMOTE STATION AND BASE STATION


Gary A. Cannalte, Hoffman Estates, Ill., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Dec. 20, 1968, Ser. No. 785,526

Int. Cl. H04b 1/60

U.S. Cl. 325-183

20 Claims



Remote control system for controlling radio at base station from remote point over single audio channel which provides voice signals between remote and base stations, and which does not require DC continuity and operates within a fixed maximum frequency. A short burst of high amplitude guard tone is applied over the channel from the remote station to the base station to actuate a control at the base station which renders the controls thereat operative and blocks transmission of audiosignals from the base station to the channel. The remote station then applies lower amplitude tones to the audiochannel to actuate controls at the base station, with guard tone being applied continuously at low level during application of audio signals from the remote station to the base station. The base station responds to termination of tone signals (or to disconnect tones) to provide disconnect action, reset the controls and permit the base station to apply signals to the audio channel.

3,577,081

METHOD AND ARRANGEMENT FOR SYNCHRONIZATION OF THE SUPPLEMENTARY CARRIER FREQUENCY OSCILLATOR


Hansrichard Schulz, Villingen, Black Forest, Germany, assignor to Saba Schwarzwald Apparate-Bau-Anstalt August Schwer Sohne GmbH, Villingen, Schwarzwald, Germany

Filed June 26, 1968, Ser. No. 740,238

Int. Cl. H04b 1/68

U.S. Cl. 325-329

6 Claims



A suppressed carrier single sideband signal is received, converted to an intermediate frequency, and fed to a preferably square law detector for generating a reference

signal derived from the difference in frequency between a harmonic and the fundamental of the modulation frequency, or between two harmonics of the modulation frequency. The intermediate frequency signal is also fed to a mixer where it is combined with the supplementary carrier frequency oscillator signal thus generating a low frequency signal whose exact frequency depends both on the modulation signal frequency and any difference in frequency between the transmitter carrier frequency and the receiver supplementary carrier frequency. The reference signal and low frequency signal are compared in a phase discriminator yielding an error signal which is applied to a reactance stage which in turn serves to change the frequency of the supplementary carrier frequency oscillator in the receiver.

3,577,082


CARRIER FREQUENCY PHASE-ADJUSTMENT DEVICE

Alex Honore Lautier, Vence; Henri Jean Nussbaumer, La Gaude, and Jean Marc Pierret, Falcon Nice, France, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Mar. 5, 1969, Ser. No. 804,570
Int. Cl. H04b 1/16

U.S. Cl. 325-416

6 Claims



A phase synchronizing device for the carrier of a single sideband transmission system. Two pilot frequencies are transmitted with the synchronization signal and are decoded at the receiver to provide a signal indicating the correct phase of the demodulating carrier signal. The transmitted carrier signal controls the frequency of an oscillator and the initial phase of the regenerated carrier signal is set at the start of reception by the decoded pilot signals.

3,577,083

MODIFIED LATCH CIRCUIT SPECIFICALLY FOR SEARCH TUNING ARRANGEMENT

James S. Adams, Batesville, Ind., assignor to The Magnavox Company, Ft. Wayne, Ind.


Filed Aug. 5, 1968, Ser. No. 750,079
Int. Cl. H04b 1/32

U.S. Cl. 325-471

10 Claims

A latch circuit is provided for a reversible motor, particularly for a search tuning motor on a television set, in which a relay is provided for each direction of rotation of the reversible motor and which relays can be energized manually or by remote control, and a holding circuit is provided for each relay comprising the collector-emitter circuit of a pair of serially arranged transistors, the second transistor in each pair of serially arranged transistors being the same transistor and being normally nonconductive and becoming conductive upon energization of the motor to run in either direction.

The energization circuit to the motor is deenergized when



the motor reaches a predetermined position and this also interrupts the holding circuit which is at that time effective.

3,577,084


COMPUTER SOUND GENERATOR

Samuel M. Atcherson, Bowie, and Robert P. Rodgers, Silver Spring, Md., assignors to Singer-General Precision, Inc., Binghamton, N.Y.

Filed Nov. 3, 1969, Ser. No. 873,193
Int. Cl. H03k 23/00

U.S. Cl. 328-14

10 Claims



The generation of desired sounds and sound waveforms is useful in many fields. For this reason there have been many sound generators devised over the years. The system of this invention utilizes an automatic programming device to control the generation of a large variety of different sounds and sound waveforms. The apparatus comprises a flip-flop or similar device having a plurality of stable conditions. The flip-flop is alternately placed in each of its stable operative states under the control of an automatic programming device. The duration of a complete flip-flop cycle is determinative of the frequency of the generated waveform. The flip-flop output which may be processed through wave-shaping circuitry is subsequently amplitude controlled by a digital ladder attenuator. One automatic programming device which has been useful in this system is a general-purpose digital computer. The system described herein is an improvement over the systems described in the copending patent applications Ser. No. 707,615, SOUND GENERATOR, filed in the names of William E. Beavers, Jr. and William H. Sturdevant, and Ser. No. 710,237, COMPUTER SOUND GENERATOR, filed in the names of Robert A. Atchison, Robert E. Lutolf, and Edward F. Magee.

3,577,085

QUINARY REDUCTION STAGE AND FORWARD-REVERSE COUNTER

Theo Stutz, Geerlisbergstrasse, 8303 Bassersdorf, Switzerland
Continuation-in-part of application Ser. No. 679,966, Aug.

24, 1964, now abandoned, Continuation-in-part of application Ser. No. 538,663, Aug. 24, 1964, now abandoned,

Continuation-in-part of application Ser. No. 392,998, Aug. 24, 1964, now abandoned, Continuation-in-part of

application Ser. No. 279,039, May 6, 1963, now abandoned.


This application Jan. 9, 1969, Ser. No. 856,225

Int. Cl. H03k 21/00

Claims priority, applications Switzerland, May 4, 1962, Aug. 23, 1963, Apr. 7, 1965, Aug. 3, 1966, 5370/62, 10417/63, 4849/65 and 12559/66

U.S. Cl. 328-42

14 Claims



Two forms of a quinary reduction stage, for reducing the frequency of an input multiphase binary signal by a factor of five are illustrated. One corresponds to the use of a substantially minimum number of elements, while the other corresponds to use of identical binary circuits, all having the same number of inputs. By counting quarter periods of the input signal and half periods of the output signal, a decade reduction stage results. Further, each quinary reduction stage may be connected with a binary reduction stage thus furnishing a decade reduction stage, which may interconnect with other similar ones to constitute a decade forward-reverse counter.

3,577,086

GENERATOR OF DELAYED SEQUENCES EMPLOYING SHIFT REGISTER TECHNIQUES


Ivan M. Kliman, Glen Head, and Harold Smola, Carle Place, N.Y.

Filed Sept. 30, 1968, Ser. No. 763,677

Int. Cl. H03k 5/00

U.S. Cl. 328-62

4 Claims



The circuitry involves a plurality of groups of shift register stages connected in cascade with temporary storage stages connected between each group of stages. A reference sequence is applied serially to the generator input and a number of substantially equally delayed replicas thereof are obtained from taps spaced along the generator, the number of the taps being different from the number of bits of the input reference sequence. In order to accomplish this, several different shift pulse trains must be applied to different of the groups of stages, the different shift pulse trains having different time delays or phases.

3,577,087

SEQUENCE "AND" GATE WITH RESETTING MEANS


Thomas B. Martin, Delran, and Henry J. Zadel, Haddonfield, N.J., assignors to Radio Corporation of America

Filed Sept. 27, 1968, Ser. No. 763,196

Int. Cl. H03k 5/20

U.S. Cl. 328-110

6 Claims



Circuit for sensing two signals and producing an output when the signals are in sequence, with resetting means to inhibit the output after a specific time interval has elapsed between the two signals or whenever an intervening other signal occurs.

3,577,088

SINE-COSINE TO MAGNITUDE-PHASE ANGLE CONVERTER


William B. Goggins, Jr., Winchester, Mass., assignor to the United States of America as represented by the Secretary of the Air Force

Filed Feb. 3, 1969, Ser. No. 795,796

Int. Cl. H03d 3/06

U.S. Cl. 328-134

4 Claims



An analogue device for converting two voltages (AC or DC) each proportional to quadrature components $E \sin \Phi$ and $E \cos \Phi$ to two voltages, one proportional to E and one proportional to the phase angle Φ .

3,577,089

DATA TRANSMISSION TIME DOMAIN EQUALIZER

Etienne Gorog, White Plains, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 14, 1966, Ser. No. 520,798

Claims priority, application France, Feb. 26, 1965, 7545


Int. Cl. H03k 5/00

U.S. Cl. 328-165

3 Claims

Apparatus for equalizing digital data which has been distorted in transmission. The value of the signal at each instant of time is delayed and modified by a weighting junction and added to the value of the signal input at the next instant of time in an analog adder. The output of the analog adder is applied to a series of cascaded digital correction devices, the

outputs of which are each connected through weighting junctions and switches to the analog adder to control the



equalization of the signal input. The equalized signal output is taken from the last of these cascaded correction devices.

3,577,090

FAST SETTLING, STABLE AMPLIFIER CIRCUIT


William C. Montgomery, Jr., Houston, Tex., assignor to Shell Oil Company, New York, N.Y.

Filed Aug. 25, 1969, Ser. No. 852,840

Int. Cl. H03f 1/00

U.S. Cl. 330-69

5 Claims



Two operational amplifiers are connected in series. The first operational amplifier has a very stable drift characteristic and a feedback capacitor such that it has a very low frequency breakpoint. The second operational amplifier has a very fast response characteristic but may have a poor drift characteristic. A feedback impedance connects the output of a second operational amplifier to the input of the first operational amplifier and the input to the entire circuit is through an input impedance to the inverting input of both the first and second operational amplifiers.

3,577,091

REMOTE CONTROLLED MONITOR CIRCUIT

Francis Rachal, Baltimore, and Donald B. McKone, Glen Burnie, Md., assignors to the United States of America as represented by the Secretary of the Air Force

Filed May 26, 1969, Ser. No. 827,553


Int. Cl. H03f 3/16, 3/18

U.S. Cl. 330-24

2 Claims

An electronically operated remotely controlled circuit.

The circuit provides desired logarithmic volume control from



3,577,092

SIGNAL PATH SERIES STEP-BIASED MULTIDEVICE HIGH-EFFICIENCY AMPLIFIER


Arthur P. Kubicz, Richardson, Tex., assignor to Collins Radio Company, Cedar Rapids, Iowa

Filed July 9, 1968, Ser. No. 743,525

Int. Cl. H03f 3/20, 3/68

U.S. Cl. 330-124

7 Claims



A high-efficiency transformerless amplitude modulation system with an audio frequency power amplifier having at least two amplifier segments with at least one amplifier device in each, a different level voltage power supply for each amplifier segment, and a bias step between adjacent amplifier segments, and with a modulation output direct DC connection from the AFPA to the RF power amplifier of the system.

3,577,093

MEANS FOR OBTAINING MULTIPLE COHERENT-LASER APERTURES


George R. Simpson, Webster, N.Y., assignor to the United States of America as represented by the Secretary of the Army

Filed Sept. 13, 1968, Ser. No. 759,594

Int. Cl. H01s 3/05

U.S. Cl. 331-94.5

6 Claims



Multiple coherent-laser apertures produced by directing

laser beams through a prism for optical interaction and coherence.

3,577,094

FRESNEL ZONE LASER COUPLING MIRROR


Richard G. Tomlinson, Glastonbury; Clyde O. Brown, Newington, and Alan F. Haught, Glastonbury, Conn., assignors to United Aircraft Corporation, East Hartford, Conn.

Filed Sept. 27, 1968, Ser. No. 763,222

Int. Cl. H01s 3/08; G02b 5/18

U.S. Cl. 331-94.5

1 Claim



A laser cavity includes a spherical mirror and a flat mirror, the flat mirror having a plurality of holes arranged in a Fresnel zone pattern so as to provide distributed output coupling having a near-field focal point; alternatively, the flat mirror may comprise a pattern of reflecting material on a light-transmissive medium.

3,577,095

SEMIELLIPTICAL PUMP CAVITY


Richard C. Benner, Palos Verdes Estates, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.

Filed Dec. 28, 1966, Ser. No. 606,521

Int. Cl. H01s 3/00

U.S. Cl. 331-94.5

5 Claims



Cavity structure having a first section with a highly specularly reflective semielliptical inner surface and a second section of relatively high thermal conducting material enclosing the semielliptical inner surface along its longitudinal dimension. The second section has a relatively flat inner surface in which two longitudinal grooves are disposed, one for carrying a laser rod and the other carrying an elongated pump lamp. The second section also has a rod-clamping portion as part of the sidewall of the laser-rod-holding groove, the clamping portion extending above the second section's flat inner surface for holding the laser rod in both mechanical and thermally conducting contact with the second section.

3,577,096

TRANSVERSE DISCHARGE GAS LASER

William B. Bridges, Thousand Oaks, and Peter O. Clark, Malibu, Calif., assignors to Hughes Aircraft Company, Culver City, Calif.

Filed Nov. 1, 1967, Ser. No. 679,704


Int. Cl. H01s 3/00

U.S. Cl. 331-94.5

12 Claims

This invention relates to a gas laser wherein laser energy regeneratively propagates along regenerative paths through a

gaseous laser medium and between spaced reflectors. The laser medium is pumped to an excited state to generate laser energy along said regenerative paths by causing an electrical discharge to be maintained through the laser medium across



or transverse to the regenerative paths. In one embodiment, the gaseous laser medium is caused to flow through the laser cavity transverse to the laser optical path; and in another embodiment, a multiply folded path laser cavity is utilized.

3,577,097

LASER WITH COMBINED Q-SWITCH AND SYNCHRONIZED CAVITY DUMP CIRCUIT


Ronald P. Hilberg, Redondo Beach, Calif., assignor to TRW Inc., Redondo Beach, Calif.

Filed Nov. 28, 1967, Ser. No. 686,076

Int. Cl. H01s 3/00

U.S. Cl. 331-94.5

3 Claims



A laser employing a single modulator in the form of a Pockels cell in the laser cavity and a polarizer. The polarizer in the cavity passes radiation having one polarization direction coming from one direction and diverts radiation having another polarization direction into an absorber. The polarizer passes radiation having one polarization direction coming from an opposite direction and diverts radiation having the other polarization direction into an output path. The modulator in the cavity rotates the polarization direction of radiation to establish the other polarization direction when energized and permits passage of radiation when it is deenergized. A high voltage electrical waveform generator circuit is provided which generates a voltage waveform having a positive DC voltage leading edge and a negative DC voltage trailing edge to the modulator. A gas trigger tube is provided in the circuit which generates a positive DC voltage leading edge in its plate circuit when it is independently triggered by a trigger signal. Another gas trigger tube generates a positive voltage when it is triggered by another trigger signal from a photodiode positioned to intercept radiation leaking from laser cavity. A coupling circuit which couples the plate circuits of the trigger tubes includes a capacitor which converts the positive voltage generated by the other trigger tube into the negative DC voltage trailing edge of the voltage waveform. The coupling circuit may also include a differentiator which allows the voltage levels on the trigger tube plates to be independently varied without affecting each other.

3,577,098

THERMALLY COMPENSATED LASER


Harvey V. Winston, Los Angeles, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.

Filed July 1, 1968, Ser. No. 741,682

Int. Cl. H01s 3/02

U.S. Cl. 331—94.5

5 Claims



The invention is a laser in which an undesired thermal lensing effect of the active laser material is compensated by an addition of a material having a thermal lensing characteristic opposite that characteristic of the laser material. The active laser element and the compensating element are disposed within a regenerative cavity in a regenerative path defined between two end reflectors. As the active laser element is excited by pump energy, a thermal gradient in the laser material results from the excitation and a similar thermal gradient also results in the compensating material to negate the aforementioned thermal lensing effect.

3,577,099

MICROWAVE OSCILLATOR HAVING DIRECTIONAL COUPLER IN FEEDBACK PATH


James A. Hall, and Harry J. Peppiatt, Lynchburg, Va., assignors to General Electric Company

Filed Feb. 27, 1969, Ser. No. 802,771

Int. Cl. H03b 5/12, 5/18

U.S. Cl. 331—96

7 Claims



A microwave oscillator is provided with a solid-state amplifier device whose output is coupled to the input by a directional coupler. The oscillator characteristics can be reliably calculated, and the oscillator signals have a relatively small amount of noise.

3,577,100

METEOROLOGICAL DEVICE EMPLOYING A TEMPERATURE COMPENSATED TRANSMITTER

Robert E. Askew, Berkeley Heights, and Henry C. Johnson, Neshanic, N.J., assignors to the United States of America as represented by the Secretary of the Army

Filed Feb. 28, 1969, Ser. No. 803,156


Int. Cl. H04b 1/02

U.S. Cl. 331—117

9 Claims

This invention relates to a meteorological device that is used to transmit atmospheric conditions such as temperature, pressure, humidity, or the like, to a remote station. The transmitter of such device utilizes temperature-compensating means with a high-frequency transistor oscillator thereby obtaining a highly stable output over a wide temperature range. Temperature compensation is provided by mounting the transistor directly onto dual resonant coaxial cavities with one cavity connected to the transistor emitter and the other cavity connected to the base lead. The cavities are constructed of dissimilar metals thereby providing temperature

dependent capacitance. The cavities are provided with sets of adjusting screws to provide for adjustments in cavity



3,577,101

ELECTROMECHANICAL TORSIONAL OSCILLATOR

Lotar Pege, Bad Schwalbach, Zur Hardt, Germany, assignor to Forschungslaboratorium, Prof. Dr. Ing. W. Heimann

Filed Oct. 16, 1968, Ser. No. 769,473


Claims priority, application Germany, Oct. 20, 1967,

P 15 89 795.7

Int. Cl. G02f 1/34; H03b 5/30

U.S. Cl. 331—154

9 Claims



An electromechanical torsional oscillator for the modulation of devices for measuring electromagnetic radiation frequencies, the oscillator including a mechanical vibrator device with two opposing cylindrical plugs linked to one another by a plurality of double-cantilever-type leaf springs attached by their ends alternately to one or the other plug, so as to give the plugs only a single (rotational) degree of freedom relative to one another. The device further includes electromagnetic driving means to maintain an oscillating motion which, in an exemplary application, is used to vibrate the shading shutter of a radiation-modulating-type temperature-measuring apparatus. Means are provided to adjust the resonant frequency.

3,577,102

SUM OR SELECT NETWORK HAVING SHORT CIRCUITING MEANS CONNECTABLE TO HYBRID TEE CIRCUIT

Joseph Gindsberg, Brookline, Mass., assignor to Raytheon Company, Lexington, Mass.

Filed Dec. 30, 1968, Ser. No. 787,914


Int. Cl. H01p 1/10

U.S. Cl. 333—7

7 Claims

This invention relates to a sum-or-select network for connecting two coherent sources of electrical power to a useful

load such that the total available power from both sources, or either source alone, can be applied to the load with minimum



loss. The network uses a single hybrid tee which can be connected to suitably placed short-circuit terminations if the power from either source fails.

3,577,103

VARIABLE ATTENUATOR FOR A WAVE SIGNAL RECEIVER


David E. Sparks, Chicago, Ill., assignor to Zenith Radio Corporation, Chicago, Ill.

Filed Apr. 1, 1969, Ser. No. 811,893

Int. Cl. H04h 3/04; H01p 1/22

U.S. Cl. 333—17

9 Claims



Attenuation of a received carrier, such as a television signal, may be made dependent on the carrier's signal strength by means of a pi network of variable-resistance diodes, the bias currents of which are controlled by an automatic gain control signal. The diodes in the two shunt arms of the pi network are supplied with forward bias currents that vary directly with received signal strength variations, whereas each diode in the network's series arm receives forward bias current that changes inversely with signal strength variations. In this way, the series arm resistance varies directly, while the resistances of the shunt arms vary inversely, with changes in the carrier's signal strength.

3,577,104

WAVEGUIDE FILTER HAVING SEQUENCE OF THICK CAPACITIVE IRISES


Ralph Levy, Newton, Mass., assignor to Microwave Development Laboratories, Inc., Needham Heights, Mass.

Filed Dec. 26, 1968, Ser. No. 786,967

Int. Cl. H03h 7/10

U.S. Cl. 333—73

1 Claim



A compact microwave band-pass filter utilizes a sequence of thick capacitive irises stationed along the interior of a

waveguide to form a series of directly coupled resonant chambers. The spacing between consecutive irises is $\lambda_g/4$ or less, where λ_g is the upper cutoff frequency of the filter. The close iris spacing causes the second harmonic pass band for the fundamental mode to be far above the main pass band.

3,577,105

METHOD AND APPARATUS FOR JOINING PLATED DIELECTRIC-FORM WAVEGUIDE COMPONENTS


Howard S. Jones, Jr., Washington, D.C., assignor to the United States of America as represented by the Secretary of the Army

Filed May 29, 1969, Ser. No. 828,891

Int. Cl. H01p 1/04, 3/12; F16b 7/00

U.S. Cl. 333—95

10 Claims



A plated dielectric waveguide component which includes a dielectric foam substrate propagating medium and a thin metallic surface encapsulating the substrate for carrying a conducting current therealong and a method of interconnecting the same. The waveguide component has a quarter wavelength step-shaped end which may be readily butt joined with another plated dielectric waveguide component having a similar construction and matching end whereby a lightweight, sturdy and highly efficient connection is obtained.

3,577,106

ADJUSTABLE IRIS


Leslie Giza Varhelyi, Ottawa, Ontario, Canada, assignor to Northern Electric Company Limited, Montreal, Quebec, Canada

Filed July 14, 1969, Ser. No. 841,693

Int. Cl. H01p 1/00, 5/04; F16k 3/03

U.S. Cl. 333—98

5 Claims



A variable aperture iris located at a waveguide T-junction. Two sliding gates and their related positioning members are of a suitable configuration to form a smooth continuous surface along the waveguide for all sizes of aperture opening.

3,577,107

AC OPERATED MAGNET

Gerhard Widl, Ditzingen; Kurt Groetzner, Stuttgart-rot, and Adolf Knodler, Fellbach, Germany, assignors to Robert Bosch G.m.b.H., Stuttgart, Germany

Filed Feb. 7, 1969, Ser. No. 797,583

Claims priority, application Germany, Feb. 28, 1968,

P 16 39 210.2


Int. Cl. H01f 7/12

U.S. Cl. 335—248

7 Claims

A magnet with laminated core and armature arranged for operation with AC current. A plastic casing surrounds the

laminated iron in the core and armature members and subdivides the lamination into two identical sections. The intermediate plastic layer which subdivides the lamination serves



as an impact surface between the armature and the core member of the magnet. The laminations are reinforced and held together through plastic filled notches, as well as stress take-up rods.

3,577,108

ANNULAR MAGNETOELASTIC TRANSDUCER

Waldemar Bengtson, and Orvar Dahle, Vasteras, Sweden, assignors to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden


Filed Sept. 8, 1969, Ser. No. 855,922

Claims priority, application Sweden, Sept. 10, 1968, 12124/68

Int. Cl. H01f 21/02

U.S. Cl. 336-20

2 Claims



An annular magnetoelastic transducer has a core in the shape of a cylindrical ring. The core is manufactured by winding a striplike magnetostrictive material so that the plane of the strip is parallel to the central axis of the ring. In the core is a number of holes which are arranged substantially radially through the core. The holes are arranged in groups which are evenly distributed around the circumference of the core. In the holes there is a winding connected to a current source for generating a magnetic flux in the core and a winding connected to a measuring device for indicating the alterations of the magnetic flux which appears when the core is subjected to mechanical forces.

3,577,109

MAGNETIC SHIELDING CONSTRUCTION FOR ELECTRIC TRANSFORMERS

Samuel L. Foster, Eagle, Wis., and Reed H. Johnston, Wellesley, Mass., assignors to Allis-Chalmers Manufacturing Company, Milwaukee, Wis.

Filed Sept. 18, 1968, Ser. No. 760,430


Int. Cl. H01f 15/04

U.S. Cl. 336-84

13 Claims

In an electric transformer, magnetic laminations for shielding the main magnetic core from leakage magnetic flux are positioned between the inner periphery of the coil and the portion of the main magnetic core which extends through the coil window. The shield laminations are arranged in closed magnetic loops, with the major surfaces of the shielding laminations lying in planes perpendicular to the major sur-

faces of the main core laminations, whereby only the edges of the shielding laminations are presented to the leakage



magnetic flux, thereby minimizing eddy current losses and consequent overheating of the laminations.

3,577,110

TRANSFORMER HAVING A WOUND CORE AROUND LINEAR CONDUCTORS


Robert L. Arntz, and John R. Marker, Jr., Mansfield, Ohio, assignors to Dominion Electric Corporation, Mansfield, Ohio

Filed May 9, 1969, Ser. No. 823,326

Int. Cl. H01f 17/06

U.S. Cl. 336-175

4 Claims



A transformer having a pair of insulated wires disposed generally adjacent and parallel to each other, one wire being the primary and the other wire being the secondary of the transformer, said insulated wires being wrapped by a film of insulating material. The wrapped wires have a ferrous foil, coated with an insulating film, wrapped in several layers tightly therearound. The assembly of wrapped wires with foil therearound is bound together by a binder. The inner margin of the foil is adhered to the outer margin of the film of insulating material to anchor it and the outer margin of the foil is adhered to the binder. The binder is turned inward at the axially spaced ends of the transformer to protect the foil at those ends. A method of making the transformer is disclosed, including the steps of disposing the insulated wires as stated, wrapping the insulation material therearound, wrapping the foil therearound, and binding the wrapped foil in place.

3,577,111

MINIATURIZED SNAP ACTING THERMOSTATIC SWITCH

Antonio Nardulli, Marigliano, Naples, Italy, assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Apr. 2, 1969, Ser. No. 812,699

Claims priority, application Italy, Apr. 3, 1968, 36032A/68


Int. Cl. H01h 37/54

U.S. Cl. 337-89

8 Claims

A miniature thermostatic switch in which a snap acting thermostatic element having a nondevelopable portion

responsible for its snap action is cantilever mounted in a metallic shell. A second mating shell is of electrically insulating material and clamped thereto is an adjustable stationary contact member. In one embodiment the operating temperature of the snap acting thermostatic element is controlled by



eliminating creep action prior to snapping of the element by means of a dimple in the metallic shell which applies a bias to the nondevelopable portion of the thermostatic element. In another embodiment the creep action is avoided by forming the entire thermostatic element in the nondevelopable shape.

3,577,112

APPARATUS FOR HIGH PRESSURE MEASUREMENT


John C. Bowen, Huntingdon Valley, and Howard G. Fischer, II, Hatboro, Pa., assignors to The Duriron Company, Inc., Dayton, Ohio

Continuation-in-part of application Ser. No. 723,030, Apr. 22, 1968, now abandoned. This application May 22, 1969, Ser. No. 826,892

Int. Cl. G01l 1/22

U.S. Cl. 338-4

18 Claims



Apparatus for high pressure measurement utilizing strain gages removably mounted in an opening in an object to which a force, such as fluid pressure, is applied. The mounting is separated from the location of application of the high pressure. The strain gages are carried on plates or the like or may comprise plates, for ready insertion and removal.

3,577,113

ELECTRONICS CARD EXTRACTOR

Robert Thomas Maitland, Franklin Lakes, N.J., assignor to The Bendix Corporation


Filed Oct. 2, 1969, Ser. No. 764,483

Int. Cl. H01r 13/62; H05k 5/02

U.S. Cl. 339-17

4 Claims

An electronics card extractor utilized in the insertion and extraction of circuit cards from a card holder or electronics box having guiding elements or card slides secured at opposite sides of the box and extractors pivotally mounted at opposite outer corners of the card, the extractor being operative by a handle to cause projecting end portions of both extractors to simultaneously bear upon opposite reinforced upper edge portions of the card holder which in effect become fulcrums about which the force applied to the handle may initially provide an extraction force to effect a full disengagement of a card connector at a lower edge of the card from a connector mounted on the lower surface of the box,



3,577,114

CONNECTING DEVICE


William M. Hawkins, Scotch Plains, N.J., assignor to Thomas & Betts Corporation, Elizabeth, N.J.

Filed Dec. 12, 1969, Ser. No. 884,564

Int. Cl. H01r 13/52; H01r 7/06

U.S. Cl. 339-94

22 Claims



An insulated, sealable, connecting device for mechanically and electrically releasably coupling at least two conductors to provide a substantially watertight assembly, comprising, in combination, an insulated, electrically conductive body member having at least two apertures therethrough, at least two selectively bored, partially insulated, conductor-receiving stubs adapted to be releasably engaged therein, at least two threaded fastening means adapted to releasably couple an associated stub within the apertured conductive body member, and at least two first and at least two second resilient sealing means to provide sealing engagement between, respectively, the conductive body member and an associated stub, and the conductive body member and an associated fastening means.

3,577,115

ELECTRICAL CONNECTOR STORING DEVICE FOR MOTOR VEHICLE TRAILERS

Joseph W. E. Whwright, Cheshire, Conn., assignor to Cheshire Manufacturing Co., Inc., Cheshire, Conn.

Continuation-in-part of application Ser. No. 706,305, Feb. 19, 1968, now abandoned. This application Oct. 17, 1969, Ser. No. 867,342


Int. Cl. H01r 13/44; A44b 21/00

U.S. Cl. 339-36

2 Claims

A device for storing and protecting an electrical plug on a trailer when disconnected from the motor vehicle by which

the trailer is drawn, in which an inverted hood is provided on a mounting channel that is attached to a fixed portion of the trailer. The hood is attached to the mounting channel by



simply inserting its wall into slots in the upper end of the channel, these slots being positioned so that the wall of the hood is gripped tightly between the flanges on one side and the web of the channel on the other.

3,577,116

LAMP SOCKET AND TERMINAL


Bruno Baumanis, River Forest, Ill., assignor to Molex, Incorporated, Downers Grove, Ill.

Filed Aug. 8, 1968, Ser. No. 751,079

Int. Cl. H01r 13/60

U.S. Cl. 339—125

6 Claims



A lamp socket for receiving an easily replaceable lamp bulb, comprising a plastic housing having a pair of opposing terminals extending therethrough for receiving the base of the lamp bulb therebetween to make both mechanical and electrical contact therewith, and mounting means integrally formed with a sidewall of the housing for snapping the lamp socket onto a mounting tab extending from a panel. A first embodiment of mounting means includes a resilient arm having a lock tab at the free end thereof for insertion into an aperture in the panel mounting tab, and a second embodiment includes a pair of opposing arms and a nib extending therebetween from one wall of the housing. The arms hold the panel tab against the housing wall and the nib is received in the aperture of the panel tab to retain the socket on the panel.

3,577,117

ELECTRICAL CONNECTOR

Heold Louis Bruetsch, New Cumberland, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Feb. 24, 1969, Ser. No. 801,473


Int. Cl. H01r 13/12

U.S. Cl. 339—248

3 Claims

This invention relates to a cylindrical wire splice having an internal metallic connector portion formed by rolling multiple pre-cut metal strip, and an insulating cover rolled about

the connector portion to insulate the electrical contact of the connector portion from points external of the device. The ends of the wires to be spliced have a radially enlarged collar which is engaged by oppositely directed tines of the connector portion to position the ends of the wire within the device. Cantilever surfaces at the center of the connector portion rigidly grip the ends of the wire to form a proper electrical contact therebetween. The ends of the insulating cover have



resilient plug members which are inserted therein to seal the wires both before and after insertion into the device. The plug members have an opening to allow the insertion of the wires therein, and a portion of the plug member extends across the opening to seal the interior of the connector portion prior to the insertion of wires in the device.

3,577,118

ELECTRICAL TERMINAL

George Sylvester Reider, Highspire, Pa., assignor to AMP Incorporated, Harrisburg, Pa.


Continuation of application Ser. No. 669,551, Sept. 21, 1967.

This application Apr. 23, 1969, Ser. No. 869,405

Int. Cl. H01r 11/08, H01r 11/22

U.S. Cl. 339—258

4 Claims



A detachable flag-type terminal which may be stacked on a post is disclosed. The terminal is generally U-shaped in cross section. The web is extended and arched rearwardly to form a spring means which acts as a post-holding means. Openings are formed in the sidewalls of the web. The openings are formed in the sidewalls of the web. The openings are aligned thereby creating a passage through which a post may be inserted in a direction normal to the axis of the ferrule of the terminal.

3,577,119

ELECTRICAL CONNECTORS ON A CARRIER STRIP

Armand Rene Delyon, Harrisburg, and Lex Donald Kensinger, Hershey, Pa., assignors to AMP Incorporated, Harrisburg, Pa.

Filed June 4, 1969, Ser. No. 830,357


Int. Cl. H01r 11/08

U.S. Cl. 339—276

5 Claims

Plural different electrical connectors are provided on a common carrier strip so that each conductor of a multiconductor wire may have a specific connector secured or terminated thereto. The resulting terminated conductors are particularly useful in e.g., automobile wiring harnesses. The strip is adapted to be fed into automatic crimping presses

wherein one set of crimping dies is used to crimp all of the connectors on the strip. Connectors are severed from the



carrier strip when they are crimped onto the conductors of the multiconductor wires.

3,577,120

DISPLAY SYSTEM FOR USE IN VTOL-TYPE AIRCRAFT


Archie T. Sherbert, Jr., Media, Pa., assignor to The Boeing Company, Seattle, Wash.

Filed Oct. 14, 1968, Ser. No. 767,182

Int. Cl. B64d 45/04

U.S. Cl. 340—27

15 Claims



A system for displaying information relating to the operation of a vehicle, such as an aircraft. An integrated approach/hover indicator provides a pictorial representation of an intended landing site for the aircraft and indicates the position of the aircraft relative to the landing site and relative to a preselected path leading to the landing site. The pictorial representation is displayed in proper perspective such that a pilot viewing the instrument would think he is actually viewing the landing site. In addition, the instrument provides digital readout and other devices which visually display a number of operating values relating to the performance of the aircraft.

3,577,121

BRAKE FLUID LEVEL SWITCH

Douglas J. Wing, St. Clair Shores, and William A. Ramey, Warren, Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Nov. 10, 1969, Ser. No. 875,080


Int. Cl. B60q 1/00

U.S. Cl. 340—59

6 Claims

A vehicle brake master cylinder assembly of the dual reservoir type including a fluid level responsive diaphragm positioned in each of the reservoirs. Each diaphragm supports a flexible insulator member which in an acceptable fluid level position is placed between a resilient spring-biased contact member and an electrically grounded reservoir cover maintaining a signal circuit therebetween open. Should the level of fluid in a reservoir decrease to a predetermined minimum

level, its resilient insulator is pulled from between one of the spring-biased contacts and the reservoir cover closing the circuit to the signalling device, thereby informing the operator of the low fluid condition. Removal of the reservoir cover



and filling of the reservoir raises the diaphragm to its uppermost position, but does not again open the signal circuit until the attendant performs the positive act of placing the insulator member between the spring-biased contact and the cover.

3,577,122

FLAT PANEL TRAFFIC WARNING SIGN HAVING LIGHT MOUNTED THEREON


James O. Lapham, 308 N. Westridge Ave., Covina, Calif.

Filed Jan. 9, 1969, Ser. No. 790,032

Int. Cl. G08b 5/36, G08b 5/38

U.S. Cl. 340—114

2 Claims



A traffic warning sign having a flasher mounted within an opening in a panel of the sign so as to be visible from either side of the panel and connected to a flasher circuit and battery by leads contained within a concealed passageway or groove in the panel. One disclosed embodiment of the invention is a street barricade in which the flasher circuit and battery are contained within a housing which also tends to shield the lenses of the flasher lamp. A second disclosed embodiment is a traffic lane divider.

3,577,123

METER READING SYSTEM

James R. Taylor, Allendale, N.J., and Thomas C. Clements, New York, N.Y., assignors to Neptune Meter Company, New York, N.Y.

Filed May 31, 1968, Ser. No. 733,372


Int. Cl. G01d 3/08; G11b 27/36; H03k 13/34

U.S. Cl. 340—146.1

9 Claims


In a system for reading meter registers and the like, special error detecting circuits are provided in the meter reading and recording apparatus forming part of the system. For every character recorded two error checks are performed, one at the decimal level, and a further one at the binary level. The decimal check determines if there are any errors that have been introduced due to faults anywhere in the decimal por-

tion of the system, including the entire house installation. Such errors might arise, for example, due to open or short circuits within such installation. A fault at the decimal level will result in a "no digit/multidigit" or "house error" indication being given. The binary check determines if the recorder electronics are working properly. A fault at the binary level will result in an incorrect parity indication, or "recorder error" being given.



3,577,124

PRE-ENGAGEMENT CARD CONTROLLED PATIENTS
Tadataka Kobayashi, Kyoto Prefecture, Japan, assignor to Iwao Ueda, Kyoto, Japan
Filed July 24, 1969, Ser. No. 844,265
Claims priority, application Japan, July 25, 1968, 43/52808
Int. Cl. H04q 3/00, H04q 5/00
U.S. Cl. 340-153 10 Claims




Appointment selection device formed by a plurality of card holding compartments arranged in rows and columns. The rows designate days and the columns designating time periods within a day, the compartments including adjustable means for regulating the size thereof thereby permitting introduction of no more than a prescribed number of cards in a given compartment. Indicating means is provided for indicating when a compartment contains a prescribed number of cards.

3,577,125

MONOLITHIC ELECTRONIC SWITCHING NETWORK HAVING VARIABLE VOLTAGE LEVELS
Jack G. Frisbie, Great Falls, Va., assignor to International Telephone & Telegraph Corporation, New York, N.Y.
Filed Oct. 16, 1968, Ser. No. 767,973
Int. Cl. H04q 1/00
U.S. Cl. 340-166 9 Claims

The invention relates to a solid state switching matrix, a plurality of which may be cascaded to provide a switching network. Various means are disclosed for controlling the amount of energy required to fire a diode in one matrix and the amount of energy passing through the diode after it has fired. By the selection of proper characteristics, the diodes in


each state may be made to fire on less energy than was required to fire the diodes in the next preceding state. This



way, the diodes may be made to scan idle points in the network without causing offensive levels of fan-out current to build up.

3,577,126


PULSE RESPONSIVE CONTROL NETWORK
Robert J. Molnar, New York, N.Y., and Walter Parfomak, Wallington, N.J., assignors to The Bendix Corporation
Filed Sept. 11, 1968, Ser. No. 758,946
Division of Ser. No. 535,745, Mar. 21, 1966, Pat. No. 3,440,637.
Int. Cl. H04q 3/00
U.S. Cl. 340-167 31 Claims



A pulse responsive control network including a first and second plurality of control devices sequentially operated by electrical signal pulses of one sense for effecting control functions, together with first and second means operable respectively in response to initial sequential operation of a last of said first and second plurality of control devices for providing clearing pulses of another sense to condition other of the respective first and second plurality of control devices for sequential reoperation to effect a multiplexing action, together with switching means effective upon completion of the reoperation of the other of said first plurality of control devices to condition the second plurality of control devices for sequential operation by the electrical signal pulses of said one sense; and other means to effect electrical signal pulses of said other sense to selectively terminate the operation of the first and second plurality of control devices, said last mentioned means including a time delay means to cause the signal pulses of said other sense to terminate the operation of said second plurality of control devices after termination of the operation of the first plurality of control devices has been effected.



3,577,127 COMPOSER SYSTEM FOR PROCESSING DATA IN PARALLEL COLUMNS

David Bishop, Austin; David W. Terry, Georgetown, Tex.; John E. Jones, Raleigh, N.C.; Roderick S. Heard, and William H. Davis, Lexington, Ky., assignors to International Business Machines Corporation, Armonk, N.Y.
Filed Apr. 26, 1968, Ser. No. 724,552
Int. Cl. G06f 15/06; G06f 15/46
U.S. Cl. 340-172.5 35 Claims



The invention concerns composing systems including techniques and apparatus for achieving justification of columnar data. In one version, Method A, the system derives columnar data from a source media, such as the familiar "Presswire" paper tape having pairs of text columns arranged in successive justified lines, recognizes the occurrence of a code in the media identifying the center of the line between the two columns, if such occurs within a certain range, compares the line center code with a predetermined range about the center location of a previously entered line measure, and develops the necessary justification routines to insure that each of the double columns in successive lines is justified to a standard width thereby insuring that the gutter (or white space) between the column segments is of a uniform width and has straight edges. In a second version, Method B, data derived from the tape media is also scanned to determine the occurrence of the line center in successive lines, but the necessary justification routines for insuring a uniform placement of the gutter (or white space) is based upon a comparison of the center indicating code with a range about the center of the fixed width of both column segments in an individual line. The system readily accommodates a number of column segments greater than two in individual lines and column segments that differ in width. Also, it is receptive to input data derived from sources other than a paper tape media, and the output of the system, rather than being a printer, as described herein, can be any one of a number of composing entities, recording units, communicating units, or the like.

**3,577,128
SYNCHRONIZING CLOCK SYSTEM**
Tony N. Criscimagna, Woodstock, and Robert J. Fournier, Staatsburg, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Filed Jan. 14, 1969, Ser. No. 790,952
Int. Cl. H03k 3/64
U.S. Cl. 340-172.5 3 Claims




In a data processing system, apparatus for synchronizing a slave clock in an input/output device with a master clock in a

central processing unit. A set of clock signals from a CPU are received in parallel, converted to serial and pulses are generated in response to the leading and trailing edge of each of the series of signals. The series of pulses is then delayed and shaped to drive a slaved I/O clock. A delay line is adjusted so that the total equivalent system delay is equal to an integral number of CPU pulse durations.


3,577,129

INFORMATION READ-OUT CONTROL SYSTEM
Klaus Jorg Hecker, Main-Taunus Kreis, Germany, assignor to Eichner Organisation GM/BH, Frankfurt Am Main, Germany
Filed Sept. 18, 1968, Ser. No. 760,616
Int. Cl. G11b 19/00; G11c 19/00
U.S. Cl. 340-172.5 6 Claims



A tape transport requires a predetermined time period for stopping after receipt of a stop signal. During this predetermined time period the information items from the tape are stored in a shift register. A second shift register with the same number of stages as the first shift register generates a signal from each stage corresponding to a stage in the first shift register wherein an information item was stored. When the tape transport is restarted the information from the first shift register is read out under control of timing signals and signals from the second shift register.

**3,577,130
MEANS FOR LIMITING FIELD LENGTH OF COMPUTED DATA**
Rex Rice, Menlo Park; Gilman D. Chesley, Los Altos, and William R. Smith, Mountain View, Calif., assignors to Fairchild Camera and Instrument Corporation, Mt. View, Calif.
Filed Oct. 3, 1969, Ser. No. 863,454
Int. Cl. G06f 7/00
U.S. Cl. 340-172.5 2 Claims



Limit hardware for controlling the field length of resultant data produced by a data processor including a limit register, a counter and a comparator. The limit register is loaded with

any desired number representing the desired number of fields of the resultant data, while the counter is incremented as each field of resultant data is produced by the processor. When the contents of the limit register and the counter are equal, data processing is terminated and the desired number of resultant data produced by the processor is supplied to any appropriate user, before a new processing operation is initiated.

3,577,131

DOMAIN PROPAGATION ARRANGEMENT


Robert H. Morrow, Lebanon Township, Hunterdon County, and Anthony J. Perneski, Martinsville, N.J., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Jan. 30, 1969, Ser. No. 795,148

Int. Cl. G11c 19/00; G11c 11/14

U.S. Cl. 340-174

14 Claims



Interactions between single wall domains permit logic operations to be realized in magnetic sheets in which such domains are moved. Magnetically soft overlay patterns not only define propagation channels for such domains in response to magnetic fields reorienting in the plane of the sheet but also define channel intersections where logic functions are carried out. Domains are idled or, alternatively, in direction at those intersections depending on the positions of preceding domains. A variety of counter circuits are described.

3,577,132

PHASE LOCKED OSCILLATOR FOR STORAGE APPARATUS


Donald E. Anderson; Lawrence M. Koch; Robert E. Lloyd, and Frank J. Sordello, San Jose, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed June 6, 1968, Ser. No. 735,137

Int. Cl. G11b 5/44; G11b 19/28; G11b 27/10

U.S. Cl. 340-174.1A

9 Claims



A phase-locked oscillator useful for a magnetic storage system receives timing pulses from a means for generating reference pulses connected to a rotary storage medium. Variations in the angular velocity and phase of the rotating storage medium result in corresponding variations of frequency and phase of a voltage-controlled oscillator, which controls the write or record circuitry. During readout, the phase-locked oscillator is employed to locate the selected data records accurately.

3,577,133 DISC MEMORY SYSTEM INCLUDING UNITARY SUPPORT MEMBER AND PRINTED CIRCUIT BOARD


Allen E. Garfein, Woodland Hills, and Irwin B. Garfein, Los Angeles, Calif., assignors to Engineered Data Peripherals Corporation, Santa Monica, Calif.

Filed Nov. 19, 1968, Ser. No. 776,936

Int. Cl. G11b 5/48

U.S. Cl. 340-174.1

16 Claims



The present invention is directed to a disc memory system which includes a magnetic memory disc and the companion electronics for recording and reading out the information on the memory disc and wherein the bulk of the electronics is located on a single printed circuit board mounted adjacent to and in a parallel plane to the plane of the memory disc. All of the electronics except the diode boards are on this single printed circuit board. A single unitary casting supports all of the major components of the disc memory system such as the motor, shaft, magnetic heads, etc., and all of the major tolerances which must be maintained in order to insure the proper function of the interrelated parts of the disc memory system are held on this single casting. The memory disc is maintained in a first sealed compartment which is supported on the single casting and the single printed circuit board is maintained in a second sealed compartment separate from the first sealed compartment.

3,577,134

METHOD OF OPERATING A CONVERTIBLE MEMORY SYSTEM

Robert J. Bergman, St. Paul, Minn., assignor to Sperry Rand Corporation, New York, N.Y.


Filed Sept. 16, 1969, Ser. No. 858,372

Division of Ser. No. 671,026, Sept. 27, 1967, Pat. No. 3,480,929.

Int. Cl. G11c 11/14; G11c 5/02

U.S. Cl. 340-174

8 Claims



A magnetizable memory element that includes a plurality of layers of thin-ferromagnetic-films that are formed in a stacked, superposed relationship about and sandwiching therebetween a current conducting drive line. The magnetizable layers have opposing sides that overlap the drive line to form closely coupled portions on both sides of the enveloped drive line for creating a substantially closed flux path about the enveloped drive line. The layers' easy axes are skewed away from the magnetic axis, i.e., a line orthogonal to the longitudinal axis, of the enveloped drive line providing single-domain rotational switching of the layers' magnetization during both the write and read operations. Pairs of layers

on each side of the enveloped drive line are comprised of layers of relatively high and low H_k characteristics whereby an energized enveloped drive line substantially effects only the low H_k layers upon readout providing nondestructive readout of the information stored in the high H_k layers.

3,577,135

UNATTENDED FLASHING NAVIGATION BEACON SYSTEM


Donald B. Steen, Baltimore, Md., assignor to the United States of America, as represented by the Secretary of the Navy

Filed Mar. 26, 1968, Ser. No. 716,154

Int. Cl. H05b 41/46

U.S. Cl. 340-251

11 Claims



An unattended flashing navigation beacon system comprising a solid-state thermoelectric generator to supply power to the system, a Zener voltage limiter to regulate the system voltage, a capacitor bank to store power supply energy during eclipse time, a solid-state flasher, a motorized lamp changer, a first time delay circuit means for controlling the amount of time said flasher is actuated and a second time delay circuit means for controlling the amount of time said flasher is eclipsed. The flasher and lamp changer are interconnected such that a relay is activated when a lamp burns out. The relay initiates operation of the lamp changer motor and simultaneously prevents the flasher from switching to the eclipse state until a new lamp bulb is placed into position at which time the relay turns off the motor and allows the flasher to resume operation.

3,577,136

SHORT-RANGE SIGNALING SYSTEM


John E. Wolf, Marengo, Ill., assignor to Security Systems, Inc.

Filed Aug. 4, 1967, Ser. No. 658,491

Int. Cl. G08b 13/24; H03b 5/30

U.S. Cl. 340-280

15 Claims



A merchandise protection system in which an encapsulated, magnetically latched reed is hidden on the article to be

protected against theft. Magnets placed adjacent an exitway from the protected enclosure release the reed, allowing it to thereafter vibrate at a predetermined frequency. The reed produces a magnetic disturbance which is detected by a sensitive, frequency-selective pickup device which, in turn, actuates an alarm.

3,577,137

TEMPERATURE COMPENSATED ELECTRONIC DISPLAY


James Brennan, Jr., Houston, Tex., assignor to Texas Instruments, Incorporated, Dallas, Tex.

Filed Dec. 31, 1968, Ser. No. 788,178

Int. Cl. H04l 15/34

U.S. Cl. 340-324

20 Claims



A high speed electronic display system having a circuit for adjusting the power applied to a thermal display matrix during a printing cycle based upon the temperature of the print head. In one embodiment, the temperature of a matrix of air isolated semiconductor means is sensed by a diode diffused in an adjacently mounted integrated circuit immediately prior to the print cycle, and the power applied to drive the matrix during the print cycle is adjusted in accordance with the offset voltage across the diode. In another embodiment, the temperature of the matrix of elements is estimated using a temperature sensing element located on the heat sink and correcting the sensed temperature to compensate for the repetition rate of the print cycle, the number of elements activated during each print cycle, the rate at which heat is transferred to the heat sensing element, and the rate at which heat is dissipated from the heat sensing element. There is a single sensor for the thermal display matrix.

3,577,138

FEEDBACK TYPE PULSE AMPLITUDE MODULATION CODING SYSTEM

Masao Kawashima; Shunroku Sasaki, Yokohama-shi, and Syoichi Kurita, Kawasaki-shi, Japan, assignors to Fujitsu Limited, Kawasaki-shi, Japan


Filed Dec. 13, 1966, Ser. No. 601,467

Claims priority, application Japan, Dec. 16, 1965, 40/77471

Int. Cl. H03k 13/02

U.S. Cl. 340-347

8 Claims



A pulse amplitude modulated signal is held in a first holding circuit and is supplied to a summing node via a switch. A reference signal from a reference signal source is also supplied

plied to the summing node which provides a difference signal indicative of the difference in amplitude between the pulse amplitude modulated signal and the reference signal. An amplifier amplifies the difference signal and a comparator determines the polarity of the difference signal and provides a corresponding binary output signal. The comparator is also connected to the reference signal source in a first feedback path. A second holding circuit is connected in a second feedback path between the amplifier and the switch and the amplified difference signal is supplied to the summing node via the switch in selective alternation with the pulse signal.

3,577,139


ANALOG-TO-DIGITAL CONVERTER

Roy P. Foerster, Thousand Oaks, Calif., assignor to The Bunker-Ramo Corporation, Canoga Park, Calif.
Filed June 12, 1967, Ser. No. 645,191

Int. Cl. H03k 13/02

U.S. Cl. 340-347

10 Claims



A converter responsive to analog input signals for providing "reflected binary" or Gray code output signals. The converter is comprised of a plurality of substantially identical stages connected in cascade. Each stage provides both a digital output signal and a residual analog output signal in response to an analog input signal applied thereto. The level of the residual output signal provided by each stage is determined by a V-shaped transfer characteristic defined by a differential amplifier therein. The residual output signal from each stage constitutes the input signal to a subsequent stage.

3,577,140


TRIPLE INTEGRATING RAMP ANALOG-TO-DIGITAL CONVERTER

Hans Bent Aasnaes, Trondheim, Norway, assignor to International Business Machines Corporation, Armonk, N.Y.
Filed June 27, 1967, Ser. No. 649,161

Int. Cl. H03k 13/02; H03k 13/20

U.S. Cl. 340-347

14 Claims




An integrating ramp voltage type analog-to-digital converter apparatus is disclosed. An unknown analog voltage is integrated for a fixed time period. During subsequent, successive integration of reference voltages, pulses are gated into a partitioned counter, filling the higher order positions in that counter first. The counter then contains a digital representation analog the analog voltage.

3,577,141
BINARY TO DECIMAL TREE RELAY DECODER
CIRCUIT WITH MEMORY DISPLAY
Eusebio V. Quintero, Greenville, S.C., assignor to United Merchants and Manufacturers, Inc., New York, N.Y.
Filed Nov. 14, 1968, Ser. No. 775,737


Int. Cl. G06f 5/00

U.S. Cl. 340-347

4 Claims



reactive impedance for reducing the catastrophic effect produced by end-fire grating lobes and surface waves. A series capacitance or shunt inductance is placed in the trans-



mission path formed by the ground plane and free space in order to increase the phase velocity of any TM wave that might propagate along the ground plane so that it is at least equal to the phase velocity of a free space wave.

3,577,148

PORTABLE REELABLE DIPOLE ANTENNA HAVING FREQUENCY CALIBRATED DIAL


Donald L. Holzschuh, Richardson, and Betty M. Wicker, Richardson, Tex., assignors to Collins Radio Company, Dallas, Tex.

Filed Nov. 6, 1968, Ser. No. 773,826

Int. Cl. H01q 9/16

U.S. Cl. 343-821

1 Claim



An adjustable dipole antenna which is compact, portable and easily assembled in the field including reel means for accommodating two lengths of wire and calibrated dial means mechanically coupled to the reel means for indicating an operating frequency as the two lengths of wire are unreel. Impedance matching means is provided to match the balanced antenna impedance to the unbalanced impedance of the input feedline.

ERRATUM

For Class 346-46 see:
Patent No. 3,577,131

3,577,149

COLOR PRINTING APPARATUS FOR POTENTIOMETRIC RECORDING INSTRUMENTS

Ugo Carpino, Milan, Italy, assignor to Pio Guardigli, Milan, Italy

Filed Nov. 15, 1968, Ser. No. 776,044


Claims priority, application Italy, Nov. 20, 1967, 22899/67
Int. Cl. G01d 9/34

U.S. Cl. 346-46

6 Claims

Writing apparatus in multicurve electronic potentiometric recording instruments to record the values of a plurality of variables on a continuous movement single chart. The writing apparatus comprises a movable writing carriage, means for inking in a plurality of colours and changeover means for

selecting the variables. The writing carriage moves parallel to itself to assume the stamping and inking position and oscill-



lates at right angles to the direction of movement to effect the stamping and inking operations.

3,577,150

RECORDING HELIX


Milton Alden, Needham, Mass., assignor to Alden Research Foundation, Brockton, Mass.

Filed Jan. 22, 1969, Ser. No. 793,132

Int. Cl. G01d 15/06

U.S. Cl. 346-139

11 Claims



This invention relates to a recording helix and, more particularly, to drum for use in a graphic communications recorder having a helical electrode mounted thereon.

ERRATA

For Classes 174-128 thru 346-75 see:
Patent Nos. 3,577,151 thru 3,577,198

3,577,151

FULLY OR PARTLY STABILIZED CONDUCTOR COMPRISED OF SUPERCONDUCTING AND NORMAL-CONDUCTING METALS

Gunther Bogner, Tennenlohe, and Richard Maier, Erlangen, Germany, assignors to Siemens Aktiengesellschaft, Berlin, Germany

Filed Apr. 1, 1969, Ser. No. 812,040

Claims priority, application Germany, Apr. 6, 1968,
P 17 65 132.0


Int. Cl. H01v 11/04; H01f 7/22

U.S. Cl. 174-128

11 Claims

Described is a fully or partly stabilized conductor combined of superconducting and normal-conducting metals. The conductor is characterized in that several superconductors with small cross section are combined with a copper matrix to form a multicore conductor. The superconductors

are completely embedded in the copper matrix and in metallurgical connection therewith. Several multiconductors are



enclosed with one aluminum jacket and are electrically and thermally connected with the same.

3,577,152

ARRANGEMENT FOR COLOR TELEVISION RECEIVER


Koichi Yahagi, Kawasaki-shi, Japan, assignor to Nippon Columbia Company, Limited

Continuation-in-part of application Ser. No. 760,603, Sept. 18, 1968. This application June 10, 1969, Ser. No. 834,220

Int. Cl. H04n 9/12

U.S. Cl. 178-5.4

11 Claims



A video amplifier circuit arrangement for a color television receiver which is capable of effectively meeting a contradictory relationship between the production of a picture with high resolution during reception of black-and-white television broadcast and the production of a color picture free from dotted pattern during reception of color television broadcast.

3,577,153

IMAGE PICKUP APPARATUS

Motoi Yagi, Zushi-shi, and Yasuo Takemura, Kawasaki-shi, Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki-shi, Japan


Filed Aug. 19, 1968, Ser. No. 753,638

Claims priority, application Japan, Aug. 23, 1967, Jan. 18, 1968, 42/53768; 42/53767; 42/71998; 43/2337

Int. Cl. H04n 7/18, 5/30

U.S. Cl. 178-7.2

8 Claims



A position detector detects the presence of a travelling foreground subject and then enables a light projector, such as

a Strobe tube, to provide short duration flashes when the foreground subject is at an optimum predetermined position relative to the position of the light projector. A photoelectric conversion device is provided to pick up an image of the illuminated foreground subject, signals corresponding to the picked up image being processed and, if desired, stored to provide a permanent record.

3,577,154

CODE CALL FACILITY FOR ELECTRONIC TELEPHONE EXCHANGE



William F. Bartlett, Irondequoit, N.Y., assignor to Stromberg-Carlson Corporation, Rochester, N.Y.

Filed Apr. 1, 1969, Ser. No. 811,757

Division of Ser. No. 557,042, June 13, 1966, Pat. No. 3,459,896.
Int. Cl. H04m 11/02

U.S. Cl. 179-18

3 Claims



A telephone exchange code call circuit wherein a static store applies gating signals to a selected gate in each of two sets of gates, the first set designating a tens digit and the second set designating a units digit. The gates in the first and second set receive time spaced signals in a predetermined sequence so that the selected gate in the first set is first enabled and the selected gate in the second set is subsequently enabled, by the simultaneous presence of the gating and timed spaced signals. An output circuit, responsive to the enabled gates in the first and second set produce a code call signal corresponding to that in the static store.

3,577,155

ALLOTTER CIRCUIT FOR SEQUENTIAL INDICATION OF INCOMING TELEPHONE CALLS


Witold E. Swierczewski, Daly City, Calif., assignor to American Telephone and Telegraph Company, New York, N.Y.

Filed Jan. 15, 1969, Ser. No. 791,395

Int. Cl. H04m 5/04

U.S. Cl. 179-27

7 Claims



A telephone call allotter circuit is disclosed for lighting the line lamps on an attendant console or switchboard, one at a time, in the same sequence in which calls arrive. A crossbar switch is interposed between the line relays and the line lamps. The horizontal magnets of the switch are operated sequentially in the order in which calls arrive. The line lamp of each line is associated with a respective vertical of the crossbar switch. Transfer contacts of relays controlled by the crossbar switch permit only one line lamp at a time to operate.

3,577,156

PULSE GENERATOR

Boris Evgenievich Paton, Ulitsa Kotsjubinskogo, 9, Kv. 21; Vladimir Konstantinovich Lebedev, Ulitsa Engelsa, 25, Kv. 12; Petrovich Pavel Sheiko, Ulitsa Tatarskaya 2-b Kv. 12, and Mikhail Petrovich Pashulya, Ulitsa Konstantinovskaya-61, Kv. 11, Kiev, U.S.S.R.

Filed Mar. 10, 1969, Ser. No. 805,656


Claims priority, application U.S.S.R., June 14, 1968,

1250703

Int. Cl. B23k 9/10

U.S. Cl. 219-131

2 Claims



A novel pulse generator for pulse arc welding and building up of parts by one or several arcs is disclosed, the novel generator comprising a pulse unit and a control unit. The pulse unit comprises a transformer, the number of secondary windings of which corresponds to the number of welding arcs, or the number of secondary windings is half the number of welding arcs, so as to ensure simultaneous operation of the required number of welding arcs.

INTEGRATING DEVICE FOR USE IN INDUSTRIAL PROCESS CONTROL APPARATUS

Robert J. Robinson, Lexington, Mass., assignor to The Foxboro Company, Foxboro, Mass.


Division of Ser. No. 500,612, Oct. 22, 1965, Pat. No. 3,441,053.

Filed May 16, 1968, Ser. No. 749,230

Int. Cl. G06g 7/18; F16k 31/143

U.S. Cl. 235-183

13 Claims



An industrial process control system wherein a digital data processor controls process conditions in a time shared manner by periodically sampling the conditions and then communicating in sequential order with the process regulating means by use of a series of constant amplitude command signals whose time duration is proportional to the change to be made in the process regulating means and a device for translating a command signal of this type to a suitable control signal for changing the setting of the process regulating means.

3,577,158

MASS FLOW RATE MEASURING UTILIZING THE SCATTERING CROSS SECTION OF A MATERIAL FOR FAST NEUTRONS


Linus K Hahn, Columbus, Ohio, assignor to Industrial Nucleonics Corporation

Continuation of application Ser. No. 522,778, Jan. 24, 1966, now abandoned. This application Jan. 7, 1969, Ser. No. 792,201

Int. Cl. G01n 23/12

U.S. Cl. 250-43.5

17 Claims



Measuring mass flow rate of a fluid material having a high scattering cross section for fast high energy neutrons by radiating the material with such neutrons which are slowed to lower energy thermal neutrons and detecting the thermal neutrons downstream to effect a determination therefrom of the mass flow rate. For a more accurate determination of the mass flow rate, a second thermal neutron detector

downstream has its output compared to the first detector output. Further, a gamma source and detector is employed to derive the density of the material and to obtain the velocity thereof by division of the mass flow by the density.

3,577,159

DIFFRACTION GRATING X-RAY SPECTROMETER WHEREIN AN ELECTRON BEAM IS SCANNED ACROSS A FIXED X-RAY EMITTING ELEMENT


Masao Sawada, 525 Ikejiri, Sayama-cho Minami Kawachigun, Osaka-Fu, Japan

Filed Jan. 2, 1968, Ser. No. 694,933

Int. Cl. G01n 23/22

U.S. Cl. 250-51.5

6 Claims



A diffraction grating spectrometer having an X-ray tube in a fixed position, the ray-source of which is rapidly moved back and forth on a definite curve. Diffracted beams from the grating surface are focused on a slit of a fixed electronic counter and the intensities of the spectral distribution are observed or measured by a suitable means. The positions of the ray-source and the counter are the reverse of those in the previously known spectrometers.

3,577,160

X-RAY GAUGING APPARATUS WITH X-RAY OPAQUE MARKERS IN THE X-RAY PATH TO INDICATE ALIGNMENT OF X-RAY TUBE, SUBJECT AND FILM


James E. White, 7342 E. Thomas, Scottsdale, Ariz. 85257

Filed Jan. 10, 1968, Ser. No. 696,730

Int. Cl. G03b 41/16

U.S. Cl. 250-59

13 Claims



X-ray photographic apparatus through which reference data is photographically recorded on the film exposed to the X-rays together with the image of a subject being diagnosed. A locator for producing landmark images is also mounted on the subject, so that photographic records of the subject may be evaluated in light of both image distortion due to geometric misalignment and variation in the anatomy of the subject.

3,577,161

RADIATION DOSIMETER HAVING SENSITIVE MATERIAL CONTAINING LITHIUM HYDRIDE

Martin Oberhofer, Taino, and Jurgen Jaspert, Cittiglio, Italy, assignors to European Atomic Energy Community (Euratom), Brussels, Belgium


Filed Dec. 8, 1967, Ser. No. 689,098

Claims priority, application Netherlands, Dec. 21, 1966, 66/17951

Int. Cl. G01t 1/11, 3/00

U.S. Cl. 250-71

10 Claims



A radiation dosimeter based on the phenomenon of thermoluminescence. The sensitive material in the dosimeter is, at least in part, lithium fluoride, and to the sensitive material is added lithium hydride.

3,577,162

AUTOMATIC COUNTING SYSTEM FOR FLUID SUSPENDED PARTICLE

Hermann Gaehwiler, and Kurt Schoen, Zurich, Switzerland, assignors to Contraves AG., Zurich, Switzerland

Filed Mar. 21, 1969, Ser. No. 809,332


Claims priority, application Switzerland, Apr. 19, 1968,

5869/68

Int. Cl. G01n 21/26

U.S. Cl. 250-218

4 Claims




A novel counting system for counting particles suspended in a fluid medium is disclosed. The counting system comprises electrode means for sensing the presence of particles in a fluid means and producing a signal representative thereof; conveying means for conveying the fluid medium through said electrode means into a measuring tube; an upper and a lower spaced apart fluid level sensing means disposed at the measuring tube; and counter means coupled with said sensing means and said electrode means for counting said signals, said counter means being turned on by said lower sensing means when the fluid reaches the lower level in the measuring tube, and being turned off by said upper sensing means when the fluid reaches the upper level in the measuring tube.

3,577,163

PRINT READER COMPRISING TWO MUTUALLY ORTHOGONAL SCANNING SLITS AND A DRUM HAVING A LIGHT TRANSMISSIVE SURFACE

William J. Riffe, R.R. #2, Short Line Pike, Berea, Ky.
 Filed May 6, 1969, Ser. No. 822,155
 Int. Cl. G01n 21/30; H01j 3/14, 5/02
 U.S. Cl. 250-219

3 Claims



An apparatus is disclosed for converting printed material of any typefont into electrical signals suitable for conversion and use with a digital computer. Light transparent paper, with light impervious printed matter thereon, is placed on a roll and illuminated uniformly from within such roll. The page is scanned on a line to line basis by rotating the roll intermittently, and on a character by character basis by a motor driven tape carrying a light slit. The resulting light signal is converted into an analog electric signal representative of the scanned print, which can be converted to digital form for use in electronic data processing equipment.

3,577,164


REMOTE CONTROL STARTING SYSTEM

Giuseppe Re Baratelli, Glenview, and Theodore J. Galvani, Deerfield, Ill., assignors to Ramostar Corporation, Deerfield, Ill.

Filed June 5, 1968, Ser. No. 734,744
 Int. Cl. F02n 11/08

U.S. Cl. 290-38

13 Claims



A system for remotely controlling electrical devices as in the starting of automobiles and the like employing a transceiver/a receiver-transmitter and an actuating solenoid. The transceiver includes circuitry adapted to transmit selected radio frequency signals for performing selected functions during starting of the automobile. The receiver-transmitter includes circuitry adapted to transmit a signal to the transceiver upon receipt of a first check range signal from the transceiver, energize the auto ignition circuit and energize the auto starter upon receipt of a second signal from the transceiver, and energize the actuating solenoid upon receipt of a third signal. The solenoid is adapted to actuate the fuel linkage upon being energized. The receiver-transmitter circuit is further adapted to limit the running time of the engine upon starting, transmit an intermittent signal to the trans-

ceiver during initial engine running, and stop the engine upon opening a door of the auto during the initial engine running period.


3,577,165

LINEAR SCANNING ARRANGEMENT FOR A CYCLOIDAL MASS SPECTROMETER

Bradley A. Helliwell, Mountain View, and Donald D. Briglia, Palo Alto, Calif., assignors to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed May 31, 1968, Ser. No. 733,564
 Int. Cl. H03k 5/00, 7/00, 9/00
 U.S. Cl. 307-228

9 Claims



A partial pressure gauge scanning circuit arrangement for generating an electrostatic ion beam deflection voltage having a deflection waveform segment defined by the function $V=f(1/t)$, where V =deflection voltage and t =time, includes a circuit means having a nonlinear transfer characteristic, the derivative of which is proportional to the function $f(1/t)$. Circuit means apply an alternating signal of frequency f_1 and a signal of relatively lower frequency f_2 to the nonlinear circuit means in a manner for providing an amplitude modulated output signal of frequency f_1 . The output signal exhibits a modulation envelope defined by the differential of the logarithmic characteristic. Circuit means are provided for demodulating and integrating the amplitude modulated signal to provide a scanning output signal having a waveform defined as an inverse function of time.

3,577,166


C-MOS DYNAMIC BINARY COUNTER

Abraham K. Yung, East Brunswick, N.J., assignor to RCA Corporation

Filed Sept. 17, 1968, Ser. No. 760,218
 Int. Cl. H03k 3/26

U.S. Cl. 307-279

14 Claims



A dynamic flip-flop comprising two inverter means and two switching means is described. The switching means couple, by different conduction paths, the input node of one inverter means to the input node and to the output means of the other inverter. The switching means are alternately enabled by a clocking signal varying at a first rate causing the signals at the inputs and outputs of both inverter means to vary at one half said first rate.

The temporary or momentary storage provided by the capacitance at the input node of an inverter stage, coupled with the single pole, double throw action of the switching means, enables the design of a dynamic binary counter using a minimum number of components.

3,577,167

INTEGRATED CIRCUIT BIASING ARRANGEMENTS


Jack Avins, Princeton, N.J., assignor to RCA Corporation

Filed Feb. 29, 1968, Ser. No. 709,274

Int. Cl. H02m 3/14

U.S. Cl. 307-296

10 Claims



A low output impedance bias supply for integrated circuit amplifier configurations capable of delivering an output voltage that is a constant fraction of a power supply potential. Two transistors are connected in a degenerative feedback arrangement with a pair of resistors and with a pair of semiconductor diodes, the ratio of the resistors determining the fractional output voltage developed and the diodes serving to provide a low output impedance at high frequencies.

3,577,168

LONG DELAY TIMING SYSTEM


William J. Tuten, and Godfrey R. Gauld, Richmond, Ind., assignors to Avco Corporation, Richmond, Va.

Filed June 21, 1968, Ser. No. 739,011

Int. Cl. H03k 17/28

U.S. Cl. 307-293

7 Claims



The disclosure illustrates a longterm timing system comprising a battery coupled to an electrochemical cell through a pulsing circuit. The electrochemical cell is of the type that requires current flow above a minimum value to enable proper operation. The pulses from the pulsing circuit have a peak substantially greater than the minimum permissible current level but the pulses are substantially spaced in time. The resultant average current flow is then low enough so that the time at which the impedance of the electrochemical cell changes is greatly increased.

3,577,169

COEXISTING CRYSTALLINE SOLUTION PHASES ACTIVATED BY DIVALENT EUROPIUM

Thomas L. Barry, Beverly, Mass., assignor to Sylvania Electric Products, Inc.

No. drawing. Continuation-in-part of application Ser. No. 506,868, Nov. 8, 1965, now abandoned. This application Aug. 5, 1968, Ser. No. 750,122

Int. Cl. H01j 1/63

U.S. Cl. 313-109

3 Claims

A blue-emitting Eu^{2+} activated, fluorescent phosphor of coexisting crystalline phases of the spinel structure of MgAl_2O_4 and the corundum structure of $\alpha\text{-Al}_2\text{O}_3$ is useful in fluorescent and mercury vapor lamps. The essential cations of each structure are Al, Mg and Si. In the corundum phase, the Si^{4+} and Mg^{2+} ions displace Al^{3+} ions, are disposed in the corundum lattice of Al_2O_3 and are present in significant quantities, but less than the limit of mutual solubility of the Si^{4+} and Mg^{2+} ions in the corundum lattice. In the spinel phase, Si atoms and site vacancies displace Mg atoms in the

spinel lattice and are present in significant quantities, but less than the limit of solubility of Si atoms and vacancies in the spinel lattice.

3,577,170

DOUBLE-GAP SPARK PLUG


Gustav P. Nylén, 5868 Picker St., Arlington, Calif.

Filed Jan. 15, 1969, Ser. No. 791,446

Int. Cl. H01t 13/46, 13/22

U.S. Cl. 313-123

2 Claims



A spark plug having two spark gaps connected in series, the first gap being formed between the main, positive electrode extending lengthwise through the plug and a first electrode finger attached to a conductor sleeve embracing the lower end of the porcelain insulating stem of the plug. The second spark gap is defined between the conductor sleeve and a second electrode finger attached to the conductive base portion of the plug which is secured in threaded engagement with an engine block.

3,577,171

SYSTEM USING A MODIFIED ULTRASONIC IMAGING TUBE


William R. Turner, Rockville, Md., assignor to Vitro Corporation of America, New York, N.Y.

Filed Sept. 3, 1968, Ser. No. 756,866

Int. Cl. G01n 9/24, 29/00; H01j 29/41, 31/48


U.S. Cl. 315-9

2 Claims




An improved ultrasonic to visual signal conversion system utilizing a cathode ray tube, said tube having a piezoelectric face plate or conversion plate, a controlling screen adjacent thereto and a collector electrode back of the screen for receiving current generated by the conversion plate. The collector current is utilized to control a video tube synchronized with the first tube, and is shunted in feedback fashion to the screen to control terminal admittance thereof and thereby increase the signal to noise ratio of the system as well as to raise the effective signal level.

3,577,172
SELF-QUENCHING ELECTRODE FOR CROSSED FIELD TRAVELING WAVE DEVICES
 Edward C. Dench, Annisquam, Mass., assignor to Raytheon Company, Lexington, Mass.
 Filed Nov. 28, 1969, Ser. No. 880,580
 Int. Cl. H01j 25/34
 U.S. Cl. 315—39.3 11 Claims



A crossed field device of the reentrant electron beam and nonreentrant nonresonant transmission network type having means for substantially automatically quenching electron-traveling wave interaction initiated by electromagnetic energy signal pulses during nonoperation intervals. Such means are disposed adjacent to the drift space area of the interaction region and include a lumped capacitive-resistive network coupled to electrode means to rapidly terminate electron emission.

3,577,173
LAMP FAILURE DETECTION AND CHANGE DEVICE
 Jack P. Blomgren, Maplewood, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.
 Filed Jan. 10, 1969, Ser. No. 790,415
 Int. Cl. F21v 19/04; H05h 37/04
 U.S. Cl. 315—88 5 Claims




A projector which has a device for automatically replacing an expired main lamp with a spare lamp. The main lamp and the spare lamp are socketed in a lamp-changing mechanism which is operated in response to the operation of a lamp failure detector. The detector radiantly senses the failure of the main lamp and automatically activates the lamp-changing mechanism which will remove the main lamp from the focus position, advance the spare lamp into the focus position, and energize the spare lamp.

3,577,174
CIRCUIT FOR STARTING AND MAINTAINING A DISCHARGE THROUGH A GAS DISCHARGE TUBE
 Richard W. Longsdorff, Lancaster, Pa., assignor to RCA Corporation
 Filed Sept. 20, 1968, Ser. No. 761,083
 Int. Cl. H05b 37/00
 U.S. Cl. 315—170 9 Claims


A capacitance, which is charged by the output of a DC power supply, is placed in series aiding relationship with the output of the DC power supply during the start period of a gas discharge tube, i.e., until ignition is achieved and the

capacitance discharges through the tube. This permits the required "fill in" or "boost" voltage to be obtained during



starting without drawing excessive peak currents from the power supply when ignition is started.

3,577,175
INDIUM ANTIMONIDE INFRARED DETECTOR CONTACT
 Norman I. Gri, Cincinnati, and Eugene T. Yon, Cleveland, Ohio, assignors to Avco Corporation, Cincinnati, Ohio
 Division of Ser. No. 723,994, Apr. 25, 1968, Pat. No. 3,483,096.
 Filed July 3, 1969, Ser. No. 860,448
 Int. Cl. H01l 15/06
 U.S. Cl. 317—237 2 Claims




The invention here disclosed is an indium antimonide infrared detector having a novel contact region. The detector comprises a substrate, constituted of an N-material with a P-region fused thereon. An anodized surface oxide film is superimposed over the diffused P-region and over the adjacent surface of the substrate. A silicon oxide layer is disposed over most of the anodized surface oxide film but exposes a portion of the P-region which portion comprises superimposed layers of chromium and gold which form the contact region, said layers masking the contact area and rendering it insensitive to infrared radiation and simultaneously providing a pad to which an electrical connection may conveniently be made.

3,577,176
CONSTANT CURRENT STEP MOTOR SYSTEM
 Marvin L. Kreithen, Feasterville, and John J. Lawler, Newportville, Pa., assignors to Compudyne Corporation, Hatboro, Pa.
 Filed Apr. 26, 1968, Ser. No. 724,556
 Int. Cl. H02p 7/06
 U.S. Cl. 318—432 7 Claims

In a control circuit for a step motor, current through the motor windings is sensed by voltage drop across a series resistor. This voltage is used to control a feedback circuit which regulates the power supply in such a way that the output torque of the step motor remains constant. Preferably the potential across the series resistor is compared with a voltage reference. Any error signal generated as a result of a difference is used to generate pulses at a frequency proportional to the error voltage derived from the sensing resistor. These


pulses are synchronized with a rectified alternating current input and are used to determine and select whatever part of

phase detector which is time-shared by the several loops is fed to a reset integrator, then a level detector, and to the set-reset terminals of a plurality of flip-flops. The flip-flops are sequentially clocked by respective timing signals correspond-



that input, if any, will be used to supplement available current to maintain constant the torque of the step motor.

3,577,177
ZERO-CROSSING SILICON CONTROLLED RECTIFIER CONTROL SYSTEM
 Clarence Wilson Hewlett, Jr., Hampton, N.H., assignor to General Electric Company
 Filed June 26, 1969, Ser. No. 836,816
 Int. Cl. G05f 1/44
 U.S. Cl. 323—18 12 Claims



A zero-crossing silicon controlled rectifier control system for single-phase, full-wave and three-phase operation. An error signal representing the difference between desired and actual load values is integrated to control a first switch constituted by complementary transistors. A second switch, in series with a pulse generator and the first switch, is conductive during portions of alternate half cycles. Concurrent conduction by both switches energizes the pulse generator which causes a pulse to be generated on the energization. This turns on a first silicon controlled rectifier at the beginning with the positive-going zero crossing. A second silicon controlled rectifier controlled by a trigger circuit conducts during the next half cycle in response to load energization.

3,577,178
PHASE LOCK INDICATOR FOR PLURAL PHASE LOCK LOOPS
 Opie D. Hawley, San Pedro, Calif., assignor to Northrop Corporation, Beverly Hills, Calif.
 Filed Apr. 15, 1969, Ser. No. 816,225
 Int. Cl. G01r 25/00
 U.S. Cl. 324—83D 6 Claims

An indicator or monitor is disclosed which shows whether each of a plurality of phase lock loops are locked onto their respective incoming signals or not. The output of a single in-

ing to the occurrence of the incoming signals associated with their particular loop. The output state of each flip-flop drives an indicator lamp circuit to show the desired locked or not locked condition.

3,577,179
ACTIVE FILTER
 Duval West, Houston, Tex., assignor to Geo Space Corporation
 Filed Aug. 6, 1969, Ser. No. 847,860
 Int. Cl. H03f 1/36
 U.S. Cl. 330—107 12 Claims




This invention relates to an improved low-pass, active, elliptic-function filter. One state of the filter includes a twin-T, RC network having an input terminal, an output terminal and a feedback terminal. The output terminal is connected to ground through a capacitor; the input terminal is connected to ground through a capacitor; and the feedback terminal is connected to the output terminal of a noninverting amplifier having a gain greater than or equal to unity. The input terminal of the amplifier is connected to the output terminal of the twin-T network. The source of incoming signals is connected through a resistor to the input terminal of the twin-T network. The filter can be made to include two or more stages connected in tandem combination.

3,577,180
ELECTROMECHANICAL FILTER
 Hans Albsmeier, and Karl Traub, Munich, Germany, assignors to Siemens Aktiengesellschaft, Berlin, Germany
 Filed May 1, 1968, Ser. No. 725,790
 Claims priority, application Germany, May 12, 1967, S109,856
 Int. Cl. H03h 9/26
 U.S. Cl. 333—72 12 Claims

An electromechanical filter utilizing a plurality of rods mounted on a base plate parallel to each other and having

one side of each resonator flattened or coupled together by a driving rod. Input and output electromechanical transducers



are provided and a second rod is connected to certain of said resonators to eliminate undesired frequency characteristics.

3,577,181

TRANSISTOR PACKAGE FOR MICROWAVE STRIPLINE CIRCUITS


Erwin F. Belohoubek, Kendall Park, N.J., assignor to RCA Corporation

Filed Feb. 13, 1969, Ser. No. 799,019

Int. Cl. H01p 3/08

U.S. Cl. 333-84

3 Claims



Package for mounting a transistor in a microwave stripline circuit comprising a metal base member, means disposed on the base member for grounding the emitter or base electrode of the transistor, and segments of low impedance microwave transmission lines disposed adjacent the grounding means, one of these including a ceramic core having both good dielectric and good heat conducting properties and being adapted to support the transistor and connect it to an RF output circuit. The other segment is adapted to electrically connect the transistor to an RF input circuit.

3,577,182

SWITCH-OVER CONTACT ARRANGEMENT FOR POWER RELAYS

Herbert Krautwald; Helmut Moller, and Richard Siepmann, Munich, Germany, assignors to Siemens Aktiengesellschaft, Berlin and Munich, Germany


Filed Feb. 17, 1969, Ser. No. 799,785

Claims priority, application Switzerland, Feb. 19, 1968, 2470/68

Int. Cl. H01h 1/12

U.S. Cl. 335-185

10 Claims



A low profile power relay contact is made possible by an assembly comprising a bifurcated contact spring having one

shank bent above a level of the spring and overlapping an unbent shank whereby the bifurcated portions securely grip but do not impart rotative forces to an operating member which is moved up and down in response to movement of an armature by an electromagnetic field. A first carrier plate lies in generally the same plane as the unbent portion of the contact spring and is below the bent contact spring while a second carrier plate is bent to lie above the unbent carrier spring whereby upon movement of the operating member a contact is made and a contact is broken.

3,577,183

ELECTRICAL TEMPERATURE SENSOR

Hermann Walter Gruenling, Erlangen-Bruck, Germany, assignor to Siemens Aktiengesellschaft, Berlin and Munich, Germany

Filed Feb. 28, 1968, Ser. No. 708,882

Claims priority, application Germany, Mar. 25, 1967, S109022

Int. Cl. H01c 7/08

U.S. Cl. 338-26

4 Claims



Wire of a material having electrical resistance which varies in magnitude in accordance with temperature variations is covered with glass insulation and is directly mounted on a body whose temperature is to be sensed.

3,577,184

LOW-DISTORTION SEISMOMETER


William O. McNeel, and Louis W. Erath, Houston, Tex., assignors to Geo Space Corporation

Filed Mar. 14, 1969, Ser. No. 807,186

Int. Cl. H04r 9/04

U.S. Cl. 340-17

9 Claims



A compact, high-sensitivity, low-distortion, electromagnetic-type seismometer having a pair of coils forming part of a mass-coil assembly concentrically suspended in an annular airgap established by a permanent magnet. The suspension system includes a pair of spring spiders which are clampingly secured to the mass-coil assembly by a pair of insulating retainer rings to allow the springs and the mass-coil assembly freedom of relative motion when the mass-coil assembly becomes subjected to unbalanced rotational moments. The symmetry of construction assures a compact, rugged seismometer of very low distortion. Advantage is taken of the preformed stresses in the springs to assure continuous, wiping, low-resistance contacts between the current-carrying springs and the coil terminals.

3,577,185

ON-LINE SYSTEM FOR MEASURING THE EFFICIENCY OF REPLACEMENT ALGORITHMS


Laszlo A. Belady, Yorktown Heights, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Oct. 2, 1969, Ser. No. 863,265

Int. Cl. G06f 15/00

U.S. Cl. 340-172.5

10 Claims



Technique for dynamically measuring the efficiency of a replacement algorithm in a virtual-memory data processing system. Each time the actual replacement algorithm effects the replacement of a "block" or "page" stored in the working memory, the measurement system automatically compares the number of such replacement that have been made with the number that would have been required by an assumed "optimal" replacement algorithm, the latter being unable to make its determinations in real time. The difference between the actual replacement count and the optimal replacement count is the number of unnecessary block transfers. The efficiency measurement functions are performed during those periods when the processor has been interrupted for a block replacement and is awaiting the entry of a newly demanded block into the working memory. Thus, the present system makes its efficiency measurements in an efficient manner. To accomplish this, the system utilizes an associative memory or equivalent storage mapping means having provisions for storing special reference bits (R' bits) in the words respectively associated with the addresses in working memory. Each time a block stored in working memory is referenced by the processor, the R' bit associated with that block is set. Then, when the next block replacement occurs, the measurement system is able, with the aid of these R' bits, to update the optimal replacement pattern, or more specifically, to determine what blocks currently would have been present in the working memory if the optimal replacement algorithm had been followed and, therefore, whether the currently demanded replacement operation would have been necessary if said algorithm had been followed. The measurement system also is able to detect the occasional instances, if any, in which the actual replacement algorithm is able to avoid making a block replacement that the optimal algorithm would have found necessary. The system is further able to detect when, due to incomplete knowledge of the order of referencing, it is uncertain whether the optimal algorithm could have avoided making the currently demanded block replacement, and in such a case the system specifies a possible range of values for the replacement efficiency.

3,577,186

INVERSION-TOLERANT RANDOM ERROR CORRECTING DIGITAL DATA TRANSMISSION SYSTEM

Michael E. Mitchell, Syracuse, N.Y., assignor to General Electric Company

Filed May 28, 1969, Ser. No. 828,485


Int. Cl. G08c 25/00; H04l 7/00

U.S. Cl. 340-146.1

4 Claims

A digital data transmission system is disclosed which decodes received error correction coded digital signals properly, irrespective of whether or not the polarities of

these signals have become inverted during transmission or reception. The system thus permits a 180° phase ambiguity in the reinsertion of a regenerated suppressed carrier or subcarrier signal in the receiver, thereby simplifying the receiver in addition to correcting errors to improve the reliability of data transmission. The disclosed decoder circuitry includes a plurality of modulo 2 adder circuits for generating a plurality of



estimators each of which is the mod 2 sum of an even number of the received digits. These estimators are fed to a threshold decision circuit which provides a serial readout of the decoded digits. The threshold decision circuit may consist of a simple majority decision circuit or a multiple input threshold circuit with either equal or unequal weighting factors on its input estimators.

3,577,187

DIGITAL INFORMATION TRANSFER SYSTEM HAVING INTEGRITY CHECK


Ralph A. Benson, Peabody, Mass., assignor to General Electric Company

Filed Sept. 3, 1968, Ser. No. 756,995

Int. Cl. H04g 1/00, 3/00, 5/00

U.S. Cl. 340-163

14 Claims



A digital information transfer system for selecting and then enabling a remote utilization device by a digital address including means for assuring system integrity. A selector is actuated to energize one comparator input and generate a unique digital address to enable one utilization device. The digital complement of the enabled utilization device address is generated and transmitted to a decoder at the selector. If the correct utilization device is enabled, the digital complement is decoded to energize the second comparator input. Simultaneous energization of two comparator inputs enables means for operating the utilization device. If a system malfunction occurs, inputs to two different comparators are energized, thereby blocking further operation.

3,577,188

COUNTER-OPERATED CONTROL SYSTEMS


John A. Thomson, and Brian R. Evill, Surrey, England, assignors to Avery-Hardoll Limited, Chessington, Surrey County, England

Filed Apr. 30, 1968, Ser. No. 725,303

Int. Cl. H04q 1/20

U.S. Cl. 340—164

4 Claims



A counter-operated control system which can be set to initiate at least two control operations, one at a count which is less by a predetermined number than a selected maximum count, the other comprises a series of counters counting, for example, units, tens, hundreds etc., a separate settable unit associated with each counter and means responsive to the arrival of the counters at at least two numbers bearing different relations to the settings of the associated settable units to provide successive operation initiating signals to initiate the two control operations.

3,577,189

APPARATUS AND METHOD IN A DIGITAL COMPUTER FOR ALLOWING IMPROVED PROGRAM BRANCHING WITH BRANCH ANTICIPATION REDUCTION OF THE NUMBER OF BRANCHES, AND REDUCTION OF BRANCH DELAYS


John Cocke, Mount Kisco; Brian Randell, Pleasantville; Herbert Schorr, Briar Cliff, N.Y., and Edward H. Sussenguth, Los Altos, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 15, 1969, Ser. No. 791,255

Int. Cl. G06f 9/00, 9/16

U.S. Cl. 340—172.5

13 Claims



Apparatus and a method in a digital computer is disclosed for allowing improved program branching from a first instruction sequence to a second instruction sequence. Said apparatus includes means for decoding a branch instruction in said first sequence; means for determining parameters which are to enter into a condition determination, the resolution of which defines whether or not the branch is to be made; means for detecting a specific type instruction in said first

sequence subsequent to said branch instruction, said specific type instruction indicative of the point in the first instruction sequence at which the branch is to be made; and means responsive to said detection for ordering instructions from said second instruction sequence to be processed subsequent to the processing of said specific type instruction.

3,577,190

APPARATUS IN A DIGITAL COMPUTER FOR ALLOWING THE SKIPPING OF PREDETERMINED INSTRUCTIONS IN A SEQUENCE OF INSTRUCTIONS, IN RESPONSE TO THE OCCURRENCE OF CERTAIN CONDITIONS


John Cocke, Menlo Park; Philip S. Dauber; Herbert Schorr, and Edward H. Sussenguth, Los Altos, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed June 26, 1968, Ser. No. 740,360

Int. Cl. G06f 9/10

U.S. Cl. 340—172.5

9 Claims



Apparatus in a digital computer for allowing the skipping of predetermined instructions in a sequence of instructions is disclosed. Means are provided for detecting a specific type of instruction in a sequence of instructions. This specific type of instruction is referred to as a skip instruction and indicates that upon the occurrence of a specified machine condition, predetermined subsequent instructions in said sequence are to be skipped. Further means are provided to determine the occurrence of the specified machine condition, and to emit an output signal indicative of the occurrence. Means responsive to the output signal effect the skipping of the predetermined instructions.

3,577,191

MAGNETIC HEAD ASSEMBLY WITH SIDEBAR


Eduard E. Haertlein, Fremont, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Aug. 5, 1968, Ser. No. 750,227

Int. Cl. G11b 5/10, 5/42

U.S. Cl. 340—174.1F

8 Claims



A magnetic head assembly, useful for noncontact magnetic recording, is formed to provide an inner cavity, wherein a thin magnetic core is fixed against a cavity wall. A magnetic sidebar, to which electrical coils are mounted, is secured adjacent to the core to complete the magnetic circuit.

3,577,192

REPRODUCE HEAD WITH PEAK SENSING CIRCUIT


Carl E. Schlaepfer, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Feb. 1, 1968, Ser. No. 702,265

Int. Cl. G11b 5/02

U.S. Cl. 340—174.1H

2 Claims



In an apparatus for reproducing a data signal recorded on a magnetic medium, a playback circuit comprising a transducer providing an electrical signal, a linear integrator coupled to said signal transducing means for detecting the peaks of the electrical signal and for developing a peak-detected signal that traverses and is equal to a reference signal level in substantially simultaneous time correspondence with said peak; and a wave shaper for producing a digital waveform having transitions in simultaneous time correspondence with said peaks.

3,577,193

THERMAL CELL

Irving J. Hutkin, San Diego, Calif., assignor to Whittaker Corporation, Los Angeles, Calif.

Division of Ser. No. 475,022, July 26, 1965, Pat. No. 3,416,971.

Filed Mar. 22, 1968, Ser. No. 737,266

Int. Cl. G08b 17/06; H01c 7/00; H01v 1/14

U.S. Cl. 340—228

2 Claims



An improved device in the form of a web for detecting fires and other high temperature conditions comprises a conductive ring with a number of filamentary thermal cells mounted thereon, each cell including a core comprising stainless steel with a glass coating of specific composition disposed on the core and ionically conductive at a certain temperature. A sheath of metal, such as silver, dissimilar to the core metal is disposed on the glass coating. A lattice form of a spaced plurality of intersection cells connected at opposite ends to the ring and interwoven with one another at the intersections is provided.

3,577,194

ANALOG TO DIGITAL CONVERSION CIRCUIT


Donald L. Beall, Syracuse, N.Y., assignor to General Electric Company

Filed Jan. 3, 1969, Ser. No. 788,867

Int. Cl. H03k 13/02

U.S. Cl. 340—347AD

4 Claims



An analog-to-digital conversion circuit is disclosed, which converts a varying analog signal to the nearest available digital value by the successive approximation technique. The

circuit includes a summing mode for the analog and various digital voltages, followed by a chopper switch, AC amplifier, sample-and-hold circuit, voltage comparator, and digital approximation control circuits. The advantageous results are high speed, excellent resolution and accuracy, and low drift characteristics.

3,577,195

SERVOED METER APPARATUS


Charles E. Clift, Phoenix, Ariz., assignor to Sperry Rand Corporation

Filed Apr. 14, 1969, Ser. No. 815,933

Int. Cl. G01r 17/06

U.S. Cl. 343—108

13 Claims



Apparatus for positioning an indicator in accordance with a control signal including a D'Arsonval-type meter movement having an auxiliary AC excitation winding on the field magnet thereby providing both a unidirectional and an alternating flux field for the meter movement magnetic circuit. The meter armature has two windings, one being excited by a control signal and reacting with the unidirectional field to displace the armature and the other operating to sense both the displacement of the armature and the rate of change of said displacement by reacting respectively with the alternating and unidirectional fields. When included in a closed-loop servosystem the meter movement operates as both a servodrive and an angular motion transducer providing displacement and rate feedback terms.

3,577,196

ROLLABLE SLOT ANTENNA


Eugene F. Pereda, 460 Electric Ave., Seal Beach, Calif.

Filed Nov. 25, 1968, Ser. No. 778,487

Int. Cl. H01q 13/10

U.S. Cl. 343—770

5 Claims



An antenna having a rectangular sheet of metal foil with parallel spaced slots formed therein. The slotted sheet serves as a radiator operating in the UHF band. The metal sheet is enclosed between overlying and underlying plastic sheets

which are heat sealed to the metal sheet. The composite laminate structure is flexible thus permitting the rolling thereof.

3,577,197

SLOTTED CABLE LOCALIZER ANTENNA


Chester B. Watts, Jr., 6505 Pinecrest Court, Annandale, Va.

Filed Sept. 4, 1969, Ser. No. 855,142

Int. Cl. H01q 13/10

U.S. Cl. 343-771

4 Claims



This invention relates to antennas for simultaneous transmission of sum and difference patterns as in a runway localizer for instrument landing of airplanes. A straight horizontal run of coaxial cable, placed centrally perpendicular to the extension of the runway centerline, is symmetrically fed from both ends by an RF bridge in sum and difference modes. The outer conductor of the cable is periodically interrupted by slots which permit currents to flow on the outside of the outer conductor. The antenna current distributions corresponding to the two modes are controlled by low-resistance shunts placed across the slots and by the relationship between the slots spacing and the internal guide-wavelength. To maintain the relationship over the 4 percent band of localizer frequencies, the guide-wavelength is adjusted always to the same value by filling the cable with the necessary quantity of a gas of relatively high-dielectric constant.

3,577,198

CHARGED DROP GENERATOR WITH GUARD SYSTEM


Dale R. Beam, Chillicothe, Ohio, assignor to The Mead Corporation, Montgomery County, Ohio

Continuation-in-part of application Ser. No. 782,048, Dec. 9, 1968, now abandoned. This application Nov. 24, 1969, Ser. No. 879,131

Int. Cl. G01d 15/18

U.S. Cl. 346-75

1 Claim



In apparatus for selectively charging of individual drops in a liquid stream or fluid filament divided into drops, a grounded guard electrode surrounds the stream between a charging electrode and a set of electrodes which create a deflection field. This isolates the fluid filament tip from the deflecting electrodes and avoids induced charges on it from the deflection field.

3,577,199 MEASURING IRRADIATION-INDUCED DEFORMATIONS OF MATERIALS


Warner W. Schultz, Schenectady, N.Y., assignor to the United States of America as represented by the United States Atomic Energy Commission

Filed Aug. 22, 1969, Ser. No. 852,360

Int. Cl. G01t 3/00, 5/00

U.S. Cl. 250-83.1

8 Claims



This invention relates to a method and apparatus for measuring irradiation-induced change in length of a test sample. Neutron irradiation produces a differential change in length between the lengths of a test sample and a comparison standard. Mechanical pivot means are provided for magnifying the differential change in length. Means including a source of fissionable material and a track detector surface are provided for recording the magnified differential change in length.

3,577,200

REAL-TIME SOLID STATE CAMERA SYSTEM


Ralph E. Aldrich, Arlington, and Paul J. Caruso, Bedford, Mass., assignors to Itek Corporation, Lexington, Mass.

Filed Sept. 12, 1968, Ser. No. 759,360

Int. Cl. H04n 3/10

U.S. Cl. 178-7.1

13 Claims



Camera apparatus is disclosed for sensing the pattern of modulation imposed by an electro-optic medium on radiation as a function of the electric field established across the electro-optic medium by the effect of a radiant image projected on a photoconductor medium associated with the electro-optic medium across which mediums an electric field has been established.

3,577,201

PORTABLE COMPUTER TERMINAL

Jesse T. Quatse, Pittsburgh, Pa., and Brook Dixon, Seldon, N.Y., assignors to Vernitron Corporation, Farmingdale, N.Y.

Filed Jan. 8, 1968, Ser. No. 696,174


Int. Cl. H04m 11/06

U.S. Cl. 179-2DP

5 Claims

The invention is concerned with a logic decoder means which senses a signal indicative of whether a teletype machine or a computer originates a communicative line between a portable computer terminal and the computer. The modulator and demodulator within the portable terminal computer operate in different frequency bands and have

filter networks adapted to be switched into circuit with the information signals, in response to output signals from the



logic decoder and thereby set the respective frequency bands in the modulator and demodulator.

3,577,202

TELEPHONE HYBRID ARRANGEMENT WITH FREQUENCY SEPARATION FOR USE WITH TDM SYSTEMS


Barrie Brightman, Webster, N.Y., assignor to Stromberg-Carlson Corporation, Rochester, N.Y.

Filed July 6, 1967, Ser. No. 651,568

Int. Cl. H04j 1/06

U.S. Cl. 179-15A

6 Claims



A telephone hybrid system for use with a TDM switching center including filter arrangements at the center and at the subscriber subsets, which serve as hybrid circuits to establish directivity of signalling. A carrier signal at the frequency of the TDM frame rate and derived from the TDM system is used to transmit signals from the switching center to the subsets, thus enabling directional separation by simple filtering.

3,577,203

CHARACTER RECORDING AND RECOGNITION SYSTEM

Kenneth M. Beach, Jr., Webster, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Filed Apr. 18, 1968, Ser. No. 722,293


Int. Cl. G06k 7/08, 9/18

U.S. Cl. 235-61.11

7 Claims

A system for automatically reading alphanumeric characters recorded on a document wherein the symbols are shaped so as to be also recognizable by human beings. The apparatus comprises a transport for advancing a document strip past a

plurality of stations which include a marking station at which magnetic material is applied as alphanumeric characters in response to discrete signals, a recording station at which flux patterns associated with the characters are impressed in superposed relationship therewith in response to frequency signals, and frequency signals in timed relation to the move-



ment of the document. The magnetic material may have an electrostatic component to enable electrostatic recording or may comprise magnetic particles in solid or liquid form. A detection circuit is provided for reading out the character frequency patterns and supplying this information in signal form to a utility device.

3,577,204

NOVEL PHOTOGRAPHIC PROCESS OF DIFFUSION TRANSFER OF X-RAY IMAGE WITH PHOSPHORESCENT LUMINOPIHOR

Joel M. Peisach, Hudson, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

No drawing. Filed Mar. 17, 1967, Ser. No. 623,990

Int. Cl. G01n 21/34

U.S. Cl. 250-65

6 Claims

X-ray exposures may be reduced by using a film containing an integral X-ray intensifier screen composed of phosphorescent luminophors, and intensifying the latent image by actinic radiation emitted after the X-ray exposure has ceased. The thus exposed and intensified film is diffusion transfer processed to provide a silver transfer image.

3,577,205

AUTOMATIC IMAGE MOTION STABILIZATION SYSTEM


Gilbert L. Hobrough, Woburn, Mass., assignor to Itek Corporation, Lexington, Mass.

Filed Nov. 19, 1965, Ser. No. 508,779

Int. Cl. H01j 31/50

U.S. Cl. 250-213

5 Claims



An image motion stabilization system for use with telescopes, cameras, and the like. An inner casing containing an objective lens and an image converter is mounted within an outer support casing so as to be movable with respect thereto. Displacement of the outer casing with respect to the

inner casing caused by vibration or movement produces a corresponding displacement of the electron stream in the image converter such that a stable image of a scene viewed by the objective lens will be presented to an ocular in the outer casing.

3,577,206

COMPLEMENTARY FIELD-EFFECT TRANSISTOR MIXER


Philip J. Ferrell, Seattle, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed Apr. 28, 1969, Ser. No. 819,591

Int. Cl. H03k 17/00

U.S. Cl. 307-240

7 Claims



A pair of complementary field-effect transistors with common source connections are connected with a first input signal identically common to both drains and a second input signal identically common to both gates so as to give a mixed first and second signal output through a balanced subtractor connected between the drains.

3,577,207

MICROWAVE PLASMATRON


Vladimir Pavlovich Kirjushin, ulitsa Sovetskaya 1-a, kv.5., Fryazino, U.S.S.R.

Filed May 7, 1969, Ser. No. 822,450

Int. Cl. H01j 7/46; 19/80

U.S. Cl. 315-39

4 Claims



A device for producing low-temperature plasma of microwave discharge at atmospheric pressure of a plasma-forming gas suitable for conducting chemical reactions of extreme purity, depositing thin films, growing crystals, producing powders and other technological purposes. The device includes a spherical or radial waveguide wherein there is excited a converging symmetrical electromagnetic wave, and a discharge tube disposed on the axis of symmetry of the waveguide.

3,577,208

ELECTROSTATIC GROUNDING PROBE FOR USE IN EXPLOSIVE ATMOSPHERES

John T. Petrick, Fredericksburg, Va.

Filed July 3, 1969, Ser. No. 838,923


Int. Cl. H01r 3/06; H05f

U.S. Cl. 317-2R

6 Claims

A grounding probe having a stationary contact connected to ground through a high resistance. A movable contact is normally biased away from the stationary contact but can be

moved adjacent the stationary contact by pressing it against the object to be grounded. The area where stationary and



movable contacts come together is enclosed so that any spark is isolated from the atmosphere.

3,577,209

ELECTRIC IGNITION SYSTEM


Charles H. Perkins, Richmond, Va., assignor to Robertshaw Controls Company, Richmond, Va.

Filed Feb. 28, 1969, Ser. No. 803,297

Int. Cl. F23g 7/10

U.S. Cl. 317-98

4 Claims



An electric ignition system utilizing an electric ignitor having a positive temperature coefficient of resistance and a negative temperature coefficient resistor coupled in series therewith to provide a constant resistance series network.

3,577,210

SOLID-STATE STORAGE DEVICE


Hans G. Dill, Costa Mesa, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.

Filed Feb. 17, 1969, Ser. No. 799,817

Int. Cl. H01l 11/00; 11/14

U.S. Cl. 317-235

30 Claims



A solid-state storage device in the form of an insulated gate field effect tetrode. A depletion region is created in the channel so that an electric field emanating from one gate can penetrate the channel and attract high energy charge carriers into traps in the insulator. The charge carriers enter the insulator by surmounting the Schottky barrier at the semiconductor-insulator interface.

CHEMICAL

3,577,211

STABILIZATION OF POLYESTERS

Warren K. Wilson, Cuyahoga Falls, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed May 22, 1967, Ser. No. 640,403

Int. Cl. D06m 13/12, 13/16

U.S. Cl. 8-115.5

3 Claims

This invention relates to the process in which an organic polymeric structure is treated with a polyacid chloride and then with a reactive ultraviolet light stabilizer to form a structure having a chemically bonded stabilizer.

3,577,212

PROCESS FOR THE MODIFICATION OF POLYAMIDE FIBERS

Marcel Georges Jirou, Sotteville les Rouen, and Pierre Charles Victor Bouvet, Petit-Quevilly, France, assignors to Ugine Kuhlmann, Paris, France

No Drawing. Filed Aug. 7, 1967, Ser. No. 658,613

Claims priority, application France, Aug. 8, 1966,


72,363

Int. Cl. D06p 3/34

U.S. Cl. 8-115.5

7 Claims

Process for the modification of synthetic polyamide fibers which comprises treating the fibers at a pH of from 3 to 11 inclusive and at a temperature of from 40° C. to the boiling temperature of the bath with a compound of the formula:



in which A₁ represents a non-colouring, aliphatic, aromatic or heterocyclic radical, W represents the residue of an acylating agent carrying an atom or group of atoms capable of reacting with the polyamide fibers, and R represents a hydrogen atom or an alkyl group having 1 to 4 carbon atoms, the amount of compound (I) used being between 0.1% and 20% by weight of the polyamide fibers. The treated fibers have different properties from untreated polyamide fibers and in particular their affinity for acid dyestuffs is reduced or rendered practically nil.

3,577,213

FIBER PRODUCT AND PROCESS

William J. Myles, Charlotte, N.C., and Roland K. Kunkel, Berkeley Heights, N.J., assignors to Celanese Corporation, New York, N.Y.

Original application Jan. 4, 1965, Ser. No. 423,137.


Divided and this application July 12, 1968, Ser.

No. 758,174

Int. Cl. D06m 1/100

U.S. Cl. 8-130

3 Claims



A process comprising preparing filaments each of which contains at least two segments in eccentric relationship

in its cross-section all along its length, one of said segments being a saponifiable cellulose ester containing quaternary ammonium salt dispersed throughout its interior and the other segment being a cellulose ester free of quaternary ammonium salts.

3,577,214

PROCESS FOR CLEANING FABRICS

Ambrose E. Le Van, Short Hills, N.J., and David Tatum, Swarthmore, Pa., assignors to Ametek, Inc., New York, N.Y.

Filed Oct. 19, 1967, Ser. No. 676,503

Int. Cl. B08b 7/04

U.S. Cl. 8-137

9 Claims

A process for cleaning soiled fabrics which utilizes an apparently dry cleaning medium comprising a finely particulate carrier adsorbed with a cleaning liquid. The soiled fabric is placed into a plenum containing the cleaning medium and the medium is fluidized by directing an air stream through the plenum. Differential motion is applied by transducer means to the particulates of the medium while the fabric is in the plenum. The foreign material carried by the fabric is transferred to the cleaning medium due to the scouring action of the medium. The apparatus for the process comprises an enclosure having within it the mentioned plenum, means for retaining the soiled fabric within the plenum and means for directing an air stream through the cleaning medium to fluidize the cleaning medium and thereafter to recirculate the air stream. Transducer means applies a differential motion to the particulates to aid in the cleaning action.

3,577,215

DRY CLEANING PROCESS

Ector P. Impullitti, Detroit, Mich., assignor to F. W. Means & Company, Chicago, Ill.

Filed Feb. 3, 1969, Ser. No. 796,069

Int. Cl. D06l 1/02

U.S. Cl. 8-142

10 Claims

Oil impregnated textile cleaning utensils can be cleaned and prepared for reuse in a single brief operation by using a petroleum mineral oil as the cleaning medium. The utensils are cleaned by placing them into the wheel of a commercial dry cleaning apparatus then adding an excess of oil beyond that necessary to saturate the utensils at a temperature between 60-250° F. and agitating the wheel for about 15 minutes. The oil is drained off and the utensils are spun to remove excess oil but leave about 20 to 40 wt. percent oil in the utensil based on the weight of the clean, dry utensil or implement.

3,577,216

PROCESS FOR THE RECOVERY OF SELENIUM IV UTILIZED AS A CATALYST FOR OXIDATION REACTIONS

Francis Weiss and Andre Lakodey, Pierre-Benite, Rhone, France, assignors to Ugine Kuhlmann, Paris, France

No Drawing. Filed Nov. 24, 1967, Ser. No. 685,282

Claims priority, application France, Nov. 29, 1966,

85,385

Int. Cl. C01b 19/00

U.S. Cl. 23-50

11 Claims

A process for the recovery of selenium IV which has been used as a catalyst in the oxidation of organic compounds by oxygen, hydrogen peroxide, or organic peroxides which comprises precipitating a metal selenite from the reaction environment or medium at the end of the

oxidation process, separating the precipitated metal selenite from the medium and extracting therefrom selenious acid or anhydride which may be recycled.

3,577,217

PROCESS FOR RECOVERING A CHROMATE AND CUPRIC OXIDE BY DECOMPOSITION OF A CATALYST OR WASTE CATALYST OF COPPER CHROMITE

Takuo Machida, Takarazuka-shi, and Masataka Nakagawa, Yamato-Takada-shi, Japan, assignors to Sumitomo Chemical Company, Ltd., Osaka, Japan
No Drawing. Filed Sept. 30, 1968, Ser. No. 763,984
Int. Cl. C01g 37/14, 3/02

U.S. Cl. 23—56


2 Claims

A process is provided for recovering a chromate and cupric oxide by decomposition of a catalyst or waste catalyst of copper chromite mainly represented by the formula



which comprises the steps of

- (a) mixing said catalyst or waste catalyst with an alkali metal compound of the formula



wherein

M is an alkali metal selected from sodium and potassium;

B is an oxygen atom, a carbonic radical, a bicarbonic radical or a hydroxy radical; and each m and n is either 1 or 2, dependent upon the respective valences of M and B;

- (b) heating the resultant mixture of (a) at a temperature of from 300° C. to 1200° C. in the presence of oxygen or a molecular oxygen-containing gas; and
- (c) mixing the resultant mixture of (b) with water to recover cupric oxide as an insoluble solid and a chromic acid salt of said alkali metal as an aqueous solution.

3,577,218

METHOD FOR THE PRODUCTION OF HYDROGEN CYANIDE WHEREIN PLATINIZED MULLITE SERVES AS A CATALYST


Patrick M. Brown, Catonsville, and Heyman C. Duecker, Rockville, Md., assignors to W. R. Grace & Co., New York, N.Y.

Filed Aug. 28, 1968, Ser. No. 755,938

Int. Cl. C01c 3/02; B01j 9/04

U.S. Cl. 23—151

3 Claims



A mixture of ammonia and methane is reacted over platinated mullite catalyst to give high yields of hydrogen

cyanide. The catalyst is prepared by depositing platinum on either natural or synthetic mullite; it possesses improved stability and avoids the problem of carbonitridation frequently encountered in use of alumina as a catalyst support in the production of hydrogen cyanide.

3,577,219

RECOVERY OF SULFUR DIOXIDE FROM WASTE GASES

Indravadan S. Shah, Forest Hills, N.Y., assignor to Chemical Construction Corporation, New York, N.Y.

Filed Nov. 1, 1968, Ser. No. 772,547

Int. Cl. C01b 17/72; C01f 5/42

U.S. Cl. 23—168

12 Claims

A process is provided to efficiently and economically absorb and recover sulfur dioxide from a waste gas stream such as the tail gas from a sulfuric acid facility, or flue gas from the combustion of a sulfur-containing fuel. The process thus eliminates air pollution, and produces a useful sulfur-containing product from the recovered sulfur dioxide. The waste gas stream is scrubbed with a recirculating aqueous slurry containing magnesium oxide and magnesium sulfite. A small quantity of magnesium sulfate may be present if formed as a result of oxidation of magnesium sulfite or absorption of sulfur trioxide.

3,577,220

PROCESS FOR PRODUCTION OF MONOSILANE (SiH₄) AND GERMANIUM HYDRIDE (GeH₄)

Tatsuo Kuratomi, 4-2-18 Hamatake, Chigasaki, and Yoshifumi Yatsurugi, 6-507, 7-2-chome, Tsujido Nishi-kaigan, Fujisawa, both of Kanagawa, Japan


Filed Oct. 29, 1968, Ser. No. 771,405

Claims priority, application Japan, Oct. 31, 1967, 42/69,592

Int. Cl. C01b 33/04; C22b 41/00

U.S. Cl. 23—204

9 Claims



A process for producing monosilane (SiH₄) comprising reacting magnesium silicide with a concentration of ammonium thiocyanate in liquid ammonia at ambient temperature and pressure. Also, a process for producing germanium hydride (GeH₄) comprising reacting magnesium germanide with a concentration of ammonium thiocyanate in liquid ammonia at ambient temperature and pressure.

3,577,221

HYDROGEN MANUFACTURE

Calvin S. Smith and William J. McLeod, El Cerrito, Calif., assignors to Chevron Research Company, San Francisco, Calif.

Continuation-in-part of application Ser. No. 736,520, May 17, 1968, which is a continuation-in-part of abandoned application Ser. No. 665,106, Sept. 1, 1967. This application Dec. 31, 1968, Ser. No. 788,300

Int. Cl. C01b 1/02, 1/18


U.S. Cl. 23—213

7 Claims

According to the present invention a process is provided for producing high pressure hydrogen which comprises:

- (a) generating a hydrogen-rich gas stream containing CO and CO₂;

- (b) removing CO₂ from the hydrogen-rich gas stream to obtain a CO₂ lean, hydrogen-rich gas stream;
- (c) centrifugally compressing the CO₂-lean, hydrogen-rich gas stream to a pressure of above about 400 p.s.i.g.; and



- (d) reacting CO contained in the CO₂-lean, hydrogen-rich gas stream with H₂O at a pressure of above about 400 p.s.i.g.

Preferably CO₂ is removed from the hydrogen obtained after step (d) and the purified compressed hydrogen is used in a hydroconversion process.

3,577,222

CARBON MONOXIDE DETECTOR


John M. Ward, Lancaster, Pa., assignor to Armstrong Cork Company, Lancaster, Pa.

Filed Nov. 15, 1968, Ser. No. 776,011

Int. Cl. G01n 31/10

U.S. Cl. 23—254

3 Claims



The carbon monoxide detector comprises two parallel mounted cylinders of metal having a high coefficient of linear expansion and spaced apart from one another on a common base. A chemical catalyst of the type capable of generating heat when exposed to a minimal concentration of carbon monoxide is mounted within a porous tube placed within one of the cylinders. Free air is allowed to enter the catalyst containing cylinder from its base and circulate about the catalyst. The heat generated by the catalytic reaction of carbon monoxide in air will cause the linear expansion of the cylinder thereby closing the microswitching mechanism mounted partly at the top of each cylinder. By using two cylinders having a high coefficient of linear expansion, changes in ambient temperature may be compensated for.

3,577,223

SLURRY DISTRIBUTOR

Alan Longacre, Whittier, Calif., assignor to Fluor Corporation, Los Angeles, Calif.

Filed Aug. 11, 1969, Ser. No. 849,096


Int. Cl. B01j 2/12

U.S. Cl. 23—259.1

10 Claims

Partially ammoniated phosphoric acid slurry is distributed onto a bed of ammonium phosphate granules

by a tubular distributor comprising concentric pipes spaced to provide a passage for the slurry which is



aspirated by steam discharged from the inner pipe through nozzles spaced from and aligned with counter-sunk openings in the outer pipe.

3,577,224

APPARATUS FOR PRODUCTION OF HIGH PRESSURE POLYETHYLENE


Martin Hess, Pittsburgh, and Lawrence Saroff, Carnegie, Pa., assignors to Sinclair-Koppers Company

Filed Sept. 9, 1968, Ser. No. 758,315

Int. Cl. B01j 9/08; C08f 1/60, 3/04

U.S. Cl. 23—285

3 Claims



An improved method and apparatus is provided for production of high pressure polyethylene in a sparger tube reactor. Cold ethylene gas is radially injected into the polymerization zone in variable amounts at spaced increments. Catalyst-rich gas is also injected into the polymerization zone at spaced increments in variable amounts with respect to the cold ethylene gas injection. Injection of both cold ethylene gas and catalyst-rich gas, at spaced increments and in various amounts with respect to each other provides control of reaction and, therefore, of temperature profile. Thus, an essentially constant temperature and pressure profile can be maintained throughout the polymerization zone.

3,577,225
METHOD FOR SEPARATING URANIUM, PROTACTINIUM, AND RARE EARTH FISSION PRODUCTS FROM SPENT MOLTEN FLUORIDE SALT REACTOR FUELS


James H. Shaffer, Oak Ridge, David M. Moulton, Knoxville, and Warren R. Grimes, Oak Ridge, Tenn., assignors to the United States of America as represented by the United States Atomic Energy Commission
 Continuation-in-part of application Ser. No. 745,837, July 18, 1968. This application May 15, 1969, Ser. No. 824,944

The portion of the term of the patent subsequent to Oct. 21, 1986, has been disclaimed

Int. Cl. C22b 61/04

U.S. Cl. 23—325

5 Claims



A method for reprocessing spent molten metallic fluoride salt mixtures suitable as molten salt breeder reactor fuels is provided whereby uranium and bred-in protactinium values as well as certain fission products of the lanthanide series are selectively and consecutively extracted from the salt phase into an immiscible molten bismuth solution by controlling the reduction potential between the metal and salt phases. Uranium values, which are extracted first, are oxidized and transferred from the bismuth solution into a barren salt mixture for ultimate recycle to the reactor prior to extracting the contaminants. The protactinium values are then extracted at a slightly higher reduction potential into the bismuth solution, oxidized, and transferred to a molten salt outside the reactor environment to await decay of the protactinium-233 to uranium-233. Finally, the lanthanide elements are extracted at a yet higher reduction potential into the bismuth solution, oxidized, and transferred to a separate salt mixture for their recovery or disposal.

3,577,226
METAL BODIES OF UNIFORM POROSITY
 Raymond J. Elbert, Middleburg Heights, and Ernest G. Farrier, Parma, Ohio, assignors to Union Carbide Corporation, New York, N.Y.

No Drawing. Application June 30, 1967, Ser. No. 650,250, now Patent No. 3,433,632, dated Mar. 18, 1969, which is a continuation-in-part of application Ser. No. 484,123, Aug. 31, 1965. Divided and this application Feb. 10, 1969, Ser. No. 798,142

Int. Cl. B22f 1/00

U.S. Cl. 29—182

2 Claims

Sintered porous metal sheet, having not more than about one pore per twenty-five (25) square feet of sheet with a size larger than three times the average pore size of said sheet.

3,577,227
TUNGSTEN MATERIALS AND A METHOD FOR PROVIDING SUCH MATERIALS

Gall F. Davies, Mentor, Ohio, assignor to the United States of America as represented by the Secretary of the Navy

No Drawing. Filed Oct. 4, 1968, Ser. No. 766,038

Int. Cl. C22c 15/00

U.S. Cl. 29—182

2 Claims

A method for shaping and forming metallic tungsten by coating tungsten particles with a minor amount of me-

tallic rhenium and thereafter compacting and partially sintering said coated particles. A method for providing intricate shapes of high temperature resistant, non-ductile tungsten by re-sintering said compacted and sintered rhenium coated tungsten particles at a temperature sufficient to diffuse the metallic rhenium into the tungsten. A ductile, readily formable tungsten mass and a non-ductile, highly temperature resistant, tungsten mass provided by the foregoing methods.

3,577,228
SMOKE SUPPRESSANT FUEL MIXTURE
 Charanjit Rai, Somerset, Sherman D. Collins, Edison, and Elmer J. Badin, Hightstown, N.J., assignors to Cities Service Oil Company, Tulsa, Okla.

No Drawing. Filed Jan. 3, 1969, Ser. No. 788,922

Int. Cl. C101 1/18, 1/26

U.S. Cl. 44—76

25 Claims

A liquid fuel mixture having reduced soot and smoking characteristics comprises a major portion of a hydrocarbon fuel and a minor portion of a Group II-A metal organyl orthophosphate. Preferably, a barium salt of a dialkyl orthophosphoric acid is employed in amounts from about 0.1 to 2% by weight. Further improvement results when an ether, particularly a glycol ether, is additionally incorporated into the orthophosphate and fuel mixture.

3,577,229
METHOD AND APPARATUS FOR MAKING FERTILIZER

Hans-Erwin Brück, 16 Gartenfeldstr., 55 Trier, Germany


Filed Dec. 26, 1968, Ser. No. 786,984

Claims priority, application Germany, Feb. 23, 1968, P 16 67 788.6

Int. Cl. C05f 7/00

U.S. Cl. 71—9

15 Claims



In producing a spreadable grain size fertilizer from a mixture of garbage and fecal matter the garbage is treated to place it in a relatively small grain size after any metallic and fibrous materials have been removed, and the fecal matter, such as in a sewage system, is treated to remove solids, fats and detergents. The treated garbage and fecal matter is mixed as a sludge and is biologically fermented after which water is added to the fermented sludge. After a drying and granulating operation, the fermented sludge is bagged for use as a fertilizer.

3,577,230
PROCESS OF APPLYING NOVEL ALGICIDES
 Edward Helmut Sheers, Flushing, N.Y., assignor to Arizona Chemical Company, New York, N.Y.

No Drawing. Filed Oct. 18, 1968, Ser. No. 768,919

Int. Cl. A01n 9/26

U.S. Cl. 71—67

3 Claims

A method for destroying or inhibiting microorganisms by contacting them with a trans-hydroxy-stilbene derivative, and a composition comprising said stilbene.


3,577,231
PROCESS FOR PREPARING METAL SULFIDES
 Marvin Pesses, Youngstown, Ohio, assignor to Mercer Alloys Corporation

Filed Aug. 23, 1968, Ser. No. 754,811

Int. Cl. C01g 3/12, 51/00, 53/00

U.S. Cl. 75—1

4 Claims



A process for producing a concentrate of metallic sulfides (especially nickel sulfide, copper sulfide and cobalt sulfide) from metallic scrap materials. The scrap materials are melted under a reducing atmosphere and injected with sulfur-bearing material during the pouring of the molten material from the melting furnace to a ladle. Thereafter, the molten mixture of sulfides is rapidly cooled and subdivided to produce a homogeneous, friable, synthetic ore.

3,577,232
REMOVING NICKEL FROM CADMIUM
 John A. Ruppert, Edgewood Farms, Ellicott City, Md. 21042, and Dominic Montagna, 6144 31st St. NW., Washington, D.C. 20015

No Drawing. Filed May 29, 1969, Ser. No. 829,092

Int. Cl. C22b 9/10, 17/00, 23/00

U.S. Cl. 75—71

10 Claims

A molten halide flux is formed on top of a metallic melt of nickel-contaminated cadmium. Phosphorus is then added to the flux, and the phosphorus ingests into the metallic melt through the flux-metal interface to react with the nickel so as to form insoluble nickel-phosphorus compounds which are then removed from the molten cadmium.

3,577,233
HIGH TEMPERATURE BRAZING ALLOYS
 Nicholas T. Gamer, Palo Alto, Calif., assignor to Western Gold & Platinum Company

No Drawing. Filed Sept. 10, 1968, Ser. No. 758,705

Int. Cl. C22c 5/00

U.S. Cl. 75—134

11 Claims

Brazing alloys comprising in percent by weight 25-70% gold, 5-30% palladium, 15-40% nickel, 4-12% chromium and .01 to 2% yttrium. These alloys exhibit substantial ductility and high oxidation and corrosion resistance at service temperatures of 1600-1800° F. and above continuously for 100 hours or more and therefore having particular utility in joining stainless steel and superalloys in aircraft and space craft engines and components. The addition of up to about 2% by weight of tungsten, tantalum or molybdenum to these alloys further improves their high temperature strength.

3,577,234
BRAZING ALLOYS
 John D. Boughton, Philip M. Roberts, and Mieczyslaw Herman Sloboda, London, England, assignors to Johnson, Matthey & Co. Limited, London, England

No Drawing. Filed Aug. 4, 1967, Ser. No. 658,350

Claims priority, application Great Britain, Aug. 18, 1966, 37,053/66

Int. Cl. C22c 9/06; B32b 15/20

U.S. Cl. 75—159

4 Claims

This invention relates to a brazing alloy suitable for the fluxless brazing of steels (unalloyed and alloy steels

including stainless steel). The brazing alloy consists essentially of 0.5-10% nickel, 0.01-0.05% boron and the balance copper.

3,577,235
ELECTROPHOTOGRAPHIC COMPOSITION AND ELEMENT
 Lawrence E. Contois, Webster, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 754,499, Aug. 21, 1968. This application Feb. 17, 1969, Ser. No. 799,917

Int. Cl. G03g 5/08, 5/06

U.S. Cl. 96—1.6

10 Claims

4-aminobenzo[b]pyrylium and 4-aminobenzo[b]thiapyrylium salts are sensitizers for organo-metallic photoconductors. Photoconductive compositions sensitized with these compounds have increased electrophotographic speed and are sensitive in the ultraviolet region of the spectrum.

3,577,236
COLOR DIFFUSION TRANSFER PROCESSES AND ELEMENTS COMPRISING AUXILIARY DEVELOPERS OR THEIR PRECURSORS

Delbert D. Fix, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Sept. 29, 1969, Ser. No. 861,997

Int. Cl. G03c 7/00, 5/30

U.S. Cl. 96—3

28 Claims

Improved minimum print densities are produced in color diffusion transfer systems by processing in the presence of a lactone derivative silver halide developing agent, such as a coumarin derivative, which has the property of forming a lactone developing agent precursor under acid, neutral and slightly alkaline conditions.

3,577,237
DIFFUSION TRANSFER PHOTOGRAPHIC PRODUCTS AND PROCESSES COMPRISING ACID-REACTING REAGENTS AND POLYETHER BLOCK COPOLYMERS AS PLASTICIZERS THEREFOR


Lloyd D. Taylor, Everett, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed Sept. 23, 1968, Ser. No. 761,772


Int. Cl. G03c 7/00, 5/54

U.S. Cl. 96—3

27 Claims



Plasticization of the layer of a diffusion transfer image-receiving sheet containing an acid-reacting reagent may be accomplished by incorporating therein a compound selected from the group consisting of block polyether compounds of the formulae:



where R, R₁ and R₃ are alkylene groups and x and y are integers representing the molar ratio of respective blocks. Concomitant with the plasticization effect increased temperature latitude is imparted to the system.

3,577,238 FERROCENE DYES AND PHOTOGRAPHIC ELEMENTS


Jacque K. Lindsay, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.
No Drawing. Filed Mar. 28, 1969, Ser. No. 811,567
Int. Cl. G03c 1/64; G03f 7/10

U.S. Cl. 96—28 9 Claims
Light-sensitive ferrocene dyes are prepared by condensing formylferrocene or a vinyllog thereof such as formylvinylferrocene with a heterocyclic reagent in an alkaline medium. The dyes so prepared are light-sensitive and operate to harden or tan gelatin upon exposure to light.

3,577,239 METHOD OF PHOTOGRAPHICALLY PRODUCING PLATED-THROUGH HOLES IN PRINTED CIR- CUIT BOARDS

Matthew W. Lesniewski, Bloomingdale, N.J., assignor to Monsanto Company, St. Louis, Mo.
Filed Dec. 16, 1968, Ser. No. 783,924
Int. Cl. G03c 5/00

U.S. Cl. 96—36.2 4 Claims




Production of plated-through holes in printed circuit cards by drilling holes at predetermined locations in a base material, plating the interior hole surfaces with a thin layer of conductive metal, coating with a layer of photo-resist, vacuum-drawing portions of a flexible metal foil into the holes, and exposing the photo-resist and foil to light, whereby the photo-resist covering the interior surfaces of the holes is properly exposed.


3,577,240 DIFFUSION TRANSFER PHOTOGRAPHIC MATERIALS

Fumihiko Nishio, Odawara-shi, and Reichi Ohi and Tatsuyo Tajima, Minamiashigara-machi, Japan, assignors to Fuji Shashin Film Kabushiki Kaisha, Ashigarakami-gun, Kanagawa-ken, Japan
No Drawing. Continuation-in-part of application Ser. No. 431,453, Feb. 9, 1965. This application Oct. 24, 1968, Ser. No. 770,412

U.S. Cl. 96—52 12 Claims
A toning agent represented by the general formula



wherein R and R₁ each represents a hydrogen atom, a lower alkyl group or an aryl group; X represents a hydroxyl group and



(where R₁ and R₂ each represents a lower alkyl group or aryl group and R₁ and R₂ may together complete a heterocyclic ring); and Y represents



(where R₃ represents a lower alkyl group or an aralkyl group), is used in diffusion transfer photographic material to give deep black images or printings on a positive material in diffusion transfer photography.

3,577,241 METHOD OF PREPARING EDIBLE ANIMAL FEET

Ray H. Means, Omaha, and Michael Kussman and Jack Wade, Papillion, Nebr., and Victor H. Vodra, Denver, Colo., assignors to American Beef Packers, Inc., Omaha, Nebr.

No Drawing. Filed Apr. 10, 1969, Ser. No. 815,224
Int. Cl. A22c 18/00
U.S. Cl. 99—7 9 Claims
A new process for preparing edible animal feet (particularly cattle and horses' feet) cleans and dehaired the feet mechanically by scalding the same in a hot caustic wash in a mechanical washing machine to remove dirt and hair from the feet; the cleaned and dehaired feet are bleached in a sodium percarbonate treatment at a lower temperature than the scald, and the resulting feet are rinsed and neutralized in non-toxic acid rinse solution.

3,577,242 ANTEMORTEM METHOD OF TENDERIZING MEAT

Edwin P. Jenevein, Jr., 7036 Town N., Dallas, Tex. 75231
No Drawing. Filed June 6, 1966, Ser. No. 555,289
Int. Cl. A22c 18/00

U.S. Cl. 99—107 6 Claims
An antemortem method of tenderizing meat by administering to an animal before slaughter a collagen diminution agent (an agent which will destroy and/or inhibit collagen formation, but will not materially attack muscle cells in the subject animal), and allowing the collagen diminution agent to assimilate within the animal before it is slaughtered.

3,577,243 PROCESS OF EXTRACTING MEAT FROM CRABTAILS


Peter W. Bynagte, San Diego, Calif., assignor to Westgate-California Foods, Inc., San Diego, Calif.
No Drawing. Filed Oct. 17, 1968, Ser. No. 768,503
Int. Cl. A22c 29/00; A23l 1/33

U.S. Cl. 99—111 5 Claims
The process of extracting the meat from crabtails wherein the crabtails are dipped into a solution of salt water, sodium acid pyrophosphate or calcium acid pyrophosphate and sodium tripolyphosphate for a period of at least two minutes during which time the solution is agitated and then removing the meat from the crabtails and pre-cooking the meat in boiling water.

3,577,244 PRESERVATION OF LIMESTONE STRUCTURES

Seymour Z. Lewin, New York, N.Y., assignor to New York University, New York, N.Y.
Continuation-in-part of application Ser. No. 529,213, Feb. 23, 1965. This application Dec. 19, 1968, Ser. No. 785,316
Int. Cl. C09k 3/10
U.S. Cl. 106—12 20 Claims
This application is directed to a process and composition for preserving stone objects having at least 10%

calcium carbonate by maintaining the stone in contact with an aqueous solution for a sufficient period of time to



improve the weathering properties of the stone. One embodiment includes applying a solution of barium hydroxide, urea, glycerin and water to the stone.

3,577,245 BORON NITRIDE ARTICLE HAVING IMPROVED THERMAL STABILITY

Herbert C. Quandt, Lakewood, Ohio, assignor to Union Carbide Corporation
No Drawing. Filed Nov. 3, 1967, Ser. No. 680,330
Int. Cl. C04b 33/00; C01b 21/06

U.S. Cl. 106—39 5 Claims
Method of improving the high temperature stability of boron nitride articles by treatment with calcium cyanamide.

3,577,246 REFRACTORY SHAPE WITH PREREACTIONED GRAIN

Joseph E. Neely, Los Gatos, Calif., assignor to Kaiser Aluminum & Chemical Corporation, Oakland, Calif.
No Drawing. Filed Nov. 25, 1968, Ser. No. 778,764
Int. Cl. C04b 35/42
U.S. Cl. 106—59 8 Claims
A refractory shape of lower porosity and enhanced high temperature strength is made from coarse refractory grain retained on a 100 mesh screen and prereacted magnesia-chrome grain passing a 100 mesh screen by incorporating from about 0.5% to about 15%, by weight of the total composition, finely divided alumina.

3,577,247 MAGNESIUM ALUMINATE SPINEL BONDED REFRACTORY

Bernard D. McKenna, San Jose, Calif., assignor to Kaiser Aluminum & Chemical Corporation, Oakland, Calif.
No Drawing. Filed Nov. 25, 1968, Ser. No. 778,756
Int. Cl. C04b 35/44

U.S. Cl. 106—62 7 Claims
A magnesium aluminate spinel bonded shape is made by admixing refractory grain retained on a 100 mesh screen with magnesium aluminate grain passing a 100 mesh screen and containing up to three moles of magnesia for each mole of alumina, and sufficient —100 mesh alumina to react with the —100 mesh magnesium aluminate grain to form a matrix containing not over 1.25 moles of magnesia for each mole of alumina, and firing the admixture after forming it into a shape.

3,577,248 LOW MOLECULAR WEIGHT LINEAR ALKYL BEN- ZENE SULFONATE AS FROTHING AGENTS FOR GYPSUM BOARD MANUFACTURE

Robert B. Doan, Drexel Hill, and Robert C. Taylor, King of Prussia, Pa., assignors to Atlantic Richfield Company, Philadelphia, Pa.
No Drawing. Filed Nov. 6, 1967, Ser. No. 680,989
Int. Cl. C04b 11/00
U.S. Cl. 106—111 8 Claims
This invention relates to gypsum boards and to a method for producing the board which utilizes as a frothing agent an alkyl benzene sulfonate having a linear secondary alkyl side chain with an average carbon content ranging from 8.5 to 10.5 and a maximum carbon number spread of 8 carbon atoms. Preferably, the average carbon content ranges from 9.5 to 10.5 and the carbon number spread is a maximum of 5 carbon atoms. This frothing agent is generally utilized in amounts ranging from 0.01 to 0.1 part per 100 parts by weight gypsum.

3,577,249 BITUMINOUS DISPERSIONS HAVING IMPROVED ADHESION AND PROCESS THEREOF

Jack N. Dybalski, Chicago, Ill., assignor to Armour Industrial Chemical Company, Chicago, Ill.
No Drawing. Filed Feb. 10, 1969, Ser. No. 798,135
Int. Cl. C08h 13/00; C08k 1/62; C09d 3/24

U.S. Cl. 106—269 9 Claims
Bituminous dispersion containing a bituminous phase in an amount from 20–90 wt. percent can be provided with unusually good adhesion by the addition of certain aryl-substituted aliphatic nitrogen compounds. These compounds are long chain mono-aralkyl or di-aralkyl amines, aralkyl diamines, and their oil-soluble salts.


3,577,250 METHOD OF RUBBERIZING ASPHALT

Fritz S. Rostler, Berkeley, Calif., assignor to Phillips Petroleum Company, Bartlesville, Okla.
No Drawing. Filed Mar. 20, 1968, Ser. No. 714,424
Int. Cl. C08h 13/00; C08j 1/46; C09d 3/24
U.S. Cl. 106—278 16 Claims
Method of incorporating an elastomer into asphalt by treating the asphalt pavement with an emulsion having an external water phase and an oil phase containing a dissolved elastomer, the oil preferably having an initial boiling point of not substantially less than 300° C. at 760 mm. Hg and a viscosity of above about 50 SUS at 210° F., the oil being mutually compatible with the asphalt and the elastomer.

3,577,251 MOLDING POWDER FOR PROJECTABLE TARGET

Vernon C. Moehlman, St. Louis, and Robert J. Klein, Florissant, Mo., assignors to Olin Corporation
Continuation of application Ser. No. 680,276, Sept. 14, 1967, which is a division of application Ser. No. 569,283, Aug. 1, 1966, which in turn is a continuation-in-part of application Ser. No. 338,031, Jan. 16, 1964. This application Feb. 26, 1969, Ser. No. 804,370
Int. Cl. C08h 13/00

U.S. Cl. 106—284 9 Claims



A molding powder adapted to be briquetted to a coherent but brittle compact of the size and shape of a

frangible target of the projectable type. The molding powder comprises granules of limestone all of which are at least partially encapsulated by a coal tar pitch.

3,577,252

PROCESS OF PRODUCING ZIRCONIUM SILICATE CERAMIC COLORING SUBSTANCES

Wilhelm Brugger, Essen, Germany, assignor to Th. Goldschmidt A.G., Essen, Germany
No Drawing. Filed Sept. 11, 1968, Ser. No. 759,223
Claims priority, application Germany, Sept. 13, 1967, P 16 46 550.2
Int. Cl. C03c 5/02; C09c 1/00

U.S. Cl. 106—299 8 Claims

Process of producing ceramic coloring substances suitable as glaze stains. Metal oxide containing, color producing mixtures are calcined or sintered in the presence of 1-5% by weight, calculated on the amount of the mixture to be sintered, of a halogenated hydrocarbon having a boiling or sublimation point above 50° C.

3,577,253

TITANIUM DIOXIDE PIGMENT COMPOSITION

Warren M. Foss, Metuchen, N.J., assignor to National Lead Company, New York, N.Y.
No Drawing. Filed Aug. 28, 1968, Ser. No. 755,776
Int. Cl. C09c 1/36, 3/02; C09d 5/02

U.S. Cl. 106—300 4 Claims

This invention describes a new type of titanium dioxide pigment composition which is vastly superior to any of the prior art pigments when used in acrylic systems, such as thermosetting or thermoplastic acrylic automotive finishes and exterior acrylic latex paints. The new titanium dioxide pigment composition is finely divided TiO₂ pigment particles containing a calcined coating of



composition in which the ratio of SiO₂ to Al₂O₃ is 3-8 to 1 and the ratio of SiO₂ to Na₂O is 5-20 to 1. The amount of coating is from 5% to 12%. A method for the preparation of this pigment composition is also described. The SiO₂-Al₂O₃-Na₂O composition is precipitated onto the surface of the pigment at pH 3.5-6.5 and after adjusting the pH to 7.0-8.5 the coated TiO₂ pigment is calcined at 700-825° C.

3,577,254

PIGMENT DISPERSIONS

Frederick E. Petke, Princeton, N.J., assignor to Cities Service Company
No Drawing. Filed Mar. 22, 1968, Ser. No. 715,151
Int. Cl. C09c 3/02

U.S. Cl. 106—308 17 Claims

Highly concentrated, stable base pigment dispersions in organic solvents are prepared by adding pigment to an organic solvent in the presence of surfactant. The rate of pigment addition is adjusted so that proper wetting out of the pigment in the solvent occurs. Pigment addition is continued until a high shear mass is obtained. This mass is then subjected to agitation for a sufficient period of time to break down pigment agglomerates and to disperse the pigment throughout the organic solvent. In order to obtain a base pigment dispersion composition that can be readily mixed with additional solvent and binder material, the viscosity of the high shear mass may be reduced by mixing additional organic solvent therewith. Pigment concentrations of from about 45% to about 90% by weight of the resulting base pigment dispersions are obtained. Any suitable binder material may be thereafter incorporated in the base pigment dispersion composition to produce a finished pigment-binder dispersion composition of high gloss and excellent dispersion characteristics.

3,577,255

PIGMENT DISPERSIONS

Frederick E. Petke, Princeton, N.J., assignor to Cities Service Company

No Drawing. Continuation-in-part of application Ser. No. 715,151, Mar. 22, 1968. This application Nov. 29, 1968, Ser. No. 780,298

Int. Cl. C09c 3/02

U.S. Cl. 106—308 19 Claims

Highly concentrated stable base pigment dispersions in organic solvents are prepared by adding pigment to an organic solvent or a blend of miscible organic solvents in the presence of surfactant. The rate of pigment addition is adjusted so that proper wetting out of the pigment in the solvent occurs. Pigment addition is continued until a high shear mass is obtained. This mass is then subjected to agitation for a sufficient period of time to break down pigment agglomerates and to disperse the pigment throughout the organic solvent. In order to obtain a base pigment dispersion composition that can be readily mixed with additional solvent and binder material, the viscosity of the high shear mass may be reduced by mixing additional organic solvent therewith. Pigment concentrations of from about 45% to about 90% by weight of the resulting base pigment dispersions are obtained. Any suitable binder material may thereafter be incorporated in the base pigment dispersion composition to produce a finished pigment-binder dispersion composition of high gloss and excellent dispersion characteristics. Great adaptability in determining the characteristics of the final coating composition can be achieved when the pigment is initially dispersed in a solvent blend rather than a single organic solvent. In addition, the desirable properties of the final composition are often enhanced by the use of such a solvent blend.

3,577,256

SCRATCH AND ABRASION RESISTANT COATINGS FOR GLASS

Charles L. Benford, Jr., and James E. Mielke, Toledo, Ohio, assignors to Owens-Illinois, Inc.
No Drawing. Continuation of application Ser. No. 480,130, Aug. 16, 1965. This application June 26, 1969, Ser. No. 841,677

Int. Cl. C03c 17/32

U.S. Cl. 117—6 6 Claims

Freshly formed glass tubing is provided with a water soluble, scratch and abrasion resistant coating which may also be removed by volatilization at annealing temperatures. The coating is applied as an aqueous solution containing 0.5% to 2% of an acrylic solution resin, 0.75% to 1.5% polyoxyethylene glycol and 0.075% to 0.25% melamine-formaldehyde solution resin. The solution may also include 0.025% to 0.05% polyvinyl alcohol.

3,577,257

METHOD FOR FORMING DECORATIVE POLYURETHANE COATINGS

George J. Hutzler, Williamsville, and Carl L. Schwenk, Cheektowaga, N.Y., assignors to Textron Inc.
No Drawing. Filed Oct. 30, 1968, Ser. No. 771,988
Int. Cl. B44d 1/16; B44c 1/06

U.S. Cl. 117—26 10 Claims

There is disclosed a method for forming decorative polyurethane coatings and in the procedure a solid substrate is coated with a liquid polyurethane composition, for instance, of the moisture-curing type. While the thus applied polyurethane is still tacky, particulate pigment solids bearing a curing aid for polyurethanes are placed on the coating. The solids-bearing coating is then covered with a clear polyurethane which again may be of the moisture-curing variety, and the curing air which is an integral part of the pigment solids has a curing effect on both the underlying and overlying polyurethane coat-

MAY 4, 1971

ings. The pigmented solids thus exert a decorative or coloring effect through the overlying clear coating. The curing aid may be either of the catalytic or reactive type. Since the curing aid is included in the particulate solids which do not contact the polyurethane vehicles until they are in place on the supporting substrate, the vehicles as a result, have adequate working time, and construction jobs, for instance, wherein the vehicles are formed as a monolithic or seamless flooring can be planned and executed with facility. The particulate solids are frequently thin chips composed of finely divided pigment solids, binder and curing aid.

3,577,258


WRAPPING MATERIAL FOR MOISTURE-CONTAINING ARTICLE AND METHOD FOR MAKING THE SAME

Joseph T. Sincavage, Knowltonwood, Pa., Carl R. Pepmeier, Fredericksburg, Va., and Louis E. Stoffregen, Springfield, Pa., assignors to FMC Corporation, Philadelphia, Pa.

Filed Mar. 19, 1968, Ser. No. 714,281

Int. Cl. B44d 1/44; B32h 23/08

U.S. Cl. 117—62 6 Claims



A wrapping material for encasing moisture-containing products formed of a non-fibrous, hydrophilic regenerated cellulose sheet having on at least one side thereof a coating of moistureproof material, such as, nitro-cellulose, polyethylene, vinyl copolymers, vinylidene copolymers, with the coated side having a selected area of lower moistureproof properties than the remainder thereof whereby the portion of the regenerated cellulose sheet adjacent to such selected area of a coated side is more receptive to moisture and thus more frangible than the remainder thereof.

3,577,259


LIQUID DEVELOPMENT OF ELECTROSTATIC LATENT IMAGES UTILIZING A TONER-FREE ZONE

Masamichi Sato, Yasuo Tamai, and Selji Matsumoto, Asaka-shi, and Goro Akashi, Odawara-shi, Japan, assignors to Xerox Corporation, Stamford, Conn.

Filed Sept. 19, 1968, Ser. No. 760,956

Int. Cl. C03g 13/10, 15/10

U.S. Cl. 117—37 15 Claims



Images are formed by providing a liquid developer bath comprising a continuous insulating liquid carrier

phase and a discontinuous particulate toner phase, forming in the bath at least one zone substantially free of the toner phase, transporting an imaging member bearing an electrostatic latent image through the toner-free zone and thereafter passing the imaging member through the remainder of the bath. The imaging member may be transported through a substantially toner-free zone in the bath after development of the latent image to further improve image quality.

3,577,260

DECORATIVE ARTICLE AND METHOD OF MANUFACTURE THEREFOR

Roberta J. Hanna, 7555 Ashburn St., Houston, Tex. 77017

No Drawing. Filed Nov. 21, 1967, Ser. No. 685,247

Int. Cl. B44d 1/02; B44c 5/06

U.S. Cl. 117—68 5 Claims

A manufactured, decorative article and method preferably formed on a base material having the desired shape and serving as a source of pigmentation wherein a resin coating essentially dissolves the base member while maintaining its shape, and dries with the pigmentation fused therethrough to define a decorative body having a desired color and texture of surface.

3,577,261

SUBSTRATE WITH ADHERENT LAYER HAVING COLOR IMPARTED BY SAID SUBSTRATE

Kenneth K. Klar, Cuyaboga Falls, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed Nov. 25, 1968, Ser. No. 778,778

Int. Cl. B32b 25/04, 27/20

U.S. Cl. 117—80 4 Claims

A composite structure comprising a substrate and an adherent layer deposited thereon having a color imparted by the substrate prepared by the method which comprises (A) obtaining a substrate comprising a mixture of a rubbery polymer selected from the group consisting of natural rubber and synthetic rubber, at least one rubber processing oil and a dye soluble in the processing oil, (B) depositing a layer on the surface of the substrate comprising a mixture of a particulate pigment and a solvent for the said dye, the said layer colored by the pigment in contrast to the color of the dye and the color of the substrate, (C) dissolving a portion of the dye in the solvent contained in the deposited layer to effect a change in color of the layer, and (D) substantially drying the said layer.

3,577,262

POLYESTER-SILOXANE COATED PRODUCT

John D. Nordstrom, Detroit, Mich., assignor to Ford Motor Company, Dearborn, Mich.

No Drawing. Filed Nov. 18, 1968, Ser. No. 776,780

Int. Cl. B44d 1/50; B41m 7/00

U.S. Cl. 117—93.31 8 Claims

A radiation-curable, film-forming paint binder is prepared from an alpha-beta olefinically unsaturated polyester and an alpha-beta olefinically unsaturated siloxane formed by reacting a siloxane having at least two functional groups selected from hydroxyl groups and hydrocarboxy groups with a hydroxyl bearing ester of an alpha-beta olefinically unsaturated carboxylic acid. The binder may also include vinyl monomers. The preferred hydroxyl bearing esters are acrylates and methacrylates. The paint binder is applied as a liquid film to a substrate and cured thereon by an electron beam.

3,577,274

RESIN COATINGS CONTAINING ZINC INCLUSIONS

Charles W. Taylor, Jr., Akron, and Daniel T. Conrad, Cuyahoga Falls, Ohio, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed Nov. 15, 1968, Ser. No. 776,267

Int. Cl. H01l 5/16

U.S. Cl. 117—213

8 Claims

Corrosion resistance together with electrical insulation is provided for ferrous substrates by a solid resinous coating containing between 9 to 35 percent by weight (1.6 to 10 percent by volume) of pulverulent zinc in a heat fusible resin such as polyester. The coating may be applied by any suitable powder coating method, e.g. fluidized-bed. The application process and articles produced thereby are disclosed.

3,577,275

SEMI-CONDUCTOR CRYSTAL SUPPORTS

John C. Kosco, St. Marys, Pa., assignor to Stackpole Carbon Company, St. Marys, Pa.

No Drawing. Continuation-in-part of application Ser. No. 569,575, Aug. 2, 1966. This application Apr. 2, 1969, Ser. No. 812,854

Int. Cl. C23c 13/08

U.S. Cl. 117—213

5 Claims

Semi-conductor crystal supports comprising a base of the group consisting of tungsten and molybdenum are prepared by oxidizing at least the surface of the base to which a current lead is to be soldered, coating at least that surface of the base with a metal of the group consisting of silver and copper, and then subjecting the coated base to hydrogen or other reducing atmosphere at a temperature above the melting point of the coating metal. Preferably the density of the base is at least 93 percent of theoretical.

3,577,276

ELECTRICAL RESISTORS

James Edge, Morpeth, England, assignor to Welwyn Electric Limited, Bedlington, Northumberland, England

Original application Sept. 26, 1967, Ser. No. 670,687.

Divided and this application Nov. 12, 1969, Ser. No. 871,279

Claims priority, application Great Britain, Sept. 27, 1966, 43,028/66

Int. Cl. C23b 5/62

U.S. Cl. 117—213

2 Claims

Electrical precision resistors having a ceramic former are provided with a resistance film of a nickel-phosphorus alloy with an electrical surface resistance value between 0.5 ohm to 500 kilohms per square, the alloy containing from 5 to 16% by weight of phosphorus, the thickness of the film varying from 220 Å. to 25,000 Å. and the root-mean-square deviation of film thickness between different samples of area with a dimension greater than 0.01 x 0.01 cm. is at most 8% of the mean thickness at the lowest electrical resistance value and at most 4% at the highest electrical resistance value; the manufacture of these resistors is effected batch-wise by a method involving reactivating a catalytic palladium layer, before electrolessly depositing the nickel-phosphorus film while tumbling the resistors in the plating solution, by washing with a reactivating solution containing hypophosphite and nickel ions, and the deposited nickel-phosphorus film is stabilized by heating in air to a temperature of from 100 to 400° C.

3,577,277

POLYMER COATINGS


Robert D. Fisher, Woodstock, and James A. Magee, Saugerties, N.Y., assignors to Ferroxcube Corporation, Inc., Saugerties, N.Y.

Filed Dec. 26, 1968, Ser. No. 786,998

Int. Cl. H01f 10/02; B44d 1/46

U.S. Cl. 117—234

2 Claims



A post treatment process of improving the characteristics of poly p-(xylylene) coated ferrite articles by heating the article to at or just above the melting point of the polymer and maintaining the temperature for a specified duration.

3,577,278

ARTICLE SURFACE TREATING APPARATUS AND METHOD


Robert L. Rohr, Scarsdale, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 23, 1968, Ser. No. 786,067

Int. Cl. B08b 3/02

U.S. Cl. 134—1

12 Claims



An article surface treating apparatus is described herein in which an article holder having a plurality of articles mounted thereon is buoyantly disposed in a tank containing a fluid. The article holder is continuously caused to rotate by a stream of a liquid solution impinging thereon, so as to cause the successive surface treatment of the articles. The articles may be subjected to a process, e.g. (cleaning and rinsing or etching and rinsing) wherein several solutions may be programmed to serially treat the surfaces of the plurality of articles.

3,577,279

METHOD AND APPARATUS FOR AUTOMATICALLY CLEANING SYRINGES

Gene E. Lightner, Kennett Square, Pa., and Howard Blair Muhlestein, Wilmington, and Louis E. Green, Newark, Del., assignors to Hewlett-Packard Company, Palo Alto, Calif.

Filed Nov. 26, 1968, Ser. No. 779,019

Int. Cl. B08b 9/00

U.S. Cl. 134—23

13 Claims



A sealed chamber is placed on the plunger end of an otherwise conventional syringe. The plunger is automatically moved axially through the sealed chamber. A wash solvent is introduced in the chamber such that as the plunger is withdrawn from the syringe, the plunger is cleaned by the solvent. Next a drying gas is introduced into the chamber to force the wash solvent down through the syringe, thereby cleaning the syringe and the syringe needle with the wash solvent. The plunger is reinserted in the syringe and the syringe is ready for reloading.

3,577,280

FAUCET-MOUNTED CLEANING DEVICE FOR PAINT ROLLERS


Robert W. George, 5620 26th Ave. S., Minneapolis, Minn. 55417

Filed Apr. 2, 1969, Ser. No. 812,694

Int. Cl. B08b 3/00

U.S. Cl. 134—138

3 Claims



A cylindrical casing has an open top and open bottom. A tubular member secured to the casing is provided with

a series of vertically spaced apertures which spray water onto the paint roller when inserted through the open top, the water being free to drain through the open bottom after impinging upon the paint roller. The upper end of the tubular member is equipped with coupling means for attaching the tubular member directly to a faucet so that the entire device is supported by the faucet when cleaning the roller.

3,577,281

RECHARGEABLE MOVING TAPE CELL


Clifford Harold Pountney and Edward Francis Miller, Harrisburg, Pa., assignors to AMP Incorporated, Harrisburg, Pa.

Filed Apr. 28, 1969, Ser. No. 819,548

Int. Cl. H01m 35/00

U.S. Cl. 136—6

20 Claims



A rechargeable cell comprising, in a charged state, a bulk aqueous electrolyte of potassium hydroxide saturated with zinc oxide; a cathode; and an anode comprising a long steel tape coated with zinc on its active surface. The tape is driven from a storage reel through a region in the electrolyte adjacent to the cathode, and onto a takeup reel, at speeds dependent on the load current or voltage, or both. During charging, the tape is driven in the opposite direction. The cathode may be a stationary air permeable electrode; or it may comprise a tape similar to the anode and tape and similarly driven, coated with silver oxide on its active surface.

3,577,282

METHOD OF OXIDIZING TIN

Walter A. Schubert, South Elgin, Ill., assignor to Elgin Metal Casket Company, Elgin, Ill.

No Drawing. Filed Apr. 1, 1969, Ser. No. 812,331

Int. Cl. C23f 5/02, 7/00

U.S. Cl. 148—6.24

9 Claims

A method of plating metallic articles with tin and of treating the tin plated articles to produce oxidation or the appearance of oxidation. The method includes an acid treatment of metallic articles which have been plated with tin by any suitable method of plating, by means of which the tin plate is altered to provide an appearance of oxidation and they may be mechanically treated thereafter to remove some of the material to produce an effect sometimes called "antiquing."


3,577,283

METHOD OF CASEHARDENING VANADIUM AND VANADIUM ALLOYS

John A. Zic, Oak Lawn, and George F. Hill, Chicago, Ill., and Ross M. Mayfield, deceased, late of Glen Ellyn, Ill., by Georgia P. Mayfield, sole heir, Glen Ellyn, Ill., assignors to the United States of America as represented by the United States Atomic Energy Commission
Filed Mar. 7, 1969, Ser. No. 805,384
Int. Cl. C21d 1/74

U.S. Cl. 148—20.3

1 Claim



A method of casehardening vanadium and vanadium alloys consisting predominantly of vanadium by heating the material briefly at 1100 to 1300° C. in an atmosphere of argon saturated with water vapor.

3,577,284

ACTIVATED FLUX

Alvin Schneider, Edison, and Joseph Tarnowsky, Teaneck, N.J., assignors to Alpha Metals, Inc., Jersey City, N.J.
No Drawing. Filed Apr. 7, 1969, Ser. No. 822,821
Int. Cl. C23c 1/12

U.S. Cl. 148—23

28 Claims

A flux for low melting point alloys composed of a fluxing agent and an activating agent of a phenacyl halide or a derivative thereof, which does not exceed safe limits for corrosion and electrical properties.

3,577,285

METHOD FOR EPITAXIALLY GROWING SILICON CARBIDE ONTO A CRYSTALLINE SUBSTRATE


Richard F. Rutz, Cold Spring, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Mar. 28, 1968, Ser. No. 716,928
Int. Cl. H01l 7/36; C01b 31/36; C23c 11/00

U.S. Cl. 148—175

9 Claims

Epitaxial growth of semiconductive materials is effected in an inert atmosphere by physically contacting the surfaces of a source of semiconductive material to particular surface areas of a crystalline substrate onto which such growth is to be effected. The source is heated to a temperature to cause rapid vaporization of the semiconductive material; the substrate is maintained at a slightly lower temperature to promote the condensation and epitaxial growth of the vaporized semiconductive material on the contacted substrate surfaces. The surface of the source

can be preformed so as to grow particular patterns of the semiconductive material onto the substrate surface. Conductivity-type determining impurities can be introduced



either into the inert atmosphere or be present in the source so as to impart a particular conductivity to the grown semiconductive material.


3,577,286

SEMICONDUCTOR PREPARATION AND DEPOSITION PROCESS

Melvin Berkenblit and Arnold Reisman, Yorktown Heights, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Filed Oct. 11, 1967, Ser. No. 674,471
Int. Cl. H01l 7/36, 7/00; C23c 11/00

U.S. Cl. 148—175

6 Claims



A process which includes the preparation of a substrate and subsequent epitaxial deposition of germanium on the substrate is described. Preparation of the substrate, either germanium or gallium arsenide, includes a chemical treatment step to remove surface films, rapid quenching, rinsing and drying steps, and a heating step prior to deposition. Deposition of germanium is carried out in an open tube disproportionation system, by introducing a germanium halide specie which is capable of disproportionating at a deposition site in concentrations and at velocities such that the deposition of germanium tends to be surface limited rather than mass transport limited. The deposition, preferably carried out on a (110) oriented substrate, is epitaxial, smooth and shiny and is suitable for subsequent processing requiring photographic techniques.

3,577,287

ALUMINUM DIFFUSION TECHNIQUE

John F. Norwich and Edward J. Roesener, Jr., Kokomo, Ind., assignors to General Motors Corporation, Detroit, Mich.
Filed Feb. 12, 1968, Ser. No. 704,676
Int. Cl. H01l 7/44

U.S. Cl. 148—189

5 Claims

A technique for producing an improved aluminum diffusion region in a silicon surface adjacent a surface region that is heavily doped with an N-type impurity such as phosphorus. Improved rectifying junctions sustaining higher back voltages and having lower forward voltage drop and lower reverse current leakage are produced by simultaneously exposing said silicon surface to a P-type impurity such as boron, during the aluminum diffusion. A pretreatment of a diffusion furnace tube with boron and aluminum is also described.

3,577,288

BOEHMITE-COATED ALUMINUM TEXTILE PIRN

Walter G. Zelle and Charles J. Walton, Lower Burrell, Pa., assignors to Aluminum Company of America, Pittsburgh, Pa.
No Drawing. Filed Nov. 25, 1968, Ser. No. 778,744
Int. Cl. C23f 7/06; B65h 75/18

U.S. Cl. 148—6.27

11 Claims

A tubular aluminum textile pirn having an alpha-alumina hydrate coating thereon.

3,577,289

COMPOSITE HIGH ENERGY SOLID ROCKET PROPELLANTS AND PROCESS FOR SAME

Jacque C. Morrell, 8 Oxford St., Chevy Chase, Md. 20015

No Drawing. Continuation-in-part of application Ser. No. 404,896, Oct. 19, 1964. This application Feb. 12, 1968, Ser. No. 706,749
Int. Cl. C06d 5/06

U.S. Cl. 149—19

6 Claims

The invention relates to high energy solid rocket propellants comprising an elastomeric organic fuel binder, a finely divided solid inorganic oxidizing agent, and an additive mixture of finely divided solid combustible high energy substances, one substance more readily ignitable than the other.


3,577,290

PROCESS OF MAKING A NONWOVEN FABRIC

Ralph J. Baskerville, Jr., and Joseph S. Baker, Cincinnati, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
Filed Aug. 19, 1968, Ser. No. 753,352
Int. Cl. B31d 1/00

U.S. Cl. 156—62.2

6 Claims



A process of making a nonwoven fabric in which the newly completed nonwoven fabric is recycled and used as a moving support for new fabric web being formed until the latter becomes self-supporting. Then, the superposed webs are separated. The portion that was recycled is removed from the process; the newly completed web portion is continuously recycled as a moving support in the aforesaid manner.

3,577,291

PROCESS FOR CONTINUOUSLY MOLDING BOTTLE FROM THERMOPLASTIC RESIN, CHARGING AND SEALING

Masaaki Uchida, 5, 4-chome, Fukagawa Takahashi, Koto-ku, Tokyo, Japan
Filed Jan. 23, 1969, Ser. No. 793,315


Claims priority, application Japan, Feb. 1, 1968, 43/5,711; Feb. 3, 1968, 43/6,273; Feb. 8, 1968, 43/7,450
Int. Cl. B29c 17/07; B65b 7/16

U.S. Cl. 156—64

5 Claims

A hollow plastic tube is molded of thermoplastic resin. The tube is transferred to a split metal mold and molded

therein into the form of a bottle or container. The bottle or container, while still within the split metal mold, is checked for pinholes and/or other crack defects by feed-



ing compressed air into the bottle. Those bottles or containers found to be non-defective are selected, charged, sealed and packaged.

3,577,292

METHOD FOR JOINING THERMOPLASTIC MEMBERS BY SONIC OR ULTRASONIC ENERGY

Edward G. Obeda, Brookfield, Conn., assignor to Branson Instruments, Incorporated, Stamford, Conn.
Filed Mar. 7, 1969, Ser. No. 805,206
Int. Cl. B29c 27/08

U.S. Cl. 156—73

4 Claims

Juxtaposed thermoplastic members abutting along a common interface surface are joined by contacting both members with a sonically or ultrasonically vibrating horn having toothlike protrusions at its output end. The protrusions are caused to penetrate through the surface of each member and, responsive to the dissipation of energy, cause softened material which is urged to flow across the interface surface to provide, upon hardening, a joint.


3,577,293

METHOD OF LABELLING CYLINDRICAL OBJECTS

Eric K. Ritterhoff, Hinsdale, Ill., assignor to Continental Can Company, Inc., New York, N.Y.
Original application Sept. 19, 1962, Ser. No. 224,660, now Patent No. 3,404,059, dated Oct. 1, 1968. Divided and this application Aug. 9, 1968, Ser. No. 751,439
Int. Cl. B32b 31/20; B65c 3/12

U.S. Cl. 156—156

4 Claims



This disclosure relates to a method of labelling cylindrical objects wherein the objects are primarily in the form of tubes which are flexible. The label is supplied in web form and initially a correct length of the web

is cut off and carried by a drum past an adhesive applicator after which the section of the web is applied to a tube. The tube is carried by a turret and is pressurized at the time the web is being applied thereto. The tube is rotated during the application of the label with the two being rotated at the same speed as the labels being fed. The labelled tube is later cut into individual sections.

3,577,294

METHOD FOR MAKING 3-D FILAMENT REINFORCED ARTICLES


Constant David, 2625 Loring St.,
San Diego, Calif. 92109

Filed Mar. 17, 1969, Ser. No. 815,515

Int. Cl. B65h 54/06

U.S. Cl. 156—173

10 Claims



Method and apparatus for making 3-D filament reinforced shells by securing short reinforcing fibers onto a form which fibers project in a substantially normal direction from the surface of the form, and winding in helical arrangement strands coated with plastic resin onto the form either as individual strands or as tapes formed by a plurality of strands, which strands are substantially normal to the fibers.

3,577,295

METHOD OF BONDING TEXTILE FABRIC BELTS


Louis Seelbach Kraft, Stow, and Charles W. Quiner,
Akron, Ohio, assignors to The Goodyear Tire & Rubber
Company, Akron, Ohio

Filed Apr. 10, 1968, Ser. No. 720,099

Int. Cl. B32b 5/00

U.S. Cl. 156—177

10 Claims



A method of preparing a composite structure comprising at least two support layers adhered to at least one

layer of a cured polyurethane interposed therebetween which comprises controllably and continuously feeding support layers through a first station having a rear retaining means, a forward control means, and a reservoir of a liquid polyurethane mixture therein, and curing the polyurethane reaction mixture layer thereby superposed between the said layers to form the said composite structure.

3,577,296

METHOD FOR PRINTING AND APPLYING LABELS


Duane Phillips, Oxford, Roger C. Schultz, Pardeeville,
and Herbert H. Beck, Portage, Wis., assignors to
Armour and Company, Chicago, Ill.

Original application July 23, 1965, Ser. No. 474,441, now
Patent No. 3,461,984, dated Aug. 19, 1969. Divided
and this application June 18, 1969, Ser. No. 834,437

Int. Cl. B32b 31/00

U.S. Cl. 156—249

7 Claims



Packages, especially those containing perishable foods, are labeled with pressure-sensitive labels in a process which provides for weighing each package, printing the weight and cost on a label adhered to a backing strip, removing the label from the strip, and applying to the package.

3,577,297

TAPING APPARATUS AND METHOD


James S. Howard, Riverside, Calif., assignor to Rohr
Corporation, San Diego, Calif.

Filed Jan. 27, 1969, Ser. No. 794,107

Int. Cl. B32b 31/10, 31/18

U.S. Cl. 156—265

6 Claims



Apparatus for, and method of, laying strips of tape on a surface in adjacently disposed relation from two sides thereof, by means of the arrangement of two tape feeding and two tape cutting mechanisms on opposite sides of a

pressure roller carried by a support head which is adapted to move in opposite directions along parallel paths on said surface.

3,577,298

METHOD OF MAKING A BUILDING PANEL

Scilla de Glauco, 3921 Vasconia St. 33609, and Claudio
Poccia, 4746 W. Anita Blvd. 33611, both of Tampa,
Fla.

No Drawing. Filed June 5, 1969, Ser. No. 832,553

Int. Cl. B44c 1/06

U.S. Cl. 156—239

14 Claims

Compositions for building materials such as partitions, walls, etc., which are readily prepared and have all of the architectural requirements for prefabricated building materials. They consist of fiber glass, PVC expansion panels, unsaturable polyester resin, comminuted amethyst rock and, optionally, aerated calcium carbonate, besides the usual accelerators, diluents and catalysts.

3,577,299

REGISTER AND CONTROL APPARATUS FOR CORRUGATOR


Charles H. Klein and James K. Haley, Cincinnati, Ohio,
assignors to Novelart Manufacturing Company, Cin-
cinnati, Ohio

Filed Dec. 26, 1968, Ser. No. 787,105

Int. Cl. B32b 31/00; B65h 25/00

U.S. Cl. 156—361

5 Claims



Apparatus for first forming single face corrugated paperboard and thereafter combining it with printed sheets to form double face corrugated board, the disclosure including means for controlling the feed and side register of the constituent webs and sheets.

3,577,300


BAG FOLDING AND SEALING APPARATUS

John W. Glaze, Jr., and Joseph P. Worth, Charlotte,
N.C., assignors to Intech Corporation, Charlotte, N.C.
Continuation-in-part of application Ser. No. 604,016,
Dec. 22, 1966. This application Dec. 1, 1969, Ser.
No. 881,175

Int. Cl. B43m 5/04

U.S. Cl. 156—441.5

20 Claims



A shaft driven by a single revolution clutch operates (a) a mechanism for folding a closure flap against the body of a bag, (b) a mechanism for heat sealing the flap to the bag, and (c) a conveying mechanism for ejecting the sealed bag from the apparatus. A movable stop actuated by the shaft serves as a guide for properly locating

a bag in the apparatus, and the stop is retracted after a flap is folded to permit ejection of the bag by the conveying mechanism.

The flap folding mechanism includes a pivoted flap folding plate which has spaced apart openings permitting access of a series of similarly spaced apart heat sealing elements to a folded but unsealed flap.

3,577,301

APPARATUS FOR THE PRODUCTION OF TETRAHEDRAL HOLLOW ARTICLES

Ake Gustafson, Le Chatelet, Chatel-Saint-Denis, Switzer-
land, assignor to Tetra Pak AG, Zurich, Switzerland


Filed Sept. 28, 1967, Ser. No. 671,397

Claims priority, application Switzerland, Sept. 28, 1966,
13,999/66, 14,000/66

Int. Cl. B32b 31/02

U.S. Cl. 156—461

5 Claims



Tetrahedral hollow articles are produced by forming a tube from a travelling web and passing the tube through a rigid guide means contacting the tube in at least two diametrically opposite regions so as to displace the position of undesirable kinks in the articles formed. Subsequently spaced apart transverse seams are provided across the tube. The guide means may be a plate having a square opening and a flexible sleeve of inelastic material is secured in the square opening. The total internal peripheral length of the opening is substantially equal to the circumference of the tube passing through the opening.

3,577,302

AUTOMATIC FILM SPLICING MACHINE


James Szakacs, 150 Pueblo Road,
New Britain, Pa. 18901

Filed May 8, 1968, Ser. No. 727,414

Int. Cl. B65h 21/00; G03d 15/04

U.S. Cl. 156—504

20 Claims




A machine for automatically splicing together lengths of exposed photographic roll film to form a continuous film strip suitable for processing through high speed automatic film processing, printing or other film handling

equipment. The machine includes means for determining the length of a roll of film and for accurately cutting the film in proper registration with the film sprocket holes to remove the spool and paper backer. The machine automatically advances the lead edge of a film into abutting relation with the trailing edge of the preceding film in a splicing station, with the respective film sprocket holes in the proper registration. A strip of heat sealing splicing tape is then automatically inserted beneath the abutting film edges and a heat sealing ram is actuated for a predetermined time to complete the splice. The spliced film is then automatically wound onto a storage reel, the trailing edge of the film strip being stopped in the splicing station for attachment of the succeeding film length.

3,577,303

TAPE APPLYING APPARATUS

Erville C. Buck, Springfield, Oreg., assignor to Willamette Valley Company, Eugene, Oreg.
Filed Nov. 18, 1968, Ser. No. 776,525
Int. Cl. B23b 31/18; B44c 7/02
U.S. Cl. 156—522 11 Claims



An apparatus for applying a pressure-sensitive adhesive tape to a surface having a carriage means to support a supply of pressure-sensitive adhesive tape above the surface with a length of the tape hanging down, means to lower the carriage to a point at which the length of tape contacts the surface and adheres thereto, means to advance the carriage horizontally and apply a length of the tape to the surface and simultaneously withdraw a slight excess of tape from the supply, means to sever the tape at a point prior to the termination of the horizontal advance of the carriage, and means to return the carriage to its initial position with the excess tape hanging therebeneath.


3,577,304

APPARATUS FOR CONTINUOUS LAMINATION

Hubert A. Guyer, 119 Ridgeland Road, Lynnfield, Wilmington, Del. 19803
Filed June 30, 1967, Ser. No. 650,368
Int. Cl. B32b 31/00 13 Claims

Materials to be laminated are passed between two continuous opposed bodies, as, for example, opposed pressure elements on the backside of two continuous belts which operate in alternation to apply pressure with or without heat, to the belts and hence to the laminate. The pressure elements also move the belt. One of the pressure

elements is spring loaded and floating so as to maintain constant pressure at all times on the portion of the belts




and the material being laminated while said portion is in the laminating process.

3,577,305

THERMAL AND AIR SHOCK INSULATING STRUCTURE

Theodore G. Hines and Wayne C. Engle, both % Pine Instrument Co., 322 Oak St., Grove City, Pa. 16127
Filed Aug. 22, 1968, Ser. No. 754,534
Int. Cl. B32b 31/12, 15/08; A41d 31/00
U.S. Cl. 161—4 10 Claims



There is disclosed a flexible thermal and shock insulating structure which can be fabricated substantially from layers of plastic material. At least two of the layers are sealed to form a multitude of dead air cells. A reflective member is placed adjacent the dead air cells, and the assembly thus formed is sealed along its peripheral edges to prevent entry of dirt or other foreign material and deterioration of the reflective quality of the reflective surface. The air cell material and the reflective member are not otherwise joined, with the result that the assembly retains sufficient flexibility for use in manufacturing articles of clothing or the like. The assembly is further arranged to present a relatively smooth outer surface for protection of the sealed air cells and to enhance the qualities of the assembly for use as clothing or as other insulated articles subject to relatively rough handling and usage.

3,577,306

POLYMER LAMINATE TO PREVENT SEVERE METAL PETALLING DAMAGE

Ronald E. Baker, Maricopa, Richard L. Cook, Flagstaff, and Edwin C. Slagel, Maricopa, Ariz., assignors to Goodyear Aerospace Corporation, Akron, Ohio
Filed Dec. 30, 1968, Ser. No. 787,716
Int. Cl. B64b 1/14; D03d 11/00
U.S. Cl. 161—90 6 Claims



A dual layer composite laminate consisting of at least one layer of high strength nylon cloth saturated with a polyurethane and cured to be made semi-flexible with a urethane elastomer pad bonded to one surface of the layer. The other surface of the pad is positioned adjacent the internal surface of metal aircraft skins or other metal structural members to prevent the inward protrusion of the material around a projectile hole through the skin or member so as to prevent petalling of the metal skin into the wound upon the passage of the projectile therethrough.

3,577,307

LEAD STRIP FOR WEIGHING DOWN CURTAINS

Franz Baier, Teichstrasse 3, Saerback, Germany, and Rudolf Schmitz, Austum 43, Emsdetten, Germany
Filed Sept. 19, 1966, Ser. No. 580,326
Claims priority, application Germany, Oct. 15, 1965, P 12 97 304.5
Int. Cl. A47h 1/00

U.S. Cl. 161—175

3 Claims



A lead strip to be secured to the lower edge of a curtain or drape as weight means in which the individual lead members are surrounded by a relatively thin, hose-like sleeve made from polyterephthalate foil strip which is formed into a tube upon insertion of the lead member, by means of a glued seam.

3,577,308

MANUFACTURE OF A MULTICOMPONENT POLYMERIC PRODUCT

Korstiaan J. Marinus van Drunen and Wilhelmus J. Fontijn, Dieren, Netherlands, assignors to American Enka Corporation, Enka, N.C.
Filed Aug. 28, 1968, Ser. No. 755,903
Claims priority, application Netherlands, Sept. 27, 1967, 6712079
Int. Cl. D02g 3/00; B29f 3/10 17 Claims

U.S. Cl. 161—176

A process for the manufacture of a synthetic polymeric product consisting of a basic mass having a large number of endless threads embedded therein, which includes the steps of placing at least two polymeric components (e.g., a polyamide and a polyester), while in

the liquid state, side by side to form a single main stream, repeatedly dividing and multiplying the main stream to form a stream having a first multi-layer structure, superimposing at least a second multi-layer structure onto the first, with the layers of the second being at an angle to the first multi-layer structure and thereafter extruding the resulting stream through a die.



Apparatus for effecting this process includes a feed means for supplying at least two polymeric components side by side to a main channel. A first mixer is located in the main channel and has stationary guiding means by which the main stream may be repeatedly divided and doubled into a stream having a multi-layer structure. A second mixer similar to the first is positioned downstream thereof and is turned on its longitudinal axis through an angle of at least 10° so that the resulting stream has a second layered structure that is at an angle to the first layered structure formed in the first mixer. A die means is used for extruding the resulting stream.

ERRATUM

For Class 161—189 see:
Patent No. 3,577,314

3,577,309

METALLIC CONDUCTOR WITH CERAMIC FIBER INSULATION

Wesley W. Pendleton and George W. Ostrander, Muskegon, Mich., assignors to Anaconda Wire and Cable Company
Original application Nov. 2, 1964, Ser. No. 408,125, now Patent No. 3,464,836, dated Sept. 2, 1969. Divided and this application Apr. 23, 1969, Ser. No. 835,845
Int. Cl. B32b 15/14, 17/02; H01b 3/08
U.S. Cl. 161—196 4 Claims



In the manufacture of magnet wire with glass-fiber insulation the fibers are drawn from a crystallizable composition which is subsequently heat-treated to form ceramic fibers in situ, said ceramic fibers having at least fifteen weight percent B₂O₃ and at least fifty weight percent of crystals of either spodumene, jadeite, or benitoite.

3,577,310

METHOD OF BONDING OLEFIN ELASTOMER TO TEXTILE FIBER AND PRODUCT OBTAINED

Luigi Torti and Guido Bertelli, Ferrara, Italy, assignors to Montecatini Edison S.p.A., Milan, Italy

No Drawing. Filed Oct. 10, 1967, Ser. No. 674,132

Claims priority, application Italy, Oct. 14, 1966, 28,859/66

Int. Cl. B32b 27/06

U.S. Cl. 161—227

11 Claims

Process for bonding elastomeric saturated ethylene/alpha-olefin copolymer or ethylene/alpha-olefin/polyene terpolymer of low degree of unsaturation to natural or synthetic fibers or fabric. Involves treating the fibers or fabric with aqueous dispersion containing halogenated or chlorosulfonated ethylene/propylene/polyene terpolymer and phenol-formaldehyde resin; drying the treated fabric; placing the fabric in contact with a composition of the elastomer containing a vulcanizing agent; and heating the assembled product to vulcanize the elastomer.

3,577,311

FLOOR COVER

Richard W. Reiter, Plainfield, and Felix P. Liberti, Totowa Borough, N.J., assignors to National Starch and Chemical Corporation, New York, N.Y.

No Drawing. Filed Aug. 4, 1969, Ser. No. 847,418

Int. Cl. B32b 27/04, 27/08, 27/12; C08f 37/00, 45/04

U.S. Cl. 161—254

4 Claims

A flooring sheet including a felt backing layer and an upper surface plastisol layer bonded together with at least one tie-coat binder obtained from compositions which are based on selected copolymers, said copolymers containing moieties derived from vinyl acetate and at least one vinyl ester of an alpha-branched saturated aliphatic monocarboxylic acid.

3,577,312

FELTED FIBROUS WEB OR BATT


Otis R. Videen, St. Paul, and Donald E. Wiegand, Minneapolis, Minn., assignors to Conwed Corporation, St. Paul, Minn.

Filed Feb. 21, 1968, Ser. No. 707,147

Int. Cl. D21h 5/12

U.S. Cl. 162—148

10 Claims



A felted fibrous web or batt having enhanced resiliency is produced with from 10% to 100% short fibers of chemically pulped wood. A resin binder is used which includes a cellulose reactive crosslinking reagent.

3,577,313

CONDENSATION PRODUCTS OF AMINES WITH EPIHALOHYDRINS

Justin C. Bolger, Needham, Hugh Evan McCollum, Cambridge, and Robert William Hausslein, Lexington, Mass., assignors to Amicon Corporation, Lexington, Mass.

No Drawing. Filed Oct. 16, 1967, Ser. No. 675,354

Int. Cl. D21d 3/00; D21h 3/36

U.S. Cl. 162—164

7 Claims

A condensation product, with an epihalohydrin, of a polyalkylene polyamine having the composition



in which A represents a straight chain alkylene group having 4 to 8 carbon atoms and n is a number from 2 to 6, and a second amino compound selected from the class consisting of ammonia; hydrazine; and the polyethylene polyamines, polypropylene polyamines, alkanolamines, and ethylamine alkanolamines having at least two hydrogen atoms attached to amino nitrogen, having a miscibility with water of at least 20% by weight of amino compound, and having a pK_a at 25° C. of at least about 9.0.

3,577,314

LAMINATED FUEL CELL CONTAINER

Theodore A. Evans, Akron, Ohio, assignor to The Good-year Tire & Rubber Company, Akron, Ohio

No Drawing. Filed Mar. 24, 1969, Ser. No. 810,019

Int. Cl. B65g 3/00

U.S. Cl. 161—189

5 Claims

This invention relates to a method of preparing a container by forming a laminate comprising a polyamide fabric having a coating of a fluorocarbon composition thereon and having a polyamide film adhered to the fluorocarbon coating, the fluorocarbon composition being cured with an organic peroxy compound, an organic amine or a Schiff's base when compounded with metal oxides and iron oxide.

3,577,315

FORAMINOUS FORMING ROLLS FOR A PAPER-MAKING MACHINE PRODUCED FROM SYNTHETIC RESINS


George H. Franklin, 734 Bliss Road, Longmeadow, Mass. 01106

Continuation-in-part of application Ser. No. 610,280, Jan. 19, 1967. This application Aug. 28, 1968, Ser. No. 767,023

Int. Cl. D21f 1/60, 3/10

U.S. Cl. 162—210

27 Claims



Forming rolls, such as the dandy rolls and the cylinder molds employed in the papermaking art, are fabricated from synthetic resins to reduce their weight and cost while increasing the corrosion resistance and ease of fabrication thereof to provide highly porous structures facilitating water passage. The structure of the invention comprises a hollow cylindrical foraminous body portion with head members at each end thereof to provide for mounting. The body portion is comprised of circumferentially extending support means spaced along the length thereof and a multiplicity of axially extending stiffening rods and top rods arranged about the circumference thereof, the support means in part lying radially outwardly of the stiffening rods, and the top rods lying radially outwardly of the support means. The winding wire and screen are supported upon the top rods, and may be synthetic resin if so desired.

3,577,316

REPLACEABLE DEFLECTOR BLADE STRUCTURE FOR A PAPERMAKING MACHINE


Andre G. Piette, Tracy, Quebec, Canada, assignor to Beloit Corporation, Beloit, Wis.

Filed Jan. 6, 1969, Ser. No. 789,130

Int. Cl. D21f 7/00

U.S. Cl. 162—352

5 Claims



Arrangement for releasing a foil or deflector blade associated with a traveling Fourdrinier wire to enable the blade to be quickly replaced. The deflector blade, which constitutes a de-watering element, has a dovetail by which it is held on a rail by a dovetail recess formed by the rail and a slide positioned in the rail. Longitudinal position of the slide in the rail determines whether the dovetail recess is narrowed to grip the dovetail of the deflector blade and thereby hold it on the rail or is widened to release the dovetail and thereby permit easy removal of the blade from the rail.

3,577,317

CONTROLLED FUSION REACTOR

Cornelius H. Woods, Livermore, Calif., assignor to the United States of America as represented by the United States Atomic Energy Commission

Filed May 1, 1969, Ser. No. 820,750

Int. Cl. G21b 1/00

U.S. Cl. 176—4

8 Claims

Controlled fusion reactor of the Astron type having a magnetic containment zone created by the interaction of the magnetic field of a high energy cylindrical layer of charged particles rotating in an axially symmetric magnetic field region in which an additional axial conductor introduces a shear magnetic field component to suppress instabilities which cause plasma loss.

3,577,318

PROCESS FOR MAKING 6-HYDROXY-3-KETO Δ^4 -STEROIDS OF THE PREGNANE AND ANDROSTANE SERIES

Klaus Kieslich, Berlin, and Wolfgang Koch, Darmstadt-Arheilgen, Germany, assignors to Schering Aktiengesellschaft, Berlin, Germany

No Drawing. Filed Jan. 28, 1970, Ser. No. 12,877

Claims priority, application Germany, Jan. 27, 1969, P 19 04 543.3

Int. Cl. C07c 167/14

U.S. Cl. 195—51

3 Claims

6-hydroxy-3-keto- Δ^4 -steroids of the pregnane or androstane series are made by fermenting a 3 β -hydroxy or 3 β -acyloxy-5,6-epoxy steroid of the pregnane or androstane series which is saturated in the A-ring with bacteria of the genus *Flavobacterium* of *Pseudomonas*, or enzymes thereof.

3,577,319

LARGE SCALE CULTIVATION OF *BORDETELLA PERTUSSIS* CELLS FOR VACCINE PRODUCTION

Peter Adams Nielsen, Ridgewood, Murray Sam Cooper, Dumont, and Ernest Robert Doyne, Woodcliff Lake, N.J., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed May 27, 1968, Ser. No. 732,063

Int. Cl. C12k 3/00

U.S. Cl. 195—96

6 Claims

A *Bordetella pertussis* vaccine is prepared by deep tank cultivation using a seed grown in a biphasic culture system. The process eliminates cultivation on a blood-free seed agar, reduces the number of containers, and results in increased antigenicity of the phase I *Bordetella pertussis* vaccine.

3,577,320

DISTILLATION APPARATUS WITH VACUUM CONTROLLED BY RATE OF DISTILLATE FLOW

Forrest Thompson Randell, Glasgow, Scotland, assignor to G. & J. Weir Limited, Cathcart, Glasgow, Scotland

Filed Nov. 6, 1968, Ser. No. 773,885

Claims priority, application Great Britain, Nov. 24, 1967, 53,475/67

Int. Cl. B01d 3/42

U.S. Cl. 202—160

4 Claims

Distillation apparatus comprises a vessel having an evaporation section including a heating coil for the liquid to be distilled; and a condensing section including a vapour cooling coil; a heating medium supply to the heating coil; a pump or air ejector for creating a vacuum within the vessel; and a distillate outlet conduit from the condensing section. There are provided a sensor for sensing the rate of distillation of liquid, and a valve to regulate the vacuum within the vessel, the valve being operable by the sensor to regulate said vacuum in accordance with the rate of distillation whereby the rate of evaporation and consequently distillation are maintained at a desired value.

3,577,321

COMBINED COKE OVEN DOOR JAMB CLEANING APPARATUS AND DOOR HANDLING APPARATUS

Paul Schaten, Recklinghausen, Germany, assignor to Heinrich Koppers Gesellschaft mit beschränkter Haftung, Essen, Germany


Filed Mar. 4, 1969, Ser. No. 804,143

Claims priority, application Germany, Mar. 7, 1968, P 16 71 333.0

Int. Cl. C10b 25/14, 33/08, 37/07

U.S. Cl. 202—241

4 Claims



A coke oven pusher machine has a supporting arm extending therefrom and movable longitudinally toward and

away from the coke oven chamber. A connecting member is pivotally secured to the end of the supporting arm and has door jamb cleaning apparatus and door handling apparatus secured thereto in angular spaced relation to each other. A suitable drive means is provided to pivot the connecting member relative to the end of the supporting arm to position either the door jamb cleaning apparatus or the door handling apparatus in operative position with the coke oven door jamb. With this arrangement, the coke oven door jamb can be cleaned and the coke oven door replaced without moving the pusher machine.

3,577,322

MICROWAVE HEATING IN THE DESALINATION OF WATER


Stephen J. Nesbitt, 1111 Massachusetts Ave., Washington, D.C. 20005, and Edward M. Knapp, 951 N. Livingston St., Arlington, Va. 22205

Filed Dec. 3, 1968, Ser. No. 780,659

Int. Cl. B01d 1/18, 1/02, 3/08

U.S. Cl. 203—11

1 Claim



A system for the single stage flash distillation of saline or polluted water, combining the use of microwave output power as well as the waste heat in the microwave coolant as a source of heat and including centrifugal separation of particulate matter separated from the solute system by the change of state.

3,577,323

HIGH QUALITY SUBMASTERS

Marlowe A. Pichel, Altadena, Calif., assignor to Xerox Corporation

Original application Apr. 13, 1964, Ser. No. 359,280, now Patent No. 3,428,533, dated Feb. 18, 1969. Divided and this application Dec. 30, 1968, Ser. No. 806,765 (Filed under Rule 47(b) and 35 U.S.C. 118)

Int. Cl. C23b 7/06

U.S. Cl. 204—7

2 Claims

This application relates to a replica metal master having a thin sheet of metal electroformed in a desired shape and a rigidizing structure for maintaining the optical accuracy of said sheet, said rigidizing structure being mounted on said sheet solely along the edges thereof.

3,577,324

PROCESS OF COATING PARTICLES WITH METALS

James A. Patterson, Los Altos, Calif., assignor to Sondell Research Development Co., Palo Alto, Calif.

Filed Jan. 24, 1968, Ser. No. 700,053


Int. Cl. B01k 3/00; C23b 5/60

U.S. Cl. 204—20

5 Claims

A process and apparatus for simultaneously and uniformly plating numerous particles of small diameter. The apparatus comprises a column containing plating solution

flowing vertically therethrough. Upper and lower transverse screens border the inside dimensions of the column interior of the plating solution and therebetween confine the particles being plated. Vibrational energy in the range of 20 to 20,000 cycles per second imparted to the plating solution strips the particles being plated of the gaseous



by-products of plating thereby preventing gas blinding of the plating reaction. Plating solution as vertically flowing through the plating segment moves those particles having low plating size and density into zones of the segment where plating occurs and permits those particles having the desired plating deposit thereon to settle into zones of the segment where plating is arrested.

3,577,325

METHOD OF RECLAIMING GRAPHITE MASK


Albert R. Fairchild, Winston-Salem, N.C., assignor to Western Electric Company, Incorporated, New York, N.Y.

Filed May 29, 1968, Ser. No. 732,965

Int. Cl. C23b 1/00, 5/48

U.S. Cl. 204—24

2 Claims



A pallet and a mask for use in the manufacture of thin film components are machined from a block of high density fine grain pressed graphite to the desired size and shape. The graphite pallet and mask are plated with a flash of copper so that the copper may be dissolved or reacted with an acid to release the layer of precious metals which accumulate during repeated use of the pallet and mask. Thin film substrates are placed in the pallet and covered by the mask. In use, the assembled pallet and

mask are inverted such that gravity forces the substrates against the mask to insure that the metal is deposited only on the desired areas of the substrate.

3,577,326

PROCESS FOR MAKING A MAGNETIC DATA STORAGE ELEMENT


Lynn C. Liebschutz, Endicott, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed July 12, 1968, Ser. No. 744,401

Int. Cl. C23b 5/32; C23c 3/00; H01f 41/14

U.S. Cl. 204—43

2 Claims



A process of making a magnetic material in the form of a film on a conductive cylindrical substrate comprises applying an alternating current to the substrate to generate an alternating orienting magnetic field circumferentially about the substrate. The orienting magnetic field strength is adjusted to produce an isotropic magnetic layer on the substrate or at higher intensities produces films with circumferentially closed easy axis. The alternating current is applied concurrently with deposition of ferromagnetic films from an electrolytic or electroless ferromagnetic bath solution. In an electroless deposition system and the electrolytic system, a direct current applied to electroplate or to initiate and sustain deposition is isolated from the alternating orienting field energization. The alternating orienting current may be sinusoidal but is preferably a square wave and has a zero D-C component.

3,577,327

METHOD AND COMPOSITION FOR ELECTROPLATING CADMIUM (B)

Tibor Joachim, Vernon, and Merton M. Beckwith, Tolland, Conn., assignors to Conversion Chemical Corporation, Rockville, Conn.

No Drawing. Filed Feb. 19, 1969, Ser. No. 800,725

Int. Cl. C23b 5/10, 5/12, 5/46

U.S. Cl. 204—50

15 Claims

An aqueous bath for producing bright, adherent cadmium electrodeposits upon metallic surfaces contains cadmium ion, chloride ion, a nicotinic acid and an aminopolyacetic acid type of chelating agent. The bath is highly conductive and operable at low voltages, and has a pH which is acidic or slightly alkaline.

3,577,328

METHOD AND BATH FOR ELECTROPLATING TIN

George B. Rynne, Rockville, and Merton M. Beckwith, Tolland, Conn., assignors to Conversion Chemical Corporation, Rockville, Conn.

No Drawing. Filed Nov. 7, 1968, Ser. No. 774,177

Int. Cl. C23b 5/46

U.S. Cl. 204—54

25 Claims

An aqueous bath for electroplating tin upon various conductive substrates contains stannous ion, sulfate radical, an imidazoline derivative and a heterocyclic aldehyde. The bath is highly acid and is operable to produce smooth adherent deposits over a wide range of current densities and deposits of spectral brightness with the optimum formulations.

3,577,329

PROCESS FOR THE PRODUCTION OF HIGH PURITY HYDROGEN


Harold Shalit, Drexel Hill, Pa., assignor to Atlantic Richfield Company, Philadelphia, Pa.

Filed Mar. 17, 1969, Ser. No. 807,865

Int. Cl. C01b 13/04; H01m 27/20

U.S. Cl. 204—60

9 Claims



An improved process and apparatus for the production of hydrogen of high purity whereby a carbonaceous fuel is reformed to produce hydrogen and said hydrogen is recovered economically from said reforming operation through the use of an electrolytic process using chemical energy of the reforming process to reduce electrical energy needed and wherein a moist gas is added to the electrolyte to facilitate the electrolytic recovery of hydrogen at the cathode.

3,577,330

PROCESS FOR PRODUCING ELECTROREFINED NICKEL HAVING CONTROLLED SIZE

Burton Bower Knapp, Allendale, N.J., and Leander Ernest Cupp, Port Colborne, Ontario, Canada, assignors to The International Nickel Company, Inc., New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 338,309, Jan. 17, 1964. This application Nov. 17, 1967, Ser. No. 683,801

Int. Cl. C22d 1/14; C23b 7/08

U.S. Cl. 204—112

7 Claims

An improved process for producing electrorefined nickel cathode material of controlled dimension and substantial thickness wherein the nickel is deposited upon a substantially flat, permanent metal cathode mandrel such as stainless steel, and having conductive islands of controlled size defined on the surface thereof, e.g., by the use of interconnecting lines of nonconductive resist, from a nickel electrorefining catholyte containing controlled amounts of sulfur dioxide and a levelling agent to facilitate adherence of the electrodeposited nickel upon the mandrel surface by controlling the stress level therein to a tensile value not exceeding about 6,000 pounds per square inch and thereafter stripping the nickel deposit from the mandrel to recover electrodeposited nickel in sizes corresponding to the original areas of the conductive islands and to recover the mandrel in a condition suitable for further plating.

3,577,331

APPARATUS AND PROCESS FOR EFFECTING CHANGES IN SOLUTION CONCENTRATIONS

Robert E. Lacey, Homewood, Ala., and Milton S. Mintz, Stamford, Conn., assignors to the United States of America as represented by the Secretary of the Interior and Southern Research Institute

Filed June 8, 1967, Ser. No. 645,571


Int. Cl. B01d 13/02

U.S. Cl. 204—180

16 Claims

The present invention relates to an apparatus and a process for effecting changes in solution concentrations wherein a component of the solution is passed through a

separatory membrane which is selectively permeable to that component. This invention enhances the efficiency of all existing membrane separation processes by reducing the thickness of the boundary layers formed at the membrane-solution interface. The reduction in thickness is



accomplished by placing in spaced relationship to the selectively permeable membrane a second porous membrane permeable to the solution. While the apparatus and process are useful in all membrane separation systems, particular utility is found in electrically driven or pressure-driven desalination systems.

3,577,332

POLAROGRAPHIC CELL


Joe A. Porter, Whittier, and Stuart L. Couch, Santa Ana, Calif., assignors to Beckman Instruments, Inc.

Filed July 12, 1967, Ser. No. 652,745

Int. Cl. G01n 27/46

U.S. Cl. 204—195

4 Claims



A cell for polarographic analysis of the type employing a pair of electrodes joined by an electrolyte and separated from the sample medium by a selectively permeable membrane. Pressure compensation is provided for the cell by employing an ion impermeable barrier which closes a passage leading to the electrolyte reservoir in the cell so that contaminants outside of the cell cannot reach the electrolyte reservoir. The barrier has a sensitivity to pressure changes greater than that of the membrane so that the spacial relationship between the membrane and the sensing electrode of the cell is not influenced by changing pressure conditions.

3,577,333

APPARATUS FOR ELECTROCHEMICAL REMOVAL OF MATERIAL FROM AN ARTICLE

Edward R. Derrough, South Bend, Ind., assignor to


The Bendix Corporation

Filed Sept. 24, 1968, Ser. No. 761,966

Int. Cl. B23p 1/04, 1/12

U.S. Cl. 204—212

4 Claims



An electrochemical machining apparatus having a hollow electrode tool with a working face for eroding a core

of material from a workpiece in response to a rotational input.

3,577,334

APPARATUS FOR ELECTROLYTIC RECOVERY OF A METAL FROM A SOLUTION


Charles L. Graham and Harlow R. Brigham, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Dec. 14, 1967, Ser. No. 690,621

Int. Cl. B01k 3/10; C22d 1/02, 1/12

U.S. Cl. 204—223

18 Claims



A metal is recovered from a solution in which the metal is present in ionic form by supporting a thin moving layer of the solution in contact with an electrode, impressing an electric potential across the moving layer, and mixing the solution within the layer as it travels past the electrode so as to replenish metal ions as they are depleted from immediately adjacent the electrode surface at which plating of the metal occurs. Apparatus for carrying out this method includes electrode means and a moving belt which supports the thin layer of solution in contact with the electrode means, the movement of the belt acting to ensure flow of the solution past the electrode and to simultaneously agitate the moving layer to effect mixing of the solution within the layer. The method and apparatus are of particular utility in the recovery of silver from viscous fixing solutions employed in photographic processing.

3,577,335

FEEDBACK CIRCUIT FOR ANODIZING THIN-FILM RESISTORS


Frank H. Blitchington, Jr., Greensboro, N.C., assignor to Western Electric Company, Incorporated, New York, N.Y.

Filed May 9, 1968, Ser. No. 727,948

Int. Cl. B01k 3/00

U.S. Cl. 204—228

6 Claims



A thin-film resistor, which is to be anodized to increase its resistance to a preselected value is connected to one

arm of a bridge circuit. As the resistor is being anodized, an imbalance in the bridge drives a monitor circuit which controls a variable resistance in series with a supply of anodizing voltage. As the thin-film resistor being anodized approaches the preselected value, the bridge becomes more nearly balanced and the variable resistor increases in value to interrupt the flow of anodizing current.

3,577,336

ELECTRIC TREATER FOR TREATING JET FUEL AND OTHER DISPERSIONS


William L. Shirley, Houston, Tex., assignor to Petrolite Corporation, St. Louis, Mo.

Filed Aug. 23, 1968, Ser. No. 754,847

Int. Cl. B03c 5/02

U.S. Cl. 204—302

23 Claims



An electric treater for removing dispersed materials from oil flowing through electric fields in side-by-side flow passages that are other than vertical. Grid electrodes having side-by-side rods are disposed in the central planes of the flow passages. With such or other electrode configurations in an electric treating chamber, oil flows into or from the latter through a space packed with masses, usually solids, that can be continuously or periodically replaced. The masses may have surface properties or coatings facilitating the separation of the dispersed material from the oil or such masses or materials coating or impregnating same may be reactive with some component of the oil.

3,577,337

SOLVENT EXTRACTION OF COAL

Theodore Kessler, Andrew G. Sharkey, Jr., Joseph Malli, Jr., and Robert A. Friedel, Pittsburgh, Pa., assignors to the United States of America as represented by the Secretary of the Interior

No Drawing. Filed Mar. 11, 1970, Ser. No. 18,693

Int. Cl. C10g 1/04

U.S. Cl. 208—8

7 Claims

Coal is extracted in quinoline by treatment of a coal-quinoline slurry with ultrasonic irradiation at ambient temperature. The quinoline may then be removed from the solubilized coal fraction by conversion to a water-soluble quinoline salt. The solubilized fraction may be used for production of gasoline, aromatic chemicals, carbon black, electrode carbons, low-sulfur and -ash fuels for power plants, etc.

3,577,338

PROCESS FOR RECOVERY OF OIL FROM OIL SHALE SIMULTANEOUSLY PRODUCING HYDROGEN

Phillip H. Gifford II, Carbondale, Colo.
(1824 K 4/10 Road, Fruita, Colo. 81521)

Filed Feb. 19, 1969, Ser. No. 800,594


Int. Cl. C10b 53/06

U.S. Cl. 208—11

11 Claims

A process for retorting oil shale and simultaneously producing hydrogen as a by-product with high yields of

both oil and hydrogen, the process comprising continuously passing oil shale through a combustion zone in a retort while continuously introducing steam and oxygen into the combustion zone, removing spent shale below the



combustion zone and recovering oil and hydrogen from the retort off gas from the combustion zone. Hydrogen is produced by the reaction of carbon containing material with steam.

3,577,339

FILTRATION METHOD OF SEPARATING LIQUIDS FROM EXTRANEEOUS MATERIALS

Justus N. Baird, Jr., Kingston, and James S. Johnson, Kurt A. Kraus, and Joseph J. Perona, Oak Ridge, Tenn., assignors to the United States of America as represented by the United States Atomic Energy Commission
No Drawing. Continuation of application Ser. No. 718,231, Apr. 2, 1968. This application Jan. 29, 1970, Ser. No. 7,387

Int. Cl. B01d 13/00

U.S. Cl. 210—23

3 Claims

A cross flow filtration method of separating a liquid from extraneous material comprising establishing a filtering medium comprising a bed of fine particles dispersed on a porous substrate and forcing a liquid across said filtering medium under conditions whereby a portion of said liquid passes through said filtering medium.

3,577,340

METHOD FOR DISPERSING OIL SPILLS ON WATER

Stanley C. Paviak, Shaler Township, Warren K. Porter, Jr., Richland Township, Allegheny County, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.


No Drawing. Filed Apr. 16, 1970, Ser. No. 29,295

Int. Cl. B01d 17/04

U.S. Cl. 210—42

9 Claims

A method for dissipating oil spills in water by dispersing the spilled oil with a novel alkylphenol ethoxylate having the structural formula



wherein n is an integer from about 5 to about 25, R_1 is an alkyl group having at least 20 carbon atoms and R_2 and R_3 are independently selected from said alkyl group and hydrogen; and mixtures of the same.

3,577,341

WATER TREATMENT


Frederick W. Kelth, Jr., Gladwyne, Everett M. Jones, Ardmore, and Joseph R. Townsend, Jr., West Chester, Pa., assignors to Pennwalt Corporation

Filed Oct. 18, 1968, Ser. No. 768,848

Int. Cl. C02b 1/20

U.S. Cl. 210—53

13 Claims



In water treatment, immediately following treating with chemicals and settling of sedimented material, the latter no longer need be returned as a pollutant to a water course, or otherwise disposed of. Rather, the sedimented material is centrifugally concentrated for convenient disposal in compact form and the water separated therefrom may be reprocessed.

3,577,342

FIRE-RESISTANT FINISH FOR TEXTILES COMPRISING ZINC FLUOROBORATE

Louis Isadore Fidell, Bound Brook, N.J., assignor to American Cyanamid Company, Stamford, Conn.

No Drawing. Continuation-in-part of application Ser. No. 647,603, June 21, 1967, which is a continuation-in-part of application Ser. No. 457,209, May 19, 1965. This application Sept. 2, 1969, Ser. No. 854,750

Int. Cl. C09k 3/28

U.S. Cl. 252—8.1

4 Claims

Fire retardant finishing compositions, especially useful for synthetic fibers, incorporating zinc fluoroborate and emulsification and other additives to maintain the desirable hand and feel of the textile material.

3,577,343

DIBENZAZEPINE COMPOUNDS AS STABILIZER FOR OXIDIZABLE ORGANIC COMPOSITIONS

Hans Jakob Peterli, Fullingsdorf, Switzerland, and Donald Richard Randell, Stockport, England, assignors to Geigy Chemical Corporation, Greenburgh, N.Y.


No Drawing. Division of application Ser. No. 588,225, Oct. 20, 1966, now Patent No. 3,475,412, which is a continuation of application Ser. No. 523,539, Jan. 28, 1966, which is a continuation-in-part of application Ser. No. 424,210, Jan. 8, 1965, which in turn is a continuation-in-part of application Ser. No. 158,169, Dec. 8, 1961. This application Oct. 27, 1969, Ser. No. 870,959

Int. Cl. C10m 1/32; C08f 45/60


U.S. Cl. 252—51.5

7 Claims

Oxidizable organic materials are rendered less susceptible to oxidative deterioration by incorporation of an effective amount of a compound from the group of



and an N-substituted azepine compound of the formula



in which formulas R is a member selected from the group consisting of hydrogen, alkyl having from 1 to 12 carbon atoms, hydroxy-substituted lower alkyl, phenyl-substituted lower alkyl, benzoyl and alkanoyl with 1 to 8 carbon atoms.

3,577,344

FIBROUS THERMAL INSULATION AND METHOD OF MAKING SAME

Zane L. Ardary, Oak Ridge, Andrew W. Maxey, Knoxville, and Carl D. Reynolds, Oak Ridge, Tenn., assignors to the United States of America as represented by the United States Atomic Energy Commission

Filed Jan. 29, 1969, Ser. No. 794,980

Int. Cl. C04b 43/02; E04b 1/76; F16l 59/00

U.S. Cl. 252—62

11 Claims

Lightweight, high-temperature, thermal insulating material is prepared by molding an admixture or water slurry of small-diameter fibers of a refractory or carbonaceous material and a carbonizable binder consisting of starch particulates. The molded admixture is heated sufficiently to gelatinize the starch, then dried, and thereafter heated sufficiently in an inert atmosphere to pyrolyze the starch for effectively bonding together the fibers. The thermal insulating material is of a density less than 10 lbs./ft.³ and has a thermal conductivity of less than about 1 B.t.u.-in./hr.-° F.-ft.² at a temperature of 1400° F.

3,577,345

SOLID XEROGRAPHIC DEVELOPER

Burton B. Jacknow and Joseph H. Moriconi, Rochester, N.Y., assignors to Xerox Corporation, Rochester, N.Y.

No Drawing. Filed June 5, 1967, Ser. No. 643,394

Int. Cl. G03g 9/02

U.S. Cl. 252—62.1

9 Claims

A finely-divided low melting toner comprising a colorant, a thermoplastic resin comprising a vinyl resin, a solid metal salt of a fatty acid, and a solid additive having a melting point between about 115° F. to about 270° F. comprising a benzoate, a sulphamide or a polychlorinated polyphenyl compound.

3,577,346

INSULATED ELECTRICAL CONDUCTORS HAVING CORONA RESISTANT POLYMERIC INSULATION CONTAINING ORGANO METALLIC COMPOUNDS

James J. McKeown, Mahtomedi, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Continuation-in-part of application Ser. No. 555,695, June 7, 1966. This application Nov. 14, 1968, Ser. No. 775,958

Int. Cl. C08f 45/62; C08g 51/62; H01b 3/28

U.S. Cl. 252—63.5

49 Claims

Insulated electrical conductors having improved corona resistance comprising a metal conductor surrounded by a major portion of a dielectric polymer containing intermixed therewith a minor amount of an organo-metallic compound of a metal selected from silicon, germanium, tin, lead, phosphorous, arsenic, antimony, bismuth, iron, ruthenium and nickel and a method for the preparation of the insulated electrical conductors.

ERRATUM

For Class 252—73 see:
Patent No. 3,577,361

3,577,347

WATER-SOLUBLE SCOURING COMPOSITION

John Alexander Monick, 102 Jasper Ave.,

Teaneck, N.J. 07666

No Drawing. Filed Apr. 3, 1968, Ser. No. 718,325

Int. Cl. C11d 7/56

U.S. Cl. 252—99

4 Claims

A stable nongritty cleanser composition comprising a detergent, bleach, and a water soluble salt, said salt having less than 6 molecules of water of hydration.

3,577,348

TRICHLOROTRIFLUOROETHANE WATER EMULSION SYSTEM

John Joseph Clementson, Runcorn, England, assignor to Imperial Chemical Industries Limited, London, England

No Drawing. Filed May 1, 1968, Ser. No. 725,897

Claims priority, application Great Britain, May 8, 1967, 21,221/67, 21,222/67; Aug. 14, 1967, 37,321/67, 37,719/67

Int. Cl. C11d 1/12, 7/50; B01f 17/10

U.S. Cl. 252—153

16 Claims

Cleaning compositions containing a fluorochlorohydrocarbon solvent and a sodium, ammonium or amine salt of a monosulphonic acid derivative of a di-ester of succinic acid, optionally also containing a non-ionic surfactant, ammonia, water and a stabilizer for the said solvent.

3,577,349

COMPOSITION FOR DESTROYING HARDENED CEMENTITIOUS MIXTURES

Robert Glenn Haines, South Charleston, W. Va., assignor to Union Carbide Corporation, New York, N.Y.

No Drawing. Filed Jan. 31, 1969, Ser. No. 795,709

Int. Cl. C09d 9/00; C11d 7/05; C23g 5/02

U.S. Cl. 252—170

8 Claims

A composition for destroying hardened cementitious mixtures comprising methyl acetoacetate and water. A method for destroying hardened cementitious mixtures utilizing said composition is also covered.

3,577,350

EUROPIUM AND MANGANESE ACTIVATED SODIUM OR POTASSIUM ALUMINATE PHOSPHORS

Robert L. Amster, Great Neck, N.Y., assignor to General Telephone & Electronics Laboratories, Incorporated

Filed Nov. 27, 1968, Ser. No. 786,804

Int. Cl. C09k 1/68

U.S. Cl. 252—301.4

6 Claims

A phosphor system consisting of an alkali metal β -alumina activated by divalent europium or by divalent europium together with divalent manganese. These phosphors are photoluminescent and cathodoluminescent and are suitable for use in fluorescent lamps or cathode ray tube screens.

3,577,351

METHOD FOR THE RECOVERY OF RARE EARTH OXIDES

Robert E. Dodds, Wysox, Pa., assignor to Sylvania Electric Products Inc.

No Drawing. Filed Jan. 30, 1969, Ser. No. 795,346

Int. Cl. C09k 1/10

U.S. Cl. 252—301.4

10 Claims

A process is disclosed that is suitable for recovering rare earth oxide phosphors from an impure material con-

taining rare earth oxides contaminated with other phosphors used in color television cathode ray tubes. The process comprises: heating the impure material to remove volatile material, forming an aqueous material containing the impure rare earth material, adjusting the temperature of the mixture to about 80° C., maintaining the pH of the mixture at from about 3 to about 5 to dissolve the rare earth oxides, separating the solids from the mixture to form a liquid phase containing the rare earth values and precipitating the rare earth values and converting said rare earth values to rare earth oxide phosphors.

3,577,352

TEMPERATURE INDICATING DEVICE OF DISPERSION FILTER ADJUSTED TO PRODUCE COLOR CHANGES NEAR 0° C.

Jan Bol, Kelkheim, Taunus, Germany, assignor to Battelle-Institute e.V., Frankfurt am Main, Germany

No Drawing. Filed May 17, 1968, Ser. No. 730,201

Claims priority, application Great Britain, May 17, 1967, 58,798/67

Int. Cl. G01k 11/16, 11/18

U.S. Cl. 252—408

8 Claims

A temperature indicating device using a Christiansen filter wherein the refractive indices and dispersion values of the solid and the fluid phase are so adjusted as to produce color changes near the freezing point.

3,577,353

PREPARATION OF A COGELLED CATALYST OF ALUMINA AND A GROUP VI HYDROGENATING COMPONENT

Robert J. White, Pinole, Calif., assignor to Chevron Research Company, San Francisco, Calif.

No Drawing. Filed Nov. 22, 1968, Ser. No. 778,332

Int. Cl. B01j 11/34, 11/40

U.S. Cl. 252—465

2 Claims

A hydrofining catalyst is prepared by cogelation of hydrous alumina and a Group VI metal or metal compound, washing said gel to remove occluded salts and then contacting the washed gel with an organic solvent before the gel is dried and calcined. This contacting step, which may be carried out with methanol or ethanol, serves to extract water from the hydrous gel and thus provides less shrinkage of the gel after final drying.

3,577,354

MAGNESIUM CHROMIUM FERRITE CATALYST

William L. Kehl, Indiana Township, Allegheny County, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.

No Drawing. Division and continuation-in-part of application Ser. No. 493,222, Oct. 5, 1965. This application June 27, 1969, Ser. No. 837,376

Int. Cl. B01j 11/06, 11/32

U.S. Cl. 252—468

13 Claims

A hydrocarbon conversion catalyst comprising magnesium, chromium, iron and oxygen in a magnesium chromium ferrite spinel-type structure.

3,577,355

RESISTOR COMPOSITION

Jack F. Blum, Flint, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Dec. 21, 1967, Ser. No. 692,485


Int. Cl. H01t 13/36; H01b 1/02

U.S. Cl. 252—512

6 Claims

An improved resistor composition for use in resistor spark plugs and other electrical devices is disclosed. The resistor composition contains a metal powder taken from the group consisting of zinc, antimony and tellurium in

addition to the conventional resistor composition ingredients. The metal, for example, zinc, causes the resistor



mass to bond tightly to the center electrode head in the spark plug insulator centerbore.

3,577,356

HIGHLY FLUORINATED POLYMERS


Floyd D. Trischler and Jerome Hollander, San Diego, Calif., assignors to Whittaker Corporation, Los Angeles, Calif.

No Drawing. Filed Feb. 23, 1968, Ser. No. 707,440
Int. Cl. C08g 23/00, 33/00

U.S. Cl. 260—2

7 Claims

This patent describes novel hydroxy containing polyethers which are prepared by the base polymerization of 2-hydro-perhaloisopropyl alcohols having the formula



wherein X is fluorine, chlorine, bromine or iodine.

3,577,357

SELECTIVELY SULFONATED BLOCK COPOLYMERS

De Loss E. Winkler, Orinda, Calif., assignor to Shell Oil Company, New York, N.Y.

No Drawing. Filed Nov. 29, 1968, Ser. No. 780,179
Int. Cl. C08j 1/34

U.S. Cl. 260—2.2

7 Claims

Block copolymers exhibiting water absorption characteristics indicating their use in water purification membranes and the like comprise block copolymers having sulfonated polyvinyl arene blocks and alpha-olefin elastomeric blocks, the sulfur content of the copolymers varying from about 1% by weight to one sulfonated radical per monovinyl arene unit.

3,577,358

ORGANIC ISOCYANATE-LIGNIN REACTION PRODUCTS AND PROCESS

Thomas R. Santelli, Sylvania, and Robert T. Wallace, Toledo, Ohio, assignors to Owens-Illinois, Inc.

No Drawing. Continuation-in-part of application Ser. No. 846,822, Oct. 16, 1959. This application Feb. 10, 1967, Ser. No. 615,072

Int. Cl. C08g 22/44

U.S. Cl. 260—2.5

16 Claims

New polymeric materials, such as synthetic resins, foamed cellular synthetic resins, and the like, are formed by reacting an organic polyisocyanate with lignin, preferably in the presence of varying amounts of catalysts, plasticizers, emulsifiers, solvents, and co-reactants, depending upon the desired characteristics of the final product. Such product has repeating urethane linkages in the molecule. Products of the invention are suitable for many uses, among which uses are as foams, plastics, adhesives, etc.

3,577,359

METHOD OF RETICULATING NYLON MATERIALS

Frank E. Carevic and Theodore H. Fairbanks, West Chester, Pa., assignors to FMC Corporation, Philadelphia, Pa.

Filed Feb. 5, 1968, Ser. No. 703,068
Int. Cl. C08g 53/08, 53/20

U.S. Cl. 260—2.5

7 Claims

A foamed nylon material, formed of contacting cells which provide a skeletal structure of interconnected strands with membranes partitioning contiguous cells and joined to the skeletal structure, is exposed to a solution of a strong acid and a non-aqueous solvent to remove the cell membranes, leaving the skeletal structure of nylon material which is suitable, for example, as a filter.

ERRATUM

For Class 260—2.5 see:
Patent No. 3,577,554

3,577,360

PROCESS FOR PRE-EXPANDING POLYMER BEADS

Richard H. Immel, Sewickley, Pa., assignor to Sinclair-Koppers Company

Filed Oct. 7, 1968, Ser. No. 765,342
Int. Cl. B29d 1/00; B29h 7/20

U.S. Cl. 264—53

5 Claims

An apparatus and process are provided for expanding polymeric particles to a predetermined density, which particles are subject to further expansion. Agitated particulate expandable polymer is heated in a dry atmosphere in a closed vessel, under vacuum, to a predetermined density. To achieve ultra-low density expandable prepuff, a coolant such as water is introduced into the closed vessel after the predetermined density is reached, but prior to the release of the vacuum. Following release of the vacuum, the beads are removed from the closed vessel and may be molded directly, without any aging period such as that necessary following steam pre-expansion.

3,577,361

SYNTHETIC POWER TRANSMISSION FLUIDS

William C. Hammann, Creve Coeur, and Robert M. Schisla, Kirkwood, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed May 22, 1968, Ser. No. 731,254
Int. Cl. C09k 3/00

U.S. Cl. 252—73

6 Claims

An improved method of transmitting power in hydraulically-operated mechanisms which comprises using as the operative fluid certain tetraalkyl substituted alkylene-linked dicyclohexyl compounds.

3,577,362

METHOD OF MANUFACTURING URETHANE FOAM BY THE USE OF POLY(VINYL-ALKOXY SILANES)

Kihachi Tamura, Musashino-shi, and Isao Nakajima and Kaname Inoue, Tokyo, Japan, assignors to Shin-Etsu Chemical Industry Co., Ltd., Tokyo, Japan

No Drawing. Original application Jan. 29, 1964, Ser. No. 341,123, now Patent No. 3,461,148, dated Aug. 12, 1969. Divided and this application Oct. 30, 1968, Ser. No. 785,431

Claims priority, application Japan, Jan. 29, 1963, 38/3,960; Jan. 31, 1963, 38/4,970, 38/4,971; Feb. 1, 1963, 38/5,069

Int. Cl. C08g 22/46, 53/08

U.S. Cl. 260—2.5

8 Claims

A process for manufacturing a polyoxyalkylene polyvinylsilane by condensing a polyoxyalkylene compound

with a vinylsilane and polymerizing the resulting condensate in the presence of the catalyst selected from organic peroxides and organic azo compounds, the polyoxyalkylene polyvinylsilanes so produced and use of the polyoxyalkylene polyvinylsilane as a surfactant in the manufacture of polyurethane foam.

3,577,363

CELLULAR PLASTICS MATERIAL CONTAINING POLYSTYRENE AND A PROCESS FOR ITS MANUFACTURE

Oluf Walter Henry Klug, Stockholm, Sweden, assignor to AB Electrolux, Stockholm, Sweden

No Drawing. Filed June 20, 1969, Ser. No. 835,214
Claims priority, application Sweden, July 5, 1968, 9,319/68

Int. Cl. C08f 47/10; C08g 53/10

U.S. Cl. 260—2.5

10 Claims

A material consisting of closed cells of polystyrene which are surrounded by cured urea formaldehyde resin is produced in the following manner: Small, unexpanded polystyrene particles are mixed with urea formaldehyde resin in a liquid medium; the urea formaldehyde resin is then converted to a foam and cured in the form of this foam without any substantial expanding of the polystyrene particles; after the curing step, the polystyrene particles are expanded by heating.

3,577,364

COMPOSITIONS OF MATTER

Daniel S. Raden, Chicago, Ill., assignor to Velsicol Chemical Corporation, Chicago, Ill.


No Drawing. Original application Oct. 22, 1965, Ser. No. 502,552, now Patent No. 3,509,199, dated Apr. 28, 1970. Divided and this application June 17, 1968, Ser. No. 761,358

Int. Cl. C08g 22/24, 22/26, 22/44

U.S. Cl. 260—2.5

6 Claims

The subject matter of this application is a new flame retardant rigid cellular plastic foam prepared from (5-methylene - 1,2,3,4,7,7 - hexachlorobicyclo[2.2.1] - 2-heptenyl)-2,4-diisocyanatophenyl ether, or compounds generically defined as



wherein X is halogen and n is 0 or 1.

3,577,365

NOVEL BLENDS OF CHLORINATED CARBOXYL GROUP CONTAINING POLYMERS AND ETHYLENE-VINYL ACETATE COPOLYMERS

Paul D. Folzenlogen and Hugh J. Hagemeyer, Jr., Longview, Tex., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Feb. 7, 1969, Ser. No. 797,703
Int. Cl. C08f 29/12

U.S. Cl. 260—4

12 Claims

Compositions comprising blends of chlorinated carboxyl group containing polymers and ethylene-vinyl acetate copolymers. These compositions provide tough, flexible coatings having excellent adhesion to various substrates. These coatings have good resistance to chemical and solvent attack and embrittlement on aging and are useful in the protective coatings field.

3,577,366

9,10-BRIDGED ANTHRACENE COMPOUNDS

Bruce H. Klanderman, Rochester, and Jan W. H. Faber, Hilton, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Application Feb. 17, 1967, Ser. No. 616,789, now Patent No. 3,457,235, which is a continuation-in-part of application Ser. No. 530,381, Feb. 28, 1966. Divided and this application Mar. 28, 1969, Ser. No. 811,655

Int. Cl. C07c 31/14

U.S. Cl. 260—618

8 Claims

New 9,10 - bridged anthracene compounds, such as 9,10 - bis(hydroxymethyl)tritycene and 9,10 - dihydro-9,10 - bis(hydroxymethyl) - 9,10 - ethanoanthracene improve certain properties of polyesters prepared by polymerization of a dicarboxylic acid, such as terephthalic acid, and an alkylene glycol, such as ethylene glycol, when incorporated in the polymerization mixture. The 9,10-bis(acyloxyalkyl) - 9,10 - bridged anthracene compounds from which the anthracene compounds used in preparing the polyesters are prepared are new compounds.

3,577,367

FOUNDRY SAND COMPOSITIONS CONTAINING GRAFT COPOLYMERS OF ACRYLIC ACID WITH METHYL CELLULOSE

William J. Lang, Libertyville, Ill., assignor to International Minerals & Chemical Corporation

No Drawing. Filed Sept. 4, 1968, Ser. No. 757,469
Int. Cl. C08f 29/36; B22c 1/26

U.S. Cl. 260—17

15 Claims

A sand core and mold composition for use in casting metals comprising foundry sand, clay, water and from about 0.0025% to about 1% by weight of a water-soluble graft copolymer of acrylic acid and a minor amount of methyl cellulose, including water-soluble salts thereof.

3,577,368

BARK FIBER AS A REINFORCING AND STABILIZING AGENT FOR HIGH TEMPERATURE MOLDING THERMOPLASTICS

Hubert E. Hendrickson and Charles N. McCain, Longview, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

No Drawing. Filed Mar. 8, 1967, Ser. No. 621,436
Int. Cl. C08f 29/10, 45/18

U.S. Cl. 260—17.4

4 Claims

The invention comprises the use of Douglas fir bark fiber as a stabilizer for polypropylene molding compounds. The bark fibers may be incorporated into the molding compound by simple blending methods to provide a homogeneous molding premix, yet provide superior physical properties to the article of manufacture as well as improved heat stability.

3,577,369

BARK FIBER AS A DISPERSING AGENT FOR HIGH TEMPERATURE MOLDING THERMOPLASTICS

Hubert E. Hendrickson and Charles N. McCain, Longview, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

No Drawing. Filed Mar. 8, 1967, Ser. No. 621,420
Int. Cl. C08f 45/18

U.S. Cl. 260—17.4

4 Claims

The invention comprises the use of Douglas fir bark fiber as a dispersing agent for reinforced polypropylene molding compound which can be used at elevated molding conditions. The bark fiber may be incorporated into the reinforced molding compound by simple blending methods to provide a homogeneous molding premix, yet provide the article manufactured and produced thereby with the reinforcing material dispersed uniformly therein.

ERRATUM

For Class 260—17.4 see:
Patent No. 3,577,555

3,577,370

MODIFIER FOR PHENOLIC RESINS

Anthony J. Castro, Oak Park, Frederick S. Marsh, Chicago, Layton E. Kinnney, Villa Park, and Frank J. Fischl, Chicago, Ill., assignors to Armour Industrial Chemical Company, Chicago, Ill.
No Drawing. Filed Aug. 5, 1968, Ser. No. 749,946
Int. Cl. C08g 37/18

U.S. Cl. 260—19 8 Claims
Hydroxyphenylstearic acid-phenol copolymers with aldehyde bridging, useful with epoxy resins as coating compositions.

3,577,371

NITRILOTRIACETIC ACID ALKYD RESINS

Noel D. Blair, Grand Island, N.Y., assignor to Hooker Chemical Corporation, Niagara Falls, N.Y.
No Drawing. Filed Nov. 13, 1967, Ser. No. 682,586
Int. Cl. C08g 17/04, 17/16; C09d 3/64

U.S. Cl. 260—22 12 Claims
There are provided: Novel nitrilotriacetic acid alkyd resins and their water soluble ammonium or amine salts having utility as coating compositions on metal.

3,577,372

HOT MELT ADHESIVE COMPOSITIONS

Thomas P. Flanagan, Green Brook, and Irving I. Kaye, Murray Hill, N.J., assignors to National Starch and Chemical Corporation, New York, N.Y.
No Drawing. Filed July 30, 1968, Ser. No. 748,607
Int. Cl. C08f 45/52; C09j 3/14, 7/00

U.S. Cl. 260—23 6 Claims
Hot melt adhesive compositions comprising a blend of an atactic polypropylene resin and an aliphatic petroleum hydrocarbon tackifying resin. The resulting hot melts are utilizable in a variety of packaging, laminating and specialty hot melt applications.

3,577,373

WAX COMPOSITIONS CONTAINING AN ETHYLENE-ISOBUTYLACRYLATE COPOLYMER AND AN ORGANIC ACID

Charles J. Kremer, Brookhaven, and Donald S. Brown, Havertown, Pa., Dominic Apikos, Laurel Springs, N.J., and John T. Thean, Philadelphia, Pa., assignors to Atlantic Richfield Company, Philadelphia, Pa.
No Drawing. Filed Dec. 9, 1968, Ser. No. 782,408
Int. Cl. C08f 21/04, 45/52

U.S. Cl. 260—23 18 Claims
This invention relates to wax compositions containing an acid component and an ethylene-isobutylacrylate copolymer. These compositions have highly improved resistance to stress cracking, and improved break energy and film toughness. They can be utilized as hot melt coatings for items such as paperboard and corrugated board for use in the food packaging industry.

3,577,374

COATING COMPOSITIONS COMPRISING POLYVINYL ACETAL

Robert A. Isaksen, Longmeadow, Mass., assignor to Monsanto Company, St. Louis, Mo.
No Drawing. Continuation-in-part of application Ser. No. 624,702, Mar. 21, 1967. This application Dec. 26, 1968, Ser. No. 787,251
Int. Cl. C09d 3/74, 5/08, 5/10

U.S. Cl. 260—23 11 Claims
Disclosed herein is a coating composition for application to various surfaces particularly wood or metal. When

applied to metal, it is not necessary that the metal be previously cleaned of oxidation products and/or greasy, oily contaminants. The coating is based upon a blend of polyvinyl acetal and a styrene-alcohol interpolymer, such as styrene-allyl alcohol interpolymer, and/or esters and/or ester adducts thereof. Optionally, the coating may also contain chromium trioxide and/or aluminum powder.

3,577,375

STABLE AQUEOUS DISPERSIONS OF ETHYLENE POLYMERS PRODUCED BY CONTACTING THE DISPERSIONS WITH AN ACIDIC SULFONATED CATION EXCHANGE RESIN CHARGED WITH AMMONIUM IONS

Bert H. Clamplitt, Overland Park, Kans., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
No Drawing. Continuation of application Ser. No. 585,283, Oct. 10, 1966. This application June 20, 1969, Ser. No. 835,249

The portion of the term of the patent subsequent to May 12, 1987, has been disclaimed
Int. Cl. C08f 27/00

U.S. Cl. 260—29.6 10 Claims
Stable aqueous dispersions of water-insoluble, self-emulsifiable ethylene-alkyl acrylate polymers substantially free of metallic cations are obtained by contacting aqueous dispersions of water-insoluble, self-emulsifiable ethylene-alkyl acrylate polymers containing metallic cations with a strongly acidic cation exchange resin charged with ammonium ions.

3,577,376

INTERPOLYMERIZATION OF ACRYLAMIDE, VINYL ACETATE AND OTHER MONOMERS BY USING A SOLUBILIZING AGENT TO DISSOLVE THE ACRYLAMIDE IN THE VINYL ACETATE

Raymond Lanthier, Pierrefonds, Quebec, and Lorenzo Quellet, Dorion, Quebec, Canada, assignors to Gulf Oil Canada Limited, Toronto, Ontario, Canada
No Drawing. Continuation-in-part of application Ser. No. 688,348, Dec. 6, 1967. This application Oct. 24, 1968, Ser. No. 770,441

Int. Cl. C08f 1/08, 15/16
U.S. Cl. 260—29.6 11 Claims
Process for aqueous emulsion interpolymerization of vinyl acetate and acrylamide with or without additional monomers in proportions to form stable 50–70% interpolymer solids emulsions, with 2–15% acrylamide by weight of the other monomers in the interpolymer, by dissolving the acrylamide in the vinyl acetate with the aid of a solubilizing agent before dispersing the monomers in an aqueous medium for interpolymerization. Examples of suitable specific solubilizing agents are methanol and formamide, materials which render acrylamide soluble in vinyl acetate and do not interfere with subsequent interpolymerization nor adversely affect the properties of the resulting interpolymer emulsion.

3,577,377

POLYESTER TIRE CORD ADHESIVE DIPS

Wun T. Tai, Monroeville, Pa., assignor to Koppers Company, Inc.
No Drawing. Filed Nov. 29, 1968, Ser. No. 780,208
Int. Cl. C08d 7/00; C09d 5/02

U.S. Cl. 260—29.7 1 Claim
Adhesive dips suitable for the bonding of polyester fibers to rubber in the manufacture of reinforced rubber articles are prepared from tris(monohydroxybenzyl) phenol and an aqueous rubber latex.

3,577,378

GLASS FIBER REINFORCED POLYCARBONATES

Hugo Strelb and Wilhelm Hechelhammer, Krefeld-Bockum, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Continuation-in-part of application Ser. No. 439,082, Mar. 11, 1965. This application Sept. 9, 1968, Ser. No. 758,614

Claims priority, application Germany, Mar. 12, 1964, F 42,281
Int. Cl. C08g 51/10 8 Claims
The invention meets with a process for the production of glass fiber reinforced polycarbonates by introducing milled, filamentized, water-sized glass fibers into a solution or a melt of polycarbonate resin, removing the solvent if necessary and extruding the glass fiber containing melt through a nozzle.

3,577,379

DARK COLORED COATINGS OF HIGH SOLAR HEAT REFLECTANCE

Melvin H. Sandler, Baltimore, and Merrill Cohen, Havre de Grace, Md., assignors to the United States of America as represented by the Secretary of the Army
Continuation-in-part of abandoned application Ser. No. 567,162, July 22, 1966. This application Mar. 11, 1969, Ser. No. 834,571

Int. Cl. C08g 51/04 5 Claims
A dark colored coating of high solar heat reflectance utilized to minimize heat build-up in the interior of objects exposed to sunlight comprising a mixture of pigments having a high-infrared reflectance such as quinacridone red, the violet to red shade of carbazole dioxazine, and titanium dioxide in combination with pigments such as lead chromate, molybdate orange, and phthalocyanine blue in order to obtain an acceptable color match. The pigment mixture is dispersed with extender pigments and suitable vehicles together with driers, volatile solvents, antioxidants, wetting agents, stabilizers and other additives of the art to form an enamel.

3,577,380

CROSS-LINKED CARBOXYLATED ELASTOMERS

Charles R. Binder, Romeo, Mich., assignor to General Motors Corporation, Detroit, Mich.
No Drawing. Filed June 28, 1968, Ser. No. 740,981
Int. Cl. C08g 41/00, 41/02

U.S. Cl. 260—41.5 5 Claims
The strength of uncured elastomeric polymers containing pendant carboxyl groups may be markedly improved by cross-linking such elastomers through the carboxyl groups with polymethylene polyphenylisocyanate. In a preferred embodiment, a filler material containing reactive hydroxyl groups is incorporated into the curable mixture for additional cross-linking and further improvement in physical strength.

3,577,381

HEAT STABILIZATION OF POLYESTER RESIN WITH PHENYLPHOSPHINIC ACIDS

Mary J. Stewart, Riddlewood, Media, and John A. Price, Swarthmore, Pa., assignors to FMC Corporation, Philadelphia, Pa.
No Drawing. Filed Apr. 25, 1968, Ser. No. 724,280
Int. Cl. C08g 51/58

U.S. Cl. 260—45.7 9 Claims
A composition including a high molecular weight, thermoplastic linear polyester resin and a heat stabilizing amount of diphenyl phosphinic acid or phenyl phosphinic acid, is disclosed herein.


3,577,382

POLYMERIC COMPOSITIONS COMPRISING ORGANO-AMINO-PHOSPHONATE ESTERS

Al F. Kerst, Creve Coeur, Mo., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Continuation-in-part of application Ser. No. 759,250, Sept. 11, 1968. This application June 11, 1969, Ser. No. 832,441

Int. Cl. C09k 3/28 13 Claims
U.S. Cl. 260—45.8
This invention relates to polymeric compositions containing esters, salts and acids of partial anhydrides of organophosphonates which include such a compound as shown below.



ERRATUM

For Class 260—45.85 see:
Patent No. 3,577,556

3,577,383

DIBUTYL THIO UREA AS A UV ABSORBER FOR POLYURETHANES

Grant O. Sedgwick, Minneapolis, Minn., assignor to Ashland Oil, Inc., Ashland, Ky.
No Drawing. Filed Nov. 1, 1966, Ser. No. 591,129
Int. Cl. C08g 51/60

U.S. Cl. 260—45.9 5 Claims
Aromatic diisocyanate derived polyurethanes which inherently exhibit a pronounced tendency toward discoloration upon exposure to UV light are stabilized against such deleterious effect by the presence therein of a small amount of a dialkyl substituted thio urea.

3,577,384

STABILIZED MOULDING COMPOSITIONS FROM POLYMERS OF α -OLEFINS

Otto Mauz, Niederhofheim, Taunus, and Eberhard Prinz, Kelkheim, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Filed July 7, 1969, Ser. No. 839,713
Claims priority, application Germany, July 10, 1968, P 17 69 765.3
Int. Cl. C08f 45/58

U.S. Cl. 260—45.85 4 Claims
Moulding compositions from polyolefins and a stabilizer mixture which consists of a tetraphenol and a dialkyl disulfide which are especially suitable for the manufacture of shaped articles coming into contact with hot water.

3,577,385

POLYURETHANE ELASTOMERS PREPARED BY REACTING A MIXTURE OF A POLYOXYALKYLENE ETHER DIOL OF A DIHYDROXY PHENOL AND A POLYOXYALKYLENE ETHER OF A POLYOL WITH AN ORGANIC POLYISOCYANATE

Joseph Feltzin and Nadji Y. Tehrani, Wilmington, Del., assignors to Atlas Chemical Industries, Inc., Wilmington, Del.
No Drawing. Filed May 15, 1967, Ser. No. 638,630
Int. Cl. C08g 22/26

U.S. Cl. 260—47 8 Claims
Polyurethanes having improved properties are prepared by reacting polyoxyalkylene ether diols containing a carboxycyclic or oxacyclic ring and from 2 to 10 oxyalkylene

groups, polyoxyalkylene ether polyols containing from 5 to 10 hydroxyl groups and from 15 to 90 oxyalkylene groups, and organic polyisocyanates.

3,577,386

PRODUCT AND PROCESS

John E. Maier, White Bear Lake, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Oct. 7, 1968, Ser. No. 765,676
Int. Cl. C08g 30/14, 30/16

U.S. Cl. 260—47

12 Claims

A composition curable to an elastomer having outstanding physical properties, the composition having an epoxy resin, a polyether polyprimary polyamine containing recurring oxytetramethylene units and a tin acrylate dissolved therein.

3,577,387

PROCESS OF PREPARING HEAT-RESISTANT POLYMERS


Hilde Kersten, Mechenhard, Erhard Siggel, Seckmauern, and Gerhard Meyer, Obernburg, Germany, assignors to Glanzstoff AG, Wuppertal, Germany
No Drawing. Filed Jan. 3, 1969, Ser. No. 788,931
Claims priority, application Germany, Jan. 8, 1968, P 17 20 884.3

Int. Cl. C08g 15/00

U.S. Cl. 260—47

3 Claims

A high molecular weight polymer having recurring units of the formula



wherein Ar is one of the tetravalent aromatic radicals selected from the class consisting of phenylene, diphenylene, naphthylene, diphenylether and diphenylmethane as derived from a condensed aromatic bis-(2,4-dihydroxypyridine) compound by the steps of chlorination, alkoxylating, decarboxylating and finally polymerizing in an acid medium at about 20–300° C. Preferred long chain or relatively higher molecular weight polymers are achieved by polymerizing in inorganic non-oxidizing acids especially in polyphosphoric acid. The polymers are especially useful where stability to high temperatures and solvents is required.

3,577,388

FIBER PREPARED FROM POLYESTER BASED POLYURETHANE PREPOLYMER

Ignazio Salvatore Megna and Anthony Koroscil, Somerville, N.J., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Continuation-in-part of application Ser. No. 566,229, July 19, 1966. This application May 14, 1969, Ser. No. 824,685

Int. Cl. C08g 22/10, 22/16

U.S. Cl. 260—75

2 Claims

Polyurethane spinning solutions which yield spandex fibers of improved elasticity are prepared by reacting an excess of an organic diisocyanate with a hydroxyl terminated polyester prepared by reacting adipic acid with an excess of a mixture of 1,4-butylene glycol and 1,2-propylene glycol wherein the glycols are present in a mole ratio of between 80:20 and 95:5, and then chain extending the resulting prepolymer with a diamine.

3,577,389

CHAR RESISTANT POLYURETHANE

George A. Kuhar, Greensburg, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
No Drawing. Filed Aug. 19, 1968, Ser. No. 753,756

Int. Cl. C08g 22/06, 22/12

U.S. Cl. 260—75

5 Claims

A polyurethane composition prepared by reacting o-tolidine diisocyanate, dicumyl peroxide and an unsaturated polyester diol of the structure obtained by the condensation of adipic acid and a mixture of ethylene glycol and glycerol α -allyl ether where the said composition has a Shore A hardness of from about 25 to about 45 and an arc image char rate of from about 1.5 to about 3 mils/second.

3,577,390

ORGANOSILICON-AMINO COMPOUNDS AS CATALYSTS IN POLYURETHANE PRODUCTION

William J. Owen, Penarth, Glamorgan, and Norman C. Lloyd, Cardiff, Glamorgan, Wales, assignors to Midland Silicones Limited, Reading, Berkshire, England
No Drawing. Filed Sept. 18, 1968, Ser. No. 760,710
Claims priority, application Great Britain, Sept. 27, 1967, 44,033/67

Int. Cl. C08g 22/26, 22/38, 22/44

U.S. Cl. 260—77.5

5 Claims

Organosilicon amino compounds are employed as curing catalysts in the production of polyurethanes. The novel catalysts are defined by the formula



where R is hydrogen or certain organic radicals, R' and R'' are certain organic radicals, Q is methylene, ethylene or propylene and a and b are 0 or 1.

3,577,391

ALCOHOL-BLOCKER ISOCYANATE COMPOSITIONS AND DERIVATIVES

Perry A. Argabright, Brian L. Phillips, and Vernon J. Sinkey, Littleton, Colo., assignors to Marathon Oil Company, Findlay, Ohio

No Drawing. Original application Mar. 4, 1966, Ser. No. 531,772. Divided and this application Oct. 8, 1968, Ser. No. 798,506

Int. Cl. C08g 22/32

U.S. Cl. 260—77.5

11 Claims

Urethane-containing compositions, particularly baked on coatings, are produced by the reaction of organic polyhalides with metal cyanates in the presence of monohydric alcohol and aprotic solvent.

3,577,392

WORKABLE POLYAMIDES BY BLENDING WITH INORGANIC THIOCYANATES

Rajindar K. Kochhar and Bert H. Clappitt, Overland Park, and Ronald E. Gilbert, Shawnee Mission, Kans., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

No Drawing. Filed Oct. 31, 1968, Ser. No. 772,396

Int. Cl. C08g 20/38

U.S. Cl. 260—78

3 Claims

Polyamides can be tailored to have more workable properties by blending with a minor portion of an inorganic thiocyanate such as sodium or potassium thiocyanate. With the exception of ammonium thiocyanate, which has the opposite effect on melt viscosity, the blends raise melt viscosity, and lower the normal freezing point. Individual physical properties of the extruded or molded polyamide blend remain the same or are improved, except with ammonium thiocyanate which reduces tensile strength and elongation.

3,577,393

ETHYLENE-PROPYLENE-DIENE TERPOLYMER RUBBERS AND PROCESSES THEREFOR

Albert Schrage, East Orange, and Jules Ernest Schoenberg, Bergenfield, N.J., assignors to Dart Industries Inc., Los Angeles, Calif.

Continuation-in-part of application Ser. No. 695,468, Jan. 3, 1968. This application Aug. 20, 1968, Ser. No. 753,995

Int. Cl. C08f 15/40

U.S. Cl. 260—80.78

7 Claims

Substantially gel-free novel sulphur-curable elastomers prepared by reacting ethylene, an alpha-olefin (preferably propylene) and the cross-dimer of cyclopentadiene and methylcyclopentadiene.

3,577,394

2-CHLOROETHYL 2-CYANOACRYLATE AND COMPOSITIONS THEREOF

Joseph K. Harrington, Edina, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Sept. 27, 1968, Ser. No. 763,378

Int. Cl. C08f 3/74

U.S. Cl. 260—78.4

3 Claims

A useful cyanoacrylate monomer, 2-chloroethyl 2-cyanoacrylate, is provided, having utility in adhesive compositions. A process for its preparation is described.

3,577,395

NOVEL CATALYST FOR THE POLYMERIZATION OF CONJUGATED DIENES

Joginder Lal and Morford C. Throckmorton, Akron, Ohio, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed Apr. 9, 1969, Ser. No. 814,831

Int. Cl. C08d 3/06

U.S. Cl. 260—82.1

10 Claims

There is disclosed a process of the polymerization of butadiene and butadiene in mixture with other conjugated diolefins to form polymers containing a high portion of butadiene units in the cis-1,4 configuration comprising contacting at least one diolefin with a catalyst comprising (A) at least one compound selected from the group consisting of organometallic compounds wherein the metal is selected from Groups I, II and III of the Periodic Table and hydrides of metals of Groups II and III of the Periodic Table and their monomeric or polymeric halide derivatives, amine derivatives and complexes of these hydrides with amines, ethers or other molecules capable of forming complex compounds with these hydrides, (B) at least one organonickel compound and (C) at least one organic fluoro-chemical compound.

3,577,396

POLYMERIZATION OF CONJUGATED DIENES BY MEANS OF A NICKEL FLUOROBORATE HYDRATE/ORGANOMETALLIC COMPOUND CATALYST SYSTEM

Morford C. Throckmorton, Akron, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed June 30, 1969, Ser. No. 837,906

Int. Cl. C08d 3/06

U.S. Cl. 260—82.1

7 Claims

There is disclosed a process for the polymerization of butadiene and butadiene in mixture with other conjugated diolefins to form polymers containing a high portion of the butadiene units in the cis-1,4 configuration comprising contacting at least one diolefin under polymerization conditions with a binary catalyst system comprising (A) at least one nickel fluoroborate hydrate containing from 15% to 31% by weight of water of hydration and (B) at least one organometallic compound wherein the metal is selected from Groups I, II and III of the Periodic Table.

3,577,397

PROCESS AND PRODUCT FROM TREATING LIVE ELASTOMERS WITH PHOSPHAZENES

Adel F. Halasa, Bath, Ohio, and Russell W. Koch, Blacksburg, Va., assignors to The Firestone Tire & Rubber Company, Akron, Ohio

No Drawing. Continuation of application Ser. No. 711,927, Mar. 11, 1968. This application Nov. 24, 1969, Ser. No. 879,596

Int. Cl. C08d 5/04; C08f 27/08

U.S. Cl. 260—85.1

13 Claims

The process described herein involves a method of converting relatively low molecular weight elastomers prepared by alkali metal-catalyzed polymerizations, such as alkyllithium catalyst polymerizations, and still containing active lithium or other alkali metal therein, by post-reaction with phosphazenes, which can be represented as $(PNCl_2)_x$ wherein x is 3 or 4. The postreacted products are highly branched elastomers having a broad molecular weight distribution and possessing less cold flow than the polymers from which they are produced. Surprisingly, even though the molecular weight of the polymer is increased many times, the reaction product displays little or no cold flow even after extension with oil.

3,577,398

SYNTHETIC RESIN

Henry A. Pace and Victor J. Anhorn, Akron, Ohio, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Continuation of application Ser. No. 556,293, June 9, 1966. This application Sept. 12, 1969, Ser. No. 857,598

Int. Cl. C08d 3/04

U.S. Cl. 260—85.3

1 Claim

A polymeric resinous composition comprising from about 40 to about 80 weight percent units derived from piperylene and from about 60 to about 20 weight percent units derived from 2-methyl-2-butene wherein the said resinous composition has a softening point of from about 80° C. to about 110° C. The said polymeric resinous composition can be modified by having up to about 25 weight percent units derived from certain other unsaturated hydrocarbons. The polymeric resinous composition is prepared by polymerizing a mixture comprising from about 20 to about 75 weight percent of piperylene and from about 80 to about 25 weight percent of 2-methyl-2-butene in the presence of an anhydrous metal halide selected from aluminum chloride and stannic chloride.

3,577,399

ETHYLENE INTERPOLYMERS

George A. Mortimer, La Marque, Tex., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Sept. 23, 1968, Ser. No. 761,837

Int. Cl. C08f 15/04

U.S. Cl. 260—88.1

4 Claims

Compositions of matter comprised of interpolymers of ethylene and from 1 to 10 mole percent of a monovinyl silane and a method for their preparation.

3,577,400

NOVEL CATALYSTS FOR THE POLYMERIZATION OF ALICYCLIC OLEFINS

William Allen Judy, Akron, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

No Drawing. Filed Aug. 26, 1968, Ser. No. 755,376

Int. Cl. C08f 15/04

U.S. Cl. 260—88.2

13 Claims

A method for the ring opening polymerization of unsaturated alicyclic compounds containing at least 4 and not more than 5 carbon atoms and one double bond in

the cyclic ring and unsaturated alicyclic compounds containing at least 8 carbon atoms and at least one double bond in the cyclic ring is disclosed which comprises subjecting such unsaturated alicyclic compounds to a catalyst system comprising (A) a tungsten or molybdenum halide or oxyhalide and (B) at least one Lewis acid of the formula $M-X_n$ where M is a metal represented by aluminum, zinc, gallium, tin and antimony; X is a halogen such as bromine, chlorine, iodine and fluorine and n is an integer equal to the valence of M.

3,577,401

POLYMERIZATION OF VINYL CHLORIDE USING AN IN-SITU INITIATOR AND A BASIC CALCIUM COMPOUND AS A BUFFER

Edwin Studley Smith, Cuyahoga Falls, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
No Drawing. Filed Feb. 17, 1969, Ser. No. 799,953
Int. Cl. C08f 1/11, 1/60, 3/30

U.S. Cl. 260—92.8

5 Claims

Process for making polyvinyl chloride having improved resistance to "plate out" using a basic calcium compound as a buffer in combination with a peroxydicarbonate initiator formed in-situ.

3,577,402

PASTE ROSIN SIZE CONTAINING VISCOSITY DEPRESSANT

Robert Alan Dorbransky, Stamford, Conn., assignor to American Cyanamid Company, Stamford, Conn.
No Drawing. Filed July 24, 1968, Ser. No. 747,132
Int. Cl. C08h 11/00

U.S. Cl. 260—97

2 Claims

Paste rosin size at 150°–200° F. containing 0.5%–5% of a water-soluble alkanepolyol which has a molecular weight below 250 and a boiling point above 150° C. possesses low viscosity and decreased tendency to develop a hard, brittle, foamy crust when exposed to the air in that temperature range.

3,577,403

1,1-BIS-[4-(1'-BENZYL-3'-METHYL-PYRAZOLONE-AZO)PHENYL]CYCLOHEXANE

Hans Raab and Günter Hageloch, Cologne-Stammheim, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany
No Drawing. Filed Dec. 12, 1967, Ser. No. 689,786
Claims priority, application Germany, Dec. 17, 1966, F 50,995

Int. Cl. C09b 31/14; C09d 11/16, 11/18

U.S. Cl. 260—160

1 Claim

A water-insoluble diazo dyestuff particularly advantageous in the dyeing of inks and pastes for ball point pens is produced by coupling 1-benzyl-3-methyl-pyrazolone with 1,1-bis-(4-aminophenyl)cyclohexane.

3,577,404


BASIC PYRAZOLONE MONOAZO DYES CONTAINING AN AMMONIUM OR HYDRAZINIUM GROUP
Roland Entschel, Basel, Curt Mueller, Binningen, Basel-Land, and Willy Steinemann, Basel, Switzerland, assignors to Sandoz Ltd., also known as Sandoz A.G., Basel, Switzerland

No Drawing. Filed July 23, 1968, Ser. No. 746,758
Claims priority, application Switzerland, Aug. 11, 1967, 11,369/67; July 15, 1968, 10,552/68
Int. Cl. C09b 29/38; D06p 1/06, 3/04

U.S. Cl. 260—162

12 Claims

Basic dyes of the formula



wherein

K_1 stands for a coupling compound of the pyrazolone series,
Y stands for an alkylene or arylene radical,
Z stands for —O—, —S— or —SO₂—,
 $K^\oplus$ stands for a hydrazinium- or an ammonium group and wherein the ring B may bear further substituents; are useful for dyeing acrylonitrile polymers and copolymers. Resulting dyeings have good fastness properties.

3,577,405


WATER-SOLUBLE, YELLOW MONO-AZO DYES WITH ACTIVE METHYLENE COUPLER

Hermann Hoffmann, East Greenwich, and Helmut Schmidt, Warwick, R.I., assignors to American Hoechst Corporation, New York, N.Y.
No Drawing. Filed May 8, 1968, Ser. No. 727,715
Int. Cl. C07c 107/04; C09b 29/32


U.S. Cl. 260—193

8 Claims

Azo dyes of the formula



in which R stands for methyl or ethyl, X stands for hydrogen or chlorine, and Me represents an alkali metal or ammonium, are prepared by combining diazotized 2-(4'-amino-benzenesulfonylamino)-ethyl-thiosulfuric acid with a coupling component of the formula



in which R stands for methyl or ethyl and X stands for hydrogen or chlorine, at a temperature between 0° C. and 20° C. and a pH between 2 and 6, which azo dyes are readily soluble in water and have good to excellent fastness when applied to native or regenerated cellulose, cellulose acetate, wool, silk, leather and synthetic materials such as polyester and especially polyamide fibers.

3,577,406

PROCESS FOR PREPARING THE ANTIBIOTIC STREPTOZOTOCIN

Edward J. Hessler, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.
No Drawing. Filed May 23, 1968, Ser. No. 731,615
Int. Cl. C07c 95/04

U.S. Cl. 260—211

6 Claims

A chemical process for preparing the antibiotic streptozotocin starting with D-glucosamine which is reacted with N-methylisocyanate to produce N-(methylcarbamyl)-D-glucosamine, and then reacting this latter compound with a nitrosating agent to produce streptozotocin. Streptozotocin is disclosed in U.S. Patent 3,027,300 as useful for veterinary purposes because of its high activity against *Pasteurella multocida* and *Salmonella pullorum*.

3,577,407

HIGHLY HYDROXYPROPYLATED GRANULE POTATO STARCH

Erling I. Hjermstad, Cedar Rapids, Iowa, assignor to Penick & Ford, Limited, Cedar Rapids, Iowa
No Drawing. Filed May 19, 1969, Ser. No. 826,027
Int. Cl. C08b 19/06

U.S. Cl. 260—233.3

3 Claims

A process for the production of hydroxypropylstarch in the water-washable granule form even after reaction to a high degree of substitution (up to 20–30% hydroxypropyl content) by treating potato starch granules at elevated temperatures in water suspension of near-neutral pH for at least one hour followed by alkaline catalyzed hydroxypropylation.

3,577,411

6-PHENYLBENZAZOLYL DERIVATIVES

Peter Liechti, Binningen, Leonardo Guglielmetti, Birsfelden, Erwin Maeder, Aesch, Basel-Land, and Adolf Emil Siegrist, Basel, Switzerland, assignors to Ciba Limited, Basel, Switzerland

No Drawing. Continuation-in-part of application Ser. No. 483,355, Aug. 27, 1965. This application Oct. 9, 1967, Ser. No. 673,953


Claims priority, application Switzerland, Sept. 4, 1964, 11,401

Int. Cl. C07d 85/48

U.S. Cl. 260—240

10 Claims

The present invention relates to new and valuable 6-phenyl-2-stilbenyl-benzoxazoles which may be represented by the formula



wherein R₁, R₂ and R₃ are identical or different and each represents a member selected from the group consisting of hydrogen, halogen, alkyl or alkoxy containing 1 to 12 carbon atoms, phenyl, phenylalkyl with 1 to 4 carbon atoms in the alkyl portion, nitrile, free or neutralized carboxyl (—COO cation), carboxylic acid alkyl ester with 1 to 12 carbon atoms in the alkyl portion, carbon amide, carbon alkyl amide with 1 to 12 carbon atoms, free or neutralized sulphonic acid (—SO₂O cation) or sulphonamide, and n stands for the whole numbers 1 to 3.

The compounds of this invention are especially useful as optical brighteners for organic materials.

3,577,408

TETRAHYDRO-2-OXOFURAN PENICILLINS

Harvey E. Alburn, West Chester, William Dvornch, Radnor, and Stephan Sallay, Wynnewood, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed Oct. 15, 1968, Ser. No. 767,822
Int. Cl. C01d 99/16

U.S. Cl. 260—239.1

3 Claims

6-(tetrahydro-2-oxofuran-3-carboxamido)penicillanic acids which may be substituted in the 3 and 5 positions, or the opened ring forms of these penicillins are produced, having antibiotic activity.

ERRATUM

For Class 260—239.3 see:
Patent No. 3,577,557

3,577,409

2-RCH₂NH-4-X-5-SULFAMYL BENZOIC ACIDS

Edward J. Cragoe, Jr., Lansdale, Pa., assignor to Merck & Co., Inc., Rahway, N.J.
No Drawing. Filed Dec. 7, 1965, Ser. No. 512,217
Int. Cl. C07d 7/04, 15/04, 15/12

U.S. Cl. 260—239.6

6 Claims

4-chloro or bromo-5-sulfamyl-N-substituted-anthranilic acid diuretic compounds, having as N-substituents a saturated pyranylmethyl, a dioxolanylmethyl, or a dioxanylmethyl group are described. These products are prepared by the reaction of 2,4-dihalo-5-sulfamylbenzoic acid and RCH₂NH₂ where R is a tetrahydropyranyl, a dioxolanyl or a dioxanylmethyl group.

3,577,410

13β-ALKYL-17-HYDROXYGONA-4,14-DIEN-3-ONES
Daniel M. Teller, King of Prussia, George H. Douglas, Paoli, and Herchel Smith, Wayne, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed July 30, 1968, Ser. No. 749,922
Int. Cl. C07c 173/00

U.S. Cl. 260—239.55

25 Claims

New steroids of the 13β-alkyl-17β-hydroxygona-4,14-dien-3-one series optionally substituted at C-7 and C-17 by α-methyl (I) are provided by either (a) isomerizing a corresponding 17-hydroxy-13β-alkylgona-5(10),14-dien-3-one (II) or (b) reacting with a methyl Grignard reagent a corresponding 17-hydroxy-13β-alkylgona-4,6,14-trien-3-one (III). Means are provided to prepare the intermediate compounds II and III. Compounds I and Ia are androgenically-active in warm-blooded lower animals.

3,577,413

PROCESS OF PREPARING TRITYLAMINES

Charles R. Adams, Oakland, Calif., and Hans J. Arpe, am Quintengarten, Hans J. Schulze-Steinen, Bad Soden, Taunus, and Jürgen F. Falbe, Wasserland, Germany, Alan C. Edwards, The Hague, Netherlands, and Hans Tetteroo, Wasserland, Germany, assignors to Shell Oil Company, New York, N.Y.

No Drawing. Filed Oct. 11, 1967, Ser. No. 674,637
Claims priority, application Germany, Oct. 14, 1966, P 16 20 412.9

Int. Cl. C07d 87/26

U.S. Cl. 260—247

8 Claims

Process of preparing tritylamines by reacting a primary or secondary amine with a trityl chloride-Friedel-Crafts catalyst complex, e.g., N-tritylmorpholine is prepared by reacting morpholine with a trityl chloride-aluminum trichloride complex.

3,577,414

BERYLLIUM HYDRIDE TERTIARY AMINE COMPLEXES

Lawrence H. Shepherd, Jr., Baton Rouge, La., assignor to Ethyl Corporation, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 645,560, June 5, 1967. This application Mar. 27, 1968, Ser. No. 716,669

Int. Cl. C07d 87/26, 27/04

U.S. Cl. 260—247

6 Claims

Complexes of beryllium hydride with tertiary amines, containing one molecule of beryllium hydride for each tertiary amino nitrogen atom in the amine, are prepared by reaction of beryllium hydride with an excess of a tertiary amine in a ball or rod mill at ambient temperature and pressure.

3,577,415

1-SUBSTITUTED-3-SUBSTITUTED PHENOXYPYRROLIDINES

Albert Duncan Cale, Jr., Mechanicsville, Va., assignor to A. H. Robins Company, Incorporated, Richmond, Va.

No Drawing. Filed Dec. 23, 1968, Ser. No. 786,395

Int. Cl. C07d 27/04

U.S. Cl. 260—247.2

10 Claims

1-substituted-3-substituted phenoxy-pyrrolidines useful as anti-depressants are disclosed. The compounds are prepared from 1-methyl-3-pyrrolidinols and 1-benzyl-3-pyrrolidinols.

3,577,416

PROCESS FOR THE SELECTIVE CHLORINATION OF ALKYL MERCAPTO-SUBSTITUTED s-TRIAZINES

Werner Schwarze, Frankfurt am Main, Günter Gieselmann, Neu-Isenburg, and Wolfgang Weigert, Offenbach am Main, Germany, assignors to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler, Frankfurt am Main, Germany

No Drawing. Filed Feb. 13, 1969, Ser. No. 799,099

Claims priority, application Germany, Feb. 17, 1968, P 16 70 590.1

Int. Cl. C07d 55/48

U.S. Cl. 260—248

18 Claims

s-Triazines which are 2 or 2,4 or 2,4,6 substituted by alkylmercapto groups and wherein the balance of said 2,4,6 substituents is substituted by chlorine, if any, are selectively chlorinated by subjecting the triazines to the action of a chlorinating agent, the amount of chlorinating agent in said reaction being selected to provide for at least two chlorine atoms for each alkylmercapto group to be converted, whereby a predetermined number of said alkylmercapto groups may be converted to chlorine. The products of the reaction are valuable for making herbicides, optical brighteners, light stabilizers, and other compounds and are useful also as stabilizers for polyformaldehyde and as starting products for making stabilizers for the rubber industry.

3,577,417

2,4,6-TRISUBSTITUTED-s-TRIAZINES

Margot Louise Cantrall, New City, Martin Leon Sassiver, Monsey, and Robert Gordon Shepherd, South Nyack, N.Y., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed May 22, 1969, Ser. No. 827,048

Int. Cl. C07d 55/22

U.S. Cl. 260—249.6

10 Claims

This disclosure describes compounds of the class of N^2 - (polycycloalkyl) - N^4, N^6 -bis(aliphatic or alicyclic) melamines useful as anti-mycobacterial agents.

3,577,418

PYRAZINAMIDE DERIVATIVES AND PROCESSES FOR THEIR PREPARATION

Edward J. Cragoe, Jr., Lansdale, and Kenneth L. Shepard, Ambler, Pa., assignors to Merck & Co., Inc., Rahway, N.J.

No Drawing. Continuation-in-part of application Ser. No. 718,976, Mar. 21, 1968, which is a continuation-in-part of application Ser. No. 666,004, Sept. 7, 1967. This application Feb. 12, 1969, Ser. No. 798,809

Int. Cl. C07d 51/76

U.S. Cl. 260—250

49 Claims

A new method is disclosed for the preparation of pyrazinamide derivatives. The process involves reaction of an amine derivative with a very reactive pyrazinoyloxyacrylamide prepared by reaction between a pyrazinoic acid and an isoxazolium salt. The reactivity of the pyrazinoyloxyacrylamide permits the preparation of compounds previously unavailable and hence many of the products are new compounds. The compounds prepared by this process have utility as diuretics.

3,577,419

2,6-DISUBSTITUTED-4-(ω-AMINOALKOXY) PHENYL PYRIMIDINES

Rudolf G. Griot, Riehen, Switzerland, assignor to Sandoz-Wander, Inc., Hanover, N.J.

No Drawing. Continuation-in-part of application Ser. No. 725,197, Apr. 29, 1968. This application Oct. 24, 1969, Ser. No. 869,330

Int. Cl. C07d 51/36

U.S. Cl. 260—256.4

12 Claims

This invention relates to 2-substituted-6-cyclosubstituted-4-[4-(ω-aminoalkoxy)phenyl]pyrimidines useful as hypolipidemics and/or as anti-convulsants, and to preparation of said compounds.

3,577,420

CERTAIN 4-AMINOFURO[2,3-d]PYRIMIDINES

Hans-Jürgen E. Hess, Groton, and Timothy H. Cronin, Niantic, Conn., assignors to Pfizer Inc., New York, N.Y.

No Drawing. Filed Jan. 5, 1968, Ser. No. 695,868

Int. Cl. C07d 99/04

U.S. Cl. 260—256.4

4 Claims

4-aminofuro[2,3-d]pyrimidines relax smooth muscle and inhibit cyclic 3',5'-nucleotide phosphodiesterase activity. The compounds are synthesized by condensing α-halo-ketone or aldehyde with dimethyl malonate, reacting the ethylene ketal malonamide therewith alkanolic acid ester, cyclizing with acid to obtain the furo[2,3-d]pyrimidine-4-one, then obtaining a 4-amino derivative through the 4-chloro intermediate. The 5,6-alkylene compounds are prepared by condensing α-hydroxy cyclic ketone with malonitrile and cyclizing with alkanolic acid amide.

3,577,421

PIPERAZINE SUBSTITUTED DITHIOSEMI-CARBAZONES

Paul Anthony Barrett, London, England, assignors to Burroughs Wellcome Co., Triangle Park, N.C.

No Drawing. Filed May 18, 1966, Ser. No. 550,934

Claims priority, application Great Britain, May 25, 1965, 22,006/65


The portion of the term of the patent subsequent to Nov. 11, 1986, has been disclaimed

Int. Cl. C07d 51/70

U.S. Cl. 260—268

5 Claims

A compound



where R and R¹ are hydrogen, alkyl, cyclohexyl, benzyl, phenyl, halogen substituted phenyl or alkoxyalkyl, R² is lower alkyl and n is a number from 1 to 8. The compounds are useful in the treatment of coccidiosis.

3,577,422

4-[ω-[4-(2-, OR 3-HALO-P-TOLYL) - 1-PIPERAZINYL] ALKOXY] - β,β - DIMETHYLHYDROCINNAMIC ACID ESTERS

Norman E. Wideburg and Laura H. Miller, Waukegan, Ill., assignors to Abbott Laboratories, North Chicago, Ill.


No Drawing. Continuation of application Ser. No. 717,392, Mar. 29, 1968. This application Apr. 10, 1968, Ser. No. 720,348

Int. Cl. C07d 51/70

U.S. Cl. 260—268

4 Claims

Newly synthesized 4-[ω-[4-(2-, or 3-halo p-tolyl)-1-piperazinyl]alkoxy] - β,β - dimethylhydrocinnamic acid esters useful for chemotherapeutically reducing the number of flukes of genus Schistosoma present in infected warm-blooded animals have been found to alleviate symptoms of schistosomiasis. These esters have the structural formula



wherein X is a halogen; n is an integer of from 3 to 6; R₁ is hydrogen or lower alkoxy; and R₂ is methyl, ethyl, or a straight or branched chain alkyl radical of up to 5 carbon atoms. The esters are prepared by microbiologically oxidizing a 1-(2-, or 3-halo-p-tolyl)-4-[ω-(p-tert-pentylphenoxy)alkylene]piperazine to the corresponding hydrocinnamic acid and then esterifying the acid.

3,577,423

1,4-BIS-(3-INDOLEGLYOXYLOYL) PIPERAZINES AND DERIVATIVES THEREOF

John L. Archibald, Malvern, and Meier E. Freed, Philadelphia, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Original application Dec. 3, 1965, Ser. No. 511,362, now Patent No. 3,471,499, dated Oct. 7, 1969. Divided and this application June 26, 1969, Ser. No. 844,717

Int. Cl. C07d 57/100

U.S. Cl. 260—268

14 Claims

The compounds are 1,4-bis-(3-indoleglyoxyloyl)piperazines. Said compounds are useful as intermediates in the preparation of corresponding 1,4-bis(2-indol-3-yl-ethyl)piperazines and their salts, which are pharmacologically active as hypotensives.

3,577,424

4-PHENYL-8-AMINO TETRAHYDROISOQUINOLINES

Gustav Ehrhart, Bad Soden, Taunus, Karl Schmitt, Frankfurt am Main, Irmgard Hoffmann, Bad Soden, Taunus, and Heinrich Ott, Eppstein, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Continuation-in-part of application Ser. No. 635,398, May 2, 1969. This application Oct. 20, 1969, Ser. No. 867,932

Claims priority, application Germany, May 5, 1966, F 49,122; Aug. 12, 1966, F 49,122; Apr. 15, 1967, F 52,134, F 52,135

Int. Cl. C07d 35/38

U.S. Cl. 260—287

9 Claims

4-phenyl-8-amino tetrahydroisoquinolines having centrally stimulating and thymoleptic action. Methods for their manufacture by ring closure, acylation, or reduction. Pharmaceutical compositions containing these compounds.

3,577,425

8-(1,4-BENZODIOXAN-2-YLMETHYL)-3-OXO-1-THIA-4,8-DIAZASPIRO[4.5]DECANES

Michio Nakanishi, Oita, Katsuo Arimura, Fukuoka, Hiroshi Imamura, Chiba, and Toshihiro Kobayakawa, Fukuoka, Japan, assignors to Yoshitomi Pharmaceutical Industries, Ltd., Osaka, Japan

No Drawing. Filed Dec. 10, 1968, Ser. No. 782,752


Claims priority, application Japan, Dec. 11, 1967, 42/79,638; Dec. 13, 1967, 42/80,743

Int. Cl. C07d 29/34

U.S. Cl. 260—293.4

19 Claims

Benzodioxane derivatives of the formula



and pharmaceutically acceptable salts thereof, wherein R¹ is H, Cl, methyl or methoxy, R² is H, alkyl of 1 to 4 carbon atoms, benzyl, phenyl or substituted phenyl in which the substituent is selected from the group consist-

ing of Cl, methyl methoxy and trifluoromethyl, A¹ is —CH₂—, —CH₂CH₂—, —CO— or —CH₂CO— the carbonyl portion of which is bound to the N atom of the piperidine ring or —CH(OH)—CH₂— the methylene (—CH₂—) portion of which is bound to the N atom of the piperidine ring, A² is —CH₂—, or —CHCH₃, and Z is —S—, —SO— or —SO₂—, are vasodilators of low toxicity in mammals.

3,577,426

4-(4-TETRAHYDROPYRANYL)PYRIDINES

Charles K. McGill and George W. Campbell, Jr., Indianapolis, Ind., assignors to Reilly Tar & Chemical Corporation, Indianapolis, Ind.


No Drawing. Filed Jan. 31, 1969, Ser. No. 795,714

Int. Cl. C07d 31/30

U.S. Cl. 260—297

10 Claims

4-(tetrahydropyranyl)pyridines having the formula:



in which R₁ and R₂ represent hydrogen or lower alkyl; R₃ and R₄ represent hydrogen, lower alkyl, or phenyl; they may be alike or they may be different. In general the tetrahydropyranylpyridines are made by the dehydration of a pyridyl pentanediol.

3,577,427

BROMINATION OF 2,1,3-BENZOTHIADIAZOLES AND BENZOFURAZANS

Kurt H. Pilgram, Modesto, Calif., assignor to Shell Oil Company, New York, N.Y.

No Drawing. Filed Sept. 5, 1968, Ser. No. 757,768

Int. Cl. C07d 85/48, 91/44

U.S. Cl. 260—304

5 Claims

Aqueous hydrobromic acid or nitric acid is used as the reaction medium for bromination of 2,1,3-benzothiadiazoles and benzofurazans.

3,577,428
2-AMINO-4-ARYLOXYALKYL-4-ALKYL-2-OXAZOLINES

John T. Suh, Mequon, and Joseph A. Skorcz, Milwaukee, Wis., assignors to Colgate-Palmolive Company, New York, N.Y.

No Drawing. Filed Apr. 14, 1969, Ser. No. 816,078
 Int. Cl. C07d 85/36

U.S. Cl. 260—307 5 Claims
 Compounds are 2-amino-4-aryloxyalkyl-4-alkyl-2-oxazoles which are useful as central nervous system stimulants and antihypertensive agents. The compounds may also be used as intermediates in the preparation of pickling agents, mothproofing agents and wood preservatives. Among the compounds disclosed is 2-amino-4-methyl-4-(o-methoxyphenoxy)methyl-2-oxazoline hexamate.

3,577,429
PHTHALOCYANINE DYE AND METHOD FOR MAKING SAME

Thomas C. Crawford, 4423 Ridgevalley Drive, Charlotte, N.C. 28208

No Drawing. Filed Mar. 11, 1968, Ser. No. 711,913
 Int. Cl. C09b 47/08

U.S. Cl. 260—314.5 6 Claims
 Copper tetra-(4)-sodiethiosulfatophthalocyanine dye useful for dyeing cotton and regenerated cellulose textiles green is prepared by simultaneously heating and aerating for 1–36 hours at 40° C.–90° C. and at pH 6.5–7.5 an aqueous composition comprising 1 part copper tetra-(4)-thiocyanophthalocyanine, 0.65–1.3 parts sodium bisulfite, and 0.65–1.3 parts sodium sulfite, and further characterized in that the parts of sodium sulfite and sodium bisulfite are approximately equal.

3,577,430
OXINDOLE ACETIC ACID AMIDES

Janis Plostnieks, Philadelphia, Pa., assignor to McNeil Laboratories, Inc.

No Drawing. Continuation-in-part of application Ser. No. 642,685, June 1, 1967. This application Feb. 17, 1969, Ser. No. 799,948

Int. Cl. C07d 27/40

U.S. Cl. 260—325 14 Claims
 The compounds are of the class of 2-oxindole acetamides useful as ultra-violet light absorbers and having central nervous system depressant activity; and of the class of 2-oxo-3-indoline acetate esters useful as intermediates in the preparation of said acetamides.

3,577,431
SANDWICH-TYPE CHEMICAL COMPOUNDS AND METHOD FOR THEIR PREPARATIONS

Earl Dan Flickinger, El Dorado, and Charles Merlyn Buess, Wichita, Kans., assignors to Skelly Oil Company, Tulsa, Okla.

No Drawing. Continuation-in-part of application Ser. No. 554,651, June 2, 1966. This application Feb. 19, 1968, Ser. No. 706,663

Int. Cl. C07d 27/28

U.S. Cl. 260—326.1 5 Claims
 New compositions of matter having two ring nuclei composed of 6 carbon atoms essentially superimposed in fixed parallel planes with respect to each other and process of preparing the same.

3,577,432
1-SUBSTITUTED-3-PHENOXYPYRROLIDINES

Grover Cleveland Helsley, Richmond, Va., assignor to A. H. Robins Company, Incorporated, Richmond, Va.

No Drawing. Filed Dec. 23, 1968, Ser. No. 786,383

Int. Cl. C07d 27/04

U.S. Cl. 260—326.3 15 Claims
 1-substituted-3-phenoxy-pyrrolidines useful as muscle relaxants, anti-convulsants and major tranquilizers are

disclosed. The compounds are prepared from 3-phenoxy-pyrrolidines.

3,577,433
KETO-ENOL NITROGEN-CONTAINING HETEROCYCLES HAVING AN AMINO SUBSTITUENT

Robert Fuks, Ixelles, Brussels, and Heinz G. Viehe, Beersel, Linkebeek, Belgium, assignors to Union Carbide Corporation

No Drawing. Filed Aug. 8, 1967, Ser. No. 659,013

Int. Cl. C07d 27/16

U.S. Cl. 260—326.5 9 Claims
 There is disclosed a new class of nitrogen-containing heterocyclic compounds. The new compounds have a nitrogen hetero atom in a five- or six-membered ring (the ring can be fused to one or more other rings), an amino substituent on the ring carbon alpha to the hetero nitrogen, and an oxygen (either carbonyl or hydroxyl) bonded to the ring carbon gamma to the hetero nitrogen. The new compounds are exemplified by 3-hydroxy-5-amino-pyrrolidines and 4-hydroxy-2-amino-quinolines (or the ketone tautomers thereof). The new compounds are produced by reacting an alpha- or a beta-aminoester with an N,N-disubstituted-1-amino-1-alkyne or an N,N,N',N'-tetrasubstituted-1,1-diamino-1-alkene. This process for producing the new compounds is also novel. The compounds are useful as hydrogen halide acceptors and catalysts.

3,577,434
N-ARYL - α - (HYDROXYMETHYLENEIMINO)- α' -OXO-CYCLOPOLYMETHYLENEAMINE AND RELATED COMPOUNDS AND A METHOD FOR THEIR PREPARATION

Stanley C. Bell, Penn Valley, and Peter H. L. Wei, Upper Darby, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed June 10, 1968, Ser. No. 735,524

Int. Cl. C07d 27/08

U.S. Cl. 260—326.5 10 Claims
 The disclosure is directed to N-aryl - α - (hydroxymethyleneimino) - α' - oxocyclopolymethylenamines, N-aryl - α - (methyleneimino) - β - alkanoyl - α' - oxocyclopolymethylenamines, their substituents, and a method for their preparation. The compounds have central nervous system activity as depressants. That is, they produce a calming effect in the host.

3,577,435
PROCESS FOR THE PREPARATION OF 3-ARYL-2-IMINO-3-INDOLINOLS AND RELATED COMPOUNDS

Stanley C. Bell, Narberth, and Carl Gochman, Philadelphia, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 694,066, Dec. 28, 1967. This application Aug. 14, 1968, Ser. No. 752,488

Int. Cl. C07d 27/38

U.S. Cl. 260—326.11 9 Claims
 A new process is disclosed reacting a 2-benzoyl acyl-anilide with ionic cyanides to form new 3-aryl-2-imino-3-indolinols and 2-amino-3-aryl-3H-indol-3-ols. These products may be further reacted to form a number of new derivatives which have pharmacological activity as central nervous system depressants.

ERRATUM

For Class 260—328 see:
 Patent No. 3,577,558

3,577,436
2-SUBSTITUTED-CYCLOPENTA[β]THIANAPHTHENE-3-ONES

John T. Suh, Mequon, Wis., assignor to Colgate-Palmolive Company, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 599,698, Dec. 7, 1966. This application Nov. 25, 1969, Ser. No. 879,904

Int. Cl. A61k 27/00; C07d 63/22

U.S. Cl. 260—330.5 6 Claims
 The compounds are 2-substituted-cyclopenta[β]thianaphthene-3-ones useful as tranquilizing agents. A compound disclosed is 1-H-2(dimethylaminomethyl)cyclopenta[β]thianaphthene-3-one.

3,577,437
EPOXY RESINS FROM ALKYLATED PHENOL NOVOLAC RESINS

John R. Le Blanc, Wilbraham, Mass., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Jan. 6, 1969, Ser. No. 789,346

Int. Cl. C08g 5/08, 30/06

U.S. Cl. 260—33.6 14 Claims
 Improved epoxy novolac resins produced by first reacting epichlorohydrin with an alkylated phenol aldehyde novolac resin wherein said alkylate is a specific C₈ through C₁₃ mixture of carbocyclic compounds, and then thereafter dehydrohalogenating the resulting product.

3,577,438
METHOD OF PRODUCING OXETANE ESTERS

Bruce Allen Melaas, Corpus Christi, Tex., assignor to Celanese Corporation

No Drawing. Original application Oct. 31, 1963, Ser. No. 320,557, now Patent No. 3,328,427, dated June 27, 1967. Divided and this application Mar. 13, 1967, Ser. No. 635,936

Int. Cl. C07d 3/00

U.S. Cl. 260—333 1 Claim
 Disclosed herein are methods for producing bicyclic ortho esters and their isomers, oxetane esters. Bicyclic ortho esters are prepared by direct esterification of trimethylolalkanes with certain monocarboxylic acids. The bicyclic ortho ester can be converted to the oxetane isomer by heating at a temperature of from 275° C. to 525° C. in the presence of an alumina isomerization catalyst.

3,577,439
3-(1,8-DIMETHOXY-4-METHYL-2-NAPHTHYL)-4,6-DIALKOXY-5-SUBSTITUTED PHTHALIDES

Jerry Robert Daniel McCormick, Spring Valley, and Nancy Hazlett Arnold, Pearl River, N.Y., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Aug. 19, 1969, Ser. No. 851,463

Int. Cl. C07d 5/38

U.S. Cl. 260—343.3 10 Claims
 This disclosure describes 3-(1,8-dimethoxy-4-methyl-2-naphthyl)-4,6-dialkoxy-5-substituted phthalides useful as intermediates for the preparation of 6-methyl-1,3,10,11,12-pentahydroxynaphthacene-2-carboxamide.

3,577,440
1-SUBSTITUTED-3-AMIDO-PYRROLIDINES

Carl Dalton Lunsford and Grover Cleveland Helsley, Richmond, Va., assignors to A. H. Robins Company, Incorporated, Richmond, Va.

No Drawing. Continuation-in-part of abandoned application Ser. No. 786,420, Dec. 23, 1968. This application Nov. 7, 1969, Ser. No. 874,986

Int. Cl. C07d 27/04

U.S. Cl. 260—326.3 15 Claims
 1-substituted-3-amidopyrrolidines useful as analgesics and anti-depressants are disclosed. The compounds are prepared by acylation of 1-substituted-3-aminopyrrolidines.

3,577,441
NITRO SUBSTITUTED BENZOFURANS

Daniel Kaminsky, East Paterson, Robert I. Meltzer, Rockaway, and John Shavel, Jr., Mendham, N.J., assignors to Warner-Lambert Pharmaceutical Company, Morris Plains, N.J.

No Drawing. Filed Mar. 7, 1967, Ser. No. 621,156

Int. Cl. C07d 5/42, 5/44

U.S. Cl. 260—346.2 3 Claims
 A novel method for the production of substituted benzofurans by reacting an activated halo compound with an oxime in the presence of a suitable base to obtain an oxime ether. The oxime ether is then treated to yield the benzofuran nucleus.

3,577,442
1-(DICARBOXYPHENYL)-INDANE DICARBOXYLIC ACID DIANHYDRIDE

Howard V. Holler, Oakland, Calif., assignor to Shell Oil Company, New York, N.Y.

No Drawing. Filed Nov. 12, 1968, Ser. No. 776,000

Int. Cl. C07c 63/48, 63/02

U.S. Cl. 260—346.3 2 Claims
 The novel compounds 1-(3',4'-dicarboxyphenyl)-1,3,3-trimethyl-5,6 and 6,7-indane dicarboxylic dianhydrides, useful as curing agents for epoxy resins, are prepared by the dehydration of the corresponding novel tetracarboxylic acids. The acids are formed by oxidation of the isomeric dimers of 1,2-dimethyl-4-isopropenylbenzene.

3,577,443
SEPARATION OF OLEFINS FROM EPOXIDES

Thomas A. Washall, Wilmington, Del., and Sidney Blittman, Philadelphia, Pa., assignors to Atlantic Richfield Company, New York, N.Y.

No Drawing. Filed Nov. 12, 1968, Ser. No. 775,149

Int. Cl. C07d 1/12

U.S. Cl. 260—348 9 Claims
 C₆-C₁₈ olefins are separated from C₆-C₁₈ epoxides in mixtures wherein the boiling range of the epoxides overlaps the boiling range of the olefins utilizing a cyclic silica gel adsorption process.


3,577,444
SUBSTITUTED ANTHRAQUINONES

Nicholas J. Clecak, San Jose, and Robert J. Cox, Los Gatos, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

No Drawing. Filed Jan. 8, 1969, Ser. No. 789,928

Int. Cl. C07c 119/10

U.S. Cl. 260—378 3 Claims
 Anthraquinones having at the 2 and the 6 positions substituents selected from the group consisting of



wherein R is lower alkyl. The compounds are useful as dichroic photoconductors and as photosensitizers for photoconductive polymers such as polyvinylcarbazole.

3,577,445
19-NORSTEROIDAL 3-CHLORO-3,5-DIENES

Donald W. Oliver, West Chester, and Gerhard R. Wendt, Havertown, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed Dec. 23, 1968, Ser. No. 786,374

Int. Cl. C07c 169/08

U.S. Cl. 260—397.5 1 Claim
 Novel 19-norsteroidal 3-chloro-3,5-dienes, particularly, 3-chloro-13-ethyl-17 α -ethynyl (or chloroethynyl)gon-3,5-dien-17-ols (I) are provided by chloro/enolizing the corresponding gon-4-en-3-ones (II) with a reagent such as oxalyl chloride. Compounds I are pharmacologically active as bronchodilators and biocidally-active, as bactericides.

3,577,446

PHOSPHATIDYLALKANOLAMINE DERIVATIVES
Sumanas Rakhit, Dollard des Ormeaux, Quebec, Canada, assignor to American Home Products Corporation, New York, N.Y.No Drawing. Filed Sept. 9, 1968, Ser. No. 758,587
Int. Cl. A23j 7/00

U.S. Cl. 260—403

1 Claim

There are disclosed herein phosphatidylalkanolamines in which the alkanolamine is 2-hydroxyethyl-, 2- or 3-hydroxypropyl-, or 3-hydroxybutylamine and the acyl groups contain from 18–20 carbon atoms and three or more double bonds. The compounds have anti-hypertensive properties, and methods for their preparation and use are also disclosed.

3,577,447


ALKANOYL DERIVATIVES OF FLUORINATED AMIDES

Richard F. Sweeney, Randolph Township, and Alson K. Price, Morris Township, Morris County, N.J., assignors to Allied Chemical Corporation, New York, N.Y.
No Drawing. Filed Aug. 1, 1968, Ser. No. 749,316
Int. Cl. C09f 7/00

U.S. Cl. 260—404.5

18 Claims

Alkanoyl derivatives of fluorinated amides useful as oil-repellency agents have the structural formula



wherein x and y are integers from 2 to 6 and 1 to 4, respectively; wherein R_f is a perfluoroalkyl or a fluorinated isoalkoxyalkyl radical; Z is H, alkyl, hydroxyalkyl, a fluorinated acyl radical R_fCO- wherein R_f is as described above, or a hydrocarbon acyl radical; Z' is H, alkyl, hydroxyalkyl, a fluorinated acyl radical R_fCO- wherein R_f is as described above, a hydrocarbon acyl radical or a radical of the formula $-C_xH_{2x}NHZ$ wherein x and Z are as described above, there being at least one fluorinated acyl radical R_fCO- and at least one hydrocarbon acyl radical in the molecule represented by Z and/or Z'.

ERRATUM

For Class 260—410.6 see:
Patent No. 3,577,559

3,577,448


BIS(CYCLOPENTADIENYL) COMPOUNDS OF VANADIUM

John F. Deffner, Glenshaw, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
No Drawing. Filed Dec. 26, 1967, Ser. No. 693,057
Int. Cl. C07j 9/00; C08g 7/04; C06d 5/00

U.S. Cl. 260—429

14 Claims

β -Diketonebis(cyclopentadienyl)vanadium nitrates and perchlorates and β -diketonobis(C_1-C_4 alkylcyclopentadienyl)vanadium nitrates and perchlorates are disclosed as new compounds useful in modifying the polymerization of an olefin such as styrene. Examples show that polymerization of styrene is accelerated by acetylacetonobis(cyclopentadienyl)vanadium nitrate; acetylacetonobis(methylcyclopentadienyl)vanadium perchlorate; 6-methyl-2,4-heptanedionobis(methylcyclopentadienyl)vanadium nitrate; and 1,3-diphenyl-1,3-propanedionobis(cyclopentadienyl)vanadium perchlorate. Polymerization of styrene is inhibited by 3,5-heptanedionobis(cyclopentadienyl)vanadium perchlorate.



3,577,449

PROCESS FOR THE PREPARATION OF A COMBUSTION ADDITIVE

Charles I. Ashmore, Manassas, Va., assignor to Thiokol Chemical Corporation, Bristol, Pa.

No Drawing. Filed Jan. 7, 1969, Ser. No. 789,623
Int. Cl. C07j 15/02

U.S. Cl. 260—439

2 Claims

A process for the preparation of 1,3-diferrocenyl-1-butene which comprises the mixing and reacting under the application of heat 1-ferrocenylethanol with acetic acid.

3,577,450

PROCESS FOR PREPARING METHYLENE BIS-(ALUMINUM DIHALIDES)


Morris R. Ort, Seabrook, Tex., and Edward H. Mottus, Ballwin, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Dec. 23, 1968, Ser. No. 786,449
Int. Cl. C07f 5/06

U.S. Cl. 260—448

3 Claims

Aluminum, a methylene dihalide and the corresponding halogen are reacted to form a methylene bis-(aluminum dihalide) and there may be some by-product formed, which will contain an aluminum atom having only a single halogen atom attached. For example, when chlorine, methylene dichloride and aluminum are reacted, the following compounds are formed:



It is preferred that the halogen and aluminum be reacted in a ratio of about 1:1 on a gram-atom basis for optimum yields of the bis-aluminum compound, and it is preferred to use high purity aluminum, that all reactants be substantially moisture-free and the reaction be carried out in an inert atmosphere. It is preferred to carry the reaction out in the dark to inhibit the halogenation of the methylene dihalide, especially chlorination.

3,577,451

SULFAMIDE DERIVATIVES

Engelbert Kühle, Bergisch-Gladbach, Erich Klauke, Cologne-Flittard, Paul-Ernst Frohberger, Burscheid, Bezirk, Düsseldorf, and Hans Scheinpflug, Leverkusen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Filed Jan. 20, 1967, Ser. No. 610,500
Claims priority, application Germany, Feb. 17, 1966, F 48,451

Int. Cl. C07c 143/00

U.S. Cl. 260—453

7 Claims

The disclosure covers broadly N,N'-di(alkyl and/or alkenyl) - [N - mono(fluorodichloromethylmercapto) or N,N' - di(fluorodichloromethylmercapto)] - sulfamides which possess fungicidal properties and which may be prepared by conventional procedures.

3,577,452

ORGANIC ESTERS OF BIVALENT SULFUR

Quentin E. Thompson, Belleville, Ill., assignor to Monsanto Company, St. Louis, Mo.


No Drawing. Original application Dec. 28, 1964, Ser. No. 421,672, now Patent No. 3,357,993, dated Dec. 12, 1967. Divided and this application Aug. 10, 1967, Ser. No. 668,734

Int. Cl. C07c 145/00

U.S. Cl. 260—456

5 Claims

Compounds represented by the structure:



3,577,456

PROCESS FOR THE MANUFACTURE OF AQUEOUS ALKALI PARAFFIN SULPHONATE SOLUTIONS CONTAINING SMALL AMOUNTS OF ALKALI SULFATE

Hans-Jerg Kleiner, Bad Soden, Taunus, and Karl Rehn, Hofheim, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Filed Feb. 16, 1968, Ser. No. 705,904
Int. Cl. C07c 143/02, 139/14; B01f 17/02

U.S. Cl. 260—513

6 Claims

An aqueous solution of alkali paraffin sulphonates having a low content of alkali sulphate is obtained from sulphoxidation products by separating the main part of the hydrotropically dissolved paraffin by addition of a low molecular alcohol, neutralizing the aqueous-alcoholic solution with an alkali and separating the precipitated alkali sulphate.

3,577,453

TRIFLUOROMETHYL PHENYL-N-(HALOPHENYL)-CARBAMATES AND PESTICIDAL PREPARATIONS CONTAINING SAME

Otto Rohr, Therwil, and Hans Rudolf Hitz, Muttens, Switzerland, assignors to Ciba Limited, Basel, Switzerland

No Drawing. Continuation-in-part of application Ser. No. 351,234, Mar. 11, 1964. This application June 16, 1967, Ser. No. 646,449


Claims priority, application Switzerland, Mar. 15, 1963, 3,294/63

Int. Cl. C07c 125/06; A01n 9/20

U.S. Cl. 260—471

3 Claims

Compounds are provided of the formula



wherein R_1 represents hydrogen or halogen, alkyl with 1 to 4 carbon atoms, $-NO_2$, $-CF_3$ or $-CN$; R_2 represents hydrogen or halogen; R_3 represents alkyl containing 1 to 4 carbon atoms, $-NO_2$, $-CF_3$ or $-CN$, and R_4 represents halogen and $n=1$ or 2. The compounds of this invention are especially useful as pesticides for controlling bacteria and fungi.

3,577,454

PROCESS FOR CRYSTALLIZING BIS(β -HYDROXYETHYL)TEREPHTHALATE

Max H. Keck, Cuyahoga Falls, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
No Drawing. Filed July 1, 1968, Ser. No. 741,312

Int. Cl. C07c 69/82

U.S. Cl. 260—475

4 Claims

A process for purifying bis(β -hydroxyethyl)terephthalate by crystallization in which crystal modifying agents are added to solutions of the ester to induce formation of crystals of a size and shape that permits their recovery from the solution in pure state.

3,577,455

t-BUTYL- α -METHYL- γ -NITRO VALERATE

Robert E. Jones, North Muskegon, Mich., and Harold Reynolds, Kankakee, Ill., assignors to Merck & Co., Inc., Rahway, N.J.

No Drawing. Filed Feb. 10, 1966, Ser. No. 526,369

Int. Cl. C07c 69/24, 69/66, 103/08

U.S. Cl. 260—478

1 Claim

t-Butyl- α -methyl- γ -nitro valerate useful as an intermediate in the preparation of a levulinic acid derivative which is useful in the preparation of non-steroidal anti-inflammatory agents.

3,577,459

N-ALKYL AND N,N-DIALKYL ALKANESULFONAMIDE BIS(ALKYLIMINES) AND N-ALKYL AND N,N-DIALKYL ALKYLIMINES AND PROCESSES FOR PREPARING SAME

Robert G. Laughlin, Springfield Township, Hamilton County, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed May 20, 1968, Ser. No. 730,637
Int. Cl. C01c 145/00

U.S. Cl. 260—551

17 Claims


Novel N-alkyl and N,N-dialkyl alkanesulfonamide bis(alkylimine) and N-alkyl and N,N-dialkyl alkanesulfonamide alkylimine compounds and novel processes for their preparation. These compounds have utility as extreme pressure lubricant additives, as anti-microbial agents and as accelerators in the synthesis of rubber.

3,577,460 SYNTHESIS OF PERFLUOROISOPROPYL- IDENIMINE


Robert A. Falk, Rockaway, N.J., assignor to Thiokol Chemical Corporation, Bristol, Pa.
Filed Nov. 7, 1968, Ser. No. 774,161
Int. Cl. C07c 119/00

U.S. Cl. 260—566 6 Claims

The compound perfluoroisopropylidenimine,



is prepared by a novel method comprising treating




with N_2F_4 to form $(\text{CF}_3)_2\text{CFNF}_2$ and defluorinating the latter product with ferrocene to form $(\text{CF}_3)_2\text{C}=\text{NF}$. The compound $(\text{CF}_3)_2\text{C}=\text{NF}$ is useful as a monomer, which form copolymers with tetrafluoroethylene useful in preparing extruded and molded plastic bodies.

3,577,461 α -PROPARGYLAMINO-PROPIO-PHENONES AND THE SALTS THEREOF

Edward John Warawa, 2575 N. 37th St., and John Hans Biel (522 Green Bay Road, Lake Bluff, Ill.), both of Milwaukee, Wis. 53210
No Drawing. Filed Oct. 10, 1968, Ser. No. 766,626
Int. Cl. C07c 97/10

U.S. Cl. 260—570.5 9 Claims

α -Propargylaminopropiophenone derivatives of the formula



wherein R^1 is (lower)alkyl, (lower)alkenyl, (lower)alkynyl, benzyl, cyclopropyl or cyclopropylmethyl and R^2 is hydrogen, (lower)alkyl, phenyl or benzyl; and the pharmaceutically acceptable nontoxic salts thereof exhibit central nervous system stimulant activity and anorexic activity and are useful as central nervous system stimulants and to inhibit appetite in mammals.

3,577,462 N-ARYLALKYL- β -HYDROXY- β -PHENYL-ETHYL- AMINES AND THE SALTS THEREOF

William F. Bruce, Havertown, Pa., assignor to American Home Products Corporation, New York, N.Y.
No Drawing. Continuation-in-part of application Ser. No. 502,370, Oct. 22, 1965. This application Aug. 8, 1968, Ser. No. 751,028

Int. Cl. C07c 91/22

U.S. Cl. 260—570.6 6 Claims

Diaralkylamines are prepared by prolonged reaction of styrene oxide with dialkylaminoalkyl, hydroxyalkyl, halobenzyl, and heteroalkyl amines. The compounds show central nervous system depressant activity.

3,577,463 SYNTHESIS OF STEROIDS

Patrick A. Diassi, Westfield, N.J., assignor to E. R. Squibb & Sons, Inc., New York, N.Y.
No Drawing. Application June 11, 1968, Ser. No. 736,028, now Patent No. 3,449,378, dated June 10, 1969, which is a continuation-in-part of application Ser. No. 370,114, May 25, 1964. Divided and this application Jan. 16, 1969, Ser. No. 791,794

Int. Cl. C07c 49/00

U.S. Cl. 260—586 3 Claims

This invention relates to and has as its object the provision of new physiologically active steroids, processes

for their production and novel intermediates useful in the preparation thereof.

3,577,464 POLYENE COMPOUNDS AS COLORING AGENTS

Hugo Gutmann, Reinach, Ulrich Manz, Basel, and Ulrich Schwieter, Reinach, Switzerland, assignors to Hoffmann-La Roche Inc., Nutley, N.J.
No Drawing. Filed Jan. 11, 1967, Ser. No. 608,487
Claims priority, application Switzerland, Jan. 21, 1966, 856/66

Int. Cl. C07c 45/00

U.S. Cl. 260—601 4 Claims

Conjugated polyene dialdehyde compounds having 14–44 carbon atoms and mixtures thereof which are useful as coloring agents for foodstuffs, pharmaceutical preparations and cosmetic preparations and a method for preparing these dialdehydes including various intermediates in this method. This method is carried out by reacting a phosphonium salt of a conjugated aliphatic olefine having a terminal aldehyde radical with a conjugated aliphatic olefine having a terminal acetal linkage radical and terminal aldehyde radical and thereafter hydrolyzing the reaction product to produce the dialdehyde. This dialdehyde may be further chain lengthened by reacting this dialdehyde with a phosphonium salt of a conjugated olefine having a terminal aldehyde radical, or by reacting with a vinyl ether or propenyl ether.


3,577,465 TERMINALLY UNSATURATED FLUOROOLEFINS

Louis Gene Anello, Basking Ridge, and Richard Francis Sweeney, Dover, N.J., and Morton Herbert Litt, University Heights, Cleveland, Ohio, assignors to Allied Chemical Corporation, New York, N.Y.
No Drawing. Continuation-in-part of application Ser. No. 633,359, Apr. 25, 1967. This application Apr. 12, 1968, Ser. No. 721,113

Int. Cl. C07c 43/00

U.S. Cl. 260—614 5 Claims


Terminally unsaturated polyfluoroolefinic compounds of the formula



wherein R_1 and R_2 are Cl, F, alkyl, haloalkyl, or alkylene and haloalkylene groups forming a cycloaliphatic structure, wherein A represents alkylene or haloalkylene groups, wherein $-(\text{CZ}_1\text{Z}_2-\text{CZ}_3\text{Z}_4)-$ and



wherein Z_1-Z_4 may be selected from H, F, Cl and perhalomethyl groups, wherein Z_2 and Z_4 may additionally be selected from haloalkyl groups and aralkyl groups and alkyl or haloalkyl which may be interrupted with ether linkages; and X_1-X_7 may be selected from H, F and Cl groups; are bifunctional groups derived from certain telomerizable unsaturated compounds, wherein m and n are integers of from 0 to 75, and wherein $-\text{CX}_5=\text{CX}_6\text{X}_7$ is derived from bifunctional group $-(\text{CX}_1\text{X}_2-\text{CX}_3\text{X}_4)-$ are prepared from polyfluoroaldehydes of the formula



wherein Y is H or a halogen and $\text{R}_1, \text{R}_2, \text{A}, \text{Z}_1-\text{Z}_4, \text{X}_1-\text{X}_4$, with C_4-C_5 tertiary alkyl chloride, bromide or fluoride. m and n are as defined above by methods such as dehydrohalogenation or dehalogenation of the terminal



group. These terminally unsaturated fluoro-olefinic compounds are useful as intermediates for the preparation of fluorocarbon acids of art recognized utility.

3,577,466 PRODUCTION OF ALLYLIC ETHERS

Kenzie Nozaki, El Cerrito, Calif., assignor to Shell Oil Company, New York, N.Y.

No Drawing. Filed July 30, 1968, Ser. No. 748,652

U.S. Cl. 260—614 9 Claims

Production of allylic ethers by reacting in high conversion an allylic alcohol of the formula



where R is hydrogen, methyl or hydroxymethyl and R' is hydrogen or methyl, with itself or with a nonallylic alcohol in the presence as catalyst of cupric chloride or bromide or additionally in the presence as catalyst promoter of an acidic material or an allylic halide, where the halide is chloride or bromide.

3,577,467 PROCESS FOR THE HYDROLYSIS OF LIGNIN

Irving S. Goldstein, Downers Grove, and Joseph D. Benigni, Chicago, Ill., assignors to Continental Can Company, Inc., New York, N.Y.

No Drawing. Filed May 29, 1968, Ser. No. 732,836

U.S. Cl. 260—627 5 Claims

High yields of low molecular weight phenolic substances are obtained by heating, at 250° to 380° C. for 3 to 45 minutes, a slurry of water and a lignin material separated from the liquor resulting from the alkaline pulping of lignocellulose, and then recovering the phenolic materials from the reaction mixture.

3,577,468 MONOHALOGENATION OF ALKYL- ADAMANTANE HYDROCARBONS

Abraham Schneider, Overbrook Hills, Pa., assignor to Sun Oil Company, Philadelphia, Pa.

No Drawing. Filed Mar. 26, 1968, Ser. No. 715,958

U.S. Cl. 260—648 18 Claims

$\text{C}_{11}-\text{C}_{20}$ alkyladamantane hydrocarbons are monochlorinated, monobrominated or monofluorinated at an unsubstituted bridgehead position by reacting the same at -30° C. to 10° C. with a C_4-C_5 tertiary alkyl chloride, bromide or fluoride, using as catalyst 90–100% sulfuric acid or 90–100% hydrofluoric acid. The corresponding 1-halo-alkyladamantane is obtained with little if any other reaction products.


3,577,469 PREPARATION OF 9-HALODECAHYDRO- NAPHTHALENE

Abraham Schneider, Overbrook Hills, Pa., assignor to Sun Oil Company, Philadelphia, Pa.

Filed May 2, 1968, Ser. No. 726,132

U.S. Cl. 260—648 15 Claims

Cis-decahydronaphthalene is converted to trans-9-chlorodecahydronaphthalene, or to the corresponding bromine or fluorine analogue, in a highly selective reaction



reactants with 90–100% H_2SO_4 at -20° C. to 25° C., preferably at -10° C. to 10° C.

3,577,470 PROCESS FOR PREPARING 1,3,5-HALOXYLENE

John D. Bacha, Monroeville, and Charles M. Selwitz, Pittsbrgh, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

No Drawing. Filed Dec. 20, 1968, Ser. No. 785,798

U.S. Cl. 260—650 4 Claims

A process for isomerizing a haloxylylene to a 1,3,5-haloxylylene which involves contacting such haloxylylene charge with hydrogen fluoride and boron trifluoride, preferably in the presence of ortho-halotoluene.

3,577,471 HALOGEN INTERCHANGE PROCESS

John G. McNulty and William L. Walsh, Glenshaw, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

No Drawing. Filed Feb. 1, 1968, Ser. No. 702,214

U.S. Cl. 260—656 5 Claims

Halides can be made to undergo transhalogenation in a process wherein two compounds containing different halogen substituents are contacted at elevated temperatures. By this process, organic halides, such as vinyl bromide and dibromoethane, can be directly converted to vinyl chloride by contact with a suitable halide such as hydrogen chloride. Ethylene, which is easily brominated, can thus readily be converted to vinyl chloride.

3,577,472 METHOD FOR CHLORINATING PARAFFINS

John C. Jubin, Jr., Wallingford, and Matthew L. Becker, Philadelphia, Pa., assignors to Atlantic Richfield Company, Philadelphia, Pa.

No Drawing. Filed May 28, 1968, Ser. No. 732,507

U.S. Cl. 260—660 7 Claims

Paraffins are chlorinated to avoid production of dark colored impurities and to maintain maximum selectivity for the production of monochloroparaffins by admixing the chlorine with a portion of the cold paraffin charge and thereafter combining this cold chlorine-containing stream with the remainder of the charge paraffin which has been heated to a temperature above the desired reaction initiation temperature.

3,577,473

METHOD FOR PRODUCING 5-ISOPROPYLIDENE-2-NORBORNENE

Tsuneaki Nagase, Gohu Suzukamo, Fujio Masuko, and Yukio Yoneyoshi, Takatsuki-shi, Masami Fukao, Ibaragi-shi, and Masahiro Fujiwara, Takatsuki-shi, Japan, assignors to Sumitomo Chemical Company, Ltd., Osaka, Japan

No Drawing. Filed Oct. 4, 1968, Ser. No. 764,995
Claims priority, application Japan, Dec. 25, 1967, 42/68,966; Jan. 23, 1968, 43/3,900, 43/3,902; Jan. 24, 1968, 43/4,490

Int. Cl. C07c 5/24

U.S. Cl. 260—666

15 Claims

5-isopropylidene-2-norbornene is produced by subjecting cyclopentadiene and 2-methyl-3-butene-2-ol to Diels-Alder reaction to obtain α,α -dimethyl-5-norbornene-2-methanol (a mixture of endo-form and exo-form), dehydrating the α,α -dimethyl-5-norbornene-2-methanol to form a mixture of endo- and exo-5-isopropenyl-2-norbornene, and contacting the mixture with an alkaline catalyst.

The 5-isopropylidene-2-norbornene is useful as a monomer of a so-called ethylene-propylene terpolymer rubber, and the incorporation thereof results in a terpolymer having excellent curing characteristics.

3,577,474

CONVERSION OF C₆—C₇ CYCLOALKANES TO BENZENE AND TOLUENE

Robert L. Jacobson, Pinole, Calif., assignor to Chevron Research Company, San Francisco, Calif.

Filed Nov. 18, 1968, Ser. No. 776,533

Int. Cl. C07c 15/04

U.S. Cl. 260—668

7 Claims

High conversion of C₆—C₇ cycloalkanes to aromatics is obtained by contacting the cycloalkanes in the presence of hydrogen with a catalyst comprising 0.01 to 3 weight percent platinum and 0.01 to 5 weight percent rhenium in association with a porous inorganic oxide carrier and maintaining the conversion conditions sufficiently severe to convert at least 85 percent, and preferably 90 percent, of the cycloalkanes to aromatics and alkanes.

3,577,475

ISOMERIZATION OF C₈ ALKYL AROMATICS

Sigmund M. Csicsery, Lafayette, Calif., assignor to Chevron Research Company, San Francisco, Calif.

No Drawing. Filed Jan. 30, 1969, Ser. No. 795,359

Int. Cl. C07c 5/24, 15/08

U.S. Cl. 260—668

6 Claims

C₈ alkyl aromatic hydrocarbons are isomerized under isomerization conditions and in the presence of hydrogen with a catalyst comprising a porous solid carrier containing from 0.01 to 3 weight percent of a platinum group component and from 0.01 to 5 weight percent of a rhenium component.

3,577,476

ARYLENE AND ARLIDENE POLYMERS AND COPOLYMERS

John A. Gurney, Tarrytown, N.Y., and Luther A. R. Hall, Woodcliff Lake, N.J., assignors to Gelgy Chemical Corporation, Ardsley, N.Y.


No Drawing. Continuation-in-part of application Ser. No. 529,214, Feb. 23, 1966. This application Feb. 18, 1969, Ser. No. 800,269

Int. Cl. C07c 15/02

U.S. Cl. 260—668

15 Claims

The compounds are of the class of aromatic polymeric and copolymeric compounds of the formula:



The polymeric and copolymeric compounds relate also to hydrocarbons wherein R, R₁, n, m, x, y, B, p, and A are as defined below. These compounds are useful as color pigments for paints, fibers and motor oil, and as color pH-indicators. They are prepared by treating dihalomethyl benzene derivatives with (a) a tertiary amine and alkaline agent; or (b) an alkali metal amide in the presence of liquid ammonia; or (c) a tertiary amine and gaseous iodine. Illustrative embodiments are poly(trimethylsilylidyne) and poly(radialene).

3,577,477

PROCESS FOR CONVERTING SATURATED HYDROCARBONS TO UNSATURATED HYDROCARBONS BY OXIDATION

Pierre Boutry, Port Marly, Jean Claude Daumas, Marly-le-Roi, and Roger Montarnal, Mareil Marly, France, assignors to Institut Francais du Pétrole, des Carburants et Lubrifiants, Rueil Malmaison, Hauts-de-Seine, France

No Drawing. Filed Jan. 3, 1969, Ser. No. 788,923

Claims priority, application France, Jan. 10, 1968, 135,566

Int. Cl. C07c 11/22, 5/18, 3/28

U.S. Cl. 260—683.3

15 Claims

A process for oxidizing saturated hydrocarbons to olefins and/or dienes, without the substantial formation of oxygen-containing by-products, due to the control of the amount of oxygen used during the oxidation reaction and the selection of particular conditions for manufacturing the catalyst.

3,577,478

GRAFT POLYMER OF A VINYL MONOMER AND A POLYESTER, AND A BUTADIENE POLYMER

Donald H. Thorpe, Williamsville, N.Y., assignor to Hooker Chemical Corporation, Niagara Falls, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 544,817, Apr. 25, 1966. This application Nov. 12, 1968, Ser. No. 775,161

Int. Cl. C08f 43/08; C08g 39/10

U.S. Cl. 260—862

39 Claims

Graft copolymers are produced by reacting a polymerizable monomer with a polyester of a polycarboxylic compound and a polyhydric alcohol, wherein the polyester comprises a maximum of 5 mole percent of carboxylic and hydric components which contains aliphatic carbon-to-carbon unsaturation. Halogen-containing polyesters and phosphorus-containing polyesters are particularly useful in producing fire-retardant graft copolymers. The graft copolymers can be blended with a polymer of butadiene, such as a graft copolymer of a polymerizable monomer and polybutadiene to produce additional products. The polymer products are suitable for producing molded articles, laminates, extruded products, protective coatings, and the like, which have superior toughness, high-impact strength, fire resistance and chemical resistance.

3,577,479

ALUMINUM HALIDE ISOMERIZATION OF SATURATED HYDROCARBONS

Donald E. Jost, Media, Edward J. Janoski, Havertown, and Abraham Schneider, Philadelphia, Pa., assignors to Sun Oil Company, Philadelphia, Pa.

No Drawing. Filed Aug. 9, 1968, Ser. No. 751,360

Int. Cl. C07c 5/28

U.S. Cl. 260—683.75

8 Claims

In the isomerization of C₄—C₇ paraffins with an aluminum halide catalyst in the presence of an inert halogenated hydrocarbon solvent, it has been found that the rate

of isomerization and percentage yield is significantly increased when the solvent is present in amounts of from 10–50 volume percent based on the volume of the hydrocarbon feedstuff, and when, further, the aluminum halide catalyst is present in amounts in excess of what would be soluble in the solvent and paraffin feedstuff at the temperature employed.

3,577,480

GRAFT POLYMER OF A VINYL MONOMER AND A FIRE RETARDANT POLYESTER

Donald H. Thorpe, Williamsville, N.Y., assignor to Hooker Chemical Corporation, Niagara Falls, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 544,816, Apr. 25, 1966. This application Nov. 12, 1968, Ser. No. 775,160

Int. Cl. C08f 21/00; C09k 3/28

U.S. Cl. 260—869

34 Claims

Graft copolymers are produced by reacting a polymerizable monomer with a polyester of a polycarboxylic compound and a polyhydric alcohol, wherein the polyester comprises a maximum of 5 mole percent of carboxylic and hydric components which contains aliphatic carbon-to-carbon unsaturation. Halogen-containing polyesters and phosphorus-containing polyesters are particularly useful in producing fire-retardant graft copolymers. The graft copolymers can be blended with a polymer of butadiene, such as a graft copolymer of a polymerizable monomer and polybutadiene to produce additional useful products. The polymer products are suitable for producing molded articles, laminates, extruded products, protective coatings, and the like, which have superior toughness, high-impact strength, fire resistance and chemical resistance.

3,577,481

PHOSPHORIC ACID ESTERS

Max Schuler, Arlesheim, Switzerland, assignor to Sandoz Ltd. (also known as Sandoz AG), Basel, Switzerland

No Drawing. Continuation-in-part of application Ser. No. 715,138, Mar. 22, 1968. This application Nov. 12, 1969, Ser. No. 876,102


Claims priority, application Switzerland, Apr. 3, 1967, 4,689/67

Int. A01n 9/36; C07f 9/08

U.S. Cl. 260—942

10 Claims

Compounds of the Formula I



wherein

each of R₁ and R₂ represents a methyl or ethyl radical, each of R₃ and R₄ represents an alkyl radical with 1 to 4 carbon atoms, and

X represents a hydrogen or halogen atom,

are exemplified and their use as pest combating agents in plant cultivation is given; specific pesticidal effects tested are those against *Bruchidius obtectus*, *Ephestia* (*Anagasta*) *kuehniella*, *Aphis fabae* and *Tetranychus telarius* as well as toxicity comparison studies on rats.

3,577,482

PROCESS FOR THE PREPARATION OF THIONOPHOSPHONATES

Delbert L. Hanna, Oak Park, Ill., assignor to Velsicol Chemical Corporation, Chicago, Ill.

No Drawing. Filed May 31, 1968, Ser. No. 733,331

Int. Cl. C07f 9/40

U.S. Cl. 260—973

5 Claims

A process for preparing an O-alkyl-O-phenyl phenylthionophosphonate which comprises

(a) reacting a phenylthionophosphonoyl dihalide with an alkanol in the presence of trimethylamine and,

(b) reacting the resulting intermediate reaction mixture with a phenol in the presence of trimethylamine, and thereafter recovering the desired product.

ERRATUM

For Class 264—8 see:
Patent No. 3,577,560

3,577,483

PROCESS FOR THE PREPARATION OF PHOSPHORIC ACID ESTERS BY REACTION OF PHOSPHORUS OXYCHLORIDE WITH ALKYLENE OXIDES

Arnold Kotzschmar, Burgkirchen (Alz), Hermann Metzger, Burghausen (Salzach), and Richard Reinhard Gustav Adolf Rothe, deceased, late of Altötting, by Rudolphe Rothe, nee Roessler, heiress, Altötting, and Willy Seidel, Burgkirchen (Alz), Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Filed Aug. 9, 1967, Ser. No. 659,533
Claims priority, application Germany, Aug. 13, 1966, F 49,943, Patent 1,290,532

Int. Cl. C07f 9/08; C08f 45/58

U.S. Cl. 260—977

5 Claims

Process for the continuous preparation of phosphoric acid esters having utility as plasticizers and for imparting flame resistant properties by reaction of phosphorus oxychloride with alkylene oxides, in which a large amount of the final product is used as reaction medium. The products produced according to the process of the present invention are superior to the discontinuously prepared esters because they have an extraordinarily low acid value.

3,577,484

METHOD FOR FORMING LINES OF WEAKNESS IN THERMOPLASTIC


William P. Jacobson, Rockford, Ill., assignor to Anderson Bros. Mfg. Co., Rockford, Ill.

Filed Feb. 27, 1969, Ser. No. 802,781

Int. Cl. B29c 25/00; B29d 7/22

U.S. Cl. 264—92

9 Claims



A line of weakness is formed in a sheet of thermoplastic which has been heated to render it soft and flowable by the disclosed method of cooling the surface of the heated sheet but not at the desired line of weakness and shrinking the sheet away from said line to reduce the thickness thereof. The line of weakness may be a fold line or a tear line, both of which are utilized in the disclosed carton. A carton blank is formed by apparatus which includes opposed heating heads, opposed forming heads and a trimming station. The forming heads have grooves in their surfaces at the desired location of the lines of weakness. Mechanisms are provided for cooling the forming heads and for drawing a vacuum on the grooves.

3,577,485

METHOD FOR PREPARATION OF CARBONITRIDE NUCLEAR FUEL MATERIALS

Ronald L. Beatty, Oak Ridge, James M. Leitnaker, Kingston, and Karl J. Notz, Jr., Oak Ridge, Tenn., assignors to the United States of America as represented by the United States Atomic Energy Commission
No Drawing. Filed Feb. 3, 1969, Ser. No. 796,175
Int. Cl. G21c 21/00

U.S. Cl. 264—5

7 Claims

A rapid method for converting actinide oxide-carbon particles to actinide carbonitride is given and comprises contacting the actinide oxide-carbon particles with nitrogen in a fluidized bed furnace at elevated temperatures.


3,577,486

METHOD OF FORMING AN AIR CLEANER SEAL

Joseph B. Sebok, Dearborn Heights, Mich., assignor to Ford Motor Company, Dearborn, Mich.
Filed Sept. 20, 1968, Ser. No. 761,226
Int. Cl. B29d 27/02, 27/04

U.S. Cl. 264—45

6 Claims



Liquid curable to elastic polyvinylchloride, polybutadiene or polyurethane is dispensed into a groove near the periphery of an air cleaner cover while the cover is rotating at about one revolution per second through a finite number of revolutions. A subsequent application of heat simultaneously cures the liquid and bonds the resulting seal to the cover.

ERRATUM

For Class 264—53 see:
Patent No. 3,577,360

3,577,487

PREPARATION OF SUBMICRON SIZED ALKALINE EARTH TITANATE AND ZIRCONATE POWDERS

Moises Gali Sanchez, Severna Park, Newton Levy, Jr., Ellicott City, and Richard R. Rettew, Laurel, Md., assignors to W. R. Grace & Co., New York, N.Y.
No Drawing. Filed May 22, 1968, Ser. No. 731,306
Int. Cl. C04b 33/32; F27b 9/04

U.S. Cl. 264—56

4 Claims

Highly reactive, high purity, submicron sized alkaline earth titanates and zirconates are prepared by first blending hydroxides, nitrates, etc. and hydrogels and then passing the resulting product through a fluid energy mill.

3,577,488

MANUFACTURE OF PLASTIC TUBULAR FILM

Bernard K. Bigland, Radcliffe, Manchester, England, assignor to General Engineering Company (Radcliffe) Limited
Continuation-in-part of application Ser. No. 557,581, June 14, 1966. This application July 15, 1969, Ser. No. 841,871

Claims priority, application Great Britain, June 15, 1965, 25,190/65


Int. Cl. B29d 7/24

U.S. Cl. 264—95

6 Claims

A method of forming an extruded tube of plastic material comprising extruding the material in a semi-molten

state as a tubular film, having a wall of greater thickness than that of the finished tube, locating a first former within the tube near the extrusion point, passing the film over the face of the former in close proximity thereto, locating a second former at a point more remote from the extrusion point, passing the film over the face of the second former in close proximity thereto, directing a high velocity stream of air against the inner face of the film from below the first former and creating a further high velocity stream of air against the inner face of the film and between it and the second former, extracting air from



the space between the two formers to maintain the air pressure in said space between the formers at or below atmospheric pressure, said streams of air moving at a velocity sufficient to prevent actual contact between the film and the formers, and arranging that the freeze zone of the film is in the region of maximum diameter of the second former and preferably between the position of maximum diameter and the downstream end thereof. The diameter of the tube being extruded can be varied by varying the diameter of the second former. In order to obtain still greater speeds of extrusion external cooling can be applied.

3,577,489

METHOD FOR AGGLOMERATING SUSPENDED PARTICLES

Christian Rosenthal, Munich, Germany, assignor to Chemische Werke Munich Otto Barlocher G.m.b.H., Munich, Germany

No Drawing. Continuation-in-part of application Ser. No. 649,088, June 26, 1967. This application Apr. 26, 1968, Ser. No. 725,271

Claims priority, application Germany, June 28, 1966, C 39,466; July 1, 1966, C 39,506; Sept. 16, 1966, C 40,148; Mar. 9, 1967, C 41,719; Apr. 28, 1967, C 42,182

Int. Cl. B01j 2/10

U.S. Cl. 264—117

13 Claims

A plurality of finely subdivided solid particles is converted into a mass of distinct agglomerated bodies by suspending the solid subdivided particles in water heated to at least 80° C. The particles must be such that water is inert thereto and which are at most slightly soluble in water. The granulating agent is a synthetic organic plastic which is dissolved in a liquid organic solvent at at least 80° C. The granulating solution is then added to the suspension and the thus-formed mixture is maintained, preferably under stirring, at an elevated temperature below 100° C. and sufficiently high to form granules of the finely subdivided particles and the granulating agent so

that a plurality of agglomerated bodies each comprising a plurality of the finely subdivided particles adhered to each other by the granulating agent will be obtained.

3,577,490

EFFERVESCENT TABLET AND PROCESS FOR MAKING SAME

Thomas Laurence Welsh, Donald Leroy Peterson, Blasey Thomas Palermo, and George Carr Hoss, Elkhart, Ind., assignors to Miles Laboratories, Inc., Elkhart, Ind.
No Drawing. Original application Oct. 10, 1967, Ser. No. 671,948, now Patent No. 3,518,343, dated June 30, 1970. Divided and this application Dec. 29, 1969, Ser. No. 1,923

Int. Cl. A61j 3/10; A61k 7/16

U.S. Cl. 264—120

9 Claims

An effervescent tablet is produced by preparing a powdered tabletable composition comprising an effervescent couple, an antimicrobial substance, a tableting lubricant, and preferably, a flavoring, sweetening and/or coloring agent, mixing the same to achieve uniformity, and compressing into coherent tablet form. The lubricant can be fumaric acid or particles of a liquid lubricant coated with an oil-insoluble film-forming substance. Upon dissolution, a solution having antimicrobial properties is produced. The solution is useful for cleaning solid surfaces, particularly, the teeth and periodontal gum areas of the oral cavity.

3,577,491

TABLETING

Peter Henry Cox, Oss, Netherlands, assignor to Miles Laboratories Incorporated, Elkhart, Ind.
No Drawing. Original application Jan. 2, 1968, Ser. No. 694,890, now Patent No. 3,518,346, dated June 30, 1970. Divided and this application Dec. 29, 1969, Ser. No. 1,924

Int. Cl. A61j 3/10; A61k 7/16

U.S. Cl. 264—120

7 Claims

An improvement in the process of compressing powdered tabletable compositions is gained by mixing fumaric acid with said composition prior to compression. The fumaric acid acts as a surface lubricant and as an internal compression lubricant for said tabletable compositions. The powdered tabletable compositions lubricated with fumaric acid can be those intended for internal employment such as for alkalizing of the stomach or intended for external use such as for general cleaning of solid surfaces.

3,577,492

TABLETING LUBRICANT

Thomas Laurence Welsh and George Ronald Tomalch, Elkhart, Ind., assignors to Miles Laboratories, Inc., Elkhart, Ind.
No Drawing. Original application Oct. 2, 1967, Ser. No. 672,004, now Patent No. 3,518,344, dated June 30, 1970. Divided and this application Dec. 29, 1969, Ser. No. 1,944

Int. Cl. A61j 3/10; A61k 7/16

U.S. Cl. 264—120

6 Claim

An improvement in the process of compressing powdered tabletable materials is gained by mixing with said materials prior to tableting, a lubricant comprising, in combination, a siloxane polymer and dry-mixable particles of a lubricating oil coated with an oil-insoluble film-forming substance. The lubricant acts as both a punch face lubricant and as a diwall lubricant for said tabletable materials. The powdered tabletable materials lubricated with the above lubricant can be those intended for general cleaning of solid surfaces or those intended for therapeutic employments.

3,577,493

METHOD OF FABRICATING A GLASS FABRIC LAMINATE MATERIAL

Henry J. Lee, Cherry Hill, N.J., assignor to the United States of America as represented by the Secretary of the Navy
No Drawing. Filed Oct. 30, 1968, Ser. No. 772,012
Int. Cl. B29g 1/00, 5/00

U.S. Cl. 264—137

2 Claims

The present invention relates to a novel and improved method of synthesizing a polyurethane polymer which has outstanding chemical and mechanical properties and which is particularly useful as an adhesive resin in a glass cloth reinforced laminate material. The improved process utilizes the ability of aromatic polyisocyanates to dimerize and trimerize and react with a short chain aliphatic glycol under carefully controlled conditions of heat to form a unique prepolymer that is subsequently cured at a specified temperature.

3,577,494

METHOD FOR THE PREPARATION OF EXTRUDABLE SYNTHETIC RESINOUS MATERIALS


Douglas S. Chisholm and James K. Rieke, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Continuation-in-part of application Ser. No. 796,937, Oct. 31, 1968, which is a continuation-in-part of application Ser. No. 677,440, Oct. 23, 1967. This application Sept. 5, 1969, Ser. No. 857,298

Int. Cl. B28b 3/22

U.S. Cl. 264—143

10 Claims



Improved feed of granular synthetic resinous material in screw extruders is obtained and fiber breakage is significantly reduced when chopped glass fiber and extrudable resin are mixed in an extruder having an increasing working volume screw. The product has significantly improved impact strength.

3,577,495

EGG CARTON FORMING METHOD


David L. Pearl, 55 Enterprise Blvd. SW., Atlanta, Ga. 30336; Beverly P. Head, Jr., 3528 Victoria Road, Birmingham, Ala. 35223; and John G. Waller, 1429 E. Cambridge Ave., College Park, Ga. 30337

Filed July 28, 1969, Ser. No. 845,462

Int. Cl. B26d 1/56; B29c 17/10

U.S. Cl. 264—153

7 Claims




An egg carton forming method wherein a sheet of polystyrene is passed through a predetermined path where the

sheet is heated at a first station. A plurality of egg carton impressions each complete with egg tray, lid and locking flap are formed across the width of the sheet at a second station. Latching holes are punched in the lid impressions at a third station, and the egg carton impressions are cut away from the sheet of material at a fourth station.

3,577,496

METHOD OF MAKING A SEALED ELECTRICAL CONNECTING DEVICE

Norman Edwin Hoffman, Harrisburg, Pa., assignor to AMP Incorporated, Harrisburg, Pa.
Original application Sept. 23, 1965, Ser. No. 489,697, now Patent No. 3,409,864, dated Nov. 5, 1968. Divided and this application Mar. 21, 1968, Ser. No. 714,829
Int. Cl. B29c 27/16, 27/20
U.S. Cl. 264—156 1 Claim




A sealed assembly is provided and comprises a member formed of thermoplastic material having memory characteristics. An opening extends through the member for receiving an electrical contact, which contact is sealed in place by internal forces within the thermoplastic member. Additional means are provided for surrounding the member and for providing a seal therebetween due to thermal expansion of the member.

3,577,497

METHOD FOR HEAT-SETTING BIAXIALLY STRETCHED FILMS OF THERMOPLASTIC MATERIALS

Tomoyuki Matsugu, Ryota Notomi, and Teruchika Kanoh, Shizuoka-ken, Japan, assignors to Kohjin Company Limited, Tokyo, Japan
Filed Apr. 28, 1969, Ser. No. 819,549
Int. Cl. B29c 25/00
U.S. Cl. 264—159 6 Claims



Simultaneously heat-setting of a pair of flat, biaxially oriented films formed of thermoplastic material. Maintaining the films in spaced apart relationship during the heat-setting procedure.


3,577,498

METHOD OF PRODUCING CRIMPED POLYPROPYLENE FIBERS

Tatsuki Matsuo, Shosuke Nanri, and Ryunosuke Masuda, Otsu, Hikoyuki Uchihashi, Moriguchi, and Katsuya Ishitobi, Otsu, Japan, assignors to Toyo Boseki Kabushiki Kaisha, Osaka, Japan
Continuation-in-part of abandoned application Ser. No. 678,616, Oct. 27, 1967. This application Oct. 25, 1968, Ser. No. 770,776
Claims priority, application Japan, Nov. 1, 1966, 41/72,222
Int. Cl. D01d 5/22
U.S. Cl. 264—168 10 Claims

Bulky crimped polypropylene fibers, the coil crimps of which have a coil diameter of e.g. less than 0.7 mm., and

are of good reproducibility, are made by cooling or quenching polypropylene filament, immediately after coming out of the spinning orifice, asymmetrically in the cross-sectional direction of the filament so as to create a cross-sectional anisotropy in the filament structure, and then stretching the filament and heat treating the same in a relaxed state. Use is made of a spinnerette in which the




minimum distance between the orifices is more than 4.0 mm. Cooling is effected by cooling gas under particular conditions of velocity and distance between spinnerette face and gas. The fiber is stretched 2.5 or more times its length at a particular temperature so that the fine voids are distributed asymmetrically in the cross section of the fiber.

3,577,499

METHOD FOR PREPARING PERMANENTLY OPAQUE FIBERS

John P. Knudsen, Raleigh, N.C., assignor to Monsanto Company, St. Louis, Mo.
Filed Sept. 5, 1967, Ser. No. 665,504
Int. Cl. D01f 7/00
U.S. Cl. 264—182 9 Claims



Smooth delustered acrylic fibers having a highly porous internal microvoid structure which is permanently sealed and not collapsed by drying have been prepared by coagulation of solution spun acrylic polymers in a coagulation bath containing volatile fluorinated aliphatic compounds dissolved therein and thereafter heating the fiber.

3,577,500

PROCESS FOR THE PRODUCTION OF POLYAMIDE FIBRES HAVING HIGH LINEAR STRENGTH AND KNOT STRENGTH

Armin Kohler, Bela von Falkai, Klaus Offermann, and Alfred Reichle, Dormagen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany
No Drawing. Filed May 22, 1969, Ser. No. 827,018
Claims priority, application Germany, June 1, 1968, P 17 60 539.9
Int. Cl. D02j 1/22
U.S. Cl. 264—210 2 Claims

Process for the production of polyamide fibres having linear strength and knot strength by stretching polyamide monofilaments at temperatures of 25 to 35° C. below the temperature level of the crystallite melting maximum at a ratio of 1:4.5 to 1:6.5.

3,577,501

MOLD DOPE AND PROCESS OF USING

Monte H. York, Akron, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
No Drawing. Continuation of application Ser. No. 752,428, July 2, 1968, which is a continuation of application Ser. No. 395,915, Sept. 11, 1964. This application Dec. 4, 1969, Ser. No. 878,965
Int. Cl. B29c 1/04; B29d 27/04
U.S. Cl. 264—213 10 Claims

This invention relates to a method of molding polyurethane foam materials utilizing an improved mold release agent comprising an alpha olefin having from 2 to about 4 carbon atoms and a melting point of about 100 to 250° F. in a carrier and containing .3 to about 5 parts per 100 of a substituted phenylene diamine as an antioxidant.

3,577,502

PROCESS FOR ANNEALING SUBSTANTIALLY UNSTRETCHED POLYLACTONE ARTICLES


Jan Selman and Hendricus A. Oosterhof, Amsterdam, Netherlands, assignors to Shell Oil Company, New York, N.Y.
No Drawing. Filed Feb. 9, 1968, Ser. No. 704,269
Claims priority, application Great Britain, Feb. 24, 1967, 8,861/67
Int. Cl. B29c 25/00; C08g 17/02; D01f 1/02
U.S. Cl. 264—235 10 Claims

The extensibility, impact properties, hardness, softening temperature, water absorption and solvent resistance of shaped articles of substantially unstretched polylactones (polypivalolactone) are significantly improved by thermal after-treatment, i.e., by annealing without deformation at a temperature between about 140° and 230° C.

3,577,503

PROCESS OF MAKING ATHLETIC SHOES WITH INJECTION MOLDED SOLE

Thomas J. Innocenti, Beverly, Mass., assignor to USM Corporation, Flemington, N.J.
Original application Nov. 13, 1967, Ser. No. 681,997. Divided and this application Dec. 5, 1968, Ser. No. 781,346
Int. Cl. A43d 65/02; B29h 7/08
U.S. Cl. 264—244 1 Claim



Method for making an athletic shoe with an injection molded sole having means for receiving spikes or other projections to be attached to the sole, said means being embedded in the sole.


3,577,504

METHOD OF MANUFACTURING A GIRDER WITH A WEB OF REINFORCED AND/OR PRESTRESSED CONCRETE

Abraham Icchok Lipski, 85 Avenue de Boetendaal, Brussels, Belgium
Continuation-in-part of application Ser. No. 533,697, Mar. 11, 1966. This application Feb. 28, 1969, Ser. No. 803,217
Claims priority, application Belgium, Mar. 26, 1965, 661,699; Dec. 8, 1965, 673,451
Int. Cl. B28b 1/02; F04b 1/02, 1/08
U.S. Cl. 264—255 5 Claims

A method for manufacturing a girder with a thin web in reinforced or prestressed concrete, the web thickness being 2 cm. plus 6% of the width up to 50 cm. width

and 5 cm. plus 2.5% of the width thereafter. Said thin web is prefabricated independently of at least one flange




in a horizontal flat mould. Said flanges are thereafter integrated with said thin web.

3,577,505

CENTRIFUGAL MOLDING PROCESS FOR MANUFACTURING HUME-TYPE CONCRETE PIPES

Koreyoshi Ichihara, Kawasaki, Japan, assignor to Nippon Hume Pipe Co., Ltd.
Continuation-in-part of application Ser. No. 492,516, Oct. 4, 1965. This application July 17, 1969, Ser. No. 842,574
Claims priority, application Japan, Feb. 8, 1965, 40/6,879
Int. Cl. B28b 1/16, 1/20
U.S. Cl. 264—256 6 Claims



A method of manufacturing Hume-type concrete pipes by centrifugal molding. A predetermined quantity of cement slurry is introduced into a rotating pipe mold to form a layer of one density and rigidity and subsequently, a predetermined quantity of cement slurry having another density and rigidity is introduced to form another layer. One of the slurries is a hard kneaded slurry having a water content of less than saturation and of less than that required for molding. Another of the slurries is a soft kneaded slurry having a water content greater than saturation and of more than required for molding. The pipe mold is rotated such that centrifugal force commingles the surplus water from the one layer into the other layer to form a single layer having a uniform thickness and having a water content having substantially no surplus. The force created is insufficient to provide a separation of water from the slurry during molding. A single layer water content ratio of 30 to 35% water to cement is achieved.


3,577,506

FABRICATION OF ULTRA-THIN WALL BOBBINS

Augustus B. Brown, Longmont, Colo., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Mar. 4, 1969, Ser. No. 804,173
Int. Cl. B29d 3/00 3 Claims

A short length of sheet-like B-stage polyesters supported by a nylon substrate is partially wrapped around a center

portion of a laminated pole piece for a magnetic read-record head, preferably with the B-stage polyester contacting the pole piece. The assemblage is placed in a heated compression mold. The mold is closed to form an annular space about the center portion of the pole piece and



causes the polyester and nylon to flow about the pole piece to fill the space, thereby forming a unitary annular bobbin with a wall thickness selected in the range from about 1 mil to 15 mils. After the polyester/nylon conglomerate has cured, the pole piece with the bobbin is removed from the mold.

3,577,507

TUFTING PROCESS FOR FOAMED PLASTIC STRUCTURES


Herbert O. Corbett, Bridgeport, Conn., assignor to National Distillers and Chemical Corporation, New York, N.Y.

Filed Jan. 3, 1967, Ser. No. 606,802

Int. Cl. B26d 3/00

U.S. Cl. 264—321

3 Claims



A tufted product such as a blanket or rug or other material having a rug or blanket like structure is formed by shredding the outer surface of an elongated foamed plastic sheet. In the shredding process, the foamed plastic sheet is carried over rolls having wire bristles extending from their surface which stab into the surface of the foamed sheet and shred the surface to produce the effect of a tufted or napped surface. Both sides of the foamed sheet are tufted by threading the sheet above and below sequentially arranged wire bristle rollers.

3,577,508

COATING AND LAMINATING PROCESS

Charles W. Desaulniers, Franklin, Mass., assignor to W. R. Grace & Co., New York, N.Y.

Original application Oct. 17, 1966, Ser. No. 587,194, now Patent No. 3,499,820, dated Mar. 10, 1970. Divided and this application July 15, 1969, Ser. No. 869,414


Int. Cl. B32b 19/02; B44d 1/14

U.S. Cl. 264—331

10 Claims

A process for preparing a self-supporting laminate having a low permeability to gases, comprising applying a coating of a film-forming polymer-diluent system to a substrate; adjusting the thickness of the coating; drying the coating to a solid state; applying a coating of a dispersion of a mineral, inorganic, or organic filler having

a platelike structure to the resulting film; adjusting the thickness of the coating of filler; applying at least one coating or the film-forming polymer-diluent system to the



dried coating of filler; adjusting the thickness of the coating of film-forming diluent system; and drying the coating of film-forming diluent system.

3,577,509

PREVENTION OF SLUMPING IN THE MANUFACTURE OF A TAR BONDED REFRACTORY

Max Hicguet, Boulogne, Hauts-de-Seine, France, assignor to Societe d'Etudes et de Recherches Scientifiques et Minieres, Paris, France

No Drawing. Continuation of application Ser. No. 577,136, Sept. 6, 1966. This application July 25, 1967, Ser. No. 655,963

Claims priority, application France, Sept. 8, 1965, 30,765

Int. Cl. C04b 41/30

U.S. Cl. 264—336

13 Claims

To prevent pressed hot tar bonded brick from slumping while cooling to a temperature below the softening point of the tar binder the ejected brick are placed on pallets that support at least two of the vertical faces of the brick. The mold box on the brick press is maintained at a controlled temperature to harden the pressed brick to a sufficient depth to allow them to be handled from the press onto the pallets. This technique is used in processes that use low softening point tar binders, e.g., a tar having a softening point in the range of 39–80° C.

3,577,510

PROCESS FOR THE PRODUCTION OF DEEP-DRAWABLE, STERILIZABLE POLYESTER FILM

Peter Josef Schmitz, Eberhard Werner, and Walter Seifried, Wiesbaden-Biebrich, Germany, assignors to Kalle Aktiengesellschaft, Wiesbaden-Biebrich, Germany


Filed Oct. 10, 1967, Ser. No. 674,244

Claims priority, application Germany, Oct. 13, 1966, K 60,455

Int. Cl. B29c 25/00

U.S. Cl. 264—342

2 Claims



This invention relates to a process for the production of deep-drawable, sterilizable polyester film having a good shelf life in which stress is applied to an amorphous polyester film in orthogonal directions in the plane of the

film, whereby the film is thinned to at most 1/4 of the original film thickness, and the film is then at most doubled in thickness due to retardation at temperatures between 120° and 140° C.

3,577,511

PROCESS AND COMPOSITIONS FOR DIFFERENTIAL DIAGNOSIS OF THE MEGALOBlastic ANEMIA SYNDROMES

Adrian Leonard Lohby, 2794 Webb Ave., New York, N.Y. 10468

No Drawing. Filed Feb. 21, 1968, Ser. No. 707,303

Int. Cl. G01n 33/16

U.S. Cl. 424—9

22 Claims

A method and several compositions for the accurate and early differential diagnosis of the deficiency states causing macrocytic megaloblastic anemia syndrome is provided in which one of several combinations of specified amino acids or other specific precursor compounds are administered to the test subject in metabolic loading doses and the urinary excretion of certain unusual metabolic products is determined. The metabolic anomaly in folic acid deficiency states is formiminoglutamic acid (FIGLU); in cobalamin vitamin B₁₂ deficiency states it is methylmalonate (MMA). This diagnostic procedure described herein is positive even before the characteristic anemia is developed. The results of the diagnostic procedure described permits from the analysis of one urine specimen the accurate and definitive identification of the presence and severity of a folic acid and/or vitamin B₁₂ deficiency state and thus affords a basis for determining specifically those two deficiency states. Other aspects of the invention are described in the specification.

3,577,512

SUSTAINED RELEASE TABLETS

Thomas H. Shepherd, Hopewell, and Francis E. Gould, Princeton, N.J., assignors to National Patent Development Corporation, New York, N.Y.

Continuation-in-part of applications Ser. No. 567,856, July 26, 1966, Ser. No. 650,259, June 30, 1967, and Ser. No. 654,044, July 5, 1967. This application Oct. 11, 1968, Ser. No. 766,840

The portion of the term of the patent subsequent to Apr. 27, 1988, has been disclaimed

Int. Cl. A61j 3/06, 3/10; A61k 27/12

U.S. Cl. 424—21

13 Claims

Sustained release dosage forms, e.g. tablets or pills, are prepared comprising a therapeutically active material and a hydrophilic acrylate or methacrylate polymer mixed therewith and/or as a coating therefor. Preferably, the polymer is cross-linked, most preferably by employing a diester of the acrylate or methacrylate in minor amounts.

3,577,513

PELLETS FOR SUPPLYING BIOLOGICALLY ACTIVE SUBSTANCES TO RUMINANTS CONTAINING MAGNESIUM AND COATED IRON PARTICLES

Peter Roebuck and Derek James Whitehead, Swinton, Manchester, England, assignors to Pfizer Inc., New York, N.Y.

No Drawing. Filed Dec. 20, 1967, Ser. No. 691,962

Claims priority, application Great Britain, Dec. 21, 1966, 57,219/66

Int. Cl. A61j 3/00, 3/07, 3/08

U.S. Cl. 424—22

4 Claims

A pellet for ruminants containing magnesium or magnesium alloy and iron particles, the latter having been treated to form an oxide or other refractory coating thereon.

3,577,514

SUSTAINED RELEASE PHARMACEUTICAL TABLETS

Ira C. Robinson, Groton, Conn., assignor to Pfizer Inc., New York, N.Y.

No Drawing. Filed June 10, 1968, Ser. No. 735,571

Int. Cl. A61k 27/12

U.S. Cl. 424—22

4 Claims

A sustained release pharmaceutical tablet characterized by a substantially constant rate of drug release comprising: (a) a medicament; (b) a hydrophobic dissolution retardant; (c) an acid-insoluble release agent; and (b) a water-soluble or dispersible binder.

3,577,515

ENCAPSULATION BY INTERFACIAL POLYCONDENSATION


Jan E. Vandegaer, Wayne, N.J., assignor to Pennwalt Corporation

Continuation-in-part of abandoned application Ser. No. 525,038, Feb. 4, 1966, which is a continuation-in-part of abandoned application Ser. No. 330,255, Dec. 13, 1963. This application Mar. 4, 1968, Ser. No. 710,293

Int. Cl. A01n 17/00; B01j 13/02; B44d 1/02

U.S. Cl. 424—32

19 Claims



Procedure for encapsulation of materials initially embodied, contained or carried in liquid is effected by interfacial polycondensation between coating intermediates respectively in immiscible liquids, droplets of one liquid which is to be encapsulated and which contains one intermediate, being first established in a body of the other liquid. Thereafter the second intermediate is incorporated in the other liquid to produce minute capsules of the first liquid having a skin of polycondensate, e.g. polyamide, polysulfonamide, polyester, polycarbonate, polyurethane, or polyurea. Notably effective operation involves continuously supplying both the first liquid containing the first intermediate, and the second liquid, into a region where continuous agitation effects dispersion of the first liquid as droplets, the dispersion being continuously brought together with the second intermediate, thereby continuously establishing the droplet dispersion in liquid containing the second intermediate, and in consequence continuously producing encapsulated droplets by interfacial polycondensation between the intermediates.

3,577,516

PREPARATION OF SPRAY ON BANDAGE

Francis E. Gould, Princeton, and Thomas H. Shepherd, Hopewell, N.J., assignors to National Patent Development Corporation, New York, N.Y.

Continuation-in-part of applications Ser. No. 567,856, July 26, 1966, now Patent No. 3,520,949, Ser. No. 650,259, June 30, 1967, and Ser. No. 654,044, July 5, 1967. This application Dec. 2, 1969, Ser. No. 881,376

Int. Cl. A61l 15/00

U.S. Cl. 424—46

17 Claims

A bandage is formed in situ on a wound by spraying on separately or simultaneously a hydrophilic water insoluble polymer and a high-boiling plasticizer or solvent

therefor. Preferably the polymer is a hydroxy lower alkyl acrylate or methacrylate. Medically active ingredients can be included in the composition.

3,577,517

ACRYLIC OR METHACRYLIC ACID COPOLYMER IN RESINOUS AEROSOL HAIR PREPARATIONS

Ikuo Kubot, Sakai-shi, and Masakatsu Mikami and Selkichi Kitamura, Kyoto, Japan, assignors to Mitsubishi Rayon Co., Ltd., Tokyo, and Goo Chemical Industry Co., Ltd., Kyoto, Japan

No Drawing. Filed Mar. 21, 1966, Ser. No. 535,675
Claims priority, application Japan, Mar. 26, 1965, 40/17,174

Int. Cl. A61k 7/06

U.S. Cl. 424—47

6 Claims

A composition suitable for use as an aerosol hair lacquer comprises 30–70% of an organic solution containing 1–10 weight percent of a copolymer of (1) 5–40 weight percent of an ester of an aliphatic alcohol with acrylic or methacrylic acid; (2) 6–35 weight percent acrylic or methacrylic acid; and (3) 25–89 weight percent of some other vinyl monomer neutralized with a water soluble base and 70–30% of a spraying agent.

3,577,518

HYDROPHILIC HAIRSPRAY AND HAIR SETTING PREPARATIONS

Thomas H. Shepherd, Hopewell, and Francis E. Gould, Princeton, N.J., assignors to National Patent Development Corporation, New York, N.Y.

No Drawing. Continuation-in-part of applications Ser. No. 567,856, July 26, 1966, now Patent No. 3,520,949, Ser. No. 650,259, June 30, 1967, Ser. No. 654,044, July 5, 1967, and Ser. No. 743,626, July 10, 1968. This application July 18, 1969, Ser. No. 843,245

Int. Cl. A61k 7/10

U.S. Cl. 424—47

27 Claims

Hair spray and hair setting compositions are prepared from hydrophilic copolymers of hydroxyalkyl acrylates or methacrylates with mere hydrophobic alkyl acrylates or methacrylates or alkoxyalkyl acrylates or methacrylates. There can also be included polymerizable amino compounds or olefinic carboxylic acids.

Terpolymers of alkoxyalkyl acrylates or methacrylate with alkyl acrylates or methacrylates with olefinic carboxylic acids or unsaturated amines can also be used as can tetrapolymers of the monomers set forth.

3,577,519

PROCESS FOR CONTROLLING THE AMOUNT OF DENSIFICATION IN POLYURETHANE FOAMS AND PRODUCTS PRODUCED THEREBY

Mario A. Gambardella, Milford, Conn., assignor to Olin Mathieson Chemical Corporation

No Drawing. Continuation-in-part of abandoned applications Ser. No. 658,314, Aug. 4, 1967, and Ser. No. 715,116, Feb. 27, 1968. This application Nov. 29, 1968, Ser. No. 780,246

Int. Cl. C08g 22/44; B29d 27/00

U.S. Cl. 264—54

8 Claims

The exterior, less dense layers in a selected, flexible densified polyurethane foam prepared by applying a compressive force to a partially cured cellular material at a critical time to reduce its volume by a specified amount are reduced by maintaining the compressive force for between about 0.1 and about 10 minutes. If desired, the compressive means can be heated to a temperature between about 40° and about 200° C. The resulting foams are particularly useful for such applications as rug padding.

3,577,520

DENTIFRICE COMPOSITIONS CONTAINING 5,5-DIARYL-2,4-IMIDAZOLIDINEDIONES AND PROCESS OF TREATING PYORRHEA

Emile Constantin Savini, 44 Rue du Magasin a Poudre, 14 Caen, France, and Robert Poitevin, 6 Rue Anatole de la Forge, 75 Paris 17, France

No Drawing. Continuation-in-part of application Ser. No. 669,271, Sept. 20, 1967. This application Dec. 19, 1969, Ser. No. 886,754

Int. Cl. A61k 7/16

U.S. Cl. 424—54

8 Claims

This invention relates to dentifrice compositions for treatment of dental alveolus pyorrhea containing a safe but effective amount of 5,5-diaryl-2,4-imidazolidinediones and to the method of treatment of dental alveolus pyorrhea which comprises topically applying to the effected area of the gums a dentifrice composition containing a safe but effective amount of 5,5-diaryl-2,4-imidazolidinediones.

3,577,521

STORAGE-STABLE FROTHING TOOTHPASTE

Karlheinz Scheller, Eisingen (Fils), Else Koddermann, Ebersbach (Fils), and Hans Trebs, Eisingen (Fils), Germany, assignors to Firma Dr. Scheller Duro Dont, Eisingen (Fils), Germany

No Drawing. Filed July 14, 1967, Ser. No. 653,315
Claims priority, application Germany, July 29, 1966, D 50,712

Int. Cl. A61k 7/16

U.S. Cl. 424—55

4 Claims

A storage-stable toothpaste that froths in use; comprising a colloidal silica thickened alcohol system that contains a limited amount of water, peroxide as a gas producing agent and an acid salt as an acidifying agent. When mixed with water and/or saliva the peroxide reacts causing the paste to foam and the pH of the mixture shifts from acidic to basic within a few minutes.

3,577,522

METHODS FOR THE TREATMENT OF SHOCK WITH ETHYLENE OXIDE-POLYPROPYLENE GLYCOL CONDENSATES AS BLOOD PLASMA SUBSTITUTES

Alan C. Hymes, Hopkins, Minn., assignor to Wyandotte Chemicals Corporation, Wyandotte, Mich.

No Drawing. Continuation-in-part of application Ser. No. 762,633, Sept. 25, 1968, which is a continuation-in-part of application Ser. No. 670,408, Sept. 25, 1967. This application Oct. 10, 1969, Ser. No. 865,521

Int. Cl. A61k 27/00

U.S. Cl. 424—78

5 Claims

Isotonic solutions of certain ethylene oxide-polypropylene glycol condensation products have been found to be extremely effective as blood plasma substitutes in the treatment of shock.

3,577,523

WATER-INSOLUBLE ANTIGENIC SUBSTANCES AND METHOD OF PREPARING THE SAME AND ANTIGENIC DEPOT AGENTS INCORPORATING SUCH SUBSTANCES

Morris Emmanuel Stolar, Trumbull, Conn., and Joseph George Feinberg, London, England, assignors to Miles Laboratories, Inc., Elkhart, Ind.

No Drawing. Filed Mar. 7, 1969, Ser. No. 805,378
Int. Cl. A61k 23/00; C12k 5/00

U.S. Cl. 424—88

8 Claims

Water-insoluble antigenic substances prepared by combining a liquid extract or suspension of an antigenic material with an insolubilizing agent such as a preformed aluminum tannate or in situ formed aluminum tannate, and antigenic depot agents incorporating these water-insoluble antigenic substances useful for stimulating prolonged antibody response.

3,577,524

DIMETHYLPOLYSILOXANE SUSPENSIONS OF BIOLOGICS AND PREPARATION THEREOF

Walter David Pratt, Spring Valley, N.Y., assignor to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Mar. 4, 1968, Ser. No. 709,940

Int. Cl. C12k 5/00

U.S. Cl. 424—89

8 Claims

A stable suspension of a biological in dimethylpolysiloxane is provided containing one or more polyhydric alcohols. Exemplary of such stable suspensions is a suspension containing smallpox vaccine, dimethyl polysiloxane, 4 to 10% by weight mannitol, and 4 to 10% by weight sorbitol. The biological suspensions maintain their efficacy, potency, and suspension characteristics under prolonged storage and can be directly withdrawn from their containers and administered to the patient.

3,577,525

ADENOVIRUS VACCINE AGAINST CANINE HEPATITIS

James A. Baker, Ithaca, N.Y., assignor to Cornell Research Foundation, Inc., Ithaca, N.Y.

No Drawing. Original application July 1, 1964, Ser. No. 379,744, now Patent No. 3,346,456, dated Oct. 10, 1967. Divided and this application Aug. 15, 1967, Ser. No. 660,616

Int. Cl. C12k 71/00

U.S. Cl. 424—89

1 Claim

A method of protecting a dog against infectious canine hepatitis by inoculation of the dog with live adenovirus alien to the dog.

3,577,526

STABILIZED SMALLPOX VACCINE

Louis R. Valette, Marcy L'Etoile, Rhone, France, assignor to Societe Anonyme dite: Institut Merleux, Lyon, Rhone, France

No Drawing. Filed June 13, 1969, Ser. No. 833,170

Int. Cl. A61k 27/10; C12k 5/00

U.S. Cl. 424—89

5 Claims

Smallpox vaccine is stabilized by dispersing the same in an aqueous solution containing sucrose. The solution can also contain dextran.

3,577,527

NEISSERIA MENINGITIDIS ANTIGEN

Earl A. Edwards, Lake Bluff, Ill., assignor to the United States of America as represented by the Secretary of the Navy

No Drawing. Filed Jan. 27, 1969, Ser. No. 794,341

Int. Cl. A61k 27/00

U.S. Cl. 424—92

8 Claims

An antigen of *N. meningitidis* which has a high degree of sensitivity and specificity for determining the presence of antibodies in blood is provided by a method in which *N. meningitidis* is subjected to a mild alkaline hydrolysis with production of a lipopolysaccharide antigen.

3,577,528

TWO PHASE HAIR CONDITIONER COMPOSITIONS

Everett G. McDonough, Yonkers, and Walter W. Edman, Port Washington, N.Y., assignors to Zotos International, Inc., Darien, Conn.

No Drawing. Filed May 27, 1966, Ser. No. 553,278

Int. Cl. A61k 7/06

U.S. Cl. 424—70

5 Claims

A two phase hair conditioner having an aqueous and a water immiscible phase which evaporate at the same rate, which imparts along the hair shaft various hair treatment agents.

3,577,529

COMPOSITIONS AND METHODS FOR ENHANCEMENT OF THE GROWTH RATE OF POULTRY AND ANIMALS EMPLOYING ALKALI METAL FORMALDEHYDE SULFOXYLATES AND BISULFITES

Joseph Michael Pensack, Hopewell Township, Trenton, N.J., assignor to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Apr. 17, 1968, Ser. No. 721,921

Int. Cl. A61k 21/00

U.S. Cl. 424—114

11 Claims

A growth rate accelerator for poultry and farm animals having as one active component, an alkali metal formaldehyde bisulfite or an alkali metal formaldehyde sulfoxylate. The compositions can, in addition, contain other materials which enhance the growth rate of the host, such as tetracycline antibiotics, penicillins, zinc bacitracin, erythromycin and/or bis(5-nitrofurfurylidene)-acetone-guanylhydrazones. Growth rate accelerating compositions comprising the above-mentioned growth rate accelerators and ingestible diluents are also provided.

3,577,530

JANIEMYCIN

Edward Meyers, East Brunswick, William Lawrence Parker, Brunswick, Frank Lee Weisenborn, Somerset, Felix Edward Pansy, Jamesburg, and Pacifico Anthony Principe, South River, N.J., assignors to E. R. Squibb & Sons, Inc., New York, N.Y.

Filed July 24, 1969, Ser. No. 844,342

Int. Cl. A61k 21/00

U.S. Cl. 424—118

7 Claims

The antibiotic janiemycin is obtained by the cultivation under controlled conditions, of *Streptomyces macrosporeus* ATCC 21388. Janiemycin is active against bacteria.

3,577,531

DIANEMYCIN FOR TREATING COCCIDIOSIS

Marvin Gorman and Robert L. Hamill, Indianapolis, Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.

No Drawing. Filed Sept. 11, 1968, Ser. No. 759,198

Int. Cl. A61k 21/00

U.S. Cl. 424—122

1 Claim

Methods and compositions for controlling coccidiosis employing the antibiotic dianemycin and its alkali metal, alkaline earth, and basic nitrogen salts as the active anti-coccidiosis agent.

3,577,532

DISINFECTED ANTACID COMPOSITIONS AND METHOD FOR THE PREPARATION THEREOF

George H. Schneller, Devon, and Ralph S. Levi, Norristown, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed June 30, 1967, Ser. No. 650,243

Int. Cl. A61k 27/00; A61i 13/00

U.S. Cl. 424—149

6 Claims

Pharmaceutical or cosmetic compositions especially susceptible to microbiological contamination, are disinfected by treatment with chloramines.

3,577,533

ANTACID COMPOSITIONS CONTAINING BISMUTH ALUMINATE AND COPRECIPITATED ALUMINUM HYDROXIDE AND MAGNESIUM CARBONATE

Joseph Alfred Rider, Mill Valley, Calif. (255 Hugo St., San Francisco, Calif. 94122)

No Drawing. Continuation-in-part of abandoned application Ser. No. 500,268, Oct. 21, 1965. This application Feb. 21, 1968, Ser. No. 707,278

Int. Cl. A61k 27/00

U.S. Cl. 424—155

3 Claims

The antacid compositions are novel pharmaceutical compositions containing bismuth aluminate and a copre-

cupitate of aluminum hydroxide and magnesium carbonate which are useful in the treatment of gastric disorders such as ulcer of the stomach or duodenum, gastritis, hiatal hernia, duodenitis and marginal ulcer.

3,577,534

STABLE ORALLY ACTIVE HEPARINOID COMPLEXES

Teow Yan Koh and Kekhusroo Rustomji Bharucha, Toronto, Ontario, Canada, assignors to Canada Packers Limited, Toronto, Ontario, Canada

No Drawing. Continuation-in-part of application Ser. No. 650,621, July 3, 1967. This application Feb. 14, 1969, Ser. No. 799,521

Claims priority, application Canada, June 20, 1968, 22,996/68

Int. Cl. A61k 17/18

U.S. Cl. 424—183

29 Claims

This invention relates to new stable heparinoid complexes which are absorbable through the mucous membranes of the mammalian body, prepared by reacting heparinic acid or other acid heparinoids with non-toxic organic compounds having weakly basic or amphoteric properties and characterized by a base strength pK_b in the range of from about 7.0 to 12.5 or by an isoelectric point pI below about 9.7, to methods for preparing and using these new heparinoid complexes, and to therapeutic compositions containing them. Particularly suitable heparinoid complexes are those prepared from heparinic acid and amino acids having an isoelectric point pI below about 9.7.

3,577,535

TREATMENT OF THYROID HORMONE IMPAIRMENT PHARMACEUTICAL COMPOSITIONS CONTAINING 3,5,3'-L-TRIODOETHYRONE COMPLEXES

Harold C. Reynolds, Kankakee, and Donald B. Olsen, Bonfield, Ill., assignors to Armour Pharmaceutical Company, Chicago, Ill.

No Drawing. Original application June 29, 1966, Ser. No. 561,357, now Patent No. 3,477,954. Divided and this application Jan. 27, 1969, Ser. No. 794,408

Int. Cl. A61k 27/00

U.S. Cl. 424—198

3 Claims

A pharmaceutical composition consisting of a pharmaceutically acceptable carrier and the reaction product formed by reacting less than a stoichiometric amount of a tertiary phosphine with thyroxine (free acid) in a dipolar aprotic solvent. The composition contains thyroxine (free acid) and 3,5,3'-L-triiodothyronine in a preselected ratio to each other and is useful for the treatment and control of body disorders associated with an impairment of the thyroid hormone function.

3,577,536

METHOD OF CONTROLLING INSECTS AND ARACHNIDS WITH TETRAHYDROQUINOXALINYL PHOSPHATES OR THIOPHOSPHATES

Bernard Miller, Amherst, Mass., and Tamara Helen Mladineo Gund, Mercer, N.J., assignors to American Cyanamid Company, Stamford, Conn.


No Drawing. Original application Aug. 7, 1967, Ser. No. 658,637, now Patent No. 3,505,327, dated Apr. 7, 1970. Divided and this application Mar. 31, 1970, Ser. No. 24,381

Int. Cl. A01n 9/36

U.S. Cl. 424—200

10 Claims

A method of protecting crops and controlling insects or arachnids by applying a compound having the formula:



wherein X is a member selected from the group consisting of sulfur and oxygen; R_1 and R_2 are each lower alkyl, lower alkoxy, lower thioalkyl, phenyl, halophenyl, benzyl or $-NR_4R_5$; R_3 is hydrogen or lower alkyl; and R_4 and R_5 are each selected from the group consisting of hydrogen and lower alkyl.

3,577,537

TOPICAL ADMINISTRATION OF VITAMIN B-12

Eugene E. Howe, Somerset, and Charles Rosenblum, Princeton, N.J., assignors to Merck & Co., Inc., Rahway, N.J.

No Drawing. Continuation-in-part of application Ser. No. 629,918, Apr. 11, 1967. This application Mar. 9, 1970, Ser. No. 17,897

Int. Cl. A61k 25/02

U.S. Cl. 424—201

4 Claims

Vitamin B-12 is administered to animals by topical application in a non-toxic solvent.

3,577,538

HALOGENATED PHOSPHONATES USED FOR CHEMOSTERILIZING SCREW-WORM FLIES

Philip C. Hamm, Glendale, Mo., assignor to Monsanto Company, St. Louis, Mo.


No Drawing. Filed Oct. 23, 1967, Ser. No. 677,076

Int. Cl. A01n 9/36

U.S. Cl. 424—214

4 Claims

Compounds of the following formula are insect chemosterilants:



wherein X and X^1 are halogen (Cl, Br, F and I).

3,577,539

SYNERGISTIC ANTIBACTERIAL COMPOSITION

Leonard J. Vinson, Glen Rock, N.J., assignor to Lever Brothers Company, New York, N.Y.

No Drawing. Continuation of application Ser. No. 800,732, Feb. 19, 1969, which is a continuation-in-part of application Ser. No. 642,327, May 31, 1967, which in turn is a continuation-in-part of application Ser. No. 444,411, Mar. 31, 1965. This application Jan. 19, 1970, Ser. No. 4,471

Int. Cl. A61k 27/00

U.S. Cl. 424—231

2 Claims

The specification discloses germicidal compositions containing phenolic germicides, such as p-tert-amylphenol, o-phenylphenol, o-benzyl-p-chlorophenol, and polybromosalicylanilide, such as 3,4',5-tribromosalicylanilide and 4',5-dibromosalicylanilide.

3,577,540

METHOD OF PROMOTING OSTEOGENESIS

Dirck V. Myers, Atlanta, Ga., assignor to E. R. Squibb & Sons, Inc., New York, N.Y.


No Drawing. Filed Nov. 12, 1968, Ser. No. 775,162

Int. Cl. A61k 27/00


U.S. Cl. 424—244

8 Claims

A method of promoting osteogenesis in animal hosts which comprises applying to the area of a bone defect a quaternary ammonium compound of the formula



wherein R represents lower alkyl, X represents chlorine or bromine, and n is an integer from six to twelve; or of the formula



wherein R^4 represents an alkyl group containing twelve to twenty carbon atoms; R^1 , R^2 and R^3 each represent lower alkyl, and R^1 , R^2 and R^3 taken together with the nitrogen atom represent pyridinium; and X represents chlorine or bromine.

3,577,541

COMPOSITIONS AND METHODS FOR EFFECTING TRANQUILITY WITH TRIAZINES

John Thomas Shaw, Middlesex, N.J., assignor to American Cyanamid Company, Stamford, Conn.

No Drawing. Continuation-in-part of application Ser. No. 240,745, Nov. 28, 1962, now Patent No. 3,505,322, dated Apr. 5, 1970. This application July 23, 1963, Ser. No. 296,915

Int. Cl. A61k 27/00

U.S. Cl. 424—249

5 Claims

(N-monooxyamino)-s-triazines for effecting tranquilization.

3,577,542

INSECT CHEMOSTERILANT HYDROXYETHYL-AMINO PYRIMIDINES

Philip C. Hamm, Glendale, Mo., assignor to Monsanto Company, St. Louis, Mo.


No Drawing. Filed Oct. 23, 1967, Ser. No. 677,081

Int. Cl. A01n 9/22

U.S. Cl. 424—251

8 Claims

Compounds of the following formula are insect chemosterilants:



wherein R, R^1 and R^2 are selected from the group consisting of hydrogen and alkyl of not more than 4 carbon atoms.

3,577,543

INSECTICIDAL AND FUNGICIDAL 2-AMINO-PYRIMIDINYL-6-CARBAMATE COMPOSITIONS

Francis Leslie Charles Baranyovits, Ranajit Ghosh, Nigel Douglas Bishop, and Peter Frank Hilary Freeman, Bracknell, and William Glynn Moss Jones, Macclesfield, England, assignors to Imperial Chemical Industries Limited, London, England

No Drawing. Original application Mar. 10, 1967, Ser. No. 622,043, now Patent No. 3,493,574, dated Feb. 3, 1970. Divided and this application Nov. 14, 1969, Ser. No. 871,296

Claims priority, application Great Britain, Mar. 31, 1966, 14,272/66

Int. Cl. A01m 9/22

U.S. Cl. 424—251

6 Claims

Pesticidal compositions containing a 2-aminopyrimidinyl-6-carbamate or salts thereof. Representative active ingredients are 5,6-dimethyl-2-dimethylamino-4-dimethylcarbamoyloxypyrimidine and the corresponding 5-ethyl-6-methyl-, 5-n-propyl-6-methyl-, 5-cyanoethyl-6-methyl derivatives. These compounds may be used in the form of dusting powders or granules, dips or sprays to combat fungal and/or insect infestations in plants and animals. They may also be used in fertilizers or otherwise to treat agricultural soils.

3,577,544

METHODS FOR PRODUCING MUSCLE RELAXANT AND CNS-DEPRESSANT EFFECTS WITH 3-AMINO-4-PHENYL FURAZAN AND COMPOSITION THEREFOR

Claude Lehmann and Ernst Renk, Basel, Switzerland, assignors to Geigy Chemical Corporation, Ardsley, N.Y.

No Drawing. Filed Feb. 2, 1968, Ser. No. 702,550

Int. Cl. A61k 27/00

U.S. Cl. 424—272

2 Claims

Methods and compositions for producing anti-convulsive, muscle-relaxing, and CNS-depressing effects in mammals, by administration of an effective amount of 3-amino-4-phenyl-furazan.

3,577,545

N-TETRAHALOETHYLTHIO PYRAZOLES AS BACTERICIDES AND FUNGICIDES

Joseph G. E. Fenyes, Oakland, Calif., assignor to Chevron Research Company, San Francisco, Calif.

No Drawing. Original application June 5, 1967, Ser. No. 643,415, now Patent No. 3,409,632, dated Nov. 5, 1968. Divided and this application Dec. 21, 1967, Ser. No. 703,816

Int. Cl. A01n 9/22

U.S. Cl. 424—273

8 Claims

N-(1,1,2,2-tetrahaloethylthio) pyrazoles in which the pyrazole nucleus is substituted in the 3 and 5 positions with hydrogen or lower alkyl groups and in the 4 position with hydrogen, halogen or a nitro group. Compounds of this class are fungicidal and bactericidal. They are made by reacting a pyrazole or its alkali metal salt with tetrahaloethylsulfenyl halides.

3,577,546

USE OF POLYCHLORO KETO-ALKENOIC ACIDS AND DERIVATIVES THEREOF AS INSECTICIDES

William A. Erby, Alburts, and Robert A. Walde, Emmaus, Pa., assignors to Air Products and Chemicals, Inc., Allentown, Pa.

No Drawing. Filed Apr. 8, 1966, Ser. No. 541,096

Int. Cl. A01n 9/28

U.S. Cl. 424—279

7 Claims

A method for killing insects which comprises contacting the insects with an insecticidally effective amount of a polychloro keto-alkenoic acid or derivative thereof.

3,577,547

COMPOSITION PROTECTING AGAINST THE ACTION OF MICROORGANISMS AND ITS MANNER OF USE

Jean-Paul Pelissier, Vitry-sur-Seine, and Pierre Chiffert, Marseille, France, assignors to Societe Anonyme: Produits Chimiques Industriels & Agricoles Proclida S.A., St. Marcel Marseille, Bouches du Rhone, France

No Drawing. Continuation-in-part of application Ser. No. 318,440, Oct. 23, 1963. This application Apr. 8, 1968, Ser. No. 719,715

Claims priority, application France, Nov. 23, 1962, 916,456

Int. Cl. A01n 9/02

U.S. Cl. 424—286

6 Claims

The invention prevents damage to liquid or wet paper pulp by microorganisms and forestalls or destroys the microbic ooze that forms in the water of systems of paper mills by use of a composition comprising a mixture of (1) alkali metal or alkaline earth metal salts of di(lower alkyl) dithiocarbamic acid, chiefly alkali metal dimethyl dithiocarbamate, (2) alkali metal of (lower alkylene)-bis-dithiocarbamic acid, chiefly (ethylene) - bis - dithio-

carbamic acid, and (3) a stabilizer consisting of 1,8,3,6 diendomethylene 1,3,6,8 tetraazacyclodecane, also known as 1,3,6,8 diendomethylene 1,3,6,8 tetraazacyclodecane.

3,577,548


METHODS FOR STERILIZING INSECTS WITH TRIARYLTIN COMPOUNDS

Eugene E. Kenaga, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.


No Drawing. Continuation-in-part of application Ser. No. 244,917, Dec. 17, 1962. This application Dec. 31, 1964, Ser. No. 422,554

Int. Cl. A01n 9/22, 9/00


U.S. Cl. 424—288 25 Claims
Methods for administering to an animal a minimal sterilant amount of a triaryltin compound of the group of




and




wherein, in all of its occurrences in any given triaryltin compound, R represents the same member selected from the group consisting of phenyl, mono-substituted phenyl wherein the substituent is a member selected from the group consisting of halo, loweralkyl, and loweralkoxy; Z represents a monovalent moiety selected from the group consisting of (phenyl)loweralkyl, alkenyl, alkadienyl, cycloalkenyl, cycloalkadienyl, halo, hydroxy, mercapto, hydrogen, alkanoate, alkenoate, loweralkoxy, loweralkylthio, diloweralkylcarbamate, diloweralkylthiocarbamate, diloweralkyldithiocarbamate, radical of the formula




radical of the formula



and radical of the formula $-Sn-R_3$; and Y represents a divalent moiety selected from the group consisting of $-O-$, $-S-$, methylene, ethylene, ethynylene,



carbonyl, 1,3-butadien-1,4-ylene, and



wherein g is an integer of from 1 to 10, both inclusive.

3,577,549

TREATMENT OF PAIN OR INFLAMMATION WITH P-BENZOYL-PHENYLACETIC ACID OR O-BENZOYL-PHENYLACETIC ACID

David Jack and Deryck Rhodes, London, England, assignors to Allen & Hanburys Limited, London, England

No Drawing. Filed Aug. 9, 1968, Ser. No. 751,379
Claims priority, application Great Britain, Aug. 21, 1967, 38,424/67

Int. Cl. A61k 27/00

U.S. Cl. 424—317 2 Claims
Pharmaceutical compositions comprising as active ingredient either p-benzoyl-phenylacetic acid, or o-benzoyl-phenylacetic acid, which compounds may be used in the

form of physiologically acceptable salts. These active ingredients have anti-inflammatory and analgetic activity. They may be administered in dosage unit form.

3,577,550

N-(PHENOXY)PHENYL-SALICYLAMIDES AND THEIR UTILIZATION AS MOLLUSCIDIDES

Clarence L. Moyle, Clare, Mich., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed May 2, 1968, Ser. No. 726,205
Int. Cl. A01n 9/20

U.S. Cl. 424—324

3 Claims

Novel N-(phenoxy)phenyl-salicylamides and their preparation by reaction between a salicylic acid, phosphorus trichloride and a phenoxyaniline. They are useful as molluscicides.

3,577,551

METHODS FOR TREATING PAIN, INFLAMMATION AND COUGH

Masuo Murakami and Kaname Kuriaki, Tokyo, Masaru Iwanami, Kanagawa, Hideki Arima, Tokyo, Kenji Sano and Hiroshi Suzuki, Saitama, and Soichi Kagami, Tokyo, Japan, assignors to Yamanouchi Pharmaceutical Co., Ltd., Tokyo, Japan


No Drawing. Filed Apr. 15, 1969, Ser. No. 816,400
Claims priority, application Japan, Apr. 20, 1968, 43/26,514

Int. Cl. A61k 27/00

U.S. Cl. 424—325

3 Claims

A method of alleviating pain, inflammation and/or cough which comprises administration of a compound selected from the group consisting of compounds of the formula:



wherein R may be hydrogen or lower alkyl, and their pharmaceutically acceptable acid addition salts.

3,577,552

METHOD OF INDUCING LOCAL ANESTHESIA

Bernard M. Regan, Chicago, Ill., assignor to Baxter Laboratories, Inc., Morton Grove, Ill.

No Drawing. Continuation-in-part of application Ser. No. 741,235, June 28, 1968. This application May 8, 1970, Ser. No. 35,941

Int. Cl. A61k 27/00

U.S. Cl. 424—326

6 Claims

A method of inducing local anesthesia by administering to animals a benzoxyalkyl substituted thiopseudourea, for example, 2-(2-benzoxyethyl)-2-thiopseudouronium chloride.

3,577,553

COMPOSITIONS AND METHODS FOR CONTROLLING COCCIDIOSIS IN POULTRY EMPLOYING TRIAZOLE DERIVATIVES

Robert J. Ferlauto, Perkase, Pa., assignor to Smith Kline & French Laboratories, Philadelphia, Pa.

No Drawing. Filed Jan. 29, 1969, Ser. No. 795,043
Int. Cl. A61k 27/00

U.S. Cl. 424—269

10 Claims

Chemotherapeutic compositions useful for the prevention and control of coccidiosis comprising adducts between a benzaldehyde or a cinnamaldehyde and an amino-triazole or between an alkyl aryl ketone and an amino-

triazole, optionally substituted in the aromatic ring, are described as specific and novel compounds useful for the prevention and control of coccidiosis.

3,577,554

SELF-CURING LATEX FOAM COMPOSITIONS

Donald B. Parrish, Lake Jackson, and James M. McDuff, Angleton, Tex., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed May 24, 1967, Ser. No. 640,791
Int. Cl. C08f 47/10; C08j 1/16

U.S. Cl. 260—2.5

13 Claims

A film-forming latex of a copolymer of an α,β -ethylenically unsaturated carboxylic acid, such as an acrylic acid, and a copolymerizable ethylenically unsaturated monomer is reacted with an aziridine at a pH below about 5 to form a copolymer having aminoester groups and carboxyl groups and the pH then is adjusted to above 7. The resulting stable latex, optionally containing formulating ingredients, is frothed, dried and cured to obtain a latex foam. Often the frothed composition is applied in the wet state to an adherent substrate, e.g., to a textile, then cured and dried to form an article such as a drapery.

3,577,555

CARBON BLACK IN PAPER COATING LATEX

Robert A. Forrester and Ralph E. McNay, Houston, Tex., assignors to Ashland Oil, Inc., Houston, Tex.

No Drawing. Filed June 22, 1966, Ser. No. 559,423

Int. Cl. C08d 7/00

U.S. Cl. 260—17.4

8 Claims

Stable aqueous slurries of carbon black and latexes of polymers of ethylenically unsaturated monomers, especially diene polymers, are prepared by adding a dispersing agent prepared by mixing a water soluble natural gum with an anionic surface active agent to the polymer latex, and then adding dry carbon black. The amount of dispersing agent is selected to be sufficient to stabilize the latex against the destabilizing effect of the carbon black. Stable latex slurries can be prepared at 30–60% latex polymer and an amount of carbon black equal to or greater than the latex polymer content.

3,577,556

POLYAMINES STABILIZED WITH AMINO-CARBOXYLATE CHELANTS


Juan Longoria III, Lake Jackson, Tex., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Jan. 5, 1968, Ser. No. 695,835
Int. Cl. C07c 87/14, 119/00; C08g 51/60

U.S. Cl. 260—45.85

9 Claims

Aminocarboxylate chelants of the formula:



where A and B are independently $-C_2H_4OH$ or



a is 0–2, and M is a monovalent cation are effective stabilizers for polyamines including alkylenepolyamines, polyalkylenepolyamines and polyalkylenimines. Addition of about 0.05–10.0 weight percent of the chelant reduces the acid catalyzed and oxidative degradation and discoloration of these polyamines.

3,577,557

BENZO[1,5]DIAZOCINONES

Hans Ott, Convent Station, N.J., assignor to Sandoz-Wander, Inc., Hanover, N.J.

No Drawing. Filed Dec. 9, 1966, Ser. No. 600,403
Int. Cl. C07d 53/00, 51/48

U.S. Cl. 260—239.3

20 Claims

The invention discloses compounds of the class of 6-phenyl-3,4-dihydro[1,5]benzodiazocin-2-(1H)-ones useful as tranquilizers. Also disclosed is preparation of said compounds featuring intermediates which are 1,5-methano-1,5-benzodiazocin-2-ones which are converted by acid treatment to the corresponding 6-phenyl-3,4,5,6-tetrahydro[1,5]benzodiazocin-2-(1H)-ones which in turn may be oxidized to obtain the first-mentioned class of compounds.

3,577,558

1-AMINOALKYLAMINO-4-ALKOXYMETHYL-THIOXANTHENE DERIVATIVES

David Rosi, East Greenbush, N.Y., assignor to Sterling Drug Inc., New York, N.Y.

No Drawing. Filed Apr. 15, 1968, Ser. No. 721,190
Int. Cl. C07d 65/16, 7/42; A61k 27/00

U.S. Cl. 260—328

5 Claims

1-aminoalkylamino - 4 - (lower-alkoxymethyl)thioxanthenes, -thioxanthene-S-oxides or -dioxide, -xanthenes and -9-one derivatives thereof, having schistosomicidal activity, are prepared by reacting the corresponding 4-hydroxymethyl compounds with a lower-alkanol in an acidic medium, e.g., in the presence of a strong acid, e.g., p-toluenesulfonic acid.

3,577,559

PROCESS FOR MAKING GLYCOL ETHERS AND GLYCOL ESTERS

Lee H. Horsley, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Jan. 19, 1968, Ser. No. 699,055
Int. Cl. C07c 69/76

U.S. Cl. 260—410.6

11 Claims

Glycol ethers or glycol esters having the formula $ROC_mH_{2m}ZC_nH_{2n}OH$ are prepared by reacting a compound having the formula ROH, a cyclic compound having the formula $C_mH_{2m}Z$ and having at least three and not more than five carbon atoms in the ring and a vicinal alkylene oxide having the formula $C_nH_{2n}O$ where the molar ratio of $C_mH_{2m}Z$ to vicinal oxide is between one to ten and ten to one, the molar ratio of vicinal oxide plus $C_mH_{2m}Z$ to ROH is at least one to one, R is acyl having at least two and not more than eighteen carbon atoms or aryl having up to two aromatic rings, Z is oxygen or sulfur, m is an integer of from three to fifteen inclusive and n is an integer of from two to four inclusive. They are useful as solvents, lubricants, hydraulic fluids and chemical intermediates.

3,577,560

METHOD OF FORMING PELLETS OF A FLUX COMPOSITION

Garth D. Lawrence, Midland, and Jack J. Ott, Hemlock, Mich., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Mar. 27, 1968, Ser. No. 716,359
Int. Cl. B01j 2/02

U.S. Cl. 264—8

5 Claims

The present invention comprises a method of preparing a pelleted flux product by melting a flux composition while maintaining a continuous cover of unmelted flux over the molten portion, forming the melt into molten droplets, and solidifying the droplets into discrete particles or pellets.

GENERAL AND MECHANICAL

3,577,561


HELMET FOR ACCIDENT PREVENTION

Ichiro Oshima, Ota-Shi, Japan (c/o Oshima Denki Seisakusho Co. Ltd., No. 42, Fujikura)
Continuation of application Ser. No. 648,393, June 23, 1967, now abandoned. This application Aug. 13, 1969, Ser. No. 850,345

Int. Cl. A42b 3/00

U.S. Cl. 2-3

3 Claims U.S. Cl. 2-8



This invention is intended to provide a helmet for accident prevention comprising in combination a helmet and a plurality of reflectors, said reflectors being attached to outer portions of the helmet, each of said reflectors having a number of reflector elements and adapted to reflect an incident ray of light substantially in the direction of the light source, thereby enabling the user, such as, for example, a driver of motorcycle, to be easily found even in the dark by other person, such as, for example, a driver of car. Thus, with the helmet, accidents, particularly a night traffic accident may be prevented from occurring.

3,577,562


ATHLETES' PROTECTIVE HELMET PARTICULARLY FOOTBALL

Mike C. Holt, Leesburg, Fla. (Southern Athletic Service, Inc., P. O. Box 46, Leesburg, Fla. 32748)
Continuation-in-part of application Ser. No. 839,585, July 7, 1969. This application Oct. 1, 1969, Ser. No. 862,663

Int. Cl. A42b 3/00

U.S. Cl. 2-3

5 Claims



The protective helmet has a shell of hard, rigid plastic material, and radially suspended pads that entirely encircle the wearer's head. The front pad and the rear pad are each fastened to the horizontal plastic bands, which encircle the inner circumference of the shell. The pads are affixed to the respective plastic bands by mating tapes, one on the inside surface of the plastic band and the other on the outer surface of the pad, whereby when pushed together the pad is held to the plastic band. Each plastic band is held securely to the shell by spaced rivets. In the front there is one plastic band, and in the rear there are two longitudinal plastic bands, one being higher than the other, the higher band being at approximately the same level as the front plastic band. The rear pad extends slightly below the edge of the helmet to protect the neck better. Because the plastic bands are spaced from the inner surface of the shell, this affords air circulation that keeps the helmet cool—the advantage of this padded helmet over other padded helmets.


3,577,563

INSERT FOR HEAD PROTECTING HOODS

Herbert A. Raschke, Greenbrae, Calif., assignor to E. D. Bulard Company, Sausalito, Calif.
Continuation of application Ser. No. 697,950, Jan. 15, 1968, now abandoned. This application Aug. 25, 1969, Ser. No. 853,622

Int. Cl. A61f 9/06

3 Claims



An insert for the faceplate of a protective hood, which insert is curved on one side to conform with the curvature of the faceplate and flat at another side so as to define a planar opening for receiving a flat transparent plate. Clips or a resilient frame member on the insert retain the transparent plate in place and are conveniently movable to afford quick insertion and removal of the transparent plate so that such plate can be replaced as needed.

3,577,564

FACE SHIELD


Rodney S. Hill, Dover, Del., assignor to ILC Industries, Inc., Dover, Del.

Filed Aug. 26, 1968, Ser. No. 755,463

Int. Cl. A61f 9/04

U.S. Cl. 2-10

6 Claims



Protective face shield and mounting means therefor which enable quick and easy structural association and disassociation relative to protective headgear, such as a helmet shell, while providing positive restraint against rotation or pivoting movement of the face shield inwardly toward the face of a wearer.

3,577,565

FACE SHIELD

Frederick W. Feldmann, and Rodney S. Hill, Dover, Del., assignors to ILC Industries, Inc., Dover, Del.

Filed Aug. 26, 1968, Ser. No. 755,464

Int. Cl. A61f 9/04

U.S. Cl. 2-10

8 Claims


Protective face shield and mounting means therefor which enable quick and easy structural association and disassociation

MAY 4, 1971

GENERAL AND MECHANICAL

133

tion relative to protective headgear, such as a helmet shell, while providing positive restraint against rotation or pivoting



movement of the face shield inwardly toward the face of a wearer.

3,577,566


SPECTACLE HOOD

Benjamin Kislin, and J. W. Miller, San Antonio, Tex.
Filed Nov. 21, 1968, Ser. No. 777,791

Int. Cl. A61f 9/04; G02c 7/16

U.S. Cl. 2-12

1 Claim



A spectacle hood having an opaque front with an appropriate cutout section conforming to the configuration of the cowl above an aircraft instrument panel. The device is held in place on the face by spectacle temples and peripheral vision is excluded by flexible sid shields. Where individual corrective lenses are required, the proper prescription can be incorporated in the clear area of the device.

3,577,567


MODIFIED MULTI-PURPOSE BIDET

Andrew F. Wintercorn, 2449 Clinton Road, Rockford, Ill.
Filed Oct. 14, 1968, Ser. No. 767,227

Int. Cl. A47k 3/22

U.S. Cl. 4-7

15 Claims



The device in both forms may be used with an adapter attached to the mixing faucet on a lavatory or bathtub, or may be connected permanently or semipermanently with a mixing valve that has connections with the hot and cold water valves under a lavatory. In either event, the basin has its flange resting on the toilet bowl for support and is provided with a substantially central upwardly directed spray nozzle to which water of the desired temperature is delivered normally when a spring closed valve on the rear flange is automatically

opened by the operator sitting on the basin, the flow being controllable by the user leaning forward, more or less, to relieve pressure on the rear portion, which is an especially important feature when a douche or enema nozzle is being used in lieu of the ordinary bidet nozzle. Jet sprays around the rim of the basin to which water is delivered continuously independently of the automatic valve, serve for rinsing purposes and also for temperature testing, while the flow to these jets warms up the rim of the basin for better comfort prior to the operator sitting on the basin. In the combination bidet and sitz bath the basin is somewhat deeper, and, in addition to the holes provided in the bottom around the nozzle for drainage, there are overflow holes provided in the sidewalls of the basin near the top in circumferentially spaced relation between the jet openings, and one may, by shutting off flow through the bottom drain holes, trap sufficient water in the basin for sitz bath operation. Medication may be added by passing the incoming warm water through a container for the medication, that is transparent so that one can tell immediately when the medication is used up.

3,577,568

WATER CLOSET


Ole Bjerke Johansen, Asmundtorp 147, S-430 61, Harryda, and Jan Ove Hertil Herveus, Nygardsvagen 18 D, S-433 00, Partille, Sweden

Filed Oct. 10, 1969, Ser. No. 865,538

Int. Cl. E03d 5/016

U.S. Cl. 4-77

4 Claims



A water closet using a very limited amount of flushing water owing to recirculation of the same by means of a pump system. The flushing liquid receptacle is positioned beneath the closet bowl and through said receptacle extends in the vertical direction a discharge pipe which at its lower end opens into a sludge tank and which has its upper end positioned vertically below the lower opening of the closet bowl. A disclike valve is adapted to provide preferably airtight sealing of the upper end of the discharge pipe.

3,577,569

TOILET APPARATUS

Ronald J. Sargent, Ann Arbor; Charles L. Sargent, Ypsilanti; Frank T. Sargent, Clio, and John A. Hoffman, Brighton, Mich., assignors to Thetford Corporation, Ann Arbor, Mich.

Filed Mar. 21, 1969, Ser. No. 809,225


Int. Cl. E03d 11/10, 11/08

U.S. Cl. 4-79

11 Claims

A toilet having a flushing apparatus whereby a fixed

volume of water is discharged from a single nozzle into the



bowl of the toilet in a vortex pattern.

3,577,570

SWIMMING POOLS

Georges Vincent, Grenoble, France, assignor to Societe Grenobleise d'Etudes et d'Applications Hydrauliques (Sogreah), Grenoble, France


Filed Mar. 8, 1968, Ser. No. 711,628

Claims priority, application France, Mar. 8, 1967, 5070

Int. Cl. E04h 3/18

U.S. Cl. 4-172.17

12 Claims



The swimming pool is provided with edges having a gentle slope with respect to the static water surface in the pool so that wave reflection from the edges of the pool is eliminated.

3,577,571

COMBINATION CLEANING, FOUNTAIN AND THERAPEUTIC WHIRLPOOL APPARATUS FOR SWIMMING POOLS


Bernard Bellinson, Sherman Oaks, and Henry R. Young, Arleta, Calif., assignors to Marine Swimming Pool Equipment Co., North Hollywood, Calif.

Filed Mar. 19, 1969, Ser. No. 808,630

Int. Cl. E04h 3/16, 3/18

U.S. Cl. 4-172.17

5 Claims



A swimming pool having in its sidewall a plurality of water-delivery outlet sockets; in combination with selectively actuable

cleaning hoses of the jet-propelled type, fountain heads for converting the water flow into a series of fountain sprays during nonuse of the cleaner hoses, and therapeutic jet nozzles for converting the flow into a water and air bubble mixture for "whirlpool" agitation of the water.

3,577,572

INTEGRAL LAVATORY BOWL AND VANITY TOP COMBINATION


Kay L. Ruggles; Dale B. Gunnerson, and Howard S. Clark, Salt Lake City, Utah, assignors to American Standard, Inc., New York, N.Y.

Division of Ser. No. 606,324 Dec. 30, 1966, Pat. No. 3,433,860. Filed Jan. 21, 1969, Ser. No. 872,779

Int. Cl. E03c 1/18; A47k 1/04

U.S. Cl. 4-187

6 Claims



The Article of Manufacture comprises an integral lavatory bowl and vanity top combination of a thermosetting synthetic plastic composition, preferably of the polyester resin type, wherein the bowl area is integrally formed with the vanity top area. The bowl area may be provided with a preformed overflow tube which is embedded within the material of the sidewall of the bowl.

3,577,573

AMBULANCE STRETCHER DEVICE


Wencle J. Mrnak, Bowman, N. Dak.

Filed Feb. 14, 1969, Ser. No. 799,346

Int. Cl. A47b 83/04

U.S. Cl. 5-82

2 Claims



The invention comprises an ambulance stretcher having a pair of sections with bottom support plate members in each section disposed in horizontal planes, said bottom support members having their inner edges overlapping in flush relationship to one another, a pin pivotally connecting said bottom members together along their overlapping portions whereby one section may be pivoted relative to the other section in a horizontal direction to facilitate transporting the stretcher about sharp corners.

3,577,574

SPRING ASSEMBLY FOR FURNITURE AND METHOD OF MANUFACTURE


Fred A. Ciampa; Angelo Serafini, and Louis Mazzarella, Boston, Mass., assignors to Standard Box Spring Co., East Boston, Mass.

Filed Jan. 3, 1969, Ser. No. 788,893

Int. Cl. A61j 19/00

U.S. Cl. 5-267

6 Claims



A spring assembly for bed springs or other furniture is prepared from wires having a series of longitudinally spaced return bends. Two groups of wires are welded in right angular relation to form a planar wire mesh. The return bends are located in at least one group of the wires, and form pairs of channels which are open in a direction normal to the plane of the mesh. The mesh is inverted with the channels open upwardly, and a number of coil springs are positioned on it, with the upper convolution of a coil spring inserted into each pair of channels. The return bends are then bent over the convolutions to lock them to the mesh. The free ends of the springs of the resulting spring assembly are then attached to a frame in a conventional manner.

3,577,575

BINDING AND OPENING DEVICE

Fumio Taniguchi, 2-3 Ueno-cho-3-chome, Tajimi-shi, Japan


Filed Feb. 28, 1969, Ser. No. 803,183

Claims priority, application Japan, Mar. 29, 1968, 43/20001

Int. Cl. B25b 27/14; B26b 27/00; B31f 5/02

U.S. Cl. 7-14.1

7 Claims



The binding device has a cutter for making a U-shaped slot in papers, a cam for bending down the U-shaped portion of the papers, and a knife for making an I-shaped slot in the papers and for inserting the portion into the I-shaped slot. The binding and opening device has a plurality of sets of the cutter, cam, and knife and further has a pair of edges for opening a letter.

3,577,576

COLLAPSIBLE SURFBOARD OR SAILBOAT


Edward Vernon Lobb, Port Murray, N.J., and Raymond W. Coburn, Jr., New York, N.Y., assignors to Colgil Enterprises, Inc., Oyster Bay Cove, N.Y.

Filed June 24, 1969, Ser. No. 836,115

Int. Cl. B63b 7/00, 35/00

U.S. Cl. 9-2A

9 Claims



The present invention relates to a collapsible vessel having an inflatable hull which is suitable for use as a surfboard or sailboat. The inflatable hull is formed of a flexible sheet material such as polyvinyl chloride and incorporates inflatable air and watertight compartments therein which are interconnected by chambers or pockets to receive and hold rigid reinforcing elements in place relative to the hull.

The reinforcing elements extend lengthwise of the hull and may be interconnected by crossmembers to form a rigid reinforcing frame. Both the hull and the reinforcing elements are collapsible for purposes of transportation and storage. Components which enable the hull to be utilized as a sailboat are attached to and are supported by elements of the reinforcing frame.

3,577,577

LOCK WASHER


Alfred M. Zak, 6110 Casmere Ave., Detroit, Mich.

Filed May 13, 1969, Ser. No. 824,192

Int. Cl. B21d 53/20

U.S. Cl. 10-73

12 Claims



An electrical connector formed with a lock washer portion having a plurality of inwardly extending locking tabs. Each tab is formed into a bent configuration between a punch and

die which are so shaped that each tab remains integrally connected throughout its circumferential extent with the body portion of the lock washer section by a bend line with one side edge portion of each tab projecting above and the other below the plane of the body portion of the washer.

3,577,578

SHOE LAST REMODELING JIG


Arthur P. Alexander, Hingham; Steven R. Aronson, Mattapan, and Charles F. Langenhagen, Jr., South Weymouth, Mass., assignors to Packaged Resins Company Inc., Braintree, Mass.

Filed Mar. 5, 1969, Ser. No. 804,479

Int. Cl. A43d 3/00

U.S. Cl. 12-146

27 Claims



A method and apparatus for fitting, in predetermined registration, a mold cap to the toe end of a last which is supported in a predetermined position and orientation. Gauges, adapted to contact the last at predetermined locations about its bottom pattern, are adjustable to the particular bottom pattern to insure that successive lasts of the same size and style will be supported in the same position and orientation. A mold cap gauge supported is also provided to support successive mold caps repetitively in the same orientation with respect to that of the supported last. The last and mold caps are then combined while in their respective, proper orientations to insure proper and uniform registration.

3,577,579


ELECTRIC TOOTHBRUSH

John P. Duve, 8625 Parkview Ave., Brookfield, Ill., and Douglas E. Beck, 3001 S. King Drive, Chicago, Ill. Division of Ser. No. 824,110, May 13, 1969, filed Oct. 29, 1969, Ser. No. 872,255

Int. Cl. A46b 13/00

U.S. Cl. 15-22

12 Claims



An electric cordless toothbrushing device having a power handle with a drive shaft extending from one end thereof and

a toothbrush attachment which is securable to the remote end of said shaft. The power handle includes a battery-powered motor which by means of a motion-converting mechanism drives the shaft so that the rotary power of the motor is translated to an orbital motion at the toothbrush attachment. An improved electric switch is provided to control the energization of the motor.

3,577,580

SELF-CLEANABLE HAIR BRUSH


Robert B. Rand, P.O. Box 2461, Charleston, W. Va.

Filed July 18, 1969, Ser. No. 842,140

Int. Cl. A46b 17/06

U.S. Cl. 15-169

2 Claims



A self-cleanable hair brush comprising a main body portion having a handle at one end, a back normally disposed in contact with one side of said main body portion, tufts of bristles secured to said back and extending through openings in said body portion, a plurality of pins rigidly secured to said body portion and normally extending through apertures provided in said back, and a U-shaped clip member pivotally secured to each pair of pins, said clip members in normal operative position of the brush being secured to the upper side of said brush, and said clip members being pivotable to a position in which the legs of the U are in alignment with said pins whereby said back and said body member may be moved away from each other to a brush cleaning position in which the crossmembers of the U-shaped clip members constitute abutments limiting movement so that the back does not become disengaged from the tufts of bristles.

3,577,581

SHOE SCRAPER FLOOR GRATINGS FOR AUTOMOBILE FLOORS


Stanley S. Stata, Rockford, Ill., assignor to Andrew F. Winterconn, Rockford, Ill., fractional part interest to each

Filed July 17, 1969, Ser. No. 842,605

Int. Cl. B62d 25/20; B60n 3/06

U.S. Cl. 15-215

13 Claims



This vehicle floor mat consists of a rigid frame secured to the floor, and a mat of flexible material including a pan having a shoe scraper means therein, whereby dirt and moisture scraped from shoes is retained in the pan, and interfitting portions on the marginal edge portions of the pan and in the frame providing for detachably securing the pan in the frame against displacement from its position on the carpet these portions being designed to have a snap fit. A front cross portion on the frame in one form underlies the junction of a toeboard extension with the pan so as to allow free drainage of moisture from the toeboard extension into the pan over this cross portion.

3,577,582

METHOD OF MAKING AN APPLICATOR FOR COSMETICS


Bruno D. Aston, 14211 Skyline Drive, Hacienda Heights, Calif.

Continuation of application Ser. No. 660,124, Aug. 11, 1967, now abandoned. This application Apr. 11, 1969, Ser. No. 816,183

Int. Cl. A47k 7/02

U.S. Cl. 15-244

4 Claims



An applicator element mounted on a handle to serve the general purpose of a brush comprises a bulbous body of a soft, resilient, foamed plastic with the cells open to provide communication among the cells and to provide numerous minute outwardly open cavities formed by the outer cells. The applicator element is of folded construction. Preferably, a stiffener element is enclosed by the foamed plastic applicator element and is substantially smaller in cross-sectional area than the applicator element.

3,577,583

MAGNETIC CLAMP


Willard R. Amann, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Nov. 29, 1968, Ser. No. 780,016

Int. Cl. E05d 13/02

U.S. Cl. 16-87.2

9 Claims



A clamp for releasably holding sheet material includes a rigid base of nonmagnetic material and an elongated strip of flexible material. The base carries a permanent magnet at one end, and the elongated strip is attached to the other end of the base and carries a second permanent magnet overlying the permanent magnet in the base. A recess is formed in the base underlying the central portion of the strip in such a manner that, by depressing that portion of the strip, the magnets are caused to part permitting insertion or removal of a piece of sheet material.

3,577,584

HINGE FOR CABINET DOOR

Louis E. Himelreich, Louisville, Ky., assignor to H. J. Scheirich Company, Louisville, Ky.

Filed July 22, 1969, Ser. No. 843,703


Int. Cl. E05d 5/06

U.S. Cl. 16-135

2 Claims

A hinge for mounting a door on a cabinet stile requires

only a single-mounting fastening entering the stile and is illustrated with respect to a stile formed of folded material and



having a door overlying the edge of the stile while in closed position.

3,577,585

MEAT-TENDERIZING MACHINE


Fernand Stanislas Allinquant, 53 Avenue LeNotre, Sceaux, France

Filed July 18, 1968, Ser. No. 745,758

Int. Cl. A22c 9/00

U.S. Cl. 17-25

8 Claims



The invention relates to a meat-tenderizing machine comprising stationary columns, a grid pressing upon the piece of meat which, owing to inclined hinged rings rubbing against the columns, should be maintained in position while the tenderizing blades are pulled upwardly out of the piece of meat, the improvement being that the columns bear at these tops owing to which the grid is prevented from ascending beyond a given topmost position, should the grid accompany the blades in their ascending movement in spite of the inclined rings.

3,577,586

APPARATUS FOR CONTINUOUSLY TRANSVERSELY STRETCHING ORIENTABLE SHEET MATERIAL

Frank Kalwaites, Somerville, and Peter L. Doviak, Kendall Park, N.J., assignors to Johnson & Johnson

Filed Dec. 20, 1967, Ser. No. 692,006


Int. Cl. B29g 7/00

U.S. Cl. 18-1

8 Claims

Method and apparatus for transversely stretching sheet material wherein the material is moved in its longitudinal direction, tension is applied in the transverse direction, the material heated and uniformly stretched in its transverse direction at a rate sufficient to orient the material. After the material is uniformly transversely stretched the desired amount the edges of the material are kept parallel and the material cooled. The apparatus comprises means for applying tension in the transverse direction of continuously moving sheet material, means for heating the material while said ten-

sion is applied, a pair of diverging conveyors which diverge at an angle greater than 40°, the diverging conveyors having clamping means which clamp the edges of the material to uniformly transversely stretch the material as the conveyors



diverge and means for removing the continuously moving sheet material from the clamping means of the diverging conveyors while maintaining the edges of the material substantially parallel and under control.

3,577,587


APPARATUS FOR MAKING RETICULATED STRUCTURES

Theodore H. Fairbanks, West Chester, Pa., assignor to FMC Corporation, Philadelphia, Pa.

Filed Nov. 22, 1968, Ser. No. 778,134
Int. Cl. B29f 3/04

U.S. Cl. 18-12

7 Claims



Apparatus for making reticulated structures by periodically contacting adjacent streams of a series of generally like streams of flowable material as they are extruded along sinusoidal paths, and thereafter setting the extruded streams.

3,577,588


EXTRUSION APPARATUS

Douglas S. Chisholm, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Filed May 5, 1969, Ser. No. 821,827
Int. Cl. B29f 3/01

U.S. Cl. 18-12

8 Claims



A screw having increasing lead or pitch is employed on an

extruder with central feed or discharge to provide a self-balancing extrusion apparatus which does not require heavy thrust bearings.

3,577,589

APPARATUS FOR INCREASING THE DENSITY OF THERMOPLASTIC FOAM


Mario Serrano, and William D. Wolf, Simsbury, Conn., assignors to Monsanto Company, St. Louis, Mo.

Division of Ser. No. 705,443, Feb. 14, 1968, abandoned. Filed Mar. 12, 1969, Ser. No. 827,081

Int. Cl. B29f 3/02

U.S. Cl. 18-125M

4 Claims



A method and apparatus for densifying thermoplastic foam wherein the foam cells are crushed by mulling within a narrow chamber formed by plates or members mounted for relative rotation with respect to each other. The densified foam emerges as a high density curdlike extrudate at the periphery of the members.

3,577,590

HIGH-PRESSURE CHAMBER


Victor C. D. Dawson, Silver Spring, and Arnold E. Seigel, Chevy Chase, Md.

Filed June 27, 1968, Ser. No. 740,606

Int. Cl. B29c 3/00

U.S. Cl. 18-16.5

3 Claims



A high-pressure chamber having an inner tubular member circumscribed by a concentric outer tubular member of fully autofrettaged fabrication with a segmented circumferentially complete cylinder of high compressive strength material extending between the inner and outer tubular members.

3,577,591

FLAT BED TYPE CASTING MACHINE IMPROVEMENTS

Charles L. Ricards, South Plainfield, and Daniel McColley, Plainfield, N.J., assignors to Wood Industries, Inc., Plainfield, N.J.

Filed Mar. 29, 1968, Ser. No. 718,027


Int. Cl. B29h 5/00

U.S. Cl. 18-17

6 Claims

A casting machine for casting thin plastic articles having a

the lower platen with a clamshell motion and having fluid motor means associated with the upper platen whereby the



rate of closure of the upper platen may be progressively varied. A floating clamping frame associated with the lower platen for securing a matrix to the lower platen.

3,577,592

APPARATUS FOR REPAIRING TIRE CASINGS


Benjamin Whittle, R.R. #3, Paw Paw, Mich.

Filed Jan. 10, 1969, Ser. No. 790,198

Int. Cl. B29h 5/16

U.S. Cl. 18-18

6 Claims



Flexible plug rubber is cured into the void formed by retaining the rubber between inner and outer plates, while holding the plates together by tension strands passed through the casing. The strands are cut off after the plug is set. The strands may pass centrally through the void and the plug material, or in spaced relation through uninjured parts of the casing.

A variation shows the tension strand also passing through an inner patch so that the patch is attached to the inside of the casing at the same time that the plug rubber is cured in place.

3,577,593

APPARATUS FOR HEAT AND VACUUM-PRESSURE MACHINE MOLDING

James W. Jackson, East Walpole, Mass., assignor to Bird & Son, Inc., East Walpole, Mass.


Filed Oct. 29, 1968, Ser. No. 771,576

Int. Cl. B29c 17/04, 23/00

U.S. Cl. 18-19

7 Claims

Apparatus and methods for heat and vacuum-pressure machine molding of hollow articles from thermoplastic sheet material, involving a mold (normally with alternate vacuum and air pressure sources) having one or more relatively movable complementary molding members for forming undercut, reverse band, flanged or reentrant portions of said articles, with said member or members being mounted for relative movement, with respect to the molding surface of the mold, into molding position, and thereafter out of such molding position so that a molded article may be freely removed from said mold, said complementary molding member or



vacuum, with or without the aid of a plug-assist, e.g. where a female external mold is employed.

3,577,594

APPARATUS FOR FORMING HOLLOW ARTICLES


John D. Al-Roy, Union City, N.J., assignor to Monsanto Company, St. Louis, Mo.

Filed Dec. 30, 1968, Ser. No. 787,840

Int. Cl. B29c 17/04, 3/02, 1/16

U.S. Cl. 18-19

8 Claims



Apparatus for thermoforming synthetic plastic sheet material into hollow articles includes a platen member providing a rigid surface and a mold member having the desired cavity and a cutting blade edge. The two members are movable relative to each other and one of the members is mounted for pivotal movement relative to the other about the axis of movement of the movable member so as to accommodate misalignment of the two members.

3,577,595

ROTATABLE CROWN-FILLING MACHINE AND METHOD FOR APPLYING SEALING RINGS OF PLASTIC TO THE PERIPHERY OF THE CROWN INTERIOR

Donald C. Smith, Pottsville, and Robert E. Koshada, Orwigsburg, Pa., assignors to Zapata Industries, Inc., Frackville, Pa.

Filed Aug. 26, 1968, Ser. No. 755,244


Int. Cl. B29c 3/00

U.S. Cl. 18-20

9 Claims

A machine for forming sealing rings in container closures comprising a rotatable-type carrier having a multiplicity of locations for receiving closures to be provided with sealing rings, means at each location for supplying a stream of fluid gasket-forming material to the peripheral portion of each closure at each location, means for rotating each closure on its axis a plurality of times during the supply of said stream thereto and means for controlling the delivery of said stream

of gasket material to each closure on the carrier while it is rotating a predetermined plurality of times, so that a ring of



gasket material of substantially uniform dimensions throughout is deposited in each closure.


3,577,596

TWO-PHASE MOLD PRESS

Calvin P. Bullard, East Longmeadow, and Francis P. Szubelick, Springfield, Mass., assignors to Vigeant Gaston, East Longmeadow, Mass., a fractional part interest
Filed June 26, 1968, Ser. No. 740,179
Int. Cl. B29f 1/00

U.S. Cl. 18—30

10 Claims



A two-stage power-operated press for closing molds as used in the manufacture of plastic articles by injection molding. The press incorporates a first fluid motor means for advancing and retracting the movable platen at a rapid traverse rate at relatively low pressure and a second fluid motor means for imparting a high-locking pressure to the movable platen at the end of its stroke in order to close the mating mold segments carried by the movable and fixed platens, respectively. The arrangement of the operating parts of the press is such as to achieve maximum platen stroke in order to obtain increased mold opening for accommodating molds for the manufacture of deep-draw articles.

3,577,597

SUPPORT FOR INJECTION-MOLDING MACHINE


Donald A. Draudt, 27180 Pompton Drive, and Herbert T. Draudt, 28520 Lynhaven, North Olmsted, Ohio
Continuation-in-part of application Ser. No. 551,386, May 19, 1966, now Patent No. 3,406,429. This application Sept. 20, 1968, Ser. No. 761,095
Int. Cl. B29f 1/00

U.S. Cl. 18—30

4 Claims

Apparatus for molding articles from thermoplastics wherein the moldable plastic material is plasticized and in-

jected into a mold cavity. The plasticizing and injecting unit is pivotally mounted in a frame fixed relative to the mold and




3,577,598

APPARATUS FOR THE AUTOMATIC DETERMINATION OF FIBER LENGTH DISTRIBUTION OF A FIBER POPULATION

Eric Schwarz, 9 Hochstrasse 8044, Zurich, Switzerland
Filed Nov. 13, 1968, Ser. No. 775,411
Claims priority, application Austria, Nov. 17, 1967, 10373/67
Int. Cl. D01h 19/00

U.S. Cl. 19—65

9 Claims



A drum containing fibers has a perforated wall portion swept exteriorly by a comb which picks up protruding fibers and forms a beard. Carding means on a successive wall portion is swept by the comb to parallelize the fibers in the beard. The comb sweeps past another successive wall portion where the beard is scanned optically to develop electric signals which are a function of the fibers in the beard. The beard is removed as the comb sweeps past another successive wall portion. Whereupon the cycle can be repeated.

3,577,599

APPARATUS FOR MIXING FIBROUS COMPONENTS

Georg Goldammer, Ingolstadt, and Gunther Mahrt, Etting, Germany, assignors to Schubert & Salzer Maschinenfabrik Aktiengesellschaft, Ingolstadt, Germany
Filed Jan. 16, 1969, Ser. No. 792,234
Int. Cl. D01g 13/00


U.S. Cl. 19—145.5

7 Claims

The invention relates to a process for the accurate mixing

of fibrous components in a predetermined ratio, and to ap-

tail end portion is generally formed in an arcuate manner to facilitate its being returned through the article once it has been inserted therein. The tail end portion may be provided in one of three ways; (1) a preformed metallic member is joined to the end of the body portion; (2) the end of the



paratus for the performance of the process.

3,577,600


APPARATUS FOR RAPID AUTOMATED MEASUREMENT OF DRAFTING FORCE AND DRAFTING FORCE VARIABILITY

John S. Graham, Clemson, S.C.

Filed Sept. 26, 1968, Ser. No. 762,951
Int. Cl. D01h 5/18

U.S. Cl. 19—293

1 Claim



An apparatus for measuring the drafting force and drafting force variability in conventional drafting systems. The force sensing assembly together with the drafting rolls and the associated roll driving mechanism of the apparatus are oscillatingly supported on a resilient directionally restricted pivot, so that drafting force is transformed into bending movement which movement causes angular displacement of the assembly around the resilient pivot as a center. Force measurement is accomplished via an electronic strain gauge. The electrical signals generated by the strain gauge are employed as analogs of drafting force and drafting force variability and accordingly analyzed automatically or semiautomatically.

3,577,601

ARTICLE FASTENING DEVICE

Remo Mariani, Berkeley Heights, and George H. Geisinger, Union County, N.J., assignors to Thomas & Betts Corporation, Elizabeth, N.J.


Filed Mar. 12, 1969, Ser. No. 806,369
Int. Cl. B65d 63/00; A61b 17/08

U.S. Cl. 24—16

11 Claims

The disclosure is directed to a device for fastening two or more articles together and which does not require threading apertures. The device is constructed of a generally elongated flexible body portion terminating at a first end in a head member having a transverse aperture therein to permit passage of the body portion therethrough. The opposite end of the body portion terminates in a substantially rigid tail end portion having thereon a cutting edge such as a point. The

A shoe buckle, especially for ski boots, which includes: an approximately triangular plate, and bearing means connected to said plate and having a substantially U-shaped contour, said bearing means comprising two-spaced supporting members at least approximately perpendicular to the respective adjacent major surfaces of said plate and provided with axially aligned bores for receiving a pivot pin, said bearing means also comprising a flat arm integral with said supporting members and forming the transverse arm of said U-shaped contour, said flat arm being spot-welded to said plate at an area thereof which is wider than the length of said flat arm.




3,577,603 FASTENER

Clifford Alexander Seckerson, Iver Heath, and Robert C. Collyer, Harefield, England, assignors to United-Carr Incorporated, Boston, Mass.

Filed Sept. 29, 1969, Ser. No. 861,749
Claims priority, application Great Britain, Oct. 2, 1968, Oct. 22, 1968, Nov. 11, 1968, June 27, 1969,
46829/68;50022/68;5322568;32682/69
Int. Cl. F16b 21/00; A44b 21/00

U.S. Cl. 24-73

13 Claims



A two-part fastener for attaching two apertured panels together so that one panel is readily removable from the other, the fastener comprising a stud portion having a shank adapted for snap engagement rough a circular aperture in one of the panels, a flange at one end of the shank adapted to abut the outer surface of the said one panel to limit insertion of the shank therethrough and a stud projecting from the opposite side of the flange from the shank and adapted to project outwardly through a circular aperture in the other panel when the other panel is resting on the flange of the stud portion and a socket portion formed with a bore open at one end shaped to receive the stud of the stud portion and with an external flange which is spaced from the said one end of the bore and adapted to clamp the said other panel against the said flange of the stud portion, the stud and the bore in the socket portion being provided with means which interengage when the stud is within the bore to resist withdrawal of the socket portion from the stud.

3,577,604


WRITING IMPLEMENT HOLDER FOR BOOKS OR LIKE ARTICLES

Jeffrey Owen Brosk, 150 E. 69th St., New York, N.Y.
Filed Sept. 4, 1968, Ser. No. 757,432

Int. Cl. A44b 21/00

U.S. Cl. 24-81

5 Claims



An elastic holder for writing implements adapted to encompass a book and capable of use as a bookmark.

3,577,605

TOW CABLE TERMINATION

Raymond C. Fischer, Severna Park, and Norton J. Levenson, Baltimore, Md.

Filed Mar. 25, 1969, Ser. No. 810,268


Int. Cl. F16g 11/00

U.S. Cl. 24-114.5

2 Claims

This invention is concerned with a termination to be applied to a double stranded counterwound electromechanical tow cable. By the insertion of a wedgelike member between the strands a hump is built into the cable which may be

gripped at the point of the hump by a split tow ball without



chance of slipping of the strands, while still permitting even winding of the cable on a winch.

3,577,606

STRING AND THE LIKE DETENTION SYSTEM


Cyril M. Tyrrell, Sr., 13 Kaden Court, Novato, Calif.

Filed Feb. 28, 1969, Ser. No. 810,081

Int. Cl. F16g 11/00

U.S. Cl. 24-117

10 Claims



A string and the like detention system particularly suited for detention of shoe laces in a selective secured and releasable condition with respect to a shoe including a spoollike lashing button fixed to an article and including a circular base, a centrally open circular hub portion above and integral with the base, a flange integrated with and positioned above the hub and vertically spaced from the base, a plurality of resilient members in the nature of prongs being secured peripherally around, and on the upper surface of, the flange, a recess is provided in the periphery of the flange adapted for coacting with guide means on the base, and constituting a guide for passage therethrough of an end of the string and the like, for subsequent winding of the string about the hub and the prongs, following insertion of a string end through the guide means on the base and the recess in the flange for releasable detention of a string end, release being effected by inward pressure on the resilient prongs to permit the wound string end to be vertically lifted from engagement with the prongs and subsequent removal from the button.

3,577,607

SEPARABLE FASTENING FABRIC

Yasaburo Ikoma, and Ikuta Yabu, Sumiyoshi-ku, Osaka, Japan, assignors to Ikoma Orimono Co., Ltd., Osaka, Japan


Filed June 13, 1968, Ser. No. 736,838

Claims priority, application Japan, June 19, 1967, 52414

Int. Cl. A44b 17/00

U.S. Cl. 24-204

6 Claims



A separable fastening fabric for engagement of a first and second fabric in face-to-face relation comprising a number of

3,577,610

APPARATUS FOR MANUFACTURING PRESTRESSED CONCRETE MEMBERS


Stanley V. Margolin, Auburndale; Paul W. Glaser, Islington, and Leonard V. Gallagher, Wollaston, Mass., assignors to Arthur D. Little, Inc., Cambridge, Mass.

Filed Apr. 16, 1968, Ser. No. 721,834

Int. Cl. B28b 15/00, 23/06

U.S. Cl. 25-2

16 Claims



3,577,608 SEPARABLE FASTENER ELEMENTS

Jean Pierre Texler, Neuilly, France, assignor to Societe Gobin Daude (Societe Anonyme), Paris, France


Filed Dec. 16, 1968, Ser. No. 784,026

Claims priority, application France, Dec. 14, 1967, 132,317

Int. Cl. A44b 17/00

U.S. Cl. 24-221

2 Claims



The device of this invention includes preformed plastic fastener elements, one of which includes a socket containing diametrically opposed rigid means disposed therewithin and the other including an operator which is assemblable into locking engagement with the rigid means, said operator including bendable bifurcated leg means including lock means for securing said operator relative to said socket to permit relative rotation between the socket and the operator in order to permit assembly of an eyelet over the perimeter of said socket.

3,577,609

HOOK AND EYE TYPE FASTENER

Franz Gottfried, Stolberg-Dorff, Germany, assignor to Firma Kurt Dorpinghaus, Hucksowagen, Germany


Filed Mar. 7, 1969, Ser. No. 805,256

Claims priority, application Germany, Mar. 8, 1968, D37699

Int. Cl. A44b 13/00

U.S. Cl. 24-228

1 Claim



The fastener consists of interlocking hook and eye elements. The eye element comprises a closed loop of resilient wire. The loop is intended to form merging curved and stepped formations to provide an end portion which is secured to the fabric, and intermediate portion and an eye. The loop is further indented at the junction of the intermediate portion and eye to provide an opening of a given dimension. The hook element is also a closed loop having an end portion to be secured to the fabric, a neck portion slightly larger than the opening in the eye element, and a hook which can pass through the intermediate portion. The edge of the eye is angularly bent to the extent of the diameter of the wire. The neck is indented to a depth equal to the diameter of the wire. To close the fastener, the hook is inserted within the intermediate portion, and upon the closing movement, the neck spreads the opening to permit the neck and the hook to pass into the eye. The opening returns to its initial dimension, thereby retaining the parts in closed position. In the closed position, the bent edge lies within the indentation to permit the alignment of the elements to present a flat closure.

3,577,611

CONCRETE SLAB FORMING MACHINE WITH REMOVABLE SOFFIT EDGES

Frederick Maxwell Hewitt, Winnipeg, Manitoba, Canada, assignor to Spiroll Corporation, Ltd., Winnipeg, Manitoba, Canada

Filed July 28, 1967, Ser. No. 656,798

Claims priority, application Great Britain, Aug. 5, 1966, 35186/66


Int. Cl. B28b 7/00

U.S. Cl. 25-41

19 Claims

This device is a removable soffit edge for forming accurate, smooth, lower corners to a concrete slab or the like being extruded or slip formed on a bed. It consists of an elongated form placed on the bed and engaged within a groove

on the underside of the side plates of the machine which maintains the parallel relationship of the forms as the machine passes thereover. These forms can be any desired shape and in fact can be extended to act as the sidewalls of a slab if it is desired that the side faces of the slab be accurately and smooth finished. After the slab has been formed and



cured sufficiently, the slab can be lifted from the bed leaving the forms in place or, alternatively, the forms can be removed and replaced with forms having a different configuration or different spacing. The device will also permit the use of a different soffit form as either the complete form itself may be replaced or a "liner," such as a plastic or rubber sheet, can be inserted underneath the soffit edges.

3,577,612


APPARATUS FOR MAKING MULTIDUCT CONDUIT
Victor G. Susin, 834 Santa Maria Drive, Naperville, Ill.

Filed Sept. 25, 1968, Ser. No. 763,494

Int. Cl. B28b 7/18, 7/28; B28b 7/06

U.S. Cl. 25-41

11 Claims



Improved pressure heads and platens for use in concrete conduit mold assemblies. The heads control flexible platens to make it possible to completely fill the end web sections of the molded conduit and nonetheless obviate concrete flashing.

3,577,613

PORTABLE MOLDING APPARATUS


William P. Hidden, Wenham, Mass., assignor to Arthur D. Little, Inc., Cambridge, Mass.

Filed Apr. 16, 1968, Ser. No. 721,767

Int. Cl. B28b 7/00, 23/06

U.S. Cl. 25-118

11 Claims



A portable molding apparatus for prestressed concrete members including a hollow mold body for receiving a

charge of concrete and reinforcing strand for emplacement in the molded concrete. Mold end members, at least one of which is moveable, define opposite end portions of the body and include strand gripping means to receive and engage a portion of reinforcing strand to retain a strand suspended within the mold cavity. Releasing means provided on each end member are engageable with the gripping means to disengage the gripping means from the strand, and at least one of the end members is moveable with respect to the mold body with the releasing and gripping means engaged so that the strand can be withdrawn from the gripping means and the cast concrete member removed from the mold body.

3,577,614

YARN-TEXTURING JET DEVICE


Samuel T. Price, Wilmington, Del., assignor to E. I. du Pont Nemours and Company, Wilmington, Del.

Filed Nov. 10, 1969, Ser. No. 875,093

Int. Cl. D02g 3/00

U.S. Cl. 28-1.4

6 Claims



Improved fluid jet yarn-texturing devices have a nozzle portion which is moved to a stringup position for sucking a yarn end through the device and is then returned to a preset operating position for texturing the yarn when stringup has been completed.

3,577,615

PROCESS FOR COMINGLING CRIMPED YARN

Fred W. LeNoir, Hopewell, Va., assignor to Allied Chemical Corporation, New York, N.Y.


Division of Ser. No. 535,480 Oct. 21, 1969, Pat. No. 3,473,315

filed June 11, 1969, Ser. No. 840,099

Int. Cl. D02q 1/16

U.S. Cl. 28-72.12

4 Claims



A process is provided for comingling a crimped multifilament yarn in a tubular passageway wherein the yarn is maintained under a slight tension while being subjected to a stream of gas directed against said yarn at an angle whereby substantially all of said gas flows through the tubular passageway countercurrent to the travel of the yarn.

3,577,616

ARC DISCHARGE LAMPS

Kenneth Scott, and Dennis A. Ramsey, London, England, assignors to British Lighting Industries Limited, London, England

Filed Jan. 5, 1968, Ser. No. 696,023

Claims priority, application Great Britain, Jan. 17, 1967,

2491/67


Int. Cl. H01j 9/18, 9/36

U.S. Cl. 29-25.15

5 Claims

A method of mounting an arc tube, having pinch seals, between two parallel struts by using a staple having a bar

with two legs, passing the legs through the plane of the struts,



and binding the legs back around the struts to secure the arc tube thereto.

3,577,617

MACHINE TOOLS

William Owen McKenzie Jones, Hurle, Berkshire, England

Filed July 3, 1968, Ser. No. 750,408


Claims priority, application Great Britain, July 12, 1967,

32032/67

Int. Cl. B23b 29/24

U.S. Cl. 29-54

10 Claims



The invention relates to a tool-changing mechanism for use with machine tools and in particular with lathes. The mechanism comprises a conveyor which can carry an unspecified number of tools sequentially to a tool-receiving station at which they are located in order to perform a cutting operation. The tools are intended normally to be preset away from the machine tool and in this condition can be mounted on the conveyor ready for a sequence of machining operations.

3,577,618

TOOLHOLDER CONSTRUCTION


Robert W. Cashman, Saginaw, Mich., assignor to Saginaw Machine and Tool Company, Saginaw, Mich.

Filed Aug. 19, 1968, Ser. No. 753,571

Int. Cl. B26d 1/00

U.S. Cl. 29-96

17 Claims



A toolholder comprising an elongated body terminating at its forward end in a recess provided with a rearward arcuate wall and within which is mounted a correspondingly-shaped tool bit support having a pocket defined by a base and a pair

of upstanding sides which converge both upwardly and rearwardly. A tool bit having a shape corresponding to the shape of the pocket is removably accommodated in the latter and is provided with a central opening for the reception of a lug formed on a clamp which overlies the tool bit and is anchored to the holder body. The clamp and the clamp anchor are so oriented with respect to the tool bit that anchoring of the clamp causes the latter to rock about a fulcrum in such manner as to urge the tool bit forcibly against the base of the pocket and forcibly against the sidewalls of the pocket.

3,577,619

METHOD OF MANUFACTURING COMPOSITE HARDMETAL ROLLS

Per-Olof Strandel, Nasby Park, Sweden, assignor to Sandvikens Jernverks Aktiebolag, Sandviken, Sweden


Division of Ser. No. 614,227, Feb. 6, 1967, Pat. No. 3,461,527

this application May 12, 1969, Ser. No. 823,629

Int. Cl. B23p 11/00; B21b 27/00, 31/08

U.S. Cl. 29-148.4

2 Claims



A method for manufacturing working rolls for rolling mills of the type formed by a roll core with a roll ring attached to the core, the roll ring being made of some hard material, such as hard metal or ceramic material. The roll ring is mounted with a clearance fit on the heated roll core and is secured thereto by pressure means which act axially against only the flat end surfaces of the roll ring, the pressure means imparting to the roll ring the force necessary for fixing and prestressing the ring so that it is capable of withstanding the rolling forces.

3,577,620

BALL CASTER AND METHOD MAKING THE SAME

George J. Hoffman, Northfield; William O. Setele, Independence, and Lester E. Law, North Royalton, Ohio, assignors to Kindale Industries, Inc., Independence, Ohio


Division of Ser. No. 774,031, Nov. 7, 1968, Pat. No. 3,514,804,

June 2, 1970, this application Aug. 27, 1969, Ser. No. 853,445

Int. Cl. B23p 11/00, 19/00

U.S. Cl. 29-148.4A

3 Claims



Method of assembling the caster parts and locking them in assembled condition of a ball-type caster.

3,577,621

STRETCH METHOD FOR MAKING A TUBULAR PRODUCT


William J. De Gain, Warren, Mich., assignor to Koppy Tool Corporation, Ferndale, Mich.

Continuation-in-part of application Ser. No. 627,718, Apr. 3, 1967, now abandoned. This application May 14, 1969, Ser. No. 824,440

Int. Cl. B23p 17/00

U.S. Cl. 29—155

10 Claims



A tubular metal blank to be formed into a vehicle steering column or other corrugated tubular product is first deformed by radially inwardly moving dies to produce a plurality of substantially equally spaced shallow annular depressions separated by slightly raised crowns. The blank is then axially compressed to form and close a plurality of convolutions under a selected load within predetermined limits and to a selected closed length within predetermined limits, the variations being dependent on the strength of the material. Finally, the blank is stretched, expanding the convolutions to a plurality of generally similar spaced corrugations, with a selected stretch pressure within predetermined limits and to a selected expanded length within predetermined limits. If the end product is used as an energy-absorbing tube, the above method minimizes the variations in a selected compressive axial load required to collapse the finished column.

In another embodiment, a series of annularly spaced notches are cut in the convolutions after they have been compressed to abutting configuration to determine the hoop strains developed in the walls of the finished product corrugations when subjected to the axial collapse loading.

3,577,622

SWAGING DEVICE FOR CABLE FITTINGS


Frank E. Shaffer, P.O. Box 1546, Costa Mesa, Calif.

Filed Feb. 20, 1969, Ser. No. 801,070

Int. Cl. B23p 19/00

U.S. Cl. 29—200

11 Claims



A swaging device for cable fittings which includes a pair of die blocks formed on their adjacent sides with confronting cavities which cooperate to receive and confine the shank of the cable fitting, one of such blocks including a plurality of pin-receiving threaded bores aligned with the cavities and projecting transversely thereof. Means are provided for fastening the blocks together and swaging pins are insertable into the passages whereby the shank of a cable fitting may be placed in the cavity, the blocks secured together, and the pins screwed inwardly in the passages to deform the wall of the shank inwardly to compress the cable while the shank is confined against undue flattening or radially outward deformation.

3,577,623

APPARATUS AND METHOD FOR AUTOMATICALLY ASSEMBLING ANTIFRICTION BEARINGS

Yosio Ono; Hiroshi Nakamura; Takasi Inoue; Yosio Horie; Juniro Matui, and Fumito Uono, Iwata, Shizuoka, Japan, assignors to Toyo Bearing Manufacturing Company Limited, Osaka-shi, Japan


Filed Jan. 30, 1969, Ser. No. 795,162

Claims priority, application Japan, Feb. 3, 1968, Feb. 24, 1968, 43/6853; 43/13988

Int. Cl. B23p 19/04; B23g 17/00

U.S. Cl. 29—201

11 Claims



An apparatus for automatically assembling antifriction bearings comprising an electric measuring mechanism for measuring the outer diameter of the groove in an inner ring and deriving an electric signal corresponding to the measured size, an electric measuring mechanism for measuring the inner diameter of the groove in an outer ring and deriving an electric signal corresponding to the measured size, an arithmetic unit for comparing the two measured values derived from said measuring mechanisms and deriving a single electric signal corresponding to the difference between the electric signals, a mechanism for selecting rolling elements to be combined with the pair of inner and outer rings by means of said differential electric signal and counting and storing such rolling elements in order of measurements of successive pairs of inner and outer rings, a mechanism for pairing the measured inner and outer rings, and a mechanism for feeding the selected and counted rolling elements into the eccentric clearance between the thus paired inner and outer rings and incorporating a retainer therein, whereby antifriction bearings are automatically assembled by a series of operations of said mechanisms.

3,577,624

CENTER FEED DRIVER ASSEMBLY


Eugene E. Bentschneider, Manchester, Mich., assignor to Manchester Tool & Die, Inc., Manchester, Mich.

Filed Aug. 19, 1969, Ser. No. 851,317

Int. Cl. B23q 7/10

U.S. Cl. 29—211

11 Claims



Stud driving apparatus that includes a center feed driver which has a center bore into which studs can be fed singly, and a positioning rod which is movable in the bore relative to the driver for positioning the stud at one end of the driver.

3,577,627

METHOD AND APPARATUS FOR ALIGNING STRIP IN STRIP JOINING EQUIPMENT


Foster R. Woodward, Warren, Ohio, assignor to The Taylor-Winfield Corporation, Warren, Ohio

Filed Mar. 26, 1968, Ser. No. 716,116

Int. Cl. B23q 3/00

U.S. Cl. 29—464

10 Claims



Method and apparatus for joining metal strip in general end-to-end relationship involving first aligning the strip lengths both transversely and angularly (to prevent dogleg) whereby the joint will be made so that the centerline of the strips will coincide with the longitudinal centerline of a machine. The control system includes, at each side of the joining means or welder, two sensors along one side of the strip which are interconnected by a sprocket and chain or equivalent means so that as one of the sensors follows the edge of the strip, the other will move correspondingly whereby both sensors will always be equidistant from the longitudinal centerline of the machine and one will control lateral movement of an auxiliary strip clamp to move the strip accordingly. A third sensor on the opposite side of the strip and of one of said sensor, and similarly linked thereto by a sprocket and chain or the like, is effective to control the main clamp to finally move the strip laterally so that its centerline will coincide with that of the machine. Similar controls are provided at the exit (tail end) and the entry (head end) of the machine. A fourth sensor control is optional to prevent the necessity of circuit switching.

3,577,626

METHOD OF MAKING A TRIM MOLDING


Darl L. Link, Charlotte, Mich., assignor to Hoover Ball and Bearing Company, Saline, Mich.

Filed Feb. 6, 1969, Ser. No. 797,137

Int. Cl. B23p 9/00

U.S. Cl. 29—445

10 Claims



A method of manufacturing a trim molding having an anodized aluminum channel member in which is locked a vinyl bumper strip. The method includes the steps of extruding the aluminum in the form of an open channel with the bottom wall inclined upwardly from the sides to the center, inserting the vinyl strip into the open channel, and pressing down on the strip so that the bottom wall of the channel is flattened, causing the sides of the channel to close on the vinyl strip, thereby locking it in place in the channel. Appropriate buffing, anodizing of the aluminum, and cutting to length of the interlocked parts then follows. A product made according to the method is also disclosed.

3,577,628

MOUNTING OF PROPELLERS, IMPELLERS, WHEELS AND THE LIKE IN TORQUE AND THRUST TRANSMITTING CONNECTION ON SHAFTS

Thomas Walter Bunyan, London, England, assignor to P & O Pilgrim Valve Limited, London, England


Filed Feb. 27, 1969, Ser. No. 802,904

Claims priority, application Great Britain, Mar. 11, 1968, 11,816/68

Int. Cl. B23k 31/02

U.S. Cl. 29—471.1

8 Claims



A method of mounting a propeller, impeller, wheel or the like on a shaft with a separate metallic externally tapered member.

sleeve in torque and thrust transmitting connection on the shaft and force-fitted for torque and thrust transmitting connection in a correspondingly internally tapered hub of the member being mounted, in which a layer of a hardenable or cold-setting synthetic resin composition such as Araldite in liquid condition is introduced between the outer surface of the sleeve and the inner surface of the hub and the force-fitting pressure between the sleeve and hub maintained until the resin composition has set.

3,577,629

BONDING OXIDIZABLE METALS TO INSULATORS

George Wallis, Lexington, and John J. Dorsey, Waltham, Mass., assignors to P. R. Mallory & Co., Inc., Indianapolis, Ind.

No drawing. Filed Oct. 18, 1968, Ser. No. 768,911

Int. Cl. B23k 31/02

U.S. Cl. 29—472.9

12 Claims

An insulating member, such as a glass or fiber-optic, is bonded to a metallic member without excessive oxidation thereof by first heating the insulating member to a relatively low temperature and impressing a voltage across the members, causing an attraction between them which largely excludes atmospheric oxygen from the region to be bonded. The lowered resistivity of the insulator at this temperature also causes a low-density electric current to flow from one member to the other. The insulating member is then heated to a higher temperature while a voltage is maintained across the members, at which temperature a permanent bond is formed between the members in a relatively short time.

3,577,630

METHOD OF ATTACHING TRANSMISSION BELT AND PIN


Bernard S. Appleton, 926 Midway, Woodmere, N.Y.

Division of 699,970, Jan. 23, 1968, Pat. No. 3,479,893. Continuation-in-part of Ser. No. 566,960, July 21, 1966, Pat. No. 3,451,282. Application Sept. 4, 1969, Ser. No. 855,346

Int. Cl. B21d 39/00; B23p 11/00

U.S. Cl. 29—517

3 Claims



This invention relates to flexible transmission belts adapted for use with sprocket wheel means. The transmission belts comprise transmission pin means with, or without, rollers, held together serially by an elongated body construction such as cable made of wire, cord, fabric or other suitable material. The invention contemplates a method of attaching the pins to the belt or cable, or cables by providing a pin with an opening adapted to encircle the cable, greater in diameter than the diameter of the cable, and then applying pressure to the pin until the material of the pin flows into at least a portion of the clear space between the cable and the opening in the pin so that a mass of material of the pin will grip the cable securely.

3,577,631

PROCESS FOR FABRICATING INFRARED DETECTOR ARRAYS AND RESULTING ARTICLE OF MANUFACTURE

Ernest G. Bylander, and Hall E. Jarman, Dallas, Tex., assignors to Texas Instrument Incorporated, Dallas, Tex.

Filed May 16, 1967, Ser. No. 638,915


Int. Cl. B01j 17/00; H01c 7/08

U.S. Cl. 29—572

22 Claims

An infrared detector array is fabricated by alloying a slice of mercury doped germanium to a degenerate germanium

substrate. After being lapped to the desired thickness, the slice is etched through to the substrate to form individual detector bars using a metal mask which is then partially removed to form a gold contact strip on each bar. Output conductors are formed by patterning copper films there-



mocompression bonded to high temperature plastics, gold plating the conductors, and connecting the gold plated conductors to the gold contact strips by gold jumper wires thermocompression bonded to the conductors and to the contact strips.

3,577,632

METHOD OF PRODUCING SEMICONDUCTOR DEVICE IN GLASS HOUSING


Ernst Hofmeister, Munich, Germany, assignor to Siemens Aktiengesellschaft, Berlin, Germany

Continuation of application Ser. No. 635,919, May 3, 1967, now abandoned. This application Sept. 18, 1969, Ser. No. 859,596

Int. Cl. B01j 17/00; H01l 7/20

U.S. Cl. 29—585

4 Claims



An electrical conductor is extended through an open end of a glass housing into permanent electrical contact with a semiconductor body of a semiconductor device affixed to and supported by an electrically conductive support member. The open end of the housing is hermetically sealed by heating such open end. The support member passes through the opposite closed end of the housing. An electrical current is passed through the semiconductor device via the support member and the electrical conductor during the hermetic sealing of the open end of the housing.

3,577,633

METHOD OF MAKING A SEMICONDUCTOR DEVICE

Makoto Homma, Tokyo, and Toshiaki Saito, Kodaira-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of application Ser. No. 685,878, Nov. 27, 1967, now abandoned. This application Oct. 1, 1969, Ser. No. 864,288

Claims priority, application Japan, Dec. 2, 1966, 41/78682


Int. Cl. B01j 17/00; H01l 1/10

U.S. Cl. 29—588

8 Claims

A method of assembly of a transistor, wherein a lead support member and pairs of collector lead molds are punched in advance in a tape-shaped metal sheet; a lead support member corresponding to said lead support member and

pairs of emitter-base lead molds are punched in another tape-shaped metal sheet; a collector electrode of a planar type transistor is put into contact with the center of said collector lead; the position of the end parts of the base and emitter leads with respect to the position of said collector lead is defined by piling up said two support members and thereby



the end parts of said two leads are put into contact with said base and emitter electrodes of the transistor; all of said leads and electrodes corresponding thereto are coupled mutually by soldering; said transistor part is molded with resin; and said leads are removed from said respective support members.

3,577,634

METHOD OF MANUFACTURING A MAGNETIC HEAD ASSEMBLY


Duane R. Secrist, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed June 18, 1969, Ser. No. 834,476

Int. Cl. H01f 7/06

U.S. Cl. 29—603

6 Claims



A magnetic head slider assembly, used in disc storage files for air bearing noncontact recording is formed from three parts that enclose a glass-bonded ferrite core. During manufacture, a high temperature glass is used to form the nonmagnetic gap in the core, and a low temperature glass is disposed adjacent to the gap glass between the pole pieces of the core. When the core is positioned within a cavity of the slider, the core containing both glasses is heated sufficiently to cause only the low temperature glass to flow and fill the cavity, thereby bonding the core to an inner wall of the cavity within the slider assembly.

3,577,635

METHOD FOR ISOSTATIC COMPRESSION, SUCH AS THE MANUFACTURE OF POWDER BODIES

Carl Bergman, and Harry Claesson, Vasteras, Sweden, assignors to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden

Filed Oct. 30, 1968, Ser. No. 771,966

Claims priority, application Sweden, Nov. 8, 1967, 15322/67


Int. Cl. H01c 15/04, 17/00

U.S. Cl. 29—615

4 Claims

A body to be compressed is inserted within a flexible container containing a compression medium compatible with the

body and the container is then placed within an outer com-



pression chamber containing another compression medium compatible with the container and chamber.

3,577,636

RESILIENT CUTTER


Robert P. Detorre, Pittsburgh, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Continuation of application Ser. No. 640,285, May 22, 1967, now abandoned. This application Jan. 7, 1969, Ser. No. 789,468

Int. Cl. B26b 3/00; B26d 3/08

U.S. Cl. 30—164.95

2 Claims



A scoring device with a resilient connection between a support and a scoring head to provide a uniform scoring pressure on a glass surface resulting in a uniform severing line.

3,577,637

RETRACTABLE BLADE KNIFE


Paul A. Braginetz, Augusta County, Va., assignor to Philip Morris Incorporated, New York, N.Y.

Filed Sept. 24, 1968, Ser. No. 761,903

Int. Cl. B26b 3/08

U.S. Cl. 30—162

6 Claims



An industrial blade holder combination with the blade being mounted on a carrier and selectively movable to retracted and operative positions including a position in which the blade is readily removable for replacement, the combination including a blade magazine for replacement blades, the magazine being replaceably mounted in the handle and arranged to enable individual blades to be dispensed therefrom for insertion in the handle while the magazine remains in the handle.


3,577,638

CUTTING TOOL ATTACHMENT FOR A POWER HAMMER

Earl Chandler, 17211 N.W. 37th Ave., Opa-Locka, Fla.
Filed May 1, 1969, Ser. No. 821,044
Int. Cl. B26b 7/00

U.S. Cl. 30—277

6 Claims



A powered panel cutter attachment for a power hammer having an impactor element and including a tubular housing removably attached to the impactor had having a reciprocable plunger oscillatable in a housing which terminates in a substantially C-shaped guide and support foot including a rear guide surface parallel to the path of reciprocation of the plunger and in spaced relation therefrom a T-shaped slot, and in which a tool element body includes opposed, parallel portions reciprocably and guidingly engaged by the respective parallel inner surface and T-shaped slot portions and is detachably connected to the plunger, and in which said tool body terminates in a lower metal-cutting means generally at the axis of reciprocation and below the foot of said housing; the metal-cutting means including on different attachments a cutting element for removing a relatively thin strip of metal, a chisel element and a spot-weld removing element.

3,577,639


FACE BOW WITH THREE-DIMENSIONALLY ADJUSTABLE SUPPORT MEANS

Robert L. Lee, Colton, Calif., assignor to said assignor to Gene W. Arant, Los Angeles, Calif.; said assignor to Juanita F. Arant, Los Angeles, Calif.; said assignor to Robert L. Lee, Los Angeles, Calif. and said assignor to Arlene M. Lee, Los Angeles, Calif., fraction part interest to each

Filed June 13, 1968, Ser. No. 736,613
Int. Cl. A61c 9/00

U.S. Cl. 32—19

15 Claims



Jaw movement recording apparatus including an upper face bow supported from an upper clutch, and a lower face bow supported from a lower clutch. Each clutch carries a vise grip, and a U-shaped bolt or rod has its base or middle portion supported from the vise grip. The legs of each U-shaped bolt or rod project in a generally forward direction for supporting the associated face bow. Four adjustment members are used which are hollow, one being associated with each of these legs. After precise adjustment of the position of the face bow in three dimensions has been achieved,

each of the hollow adjustment members is filled with quick-setting plaster to capture the then existing position of an associated rod end which projects into the cavity of the member.


3,577,640

DENTAL CLUTCHES, AND METHOD AND APPARATUS FOR MAKING

Robert L. Lee, 22937 Grand Terrace Road, Colton, Calif.
Filed Oct. 8, 1969, Ser. No. 864,742
Int. Cl. A61c 11/00

U.S. Cl. 32—32

3 Claims



A dental clutch is disclosed consisting of a rigid tray made of a sheet of plastic material which is shaped to fit over and around the tooth structure of one jaw of a patient; and a preformed plastic stud block having a curved rear face and having a front flat face in which two laterally separated, parallel threaded openings are formed; the stud block being secured to the front vertical surface of the tray so that the threaded openings lie in a plane which is common to the tooth structure.

A method of aligning upper and lower clutches for a patient is also disclosed, in which the threaded openings of the two stud blocks are located in planes which are spaced apart but parallel to each other.

Also disclosed is an alignment fixture for supporting the stud blocks in their aligned relationship during attachment to the respective trays.


3,577,641

COMBINATION TAPE MEASURE AND COMPASS

Leedice Solomon Smith, Rte. 1, Box 132, Elk, Wash.
Filed Sept. 3, 1969, Ser. No. 854,953
Int. Cl. B43I 9/04

U.S. Cl. 33—27

9 Claims



A coiled measuring tape is mounted within a case having an inner recess. A releasable locking clamp is located within the case recess for selectively fixing the tape relative to the case. It is operated by an external movable member that extends within the case for manually locking the tape and simultaneously causing a compass point fixed to it to protrude beyond the case. By use of the compass point, a circle can be scribed at the outer end of the tape. When released, the device permits the tape to be used for measuring purposes in the normal fashion.

3,577,642


IN-PROCESS WORKPIECE GAGING APPARATUS

Joseph V. Tripoli, 329 Troy-Del Way, Williamsville, and John J. Caligiuri, West Seneca, N.Y.

Filed Feb. 12, 1968, Ser. No. 704,726
Int. Cl. G01b 13/00

U.S. Cl. 33—172

6 Claims



There is disclosed a system for gauging the dimensions of a machined surface of a workpiece being machined by a lathe or similar device, while it is being machined. To accomplish this, a machine tool having the cutting edge has affixed thereto a feeler gauge in such position as to encounter the workpiece in a region where it has just been machined. This gauge then moves with the cutting edge over the newly worked surface to give an indication of any variations from tolerance while the work is in process. A pneumatic gauge system is disclosed with particular feeler gauge structure to permit it to be used with various size parts.

3,577,643


BOREHOLE DEFORMATION GAGE

Thomas R. Schmidt, Lafayette, and Walter H. Husing, Walnut Creek, Calif., assignors to Shell Oil Company, New York, N.Y.

Filed May 18, 1967, Ser. No. 639,368
Int. Cl. E21b 47/08

U.S. Cl. 33—178

10 Claims



Internal stress of earth structure in situ may be determined by drilling a pilot hole and inserting a recording borehole deformation gage therein. Subsequently, the pilot hole including the recorder is recovered as a core by drilling out an

annulus of the earth including the pilot hole. The borehole deformation gage is an optical interferometer instrument that is continuously monitored at short time intervals photographically.

3,577,644


WHEEL TREAD CONTOUR APPARATUS

Edward Ratcliffe, and William N. Crawford, Mont. St. Hilaire, Quebec, Canada, assignors to AMSTED Industries Incorporated, Chicago, Ill.

Filed July 26, 1968, Ser. No. 747,937
Int. Cl. B61k 9/12

U.S. Cl. 33—203.11

9 Claims



A testing apparatus has indicators to measure the elevational distance between points on the periphery of wheels having treads and flanges and means to trace and reproduce peripheral section contours of said wheels. The measurements and reproductions may be used to determine wheel wear and high wear areas of the wheels.

3,577,645


LEVELING APPARATUS FOR INSTALLATION OF RAISED FLOORS

Walter S. Zurawski, 7500 N. Elmhurst Road, Box 263, Bensenville, Ill.

Filed July 22, 1969, Ser. No. 843,624
Int. Cl. G01c 5/04

U.S. Cl. 33—209

10 Claims



Apparatus for installing raised floors by means of adjusting leveling jacks, which apparatus includes a leveling head with a sight glass connected to a liquid reservoir, rotatable support shaft for the head having a base adapted for driving engage-

ment with a floor support jack and a rolling contact marker for scribing a level line for installing a drop ceiling.

3,577,646

METHOD OF DAMPING DEVICES HAVING OSCILLATORY MOTION


Harry Nils Eklund, Pacific Palisades, Calif., assignor to Lear Siegler, Inc., Santa Monica, Calif.

Filed Nov. 30, 1967, Ser. No. 687,049

Int. Cl. G01c 19/38

U.S. Cl. 33-226

10 Claims



A method for damping an oscillating mechanical system to bring it to rest at or near its equilibrium position employing iteratively a fixed damping cycle consisting of a first interval of undamped motion followed by a second interval of supercritically damped motion, the process being iterated a sufficient number of cycles to position the system as close as desired to the equilibrium position.

A preferred application of this method of damping is in connection with a meridian-seeking gyroscope, where the first interval of undamped motion consists of free precession of the gyroscope spin axle toward the meridional plane, followed by a second interval of supercritical damping that positions the spin axle closer to the meridional plane than at the release of the motion. By repeating the appropriately timed intervals of the cycle a number of times, the spin axle of the meridian-seeking gyroscope can be brought as close to the meridional plane as desired.

3,577,647

FLOWER-ENCAPSULATING APPARATUS AND METHOD


Mike S. Shimooka, P.O. Box 11184, Honolulu, Hawaii

Filed May 19, 1969, Ser. No. 825,753

Int. Cl. F26b 3/00

U.S. Cl. 34-9

11 Claims



Apparatus and method for encapsulating flowers, particularly orchids, in plastic, comprising mounting a flower on a

jig assembly that holds it in its natural-appearing shape, and sinking the assembly in an alcohol solution to dehydrate the flower so that it can be encapsulated in plastic.

3,577,648

BITUMINOUS MIXING METHOD AND APPARATUS


James D. Brock, Chattanooga, Tenn.

Filed Apr. 23, 1969, Ser. No. 827,448

Int. Cl. F26b 3/00

U.S. Cl. 34-9

11 Claims



A mixing method and apparatus wherein rock aggregates of graded sizes are stored in separate storage bins and conveyed separately through a heating zone, simultaneously heated, and combined together in predetermined portions. A heated bituminous liquid is added to the combined aggregates in predetermined proportions, and the aggregates and bituminous liquid are mixed together to form a hot asphaltic composition.

3,577,649

DEVICE AND METHOD FOR CONTROLLING BULK DENSITY OF DEHYDRATED FOODSTUFFS


James I. Wadsworth; Alexander S. Gallo, Metairie; George M. Ziegler, Jr., Harahan, and James J. Spadaro, New Orleans, La.

Division of Ser. No. 690,536, Dec. 14, 1967, Pat. No. 3,494,050, Feb. 10, 1970, application Aug. 29, 1969, Ser. No. 872,795

Int. Cl. F26b 17/28

U.S. Cl. 34-110

1 Claim



Bulk density of high-sugar-content dehydrated foodstuff is regulated by varying the thickness of the sheet of the said dehydrated foodstuff as it is being discharged from a drum dryer. The thickness of the said sheet is here varied upon varying the angle of attack of the doctor blade in respect to the drum surface of a drum dryer.

3,577,650

PORTABLE AND COLLAPSIBLE CLOTHES DRIER RECEPTACLE


Harry Brahm, P.O. Box 372, Riverside Station, Miami, Fla.

Filed Feb. 18, 1969, Ser. No. 800,073

Int. Cl. F26b 19/00

U.S. Cl. 34-151

4 Claims



A portable and collapsible clothes drier receptacle mounted on a foldable frame and adapted for attachment to a heater-blower unit.

3,577,651

APPARATUS FOR AIR-TREATING SHEET MATERIAL SURFACES AND THE LIKE


John A. Nichols, Canton, Mass., assignor to Industrial Air Company, Inc., Shreveport, La.

Filed Dec. 5, 1968, Ser. No. 781,440

Int. Cl. F26b 13/02

U.S. Cl. 34-155

6 Claims



This disclosure deals with the air-treating of sheet material surfaces and the like by introducing pressurized air upon the material through novel transversely extending and longitudinally spaced nozzle members provided with vertically separated perforated discharge members for providing substantially uniform air flow.

3,577,652

APPARATUS FOR THE DRYING OF SHEET MATERIAL

Raymond Victor Evans, Blackburn, and John Edward Hibbitt, Darwen, England, assignors to Singer-Cobb Limited, Blackburn, Lancashire, England

Filed Mar. 17, 1969, Ser. No. 807,855

Claims priority, application Great Britain, Mar. 18, 1968, 12970/68


Int. Cl. F26b 13/02

U.S. Cl. 34-155

14 Claims

An apparatus for applying heated air to the surface of a sheet material has a dryer surface at an outer wall of a boxlike structure, the dryer surface being defined by alternate openings and apertured surface regions in the said

outer wall, the apertured surface regions being connected together inwardly of the boxlike structure and being isolated from the openings, and a substantially closed air circulation system is developed by the apparatus when in use, air passing outwardly through the apertured surface regions and inwardly through the openings, or vice versa, during the surface treatment of a sheet material arranged in closely spaced



adjacent disposition relative to the dryer surface. For simultaneous treatment of both surfaces of a sheet material two apparatuses as aforesaid will be used, such apparatuses being arranged in opposed closely spaced disposition with the material passing therebetween, and the air circulation systems of the individual apparatuses will be isolated one from the other to enable independent treatment conditions to exist at the opposite sides of the material.

3,577,653

WEB DRYING TUNNEL


John A. McClenathan, and Donald L. Nielsen, Beloit, Wis., assignors to Beloit Corporation, Beloit, Wis.

Filed Jan. 20, 1970, Ser. No. 4,293

Int. Cl. F26b 13/00

U.S. Cl. 34-156

7 Claims



An elongate moving web passing through a drying tunnel is supported along a slightly arched path by pressurized air directed against its concave lower face. The arched path of the web tends to prevent it from bowing transversely, thereby facilitating maintaining it in central relation to the tunnel by means of the air escaping upwardly around its edges. Additionally, the resulting profile of the web inherently reduces its tendency to wrinkle or sag, thus allowing it to be drawn through the tunnel under relatively low longitudinal tension.

3,577,654

FORCED AIR DIFFUSER


James A. Marley, 801 W. Hudson St., Fayetteville, N.C.

Filed Aug. 13, 1969, Ser. No. 849,757

Int. Cl. F24f 13/06; F26b 19/00

U.S. Cl. 34-231

3 Claims



In abstract, a preferred embodiment of this invention is a portable air diffuser including an air duct network fitted at


the intake extremity with a blower and having a series of baffles attached to the outflow extremity with intermediate dampening control means.

3,577,655 MOTION SIMULATOR

Edward G. Pancoe, Chenango Forks, N.Y., assignor to Singer-General Precision, Inc., Binghamton, N.Y.
Filed May 19, 1969, Ser. No. 825,652
Int. Cl. G09b 9/08; F16m 11/32

U.S. Cl. 35-12

5 Claims




A motion system for a vehicle simulator, or the like, of the type wherein independent, extensible actuators are provided for moving the motion platform in each single axis of freedom relative to a fixed base. The present invention provides such a system with greatly improved excursion limits and simultaneous motion in more than one axis (by simultaneous movement of more than one actuator) by erecting the platform and linkage from a settled to a reference position through the use of an additional actuator which is not used for movement of the platform during operation of the system. The arrangement also allows actuator power to be turned off with the platform in a level, settled position without the use of gates or blocks normally required in motion systems of the independent type.

3,577,656 TEACHING APPARATUS

William H. Lyon, Woodbridge, Conn., assignor to KMS Industries, Inc., Ann Arbor, Mich.
Filed Apr. 21, 1969, Ser. No. 817,803
Int. Cl. G09b 3/06

U.S. Cl. 35-9

20 Claims



A teaching apparatus has a student-answer registering device including a number of individually manipulatable keys bearing different marks, with the device indicating a correct student answer on manipulation of any key the mark of which is in the order of the same key mark in a preassigned recurring sequence of successive manipulations of the keys, and the apparatus being adapted for use with successive cards or the like of which each card displays a problem question and as many answers thereto, including one correct one, as there are keys, with the answers on each card being marked the same as the keys, and the marks applied to the correct answers on successive cards conforming to the preassigned key mark sequence.

3,577,657 APPARATUS FOR PROGRAMED INSTRUCTION AND TESTING


George W. Plumly; Jack B. Hunnicutt, and Charles R. Deyo, Fort Worth, Tex., assignors to Edu-Tronics Corporation, Fort Worth, Tex.

Filed May 8, 1969, Ser. No. 823,058

Int. Cl. G09b 7/04

U.S. Cl. 35-9

19 Claims



A programmable system for effecting automated teaching and including modes effecting testing and grading also, for use in conjunction with problem and answer material wherein a plurality of answers are provided for each problem arranged in accordance with a given program, characterized by an encoding means for conforming the system to the program, a problem display means for displaying the number of a given problem; a correct answer display means for displaying the number of correct answers selected and registered; advancing means selectively operable for advancing both the correct answer number display means and the problem number display means, only the problem number display means, or neither in accord with the mode selected and the correctness of the answer selected and registered; and apprising means for showing whether a selected and registered answer to a given problem is correct or incorrect. The encoding means includes a separable setting means, an answer selector means for selecting an answer to a given problem and a programming network that is programmed by the separable setting means to select the number of answers for each problem, the problem-correct answer sequence, the mode of operation and define whether or not an answer selected and registered is correct. Also disclosed are the mechanical and electronic details of each of the means, as well as embellishments of each of the means that facilitate use of the system.

3,577,658 TEACHING AID


Harold Weinstein, 1820 Avenue V, and Edward Snyder, III, 3323 Fillmore Ave., Brooklyn, N.Y.

Filed Aug. 11, 1969, Ser. No. 849,000

Int. Cl. G09b 7/00

U.S. Cl. 35-9R

8 Claims



A teaching machine for use in self-instruction. A programmed card containing a problem and coded answer in the

form of punched holes is inserted in the housing of the machine beneath a pair of wheels which are mounted in the housing for independent rotation and axial movement. The answer to the problem is selected by rotating the pair of wheels which have multiple indicia imprinted thereon which are selectively exposed to view during rotation. When the exposed indicia on each wheel are read together, they provide a proposed answer to the problem on the card. The wheels carry electrical contact elements about their circumference, and if the answer selected, as represented by the exposed indicia on each wheel, is correct, the contact elements will be positioned relative to the card so that when the wheels are moved axially towards the card the contact elements will pass through the punched holes to establish an electric circuit. A lamp in the circuit is then actuated to indicate that the correct answer to the problem has been selected. If the lamp is not actuated, then the answer selected is incorrect and the student can select another answer in an attempt to solve the problem.

3,577,659 MOTION SIMULATOR ACTUATOR JOINT


Karl Kail, Montrose, Pa., assignor to Singer-General Precision, Inc., Binghamton, N.Y.

Filed Aug. 6, 1969, Ser. No. 847,931

Int. Cl. G09b 9/08

U.S. Cl. 35-12

7 Claims



A three degree-of-freedom joint for attaching the upper end of a linear actuator to the motion platform of a six degree-of-freedom motion system. The disclosed configuration combines certain features of a ball-and-socket joint with a gimbal joint to achieve advantages and allow motion excursions not attainable with conventional joints previously used in such applications.

3,577,660 LINKAGE FOR MODEL-FORMING DISCS


Malcolm E. Kenney, 1203 Hereford Road, Cleveland Heights, Ohio

Filed Oct. 28, 1968, Ser. No. 771,121

Int. Cl. G09b 23/26

U.S. Cl. 35-18

1 Claim



An apparatus for constructing molecular models having, as atom-representing members, both single discs and in-


terengaged mutually perpendicular double discs and, as chemical bond-representing members, hollow tubes which are frictionally received over valence-representing recessed nibs on the discs.

3,577,661 TEACHING AID

Eldo Gene Usrey, 2052 Sunnybrook, Garland, Tex.
Filed July 16, 1969, Ser. No. 842,120
Int. Cl. G09b 19/02; G06c 27/00

U.S. Cl. 35-32

6 Claims




The present invention relates to apparatus for aid in the instruction of mathematics and, more particularly, it relates to apparatus for demonstrating counting systems to a base other than 10. In one form, the present invention may comprise a mechanical input means which functions to place arithmetical units of one into the system. In operative engagement with the unit input means is provided a variant base register means for registering the sum of units from the unit input means in a counting system having a base other than 10. In a preferred embodiment, a decimal register means is also provided in operative engagement with the unit input means for registering the sum of units from the unit input means in the decimal system for purposes of comparison of the totals in the decimal system with the totals in the variant base system.

3,577,662 FOOTWEAR

Tatsuo Fukuoka, No. 3, 3-Ban, 2-chome Shin-minami-Fukushima, Tokushima, Japan
Filed Jan. 14, 1970, Ser. No. 2,877
Int. Cl. A43b 3/12

U.S. Cl. 36-11.5

4 Claims



A sandal having a sole and a band member integrally molded from synthetic resinous material having a foamy interior and a nonfoamy exterior. The specific gravity of the sole is lower than the specific gravity of the band member.

3,577,663 ATHLETIC SHOE AND CLEAT

Howard Bruce Mereshon, 14 Saint Lawrence Ave., Maplewood, N.J. 07040

Filed Aug. 11, 1969, Ser. No. 849,099

Int. Cl. A43c 15/00


U.S. Cl. 36-67

8 Claims

An athletic shoe and cleat wherein the exposed portion of the cleat is formed of a polyhedron forming at least two lines in a common plane, with one of the lines extending at a

greater angle with respect to the sole of the shoe than the other of the lines. A portion of the planes forming the polyhedron each have a vertex lying in a common point to

fabrics comprising polyester-cotton flatwork with a resin finish, polyester-cotton flatwork with no resin finish, as well as plain cotton flatwork. The provided apparatus includes a high-speed ironer cylinder having an extremely large portion



form an apex which is engaged by the ground, and the exposed portion of the cleat is manually movable with respect to the sole of the shoe to a plurality of angular positions.

3,577,664


EXCAVATION MACHINE HAVING IMPROVED DIGGING ELEMENTS

T. J. Sing, and Reuben C. Sing, Pharr, Tex., assignors to Delta Diggers, Inc.

Filed July 22, 1968, Ser. No. 746,411
Int. Cl. E02f 3/14, 5/20

U.S. Cl. 37-192

6 Claims



An excavation machine which is especially suitable for digging graves, wherein a mobile frame has an excavating assembly mounted thereon for movement substantially vertically and also horizontally relative to the frame for excavating the grave or other hole. The machine is compact, capable of being pulled on the highway, and is controlled hydraulically for the excavating operation. The excavation is effected with a plurality of scratching elements which scratch the dirt from the vertical wall and collect same in buckets on an endless conveyor, with such conveyor preferably being at a small angle with respect to vertical to obtain more effective, smooth excavating action so that the frame for the machine does not shift or move from its location during the excavating operation.

3,577,665

LAUNDRY APPARATUS


Eduard F. Kamberg, Deerfield, Ill., assignor to Chicago Dryer Company, Chicago, Ill.

Filed Sept. 8, 1969, Ser. No. 856,126
Int. Cl. D06f 61/08, 65/10, 69/02, 89/00

U.S. Cl. 38-2

5 Claims

A finishing apparatus comprising a high-speed ironer cylinder and folder is provided which is adapted to process



of the circumferential surface contacting flatwork to be ironed, and a folder portion arranged in series with said ironer and adapted to impart a plurality of transverse folds and cross-folds in the freshly ironed piece.

3,577,666

PICTURE HOLDER


Norman Wexler, 21218 Chase St., Canoga Park, Calif. 91304

Filed Dec. 15, 1969, Ser. No. 885,100

Int. Cl. G09f 1/12

U.S. Cl. 40-152

7 Claims



A solid picture holder having an interlocked enclosed series of identical side panels with each alternate side panel being inverted, a pair of end panels attached to the top and bottom of the series of side panels, and a retainer within said side and end panels to hold pictures against their interior surface.

3,577,667

LOCK FOR PERCUSSION CAP RIFLE


Robert P. Kern, 319 E. Main St., Ligonier, Pa., and Allen J. Hamm, 251 McKimm Drive, Pittsburgh, Pa.

Filed Oct. 29, 1968, Ser. No. 771,411

Int. Cl. F41c 19/00

U.S. Cl. 42-69

5 Claims



A gunlock having a hammer which pivotally mounts a ratchet member. A separate sear includes a pawl element

which engages the ratchet member upon cocking of the hammer. A coil spring device bears against the ratchet so that release of the sear by a trigger causes rapid rotation of the ratchet and commensurate striking of the hammer.

3,577,668

TRIGGER AND SAFETY ASSEMBLY FOR FIREARMS


William B. Ruger, Southport, Conn., and Leroy J. Sullivan, Huntington Beach, Calif., assignors to Sturm, Ruger & Co., Inc., Southport, Conn.

Filed July 22, 1969, Ser. No. 843,385

Int. Cl. F41c 17/02, 19/00

U.S. Cl. 42-70E

9 Claims U.S. Cl. 46-1



A trigger assembly and an anticreep safety mechanism therefor particularly for use in rifles and shotguns having a cartridge striker of the Mauser bolt action type. The trigger and safety assembly comprises a combination of elements which includes a trigger having a bifurcated trigger extension one leg of which releasably engages the sear of the striker and the other leg of which has a yoke that engages a rotatable safety element. When the rotatable safety element is rotated to the "safe" position the trigger and the bifurcated extension thereof are immovably positioned with respect to the sear, and rotation and withdrawal of the bolt is prevented.

3,577,669

FISHING BOBBER


Joseph A. Johnson, 12272 W. Mississippi Ave., Denver, Colo., and Ray Key, 4858 Meade, Denver, Colo.

Filed June 23, 1969, Ser. No. 835,519

Int. Cl. A01k 93/00

U.S. Cl. 43-43.11

4 Claims



Fishing bobber of the type having a coiled supply of drop line with a terminal sinker adapted to descend after the bobber is delivered to a desired target point on the water, characterized by an inclined surface on the bobber which maintains the sinker attached to same until the bobber strikes the water, the buoyancy and attitude at which time permits a

securing loop of drop line to slide off of the inclined surface; further characterized by a manually operable line clutch for adjusting the length of the drop line, the clutch also adapted to slip relative to the line during retrieval of a fish when the bobber engages the end of a fishing rod to thereby permit the drop line to be reeled in for landing the fish.

3,577,670


WING FLAPPING TOY

Peter Paul Gutierrez, 3101 Fresno St., Santa Clara, Calif.

Filed Feb. 19, 1969, Ser. No. 800,615

Int. Cl. A63h 11/00

6 Claims



A wing flapping toy simulating a creature of nature such as a butterfly and the like by a simple wing mount on a handle and gripping means on the latter for manipulating the wings in unison.

3,577,671

CONSTRUCTION KITS FOR TOYS AND MODELS


Roy Perry Woollett, Apsley Mead, Cocking, Midhurst, England

Filed Feb. 26, 1969, Ser. No. 802,550

Int. Cl. A63h 33/00

U.S. Cl. 46-16

14 Claims



A construction kit for toys comprises a plurality of components for fitting together in various ways. One component is in the form of a hollow cube open on one, and only one face, having projections on some faces and recesses on the other faces, adapted for frictional interengagement. Half-cube components may be provided for sliding into said cubic components. Other components comprise a flat sheet with upstanding projections, and a flat sheet with recesses, adapted for engagement respectively with recesses and projections of cubic components; a like flat sheet with integral guide or rail means; and a like flat plate with legs extending perpendicular thereto.

3,577,672

MODULAR RIGID BLOCK-TYPE DOLLHOUSE

CONSTRUCTION TOY

William Nutting, 15 Charles St., New York, N.Y.

Filed Sept. 1, 1967, Ser. No. 665,035


Int. Cl. A63h 33/06

U.S. Cl. 46-19

3 Claims

This disclosure is directed to a constructional toy and more specifically to a modular dollhouse construction toy comprising a plurality of rigidly constructed hollow blocks some of

which are open at least one side and adapted to be randomly arranged in unconnected, side-by-side and/or stacked relationship with respect to one another to simulate varying doll-house floor plans. Simulated furniture and little people con-



structions are provided as accessory pieces. Wall surfaces are simulated by means of adhesive sheets to cover the inner and/or outer block surfaces, or two transparent telescoping blocks may receive one or more die cut sheets therebetween showing interior and exterior wall simulations.

3,577,673

BLOCK ELEMENTS OF VARIABLE ANGULAR FORM
Ottorino Monestier, Via Abbondio Sangiorgio 12, Induno Olona, Italy


Filed Jan. 24, 1969, Ser. No. 793,787

Claims priority, application Italy, Jan. 31, 1968, 12245

Int. Cl. A63h 33/06

U.S. Cl. 46-24

2 Claims



A dismemberable toy is disclosed, which comprises geometric solid elements, preferably cubic elements, having slotted faces defining a through-hole and adapted to afford a passageway for a threadlike resilient connection element to be fastened to the solids which form the ends of the assembly.

3,577,674

AMUSEMENT DEVICE

John Maguire, Littleton, Colo.; Tim M. Uyeda, South San Gabriel, Calif., and Theodore George Wahler, Denver, Colo., assignors to Samsonite Corporation, Denver, Colo.

Filed June 12, 1969, Ser. No. 832,585


Int. Cl. A63h 29/10

U.S. Cl. 46-41

10 Claims

The amusement device is a water toy having a watercourse structure, vacuum formed from a plastic sheet to provide interleaved and interspaced ridges, with a pair of corresponding, circuitous channels therebetween and merging prior to a common drain. Islands also upstand from the channels. From a sump plate beneath, posts support the watercourse structure, while the watercourse structure and sump plate are also attached around their peripheral edges to an upright frame. The discharge from a battery-operated pump is carried by tubes to a pair of fluid control devices, from which tubes lead to nozzles extending upwardly through the watercourse structure. The nozzle outlets discharge in a direction to direct simulated boats away from impediments along and at corresponding positions in the channels. The connecting tubes are placed in the space between the watercourse structure and the sump plate. The fluid control devices are mounted

on the sump plate and extend upwardly through the watercourse structure, while buttons thereon control diversion of



water to the respective nozzles, the normal flow of water being to a channel inlet end.

3,577,675

CHILD'S BATHING TOY


Frank Kohner, New York, N.Y., and Albert Stubbmann, Franklin Lakes, N.J., assignors to Kohner Bros., Inc., East Paterson, N.J.

Filed July 15, 1969, Ser. No. 841,872

Int. Cl. A63h 29/10

U.S. Cl. 46-41

18 Claims



The bathing toy includes a casing to be located on the inside wall of a bathtub. The casing is supported by straps slung over the tub wall and fastened to the outside wall by suction cups. Mounted in the casing is a water pump, the nozzle of which can be rotated to direct a stream of water from the pump for activating selected water powered components. Bathtub water is drawn to the pump from an intake tube immersed below the bathtub water level. With the nozzle pointed in one direction, the water stream strikes a carousel, rotating the carousel figures. The water drains from the carousel to a teeter-totter bucket from which it is discharged into the bathtub. If the nozzle is pointed in another direction, the water stream actuates a turbine wheel and subsequently drains into a bucketlike container seated within the casing. The container includes a circular dish pivotally mounted on the bottom. The circular dish and the container bottom have a plurality of holes which are aligned when the dish is rotated

to a certain position. When the holes in the dish and the bucket bottom are in alignment and the bucket is lifted out of the container, the water flows from the bucket in tiny streams simulating a bathing shower. The pump is so constructed that it has a protracted discharge period after each actuating down stroke of its operating handle.

3,577,676

STRIP-PROJECTING SQUEEZE TOY

Truman W. Powell, 1146 St. Augustine Place N.E., Atlanta, Ga.

Filed Feb. 16, 1965, Ser. No. 433,004

Int. Cl. A63h 7/00

U.S. Cl. 46-123

14 Claims



A squeeze toy wherein an elongated flexible element is disposed within a body having squeezable walls, the substantial length of the flexible element being projected from the body through an opening wherein upon the application of inward pressure to the walls causing a compression of air within the body which impinges the flexible element and carries the substantial length of it outwardly through the opening.

3,577,677

GRAVITY ACTUATED TOY VEHICLE HAVING AUXILIARY JET PROPULSION MEANS


Ambrose L. Bennett, Spotswood, and Sidney Tepper, Millburn, N.J., assignors to Topper Corporation

Filed Oct. 1, 1969, Ser. No. 862,662

Int. Cl. A63h 17/00

U.S. Cl. 46-206

10 Claims



A toy wheeled vehicle carries a tank adapted to be filled with a pressurized fluid through an inlet provided with a one-way valve. A tank outlet at the rear of the vehicle is closed by a plug hinged to the vehicle. The plug carries an arm adapted to strike a projection located along the path of travel of the vehicle while the latter is moving under the influence of gravity. The plug is thereby removed from the outlet permitting a jet of fluid to issue from the outlet and give the vehicle a burst of forward thrust.

3,577,678

COMBINED WASTE TREATMENT AND GROWTH CHAMBER PROCESS

Robert Edward Burton, Willits, Calif., assignor to Microphor, Inc., Willits, Calif.

Filed Aug. 14, 1969, Ser. No. 850,178


Int. Cl. A01g 9/18; C02c 1/02

U.S. Cl. 47-58

10 Claims

A hermetically sealed combination of a liquid waste treatment system, of a type that utilizes aerobic microorganisms for consumption of waste and production of carbon dioxide

as a byproduct, and a growth chamber, such as a conventional greenhouse, for the commercial growth of valuable plants which utilize carbon dioxide for photosynthesis. The



waste treatment system preferably includes a liquid body-containing bark strips to provide a convenient place for microbiological activity. A gas circulation system connects the air in the two components.

3,577,679

MULTIPLE AUTOMATICALLY RETRACTABLE AND EXTENSIBLE SLIDING DOORS IN PLANAR ALIGNMENT


Emil M. Petterborg, 1442 Wright Ave., Sunnyvale, Calif.

Filed May 18, 1970, Ser. No. 37,983

Int. Cl. E05d 13/02

U.S. Cl. 49-127

18 Claims



Presented is a sliding door structure for wide openings or for use as a partition to divide a large room into separate rooms and which utilizes separate door panels arranged in close juxtaposition while stored and which are moved individually from storage and placed in edge-to-edge planar alignment to close an opening when extended.

3,577,680

CLOSURE-GATE-ACTUATING MECHANISMS FOR HOPPER DISCHARGE ARRANGEMENT

Ernest J. Nagy, Munster, Ind., assignor to Pullman Incorporated, Chicago, Ill.

Filed Feb. 24, 1969, Ser. No. 801,631


Int. Cl. E05f 11/04; B61d 7/20

U.S. Cl. 49-358

5 Claims

A hopper discharge outlet arrangement including a frame and a closure member slidably movable horizontally relative to a hopper discharge opening, the closure member being moved by the rotation of an operating rod having reels connected thereto on which flexible members are wound and un-

wound and are so anchored and positioned on the frame that in response to the direction of rotation the closure member is



moved between open and closed positions with respect to said opening.

3,577,681

SAND BLASTING EQUIPMENT

Norman E. Waag, 3110 Broadview Road, Cleveland, Ohio
Filed Dec. 11, 1968, Ser. No. 782,854

Int. Cl. B24c 3/06

U.S. Cl. 51-8

1 Claim



A sand aspirator probe for a portable sandblasting apparatus having two parallel tubes of unequal length and welded together along their axes and incorporating therein a sand-air mixing aspirator port in the proximity of the bottom ends of said tubes.

3,577,682

ABRADING APPARATUS


Walter Kulischenko, East Brunswick, N.J., assignor to Pennwalt Corporation, Philadelphia, Pa.

Filed June 2, 1969, Ser. No. 829,271

Int. Cl. B24b 41/06

U.S. Cl. 51-8

1 Claim



Abgrading apparatus is provided with an improved workpiece holder including a plate on which is mounted structure having diverging edge portions and a spring-biased member for clamping the workpiece therebetween.

3,577,683

INVOLUTE GENERATING APPARATUS


Joseph Silvagi, Warren, and John W. Conforti, Detroit, Mich., assignors to Camdale Enterprises, Roseville, Mich.; Joseph Silvagi, fractional part interest to each and John W. Conforti, fractional part interest to each

Filed Aug. 15, 1968, Ser. No. 752,845

Int. Cl. B24b 3/00, 47/02

U.S. Cl. 51-94

9 Claims



A fixture is disclosed for grinding involute teeth profiles in a gear blank. Each tooth is generated by reciprocating the gear blank tangentially with respect to the grinding edge of a rotating wheel while oscillating the blank about its axis as the axis is constrained to move in a plane that is parallel to the axis of the grinding wheel.

3,577,684

ABRADING MACHINE WITH STEERING ROLL AND TENSIONED ABRADING BELT


Zigmant Jakimcius, Rockford, Ill., assignor to Barnes Drill Co., Rockford, Ill.

Filed Dec. 30, 1968, Ser. No. 787,656

Int. Cl. B24b 21/18

U.S. Cl. 51-135

8 Claims



An endless belt abrading machine with a combined steering and tensioning roll which is mounted for up and down tilting movement and which is tilted alternately by oppositely inclined positions by a steering actuator so as to induce edgewise travel of the belt across the roll. The roll also is mounted for swinging toward and away from a second roll for driving the belt and is urged continuously away from the driving roll by a tensioning actuator to tension the belt and keep the latter taut on the rolls as the belt stretches during service use.

3,577,685

GRINDING MACHINE WITH A FEED CONTROL DEVICE

Louis Corbex, and Roger Burdet, Annecy, France, assignors to Societe Nouvelle De Roulements, Annecy (Haute-Savoie), France


Filed Apr. 10, 1968, Ser. No. 720,086

Claims priority, application France, June 13, 1967, 110151

Int. Cl. B24b 49/00

U.S. Cl. 51-165

8 Claims



The device comprises the combination of two movable wedge members having each a moderately inclined plane, said wedge members being displaceable in two directions substantially at right angles to each other, the first wedge member abutting at the end of the approach stroke of the grinding wheel against a fixed stop of the frame structure of the machine, the second wedge member determining the end position of the first one, electric means for detecting the end position of the first wedge member in relation to the other one and controlling the finishing and planishing operations performed on the workpiece, by controlling the relative positions of the wedge members.

3,577,686

MOUNTING FOR A GRINDING WHEEL


Robert C. Fisher, Milford, Ohio, assignor to Cincinnati Milacron, Inc., Cincinnati, Ohio

Filed June 13, 1969, Ser. No. 833,005

Int. Cl. B24b 41/00

U.S. Cl. 51-168

7 Claims



A removable flange for supporting one end of a grinding wheel. The flange is provided with wedge blocks which are held away from the spindle to allow radial positioning of the flange with respect to the spindle in accordance with the alignment of the wheel. The blocks are then released and radially lock the flange with respect to the spindle.

3,577,687

RUBBING MACHINE WITH THRUST-TRANSMITTING MEMBERS


Roy J. Champayne, c/o National-Detroit, Inc., 2810 Aulwin St., Rockford, Ill.

Filed May 29, 1969, Ser. No. 828,857

Int. Cl. B24b 23/00

U.S. Cl. 51-170

12 Claims



A rubbing machine of the type in which a support is spaced from and overlies a rubbing shoe and in which the rubbing shoe is connected to the support by a drive mechanism operable to gyrate the shoe. The rubbing shoe is rectangular in shape with the drive mechanism connected at the center of the shoe, and two flexible boots are connected between the support and the shoe on diametrically opposite sides of the drive mechanism. In the preferred embodiment, two pair of opposed, rigid studs are mounted between the support and the shoe to transmit thrust therebetween, and each pair of studs is mounted within a respective one of the boots with one of the studs connected to the support and one to the shoe. The opposed ends of the studs are smooth and positioned face-to-face so that the studs may slide on one another and still transmit thrust as the shoe gyrates.

3,577,688

VALVE STEM GRINDER ATTACHMENT


Orville A. Brenden, 1625 Fifth Ave. South, Fargo, N. Dak.

Filed Sept. 26, 1968, Ser. No. 762,942

Int. Cl. B24b 19/00

U.S. Cl. 51-241

2 Claims



The invention comprises an aligner for grinding valve stems having an elongated plate member with a laterally extending shaft mounted at one end and with the plate having a bore at its other end, said plate has an open area intermediate its length to receive the upper end of the valve stem and valve spring therebetween, said bore at the other end of said plate being adapted to receive the mounting stud of the rocker arm of an engine head and to be locked thereto by a nut threaded onto said stud, said shaft being adapted to receive the hollow shaft of a grinder wheel to allow the grinder wheel to be lowered on to the upper end of the valve stem perpendicular to its length to grind the upper end of the valve stem.


3,577,689

METHOD FOR POLISHING METALLOGRAPHIC SPECIMENS

William F. Stuhke, and Charles R. Underwood, Dayton, Ohio
Division of Ser. No. 730,831, May 21, 1968, filed Dec. 19, 1969,
Ser. No. 889,863
Int. Cl. B24b 1/00

U.S. Cl. 51—281

2 Claims



A metallographic specimen is moved in a figure-of-eight motion over a stiff paper supported by a hard backing surface on which the polishing compound is positioned at the crossover point of the figure-of-eight motion. The specimen is rotated about its axis after each predetermined number of motions. Apparatus is provided to give a continuous range of selectable pressures between the specimen and paper.


3,577,690

METHOD OF MAKING ONE-PIECE MULTIFOCAL LENS BLANKS

William M. Catron, 6900 Northwest 6th Court, Plantation, Fla.
Division of Ser. No. 688,454, Dec. 6, 1967, filed Aug. 4, 1969,
Ser. No. 861,533
Int. Cl. B24b 1/00

U.S. Cl. 51—284

2 Claims



The method of manufacturing a multifocal lens blank which may finally be processed into a prescription lens having reading and distance portions separated by a shoulder extending the width of the lens, wherein a plurality of optical glass workpieces, specially shaped for efficient further processing, are blocked about the circumferential edge of a blocking wheel and auxiliary slabs of optical glass are provided in the spaces between adjacent pieces. During the grinding and polishing operations, which are performed on the workpieces to transform them to lens blanks, the auxiliary slabs provide the additional support needed by the processing tools to form relatively undistorted lens surfaces.

3,577,691

MOVABLE ROOF WINDOW HAVING A PYRAMIDAL FRAME CONSTRUCTION


Per Anders Persson, and Bror Lennart Sodersten, Stockholm, Sweden, assignors to Ruth L. Kallin, Uttran, Sweden
Filed Apr. 28, 1969, Ser. No. 819,638
Claims priority, application Sweden, June 17, 1968, 8186/68
Int. Cl. E04b 7/16; E04d 13/035

U.S. Cl. 52—72

10 Claims

A roof window includes support beams forming a pyramidal frame structure having an upper top roof and in-

dividually movable parallel trapezium-shaped roof or window sections. Each section can be moved between an open and a closed position, an upper guide extending between the base of a side of the pyramid and the top roof and a lower guide projecting outwardly from the said base being provided so as to cooperate with the upper and bottom portions, respectively, of the section. The guides form an angle with each other so that the section performs a combined displacing and swinging movement between its open and closed positions. Seals are provided between the sections and the frame structure. The lower guide is mounted or capable of being mounted on the roof of a building structure supporting the frame structure. The drive for the section may include a wire,



a chain or the like extending along the upper guide and connected with the upper portion of the sections and passing over end wheels arranged at the base of the frame structure or in the top roof. At least one of the wheels and preferably the one in the top roof is actuated by a drive motor. The seal includes sealing strips which extend along the side edges of the sections and cooperate with corresponding strips jutting from adjacent sections, said strips being of such configuration that, when the sections are in closed position, they present both an upper and a lower contact line with an insulating space therebetween. In the top roof is arranged a ventilation line provided with a fan which prevents misting or condensation in the region beneath the top roof when the sections are in closed position.

3,577,692

TANK STRUCTURE AND METHOD OF ERECTING SAME


Oscar Sircovich, Harbaron Hirsch 9, Jerusalem, Israel
Filed July 15, 1968, Ser. No. 744,928

Claims priority, application Israel, Dec. 25, 1967, 29212

Int. Cl. E04c 3/10; E04b 1/14; E04g 11/04

U.S. Cl. 52—224

10 Claims



A concrete tank structure comprises a bottom slab, a plurality of inner and outer vertical columns arranged in circular arrays with each inner column spaced between and tied to a pair of outer columns, a plurality of wall panels each spanning one of the inner and one of the outer columns, and restraining means, preferably two or more cables, applied around all the outer columns for restraining their outward movement. According to a preferred method of erecting the tank and for introducing prestressing forces, a temporary structure is provided at the center and pulls inwardly on the inner columns before the restraining cables are applied to the outer columns.

3,577,693

CELLULAR BUILDING STRUCTURE


Uri Y. Sofer, Berkeley, and Irwin L. Kaltman, El Cerrito, Calif., assignors to Technology Consortium, Inc., Berkeley, Calif.

Filed Dec. 9, 1968, Ser. No. 782,215

Int. Cl. E04h 1/38, 1/04

U.S. Cl. 52—236

10 Claims



A building system containing a plurality of room-sized rectangular cells formed of panels and upright corner posts, each corner post providing vertical support for respective ends of up to four panels. The system possesses flexibility for expansion as well as versatility of design at low cost to the builder.

3,577,694

FLOORING SYSTEMS

Ray E. Omholt, Berwyn, Pa., assignor to Powerlock Floors, Inc., Philadelphia, Pa.

Continuation-in-part of application Ser. No. 534,371, Mar.

19, 1969, now abandoned, Continuation-in-part of


application Ser. No. 724,799, Apr. 29, 1968, now abandoned.

This application Aug. 18, 1969, Ser. No. 850,989

Int. Cl. E04b 5/00

U.S. Cl. 52—483

9 Claims



A flooring system utilizing standard pattern conventional tongue and groove wood floorboards, the boards being supported on transversely disposed spaced channels, metallic holding clips securing the boards in bearing engagement with the channels, the boards being free from any special slots for clip engagement, the clips engaging the boards in a driven penetrating relation below the tongues and grooves in a manner which does not interfere with the tight vertical engagement of the tongues and grooves nor cause splitting of the boards, the clips engaging the channels each having a body portion vertically disposed between the boards below the tongues and grooves and having at the upper margin of the body portion a horizontally extending toothed portion driven in fiber-penetrating engagement into the board along the edge at locations wholly below the lower margin of the tongue on the tongue side of the board, and optionally, for greatly increased holding power having a penetrating portion extending into the groove side of the board below the groove.

3,577,695

CONSTRUCTION OF HEATERS


Heinz W. Huybers, Ashtead, Surrey, England, assignor to Foster Wheeler Corporation

Filed Mar. 18, 1969, Ser. No. 808,279

Int. Cl. E04b 1/35

U.S. Cl. 52—745

6 Claims



This invention describes the construction of heaters in which chemical process streams are heated by making a composite sheet having the developed length of the cylindrical heater. The composite sheet is then rolled up rather like a "Swiss roll" to a size suitable for transport. Then on site the composite sheet is unrolled to a cylindrical shape to form one cylindrical section of the heater, the latter being formed by stacking a number of such sections one upon another.

3,577,696

METHOD OF FILLING A PRESSURE VESSEL ASSEMBLY

Herbert G. Bock, Farmington, and Walter J. Szerejko, Newington, Conn., assignors to Chandler Evans Inc., West Hartford, Conn.


Division of Ser. No. 758,904, Sept. 10, 1968, filed Apr. 29, 1969,

Ser. No. 856,226

Int. Cl. B65b 31/02

U.S. Cl. 53—7

3 Claims



A metal high-pressure gas storage vessel has a threaded neck adapted to engage a threaded cap such that both cap and neck sealingly bear against an interposed seal element. The seal and cap are loosely assembled with the empty bottle and placed in a fluidtight filling fixture whereupon highly pressurized gas is introduced to the fixture, causing the bottle to fill by leakage between the loosely engaged threads. Then the cap is tightened and the fixture is vented prior to removal of the filled bottle. To lock the cap against rotation, the cap is locally upset into grooves in the neck after the acceptability of the charge has been verified.

3,577,697

HIGH-PRESSURE GAS-FILLING APPARATUS AND METHOD


Teddy J. Peacher, Huntsville, Ala., assignor to the United States of America as represented by the Secretary of the Army

Filed July 1, 1969, Ser. No. 838,117

Int. Cl. B65b 31/00

U.S. Cl. 53-12

4 Claims



A high-pressure gas-filling apparatus and method for filling gas containers such as lamps to a positive pressure of several atmospheres to minimize waste of supply gas. Empty lamp bodies are attached to a filling manifold and the filling apparatus is evacuated to a desired pressure range before filling occurs. After the lamps have been filled and sealed, control valves are closed to trap unused supply gas in the system. The trapped gas is then liquified and collected in a freezeout chamber by applying cooling to the freezeout chamber. When cooling is discontinued, the liquified gas in the chamber reevaporizes and when sufficient pressure builds up, the gas reenters the high-pressure supply side of the apparatus for reuse. Through the use of the freezeout chamber one of the supply containers can be purged, when its pressure will not operate a regulator, and the residual gas therein be placed into the other supply container.

3,577,698

METHOD AND MEANS FOR FILLING AND SEALING A FLEXIBLE CONTAINER


Herbert S. Rueckberg, Highland Park, Ill., assignor to Continental Can Company, Inc., New York, N.Y.

Filed June 11, 1968, Ser. No. 736,139

Int. Cl. B65b 3/04

U.S. Cl. 53-37

10 Claims



A means and process for filling a plastic bottle with a premeasured amount of liquid, squeezing the plastic bottle until the level of liquid in the bottle comes to a predetermined height and then capping and sealing the bottle.

3,577,699

METHOD OF CARTONING

Stanley Milton Silver, 10 Blenheim Street, London, W. 1, England

Filed Sept. 4, 1969, Ser. No. 855,283

Claims priority, application Great Britain, Sept. 17, 1968, 44074/68


Int. Cl. B65b 11/58; B31b 7/60, 49/02

U.S. Cl. 53-27

8 Claims

A package is described wherein the contents are hermetically sealed in an inner lining of moisture resistant flexible

sheeting material, which is wholly contained in a closed and sealed container of a substantially rigid material, such as boxboard, and yet the flexible sheeting initially constituted a layer sealed over the entire area of the board by means of a thermoplastic coating such as a microcrystalline wax. The lining remains sealed over a substantial area of the board after completion of the package. The package is rectangular and formed from a single unitary blank, the ends of the container being closed by flaps that have been severed from one another and, over the major portion of their area, detached



from the inner lining by the heating of the thermoplastic coating which is then absorbed in the boxboard material. The inner lining is sealed at each end by means of fin seals with web-gusseted ends. These are created by inwardly folding the ends of the container before the flaps are severed from one another, this initial folding involving gusset folding and the subsequent folding, after the severance of the flaps, being that of ordinary dust flaps and cover flaps. The fin seals are heat sealed when the heat is applied to strip the neighboring boxboard from the flexible material.

3,577,700

METHOD AND APPARATUS FOR PRODUCING CONTAINER PARTS FROM SHEET MATERIAL

Walter Bippus, Bensheim, and Horst Ackermann, Wiesbaden, Germany, assignors to Demag A.G., Duisburg, Germany


Filed Nov. 20, 1969, Ser. No. 878,282

Claims priority, application Germany, Dec. 20, 1968, P 18 15 983.6

Int. Cl. B65b 41/04, 47/10

U.S. Cl. 53-30

7 Claims



A method for the mechanical production of containers and container bottom parts includes the feeding out of a sheet of a material which is thermoplastically deformable and the indexing of the sheet past cutting, heating or molding, filling, covering and sealing apparatus to effect the deep drawing and filling and sealing of the container. The material is fed out and cut into a predetermined length from a web of such material and the individual cut portions are provided with raster holes by means by which the cut elements are centered in respect to the subsequent operations thereon. The apparatus for carrying out the method includes a conveyor having raster elements which are movable to engage in the raster holes of the individual cut elements and to move them to each additional working station and to center them at each station. The web material from which the molded containers are formed advantageously includes a printed distorted picture thereon for facilitating the centering and cutting thereon.

3,577,701

PRINTING AND CRIMPING ALUMINUM SEAL CLOSURES


George Spencer Bott, Westwood, N.J., and William Henry Marlow, Pearl River, N.Y., assignors to American Cyanamid Company, Stamford, Conn.

Filed Oct. 31, 1968, Ser. No. 772,096

Int. Cl. B65b 61/26; B67b 5/04

U.S. Cl. 53-131

5 Claims



A process and apparatus for printing indicia by indentation on vial or bottle seal closures made of soft stock, such as aluminum. The marking is impressed on the closure while it is capped over a glass vial or bottle held in position with resilient chucks which turn the bottle, and thereafter while the bottles are still being turned the closure is crimped under the flange or shoulder of the bottle by rotating against a crimping or curling bar. The indicia may be letters or numbers.

3,577,702

BANDING MACHINE


Frederick Bescrypt, Cherry Hill, N.J., assignor to Smith Kline & French Laboratories, Philadelphia, Pa.

Filed Jan. 13, 1969, Ser. No. 790,587

Int. Cl. B65b 13/02

U.S. Cl. 53-198

10 Claims



A banding machine wherein a strip of banding material is fed onto an article supported at a banding station. The article and the strip of banding material are gripped together and then given a revolving motion to cause the banding material to be wrapped completely around the articles. The wrapped portion of the banding material is then secured together in a wrapped condition by a heat sealing operation and served from the supply strip.

3,577,703

MEANS FOR FOLDING IN WRAPPING MATERIAL AT THE END OF AN APPROXIMATELY CYLINDRICAL ARTICLE

Karl Gustav Kohler, Folkungavägen, Sweden, assignor to Aktiebolaget Nordstroms Libanor, Stockholm K., Sweden

Filed Feb. 12, 1969, Ser. No. 798,620


Int. Cl. B65b 49/12

U.S. Cl. 53-380

3 Claims

The invention is concerned with wrapping of a cylindrical article, such as a roll, for example a paper roll. Hence particularly, the invention relates to folding the end of the wrapping while rotating the wrapped cylinder. According to

the invention there is provided a rotatable folding body having a helical groove or land surface extending around the periphery of said body and during the rotation of said folding body, abutting the wrapping material at the end of said



wrapped cylinder so as to fold in said material at said end substantially continuously. The helical groove or land surface may have a varying pitch and/or width, for example decreasing towards one end of the folding body.

3,577,704

PIVOT ASSEMBLY FOR MOUNTING SWINGABLE OPERATING MECHANISMS OF A PACKAGING MACHINE


Robert F. Lense, Rockford, Ill., assignor to Riegel Paper Corporation, New York, N.Y.

Filed Sept. 19, 1969, Ser. No. 859,306

Int. Cl. B65b 43/30

U.S. Cl. 53-386

5 Claims



The bag openers of a packaging machine are mounted for in and out swinging relative to the bag path by a pivot assembly which may be adjusted quickly and easily to change the length of the swinging stroke of each opener independently of the stroke length of the other opener and without changing the home positions to which the openers swing at the inner ends of their strokes.

3,577,705

FILTER SYSTEM

Ian B. Sharlit, Los Angeles, Calif., assignor to Hitco Continuation-in-part of application Ser. No. 627,914, Apr. 3, 1967, now abandoned. This application Dec. 23, 1968, Ser. No. 805,065


Int. Cl. B03c 3/36

U.S. Cl. 55-4

19 Claims

An air filtering system in which the filter elements through which the air passes are composed of an electrically conductive cloth having a high carbon content. The cloth is maintained at a substantial electrical potential relative to electri-

cal ground. The electrical charge is conducted to the particles present in the filter bag, thereby causing mutual repul-



sion and other effects between the charged particles and increasing the gas permeability of the filter system.

3,577,706

SULFUR DIOXIDE DRYING

Leopold Moller, Avonmouth, Bristol, England, assignor to Imperial Smelting Corporation (M.S.C.) Limited, London, England


Filed Aug. 30, 1968, Ser. No. 756,463

Claims priority, application Great Britain, Sept. 20, 1967, 42775/67

Int. Cl. B01d 53/14

U.S. Cl. 55—30

4 Claims



In the production of sulfuric acid, a two-stage drying process for drying gas which contains SO₂, organic material and water by contact with weak sulfuric acid of less than 70 percent strength to absorb a major proportion of the water but little of the organic material and then by contact with strong sulfuric acid to absorb the remaining water and the organic material.

3,577,707

SORPTION

Trevor Raymond White, Pontypool, England, assignor to Imperial Chemical Industries Limited, London, England

No drawing. Filed Dec. 19, 1969, Ser. No. 886,784

Claims priority, application Great Britain, Dec. 30, 1968, 61,660/68

Int. Cl. B01d 53/02

U.S. Cl. 55—68

9 Claims

A process for sorbing nitrogen dioxide from a gaseous mixture with air, nitrous oxide or other gases by contact with a polyamide material such as polyhexamethylene adipamide in fibrous, powder or sintered form. The polyamide fibers may also be in bicomponent form wherein one component possesses potentially adhesive properties.

3,577,708
SPARK INTERVAL RESPONSIVE PRECIPITATOR VOLTAGE CONTROL


John W. Drenning, and Richard J. Bridges, Baltimore, Md., assignors to Koppers Company, Inc., Pittsburgh, Pa.

Filed May 28, 1968, Ser. No. 732,615

Int. Cl. B03c 3/66

U.S. Cl. 55—105

28 Claims



A method and digital circuit for modifying the voltage applied to the electrodes of a precipitator in accord with the elapsed time interval between the presently detected spark and the spark immediately preceding. Four predetermined time intervals are established by astable multivibrators each set by each detection of a spark in the precipitator. The outputs of the multivibrators enable gates to control the application of the next successive spark responsive pulse to a reversible digital counter which controls precipitator voltage. The counter is periodically advanced by clock pulses if the time interval between the detection of the next subsequent sparks falls outside the three shorter of the predetermined time intervals. Advancement of the counter is inhibited if the next subsequent spark responsive pulses occur within the second longest of the predetermined time intervals and the counter is respectively reversed one and two steps if the next subsequent spark responsive pulse occurs within the third longest or shortest of the predetermined time intervals.

3,577,709

GAS WASHER APPARATUS


John G. Hoad, Dearborn, Mich., assignor to John G. Hoad & Associates, Inc., Ypsilanti, Mich.

Filed May 9, 1968, Ser. No. 727,814

Int. Cl. B01f 3/04

U.S. Cl. 55—228

6 Claims



A combined wet scrubber and clarifier or settling basin for removing dust and other particulate matter from exhaust gases associated with various metallurgical and chemical processes.

3,577,710

AIR-TREATMENT APPARATUS


Elliot I. Feldman, 2850 E. Second St., Tucson, Ariz. 85716

Filed Sept. 30, 1968, Ser. No. 763,903

Int. Cl. B01d 53/04

U.S. Cl. 55—316

3 Claims



A reactant element for use in air-treating apparatus, including a honeycomblike structure having contiguous channels, the longitudinal axes of which are disposed parallel to the direction of airflow, particulate reactant material disposed within the contiguous channels and a frame which, with the honeycomb structure, forms a unitary cartridgelike assembly which is fully self-supporting in the direction of the airflow.

3,577,711

APPARATUS FOR REMOVING ENTRAINED PARTICLES FROM GASES


Luigi U. De Bernardo, San Dimas, Calif., assignor to the United States of America as represented by the Secretary of Agriculture

Continuation-in-part of application Ser. No. 592,888, Nov. 8, 1966, now abandoned. This application June 2, 1969, Ser. No. 829,125

Int. Cl. B01d 45/12

U.S. Cl. 55—399

8 Claims



An apparatus for removing entrained particles from gases, of particular use as a spark arrester with internal combustion engines, comprises, essentially, an elongated cylinder, closed at one end and having a spiral member secured to the inner wall. Exhaust gases enter tangentially at a point near the open end and travel in a thin layer along a spiral path adjacent the wall toward the closed end. Near the closed end, the gases reverse direction and travel in an axial spiral path along the center of the cylinder and out the open end, while incandescent carbon particles continue by inertia in their

original spiral path and are retained or pulverized by rubbing against the cylinder wall as they continue to circulate at the base of the cylinder. The absence of baffles minimizes back pressure on the engine.

3,577,712

COMBINATION AIR FILTER AND FRAME FOR HOLDING THE SAME


Peter Ballennie, deceased, late of West Hill, Eileen Margaret Ballennie, Executrix, West Hill, Ontario, Canada, and Angelo P. Ruffo, Montreal, Canada, assignors to Industrial Air Filters Limited

Continuation-in-part of application Ser. No. 683,197, Nov. 15, 1967, now abandoned. This application May 28, 1969, Ser. No. 829,163

Int. Cl. B01d 46/10

U.S. Cl. 55—501

1 Claim



A frame comprising plural frame members in rectangular configuration for removably mounting air filter media. Each frame member has a base and a resilient wall in spaced apart relationship. A rigid finger extends downwardly from the rigid wall towards the resilient wall so that air filter media is gripped between the finger wall and the resilient wall. The frame member has a flange as an extension of the base portion.

3,577,713

HEADER LOCK MEANS FOR AGRICULTURAL HARVESTING MACHINES

Horace G. McCarty; Henry N. Lausch, and Earl A. Hudson, Leola, Pa., assignors to Sperry Rand Corporation, New Holland, Pa.

Filed July 26, 1968, Ser. No. 748,021

Int. Cl. A01d 43/10

U.S. Cl. 56—11.9

9 Claims




This invention relates to a header locking means for agricultural harvesting machines having a mobile main frame, and a subframe and harvesting header mounted on the main frame. The subframe and header are mounted as a unit for pivotal movement relative to the main frame about a predetermined transverse axis between a lowered operating position and a fully raised nonoperating, transport or servicing position. Novel safety mechanical locking means in the form of a telescopic link assembly are provided to lock the header unit in a fully raised or intermediate position for various reasons including safety in transport or servicing of the header unit.

3,577,714

REAR ROLLER GUARD FOR ROTARY MOWERS
 Einar S. Dahl, Galesburg, Ill., assignor to Outboard Marine Corporation, Waukegan, Ill.
 Continuation-in-part of application Ser. No. 649,259, June 27, 1967, now abandoned. This application Aug. 27, 1969, Ser. No. 853,310
 Int. Cl. A01d 75/20

U.S. Cl. 56-17.2

21 Claims



A rear roller guard assembly which prevents ejection of missiles rearwardly from beneath a rotary mower blade housing. The roller guard assembly includes two or more paddle wheels having radially extending vanes which are rotatably supported on an axle which is supported rearwardly of the housing by two sidearms. The sidearms are pivotally connected to the mower housing and extend rearwardly therefrom.

In one embodiment, the paddle wheels are located rearwardly of the rear wheel axle. In a further embodiment, the paddle wheels support the rear of the mower housing above the ground. A shield located over the roller prevents the escape of missiles from the rear edge of the mower housing and the roller.

3,577,715


SUSPENSION FOR MOUNTING A HEADER ON A TRACTOR

Lawrence M. Halls, New Holland, and Henry N. Lausch, Leacock, Pa., assignors to Sperry Rand Corporation, New Holland, Pa.

Filed Apr. 3, 1969, Ser. No. 813,182
 Int. Cl. A01d 67/00

U.S. Cl. 56-208

9 Claims



A self-propelled agricultural harvesting machine has a link-type suspension mounting a crop cutting header on a tractor. The suspension comprises two spaced suspension assemblies each having upper and lower links and suspension springs supporting the header in cooperation with ground engaging skid shoes and moving the header on variations in ground level so that cut crops are discharged against the windrow- or swath-forming means underneath the tractor at substantially the same location and having deflection means for smoothly guiding end discharged crops from the long conditioning rolls to the narrower windrow and swath forming means.

3,577,716

MOWING DEVICE


Horace G. McCarty, Leola; Lawrence M. Halls; Edmund O. Howell, New Holland, and Joseph C. Hurlburt, Leola, Pa., assignors to Sperry Rand Corporation, New Holland, Pa.
 Filed Aug. 26, 1968, Ser. No. 755,318
 Int. Cl. A01d 55/02

U.S. Cl. 56-259

2 Claims

A mowing device comprising a frame structure, a split sickle mounted in the frame structure and drive means

disposed on either side of said frame structure for independently driving each of said sickle halves so that the knife ele-



ments fixed to the sickle bars cut crop materials directed thereto across the entire length of the sickle.

3,577,717

CUTTING BLADE FOR ROTARY MOWER

Peter J. W. Van Den Munckhof, Meterikseweg 79, Horst, Netherlands


Filed Nov. 15, 1968, Ser. No. 776,211

Claims priority, application Netherlands, Nov. 16, 1967, 6,715,578

Int. Cl. A01d 55/18

U.S. Cl. 56-295

2 Claims



The invention relates to a toothed cutting blade manufactured of thin sheet steel material for a rotary mower and forming at least a portion of a flat ring, its teeth each having an active cutting edge receding from the point of the tooth in respect of the radius going through the said point and an inactive edge being about square to the said radius.

3,577,718

YARN-COVERING MACHINE

James J. Purcell, Wyomissing, Pa., assignor to Sheer Elastic Corporation

Filed Mar. 24, 1969, Ser. No. 809,716

Int. Cl. D02g 3/28, 3/38


U.S. Cl. 57-18

3 Claims

A hollow spindle for the passage therethrough of a yarn to be covered, (herein referred to as the core), by another, (herein referred to as covering filament). The driving spindle of this invention is about double the length of a conventional spindle and it has an irreducibly small diameter. The covering filament is wound in the form of a long, small-diameter, cylindrical cake directly onto the spindle instead of on a bobbin which is mounted on the driving spindle. The spindle is rotated at a rate of speed about three times the rate attainable by conventional machines of this type. The spindle is

mounted for quick and easy removal and replacement and in a manner such that, replacing an empty spindle with a loaded

energy of an air vortex. The device is provided with means



one will not disturb the closely spaced spindles of a multispindle installation.

3,577,719

METHOD AND APPARATUS FOR LOADING BOBBINS OR REELS INTO AND OUT OF CRADLES OR MOUNTINGS

Mario Martinez, Dibden Mannor, Dibden Hythe, and Colin Monday, Southampton, England, said Monday assignor to said Martinez


Filed Feb. 25, 1969, Ser. No. 802,096

Claims priority, application Great Britain, Mar. 12, 1968, 11,977/68

Int. Cl. D07b 3/12, 7/00

U.S. Cl. 57-34

13 Claims



The invention comprises a method and apparatus for loading and unloading spools into and out of pintles of a machine having a plurality of spools and the method comprises the steps of loading full spools to be mounted in the supports onto a conveyor, conveying said full spools below said spool supports and locating each spool in a vertical plane displaced to one side of a vertical plane containing the respective axis of the spool support, lowering any empty spools from the spool supports onto the conveyor, operating the conveyor to position each full spool to be loaded in the vertical plane containing the respective axis of the spool support, raising each full spool to be loaded into the respective spool support and then operating the conveyor to convey unloaded empty spools thereon away from the apparatus.

3,577,720

DEVICE FOR TWISTING YARN

Natan Albertovich Zax, B. Eldoradousky pereulok, 1, Kv. 35; Vasily Porfirievich Korzhov, Varshauskoe Shosse, 44/46, Korpus 3, Kv. 84, and Roza Semenovna Rabinovich, Dauyd Kouskaya ulitsa, 34, Korpus 45, Kv. 33, Moscow, U.S.S.R.


Filed Dec. 18, 1968, Ser. No. 784,768

Int. Cl. D01h 7/00

U.S. Cl. 57-58.89

2 Claims

A yarn-twisting device is provided in which twisting single fibers fed into a spinning chamber is carried out by using the



3,577,721

YARN STRING-UP DEVICE


Hayes J. Schmick, and Hans Van Doornewaard, Greenville, S.C., assignors to Phillips Fibers Corporation

Filed Feb. 12, 1969, Ser. No. 798,667

Int. Cl. D01h 7/92; D02g 1/04

U.S. Cl. 57-77.33

12 Claims



A jet can be utilized to pass yarn through a deflection valve. The direction of rotation of the fluid in the jet and the resulting torque on the yarn can be varied to impart a desired amount of twist to the yarn. The deflection valve can pass the yarn to the next processing station or to waste, as desired, and cuts the yarn upon being charged from one condition to the other.

3,577,722

SENSING DEVICE FOR AUTOMATIC BRAKING OF THE SPINDLE IN RING SPINNING AND RING TWISTING MACHINES

Kazimierz Adamaszek, Komorowice Kreis Bielska-Biala near, Poland

Filed Mar. 4, 1969, Ser. No. 804,152

Claims priority, application Poland, Mar. 7, 1968, P125,648


Int. Cl. D01h 13/16

U.S. Cl. 57-80

9 Claims

A device which automatically regulates yarn tension including a lever upon which resultant yarn forces act and

which forces are counterbalanced by the weight distribution of the lever: a spindle brake actuator is held in an inactive



position until released by lever movement occasioned by yarn breakage.


3,577,723

BOBBIN SUPPORT FOR TEXTILE SPINDLE ASSEMBLY
John D. Page, Clemson, S.C., assignor to Maremount Corporation, Chicago, Ill.

Filed Sept. 2, 1969, Ser. No. 854,453
Int. Cl. D01h 7/16, 7/08

U.S. Cl. 57—129

10 Claims



In a bobbin support for a textile spindle assembly, a pair of superposed annular members encircle the spindle blade and are connected to it for positional adjustment in an axial direction by connections of the spline and screw-thread types, respectively. Precise axial adjustment of the elevation of the annular members and of a bobbin mounted upon the spindle blade is made possible, and a nonslip driving connection between the blade and bobbin is provided.


3,577,724

METHOD OF FIBRILLATING AND TWISTING ORIENTED FILM

Max E. Greene, Bartlesville, Okla., assignor to Phillips Petroleum Company
Filed Jan. 27, 1969, Ser. No. 793,996
Int. Cl. D02g 1/02

U.S. Cl. 57—157

5 Claims



An apparatus and method for fibrillating and texturizing an oriented film of thermoplastic material. The apparatus in-

cludes a cutting roller rotatable about a fixed axis for cutting elongate slits in said film. The method comprises moving forming elongate slits in a thermoplastic film and texturizing said slit film by the false twisting technique to form a bulky yarn.

3,577,725


SOUND GENERATOR FOR ALARM CLOCKS

Wolfgang Ganter, Schramberg-Sulgen, and Georg Kunz, Lauterbach, Germany, assignors to Gebrüder Junghans G.m.b.H., Schramberg Wurt, Germany

Filed July 9, 1969, Ser. No. 840,238
Claims priority, application Germany, July 10, 1968, P1,773,812.4
Int. Cl. G04c 9/00

U.S. Cl. 58—38

11 Claims



A sound generator for an alarm clock including a mechanical oscillator driven by a transistor circuit. The transistor circuit includes a drive coil on the output and a control coil on the input. The drive coil excites a mechanical oscillator which in turn varies the reluctance of the control coil. The drive and control coils are magnetically coupled together so that the circuit operates initially as a conventional blocking oscillator whose frequency depends upon the values of the circuit elements. Once the mechanical oscillator begins to move, however, the control coil reluctance is affected so as to convert the operation of the circuit into an amplifying circuit which amplifies the pulses on the control coil and operates the mechanical oscillator at its mechanical resonant frequency.

3,577,726


FUEL SYSTEM FOR NATURAL GAS TURBOCHARGED ENGINE

Harold H. Wagner, Peoria, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Filed July 24, 1969, Ser. No. 844,517
Int. Cl. F02b 37/00; F02m 21/04

U.S. Cl. 60—13

5 Claims



A turbocharged natural gas engine adapted for use with very low pressure gas by virtue of introducing the gas and combining it with air to provide a combustible mixture upstream of or on the low pressure side of the turbocharger. Safety means are provided to insure against damage by backfire and against admission of explosive gases to the engine crankcase.

3,577,727


METHOD OF REDUCING INTERNAL COMBUSTION ENGINE EMISSIONS

Joel A. Warren, Birmingham, and Frederick J. Marsee, Clawson, Mich., assignors to Ethyl Corporation, New York, N.Y.

Filed Oct. 7, 1968, Ser. No. 765,361
Int. Cl. F02b 75/10

U.S. Cl. 60—29

10 Claims



A system is described for reducing unburned hydrocarbons and carbon monoxide emitted from internal combustion spark ignition engines. The system comprises means for supplying a leaner-than-stoichiometric air/fuel mixture to the cylinders of the engine for combustion, means for conserving the heat of the exhaust products formed on combustion of the air/fuel mixture, and means for controlling the exhaust back pressure under low power demand. The means for conserving the exhaust heat includes the combination of an insulated exhaust port, insulated exhaust manifold and an insulated exhaust pipe; the back pressure control means consists of a valve placed in the exhaust pipe, said valve being responsive to vacuum signal and an exhaust back pressure signal.

A method of operating an engine utilizing said system is also described.

3,577,728


EXHAUST GAS PROCESSING SYSTEM

Joe W. Von Brimer, Sherman Oaks, and Herman P. Roth, Manhattan Beach, Calif., assignor said Von Brimer to General Scientific Laboratories, Inc., a fractional part interest

Continuation of application Ser. No. 601,468, Dec. 13, 1966, now abandoned. This application Mar. 19, 1969, Ser. No. 809,480
Int. Cl. F01n 3/10

U.S. Cl. 60—30

27 Claims



An exhaust gas processing device for use with internal combustion engines which is generally of the afterburner type, including a cylindrical reactor in which the unburned hydrocarbons are consumed and an exhaust pipe connected near one end of the cylindrical reactor in such manner as to direct the flow of gases tangentially into the reactor to produce a vortical flow pattern to assure adiabatic heating and mixing with air from outside the reactor chamber. Various arrangements are described for igniting the mixture in the chamber, for controlling the effective area of the exhaust

gas inlet to the reactor and the air inlet to the reactor, for controlling the reactor outlet including additional air mixing means, for compounding the reactors and for using a plurality of reactors for multicylinder engines. Arrangements are also shown for utilizing the heat radiating from the sides of the reactor to heat the incoming air and for conserving the heat by means of an insulating layer or a labyrinth structure which redirects the exhaust flow back across the outside of the reactor cylinder. A still further embodiment utilizes a helical member within the reactor chamber to direct the flow in a vortical pattern which also is effective to reduce sound output.


3,577,729

RECIPROCATING INTERNAL COMBUSTION ENGINE WITH CONSTANT PRESSURE COMBUSTION

Glenn B. Warren, 1361 Myron St., Schenectady, N.Y.
Filed Mar. 11, 1969, Ser. No. 806,159
Int. Cl. F02g 3/02

U.S. Cl. 60—39.63

11 Claims



A reciprocating internal combustion engine adapted to provide substantially constant pressure combustion in a combustion chamber separated from the compression and expansion cylinders of the engine is provided.


3,577,730

VAPORIZER CUP

William J. Oliphant, Wakefield, Mass.
Filed July 25, 1969, Ser. No. 844,958
Int. Cl. F23d 1/14

U.S. Cl. 60—39.71

3 Claims



A vaporizer for gas turbine engines formed of three simple parts, a tube, a retaining band and an end cup joined inseparably together to control the passage of the air/fuel mixture through 180° and to vaporize the mixture of contact of the mixture with the forward head plate of the combustion chamber.

3,577,731

ENGINE IGNITION SYSTEM


Raymond J. Bruchez, Jr., Lake Park, Fla., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed Aug. 1, 1969, Ser. No. 846,833

Int. Cl. F02c 7/26

U.S. Cl. 60—39.82

11 Claims



An ignition device for a turbine engine wherein said device has means for compressing air to a specified temperature and then directing said air into a combustion chamber. A predetermined metered amount of fuel is injected into the hot air so that auto ignition temperature is reached within the passageways of a catalytic restrictor-emitter. The flame started by the restrictor-emitter is held on its surface as a flame holder while the flame front projects into the combustion chamber to ignite a fuel/air mixture.

3,577,732

MOTION CONVERSION SYSTEM

Jacobus De Haas, Haren, Netherlands, assignor to Shell Oil Company, New York, N.Y.

Filed May 19, 1969, Ser. No. 825,782


Claims priority, application Netherlands, May 27, 1968,

6,807,442

Int. Cl. F15b 15/18

U.S. Cl. 60—52

7 Claims



A system for the conversion of the rotary movement of a shaft into a corresponding displacement of an element such as a moving element of a control valve.

3,577,733

RAPID LOADING OF STEAM TURBINES

Eric Manuel, Peterborough, Ontario, Canada, and James H. Moore, Jr., Scotia, N.Y., assignors to General Electric Company

Filed May 8, 1969, Ser. No. 822,933

Claims priority, application Canada, July 16, 1968, 25,244


Int. Cl. F01k 13/02

U.S. Cl. 60—105

3 Claims

A method for loading a steam turbine and transferring from full arc to partial arc admission during loading while

maintaining a constant rate of heating, so as to eliminate the



cooling and reheating which previously took place during a transfer at constant load.

3,577,734

LIQUID-METAL FEED SYSTEM FOR FEEDING PROPELLANT TO AN ION THRUSTOR

Harry J. King, Canoga Park, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.


Division of Ser. No. 602,664, Dec. 19, 1966, Pat. No. 3,443,383.

Filed July 19, 1968, Ser. No. 746,114

Int. Cl. F03h 5/00

U.S. Cl. 60—202

2 Claims



A reservoir of liquid metal is connected to an ion thruster for a supply of ionizable material thereto. The reservoir is in the form of a reservoir cylinder having a reservoir piston therein. An associated drive cylinder contains a drive piston connected to the reservoir piston. A liquid in equilibrium with its vapor is positioned in the drive cylinder, and as heat is added, the pistons move to deliver liquid metal to the thruster. The amount of heat supplied to the drive cylinder is preferably a function of the liquid-metal requirements of the ion thruster.

3,577,735

LIQUID FUEL ROCKET ENGINE CONSTRUCTION

Gunther Schmidt, Ottobrunn-Riemerling, Germany, assignor to Bolkow Gesellschaft mit beschränkter Haftung, Ottobrunn, Germany

Continuation of application Ser. No. 698,574, Jan. 17, 1968, now abandoned. This application Nov. 5, 1969, Ser. No. 871,644

Int. Cl. F02k 9/02; F01d 9/04

U.S. Cl. 60—207

6 Claims

A liquid fuel rocket engine construction includes the usual main combustion chamber having a nozzle discharge. One or more precombustion chambers are arranged ahead of the main combustion chamber in a position to discharge combustion gases generated therein through turbine blades of an auxiliary turbine arranged directly adjacent the rear end of the main combustion chamber. The auxiliary turbine drives at least two separate fuel component pumps, one of which

3,577,737

WATERTIGHT PLUG FOR TUBULAR PILE WELLS

Hulbert M. Burleson, P.O. Box 301, Russellville, Ala.

Filed Apr. 14, 1969, Ser. No. 815,829


Int. Cl. E02b 17/04; E16l 55/00; E21b 23/06

U.S. Cl. 61—46.5

5 Claims

discharges first through the walls of the main combustion chamber for cooling purposes and then into a precombustion chamber, and the other of which discharges only partially into the precombustion chamber and then into the discharge from the auxiliary turbine and into the main combustion chamber. The precombustion chamber is operated either with excess fuel or oxidizer.

The construction includes a preguide lattice or guide fin arrangement for discharging into the turbine blades and in



addition in accordance with a feature of the construction, the discharge section immediately after the turbine blades is provided with a retarding afterguide lattice for guiding the fuel discharged by the turbine into the main combustion chamber and also for adding an additional fuel component, either fuel or oxidizer, at such location. In a preferred form, the trailing ends of the afterguide lattice are provided with nozzle discharge openings for facilitating the discharge of the fuel component into the main combustion chamber at such location.

3,577,736

THRUST DIVERTER VALVE


Emerson W. Stevens, Snyder, N.Y., assignor to the United States of America as represented by the Secretary of the Air Force

Filed Aug. 21, 1969, Ser. No. 852,010


Int. Cl. F02k 1/20

U.S. Cl. 60—226

8 Claims



A thrust diverter valve for turbofan jet engines producing two different angular flow patterns for the fan exhaust from a turbofan jet engine, which includes two similar spherical curved portions of half of a split substantially hemispherical shell which are concentrically rotatable in opposite directions in a confining chamber around the axis of a turbofan jet engine with the axis of rotation of each portion of the shell disposed in canted relation with respect to horizontal and vertical flow directions. The spherical shell portions are rotatable about their axis in opposite directions into one position in the path of flow from the fan to form an inclined hemispherical deflector shell and deflect the flow from the fan downwardly at substantially 90° to the fan axis for vertical thrust, and movable about their axis in the opposite directions out of the flow path from the fan and allow the fan flow to pass between the spherical shell portions parallel to the axis of the turbofan jet, without deflection, to provide for horizontal thrust.



3,577,738
APPARATUS FOR INJECTING SAND BENEATH SUBMERGED CONSTRUCTIONS
Kaj Havno, Copenhagen, Denmark, assignor to Christiani & Nielsen A/S, Copenhagen, Denmark

Filed June 9, 1969, Ser. No. 831,302

Claims priority, application Denmark, June 18, 1968,

2854/68

Int. Cl. E02d 3/12, 27/00

U.S. Cl. 61—63

4 Claims

Apparatus for injecting sand under a construction or excavation in the water in which the construction is temporarily

suspended or rests on temporary supports comprising combined feed and suction pipes each having a branch adapted to extend beneath the construction and a branch extending vertically above the surface of the body of water; means for reciprocating or oscillating the branches beneath the construction and including a feedpipe through which a mixture of sand and water can be pumped into the space below the construction, and at least one suction pipe through which a corresponding quantity of water can be extracted or withdrawn from the space into which sand and water are being deposited, and at least a flushing feedpipe through which water can be forcibly ejected to flush suspended or partially deposited lightweight materials.

3,577,739

METHOD AND APPARATUS FOR TRANSPORTING LIQUEFIED GAS


Lawrence A. Botkin, Omaha, Nebr., assignor to Freuhauf Corporation, Detroit, Mich.

Filed Oct. 29, 1968, Ser. No. 771,550

Int. Cl. F17c 5/02, 7/02

U.S. Cl. 62-45

16 Claims



A movable pressure vessel has an insulated wall portion for limiting the temperature rise of liquefied gas therewithin. A relief valve is provided for limiting the pressure within the vessel to establish a working pressure. The filling means of the vessel includes a relief valve for limiting the maximum pressure of the gas entering the vessel to a pressure of approximately 15 p.s.i.g. less than the working pressure of the vessel. Liquefied gas is loaded into the vessel at a maximum temperature and pressure as determined by the relief valve in the filling means, and temperature rise of the liquefied gas during transport is limited so that the pressure produced by the gas does not exceed the working pressure of the vessel. A vapor return means extends along the bottom of the vessel and opens therewithin at a point remote from the outlet means of the vessel and adjacent the front end of the vessel.

3,577,740

VIBRATED REFRIGERATED SURFACE

Jeffrey Stuart Kenworthy, and Hans Berthold Wiener, Stockton-on-Tees, England, assignors to Imperial Chemical Industries Limited, London, England


Filed Aug. 11, 1969, Ser. No. 849,066

Claims priority, application Great Britain, Sept. 5, 1968, 42217/68

Int. Cl. F25c 1/12

U.S. Cl. 62-72

12 Claims



Apparatus for chilling a liquid to produce a slurry includes three coaxial lengths of tube meeting in a junction, one of them being torsionally sonically vibrated and another, which chills the liquid, contacts the liquid on one of its sides and a refrigerant on the other. Extremities of the lengths of tube

are supported at nodal points and the junction is at an antinodal point if the vibrated and chilling lengths of the tube are of different diameters. The design is robust whilst avoiding large losses of sonic energy.

3,577,741

REFRIGERATION APPARATUS


David N. Shaw, Liverpool, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Filed June 2, 1969, Ser. No. 829,417

Int. Cl. F25b 43/02

U.S. Cl. 62-84

2 Claims



A refrigeration circuit comprising a motor-driven compressor, a condenser, an evaporator, and expansion means. The compressor includes an oil reservoir, where a supply of oil is disposed for lubricating the compressor during normal operation thereof. Associated with the compressor is a heating element, operable to heat the oil when the compressor is inoperative. A safety switch prevents the compressor from becoming energized if the heating element has not functioned while the compressor was inoperative.

3,577,742

REFRIGERATION SYSTEM HAVING A SCREW COMPRESSOR WITH AN AUXILIARY HIGH PRESSURE SUCTION INLET


Erich J. Kocher, Milwaukee, Wis., assignor to Vilter Manufacturing Corporation, Milwaukee, Wis.

Filed June 13, 1969, Ser. No. 832,979

Int. Cl. F25b 5/00

U.S. Cl. 62-199

8 Claims



A refrigeration system having a screw compressor for compressing low pressure suction gas that is received from an evaporator and compressing it and discharging it into a condenser, including an auxiliary high-pressure suction inlet to the compressor for conducting high-pressure suction vapor from a pressure-reducing means and to the compressor for being compressed along with low-pressure suction vapor. The invention is used with a refrigeration system having either two operating suction pressure levels, or having a single suction level. The high-pressure suction vapor is introduced into the compressor at a point after the low-pressure suction is cut off, and therefore no reduction in the low-pressure suction capacity results. Increased compressor capacity is thus accomplished by the addition of this high pressure vapor.

3,577,743

CONTROL FOR REFRIGERATION SYSTEMS


Joseph N. Long, Wauwatosa, Wis., assignor to Vilter Manufacturing Corporation, Milwaukee, Wis.

Filed June 10, 1969, Ser. No. 831,873

Int. Cl. F25b 41/00

U.S. Cl. 62-212

8 Claims



A control system for a refrigeration system employs first and second temperature sensors located in the system evaporator to control the superheat condition of the system refrigerant. One temperature sensor senses the temperature of liquid phase refrigerant in the evaporator while the other temperature sensor senses the temperature of gaseous phase refrigerant in the evaporator. The temperature sensors are connected to a differential temperature control means which regulates the system expansion valve in accordance with a desired differential temperature or superheat condition between the liquid and gaseous phase refrigerant.

3,577,744

DRY AIR REFRIGERATED DISPLAY CASE SYSTEM


John F. Mercer, P.O. Box 143, Globe, Ariz. 85501

Filed Dec. 29, 1969, Ser. No. 888,289

Int. Cl. A47f 3/04; F25b 5/00

U.S. Cl. 62-256

4 Claims



In order to provide an open refrigerated display case in which the product zone remains frost-free and in which the evaporator coils remain ice-free, a small secondary evaporator unit is utilized to dry ambient air which is stored under pressure and metered into the air flow path of the primary cooling system. The display case is coilless, the depressed temperature being maintained primarily through conduction panels forming the bottom and walls of the product zone, which conduction panels are disposed in intimate contact with the refrigerated air supply from the primary evaporator unit. Apertures through the conduction panels are provided to leak cold dry air into the product display zone to attain spillage at a low rate. System efficiency is increased by providing baffles to insure intimate contact of the dry

refrigerated air against the thermally conductive panels comprising the walls as well as the bottom panel of the product zone.

3,577,745

ICE MAKING APPARATUS


Elmer W. Zearfoss, Jr., Philadelphia, Pa., assignor to Philco-Ford Corporation, Philadelphia, Pa.

Filed May 23, 1969, Ser. No. 827,239

Int. Cl. F25c 1/10

U.S. Cl. 62-345

7 Claims



Centrifugal ice-freezing apparatus including a plurality of flexible or otherwise deformable molds or pockets disposed in circular array, and having open portions presented radially inwardly toward a central axis about which they are rotatable. Means is provided for filling the pockets, and for rotating them to retain water therein by centrifugal force. While rotating, the molds are flexed and pivoted to ice freezing position, and are subjected to below freezing temperatures until the water is frozen. Upon freezing of the water, rotation is halted to accommodate both flexing and pivoting of the molds to ice ejecting position.

3,577,746

SELF-CONTAINED LUBRICATION SYSTEM FOR HIGH SPEED DRIVE SHAFT COUPLING


Clarence F. Dolan, Erie, Pa., assignor to General Electric Company

Filed Jan. 29, 1969, Ser. No. 795,116

Int. Cl. F16d 3/06

U.S. Cl. 64-23

1 Claim



A self-contained lubrication system for a splined high speed drive shaft coupling. One of the splined shafts is coated with a mixture of a solid lubricant and grease. A grease reservoir is mounted on one of the shafts to replenish the lubricant required at the spline surfaces. Rotation of the shafts forces the oil in the grease from the reservoir onto the spline surfaces thereby constantly replenishing the oil content of the lubricant mixture provided at the spline surfaces.

3,577,747

TORQUE LIMITING CLUTCH

James Murrell Brown, Box 1388, Levelland, Tex.

Filed June 17, 1969, Ser. No. 833,955


Int. Cl. F16d 7/00

U.S. Cl. 64-29

3 Claims

A self-aligning, adjustable torque-limiting clutch has a can-shaped body which is attached to the driving shaft. A bolt is attached to the driven shaft and the bolt extends through the body and journaled at each end thereof for alignment sup-

port. One serrated plate is attached to the body and another serrated plate to the bolt and the serrated plates are held



together by a compression spring inside the body, acting against an adjustable nut on the bolt.

3,577,748

DEVICE FOR HAND KNITTING


Dena S. Nortland, 46 Washington Ave., Dumont, N.J.

Filed Mar. 2, 1970, Ser. No. 15,681

Int. Cl. D04b 3/00

U.S. Cl. 66-4

6 Claims



A device for use in knitting by hand which includes a bar adapted to be held in one hand and having a series of aligned posts on which are mounted yarn-receiving members respectively. The said members have oppositely disposed confronting ends which are spaced apart to provide openings therebetween. The yarn-receiving members are mounted on the posts for relative movement to dispose said members in any one of three positions, namely a position in which said openings between the confronting ends of said members are closed, a position in which passageways into said members are provided on one side of the posts respectively and a position in which passageways are provided on the opposite side of the posts respectively. Means is also provided forming stops for limiting the movement of said yarn-receiving members respectively.

3,577,749

CIRCULAR KNITTING MACHINES

Dennis Wright, Aylestone, England, and Thomas Adams, West Knighton, England, assignors to The Bentley Machine Development Company Limited


Filed July 18, 1968, Ser. No. 745,753

Claims priority, application Great Britain, July 22, 1967, 33820/67

Int. Cl. D04b 15/32, 15/68

U.S. Cl. 66-50

4 Claims



A needle selecting system in a circular knitting machine employing rockable selecting instruments cooperating with

needles in the needle cylinder tricks, such instruments being adapted to be projected from their tricks and to have particular ones depressed selectively to miss a raising cam which the others engage, wherein the instruments are controlled by cam means so organized that instruments which through being depressed have remained at low level are rocked to project them out of their tricks before the remaining instruments raised by the raising cam have been subsequently lowered to the low level, means being provided to cause a fresh selection to be made immediately after the raised instruments descend to the level of those not raised. Thereby the needle selection and its subsequent cancellation are performed in a shorter than normal circumferential distance round the needle cylinder, this being particularly advantageous in a multifeed machine.

3,577,750

INSPECTION APPARATUS FOR CIRCULAR KNITTING MACHINES

Joseph Venczel, St. Lawrence, Jersey, Channel Islands, Great Britain, assignor to Electronit Limited, St. Lawrence, Jersey, Channel Islands, Great Britain


Filed July 18, 1969, Ser. No. 843,005

Claims priority, application Great Britain, July 22, 1968, 34979/68

Int. Cl. D04b 35/18

U.S. Cl. 66-157

7 Claims



Inspection apparatus in combination with a circular knitting machine, the apparatus performing the function of detecting a broken knitting needle and giving an alarm or stopping the machine in response to such detection. A sensing arrangement of a photoelectric or magnetic kind is positioned near the needles as they rotate and is so arranged to give curved pulses of amplitude corresponding to the size of the needle. A timing circuit gives an initial timing pulse when the amplitude of the curved pulse rises above a predetermined level and a final timing pulse when the amplitude of the curved pulse falls below the predetermined level. A multivibrator is triggered or synchronized to give reference pulses to predetermined lengths in response to each initial timing signal. Reference pulses are applied to a gate which is closed during the periods between initial timing signals and the following final timing signals. If a reference pulse or part of it is applied to the gate at any other time an alarm output signal is given. The multivibrator may be a monostable circuit, in which case gaps between groups of needles do not give an output or it may be a free-running multivibrator in which case missing needles are also detected.

3,577,751

THREE-COMPARTMENT SIX-DOOR WASHER AND EXTRACTOR

Max Hertig, and Peter J. Meier, Syracuse, N.Y., assignors to G. A. Braun, Inc., Syracuse, N.Y.

Filed Feb. 13, 1969, Ser. No. 798,973


Int. Cl. D06f 37/08, 37/10

U.S. Cl. 68-143

2 Claims

Laundry washer and extractor having a perforate wash drum rotatable on a horizontal axis, partitions within the drum dividing the drum into three like compartments, separate access doors for each compartment disposed adjacent each compartment partition, and a surrounding stationary shell for retaining wash and rinse water, and having a

sump and rain valve and having an arcuate doorway in one side thereof extending from levels above and below the drum



axis by amounts substantially the circumferential width of the drum doors, and a door for the arcuate shell doorway.

3,577,752

LAUNDRY APPARATUS


Max Hertig, and Peter J. Meier, Syracuse, N.Y., assignors to G. A. Braun, Inc., Syracuse, N.Y.

Filed Nov. 12, 1968, Ser. No. 775,088

Int. Cl. D06f 39/14

U.S. Cl. 68-210

4 Claims



Institutional laundry equipment including laundry washing and extracting apparatus having a substantially airtight casing, with separate loading and unloading doors, disposed in a partition dividing a laundry area into a laundry-receiving room and a clean laundry room, the receiving room having an exhaust fan for maintaining subatmospheric pressure in the receiving room, an air duct connecting the casing with outside air, port means in the casing opening into the receiving room, and interlocking means for the doors to maintain at least one of the doors closed at all times, the port means being either an air duct or a casing water dump valve open to the receiving room or both.

3,577,753

METHOD AND APPARATUS FOR FORMING THIN-WALLED CYLINDRICAL ARTICLES

Dipak C. Shah, Bethlehem, and Louis S. Schwartz, Schnecksville, Pa., assignors to Bethlehem Steel Corporation


Filed Sept. 30, 1968, Ser. No. 763,715

Int. Cl. B21d 22/28, 37/16, 37/18

U.S. Cl. 72-41

5 Claims

A method and apparatus for forming thin-walled containers from flat blanks is disclosed herein. The flat blanks are precoated with a dry film lubricant and drawn and ironed



thermal breakdown of the lubricant comprising an internally fluid-cooled punch and fluid-cooled dies.

3,577,754

PROCESS AND APPARATUS FOR ROLLING SEAMLESS TUBES

Albert H. Calmes, 4, Avenue DuJaman, Lausanne, Switzerland

Division of Ser. No. 421,845, Dec. 29, 1964, Pat. No. 3,394,568.


Filed May 14, 1968, Ser. No. 728,938

Claims priority, application Great Britain, Sept. 9, 1964, 36988/64

Int. Cl. B21b 45/02, 27/10, 17/04

U.S. Cl. 72-45

6 Claims



A hollow metal blank is rolled forward upon an advancing hollow tapered mandrel to reduce the wall thickness of the blank in longitudinally-spaced steps and thereby elongate it and form gaps around the mandrel between those steps. Lubricant is forced into the mandrel and discharged laterally from it into at least one of said gaps to fill it. The lubricant is prevented from flowing from the gaps back into the mandrel as the gaps are shortened by the advancing mandrel, so the shortening of the gaps with their restricted rear ends increases the pressure on the lubricant above the supply pressure.

3,577,755

SLEEVE FOR PROTECTING THE PEG IN THE HEAD OF A CARBON ANODE ELECTRODE AND APPARATUS FOR PRODUCING THIS SLEEVE

Karl Fricker, Meilen, Zurich, Switzerland, assignor to Swiss Aluminium Ltd., Chippis, Switzerland

Division of Ser. No. 582,117, Sept. 26, 1966.

Filed Dec. 24, 1968, Ser. No. 786,571


Int. Cl. B21d 39/02

U.S. Cl. 72-51

4 Claims

Sleeve-forming apparatus comprising a former of rectangular section around which a strip of sheet aluminum is arranged to be bent to form the sleeve or tube and which has three smooth faces for forming the three flat walls of the tube and a fourth face formed with a V-shaped groove extending

parallel to the edges of the former with the base of the groove adjacent to that face of the former over which the wall of the tube which will carry the part of the fourth wall of the tube on which the first flange is formed, a pressure jaw for clamping the aluminum strip against the middle of the three flat faces of the former, a pair of shaping jaws which are arranged to be swung up so that they each closely embrace a different one of the other two flat faces and part of



the grooved face of the former in order to bend the strip which is clamped by the clamping jaw against one flat face of the former along the other two flat faces of the former and over the grooved face of the former, and an element having a folding edge which is arranged to be swung against the grooved face of the former so that the folding edge enters the V-shaped groove and forms the first flange and the inclined portion and second flange on the edges of the strip by forcing them into the groove of the former.

3,577,756

TWO-PASS WELD BEAD FINISHING PROCESS FOR PIPE AND TUBING


James E. Cramer, Rte. 6, Box 118, Burlington Township, Racine County, Wis.

Filed June 4, 1969, Ser. No. 830,374

Int. Cl. B21b 21/00, 17/10

U.S. Cl. 72-193

4 Claims



This invention relates to apparatus for removing an internal weld bead from longitudinally welded metal tubing during longitudinal movement of the tubing. The apparatus has a plurality of spaced-apart plugs each positioned axially within the tubing and having a diameter portion in simultaneous contact with the weld bead and an opposite internal surface area of the tubing. Separate means are associated with each plug for sequentially applying a compressive force to the tubing over an external surface area thereof adjacent the plug to compress the tubing against the contacting diameter portions of the plug. During force application the plug moves axially a distance with the tubing. The plug is flexibly anchored which permits it to return to its original position upon release of the compressive force.

3,577,757 ROLLER FRAME STRUCTURE WITH ONE OR MORE PRESSING DEVICES FOR MAINTAINING CONSTANT THE GAP BETWEEN THE ROLLERS

Ernst H. Barten, Buschhütten, Germany, assignor to Achenbach Sohne G.m.b.H., Buschhütten near Siegen, Germany


Filed Mar. 14, 1968, Ser. No. 713,192

Claims priority, application Germany, June 27, 1967, A56096

Int. Cl. B21b 31/30, 31/32

U.S. Cl. 72-237

6 Claims



Roller frame in which the rollers are urged toward each other under a certain preload as by a threaded spindle with hydraulic piston-cylinder means acting between the rollers in separating direction. The pistons bottom in the cylinders at a predetermined point and the cylinders are supplied with fluid under pressure in conformity with the movement of the rollers away from each other when a strip is passing therebetween.

3,577,758

APPARATUS FOR EXTRACTING CHOCKS, GUIDES, AND COUPLINGS FROM ROLL ASSEMBLIES


James Richard Adair, Pittsburgh, Pa., assignor to United Engineering and Foundry Company, Pittsburgh, Pa.

Filed Apr. 21, 1969, Ser. No. 817,881

Int. Cl. B21b 31/08

U.S. Cl. 72-239

13 Claims



The roll-disassembling apparatus disclosed is provided with saddle surfaces to support a roll assembly by engaging neck portions on the roll which are located between the bearing chocks and roll body. These saddle surfaces form part of a cradle assembly that is vertically movable to locate a roll assembly that is vertically movable to locate a roll assembly at a desired elevation where disassembling thereof takes place. At each side of the roll body there is provided a movable car having latches to support and extract a rest bar along with a roll guide mounted thereon. A coupling member at one end of the roll assembly is extracted by a movable carriage having a coupling support platen that may be elevated by a screwjack. The bearing chocks are next extracted from the roll journals by displaceable sleds, each having a chock support platen that may be elevated by a screwjack. The carriage used to remove the coupling member is independently supported by one of the chock-extracting sleds.

3,577,759 METHOD OF AND APPARATUS FOR PREPARING COPPER AND BRASS BILLETS FOR EXTRUSION INTO HOLLOW SHELLS


Paul Tandler, Clayton, Mo., and Ellis R. Blackwell, East St. Louis, Ill., assignors to Cerro Corporation, New York, N.Y.

Filed Mar. 13, 1968, Ser. No. 712,857

Int. Cl. B21c 23/01

U.S. Cl. 72-254

13 Claims



This invention is concerned with a prepiercing and scalping method, in which the billet is precompressed, pierced and scalped, in a substantially continuous closely controlled operation, in a single press, for the purpose of preparing the billet for subsequent extrusion in an extrusion press. The method is designed to prevent distortion or deflection of the piercing mandrel, prevent the wear and tear encountered in the conventional extrusion cycle, and to save time. Provision is made for removal of the slug or breakout resulting from the prepiercing operation, as well as to sever the scalped material into easily removable segments or parts. The invention is further concerned with a press of novel construction for performing the method.

3,577,760

ROLL FORGING MACHINE

Rolf Franke, Osterath, Germany, assignor to Brightside Foundry & Engineering Company Limited, Sheffield, Yorkshire, England


Filed Dec. 18, 1968, Ser. No. 784,784

Claims priority, application Great Britain, Dec. 18, 1967, Aug. 17, 1968, 57417/67; 39456/68

Int. Cl. B21b 13/20

U.S. Cl. 72-215

12 Claims



A forging machine comprising at least two roll carriers arranged on opposite sides of material to be reduced. Each roll carrier includes a bush having one or more arms attached thereto. Work rolls are arranged in the ends of the arms. The roll carriers are moved in noncircular paths, the paths being somewhat flattened when engaging the material to be reduced. The machine also includes means for altering the distance between the work rolls in the flattened portion of their paths.

3,577,761

METHOD OF MANUFACTURING COMPONENTS FROM A PART PROJECTING FROM A LARGER PART, HAVING SLIM AND/OR ELONGATED FORM

Eskil Monestam, Umea, Sweden, assignor to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden


Filed Mar. 4, 1968, Ser. No. 711,829

Claims priority, application Sweden, Mar. 7, 1967, 3082/67

Int. Cl. B21c 23/00

U.S. Cl. 72-256

2 Claims



In the manufacture of objects or components with one part having larger dimensions and one part having slim and/or elongated form, a billet is used which in a first step is forged, preferably cold-forged to a blank with decreasing cross section. This blank is thereafter, possibly after annealing and machining, extruded by means of liquid pressure to the desired shape and dimension at the narrow end of the blank.

3,577,762

METHODS AND DEVICES FOR THE DYNAMIC TESTING OF MATERIALS


Erhard Hornbogen, Göttingen; Erwin Niessner, Neuenburg, Baden, and Gert Buck, Bad Überkingen, Germany, assignors to Buck K. G., Bad Überkingen, Germany

Filed Mar. 27, 1969, Ser. No. 811,053

Int. Cl. G01n 3/08

U.S. Cl. 73-12

7 Claims



A conical housing is provided with a stick of explosive disposed axially within the housing. The apex angle of the housing is chosen so that a shock wave front produced by igniting the explosive is tangential to an internal conical wall of the housing. A plurality of measurement sites are disposed over the internal wall and specimens to be tested are mounted therein. The stick of explosive is ignited and the resulting distortion of the specimens is observed.

3,577,763

APPARATUS FOR SELECTIVELY PROGRAMMING DIFFERENT TYPES OF SHOCK TESTS

John O. Beal, Pacific Grove, Calif., assignor to Monterey Research Laboratory, Inc., Monterey, Calif.

Filed June 2, 1969, Ser. No. 829,405


Int. Cl. G01n 3/08

U.S. Cl. 73-12

7 Claims

Apparatus for selectively programming different types of shock tests in which a movable shock table is moved toward

a reaction mass. A programmer in series with the shock table and the reaction mass controls the shock pulse produced by the impact between the shock table, the programmer and the



reaction mass. The movable shock table is formed with a gas filled chamber. The programmer includes a piston and an elastomer assembly. The piston is received by the gas filled chamber formed in the movable shock table.

3,577,764

TARGET HOLDING CONTROL UNIT


Abraham L. Korr, Philadelphia, Pa., assignor to the United States of America as represented by the Secretary of the Army

Filed Aug. 14, 1969, Ser. No. 850,129

Int. Cl. G01n 3/08

U.S. Cl. 73-12

6 Claims



A multitarget holding control unit for collecting specimens from a particle accelerator arrangement normally operating under a vacuum condition to enable performance studies in the hypervelocity impact phenomena of accelerated small solid particles having a size on the order of 10^{-14} cm. in diameter. A cup-shaped housing has its base secured to the hub of a centrally apertured adapter for sealed connection to a particle accelerator arrangement. A plurality of apertured cover, sealingly secured to an outward face of the cup peripheral sidewall, supports respective target plate shafts, index means and control knob. Within the completely sealed unit, a plurality of overlapping and longitudinally spaced target plates are arranged on their shafts such that a peripheral target space on each target plate disc can be simultaneously aligned with the adapter aperture. Each of the peripheral targets on each plate is provided with an electrical conductive means to collect electrical charges carried by particles and controllably delivered through the adapter aperture to the peripherally mounted target.

3,577,765 APPARATUS FOR DETERMINING CRYSTALLIZATION TEMPERATURE


Joseph Bertoglio, Collinsville, Ill.; Philip L. Deming, St. Louis, Mo.; Joyce G. Eckert, Columbia, Ill., and James R. Shafer, Bridgeton, Mo., assignors to Monsanto Company, St. Louis, Mo.

Filed Dec. 26, 1967, Ser. No. 693,211

Int. Cl. G01n 1/00

U.S. Cl. 73-17

6 Claims



Method and apparatus for automatically determining the crystallization temperature of a flowing liquid. Temperature control means are adapted to vary the liquid viscosity within a crystallization zone. Changes in flow or pressure drop caused by the viscosity changes provide the basis for temperature control. Because operation of the system is cyclic, the effects of heat of crystallization of the liquid can be observed on a recording of crystallization zone temperature, thus identifying the crystallization temperature.

3,577,766

FLUIDIC GAGE


John H. Walker, Dayton, Ohio, assignor to The Bendix Corporation

Filed Jan. 23, 1969, Ser. No. 793,270

Int. Cl. G01b 13/10

U.S. Cl. 73-37.9

18 Claims



3,577,767

FELT PERMEABILITY TESTING APPARATUS

Udino Stedile, Pinnerolo, Italy, assignor to Beloit Corporation, Beloit, Wis.

Filed Nov. 24, 1969, Ser. No. 879,289


Int. Cl. G01n 15/08

U.S. Cl. 73-38

2 Claims

Various permeability characteristics of a sample of felt or other permeable web materials are determined by testing ap-

paratus comprising a pair of interchangeable platens between which the sample is subjected to controlled compression as a measured flow of liquid is forced through the sample from leak, flows into the accumulator from which it is pumped through a sample gas conduit to a gas sensor sensitive to the tracer gas. The sensor activates valves to supply a purging gas



one platen to the other along a predetermined flow path established by the particular pair of platens installed in the apparatus.

3,577,768

HYDROSTATIC TESTING APPARATUS


Theophil Aprill, Jr., and John R. Leerkamp, Ann Arbor, Mich., assignors to A & L Battery & Electric Service, Inc., Ann Arbor, Mich.

Filed Sept. 2, 1969, Ser. No. 854,614

Int. Cl. G01m 3/26

U.S. Cl. 73-40.5R

14 Claims



Portable apparatus for hydrostatically testing hydraulic equipment such as hydraulic-electric and air-over-oil car, truck and bus lifts, hydraulic dock leveling devices, hydraulic docks, and the like, to ensure its safe functioning and for preventative maintenance. The apparatus includes a reservoir for hydraulic fluid, supply means for supplying hydraulic fluid under pressure to the equipment being tested, a pressure gauge assembly including a fitting for connection to the equipment being tested and a pressure gauge in communication with the fitting for registering the pressure in the equipment, and valve means for isolating the gauge and the fitting from the supply means.

3,577,769

LEAK-DETECTION SYSTEM

John Alfred Roberts, Lynnfield Center, Mass., assignor to General Electric Company


Filed Apr. 2, 1969, Ser. No. 812,710

Int. Cl. G01m 3/20

U.S. Cl. 73-40.7

10 Claims

Leak-detecting apparatus having an enclosure for a container to be tested providing a sample gas accumulator. The container is charged with a tracer gas which in the case of a



to the sample gas conduit to purge the sensor thereby cutting off all flow of tracer gas to the sensor. This occurs before saturation of the sensor thereby preventing saturation with the resultant long recovery time.

3,577,770

TEST-CLOSURE FOR OPEN-TOPPED CONTAINERS


Stanley B. Shaw, Sunol; Ronald H. Gehl, and Gordon R. Roemer, Fremont, Calif., assignors to C T Supply Co., Fremont, Calif.

Filed May 5, 1969, Ser. No. 821,793

Int. Cl. G01m 3/32

U.S. Cl. 73-49.8

7 Claims



A test closure for use in an automatic can-testing machine operative to test open-topped containers prior to their being filled with a food product and sealed to make certain that an airtight chamber is established by the sidewall and bottom closure attached thereto. The test closure includes a thick resilient pad engageable with the angularly disposed, outwardly flared rim of such container to establish an hermetic seal therewith. The face of the test closure pad engageable with the container rim has an angular disposition essentially corresponding to that of the rim so as to be engageable with a relatively wide surface portion thereof.

3,577,771

SWING-WEIGHT AND STATIC WEIGHT BALANCE FOR GOLF CLUBS

Karsten Solheim, 10412 North 37th St., Phoenix, Ariz.

Filed Aug. 30, 1968, Ser. No. 756,535


Int. Cl. G01m 1/12

U.S. Cl. 73-65

9 Claims

Apparatus for measuring swing weight and static weight of golf clubs adapted to employ a table or counter top as a base is provided by an elongated rigid member having: a first upright section at one end thereof to support a golf club shaft; a second upright section at the other end to hold the grip end of the club; and two longitudinally displaced rockers

functioning as fulcrums between the two end sections. The position of a balance weight is adjusted to balance the rigid member on one rocker with a golf club held by the upright sections with the shaft supported by the first upright section and extending away from the second upright section. For measuring the swing weight of clubs without grips, there is provision for adjusting the position of each club so held rela-



tive to the upright sections depending on the length of its shaft. For measuring static weight, the club is held with its shaft transverse the elongated rigid member at the one end thereof and balance is obtained on the second rocker by adjusting the position of the balance weight. Swing weight or static weight is then read on a scale from the position of the balance weight, depending upon which rocker is used.

3,577,772

DEVICE FOR DIAGNOSTIC EXAMINATION BY ULTRASONIC OSCILLATIONS

Jean Perihou, Bourg La Reine, and Michel Joseph Auphan, Neuilly Sur Seine, France, assignors to U.S. Philips Corporation, New York, N.Y.


Filed May 8, 1967, Ser. No. 637,000

Claims priority, application France, May 6, 1966, 60559

Int. Cl. G01n 29/04

U.S. Cl. 73-67.7

8 Claims



An ultrasonic device for examining the internal parts of the body comprising a plurality of ultrasonic transmitters mounted along a horizontal line on a movable carriage and triggered sequentially. A plurality of receivers is mounted on the carriage along a vertical line that intersects the horizontal line at right angles. The movement of the carriage is synchronized with the deflection of an electron beam in a PPI cathode-ray tube to provide a visual display of the surface contour of the internal body part under investigation.

3,577,773 METHOD AND APPARATUS FOR MEASURING THE PERCENTAGE OF ELONGATION OF METAL STRIPS

Moritada Kubo, Tokyo, and Kuniji Asano, Kawasaki-shi, Japan, assignors to Tokyo Shibawra Electric Co., Ltd., Kawasaki-shi, Japan


Filed Sept. 24, 1969, Ser. No. 860,753

Claims priority, application Japan, Sept. 30, 1968, Oct. 4, 1968, 43/70226; 43/71849

Int. Cl. G01n 29/00

U.S. Cl. 73-67.7

9 Claims



The percentage of elongation of a rolled metal strip is measured by apparatus comprising a plurality of spaced apart magnetic or ultrasonic detectors which are disposed along a line parallel to the direction of movement of the metal strip and not in contact therewith. Signals produced by adjacent pairs of detectors are compared to obtain difference signals which are squared and then added together to provide a signal representing the percentage of elongation of the metal strip.

3,577,774

ELECTROSTATIC ULTRASONIC NONDESTRUCTIVE TESTING DEVICE


Robert W. Steffens, Richland, and Milton F. Zeuschel, Bellevue, Wash., assignee The United States of America as represented by the United States Atomic Energy Commission

Filed Feb. 24, 1969, Ser. No. 801,389

Int. Cl. G01n 29/00

U.S. Cl. 73-67.8

1 Claim



An ultrasonic device for nondestructively testing an electrically conductive sample comprises an electrode mounted to said sample and electrically insulated therefrom. Means are provided for generating a pulsed potential difference between the sample and the electrode to generate an elastic wave in the sample. A bias voltage is applied to the electrode and an oscilloscope is used to detect, relative in time to the applied pulsed potential difference of the electrode, changes in the bias potential of the electrode response to the elastic wave.

3,577,775 BOND LINE TEST TOOL


Albert G. Henderson, Hereford, Md., assignor to The United States of America as represented by the Secretary of the United States Air Force

Filed June 17, 1969, Ser. No. 833,911

Int. Cl. G01n 19/04

U.S. Cl. 73-95

2 Claims



A tool for testing the integrity of a bond line at the interface of the skin and core of a honeycomb panel structure. The tool includes, as major components, means for gripping a wall of a core cell of the honeycomb panel, means for applying a controlled tensile pull to the bond line at the skin-to-core interface by pulling on the gripped core cell wall, and means for supporting and guiding the gripping means and the tensile pull means.

3,577,776

FUEL PUMP TESTING METHOD AND APPARATUS


Thomas J. Brown, Jr., Columbus, Ind., assignor to Cummins Engine Company, Inc., Columbus, Ind.

Filed May 22, 1969, Ser. No. 826,912

Int. Cl. G01m 15/00

U.S. Cl. 73-119A

7 Claims



Method and apparatus for testing and calibrating a fuel pump of the type used in "common rail" fuel systems for diesel engines. The fuel pump remains mounted on and driven by the engine. The method involves disconnecting the pump from the injectors, or other fuel delivery means of the engine, and connecting the pump to flow measuring apparatus. The pump remains mounted on and driven by the engine, and the engine in turn receives fuel for its operation from a second fuel pump. An important requirement of the test apparatus is that the pump to be tested must be driven at various controlled speeds. This is accomplished by means for controlling the pressure output of the second fuel pump.

3,577,777

INERTIA SYSTEMS FOR DYNAMOMETERS


Ray W. Whelan, Redwood City, and Edmond J. Atelian, San Carlos, Calif., assignors to Western Gear Corporation, Lynwood, Calif.

Filed Apr. 1, 1969, Ser. No. 812,200

Int. Cl. G01l 5/28

U.S. Cl. 73-133

4 Claims



An inertia system for supplying a predetermined amount of energy through a rotating shaft to a dynamometer or like apparatus to permit testing various devices such as brakes. The system includes rotatably supported inertia elements on preferably two shafts connected together by a gear train to permit a substantially infinite variation of inertia and at the same time reduce the required strength of the torque transmitting gearing by employing a connecting gear train.

3,577,778

TORQUE MEASURING TOOL


Gunar Liepins, 1215 Wines Drive, Ann Arbor, Mich.

Filed July 1, 1969, Ser. No. 838,228

Int. Cl. G01l 5/24

U.S. Cl. 73-139

9 Claims




A torque wrench which is particularly adapted for supporting an Allen-type wrench and for indicating the torque that is applied. A shaft is provided on one end of which is mounted a chuck, the shaft being slotted to permit insertion of the Allen-type wrench through the chuck. A hollow transparent plastic handle is connected to the other end of the shaft by an elastomeric coupling, and a torque indicator mechanism extends between the shaft and the handle and is visible through the transparent handle to indicate the torque applied to the Allen-type wrench.

3,577,779
CONSTANT MOMENT BEAM TRANSDUCERS
 Eric Laimins, Belmont, Mass., assignor to BLH Electronics Inc., Waltham, Mass.
 Filed Mar. 14, 1969, Ser. No. 807,190
 Int. Cl. G011 1/22

U.S. Cl. 73-141

5 Claims




A strain-responsive force transducer includes a constant moment parallelogram-type cantilever-beam unit equipped with strain gages wherein the cantilever-beam unit is held fixed at one end to a support and has a movable end rigidly secured to a force-applying member, guided by spaced diaphragms, the cantilever-beam unit being directly connected between the support and force-applying member without auxiliary flexure provisions and accommodating relative movement between the force-applying member and support with minimum attendant nonlinearities in electrical outputs developed by the strain gages.

3,577,780
METHOD OF MEASURING TIRE UNIFORMITY
 Lawrence R. Sperberg, 6740 Fiesta Drive, El Paso, Tex. 79912
 Continuation-in-part of application Ser. No. 608,344, Jan. 10, 1967, now Patent No. 3,478,581, dated Nov. 18, 1969. This application Nov. 12, 1969, Ser. No. 875,763
 Int. Cl. G01m 17/02

U.S. Cl. 73-146

7 Claims




A tire uniformity machine having means for rotatably mounting a pneumatic tire and a test wheel on an elongated frame and wherein the outer periphery of the test wheel is held adjacent the outer periphery of the tire with a predetermined pressure. The elongated frame is hinged on each side and provided with axially rotatable means to enable the test wheel to be aligned with the buttress area or sidewall of the tire, in addition to the conventional location adjacent the tread. The test wheel is provided with strain gauges and the diameter of the test wheel with respect to the diameter of the tire is held between the limits of 1:30 and 1:4, with the ratio of 1:16 being ideal or optimum.

3,577,781
TOOL TO TAKE MULTIPLE FORMATION FLUID PRESSURES
 Maurice P. Lebourg, and Roger Q. Fields, Houston, Tex., assignors to Schlumberger Technology Corporation, Houston, Tex.
 Filed Jan. 10, 1969, Ser. No. 790,321
 Int. Cl. E21b 47/06

U.S. Cl. 73-152

12 Claims



A number of pressure readings with respect to fluids in formations traversed by a well bore are obtained in a single traverse of the well bore by a special tool. The tool has a sample chamber comprising one or more compartments for receiving separate samples of formation fluid. The pressure of the fluid in each sample (and hence the pressure of the corresponding fluid in the formation) is measured. In the one-compartment embodiment, fluid is expelled from the compartment after each collection and pressure measurement of a fluid sample. In the two-compartment embodiment, fluid is collected in one compartment and a pressure measurement is made, and fluid previously collected and measured for pressure is expelled. In one embodiment, the samples are expelled into the well bore; in another, into a dump chamber carried in the tool. In embodiments in which the chamber is divided into a large number of compartments, each compartment is used for the collection of only one sample, and the collected samples are not expelled until the tool is recovered.

3,577,782
WELL LOGGING TOOL FOR MAKING MULTIPLE PRESSURE TESTS AND FOR BOTTOM HOLE SAMPLING

John Aitken, Paris, France, assignor to Schlumberger Technology Corporation, Houston, Tex.

Filed Jan. 10, 1969, Ser. No. 790,322
 Int. Cl. E21b 49/00


U.S. Cl. 73-155

13 Claims

Apparatus is provided for obtaining a plurality of readings with respect to fluids in formations traversed by a well bore. The apparatus includes a housing, annular sealing means for sealing off an area of the wall of the well bore from fluid within the well bore, and formation-fluid-receiving sample chamber means within the housing in communication with sealed-off area of the wall. Gauge means operatively associated with the chamber means is provided for obtaining a reading with respect to fluid within the chamber means, and motive means is provided for bringing the chamber means into cooperation with discrete samples of formation fluid col-

lected at spaced-apart locations in the well bore. In this way, a plurality of readings with respect to fluid in the formations

pressure therein and facilitate collection of a fluid sample from the formation. The delay is facilitated by a choke formed in one branch of the conduit and, in one embodiment, by a check valve and a piston-cylinder assembly mounted in the same branch.




3,577,783
TOOL TO TAKE MULTIPLE FLUID MEASUREMENTS
 Frank R. Whitten, and Roger Q. Fields, Houston, Tex., assignors to Schlumberger Technology Corporation, Houston, Tex.

Filed Jan. 10, 1969, Ser. No. 790,199
 Int. Cl. E21b 47/06

U.S. Cl. 73-152

10 Claims




A plurality of readings with respect to fluids in formations traversed by a well bore is obtained in a single traverse of the well bore by a special tool. The tool includes a piston-cylinder assembly having two pistons of differential diameter and serving as a pressure multiplier responsive to the pressure of fluid in the well bore for generating pressure in an operating fluid in a branching conduit in the tool greater than the pressure of the fluid in the well bore at the depth of the tool. Upon opening of a valve in the conduit, the operating fluid sets a shoe against the wall of the well bore and, by reaction, forces annular sealing means on the tool against the wall of the well bore to seal off an area of the wall from fluid in the well bore. After a short delay to permit the setting and sealing, a collection chamber in the tool in communication with the annular sealing means is expanded to reduce the

3,577,784
METHOD AND APPARATUS FOR MEASURING COKE OVEN FLUE WALL TEMPERATURES
 Joseph E. Kovacic, Pittsburgh, Pa., assignor to Koppers Company, Inc.

Filed Dec. 30, 1968, Ser. No. 787,879
 Int. Cl. G01j 5/08

U.S. Cl. 73-355R

10 Claims




A hollow probe having an angularly positioned reflective surface is inserted through an inspection opening in a coke oven battery roof into an "off" flue. The reflective surface is focused on the flue wall at a preselected elevation and reflects the radiant energy emitted by the flue wall along an unobstructed vertical passageway within the probe to a radiation pyrometer positioned externally of the flue where the flue wall temperature is determined and recorded. The probe includes three concentric cylindrical members. Adjacent the lower end portion of the probe there is an opening in the cylindrical members providing a window for the reflective surface. A coolant is circulated between the outer and intermediate cylindrical members and an inert gas is blown through the central passageway to prevent contamination of the reflective surface.

3,577,785
TRANSDUCER CLEANING DEVICE
 Lawrence Norayr Guevrekian, Kendall Park, N.J., assignor to Hoffman-La Roche Inc., Nutley, N.J.

Filed June 11, 1969, Ser. No. 832,351
 Int. Cl. G011 9/00, G011 7/18

U.S. Cl. 73-398

5 Claims



A measuring instrument comprising, in a tube, a column of an electrically conductive liquid having a height which is

responsive to the input parameter to be measured, an electrical circuit to transform the height of the liquid column into an electrical output value by measuring the voltage drop across the nonimmersed part of a current-carrying wire extending through the tube, and maintaining exact longterm performance of the wire by providing an application of heat thereto thereby preventing contamination of the wire which would otherwise cause nonlinearities between input and output values.


3,577,786

FLUERIC ACCELEROMETER

Albertus E. Schmidlin, Caldwell, N.J., assignor to General Precision Systems, Inc., Little Falls, N.J.
Filed June 25, 1968, Ser. No. 739,882
Int. Cl. G01p 15/02


U.S. Cl. 73-515

17 Claims



A flueric accelerometer comprising a chamber for a non-wetting liquid along with means to pass a pressurized gas through the liquid for detecting differences in hydrostatic pressure of the liquid in response to changes in acceleration of the chamber.

bolometer circuit senses deviations of the gyro rotor and adjusts the gyro housing relative to the gyro rotor to correct deviations.




3,577,789

POWER TAKEOFF ACTUATOR

Claude Sansam, P.O. Box 235, North Land O'Lakes, Wis.
Filed Mar. 19, 1969, Ser. No. 808,549
Int. Cl. F16h 37/100, F16h 21/44, F16h 5/06
U.S. Cl. 74-11

9 Claims



The apparatus includes a rotary reversible electric motor which is energized by the electrical system of a vehicle. The motor has an oscillatable output shaft which carries a radially extending link having an opening in its outer end. A translatable link transmits power between the shaft and a shiftable lever of the power takeoff unit which accomplishes engagement and disengagement of the takeoff unit. The translatable link either rigid or flexible has oppositely offset end portions which engage openings in the radially extending link and shift lever to effect a connection therebetween.

3,577,788

SPHERICAL AIR BEARING GYRO

Friedrich J. Tischer, 2300-M4-Avent Ferry Road, Raleigh, N.C.


Filed Jan. 16, 1969, Ser. No. 791,599

Int. Cl. G01c 19/12, G01c 19/28

U.S. Cl. 74-5.6

10 Claims

A spherical air bearing gyro that is pneumatically actuated and supported as a two-degree-of-freedom gyro. One specie



Two members having abutting surface portions are pressed into frictional engagement by rivet means so the relative position of the members can be adjusted by overcoming the friction. The adjustment is effected by a tool inserted into a bearing opening of one of the members and effecting displacement of the other member. A rivet passes through a camming slot in one of the members, and through a bore in the other member, and by displacing the rivet in the camming slot, the adjustment is effected. The camming slot is slanted prevents undesired relative adjustment of the two members.

3,577,790

MECHANISMS FOR EFFECTING FINE AND COARSE ADJUSTMENT


Alexander John Munro, Acomb, and John Francis Taplin, Croydon, England, assignors to Vickers Limited, London, England

Filed Oct. 10, 1969, Ser. No. 865,307

Int. Cl. F16h 29/20

U.S. Cl. 74-89.14

4 Claims



A mechanism for effecting fine and coarse adjustment in which a first member is mounted for movement relatively to a second member. The mechanism includes two substantially mutually perpendicular shafts which are geared together and which are rotatable relatively to each other to effect said movement.

3,577,791


CONTROL SYSTEM

Jan Abraham Vanden Broek, Ann Arbor, Mich., assignor to Conduction Corporation, St. Charles, Mo.
Filed Jan. 22, 1969, Ser. No. 792,949

Int. Cl. F16h 27/02

U.S. Cl. 74-89.15

7 Claims



A mount for an optical element has a stationary base, a mounting plate, and four interacting surfaces carried by that base and mounting plate. One of those interacting surfaces provides an essentially fixed spacing between predetermined areas on the base and mounting plate, a second of those interacting surfaces coacts with said one of those interacting surfaces to permit adjustment of the mounting plate relative to the base about one axis, a third of those interacting surfaces coacts with said one of those interacting surfaces to permit adjustment of the mounting plate relative to the base about a second axis, and the fourth of those interacting surfaces coacts with said one of those interacting surfaces to prevent rotation of the mounting plate in its own plane relative to the base.

3,577,792

ROTARY ACTUATOR AND METHOD OF MOUNTING SAME


Earl E. Parks, Los Angeles, Calif., assignor to Northrop Corporation, Beverly Hills, Calif.

Filed Nov. 10, 1969, Ser. No. 875,420

Int. Cl. F16h 21/44

U.S. Cl. 74-96

3 Claims



A rotary actuator and means for installing the same, the latter functioning to arrest axial loads prior to being transmitted to and resisted by the actuator proper and including means permitting the housing of the actuator to "float" or operate in a plurality of positions.

3,577,793


MECHANICAL MOTION TRANSMITTER

Allen V. C. Davis, 5600 Alta Canyon, La Canada, Calif.
Continuation-in-part of application Ser. No. 717,522, Apr. 1, 1968, now abandoned. This application June 30, 1969, Ser. No. 868,660

Int. Cl. F16h 21/44; F16j 15/50

U.S. Cl. 74-100

7 Claims



There is disclosed a switch unit having a metal plate forming one wall of a fluid chamber, such plate supporting an electrical switch exteriorly of the chamber. A thin-walled tube is welded at one end in an opening in the metal plate, with the outer end of the tube positioned to actuate the switch plunger. Extending through the tube is a rod having a modulus of elasticity that is greater than that of the tube. A transverse arm on the end of the rod in the chamber is movable by a pressure-responsive element to subject the outer end of the rod, and hence the tube, to transverse operation for actuating the switch plunger.

3,577,794

LAMINATED SPROCKET BELT

Franklin W. Kerfoot, Jr., 678 Andover Road, Newton Square, Pa. 19073

Filed June 17, 1968, Ser. No. 737,541


Int. Cl. F16g 1/26

U.S. Cl. 74-232

7 Claims

An endless belt for driving sprocket wheels is made of a plurality of layers, each layer having a butt joint which is spaced longitudinally of the belt from the joint of other layers. In one form the length of the joint is at least twice the

width of the belt. The joints pass between adjacent ones of the sprocket holes. Other forms include reinforcing bands



and belts which are thicker in the region between sprocket holes.

3,577,795

MEANS TO OVERCOME DIFFERENTIAL THERMAL EXPANSION EFFECTS IN BIMETALLIC SPLINED SHAFT ASSEMBLIES


John A. Bennett, Peterborough, England, assignor to Chandler Evans, Inc., West Hartford, Conn.

Filed Oct. 27, 1969, Ser. No. 869,742

Int. Cl. F16h 55/06; B21b 53/28; F16d 1/06

U.S. Cl. 74-446

4 Claims



A steel shaft having peripheral lands is broached by a splined carbide blank to form a broached assembly having interfaces between the lateral flanks of the lands and lateral flanks of the splines. The inner and outer peripheral portions of the steel shaft are spaced from the carbide blank to prevent radial stresses from being produced during broaching and to accommodate thermal expansions in the broached assembly. Circumferential chip grooves are provided in that portion of the shaft which is to be broached by the carbide blank to prevent continuous chips from forming during the broaching process which could seize on the cutting face of the carbide blank. The carbide blank of the broached assembly resists displacements relative to the steel shaft. The interfaces may be angularly disposed to alleviate large circumferential thermal stresses.

3,577,796

SPINDLE GUIDE

Werner Eissfeldt, Wiesbaden-Rambach, Germany, assignor to Nirona-Werke, Nier & Ehmer KG, Bleidensladt, Germany

Filed Aug. 11, 1969, Ser. No. 848,853

Claims priority, application Germany, Aug. 13, 1968, July 16, 1969, P 17 52 958.7, P 19 36 170.7


Int. Cl. F16h 1/18, 55/22

U.S. Cl. 74-59

12 Claims

An antifriction nut and threaded spindle assembly uses a plurality of continuously recirculating roller bodies traveling through a plurality of individually continuous ways. The ways are positioned sequentially along the axis of the spindle. The ways are each formed by a groove in the nut body and a retainer strip surrounding the groove. That portion of the strip adjacent the spindle fits between the lands of the spindle threads. The nut is split and a clamping ring, whole or split,

circumscribes the nut for compressing the nut about the spindle for control of play between the nut and spindle. In one embodiment the nut is formed in two halves having a plurality of the individually continuous ways in each half. The halves (as seen in cross section) may have an inner curvature formed about the axis of the spindle and outer curvature formed about axes spaced from the spindle axis in the direction of the respective nut half. In some embodiments the



roller bodies are each of truncated conical configuration with the small end directed toward the spindle when in operative contact with the spindle. For heavy loads the truncated conical roller bodies meet the lands of the spindle threads in a line contact such that the lines extended, along with the conical axis, meet at a point on the spindle axis. The large end of the truncated conical bodies is concave and in the return portion of the way contact a crown on the portion of the nut defining the return portion of the way.

3,577,797

BRAKING SYSTEM FOR A VEHICLE

Eugenio Todeschini, Reggio Emilia, Italy, assignor to Massey-Ferguson Services N.V., Curacao, Netherlands


Filed June 5, 1969, Ser. No. 830,737

Claims priority, application Italy, June 10, 1968, 17559A/68

Int. Cl. G05g 11/00

U.S. Cl. 74-479

1 Claim



A braking system for a vehicle includes primary powered and secondary mechanical brake actuation means for alternative operation of a brake. The secondary mechanical brake actuation means includes connection means adapted to be adjusted automatically in response to repeated operation of the primary powered brake actuation means. In a preferred embodiment the connection means includes a ratchet and a cooperating pawl for stepwise adjustment of the connection means and a lost motion connection to accommodate free movement within the connection means during operation of the primary powered brake actuation means. When a predetermined amount of brake wear has taken place operation of the primary powered brake actuation means is effective to cause movement between the pawl and the ratchet and adjust the connection means.

3,577,798

HAND BRAKE CONTROL MECHANISMS

Michel Guettier, Billancourt, France, assignor to Regie Nationale Des Usines Renault, Billancourt, Hauts de Seine, France and Automobiles Peugeot, Paris, France

Filed Apr. 17, 1969, Ser. No. 817,111

Claims priority, application France, Apr. 22, 1968, 148934

Int. Cl. G05g 1/00

U.S. Cl. 74-503

5 Claims



A handbrake control mechanism having a control member slidably mounted in a slideway guide and connected to the brake control cable. The control member has a tubular body with a handgrip and counter grip at one end, several longitudinal slits, a retaining member constituted by a spring biased pawl pivoted on a pivot pin carried by a shuttle inside the tubular body and operatively connected to the counter grip by a rod. The slideway-guide is cylindrical and has a rack formed along one side to coact with the pawl when the brake is set. A brake cable is connected to the shuttle.

3,577,799

CAMSHAFT


Warren L. Harvey, New Providence, N.J. (P.O. Box 622 West Main St., Mendham, N.J., 07945)

Filed July 1, 1969, Ser. No. 838,097

Int. Cl. F16h 53/02

U.S. Cl. 74-567

1 Claim



A camshaft as used to actuate a plurality of spring returned followers. The camshaft resists the bending loads imposed on it by utilizing a rigid tubular construction in which the inside diameter tapers to a minimum near the center of the length of the camshaft resulting in greater material strength at a section furthest from the bearing support at either end.

3,577,800

ADJUSTABLE ECCENTRIC

Edwin L. Jones, Brookfield, Wis., assignor to Douglas Dynamics Corporation, Milwaukee, Wis.

Filed Mar. 3, 1969, Ser. No. 803,700


Int. Cl. G05g 1/24

U.S. Cl. 74-571

7 Claims

An eccentric is mounted on a rotatable shaft and includes three axially spaced masses one of which is fixed, another is

circumferentially fixed and axially slidable, and a third is adjustable circumferentially. The axially slidable mass holds the third mass in a selected position and is slidable axially to



release the third mass for rotation. The fixed and axially slidable masses have equal and common eccentricities relative to the shaft and the combined masses thereof equals that of the third mass.

3,577,801

LOCKING DEVICE FOR AN ECCENTRIC MEMBER


Louis A. Netta, North Brunswick, N.J., assignor to Thomas & Betts Corporation, Elizabeth, N.J.

Filed Aug. 25, 1969, Ser. No. 852,642

Int. Cl. G05g 3/00

U.S. Cl. 74-571

5 Claims



The eccentric locking device comprises an extension on the eccentric itself, a bushing placed about the aperture into which the eccentric is positioned and means for conjointly engaging the bushing and the extension of the eccentric to prevent relative movement therebetween. In a first embodiment a plurality of cavities is placed about the outer surface of the extension and the inner surface of the bushing. A pin is inserted conjointly in the cavities of both in order to prevent relative movement therebetween. In a further embodiment, the extension terminates in a transverse tab; a cap having a slot therein is then inserted atop the bushing's outer surface and the tab is made to engage the slot to thereby prevent relative motion between the bushing and the eccentric.

3,577,802

LEAF SPRING TUNED VISCOUS VIBRATION DAMPER

Rollin Douglas Rumsey, Buffalo, N.Y., assignor to Houdaille Industries, Inc., Buffalo, N.Y.

Filed Mar. 7, 1969, Ser. No. 805,271


Int. Cl. F16f 15/16

U.S. Cl. 74-574

16 Claims

Resilient generally axially extending spokes are anchored at radially outer ends thereof to the radially outer wall within a circular working chamber of a housing, with the radially inner ends of the spokes connected to an inertia mass flywheel for energy absorption, tuned damping of relative oscillatory vibratory motions between the flywheel and the

housing. Relative vibratory oscillations are also resisted by a viscous damping medium coupling between confronting



shear film spaced parallel surfaces of the housing and the inertia mass.

3,577,803

VARIABLE TORQUE TRANSMISSION


Otto Mueller, 13 Byfield Lane, Dearborn, Mich.

Filed May 12, 1969, Ser. No. 823,872

Int. Cl. F16h 37/06

U.S. Cl. 74—665

9 Claims



Apparatus for a four or six wheel drive motor vehicle which includes a variable ratio torque transmission assembly connected by drive shafts to front and rear axles. The variable ratio torque transmission assembly has a rotary input member which receives torque from the engine, and first and second rotary output members connected to the front and rear axles respectively. The output members are coupled together by a hydraulic torque transmitting mechanism which includes means for selectively setting the ratio of the input torque that is transmitted to the two output members and thereby to the front and rear axles. This arrangement permits any desired ratio of torque transmission, such as one-third of the torque being transmitted to the front axle and two-thirds of the torque being transmitted to the rear axle. The assembly also includes a remote control means whereby the driver of the vehicle can lock the mechanism between the two output members so that full or maximum torque is transmitted to the front axle.

3,577,804 TORQUE SPLIT TYPE AUTOMATIC SPEED CHANGE DEVICE

Kazuhiko Ohno, and Yoichi Mori, Yokohama, Japan, assignors to Nissan Jidosha Kabushiki Kaisha, Yokohama City, Japan

Division of Ser. No. 640,219, May 22, 1967, Pat. No. 3,455,185.


Filed Mar. 13, 1969, Ser. No. 822,345

Claims priority, application Japan, June 30, 1966, 41/42125

Int. Cl. F16h 47/08, F16h 37/08

U.S. Cl. 74—688

10 Claims



A torque split type automatic speed change device comprising a hydraulic power transmission means having a pump connected to one end of an engine crankshaft and a turbine, a planetary gear assembly disposed in parallel with the axis of the hydraulic power transmission means, a first power transmission route extending between said pump and said planetary gear assembly through suitable transmitting means, and a second power transmission route extending between said turbine and said planetary gear assembly through another transmitting means, thereby powers transmitted to said planetary gear assembly through said two routes are synthesized.

3,577,805

TORQUE SPLIT TYPE AUTOMATIC SPEED CHANGE DEVICE

Kazuhiko Ohno, and Yoichi Mori, Yokohama, Japan, assignors to Nissan Jidosha Kabushiki Kaisha, Yokohama City, Japan

Division of Ser. No. 640,219, May 22, 1967, Pat. No. 3,455,185.


Filed Mar. 13, 1969, Ser. No. 822,346

Claims priority, application Japan, June 30, 1966, 41/42125

Int. Cl. F16h 47/08, F16h 37/08

U.S. Cl. 74—688

5 Claims



A torque split type automatic speed change device comprising a hydraulic power transmission means having a pump connected to one end of an engine crankshaft and a turbine, a planetary gear assembly disposed in parallel with the axis of the hydraulic power transmission means, a first power transmission route extending between said pump and said planetary gear assembly through suitable transmitting means, and a second power transmission route extending between said turbine and said planetary gear assembly through another transmitting means, thereby powers transmitted to said planetary gear assembly through said two routes are synthesized.

3,577,806 HYDRAULIC MODULATOR VALVE CONTROL


Robert H. Schaefer, Westfield, Ind., assignor to General Motors Corporation, Detroit, Mich.

Filed Aug. 25, 1969, Ser. No. 852,709

Int. Cl. B60k 21/00, B60k 19/00

U.S. Cl. 74—868

11 Claims



A transmission for an engine having a fuel feed control member movable from zero to full throttle position and an automatic shift control system operative in response to an output governor pressure signal and a torque demand pressure signal for shifting the transmission between low and high speed drives. A force transmitting system for transmitting a force proportional to torque demand position having a pair of expansible chambers interconnected by a fluid passage filled with fluid and each chamber having a movable wall. A spring positioned between said movable torque demand member and one movable wall generates a force proportional to torque demand position on the one movable wall so the system pressure is proportional to torque demand and the system transmits to the other movable wall a force proportional to the position of the torque demand member without significant fluid movement in the system. The other movable wall actuates a regulator valve to provide a torque demand pressure proportional to the position of said torque demand member which functions with a governor pressure to control the automatic shift valves.

3,577,807

PORTABLE POWER TOOL


Robert H. Alexander; Ronald C. Falter; Cecil D. Ringer, Columbia, S.C., and Eugene Linsker, Dayton, Ohio, assignors to Rockwell Manufacturing Company, Columbia, S.C.

Filed Oct. 31, 1968, Ser. No. 772,132

Int. Cl. B23b 45/14

U.S. Cl. 408—17

22 Claims



A portable tool incorporates an air motor which drives a tubular drive shaft splined to a spindle movable axially in a direction parallel to the axis of the motor. The spindle has a hollow rearward end portion with internal threads which receive screw members mounted on a tubular feed shaft also driven by the motor through an adjustable detent clutch. An adjustable stop collar surrounds the spindle and provides precise depth control, an air cylinder provides rapid advancement of the spindle, and the clutch provides automatic disen-

gement of the positive feed as well as limited rotation of the spindle at the forward end of the feed stroke before the spindle retracts. The controls for adjusting the stop collar and for effecting positive feed and rapid advancement and retraction of the spindle are located at the rear of the tool.

3,577,808

SUB-ZERO CUTTING FLUID GENERATOR


Gerrit A. Visser, Edmonds, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed Dec. 13, 1968, Ser. No. 785,964

Int. Cl. B23b 47/00

U.S. Cl. 408—61

2 Claims



This cutting fluid generator comprises a variety of components connected and arranged so that an improved method for applying cutting fluids (consisting of a coolant-lubricant mixture) through an external mist delivery to drills is obtained. Pressurized, dry, clean air is delivered to a mixing station provided with a venturi which increases the speed of the air via a suction chamber connected to the cutting fluid supply. The cutting fluid is micronized and intermixed into the airstream by vacuum suction of the passing air and the micronized cutting fluid will instantaneously evaporate in the mist projected onto the drill and workpiece, which will result in thorough lubrication and a -26° F. cooling.

3,577,809

QUICKSET TOOLHOLDER

Walter Brandl, Bad Homburg vor der Höhe, and Rudolf Mathes, Niedereschbach, Germany, assignors to Reimers Getriebe A. G., Zug, Switzerland

Filed Aug. 22, 1968, Ser. No. 754,612


Claims priority, application Germany, Aug. 30, 1967,

P 16 02 941.7

Int. Cl. B23b 29/034

U.S. Cl. 77—58

2 Claims



A toolholder for holding cutting tools is provided with a standard cone at its rear end for insertion into a machine tool. The front end consists of an axially projecting stud. Disc-shaped tool carriers are provided with a central bore and further with means for receiving and holding at least one cutting tool. By means of their bore, the tool carriers are arranged on the stud to which they are positively secured by clamping means, for example, by a bayonet coupling. The distance between the nose of the cutting tools and the rear surface of the tool carriers is at all carriers set to a uniform predetermined range, thereby avoiding any shifting of the zero-point when one tool carrier is exchanged for another one.


3,577,810

BORING BAR INSERT

Otto Eckle, Lochgau, Germany, assignor to Firma Komet Stahlhalter-Und Werkzeugfabrik, Robert Breuning-G.m.b.H., Neckar, Germany
 Filed Mar. 12, 1969, Ser. No. 806,572
 Claims priority, application Germany, Mar. 20, 1968, P 17 52 014.8, P 17 52 012.6
 Int. Cl. B23b 29/034

U.S. Cl. 77-58

8 Claims



A boring bar insert having two counterwise movable boring tool carriers, the tools of which are arranged at oppositely actuated ends of the boring tool carriers when rotated through 180° to one another. For counterwise movement and adjustment of the boring tool carriers there is between their mutually facing shank ends an adjusting ring cooperating with two counterwise screwthreads of the boring tool carriers and a centering device. The boring tool holders are securely held and also can be moved counterwise in the clamped condition. Centering of the boring tool carriers with respect to the boring bar axis is possible.


3,577,811

DEVICE FOR RETENSIONING EYEGLASS FRAMES

Ambrose D. Walker, Clinton, Mo., assignor to Leo X. O'Brien, Independence, Mo., fractional part interest
 Filed Dec. 12, 1968, Ser. No. 783,338
 Int. Cl. B25b 11/00

U.S. Cl. 81-3.5

8 Claims



This invention has to do with a retensioning device for eyeglass frames and is adaptive for use on different sized frames. The retensioner employs a pressure lever pivoted centrally upon its base remote from the nosepiece of the glasses to permit the free end of the pressure lever to nest in the nosepiece curvature, and a tensioning assembly for manually imposing and maintaining for desired intervals an adjusted downward pressure on the nosepiece and frame.

3,577,812


OPENING DEVICE FOR CANS AND SIMILAR CONTAINERS PROVIDED WITH TWIST LIDS

Ivar Alvar Asp, Storbergsliden 15, Sollentuna, Sweden
 Filed May 31, 1968, Ser. No. 733,478
 Claims priority, application Sweden, June 5, 1967, 7864/1967

Int. Cl. B67b 7/18; B25b 13/48

U.S. Cl. 81-3.36

4 Claims



An opener in the form of a pair of tongs for cans, jars and similar containers provided with twist lids, which includes two leg members presenting handle portions and jaw portions, wherein one jaw portion is adapted to be applied to the surface of the container, while the other is brought to bear against the lid, and wherein the leg members are so connected that slight pressure on the handle members causes the lid to rotate relative to the body of the container.

3,577,813

DEVICE FOR STRIPPING OUT SHIELDING SHEATH


Evgeny Nikolavich Vorontsov, Blagodatnaya ulitsa, 25, kv. 45, Leningrad, U.S.S.R.

Filed Apr. 9, 1969, Ser. No. 814,573

Int. Cl. H02g 1/12

U.S. Cl. 81-9.51

1 Claim



A device for stripping shielding sheath or insulation from the ends of wires or cables, in which two diametrically opposite cutting members each of which constitutes a milling cutter adapted to rotate in the direction of the wire feed coact with a blade fixed in position with respect to the cutter to provide shears to sever the shielding sheath or insulation.

3,577,814

APPARATUS FOR EXPOSING CORE OF AN INSULATED WIRE

James Woodrow Hammond, Camp Hill, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Aug. 28, 1969, Ser. No. 853,816

Int. Cl. H02q 1/12


U.S. Cl. 81-9.51

7 Claims

Apparatus for exposing the conducting core of an insulated wire comprises a pair of jaws movable relatively towards and away from each other between open and closed positions. Clamping means are provided on the corresponding ends of

the jaws to clamp a wire extending between the jaws when the jaws are closed. The portion of the wire which extends between the jaws is loosely confined against substantial lateral flexure. Insulation pushing fingers mounted in the jaws

maintained close to each other with these handles respectively having outer exterior side surfaces directed away from each other and respectively located substantially in planes normal to the axis of the rotary ratchet. The distance between these planes is actually the maximum thickness of the entire wrench. One handle is used for stabilizing the



are adapted to grip the insulation adjacent to the end of the wire and push it towards the clamping means. The insulation is bunched or compressed between the fingers and the clamping means and the end portion of the wire core which is thereby exposed for application of an electrical terminal.

3,577,815

TWO-WAY TORQUE WRENCH


Clifford A. Bergquist, Alhambra, Calif., assignor to Pendleton Tool Industries, Inc., Los Angeles, Calif.

Filed Apr. 2, 1969, Ser. No. 812,605

Int. Cl. B25b 13/46

U.S. Cl. 81-52.4

11 Claims



A predetermined torque release wrench which may be used to apply a torque to a fastener in either rotary direction. The wrench includes an arm connected to the ratchet head of the wrench and a spring pressed cam and follower arrangement. The arm overcomes the resistance of the cam and follower arrangement when a predetermined torque is reached. An arrangement is provided for varying the profile of the cam to permit calibration of the wrench.

3,577,816

RATCHET WRENCH

Jerry Alexander, 64 Hedgerow Lane, Jericho, N.Y., and Irving J. Stevens, 130 Margaret Blvd., Merrick, N.Y.


Filed Apr. 10, 1969, Ser. No. 815,074

Int. Cl. B25b 13/46

U.S. Cl. 81-63.1

10 Claims

A ratchet type wrench wherein a pair of swingable handles swing around a ratchet and have a pair of pawls which respectively coact with the ratchet to turn the latter in one direction with respect to one handle when the other handle is turned in a given direction and prevents backlash while providing positive ratcheting both forward and reverse without friction applied to the wrench. The wrench is of a relatively small size and is extremely thin so that it is capable of being used where only a small operating space is afforded. A very small radius of arc is required to effect a ratchet movement. The pair of handles are relatively thin and are



wrench, and the other is used for driving the ratchet. In addition, the entire wrench is composed of components which require no lubrication for effective operation and which can be sterilized without suffering any deleterious effects, so that the wrench lends itself to medical uses such as, for example, in connection with dental operations.

3,577,817

SOCKET WRENCH


Kave A. Smith, Jennings, and Henry L. Ladendecker, St. Louis, Mo., assignors to McNeil Corporation, Akron, Ohio

Filed Aug. 25, 1969, Ser. No. 852,712

Int. Cl. B25b 13/06, B25b 13/00

U.S. Cl. 81-121

9 Claims



A socket wrench is formed as a barrel having an end in which is a circular opening. The opening is of an internal diameter approximately equal to the distance across the corners of a hexagonal nut. Said end is grooved crosswise at 120° intervals. In each groove is removably fastened a bar made of wear-resistant tool-steel bar stock of square cross section chamfered on one corner. The inner flat faces of these bars bridge across said opening for flatwise engagement with every other flat face of the hexagonal nut. The segments of said circular opening between bars extend clear of the sides of the nut which are not engaged by the bars. Under the opening and the bridging bars the barrel has an internal shoulder which is engageable with the corners of the nut to determine the axial positions of the bars on the nut. The other end of the barrel is provided with an adapter for coupling to a rotary power driving element.

3,577,818

LUG WRENCH SUPPORT

Leslie Dick Cramer, 888 Amoretti St., and John R. Moore, 558 Lincoln St., P.O. Box 765, Lander, Wyo.

Filed Sept. 25, 1969, Ser. No. 861,070



Int. Cl. B25b 13/58

U.S. Cl. 81-180

8 Claims

A wheel nut wrench support for use in the removal of wheels from a vehicle, particularly in connection with trucks and similarly heavy-duty vehicles, including a plate member provided with a plurality of slotted apertures distributed in an annular pattern thereon and provided additionally with multiple elements extending radially from the plate member and adapted to engage a wheel rim to support the plate member in spaced relationship with the wheel in an orientation substantially parallel to the plane of the wheel wherein the plu-

rality of apertures are aligned axially with the plurality of ing engagement, are routed to form grooves, the groove of wheel lugs. According to a modification of the present inven-



one plate being greater in width than the groove of the other plate. Heated die means are then mounted in the grooves.

3,577,821

TRIM PRESS ASSEMBLY


Roger L. Medendorp, Grand Rapids, Mich., assignor to Kirkhof Manufacturing Corporation, Grand Rapids, Mich.

Filed Jan. 21, 1969, Ser. No. 792,618

Int. Cl. B65h 17/18

U.S. Cl. 83-238

4 Claims



Advancing apparatus for a trim press of articles formed into a web in repeat patterns, having a reciprocating pusher that has a regular stroke length, and periodically has a greater stroke length by reason of actuation of a special fluid cylinder that in one form of the invention forms a component of the connecting linkage from the power drive to the pusher, and in a second form of the invention, is attached to an extensible portion on the pusher.

3,577,822

REMOVABLE FREEWHEELING RESILIENT COVER FOR ROTARY ANVIL


Louis E. Sauer, and Robert W. Sauer, St. Louis, Mo., assignors to Centenary Central, Inc., St. Louis, Mo.

Filed Apr. 16, 1969, Ser. No. 816,657

Int. Cl. B26d 7/20

U.S. Cl. 83-659

13 Claims



This is a freewheeling resilient rotary diecutting anvil cover comprising a flexible member of one or multiple pieces

3,577,820

DIE FOR SEALING OR CUTTING THERMOPLASTIC MATERIAL

Paul Silverstein, Jamaica, N.Y., assignor to Applied Synthetics Corp., East St. Louis, Ill.

Filed Oct. 25, 1968, Ser. No. 770,654

Int. Cl. B26d 7/10

U.S. Cl. 83-171

5 Claims

A pair of die plates of insulating material, clamped in fac-

releasably secured together along a generally axial line or lines including one or more annular ribs on the inner surface for disposition in annular grooves in the cylindrical supporting base in which at least the portions of the rib or ribs leading to the releasable connection or connections are of split T-cross section and collapsible to relieve binding and to permit installation and removal from a head, or the like, without removing the head. In a modification, a cover lengthened by use can be cut to smaller size. Another modification employs a metal plate or plates to reduce lengthening.

3,577,823

ACTUATOR FOR STRINGED MUSICAL INSTRUMENT


Leonard W. Pavia, 460 Columbia Turnpike, Florham Park, N.J.

Filed Apr. 15, 1969, Ser. No. 816,198

Int. Cl. G01c 1/00; G10c 1/06; G10d 3/16

U.S. Cl. 84-174

3 Claims



I disclose an actuator or vibrator for a keyboard stringed musical instrument wherein the string is vibrated by adhesion of the string to the actuator. The adhesive effect is obtained by mixing a glazing paste of permanent flexibility in a solvent, absorbing the mixture through a felt damping pad so that it is fully impregnated, then evaporating the solvent, and affixing the thus-impregnated felt pad onto a body portion of the actuator. The glazing paste consists of an inert material, such as talcum, dispersed in a nondrying soft wax, such as a polyamide, plasticized polyethylene wax, or a soft wax of natural origin which also contains a small amount of water to obtain the proper consistency and workability.

3,577,824

MUSIC TEACHING MACHINE


Lawrence P. Lavan, 245 E. 72nd St., New York, N.Y.

Filed May 13, 1969, Ser. No. 824,111

Int. Cl. G09b 15/02

U.S. Cl. 84-478

7 Claims



A music teaching machine produces small lighted areas on a screen having musical notations in response to depressions of the keys of an associated musical instrument. The lights are color coded and physically positioned to indicate the sets of notes constituting major thirds and minor thirds. A movie picture projector, lens system, and a mirror are arranged to project notes, to be played, on the same screen.

3,577,825

BOLT ANCHOR AND METHOD FOR MAKING SAME


Hans E. Reusser, Cleveland, Ohio, assignor to Republic Steel Corporation, Cleveland, Ohio

Filed Nov. 30, 1967, Ser. No. 687,052

Int. Cl. F16b 13/06

U.S. Cl. 85-76

34 Claims



An anchor assembly particularly adapted for use with a roof plate to support a mine roof. The assembly includes a bolt having a threaded end, a camming plug threaded on the bolt, and an expansion shell. The disclosed shell structure includes a polygonal, tubular collar portion and a plurality of fingers projecting longitudinally from the collar. In use, the fingers frictionally engage the camming plug. The fingers include a plurality of cold formed teeth which have an increasing depth and pitch proceeding along the fingers toward the collar and which are, when the assembly is installed, urged into engagement with the walls of a bore hole upon rotation of the bolt to move the camming plug toward the collar and cam the fingers into engagement with the bore.

One disclosed embodiment is provided with a wirelike bail member having a portion extending over the end of the bolt and end portions engaging shoulders formed on the expansion shell so that the unexpanded shell and the plugs are maintained in assembled position for insertion into the bore. The bail member maintains the camming plug and shell assembled until the shell has been partially expanded, after which the bail member is yielded in a manner which does not impede anchoring of the assembly in the bore or tensioning of the bolt.

3,577,826

BELLOWS SEALED FIRING PIN


Eugene Ashley, Burlington, and Douglas Pray Tassie, St. George, Vt., assignors to General Electric Company

Filed July 22, 1969, Ser. No. 843,728

Int. Cl. F41f 11/00

U.S. Cl. 89-26

12 Claims



A firing pin bolt assembly includes a tubular bellows having one end sealed to and about the penetrator end and its other end sealed to the bolt about the firing pin passageway.

3,577,827

TRIGGER MECHANISM


William J. Billett, Fairmont, Minn., and Edwin S. Vartanian, North Haven, Conn., assignors to Olin Mathieson Chemical Corporation

Filed Jan. 27, 1969, Ser. No. 793,958

Int. Cl. F41c 19/00

U.S. Cl. 89—145

11 Claims



A trigger mechanism for a semiautomatic firearm having a reciprocating bolt assembly, the mechanism having a trigger member which is releasably connected to a sear member. The trigger member is disconnected from the sear by reciprocation of the bolt assembly or by actuation of a safety. Means are provided for adjusting the trigger pull and for retaining the preset trigger pull against maladjustment.

3,577,828

MILLING MACHINE


Leslie P. Stickney, Portland, Maine, assignor to Gulf & Western Precision Engineering Company, Manchester, Conn.

Filed Apr. 17, 1969, Ser. No. 817,049

Int. Cl. B23c 1/12

U.S. Cl. 90—15

1 Claim



A milling machine includes a substantially vertical support having a machine head attached thereto. The machine head extends horizontally from the vertical support and includes a mounting portion which is rotatably attached to the vertical support. An electric motor mounted in the vertical support drives a ring gear on the machine head to rotate the machine head about a substantially vertical axis. The machine head includes a tool spindle. Rotational movement of the machine head moves the tool spindle in an arcuate path so that arcuate shapes may be machined. The tool spindle is preferably pivotally attached to the machine head so that sloping arcuate surfaces may be machined.

3,577,829

METHOD AND APPARATUS FOR CUTTING COMPONENTS TO LENGTH

James Hurn, Rowley, Melksham, Wiltshire; Charles Richard Forbes King, 6 Somerset Lane, and Donald Raymond Deane, Foxhall Farm, Weston, Bath, Somerset, England


Filed Sept. 6, 1968, Ser. No. 757,912

Claims priority, application Great Britain, Sept. 13, 1967, 41799/67

Int. Cl. B23c 9/00; B26d 7/16; B27b 5/18

U.S. Cl. 90—21R

17 Claims



Apparatus and method for positioning an elongate workpiece so that it may be worked, e.g. by cutting, sawing, drilling, trenching or shearing, at any preselected point along its length, including the steps of passing the workpiece from a working tool on a longitudinal conveyor; selecting a stop from a plurality of such stops which are serially spaced from said working tool over at least part of the length of the conveyor; adjusting the longitudinal position relative to the conveyor and to the working tool of a common structure carrying said stops, the distances between the stops being uniform, and placing said selected stop in the path of the workpiece to arrest its further progress on the conveyor. Pneumatic cushioning means are interposed between the common structure and the means for adjusting the common structure. The cushioning means are employed to absorb impact by allowing limited movement to the common structure when the workpiece abuts the selected stop, and then to reverse the said movement of the common structure to reposition the stop and hence to bring the preselected location of the workpiece opposite the working tool.

3,577,830

HYDRAULIC MOTOR

Aurelio Orrelli, Bologna, Italy, assignor to Riva Calzoni S.P.A., Milan, Italy


Filed Sept. 26, 1968, Ser. No. 762,885

Claims priority, application Italy, Sept. 29, 1967, 21059A

Int. Cl. F01b 15/00

U.S. Cl. 92—66

4 Claims



A hydraulic motor with radial propelling members, which includes a shaft provided with a cam with a spherical surface, around which a plurality of radial propelling members is arranged and in which each of said propelling members is composed of a tubular element of telescopic form attached to resilient means which initially maintain one end of said tubular element in contact with the spherical surface of the cam and maintain the other end of said tubular element in contact with a cap or a fixed striker with a spherical surface, the chamber defined by the said tubular element being in alternate communication with a source of compressed fluid and with a discharge line.

3,577,831


POSITIONING DEVICE WITH AUTOMATIC RETURN STROKE

Charles L. Brinkman, 3118 Atherton Road, Dayton, Ohio Division of Ser. No. 515,260, Dec. 20, 1965, Pat. No. 3,302,902. Continuation-in-part of Ser. No. 608,523, Jan. 11, 1967, abandoned, continuation-in-part of application Ser. No. 228,866, Oct. 8, 1962, now Patent No. 3,228,624. This application June 27, 1969, Ser. No. 837,264

Int. Cl. F01b 15/02; F15b 15/17

U.S. Cl. 92—66

4 Claims



A positioning device comprises a plurality of positioning elements each having relatively movable piston and cylinder elements with restricted fluid communication between both ends of the cylinder element. Each of the relatively movable piston and cylinder elements is angularly disposed relative to other such elements which are structurally interconnected with a floating equalizer linkage to provide uniform and unrestricted movement within desired limits. Pressurized fluid is supplied to the cylinders through internal passageways to cause relative movement in one direction and the device automatically returns to its initial position when disconnected from the supply of pressurized fluid.

3,577,832

FLUID PRESSURE OPERATED SERVO DEVICES

David Parsons, Warwickshire, England, assignor to Automotive Products Company Limited, Warwickshire, England


Filed Dec. 30, 1968, Ser. No. 792,199

Claims priority, application Great Britain, Jan. 12, 1968, 1985/68

Int. Cl. F16j 3/00

U.S. Cl. 92—98

2 Claims



A flexible diaphragm providing a fluidtight partition between chambers in a fluid servomotor casing is held against movement of its inner edge away from a rigid member axially movable in the casing by a washer mounted on a cylindrical surface of said rigid member to form, with an annular surface on said member, a radially outwardly convergent channel enclosing a bead on that edge of the diaphragm.

3,577,833

FLUID CYLINDER


Darold M. Skelton, Brookfield, Wis., assignor to Milwaukee Cylinder Corporation, Cudahy, Wis.

Filed July 11, 1969, Ser. No. 841,018

Int. Cl. F16j 15/16, 15/18

U.S. Cl. 92—168

3 Claims



A fluid cylinder having an end cap and a retainer plate for the end cap for containing packing thereby permitting a simplified bushing to be inserted in the end cap insuring that the entire bearing surface of the bushing is lubricated.

3,577,834

GRIPPER BAR MOUNT FOR PLATEN PRESS

Pierre Lang, Vaud, Switzerland, assignor to J. Bobst & Fils S. A., Lausanne, Switzerland


Filed Dec. 9, 1968, Ser. No. 782,191

Claims priority, application Switzerland, Dec. 11, 1967, 17445/67

Int. Cl. B31b 1/20, 17/02; B65g 17/14

U.S. Cl. 93—58.3

14 Claims



A device for accurately centering the gripper bars carried by a pair of endless chains, in a desired working position in a press. Gripper bars are rigidly secured at their opposite ends to the endless chains during movement of the chains and when chain movement stops, the gripper bars are released from the chains for limited freedom of movement and means then cooperate with the freed gripper bars to positively accurately center the bars.

3,577,835

SKI MAT APPARATUS


John P. Horton, Bernardsville; Robert E. Sollmann, Far Hills, and Joaquim L. Santos, Harrison, N.J., assignors to Ski-Mor Inc., Kenilworth, N.J.

Continuation of application Ser. No. 536,402, Mar. 22, 1966, now abandoned. This application Jan. 17, 1969, Ser. No. 792,909

Int. Cl. E01c 5/00

U.S. Cl. 94—3

8 Claims



Sliding surfaces having a plurality of annular, rigid strips with bristles extending uniformly upward, the strips being interconnected to form a continuous surface of upward directed bristles in annular rings, are described herein.

DESIGNS

MAY 4, 1971

220,608

NECKTIE OR THE LIKE
Louis J. Schultze, 102 E. Oak St.,
Chicago, Ill. 60611

Continuation-in-part of design application Ser. No. 19,239,
Sept. 22, 1969. This application July 29, 1970, Ser.
No. 24,213

Term of patent 14 years
Int. Cl. D2—06

U.S. Cl. D2—351



220,610

JUG


David G. Hills, Collinsville, Conn., assignor to
Monsanto Company, St. Louis, Mo.

Filed Dec. 30, 1968, Ser. No. 15,137

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—48



220,611

BOTTLE

David G. Hills, Collinsville, Conn., assignor to
Monsanto Company, St. Louis, Mo.

Filed Oct. 28, 1968, Ser. No. 14,188

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—117



220,609

JUG OR SIMILAR ARTICLE

Michael Clement Dickens, Bletchley, England, assignor
to Plysu Containers Limited, Bletchley, England


Filed Oct. 20, 1969, Ser. No. 19,624

Claims priority, application Great Britain June 23, 1969

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—43



MAY 4, 1971

U. S. PATENT OFFICE

199

220,612

BEER CAN


Kenneth E. Siegler, 1004 S. Pine St.,
Port Angeles, Wash. 98362

Filed Apr. 20, 1970, Ser. No. 22,519

Term of patent 14 years

Int. Cl. D9—07

U.S. Cl. D9—216



220,615

PORTABLE OUTHOUSE


William L. Thompson, Pueblo Mountain Park,
Beulah, Colo. 81023

Filed Mar. 3, 1970, Ser. No. 21,709

Term of patent 14 years

Int. Cl. D25—04

U.S. Cl. D13—1



220,613

AEROSOL ACTUATING BUTTON PROTECTOR


Theodore Andrew Beck, Andover, Mass., assignor to
Scovill Manufacturing Company, Waterbury, Conn.

Filed Feb. 19, 1970, Ser. No. 21,518

Term of patent 14 years

Int. Cl. D9—99

U.S. Cl. D9—258



220,616

MOTOR HOME


Gerald D. Schwartz, Van Nuys, Calif., assignor to United
Bus Sales, Inc., Bell Gardens, Calif.

Filed Oct. 17, 1969, Ser. No. 19,603

Term of patent 7 years

Int. Cl. D12—09

U.S. Cl. D14—3



220,614

CUTTING BLOCK


Leonard K. Reichert, 16 Euston St.,
Brookline, Mass. 02146

Filed Dec. 12, 1969, Ser. No. 20,476

Term of patent 14 years

Int. Cl. D15—12

U.S. Cl. D11—1



220,617

**REMOVABLE LIFT FORK FOR LOADER AND
BACK HOE BUCKETS AND THE LIKE**


John R. Pavese, 771 Rivervale Road,
River Vale, N.J. 07675

Filed Dec. 22, 1969, Ser. No. 20,756

Term of patent 14 years

Int. Cl. D12—14

U.S. Cl. D14—3



220,618

AUTOMOBILE SUN VISOR


Daniel A. Berkoff, Sherman Oaks, Calif., assignor to Hollywood Accessories, a division of Orion Industries, Inc.

Filed May 11, 1970, Ser. No. 22,932

Term of patent 14 years

Int. Cl. D12—14

U.S. Cl. D14—6



220,619

SNOWMOBILE TRAILER

Ernest W. Rowley, 131 Wendell Ave., Weston, Ontario, Canada


Filed Mar. 23, 1970, Ser. No. 22,337

Claims priority, application Canada Sept. 24, 1969

Term of patent 14 years

Int. Cl. D12—13

U.S. Cl. D14—24



220,620

LOUNGE


Eugene F. Jones, 941 Reed Ave., East Point, Ga. 30344

Filed Dec. 17, 1969, Ser. No. 20,528

Term of patent 14 years

Int. Cl. D6—01

U.S. Cl. D15—11



220,621

MEASURED-VOLUME DISPENSER FOR CHEMICAL REAGENTS OR THE LIKE


John J. Moran and Robert C. Querry, Houston, Tex., assignors to Hycel, Inc., Houston, Tex.

Filed Jan. 5, 1970, Ser. No. 20,759

Term of patent 14 years

Int. Cl. D24—02

U.S. Cl. D16—1



220,622

MODULAR BUILDING BLOCK UNIT


Robert J. Passander, Indianapolis, Ind., assignor to Intercom Research, Inc., Indianapolis, Ind.

Filed Dec. 15, 1969, Ser. No. 20,650

Term of patent 14 years

Int. Cl. D25—01

U.S. Cl. D18—2



220,623

FISH LURE


Fred L. Churchman, 2820 Alaska St., Baton Rouge, La. 70803, and Garney B. Glasgow and Max A. Glasgow, both of P.O. Box 353, Ville Platte, La. 70586

Filed Dec. 15, 1969, Ser. No. 20,510

Term of patent 14 years

Int. Cl. D22—07

U.S. Cl. D22—27



220,624

BATH FAUCET


Claude Urban, Buvingen 27, Pepingen, Belgium

Filed July 16, 1969, Ser. No. 18,217

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—23



220,626

FLUIDIC LOGIC TRAINER COMPUTER

Vincent Randazzo, Brooklyn, N.Y.


(680A Front St., Hempstead, N.Y. 11550)

Filed Aug. 22, 1969, Ser. No. 18,808

Term of patent 14 years

Int. Cl. D14—02

U.S. Cl. D26—5



220,627

DATA TERMINAL CONSOLE

Elmer J. Stoltz, Castro Valley, and William J. Wohltmann, Jr., Mountain View, Calif., assignors to The Singer Company, New York, N.Y.

Filed Dec. 1, 1969, Ser. No. 20,318

Term of patent 14 years

Int. Cl. D14—02

U.S. Cl. D26—5



220,625

MAGNETIC TOY

Leonard Macpherson, Los Altos, Calif., assignor to Rathcon, Inc., Dallas, Tex.

Filed Dec. 11, 1969, Ser. No. 20,463

Term of patent 14 years

Int. Cl. D19—08


U.S. Cl. D25—1



220,628
HOLDER FOR ATTACHMENT TO A
TELEPHONE OR THE LIKE

Robert T. Crew, 3871 Gadsden Road,
Jacksonville, Fla. 32207
Filed Sept. 2, 1969, Ser. No. 18,945
Term of patent 14 years
Int. Cl. D14—99; D20—02


U.S. Cl. D26—14



220,629
SPEAKER ENCLOSURE

Yuji Shimizu, Osaka, Japan, assignor to Matsushita
Electric Industrial Co., Ltd., Osaka, Japan
Filed Jan. 9, 1970, Ser. No. 20,857
Claims priority, application Japan July 11, 1969
Term of patent 14 years
Int. Cl. D14—01


U.S. Cl. D26—14



220,630
COMBINED AMPLIFIER HOUSING AND BASE FOR
A RECORD PLAYER OR SIMILAR ARTICLE

Yuji Shimizu, Osaka, Japan, assignor to Matsushita
Electric Industrial Co., Ltd., Osaka, Japan
Filed Jan. 9, 1970, Ser. No. 20,858
Claims priority, application Japan July 11, 1969
Term of patent 14 years
Int. Cl. D14—04


U.S. Cl. D26—14



220,631
COMBINED AMPLIFIER HOUSING AND BASE FOR
A RECORD PLAYER OR SIMILAR ARTICLE

Yoshiaki Iida, Osaka, Japan, assignor to Matsushita
Electric Industrial Co., Ltd., Osaka, Japan
Filed Feb. 12, 1970, Ser. No. 21,422
Claims priority, application Japan Oct. 20, 1969
Term of patent 14 years
Int. Cl. D14—04


U.S. Cl. D26—14



220,632
COMBINED AMPLIFIER AND TAPE RECORDER

Ippei Kurihara, Osaka, Japan, assignor to Matsushita
Electric Industrial Co., Ltd., Osaka, Japan
Filed June 4, 1970, Ser. No. 23,310
Claims priority, application Japan Dec. 10, 1969
Term of patent 14 years
Int. Cl. D14—03


U.S. Cl. D26—14



220,633
INTERLOCKABLE FILE RACK UNIT

Herbert Rome, Los Angeles, and Erland G. Paulson,
Huntington Beach, Calif., assignors to Eldon Indus-
tries, Inc., Hawthorne, Calif.
Filed Dec. 12, 1969, Ser. No. 20,480
Term of patent 14 years
Int. Cl. D6—01


U.S. Cl. D33—3



220,634
GAME BOARD OR THE LIKE

Basilio Fontana, 3339 E. 112th St.,
Cleveland, Ohio 44104
Filed Sept. 24, 1969, Ser. No. 19,291
Term of patent 14 years
Int. Cl. D21—01


U.S. Cl. D34—5



220,635
ASTROLOGY GAME BOARD

Richard G. Boyer and Lola Elizabeth Boyer, both of
7045 Hawthorn Ave., Hollywood, Calif. 90028
Filed Oct. 24, 1969, Ser. No. 19,698
Term of patent 14 years
Int. Cl. D21—01


U.S. Cl. D34—5



220,636
COMBINED AUTOMOBILE DASHBOARD AND
STEERING WHEEL TOY

Albert Stubbmann, Franklin Lakes, N.J., assignor to
Kohner Bros., Inc., East Paterson, N.J.
Filed Feb. 12, 1970, Ser. No. 21,407
Term of patent 14 years
Int. Cl. D21—02

U.S. Cl. D34—15



220,637
DRAINER TRAY OR THE LIKE

James B. Swett, Barrington, R.I., and Sidney Z. Smith,
Worcester, Mass., assignors to Dart Industries, Inc.,
Los Angeles, Calif.
Filed Jan. 28, 1970, Ser. No. 21,116
Term of patent 14 years
Int. Cl. D7—01


U.S. Cl. D44—1



220,638
PLATE OR THE LIKE

Ottorino N. Mercadante, Corning, N.Y., assignor to
Corning Glass Works, Corning, N.Y.
Filed May 1, 1970, Ser. No. 22,756
Term of patent 14 years
Int. Cl. D7—01

U.S. Cl. D44—15



220,639
LADLE OR SIMILAR ARTICLE

Burt K. Todd, Ligonier, Pa., assignor to
Kerr-Hays Co., Pittsburgh, Pa.
Filed Feb. 18, 1970, Ser. No. 21,481
Term of patent 7 years
Int. Cl. D7—03

U.S. Cl. D44—29



220,640
FINDING FOR COSTUME JEWELRY OR THE LIKE
 Rolf E. Darbo, P.O. Box 2158,
 Madison, Wis. 53701
 Filed Dec. 19, 1969, Ser. No. 19,783
 Term of patent 14 years
 Int. Cl. D11—01

U.S. Cl. D45—1




220,641
LIGHTING FIXTURE
 Marilyn Lewis, Beverly Hills, Calif., assignor to
 Hamburger Hamlets, Inc.
 Filed Dec. 15, 1969, Ser. No. 20,496
 Term of patent 14 years
 Int. Cl. D26—02

U.S. Cl. D48—4



220,642
COMBINED LAMP AND PICTURE HOLDER
 Kenneth Roger Morehead, 205 Adams Ave.,
 Cuyahoga Falls, Ohio 43221
 Filed Jan. 3, 1969, Ser. No. 15,205
 Term of patent 14 years
 Int. Cl. D26—02

U.S. Cl. D48—20




220,643
VEHICLE SIGNAL LIGHT
 Joseph Nagy, 1513 Sherwood Court,
 Dearborn, Mich. 48124
 Filed Mar. 2, 1970, Ser. No. 21,701
 Term of patent 14 years
 Int. Cl. D12—99

U.S. Cl. D48—32




220,644
MONEY BOX
 Leva Delores Robinson, 2320 E. Harvard Ave.,
 Fresno, Calif. 93705
 Filed Nov. 19, 1969, Ser. No. 20,171
 Term of patent 14 years
 Int. Cl. D20—99

U.S. Cl. D52—4




220,645
WEATHER VANE
 Stephen Kwolek, 8385 Woodcrest Drive,
 Westland, Mich. 48185
 Filed June 18, 1970, Ser. No. 23,561
 Term of patent 14 years
 Int. Cl. D10—07

U.S. Cl. D52—6




220,646
INCLINOMETER
 Richard M. Provi, 1907 Brownfield Road 61107, and
 Donald L. Payne, 4849 Danforth Drive 61111, both
 of Rockford, Ill.
 Filed June 22, 1970, Ser. No. 23,582
 Term of patent 14 years
 Int. Cl. D10—08

U.S. Cl. D52—6




220,647
INCLINOMETER
 Richard M. Provi, 1907 Brownfield Road 61107, and
 Donald L. Payne, 4849 Danforth Drive 61111, both
 of Rockford, Ill.
 Filed June 22, 1970, Ser. No. 23,583
 Term of patent 14 years
 Int. Cl. D10—08

U.S. Cl. D52—6




220,648
INCLINOMETER
 Richard M. Provi, 1907 Brownfield Road 61107, and
 Donald L. Payne, 4849 Danforth Drive 61111, both
 of Rockford, Ill.
 Filed June 22, 1970, Ser. No. 23,584
 Term of patent 14 years
 Int. Cl. D10—08

U.S. Cl. D52—6




220,649
THERMOSTAT
 Yoshikazu Kuze, 31-3, 1-chome, Magome Higashi,
 Ota-ku, Tokyo, Japan
 Filed Dec. 2, 1969, Ser. No. 20,333
 Claims priority, application Japan June 5, 1969
 Term of patent 14 years
 Int. Cl. D10—99; D15—01

U.S. Cl. D52—7




220,650
**KEYBOARD-OPERATED ELECTRONIC
 MUSICAL INSTRUMENT**
 Robert N. Poznanovich, 9526 S. Manistee,
 Chicago, Ill. 60617
 Filed Aug. 4, 1969, Ser. No. 18,536
 Term of patent 14 years
 Int. Cl. D17—03

U.S. Cl. D56—1



220,651
**ELECTRONIC ORGAN CABINET
 OR SIMILAR ARTICLE**
 Hiroshi Saito, Osaka, and Masakazu Tatsumi, Hirakata,
 and Yoshiji Kon'i, Nara, Japan, assignors to Matsushita
 Electric Industrial Co., Ltd., Osaka, Japan
 Filed May 6, 1970, Ser. No. 22,862
 Claims priority, application Japan Nov. 20, 1969
 Term of patent 14 years
 Int. Cl. D17—01

U.S. Cl. D56—2



220,652

PORTABLE RADIO CABINET

Kazuhiro Hirayama and Hikaru Nakada, Tokyo, Japan,
assignors to Hitachi, Ltd., Manufacturers, Tokyo, Japan


Filed Nov. 13, 1969, Ser. No. 20,071

Claims priority, application Japan May 23, 1969

Term of patent 14 years

Int. Cl. D14—03

U.S. Cl. D56—4



220,653

COMBINED RADIO RECEIVER AND CLOCK

Setsuo Miyayama, Osaka, Japan, assignor to Matsushita
Electric Industrial Co., Ltd., Osaka, Japan


Filed June 22, 1970, Ser. No. 23,611

Claims priority, application Japan Jan. 23, 1970

Term of patent 14 years

Int. Cl. D14—03

U.S. Cl. D56—4



220,654

COMBINED RADIO AND RECORD CHANGER


Melvin H. Boldt, Glenview, and Kendrick T. Parsell,
Chicago, Ill., assignors to Zenith Radio Corporation,
Chicago, Ill.

Filed Apr. 1, 1970, Ser. No. 22,187

Term of patent 14 years

Int. Cl. D14—03

U.S. Cl. D56—4



220,655

BRIDGE EXTENSION FOR EYEGLASSES

Toni Holloway, 73—465 Feather Trail,
Palm Desert, Calif. 92260

Filed Oct. 2, 1969, Ser. No. 19,384

Term of patent 7 years

Int. Cl. D16—08

U.S. Cl. D57—1



220,656

METALLURGICAL OPAQUE PROJECTOR



Paul Rosenthal, 83—09 Talbot St.,
Kew Gardens, N.Y. 11415

Filed Oct. 13, 1969, Ser. No. 19,530

Term of patent 14 years

Int. Cl. D16—03, 04

U.S. Cl. D61—1



220,657

REAR PROJECTION VIEWER


William K. Christoffersen, North Minneapolis, James L.
Keely, Wayzata, and William T. Owens, Jr., Long Lake,
Minn., assignors to Washington Scientific Industries,
Inc., Long Lake, Minn.

Filed May 21, 1970, Ser. No. 23,075

Term of patent 14 years

Int. Cl. D16—04

U.S. Cl. D61—1



220,658

REAR PROJECTION VIEWER


William K. Christoffersen, North Minneapolis, James L.
Keely, Wayzata, William T. Owens, Jr., Long Lake, and
Larry D. Quaurud, North Minneapolis, Minn., assignors
to Washington Scientific Industries, Inc., Long Lake,
Minn.

Filed May 21, 1970, Ser. No. 23,091

Term of patent 14 years

Int. Cl. D16—04

U.S. Cl. D61—1



220,659

CALCULATING MACHINE

Mititaka Yamamoto, Kyoto-fu, Japan, assignor to Omron
Tateisi Electronics Co., Kyoto-fu, Japan


Filed Mar. 27, 1969, Ser. No. 16,478

Claims priority, application Japan Sept. 29, 1968

Term of patent 7 years

Int. Cl. D18—02

U.S. Cl. D64—11



220,660

PUMP AND FILTER UNIT


Wilbur C. Smith, Plainfield, and Philip J. Nagengast,
North Caldwell, N.J., assignors to Worthington Cor-
poration, Harrison, N.J.

Filed Jan. 21, 1970, Ser. No. 21,018

Term of patent 14 years

Int. Cl. D15—02

U.S. Cl. D65—1



220,661

BOAT

Ronald Howard Line, 15 Altamont Road,
Willowdale, Ontario, Canada


Filed Dec. 29, 1969, Ser. No. 20,663

Claims priority, application Canada Dec. 1, 1969

Term of patent 14 years

Int. Cl. D12—06


U.S. Cl. D71—1



220,662

AUTOMATIC FIRE ALARM OR SIMILAR ARTICLE
 Werner Buhner, Uetikon am See, Switzerland, assignor to
 Cerberus AG, Mannedorf, Switzerland
 Filed Nov. 12, 1969, Ser. No. 20,045
 Claims priority, application Switzerland May 12, 1969
 Term of patent 14 years
 Int. Cl. D29—01


U.S. Cl. D72—1



220,663

FOUNTAIN PEN NIB
 Homer T. Green, Milton, Wis., assignor to The Parker
 Pen Company, Janesville, Wis.
 Filed Apr. 22, 1970, Ser. No. 22,559
 Term of patent 14 years
 Int. Cl. D19—02


U.S. Cl. D74—17



220,664

CARPET DISPLAY STAND
 Ralph W. Wagoner, Naperville, Ill., assignor to
 Sears, Roebuck and Co., Chicago, Ill.
 Filed Feb. 2, 1970, Ser. No. 21,191
 Term of patent 14 years
 Int. Cl. D6—01


U.S. Cl. D80—9



220,665

HEATER HOUSING FOR HAIR CURLERS
 John L. Benty, Scotch Plains, N.J., and Svend Fischlein,
 Albertslund, Denmark, assignors to Bristol-Myers Com-
 pany, New York, N.Y.
 Filed Mar. 9, 1970, Ser. No. 21,794
 Claims priority, application Denmark Oct. 7, 1969
 Term of patent 14 years
 Int. Cl. D28—03

U.S. Cl. D86—10



220,666

THERAPEUTIC CREEPING DEVICE
 Reba M. Lillibridge, 9319 Canton Center Road,
 Plymouth, Mich. 48170
 Filed Dec. 24, 1969, Ser. No. 20,632
 Term of patent 14 years
 Int. Cl. D24—02


U.S. Cl. D88—5



220,667

BLENDER OR SIMILAR ARTICLE
 Yasuhiro Koshido and Hideo Kondou, Tokyo, and
 Koichiro Ninomiya and Itusei Sato, Hitachi, Japan,
 assignors to Hitachi, Ltd., Tokyo, Japan
 Filed June 5, 1970, Ser. No. 23,330
 Term of patent 14 years
 Int. Cl. D7—05

U.S. Cl. D89—1



220,668

SIDEWALK BICYCLE
 Frederick E. Purdy, Olney, Ill., assignor to
 AMF Incorporated
 Filed May 1, 1970, Ser. No. 22,750
 Term of patent 14 years
 Int. Cl. D12—11

U.S. Cl. D90—8



220,669


BICYCLE SEAT, OR SIMILAR ARTICLE
 Charles V. Wrobel, Lake Forest, Walter Dian, Downers
 Grove, and Gerald Golden, Highland Park, Ill., as-
 signors to Excel Incorporated, Franklin Park, Ill.
 Filed Sept. 18, 1969, Ser. No. 19,199
 Term of patent 14 years
 Int. Cl. D12—14

U.S. Cl. D90—16

220,670
TIRE

Iain C. Mills, Sutton Coldfield, England, assignor to The
 Dunlop Company Limited, Birmingham, England
 Filed Feb. 20, 1970, Ser. No. 21,543
 Claims priority, application Great Britain Aug. 28, 1969
 Term of patent 14 years
 Int. Cl. D12—14

U.S. Cl. D90—20



220,671

TOWEL OR SIMILAR ARTICLE
 Edward C. Taiman, Tarrytown, N.Y., assignor to Cannon
 Mills Company, Kannapolis, N.C.
 Filed June 9, 1970, Ser. No. 23,394
 Term of patent 14 years
 Int. Cl. D6—09


U.S. Cl. D92—26



220,672

BOTTLE CAPPER
 Iganio Ronchetti, Via Fratelli Calvi 67,
 Calolziocorte, Italy
 Filed Mar. 18, 1970, Ser. No. 21,951
 Term of patent 3½ years
 Int. Cl. D15—05


U.S. Cl. D94—3



220,673

COMBINED PLATFORM AND RAMP
 Harry W. Holbrook, 9 Donegal Way,
 Pinole, Calif. 94564
 Filed Dec. 22, 1969, Ser. No. 20,592
 Term of patent 14 years
 Int. Cl. D25—01

U.S. Cl. D13—7



LIST OF PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 4TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- Aasnaes, Hans Bent, to International Business Machines Corporation. Triple integrating ramp analog to digital converter. 3,577,140, Cl. 340-347.
- AB Electrolux: *See—*
Klug, Oluf Walter Henry, 3,577,363.
- Abbott Laboratories: *See—*
Wideburg, Norman E.; and Miller, Laura H., 3,577,422.
- Achenbach Sohne G.m.b.H.: *See—*
Barten, Ernst H., 3,577,757.
- Ackermann, Horst: *See—*
Bippus, Walter; and Ackermann, Horst, 3,577,700.
- Adair, James Richard, to United Engineering and Foundry Company. Apparatus for extracting chocks, guides and couplings from roll assemblies. 3,577,758, Cl. 72-239.
- Adamaszek, Kazimerz. Sensing device for automatic braking of the spindle in ring spinning and ring twisting machines. 3,577,722, Cl. 57-80.
- Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jürgen F.; Edwards, Alan C.; and Tettersoo, Hans, to Shell Oil Company. Process of preparing tritylamines. 3,577,413, Cl. 260-247.
- Adams, James S., to Magnavox Company, The. Modified latch circuit specifically for search tuning arrangement. 3,577,083, Cl. 325-471.
- Adams, Thomas: *See—*
Wright, Dennis; and Adams, Thomas, 3,577,749.
- Adelaar, Hans Helmut: *See—*
De Wit, Frans Corneel Leo; and Adelaar, Hans Helmut, 3,576,949.
- Advanced Peripherals, Inc.: *See—*
Bleiman, Lewis W., 3,577,023.
- Aga Aktiebolag: *See—*
Soderberg, Leif Erik Roland, 3,577,273.
- Agfa-Gevaert Aktiengesellschaft: *See—*
Kisselmann, Willy; Rumpelstein, Fritz; Kopf, Paul; and Landbrecht, Franz, 3,577,078.
- Air Products and Chemicals, Inc.: *See—*
Erby, William A.; and Walde, Robert A., 3,577,546.
- Air Reduction Company, Incorporated: *See—*
Sullivan, Cornelius J., 3,576,966.
- Aitken, John, to Schlumberger Technology Corporation. Well logging tool for making multiple pressure tests and for bottom hole sampling. 3,577,782, Cl. 73-155.
- Akashi, Goro: *See—*
Sato, Masamichi; Tamai, Yasuo; Matsumoto, Seiji; and Akashi, Goro, 3,577,259.
- Akw, Robert E.; and Johnson, Henry C., to United States of America, Army, mesne. Meteorological device employing a temperature compensated transmitter. 3,577,100, Cl. 331-117.
- Aktiebolaget Nordstroms Linbanor: *See—*
Kohler, Karl Gustav, 3,577,703.
- A&L Battery & Electric Service, Inc.: *See—*
Aprill, Theophil, Jr.; and Leerkamp, John R., 3,577,768.
- Al-Roy, John D., to Monsanto Company. Apparatus for forming hollow articles. 3,577,594, Cl. 18-19.
- Albsmeier, Hans; and Traub, Karl, to Siemens Aktiengesellschaft. Electromechanical filter. 3,577,180, Cl. 333-72.
- Alburn, Harvey E.; Dvonch, William; and Sallay, Stephan, to American Home Products Corporation. Tetrahydro-2-oxofuran penicillins. 3,577,408, Cl. 260-239.1
- Alden, Milton, to Alden Research Foundation. Recording helix. 3,577,150, Cl. 346-139.
- Alden Research Foundation: *See—*
Alden, Milton, 3,577,150.
- Aldrich, Ralph E.; and Caruso, Paul J., to Itek Corporation. Real-time solid state camera system. 3,577,200, Cl. 178-7.1
- Alexander, Arthur P.; Aronson, Steven R.; and Langenhagen, Charles F., Jr., to Packaged Resins Company, Inc. Shoe last remodeling jig. 3,577,578, Cl. 12-146.
- Alexander, Jerry; and Stevens, Irving J. Ratchet wrench. 3,577,816, Cl. 81-63.1
- Alexander, Robert H.; Falter, Ronald C.; Ringer, Cecil D.; and Linsker, Eugene, to Rockwell Manufacturing Company. Portable power tool. 3,577,807, Cl. 77-13.
- Allen & Hamburgs Limited: *See—*
Jack, David; and Rhodes, Deryck, 3,577,549.
- Allen, Frank L., Jr.: *See—*
Bliven, Roger; Allen, Frank L., Jr.; and Davis, John R., 3,577,271.
- Allen-Bradley Company: *See—*
Dummermuth, Ernst H., 3,577,012.
McCall, Amiel J.; Elms, Ronald D.; and Rice, Larry D., 3,576,979.
Weidmann, Hans E., 3,577,016.
- Allied Chemical Corporation: *See—*
Anello, Louis Gene; Sweeney, Richard Francis; and Litt, Morton Herbert, 3,577,465.
- Brownstein, Arthur M.; and Sibilla, John P., 3,577,458.
Le Noir, Fred W., 3,577,615.
Sweeney, Richard F.; and Price, Alson K., 3,577,447.
- Allinquant, Fernand Stanislas. Meat tenderizing machine. 3,577,585, Cl. 17-25.
- Allis-Chalmers Manufacturing Company: *See—*
Foster, Samuel L.; and Johnston, Reed M., 3,577,109.
Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., 3,577,050.
- Allmann Svenska Elektriska Aktiebolaget: *See—*
Nordin, Tore, 3,577,048.
- Allmanna Svenska Elektriska Aktiebolaget: *See—*
Bengtson, Waldemar; and Dahle, Orvar, 3,577,108.
Bergman, Carl; and Claesson, Harry, 3,577,635.
Hermansson, Fredrik, 3,577,055.
Kring, Arne; and Johansson, Arne, 3,577,041.
Monestam, Eskil, 3,577,761.
- Alm, Christian A.: *See—*
Stone, John G.; Buettner, George S.; and Alm, Christian A., 3,576,940.
- Alpha Metals, Inc.: *See—*
Schneider, Alvin; and Tarnowsky, Joseph, 3,577,284.
- Altendburger, Karl, KG: *See—*
Speichinger, Ferdinand, 3,577,602.
- Aluminum Company of America: *See—*
Zelley, Walter G.; and Walton, Charles J., 3,577,288.
- Amann, Willard R., to Eastman Kodak Company. Magnetic clamp. 3,577,583, Cl. 16-87.2
- American Air Filter Company, Inc.: *See—*
Vowels, Freeman M., 3,576,963.
- American Beef Packers, Inc.: *See—*
Means, Ray H.; Kussman, Michael; Wade, Jack; and Vodra, Victor H., 3,577,241.
- American Cyanamid Company: *See—*
Bott, George Spencer; and Marlow, William Henry, 3,577,701.
Cantrall, Margot Louise; Sassiver, Martin Leon; and Shepherd, Robert Gordon, 3,577,417.
Dorbransky, Robert Alan, 3,577,402.
Fidell, Louis Isadore, 3,577,342.
McCormick, Jerry Robert Daniel; and Arnold, Nancy Hazlett, 3,577,439.
Megna, Ignazio Salvatore; and Koroscil, Anthony, 3,577,388.
Miller, Bernard; and Gund, Tamara Helen Mladineo, 3,577,536.
Nielsen, Peter Adams; Cooper, Murray Sam; and Doyno, Ernest Robert, 3,577,319.
Pensack, Joseph Michael, 3,577,529.
Pratt, Walter David, 3,577,524.
Shaw, John Thomas, 3,577,541.
Voight, Heinz Kurt Walter; and Myers, Robert Lee, 3,576,987.
- American Enka Corporation: *See—*
Marinus, Korstiaan J. V.; and Fontijn, Wilhelmus J., 3,577,308.
- American Hoechst Corporation: *See—*
Hoffmann, Hermann; and Schmidt, Helmut, 3,577,405.
- American Home Products Corporation: *See—*
Alburn, Harvey E.; Dvonch, William; and Sallay, Stephan, 3,577,408.
Archibald, John L.; and Freed, Meier E., 3,577,423.
Bell, Stanley C.; and Wei, Peter H. L., 3,577,434.
Bell, Stanley C.; and Gochman, Carl, 3,577,435.
Bruce, William F., 3,577,462.
Oliver, Donald W.; and Wendt, Gerhard R., 3,577,445.
Rakhit, Sumanas, 3,577,446.
Schneller, George H.; and Levi, Ralph S., 3,577,532.
Teller, Daniel M.; Douglas, George H.; and Smith, Herchel, 3,577,410.
- American Standard, Inc.: *See—*
Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,577,572.
- American Telephone and Telegraph Company: *See—*
Swierczewski, Witold E.; and Swierczewski, Witold E., 3,577,155.
- Ametek, Inc.: *See—*
Levan, Ambrose E.; and Tatum, David, 3,577,214.
- Amicon Corporation: *See—*
Bolger, Justin C.; Mc Collum, Hugh Evan; and Hausslein, Robert William, 3,577,313.
- AMP Incorporated: *See—*
Bruetsch, Harold Louis, 3,577,117.
Delyon, Armand Rene; and Kensinger, Lex Donald, 3,577,119.
Hammond, James Woodrow, 3,577,814.
Hoffman, Norman Edwin, 3,577,496.
Pountney, Clifford Harold; and Miller, Edward Francis, 3,577,281.

- Reider, George Sylvester, 3,577,118.
Amsted Industries Incorporated: *See—*
Ratcliffe, Edward; and Crawford, William N., 3,577,644.
Amster, Robert L., to General Telephone & Electronics Laboratories, Incorporated. Europium and manganese sodium aluminate phosphors. 3,577,350, Cl. 252-301.4
Anaconda Wire and Cable Company: *See—*
Bernhard, George D.; and Schwarz, Olek, 3,577,034.
Pendleton, Wesley W.; and Ostrander, George W., 3,577,309.
Anderson Bros. Mfg. Co.: *See—*
Jacobson, William P., 3,577,484.
Anderson, Donald E.: *See—*
Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; and Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.
Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; and Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., to International Business Machines Corporation. Phase locked oscillator for storage apparatus. 3,577,132, Cl. 340-174.1
Anello, Louis Gene; Sweeney, Richard Francis; and Litt, Morton Herbert, to Allied Chemical Corporation. Terminally unsaturated fluorolefins. 3,577,465, Cl. 260-614.
Anhorn, Victor J.: *See—*
Pace, Henry A.; and Anhorn, Victor J., 3,577,398.
Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukuta, Akihiro, to Tokyo Shibaura Electric Co., Ltd. Magneton device with cooling fluid flow in longitudinal direction of magnetron tube. 3,577,033, Cl. 315-39.71
Apikos, Dominic: *See—*
Kremer, Charles J.; Brown, Donald S.; Apikos, Dominic; and Thean, John T., 3,577,373.
Appleton, Bernard S. Method of attaching transmission belt and pin. 3,577,630, Cl. 29-517.
Applied Synthetics Corporation: *See—*
Silverstein, Paul, 3,577,820.
Aprill, Theophil, Jr.; and Leerkamp, John R., to A&L Battery & Electric Service, Inc. Hydrostatic testing apparatus. 3,577,768, Cl. 73-40.5
Arant, Gene W.: *See—*
Lee, Robert L., 3,577,639.
Arant, Juanita F.: *See—*
Lee, Robert L., 3,577,639.
Archibald, John L.; and Freed, Meier E., to American Home Products Corporation. 1,4-Bis-(3-indoleglyoxyloxy) piperazines and derivatives thereof. 3,577,423, Cl. 260-268.
Ardary, Zane L.; Maxey, Andrew W.; and Reynolds, Carl D., to United States of America, Atomic Energy Commission. Fibrous thermal insulation and method of making same. 3,577,344, Cl. 252-62.
Argabright, Perry A.; Phillips, Brian L.; and Sinkey, Vernon J., to Marathon Oil Company. Alcohol-blocked isocyanate compositions and derivatives. 3,577,391, Cl. 260-77.5
Arima, Hideki: *See—*
Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
Arimura, Katsuo: *See—*
Nakanishi, Michio; Arimura, Katsuo; Imamura, Hiroshi; and Kobayakawa, Toshihiro, 3,577,425.
Arizona Chemical Company: *See—*
Sheers, Edward Helmut, 3,577,230.
Armour and Company: *See—*
Phillips, Duane; Schultz, Roger C.; and Beck, Herbert H., 3,577,296.
Armour Industrial Chemical Company: *See—*
Castro, Anthony J.; Marsh, Frederick S.; Kinney, Layton E.; and Fischl, Frank J., 3,577,370.
Dybalski, Jack N., 3,577,249.
Armour Pharmaceutical Company: *See—*
Reynolds, Harold C.; and Olsen, Donald B., 3,577,535.
Armstrong Cork Company: *See—*
Ward, John M., 3,577,222.
Armstrong, William J.; Healy, Albert M.; and Duffy, Michael C., to International Business Machines Corporation. Integrated semiconductor devices and fabrication methods therefor. 3,577,044, Cl. 317-235.
Arnold, Nancy Hazlett: *See—*
McCormick, Jerry Robert Daniel; and Arnold, Nancy Hazlett, 3,577,439.
Arntz, Robert L.; and Marker, John R., Jr., to Dominion Electric Corporation. Transformer having a wound core around linear conductors. 3,577,110, Cl. 336-175.
Aronson, Steven R.: *See—*
Alexander, Arthur P.; Aronson, Steven R.; and Langenhagen, Charles F., Jr., 3,577,578.
Arpe, Hans J.: *See—*
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jurgen F.; Edwards, Alan C.; and Tetteroo, Hans, 3,577,413.
Asano, Kuniji: *See—*
Kubo, Moritada; and Asano, Kuniji, 3,577,773.
Ashland Oil, Inc.: *See—*
Forrester, Robert A.; and Mc Nay, Ralph E., 3,577,555.
Sedgwick, Grant O., 3,577,383.
Ashley, Eugene; and Tassie, Douglas Pray, to General Electric Company. Bellows sealed firing pin. 3,577,826, Cl. 89-26.
Ashmore, Charles I., to Thiokol Chemical Corporation. Process for the preparation of a combustion additive. 3,577,449, Cl. 260-439.
Asp, Ivar Alvar. Opening device for cans and similar containers provided with twist lids. 3,577,812, Cl. 81-3.36
Asquith, Claire F.: *See—*
Walliser, Sylvan A.; and Asquith, Claire F., 3,577,077.
Aston, Bruno D. Method of making an applicator for cosmetics. 3,577,582, Cl. 15-244.
Atcherson, Samuel M.; and Rodgers, Robert P., to Singer-General Precision, Inc. Computer sound generator. 3,577,084, Cl. 328-14.
Atelian, Edmond J.: *See—*
Whelan, Ray W.; and Atelian, Edmond J., 3,577,777.
Atlantic Richfield Company: *See—*
Doan, Robert B.; and Taylor, Robert C., 3,577,248.
Jubin, John C., Jr.; and Becker, Matthew L., 3,577,472.
Kremer, Charles J.; Brown, Donald S.; Apikos, Dominic; and Thean, John T., 3,577,373.
La Force, Richard C., 3,577,068.
Shalit, Harold, 3,577,329.
Washall, Thomas A.; and Blittman, Sidney, 3,577,443.
Atlas Chemical Industries, Inc.: *See—*
Feltzin, Joseph; and Tehrani, Nadj Y., 3,577,385.
Auphan, Michel Joseph: *See—*
Perilhou, Jean; and Auphan, Michel Joseph, 3,577,772.
Automation Industries, Inc.: *See—*
Collins, Jack T., 3,577,071.
Automobiles Peugeot: *See—*
Guettier, Michel, 3,577,798.
Automotive Products Company Limited: *See—*
Parsons, David, 3,577,832.
Avco Corporation: *See—*
Gri, Norman I.; and Yon, Eugene T., 3,577,175.
Tuten, William J.; and Gauld, Godfrey R., 3,577,168.
Avery-Hardoll Limited: *See—*
Thomson, John A.; and Evill, Brian R., 3,577,188.
Avins, Jack, to RCA Corporation. Integrated circuit biasing arrangements. 3,577,167, Cl. 307-296.
Bacha, John D.; and Selwitz, Charles M., to Gulf Research & Development Company. Process for preparing 1,3,5-haloxylene. 3,577,470, Cl. 260-650.
Badin, Elmer J.: *See—*
Rai, Charanjit; Collins, Sherman D.; and Badin, Elmer J., 3,577,228.
Baier, Franz; and Schmitz, Rudolf. Lead strip for weighing down curtains. 3,577,307, Cl. 161-175.
Baird, Justus N., Jr.; Johnson, James S.; Kraus, Kurt A.; and Perona, Joseph J., to United States of America, Atomic Energy Commission. Filtration method of separating liquids from extraneous materials. 3,577,339, Cl. 210-23.
Baker, James A., to Cornell Research Foundation, Inc. Adenovirus vaccine against canine hepatitis. 3,577,525, Cl. 424-89.
Baker, Joseph S.: *See—*
Baskerville, Ralph J., Jr.; and Baker, Joseph S., 3,577,290.
Baker, Ronald E.; Cook, Richard L.; and Slagel, Edwin C., to Goodyear Aerospace Corporation. Polymer laminate to prevent severe metal petalling damage. 3,577,306, Cl. 161-90.
Balazer, Leonard P.: *See—*
Freier, Michael; and Balazer, Leonard P., 3,577,146.
Ballennie, Peter, deceased (by Ballennie, Eileen Margaret, executrix); and Ruffo, Angelo P., to Industrial Air Filters Limited. Combination air filter and frame for holding the same. 3,577,712, Cl. 55-501.
Banks, Roger W., to Everest & Jennings, Inc. Reversible fail-safe wheelchair drive control circuit. 3,577,054, Cl. 318-257.
Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, to Imperial Chemical Industries Limited. Insecticidal and fungicidal 2-aminopyrimidinyl-6- carbamate compositions. 3,577,543, Cl. 424-251.
Barnes Drill Co.: *See—*
Jakimcius, Zigmant, 3,577,684.
Barrett, Paul Anthony, to Burroughs Wellcome Co. Piperazine substituted dithiosemicarbazones. 3,577,421, Cl. 260-268.
Barry, Thomas L., to Sylvania Electric Products Inc. Coexisting crystalline solution phases activated by divalent europium. 3,577,169, Cl. 313-109.
Barten, Ernst H., to Achenbach Sohne G.m.b.H. Roller frame structure with one or more pressing devices for maintaining constant the gap between the rollers. 3,577,757, Cl. 72-237.
Bartlett, William F., to Stromberg-Carlson Corporation. Code call facility for electronic telephone exchange. 3,577,154, Cl. 179-18.
Baskerville, Ralph J., Jr.; and Baker, Joseph S., to Procter & Gamble Company. The. Process of making a non-woven fabric. 3,577,290, Cl. 156-62.
Battelle-Institute e.V.: *See—*
Bol, Jan, 3,577,352.
Bauer, David Elvis. AC motor control system with synchronous speed change. 3,577,052, Cl. 318-230.
Baumanis, Bruno, to Molex Incorporated. Lamp socket and terminal. 3,577,116, Cl. 339-125.
Baxter Laboratories, Inc.: *See—*
Regan, Bernard M., 3,577,552.

- Beach, Kenneth M., Jr., to Xerox Corporation. Character recording and recognition system. 3,577,203, Cl. 235-61.114
Beal, John O., to Monterey Research Laboratory, Inc. Apparatus for detectively programming different types of shock tests. 3,577,763, Cl. 73-12.
Beall, Donald L., to General Electric Company. Analog to digital conversion circuit. 3,577,194, Cl. 340-347.
Beam, Dale R., to Mead Corporation, The. Charged drop generator with guard system. 3,577,198, Cl. 346-75.
Beatty, Ronald L.; Leitnaker, James M.; and Notz, Karl J., Jr., to United States of America, Atomic Energy Commission. Method for preparation of carbonitride nuclear fuel materials. 3,577,485, Cl. 264-0.5
Beck, Douglas E.: *See—*
Duve, John P.; and Beck, Douglas E., 3,577,579.
Beck, Herbert H.: *See—*
Phillips, Duane; Schultz, Roger C.; and Beck, Herbert H., 3,577,296.
Becker, Matthew L.: *See—*
Jubin, John C., Jr.; and Becker, Matthew L., 3,577,472.
Beckman Instruments, Inc.: *See—*
Porter, Joe A.; and Couch, Stuart L., 3,577,332.
Beckwith, Merton M.: *See—*
Joachim, Tibor; and Beckwith, Merton M., 3,577,327.
Rynne, George B.; and Beckwith, Merton M., 3,577,328.
Behr, Bryon C.; Sprogis, Gunars; and Booth, Frederick E., to Union Carbide Corporation. Automatic battery switching device. 3,577,003, Cl. 307-66.
Belady, Laszlo A., to International Business Machines Corporation. On-line system for measuring the efficiency of replacement algorithms. 3,577,185, Cl. 340-142.5
Bell & Howell Company: *See—*
Cross, Anthony L., 3,577,007.
Bell, Stanley C.; and Gochman, Carl, to American Home Products Corporation. Process for the preparation of 3-aryl-2-imino-3- indolins and related compounds. 3,577,435, Cl. 260-326.11
Bell, Stanley C.; and Wei, Peter H. L., to American Home Products Corporation. N-Aryl- α -(hydroxymethyleneimino)- β -oxo-cyclopolymethyleneamine and related compounds and a method for their preparation. 3,577,434, Cl. 260-326.5
Bell Telephone Laboratories, Incorporated: *See—*
Morrow, Robert H.; and Perneski, Anthony J., 3,577,131.
Bellinson, Bernard; and Young, Henry R., to Marine Swimming Pool Equipment Co. Combination cleaning, fountain and therapeutic whirlpool apparatus for swimming pools. 3,577,571, Cl. 4-172.17
Belohoubek, Erwin F., to RCA Corporation. Transistor package for microwave stripline circuits. 3,577,181, Cl. 333-84.
Beloit Corporation: *See—*
Mc Clenathan, John A.; and Nielsen, Donald L., 3,577,653.
Piette, Andre G., 3,577,316.
Stedile, Udino, 3,577,767.
Bendix Corporation, The: *See—*
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., 3,576,999.
Cohen, Richard L., 3,577,058.
Derrough, Edward R., 3,577,333.
Hofmeister, Laurence C., 3,577,009.
Madurski, Joseph P.; Presley, Rex W.; and Rothfusz, Ralph W., 3,577,049.
Maitland, Robert Thomas, 3,577,113.
Molnar, Robert J.; Parfomak, Walter; Molnar, Robert J.; and Parfomak, Walter, 3,577,126.
Moorman, Charles J.; and Parmater, John Q., 3,576,992.
Russo, Frank A.; and Valek, Robert J., 3,576,976.
Sanford, Norman R.; and Wieg, Heinrich J., 3,577,039.
Walker, John H., 3,577,766.
Benford, Charles L., Jr.; and Mielke, James E., to Owens-Illinois, Inc. Scratch and abrasion resistant coatings for glass. 3,577,256, Cl. 117-6.
Bengtson, Waldemar; and Dahle, Orvar, to Allmanna Svenska Elektriska Aktiebolaget. Annular magneto-elastic transducer. 3,577,108, Cl. 336-20.
Benigni, Joseph D.: *See—*
Goldstein, Irving S.; and Benigni, Joseph D., 3,577,467.
Benner, Richard C., to Hughes Aircraft Company. Semi-elliptical pump cavity. 3,577,095, Cl. 331-94.5
Bennett, Ambrose L.; and Tepper, Sidney, to Topper Corporation. Gravity actuated toy vehicle having auxiliary jet propulsion means. 3,577,677, Cl. 46-206.
Bennett, John A., to Chandler Evans, Inc. Means to overcome differential thermal expansion effects in bimetallic splined shaft assemblies. 3,577,795, Cl. 74-446.
Benson, Ralph A., to General Electric Company. Digital information transfer system having integrity check. 3,577,187, Cl. 340-163.
Bentley Machine Development Company Limited, The: *See—*
Wright, Dennis; and Adams, Thomas, 3,577,749.
Bentschneider, Eugene E., to Manchester Tool & Die, Inc. Center feed driver assembly. 3,577,624, Cl. 29-211.
Bergman, Carl; and Claesson, Harry, to Allmanna Svenska Elektriska Aktiebolaget. Method for isostatic compression, such as the manufacture of powder bodies. 3,577,635, Cl. 29-615.
Bergman, Robert J., to Sperry Rand Corporation. Method of operating a convertible memory system. 3,577,134, Cl. 340-174.
Bergquist, Clifford A., to Pendleton Tool Industries, Inc. Two-way torque wrench. 3,577,815, Cl. 81-52.4
Berklenblit, Melvin; and Reisman, Arnold, to International Business Machines Corporation. Semiconductor preparation and deposition process. 3,577,286, Cl. 148-175.
Bernhard, George D.; and Schwarz, Olek, to Anaconda Wire and Cable Company. Power interruption control system. 3,577,034, Cl. 317-22.
Bertelli, Guido: *See—*
Torti, Luigi; and Bertelli, Guido, 3,577,310.
Bertoglio, Joseph; Deming, Philip L.; Eckert, Joyce G.; and Shafer, James R., to Monsanto Company. Apparatus for determining crystallization temperature. 3,577,765, Cl. 73-17.
Beschrip, Frederick; to Smith Kline & French Laboratories. Banding machine. 3,577,702, Cl. 53-198.
Bethlehem Steel Corporation: *See—*
Shah, Dipak C.; and Schwartz, Louis S., 3,577,753.
B&H Electronics, Inc.: *See—*
Laimins, Eric, 3,577,779.
Bharucha, Kekhusroo Rustomji: *See—*
Koh, Teow Yan; and Bharucha, Kekhusroo Rustomji, 3,577,534.
Biel, John Hans: *See—*
Warawa, Edward John; and Biel, John Hans, 3,577,461.
Bigland, Bernard K., to General Engineering Company (Radcliffe) Limited. Manufacture of plastic tubular film. 3,577,488, Cl. 264-95.
Billett, William J.; and Vartanian, Edwin S., to Olin Mathieson Chemical Corporation. Trigger mechanism. 3,577,827, Cl. 89-145.
Binder, Charles R., to General Motors Corporation. Cross-linked carbonylated elastomers. 3,577,380, Cl. 260-41.5
Bippus, Walter; and Ackermann, Horst, to Demag AG. Method and apparatus for producing container parts from sheet material. 3,577,700, Cl. 53-30.
Bird & Son, Inc.: *See—*
Jackson, James W., 3,577,593.
Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., to International Business Machines Corporation. Composer system for processing data in parallel columns. 3,577,127, Cl. 340-172.5
Bishop, David A.: *See—*
Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
Bishop, Nigel Douglas: *See—*
Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, 3,577,543.
Blackwell, Ellis R.: *See—*
Tandler, Paul; and Blackwell, Ellis R., 3,577,759.
Blair, Noel D., to Hooker Chemical Corporation. Nitrilotacetic acid alkyl resins. 3,577,371, Cl. 260-22.
Bleiman, Lewis W., to Advanced Peripherals, Inc. Moving coil actuator. 3,577,023, Cl. 310-13.
Blitchington, Frank H., Jr., to Western Electric Company, Incorporated. Feedback circuit for anodizing thin-film resistors. 3,577,335, Cl. 204-228.
Blittman, Sidney: *See—*
Washall, Thomas A.; and Blittman, Sidney, 3,577,443.
Bliven, Roger; Allen, Frank L., Jr.; and Davis, John R., to Marshall, Donald, John Bomar, Horace L., mesne. Textile bobbin. 3,577,271, Cl. 117-148.
Blomgren, Jack P., to Minnesota Mining and Manufacturing Company. Lamp failure detection and change device. 3,577,173, Cl. 315-88.
Blum, Jack F., to General Motors Corporation. Resistor composition. 3,577,355, Cl. 252-512.
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., to Bendix Corporation, The. Method and apparatus for determining the orientation of an object relative to an elliptic object. 3,576,999, Cl. 250-203.
Bobst, J., & Fils S.A.: *See—*
Lang, Pierre, 3,577,834.
Bock, Herbert G.; and Szerejko, Walter J., to Chandler Evans, Inc. Method of filling a pressure vessel assembly. 3,577,696, Cl. 53-7.
Boeing Company, The: *See—*
Ferrell, Philip J., 3,577,206.
Sherbert, Archie T., Jr., 3,577,120.
Visser, Gerrit A., 3,577,808.
Bogner, Gunther; and Maier, Richard, to Siemens Aktiengesellschaft. Fully or partly stabilized conductor comprised of superconducting and normal-conducting metals. 3,577,151, Cl. 174-128.
Bogosofo, John P., to General Motors Corporation. Brake warning switch. 3,576,959, Cl. 200-84.
Bol, Jan, to Battelle-Institute e.V. Temperature indicating device of dispersion filter adjusted to produce color changes near 0° C. 3,577,352, Cl. 252-408.
Bolger, Justin C.; Mc Collum, Hugh Evan; and Hausslein, Robert William, to Amicon Corporation. Condensation products of amines with epinaldehydins. 3,577,313, Cl. 162-164.
Bolkow Gesellschaft mit beschränkter Haftung: *See—*
Schmidt, Gunther, 3,577,735.
Bomar, Horace L.: *See—*
Bliven, Roger; Allen, Frank L., Jr.; and Davis, John R., 3,577,271.

- Booth, Frederick E.: See—
Behr, Bryon C.; Sprogis, Gunars; and Booth, Frederick E., 3,577,003.
- Bosch, Robert, G.m.b.H.: See—
Widl, Gerhard; Groetzner, Kurt; and Knodler, Adolf, 3,577,107.
- Botkin, Lawrence A., to Freuhauf Corporation. Method and apparatus for transporting liquefied gas. 3,577,739, Cl. 62-45.
- Bott, George Spencer; and Marlow, William Henry, to American Cyanamid Company. Printing and crimping aluminum seal closures. 3,577,701, Cl. 53-131.
- Boughton, John D.; Roberts, Philip M.; and Sloboda, Mieczyslaw Herman, to Johnson, Matthey & Co., Limited., 3,577,234, Cl. 75-159.
- Boutry, Pierre; Daumas, Jean Claude; and Montarnal, Roger, to Institut Francais du Petrole des Carburants et Lubrifiants. Process for converting saturated hydrocarbons to unsaturated hydrocarbons by oxidation. 3,577,477, Cl. 260-683.3
- Bouvet, Pierre Charles Victor: See—
Jirou, Marcel Georges; and Bouvet, Pierre Charles Victor, 3,577,212.
- Bowen, John C.; and Fischer, Howard G., II, to Duriron Company, Inc., The. Apparatus for high pressure measurement. 3,577,112, Cl. 338-4.
- Braginetz, Paul A., to Morris, Philip, Incorporated. Retractable blade knife. 3,577,637, Cl. 30-162.
- Brahm, Harry. Portable and collapsible clothes drier receptacle. 3,577,650, Cl. 34-151.
- Brandl, Walter; and Mathes, Rudolf, to Reimers Getriebe A.G. Quick-set tool holder. 3,577,809, Cl. 77-58.
- Branson Instruments, Incorporated: See—
Obeda, Edward G., 3,577,292.
- Braun, G. A., Inc.: See—
Hertig, Max; and Meier, Peter J., 3,577,751.
Hertig, Max; and Meier, Peter J., 3,577,752.
- Brenden, Orville A. Valve stem grinder attachment. 3,577,688, Cl. 51-241.
- Brennan, James, Jr., to Texas Instruments, Incorporated. Temperature compensated electronic display. 3,577,137, Cl. 340-324.
- Brickner, David R.; and Swift, Billy K., to Sperry Rand Corporation. Analog/digital differential apparatus for comparing resolver output data with a digital signal. 3,576,986, Cl. 235-189.
- Bridges, Richard J.: See—
Drenning, John W.; and Bridges, Richard J., 3,577,708.
- Bridges, William B.; and Clark, Peter O., to Hughes Aircraft Company. Transverse discharge gas laser. 3,577,096, Cl. 331-94.5
- Brigham, Harlow R.: See—
Graham, Charles L.; and Brigham, Harlow R., 3,577,334.
- Brightman, Barrie, to Stromberg-Carlson Corporation. Telephone hybrid arrangement with frequency separation for use with TDM systems. 3,577,202, Cl. 179-15.
- Brightside Foundry & Engineering Company Limited: See—
Franke, Rolf, 3,577,760.
- Briglia, Donald D.: See—
Helliwell, Bradley A.; and Briglia, Donald D., 3,577,165.
- Brinkman, Charles L. Positioning device with automatic return stroke. 3,577,831, Cl. 92-66.
- British Lighting Industries Limited: See—
Scott, Kenneth; and Ramsey, Dennis A., 3,577,616.
- British Railways Board: See—
Tustin, Arnold, 3,576,957.
- Brock, James D., to CMI Corporation, mesne. Bituminous mixing method and apparatus. 3,577,648, Cl. 34-9.
- Brosk, Jeffrey Owen. Writing implement holder for books or like articles. 3,577,604, Cl. 24-81.
- Brown, Augustus B., to International Business Machines Corporation. Fabrication of ultra-thin wall bobbins. 3,577,506, Cl. 264-272.
- Brown, Clyde O.: See—
Tomlinson, Richard G.; Brown, Clyde O.; and Haight, Alan F., 3,577,094.
- Brown, Donald S.: See—
Kremer, Charles J.; Brown, Donald S.; Apikos, Dominic; and Thean, John T., 3,577,373.
- Brown, James Murrell. Torque limiting clutch. 3,577,747, Cl. 64-29.
- Brown, Mark: See—
Parks, Paul B.; and Brown, Mark, 3,576,994.
- Brown, Patrick M.; and Duecker, Heyman C., to Grace, W. R., & Co. Method for the production of hydrogen cyanide wherein platinized mullite serves as a catalyst. 3,577,218, Cl. 23-151.
- Brown, Thomas J., Jr., to Cummins Engine Company, Inc. Fuel pump testing method and apparatus. 3,577,776, Cl. 73-119.
- Brownstein, Arthur M.; and Sibilla, John P., to Allied Chemical Corporation. Process for the preparation of isocyanates. 3,577,458, Cl. 260-545.
- Bruce, William F., to American Home Products Corporation. N-arylalkyl- β -hydroxy- β -phenyl-ethylamines and the salts thereof. 3,577,462, Cl. 260-570.6
- Bruchez, Raymond J., Jr., to United Aircraft Corporation. Engine ignition system. 3,577,731, Cl. 60-39.82
- Bruck, Hans-Erwin. Method and apparatus for making fertilizer. 3,577,229, Cl. 71-9.
- Bruetsch, Harold Louis, to AMP Incorporated. Electrical connector. 3,577,117, Cl. 339-248.
- Brugger, Wilhelm, to Goldschmidt, Th., A.G. Process of producing zirconium silicate ceramic coloring substances. 3,577,252, Cl. 106-299.
- Brun, Henri: See—
Malnar, Leon; and Brun, Henri, 3,577,069.
- Buck, Erville C., to Willamette Valley Company. Tape applying apparatus. 3,577,303, Cl. 156-522.
- Buck, Gert: See—
Hornbogen, Erhard; Niessner, Erwin; and Buck, Gert, 3,577,762.
- Buck K.G.: See—
Hornbogen, Erhard; Niessner, Erwin; and Buck, Gert, 3,577,762.
- Buess, Charles Merlyn: See—
Flickinger, Earl Dan; and Buess, Charles Merlyn, 3,577,431.
- Buettner, George S.: See—
Stone, John G.; Buettner, George S.; and Alm, Christian A., 3,576,940.
- Bullard, Calvin P.; and Szubelick, Francis P., 1/3 to Gaston, Vigeant. Two-phase mold press. 3,577,596, Cl. 18-30.
- Bullard, E. D., Company: See—
Raschke, Herbert A., 3,577,563.
- Bunker-Ramo Corporation, The: See—
Foerster, Roy P., 3,577,139.
- Gregg, Roland S., Jr., 3,576,984.
- Bunt, Edgar A.: See—
Cusick, Richard T.; and Bunt, Edgar A., 3,577,030.
- Bunyan, Thomas Walter, to P & O Pilgrim Valve Limited. Mounting of propellers, impellers, wheels and the like in torque and thrust transmitting connection on shafts. 3,577,628, Cl. 29-471.1
- Burdet, Roger: See—
Corbex, Louis; and Burdet, Roger, 3,577,685.
- Burleson, Hulbert M. Water-tight plug for tubular pile wells. 3,577,737, Cl. 61-46.5
- Burrage, Lawrence M.: See—
McStrack, Darrel D.; and Burrage, Lawrence M., 3,577,032.
- Burroughs Wellcome Co.: See—
Barrett, Paul Anthony, 3,577,421.
- Burton, Robert Edward, to Microphor, Inc. Combined waste treatment and growth chamber process. 3,577,678, Cl. 47-58.
- Bylander, Ernest G.; and Jarman, Hall, E., to Texas Instruments, Incorporated. Process for fabricating infrared detector arrays and resulting article of manufacture. 3,577,631, Cl. 29-572.
- Bynagte, Peter W., to Westgate-California Foods, Inc. Process of extracting meat from crabtails. 3,577,243, Cl. 99-111.
- Cabot Corporation: See—
Whitfield, Marshall G.; Parzuchowski, Richard S.; and Moore, Dennis B., 3,577,268.
- Caldor, Thomas, to Societe Sediver, Societe Europeenne d'Isolateurs en Verre. Electric insulators with spigoting elements. 3,576,942, Cl. 174-210.
- Cale, Albert Duncan, Jr., to Robins, A.H., Company, Incorporated. 1-Substituted-3-substituted phenoxypropylidines. 3,577,415, Cl. 260-247.2
- California Computer Products, Inc.: See—
Doyle, Harold W., 3,576,980.
- Caligiuri, John J.: See—
Tripoli, Joseph V.; and Caligiuri, John J., 3,577,642.
- Calmes, Albert H. Process and apparatus for rolling seamless tubes. 3,577,754, Cl. 72-45.
- Camdale Enterprises: See—
Silvagi, Joseph; and Conforti, John W., 3,577,683.
- Campbell, George W., Jr.: See—
McGill, Charles K.; and Campbell, George W., Jr., 3,577,426.
- Campbell, Richard H., Jr., to Pneumo Dynamics Corporation. Solenoid control circuit. 3,577,040, Cl. 317-148.5
- Canada Packers Limited: See—
Koh, Teow Yan; and Bharucha, Kekhusroo Rustomji, 3,577,534.
- Cannalte, Gary A., to Motorola, Inc. Remote control system for operation over same audio channel providing voice signals between remote station and base station. 3,577,080, Cl. 325-183.
- Cantrall, Margot Louise; Sassiver, Martin Leon; and Shepherd, Robert Gordon, to American Cyanamid Company. 2,4,6-Trisubstituted-s-triazines. 3,577,417, Cl. 260-249.6
- Capotosto, Frank A.; and Klint, Robert V., to General Electric Company. Electrical insulator with polymer-containing joint between the porcelain and the hardware. 3,576,938, Cl. 174-196.
- Carevic, Frank E.; and Fairbanks, Theodore H., to FMC Corporation. Method of reticulating nylon materials. 3,577,359, Cl. 260-2.5
- Carlson, Elmer Victor; Cross, Floyd Warren; and Killion, Mead Clifford, to Industrial Research Products, Inc. Acceleration insensitive transducer. 3,577,020, Cl. 310-8.2
- Carpino, Ugo, to Pio Guardigli. Color printing apparatus for potentiometric recording instruments. 3,577,149, Cl. 346-46.
- Carrier Corporation: See—
Shaw, David N., 3,577,741.
- Caruso, Paul J.: See—
Aldrich, Ralph E.; and Caruso, Paul J., 3,577,200.
- Cashman, Robert W., to Saginaw Machine and Tool Company. Tool holder construction. 3,577,618, Cl. 29-96.
- Castleberry, Daniel E.: See—
Tyrrell, Leo A.; Castleberry, Daniel E.; and Weber, Charles A., 3,577,006.
- Castro, Anthony J.; Marsh, Frederick S.; Kinney, Layton E.; and Fischl, Frank J., to Armour Industrial Chemical Company. Modifier for phenolic resins. 3,577,370, Cl. 260-19.
- Caterpillar Tractor Company: See—
Wagner, Harold H., 3,577,726.

- Catron, William M. Method of making one-piece multifocal lens blanks. 3,577,690, Cl. 51-284.
- Celanese Corporation: See—
Melaas, Bruce Allen, 3,577,438.
- Myles, William J.; and Kunkel, Roland K., 3,577,213.
- Centenary Central, Inc.: See—
Sauer, Louis E.; and Sauer, Robert W., 3,577,822.
- Cerro Corporation: See—
Stone, John G.; Buettner, George S.; and Alm, Christian A., 3,576,940.
- Tandler, Paul; and Blackwell, Ellis R., 3,577,759.
- Champayne, Roy J. Rubbing machine with thrust transmitting members. 3,577,687, Cl. 51-170.
- Chandler, Earl. Cutting tool attachment for a power hammer. 3,577,638, Cl. 30-277.
- Champayne, Roy J. Rubbing machine with thrust transmitting members. 3,577,687, Cl. 51-170.
- Chandler, Earl. Cutting tool attachment for a power hammer. 3,577,638, Cl. 30-277.
- Chandler Evans, Inc.: See—
Bennett, John A., 3,577,795.
- Bock, Herbert G.; and Szerejko, Walter J., 3,577,696.
- Chemical Construction Corporation: See—
Shah, Indravadan S., 3,577,219.
- Chemische Werke Munchen Otto Barlocher GmbH: See—
Rosenthal, Christian, 3,577,489.
- Cheroff, George, to International Business Machines Corporation. Field effect device. 3,577,047, Cl. 317-235.
- Cherry, James R., to Motorola, Inc. Quick heat and electrical power producing system. 3,576,970, Cl. 219-279.
- Cheshire Manufacturing Co., Inc.: See—
Whitright, Joseph W. E., 3,577,115.
- Chesley, Gilman D.: See—
Rice, Rex; Chesley, Gilman D.; and Smith, William R., 3,577,130.
- Chevron Research Company: See—
Csicsery, Sigmund M., 3,577,475.
- Fenyess, Joseph G. E., 3,577,545.
- Jacobson, Robert L., 3,577,474.
- Smith, Calvin S.; and McLeod, William J., 3,577,221.
- White, Robert J., 3,577,353.
- Chicago Dryer Company: See—
Kamberg, Eduard F., 3,577,665.
- Chiffert, Pierre: See—
Pelissier, Jean-Paul; and Chiffert, Pierre, 3,577,547.
- Chisholm, Douglas S., to Dow Chemical Company, The. Extrusion apparatus. 3,577,588, Cl. 18-12.
- Chisholm, Douglas S.; and Rieke, James K., to Dow Chemical Company, The. Method for the preparation of extrudable synthetic resinous materials. 3,577,494, Cl. 264-143.
- Christensen, Alton O., to Shell Oil Company. Transistor inverter circuit. 3,577,005, Cl. 307-205.
- Christiani & Nielsen A/S: See—
Havno, Kaj, 3,577,738.
- Ciampa, Fred A.; Serafini, Angelo; and Mazzarella, Louis, to Standard Box Spring Co. Spring assembly for furniture and method of manufacture. 3,577,574, Cl. 5-267.
- Ciba Limited: See—
Liechti, Peter; Guglielmetti, Leonardo; Maeder, Erwin; and Siegrist, Adolf Emil, 3,577,411.
- Rohr, Otto; and Hitz, Hans Rudolf, 3,577,453.
- Cichner Organisation G.m.b.H.: See—
Hecker, Klaus Jorg, 3,577,129.
- Cincinnati Milacron Inc.: See—
Fisher, Robert C., 3,577,686.
- Cities Service Company: See—
Petke, Frederick E., 3,577,254.
- Petke, Frederick E., 3,577,255.
- Cities Service Oil Company: See—
Rai, Charanjit; Collins, Sherman D.; and Badin, Elmer J., 3,577,228.
- Claesson, Harry: See—
Bergman, Carl; and Claesson, Harry, 3,577,635.
- Clampitt, Bert H., to Gulf Research & Development Company. Stable aqueous dispersions of ethylene polymers produced by contacting the dispersions with an acidic sulfonated cation exchange resin charged with ammonium ions. 3,577,375, Cl. 260-29.6
- Clampitt, Bert H.: See—
Kochhar, Rajindar K.; Clampitt, Bert H.; and Gilbert, Ronald E., 3,577,392.
- Clark, Howard S.: See—
Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,577,572.
- Clark, Peter O.: See—
Bridges, William B.; and Clark, Peter O., 3,577,096.
- Clecak, Nicholas J.; and Cox, Robert J., to International Business Machines Corporation. Substituted anthraquinones. 3,577,444, Cl. 260-378.
- Clements, Thomas C.: See—
Taylor, James R.; and Clements, Thomas C., 3,577,123.
- Clementson, John Joseph, to Imperial Chemical Industries Limited. Trichlorotrifluoroethane water emulsion system. 3,577,348, Cl. 252-153.
- Clevite Corporation: See—
Sand, Edward C., 3,576,954.
- Clift, Charles E., to Sperry Rand Corporation. Servoed meter apparatus. 3,577,195, Cl. 343-108.
- CMI Corporation: See—
Brock, James D., 3,577,648.
- Coburn, Raymond W., Jr.: See—
Lobb, Edward Vernon; and Coburn, Raymond W., Jr., 3,577,576.
- Cochran, David S., to Hewlett-Packard Company. Digital calculator system for computing square roots. 3,576,983, Cl. 235-158.
- Cocke, John; Dauber, Philip S.; Schorr, Herbert; and Sussenguth, Edward H., to International Business Machines Corporation. Apparatus in a digital computer for allowing the skipping of predetermined instructions in a sequence of instructions, in response to the occurrence of certain conditions. 3,577,190, Cl. 340-172.5
- Cocke, John; Randell, Brian; Schorr, Herbert; and Sussenguth, Edward H., to International Business Machines Corporation. Apparatus and method in a digital computer for allowing improved program branching with branch anticipation reduction of the number of branches, and reduction of branch delays. 3,577,189, Cl. 340-172.5
- Cohen, Merrill: See—
Sandler, Melvin H.; and Cohen, Merrill, 3,577,379.
- Cohen, Richard L., to Bendix Corporation, The. Self-synchronous motor control including an A.C. transmitter, a D.C. receiver, and a unique amplifier-demodulator. 3,577,058, Cl. 318-691.
- Colgate-Palmolive Company: See—
Suh, John T.; and Skorz, Joseph A., 3,577,428.
- Suh, John T., 3,577,436.
- Colgil Enterprises, Inc.: See—
Lobb, Edward Vernon; and Coburn, Raymond W., Jr., 3,577,576.
- Colglazier, Donald F., to International Business Machines Corporation. Flat power-distribution cable. 3,576,941, Cl. 174-117.
- Collie, Robert L. Electrode heating system. 3,576,968, Cl. 219-284.
- Collins, Jack T., to Automation Industries, Inc. Microwave material tester employing a tunable source of energy and a tunable reference cavity. 3,577,071, Cl. 324-58.5
- Collins Radio Company: See—
Holzschuh, Donald L.; and Wicker, Betty M., 3,577,148.
- Kubicz, Arthur P., 3,577,092.
- Tyrrell, Leo A.; Castleberry, Daniel E.; and Weber, Charles A., 3,577,006.
- Collins, Sherman D.: See—
Rai, Charanjit; Collins, Sherman D.; and Badin, Elmer J., 3,577,228.
- Collyer, Robert C.: See—
Seckerson, Clifford Alexander; and Collyer, Robert C., 3,577,603.
- Compudyne Corporation: See—
Kreithen, Marvin L.; and Lawler, John J., 3,577,176.
- Conductron Corporation: See—
Vanden Broek, Jan Abraham, 3,577,791.
- Conforti, John W.: See—
Silvagi, Joseph; and Conforti, John W., 3,577,683.
- Conrad, Daniel T.: See—
Taylor, Charles W., Jr.; and Conrad, Daniel T., 3,577,274.
- Constable, James M., to Del Electronics Corporation. Power transistor protection circuit. 3,577,035, Cl. 317-31.
- Continental Can Company, Inc.: See—
Goldstein, Irving S.; and Benigni, Joseph D., 3,577,467.
- Ritterhoff, Eric K., 3,577,293.
- Rueckberg, Herbert S., 3,577,698.
- Contois, Lawrence E., to Eastman Kodak Company. Electrophotographic composition and element. 3,577,235, Cl. 96-1.6
- Contraves AG: See—
Gachwiler, Hermann; and Schoen, Kurt, 3,577,162.
- Control Data Corporation: See—
Cray, Seymour R., 3,577,073.
- Conversion Chemical Corporation: See—
Joachim, Tibor; and Beckwith, Merton M., 3,577,327.
- Rynne, George B.; and Beckwith, Merton M., 3,577,328.
- Conwed Corporation: See—
Videen, Otis R.; and Wiegand, Donald E., 3,577,312.
- Cook, Charles R., Jr., to Texas Instruments, Incorporated. Semiconductor devices. 3,577,038, Cl. 317-101.
- Cook, Richard L.: See—
Baker, Ronald E.; Cook, Richard L.; and Slagel, Edwin C., 3,577,306.
- Cook, Robert C., to United Aircraft Corporation. MOSFET with improved voltage breakdown characteristics. 3,577,043, Cl. 317-235.
- Cooper, Murray Sam: See—
Nielsen, Peter Adams; Cooper, Murray Sam; and Doyno, Ernest Robert, 3,577,319.
- Corbett, Herbert O., to National Distillers and Chemical Corporation. Tufting process for foamed plastic structures. 3,577,507, Cl. 264-321.
- Corbex, Louis; and Burdet, Roger, to Societe Nouvelle de Roulements. Grinding machine with a feed control device. 3,577,685, Cl. 51-165.
- Cornell Research Foundation, Inc.: See—
Baker, James A., 3,577,525.
- Couch, Stuart L.: See—
Porter, Joé A.; and Couch, Stuart L., 3,577,332.
- Cox, Peter Henry, to Miles Laboratories, Incorporated. Tableting. 3,577,491, Cl. 264-120.
- Cox, Robert J.: See—
Clecak, Nicholas J.; and Cox, Robert J., 3,577,444.
- Craft, Jack, to RCA Corporation. Automatic frequency control apparatus. 3,577,008, Cl. 307-233.

- Cragoe, Edward J., Jr., to Merck & Co., Inc. 2-RCH NH-4-X-5-sulfamyl benzoic acids. 3,577,409, Cl. 260-239.6
- Cragoe, Edward J., Jr.; and Shepard, Kenneth L., to Merck & Co., Inc. Pyrazinamide derivatives and processes for their preparation. 3,577,418, Cl. 260-250.
- Cramer, James E. Two-pass weld bead finishing process for pipe and tubing. 3,577,756, Cl. 72-193.
- Cramer, Leslie Dick; and Moore, John R. Lug wrench support. 3,577,818, Cl. 81-180.
- Crawford, Thomas C. Phthalocyanine dye and method for making same. 3,577,429, Cl. 260-314.5
- Crawford, William N.: See—
Ratcliffe, Edward; and Crawford, William N., 3,577,644.
- Cray, Seymour R., to Control Data Corporation. Apparatus for automated computer maintenance comprising means for varying the input signal switching threshold voltage for any of a plurality of electronic circuits. 3,577,073, Cl. 324-73.
- Criscimagna, Tony N.; and Fournier, Robert J., to International Business Machines Corporation. Synchronizing clock system. 3,577,128, Cl. 340-172.5
- Cronin, Timothy H.: See—
Hess, Hans-Jürgen E.; and Cronin, Timothy H., 3,577,420.
- Cross, Anthony L., to Bell & Howell Company. Constant amplitude variable frequency sweep generator. 3,577,007, Cl. 307-228.
- Cross, Floyd Warren: See—
Carlson, Elmer Victor; Cross, Floyd Warren; and Killion, Mead Clifford, 3,577,020.
- CSF-Compagnie Generale de Telegraphie Sans Fil: See—
Girault, Pierre, 3,577,144.
- Malnar, Leon; and Brun, Henri, 3,577,069.
- Csicsery, Sigmund M., to Chevron Research Company. Isomerization of C₈ alkyl aromatics. 3,577,475, Cl. 260-668.
- C.T. Supply Co.: See—
Shaw, Stanley B.; Gehl, Ronald H.; and Roemer, Gordon R., 3,577,770.
- Cummins, Donald L., to General Motors Corporation. Electric cranking motor automatic disconnect and lockout circuit. 3,577,001, Cl. 290-38.
- Cummins Engine Company, Inc.: See—
Brown, Thomas J., Jr., 3,577,776.
- Cupp, Leander Ernest: See—
Knapp, Burton Bower; and Cupp, Leander Ernest, 3,577,330.
- Curtis, John J.; and Ruoff, Carl E., to International Business Machines Corporation. Method and means for interconnecting conductors on different metalization pattern levels on monolithically fabricated integrated circuit chips by alloying an interconnection portion of each conductor to contiguous portions of one low resistivity region of the chip. 3,577,036, Cl. 317-101.
- Cusick, Richard T.; and Bunt, Edgar A., to United States of America, Navy, mesne. Inductive energizing circuit for arc plasma generator. 3,577,030, Cl. 315-111.
- Dahl, Einar S., to Outboard Marine Corporation. Rear roller guard for rotary mowers. 3,577,714, Cl. 56-25.4
- Dahle, Orvar: See—
Bengtson, Waldemar; and Dahle, Orvar, 3,577,108.
- Dart Industries Inc.: See—
O'Brien, William J.; and Downey, Raymond E., 3,577,269.
- Schrage, Albert; and Schoenberg, Jules Ernest, 3,577,393.
- Da Silva, Herman: See—
Van Duuren, Hendrik Cornelis Anthony; and Da Silva, Herman, 3,576,952.
- Dauber, Philip S.: See—
Cocke, John; Dauber, Philip S.; Schorr, Herbert; and Sussenguth, Edward H., 3,577,190.
- Daumas, Jean Claude: See—
Boutry, Pierre; Daumas, Jean Claude; and Montarnal, Roger, 3,577,477.
- David, Constant. Method for making 3-D filament reinforced articles. 3,577,294, Cl. 156-173.
- Davies, Gail F., to United States of America, Navy. Tungsten materials and a method for providing such materials. 3,577,227, Cl. 29-182.
- Davis, Allen V. C. Mechanical motion transmitter. 3,577,793, Cl. 74-100.
- Davis, John R.: See—
Bliven, Roger; Allen, Frank L., Jr.; and Davis, John R., 3,577,271.
- Davis, William H.: See—
Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
- Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
- Dawson, Victor C. D.; and Seigel, Arnold E., to United States of America, Navy. High pressure chamber. 3,577,590, Cl. 18-16.5
- Deane, Donald Raymond: See—
Hurn, James; King, Charles Richard Forbes; and Deane, Donald Raymond, 3,577,829.
- DeBernardo, Luigi U., to United States of America, Agriculture. Apparatus for removing entrained particles from gases. 3,577,711, Cl. 55-399.
- Deffner, John F., to Gulf Research & Development Company. Bis (cyclopentadienyl) compounds of vanadium. 3,577,448, Cl. 260-429.
- De Gain, William J., to Koppy Tool Corporation. Stretch method for making a tubular product. 3,577,621, Cl. 29-155.
- De Glauco, Scilla; and Poccia, Claudio. Method of making a building panel. 3,577,298, Cl. 156-239.
- De Haas, Jacobus, to Shell Oil Company. Motion conversion system. 3,577,732, Cl. 60-52.
- Del Electronics Corporation: See—
Constable, James M., 3,577,035.
- Delta Diggers, Inc.: See—
Sing, T. J.; and Sing, Reuben C., 3,577,664.
- Delyon, Armand Rene; and Kensing, Lex Donald, to AMP Incorporated. Electrical connectors on a carrier strip. 3,577,119, Cl. 339-276.
- Demag AG: See—
Bippus, Walter; and Ackermann, Horst, 3,577,700.
- Deming, Philip L.: See—
Bertoglio, Joseph; Deming, Philip L.; Eckert, Joyce G.; and Shafer, James R., 3,577,765.
- Dench, Edward C., to Raytheon Company. Self-quenching electrode for crossed field traveling wave devices. 3,577,172, Cl. 315-39.3
- Derrough, Edward R., to Bendix Corporation. The Apparatus for electrochemical removal of material from an article. 3,577,333, Cl. 204-212.
- Desaulniers, Charles W., to Grace, W. R., & Co. Coating laminating process. 3,577,508, Cl. 264-331.
- De Staat Der Nederlanden, Ten Deze Vertegenwoordigd Door de Directeur-Generaal Der Posterijen, Telegrafie en Telefonie: See—
Van Duuren, Hendrik Cornelis Anthony; and Da Silva, Herman, 3,576,952.
- Detorre, Robert P., to PPG Industries, Inc. Resilient cutter. 3,577,636, Cl. 30-164.95
- Deutsch, Marshall E.; Mead, Louis W.; and Nagy, Zoltan, to NEN-Picker Radiopharmaceuticals, Inc., mesne. Self contained, closed system and method for generating and collecting a short lived daughter radionuclide from a long lived parent radionuclide. 3,576,998, Cl. 250-106.
- Deutsche Gold-und Silber-Scheideanstalt vormals Roessler: See—
Schwarze, Werner; Giesselmann, Gunter; and Weigert, Wolfgang, 3,577,416.
- De Wit, Frans Corneel Leo; and Adelaar, Hans Helmut, to International Standard Electric Corporation. Multi-stage switching network employing cascaded three-terminal crosspoints. 3,576,949, Cl. 179-18.
- Deyo, Charles R.: See—
Plumly, George W.; Hunnicutt, Jack B.; and Deyo, Charles R., 3,577,657.
- Diassi, Patrick A., to Squibb, E. R., & Sons, Inc. Synthesis of steroids. 3,577,463, Cl. 260-586.
- Dill, Hans G., to Hughes Aircraft Company. Solid-state storage device. 3,577,210, Cl. 317-235.
- Di Pietro, Americo R.; and Thun, Rudolf E., to International Business Machines Corporation. Diffused electrical connector apparatus and method of making same. 3,577,037, Cl. 317-101.
- Dixon, Brook: See—
Quatse, Jesse T.; and Dixon, Brook, 3,577,201.
- Doan, Robert B.; and Taylor, Robert C., to Atlantic Richfield Company. Low molecular weight linear alkyl benzene sulfonate as frothing agents for gypsum board manufacture. 3,577,248, Cl. 106-111.
- Dodds, Robert E., to Sylvania Electric Products, Inc. Method for the recovery of rare earth oxides. 3,577,351, Cl. 252-301.4
- Dolan, Clarence F., to General Electric Company. Self contained lubrication system for high speed drive shaft coupling. 3,577,746, Cl. 64-23.
- Dominion Electric Corporation: See—
Arntz, Robert L.; and Marker, John R., Jr., 3,577,110.
- Dorbransky, Robert Alan, to American Cyanamid Company. Paste rosin size containing viscosity depressant. 3,577,402, Cl. 260-97.
- Dorpinghaus, Kurt, Firma: See—
Gottfried, Franz, 3,577,609.
- Dorsey, John J.: See—
Wallis, George; and Dorsey, John J., 3,577,629.
- Douglas, Colin Grahame: See—
Horstmann, Kenneth John; and Douglas, Colin Grahame, 3,577,079.
- Douglas Dynamics Corporation: See—
Jones, Edwin L., 3,577,800.
- Douglas, George H.: See—
Teller, Daniel M.; Douglas, George H.; and Smith, Herchel, 3,577,410.
- Doviak, Peter L.: See—
Kalwaites, Frank; and Doviak, Peter L., 3,577,586.
- Dow Chemical Company, The: See—
Chisholm, Douglas S.; and Rieke, James K., 3,577,494.
- Chisholm, Douglas S., 3,577,588.
- Horsley, Lee H., 3,577,559.
- Kenaga, Eugene E., 3,577,548.
- Lawrence, Garth D.; and Ott, Jack J., 3,577,560.
- Longoria, Juan, III, 3,577,556.
- Moyle, Clarence L., 3,577,550.
- Parrish, Donald B.; and McDuff, James M., 3,577,554.

- Downey, Raymond E.: See—
O'Brien, William J.; and Downey, Raymond E., 3,577,269.
- Doyle, Harold W., to California Computer Products, Inc. Automatic corner recognition system. 3,576,980, Cl. 235-152.
- Doyno, Ernest Robert: See—
Nielsen, Peter Adams; Cooper, Murray Sam; and Doyno, Ernest Robert, 3,577,319.
- Draper, Wilburn D., to International Business Machines Corporation. Binary register. 3,576,973, Cl. 235-92.
- Draudt, Donald A.; and Draudt, Herbert T. Support for injection molding machine. 3,577,597, Cl. 18-30.
- Draudt, Herbert T.: See—
Draudt, Donald A.; and Draudt, Herbert T., 3,577,597.
- Drenning, John W.; and Bridges, Richard J., to Koppers Company, Inc. Spark interval responsive precipitator voltage control. 3,577,708, Cl. 55-105.
- Duecker, Heyman C.: See—
Brown, Patrick M.; and Duecker, Heyman C., 3,577,218.
- Duffy, Michael C.: See—
Armstrong, William J.; Healy, Albert M.; and Duffy, Michael C., 3,577,044.
- Duke, Jimmy R.; and Miller, Walter E., Jr., to United States of America, Army. Rectangular pulse modulator. 3,577,017, Cl. 307-284.
- Duke, Keith A., to International Business Machines Corporation. Error tolerant read-only storage system. 3,576,982, Cl. 235-153.
- Dummermuth, Ernst H., to Allen-Bradley Company, mesne. Circuit for controlling frequency with voltage. 3,577,012, Cl. 307-271.
- Du Pont de Nemours, E. I., and Company: See—
Kirkland, Joseph J., 3,577,266.
- Price, Samuel T., 3,577,614.
- Duriron Company, Inc., The: See—
Bowen, John C.; and Fischer, Howard G., II, 3,577,112.
- DuroDont, Dr. Scheller, Firma: See—
Scheller, Karlheinz; Koddermann, Else; and Trebs, Hans, 3,577,521.
- Duve, John P.; and Beck, Douglas E. Electric tooth-brush. 3,577,579, Cl. 15-22.
- Dvonch, William: See—
Alburn, Harvey E.; Dvonch, William; and Sallay, Stephan, 3,577,408.
- Dybalski, Jack N., to Armour Industrial Chemical Company. Bituminous dispersions having improved adhesion and process thereof. 3,577,249, Cl. 106-209.
- Dyer, George A.; and Kohler, Emil, to North American Rockwell Corporation. System for controlling the speed of a motor utilizing pulse width modulation. 3,577,057, Cl. 1.
- Eastman Kodak Company: See—
Amann, Willard R., 3,577,583.
- Contois, Lawrence E., 3,577,235.
- Fix, Delbert D., 3,577,236.
- Folzenlogen, Paul D.; and Hagemeyer, Hugh J., Jr., 3,577,365.
- Graham, Charles L.; and Brigham, Harlow R., 3,577,334.
- Klanderman, Bruce H.; and Faber, Jan W. H., 3,577,366.
- Lindsay, Jacques K., 3,577,238.
- Reithel, Raymond F., 3,577,272.
- Ebeling, William C., to Singer-General Precision, Inc. Apparatus for optically inseting one image into another image. 3,576,945, Cl. 178-68.
- Eckert, Joyce G.: See—
Bertoglio, Joseph; Deming, Philip L.; Eckert, Joyce G.; and Shafer, James R., 3,577,765.
- Eckle, Otto, to Komet Stahlhalter-und Werkzeugfabrik Robert Breuning GmbH, Firma. Boring bar insert. 3,577,810, Cl. 77-58.
- Edge, James, to Welwyn Electric Limited. Electrical resistors. 3,577,276, Cl. 117-213.
- Edman, Walter W.: See—
McDonough, Everett G.; and Edman, Walter W., 3,577,528.
- Edu-Tonics Corporation: See—
Plumly, George W.; Hunnicutt, Jack B.; and Deyo, Charles R., 3,577,657.
- Edwards, Alan C.: See—
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jürgen F.; Edwards, Alan C.; and Tetteroo, Hans, 3,577,413.
- Edwards, Earl A., to United States of America, Navy. Neisseria meningitidis antigen. 3,577,527, Cl. 424-92.
- Eguchi, Hiroaki: See—
Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.
- Ehrhart, Gustav; Schmitt, Karl; Hoffmann, Irmgard; and Ott, Heinrich, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. 4-Phenyl-8-amino tetrahydroisquinolines. 3,577,424, Cl. 260-287.
- Eissfeldt, Werner, to Nirona-Werke, Nier & Elmer KG. Spindle guide. 3,577,796, Cl. 74-459.
- Eklund, Harry Nils, to Lear Siegler, Inc. Method of damping devices having oscillatory motion. 3,577,646, Cl. 33-226.
- Elbert, Raymond J.; and Farrier, Ernest G., to Union Carbide Corporation. Metal bodies of uniform porosity. 3,577,226, Cl. 29-182.
- Eldridge, Raymond W., Jr., to International Telephone & Telegraph Corporation. Underground rigid connector housing seal. 3,576,937, Cl. 174-92.
- Electronit Limited: See—
Venczel, Joseph, 3,577,750.
- Elgin Metal Casket Company: See—
Schubert, Walter A., 3,577,282.
- Elms, Ronald D.: See—
McCall, Amiel J.; Elms, Ronald D.; and Rice, Larry D., 3,576,979.
- Engeler, William E.; and Garfinkel, Marvin, to General Electric Company. High emitter efficiency semiconductor device with low base resistance and by selective diffusion of base impurities. 3,577,045, Cl. 317-235.
- Engineered Data Peripherals Corporation: See—
Garfein, Irwin B.; and Garfein, Allen E., 3,577,133.
- Engle, Wayne C.: See—
Hines, Theodore G.; and Engle, Wayne C., 3,577,305.
- Entschel, Roland; Mueller, Curt; and Steinemann, Willy, to Sandoz, Ltd. Basic pyrazolone monoazo dyes containing an ammonium or hydrazinium group. 3,577,404, Cl. 260-162.
- Erath, Louis W.: See—
McNeel, William O.; and Erath, Louis W., 3,577,184.
- Erby, William A.; and Walde, Robert A., to Air Products and Chemicals, Inc. Use of polychloro keto-alkenoic acids and derivatives thereof as insecticides. 3,577,546, Cl. 424-279.
- Ethyl Corporation: See—
Shepherd, Lawrence H., Jr., 3,577,414.
- Warren, Joel A.; and Marsee, Frederick J., 3,577,727.
- European Atomic Energy Community (Euratom): See—
Oberhofer, Martin; and Jaspert, Jürgen, 3,577,161.
- Evans, Raymond Victor; and Hibbitt, John Edward, to Singer-Cobble Limited. Apparatus for the drying of sheet material. 3,577,652, Cl. 34-155.
- Evans, Theodore A., to Goodyear Tire & Rubber Company, The. Laminated fuel cell container. 3,577,314, Cl. 161-189.
- Everest & Jennings, Inc.: See—
Banks, Roger W., 3,577,054.
- Evill, Brian R.: See—
Thomson, John A.; and Evill, Brian R., 3,577,188.
- Faber, Jan W. H.: See—
Klanderman, Bruce H.; and Faber, Jan W. H., 3,577,366.
- Fairbanks, Theodore H.: See—
Carevic, Frank E.; and Fairbanks, Theodore H., 3,577,359.
- Fairbanks, Theodore H., to FMC Corporation. Apparatus for making reticulated structures. 3,577,587, Cl. 18-12.
- Fairchild, Albert R., to Western Electric Company, Incorporated. Method of reclaiming graphite mask. 3,577,325, Cl. 204-24.
- Fairchild Camera and Instrument Corporation: See—
Rice, Rex; Chesley, Gilman D.; and Smith, William R., 3,577,130.
- Falbe, Jürgen F.: See—
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jürgen F.; Edwards, Alan C.; and Tetteroo, Hans, 3,577,413.
- Falk, Robert A., to Thiokol Chemical Corporation. Synthesis of perfluoroisopropylidenimine. 3,577,460, Cl. 260-566.
- Falter, Ronald C.: See—
Alexander, Robert H.; Falter, Ronald C.; Ringer, Cecil D.; and Linsker, Eugene, 3,577,807.
- Farbenfabriken Bayer Aktiengesellschaft: See—
Kohler, Armin; Von Falkai, Bela; Offermann, Klaus; and Reichle, Alfred, 3,577,500.
- Kuhle, Engelbert; Klauke, Erich; Frohberger, Paul-Ernst; and Scheinplug, Hans, 3,577,451.
- Raab, Hans; and Hageloch, Gunter, 3,577,403.
- Streib, Hugo; and Hechelhammer, Wilhelm, 3,577,378.
- Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning: See—
Ehrhart, Gustav; Schmitt, Karl; Hoffmann, Irmgard; and Ott, Heinrich, 3,577,424.
- Kleiner, Hans-Jerg; and Rehn, Karl, 3,577,456.
- Kotzschmar, Arnold; Metzger, Hermann; Rothe, Richard Reinhard Gustav Adolf; and Seidel, Willy, 3,577,483.
- Farbwerke Hoechst Aktiengesellschaft vormals Meister: See—
Mauz, Otto; and Prinz, Eberhard, 3,577,384.
- Farrier, Ernest G.: See—
Elbert, Raymond J.; and Farrier, Ernest G., 3,577,226.
- Feinberg, Joseph George: See—
Stolar, Morris Emanuel; and Feinberg, Joseph George, 3,577,523.
- Feldman, Elliot I. Air-treatment apparatus. 3,577,710, Cl. 55-316.
- Feldmann, Frederick W.; and Hill, Rodney S., to ILC Industries, Inc. Face shield. 3,577,565, Cl. 2-10.
- Feltzin, Joseph; and Tehrani, Nadji Y., to Atlas Chemical Industries, Inc. Polyurethane elastomers prepared by reacting a mixture of a polyoxyalkylene ether diol of a dihydric phenol and a polyoxal-kylene ether of a polyol with an organic polyisocyanate. 3,577,385, Cl. 260-47.
- Fenyes, Joseph G. E., to Chevron Research Company. N-tetrahaloethylthio pyrazoles as bactericides and fungicides. 3,577,545, Cl. 424-273.
- Ferlauto, Robert J., to Smith Kline & French Laboratories. Compositions and methods for controlling coccidiosis in poultry employing triazole derivatives. 3,577,553, Cl. 424-269.
- Fernseh GmbH: See—
Schneider, Hans-Dieter, 3,576,943.
- Ferrell, Philip J., to Boeing Company, The. Complementary field-effect transistor mixer. 3,577,206, Cl. 307-240.
- Ferroxcube Corporation, Inc.: See—
Fisher, Robert D.; and Magee, James A., 3,577,277.

Fidell, Louis Isadore, to American Cyanamid Company. Fire-resistant finish for textiles comprising zinc fluoroborate. 3,577,342, Cl. 252-8.1

Fields, Roger Q.: See—
Lebourg, Maurice P.; and Fields, Roger Q., 3,577,781.
Whitten, Frank R.; and Fields, Roger Q., 3,577,783.

Firestone Tire & Rubber Company, The: See—
Halasa, Adel F.; and Koch, Russell W., 3,577,397.

Fischer, Artur. Assembly kit. 3,576,936, Cl. 35-19.

Fischer, Howard G., II: See—
Bowen, John C.; and Fischer, Howard G., II, 3,577,112.

Fischer, Raymond C.; and Levenson, Norton J., to United States of America, Navy, mesne. Tow cable termination. 3,577,605, Cl. 24-114.5

Fischl, Frank J.: See—
Castro, Anthony J.; Marsh, Frederick S.; Kinney, Layton E.; and Fischl, Frank J., 3,577,370.

Fisher, Robert C., to Cincinnati Milacron Inc. Mounting for a grinding wheel. 3,577,686, Cl. 51-168.

Fisher, Robert D.; and Magee, James A., to Ferroxcube Corporation, Inc. Polymer coatings. 3,577,277, Cl. 117-234.

Fix, Delbert D., to Eastman Kodak Company. Color diffusion transfer processes and elements comprising auxiliary developers or their precursors. 3,577,236, Cl. 96-3.

Flanagan, Thomas P.; and Kaye, Irving I., to National Starch and Chemical Corporation. Hot melt adhesive compositions. 3,577,372, Cl. 260-23.

Flickinger, Earl Dan; and Buess, Charles Merlyn, to Skelly Oil Company. Sandwich-type chemical compounds and method for their preparations. 3,577,431, Cl. 260-326.1

Fluor Corporation: See—
Longacre, Alan, 3,577,223.

FMC Corporation: See—
Carevic, Frank E.; and Fairbanks, Theodore H., 3,577,359.
Fairbanks, Theodore H., 3,577,587.
Sincavage, Joseph T.; Pepmeier, Carl R.; and Stoffregen, Louis E., 3,577,258.
Stewart, Mary J.; and Price, John A., 3,577,381.

Foerster, Roy P., to Bunker-Ramo Corporation, The. Analog-to-digital converter. 3,577,139, Cl. 340-347.

Folzenlogen, Paul D.; and Hagemeyer, Hugh J., Jr., to Eastman Kodak Company. Novel blends of chlorinated carboxyl group containing polymers and ethylene-vinyl acetate copolymers. 3,577,365, Cl. 260-4.

Fontijn, Wilhelmus J.: See—
Marinus, Korstiaan J. V.; and Fontijn, Wilhelmus J., 3,577,308.

Forbro Design Corporation: See—
Nercessian, Sarkis, 3,577,064.

Ford Motor Company: See—
Nordstrom, John D., 3,577,262.
Nordstrom, John D., 3,577,263.
Nordstrom, John D., 3,577,264.
Nordstrom, John D., 3,577,265.
Schiedel, George M., 3,577,625.
Sebok, Joseph B., 3,577,486.

Forrester, Robert A.; and Mc Nay, Ralph E., to Ashland Oil, Inc. Carbon black in paper coating latex. 3,577,555, Cl. 260-17.4

Foss, Warren M., to National Lead Company. Titanium dioxide pigment composition. 3,577,253, Cl. 106-300.

Foster, Samuel L.; and Johnston, Reed M., said Foster assor. to Allis-Chalmers Manufacturing Company. Magnetic shielding construction for electric transformers. 3,577,109, Cl. 336-84.

Foster Wheeler Corporation: See—
Huybers, Heinz W., 3,577,695.

Fournier, Robert J.: See—
Criscimagna, Tony N.; and Fournier, Robert J., 3,577,128.

Foxboro Company, The: See—
Robinson, Robert J., 3,577,157.

Frank, Rolf, to Brightside Foundry & Engineering Company Limited. Roll forging machine. 3,577,760, Cl. 72-215.

Franklin, George H. Foraminous forming rolls for a papermaking machine produced from synthetic resins. 3,577,315, Cl. 162-210.

Freed, Meier E.: See—
Archibald, John L.; and Freed, Meier E., 3,577,423.

Freeman, Peter Frank Hilary: See—
Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, 3,577,543.

Freier, Michael; and Balazer, Leonard P., to United States of America, Air Force, mesne. Passive monopulse ranging system. 3,577,146, Cl. 343-112.

Freuhauf Corporation: See—
Botkin, Lawrence A., 3,577,739.

Freyling, Edward N., Jr.; and Gregson, Robert E., to Motorola, Inc. Zero point switching circuit for turn-on of gate controlled conducting devices. 3,577,010, Cl. 307-252.

Fricker, Karl, to Swiss Aluminium Ltd. Sleeve for protecting the peg in the head of a carbon anode electrode and apparatus for producing this sleeve. 3,577,755, Cl. 72-51.

Friedel, Robert A.: See—
Kessler, Theodore; Sharkey, Andrew G., Jr.; Malli, Joseph, Jr.; and Friedel, Robert A., 3,577,337.

Frisbie, Jack G., to International Telephone & Telegraph Corporation. Monolithic electronic switching network having variable voltage levels. 3,577,125, Cl. 340-166.

Frizane, Kenneth, to Zenith Radio Corporation. Power supply protection circuit utilizing a silicon controlled rectifier. 3,576,946, Cl. 178-7.3

Frohberger, Paul-Ernst: See—
Kuhle, Engelbert; Klauke, Erich; Frohberger, Paul-Ernst; and Scheinplug, Hans, 3,577,451.

Frushour, James E.; Millham, Ernest H.; and Orloff, James E., to International Business Machines Corporation. Automatic range scale selection apparatus for a measuring device. 3,577,076, Cl. 324-115.

Fuji Shashim Film Kabushiki Kaisha: See—
Nishio, Fumihiko; Ohi, Reiichi; and Tajima, Tatsuya, 3,577,240.

Fujitsu Limited: See—
Kawashima, Masao; Kurita, Syoichi; and Sasaki, Shunroku, 3,577,138.
Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.

Fujiwara, Masahiro: See—
Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.

Fukao, Masami: See—
Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.

Fukatsu, Akihiro: See—
Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatsu, Akihiro, 3,577,033.

Fuks, Robert; and Viehe, Heinz G., to Union Carbide Corporation. Keto-enol nitrogen-containing heterocycles having an amino substituent. 3,577,433, Cl. 260-326.5

Fukuoka, Tatsuo. Footwear. 3,577,662, Cl. 36-11.5

Gaehwiler, Hermann; and Schoen, Kurt, to Contraves AG. Automatic counting system for fluid suspended particle. 3,577,162, Cl. 250-218.

Gallagher, Leonard V.: See—
Margolin, Stanley V.; Glaser, Paul W.; and Gallagher, Leonard V., 3,577,610.

Gallo, Alexander S.: See—
Wadsworth, James I.; Gallo, Alexander S.; Ziegler, George M., Jr.; and Spadaro, James J., 3,577,649.

Galvani, Theodore J.: See—
Re Baratelli, Giuseppe; and Galvani, Theodore J., 3,577,164.

Gambardella, Mario A., to Olin Mathieson Chemical Corporation. Process for controlling the amount of densification in polyurethane foams and products produced thereby. 3,577,519, Cl. 264-54.

Gamer, Nicholas T., to Western Gold & Platinum Company. High temperature brazing alloys. 3,577,233, Cl. 75-134.

Ganter, Wolfgang; and Kunz, Georg, to Gebrüder Junghans G.m.b.H. Sound generator for alarm clocks. 3,577,725, Cl. 58-38.

Garfein, Allen E.: See—
Garfein, Irwin B.; and Garfein, Allen E., 3,577,133.

Garfein, Irwin B.; and Garfein, Allen E., to Engineered Data Peripherals Corporation. Disc memory system including unitary support member and printed circuit board. 3,577,133, Cl. 340-174.1

Garfinkel, Marvin: See—
Engeler, William E.; and Garfinkel, Marvin, 3,577,045.

Gaston, Vigean: See—
Bullard, Calvin P.; and Szubelick, Francis P., 3,577,596.

Gauld, Godfrey R.: See—
Tuten, William J.; and Gauld, Godfrey R., 3,577,168.

Gebrüder Junghans G.m.b.H.: See—
Ganter, Wolfgang; and Kunz, Georg, 3,577,725.

Gehl, Ronald H.: See—
Shaw, Stanley B.; Gehl, Ronald H.; and Roemer, Gordon R., 3,577,770.

Geiersbach, Alois F.: See—
Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., 3,577,050.

Geigy Chemical Corporation: See—
Gurney, John A.; and Hall, Luther A. R., 3,577,476.
Lehmann, Claude; and Renk, Ernst, 3,577,544.
Peterli, Hans Jakob; and Randell, Donald Richard, 3,577,343.

Geisinger, George H.: See—
Mariani, Remo; and Geisinger, George H., 3,577,601.

General Electric Company: See—
Ashley, Eugene; and Tassie, Douglas Pray, 3,577,826.
Beall, Donald L., 3,577,194.
Benson, Ralph A., 3,577,187.
Capotosto, Frank A.; and Klint, Robert V., 3,576,938.
Dolan, Clarence F., 3,577,746.
Engeler, William E.; and Garfinkel, Marvin, 3,577,045.
Hall, James A.; and Peppiatt, Harry J., 3,577,099.
Hewlett, Clarence Wilson, Jr., 3,577,177.
Kelley, Fred W., Jr., 3,577,059.
Kurtz, Donald R., 3,576,960.
Manuel, Eric; and Moore, James H., Jr., 3,577,733.
Mitchell, Michael E., 3,577,186.
Moyson, Joseph, 3,577,046.
Roberts, John Alfred, 3,577,769.
Storm, Herbert F., 3,577,019.

General Engineering Company (Radcliffe) Limited: See—
Bigland, Bernard K., 3,577,488.

General Motors Corporation: See—
Binder, Charles R., 3,577,380.
Blum, Jack F., 3,577,355.
Bogosoff, John P., 3,576,959.
Cummins, Donald L., 3,577,001.
Norwich, John F.; and Roesener, Edward J., Jr., 3,577,287.
Schaefer, Robert H., 3,577,806.
Wing, Douglas J.; and Ramey, William A., 3,577,121.

General Scientific Laboratories, Inc.: See—
Von Brimer, Joe W.; and Roth, Herman P., 3,577,728.

General Telephone & Electronics Laboratories, Incorporated: See—
Amster, Robert L., 3,577,350.

Geo Space Corporation: See—
McNeel, William O.; and Erath, Louis W., 3,577,184.
West, Duval, 3,577,179.

George, Robert W. Faucet-mounted cleaning device for paint rollers. 3,577,280, Cl. 134-138.

Gerks, Irvin F., to Honeywell Inc. Piezoelectric transducer mounting apparatus. 3,577,021, Cl. 310-8.7

Gerst, Carl W.: See—
Worden, Robert A.; Hair, Hugh H.; Gerst, Carl W.; and Viglietta, Benadict, 3,577,145.

Ghosh, Ranajit: See—
Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, 3,577,543.

Giesselmann, Gunter: See—
Schwarze, Werner; Giesselmann, Gunter; and Weigert, Wolfgang, 3,577,416.

Gifford, Phillip H., II. Process for recovery of oil from oil shale simultaneously producing hydrogen. 3,577,338, Cl. 208-11.

Gilbert, Ronald E.: See—
Kochhar, Rajindar K.; Clappitt, Bert H.; and Gilbert, Ronald E., 3,577,392.

Gilmore Industries, Inc.: See—
Krygeris, Algirdas J., 3,577,075.

Gilmore, Thomas P.: See—
Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., 3,577,050.

Gindsberg, Joseph, to Raytheon Company. Sum or select network having short circuiting means connectable to hybrid tee circuit. 3,577,102, Cl. 333-7.

Girault, Pierre, to CSF-Compagnie Generale de Telegraphie Sans Fil. Distance measuring systems. 3,577,144, Cl. 343-14.

Glanzstoff AG: See—
Kersten, Hilde; Siggel, Erhard; and Meyer, Gerhard, 3,577,387.

Glaser, Paul W.: See—
Margolin, Stanley V.; Glaser, Paul W.; and Gallagher, Leonard V., 3,577,610.

Glaze, John W., Jr.; and Worth, Joseph P., to Intech Corporation. Bag folding and sealing apparatus. 3,577,300, Cl. 156-441.5

Gochman, Carl: See—
Bell, Stanley C.; and Gochman, Carl, 3,577,435.

Goggins, William B., Jr., to United States of America, Air Force. Sine-cosine to magnitude-phase angle converter. 3,577,088, Cl. 328-134.

Goldammer, Georg; and Maht, Gunther, to Schubert & Salzer Maschinenfabrik Aktiengesellschaft. Apparatus for mixing fibrous components. 3,577,599, Cl. 19-145.5

Goldie, Harry, to United States of America, Air Force, mesne. Chlorine-oxygen transmit-receive stage to operate at short pulse widths, low pulse repetition frequencies, and wide duty cycles. 3,577,028, Cl. 313-223.

Goldschmidt, Th., A.G.: See—
Brugger, Wilhelm, 3,577,252.

Goldstein, Irving S.; and Benigni, Joseph D., to Continental Can Company, Inc. Process for the hydrolysis of lignin. 3,577,467, Cl. 260-627.

Goo Chemical Industry Co., Ltd.: See—
Kubota, Ikuo; Mikami, Masakatsu; and Kitamura, Seikichi, 3,577,517.

Goodyear Aerospace Corporation: See—
Baker, Ronald E.; Cook, Richard L.; and Slagel, Edwin C., 3,577,306.

Goodyear Tire & Rubber Company, The: See—
Evans, Theodore A., 3,577,314.
Judy, William Allen, 3,577,400.
Keck, Max H., 3,577,454.
Klar, Kenneth K., 3,577,261.
Kraft, Louis Seelbach; and Quiner, Charles W., 3,577,295.
Kuhar, George A., 3,577,389.
Smith, Edwin Studley, 3,577,401.
Taylor, Charles W., Jr.; and Conrad, Daniel T., 3,577,274.
Wilson, Warren K., 3,577,211.
York, Monte H., 3,577,501.

Goodyear Tire and Rubber Company, The: See—
Lal, Joginder; and Throckmorton, Morford C., 3,577,395.
Pace, Henry A.; and Anhorn, Victor J., 3,577,398.
Throckmorton, Morford C., 3,577,396.

Gorman, Marvin; and Hamill, Robert L., to Lilly, Eli, and Company. Dianemycin for treating coccidiosis. 3,577,531, Cl. 424-122.

Gorog, Etienne, to International Business Machines Corporation. Data transmission time domain equalizer. 3,577,089, Cl. 328-165.

Gottfried, Franz, to Dorpinghaus, Kurt, Firma. Hook and eye type fastener. 3,577,609, Cl. 24-228.

Gould, Francis E.; and Shepherd, Thomas H., to National Patent Development Corporation. Preparation of spray on bandage. 3,577,516, Cl. 424-46.

Gould, Francis E.: See—
Shepherd, Thomas H.; and Gould, Francis E., 3,577,512.
Shepherd, Thomas H.; and Gould, Francis E., 3,577,518.

Grace, W. R., & Co.: See—
Brown, Patrick M.; and Duecker, Heyman C., 3,577,218.
Desaulniers, Charles W., 3,577,508.
Sanchez, Moises Gali; Levy, Newton, Jr.; and Rettew, Richard R., 3,577,487.

Graham, Charles L.; and Brigham, Harlow R., to Eastman Kodak Company. Apparatus for electrolytic recovery of a metal from a solution. 3,577,334, Cl. 204-223.

Graham, John S., to United States of America, Agriculture. Apparatus for rapid automated measurement of drafting force and drafting force variability. 3,577,600, Cl. 19-293.

Green, Louis E.: See—
Lightner, Gene E.; Muhlestein, Howard Blair; and Green, Louis E., 3,577,279.

Greene, Max E., to Phillips Petroleum Company. Method of fibrillating and twisting oriented film. 3,577,724, Cl. 57-157.

Gregg, Roland S., Jr., to Bunker-Ramo Corporation, The. Multi-function logic network. 3,576,984, Cl. 235-176.

Gregson, Robert E.: See—
Freyling, Edward N., Jr.; and Gregson, Robert E., 3,577,010.

Gri, Norman I.; and Yon, Eugene T., to Avco Corporation. Indium antimonide infrared detector contact. 3,577,175, Cl. 317-237.

Grimes, Warren R.: See—
Shaffer, James H.; Moulton, David M.; and Grimes, Warren R., 3,577,225.

Griot, Rudolf G., to Sandoz-Wander, Inc. 2,6-Disubstituted-4-(w-aminoalkoxy)phenyl pyrimidines. 3,577,419, Cl. 260-256.4

Groetzner, Kurt: See—
Widl, Gerhard; Groetzner, Kurt; and Knodler, Adolf, 3,577,107.

Grunling, Hermann Walter, to Siemens Aktiengesellschaft. Electrical temperature sensor. 3,577,183, Cl. 338-26.

Guettier, Michel, to Regie Nationale des Usines Renault, and Automobiles Peugeot. Hand brake control mechanisms. 3,577,798, Cl. 74-503.

Guevrekian, Lawrence Norayr, to Hoffmann-La Roche Inc. Transducer cleaning device. 3,577,785, Cl. 73-398.

Gugger, Gottfried, to Laser Technique SA. Method and device for boring workpieces, particularly watch jewels by means of laser pulses. 3,576,965, Cl. 219-121.

Guglielmetti, Leonardo: See—
Liechti, Peter; Guglielmetti, Leonardo; Maeder, Erwin; and Siegrist, Adolf Emil, 3,577,411.

Gulf & Western Precision Engineering Company: See—
Stickney, Leslie P., 3,577,828.

Gulf Oil Canada Limited: See—
Lanthier, Raymond; and Ouellet, Lorenzo, 3,577,376.

Gulf Research & Development Company: See—
Bacha, John D.; and Selwitz, Charles M., 3,577,470.
Clappitt, Bert H., 3,577,375.
Deffner, John F., 3,577,448.
Kehl, William L., 3,577,354.
Kochhar, Rajindar K.; Clappitt, Bert H.; and Gilbert, Ronald E., 3,577,392.
McNulty, John G.; and Walsh, William L., 3,577,471.
Paviak, Stanley C.; and Porter, Warren K., Jr., 3,577,340.

Gulf Research and Development Company: See—
Schulz, Johann G. D., 3,577,457.

Gund, Tamara Helen Mladineo: See—
Miller, Bernard; and Gund, Tamara Helen Mladineo, 3,577,536.

Gunnerson, Dale B.: See—
Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,577,572.

Gurney, John A.; and Hall, Luther A. R., to Geigy Chemical Corporation. Arylene and arlidene polymers and copolymers. 3,577,476, Cl. 260-668.

Gustafson, Ake, to Tetra Pak AG. Apparatus for the production of tetrahedral hollow articles. 3,577,301, Cl. 156-461.

Guth, Christian; Nachbur, Hermann; and Maeder, Arthur. Process for rendering cellulosic fibers flame-resistant. 3,577,270, Cl. 117-136.

Gutierrez, Peter Paul. Wing flapping toy. 3,577,670, Cl. 46-1.

Gutmann, Hugo; Manz, Ulrich; and Schwieter, Ulrich, to Hoffmann-La Roche Inc. Polyene compounds as coloring agents. 3,577,464, Cl. 260-601.

Guyer, Hubert A. Apparatus for continuous lamination. 3,577,304, Cl. 156-555.

Haerberli, Willy, to United States of America, Atomic Energy Commission. Method for producing ions utilizing a charge-transfer collision. 3,577,026, Cl. 313-63.

Haertlein, Eduard E., to International Business Machines Corporation. Magnetic head assembly with sidebar. 3,577,191, Cl. 340-174.1

Hagelloch, Gunter: See—
Raab, Hans; and Hagelloch, Gunter, 3,577,403.

Hagemeyer, Hugh J., Jr.: See—
Folzenlogen, Paul D.; and Hagemeyer, Hugh J., Jr., 3,577,365.

Hagg, Gunnar, to Incentive Research & Development AB. X-ray camera for X-ray diffraction analysis according to guinier. 3,576,993, Cl. 250-51.5

Hahn, Linus K., to Industrial Nucleonics Corporation. Mass flow rate measuring utilizing the scattering cross-section of a material for fast neutrons. 3,577,158, Cl. 250-43.5

Haines, Robert Glenn, to Union Carbide Corporation. Composition for destroying hardened cementitious mixtures. 3,577,349, Cl. 252-170.

Hair, Hugh H.: See—
Worden, Robert A.; Hair, Hugh H.; Gerst, Carl W.; and Viglietta, Benadict, 3,577,145.

Halasa, Adel F.; and Koch, Russell W., to Firestone Tire & Rubber Company, The. Process and product from treating live elastomers with phosphazenes. 3,577,397, Cl. 260-85.1

Haley, James K.: See—
Klein, Charles H.; and Haley, James K., 3,577,299.

Hall, James A.; and Peppiatt, Harry J., to General Electric Company. Microwave oscillator having directional coupler in feedback path. 3,577,099, Cl. 331-96.

Hall, Luther A. R.: See—
Gurney, John A.; and Hall, Luther A. R., 3,577,476.

Hall, Samuel S.; Miller, Robert A.; and Riley, Philip R. H., to Plessey Company Limited, The. Motor-generator combination. 3,577,002, Cl. 290-46.

Halls, Lawrence M.; and Lausch, Henry N., to Sperry Rand Corporation. Suspension for mounting a header on a tractor. 3,577,715, Cl. 56-208.

Halls, Lawrence M.: See—
McCarty, Horace G.; Halls, Lawrence M.; Howell, Edmund O.; and Hurlburt, Joseph C., 3,577,716.

Hamill, Robert L.: See—
Gorman, Marvin; and Hamill, Robert L., 3,577,531.

Hamm, Allen J.: See—
Kern, Robert P.; and Hamm, Allen J., 3,577,667.

Hamm, Philip C., to Monsanto Company. Halogenated phosphonates used for chemotherilizing screw worm flies. 3,577,538, Cl. 424-214.

Hamm, Philip C., to Monsanto Company. Insect chemotherilant hydroxyethylamino pyrimidines. 3,577,542, Cl. 424-251.

Hammann, William C.; and Schisla, Robert M., to Monsanto Company. Synthetic power transmission fluids. 3,577,361, Cl. 252-73.

Hammond, James Woodrow, to AMP Incorporated. Apparatus for exposing core of an insulated wire. 3,577,814, Cl. 81-9.51

Hanna, Delbert L., to Velsicol Chemical Corporation. Process for the preparation of thionophosphonates. 3,577,482, Cl. 260-973.

Hanna, Roberta J. Decorative article and method of manufacture therefor. 3,577,260, Cl. 117-68.

Hannan, Peter W., to Hazeltine Corporation. Pased array antenna having a wave speeding ground plane. 3,577,147, Cl. 343-778.

Harrington, Joseph K., to Minnesota Mining and Manufacturing Company. 2-Chloroethyl 2-cyanoacrylate and compositions thereof. 3,577,394, Cl. 260-78.4

Harvey, Warren L. Camshaft. 3,577,799, Cl. 74-567.

Hasegawa, Kenichi: See—
Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.

Hasell, Philip G., Jr.: See—
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., 3,576,999.

Hasinger, Siegfried H., to United States of America, Air Force. Thermo-ballistic generator. 3,577,022, Cl. 310-10.

Hauer, Werner, to Neo Dynamics, Inc. Magnetic tape information storage device. 3,576,953, Cl. 179-100.2

Haught, Alan F.: See—
Tomlinson, Richard G.; Brown, Clyde O.; and Haught, Alan F., 3,577,094.

Hausslein, Robert William: See—
Bolger, Justin C.; Mc Collum, Hugh Evan; and Hausslein, Robert William, 3,577,313.

Havno, Kaj, to Christiani & Nielsen A/S. Apparatus for injecting sand beneath submerged constructions. 3,577,738, Cl. 61-63.

Hawkins, William M., to Thomas & Betts Corporation. Connecting device. 3,577,114, Cl.

Hawley, Opie D., to Northrop Corporation. Phase lock indicator for plural phase lock loops. 3,577,178, Cl. 324-83.

Hazeltine Corporation: See—
Hannan, Peter W., 3,577,147.

Head, Beverly P., Jr.: See—
Pearl, David L.; Head, Beverly P., Jr.; and Waller, John G., 3,577,495.

Healy, Albert M.: See—
Armstrong, William J.; Healy, Albert M.; and Duffy, Michael C., 3,577,044.

Heard, Roderick S.: See—
Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.

Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.

Hechelhammer, Wilhelm: See—
Streib, Hugo; and Hechelhammer, Wilhelm, 3,577,378.

Hecker, Klaus Jorg, to Cichner Organisation G.m.b.H. Information read-out control system. 3,577,129, Cl. 340-172.5

Heimann, Dr., Ing., Walter, Forschungslaboratorium, Pro., Frma: See—
Pege, Lotar, 3,577,101.

Heinrich Kopper Gesellschaft mit beschränkter Haftung: See—
Schaten, Paul, 3,577,321.

Helliwell, Bradley A.; and Briglia, Donald D., to Perkin-Elmer Corporation, The. Linear scanning arrangement for a cycloidal mass spectrometer. 3,577,165, Cl. 307-228.

Helsley, Grover Cleveland, to Robins, A.H., Company, Incorporated. 1-Substituted-3-phenoxypropylidines. 3,577,432, Cl. 260-326.3

Helsley, Grover Cleveland: See—
Lunsford, Carl Dalton; and Helsley, Grover Cleveland, 3,577,440.

Henderson, Albert G., to United States of America, Air Force. Bond line test tool. 3,577,775, Cl. 73-95.

Hendrickson, Hubert E.; and Mc Cain, Charles N., to Weyerhaeuser Company. Bark fiber as a reinforcing and stabilizing agent for high temperature molding thermoplastics. 3,577,368, Cl. 260-17.4

Hendrickson, Hubert E.; and McCain, Charles N., to Weyerhaeuser Company. Bark fiber as a dispersing agent for high temperature molding thermoplastics. 3,577,369, Cl. 260-17.4

Henning, Donald S., to Phoenix Products Company, Inc. Adjustable stop for swingable floodlights. 3,576,988, Cl. 240-3.

Hermansson, Fredrik, deceased (by Hermansson, Ingrid; administrator), to Allmanna Svenska Elektriska Aktiebolaget. Means for regenerative braking of an impulse-controlled direct current series motor. 3,577,055, Cl. 318-302.

Hermansson, Ingrid: See—
Hermansson, Fredrik, 3,577,055.

Hertig, Max; and Meier, Peter J., to Braun, G. A., Inc. Three compartment six door washer and extractor. 3,577,751, Cl. 68-143.

Hertig, Max; and Meier, Peter J., to Braun, G. A., Inc. Laundry apparatus. 3,577,752, Cl. 68-210.

Herveus, Jan Ove Hertel: See—
Johansen, Ole Bjerke; and Herveus, Jan Ove Hertel, 3,577,568.

Hess, Hans-Jürgen E.; and Cronin, Timothy H., to Pfizer Inc. Certain 4-aminofuro[2,3-d]pyrimidines. 3,577,420, Cl. 260-256.4

Hess, Martin; and Saroff, Lawrence, to Sinclair-Koppers Company. Apparatus for production of high pressure polyethylene. 3,577,224, Cl. 23-285.

Hessler, Edward J., to Upjohn Company, The. Process for preparing the antibiotic streptozotocin. 3,577,406, Cl. 260-211.

Hewitt, Frederick Maxwell, to Spiroll Corporation Ltd. Concrete slab forming machine with removable soffit edges. 3,577,611, Cl. 25-41.

Hewlett, Clarence Wilson, Jr., to General Electric Company. Zero-crossing silicon controlled rectifier control system. 3,577,177, Cl. 323-18.

Hewlett-Packard Company: See—
Cochran, David S., 3,576,983.

Lightner, Gene E.; Muhlestein, Howard Blair; and Green, Louis E., 3,577,279.

Miller, Arthur, 3,577,072.

Hibbitt, John Edward: See—
Evans, Raymond Victor; and Hibbitt, John Edward, 3,577,652.

Hicguet, Max, to Societe d'Etudes et de Recherches Scientifiques et Minieres. Prevention of slumping in the manufacture of a tar bonded refractory. 3,577,509, Cl. 264-336.

Hidden, William P., to Little, Arthur D., Inc. Portable molding apparatus. 3,577,613, Cl. 25-118.

Higgins, Harvey M., Jr.: See—
Jackson, Billy G.; Spencer, John L.; and Higgins, Harvey M., Jr., 3,577,412.

Hilberg, Ronald P., to TRW Inc. Laser with combined Q-switch and synchronized cavity dump circuit. 3,577,097, Cl. 331-94.5

Hill, George F.: See—
Zic, John A.; Hill, George F.; and Mayfield, Ross M., 3,577,283.

Hill, Rodney S.: See—
Feldmann, Frederick W.; and Hill, Rodney S., 3,577,565.

Hill, Rodney S., to ILC Industries, Inc. Face shield. 3,577,564, Cl. 2-10.

Himmelreich, Louis E., to Scheirich, H. J., Company. Hinge for cabinet door. 3,577,584, Cl. 16-135.

Hines, Theodore G.; and Engle, Wayne C. Thermal and air shock insulating structure. 3,577,305, Cl. 161-4.

Hitachi, Ltd.: See—
Homma, Makoto; and Saito, Toshiaki, 3,577,633.

Hitco: See—
Sharlit, Ian B., 3,577,705.

Hitz, Hans Rudolf: See—
Rohr, Otto; and Hitz, Hans Rudolf, 3,577,453.

Hjermstad, Erling T., to Penick & Ford, Limited. Highly hydroxypropylated granule potato starch. 3,577,407, Cl. 260-233.3

Hoad, John G., & Associates, Inc.: See—
Hoad, John G., 3,577,709.

Hoad, John G., to Hoad, John G., & Associates, Inc. Gas washer apparatus. 3,577,709, Cl. 55-228.

Hobrough, Gilbert L., to Itek Corporation. Automatic image motion stabilization system. 3,577,205, Cl. 250-213.

Hoffman, Eric J., to United States of America, Navy, mesne. Low standby power monostable multivibrator having non-critical cutoff. 3,577,013, Cl. 307-273.

Hoffman, Eric J., to United States of America, Navy, mesne. Lener diode reference circuit independent of input voltage changes. 3,577,062, Cl. 323-8.

Hoffman, George J.; Setele, William O.; and Law, Lester E., to Kendale Industries, Inc. Ball caster and method of making the same. 3,577,620, Cl. 29-148.4

Hoffman, John A.: See—
Sargent, Ronald J.; Sargent, Charles L.; Sargent, Frank T.; and Hoffman, John A., 3,577,569.

Hoffman, Norman Edwin, to AMP Incorporated. Method of making a sealed electrical connecting device. 3,577,496, Cl. 264-156.

Hoffmann, Hermann; and Schmidt, Helmut, to American Hoechst Corporation. Water-soluble, yellow mono-azo dyes with active methylene coupler. 3,577,405, Cl. 260-193.

Hoffmann, Irmgard: See—
Ehrhart, Gustav; Schmitt, Karl; Hoffmann, Irmgard; and Ott, Heinrich, 3,577,424.

Hoffmann-La Roche Inc.: See—
Guevrekian, Lawrence Norayr, 3,577,785.

Gutmann, Hugo; Manz, Ulrich; and Schwieter, Ulrich, 3,577,464.

Hofmeister, Ernst, to Siemens Aktiengesellschaft. Method of producing semiconductor device in glass housing. 3,577,632, Cl. 29-585.

Hofmeister, Laurence C., to Bendix Corporation, The. Quadrature rejection and frequency conversion circuit. 3,577,009, Cl. 307-233.

Hollander, Jerome: See—
Trischler, Floyd D.; and Hollander, Jerome, 3,577,356.

Holler, Howard V., to Shell Oil Company. 1-(Dicarboxyphenyl)-indane dicarboxylic acid dianhydride. 3,577,442, Cl. 260-346.3

Holt, Mike C. Athletes' protective helmet particularly foot-ball. 3,577,562, Cl. 2-3.

Holzschuh, Donald L.; and Wicker, Betty M., to Collins Radio Company. Portable, reelable dipole antenna having frequency calibrated dial. 3,577,148, Cl. 343-821.

Homma, Makoto; and Saito, Toshiaki, to Hitachi, Ltd. Method of making a semiconductor device. 3,577,633, Cl. 29-588.

Honeywell Inc.: See—
Gerks, Irvin F., 3,577,021.

Hurd, Edward T. E., III, 3,577,063.

Stauffer, Norman L., 3,576,948.

Hooker Chemical Corporation: See—
Blair, Noel D., 3,577,371.

Thorpe, Donald H., 3,577,478.

Thorpe, Donald H., 3,577,480.

Hoover Ball and Bearing Company: See—
Link, Darl L., 3,577,626.

Horie, Yosio: See—
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniro; and Uono, Fumito, 3,577,623.

Hornbogen, Erhard; Niessner, Erwin; and Buck, Gert, to Buck K.G. Methods and devices for the dynamic testing of materials. 3,577,762, Cl. 73-12.

Horsley, Lee H., to Dow Chemical Company, The. Process for making glycol ethers and glycol esters. 3,577,559, Cl. 260-410.6

Horstmann, Kenneth John; and Douglas, Colin Graham. Watchman's radio location indicating system. 3,577,079, Cl. 325-53.

Horton, John P.; Sollmann, Robert E.; and Santos, Joaquim L., to Ski-Mor Inc. Ski mat apparatus. 3,577,835, Cl. 94-3.

Hoss, George Carr: See—
Welsh, Thomas Laurence; Peterson, Donald Leroy; Palermo, Blasey Thomas; and Hoss, George Carr, 3,577,490.

Houdaille Industries, Inc.: See—
Rumsey, Rollin Douglas, 3,577,802.

Howard, James S., to Rohr Corporation. Taping apparatus and method. 3,577,297, Cl. 156-265.

Howe, Eugene E.; and Rosenblum, Charles, to Merck & Co., Inc. Topical administration of vitamin B-12. 3,577,537, Cl. 424-201.

Howell, Edmund O.: See—
McCarty, Horace G.; Halls, Lawrence M.; Howell, Edmund O.; and Hurlburt, Joseph C., 3,577,716.

Hudson, Earl A.: See—
McCarty, Horace G.; Lausch, Henry N.; and Hudson, Earl A., 3,577,713.

Hughes Aircraft Company: See—
Benner, Richard C., 3,577,095.

Bridges, William B.; and Clark, Peter O., 3,577,096.

Dill, Hans G., 3,577,210.

King, Harry J., 3,577,734.

Winston, Harvey V., 3,577,098.

Hunnicut, Jack B.: See—
Plumly, George W.; Hunnicutt, Jack B.; and Deyo, Charles R., 3,577,657.

Hurd, Edward T. E., III, to Honeywell Inc. Voltage regulator with insignificant current drain. 3,577,063, Cl. 323-16.

Hurlburt, Joseph C.: See—
McCarty, Horace G.; Halls, Lawrence M.; Howell, Edmund O.; and Hurlburt, Joseph C., 3,577,716.

Hurn, James; King, Charles Richard Forbes; and Deane, Donald Raymond. Method and apparatus for cutting components to length. 3,577,829, Cl. 90-21.

Husing, Walter H.: See—
Schmidt, Thomas R.; and Husing, Walter H., 3,577,643.

Hutkin, Irving J., to Whittaker Corporation. Thermal cell. 3,577,193, Cl. 340-228.

Hutzler, George J.; and Schwenk, Carl L., to Textron Inc. Method for forming decorative polyurethane coatings. 3,577,257, Cl. 117-26.

Huybers, Heinz W., to Foster Wheeler Corporation. Construction of heaters. 3,577,695, Cl. 52-745.

Hymes, Alan C., to Wyandotte Chemicals Corporation. Methods for the treatment of shock with ethylene oxide-polypropylene glycol condensates as blood plasma substitutes. 3,577,522, Cl. 424-78.

Ichihara, Koreyoshi, to Nippon Hume Pipe Co., Ltd. Centrifugal molding process for manufacturing Hume-type concrete pipes. 3,577,505, Cl. 264-256.

Industrial Nucleonics Corporation: See—
Hahn, Linus K., 3,577,158.

Ikoma Orimono Co., Ltd.: See—
Ikoma, Yasaburo; and Yabu, Ikuta, 3,577,607.

Ikoma, Yasaburo; and Yabu, Ikuta, to Ikoma Orimono Co., Ltd. Separable fastening fabric. 3,577,607, Cl. 24-204.

ILC Industries, Inc.: See—
Feldmann, Frederick W.; and Hill, Rodney S., 3,577,565.

Hill, Rodney S., 3,577,564.

Imamura, Hiroshi: See—
Nakanishi, Michio; Arimura, Katsuo; Imamura, Hiroshi; and Kobayakawa, Toshihiro, 3,577,425.

Immel, Richard H., to Sinclair-Koppers Company. Process for pre-expanding polymer beads. 3,577,360, Cl. 264-53.

Imperial Chemical Industries Limited: See—
Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, 3,577,543.

Clementson, John Joseph, 3,577,348.

Kenworthy, Jeffrey Stuart; and Wiener, Hans Berthold, 3,577,740.

White, Trevor Raymond, 3,577,707.

Imperial Smelting Corporation (N.S.C.) Limited: See—
Moller, Leopold, 3,577,706.

Impullitti, Ector P., to Means, T. W., & Company. Dry cleaning process. 3,577,215, Cl. 8-142.

Inagaki, Junpei; Sakamoto, Moriyoshi; Nakakita, Tsuneo; and Kitamura, Hiroyuki, to Tokyo Shibaura Electric Co., Ltd. Liquid cooled dynamoelectric machines. 3,577,024, Cl. 310-54.

Incentive Research & Development AB: See—
Hagg, Gunnar, 3,576,993.

Industrial Air Company, Inc.: See—
Nichols, John A., 3,577,651.

Industrial Air Filters Limited: See—
Ballennie, Peter; and Ruffo, Angelo P., 3,577,712.

Industrial Research Products, Inc.: See—
Carlson, Elmer Victor; Cross, Floyd Warren; and Killion, Mead Clifford, 3,577,020.

Innocenti, Thomas J., to USM Corporation. Process of making athletic shoes with injection molded sole. 3,577,503, Cl. 264-244.

Inoue, Kaname: See—
Tamura, Kihachi; Nakajima, Isao; and Inoue, Kaname, 3,577,362.

Inoue, Takasi: See—
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniro; and Uono, Fumito, 3,577,623.

Institut Francais du Petrole des Carburants et Lubrifiants: See—
Boutry, Pierre; Daumas, Jean Claude; and Montarnal, Roger, 3,577,477.

Intech Corporation: See—
Glaze, John W., Jr.; and Worth, Joseph P., 3,577,300.

Intelligent Instruments, Inc.: See—
Slavin, Peter E., 3,576,997.

International Business Machines Corporation: See—
Aasnaes, Hans Bent, 3,577,140.

Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.

Armstrong, William J.; Healy, Albert M.; and Duffy, Michael C., 3,577,044.

Belady, Laszlo A., 3,577,185.

Berkenblit, Melvin; and Reisman, Arnold, 3,577,286.

Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.

Brown, Augustus B., 3,577,506.

Cheroff, George, 3,577,047.

Clecak, Nicholas J.; and Cox, Robert J., 3,577,444.

Cocke, John; Randell, Brian; Schorr, Herbert; and Sussenguth, Edward H., 3,577,189.

Cocke, John; Dauber, Philip S.; Schorr, Herbert; and Sussenguth, Edward H., 3,577,190.

Colglazier, Donald F., 3,576,941.

Crisimagna, Tony N.; and Fournier, Robert J., 3,577,128.

Curtis, John J.; and Ruoff, Carl E., 3,577,036.

Di Pietro, Americo R.; and Thun, Rudolf E., 3,577,037.

Draper, Wilburn D., 3,576,973.

Duke, Keith A., 3,576,982.

Frushour, James E.; Millham, Ernest H.; and Orloff, James E., 3,577,076.

Gorog, Etienne, 3,577,089.

Haertlein, Eduard E., 3,577,191.

Lautier, Alex Honore; Nussbaumer, Henri Jean; and Pierret, Jean Marc, 3,577,082.

Liebschutz, Lynn C., 3,577,326.

Norwood, Richard E., 3,576,971.

Rohr, Robert L., 3,577,278.

Rosenberg, Jack, 3,576,978.

Rutz, Richard F., 3,577,285.

Schlaepfer, Carl E., 3,577,192.

Secrist, Duane R., 3,577,634.
 Surtly, Rohinton J., and Trollmann, Conrad, 3,576,969.
 International Minerals & Chemical Corporation: See—
 Lang, William J., 3,577,367.
 International Nickel Company, Inc., The: See—
 Knapp, Burton Bower, and Cupp, Leander Ernest, 3,577,330.
 International Rectifier Corporation: See—
 Roach, Thomas J., 3,577,042.
 International Standard Electric Corporation: See—
 De Wit, Frans Corneel Leo, and Adelaar, Hans Helmut, 3,576,949.
 International Telephone & Telegraph Corporation: See—
 Eldridge, Raymond W., Jr., 3,576,937.
 Frisbie, Jack G., 3,577,125.
 International Telephone and Telegraph Corporation: See—
 Jovic, Nikola Ljotic, 3,576,950.
 Raffaelli, Joseph Gino, and Lolkart, Hendricus Johnnes, 3,577,011.
 Isaksen, Robert A., to Monsanto Company. Coating compositions comprising polyvinyl acetal, 3,577,374, Cl. 260-23.
 Ishitobi, Katsuya: See—
 Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihashi, Hikoyuki; and Ishitobi, Katsuya, 3,577,498.
 Itek Corporation: See—
 Aldrich, Ralph E., and Caruso, Paul J., 3,577,200.
 Hobrough, Gilbert L., 3,577,205.
 Iwanami, Masaru: See—
 Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
 Iwao Ueda: See—
 Kobayashi, Tadataka, 3,577,124.
 Iwasaki, Kenji: See—
 Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatu, Akihiro, 3,577,033.
 Jack, David; and Rhodes, Deryck, to Allen & Hamburys Limited. Treatment of pain or inflammation with p-benzoyl-phenylacetic acid or O-benzoyl-phenylacetic acid, 3,577,549, Cl. 424-317.
 Jacknow, Burton B., and Moriconi, Joseph H., to Xerox Corporation. Solid xerographic developer, 3,577,345, Cl. 252-62.1
 Jackson, Billy G.; Spencer, John L.; and Higgins, Harvey M., Jr. Process for recovering cephalosporin Ca antibiotics, 3,577,412, Cl. 260-243.
 Jackson, James W., to Bird & Son, Inc. Apparatus for heat and vacuum-pressure machine molding, 3,577,593, Cl. 18-19.
 Jacobson, Robert L., to Chevron Research Company. Conversion of C₆-C₇ cycloalkanes to benzene and Toluene, 3,577,474, Cl. 260-668.
 Jacobson, William P., to Anderson Bros. Mfg. Co. Method for forming lines of weakness in thermoplastic, 3,577,484, Cl. 264-92.
 Jakimcius, Zigmant, to Barnes Drill Co. Abrading machine with steering roll and tensioned abrading belt, 3,577,684, Cl. 51-135.
 Janoski, Edward J.: See—
 Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,577,479.
 Jarman, Hall, E.: See—
 Bylander, Ernest G., and Jarman, Hall, E., 3,577,631.
 Jaspert, Jurgen: See—
 Oberhofer, Martin; and Jaspert, Jurgen, 3,577,161.
 Jeffries, James E., to S&C Electric Company. Switch construction with load break device having one or more movable slats with heat spacers, 3,576,967, Cl. 200-151.
 Jenevein, Edwin P., Jr. Antemortem method of tenderizing meat, 3,577,242, Cl. 99-107.
 Jirou, Marcel Georges; and Bouvet, Pierre Charles Victor, to Ugine Kuhlmann. Process for the modification of polyamide fibers, 3,577,212, Cl. 8-115.5.
 Joachim, Tibor; and Beckwith, Merton M., to Conversion Chemical Corporation. Method and composition for electroplating cadmium (B), 3,577,327, Cl. 204-50.
 Johansen, Ole Bjerke; and Herveus, Jan Ove Hertil. Water closet, 3,577,568, Cl. 4-77.
 Johansson, Arne: See—
 Kring, Arne; and Johansson, Arne, 3,577,041.
 Johnson & Johnson: See—
 Kalwaites, Frank; and Doviak, Peter L., 3,577,586.
 Johnson, Henry C.: See—
 Akew, Robert E.; and Johnson, Henry C., 3,577,100.
 Johnson, James S.: See—
 Baird, Justus N., Jr.; Johnson, James S.; Kraus, Kurt A.; and Perona, Joseph J., 3,577,339.
 Johnson, Joseph A.; and Key, Ray. Fishing bobber, 3,577,669, Cl. 43-43.11.
 Johnson, Matthey & Co., Limited: See—
 Boughton, John D.; Roberts, Philip M.; and Sloboda, Mieczyslaw Herman, 3,577,234.
 Johnson, Wallace F.; and Tilson, William H. Lighting system, 3,576,990, Cl. 240-10.
 Johnston, Reed M.: See—
 Foster, Samuel L.; and Johnston, Reed M., 3,577,109.
 Jones, Edwin L., to Douglas Dynamics Corporation. Adjustable eccentric, 3,577,800, Cl. 74-571.
 Jones, Everett M.: See—
 Keith, Frederick W., Jr.; Jones, Everett M.; and Townsend, Joseph R., Jr., 3,577,341.

Jones, Howard S., Jr., to United States of America, Army. Method and apparatus for joining plated dielectric-foam waveguide components, 3,577,105, Cl. 333-95.
 Jones, John E.: See—
 Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
 Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
 Jones, Robert E.; and Reynolds, Harold, to Merck & Co., Inc. t-Burtyl- α -methyl- α -nitro-valerate, 3,577,455, Cl. 260-478.
 Jones, William Glynn Moss: See—
 Baranyovits, Francis Leslie Charles; Ghosh, Ranajit; Bishop, Nigel Douglas; Freeman, Peter Frank Hilary; and Jones, William Glynn Moss, 3,577,543.
 Jones, William Owen McKenzie. Machine tools, 3,577,617, Cl. 29-54.
 Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, to Sun Oil Company. Aluminum halide isomerization of saturated hydrocarbons, 3,577,479, Cl. 260-683.75.
 Jovic, Nikola Ljotic, to International Telephone and Telegraph Corporation. Self-seeking electronic switching network, 3,576,950, Cl. 179-18.
 Jubin, John C., Jr.; and Becker, Matthew L., to Atlantic Richfield Company. Method for chlorinating paraffins, 3,577,472, Cl. 260-660.
 Judy, William Allen, to Goodyear Tire & Rubber Company, The. Novel catalysts for the polymerization of alicyclic olefins, 3,577,400, Cl. 260-88.2.
 Kabel-und Metallwerke Gutehoffnungshutte Aktiengesellschaft: See—
 Ziemek, Gerhard Karl, 3,576,939.
 Kaeser, Ernst K.: See—
 Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., 3,577,050.
 Kagami, Soichi: See—
 Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
 Kail, Karl, to Singer-General Precision, Inc. Motion simulator actuator joint, 3,577,659, Cl. 35-12.
 Kaiser Aluminum & Chemical Corporation: See—
 McKenna, Bernard D., 3,577,247.
 Neely, Joseph E., 3,577,246.
 Kalle Aktiengesellschaft: See—
 Schmitz, Peter Josef; Werner, Eberhard; and Seifried, Walter, 3,577,510.
 Kallin, Ruth L.: See—
 Persson, Per Anders; and Sodersten, Bror Lennart, 3,577,691.
 Kaltman, Irwin L.: See—
 Sofer, Uri Y.; and Kaltman, Irwin L., 3,577,693.
 Kalwaites, Frank; and Doviak, Peter L., to Johnson & Johnson. Apparatus for continuously transversely stretching orientable sheet material, 3,577,586, Cl. 18-1.
 Kamberg, Eduard F., to Chicago Dryer Company. Laundry apparatus, 3,577,665, Cl. 38-2.
 Kaminsky, Daniel E.; Meltzer, Robert I.; and Shavel, John, Jr., to Warner-Lambert Pharmaceutical Company. Nitro substituted benzofurans, 3,577,441, Cl. 260-346.2.
 Kanoh, Teruchika: See—
 Matsugu, Tomoyuki; Notomi, Ryota; and Kanoh, Teruchika, 3,577,497.
 Kato, Masao: See—
 Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatu, Akihiro, 3,577,033.
 Kawashima, Masao; Kurita, Syoichi; and Sasaki, Shunroku, to Fujitsu Limited. Feedback type pulse amplitude modulation coding system, 3,577,138, Cl. 340-347.
 Kaye, Irving I.: See—
 Flanagan, Thomas P.; and Kaye, Irving I., 3,577,372.
 Keck, Max H., to Goodyear Tire & Rubber Company, The. Process for crystallizing bis(β -hydroxyethyl) terephthalate, 3,577,454, Cl. 260-475.
 Kehl, William L., to Gulf Research & Development Company. Magnesium chromium ferrite catalyst, 3,577,354, Cl. 252-468.
 Keith, Frederick W., Jr.; Jones, Everett M.; and Townsend, Joseph R., Jr., to Pennwalt Corporation. Water treatment, 3,577,341, Cl. 210-53.
 Keithly Instruments, Inc.: See—
 Praglin, Julius, 3,577,074.
 Kelley, Fred W., Jr., to General Electric Company. Electric power apparatus comprising converter, filter, regulator, and means for dynamically stabilizing the filter, 3,577,059, Cl. 321-10.
 Kenaga, Eugene E., to Dow Chemical Company, The. Methods for sterilizing insects with triaryl tin compounds, 3,577,548, Cl. 424-288.
 Kendale Industries, Inc.: See—
 Hoffman, George J.; Setele, William O.; and Law, Lester E., 3,577,620.
 Kenney, Malcolm E. Linkage for model-forming discs, 3,577,660, Cl. 35-18.
 Kensinger, Lex Donald: See—
 Delyon, Armand Rene; and Kensinger, Lex Donald, 3,577,119.

Kenworthy, Jeffrey Stuart; and Wiener, Hans Berthold, to Imperial Chemical Industries Limited. Vibrated refrigerated surface, 3,577,740, Cl. 62-72.
 Kerfoot, Franklin W., Jr. Laminated sprocket belt, 3,577,794, Cl. 74-232.
 Kern, Robert P.; and Hamm, Allen J. Lock for percussion cap rifle, 3,577,667, Cl. 42-69.
 Kerst, Al F., to Monsanto Company. Polymeric compositions comprising organo-amino-phosphonate esters, 3,577,382, Cl. 260-45.8.
 Kersten, Hilde; Siggel, Erhard; and Meyer, Gerhard, to Glanzstoff AG. Process of preparing heat-resistant polymers, 3,577,387, Cl. 260-47.
 Kessler, Theodore; Sharkey, Andrew G., Jr.; Malli, Joseph, Jr.; and Friedel, Robert A., to United States of America, Interior. Solvent extraction of coal, 3,577,337, Cl. 208-8.
 Key, Ray: See—
 Johnson, Joseph A.; and Key, Ray, 3,577,669.
 Kieslich, Klaus; and Koch, Wolfgang, to Schering Aktiengesellschaft. Process for making 6-hydroxy-3-keto- Δ^4 -steroids of the pregnane and androstane series, 3,577,318, Cl. 195-51.
 Killion, Mead Clifford: See—
 Carlson, Elmer Victor; Cross, Floyd Warren; and Killion, Mead Clifford, 3,577,020.
 King, Charles Richard Forbes: See—
 Hurn, James; King, Charles Richard Forbes; and Deane, Donald Raymond, 3,577,829.
 King, Harry J., to Hughes Aircraft Company. Liquid-metal feed system for feeding propellant to an ion thruster, 3,577,734, Cl. 60-202.
 Kingsbury, Archie R., to Union Carbide Corporation. Clip for carbon brushes, 3,577,025, Cl. 310-239.
 Kinney, Layton E.: See—
 Castro, Anthony J.; Marsh, Frederick S.; Kinney, Layton E.; and Fischl, Frank J., 3,577,370.
 Kirjushin, Vladimir Pavlovich. Microwave plasmatron, 3,577,207, Cl. 315-39.
 Kirkhof Manufacturing Corporation: See—
 Medendorp, Roger L., 3,577,821.
 Kirkland, Joseph J., to Du Pont de Nemours, E. I., and Company. Superficially porous chromatographic packing with sulfonated fluoropolymer coating, 3,577,266, Cl. 117-100.
 Kislin, Benjamin; and Miller, J. W., to United States of America, Air Force. Spectacle hood, 3,577,566, Cl. 2-12.
 Kisselmann, Willy; Rumpelstein, Fritz; Kopf, Paul; and Landbrecht, Franz, to Agfa-Gevaert Aktiengesellschaft. Electrical measuring or indicating instrument having paper pointer stops, 3,577,078, Cl. 324-154.
 Kitamura, Hiroyuki: See—
 Inagaki, Junpei; Sakamoto, Moriyoishi; Nakakita, Tsuneo; and Kitamura, Hiroyuki, 3,577,024.
 Kitamura, Seikichi: See—
 Kubota, Ikuo; Mikami, Masakatsu; and Kitamura, Seikichi, 3,577,517.
 Klanderma, Bruce H.; and Faber, Jan W. H., to Eastman Kodak Company. 9,10-Bridged anthracene compounds, 3,577,366, Cl. 260-618.
 Klar, Kenneth K., to Goodyear Tire & Rubber Company, The. Substrate with adherent layer having color imparted by said substrate, 3,577,261, Cl. 117-80.
 Klauke, Erich: See—
 Kühle, Engelbert; Klauke, Erich; Frohberger, Paul-Ernst; and Scheinplugg, Hans, 3,577,451.
 Klein, Charles H.; and Haley, James K., to Novelart Manufacturing Company. Register and control apparatus for corrugator, 3,577,299, Cl. 156-361.
 Klein, Robert J.: See—
 Moehlman, Vernon C.; and Klein, Robert J., 3,577,251.
 Kleiner, Hans-Jerg; and Rehn, Karl, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Process for the manufacture of aqueous alkali paraffin sulphate solutions containing small amounts of alkali sulfate, 3,577,456, Cl. 260-513.
 Kliman, Ivan M.; and Smola, Harold, to United States of America, Army, mesne. Generator of delayed sequences employing shift register techniques, 3,577,086, Cl. 328-62.
 Klint, Robert V.: See—
 Capotosto, Frank A.; and Klint, Robert V., 3,576,938.
 Klug, Oluf Walter Henry, to AB Electrolux. Cellular plastics material containing polystyrene and a process for its manufacture, 3,577,363, Cl. 260-2.5.
 KMS Industries, Inc.: See—
 Lyon, William H., 3,577,656.
 Knapp, Burton Bower; and Cupp, Leander Ernest, to International Nickel Company, Inc., The. Process for producing electrorefined nickel having controlled size, 3,577,330, Cl. 204-112.
 Knapp, Edward M.: See—
 Nesbitt, Stephen J.; and Knapp, Edward M., 3,577,322.
 Knodler, Adolf: See—
 Widl, Gerhard; Groetzner, Kurt; and Knodler, Adolf, 3,577,107.
 Knox, Francis P., to Redington Counters, Inc. Add and subtract counter, 3,576,974, Cl. 235-92.
 Knudsen, John P., to Monsanto Company. Method for preparing permanently opaque fibers, 3,577,499, Cl. 264-182.
 Kobayakawa, Toshihiro: See—
 Nakanishi, Michio; Arimura, Katsuo; Imamura, Hiroshi; and Kobayakawa, Toshihiro, 3,577,425.
 Kobayashi, Tadataka, to Iwao Ueda. Pre-engagement card controlled device for patients, 3,577,124, Cl. 340-153.

Koch, Lawrence M.: See—
 Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.
 Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.
 Koch, Russell W.: See—
 Halasa, Adel F.; and Koch, Russell W., 3,577,397.
 Koch, Wolfgang: See—
 Kieslich, Klaus; and Koch, Wolfgang, 3,577,318.
 Kocher, Erich J., to Vilter Manufacturing Corporation. Refrigeration system having a screw compressor with an auxiliary high pressure suction inlet, 3,577,742, Cl. 62-199.
 Kochhar, Rajindar K.; Clappitt, Bert H.; and Gilbert, Ronald E., to Gulf Research & Development Company. Workable polyamides by blending with inorganic thiocyanates, 3,577,392, Cl. 260-78.
 Koddermann, Else: See—
 Scheller, Karlheinz; Koddermann, Else; and Trebs, Hans, 3,577,521.
 Koh, Teow Yan; and Bharucha, Kekhusroo Rustomji, to Canada Packers Limited. Stable orally active heparinoid complexes, 3,577,534, Cl. 424-183.
 Kohjin Company Limited: See—
 Matsugu, Tomoyuki; Notomi, Ryota; and Kanoh, Teruchika, 3,577,497.
 Kohler, Armin; Von Falkai, Bela; Offermann, Klaus; and Reichle, Alfred, to Farbenfabriken Bayer Aktiengesellschaft. Process for the production of polyamide fibres having high linear strength and knot strength, 3,577,500, Cl. 264-210.
 Kohler, Emil: See—
 Dyer, George A.; and Kohler, Emil, 3,577,057.
 Kohler, Karl Gustav, to Aktiebolaget Nordstroms Linbanor. Means for folding in wrapping material at the end of an approximately cylindrical article, 3,577,703, Cl. 53-380.
 Kohner Bros., Inc.: See—
 Kohner, Frank; and Stubbmann, Albert, 3,577,675.
 Kohner, Frank; and Stubbmann, Albert, to Kohner Bros., Inc. Child's bathing toy, 3,577,675, Cl. 46-41.
 Koinuma, Tokuju: See—
 Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatu, Akihiro, 3,577,033.
 Kolb, Robert H., to Shell Oil Company. System and method for controlling the positioning system of a pipelaying vessel, 3,576,977, Cl. 235-150.27.
 Komat Stahlhalter-und Werkzeugfabrik Robert Breuning GmbH, Firma: See—
 Eckle, Otto, 3,577,810.
 Kondo, Takeshi: See—
 Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.
 Kopf, Paul: See—
 Kisselmann, Willy; Rumpelstein, Fritz; Kopf, Paul; and Landbrecht, Franz, 3,577,078.
 Koppers Company, Inc.: See—
 Drenning, John W.; and Bridges, Richard J., 3,577,708.
 Kovacic, Joseph E., 3,577,784.
 Tai, Wun T., 3,577,377.
 Koppy Tool Corporation: See—
 De Gain, William J., 3,577,621.
 Koroscil, Anthony: See—
 Megna, Ignazio Salvatore; and Koroscil, Anthony, 3,577,388.
 Korr, Abraham L., to United States of America, Army. Target holding control unit, 3,577,764, Cl. 73-12.
 Korzhov, Vasily Porfirievich: See—
 Zax, Natan Albertovich; Korzhov, Vasily Porfirievich; and Rabinovich, Roza Semenovna, 3,577,720.
 Kosco, John C., to Stackpole Carbon Company. Semi-conductor crystal supports, 3,577,275, Cl. 117-213.
 Koshada, Robert E.: See—
 Smith, Donald C.; and Koshada, Robert E., 3,577,595.
 Kotschmar, Arnold; Metzger, Hermann; Rothe, Richard Reinhard Gustav Adolf, deceased (by Rothe, Rudolphe, nee Roessler, heiress); and Seidel, Willy, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Process for the preparation of phosphoric acid esters by reaction of phosphorus oxychloride with alkylene oxides, 3,577,483, Cl. 260-977.
 Koury, Frederic; and Waymouth, John F., to Sylvania Electric Products Inc. High pressure electric discharge device containing mercury, halogen, scandium and samarium, 3,577,029, Cl. 313-229.
 Kovacic, Joseph E., to Koppers Company, Inc. Method and apparatus for measuring coke oven flue wall temperatures, 3,577,784, Cl. 73-355.
 Kraft, Louis Seelbach; and Quiner, Charles W., to Goodyear Tire & Rubber Company, The. Method of bonding textile fabric belts, 3,577,295, Cl. 156-177.
 Kraus, Kurt A.: See—
 Baird, Justus N., Jr.; Johnson, James S.; Kraus, Kurt A.; and Perona, Joseph J., 3,577,339.
 Krautwald, Herbert; Moller, Helmut; and Siepmann, Richard, to Siemens Aktiengesellschaft. Switch-over contact arrangement for power relays, 3,577,182, Cl. 335-185.
 Kreithen, Marvin L.; and Lawler, John J., to Compudyne Corporation. Constant current step motor system, 3,577,176, Cl. 318-432.

Kremer, Charles J.; Brown, Donald S.; Apikos, Dominic; and Thean, John T., to Atlantic Richfield Company. Wax compositions containing an ethyleneisobutyl-acrylate copolymer and an organic acid. 3,577,373, Cl. 260-23.

Kring, Arne; and Johansson, Arne, to Allmanna Svenska Elektriska Aktiebolaget. Overcurrent relay circuit. 3,577,041, Cl. 317-148.5

Kruger, Lawrence W., to United States of America, Navy. Rapid frame synchronism of serial binary data. 3,576,947, Cl. 178-69.5

Krygeris, Algirdas J., to Gilmore Industries, Inc. Digital servo indicator. 3,577,075, Cl. 324-99.

Kubicz, Arthur P., to Collins Radio Company. Signed path series step biased multi device high efficiency amplifier. 3,577,092, Cl. 330-124.

Kubo, Moritada; and Asano, Kuniji, to Tokyo Shibaura Electric Co., Ltd. Method and apparatus for measuring the percentage of elongation of metal strips. 3,577,773, Cl. 73-67.7

Kubota, Ikuo; Mikami, Masakatsu; and Kitamura, Seikichi, to Mitsubishi Rayon Co., Ltd., and Goo Chemical Industry Co., Ltd. Acrylic or methacrylic acid copolymer in resinous aerosol hair preparations. 3,577,517, Cl. 424-47.

Kuhar, George A., to Goodyear Tire & Rubber Company. The. Char resistant polyurethane. 3,577,389, Cl. 260-75.

Kuhle, Engelbert; Klauke, Erich; Frohberger, Paul-Ernst; and Scheinpfug, Hans, to Farbenfabriken Bayer Aktiengesellschaft. Sulfamide derivatives. 3,577,451, Cl. 260-453.

Kulischenko, Walter, to Pennwalt Corporation. Abrading apparatus. 3,577,682, Cl. 51-8.

Kunkel, Roland K.; See—
Myles, William J.; and Kunkel, Roland K., 3,577,213.

Kunz, Georg; See—
Ganter, Wolfgang; and Kunz, Georg, 3,577,725.

Kuratomi, Tatsuo; and Yatsurugi, Yoshifumi. Process for production of monosilane (SiH₄) and germanium hydride (GeH₄). 3,577,220, Cl. 23-204.

Kuriaki, Kaname; See—
Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.

Kurita, Syoichi; See—
Kawashima, Masao; Kurita, Syoichi; and Sasaki, Shunroku, 3,577,138.

Kurtz, Donald R., to General Electric Company. Flange fastening means for a contact button for a vacuum-type circuit interrupter. 3,576,960, Cl. 200-144.

Kussman, Michael; See—
Means, Ray H.; Kussman, Michael; Wade, Jack; and Vodra, Victor H., 3,577,241.

LaBaw, Kenneth B., to United States of America, Navy. Scanning radiometer with plural reference sources. 3,576,944, Cl. 178-6.8

Lacey, Robert E.; and Mintz, Milton S., to United States of America, Interior. Apparatus and process for effecting changes in solution concentrations. 3,577,331, Cl. 204-180.

Ladendecker, Henry L.; See—
Smith, Kave A.; and Ladendecker, Henry L., 3,577,817.

La Force, Richard C., to Atlantic Richfield Company. Optically pumped magnetic gradiometer. 3,577,068, Cl. 324-0.5

Laimins, Eric, to B&H Electronics, Inc. Constant moment beam transducers. 3,577,779, Cl. 73-141.

Lakodey, Andre; See—
Weiss, Francis; and Lakodey, Andre, 3,577,216.

Lal, Joginder; and Throckmorton, Morford C., to Goodyear Tire and Rubber Company. The. Novel catalyst for the polymerization of conjugated dienes. 3,577,395, Cl. 260-82.1

Landbrecht, Franz; See—
Kisselmann, Willy; Rumpelstein, Fritz; Kopf, Paul; and Landbrecht, Franz, 3,577,078.

Lang, Pierre, to Bobst, J., & Fils S.A. Gripper bar mount for platen press. 3,577,834, Cl. 93-58.3

Lang, William J., to International Minerals & Chemical Corporation. Foundry sand compositions containing graft copolymers of acrylic acid with methyl cellulose. 3,577,367, Cl. 260-17.

Langenhagen, Charles F., Jr.; See—
Alexander, Arthur P.; Aronson, Steven R.; and Langenhagen, Charles F., Jr., 3,577,578.

Lanooy, Cornelis; and Mensen, Herbert, to U.S. Philips Corporation, mesne. Stereophonic phonograph transducer. 3,576,956, Cl. 179-100.41

Lanthier, Raymond; and Ouellet, Lorenzo, to Gulf Oil Canada Limited. Interpolymerization of acrylamide vinyl acetate and other monomers by using a solubilizing agent to dissolve the acrylamide in the vinyl acetate. 3,577,376, Cl. 260-29.6

Lapham, James O. Flat panel traffic warning sign having light mounted thereon. 3,577,122, Cl. 340-114.

Laser Technique SA; See—
Gugger, Gottfried, 3,576,965.

Laughlin, Robert G., to Procter & Gamble Company. The. N-alkyl and N,N-dialkyl alkanesulfonamide bis (alkylimines) and N-alkyl and N,N-dialkyl alkylamines and processes for preparing same. 3,577,459, Cl. 260-551.

Lausch, Henry N.; See—
Halls, Lawrence M.; and Lausch, Henry N., 3,577,715.
McCarty, Horace G.; Lausch, Henry N.; and Hudson, Earl A., 3,577,713.

Lautier, Alex Honore; Nussbaumer, Henri Jean; and Pierret, Jean Marc, to International Business Machines Corporation. Carrier frequency phase-readjustment device. 3,577,082, Cl. 325-416.

Lavan, Lawrence P. Music teaching machine. 3,577,824, Cl. 84-478.

Law, Lester E.; See—
Hoffman, George J.; Setele, William O.; and Law, Lester E., 3,577,620.

Lawler, John J.; See—
Kreithen, Marvin L.; and Lawler, John J., 3,577,176.

Lawrence, Garth D.; and Ott, Jack J., to Dow Chemical Company. The. Method of forming pellets of a flux composition. 3,577,560, Cl. 264-8.

Lawrence, Philip L., to Mobil Oil Corporation. Method of and means for treating gravity profiles. 3,576,985, Cl. 235-181.

Lear Siegler, Inc.; See—
Eklund, Harry Nils, 3,577,646.

Lebedev, Vladimir Konstantinovich; See—
Paton, Boris Evgenievich; Lebedev, Vladimir Konstantinovich; Sheiko, Pavel Petrovich; and Pashulya, Mikhail Petrovich, 3,577,156.

Le Blanc, John R., to Monsanto Company. Epoxy resins from alkylated phenol novolac, resins. 3,577,437, Cl. 260-33.6

Lebourg, Maurice P.; and Fields, Roger Q., to Schlumberger Technology Corporation. Tool to take multiple formation fluid pressures. 3,577,781, Cl. 73-152.

Lee, Arlene M., as joint tenants; See—
Lee, Robert L., 3,577,639.

Lee, Henry J., to United States of America, Navy. Method of fabricating a glass fabric laminate material. 3,577,493, Cl. 264-137.

Lee, Robert L.; See—
Lee, Robert L., 3,577,639.

Lee, Robert L., 5% to Arant, Gene W., Arant, Juanita F., 95% to Lee, Robert L., and Lee, Arlene M., as joint tenants. Face bow with three-dimensionally adjustable support means. 3,577,639, Cl. 32-19.

Lee, Robert L. Dental clutches, and method and apparatus for making. 3,577,640, Cl. 32-32.

Leerkamp, John R.; See—
Aprill, Theophil, Jr.; and Leerkamp, John R., 3,577,768.

Legrand; See—
Nicolas, Jean-Pierre Edmond, 3,576,962.

Lehmann, Claude; and Renk, Ernst, to Geigy Chemical Corporation. Methods for producing muscle relaxant and CNS-depressant effects with 3-amino-4-phenyl furazan and composition therefor. 3,577,544, Cl. 424-272.

Leitnaker, James M.; See—
Beatty, Ronald L.; Leitnaker, James M.; and Notz, Karl J., Jr., 3,577,485.

Le Noir, Fred W., to Allied Chemical Corporation. Process for commingling crimped yarn. 3,577,615, Cl. 28-72.12

Lense, Robert F., to Riegel Paper Corporation. Pivot assembly for mounting swingable operating mechanisms of a packaging machine. 3,577,704, Cl. 53-386.

Lesniewski, Matthew W., to Monsanto Company. Method of photographically producing plated-through holes in printed circuit boards. 3,577,239, Cl. 96-36.2

Levan, Ambrose E.; and Tatum, David, to Ametek, Inc. Process for cleaning fabrics. 3,577,214, Cl. 8-137.

Levenson, Norton J.; See—
Fischer, Raymond C.; and Levenson, Norton J., 3,577,605.

Lever Brothers Company; See—
Vinson, Leonard J., 3,577,539.

Levi, Ralph S.; See—
Schneller, George H.; and Levi, Ralph S., 3,577,532.

Levy, Newton, Jr.; See—
Sanchez, Moises Gali; Levy, Newton, Jr.; and Rettew, Richard R., 3,577,487.

Levy, Ralph, to Microwave Development Laboratories, Inc. Waveguide filter having sequence of thick capacitive irises. 3,577,104, Cl. 333-73.

Lewin, Seymour Z., to New York University. Preservation of limestone structures. 3,577,244, Cl. 106-12.

Liberti, Felix P.; See—
Reiter, Richard W.; and Liberti, Felix P., 3,577,311.

Liebschutz, Lynn C., to International Business Machines Corporation. Process for making a magnetic data storage element. 3,577,326, Cl. 204-43.

Liechti, Peter; Guglielmetti, Leonardo; Maeder, Erwin; and Siegrist, Adolf Emil, to Ciba Limited. 6-Phenylbenzazoyl derivatives. 3,577,411, Cl. 260-240.

Liepins, Gunar. Torque measuring tool. 3,577,778, Cl. 73-139.

Lightner, Gene E.; Muhlestein, Howard Blair; and Green, Louis E., to Hewlett-Packard Company. Method and apparatus for automatically cleaning syringes. 3,577,279, Cl. 134-23.

Lilly, Eli, and Company; See—
Gorman, Marvin; and Hamill, Robert L., 3,577,531.

Lindsay, Jacques K., to Eastman Kodak Company. Ferrocene dyes and photographic elements. 3,577,238, Cl. 96-28.

Link, Darl L., to Hoover Ball and Bearing Company, mesne. Method of making a trim molding. 3,577,626, Cl. 29-445.

Linsker, Eugene; See—
Alexander, Robert H.; Falter, Ronald C.; Ringer, Cecil D.; and Linsker, Eugene, 3,577,807.

Lipski, Abraham Ichok. Method of manufacturing a girder with a web of reinforced and/or prestressed concrete. 3,577,504, Cl. 264-255.

Litt, Morton Herbert; See—
Anello, Louis Gene; Sweeney, Richard Francis; and Litt, Morton Herbert, 3,577,465.

Little, Arthur D., Inc.; See—
Hidden, William P., 3,577,613.

Margolin, Stanley V.; Glaser, Paul W.; and Gallagher, Leonard V., 3,577,610.

Lloyd, Norman C.; See—
Owen, William J.; and Lloyd, Norman C., 3,577,390.

Lloyd, Robert E.; See—
Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.

Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.

Lobb, Edward Vernon; and Coburn, Raymond W., Jr., to Colgil Enterprises, Inc. Collapsible surfboard or sailboat. 3,577,576, Cl. 9-2.

Lokkart, Hendricus Johannes; See—
Raffaelli, Joseph Gino; and Lokkart, Hendricus Johannes, 3,577,011.

Long, Joseph N., to Vilter Manufacturing Corporation. Control for refrigeration systems. 3,577,743, Cl. 62-212.

Longacre, Alan, to Fluor Corporation. Slurry distributor. 3,577,223, Cl. 23-259.1

Longoria, Juan, III, to Dow Chemical Company. The. Polyamines stabilized with aminocarboxylate chelants. 3,577,556, Cl. 260-45.85

Longsdorff, Richard W., to RCA Corporation. Circuit for starting and maintaining a discharge through a gas discharge tube. 3,577,174, Cl. 315-170.

Lowe, Donald S.; See—
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., 3,576,999.

Lucius & Bruning; See—
Mauz, Otto; and Prinz, Eberhard, 3,577,384.

Luhby, Adrian Leonard. Process and compositions for differential diagnosis of the megaloblastic anemia syndromes. 3,577,511, Cl. 424-9.

Lunsford, Carl Dalton; and Helsley, Grover Cleveland, to Robins, A.H., Company, Incorporated. 1-Substituted-3-amido-pyrrolidines. 3,577,440, Cl. 260-326.3

Lyon, William H., to KMS Industries, Inc. Teaching apparatus. 3,577,656, Cl. 35-9.

Maass, Joachim A. Reversible counter with read out. 3,576,975, Cl. 235-92.

Machida, Takuo; and Nakagawa, Masataka, to Sumitomo Chemical Company, Ltd. Process for recovering a chromate and cupric oxide by decomposition of a catalyst or waste catalyst of copper chromite. 3,577,217, Cl. 23-56.

Madurski, Joseph P.; Presley, Rex W.; and Rothfusz, Ralph W., to Bendix Corporation. The. Self commutated electromotive device. 3,577,049, Cl. 318-138.

Maeder, Arthur; See—
Guth, Christian; Nachbur, Hermann; and Maeder, Arthur, 3,577,270.

Maeder, Erwin; See—
Liechti, Peter; Guglielmetti, Leonardo; Maeder, Erwin; and Siegrist, Adolf Emil, 3,577,411.

Magee, James A.; See—
Fisher, Robert D.; and Magee, James A., 3,577,277.

Magnavox Company, The; See—
Adams, James S., 3,577,083.

Richeson, William E., Jr., 3,577,060.

Maguire, John; Uyeda, Tim M.; and Wahler, Theodore George, to Samsonite Corporation. Amusement device. 3,577,674, Cl. 46-41.

Mahrt, Gunther; See—
Goldammer, Georg; and Mahrt, Gunther, 3,577,599.

Maier, John E., to Minnesota Mining and Manufacturing Company. Product and process. 3,577,386, Cl. 260-47.

Maier, Richard; See—
Bogner, Gunther; and Maier, Richard, 3,577,151.

Maitland, Robert Thomas, to Bendix Corporation, The. Electronics card extractor. 3,577,113, Cl. 339-17.

Malli, Joseph, Jr.; See—
Kessler, Theodore; Sharkey, Andrew G., Jr.; Malli, Joseph, Jr.; and Friedel, Robert A., 3,577,337.

Mallory, P. R., & Co., Inc.; See—
Wallis, George; and Dorsey, John J., 3,577,629.

Malnar, Leon; and Brun, Henri, to CSF-Compagnie Generale de Telegraphie Sans Fil. Optical resonance cells containing an alloy of an alkali metal with another metal. 3,577,069, Cl. 324-0.5

Manchester Tool & Die, Inc.; See—
Bentschneider, Eugene E., 3,577,624.

Manuel, Eric; and Moore, James H., Jr., to General Electric Company. Rapid loading of steam turbines. 3,577,733, Cl. 60-105.

Manz, Ulrich; See—
Gutmann, Hugo; Manz, Ulrich; and Schwieter, Ulrich, 3,577,464.

Marathon Oil Company; See—
Argabright, Perry A.; Phillips, Brian L.; and Sinkey, Vernon J., 3,577,391.

Maremount Corporation; See—
Page, John D., 3,577,723.

Margolin, Stanley V.; Glaser, Paul W.; and Gallagher, Leonard V., to Little, Arthur D., Inc. Apparatus for manufacturing prestressed concrete members. 3,577,610, Cl. 25-2.

Margardt Industrial Products Co.; See—
Wilson, Harlan J., 3,576,991.

Mariani, Remo; and Geisinger, George H., to Thomas & Betts Corporation. Article fastening device. 3,577,601, Cl. 24-16.

Marine Swimming Pool Equipment Co.; See—
Bellinson, Bernard; and Young, Henry R., 3,577,571.

Marinus, Korstiaan J. V.; and Fontijn, Wilhelmus J., to American Enka Corporation. Manufacture of a multicomponent polymeric product. 3,577,308, Cl. 161-176.

Marker, John R., Jr.; See—
Arntz, Robert L.; and Marker, John R., Jr., 3,577,110.

Marley, James A. Forced air diffuser. 3,577,654, Cl. 34-231.

Marlow, William Henry; See—
Bott, George Spencer; and Marlow, William Henry, 3,577,701.

Marsee, Frederick J.; See—
Warren, Joel A.; and Marsee, Frederick J., 3,577,727.

Marsh, Frederick S.; See—
Castro, Anthony J.; Marsh, Frederick S.; Kinney, Layton E.; and Fischl, Frank J., 3,577,370.

Marshall, Donald, John; See—
Bliven, Roger; Allen, Frank L., Jr.; and Davis, John R., 3,577,271.

Martin, Thomas B.; and Zadel, Henry J., to RCA Corporation. Sequence and gate with resetting means. 3,577,087, Cl. 328-110.

Martinez, Mario; and Monday, Colin, said Monday assor. to said Martinez. Method and apparatus for loading bobbins or reels into and out of cradles or mountings. 3,577,719, Cl. 57-34.

Massey-Ferguson Services N.V.; See—
Todeschini, Eugenio, 3,577,797.

Masuda, Ryunosuke; See—
Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihasi, Hikoyuki; and Ishitobi, Katsuya, 3,577,498.

Masuko, Fujio; See—
Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.

Mathes, Rudolf; See—
Brandl, Walter; and Mathes, Rudolf, 3,577,809.

Matsugu, Tomoyuki; Notomi, Ryota; and Kanoh, Teruchika, to Kohjin Company Limited. Method for heat-setting biaxially stretched films of thermoplastic materials. 3,577,497, Cl. 264-159.

Matsukura, Yasuo; See—
Wada, Toshio; Matsukura, Yasuo; and Ohta, Kuniichi, 3,577,018.

Matsumoto, Seiji; See—
Sato, Masamichi; Tamai, Yasuo; Matsumoto, Seiji; and Akashi, Goro, 3,577,259.

Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihasi, Hikoyuki; and Ishitobi, Katsuya, to Toyo Boseki Kabushiki Kaisha. Method of producing crimped polypropylene fibers. 3,577,498, Cl. 264-168.

Matsushita Electric Industrial Co., Ltd.; See—
Obata, Shuichi, 3,576,955.

Matui, Juniro; See—
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniro; and Uono, Fumito, 3,577,623.

Mauz, Otto; and Prinz, Eberhard, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Stabilized moulding compositions form polymers of α -olefins. 3,577,384, Cl. 260-45.85

Maxey, Andrew W.; See—
Ardary, Zane L.; Maxey, Andrew W.; and Reynolds, Carl D., 3,577,344.

Mayfield, Georgia P.; See—
Zic, John A.; Hill, George F.; and Mayfield, Ross M., 3,577,283.

Mayfield, Ross M.; See—
Zic, John A.; Hill, George F.; and Mayfield, Ross M., 3,577,283.

Mazzarella, Louis; See—
Ciampa, Fred A.; Serafini, Angelo; and Mazzarella, Louis, 3,577,574.

Mc Cain, Charles N.; See—
Hendrickson, Hubert E.; and Mc Cain, Charles N., 3,577,368.

McCain, Charles N.; See—
Hendrickson, Hubert E.; and McCain, Charles N., 3,577,369.

McCall, Amiel J.; Elms, Ronald D.; and Rice, Larry D., to Allen-Bradley Company, mesne. Motion monitor system. 3,576,979, Cl. 235-151.11

McCarty, Horace G.; Halls, Lawrence M.; Howell, Edmund O.; and Hurlburt, Joseph C., to Sperry Rand Corporation. Mowing device. 3,577,716, Cl. 56-259.

McCarty, Horace G.; Lausch, Henry N.; and Hudson, Earl A., to Sperry Rand Corporation. Header lock means for agricultural harvesting machines. 3,577,713, Cl. 56-23.

Mc Clenathan, John A.; and Nielsen, Donald L., to Beloit Corporation. Web drying tunnel. 3,577,653, Cl. 34-156.

McColley, Daniel; See—
Ricards, Charles L.; and McColley, Daniel, 3,577,591.

Mc Collum, Hugh Evan; See—
Bolger, Justin C.; Mc Collum, Hugh Evan; and Hausslein, Robert William, 3,577,313.

McCormick, Jerry Robert Daniel; and Arnold, Nancy Hazlett, to American Cyanamid Company. 3-(1,8-Dimethoxy-4-methyl-2-naphthyl)-4,6-dialkoxy-5-substituted phthalides. 3,577,439, Cl. 260-343.3

McCormick, Richard E.; See—
Welsh, Neil R.; and McCormick, Richard E., 3,577,031.

Mc Donough, Everett G.; and Edman, Walter W., to Zotos International, Inc. Two phase hair conditioner compositions. 3,577,528, Cl. 424-70.

- McDuff, James M.: See—
Parrish, Donald B.; and McDuff, James M., 3,577,554.
- McGee, Joe H., to Sperry Rand Corporation. Brushless D.C. motor including a variable attenuator fed commutator. 3,577,053, Cl. 318-254.
- McGill, Charles K.; and Campbell, George W., Jr., to Reilly Tar & Chemical Corporation. 4-(4-Tetrahydropyranyl)pyridines. 3,577,426, Cl. 260-297.
- McGraw-Edison Company: See—
McStrack, Darrel D.; and Burrage, Lawrence M., 3,577,032.
- McIntosh, Harold A., to Robertshaw Controls Company. Electrical control system. 3,577,066, Cl. 323-69.
- McKenna, Bernard D., to Kaiser Aluminum & Chemical Corporation. Magnesium aluminate spinel bonded refractory. 3,577,247, Cl. 106-62.
- McKeown, James J., to Minnesota Mining and Manufacturing Company. Insulated electrical conductors having corona resistant polymeric insulation containing organo-metallic compounds. 3,577,346, Cl. 252-63.5
- McKone, Donald B.: See—
Rachal, Francis; and McKone, Donald B., 3,577,091.
- McLeod, William J.: See—
Smith, Calvin S.; and McLeod, William J., 3,577,221.
- McMillin, John V., to Westinghouse Learning Corporation. Code translation system code translation system. 3,577,142, Cl. 340-347.
- McNay, Ralph E.: See—
Forrester, Robert A.; and McNay, Ralph E., 3,577,555.
- McNeel, William O.; and Erath, Louis W., to Geo Space Corporation. Low distortion seismometer. 3,577,184, Cl. 340-17.
- McNeil Corporation: See—
Smith, Kave A.; and Ladendecker, Henry L., 3,577,817.
- McNeil Laboratories, Inc.: See—
Plotnicks, Janis, 3,577,430.
- McNulty, John G.; and Walsh, William L., to Gulf Research & Development Company. Halogen interchange process. 3,577,471, Cl. 260-656.
- McStrack, Darrel D.; and Burrage, Lawrence M., to McGraw-Edison Company. Series gap lightning arrester with arc extinguishing chambers. 3,577,032, Cl. 315-36.
- Mead Corporation, The: See—
Beam, Dale R., 3,577,198.
- Mead, Louis W.: See—
Deutsch, Marshall E.; Mead, Louis W.; and Nagy, Zoltan, 3,576,998.
- Means, Ray H.; Kussman, Michael; Wade, Jack; and Vodra, Victor H., to American Beef Packers, Inc. Method of preparing edible animal feet. 3,577,241, Cl. 99-7.
- Means, T. W., & Company: See—
Impulitti, Ector P., 3,577,215.
- Medendorp, Roger L., to Kirkhof Manufacturing Corporation. Trim press assembly. 3,577,821, Cl. 83-238.
- Megna, Ignazio Salvatore; and Koroscil, Anthony, to American Cyanamid Company. Fiber prepared from polyester based polyurethane prepolymer. 3,577,388, Cl. 260-75.
- Meier, Peter J.: See—
Hertig, Max; and Meier, Peter J., 3,577,751.
Hertig, Max; and Meier, Peter J., 3,577,752.
- Melaas, Bruce Allen, to Celanese Corporation. Method of producing oxetane esters. 3,577,438, Cl. 260-333.
- Meltzer, Robert I.: See—
Kaminsky, Daniel E.; Meltzer, Robert I.; and Shavel, John, Jr., 3,577,441.
- Mensen, Herbert: See—
Lanooy, Cornelis; and Mensen, Herbert, 3,576,956.
- Mercer Alloys Corporation: See—
Pesses, Marvin, 3,577,231.
- Mercer, John F. Dry air refrigerated display case system. 3,577,744, Cl. 62-256.
- Merck & Co., Inc.: See—
Cragoe, Edward J., Jr., 3,577,409.
Cragoe, Edward J., Jr.; and Shepard, Kenneth L., 3,577,418.
Howe, Eugene E.; and Rosenblum, Charles, 3,577,537.
Jones, Robert E.; and Reynolds, Harold, 3,577,455.
- Mershon, Howard Bruce. Athletic shoe and cleat. 3,577,663, Cl. 36-67.
- Metzger, Hermann: See—
Kotzschmar, Arnold; Metzger, Hermann; Rothe, Richard Reinhard Gustav Adolf; and Seidel, Willy, 3,577,483.
- Meyer, Gerhard: See—
Kersten, Hilde; Siggel, Erhard; and Meyer, Gerhard, 3,577,387.
- Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, to Squibb, E. R., & Sons, Inc. Janiemycin. 3,577,530, Cl. 424-118.
- Michel, Charles Allan: See—
Putzrath, Franz Ludwig; and Michel, Charles Allan, 3,577,065.
- Microphor, Inc.: See—
Burton, Robert Edward, 3,577,678.
- Microwave Development Laboratories, Inc.: See—
Levy, Ralph, 3,577,104.
- Midland Silicones Limited: See—
Owen, William J.; and Lloyd, Norman C., 3,577,390.
- Mielke, James E.: See—
Benford, Charles L., Jr.; and Mielke, James E., 3,577,256.
- Mikami, Masakatsu: See—
Kubota, Ikuo; Mikami, Masakatsu; and Kitamura, Seikichi, 3,577,517.
- Miles Laboratories, Inc.: See—
Stolar, Morris Emanuel; and Feinberg, Joseph George, 3,577,523.
Welsh, Thomas Laurence; Peterson, Donald Leroy; Palermo, Blasey Thomas; and Hoss, George Carr, 3,577,490.
Welsh, Thomas Laurence; and Tomaich, George Ronald, 3,577,492.
- Miles Laboratories, Incorporated: See—
Cox, Peter Henry, 3,577,491.
- Miller, Arthur, to Hewlett-Packard Company. Bridge circuit for differentially measuring capacitance. 3,577,072, Cl. 324-60.
- Miller, Bernard; and Gund, Tamara Helen Mladineo, to American Cyanamid Company. Method of controlling insects and arachnids with tetrahydroquinoxalanyl phosphates or thio-phosphates. 3,577,536, Cl. 424-200.
- Miller, Edward Francis: See—
Pountney, Clifford Harold; and Miller, Edward Francis, 3,577,281.
- Miller, J. W.: See—
Kislin, Benjamin; and Miller, J. W., 3,577,566.
- Miller, Laura H.: See—
Wideburg, Norman E.; and Miller, Laura H., 3,577,422.
- Miller, Robert A.: See—
Hall, Samuel S.; Miller, Robert A.; and Riley, Philip R. H., 3,577,002.
- Miller, Walter E., Jr.: See—
Duke, Jimmy R.; and Miller, Walter E., Jr., 3,577,017.
- Millham, Ernest H.: See—
Frushour, James E.; Millham, Ernest H.; and Orloff, James E., 3,577,076.
- Milwaukee Cylinder Corporation: See—
Skelton, Darold M., 3,577,833.
- Minnesota Mining and Manufacturing Company: See—
Blomgren, Jack P., 3,577,173.
Harrington, Joseph K., 3,577,394.
Maier, John E., 3,577,386.
McKeown, James J., 3,577,346.
- Mintz, Milton S.: See—
Lacey, Robert E.; and Mintz, Milton S., 3,577,331.
- Mitchell, Michael E., to General Electric Company. Inversion-tolerant random error correcting digital data transmission system. 3,577,186, Cl. 340-146.1
- Mitsubishi Rayon Co., Ltd.: See—
Kubota, Ikuo; Mikami, Masakatsu; and Kitamura, Seikichi, 3,577,517.
- Miyazaki, Masayuki: See—
Okamoto, Kiyokazu; and Miyazaki, Masayuki, 3,576,981.
- Mobil Oil Corporation: See—
Lawrence, Philip L., 3,576,985.
- Moehlman, Vernon C.; and Klein, Robert J., to Olin Corporation. Molding powder for projectable target. 3,577,251, Cl. 106-284.
- Molex Incorporated: See—
Baumanis, Bruno, 3,577,116.
- Moller, Helmut: See—
Krautwald, Herbert; Moller, Helmut; and Siepmann, Richard, 3,577,182.
- Moller, Leopold, to Imperial Smelting Corporation (N.S.C.) Limited. Sulphur dioxide drying. 3,577,706, Cl. 55-30.
- Molnar, Robert J.; Parfomak, Walter; Molnar, Robert J.; and Parfomak, Walter, to Bendix Corporation, The. Bendix Corporation, The Pulse responsive control network. 3,577,126, Cl. 340-167.
- Molnar, Robert J.: See—
Molnar, Robert J.; Parfomak, Walter; Molnar, Robert J.; and Parfomak, Walter, 3,577,126.
- Monday, Colin: See—
Martinez, Mario; and Monday, Colin, 3,577,719.
- Monestam, Eskil, to Allmanna Svenska Elektriska Aktiebolaget. Method of manufacturing components from a part projecting from a larger part, having slim and/or elongated form. 3,577,761, Cl. 72-256.
- Monestier, Ottorino. Block element of variable angular form. 3,577,673, Cl. 46-24.
- Monick, John Alexander. Water-soluble scouring composition. 3,577,347, Cl. 252-99.
- Monsanto Company: See—
Al-Roy, John D., 3,577,594.
Bertoglio, Joseph; Deming, Philip L.; Eckert, Joyce G.; and Shafer, James R., 3,577,765.
Hamm, Philip C., 3,577,538.
Hamm, Philip C., 3,577,542.
Hammann, William C.; and Schisla, Robert M., 3,577,361.
Isaksen, Robert A., 3,577,374.
Kerst, Al F., 3,577,382.
Knudsen, John P., 3,577,499.
Le Blanc, John R., 3,577,437.
Lesniewski, Matthew W., 3,577,239.
Mortimer, George A., 3,577,399.
Ort, Morris R.; and Mottus, Edward H., 3,577,450.
Serrano, Mario; and Wolf, William D., 3,577,589.
Thompson, Quentin E., 3,577,452.
- Montagna, Dominic: See—
Ruppert, John A.; and Montagna, Dominic, 3,577,232.

- Montague, Herbert R., to Power Concepts Corporation. Motor speed control circuit having variable reactive impedance means. 3,577,051, Cl. 318-212.
- Montarnal, Roger: See—
Boutry, Pierre; Daumas, Jean Claude; and Montarnal, Roger, 3,577,477.
- Montecatini Edison S.p.A.: See—
Torti, Luigi; and Bertelli, Guido, 3,577,310.
- Monterey Research Laboratory, Inc.: See—
Beal, John O., 3,577,763.
- Montgomery, William C., Jr., to Shell Oil Company. Fast settling, stable amplifier circuit. 3,577,090, Cl. 330-69.
- Mooney, G. Edgar, Jr.: See—
Nirschl, Joseph C.; and Mooney, G. Edgar, Jr., 3,576,995.
- Moore, Dennis B.: See—
Whitfield, Marshall G.; Parzuchowski, Richard S.; and Moore, Dennis B., 3,577,268.
- Moore, James H., Jr.: See—
Manuel, Eric; and Moore, James H., Jr., 3,577,733.
- Moore, John R.: See—
Cramer, Leslie Dick; and Moore, John R., 3,577,818.
- Moorman, Charles J.; and Parmater, John Q., to Bendix Corporation. The Time of flight mass spectrometer having both linear and curved drift regions whose energy dispersions with time are mutually compensatory. 3,576,992, Cl. 250-41.9
- Mori, Yoichi: See—
Ohno, Kazuhiko; and Mori, Yoichi, 3,577,804.
Ohno, Kazuhiko; and Mori, Yoichi, 3,577,805.
- Moriconi, Joseph H.: See—
Jacknow, Burton B.; and Moriconi, Joseph H., 3,577,345.
- Morrell, Jacques C. Composite high energy solid rocket propellants and process for same. 3,577,289, Cl. 149-19.
- Morris, Philip, Incorporated: See—
Braginetz, Paul A., 3,577,637.
- Morrow, Robert H.; and Perneski, Anthony J., to Bell Telephone Laboratories, Incorporated. Domain propagation arrangement. 3,577,131, Cl. 340-174.
- Mortimer, George A., to Monsanto Company. Ethylene interpolymers. 3,577,399, Cl. 260-88.1
- Motorola, Inc.: See—
Cannalte, Gary A., 3,577,080.
Cherry, James R., 3,576,970.
Freyling, Edward N., Jr.; and Gregson, Robert E., 3,577,010.
- Mottus, Edward H.: See—
Ort, Morris R.; and Mottus, Edward H., 3,577,450.
- Moulton, David M.: See—
Shaffer, James H.; Moulton, David M.; and Grimes, Warren R., 3,577,225.
- Moyle, Clarence L., to Dow Chemical Company, The. N-(Phenoxy) phenyl-salicylamides and their utilization as molluscicides. 3,577,550, Cl. 424-324.
- Moyson, Joseph, to General Electric Company. Monolithic compound thyristor with a pilot portion having a metallic electrode with finger portions formed thereon. 3,577,046, Cl. 317-235.
- Mrmak, Wencle J. Ambulance stretcher device. 3,577,573, Cl. 5-82.
- Mueller, Curt: See—
Entschel, Roland; Mueller, Curt; and Steinemann, Willy, 3,577,404.
- Mueller, Otto. Variable torque transmission. 3,577,803, Cl. 74-665.
- Muhlestein, Howard Blair: See—
Lightner, Gene E.; Muhlestein, Howard Blair; and Green, Louis E., 3,577,279.
- Munro, Alexander John: See—
Taplin, John Francis; and Munro, Alexander John, 3,577,790.
- Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, to Yamanouchi Pharmaceutical Co., Ltd. Methods for treating pain, inflammation and cough. 3,577,551, Cl. 424-325.
- Myers, Dirck V., to Squibb, E. R., & Sons, Inc. Method of promoting osteogenesis. 3,577,540, Cl. 424-244.
- Myers, Robert Lee: See—
Voight, Heinz Kurt Walter; and Myers, Robert Lee, 3,576,987.
- Myles, William J.; and Kunkel, Roland K., to Celanese Corporation. Fiber product and process. 3,577,213, Cl. 8-130.
- Nachbur, Hermann: See—
Guth, Christian; Nachbur, Hermann; and Maeder, Arthur, 3,577,270.
- Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, to Sumitomo Chemical Company, Ltd. Method for producing 5-isopropylidene-2-norbornene. 3,577,473, Cl. 260-666.
- Nagy, Ernest J., to Pullman Incorporated. Closure gate actuating mechanisms for hopper discharge arrangement. 3,577,680, Cl. 49-358.
- Nagy, Zoltan: See—
Deutsch, Marshall E.; Mead, Louis W.; and Nagy, Zoltan, 3,576,998.
- Nakagawa, Masataka: See—
Machida, Takuo; and Nakagawa, Masataka, 3,577,217.
- Nakajima, Isao: See—
Tamura, Kihachi; Nakajima, Isao; and Inoue, Kaname, 3,577,362.
- Nakakita, Tsuneo: See—
Inagaki, Junpei; Sakamoto, Moriyoshi; Nakakita, Tsuneo; and Kitamura, Hiroyuki, 3,577,024.
- Nakamura, Hiroshi: See—
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniro; and Uono, Fumito, 3,577,623.
- Nakanishi, Michio; Arimura, Katsuo; Imamura, Hiroshi; and Kobayakawa, Toshihiro, to Yoshitomi Pharmaceutical Industries, Ltd. 8-(1,4-Benzodioxan-2-ylmethyl)-3-oxo-1-thia-4,8-diazaspiro[4.5]decanes. 3,577,425, Cl. 260-293.4
- Nanri, Shosuke: See—
Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihasi, Hikoyuki; and Ishitobi, Katsuya, 3,577,498.
- Nardulli, Antonio, to Texas Instruments, Incorporated. Miniaturized snap acting thermostatic switch. 3,577,111, Cl. 337-89.
- National Distillers and Chemical Corporation: See—
Corbett, Herbert O., 3,577,507.
- National Lead Company: See—
Foss, Warren M., 3,577,253.
- National Patent Development Corporation: See—
Gould, Francis E.; and Shepherd, Thomas H., 3,577,516.
Shepherd, Thomas H.; and Gould, Francis E., 3,577,512.
Shepherd, Thomas H.; and Gould, Francis E., 3,577,518.
- National Starch and Chemical Corporation: See—
Flanagan, Thomas P.; and Kaye, Irving I., 3,577,372.
Reiter, Richard W.; and Liberti, Felix P., 3,577,311.
- Neely, Joseph E., to Kaiser Aluminum & Chemical Corporation. Refractory shape with prereacted grain. 3,577,246, Cl. 106-59.
- Nen-Picker Radiopharmaceuticals, Inc.: See—
Deutsch, Marshall E.; Mead, Louis W.; and Nagy, Zoltan, 3,576,998.
- Neo Dynamics, Inc.: See—
Hauer, Werner, 3,576,953.
- Neptune Meter Company: See—
Taylor, James R.; and Clements, Thomas C., 3,577,123.
- Nercessian, Sarkis, to Forbro Design Corporation. Automatic error detection and indication in a remotely programmable regulated power supply. 3,577,064, Cl. 323-20.
- Nesbitt, Stephen J.; and Knapp, Edward M. Microwave heating in the desalination of water. 3,577,322, Cl. 203-11.
- Netta, Louis A., to Thomas & Betts Corporation. Locking device for an eccentric member. 3,577,801, Cl. 74-571.
- Neumann, Manfred E.: See—
Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., 3,577,050.
- New York University: See—
Lewin, Seymour Z., 3,577,244.
- Newage Lyon Limited: See—
Wyles, Peter J., 3,577,061.
- Nibbrig, Reinhold: See—
Schmidt, Burkhard; and Nibbrig, Reinhold, 3,577,787.
- Nichols, John A., to Industrial Air Company, Inc. Apparatus for air-treating sheet material surfaces and the like. 3,577,651, Cl. 34-155.
- Nicolas, Jean-Pierre Edmond, to Legrand. Push-contact device. 3,576,962, Cl. 200-167.
- Nielsen, Donald L.: See—
Mc Clenathan, John A.; and Nielsen, Donald L., 3,577,653.
- Nielsen, Peter Adams; Cooper, Murray Sam; and Doyno, Ernest Robert, to American Cyanamid Company. Large scale cultivation of Bordetella pertussis cells for vaccine production. 3,577,319, Cl. 195-96.
- Niemann, George W.; and Stehlin, Robert A., to Texas Instruments, Incorporated. Monostable multivibrator with low power requirements. 3,577,015, Cl. 307-273.
- Niessner, Erwin: See—
Hornbogen, Erhard; Niessner, Erwin; and Buck, Gert, 3,577,762.
- Nippon Columbia Company, Limited: See—
Yahagi, Koichi, 3,577,152.
- Nippon Electric Company: See—
Okamoto, Kiyokazu; and Miyazaki, Masayuki, 3,576,981.
Wada, Toshio; Matsukura, Yasuo; and Ohta, Kuniichi, 3,577,018.
Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.
- Nippon Gakki Seizo Kabushiki Kaisha: See—
Ohno, Junji, 3,576,958.
- Nippon Hume Pipe Co., Ltd.: See—
Ichihara, Koreyoshi, 3,577,505.
- Nirona-Werke, Nier & Elmer KG: See—
Eissfeldt, Werner, 3,577,796.
- Nirschl, Joseph C.; and Mooney, G. Edgar, Jr., to United States of America, Army. Radiation survey meter counting loss compensation circuit. 3,576,995, Cl. 250-83.3
- Nishio, Fumihiko; Ohi, Reiichi; and Tajima, Tatsuya, to Fuji Shashim Film Kabushiki Kaisha. Diffusion transfer photographic materials. 3,577,240, Cl. 96-52.
- Nissan Jidosha Kabushiki Kaisha: See—
Ohno, Kazuhiko; and Mori, Yoichi, 3,577,804.
Ohno, Kazuhiko; and Mori, Yoichi, 3,577,805.
- Nordin, Tore, to Allmanna Svenska Elektriska Aktiebolaget. Plural motor anti-slip drive control. 3,577,048, Cl. 318-52.
- Nordstrom, John D., to Ford Motor Company. Polyester-siloxane coated product. 3,577,262, Cl. 117-93.31
- Nordstrom, John D., to Ford Motor Company. Epoxy resin-siloxane coated article. 3,577,263, Cl. 117-93.31
- Nordstrom, John D., to Ford Motor Company. Siloxane-unsaturated ester coated product. 3,577,264, Cl. 117-93.31
- Nordstrom, John D., to Ford Motor Company. Vinyl resin-siloxane coated article. 3,577,265, Cl. 117-93.31

Norgren, Philip E.: See—
Preston, Kendall, Jr.; and Norgren, Philip E., 3,577,267.
North American Rockwell Corporation: See—
Dyer, George A.; and Kohler, Emil, 3,577,057.
Northern Electric Company Limited: See—
Varhelyi, Leslie G., 3,577,106.
Northrop Corporation: See—
Hawley, Opie D., 3,577,178.
Parks, Earl E., 3,577,792.
Nortland, Dena S. Device for hand knitting, 3,577,748, Cl. 66-4.
Norwich, John F.; and Roesener, Edward J., Jr., to General Motors Corporation. Aluminum diffusion technique, 3,577,287, Cl.
Norwood, Richard E., to International Business Machines Corporation. Fluid-actuated translating apparatus, 3,576,971, Cl. 235-61.11
Notomi, Ryota: See—
Matsugu, Tomoyuki; Notomi, Ryota; and Kanoh, Teruchika, 3,577,497.
Notz, Karl J., Jr.: See—
Beatty, Ronald L.; Leitnaker, James M.; and Notz, Karl J., Jr., 3,577,485.
Novelart Manufacturing Company: See—
Klein, Charles H.; and Haley, James K., 3,577,299.
Nozaki, Kenzie, to Shell Oil Company. Production of allylic ethers, 3,577,466, Cl. 260-614.
Nussbaumer, Henri Jean: See—
Lautier, Alex Honore; Nussbaumer, Henri Jean; and Pierret, Jean Marc, 3,577,082.
Nutting, William. Modular rigid block-type doll house construction toy, 3,577,672, Cl. 46-19.
Nylen, Gustav P. Double-gap spark plug, 3,577,170, Cl. 313-123.
O'Neill, Robert W.: See—
United States of America, National Aeronautics and Space Administration, Administrator, 3,577,014.
Obata, Shuichi, to Matsushita Electric Industrial Co., Ltd. Armature assembly for magnetic type phonograph pickup, 3,576,955, Cl. 179-100.41
Obeda, Edward G., to Branson Instruments, Incorporated. Method for joining thermoplastic members by sonic or ultrasonic energy, 3,577,292, Cl. 156-73.
Oberhofer, Martin; and Jaspert, Jurgen, to European Atomic Energy Community (Euratom). Radiation dosimeter having sensitive material containing lithium hydride, 3,577,161, Cl. 250-71.
O'Brien, Leo X.: See—
Walker, Ambrose D., 3,577,811.
O'Brien, William J.; and Downey, Raymond E., to Dart Industries Inc. Low temperature tar tape, 3,577,269, Cl. 117-122.
Offermann, Klaus: See—
Kohler, Armin; Von Falkai, Bela; Offermann, Klaus; and Reichle, Alfred, 3,577,500.
Ohi, Reiichi: See—
Nishio, Fumihiko; Ohi, Reiichi; and Tajima, Tatsuya, 3,577,240.
Ohno, Junji, to Nippon Gakki Seizo Kabushiki Kaisha. Switching device with improved tablet actuator means, 3,576,958, Cl. 200-1.
Ohno, Kazuhiko; and Mori, Yoichi, to Nissan Jidosha Kabushiki Kaisha. Torque split type automatic speed change device, 3,577,804, Cl. 74-688.
Ohno, Kazuhiko; and Mori, Yoichi, to Nissan Jidosha Kabushiki Kaisha. Torque split type automatic speed change device, 3,577,805, Cl. 74-688.
Ohta, Kuniichi: See—
Wada, Toshio; Matsukura, Yasuo; and Ohta, Kuniichi, 3,577,018.
Okamoto, Kiyokazu; and Miyazaki, Masayuki, to Nippon Electric Company. Digital interpolator with a corrective distribution command device, 3,576,981, Cl. 235-152.
Olin Corporation: See—
Mochlman, Vernon C.; and Klein, Robert J., 3,577,251.
Olin Mathieson Chemical Corporation: See—
Billett, William J.; and Vartanian, Edwin S., 3,577,827.
Gambardella, Mario A., 3,577,519.
Oliphant, William J., to United States of America, Navy, mesne. Vaporizer cup, 3,577,730, Cl. 60-39.71
Oliver, Donald W.; and Wendt, Gerhard R., to American Home Products Corporation. 19-Norsteroidal 3-chloro-3,5-dienes, 3,577,445, Cl. 260-397.5
Olsen, Donald B.: See—
Reynolds, Harold C.; and Olsen, Donald B., 3,577,535.
Olympia Werke AG: See—
Schmidt, Burkhard; and Nibbrig, Reinhold, 3,577,787.
Omholt, Ray E., to Powerlock Floors, Inc. Flooring systems, 3,577,694, Cl. 52-483.
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniro; and Uono, Fumito, to Toyo Bearing Manufacturing Company Limited. Apparatus and method for automatically assembling anti-friction bearings, 3,577,623, Cl. 29-201.
Oosterhof, Hendricus A.: See—
Selman, Jan; and Oosterhof, Hendricus A., 3,577,502.
Ort, Morris R.; and Mottus, Edward H., to Monsanto Company. Process for preparing methylene bis-(aluminum dihalides), 3,577,450, Cl. 260-448.
Ortelli, Aurelio, to Riva Calzoni S.p.A. Hydraulic motor, 3,577,830, Cl. 92-66.
Ortloff, James E.: See—
Frushour, James E.; Millham, Ernest H.; and Ortloff, James E., 3,577,076.
Oshima, Ichiro. Helmet for accident prevention, 3,577,561, Cl. 2-3.

Ostrand, George W.: See—
Pendleton, Wesley W.; and Ostrand, George W., 3,577,309.
Ott, Hans, to Sandoz-Wander, Inc. Benzo[1,5]diazocinones, 3,577,557, Cl. 260-239.3
Ott, Heinrich: See—
Ehrhart, Gustav; Schmitt, Karl; Hoffmann, Irmgard; and Ott, Heinrich, 3,577,424.
Ott, Jack J.: See—
Lawrence, Garth D.; and Ott, Jack J., 3,577,560.
Ouellet, Lorenzo: See—
Lanthier, Raymond; and Ouellet, Lorenzo, 3,577,376.
Outboard Marine Corporation: See—
Dahl, Einar S., 3,577,714.
Owen, William J.; and Lloyd, Norman C., to Midland Silicones Limited. Organosilicon-amino compounds as catalysts on polyurethane production, 3,577,390, Cl. 260-77.5
Owens-Illinois, Inc.: See—
Benford, Charles L., Jr.; and Mielke, James E., 3,577,256.
Santelli, Thomas R.; and Wallace, Robert T., 3,577,358.
P & O Pilgrim Valve Limited: See—
Bunyan, Thomas Walter, 3,577,628.
Pace, Henry A.; and Anhorn, Victor J., to Goodyear Tire and Rubber Company, The. Synthetic resin, 3,577,398, Cl. 260-85.3
Packaged Resins Company, Inc.: See—
Alexander, Arthur P.; Aronson, Steven R.; and Langenhagen, Charles F., Jr., 3,577,578.
Page, John D., to Maremount Corporation. Bobbin support for textile spindle assembly, 3,577,723, Cl. 57-129.
Palermo, Blasey Thomas: See—
Welsh, Thomas Laurence; Peterson, Donald Leroy; Palermo, Blasey Thomas; and Hoss, George Carr, 3,577,490.
Pancoe, Edward G., to Singer-General Precision, Inc. Motion simulator, 3,577,655, Cl. 35-12.
Pansy, Felix Edward: See—
Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, 3,577,530.
Parfomak, Walter: See—
Molnar, Robert J.; Parfomak, Walter; Molnar, Robert J.; and Parfomak, Walter, 3,577,126.
Molnar, Robert J.; Parfomak, Walter; Molnar, Robert J.; and Parfomak, Walter, 3,577,126.
Parker, William Lawrence: See—
Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, 3,577,530.
Parks, Earl E., to Northrop Corporation. Rotary actuator and method of mounting same, 3,577,792, Cl. 74-96.
Parks, Paul B.; and Brown, Mark, to United States of America, Atomic Energy Commission. Neutron radiography of deuterated tissue, 3,576,994, Cl. 250-83.1
Parmater, John Q.: See—
Moorman, Charles J.; and Parmater, John Q., 3,576,992.
Parrish, Donald B.; and McDuff, James M., to Dow Chemical Company, The. Self-curing latex foam compositions, 3,577,554, Cl. 260-2.5
Parsons, David, to Automotive Products Company Limited. Fluid pressure operated servo devices, 3,577,832, Cl. 92-98.
Parzuchowski, Richard S.: See—
Whitfield, Marshall G.; Parzuchowski, Richard S.; and Moore, Dennis B., 3,577,268.
Pashulya, Mikhail Petrovich: See—
Paton, Boris Evgenievich; Lebedev, Vladimir Konstantinovich; Sheiko, Pavel Petrovich; and Pashulya, Mikhail Petrovich, 3,577,156.
Paton, Boris Evgenievich; Lebedev, Vladimir Konstantinovich; Sheiko, Pavel Petrovich; and Pashulya, Mikhail Petrovich. Pulse generator, 3,577,156, Cl. 219-131.
Patterson, James A., to Sondell Research Development Co. Process of coating particles with metals, 3,577,324, Cl. 204-20.
Pavia, Leonard W. Actuator for stringed musical instrument, 3,577,823, Cl. 84-174.
Paviak, Stanley C.; and Porter, Warren K., Jr., to Gulf Research & Development Company. Method for dispersing oil spills on water, 3,577,340, Cl. 210-42.
Peacher, Teddy J., to United States of America, Army. High pressure gas filling apparatus and method, 3,577,697, Cl. 53-12.
Pearl, David L.; Head, Beverly P., Jr.; and Waller, John G. Egg carton forming method, 3,577,495, Cl. 264-153.
Pege, Lotar, to Heimann, Dr., Ing., Walter, Forschungslaboratorium, Pro., Frma. Electro-mechanical torsional oscillator, 3,577,101, Cl. 331-154.
Peisach, Joel M., to Polaroid Corporation. Novel photographic process of diffusion transfer of X-ray image with phosphorescent luminophor, 3,577,204, Cl. 250-65.
Pelissier, Jean-Paul; and Chiffert, Pierre, to Societe Anonyme: Produits Chimiques Industriels & Agricoles Prociida S.A. Composition protecting against the action of microorganisms and its manner of use, 3,577,547, Cl. 424-286.
Pendleton Tool Industries, Inc.: See—
Bergquist, Clifford A., 3,577,815.
Pendleton, Wesley W.; and Ostrand, George W., to Anaconda Wire and Cable Company. Metallic conductor with ceramic fiber insulation, 3,577,309, Cl. 161-196.

Penick & Ford, Limited: See—
Hjermstad, Erling T., 3,577,407.
Pennwalt Corporation: See—
Keith, Frederick W., Jr.; Jones, Everett M.; and Townsend, Joseph R., Jr., 3,577,341.
Kulischenko, Walter, 3,577,682.
Vandegaer, Jan E., 3,577,515.
Pensack, Joseph Michael, to American Cyanamid Company. Compositions and methods for enhancement of the growth rate of poultry and animals employing alkali metal formaldehyde sulfoxylates and bisulfites, 3,577,529, Cl. 424-114.
Pepmeier, Carl R.: See—
Sincavage, Joseph T.; Pepmeier, Carl R.; and Stoffregen, Louis E., 3,577,258.
Peppiatt, Harry J.: See—
Hall, James A.; and Peppiatt, Harry J., 3,577,099.
Pereda, Eugene F. Rollable slot antenna, 3,577,196, Cl. 343-770.
Perilhau, Jean; and Auphan, Michel Joseph, to U.S. Philips Corporation, mesne. Device for diagnostic examination by ultrasonic oscillations, 3,577,772, Cl. 73-67.7
Perkin-Elmer Corporation, The: See—
Helliwell, Bradley A.; and Briglia, Donald D., 3,577,165.
Perkins, Charles H., to Robertshaw Controls Company. Electric ignition system, 3,577,209, Cl. 317-98.
Perneski, Anthony J.: See—
Morrow, Robert H.; and Perneski, Anthony J., 3,577,131.
Perona, Joseph J.: See—
Baird, Justus N., Jr.; Johnson, James S.; Kraus, Kurt A.; and Perona, Joseph J., 3,577,339.
Persson, Per Anders; and Sodersten, Bror Lennart, to Kallin, Ruth L. Movable roof window having a pyramidal frame construction, 3,577,691, Cl. 52-72.
Pesses, Marvin, to Mercer Alloys Corporation. Process for preparing metal sulfides, 3,577,231, Cl. 75-1.
Peterborg, Emil M. Multiple automatically retractable and extensible sliding doors in planar alignment, 3,577,679, Cl. 49-127.
Peterli, Hans Jakob; and Randell, Donald Richard, to Geigy Chemical Corporation. Dibenzazepine compounds as stabilizer for oxidizable organic compositions, 3,577,343, Cl. 252-51.5
Peterson, Donald Leroy: See—
Welsh, Thomas Laurence; Peterson, Donald Leroy; Palermo, Blasey Thomas; and Hoss, George Carr, 3,577,490.
Petke, Frederick E., to Cities Service Company. Pigment dispersions, 3,577,254, Cl. 106-308.
Petke, Frederick E., to Cities Service Company. Pigment dispersions, 3,577,255, Cl. 106-308.
Petrick, John T., to United States of America, Navy. Electrostatic grounding probe for use in explosive atmospheres, 3,577,208, Cl. 317-2.
Petrolite Corporation: See—
Shirley, William L., 3,577,336.
Pfizer Inc.: See—
Hess, Hans-Jurgen E.; and Cronin, Timothy H., 3,577,420.
Robinson, Ira C., 3,577,514.
Roebuck, Peter; and Whitehead, Derek James, 3,577,513.
Philco-Ford Corporation: See—
Zearfoss, Elmer W., Jr., 3,577,745.
Phillips, Brian L.: See—
Argabright, Perry A.; Phillips, Brian L.; and Sinkey, Vernon J., 3,577,391.
Phillips, Duane; Schultz, Roger C.; and Beck, Herbert H., to Armour and Company. Method for printing and applying labels, 3,577,296, Cl. 156-249.
Phillips Fibers Corporation: See—
Schmick, Hayes J.; and Van Doornwaard, Hans, 3,577,721.
Phillips Petroleum Company: See—
Greene, Max E., 3,577,724.
Rostler, Fritz S., 3,577,250.
Phoenix Products Company, Inc.: See—
Henning, Donald S., 3,576,988.
Pichel, Marlowe A., to Xerox Corporation, mesne. High quality submasters, 3,577,323, Cl. 204-7.
Pierret, Jean Marc: See—
Lautier, Alex Honore; Nussbaumer, Henri Jean; and Pierret, Jean Marc, 3,577,082.
Piette, Andre G., to Beloit Corporation. Replaceable deflector blade structure for a paper-making machine, 3,577,316, Cl. 162-352.
Pilgram, Kurt H., to Shell Oil Company. Bromination of 2,1,3-benzothiadiazoles and benzofurazans, 3,577,427, Cl. 260-304.
Pio Guardigli: See—
Carpino, Ugo, 3,577,149.
Plessey Company Limited, The: See—
Hall, Samuel S.; Miller, Robert A.; and Riley, Philip R. H., 3,577,002.
Plostnieks, Janis, to McNeil Laboratories, Inc. Oxindole acetic acid amides, 3,577,430, Cl. 260-325.
Plumly, George W.; Hunnicutt, Jack B.; and Deyo, Charles R., to Edu-Tonics Corporation. Apparatus for programed instruction and testing, 3,577,657, Cl. 35-9.
Pneumo Dynamics Corporation: See—
Campbell, Richard H., Jr., 3,577,040.
Poccia, Claudio: See—
De Glauco, Scilla; and Poccia, Claudio, 3,577,298.
Poirier, Joseph L.; and Schindler, John K. Extended range spectrum analysis radar, 3,577,143, Cl. 343-12.
Poitevin, Robert: See—
Savini, Emile Constantin; and Poitevin, Robert, 3,577,520.
Polaroid Corporation: See—
Peisach, Joel M., 3,577,204.
Taylor, Lloyd D., 3,577,237.
Porter, Joe A.; and Couch, Stuart L., to Beckman Instruments, Inc. Polarographic cell, 3,577,332, Cl. 204-195.
Porter, Warren K., Jr.: See—
Paviak, Stanley C.; and Porter, Warren K., Jr., 3,577,340.
Pountney, Clifford Harold; and Miller, Edward Francis, to AMP Incorporated. Rechargeable moving tape cell, 3,577,281, Cl. 136-6.
Powell, Truman W. Strip projecting squeeze toy, 3,577,676, Cl. 46-123.
Power Concepts Corporation: See—
Montague, Herbert R., 3,577,051.
Powerlock Floors, Inc.: See—
Omholt, Ray E., 3,577,694.
PPG Industries, Inc.: See—
Detorre, Robert P., 3,577,636.
Praglin, Julius, to Keithly Instruments, Inc. Bridge measuring circuit, 3,577,074, Cl. 324-98.
Pratt, Walter David, to American Cyanamid Company. Dimethylpolysiloxane suspensions of biologics and preparation thereof, 3,577,524, Cl. 424-89.
Presley, Rex W.: See—
Madurski, Joseph P.; Presley, Rex W.; and Rothfusz, Ralph W., 3,577,049.
Preston, Kendall, Jr.; and Norgren, Philip E., to United States of America, Health, Education and Welfare. Method of preparing blood smears, 3,577,267, Cl. 117-101.
Price, Alson K.: See—
Sweeney, Richard F.; and Price, Alson K., 3,577,447.
Price, John A.: See—
Stewart, Mary J.; and Price, John A., 3,577,381.
Price, Samuel T., to Du Pont de Nemours, E. I., and Company. Yarn-texturing jet device, 3,577,614, Cl. 28-1.4
Principe, Pacifico Anthony: See—
Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, 3,577,530.
Prinz, Eberhard: See—
Mauz, Otto; and Prinz, Eberhard, 3,577,384.
Procter & Gamble Company, The: See—
Baskerville, Ralph J., Jr.; and Baker, Joseph S., 3,577,290.
Laughlin, Robert G., 3,577,459.
Pullman Incorporated: See—
Nagy, Ernest J., 3,577,680.
Purcell, James J., to Sheer Elastic Corporation. Yarn covering machine, 3,577,718, Cl. 57-18.
Putzrath, Franz Ludwig; and Michel, Charles Allan, to RCA Corporation. Switching regulator having a diode connected to an intermediate tap of a choke, 3,577,065, Cl. 323-22.
Quandt, Herbert C., to Union Carbide Corporation. Boron nitride article having improved thermal stability, 3,577,245, Cl. 106-39.
Quatse, Jesse T.; and Dixon, Brook, to Vernitron Corporation. Portable computer terminal, 3,577,201, Cl. 179-2.
Quiner, Charles W.: See—
Kraft, Louis Seelbach; and Quiner, Charles W., 3,577,295.
Quintero, Eusebio V., to United Merchants and Manufacturers, Inc. Binary to decimal tree relay decoder circuit with memory display, 3,577,141, Cl. 340-347.
Raab, Hans; and Hageloch, Gunter, to Farbenfabriken Bayer Aktiengesellschaft. 1,1-Bis-[4-(1'-benzyl-3'-methyl-pyrazoloneazo) phenyl]cyclohexane, 3,577,403, Cl. 260-160.
Rabinovich, Roza Semenovna: See—
Zax, Natan Albertovich; Korzhov, Vasily Porfirievich; and Rabinovich, Roza Semenovna, 3,577,720.
Rachal, Francis; and Mc Kone, Donald B., to United States of America, Air Force, mesne. Remote controlled monitor circuit, 3,577,091, Cl. 330-24.
Raden, Daniel S., to Velsicol Chemical Corporation. Compositions of matter, 3,577,364, Cl. 260-2.5
Raffaelli, Joseph Gino; and Lokkart, Hendricus Johannes, to International Telephone and Telegraph Corporation. Test circuit, 3,577,011, Cl. 307-252.
Rai, Charanjit; Collins, Sherman D.; and Badin, Elmer J., to Cities Service Oil Company. Smoke suppressant fuel mixture, 3,577,228, Cl. 44-76.
Rakhit, Sumanas, to American Home Products Corporation. Phosphatidylalkanolamine derivatives, 3,577,446, Cl. 260-403.
Ramey, William A.: See—
Wing, Douglas J.; and Ramey, William A., 3,577,121.
Ramostar Corporation: See—
Re Baratelli, Giuseppe; and Galvani, Theodore J., 3,577,164.
Ramsey, Dennis A.: See—
Scott, Kenneth; and Ramsey, Dennis A., 3,577,616.
Rand, Robert B. Self-cleanable hair brush, 3,577,580, Cl. 15-169.
Randell, Brian: See—
Cocke, John; Randell, Brian; Schorr, Herbert; and Sussenguth, Edward H., 3,577,189.
Randell, Donald Richard: See—
Peterli, Hans Jakob; and Randell, Donald Richard, 3,577,343.

- Randell, Forrest Thompson, to Weir, G. & J., Limited. Distillation apparatus with vacuum controlled by rate of distillate flow. 3,577,320, Cl. 202-160.
- Raschke, Herbert A., to Bullard, E. D., Company. Insert for head protecting hoods. 3,577,563, Cl. 2-8.
- Ratcliffe, Edward, and Crawford, William N., to Amsted Industries Incorporated. Wheel tread contour apparatus. 3,577,644, Cl. 33-203.11
- Raytheon Company: See—
Dench, Edward C., 3,577,172.
Gindsberg, Joseph, 3,577,102.
- RCA Corporation: See—
Avins, Jack, 3,577,167.
Belohoubek, Erwin F., 3,577,181.
Craft, Jack, 3,577,008.
Longsdorff, Richard W., 3,577,174.
Martin, Thomas B., and Zedell, Henry J., 3,577,087.
Putzrath, Franz Ludwig, and Michel, Charles Allan, 3,577,065.
Yung, Abraham K., 3,577,166.
- Re Baratelli, Giuseppe, and Galvani, Theodore J., to Ramostar Corporation. Remote control starting system. 3,577,164, Cl. 290-38.
- Redington Counters, Inc.: See—
Knox, Francis P., 3,576,974.
- Regan, Bernard M., to Baxter Laboratories, Inc. Method of inducing local anesthesia. 3,577,552, Cl. 424-326.
- Regie Nationale des Usines Renault: See—
Guettier, Michel, 3,577,798.
- Rehn, Karl: See—
Kleiner, Hans-Jerg, and Rehn, Karl, 3,577,456.
- Reichle, Alfred: See—
Kohler, Armin; Von Falkai, Bela; Offermann, Klaus; and Reichle, Alfred, 3,577,500.
- Reider, George Sylvester, to AMP Incorporated. Electrical terminal. 3,577,118, Cl. 339-258.
- Reilly Tar & Chemical Corporation: See—
McGill, Charles K., and Campbell, George W., Jr., 3,577,426.
- Reimers Getriebe A.G.: See—
Brandl, Walter, and Mathes, Rudolf, 3,577,809.
- Reisman, Arnold: See—
Berkenblit, Melvin, and Reisman, Arnold, 3,577,286.
- Reiter, Richard W., and Liberti, Felix P., to National Starch and Chemical Corporation. Floor cover. 3,577,311, Cl. 161-254.
- Reithel, Raymond F., to Eastman Kodak Company. Method of making X-ray sensitive electroradio-graphic elements. 3,577,272, Cl. 117-201.
- Renk, Ernst: See—
Lehmann, Claude, and Renk, Ernst, 3,577,544.
- Republic Steel Corporation: See—
Reusser, Hans E., 3,577,825.
- Rettew, Richard R.: See—
Sanchez, Moises Gali; Levy, Newton, Jr.; and Rettew, Richard R., 3,577,487.
- Reusser, Hans E., to Republic Steel Corporation. Bolt anchor and method for making same. 3,577,825, Cl. 85-76.
- Reynolds, Carl D.: See—
Ardary, Zanc L.; Maxey, Andrew W.; and Reynolds, Carl D., 3,577,344.
- Reynolds, Harold C., and Olsen, Donald B., to Armour Pharmaceutical Company. Treatment of thyroid hormone impairment pharmaceutical compositions containing 3,5,3'-L-triiodothyronine complexes. 3,577,535, Cl. 424-198.
- Reynolds, Harold: See—
Jones, Robert E., and Reynolds, Harold, 3,577,455.
- Rhodes, Deryck: See—
Jack, David, and Rhodes, Deryck, 3,577,549.
- Ricards, Charles L., and McColey, Daniel, to Wood Industries, Inc. Flat bed type casting machine improvements. 3,577,591, Cl. 18-17.
- Rice, Larry D.: See—
McCall, Amiel J.; Elms, Ronald D.; and Rice, Larry D., 3,576,979.
- Rice, Rex; Chesley, Gilman D.; and Smith, William R., to Fairchild Camera and Instrument Corporation. Means for limiting field length of computed data. 3,577,130, Cl. 340-172.5
- Richeson, William E., Jr., to Magnavox Company, The. Alternating current power supply employing programmed turn-on and turn-off. 3,577,060, Cl. 321-11.
- Rider, Joseph Alfred. Antacid compositions containing bismuth aluminate and magnesium carbonate. 3,577,533, Cl. 424-155.
- Riegel Paper Corporation: See—
Lense, Robert F., 3,577,704.
- Rieke, James K.: See—
Chisholm, Douglas S., and Rieke, James K., 3,577,494.
- Riffe, William J. Print reader comprising two mutually orthogonal scanning slits and a drum having a light trans-missive surface. 3,577,163, Cl. 250-219.
- Riley, Philip R. H.: See—
Hall, Samuel S.; Miller, Robert A.; and Riley, Philip R. H., 3,577,002.
- Ringer, Cecil D.: See—
Alexander, Robert H.; Falter, Ronald C.; Ringer, Cecil D.; and Linsker, Eugene, 3,577,807.
- Ringland, William L.; Neumann, Manfred E.; Kaeser, Ernst K.; Gilmore, Thomas P.; and Geiersbach, Alois F., to Allis-Chalmers Manufacturing Company. Vehicle driven by synchronous motors. 3,577,050, Cl. 318-146.
- Ritterhoff, Eric K., to Continental Can Company, Inc. Method of labelling cylindrical objects. 3,577,293, Cl. 156-156.
- Riva Calzoni S.p.A.: See—
Ortelli, Aurelio, 3,577,830.
- Roach, Thomas J., to International Rectifier Corporation. Gate connection for controlled rectifiers. 3,577,042, Cl. 317-235.
- Roberts, John Alfred, to General Electric Company. Leak detection system. 3,577,769, Cl. 73-40.7
- Roberts, Philip M.: See—
Boughton, John D.; Roberts, Philip M.; and Sloboda, Mieczyslaw Herman, 3,577,234.
- Robertshaw Controls Company: See—
McIntosh, Harold A., 3,577,066.
Perkins, Charles H., 3,577,209.
- Robins, A. H., Company, Incorporated: See—
Calc, Albert Duncan, Jr., 3,577,415.
Helsley, Grover Cleveland, 3,577,432.
Lunsford, Carl Dalton; and Helsley, Grover Cleveland, 3,577,440.
- Robinson, Ira C., to Pfizer Inc. Sustained released pharmaceutical tablets. 3,577,514, Cl. 424-22.
- Robinson, Robert J., to Foxboro Company, The. Integrating device for use in industrial process control apparatus. 3,577,157, Cl. 235-183.
- Rockwell Manufacturing Company: See—
Alexander, Robert H.; Falter, Ronald C.; Ringer, Cecil D.; and Linsker, Eugene, 3,577,807.
- Rodgers, Robert P.: See—
Atcherson, Samuel M.; and Rodgers, Robert P., 3,577,084.
- Roebuck, Peter, and Whitehead, Derek James, to Pfizer Inc., mesne. Pellets for supplying biologically active substances to ruminants containing magnesium and coated iron particles. 3,577,513, Cl. 424-22.
- Roemer, Gordon R.: See—
Shaw, Stanley B.; Gehl, Ronald H.; and Roemer, Gordon R., 3,577,770.
- Roesener, Edward J., Jr.: See—
Norwich, John F.; and Roesener, Edward J., Jr., 3,577,287.
- Rohr Corporation: See—
Howard, James S., 3,577,297.
- Rohr, Otto; and Hitz, Hans Rudolf, to Ciba Limited. Trifluoromethyl phenyl-N-(halophenyl)-carbamate and pesticidal preparations containing same. 3,577,453, Cl. 260-471.
- Rohr, Robert L., to International Business Machines Corporation. Article surface treating apparatus and method. 3,577,278, Cl. 134-1.
- Rosenberg, Jack, to International Business Machines Corporation. System for accommodating various machine tool resolutions from a standard program. 3,576,978, Cl. 235-151.11
- Rosenblum, Charles: See—
Howe, Eugene E.; and Rosenblum, Charles, 3,577,537.
- Rosenthal, Christian, to Chemische Werke Munchen Otto Barlocher GmbH. Method for agglomerating suspended particles. 3,577,489, Cl. 264-117.
- Rosi, David, to Sterling Drug Inc. 1-Aminoalkylamino-4-alkoxy-methylthioxanthene derivatives. 3,577,558, Cl. 260-328.
- Rostler, Fritz S., to Phillips Petroleum Company, mesne. Method of rubberizing asphalt. 3,577,250, Cl. 106-278.
- Roth, Herman P.: See—
Von Brimer, Joe W.; and Roth, Herman P., 3,577,728.
- Rothe, Richard Reinhard Gustav Adolf/Rothe, Rudolf/ine, nee Roessler): See—
Kotzschmar, Arnold; Metzger, Hermann; Rothe, Richard Reinhard Gustav Adolf; and Seidel, Willy, 3,577,483.
- Rothfusz, Ralph W.: See—
Madurski, Joseph P.; Presley, Rex W.; and Rothfusz, Ralph W., 3,577,049.
- Ruckberg, Herbert S., to Continental Can Company, Inc. Method and means for filling and sealing a flexible container. 3,577,698, Cl. 53-37.
- Ruffo, Angelo P.: See—
Ballennie, Peter; and Ruffo, Angelo P., 3,577,712.
- Ruger, William B.; and Sullivan, Leroy J., to Sturm, Ruger & Co., Inc. Trigger and safety assembly for firearms. 3,577,668, Cl. 42-70.
- Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., to American Standard, Inc., mesne. Integral lavatory bowl and vanity top combination. 3,577,572, Cl. 4-187.
- Rumpelcin, Fritz: See—
Kisselmann, Willy; Rumpelcin, Fritz; Kopf, Paul; and Landbrecht, Franz, 3,577,078.
- Rumsey, Rollin Douglas, to Houdaille Industries, Inc. Leaf spring tuned viscous vibration damper. 3,577,802, Cl. 74-574.
- Ruoff, Carl E.: See—
Curtis, John J.; and Ruoff, Carl E., 3,577,036.
- Ruppert, John A.; and Montagna, Dominic. Removing nickel from cadmium. 3,577,232, Cl. 75-71.
- Russo, Frank A.; and Valek, Robert J., to Bendix Corporation, The. Nonlinear optimizing computer for process control. 3,576,976, Cl. 235-150.1
- Rutz, Richard F., to International Business Machines Corporation. Method for epitaxially growing silicon carbide onto a crystalline substrate. 3,577,285, Cl. 148-175.
- Rynne, George B., and Beckwith, Merton M., to Conversion Chemical Corporation. Method and bath for electroplating tin. 3,577,328, Cl. 204-54.
- Saba Schwarzwaldler Apparate-Bau-Anstalt August Schwer Sohne G.m.b.H.: See—
Schulz, Hansrichard, 3,577,081.

- Saginaw Machine and Tool Company: See—
Cashman, Robert W., 3,577,618.
- Saito, Toshiaki: See—
Homma, Makoto; and Saito, Toshiaki, 3,577,633.
- Sakamoto, Moriyoshi: See—
Inagaki, Junpei; Sakamoto, Moriyoshi; Nakakita, Tsuneo; and Kitamura, Hiroyuki, 3,577,024.
- Sallay, Stephen: See—
Album, Harvey E.; Dvonch, William; and Sallay, Stephen, 3,577,408.
- Samsonite Corporation: See—
Maguire, John; Uyeda, Tim M.; and Wahler, Theodore George, 3,577,674.
- Sanchez, Moises Gali; Levy, Newton, Jr.; and Rettew, Richard R., to Grace, W. R., & Co. Preparation of sub-micron sized alkaline earth titanate and zirconate powders. 3,577,487, Cl. 264-56.
- Sand, Edward C., to Clevite Corporation. Method of low power bias, low distortion magnetic recording. 3,576,954, Cl. 179-100.2
- Sandler, Melvin H.; and Cohen, Merrill, to United States of America, Army. Dark colored coatings of heat solar heat reflectance. 3,577,379, Cl. 260-40.
- Sandoz AG: See—
Schuler, Max, 3,577,481.
- Sandoz, Ltd.: See—
Entschel, Roland; Mueller, Curt; and Steinemann, Willy, 3,577,404.
Schuler, Max, 3,577,481.
- Sandoz-Wander, Inc.: See—
Griot, Rudolf G., 3,577,419.
Ott, Hans, 3,577,557.
- Sandvikens Jernverks Aktiebolag: See—
Strandel, Per-Olof, 3,577,619.
- Sanford, Norman R.; and Wieg, Heinrich J., to Bendix Corporation, The. Optical apparatus for flaw detection. 3,577,039, Cl. 317-127.
- Sano, Kenji: See—
Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
- Sansam, Claude. Power take-off actuator. 3,577,789, Cl. 74-11.
- Santelli, Thomas R.; and Wallace, Robert T., to Owens-Illinois, Inc. Organic isocyanate-lignin reaction products and process. 3,577,358, Cl. 260-2.5
- Santos, Joaquim L.: See—
Horton, John P.; Sollmann, Robert E.; and Santos, Joaquim L., 3,577,835.
- Sargent, Charles L.: See—
Sargent, Ronald J.; Sargent, Charles L.; Sargent, Frank T.; and Hoffman, John A., 3,577,569.
- Sargent, Frank T.: See—
Sargent, Ronald J.; Sargent, Charles L.; Sargent, Frank T.; and Hoffman, John A., 3,577,569.
- Sargent, Ronald J.; Sargent, Charles L.; Sargent, Frank T.; and Hoffman, John A., to Theford Corporation. Toilet apparatus. 3,577,569, Cl. 4-79.
- Saroff, Lawrence: See—
Hess, Martin; and Saroff, Lawrence, 3,577,224.
- Sasaki, Shunroku: See—
Kawashima, Masao; Kurita, Syoichi; and Sasaki, Shunroku, 3,577,138.
- Sassiver, Martin Leon: See—
Cantrall, Margot Louise; Sassiver, Martin Leon; and Shepherd, Robert Gordon, 3,577,417.
- Sato, Masamichi; Tamai, Yasuo; Matsumoto, Seiji; and Akashi, Goro, to Xerox Corporation. Liquid development of electrostatic latent images utilizing a toner-free zone. 3,577,259, Cl. 117-37.
- Sauer, Louis E.; and Sauer, Robert W., to Centenary Central, Inc. Removable free wheeling resilient cover for rotary anvil. 3,577,822, Cl. 83-659.
- Sauer, Robert W.: See—
Sauer, Louis E.; and Sauer, Robert W., 3,577,822.
- Savini, Emile Constant; and Poitevin, Robert. Dentifrice compositions containing 5,5-diaryl-2,4-imidazolidinediones and process of treating pyorrhea. 3,577,520, Cl. 424-54.
- Sawada, Masao. Diffraction grating X-ray spectrometer wherein an electron beam is scanned across a fixed X-ray emitting element. 3,577,159, Cl. 250-51.5
- S&C Electric Company: See—
Jeffries, James E., 3,576,967.
- Schaefer, Robert H., to General Motors Corporation. Hydraulic modulator valve control. 3,577,806, Cl. 74-868.
- Schaten, Paul, to Heinrich Kopper Gesellschaft mit beschränkter Haftung. Combined coke oven door jamb cleaning apparatus and door handling apparatus. 3,577,321, Cl. 202-241.
- Scheideler, Hans. Tool post. 3,577,819, Cl. 82-37.
- Scheiplug, Hans: See—
Kuhle, Engelbert; Klauke, Erich; Frohberger, Paul-Ernst; and Scheiplug, Hans, 3,577,451.
- Scheirich, H. J., Company: See—
Hemelreich, Louis E., 3,577,584.
- Scheller, Karlheinz; Koddermann, Else; and Trebs, Hans, to DuroDont, Dr. Scheller, Firma. Storage-stable frothing tooth paste. 3,577,521, Cl. 424-55.
- Schering Aktiengesellschaft: See—
Kieslich, Klaus; and Koch, Wolfgang, 3,577,318.
- Schiedel, George M., to Ford Motor Company. Process and mechanism for setting ignition distributor centrifugal advance. 3,577,625, Cl. 29-407.
- Schindler, John K.: See—
Poirier, Joseph L.; and Schindler, John K., 3,577,143.
- Schisla, Robert M.: See—
Hammann, William C.; and Schisla, Robert M., 3,577,361.
- Schlaepfer, Carl E., to International Business Machines Corporation. Reproduce head with peak sensing circuit. 3,577,192, Cl. 340-174.1
- Schlumberger Technology Corporation: See—
Aitken, John, 3,577,782.
Lebourg, Maurice P.; and Fields, Roger O., 3,577,781.
Whitten, Frank R.; and Fields, Roger O., 3,577,783.
- Schmick, Hayes J.; and Van Doornewaard, Hans, to Phillips Fibers Corporation. Yarn string up device. 3,577,721, Cl. 57-77.33
- Schmidlin, Albertus E., to Singer-General Precision, Inc. Fluoric accelerometer. 3,577,786, Cl. 73-515.
- Schmidt, Burkhard; and Nibbrig, Reinhold, to Olympia Werke AG. Adjustable frictional connection. 3,577,787, Cl. 74-522.
- Schmidt, Gunther, to Bolkow Gesellschaft mit beschränkter Haftung. Liquid fuel rocket engine construction. 3,577,735, Cl. 60-207.
- Schmidt, Helmut: See—
Hoffmann, Hermann; and Schmidt, Helmut, 3,577,405.
- Schmidt, Thomas R.; and Husing, Walter H., to Shell Oil Company. Borehole deformation gage. 3,577,643, Cl. 33-178.
- Schmitt, Karl: See—
Ehrhart, Gustav; Schmitt, Karl; Hoffmann, Irmgard; and Ott, Heinrich, 3,577,424.
- Schmitz, Peter Josef; Werner, Eberhard; and Seifried, Walter, to Kalle Aktiengesellschaft. Process for the production of deep drawable, sterilizable polyester film. 3,577,510, Cl. 264-342.
- Schmitz, Rudolf: See—
Baier, Franz; and Schmitz, Rudolf, 3,577,307.
- Schneider, Abraham: See—
Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,577,479.
- Schneider, Abraham, to Sun Oil Company. Monohalogenation of alkyladamantane hydrocarbons. 3,577,468, Cl. 260-648.
- Schneider, Abraham, to Sun Oil Company. Preparation of 9-halodecahydronaphthalene. 3,577,469, Cl. 260-648.
- Schneider, Alvin; and Tarnowsky, Joseph, to Alpha Metals, Inc. Activated flux. 3,577,284, Cl. 148-23.
- Schneider, Hans-Dieter, to Fernseh GmbH. Color television mixing arrangement. 3,576,943, Cl. 178-5.4
- Schneller, George H.; and Levi, Ralph S., to American Home Products Corporation. Disinfected antacid compositions and method for the preparation thereof. 3,577,532, Cl.
- Schoen, Kurt: See—
Gaehwiler, Hermann; and Schoen, Kurt, 3,577,162.
- Schoenberg, Jules Ernest: See—
Schrage, Albert; and Schoenberg, Jules Ernest, 3,577,393.
- Schorr, Herbert: See—
Cocke, John; Dauber, Philip S.; Schorr, Herbert; and Sussenguth, Edward H., 3,577,190.
Cocke, John; Randell, Brian; Schorr, Herbert; and Sussenguth, Edward H., 3,577,189.
- Schrage, Albert; and Schoenberg, Jules Ernest, to Dart Industries Inc. Ethylene-propylene-diene terpolymer rubbers and processes therefor. 3,577,393, Cl. 260-80.78
- Schubert & Salzer Maschinenfabrik Aktiengesellschaft: See—
Goldammer, Georg; and Mahr, Gunther, 3,577,599.
- Schubert, Walter A., to Elgin Metal Casket Company. Method of oxidizing tin. 3,577,282, Cl. 148-6.24
- Schuler, Max, to Sandoz Ltd., a/k/a Sandoz AG. Phosphoric acid esters. 3,577,481, Cl. 260-942.
- Schultz, Roger C.: See—
Phillips, Duane; Schultz, Roger C.; and Beck, Herbert H., 3,577,296.
- Schultz, Warner W., to United States of America, Atomic Energy Commission. Measuring irradiation-induced deformations of materials. 3,577,199, Cl. 250-83.1
- Schulz, Hansrichard, to Saba Schwarzwaldler Apparate-Bau-Anstalt August Schwer Sohne G.m.b.H. Method and arrangement for synchronization of the supplementary carrier frequency oscillator. 3,577,081, Cl. 325-329.
- Schulz, Johann G. D., to Gulf Research and Development Company. Process for preparing 4,4'-dicarboxybenzophenone. 3,577,457, Cl. 260-517.
- Schulze-Steinen, Hans J.: See—
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jürgen F.; Edwards, Alan C.; and Tetteroo, Hans, 3,577,413.
- Schwartz, Louis S.: See—
Shah, Dipak C.; and Schwartz, Louis S., 3,577,753.
- Schwartz, Sidney. Purse size face illuminating flashlight and mirror. 3,576,989, Cl. 240-4.2
- Schwarz, Eric. Apparatus for the automatic determination of fiber length distribution of a fiber population. 3,577,598, Cl. 19-65.
- Schwarz, Olek: See—
Bernhard, George D.; and Schwarz, Olek, 3,577,034.
- Schwarze, Werner; Giesselmann, Gunter; and Weigert, Wolfgang, to Deutsche Gold-und Silber-Scheideanstalt vormals Roessler. Process for the selective chlorination of alkylmercapto-substituted s-triazines. 3,577,416, Cl. 260-248.

- Schwenk, Carl L.: See—
Hutler, George J.; and Schwenk, Carl L., 3,577,257.
- Schwietz, Ulrich: See—
Gutmann, Hugo; Manz, Ulrich; and Schwietz, Ulrich, 3,577,464.
- Scott, Gerald C.: See—
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., 3,576,999.
- Scott, Kenneth; and Ramsey, Dennis A., to British Lighting Industries Limited. Arc discharge lamps. 3,577,616, Cl. 29-25.15
- Sebok, Joseph B., to Ford Motor Company. Method of forming an air cleaner seal. 3,577,486, Cl. 264-45.
- Seckerson, Clifford Alexander; and Collyer, Robert C., to United-Carr Incorporated. Fastener. 3,577,603, Cl. 24-73.
- Secrist, Duane R., to International Business Machines Corporation. Method of manufacturing a magnetic head assembly. 3,577,634, Cl. 29-603.
- Security Systems, Inc.: See—
Wolf, John E., 3,577,136.
- Sedgwick, Grant O., to Ashland Oil, Inc. Dibutyl thio urea as a UV absorber for polyurethanes. 3,577,383, Cl. 260-45.9
- Seidel, Willy: See—
Kotzschmar, Arnold; Metzger, Hermann; Rothe, Richard Reinhard Gustav Adolf; and Seidel, Willy, 3,577,483.
- Seifried, Walter: See—
Schmitz, Peter Josef; Werner, Eberhard; and Seifried, Walter, 3,577,510.
- Seigel, Arnold E.: See—
Dawson, Victor C. D.; and Seigel, Arnold E., 3,577,590.
- Selman, Jan; and Oosterhof, Hendricus A., to Shell Oil Company. Process for annealing substantially unstretched polyactone articles. 3,577,502, Cl. 264-235.
- Selwitz, Charles M.: See—
Bacha, John D.; and Selwitz, Charles M., 3,577,470.
- Serafini, Angelo: See—
Ciampa, Fred A.; Serafini, Angelo; and Mazzarella, Louis, 3,577,574.
- Serrano, Mario; and Wolf, William D., to Monsanto Company. Apparatus for increasing the density of thermoplastic foam. 3,577,589, Cl. 18-125.
- Setele, William O.: See—
Hoffman, George J.; Setele, William O.; and Law, Lester E., 3,577,620.
- Shafer, James R.: See—
Bertoglio, Joseph; Deming, Philip L.; Eckert, Joyce G.; and Shafer, James R., 3,577,765.
- Shaffer, Frank E. Swaging device for cable fittings. 3,577,622, Cl. 29-200.
- Shaffer, James H.; Moulton, David M.; and Grimes, Warren R., to United States of America, Atomic Energy Commission. Method for separating uranium, protactinium, and rare earth fission products from spent molten fluoride salt reactor fuels. 3,577,225, Cl. 23-325.
- Shah, Dipak C.; and Schwartz, Louis S., to Bethlehem Steel Corporation. Method and apparatus for forming thin-walled cylindrical articles. 3,577,753, Cl. 72-41.
- Shah, Indravadan S., to Chemical Construction Corporation. Recovery of sulfur dioxide from waste gases. 3,577,219, Cl. 23-168.
- Shalit, Harold, to Atlantic Richfield Company. Process for the production of high purity hydrogen. 3,577,329, Cl. 204-60.
- Sharkey, Andrew G., Jr.: See—
Kessler, Theodore; Sharkey, Andrew G., Jr.; Malli, Joseph, Jr.; and Friedel, Robert A., 3,577,337.
- Sharlit, Ian B., to Hitco. Filter system. 3,577,705, Cl. 55-4.
- Shavel, John, Jr.: See—
Kaminsky, Daniel E.; Meltzer, Robert I.; and Shavel, John, Jr., 3,577,441.
- Shaw, David N., to Carrier Corporation. Refrigeration apparatus. 3,577,741, Cl. 62-84.
- Shaw, John Thomas, to American Cyanamid Company. Compositions and methods for effecting tranquility with triazines. 3,577,541, Cl. 424-249.
- Shaw, Stanley B.; Gehl, Ronald H.; and Roemer, Gordon R., to C T Supply Co. Test-closure for open-topped containers. 3,577,770, Cl. 73-49.8
- Sheer Elastic Corporation: See—
Purcell, James J., 3,577,718.
- Sheers, Edward Helmut, to Arizona Chemical Company, mesne. Process of applying novel aldehydes. 3,577,230, Cl. 71-67.
- Sheiko, Pavel Petrovich: See—
Paton, Boris Evgenievich; Lebedev, Vladimir Konstantinovich; Sheiko, Pavel Petrovich; and Pashulya, Mikhail Petrovich, 3,577,156.
- Shell Oil Company: See—
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jürgen F.; Edwards, Alan C.; and Tettersoo, Hans, 3,577,413.
- Christensen, Alton O., 3,577,005.
- De Haas, Jacobus, 3,577,732.
- Holler, Howard V., 3,577,442.
- Kolb, Robert H., 3,576,977.
- Montgomery, William C., Jr., 3,577,090.
- Nozaki, Kenzie, 3,577,466.
- Pilgram, Kurt H., 3,577,427.
- Schmidt, Thomas R.; and Husing, Walter H., 3,577,643.
- Selman, Jan; and Oosterhof, Hendricus A., 3,577,502.
- Winkler, De Loss E., 3,577,357.
- Shepard, Kenneth L.: See—
Cragoe, Edward J., Jr.; and Shepard, Kenneth L., 3,577,418.
- Shepherd, Lawrence H., Jr., to Ethyl Corporation. Beryllium hydride tertiary amine complexes. 3,577,414, Cl. 260-247.
- Shepherd, Robert Gordon: See—
Cantrall, Margot Louise; Sassiver, Martin Leon; and Shepherd, Robert Gordon, 3,577,417.
- Shepherd, Thomas H.: See—
Gould, Francis E.; and Shepherd, Thomas H., 3,577,516.
- Shepherd, Thomas H.; and Gould, Francis E., to National Patent Development Corporation. Sustained release tablets. 3,577,512, Cl. 424-21.
- Shepherd, Thomas H.; and Gould, Francis E., to National Patent Development Corporation. Hydrophilic hairspray and hair setting preparations. 3,577,518, Cl. 424-47.
- Sherbert, Archie T., Jr., to Boeing Company, The. Display system for use in VTOL-type aircraft. 3,577,120, Cl. 340-27.
- Shimooka, Mike S. Flower encapsulating apparatus and method. 3,577,647, Cl. 34-9.
- Shin-Etsu Chemical Industry Co., Ltd.: See—
Tamura, Kihachi; Nakajima, Isao; and Inoue, Kaname, 3,577,362.
- Shirley, William L., to Petrolite Corporation. Electric treater for treating jet fuel and other dispersions. 3,577,336, Cl. 204-302.
- Sibilla, John P.: See—
Brownstein, Arthur M.; and Sibilla, John P., 3,577,458.
- Siegrist, Adolf Emil: See—
Liechti, Peter; Gugliemetti, Leonardo; Maeder, Erwin; and Siegrist, Adolf Emil, 3,577,411.
- Siemens Aktiengesellschaft: See—
Albsmeier, Hans; and Traub, Karl, 3,577,180.
- Bogner, Gunther; and Maier, Richard, 3,577,151.
- Grunling, Hermann Walter, 3,577,183.
- Hofmeister, Ernst, 3,577,632.
- Krautwald, Herbert; Moller, Helmut; and Siepmann, Richard, 3,577,182.
- Siepmann, Richard: See—
Krautwald, Herbert; Moller, Helmut; and Siepmann, Richard, 3,577,182.
- Siggel, Erhard: See—
Kersten, Hilde; Siggel, Erhard; and Meyer, Gerhard, 3,577,387.
- Silvagi, Joseph; and Conforti, John W., to Camdale Enterprises. In-volute generating apparatus. 3,577,683, Cl. 51-94.
- Silver, Stanley Milton. Method of cartoning. 3,577,699, Cl. 53-27.
- Silverstein, Paul, to Applied Synthetics Corporation. Die for sealing or cutting thermoplastic material. 3,577,820, Cl. 83-171.
- Simpson, George R., to United States of America, Army, mesne. Means for obtaining multiple coherent-laser apertures. 3,577,093, Cl. 331-94.5
- Sincavage, Joseph T.; Pepmeier, Carl R.; and Stoffregen, Louis E., to FMC Corporation. Wrapping material for moisture-containing article and method for making the same. 3,577,258, Cl. 117-62.
- Sinclair-Koppers Company: See—
Hess, Martin; and Saroff, Lawrence, 3,577,224.
- Immel, Richard H., 3,577,360.
- Sing, Reuben C.: See—
Sing, T. J.; and Sing, Reuben C., 3,577,664.
- Sing, T. J.; and Sing, Reuben C., to Delta Diggers, Inc. Excavation machine having improved digging elements. 3,577,664, Cl. 37-192.
- Singer-Cobble Limited: See—
Evans, Raymond Victor; and Hibbitt, John Edward, 3,577,652.
- Singer-General Precision, Inc.: See—
Atcherson, Samuel M.; and Rodgers, Robert P., 3,577,084.
- Ebeling, William C., 3,576,945.
- Kail, Karl, 3,577,659.
- Pancoe, Edward G., 3,577,655.
- Schmidlin, Albertus E., 3,577,786.
- Sinkey, Vernon J.: See—
Argabright, Perry A.; Phillips, Brian L.; and Sinkey, Vernon J., 3,577,391.
- Sircovich, Oscar. Tank structure and method of erecting same. 3,577,692, Cl. 52-224.
- Skelly Oil Company: See—
Flickinger, Earl Dan; and Buess, Charles Merlyn, 3,577,431.
- Skelton, Darold M., to Milwaukee Cylinder Corporation. Fluid cylinder. 3,577,833, Cl. 92-168.
- Ski-Mor Inc.: See—
Horton, John P.; Sollmann, Robert E.; and Santos, Joaquim L., 3,577,835.
- Skorcz, Joseph A.: See—
Suh, John T.; and Skorcz, Joseph A., 3,577,428.
- Slagel, Edwin C.: See—
Baker, Ronald E.; Cook, Richard L.; and Slagel, Edwin C., 3,577,306.
- Slavin, Peter E., to Intelligent Instruments, Inc. Particle accelerator employing a revolving electric field for generating X-rays. 3,576,997, Cl. 250-90.
- Sloboda, Mieczyslaw Herman: See—
Boughton, John D.; Roberts, Philip M.; and Sloboda, Mieczyslaw Herman, 3,577,234.
- Smith, Calvin S.; and McLeod, William J., to Chevron Research Company. Hydrogen manufacture. 3,577,221, Cl. 23-213.
- Smith, Donald C.; and Koshada, Robert E., to Zapata Industries Inc. Rotatable crown filling machine and method for applying sealing rings of plastic to the periphery of the crown interior. 3,577,595, Cl. 18-20.

- Smith, Edwin Studley, to Goodyear Tire & Rubber Company, The. Polymerization of vinyl chloride using an in-situ initiator and a basic calcium compound as a buffer. 3,577,401, Cl. 260-92.8
- Smith, Herchel: See—
Teller, Daniel M.; Douglas, George H.; and Smith, Herchel, 3,577,410.
- Smith, Kave A.; and Ladendecker, Henry L., to McNeil Corporation. Socket wrench. 3,577,817, Cl. 81-121.
- Smith Kline & French Laboratories: See—
Beschirp, Frederick, 3,577,702.
- Ferlauto, Robert J., 3,577,553.
- Smith, Leedice Solomon. Combination tape measure and compass. 3,577,641, Cl. 33-27.
- Smith, William R.: See—
Rice, Rex; Chesley, Gilman D.; and Smith, William R., 3,577,130.
- Smola, Harold: See—
Kliman, Ivan M.; and Smola, Harold, 3,577,086.
- Snyder, Edward, III: See—
Weinstein, Harold; and Snyder, Edward, III, 3,577,658.
- Societe Anonyme dite: Institut Merieux: See—
Valette, Louis R., 3,577,526.
- Societe Anonyme: Produits Chimiques Industriels & Agricoles Procidia S.A.: See—
Pelissier, Jean-Paul; and Chiffert, Pierre, 3,577,547.
- Societe d'Etudes et de Recherches Scientifiques et Minières: See—
Hicquet, Max, 3,577,509.
- Societe Gobin Daudé (Societe Anonyme): See—
Texler, Jean Pierre, 3,577,608.
- Societe Grenobloise d'Etudes et d'Applications Hydrauliques (SOGREAH): See—
Vincent, Georges, 3,577,570.
- Societe Nouvelle de Roulements: See—
Corbex, Louis; and Burdet, Roger, 3,577,685.
- Societe Seder, Societe Europeenne d'Isolateurs en Verre: See—
Caldor, Thomas, 3,576,942.
- Soderberg, Leif Erik Roland, to Aga Aktiebolag. Producing a transparent copper coating on a surface. 3,577,273, Cl. 117-211.
- Sodersten, Bror Lennart: See—
Persson, Per Anders; and Sodersten, Bror Lennart, 3,577,691.
- Sofer, Uri Y.; and Kaltman, Irwin L., to Technology Consortium, Inc. Cellular building structure. 3,577,693, Cl. 52-236.
- Solheim, Karsten. Swing-weight and static weight balance for golf clubs. 3,577,771, Cl. 73-65.
- Sollmann, Robert E.: See—
Horton, John P.; Sollmann, Robert E.; and Santos, Joaquim L., 3,577,835.
- Sondell Research Development Co.: See—
Patterson, James A., 3,577,324.
- Sony Corporation: See—
Tsujikawa, Kazunobu, 3,577,056.
- Sordello, Frank J.: See—
Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; and Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.
- Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; Sordello, Frank J.; and Anderson, Donald E.; Koch, Lawrence M.; Lloyd, Robert E.; and Sordello, Frank J., 3,577,132.
- Spadaro, James J.: See—
Wadsworth, James I.; Gallo, Alexander S.; Ziegler, George M., Jr.; and Spadaro, James J., 3,577,649.
- Sparks, David E., to Zenith Radio Corporation. Variable attenuator for a wave signal receiver. 3,577,103, Cl. 333-17.
- Speichinger, Ferdinand, to Altenburger, Karl, KG. Buckle, especially for ski boots. 3,577,602, Cl. 24-70.
- Spencer, John L.: See—
Jackson, Billy G.; Spencer, John L.; and Higgins, Harvey M., Jr., 3,577,412.
- Sperberg, Lawrence R. Method of measuring tire uniformity. 3,577,780, Cl. 73-146.
- Sperry Rand Corporation: See—
Bergman, Robert J., 3,577,134.
- Brickner, David R.; and Swift, Billy K., 3,576,986.
- Clift, Charles E., 3,577,195.
- Halls, Lawrence M.; and Lausch, Henry N., 3,577,715.
- McCarty, Horace G.; Lausch, Henry N.; and Hudson, Earl A., 3,577,713.
- McCarty, Horace G.; Halls, Lawrence M.; Howell, Edmund O.; and Hurlburt, Joseph C., 3,577,716.
- McGee, Joe H., 3,577,053.
- Spiro Corporation Ltd.: See—
Hewitt, Frederick Maxwell, 3,577,611.
- Sprogis, Gunars: See—
Behr, Bryon C.; Sprogis, Gunars; and Booth, Frederick E., 3,577,003.
- Squibb, E. R., & Sons, Inc.: See—
Diassi, Patrick A., 3,577,463.
- Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, 3,577,530.
- Myers, Dirck V., 3,577,540.
- Stackpole Carbon Company: See—
Kosco, John C., 3,577,275.
- Standard Box Spring Co.: See—
Ciampa, Fred A.; Serafini, Angelo; and Mazzarella, Louis, 3,577,574.
- Stata, Stanley S., 49% to Wintercorn, Andrew F. Shoe scraper floor gratings for automobile floors. 3,577,581, Cl. 15-215.
- Stauffer, Norman L., to Honeywell Inc. System for recording high frequency signals on a recorder having a lower frequency response. 3,576,948, Cl. 179-15.55
- Stedile, Udino, to Beloit Corporation. Felt permeability testing apparatus. 3,577,767, Cl. 73-38.
- Steen, Donald B., to United States of America, Navy. Unattended flashing navigation beacon system. 3,577,135, Cl. 340-251.
- Steffens, Robert W.; and Zeuschel, Milton F., to United States of America, Atomic Energy Commission. Electrostatic ultrasonic non-destructive testing device. 3,577,774, Cl. 73-67.8
- Stehlin, Robert A.: See—
Niemann, George W.; and Stehlin, Robert A., 3,577,015.
- Steinemann, Willy: See—
Entschel, Roland; Mueller, Curt; and Steinemann, Willy, 3,577,404.
- Sterling Drug Inc.: See—
Rosi, David, 3,577,558.
- Stevens, Donald W., to United States of America, Air Force. Instrument for measuring the net flux of radiant energy through a plane. 3,576,996, Cl. 250-83.3
- Stevens, Emerson W., to United States of America, Air Force. Thrust diverter valve. 3,577,736, Cl. 60-226.
- Stevens, Irving J.: See—
Alexander, Jerry; and Stevens, Irving J., 3,577,816.
- Stewart, Mary J.; and Price, John A., to FMC Corporation. Heat stabilization of polyester resin with phenylphosphonic acids. 3,577,381, Cl. 260-45.7
- Stickney, Leslie P., to Gulf & Western Precision Engineering Company, mesne. Milling machine. 3,577,828, Cl. 90-15.
- Stoffregen, Louis E.: See—
Sincavage, Joseph T.; Pepmeier, Carl R.; and Stoffregen, Louis E., 3,577,258.
- Stolar, Morris Emanuel; and Feinberg, Joseph George, to Miles Laboratories, Inc. Water-insoluble antigenic substances and method of preparing the same and antigenic depot agents incorporating such substances. 3,577,523, Cl. 424-88.
- Stone, John G.; Buettner, George S.; and Alm, Christian A., to Cerro Corporation. Flame-retardant wire and cable. 3,576,940, Cl. 174-113.
- Storm, Herbert F., to General Electric Company. Insulated gate field effect transistor used as a voltage-controlled linear resistor. 3,577,019, Cl. 307-304.
- Strandel, Per-Olof, to Sandvikens Jernverks Aktiebolag. Method of manufacturing composite hardmetal rolls. 3,577,619, Cl. 29-148.4
- Streib, Hugo; and Hechelhammer, Wilhelm, to Farbenfabriken Bayer Aktiengesellschaft. Glass fiber reinforced polycarbonates. 3,577,378, Cl. 260-37.
- Stromberg-Carlson Corporation: See—
Bartlett, William F., 3,577,154.
- Brightman, Barrie, 3,577,202.
- Struhrke, William F.; and Underwood, Charles R., said Underwood assor. to the United States of America, Air Force. Method for polishing metallographic specimens. 3,577,689, Cl. 51-281.
- Stubbmann, Albert: See—
Kohner, Frank; and Stubbmann, Albert, 3,577,675.
- Sturm, Ruger & Co., Inc.: See—
Ruger, William B.; and Sullivan, Leroy J., 3,577,668.
- Stutz, Theo. Quinary reduction stage and forward-reverse counter. 3,577,085, Cl. 328-42.
- Suh, John T., to Colgate-Palmolive Company. 2-Substituted-cyclopenta[β]thianaphene-3-ones. 3,577,436, Cl. 260-330.5
- Suh, John T.; and Skorcz, Joseph A., to Colgate-Palmolive Company. 2-Amino-4-aryloxyalkyl-4-alkyl-2-oxazolines. 3,577,428, Cl. 260-307.
- Sullivan, Cornelius J., to Air Reduction Company, Incorporated. Arc welding in narrow gap. 3,576,966, Cl. 219-137.
- Sullivan, Leroy J.: See—
Ruger, William B.; and Sullivan, Leroy J., 3,577,668.
- Sumitomo Chemical Company, Ltd.: See—
Machida, Takuo; and Nakagawa, Masataka, 3,577,217.
- Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.
- Sun Oil Company: See—
Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,577,479.
- Schneider, Abraham, 3,577,468.
- Schneider, Abraham, 3,577,469.
- Surdy, Rohinton J.; and Trollmann, Conrad, to International Business Machines Corporation. Solder reflow device. 3,576,969, Cl. 219-221.
- Susin, Victor G. Apparatus for making multi-duct conduit. 3,577,612, Cl. 25-41.
- Sussenguth, Edward H.: See—
Cocke, John; Dauber, Philip S.; Schorr, Herbert; and Sussenguth, Edward H., 3,577,190.
- Cocke, John; Randell, Brian; Schorr, Herbert; and Sussenguth, Edward H., 3,577,189.
- Suzukamo, Gohu: See—
Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.

- Suzuki, Hiroshi: *See—*
Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
- Sweeney, Richard F.; and Price, Alson K., to Allied Chemical Corporation. Alkanoyl derivatives of fluorinated amides. 3,577,447, Cl. 260-404.5
- Sweeney, Richard Francis: *See—*
Anello, Louis Gene; Sweeney, Richard Francis; and Litt, Morton Herbert, 3,577,465.
- Swierczewski, Witold E.; and Swierczewski, Witold E., to American Telephone and Telegraph Company. Allotter circuit for sequential indication of incoming telephone calls. 3,577,155, Cl. 179-27.
- Swierczewski, Witold E.: *See—*
Swierczewski, Witold E.; and Swierczewski, Witold E., 3,577,155.
- Swift, Billy K.: *See—*
Brickner, David R.; and Swift, Billy K., 3,576,986.
- Swiss Aluminium Ltd.: *See—*
Fricker, Karl, 3,577,755.
- Sylvania Electric Products Inc.: *See—*
Barry, Thomas L., 3,577,169.
Dodds, Robert E., 3,577,351.
Koury, Frederic; and Waymouth, John F., 3,577,029.
- Szakacs, James. Automatic film splicing machine. 3,577,302, Cl. 156-504.
- Szegho, Constantin S., to Zenith Radio Corporation. Low noise image intensifier. 3,577,027, Cl. 313-101.
- Szerejko, Walter J.: *See—*
Bock, Herbert G.; and Szerejko, Walter J., 3,577,696.
- Szbelick, Francis P.: *See—*
Bullard, Calvin P.; and Szbelick, Francis P., 3,577,596.
- Tai, Wun T., to Koppers Company, Inc. Polyester tire cord adhesive dips. 3,577,377, Cl. 260-29.7
- Tajima, Tatsuya: *See—*
Nishio, Fumihiko; Ohi, Reiichi; and Tajima, Tatsuya, 3,577,240.
- Takada, Hiroshi: *See—*
Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, 3,576,951.
- Takemura, Yasuo: *See—*
Yagi, Motoi; and Takemura, Yasuo, 3,577,153.
- Tamai, Yasuo: *See—*
Sato, Masamichi; Tamai, Yasuo; Matsumoto, Seiji; and Akashi, Goro, 3,577,259.
- Tamura, Kihachi; Nakajima, Isao; and Inoue, Kaname, to Shin-Etsu Chemical Industry Co., Ltd. Method of manufacturing urethane foam by the use of poly (vinyl-alkoxy silanes). 3,577,362, Cl. 260-2.5
- Tandler, Paul; and Blackwell, Ellis R., to Cerro Corporation. Method of and apparatus for preparing copper and brass billets for extrusion into hollow shells. 3,577,759, Cl. 72-254.
- Taniguchi, Fumio. Binding and opening device. 3,577,575, Cl. 7-14.1
- Taplin, John Francis; and Munro, Alexander John, to Vickers Limited. Mechanisms for effecting fine and coarse adjustment. 3,577,790, Cl. 74-89.14
- Tarnowsky, Joseph: *See—*
Schneider, Alvin; and Tarnowsky, Joseph, 3,577,284.
- Tassie, Douglas Pray: *See—*
Ashley, Eugene; and Tassie, Douglas Pray, 3,577,826.
- Tatum, David: *See—*
Levan, Ambrose E.; and Tatum, David, 3,577,214.
- Taylor, Charles W., Jr.; and Conrad, Daniel T., to Goodyear Tire & Rubber Company. The. Resin coatings containing zinc inclusions. 3,577,274, Cl. 117-213.
- Taylor, James R.; and Clements, Thomas C., to Neptune Meter Company. Meter reading system. 3,577,123, Cl. 340-146.1
- Taylor, Lloyd D., to Polaroid Corporation. Diffusion transfer photographic products and processes comprising acid-reacting reagents and polyether block copolymers as plasticizers therefor. 3,577,237, Cl. 96-3.
- Taylor, Robert C.: *See—*
Doan, Robert B.; and Taylor, Robert C., 3,577,248.
- Taylor-Winfield Corporation, The: *See—*
Woodward, Foster R., 3,577,627.
- Technology Consortium, Inc.: *See—*
Sofer, Uri Y.; and Kaltman, Irwin L., 3,577,693.
- Tehrani, Nadj Y.: *See—*
Feltzin, Joseph; and Tehrani, Nadj Y., 3,577,385.
- Teller, Daniel M.; Douglas, George H.; and Smith, Herchel, to American Home Products Corporation. 13 β -Alkyl-17-hydroxygon-4,14-dien-3-ones. 3,577,410, Cl. 260-239.55
- Telonic Industries, Inc.: *See—*
Welsh, Neil R.; and McCormick, Richard E., 3,577,031.
- Tepper, Sidney: *See—*
Bennett, Ambrose L.; and Tepper, Sidney, 3,577,677.
- Terry, David W.: *See—*
Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
- Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; Davis, William H.; Bishop, David A.; Terry, David W.; Jones, John E.; Heard, Roderick S.; and Davis, William H., 3,577,127.
- Tetra Pak AG: *See—*
Gustafson, Ake, 3,577,301.
- Tetteroo, Hans: *See—*
Adams, Charles R.; Arpe, Hans J.; Schulze-Steinen, Hans J.; Falbe, Jurgen F.; Edwards, Alan C.; and Tetteroo, Hans, 3,577,413.
- Texas Instruments, Incorporated: *See—*
Brennan, James, Jr., 3,577,137.
Bylander, Ernest G.; and Jarman, Hall, E., 3,577,631.
Cook, Charles R., Jr., 3,577,038.
Nardulli, Antonio, 3,577,111.
Niemann, George W.; and Stehlin, Robert A., 3,577,015.
- Texler, Jean Pierre, to Societe Gobin Daude (Societe Anonyme). Separable fastener elements. 3,577,608, Cl. 24-221.
- Textron Inc.: *See—*
Hutzler, George J.; and Schwenk, Carl L., 3,577,257.
- the United States of America, Air Force: *See—*
Struhrke, William F.; and Underwood, Charles R., 3,577,689.
- Thean, John T.: *See—*
Kremer, Charles J.; Brown, Donald S.; Apikos, Dominic; and Thean, John T., 3,577,373.
- Thetford Corporation: *See—*
Sargent, Ronald J.; Sargent, Charles L.; Sargent, Frank T.; and Hoffman, John A., 3,577,569.
- Thiokol Chemical Corporation: *See—*
Ashmore, Charles L., 3,577,449.
Falk, Robert A., 3,577,460.
- Thomas & Betts Corporation: *See—*
Hawkins, William M., 3,577,114.
Mariani, Remo; and Geisinger, George H., 3,577,601.
Netta, Louis A., 3,577,801.
- Thompson, Quentin E., to Monsanto Company. Organic esters of bivalent sulfur. 3,577,452, Cl. 260-456.
- Thomson, John A.; and Evill, Brian R., to Avery-Hardoll Limited. Counter-operated control systems. 3,577,188, Cl. 340-164.
- Thorpe, Donald H., to Hooker Chemical Corporation. Graft polymer of a vinyl monomer and a fire retardant polyester, and a butadiene polymer. 3,577,478, Cl. 260-862.
- Thorpe, Donald H., to Hooker Chemical Corporation. Graft polymer of a vinyl monomer and a fire retardant polyester. 3,577,480, Cl. 260-869.
- Throckmorton, Morford C., to Goodyear Tire and Rubber Company. The. Polymerization of conjugated dienes by means of a nickel fluoroborate hydrate/organometallic compound catalyst system. 3,577,396, Cl. 260-82.1
- Throckmorton, Morford C.: *See—*
Lal, Joginder; and Throckmorton, Morford C., 3,577,395.
- Thun, Rudolf E.: *See—*
Di Pietro, Americo R.; and Thun, Rudolf E., 3,577,037.
- Tilson, William H.: *See—*
Johnson, Wallace F.; and Tilson, William H., 3,576,990.
- Tischer, Friedrich J. Spherical air bearing gyro. 3,577,788, Cl. 74-5.6
- Todeschini, Eugenio, to Massey-Ferguson Services N.V. Braking system for a vehicle. 3,577,797, Cl. 74-479.
- Tokyo Shibaura Electric Co., Ltd.: *See—*
Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatu, Akihiro, 3,577,033.
Inagaki, Junpei; Sakamoto, Moriyoshi; Nakakita, Tsuneo; and Kitamura, Hiroyuki, 3,577,024.
Kubo, Moritada; and Asano, Kuniji, 3,577,773.
Yagi, Motoi; and Takemura, Yasuo, 3,577,153.
- Tomaich, George Ronald: *See—*
Welsh, Thomas Laurence; and Tomaich, George Ronald, 3,577,492.
- Tomlinson, Richard G.; Brown, Clyde O.; and Haught, Alan F., to United Aircraft Corporation. Fresnel zone laser coupling mirror. 3,577,094, Cl. 331-94.5
- Topper Corporation: *See—*
Bennett, Ambrose L.; and Tepper, Sidney, 3,577,677.
- Torti, Luigi; and Bertelli, Guido, to Montecatini Edison S.p.A. Method of bonding olefin elastomer to textile fiber and product obtained. 3,577,310, Cl. 161-227.
- Townsend, Joseph R., Jr.: *See—*
Keith, Frederick W., Jr.; Jones, Everett M.; and Townsend, Joseph R., Jr., 3,577,341.
- Toyo Bearing Manufacturing Company Limited: *See—*
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniti; and Uono, Fumito, 3,577,623.
- Toyo Boseki Kabushiki Kaisha: *See—*
Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihasi, Hikoyuki; and Ishitobi, Katsuya, 3,577,498.
- Traub, Karl: *See—*
Albsmeier, Hans; and Traub, Karl, 3,577,180.
- Trebs, Hans: *See—*
Scheller, Karlheinz; Koddermann, Else; and Trebs, Hans, 3,577,521.
- Tripoli, Joseph V.; and Caligiuri, John J., said Caligiuri assor. to said Tripoli. Process workpiece gaging apparatus. 3,577,642, Cl. 33-172.
- Trischler, Floyd D.; and Hollander, Jerome, to Whittaker Corporation. Highly fluorinated polymers. 3,577,356, Cl. 260-2.
- Trollmann, Conrad: *See—*
Surtz, Rohinton J.; and Trollmann, Conrad, 3,576,969.
- TRW Inc.: *See—*
Hilberg, Ronald P., 3,577,097.
- Tsoutsas, Demetrios T. Programmed timer. 3,577,004, Cl. 307-141.

- Tsujikawa, Kazunobu, to Sony Corporation. DC motor servo system. 3,577,056, Cl. 318-314.
- Turner Electric Corporation: *See—*
Turner, John L., 3,576,961.
- Turner, John L., to Turner Electric Corporation. Vacuum switch with operating means for arresting the movable contact in an intermediate position before complete opening. 3,576,961, Cl. 200-144.
- Turner, William R., to Vitro Corporation. System using a modified ultrasonic imaging tube. 3,577,171, Cl. 315-9.
- Tustin, Arnold, to British Railways Board. Pantographs. 3,576,957, Cl. 191-60.3
- Tuten, William J.; and Gauld, Godfrey R., to Avco Corporation. Long delay timing system. 3,577,168, Cl. 307-293.
- Tyrrrell, Cyril M., Sr. String and the like detention system. 3,577,606, Cl. 24-117.
- Tyrrrell, Leo A.; Castleberry, Daniel E.; and Weber, Charles A., to Collins Radio Company. Fail-safe pulsed logic and gate. 3,577,006, Cl. 307-218.
- Uchida, Masaaki. Process for continuously molding bottle from thermoplastic resin, charging and sealing. 3,577,291, Cl. 156-64.
- Uchida, Tomomi; Kondo, Takeshi; Takada, Hiroshi; Eguchi, Hiroaki; and Hasegawa, Kenichi, to Nippon Electric Company, Limited, and Fujitsu Limited. Calling subscriber identification system. 3,576,951, Cl. 179-18.
- Uchihasi, Hikoyuki: *See—*
Matsuo, Tatsuki; Nanri, Shosuke; Masuda, Ryunosuke; Uchihasi, Hikoyuki; and Ishitobi, Katsuya, 3,577,498.
- Ugine Kuhlmann: *See—*
Jirou, Marcel Georges; and Bouvet, Pierre Charles Victor, 3,577,212.
Weiss, Francis; and Lakodey, Andre, 3,577,216.
- Underwood, Charles R.: *See—*
Struhrke, William F.; and Underwood, Charles R., 3,577,689.
- Union Carbide Corporation: *See—*
Behr, Bryon C.; Sprogis, Gunars; and Booth, Frederick E., 3,577,003.
Elbert, Raymond J.; and Farrier, Ernest G., 3,577,226.
Fuks, Robert; and Viehe, Heinz G., 3,577,433.
Haines, Robert Glenn, 3,577,349.
Kingsbury, Archie R., 3,577,025.
Quandt, Herbert C., 3,577,245.
- United Aircraft Corporation: *See—*
Bruchez, Raymond J., Jr., 3,577,731.
Cook, Robert C., 3,577,043.
Tomlinson, Richard G.; Brown, Clyde O.; and Haught, Alan F., 3,577,094.
- United Engineering and Foundry Company: *See—*
Adair, James Richard, 3,577,758.
- United Merchants and Manufacturers, Inc.: *See—*
Quintero, Eusebio V., 3,577,141.
- United States of America, Army: *See—*
Kliman, Ivan M.; and Smola, Harold, 3,577,086.
- United States of America, Agriculture: *See—*
DeBernardo, Luigi U., 3,577,711.
Graham, John S., 3,577,600.
Wadsworth, James I.; Gallo, Alexander S.; Ziegler, George M., Jr.; and Spadaro, James J., 3,577,649.
- Air Force: *See—*
Freier, Michael; and Balazer, Leonard P., 3,577,146.
Goggins, William B., Jr., 3,577,088.
Goldie, Harry, 3,577,028.
Hasinger, Siegfried H., 3,577,022.
Henderson, Albert G., 3,577,775.
Kislin, Benjamin; and Miller, J. W., 3,577,566.
Rachal, Francis; and McKone, Donald B., 3,577,091.
Stevens, Donald W., 3,576,996.
Stevens, Emerson W., 3,577,736.
Warner, David A., 3,577,000.
Worden, Robert A.; Hair, Hugh H.; Gerst, Carl W.; and Viglietta, Benadict, 3,577,145.
- Army: *See—*
Akw, Robert E.; and Johnson, Henry C., 3,577,100.
Duke, Jimmy R.; and Miller, Walter E., Jr., 3,577,017.
Jones, Howard S., Jr., 3,577,105.
Korr, Abraham L., 3,577,764.
Nirschl, Joseph C.; and Mooney, G. Edgar, Jr., 3,576,995.
Peachar, Teddy J., 3,577,697.
Sandler, Melvin H.; and Cohen, Merrill, 3,577,379.
Simpson, George R., 3,577,093.
Walliser, Sylvan A.; and Asquith, Claire F., 3,577,077.
- Atomic Energy Commission: *See—*
Ardary, Zane L.; Maxey, Andrew W.; and Reynolds, Carl D., 3,577,344.
Baird, Justus N., Jr.; Johnson, James S.; Kraus, Kurt A.; and Perona, Joseph J., 3,577,339.
Beatty, Ronald L.; Leitnaker, James M.; and Notz, Karl J., Jr., 3,577,485.
Haerberli, Willy, 3,577,026.
Parks, Paul B.; and Brown, Mark, 3,576,994.
Schultz, Warner W., 3,577,199.
Shaffer, James H.; Moulton, David M.; and Grimes, Warren R., 3,577,225.
Steffens, Robert W.; and Zeitschel, Milton F., 3,577,774.
Woods, Cornelius H., 3,577,317.
- United States of America, Atomic Energy Commission: *See—*
Zic, John A.; Hill, George F.; and Mayfield, Ross M., 3,577,283.
- Health, Education and Welfare: *See—*
Preston, Kendall, Jr.; and Norgren, Philip E., 3,577,267.
- Interior: *See—*
Kessler, Theodore; Sharkey, Andrew G., Jr.; Malli, Joseph, Jr.; and Friedel, Robert A., 3,577,337.
Lacey, Robert E.; and Mintz, Milton S., 3,577,331.
- National Aeronautics and Space Administration, Administrator, with respect to an invention of:
O'Neill, Robert W. Monostable multivibrator with complementary NOR gates. 3,577,014, Cl. 307-273.
- Navy: *See—*
Cusick, Richard T.; and Bunt, Edgar A., 3,577,030.
Davies, Gail F., 3,577,227.
Dawson, Victor C. D.; and Seigel, Arnold E., 3,577,590.
Edwards, Earl A., 3,577,527.
Fischer, Raymond C.; and Levenson, Norton J., 3,577,605.
Hoffman, Eric J., 3,577,013.
Hoffman, Eric J., 3,577,062.
Kruger, Lawrence W., 3,576,947.
LaBaw, Kenneth B., 3,576,944.
Lee, Henry J., 3,577,493.
Oliphant, William J., 3,577,730.
Petrick, John T., 3,577,208.
Steen, Donald B., 3,577,135.
- United States Steel Corporation: *See—*
Williams, Alvin R., 3,576,964.
- United-Carr Incorporated: *See—*
Seckerson, Clifford Alexander; and Collyer, Robert C., 3,577,603.
- Uono, Fumito: *See—*
Ono, Yosio; Nakamura, Hiroshi; Inoue, Takasi; Horie, Yosio; Matui, Juniti; and Uono, Fumito, 3,577,623.
- Upjohn Company, The: *See—*
Hessler, Edward J., 3,577,406.
- U.S. Philips Corporation: *See—*
Lanooy, Cornelis; and Mensen, Herbert, 3,576,956.
Perilhou, Jean; and Auphan, Michel Joseph, 3,577,772.
- USM Corporation: *See—*
Innocenti, Thomas J., 3,577,503.
- Usrey, Eldo Gene. Teaching aid. 3,577,661, Cl. 35-32.
- Uyeda, Tim M.: *See—*
Maguire, John; Uyeda, Tim M.; and Wahler, Theodore George, 3,577,674.
- Valek, Robert J.: *See—*
Russo, Frank A.; and Valek, Robert J., 3,576,976.
- Valette, Louis R., to Societe Anonyme dite: Institut Merieux. Stabilized smallpox vaccine. 3,577,526, Cl. 424-89.
- Vandegaer, Jan E., to Pennwalt Corporation. Encapsulation by interfacial polycondensation. 3,577,515, Cl. 424-32.
- Vanden Broek, Jan Abraham, to Conduccion Corporation. Control system. 3,577,791, Cl. 74-89.15
- Van Den Munchhof, Peter J. W. Cutting blade for rotary mower. 3,577,717, Cl. 56-295.
- Van Doornewaard, Hans: *See—*
Schmick, Hayes J.; and Van Doornewaard, Hans, 3,577,721.
- Van Duuren, Hendrik Cornelis Anthony; and Da Silva, Herman, to De Staat Der Nederlanden, Ten Deze Vertegenwoordigd Door de Directeur-Generaal Der Posterijen, Telegrafie en Telefonie. Forward error correcting code telecommunicating system. 3,576,952, Cl. 178-23.1
- Varheli, Leslie Gaza, to Northern Electric Company Limited. Adjustable iris. 3,577,106, Cl.
- Varian Associates: *See—*
Weaver, Harry E., Jr., 3,577,067.
- Vartanian, Edwin S.: *See—*
Billett, William J.; and Vartanian, Edwin S., 3,577,827.
- Velsicol Chemical Corporation: *See—*
Hanna, Delbert L., 3,577,482.
Raden, Daniel S., 3,577,364.
- Venczel, Joseph, to Electronit Limited. Inspection apparatus for circular knitting machines. 3,577,750, Cl. 66-157.
- Vernitron Corporation: *See—*
Quatse, Jesse T.; and Dixon, Brook, 3,577,201.
- Vickers Limited: *See—*
Taplin, John Francis; and Munro, Alexander John, 3,577,790.
- Videen, Otis R.; and Wiegand, Donald E., to Conwed Corporation. Felted fibrous web or batt. 3,577,312, Cl. 162-148.
- Viehe, Heinz G.: *See—*
Fuks, Robert; and Viehe, Heinz G., 3,577,433.
- Viglietta, Benadict: *See—*
Worden, Robert A.; Hair, Hugh H.; Gerst, Carl W.; and Viglietta, Benadict, 3,577,145.
- Vilter Manufacturing Corporation: *See—*
Kocher, Erich J., 3,577,742.
Long, Joseph N., 3,577,743.
- Vincent, Georges, to Societe Grenobloise d'Etudes et d'Applications Hydrauliques (SOGREAH). Swimming pools. 3,577,570, Cl. 4-172.17
- Vinson, Leonard J., to Lever Brothers Company. Synergistic antibacterial composition. 3,577,539, Cl. 424-231.
- Visser, Gerrit A., to Boeing Company, The. Sub-zero cutting fluid generator. 3,577,808, Cl. 77-55.
- Vitro Corporation: *See—*
Turner, William R., 3,577,171.

- Vodra, Victor H.: *See—*
Means, Ray H.; Kussman, Michael; Wade, Jack; and Vodra, Victor H., 3,577,241.
- Voight, Heinz Kurt Walter; and Myers, Robert Lee, to American Cyanamid Company. Chemical lighting device to store, initiate and display chemical light. 3,576,987, Cl. 240-2.25
- Von Brimer, Joe W.; and Roth, Herman P., said Von Brimer assor. of 25% to General Scientific Laboratories, Inc. Exhaust gas processing system. 3,577,728, Cl. 60-30.
- Von Falkai, Bela: *See—*
Kohler, Armin; Von Falkai, Bela; Offermann, Klaus; and Reichle, Alfred, 3,577,500.
- Vorontsov, Evgeny Nikolavovich. Device for stripping out shielding sheath. 3,577,813, Cl. 81-9.51
- Vowels, Freeman M., to American Air Filter Company, Inc. Welding method. 3,576,963, Cl. 219-92.
- Waag, Norman E. Sand blasting equipment. 3,577,681, Cl. 51-8.
- Wada, Toshio; Matsukura, Yasuo; and Ohta, Kunitichi, to Nippon Electric Company. High-speed logic device employing a Gunn-effect element and a semiconductor laser element. 3,577,018, Cl. 307-299.
- Wade, Jack: *See—*
Means, Ray H.; Kussman, Michael; Wade, Jack; and Vodra, Victor H., 3,577,241.
- Wadsworth, James I.; Gallo, Alexander S.; Ziegler, George M., Jr.; and Spadaro, James J., to United States of America, Agriculture. Device and method for controlling bulk density of dehydrated foodstuffs. 3,577,649, Cl. 34-110.
- Wagner, Harold H., to Caterpillar Tractor Company. Fuel system for natural gas turbocharged engine. 3,577,726, Cl. 60-13.
- Wahler, Theodore George: *See—*
Maguire, John; Uyeda, Tim M.; and Wahler, Theodore George, 3,577,674.
- Walde, Robert A.: *See—*
Erby, William A.; and Walde, Robert A., 3,577,546.
- Walker, Ambrose D., 1/2 to O'Brien, Leo X. Device for retensioning eye glass frames. 3,577,811, Cl. 81-3.5
- Walker, John H., to Bendix Corporation, The. Fluidic gage. 3,577,766, Cl. 73-37.9
- Wallace, Robert T.: *See—*
Santelli, Thomas R.; and Wallace, Robert T., 3,577,358.
- Waller, John G.: *See—*
Pearl, David L.; Head, Beverly P., Jr.; and Waller, John G., 3,577,495.
- Wallis, George; and Dorsey, John J., to Mallory, P. R., & Co. Inc. Bonding oxidizable metals to insulators. 3,577,629, Cl. 29-472.9
- Walliser, Sylvan A.; and Asquith, Claire F., to United States of America, Army. Apparatus for measuring the amount of modulation response to a differential input signal. 3,577,077, Cl. 324-140.
- Walsh, William L.: *See—*
McNulty, John G.; and Walsh, William L., 3,577,471.
- Walton, Charles J.: *See—*
Zelley, Walter G.; and Walton, Charles J., 3,577,288.
- Warawa, Edward John; and Biel, John Hans. α -Propargylamino-propio-phenones and the salts thereof. 3,577,461, Cl. 260-570.5
- Ward, John M., to Armstrong Cork Company. Carbon monoxide detector. 3,577,222, Cl. 23-254.
- Warner, David A., to United States of America, Air Force. Synchro-resolver with optical feedback loop. 3,577,000, Cl. 250-230.
- Warner-Lambert Pharmaceutical Company: *See—*
Kaminsky, Daniel E.; Meltzer, Robert I.; and Shavel, John, Jr., 3,577,441.
- Warren, Glenn B. Reciprocating internal combustion engine with constant pressure combustion. 3,577,729, Cl. 60-39.63
- Warren, Joel A.; and Marsee, Frederick J., to Ethyl Corporation. Method of reducing internal combustion engine emissions. 3,577,727, Cl. 60-29.
- Washall, Thomas A.; and Blittman, Sidney, to Atlantic Richfield Company. Separation of olefins from epoxides. 3,577,443, Cl. 260-348.
- Watts, Chester B., Jr. Slotted cable localizer antenna. 3,577,197, Cl. 343-771.
- Waymouth, John F.: *See—*
Koury, Frederic; and Waymouth, John F., 3,577,029.
- Weaver, Harry E., Jr., to Varian Associates. Persistent mode superconductive orthogonal gradient cancelling coils. 3,577,067, Cl. 324-0.5
- Weber, Charles A.: *See—*
Tyrrell, Leo A.; Castleberry, Daniel E.; and Weber, Charles A., 3,577,006.
- Wei, Peter H. L.: *See—*
Bell, Stanley C.; and Wei, Peter H. L., 3,577,434.
- Weidmann, Hans E., to Allen-Bradley Company. Low pass active filter. 3,577,016, Cl. 307-297.
- Weigert, Wolfgang: *See—*
Schwarze, Werner; Giesselmann, Gunter; and Weigert, Wolfgang, 3,577,416.
- Weinstein, Harold; and Snyder, Edward, III. Teaching aid. 3,577,658, Cl. 35-9.
- Weir, G. & J., Limited: *See—*
Randell, Forrest Thompson, 3,577,320.
- Weisenborn, Frank Lee: *See—*
Meyers, Edward; Parker, William Lawrence; Weisenborn, Frank Lee; Pansy, Felix Edward; and Principe, Pacifico Anthony, 3,577,530.
- Weiss, Francis; and Lakodey, Andre, to Uguine Kuhlmann. Process for the recovery of selenium IV utilized as a catalyst for oxidation reactions. 3,577,216, Cl. 23-50.
- Welsh, Neil R.; and McCormick, Richard E., to Telonic Industries, Inc. Multi-color oscilloscope. 3,577,031, Cl. 315-13.
- Welsh, Thomas Laurence; Peterson, Donald Leroy; Palermo, Blasey Thomas; and Hoss, George Carr, to Miles Laboratories, Inc. Effervescent tablet and process for making same. 3,577,490, Cl. 264-120.
- Welsh, Thomas Laurence; and Tomaich, George Ronald, to Miles Laboratories, Inc. Tabletting lubricant. 3,577,492, Cl. 264-120.
- Welwyn Electric Limited: *See—*
Edge, James, 3,577,276.
- Wendt, Gerhard R.: *See—*
Oliver, Donald W.; and Wendt, Gerhard R., 3,577,445.
- Werner, Eberhard: *See—*
Schmitz, Peter Josef; Werner, Eberhard; and Seifried, Walter, 3,577,510.
- West, Duval, to Geo Space Corporation. Active filter. 3,577,179, Cl. 330-107.
- Western Electric Company, Incorporated: *See—*
Blitchington, Frank H., Jr., 3,577,335.
- Fairchild, Albert R., 3,577,325.
- Whitekettle, Howard C., Jr., 3,577,070.
- Western Gear Corporation: *See—*
Whelan, Ray W.; and Atelian, Edmond J., 3,577,777.
- Western Gold & Platinum Company: *See—*
Gamer, Nicholas T., 3,577,233.
- Westgate-California Foods, Inc.: *See—*
Brynagte, Peter W., 3,577,243.
- Westinghouse Learning Corporation: *See—*
McMillin, John V., 3,577,142.
- Wexler, Norman. Picture holder. 3,577,666, Cl. 40-152.
- Weyerhaeuser Company: *See—*
Hendrickson, Hubert E.; and Mc Cain, Charles N., 3,577,368.
- Hendrickson, Hubert E.; and McCain, Charles N., 3,577,369.
- Whelan, Ray W.; and Atelian, Edmond J., to Western Gear Corporation. Inertia system for dynamometers. 3,577,777, Cl. 73-133.
- White, James E. X-ray gauging apparatus with X-ray opaque markers in the X-ray path to indicate alignment of X-ray tube, subject and film. 3,577,160, Cl. 250-59.
- White, Robert J., to Chevron Research Company. Preparation of a cogelled catalyst of alumina and a group VI hydrogenating component. 3,577,353, Cl. 252-465.
- White, Trevor Raymond, to Imperial Chemical Industries Limited. Sorption. 3,577,707, Cl. 55-68.
- Whitehead, Derek James: *See—*
Roebuck, Peter; and Whitehead, Derek James, 3,577,513.
- Whitekettle, Howard C., Jr., to Western Electric Company, Incorporated. Methods of and systems for performing testing of conductors for defective insulation and continuity. 3,577,070, Cl.
- Whitfield, Marshall G.; Parzuchowski, Richard S.; and Moore, Dennis B., to Cabot Corporation, mesne. Method of coating iron, nickel or cobalt alloy with aluminum. 3,577,268, Cl. 117-107.2
- Whitright, Joseph W. E., to Cheshire Manufacturing Co., Inc. Electrical connector storing device for motor vehicle trailers. 3,577,115, Cl. 339-36.
- Whittaker Corporation: *See—*
Hutkin, Irving J., 3,577,193.
- Trischler, Floyd D.; and Hollander, Jerome, 3,577,356.
- Whitten, Frank R.; and Fields, Roger O., to Schlumberger Technology Corporation. Tool to take multiple fluid measurements. 3,577,783, Cl. 73-152.
- Whittle, Benjamin. Apparatus for repairing tire casings. 3,577,592, Cl. 18-18.
- Wicker, Betty M.: *See—*
Holzschuh, Donald L.; and Wicker, Betty M., 3,577,148.
- Wideburg, Norman E.; and Miller, Laura H., to Abbott Laboratories. 4-[τ -[4-(2-, or 3-Halo-p-tolyl)-1-piperazinyl] alkoxy]- β,β -dimethylhydrocinnamic acid esters. 3,577,422, Cl. 260-268.
- Widl, Gerhard; Groetzner, Kurt; and Knodler, Adolf, to Bosch, Robert, G.m.b.H. AC operated magnet. 3,577,107, Cl. 335-248.
- Wieg, Heinrich J.: *See—*
Sanford, Norman R.; and Wieg, Heinrich J., 3,577,039.
- Wiegand, Donald E.: *See—*
Videen, Otis R.; and Wiegand, Donald E., 3,577,312.
- Wiener, Hans Berthold: *See—*
Kenworthy, Jeffrey Stuart; and Wiener, Hans Berthold, 3,577,740.
- Williamette Valley Company: *See—*
Buck, Erville C., 3,577,303.
- Williams, Alvin R., to United States Steel Corporation. Welded joint. 3,576,964, Cl. 219-92.
- Wilson, Harlan J., to Marguardt Industrial Products Co. Track circuit pickup unit. 3,576,991, Cl. 246-40.
- Wilson, Warren K., to Goodyear Tire & Rubber Company, The. Stabilization of polyesters. 3,577,211, Cl. 8-115.5
- Wing, Douglas J.; and Ramey, William A., to General Motors Corporation. Brake fluid level switch. 3,577,121, Cl. 340-59.
- Winkler, De Loss E., to Shell Oil Company. Selectively sulfonated block copolymers. 3,577,357, Cl. 260-2.2
- Winston, Harvey V., to Hughes Aircraft Company. Thermally compensated laser. 3,577,098, Cl. 331-94.5
- Wintercorn, Andrew F.: *See—*
Stata, Stanley S., 3,577,581.
- Wintercorn, Andrew F. Modified multi-purpose bidet. 3,577,567, Cl. 4-7.
- Wolf, John E., to Security Systems, Inc. Short-range signaling system. 3,577,136, Cl. 340-280.

- Wolf, William D.: *See—*
Serrano, Mario; and Wolf, William D., 3,577,589.
- Wood, Daniel J.; and Wood, Harold E. Document carrier. 3,576,972, Cl. 235-61.12
- Wood, Harold E.: *See—*
Wood, Daniel J.; and Wood, Harold E., 3,576,972.
- Wood Industries, Inc.: *See—*
Ricards, Charles L.; and McColley, Daniel, 3,577,591.
- Woods, Cornelius H., to United States of America, Atomic Energy Commission. Controlled fusion reactor. 3,577,317, Cl. 176-4.
- Woodward, Foster R., to Taylor-Winfield Corporation, The. Method and apparatus for aligning strip in strip joining equipment. 3,577,627, Cl. 29-464.
- Woollett, Roy Perry. Construction kits for toys and models. 3,577,671, Cl. 46-16.
- Worden, Robert A.; Hair, Hugh H.; Gerst, Carl W.; and Viglietta, Benadict, to United States of America, Air Force. Radar system spin echo correlator. 3,577,145, Cl. 343-17.2
- Work, Edgar A., Jr.: *See—*
Blythe, Richard; Scott, Gerald C.; Work, Edgar A., Jr.; Lowe, Donald S.; and Hasell, Philip G., Jr., 3,576,999.
- Worth, Joseph P.: *See—*
Glaze, John W., Jr.; and Worth, Joseph P., 3,577,300.
- Wright, Dennis; and Adams, Thomas, to Bentley Machine Development Company Limited, The. Circular knitting machines. 3,577,749, Cl. 66-50.
- Wyandotte Chemicals Corporation: *See—*
Hymes, Alan C., 3,577,522.
- Wyles, Peter J., to Newage Lyon Limited. Control apparatus for electric alternators. 3,577,061, Cl. 322-27.
- Xerox Corporation: *See—*
Beach, Kenneth M., Jr., 3,577,203.
- Jacknow, Burton B.; and Moriconi, Joseph H., 3,577,345.
- Pichel, Marlowe A., 3,577,323.
- Sato, Masamichi; Tamai, Yasuo; Matsumoto, Seiji; and Akashi, Goro, 3,577,259.
- Yabu, Ikuta: *See—*
Ikoma, Yasaburo; and Yabu, Ikuta, 3,577,607.
- Yagi, Motoi; and Takemura, Yasuo, to Tokyo Shibaura Electric Co., Ltd. Image pickup apparatus. 3,577,153, Cl. 178-7.2
- Yahagi, Koichi, to Nippon Columbia Company, Limited. Arrangement for color television receiver. 3,577,152, Cl. 178-5.4
- Yamanouchi Pharmaceutical Co., Ltd.: *See—*
Murakami, Masuo; Kuriaki, Kaname; Iwanami, Masaru; Arima, Hideki; Sano, Kenji; Suzuki, Hiroshi; and Kagami, Soichi, 3,577,551.
- Yatsurugi, Yoshifumi: *See—*
Kuratomi, Tatsuo; and Yatsurugi, Yoshifumi, 3,577,220.
- Yon, Eugene T.: *See—*
Gri, Norman I.; and Yon, Eugene T., 3,577,175.
- Yoneyoshi, Yukio: *See—*
Nagase, Tsuneyuki; Suzukamo, Gohu; Masuko, Fujio; Yoneyoshi, Yukio; Fukao, Masami; and Fujiwara, Masahiro, 3,577,473.
- York, Monte H., to Goodyear Tire & Rubber Company, The. Mold dope and process of using. 3,577,501, Cl. 264-213.
- Yoshihashi, Tamaji: *See—*
Aoki, Ichiro; Iwasaki, Kenji; Yoshihashi, Tamaji; Koinuma, Tokuju; Kato, Masao; and Fukatu, Akihiro, 3,577,033.
- Yoshitomi Pharmaceutical Industries, Ltd.: *See—*
Nakanishi, Michio; Arimura, Katsuo; Imamura, Hiroshi; and Kobayakawa, Toshihiro, 3,577,425.
- Young, Henry R.: *See—*
Bellinson, Bernard; and Young, Henry R., 3,577,571.
- Yung, Abraham K., to RCA Corporation. C-MOS dynamic binary counter. 3,577,166, Cl. 307-279.
- Zadell, Henry J.: *See—*
Martin, Thomas B.; and Zadell, Henry J., 3,577,087.
- Zak, Alfred M. Lock washer. 3,577,577, Cl. 10-73.
- Zapata Industries Inc.: *See—*
Smith, Donald C.; and Koshada, Robert E., 3,577,595.
- Zax, Natan Albertovich; Korzhov, Vasily Porfirievich; and Rabinovich, Roza Semenovna. Device for twisting yarn. 3,577,720, Cl. 57-58.89
- Zearfoss, Elmer W., Jr., to Philco-Ford Corporation. Ice making apparatus. 3,577,745, Cl. 62-345.
- Zelley, Walter G.; and Walton, Charles J., to Aluminum Company of America. Bohemite-coated aluminum textile pilm. 3,577,288, Cl. 148-6.27
- Zenith Radio Corporation: *See—*
Frizane, Kenneth, 3,576,946.
- Sparks, David E., 3,577,103.
- Szegho, Constantin S., 3,577,027.
- Zeutschel, Milton F.: *See—*
Steffens, Robert W.; and Zeutschel, Milton F., 3,577,774.
- Zic, John A.; Hill, George F.; and Mayfield, Ross M., deceased (by Mayfield, Georgia P.; sole heir), to United states of America, Atomic Energy Commission. Method of case hardening vanadium and vanadium alloys. 3,577,283, Cl. 148-20.3
- Ziegler, George M., Jr.: *See—*
Wadsworth, James I.; Gallo, Alexander S.; Ziegler, George M., Jr.; and Spadaro, James J., 3,577,649.
- Ziemek, Gerhard Karl, to Kabel-und Metallwerke Gutehoffnungshutte Aktiengesellschaft. Electrical cables and method of making same. 3,576,939, Cl. 174-107.
- Zotos International, Inc.: *See—*
Mc Donough, Everett G.; and Edman, Walter W., 3,577,528.
- Zurawski, Walter S. Leveling apparatus for installation of raised floors. 3,577,645, Cl. 33-209.

LIST OF DEFENSIVE PUBLICATIONS

APPLICANTS TO WHOM
DEFENSIVE PUBLICATIONS WERE ISSUED ON THE 4TH DAY
OF MAY, 1971

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O. G. 687.

Atadan, Erdem M., to E. I. du Pont de Nemours and Company. Purification of dipotassium terephthalate. T886,004, 5-4-71, Cl. 260—325.
Du Pont de Nemours, E. I., and Company: See—
Atadan, Erdem M. T886,004.
Holness, David E. T886,009.
Wolinski, Leon E. T886,003.
Wolinski, Leon E. T886,005.
Wolinski, Leon E., and Harris. T886,002.
Ford Motor Company: See—
Gabriel, Martin G. T886,001.
Gabriel, Martin G., to Ford Motor Company. Hydrokinetic power transmission system with a substantially ideal functional relationship between output speed and tractive effort. T886,001, 5-4-71, Cl. 74—732.
Harris, Roland G.: See—
Wolinski, Leon E., and Harris. T886,002.
Harvey, John V., B. A. Robinson, and J. W. Staassen. Apparatus for detecting oversize defects in yarn. T886,007, 5-4-71, Cl. 73—160.
Holness, David E., to E. I. du Pont de Nemours and Company. Transmission cables. T886,009, 5-4-71, Cl. 174—25.
McConkey, James E. Drawing board. T886,008, 5-4-71, Cl. 312—23.
Nichols, Daniel R. Linear four-quadrant multiplier. T886,006, 5-4-71, Cl. 307—229.
Robinson, Bruce A.: See—
Harvey, John V., Robinson, and Staassen. T886,007.
Staassen, John W.: See—
Harvey, John V., Robinson, and Staassen. T886,007.
Wolinski, Leon E., to E. I. du Pont de Nemours and Company. Gauge control of foam structures. T886,003, 5-4-71, Cl. 264—51.
Wolinski, Leon E., to E. I. du Pont de Nemours and Company. Printing inks. T886,005, 5-4-71, Cl. 106—27.
Wolinski, Leon E., and R. G. Harris, to E. I. du Pont de Nemours and Company. Preparation of oriented foam laminar structures. T886,002, 5-4-71, Cl. 156—311.

LIST OF DESIGN PATENTEES

TO WHOM
PATENTS WERE ISSUED ON THE 4TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

AMF Inc.: See—
Purdy, Frederick E. 220,668.
Beck, Theodore A., to Scovill Manufacturing Co. Aerosol actuating button protector. 220,613, 5-4-71, Cl. D9—258.
Benty, John L., and S. Fischlein, to Bristol-Myers Co. A heat housing for hair curlers. 220,665, 5-4-71, Cl. D86—10.
Berkoff, Daniel A., to Hollywood Accessories. Automobile sun visor. 220,618, 5-4-71, Cl. D14—6.
Boldt, Melvin H., and K. T. Parsell, to Zenith Radio Corp. Combined radio and record changer. 220,654, 5-4-71, Cl. D56—4.
Boyer, Lola E.: See—
Boyer, Richard G., and L. E. 220,635.
Boyer, Richard G., and L. E. Astrology game board. 220,635, 5-4-71, Cl. D34—5.
Bristol-Myers Co.: See—
Benty, John L., and Fischlein. 220,665.
Buhner, Werner, to Cerberus A.G. Automatic fire alarm or similar article. 220,662, 5-4-71, Cl. D72—1.
Cannon Mills Co.: See—
Taiman, Edward C. 220,671.
Cerberus A.G.: See—
Buhner, Werner. 220,662.
Christoffersen, William K., J. L. Keely, W. T. Owens, Jr., and L. D. Quanrud, to Washington Scientific Industries, Inc. Rear projection viewer. 220,658, 5-4-71, Cl. D61—1.
Christoffersen, William K., J. L. Keely, and W. T. Owens, Jr., to Washington Scientific Industries, Inc. A rear projection viewer. 220,657, 5-4-71, Cl. D61—1.
Churchman, Fred L., and G.B. and M. A. Glasgow. Fish lure. 220,623, 5-4-71, Cl. D22—27.
Corning Glass Works: See—
Mercadante, Ottorino N. 220,638.
Crew, Robert T. Holder for attachment to a telephone or the like. 220,628, 5-4-71, Cl. D20—14.
Darbo, Rolf E. Finding for costume jewelry or the like. 220,640, 5-4-71, Cl. D45—1.
Dart Industries, Inc.: See—
Swett, James B., and Smith. 220,637.
Dian, Walter: See—
Wrobel, Charles V., Dian, and Golden. 220,669.
Dickins, Michael C., to Plysu Containers Ltd. Jug or similar article. 220,609, 5-4-71, Cl. D9—43.
Dunlop Co. Ltd.: See—
Mills, Iain C. 220,670.
Elden Industries, Inc.: See—
Rome, Herbert, and Paulson. 220,633.
Excel Inc.: See—
Wrobel, Charles V., Dian, and Golden. 220,669.
Fischlein, Svend: See—
Benty, John L., and Fischlein. 220,665.
Fontana, Basilio. Game board or the like. 220,634, 5-4-71, Cl. D84—5.
Glasgow, Garney B.: See—
Churchman, Fred L., and Glasgow, G.B. and M.A. 220,623.
Green, Homer T., to The Parker Pen Co. Fountain pen nib. 220,663, 5-4-71, Cl. D74—17.
Hamburger Hamlets, Inc.: See—
Lewis, Marilyn. 220,641.
Hills, David G., to Monsanto Co. Jug. 220,610, 5-4-71, Cl. D9—48.
Hills, David G., to Monsanto Co. Bottle. 220,611, 5-4-71, Cl. D9—117.
Hirayama, Kazuhiro, and H. Nakada, to Hitachi, Ltd., Manufacturers. Portable radio cabinet. 220,652, 5-4-71, Cl. D56—4.
Hitachi, Ltd., Manufacturers: See—
Hirayama, Kazuhiro, and Nakada. 220,652.
Koshido, Yasuhiro, Kondou, Ninomiya, and Sato. 220,667.
Holbrook, Harry W. Combined platform and ramp. 220,673, 5-4-71, Cl. D13—7.
Hollywood Accessories: See—
Berkoff, Daniel A. 220,618.
Holloway, Toni. Bridge extension for eyeglasses. 220,655, 5-4-71, Cl. D57—1.
Hycel, Inc.: See—
Moran, John J., and Querry. 220,621.
Iida, Yoshiaki, to Matsushita Electric Industrial Co., Ltd. Combined amplifier housing and base for a record player or similar article. 220,631, 5-4-71, Cl. D26—14.
Intercon Research, Inc.: See—
Passander, Robert J. 220,622.
Jones, Eugene F. Lounge. 220,620, 5-4-71, Cl. D15—11.
Keely, James L.: See—
Christoffersen, William K., Keely, Owens, and Quanrud. 220,658.
Christoffersen, William K., Keely, and Owens. 220,657.
Kerr-Hays Co.: See—
Todd, Burt K. 220,639.
Kohner Bros., Inc.: See—
Stubbmann, Albert. 220,636.
Koshido, Yasuhiro, H. Kondou, K. Ninomiya, and I. Sato, to Hitachi, Ltd. Blender or similar article. 220,667, 5-4-71, Cl. D89—1.
Kurihara, Ippli, to Matsushita Electric Industrial Co., Ltd. Combined amplifier and tape recorder. 220,632, 5-4-71, Cl. D26—14.
Kuze, Yoshikazu. Thermostat. 220,649, 5-4-71, Cl. D52—7.
Kwolek, Stephen. Weather vane. 220,645, 5-4-71, Cl. D52—6.
Lewis, Marilyn, to Hamburger Hamlets, Inc. Lighting fixture. 220,641, 5-4-71, Cl. D48—4.
Lillibridge, Reba M. Therapeutic creeping device. 220,666, 5-4-71, Cl. D88—5.
Line, Ronald H. Boat. 220,661, 5-4-71, Cl. D71—1.
Macpherson, Leonard, to Rathcon, Inc. Magnetic toy. 220,625, 5-4-71, Cl. D25—1.
Matsushita Electric Industrial Co., Ltd.: See—
Saito, Hiroshi, Tatsumi, and Kon'i. 220,651.
Shimizu, Yuji. 220,629.
Shimizu, Yuji. 220,630.
Iida, Yoshiaki. 220,631.
Kurihara, Ippli. 220,632.
Miyanaga, Setsuo. 220,653.
Mercadante, Ottorino, to Corning Glass Works. Plate or the like. 220,638, 5-4-71, Cl. D44—15.
Mills, Iain C., to The Dunlop Co. Ltd. Tire. 220,670, 5-4-71, Cl. D90—20.

Miyanaga, Setsuo, to Matsushita Electric Industrial Co., Ltd. Combined radio receiver and clock. 220,653, 5-4-71, Cl. D56—4.
Monsanto Co.: See—
Hills, David G. 220,610.
Hills, David G. 220,611.
Moran, John J., and R. C. Querry, to Hycel, Inc. Measured-volume dispenser for chemical reagents or the like. 220,621, 5-4-71, Cl. D16—1.
Morehead, Kenneth R. Combined lamp and picture holder. 220,642, 5-4-71, Cl. D48—20.
Nagengast, Philip J.: See—
Smith, Wilbur, and Nagengast. 220,660.
Nagy, Joseph. Vehicle signal light. 220,643, 5-4-71, Cl. D48—32.
Nakada, Hikaru: See—
Hirayama, Kazuhiro, and Nakada. 220,652.
Ninomiya, Koichiro: See—
Koshida, Yasuhiro, Kondou, Ninomiya, and Sato. 220,667.
Omron Tatetsu Electronics Co.: See—
Yamamoto, Mititaka. 220,659.
Owens, William T., Jr.: See—
Christoffersen, William K., Keely, Owens, and Quanrud. 220,658.
Parker Pen Co., The: See—
Green, Homer T. 220,663.
Parsell, Kendrick T.: See—
Boldt, Melvin H., and Parsell. 220,654.
Passander, Robert J., to Intercon Research, Inc. Modular building block unit. 220,622, 5-4-71, Cl. D18—2.
Paulson, Erland G.: See—
Rome, Herbert, and Paulson. 220,633.
Pavease, John R. Removable lift fork for loader and back hoe buckets and the like. 220,617, 5-4-71, Cl. D14—3.
Payne, Donald L.: See—
Provi, Richard M., and Payne. 220,646.
Provi, Richard M., and Payne. 220,647.
Provi, Richard M., and Payne. 220,648.
Plysu Containers Ltd.: See—
Dickins, Michael C. 220,609.
Poznanovich, Robert N. Keyboard-operated electronic musical instrument. 220,650, 5-4-71, Cl. D56—1.
Provi, Richard M., and D. L. Payne. Inclinator. 220,646, 5-4-71, Cl. D52—6.
Provi, Richard M., and D. L. Payne. Inclinator. 220,647, 5-4-71, Cl. D52—6.
Provi, Richard M., and D. L. Payne. Inclinator. 220,648, 5-4-71, Cl. D52—6.
Purdy, Frederick E., to AMF Inc. Sidewall bicycle. 220,668, 5-4-71, Cl. D90—3.
Querry, Robert C.: See—
Moran, John J., and Querry. 220,621.
Randazzo, Vincent. Fluidic logic trainer computer. 220,626, 5-4-71, Cl. D26—5.
Rathcon, Inc.: See—
Macpherson, Leonard. 220,625.
Relchert, Leonard K. Cutting block. 220,614, 5-4-71, Cl. D11—1.
Robinson, Leva D. Money box. 220,644, 5-4-71, Cl. D52—4.
Rome, Herbert, and E. G. Paulson, to Elden Industries, Inc. Interlockable file rack unit. 220,633, 5-4-71, Cl. D38—3.
Ronchetti, Ignazio. A bottle capper. 220,672, 5-4-71, Cl. D94—3.
Rosenthal, Paul. Metallurgical opaque projector. 220,656, 5-4-71, Cl. D61—1.
Rowley, Ernest W. Snowmobile trailer. 220,619, 5-4-71, Cl. D14—24.
Saito, Hiroshi, M. Tatsumi, and Y. Kon'i, to Matsushita Electric Industrial Co., Ltd. Electronic organ cabinet or similar article. 220,651, 5-4-71, Cl. D56—2.
Sears, Roebuck and Co.: See—
Wagoner, Ralph W. 220,664.
Schwartz, Gerald D., to United Bus Sales, Inc. Motor home. 220,616, 5-4-71, Cl. D14—3.
Schultze, Louis, J. Necktie or the like. 220,608, 5-4-71, Cl. D2—351.
Scovill Manufacturing Co.: See—
Beck, Theodore A. 220,613.
Shimizu, Yuji, to Matsushita Electric Industrial Co., Ltd. Speaker enclosure. 220,629, 5-4-71, Cl. D26—14.
Shimizu, Yuji, to Matsushita Electric Industrial Co., Ltd. Combined amplifier housing and base for a record player or similar article. 220,630, 5-4-71, Cl. D26—14.
Siegler, Kenneth E. Beer can. 220,612, 5-4-71, Cl. D9—216.
Singer Co., The: See—
Stoltz, Elmer J., and Wohltmann. 220,627.
Smith, Sidney Z.: See—
Swett, James B., and Smith. 220,637.
Smith, Wilbur C., and P. J. Nagengast, to Worthington Corp. Pump and filter unit. 220,660, 5-4-71, Cl. D65—1.
Stoltz, Elmer J., and W. J. Wohltmann, Jr., to The Singer Co. Data terminal console. 220,627, 5-4-71, Cl. D26—5.
Stubbmann, Albert, to Kohner Bros., Inc. Combined automobile dashboard and steering wheel toy. 220,636, 5-4-71, Cl. D34—15.
Swett, James B., and S. Z. Smith, to Dart Industries, Inc. Drainer tray or the like. 220,637, 5-4-71, Cl. D44—1.
Taiman, Edward C., to Cannon Mills Co. Towel or similar article. 220,671, 5-4-71, Cl. D92—26.
Tatsumi, Masakazu: See—
Saito, Hiroshi, Tatsumi, and Kon'i. 220,651.
Thompson, William L. Portable outhouse. 220,615, 5-4-71, Cl. D13—1.
Todd, Burt K., to Kerr-Hays Co. Ladle or similar article. 220,639, 5-4-71, Cl. D44—29.
United Bus Sales, Inc.: See—
Schwartz, Gerald D. 220,616.
Urban, Claude. Bath faucet. 220,624, 5-4-71, Cl. D23—23.
Wagoner, Ralph W., to Sears, Roebuck and Co. Carpet display stand. 220,664, 5-4-71, Cl. D80—9.
Washington Scientific Industries, Inc.: See—
Christoffersen, William K., Keely, and Owens. 220,757.
Wohltmann, William J., Jr.: See—
Stoltz, Elmer J., and Wohltmann. 220,627.
Worthington Corp.: See—
Smith, Wilbur C., and Nagengast. 220,660.
Wrobel, Charles V., W. D. Dian, and G. Golden, to Excel Inc. Bicycle seat or similar article. 220,669, 5-4-71, Cl. D90—16.
Yamamoto, Mititaka, to Omron Tatetsu Electronics Co. Calculating machine. 220,659, 5-4-71, Cl. D64—11.
Zenith Radio Corp.: See—
Boldt, Melvin B., and Parsell. 220,654.

CLASSIFICATION OF PATENTS

ISSUED MAY 4, 1971

NOTE.—First number, class; second number, subclass; third number, patent number

2- 3 : 3.577.561	29-603 : 3.577.634	57- 80 : 3.577.722	75- 59 : 3.577.234	156-361 : 3.577.299	235- 92 : 3.576.974
8 : 3.577.562	615 : 3.577.635	129 : 3.577.723	81- 3.36: 3.577.812	441.5 : 3.577.300	150.1 : 3.576.975
10 : 3.577.563	30-162 : 3.577.637	157 : 3.577.724	.5 : 3.577.811	461 : 3.577.301	.27: 3.576.976
12 : 3.577.564	164.95: 3.577.636	58- 38 : 3.577.725	9.51: 3.577.813	504 : 3.577.302	151.11: 3.576.977
12 : 3.577.565	277 : 3.577.638	60- 13 : 3.577.726	3.577.814	122 : 3.577.303	3.576.979
4- 7 : 3.577.566	32- 19 : 3.577.639	29 : 3.577.727	52.4 : 3.577.815	555 : 3.577.304	152 : 3.576.980
77 : 3.577.567	32 : 3.577.640	30 : 3.577.728	63.1 : 3.577.816	161- 4 : 3.577.305	153 : 3.576.982
79 : 3.577.568	33- 27 : 3.577.641	39.63: 3.577.729	121 : 3.577.817	90 : 3.577.306	158 : 3.576.983
172.17: 3.577.570	172 : 3.577.642	.71: 3.577.730	180 : 3.577.818	175 : 3.577.307	176 : 3.576.984
3.577.571	178 : 3.577.643	.82: 3.577.731	82- 37 : 3.577.819	176 : 3.577.308	181 : 3.576.985
187 : 3.577.572	203.11: 3.577.644	52 : 3.577.732	83-171 : 3.577.820	189 : 3.577.314	183 : 3.577.157
5- 82 : 3.577.573	209 : 3.577.645	105 : 3.577.733	238 : 3.577.821	196 : 3.577.309	189 : 3.576.986
267 : 3.577.574	226 : 3.577.646	202 : 3.577.734	659 : 3.577.822	227 : 3.577.310	240- 2.25: 3.576.987
7-14.1 : 3.577.575	34- 9 : 3.577.647	207 : 3.577.735	84-174 : 3.577.823	254 : 3.577.311	3 : 3.576.988
8-115.5 : 3.577.576	3.577.648	226 : 3.577.736	478 : 3.577.824	162-148 : 3.577.312	4.2 : 3.576.989
3.577.577	110 : 3.577.649	61- 46.5 : 3.577.737	85- 76 : 3.577.825	164 : 3.577.313	10 : 3.576.990
130 : 3.577.578	151 : 3.577.650	63 : 3.577.738	89- 26 : 3.577.826	210 : 3.577.315	246- 40 : 3.576.991
137 : 3.577.579	155 : 3.577.651	62- 45 : 3.577.739	145 : 3.577.827	352 : 3.577.316	250- 41.9 : 3.576.992
142 : 3.577.580	156 : 3.577.652	72 : 3.577.740	90- 15 : 3.577.828	174- 92 : 3.576.993	43.5 : 3.576.993
9- 2 : 3.577.581	231 : 3.577.653	84 : 3.577.741	21 : 3.577.829	107 : 3.576.994	51.5 : 3.576.994
10- 73 : 3.577.582	35- 9 : 3.577.654	199 : 3.577.742	92- 66 : 3.577.830	113 : 3.576.995	59 : 3.577.160
12-146 : 3.577.583	3.577.655	212 : 3.577.743	98 : 3.577.831	117 : 3.576.996	65 : 3.577.204
15- 22 : 3.577.584	3.577.656	256 : 3.577.744	168 : 3.577.832	128 : 3.577.151	71 : 3.577.161
169 : 3.577.585	12 : 3.577.657	345 : 3.577.745	93- 58.3 : 3.577.833	196 : 3.576.998	83.1 : 3.576.999
244 : 3.577.586	18 : 3.577.658	29 : 3.577.746	94- 3 : 3.577.834	210 : 3.576.999	3.576.996
16- 87.2 : 3.577.587	19 : 3.576.936	50 : 3.577.747	96- 1.6 : 3.577.835	176- 4 : 3.577.317	90 : 3.576.997
135 : 3.577.588	32 : 3.577.661	157 : 3.577.750	3 : 3.577.236	178- 5.4 : 3.576.943	106 : 3.576.998
17- 25 : 3.577.589	36- 11.5 : 3.577.662	68-143 : 3.577.751	28 : 3.577.237	6.8 : 3.576.944	203 : 3.576.999
18- 1 : 3.577.590	67 : 3.577.663	210 : 3.577.752	36.2 : 3.577.238	3.576.945	218 : 3.577.205
12 : 3.577.591	37-192 : 3.577.664	71- 9 : 3.577.753	52 : 3.577.239	7.1 : 3.577.200	213 : 3.577.162
3.577.592	38- 2 : 3.577.665	67 : 3.577.754	99- 7 : 3.577.240	.2 : 3.577.153	219 : 3.577.163
16.5 : 3.577.593	40-152 : 3.577.666	45 : 3.577.755	107 : 3.577.241	23 : 3.576.952	230 : 3.577.000
17 : 3.577.594	42- 69 : 3.577.667	51 : 3.577.756	111 : 3.577.242	69.5 : 3.576.947	252- 8.1 : 3.577.342
18 : 3.577.595	43- 43.11: 3.577.668	193 : 3.577.757	106- 2 : 3.577.243	179- 2 : 3.577.201	51.5 : 3.577.343
19 : 3.577.596	44- 76 : 3.577.669	215 : 3.577.758	39 : 3.577.244	15 : 3.577.202	62 : 3.577.344
3.577.597	46- 1 : 3.577.670	237 : 3.577.759	59 : 3.577.245	55: 3.576.948	.1 : 3.577.345
20 : 3.577.598	16 : 3.577.671	239 : 3.577.760	62 : 3.577.246	18 : 3.576.949	63.5 : 3.577.346
30 : 3.577.599	19 : 3.577.672	254 : 3.577.761	111 : 3.577.247	3.576.950	73 : 3.577.361
3.577.597	24 : 3.577.673	256 : 3.577.762	269 : 3.577.248	3.576.951	99 : 3.577.347
19- 65 : 3.577.598	41 : 3.577.674	73- 12 : 3.577.763	278 : 3.577.249	3.576.952	153 : 3.577.348
145.5 : 3.577.599	123 : 3.577.675	3.577.764	284 : 3.577.250	27 : 3.577.155	170 : 3.577.349
293 : 3.577.600	206 : 3.577.676	3.577.765	299 : 3.577.251	100.2 : 3.576.953	301.4 : 3.577.350
23- 50 : 3.577.601	47- 58 : 3.577.677	37.9 : 3.577.766	300 : 3.577.252	3.576.954	3.577.351
56 : 3.577.602	49-127 : 3.577.678	38 : 3.577.767	308 : 3.577.253	.41: 3.576.955	408 : 3.577.352
151 : 3.577.603	358 : 3.577.679	40.5 : 3.577.768	3.577.254	3.576.956	465 : 3.577.353
168 : 3.577.604	51- 8 : 3.577.680	.7 : 3.577.769	3.577.255	191- 60.3 : 3.576.957	468 : 3.577.354
204 : 3.577.605	94 : 3.577.681	49.8 : 3.577.770	3.577.256	200- 1 : 3.576.958	512 : 3.577.355
213 : 3.577.606	135 : 3.577.682	65 : 3.577.771	3.577.257	144 : 3.576.960	260- 2 : 3.577.356
254 : 3.577.607	165 : 3.577.683	67.7 : 3.577.772	3.577.258	151 : 3.576.961	.2 : 3.577.357
259.1 : 3.577.608	166 : 3.577.684	.8 : 3.577.773	3.577.259	167 : 3.576.962	.5 : 3.577.358
285 : 3.577.609	168 : 3.577.685	95 : 3.577.774	3.577.260	202-160 : 3.577.320	3.577.359
325 : 3.577.610	170 : 3.577.686	119 : 3.577.775	3.577.261	241 : 3.577.321	3.577.362
24- 16 : 3.577.611	171 : 3.577.687	133 : 3.577.776	3.577.262	203- 11 : 3.577.322	3.577.363
70 : 3.577.612	241 : 3.577.688	139 : 3.577.777	3.577.263	204- 7 : 3.577.323	3.577.364
73 : 3.577.613	281 : 3.577.689	141 : 3.577.778	3.577.264	20 : 3.577.324	3.577.365
81 : 3.577.614	284 : 3.577.690	146 : 3.577.779	3.577.265	24 : 3.577.325	4 : 3.577.366
114.5 : 3.577.615	52- 72 : 3.577.691	152 : 3.577.780	3.577.266	43 : 3.577.326	3.577.367
117 : 3.577.616	224 : 3.577.692	155 : 3.577.781	3.577.267	50 : 3.577.327	3.577.368
204 : 3.577.617	236 : 3.577.693	355 : 3.577.782	100 : 3.577.268	54 : 3.577.328	3.577.369
221 : 3.577.618	483 : 3.577.694	398 : 3.577.783	101 : 3.577.269	60 : 3.577.329	3.577.370
228 : 3.577.619	745 : 3.577.695	515 : 3.577.784	122 : 3.577.270	112 : 3.577.330	22 : 3.577.371
25- 2 : 3.577.620	12 : 3.577.696	515 : 3.577.785	136 : 3.577.271	180 : 3.577.331	23 : 3.577.372
41 : 3.577.621	27 : 3.577.697	74- 5.6 : 3.577.786	201 : 3.577.272	195 : 3.577.332	3.577.373
118 : 3.577.622	30 : 3.577.700	11 : 3.577.787	213 : 3.577.273	212 : 3.577.333	3.577.374
28- 1.4 : 3.577.623	37 : 3.577.701	89.14: 3.577.788	234 : 3.577.274	223 : 3.577.334	29.6 : 3.577.375
72.12: 3.577.624	131 : 3.577.702	.15: 3.577.789	134- 1 : 3.577.275	228 : 3.577.335	3.577.376
29- 25.15: 3.577.625	198 : 3.577.703	96 : 3.577.790	23 : 3.577.276	302 : 3.577.336	.7 : 3.577.377
54 : 3.577.626	380 : 3.577.704	100 : 3.577.791	138 : 3.577.277	208- 8 : 3.577.337	33.6 : 3.577.378
96 : 3.577.627	386 : 3.577.705	232 : 3.577.792	136- 6 : 3.577.278	11 : 3.577.338	37 : 3.577.379
148.4 : 3.577.628	30 : 3.577.706	459 : 3.577.793	148- 6.24: 3.577.279	210- 23 : 3.577.339	40 : 3.577.380
155 : 3.577.629	68 : 3.577.707	466 : 3.577.794	27: 3.577.280	42 : 3.577.340	45.7 : 3.577.381
182 : 3.577.630	105 : 3.577.708	479 : 3.577.795	20.3 : 3.577.281	53 : 3.577.341	.8 : 3.577.382
3.577.631	228 : 3.577.709	503 : 3.577.796	23 : 3.577.282	219- 92 : 3.576.963	85: 3.577.383
200 : 3.577.632	316 : 3.577.710	522 : 3.577.797	175 : 3.577.283	121 : 3.576.964	3.577.384
201 : 3.577.633	399 : 3.577.711	567 : 3.577.798	3.577.284	131 : 3.576.965	9 : 3.577.385
211 : 3.577.634	501 : 3.577.712	571 : 3.577.799	189 : 3.577.285	137 : 3.576.966	47 : 3.577.386
407 : 3.577.635	56- 11.9 : 3.577.713	574 : 3.577.800	149- 19 : 3.577.286	221 : 3.576.967	3.577.387
445 : 3.577.636	17.2 : 3.577.714	665 : 3.577.801	156- 62.2 : 3.577.287	279 : 3.576.970	75 : 3.577.388
464 : 3.577.637	208 : 3.577.715	688 : 3.577.802	64 : 3.577.288	284 : 3.576.968	3.577.389
471.1 : 3.577.638	259 : 3.577.716	688 : 3.577.803	73 : 3.577.289	235- 61.11: 3.576.971	77.5 : 3.577.390
472.9 : 3.577.639	295 : 3.577.717	688 : 3.577.804	156 : 3.577.290	.12: 3.576.972	78 : 3.577.391
517 : 3.577.640	57- 18 : 3.577.718	688 : 3.577.805	173 : 3.577.291	92 : 3.576.973	3.577.392
572 : 3.577.641	34 : 3.577.719	868 : 3.577.806	177 : 3.577.292		
585 : 3.577.642	58.89: 3.577.720	71 : 3.577.293	239 : 3.577.293		
588 : 3.577.643	77.33: 3.577.721	134 : 3.577.294	249 : 3.577.294		
			265 : 3.577.295		

260-78.4 : 3,577,394	260-453 : 3,577,451	264-321 : 3,577,507	317-235 : 3,577,042	331-94.5 : 3,577,096	340-347 : 3,577,142
80.78 : 3,577,393	456 : 3,577,452	331 : 3,577,508	331 : 3,577,043	331 : 3,577,097	340 : 3,577,143
82.1 : 3,577,395	471 : 3,577,453	336 : 3,577,509	336 : 3,577,044	336 : 3,577,098	343-12 : 3,577,144
85.1 : 3,577,396	475 : 3,577,454	342 : 3,577,510	342 : 3,577,045	96 : 3,577,099	14 : 3,577,145
88.1 : 3,577,397	478 : 3,577,455	290-38 : 3,577,001	347 : 3,577,046	117 : 3,577,100	17.2 : 3,577,146
92.8 : 3,577,398	513 : 3,577,456	46 : 3,577,002	357 : 3,577,047	154 : 3,577,101	108 : 3,577,147
97 : 3,577,399	517 : 3,577,457	307-66 : 3,577,003	237 : 3,577,048	333-7 : 3,577,102	112 : 3,577,148
160 : 3,577,400	545 : 3,577,458	141 : 3,577,004	318-52 : 3,577,049	17 : 3,577,103	770 : 3,577,149
162 : 3,577,401	551 : 3,577,459	205 : 3,577,005	138 : 3,577,050	72 : 3,577,104	771 : 3,577,150
193 : 3,577,402	566 : 3,577,460	218 : 3,577,006	146 : 3,577,051	73 : 3,577,105	778 : 3,577,151
211 : 3,577,403	570.5 : 3,577,461	228 : 3,577,007	212 : 3,577,052	84 : 3,577,106	821 : 3,577,152
233.3 : 3,577,404	586 : 3,577,462	233 : 3,577,008	230 : 3,577,053	95 : 3,577,107	346-46 : 3,577,153
239.1 : 3,577,405	601 : 3,577,463	240 : 3,577,009	254 : 3,577,054	98 : 3,577,108	139 : 3,577,154
255 : 3,577,406	614 : 3,577,464	252 : 3,577,010	302 : 3,577,055	335-185 : 3,577,109	408-17 : 3,577,155
264 : 3,577,407	627 : 3,577,465	271 : 3,577,011	314 : 3,577,056	248 : 3,577,110	61 : 3,577,156
287 : 3,577,408	648 : 3,577,466	273 : 3,577,012	328 : 3,577,057	175 : 3,577,111	162 : 3,577,157
293.4 : 3,577,409	650 : 3,577,467	279 : 3,577,013	432 : 3,577,058	337-89 : 3,577,112	186 : 3,577,158
297 : 3,577,410	656 : 3,577,468	284 : 3,577,014	691 : 3,577,059	338-4 : 3,577,113	424-9 : 3,577,159
304 : 3,577,411	660 : 3,577,469	284 : 3,577,015	321-10 : 3,577,060	339-17 : 3,577,114	21 : 3,577,160
307 : 3,577,412	666 : 3,577,470	293 : 3,577,016	322-27 : 3,577,061	36 : 3,577,115	32 : 3,577,161
314.5 : 3,577,413	668 : 3,577,471	296 : 3,577,017	323-8 : 3,577,062	94 : 3,577,116	46 : 3,577,162
325 : 3,577,414	683.3 : 3,577,472	297 : 3,577,018	16 : 3,577,063	125 : 3,577,117	47 : 3,577,163
326.1 : 3,577,415	689 : 3,577,473	299 : 3,577,019	18 : 3,577,064	248 : 3,577,118	54 : 3,577,164
328 : 3,577,416	75 : 3,577,474	304 : 3,577,020	20 : 3,577,065	258 : 3,577,119	55 : 3,577,165
333 : 3,577,417	862 : 3,577,475	310-8.2 : 3,577,021	22 : 3,577,066	340-17 : 3,577,120	70 : 3,577,166
334.3 : 3,577,418	869 : 3,577,476	10 : 3,577,022	51 : 3,577,067	59 : 3,577,121	78 : 3,577,167
343.3 : 3,577,419	942 : 3,577,477	13 : 3,577,023	58.5 : 3,577,068	114 : 3,577,122	88 : 3,577,168
346.2 : 3,577,420	977 : 3,577,478	54 : 3,577,024	60 : 3,577,069	146.1 : 3,577,123	89 : 3,577,169
348 : 3,577,421	101 : 3,577,479	239 : 3,577,025	73 : 3,577,070	153 : 3,577,124	92 : 3,577,170
378 : 3,577,422	109 : 3,577,480	313-63 : 3,577,026	83 : 3,577,071	163 : 3,577,125	114 : 3,577,171
397.5 : 3,577,423	123 : 3,577,481	101 : 3,577,027	98 : 3,577,072	164 : 3,577,126	118 : 3,577,172
404.5 : 3,577,424	127 : 3,577,482	109 : 3,577,028	115 : 3,577,073	166 : 3,577,127	122 : 3,577,173
410.6 : 3,577,425	137 : 3,577,483	223 : 3,577,029	140 : 3,577,074	167 : 3,577,128	149 : 3,577,174
429 : 3,577,426	143 : 3,577,484	315-9 : 3,577,030	154 : 3,577,075	172.5 : 3,577,129	155 : 3,577,175
439 : 3,577,427	153 : 3,577,485	13 : 3,577,031	183 : 3,577,076	357 : 3,577,130	183 : 3,577,176
448 : 3,577,428	156 : 3,577,486	36 : 3,577,032	329 : 3,577,077	357 : 3,577,131	198 : 3,577,177
	159 : 3,577,487	39 : 3,577,033	416 : 3,577,078	357 : 3,577,132	200 : 3,577,178
	168 : 3,577,488	71 : 3,577,034	471 : 3,577,079	357 : 3,577,133	201 : 3,577,179
	182 : 3,577,489	88 : 3,577,035	481 : 3,577,080	357 : 3,577,134	214 : 3,577,180
	210 : 3,577,490	111 : 3,577,036	491 : 3,577,081	357 : 3,577,135	231 : 3,577,181
	213 : 3,577,491	170 : 3,577,037	501 : 3,577,082	357 : 3,577,136	244 : 3,577,182
	235 : 3,577,492	317-2 : 3,577,038	511 : 3,577,083	357 : 3,577,137	249 : 3,577,183
	244 : 3,577,493	22 : 3,577,039	521 : 3,577,084	357 : 3,577,138	251 : 3,577,184
	255 : 3,577,494	31 : 3,577,040	531 : 3,577,085	357 : 3,577,139	269 : 3,577,185
	256 : 3,577,495	98 : 3,577,041	541 : 3,577,086	357 : 3,577,140	272 : 3,577,186
	272 : 3,577,496	101 : 3,577,042	551 : 3,577,087	357 : 3,577,141	273 : 3,577,187
		107 : 3,577,043	561 : 3,577,088		279 : 3,577,188
		124 : 3,577,044	571 : 3,577,089		286 : 3,577,189
		127 : 3,577,045	581 : 3,577,090		288 : 3,577,190
		148.5 : 3,577,046	591 : 3,577,091		317 : 3,577,191
		357 : 3,577,047	601 : 3,577,092		324 : 3,577,192
			611 : 3,577,093		325 : 3,577,193
			621 : 3,577,094		326 : 3,577,194
			631 : 3,577,095		

CLASSIFICATION OF DESIGNS

D 2-351 : 220,608	D14-6 : 220,618	D26-14 : 220,629	D45-1 : 220,640	D56-2 : 220,651	D72-1 : 220,662
D 9-43 : 220,609	24 : 220,619	220,630	D48-4 : 220,641	4 : 220,652	D74-17 : 220,663
48 : 220,610	D15-11 : 220,620	220,631	20 : 220,642	220,653	D80-9 : 220,664
117 : 220,611	D16-2 : 220,621	220,632	32 : 220,643	220,654	D86-10 : 220,665
216 : 220,612	D18-2 : 220,622	D33-3 : 220,633	D52-4 : 220,644	220,655	D88-5 : 220,666
258 : 220,613	D22-27 : 220,623	D34-5 : 220,634	6 : 220,645	220,656	D90-8 : 220,667
D11-1 : 220,614	D23-23 : 220,624	220,635	220,646	220,657	D92-26 : 220,668
D13-1 : 220,615	D25-1 : 220,625	15 : 220,636	220,647	220,658	D94-3 : 220,669
7 : 220,616	D26-5 : 220,626	D44-1 : 220,637	220,648	220,659	
D14-3 : 220,617	220,627	15 : 220,638	220,649	220,660	
	14 : 220,628	29 : 220,639	220,650	220,661	

DEFENSIVE PUBLICATIONS APPLICATIONS

(Notice of Dec. 16, 1969, 869 O.G. 687)

73-160 : T886,007	106-27 : T886,005	174-25 : T886,009	264-51 : T886,003	307-229 : T886,006	312-23 : T886,008
74-732 : T886,001	156-311 : T886,002	260-525 : T886,004			

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

1 : 3,577,017	6 : 3,577,193	6 : 3,577,793	12 : 3,577,748	18 : 3,577,287	25 : 3,577,143
3,577,077	3,577,196	3,577,815	13 : 3,577,495	3,577,333	3,577,150
3,577,331	3,577,210	8 : 3,576,948	3,577,540	3,577,385	3,577,157
3,577,697	3,577,221	3,576,971	3,577,676	3,577,412	3,577,169
3,577,737	3,577,223	3,577,071	15 : 3,577,647	3,577,467	3,577,172
4 : 3,576,986	3,577,233	3,577,391	17 : 3,576,946	3,577,490	3,577,187
3,577,010	3,577,243	3,577,506	3,576,950	3,577,531	3,577,200
3,577,160	3,577,246	3,577,669	3,576,961	3,577,680	3,577,204
3,577,195	3,577,247	3,577,674	3,576,967	3,577,776	3,577,205
3,577,306	3,577,250	9 : 3,576,940	3,576,970	3,577,806	3,577,237
3,577,710	3,577,294	3,576,974	3,577,004	19 : 3,577,006	3,577,271
3,577,744	3,577,297	3,576,985	3,577,020	3,577,142	3,577,313
3,577,771	3,577,317	3,576,987	3,577,027	3,577,407	3,577,315
6 : 3,576,944	3,577,323	3,577,003	3,577,080	3,577,426	3,577,374
3,576,947	3,577,324	3,577,094	3,577,103	20 : 3,577,375	3,577,437
3,576,969	3,577,332	3,577,115	3,577,116	3,577,392	3,577,503
3,576,973	3,577,338	3,577,267	3,577,136	3,577,431	3,577,508
3,576,978	3,577,353	3,577,268	3,577,164	21 : 3,576,963	3,577,574
3,576,980	3,577,356	3,577,269	3,577,249	3,577,163	3,577,578
3,576,983	3,577,357	3,577,292	3,577,282	3,577,584	3,577,593
3,576,984	3,577,413	3,577,327	3,577,283	22 : 3,577,414	3,577,596
3,576,990	3,577,427	3,577,328	3,577,293	3,577,649	3,577,610
3,576,991	3,577,442	3,577,402	3,577,364	23 : 3,577,828	3,577,613
3,577,007	3,577,444	3,577,420	3,577,367	24 : 3,577,013	3,577,629
3,577,011	3,577,466	3,577,507	3,577,370	3,577,028	3,577,651
3,577,023	3,577,475	3,577,514	3,577,422	3,577,030	3,577,730
3,577,031	3,577,533	3,577,519	3,577,452	3,577,062	3,577,769
3,577,042	3,577,545	3,577,523	3,577,482	3,577,070	3,577,779
3,577,052	3,577,563	3,577,589	3,577,484	3,577,084	26 : 3,576,959
3,577,054	3,577,571	3,577,656	3,577,492	3,577,091	3,576,976
3,577,057	3,577,582	3,577,668	3,577,527	3,577,135	3,576,999
3,577,066	3,577,606	3,577,696	3,577,535	3,577,171	3,577,049
3,577,067	3,577,622	10 : 3,577,266	3,577,552	3,577,218	3,577,068
3,577,095	3,577,634	3,577,304	3,577,567	3,577,232	3,577,121
3,577,096	3,577,639	3,577,443	3,577,579	3,577,289	3,577,134
3,577,097	3,577,640	3,577,564	3,577,581	3,577,379	3,577,215
3,577,098	3,577,643	3,577,565	3,577,612	3,577,487	3,577,262
3,577,122	3,577,646	3,577,614	3,577,645	3,577,590	3,577,263
3,577,130	3,577,670	11 : 3,577,014	3,577,665	3,577,605	3,577,264
3,577,132	3,577,678	3,577,105	3,577,684	3,577,708	3,577,265
3,577,133	3,577,679	3,577,322	3,577,687	3,577,775	3,577,309
3,577,139	3,577,693	12 : 3,576,968	3,577,698	25 : 3,576,996	3,577,355
3,577,146	3,577,705	3,577,009	3,577,704	3,576,997	3,577,380
3,577,155	3,577,711	3,577,038	3,577,714	3,576,998	3,577,406
3,577,165	3,577,728	3,577,298	3,577,726	3,577,000	3,577,455
3,577,170	3,577,734	3,577,562	3,577,765	3,577,029	3,577,486
3,577,178	3,577,763	3,577,638	18 : 3,577,001	3,577,072	3,577,494
3,577,190	3,577,770	3,577,650	3,577,060	3,577,088	3,577,548
3,577,191	3,577,777	3,577,690	3,577,083	3,577,102	3,577,550
3,577,192	3,577,792	3,577,731	3,577,168	3,577,104	3,577,555

26 : 3.577.560	34 : 3.577.284	36 : 3.577.189	39 : 3.577.075	42 : 3.577.354	48 : 3.577.137
3.577.569	3.577.311	3.577.194	3.577.110	3.577.359	3.577.148
3.577.577	3.577.319	3.577.199	3.577.158	3.577.360	3.577.179
3.577.588	3.577.330	3.577.202	3.577.175	3.577.373	3.577.184
3.577.592	3.577.342	3.577.203	3.577.198	3.577.377	3.577.242
3.577.618	3.577.347	3.577.230	3.577.211	3.577.381	3.577.260
3.577.621	3.577.372	3.577.235	3.577.226	3.577.408	3.577.336
3.577.624	3.577.388	3.577.236	3.577.227	3.577.409	3.577.365
3.577.625	3.577.393	3.577.238	3.577.231	3.577.410	3.577.399
3.577.626	3.577.441	3.577.244	3.577.245	3.577.418	3.577.438
3.577.683	3.577.447	3.577.257	3.577.256	3.577.423	3.577.450
3.577.709	3.577.458	3.577.272	3.577.261	3.577.430	3.577.554
3.577.727	3.577.460	3.577.277	3.577.274	3.577.434	3.577.555
3.577.768	3.577.463	3.577.278	3.577.290	3.577.435	3.577.556
3.577.778	3.577.465	3.577.285	3.577.295	3.577.445	3.577.566
3.577.791	3.577.493	3.577.286	3.577.299	3.577.448	3.577.631
3.577.803	3.577.512	3.577.326	3.577.314	3.577.457	3.577.657
3.577.821	3.577.515	3.577.334	3.577.358	3.577.462	3.577.661
27 : 3.576.941	3.577.516	3.577.345	3.577.389	3.577.468	3.577.664
3.577.173	3.577.518	3.577.350	3.577.396	3.577.469	3.577.747
3.577.280	3.577.529	3.577.366	3.577.397	3.577.470	3.577.780
3.577.312	3.577.530	3.577.371	3.577.398	3.577.471	3.577.781
3.577.346	3.577.536	3.577.417	3.577.400	3.577.472	3.577.783
3.577.383	3.577.537	3.577.439	3.577.401	3.577.474	49 : 3.577.572
3.577.386	3.577.539	3.577.476	3.577.454	3.577.479	50 : 3.577.044
3.577.394	3.577.541	3.577.478	3.577.459	3.577.496	3.577.826
3.577.522	3.577.557	3.577.480	3.577.501	3.577.532	51 : 3.577.053
3.577.827	3.577.576	3.577.511	3.577.597	3.577.546	3.577.099
29 : 3.576.937	3.577.586	3.577.524	3.577.620	3.577.553	3.577.125
3.577.251	3.577.591	3.577.525	3.577.627	3.577.587	3.577.197
3.577.361	3.577.594	3.577.528	3.577.660	3.577.595	3.577.208
3.577.382	3.577.601	3.577.558	3.577.681	3.577.636	3.577.209
3.577.395	3.577.663	3.577.573	3.577.686	3.577.659	3.577.415
3.577.538	3.577.677	3.577.583	3.577.689	3.577.667	3.577.432
3.577.542	3.577.682	3.577.604	3.577.766	3.577.694	3.577.440
3.577.759	3.577.701	3.577.630	3.577.825	3.577.713	3.577.449
3.577.811	3.577.702	3.577.642	3.577.831	3.577.715	3.577.580
3.577.817	3.577.785	3.577.655	40 : 3.577.724	3.577.716	3.577.615
3.577.822	3.577.786	3.577.658	41 : 3.577.303	3.577.718	3.577.637
31 : 3.577.241	3.577.799	3.577.672	42 : 3.576.938	3.577.745	53 : 3.577.021
3.577.739	3.577.801	3.577.675	3.576.953	3.577.746	3.577.206
33 : 3.577.040	3.577.819	3.577.729	3.576.960	3.577.753	3.577.368
3.577.177	3.577.823	3.577.736	3.577.043	3.577.758	3.577.369
34 : 3.576.966	3.577.835	3.577.741	3.577.059	3.577.764	3.577.641
3.576.975	3.576.945	3.577.751	3.577.112	3.577.784	3.577.774
3.576.995	3.576.982	3.577.752	3.577.117	3.577.794	3.577.808
3.577.008	3.576.989	3.577.802	3.577.118	3.577.814	54 : 3.577.349
3.577.034	3.577.019	3.577.816	3.577.119	3.577.119	55 : 3.576.988
3.577.058	3.577.035	3.577.820	3.577.120	3.577.120	3.577.016
3.577.063	3.577.036	3.577.824	3.577.174	3.577.025	3.577.026
3.577.065	3.577.037	3.577.213	3.577.176	3.577.141	3.577.032
3.577.087	3.577.045	3.577.300	3.577.201	3.577.600	3.577.050
3.577.100	3.577.046	3.577.325	3.577.222	3.577.721	3.577.109
3.577.113	3.577.047	3.577.335	3.577.224	3.577.723	3.577.296
3.577.114	3.577.051	3.577.429	3.577.248	3.577.807	3.577.428
3.577.123	3.577.064	3.577.499	3.577.258	47 : 3.577.225	3.577.436
3.577.131	3.577.076	3.577.654	3.577.275	3.577.339	3.577.461
3.577.166	3.577.086	3.577.788	3.577.279	3.577.344	3.577.653
3.577.167	3.577.089	3.577.688	3.577.281	3.577.485	3.577.742
3.577.181	3.577.093	3.576.954	3.577.288	3.577.648	3.577.743
3.577.214	3.577.126	3.576.964	3.577.302	3.576.972	3.577.756
3.577.219	3.577.128	3.576.979	3.577.305	3.576.977	3.577.800
3.577.228	3.577.145	3.576.992	3.577.329	3.577.005	3.577.833
3.577.239	3.577.147	3.577.012	3.577.337	3.577.015	56 : 3.577.073
3.577.253	3.577.154	3.577.022	3.577.340	3.577.090	3.577.818
3.577.254	3.577.185	3.577.039	3.577.341	3.577.092	58 : 3.577.789
3.577.255	3.577.186	3.577.074	3.577.351	3.577.127	

Design Patents

6 : 220.615	6 : 220.655	17 : 220.647	22 : 220.623	27 : 220.658	36 : 220.671
220.616	220.673	220.648	25 : 220.613	34 : 220.617	39 : 220.634
220.618	220.610	220.650	220.614	220.636	220.642
220.625	220.611	220.65	220.637	220.660	42 : 220.639
220.627	220.628	220.664	26 : 220.643	220.665	48 : 220.621
220.633	220.620	220.668	220.645	36 : 220.626	53 : 220.612
220.635	220.608	220.669	220.666	220.638	55 : 220.640
220.641	220.646	18 : 220.622	27 : 220.657	220.656	220.663
220.644					

DEFENSIVE PUBLICATIONS APPLICATIONS (Notice of Dec. 16, 1969, 869 O.G. 687)

10 : T886.004	24 : T886.006	36 : T886.002	36 : T886.005	36 : T886.008	70 : T886.007
T886.009	26 : T886.001	T886.003			

U. S. GOVERNMENT PRINTING OFFICE: O—1971

OFFICIAL GAZETTE of the UNITED STATES PATENT OFFICE

May 11, 1971

Volume 886

Number 2

CONTENTS

Issue of May 11, 1971	211
Patent Notices	
Dedication	212
Disclaimers	212
Disclaimer and Dedication	212
Certificates of Correction for the Week of May 11, 1971	212
Condition of Patent Applications	213
Defensive Publications	214
Patents Granted	
General and Mechanical	216
Chemical	348
Design Patents Granted	410
Index of Patentees	PI 1
Indices of Applicants of Defensive Publications and Designs	PI 27
Classification of	
Patents	PI 29
Designs and Defensive Publications	PI 30
Geographical Index of Residence of Inventors	
Patents	PI 31
Designs and Applicants of Defensive Publications	PI 32

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENTS SECTION), issued weekly, subscription \$89.00 per annum, foreign mailing \$22.25 additional; single copies \$2.00 each.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$17.00 per annum, foreign mailing \$4.25 additional; single copies 40 cents each.

CIRCULARS OF GENERAL INFORMATION concerning PATENTS or TRADEMARKS, price 15 cents each.

PRINTED COPIES OF PATENTS are furnished by the Patent Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS and DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents, Washington, D.C., 20231.

Printing authorized by Section 11(a)8 of Title 35, U.S. Code P.O.

PATENT OFFICE NOTICES

Dedication	Certificates of Correction for the Week of May 11, 1971			
3,480,617.— <i>Kelly Farhat</i> , Akron, Ohio. N-(p-SUBSTITUTED AMINOPHENYL) CYCLIC ALKYLENEIMINES AND THEIR PREPARATION. Patent dated Nov. 23, 1969. Dedication filed Dec. 21, 1970, by the assignee, <i>The Firestone Tire & Rubber Company</i> .	Re. 27,019	3,541,745	3,552,516	3,556,383
Hereby dedicates to the people of the United States the entire term of said patent.	3,335,010	3,542,107	3,552,694	3,556,387
	3,384,489	3,542,495	3,552,718	3,556,422
	3,395,017	3,543,651	3,553,023	3,556,459
	3,403,637	3,543,769	3,553,097	3,557,026
	3,446,792	3,543,860	3,553,155	3,557,037
	3,459,539	3,545,287	3,553,178	3,557,129
	3,492,255	3,545,333	3,553,329	3,557,193
	3,492,797	3,545,370	3,553,466	3,557,289
	3,498,372	3,545,403	3,553,516	3,557,299
3,525,317.— <i>Earl B. Muir</i> , Rolling Hills Estates, Calif. VE-HICLE ENGINE BRAKING SYSTEM. Patent dated Aug. 25, 1970. Disclaimer filed Jan. 27, 1971, by the assignee, <i>White Motor Corporation</i> .	3,509,124	3,545,571	3,553,603	3,557,337
Hereby enters this disclaimer to claims 1, 2, 6, 16 and 18 of said patent.	3,514,965	3,545,729	3,553,835	3,557,722
	3,519,603	3,545,787	3,554,135	3,557,785
	3,521,144	3,545,925	3,554,270	3,557,818
	3,522,264	3,547,688	3,554,287	3,557,999
	3,522,340	3,547,696	3,554,388	3,558,055
	3,522,599	3,548,487	3,554,417	3,558,139
3,533,155.— <i>Alexander Coucoulas</i> , Bridgewater Township, Somerset County, N.J. BONDING WITH A COMPLIANT MEDIUM. Patent dated Oct. 13, 1970. Disclaimer filed Feb. 1, 1971, by the assignee, <i>Western Electric Company, Incorporated</i> .	3,523,864	3,548,911	3,554,460	3,558,299
Hereby enters this disclaimer to claims 9, 17 and 20 of said patent.	3,527,840	3,549,027	3,554,522	3,558,444
	3,528,317	3,549,294	3,554,673	3,558,510
	3,529,282	3,549,542	3,554,898	3,558,635
	3,529,298	3,549,640	3,554,908	3,558,779
	3,529,921	3,549,786	3,554,944	3,558,898
	3,530,132	3,549,877	3,555,121	3,558,969
	3,530,241	3,550,667	3,555,203	3,559,122
	3,535,083	3,550,736	3,555,215	3,559,489
	3,536,136	3,550,879	3,555,661	3,559,583
3,085,916.— <i>William E. Zimmie</i> , Bay Village, Ohio, and <i>Fredrick W. Blocher, Jr.</i> , Stamford, Conn. METHOD OF REMOVING AND PREVENTING ACCUMULATION IN COOLING SYSTEMS. Patent dated Apr. 16, 1963. Disclaimer and dedication filed Dec. 7, 1970, by the assignee, <i>W. E. Zimmie, Inc.</i>	3,536,219	3,551,477	3,555,882	3,559,585
Hereby disclaims and dedicates to the Public the terminal portion of the patent subsequent to Mar. 5, 1980.	3,538,973	3,551,709	3,556,019	3,560,320
	3,539,555	3,551,730	3,556,047	3,560,410
	3,540,028	3,551,740	3,556,066	3,560,417
	3,541,157	3,551,781	3,556,123	3,560,520
	3,541,663	3,552,484	3,556,302	3,560,550

212

PATENT EXAMINING CORPS

R. A. WAHL, Assistant Commissioner
F. H. BRONAUGH, Deputy Assistant Commissioner

CONDITION OF PATENT APPLICATIONS AS OF APRIL 20, 1971

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—M. STERMAN, Director.....	12-01-69
Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	
GENERAL ORGANIC CHEMISTRY, GROUP 120—I. MARCUS, Director.....	8-22-69
Heterocyclic; Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—L. J. BERCOVITZ, Director.....	2-04-70
Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Natural Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g.: Coating; Molding; Ink; Adhesive and Abrading Compositions; Molding, Shaping, and Treating Processes.	
COATING AND LAMINATING, BLEACHING, DYEING AND PHOTOGRAPHY, GROUP 160—A. P. KENT, Director.....	1-26-70
Coating; Processes and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; Bleaching; Dyeing and Photography.	
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—W. B. KNIGHT, Director.....	10-03-69
Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS AND RELATED ELEMENTS, GROUP 210—N. ANSHER, Director.....	8-17-70
Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Miscellaneous.	
SECURITY, GROUP 220—R. L. CAMPBELL, Director.....	12-01-69
Ordnance, Firearms and Ammunition; Radar; Underwater Signalling; Directional Radio; Torpedoes, Seismic Exploring, Radio-Active Batteries; Nuclear Reactors, Powder Metallurgy, Rocket Fuels; Radio-Active Material.	
INFORMATION TRANSMISSION, STORAGE AND RETRIEVAL, GROUP 230—J. F. COUCH, Director.....	3-02-70
Communications; Multiplexing Techniques; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—W. L. CARLSON, Director.....	3-03-70
Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	
PHYSICS, GROUP 280—R. L. EVANS, Director.....	1-05-70
Photography; Sound and Lighting; Indicators and Optics; Measuring and Testing; Geometrical Instruments.	
DESIGNS, GROUP 290—R. L. CAMPBELL, Director.....	6-03-70
Industrial Arts; Household, Personal and Fine Arts.	
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—A. BERLIN, Director.....	1-23-70
Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet and Web Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Railways and Railway Equipment; Brakes; Rigid Flexible and Special Receptacles and Packages.	
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—D. J. STOCKING, Director.....	12-10-69
Manufacturing Processes; Assembling; Combined Machines; Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion—Bonding, Metal Founding; Metallurgical Apparatus; Plastics Working Apparatus; Plastic Block and Earthenware Apparatus; Machine Tools for Shaping or Dividing; Work and Tool Holders Woodworking; Tools; Cutlery; Jacks.	
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—A. RUEGG, Director.....	1-02-70
Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Butchering; Earth Working and Excavating; Fishing, etc.; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Stationery; Information Dissemination.	
HEAT, POWER AND FLUID ENGINEERING, GROUP 340—C. F. GAREAU, Director.....	5-07-70
Power Plants; Combustion Engines; Fluid Motors; Pumps; Turbines; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Vaporizing; Temperature and Humidity Regulation; Machine Elements; Power Transmission; Fluid Handling; Lubrication; Joint Packing.	
CONSTRUCTIONS, SUPPORTS, TEXTILES, CLEANING, GROUP 350—T. J. HICKEY, Director.....	1-06-70
Joints; Fasteners; Rod, Pipe and Electrical Connectors; Miscellaneous Hardware; Locks; Building Structures; Closure Operators; Bridges; Closures; Earth Engineering; Drilling; Mining; Furniture; Receptacles; Supports; Cabinet Structures; Centrifugal Separations; Cleaning; Coating; Pressing; Agitating; Foods; Textiles; Apparel and Shoes; Sewing Machines; Winding and Reeling.	

Expiration of patents: The patents within the range of numbers indicated below expire during May 1971, except those which may have expired earlier due to shortened terms under the provisions of Public Law 660, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 263. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents..... Numbers 2,677,129 to 2,679,644, inclusive
Plant Patents..... Numbers 1,274 to 1,281, inclusive

213

DEFENSIVE PUBLICATIONS

MAY 11, 1971

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O.G. 687. The abstracts of Defensive Publication applications are identified by distinctly numbered series and are arranged chronologically. The heading of each abstract indicates the number of pages of specification, including claims and sheets of drawings contained in the application as originally filed. The files of these applications are available to the public for inspection and reproduction may be purchased for 30 cents a sheet.

Defensive Publication applications have not been examined as to the merits of alleged invention. The Patent Office makes no assertion as to the novelty of the disclosed subject matter.

T886,010

PROCESS FOR DISTRIBUTING AQUEOUS DISPERSIONS THROUGH A PNEUMACEL BATT


Robert L. Craven and John F. Hesselberth, Wilmington, Del., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed Feb. 3, 1970, Ser. No. 8,372

Int. Cl. B44d 1/44

U.S. Cl. 117—65.2

1 Sheet Drawing, 8 Pages Specification



A process for uniformly distributing an aqueous dispersion of a thermoplastic polymeric binder composition through the thickness of a pneumacel-fiber batt. The preferred pneumacel fibers are low density, closed-cell foam fibers of polyethylene terephthalate containing 6–40 grams of an impermeant inflatant, such as perfluorocyclobutane, per 100 grams of polymer. The preferred dispersion composition comprises 40 parts ethylene/vinyl acetate copolymer (24–26% vinyl acetate), 40 parts water, and 20 parts diammonium phosphate. The process comprises (1) applying the aqueous dispersion to the pneumacel-fiber batt until the weight of the batt is increased by between 25 and 250 percent, (2) compressing the wetted batt, preferably by passing it through the nip of two rolls, until the ratio of the height of the compressed batt to the calculated height of the uncompressed batt is between about 0.4 and 0.6, and (3) releasing the compressive forces from the batt.

T886,011

SURFACE STATIC REDUCTION

Leon Edward Wolinski, Buffalo, N.Y., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed Feb. 3, 1970, Ser. No. 8,418

Int. Cl. B44d 5/04

U.S. Cl. 117—46

No Drawing, 8 Pages Specification

A process for reducing the surface static level of a thermoplastic packaging material by applying a coating of ionizable liquids having a specific conductance of at least 1×10^{-4} mhos. Optionally, the surface of the thermoplastic packaging material can be pretreated prior to coating to increase the surface polarity thereby increasing the degree of ionization of the coating liquid when applied. Low surface static improves the adhesion of printing inks, minimizes dust attraction, and reduces the tendency for sheets of the packaging material to adhere to one another.

Useful thermoplastic packaging materials include polyvinyl chloride; polystyrene; polyolefins, such as polyethylene and polypropylene; as well as polyesters, such as

polyethylene terephthalate. Useful ionizable coating liquids include water; alcohols having 1 to 4 carbon atoms, such as methanol, ethanol, propanol and butanol; glycols, such as propylene glycol; fluorocarbons which are liquid at room temperature; and solutions of ionizable salts. Preferred ionizable coating liquids are (a) water or (b) an aqueous solution of zinc chloride and an alkyl aryl polyethylene glycol ether, each present on the surface of the thermoplastic packaging material in an amount of about 0.11 to 0.034 mg./ft.² based on the dry weight of each of the components.

A typical process sequence comprises:

(A) Subjecting a thermoplastic packaging material to a surface pretreatment such as

- (1) an electrical discharge in air, oxygen, nitrogen or chlorine of at least about 3,000 to 8,000 volts and 3 to 10 kilocycles, a watt density greater than about 30 watts per square inch with an electrode gap of about from 40 to 50 mils, or
- (2) a reducing flame of a gaseous mixture of hydrocarbon fuel, oxygen and nitrogen having a fuel equivalency ratio of about from 1.05:1.25 and an oxygen ratio of about 2.78 for a period of 0.01 to 0.05 second; and

(B) Coating the pretreated surface by means including spraying, nip or doctor roll coating, or, preferably, by direct condensation, i.e., bringing the film surface into contact with the vapor of the ionizable coating liquid.

T886,012
PALLETS

William Bruce Ian Small, Welwyn Garden City, England, assignor to Imperial Chemical Industries Limited, London, England


Filed Apr. 27, 1970, Ser. No. 32,155

Claims priority, application Great Britain, May 5, 1969, 22,709/69

Int. Cl. B65d 19/18

U.S. Cl. 108—51

1 Sheet Drawing, 5 Pages Specification



Pallets in which the load-bearing surfaces consist of interwoven bands of thermoplastic material mounted within a frame are disclosed. The interwoven bands are of a high tensile material such as tapes of polypropylene or high density polyethylene having the direction of the orientation of the molecules of the material along the axis thereof. Another suitable material is a strip consisting of fibers of polyethylene terephthalate embedded in a matrix

MAY 11, 1971

U. S. PATENT OFFICE

215

of polyethylene. The frame supporting this interwoven band of plastic is of a light weight material such as, for example, tubular metal or another thermoplastic material. If a thermoplastic material is selected, foamed polypropylene is preferred for its strength and light weight. The woven load-bearing surface may be fitted within such a plastic frame by heat-sealing the strip to the frame or, with either metal or thermoplastic material, the ends of the load-bearing surface may be looped around the frame member and the material sealed to itself to secure each band to the frame.

The underside of the frame may be conveniently fitted with supports to receive the forks of a fork lift truck. Pallets thus produced are strong enough to withstand both the loads which they support and the rough handling to which they are subjected.

T886,013

TWO-PHASE GLASS SYSTEMS AND RESISTOR COMPOSITIONS CONTAINING THE SAME

Kenneth E. Schubert, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Continuation of application Ser. No. 679,525, Oct. 3, 1967. This application July 8, 1970, Ser. No. 56,156

Int. Cl. H01b 1/02

U.S. Cl. 252—514

No Drawing, 11 Pages Specification

The particular two-phase glass system is composed of 50–70% by weight of a high melting glass and 30–50% of a low melting glass. Resistor compositions composed of finely divided noble metals and the two-phase glass system are produced, and when fired will yield smooth resistors having low contact resistance and low noise value.

T886,014

GELATIN WITH IMPROVED CHEMICAL SETTING PROPERTIES

Thomas Karl Dykstra, % Eastman Kodak Co., Kodak Park Division, Rochester, N.Y. 14650

Filed Aug. 3, 1970, Ser. No. 60,710

Int. Cl. G03c 1/02

U.S. Cl. 96—114.8

No Drawing, 19 Pages Specification

Gelatin, modified by reacting it with diketene and thereafter with a suitable aldehyde, like formaldehyde, possesses desirable properties including ultra-rapid chemical setting. Particularly effective modified gelatin comprises less than all, and preferably up to about 50% of its primary amine functions converted to its acetoacetamido function and photographic emulsions and layers comprising said modified gelatin are useful in photography and in rapid coating of multilayer elements.

Silver halide emulsions and elements containing said modified gelatin can be chemically sensitized, e.g. with noble metal sensitizers alone or in combination with sulfur or selenium sensitizers. They can contain spectral sensitizers, incorporated color-forming couplers, incorporated developing agents, antifoggants, hardeners, plasticizers, coating aids, vinyl polymers, and other suitable photographic addenda such as described in U.S. Pat. 3,297,446 of Dunn issued Jan. 10, 1967 (columns 4 to 9).

T886,015

FLEXIBLE TRANSPARENT CONTACT CHARGING ELEMENT FOR ELECTROPHOTOGRAPHY


Richard W. Stahr and William W. Rees, both of 1669 Lake Ave., Rochester, N.Y. 14602

Filed Nov. 2, 1970, Ser. No. 85,943

Int. Cl. G03g 13/00

U.S. Cl. 250—49.5

1 Sheet Drawing, 13 Pages Specification




A substantially transparent, flexible element for contact charging of photoconductors is provided with a rough surface by incorporating inert granules or bead-like particles in a binder resin coated on a flexible, transparent film. Over the binder layer or imbedded into it is a semi-conducting material such as cuprous iodide. The rough surface has a Sheffield Smoothness Value of from 20 to 200 and an electrical resistance of less than 10^8 ohms/square. This rough surface controls the air gap spacing during the charging cycle when the charging film and the photoconductive element are oriented in a face-to-face mode to place a charge on the photoconductor. Such space has optimum dimensions of from 1 to 40 microns to permit gaseous ionization to occur. The element can be used for charging photoconductive elements having rough or smooth surfaces.

PATENTS

GRANTED MAY 11, 1971


GENERAL AND MECHANICAL

3,577,836
ARMORED GARMENT
 Raymond M. Tamura, 3253 N. Nimitz Hwy., Honolulu, Hawaii 96819
 Continuation-in-part of application Ser. No. 545,446, Apr. 26, 1966, now abandoned. This application Nov. 12, 1969, Ser. No. 875,770
 Int. Cl. F41h 1/02
 U.S. Cl. 2—2.5



A laminated armor construction formed of a plurality of layers adapted to protect against missiles by a combination of projectile deflection, diffusion of forces, dissipation of energy into heat, modification of force vectors and adsorption of kinetic energy. A first layer of elliptical plastic plates causes deflection with the energy dissipation and adsorption being achieved by underlying layers of foam plastic, and a metal honeycomb filled with epoxy.

3,577,837
SUBDERMAL TENDON IMPLANT
 Karl F. Bader, Jr., Chicago, Ill. (2016 Bradley Road, Rockford, Ill. 61107)
 Filed Apr. 30, 1968, Ser. No. 725,423
 Int. Cl. A61H 1/24
 U.S. Cl. 3—1




A subdermal tendon implant for use in repairing and reconstructing tendons which is compatible with the human cellular structure and includes the process of making the implant. The subdermal implant is resistant to degeneration and substantially eliminates adhesions allowing full range of motion after healing and includes in its structure a flexible sheeting of chemically inert material sculptured to a desired size and shape and means for anchoring the implant to prevent it from moving axially along the tendon.

3,577,838
AIRPORT GANGWAY
 Nicolaas Gradus Jan Willem Van Marle, Dordrecht, Netherlands, assignor to Avirolanda Maatschappij voor Vliegtuigbouw N.V., Papendrecht, Netherlands
 Filed Oct. 7, 1968, Ser. No. 767,922
 Claims priority, application Netherlands, Oct. 6, 1967, 67/13,617
 Int. Cl. B65g 1/00
 U.S. Cl. 14—71


A telescoping airport gangway incorporating means for ad-

justing its vertical position, for lengthening and shortening it,




and for pivoting it about its rear end.

3,577,839
BRUSH AND BRUSH MATERIAL
 Vernon K. Charvat, Bay Village, and Robert E. Jarvi, Judson, Ohio, assignors to The Sherwin-Williams Company
 Filed June 27, 1968, Ser. No. 740,848
 Int. Cl. A46b 13/00
 U.S. Cl. 15—179



Brush material and brushes utilizing the same, particularly power driven rotary brushes, in which the brush bristles have a central core and a thin outer plastic coating, with granular abrasive preferably secured to such core beneath such coating.

3,577,840
SELF-HOLDING HINGE
 Harry P. Buberniak, 12372 Devoe, Southgate, Mich.
 Filed Mar. 24, 1969, Ser. No. 809,710
 Int. Cl. E05d 11/08
 U.S. Cl. 16—142




A self-holding hinge of the type wherein a resilient detent-like structure is incorporated into a hinge to resiliently hold or retain the hinge in its closed position.

MAY 11, 1971

GENERAL AND MECHANICAL


217

3,577,841
EXTRUDERS WITH ROTATING PLATE
 Claude Ledoux, Massy, and Bernard Neuville, Versailles, France, assignors to Produits Chimiques Pechiney-Saint-Gobain, Neuilly-sur-Seine, France
 Filed Sept. 11, 1968, Ser. No. 759,087
 Claims priority, application France, Sept. 14, 1967, 120,988
 Int. Cl. B29f 3/012, 1/022
 U.S. Cl. 18—12C




A rotating plate extruder in which at least one of the faces of the plates is formed with grooves extending tangentially to a circle concentric with the axis of the plate to enhance use with lubricated plastic materials.

3,577,842
APPARATUS FOR COMPRESSION MOLDING A POWDER WITHIN A CONTAINER
 Miyoji Nakai, Neyagawa-shi; Akira Nakajima, Hirakata-shi; Makoto Watanabe, Osaka, and Toshio Sanukiya, Izumisano-shi, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan
 Filed July 2, 1969, Ser. No. 838,486
 Claims priority, application Japan, July 4, 1968, 43/47682
 Int. Cl. B29c 3/00; B30b 11/10
 U.S. Cl. 18—20




An apparatus for compression molding a powder within a container, which is operative in such a manner that empty containers successively loaded on an intermittently driven rotary member at a loading station of the apparatus with its open end facing downwardly are carried one after another to a molding station where a compression-moldable powder previously charged in a cavity die from a hopper is displaced into and compression molded within said container into a prescribed shape by a relative movement of said container which is held immovably, and a core die and a sleeve surrounding said core die, and upon completion of the compression molding said container is further carried by said rotary member to an unloading station with the shaped mold of said powder formed therein where it is removed from the rotary member.

3,577,843
APPARATUS FOR CONTROLLING BRISTLE DEFLECTION
 Louis F. Kutik, 8720 S. W. 23rd Place, Fort Lauderdale, Fla., and Erich W. Gronemeyer, 2100 S. Ocean Lane, Fort Lauderdale, Fla.
 Filed Apr. 9, 1969, Ser. No. 822,819
 Int. Cl. B29c 11/00
 U.S. Cl. 18—42



A method and apparatus for molding bristled products in a manner such that the degree of deflection or nondeflection of bristles if positively controlled. The apparatus includes a mold having a backing part and a chase part forming a cavity and a pin having one or more flutes in a bore in the chase part communicating with the cavity. The cross-sectional shape of the flute and the rates at which heat is withdrawn from different sides of the bristle are specifically selected and controlled to produce deflection or inhibit deflection of the bristle or bristles as desired. Certain dimensions at the base of the bristles are also controlled to prevent distortion of bristles.

3,577,844
APPARATUS FOR PREPARING FIBROUS MATERIAL FOR A CARDING MACHINE
 Jack D. Towery, Lubbock, Tex., assignor to Continental/Moss-Gordin, Inc., Prattville, Ala.
 Continuation of application Ser. No. 719,500, Apr. 8, 1968, now abandoned. This application Oct. 21, 1969, Ser. No. 868,240
 Int. Cl. D01g 15/40
 U.S. Cl. 19—105



An apparatus for preparing cotton after it has been removed from a compressed bale and without the use of the picker, the picker lap, the lap handling, the creeling and other operations sometimes employed prior to delivery to the carding machine. In the present method the fiber is supplied in very small, open tufts carried by air into a rectangular flue which passes over or into a smaller round or polygonal shaped flue across a series of carding machines, where the

fibers are loosely collected and fed through a bellows action mechanism which alternatively compresses and releases, removing a substantial portion of the air and allowing the fibers to fall by gravity into any spaces formerly occupied by air producing a uniform batt.

3,577,845

APPARATUS FOR GUIDING A FLEECE


Hansulrich Eichenberger, and Peter Schwengeler, Winterthur, Switzerland, assignors to Rieter Machine Works, Ltd., Winterthur, Switzerland

Filed Aug. 23, 1968, Ser. No. 754,800

Claims priority, application Germany, Sept. 6, 1967, M75446
Int. Cl. D01g 19/18

U.S. Cl. 19—231

13 Claims



A web guide plate is positioned above the web tray so as to direct the web onto the tray after passing from the detachment rollers. The guide plate is spaced in the plane of the nip between the detachment rollers and includes an inclined portion which serves to direct the web onto the tray. The amplitude of the web undulations is reduced so as to avoid any breaks in the fibers at the crests of the peaks. The annular member in another cycle of operation to cut the slice. Movement of the support member is also controlled by circuitry interconnected with that for controlling movement of the pivotal members.

3,577,846

THREE-PIECE TACK BUTTON


Badger Perrin, Roxbury, Conn., assignor to United-Carr Incorporated, Boston, Mass.

Filed June 30, 1969, Ser. No. 837,578

Int. Cl. A44b 1/42

U.S. Cl. 24—95

1 Claim



This is a three-piece tack button having a unitary combination vise and anvil. The combination vise and anvil is double walled and has a continuous, uninterrupted exterior wall.

3,577,847

COMPONENT PART INSERTER FOR CIRCUIT BOARD

Ronald A. Scranton, 1025 E. Thompson Ave., Hoopston, Ill.

Filed Mar. 17, 1969, Ser. No. 807,541


Int. Cl. H05k 3/30

U.S. Cl. 29—203

15 Claims

In a machine for attaching electrical components to a circuit board, wherein each of the electrical components has a body and a pair of generally aligned oppositely extending leads, and wherein the circuit board has preformed holes arranged in pairs to receive the leads of the respective electrical components, a reciprocable ram member cooperates with suitable lead-cutting dies and lead-forming cam means in cutting the leads of the respective electrical components to predetermined lengths, forming the leads so as to permit the

leads to be driven through a selected pair of holes in the circuit board, and driving the leads therethrough.



3,577,848

METHOD OF EXTRACTING O-RINGS FROM RECESSED GROOVES


Robert C. Mengle, 21330 Center Ridge Road, Cleveland, Ohio

Filed Dec. 9, 1968, Ser. No. 782,087

Int. Cl. B23p 19/02

U.S. Cl. 29—427

6 Claims



A tool for extracting O-rings from grooves which are recessed from the mouth of an opening. It includes an elongated rod with a hook on the forward end and a pivotally attached tongue adjacent the hook, the tongue being adapted to pivot from an open position with the tongue extending transverse to the rod to a closed position which substantially closes the opening in the hook. In open position, the tongue is adapted to slide into the recessed groove adjacent the O-ring; the pivoting to a closed position serves to pry the O-ring out of the groove and grasp the ring between the tongue and the hook.

A method of extracting O-rings from recessed grooves by use of a tool including a rod having a hook and a cooperating pivotable tongue at its forward end. The tongue is opened and the forward end of the rod is inserted into an opening. Within the opening is an O-ring positioned in a groove, the groove being recessed from the mouth of the opening. The tongue is pushed laterally into the groove beside the O-ring and the tool is then retracted toward the mouth of the recess. The retraction serves to close the tongue, pry the O-ring out of the groove and clamp the O-ring between the hook and the tongue.

3,577,849

METHOD AND MATERIALS FOR WELDING

Dan T. Roberts, Corsicana, Tex., assignor to Oil City Iron Works, Corsicana, Tex.

Division of Ser. No. 599,159, Dec. 5, 1966, Pat. No. 3,479,230,


filed Apr. 14, 1969, Ser. No. 844,683

1969, Ser. No. 844,683

Int. Cl. B23k 31/02, 35/36

U.S. Cl. 29—495

12 Claims



This application discloses a method and materials including a welding rod and flux for welding nodular cast iron.

3,577,850

METHOD OF FORMING SEALS


Rano J. Harris, Sr., Baton Rouge, La., assignor to Precision Sampling Corporation

Filed Sept. 26, 1968, Ser. No. 762,791

Int. Cl. B21d 39/00; B23p 11/00

U.S. Cl. 29—510

8 Claims



A method, and the apparatus formed by encapsulating and stress forming a thermoplastic material upon a male member, e.g., the needle or plunger of a syringe, or both, to provide a durable and effective leakproof seal when inserted within enclosing walls defining an opening of restricted diameter. A portion of the said male member is capped with an oversized thermoplastic material, the cap is then reduced in size to correspond to the diameter of the member with which it is to be mated in forming the seal, and then heated up to or just below the softening temperature of the thermoplastic material, generally up to about 425° F., and preferably to about 300° F. The heat stressed member, which is characterized as having very thin layers or films of the stress formed thermoplastic covering the external surface of the member, can then be inserted into snug fit within the mating bore, e.g., the barrel of a syringe, and the tight fit will endure because of the elastic memory of the material by virtue of which it tends to expand to its former size and shape thereby pressing against the enclosing sidewalls forming the bore.

3,577,851

METHOD OF MAKING DYNAMOELECTRIC MACHINES

John Stanley Detheridge, Birmingham, and John William March, Hanworth, England, assignors to Joseph Lucas (Industries) Limited, Birmingham, England

Filed Mar. 11, 1969, Ser. No. 806,130


Claims priority, application Great Britain, Mar. 18, 1968,

Aug. 9, 1968, 12895/68; 38067/68

Int. Cl. H02k 15/00

U.S. Cl. 29—596

3 Claims



A method of forming a stator assembly for a dynamoelectric machine includes the steps of forming a continuous metal strip with stator slots along one peripheral edge and gear teeth along the other peripheral edge and then using a gear wheel engaging the gear teeth to drive the strip onto a former to coil the strip helically. In a modification, in order to produce a yoke or a stator assembly for a dynamoelectric machine a continuous metal strip is formed with gear teeth along one peripheral edge thereof and a gear wheel is engaged with the gear teeth and drives the strip onto a former to coil the strip helically to produce the yoke or stator assembly. The gear teeth in the strip can be the stator slots where a stator assembly is to be produced, or can be specially provided gear teeth where a yoke assembly is to be produced.

3,577,852

CUTTING HEAD FOR MOTOR-DRIVEN SHAVERS


Bodo Futterer, Luzern, Switzerland, assignor to The Gillette Company, Boston, Mass.

Filed Aug. 1, 1968, Ser. No. 749,364

Int. Cl. B26b 19/02

U.S. Cl. 30—43.92

2 Claims



The undersurface, or at least the undersurface adjacent the openings in the movable cutting head of a dry shaver are coated with an antiadhesive material such as polytetrafluorethylene.

3,577,853

DENTAL IMPLANT AND METHOD OF MOUNTING THE SAME


Harold D. Roberts, 2717 N. E. Knott St., Portland, Oreg.

Filed July 22, 1969, Ser. No. 843,579

Int. Cl. A61c 13/00

U.S. Cl. 32—10

4 Claims



An implant designed to be mounted specifically in the ramus or retromolar portion of the mandible or jawbone, having an elongated main body carry a post extending up from the forward end of the main body and passing up through the epithelium; the main body of the implant being inserted into a partial incision made in the bone in a direction extending longitudinally and rearwardly, and driven in through and rearwardly beyond the incision and in beneath the top surface of the ramus; the main body of the implant extending rearwardly spaced a safe distance above the alveolar nerve and positioned between the signal lingual and buccal cortical plates of the ramus.

3,577,854

METHOD OF REPRESENTING THE DIAL SETTINGS OF AN ELECTRONIC YARN SMOOTHER

Ernst Felix, Uster, Switzerland, assignor to Zellweger Ltd., Uster, Switzerland

Filed Dec. 24, 1968, Ser. No. 786,679


Int. Cl. G06g 1/00

U.S. Cl. 33—1

7 Claims

The dial settings of a yarn smoother, required to remove a preselected field of flaws, are determined by plotting a field of yarn flaws in a coordinate system; plotting a family of limit curves, each representing the locus of the flaws extracted by the yarn smoother when set at a preselected fixed reference length dial setting; placing the family of limit curves over the field of flaws; and shifting the limit curves, while maintaining coincidence of the ordinate axes of the field of flaws and the limit curves, to align one of said limit curves, as nearly as possible, with the flaws to be extracted. After a single limit curve is properly aligned with the flaws to be extracted, the

proper dial settings are (1) the reference length corresponding to the aligned limit curve and (2) the value of the or-



dinate of the field of flaws graph intersected by the origin of the limit curve graph.


3,577,855

JAW HINGE AXIS LOCATOR

Lloyd Baum, 11460 Aster St., Loma Linda, Calif.
Filed Mar. 17, 1969, Ser. No. 807,824
Int. Cl. A61b 5/10

U.S. Cl. 33-174

10 Claims



A jaw hinge axis locator having a stiff wire frame with two curving segments which extend around the sides of a dental patient's face from the handle of a mouthpiece mounted on his lower jaw, and a pair of dead soft wires connected to the outer ends of the curving segments of the frame. The dead soft wires terminate near the ends of the patient's jaw hinge axis, and have flat squares of clear plastic, with grid markings, attached to their outer extremities. Each plastic square has an easily observable center of rotation which pinpoints the patient's jaw hinge axis when he moves his lower jaw.


3,577,856

APPARATUS FOR OFFSET PRINTING

Edward R. Updegraff, 4611 Harvard Road, College Park, Md. 20740
Division of Ser. No. 618,886, Feb. 7, 1967, Pat. No. 3,451,337, filed Feb. 25, 1969, Ser. No. 816,457
Int. Cl. B41b 1/00

U.S. Cl. 33-184.5

12 Claims



An apparatus for preparing straightedge printing plates for use in an offset printing system, including a light table unit having a light surface with a plurality of guide lines formed thereon in fixed relation to three flat stops mounted on and projecting upwardly from the light surface and positioned to engage and accurately orient a sheet of light-blocking paper over the guide lines in the production of flats used to prepare

the printing plates. An assembly surface is provided with three plate guides for positioning a printing plate, and three flat guides are positioned in spaced relation to the plate guides for accurately positioning flats in superimposed relation on a plate which has been positioned by the plate guides. A suitable clamp is provided to releasably retain a flat in superimposed relation on a plate on the assembly surface.

3,577,857

DRIVER TRAINER SIMULATOR HEAD UNIT


Donald H. Schuster, and Russ S. Vaught, Ames, Iowa, assignors to Iowa State University Research Foundation, Ames, Iowa

Filed Oct. 31, 1968, Ser. No. 772,082

Int. Cl. G09b 9/02

U.S. Cl. 35-11

8 Claims



A driver trainer unit having a head unit including a blinder operable between raised and lowered positions, a speaker operative with the blinder and actuated by a computer responsive to the driving actions of the student operating the driver trainer simulator in response to driving situations projected on a screen. A solenoid may be used to move the blinder between raised and lowered positions. A microphone may also be provided for receiving the audible responses from the student when reacting to a simulated crash situation.


3,577,858

FOOTWEAR

Curt E. Kaufman, Waynesville, N.C., assignor to Ro-Search, Incorporated, Waynesville, N.C.
Continuation-in-part of application Ser. No. 794,333, Jan. 27, 1969, which is a division of application Ser. No. 521,247, Jan. 14, 1966. This application July 30, 1969, Ser. No. 846,019
Int. Cl. A43b 00/00; A43d 9/00

U.S. Cl. 12-2.5

3 Claims



Footwear such as shoes, boots, etc. having a welt at its lower margin to which a prepared sole, usually of sheet stock, is fastened having a ribbon of elastomeric material molded and cured in situ along the inner perimeter of the welt so as to provide a stepless transition inside of the shoe from the upper to the sole. Such shoes having soles of soft material, such as microcellular elastomer, and also a stabilizing insert and the ribbon of elastomer is molded to secure the insert in its desired location to provide the stepless transition from the inside of the upper to the sole.

3,577,859

COMBINATION FLATIRON AND INTEGRAL CREASER

William E. Davidson, Ontario, Calif., assignor to General Electric Company

Filed Nov. 20, 1969, Ser. No. 878,323


Int. Cl. A47j 51/00

U.S. Cl. 38-71

10 Claims

A combination electrical flatiron and integral fabric creaser having a soleplate through which steam is discharged

for normal ironing. A surface of the iron body opposite the soleplate forms a second ironing surface in the form of a



fabric creaser with steam supply selectively to the creaser when in use all within the iron envelope.

3,577,860

MAGAZINE FOR FIREARMS

Leopold Jestrabek, Oberndorf (Neckar), Germany, assignor to Heckler & Koch GmbH, Oberndorf (Neckar), Germany
Filed July 8, 1968, Ser. No. 743,158


Claims priority, application Germany, May 4, 1968,

P 17 03 342.0

Int. Cl. F41c 25/02

U.S. Cl. 42-50

8 Claims



A magazine consisting of plastic upper and lower components transversely split in the area of the sidewalls. The upper component comprises the magazine lips and the lower component comprises the magazine bottom. The follower spring is a rolled spring having a wound portion which engages the underside of the follower and the free end of which is secured to the inside of the upper magazine component. The magazine components are provided with relieved teeth for positive engagement at their adjoining ends; the magazine components may be provided with reinforcements at their adjoining ends, which serve simultaneously as stops by means of the magazine bearing against the end of the magazine chamber.

ERRATUM

For Class 47-38 see:
Patent No. 3,578,482

3,577,861

TRANSFER DEVICE FOR CUTTING APPARATUS

David L. Bender, Rochester, and Robert E. Moore, Henrietta, N.Y., assignors to Kayex Corporation, Rochester, N.Y.

Filed Apr. 7, 1969, Ser. No. 822,816


Int. Cl. B24b 7/20

U.S. Cl. 51-73

15 Claims

A device for retrieving a thin slice or wafer of material that has been cut from a billet and for transferring it to a storage receptacle comprises two pivotal members. A first pivotal member retrieves the slice after cutting and moves it along one side of an annular cutting member into a transfer position relative to the inner diameter of the annular member. A

second pivotal member takes the slice at the transfer position and moves it axially and then in an arcuate path to a storage receptacle where it is released. The slice of material is retained on the pivotal members by suction. Suitable circuitry controls the application of the suction in proper timed relation to the movement of the pivotal members. A movable support member for the billet is also pivotally mounted so it can move the billet into a position in which it is spaced from



the annular member on movement of the latter to its home position, thereby preventing damage to its exposed surface by contact with the annular member. In its home position the billet is moved axially to establish the thickness of the slice to be cut next and then radially relative to the annular member in another cycle of operation to cut the slice. Movement of the support member is also controlled by circuitry interconnected with that for controlling movement of the pivotal members.

3,577,862

COMPOSITE PRECOMPRESSED GRATING STRUCTURE

Henry P. Cerutti, Mount Lebanon, Pa., assignor to Blaw-Knox Company, Pittsburgh, Pa.

Filed July 12, 1968, Ser. No. 751,663

Int. Cl. E01c 9/10; E04c 2/42; F16s 3/08

U.S. Cl. 52-223

6 Claims



This invention provides a novel floor system which has outstanding advantages in structures, such as powerhouses, nuclear power plants, chemical plants and other such large structures whereby an adequate floor is provided with a sizeable reduction in deadweight. The deadweight design of these structures exceeds the liveweight capacity designs due to the fact that a minimum number of personnel are involved in the operation of such plants. A grating is provided whereby the weight can be reduced materially and/or the span materially lengthened so that the resulting floor support and columns is also reduced. In addition to the reduction in the weight of members, the number of support members for the new floor design is reduced materially, thereby saving additional weight and cost.

3,577,863

TRENCH DUCT CONNECTING DEVICE WITH VERTICAL ADJUSTMENT MEANS

Frederick W. Hudnall, Vienna, W. Va., assignor to Textron Inc., Providence, R.I.

Filed Aug. 14, 1969, Ser. No. 849,991


Int. Cl. E04f 17/08

U.S. Cl. 52-220


4 Claims

A device for installing trenchduct, the device having a bottom and three upstanding sides, one side securing the device to the trench by being welded thereto, the other two sides being used alternatively for coupling one trench to another

and the bottom being used either to secure the trench to a cellular floor by being welded thereto or alternatively supporting a leveling lug when the trench is used over a concrete floor.



3,577,864
FRAME WITH DEFORMABLE LOCKING MEANS
Louis Sommerfeld, 165 West End Ave., New York, N.Y.
Filed Sept. 29, 1969, Ser. No. 861,781
Int. Cl. E06b 7/08; F24f 13/08
U.S. Cl. 52-473




An assembly which includes a frame and an air-guiding panel such as a louver. The frame has a pair of panel-carrying vertical ribs respectively formed with notches while the panel has opposed edge portions of a cross section matching that of the notches and received therein. Each of the ribs of the frame is provided next to its notch with a deformable locking nib while the edge portion of the panel adjacent to the locking nib is formed with a locking cutout. According to the method of the invention after the panel is situated within the notches of the ribs, the deformable locking nib is bent into the locking cutout to remain therein for providing a positive lock between the panel and the frame, thus preventing the panel from snapping or otherwise being removed out of the frame.

3,577,865
WRAPPING MACHINE METHOD
Gottfried M. Hain, Lehen Post Ramerberg an der. Inn, and Wolfgang B. Leonard, Graben Post Ramerberg an der. Inn, Germany, assignors to Alpma Alpenland-Maschinenbau-gesellschaft Hain & Co. KG., Rott Inn Rosenheimer Strasse, Germany
Filed May 15, 1967, Ser. No. 638,213
Claims priority, application Germany, May 18, 1966, A52524
Int. Cl. B65b 55/14, 51/12, 63/08
U.S. Cl. 53-25


Method of enclosing an article is a heat-shrinkable foil wrapper by subjecting portions of the wrapping material

progressively to heat, beginning with that portion of the material most remote from the closure area, and subjecting



the closure area to heat just prior to closure to cause the removal of air.

3,577,866
PACKAGING APPARATUS AND PACKAGE
John F. Ehrenfried, Akron, and Charles M. Gardner, Manchester, Ohio, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio
Division of Ser. No. 654,858, July 20, 1967, Pat. No. 3,504,476, filed Oct. 13, 1969, Ser. No. 865,795
Int. Cl. B65b 11/40, 53/02
U.S. Cl. 53-184




The material to be packaged, referred to herein as the content of a package, may be one or more boxes, or cans on a tray or trays, or a stack of magazines, etc. A series of these, all of the same size or different sizes are fed successively through the apparatus where each is individually wrapped in heat-shrinkable, heat-sealable film to form an open-ended package with the ends of the film overlapped under the package. The overlapped ends of the film are heated and sealed to one another. The entire package is then heated and the film is shrunk tight on the content, and the edges of the film which extended beyond the content are shrunk in over the ends of the content.

3,577,867
METHOD FOR COOLING HEATED ADSORBENT BEDS
Clem A. Barrere, Jr., Ponca City, Okla., assignor to Continental Oil Company, Ponca City, Okla.
Filed Aug. 19, 1968, Ser. No. 753,487
Int. Cl. B01d 53/04


Method and apparatus for cooling a heated regenerated bed in a gas sorption process. Cooling gas is continually cir-

culated through the heated bed in a closed cooling circuit; by maintaining a positive back pressure on the cooling circuit,



no gas is permitted to leave the cooling circuit during the cooling step.


3,577,868
DEVICE FOR SEPARATING FOAM INTO ITS LIQUID AND GASEOUS PHASES
Hans Muller, Im Allmandli, Erlenbach, Zurich, Switzerland
Filed Nov. 5, 1969, Ser. No. 874,102
Claims priority, application Switzerland, Nov. 6, 1968, 16660/68
Int. Cl. B01d 19/00



A vessel accommodates material to be processed, including foam, and which material is to be protected against contaminants from the exterior of the vessel. A rotatable shaft extends through an opening in the vessel into the latter and carries within the vessel a foam separator which effects foam separation into the liquid and gaseous phases when the shaft is rotated. A drive engages the shaft exteriorly of and spaced from the opening in the vessel for rotating the shaft. Wall means surrounds the shaft intermediate the opening in the vessel and the drive and forms a chamber about the surrounded portion of the shaft. A pair of sliding ring seals are provided on the shaft closing the chamber with respect to the opening in the vessel as well as with respect to the drive. Means is provided for circulating a flowing medium through the chamber to thereby prevent the passage of contaminants from the drive into the chamber and from the latter through the opening into the vessel.

3,577,869
ELECTRIC VACUUM CLEANER
Tomoyuki Hosokawa, Takarazuka-shi; Toshii Tsugeki, Takatsuki-shi, and Shigeyuki Asanari, Suita-shi, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan
Filed Aug. 5, 1968, Ser. No. 750,046
Claims priority, application Japan, Aug. 9, 1967, Aug. 9, 1967, Aug. 18, 1967, 42/69344; 42/69345; 42/71538
Int. Cl. A47l 9/28


U.S. Cl. 55-361



An electric vacuum cleaner in which a thyristor is provided to control the input to an electric motor driving a blower so as to adjust the flow of insucked air. In the cleaner, the thyristor is disposed in the path of airstream through the cleaner casing so that it can be subject to forced cooling, and means responsive to a variation in the pressure or in the air-flow is provided to vary the phase corner the gate circuit of the thyristor for controlling the flow of insucked air.

3,577,870
MOWING MACHINES
Cornelis Van Der Lely, 7 Bruschenrain, Zug, Switzerland
Filed Sept. 14, 1967, Ser. No. 668,308
Claims priority, application Netherlands, Sept. 29, 1966, 6613708
Int. Cl. A01d 75/30

U.S. Cl. 56-6



A mowing machine for attachment laterally of a tractor wherein at the side of the mowing elements, viewed in the direction of travel approximately at the same level as the front side of the mowing elements, the mowing machine is supported from the ground so that, in operation, the mowing machine is pivotally connected with the tractor by means of a pivotal shaft extending approximately at right angles to the direction of travel. The mowing machine is pivotally connected to a lateral portion of the shaft for pivotal movement about an axis extending generally in the direction of travel.

3,577,871

CHAIN CURTAIN


Anthony R. Engler, Houston, Tex., assignor to Douglass Industries, Inc., Houston, Tex.

Filed Dec. 16, 1968, Ser. No. 783,806

Int. Cl. A01d 53/08

U.S. Cl. 56—255

5 Claims



Curtain attached to a mower comprising a plurality of chain elements hanging downwardly from the mower body. Cable means extend horizontally through links near the bottom of the chain elements to provide rigidity.

3,577,872

METHOD AND APPARATUS FOR COATING TEXTILE MATERIAL

Warren W. Drummond, Allison Park, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Filed June 2, 1969, Ser. No. 829,521

Int. Cl. D01h 13/30

U.S. Cl. 57—35

13 Claims



Textile material such as strand, yarn, or cord is simultaneously false twisted and impregnated while in a slack (low-tension) condition by feeding the textile material in slack condition into one end of a rotating cylinder containing the coating and withdrawing it from the other end. The textile material in untwisted form and the coating are held against the interior of the rotating cylinder by centrifugal force and the coating impregnates the textile material while subjected to such force. The impregnated textile material passes through a heated tube to dry the coating on the textile material. A uniformly coated twisted textile material wrapped in low tension on a takeup package is produced.

3,577,873

NOVEL CORE YARNS AND METHODS FOR THEIR MANUFACTURE

Graham Thomas Waters, Pontypool, England, assignor to Imperial Chemical Industries Limited, London, England

Filed Mar. 10, 1969, Ser. No. 805,598

Claims priority, application Great Britain, Mar. 27, 1968,

Aug. 26, 1968, 14764/68; 40616/40617/40618

Int. Cl. D02g 3/38, 3/04, 3/28

U.S. Cl. 57—144

16 Claims



Core yarns having a set false twisted core and reversing helical wrapping and processes for their manufacture involving feeding at least two continuous filamentary components having differing extensibility under a given stress to a false twisting machine.

ing feeding at least two continuous filamentary components having differing extensibility under a given stress to a false twisting machine.

3,577,874

ELECTRIC CLOCKS WITH MAGNETIC DRIVES

August Mutter, Schwenningen (Neckar), Germany, assignor to Muller-Schlenker, Schwenningen (Neckar), Germany

Filed June 21, 1968, Ser. No. 738,977


Claims priority, application Germany, June 27, 1967,

M74541

Int. Cl. G04c 3/00

U.S. Cl. 58—23

13 Claims



An electric clock employs a mechanical oscillator which is driven at its natural frequency and which contains a magnetic drive for driving the clock. The magnetic drive contains a nonmagnetized ferromagnetic pole spider, which on its circumference has disposed a single ring of magnetic poles. The poles of the magnetic drive which interact with the spider poles are asymmetrically positioned with respect to poles on opposite sides of the circumference of the pole spider.

3,577,875

CLOCKWORK MOVEMENT CASED BY A ROTARY STEPPING ELECTRIC MOTOR HAVING TWO MOTIVE PHASES SUCCEEDING ONE ANOTHER IN TIME

Georges Stcherbatcheff, Paris, and Claude Houdet, Besancon, France, assignors to Societe de Recherches en Matiere de Micromoteurs Electriques Socrem, Paris, (Seine), France


Filed Jan. 15, 1969, Ser. No. 791,330

Claims priority, application France, Jan. 17, 1968, 136,305

Int. Cl. G04c 3/04

U.S. Cl. 58—28

7 Claims



The invention broadly relates to clockwork movements controlled by an electric motor. More particularly, the instant invention provides a clockwork movement which avoids

3,577,878

FLAME TUBES FOR GAS TURBINE ENGINES


Kenneth Greenwood, Burnley; Alban Heaton, Gt. Harwood, nr. Blackburn; Alwin Harrison, and Squire Ronald Jackson, Burnley, England, assignors to Joseph Lucas (Industries) Limited, Birmingham, England

Filed Dec. 11, 1968, Ser. No. 783,009

Int. Cl. F02c 9/14

U.S. Cl. 60—39.65

5 Claims



A flame tube for a gas turbine engine includes a plurality of primary combustion air inlets, a plurality of secondary combustion air inlets and a plurality of dilution air inlets and variable flow restricting means associated with at least some of the inlets for varying the ratio of primary combustion air to secondary combustion air to dilution air.

3,577,879

FLOATING BARRIER MEANS

Roger Eugene Ducrocq, Colombes, France, assignor to Pneumatiques, Caoutchouc Manufacture Et Plastiques Kleber-Colombes, Colombes, France

Filed July 10, 1969, Ser. No. 840,724


Claims priority, application France, July 10, 1968, Dec. 31,

1968, 158914; 182534

Int. Cl. E02b 15/04

U.S. Cl. 61—1

6 Claims



This invention relates to barrier elements used, for example, for restraining oil slicks and the like on the surface of the sea. In such a barrier that comprises an inflatable tube and a skirt connected thereto, the invention provides that the skirt consists of two flexible members each of which constitutes an elementary skirt: means are provided to connect together these elementary skirts by their upper portions and the lower portions of the skirts are split vertically, the splits being uniformly spaced apart and the splits in one elementary skirt being offset relatively to those in the other: at least one flexible mechanical reinforcing element is located in the upper portion of the skirt and this flexible reinforcing element may be located in a channel.

3,577,876

WATERTIGHT ALARM WRIST-WATCH

Paolo Spadini, 88, Avenue Leopold-Robert 2300 La Chaux-de-Fonds, Neuchatal, Switzerland

Filed June 12, 1969, Ser. No. 832,736


Claims priority, application Switzerland, June 17, 1968,

8971/68

Int. Cl. G04c 21/34

U.S. Cl. 58—57.5

6 Claims



The sounds of the alarm are produced by a membrane exposed to the atmosphere and against which strikes a vibrating blade located in a recess provided in the outer surface of a piece which constitutes a section of an envelope tightly surrounding the watch movement, the latter being located in a recess provided in the inner surface of said piece.

3,577,877

FUEL CONTROL SYSTEMS FOR DUAL FUEL GAS TURBINE ENGINES


Eugene Harold Warne, Solihull, England, assignor to Joseph Lucas (Industries) Limited, Birmingham, England

Filed Mar. 3, 1969, Ser. No. 803,650

Int. Cl. F02c 9/08; F02d 33/00; F02c 3/20

U.S. Cl. 60—39.28

15 Claims



The invention relates to a system for regulating the flow of two fuels to an engine adapted to run on either, regulation being achieved by two coupled valve members, each of which controls the flow of one fuel and which are moved axially by a servosystem powered by one of the fuels. The coupled valve members are rotatable about a common axis to vary the proportion of either fuel supplied to the engine. The configuration of the valve members is such that the total amount of fuel supplied to the engine remains substantially constant, in terms of the requirements of the engine. The servomechanism includes one or more control elements which are operated by signals obtained from the engine itself and/or from apparatus driven by the engine.

3,577,880
MEANS FOR VARYING THE PHYSICAL CONDITIONS OF A GAS


George W. D. Leslie, Johannesburg, Republic of South Africa, assignor to Anglo American Corporation of South Africa Limited, Johannesburg Transvaal Province, Republic of South Africa

Filed Jan. 24, 1969, Ser. No. 793,673
Claims priority, application Republic of South Africa, Feb. 2, 1968, 67/6058

Int. Cl. F25b 9/00

U.S. Cl. 62-86

14 Claims




In compression and expansion compartments embodying liquid pistons reciprocating in unison but in opposite directions gas is subjected to compression in one compartment followed by expansion in the other or vice versa and subjected to a heat exchange operation during its passage between the inlet of one compartment and the outlet of the other.

3,577,881
PORTABLE HIGHWAY CRASH RESCUE UNIT
Eugene J. Markovics, 1710 Federal St., McKeesport, Pa. 15132
Filed July 25, 1969, Ser. No. 844,908
Int. Cl. B21d 1/12

U.S. Cl. 72-302

13 Claims



A portable rescue unit to aid in the extraction of accident victims from wrecked vehicles including a base leg, a vertical actuating arm pivotally mounted to the base and an elongated power unit extending from the base to the side of the actuating arm and including a support abutment adapted to engage the vehicle frame. Extension of the power unit pivots the actuating arm which is connected to the vehicle door or other damaged part by a cable or chain having either a hook or a door piercing spike on the end thereof.


3,577,882
HYDRAULIC FORGING PRESS
Daniel L. Lombard, Youngstown, Ohio, assignor to Lombard Corporation, Youngstown, Ohio

Filed Sept. 14, 1967, Ser. No. 667,760

Int. Cl. B21J 9/02

U.S. Cl. 72-450

7 Claims




This patent discloses novel forging presses of large capacity in relation to the weight of the press. According to the invention, such presses are made by applying force, preferably hydraulically, to a long lever arm and causing a shorter lever arm to apply an accordingly multiplied force to the work. With presses of the invention, total press capacities as large as any hitherto ever designed or contemplated may be obtained. In accordance with a preferred embodiment, there is obtained a relatively unmassive and inexpensive ultra high capacity press having a working surface open on three sides.

3,577,883
CAPACITIVE STRAIN SENSOR
Frank D. Werner, Bloomington, Mich., assignor to Rosemount Engineering Company, Minneapolis, Minn.
Division of Ser. No. 669,036, Sept. 20, 1967, Pat. No. 3,471,758, filed June 26, 1969, Ser. No. 836,867
Int. Cl. G01b 7/16; G01n 3/00

U.S. Cl. 73-88.5

3 Claims



A method of measuring strain wherein a metal rod is mounted transversely within a cylindrical test hole in a metal structure. A spaced relation is maintained between the rod ends and hole surface and changes in electrical capacitance between the rod and the structure are indicative of strains in the test structure.


3,577,884
PRESSURE-MEASURING DEVICE
Takashi Fujita, Toyonaka-shi, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed July 31, 1968, Ser. No. 749,045

Int. Cl. G011 1/20

U.S. Cl. 73-141A

2 Claims



A pressure-measuring device employing a semiconductor element whose electric resistance is variable depending on a strain developed due to impartation of a pressure thereto so that a variation in the electric resistance of the semiconductor element due to an externally applied pressure can be detected by a meter thereby to measure the amount of pressure from the reading of the meter.

3,577,885
PAPER COATING COMPOSITION
Johnny L. Wells, Bartlesville, Okla., assignor to Phillips Petroleum Company

Filed July 30, 1969, Ser. No. 846,285

Int. Cl. G01n 19/04, 21/52

U.S. Cl. 73-150

8 Claims

A method for detecting coating transfer from a coated film which involves incorporating a fluorescent, ultraviolet light-detachable material in the coating, applying the coating to one surface of the film and subsequently scanning a surface of the film to detect the presence of the fluorescent material.


3,577,886
DEVICE FOR IMMERSION IN MOLTEN MATERIAL TO SAMPLE AND/OR MEASURE TEMPERATURE
John R. Wiese, Dresher, Pa., assignor to Leeds & Northrup Company, Philadelphia, Pa.

Filed Oct. 13, 1969, Ser. No. 865,876

Int. Cl. G01n 1/12

U.S. Cl. 73-425.4

2 Claims



A device for immersion in molten material for obtaining a sample and/or measuring the temperature. For obtaining a sample the device is comprised of a body structure including a cavity for reception of a sample of molten material. An entrance to the cavity may be closed by a fusible cap. The body structure is supported at the immersion end of a protective cardboard tube. A handle extending into the cardboard tube is employed to immerse the body structure in a bath of molten material. The device may or may not include one or more heat sensing devices for measuring the temperature of a sam-

ple as it cools and/or for measuring the temperature of the bath of molten material from which a sample may be taken. The device of this invention is characterized by the inclusion of a heat shielding protective enclosure surrounding the immersion end. The enclosure is automatically separable from the device upon immersion in a bath of molten material and moves away from its shielding position.


3,577,887
ENERGY STORAGE CONTROL DEVICE, IN PARTICULAR FOR ELECTRIC CIRCUIT BREAKERS
Guy Lambert, St. Egreve, and Marcel Macaire, Grenoble, France, assignors to Merlin Gerin, Societe Anonyme, Grenoble, France

Filed Nov. 25, 1969, Ser. No. 879,762
Claims priority, application France, Dec. 20, 1968, 179775

Int. Cl. G05g 17/00

U.S. Cl. 74-2

9 Claims



A stored energy closing mechanism for a circuit interrupter comprising a toggle linkage cooperating with stationary guide means so as to allow the scheduling of the torque exerted by the closing spring on the charging device and on the driven parts of the circuit interrupter during the operation of the mechanism.


3,577,888
SELF-LOCKING DIFFERENTIAL GEAR, ESPECIALLY FOR MOTOR VEHICLES
Rudolf Awarth, Munich, Germany, assignor to Bayerische Motoren Werke Aktiengesellschaft, Munich, Germany

Filed Mar. 12, 1969, Ser. No. 806,457

Int. Cl. F16h 1/44

U.S. Cl. 74-711

7 Claims



A self-locking differential gear especially for motor vehicles in which differential gears rotatably arranged in a dif-

ferential gear housing mesh with gears nonrotatably connected with the axle shafts; clamping bodies are provided between the differential gear housing and at least one axle shaft within annular spaces; the clamping bodies are in operative connection with hollow cylindrical friction surfaces coordinated to the differential gear housing and with support surfaces coordinated to the axle shaft whereby the clamping bodies are constructed as sections of a ring with outer surfaces matched to the friction surfaces and with internal inclined surfaces that are different from a coaxial cylinder.

3,577,889

METHOD AND APPARATUS FOR SLITTING AND TRIMMING PIPE COVERING


Herluf N. Eriksen, Burlington, N.J., assignor to Keene Corporation, Trenton, N.J.

Filed June 18, 1969, Ser. No. 834,262

Int. Cl. B26d 3/08; B23d 21/04

U.S. Cl. 83-7

9 Claims



An apparatus for finishing tubular members, conveyor means for moving tubular members in spaced-apart relation along a predetermined path, and along said path a first cutting station including a first saw blade for cutting one wall of the tubular member for its entire length, a second cutting station including a second cutting blade for partially slitting the inner wall of said tubular member along a line diametrically opposed to said first cut to provide a hinge, and a trimming station including a pair of spaced cutting elements to trim opposite axial ends of the tubular members upon relative movement of the tubular member and cutting elements.

3,577,890

MUSICAL TEACHING AID


Edgar F. Walker, and Montez A. Walker, Greenville, S.C.

Filed Apr. 27, 1970, Ser. No. 32,216

Int. Cl. G09b 15/02

U.S. Cl. 84-472

4 Claims




An apparatus for teaching the relationship between musical notes on a staff and the keyboard of a piano. The apparatus includes five spaced parallel elongated rods which are supported so that one end of the rods and the spaces therebetween terminate in corresponding keys on a keyboard. A display element having an elliptically shaped main body and a shank portion positioned on said rods. A transverse bore extends through the main body perpendicular to an elongated slot for accommodating the shank portion so that more than one main body portion can be positioned on the shank in order to represent the interval between notes.

3,577,891
SWASH PLATE COMPRESSOR
Mamoru Nemoto, Katsuta-shi, and Seijiro Tani, Hitachi-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Aug. 20, 1969, Ser. No. 851,687
Claims priority, application Japan, Aug. 21, 1968, 43-59171; 43-71485
Int. Cl. F01b 1/00

U.S. Cl. 92-72

2 Claims



Two cylinder blocks of a swash plate compressor are so shaped as to form a chamber between the cylinder block assembly, a shell and a head cover of the compressor near the junction of said two cylinder blocks. The chamber thus formed is communicated with the discharge ends of respective cylinder bores through high pressure passageways having a cross-sectional area smaller than that of said chamber. A pipe having a large number of apertures perforated through the wall thereof is disposed at that end of the high pressure passageway which is open in said chamber.

3,577,892

SPRAYING DEVICE AND METHOD


Clark A. Moore, Stockbridge, Mass., assignor to The Clark-Aiken Company, Lee, Mass.

Filed Mar. 7, 1969, Ser. No. 805,290

Int. Cl. B65h 33/00

U.S. Cl. 93-93

5 Claims



The subject invention is an apparatus and method for spraying material on a selected sheet of paper as counted sheets of paper are being moved to a piling section. One or more spraying nozzles are positioned near the piling section to spray a parting agent on one side of selected sheets of paper so that an increment of paper piled on a treated sheet can be readily separated from the rest of the pile. The nozzle

is activated to spray responsive to a signal received from a counter which impulses the signal after a preselected number of sheets have been counted to form an increment.

3,577,893

INSULATION METHOD AND CONSTRUCTIONS


Robert L. Towner, Pittsburgh, Pa., assignor to William B. Davison, Pittsburgh, Pa.

Filed Sept. 27, 1968, Ser. No. 763,192

Int. Cl. E01c 9/00

U.S. Cl. 94-4

12 Claims



Pavement procedures and constructions for materially reducing frost heave in pavements and the like; during construction of the pavement or like structure, an insulating layer consisting essentially of particulate thermal insulating material dispersed throughout a matrix of soil cement is applied to define a frost barrier which insulates the subgrade.

3,577,894

PLAYING COURT


Dean Emerson, Jr., 33 Saddlebrook, Houston, Tex., and Sidney B. Wood, Jr., 430 E. 56th St., New York, N.Y.

Filed Jan. 28, 1969, Ser. No. 794,641

Int. Cl. E01c 7/00

U.S. Cl. 94-7

6 Claims



This patent discloses a playing court which resembles turf in feel and in which the upper surface of the court dries extremely rapidly to permit the court to be used immediately after a rain.

3,577,895

SLIDE CONSTRUCTION


Eunice A. Carlin, 5301 Hollywood Road, Edina, Minn. 55436

Filed Feb. 10, 1969, Ser. No. 797,969

Int. Cl. E01c 7/00

U.S. Cl. 94-7

8 Claims



An elongated strip of relatively flexible material having a plurality of spaced apart generally longitudinally extending relatively narrow ridges on the upper surface thereof and

METHOD FOR PRODUCING STRUCTURE COMPONENTS OF REINFORCED CONCRETE SUBJECTED TO TENSILE STRESS

Ulrich Finsterwalder, Munich-Obermenz, and Klemens Finsterwalder, Socking near Starnberg, Germany, assignors to Dyckerhoff & Widmann Kommanditgesellschaft, Munich, Germany


Filed Oct. 17, 1968, Ser. No. 769,478

Claims priority, application Germany, Oct. 17, 1967, P 16 58 451.3

Int. Cl. E01c 7/10

U.S. Cl. 94-24

5 Claims



Method for making reinforced concrete structures or elements to be subjected to tensile stresses where pressure pads or casing presses are located in slots extending down from the surface at a predetermined distance from one another in parallel planes and splitting pressure is applied by hydraulic means through the presses in a direction perpendicular to the parallel planes.

3,577,897

SONIC METHOD AND APPARATUS FOR LAYING AND REPAIRING ASPHALT MATERIAL


Albert G. Bodine, 7877 Woodley Ave., Van Nuys, Calif.

Filed Nov. 12, 1968, Ser. No. 774,983

Int. Cl. E01c 19/30

U.S. Cl. 94-48

3 Claims



Sonic energy is generated by means of a self-contained resonant vibration system which utilizes an orbiting-mass oscillator as the sonic generator. The sonic energy is coupled from the resonant vibration system to a mixture of asphaltic material and gravel on a roadway structure or the like, this roadway material being excited as a resistive load. The resonant vibrational energy thus imparted to the roadway material causes random vibrations of the particles thereof which results in both a uniform mixing and a heating of the materials, as well as liquid migration therein, to provide a uniform asphalt concrete end structure.


3,577,898

SUPPLEMENTAL ILLUMINATING OF FILM PLANE IN PHOTOGRAPHIC CAMERAS

Herbert E. Bragg, New York, N.Y., assignor to Twentieth Century-Fox Film Corporation, New York, N.Y.
Filed Apr. 24, 1967, Ser. No. 633,250
Int. Cl. G03b 27/76

U.S. Cl. 95-11

2 Claims



Facilities are provided for introducing additional light supplementing or varying the exposure of a piece of film at the same time that it is being exposed to light from an object forming an image on the film. One way this is done is by admitting light from the same source through passages around the lens mount to the film frame area. This light is admitted through holes drilled through the housing around the lens mount, which holes may be left open or may have small lenses, or color filters, inserted in them. Preferably, however, such holes or bores are filled with bundles of light transmitting fibers. Held close together in the holes, the fibers may be separated on emergence at the inner ends of the holes for maximum distribution of the supplemental light transmitted by them over the exposure area. The supplemental light transmitting devices increase the effective exposure of the film with respect to the radiant energy coming from the object available, without the invention, to produce the image. They also enable special effects to be produced in a variety of ways: for example, the color balance of multilayered color negative films may be altered; the apparent contrast of the developed image may be changed and various other controlled changes may be introduced with respect to the recorded color images. Diaphragm means, such as relatively rotatable overlapping perforated annuli, may also be used to control the supplemental light in various ways. Supplemental light may also be admitted through passages at other positions.

3,577,899


FLASH SYSTEM FOR A PHOTOGRAPHIC CAMERA

Yoshizo Ikegami, Nishinomiyashi, Japan, assignor to Fuji Shashin Film Kabushiki Kaisha, Kanagawa, Japan
Filed Dec. 26, 1967, Ser. No. 693,384
Claims priority, application Japan, Dec. 24, 1966, 41/8469

Int. Cl. G03b 17/02

U.S. Cl. 95-11

2 Claims



A high-speed photographic flash system for a camera assembly. The camera assembly includes an outer case which is detachably connected to the main body of the camera and carries a portion of the electrical components for the photographic flash system. The flash system includes an electric cell, a trigger coil, a discharge tube and a thin plate-shaped electrolytic condenser. The plate-shaped condenser is carried by and extends along a portion of the outer case wall and is electrically connected to the main body of the camera when the outer case is connected thereto.

3,577,900

FILM-METERING AND DOUBLE-EXPOSURE PREVENTION MECHANISM FOR PHOTOGRAPHIC CAMERA


Dean M. Peterson, Littleton, Colo.; Charles E. Pickering, Irondequoit, and Fredric A. Mindler, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed July 15, 1968, Ser. No. 744,784

Int. Cl. G03b 17/42, 19/04, 1/42

U.S. Cl. 95-31

5 Claims



A double-exposure prevention device for a camera having a lockable film advance includes a trigger which is blocked to prevent a second exposure by an element controlled by a spring whose controlling function is adjustable by the mechanism in the camera which locks film advance.

3,577,901

REMOTELY CONTROLLED FOCAL PLANE SHUTTER


Earl E. Gray, Barrington, Ill., assignor to Bourns/Cai, Inc.

Filed Aug. 2, 1968, Ser. No. 749,869

Int. Cl. G03b 9/32

U.S. Cl. 95-57

10 Claims



Each one of a pair of focal plane shutter curtains is mounted independently of the other. An exposure slit is formed between the trailing edge of one curtain and a leading edge of the other curtain. A gear train and a dual-action differential arrangement drives the two curtains to move the slit across the format area of a camera. The gear train is, in turn, controlled by electromagnetic clutch, brake, and antbacklash devices which are actuated sequentially to start the shutter curtain travel, to couple the two curtains together to prevent variations in slit width, and to stop the curtain at the end of the travel. By locking one gear and turning another gear in the differential, the slit width may be adjusted by displacing one curtain with respect to the other.

3,577,902

DIGITAL INTEGRATOR

Thomas E. Gardner, Sunnyvale, Calif., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed Nov. 14, 1968, Ser. No. 775,673

Int. Cl. B64d 13/04

U.S. Cl. 98-1.5

2 Claims

An aircraft cabin air pressure controller includes a digital integrator having a 1023 counter and a counter which is adjustable for counts of 1022, 1023, or 1024. The two counters

3,577,904

SUSPENDED CEILING INTEGRATED AIR DISTRIBUTION SYSTEM


Robert R. Lambert, 442 W. Leadora Ave., Glendora, Calif. 91740

Filed Apr. 14, 1969, Ser. No. 815,835

Int. Cl. F24f 13/06

U.S. Cl. 98-40

6 Claims



A plurality of air distribution subassemblies, each having spaced sidewalls defining an air distribution passage therebetween, are mounted in a linear array transversely of a plurality of preexisting suspended ceiling main runner members, in one embodiment straddling cross T-bar members spanning the distance between said main runners, wherein a continuous air supply plenum is mounted on two or more adjacent subassemblies of such air distribution subassemblies with a continuous air supply outlet therein along a lower portion thereof and extending across the associated main runner, and in one said embodiment across the intersection of a main runner and across T-bar, to provide an effectively continuous linear air distribution passage through said ceiling across the main support members of the preexisting ceiling grid or support system.

3,577,905

AIR GUIDE STRUCTURE


W. R. Nussdorfer, and James M. Farrel, Greenville, Mich., assignors to White Consolidated Industries, Inc., Greenville, Mich.

Filed May 19, 1969, Ser. No. 825,583

Int. Cl. F06b 7/02


U.S. Cl. 98-94

5 Claims



Air guide structure for use in air conditioners comprising a plurality of vanes pivotally mounted on a support base extending across the edge of air outlet opening, drive means for oscillating said vanes to sweep the air transversely from the opening into the room conditioned thereby, the support base being adjustably positionable transversely of the opening to alter the drive connection to the vanes and thereby vary the amount of air directed respectively to the right or left of the front of the air conditioner.

are used with a set-reset flip-flop to form a pulsewidth modulator. The digital integrator can cause an increase in the width of the pulsewidth modulated signal by counting to 1024, can cause a decrease in the width of the pulsewidth modulated signal by counting to 1022, or it can hold the width of the signal by counting to 1023, which is the same count as given by the reference counter. The rate of pressure change created by the system is governed by the occurrence of special counts in the variable counter, the counter counting to 1023, many, many times between each command which causes the counter to either count to 1022 or to 1024, under the control of a manually adjustable rate clock. The output of the digital integrator is filtered and passed into a summing network together with an actual cabin pressure signal so as to generate an error signal for controlling the pressurization system. In addition, the error signal is fed into a 60-foot limiter that prevents the error signal from varying from the actual cabin pressure by more than the pressure



equivalent to 60 feet of altitude at sea level density. Whenever a 60-foot limit is reached, control of the digital integrator is taken over by an automatic tracking circuit which causes the digital integrator to generate a pressure reference signal at a rate of change which is much faster than the maximum permissible manual rate of pressure change. Thus, the 60-foot limit controls the actual pressure error signal by analog means, and additionally provides digital control for automatic tracking of the digital integrator so that it will be brought into correspondence with the pressure command which is integrally forced on the system by the 60-foot limiter. The 60-foot limiter comprises a digital indicating analog clamp having a pair of differentially operable, complementary transistors in the feedback loop such that when the error signal exceeds a given magnitude, an appropriate one of the transistors will conduct, which inserts a small resistor in parallel with a large feedback resistor, and which also provides a digital output signal indicating that the maximum error signal has in fact been exceeded.

3,577,903

HANDRAIL AND AIR-CONDITIONING DUCT SUPPORT


Walter S. Eggert, Jr., Huntingdon Valley, Pa., assignor to The Budd Company, Philadelphia, Pa.

Filed Dec. 30, 1969, Ser. No. 889,196

Int. Cl. B60h 1/24

U.S. Cl. 98-2

3 Claims




A support member providing support for a vehicle handrail and an air-conditioning duct. The support member passes through the air duct and is designed to minimize air turbulence.

3,577,906 GREASE-CATCHING DEVICE

John K. Preuss, 520 N.W. 144th St., Miami, Fla. 33168
Filed May 21, 1969, Ser. No. 826,562
Int. Cl. A47j 43/28

U.S. Cl. 99-234R

3 Claims




A cylindrical object having an open top and bottom and a flotation ring. This device when placed in stock pots containing soups, stews and the like, enables the user to skim the top of the contents of the pot allowing the grease to be easily dipped from the device without losing any of the contents in the pot.

3,577,907 ELECTRIC TOASTER CONTROL

Raymond W. Kunz, Monroe, Conn., assignor to General Electric Company
Filed May 12, 1969, Ser. No. 823,688
Int. Cl. A47j 27/00, 27/62

U.S. Cl. 99-329

7 Claims



An electric toaster with a timer for controlling the toasting cycle wherein a primary member is provided for setting a toasting time interval, and a secondary member is provided for temporarily changing the toasting time interval without changing the position of the primary setting member.

3,577,908 EGG COOKER


Frederick J. Burg, Bellrose, N.Y., assignor to Salton, Inc., New York, N.Y.
Filed June 2, 1969, Ser. No. 829,324
Int. Cl. A47j 27/62

U.S. Cl. 99-333

11 Claims

An egg cooker is disclosed which utilizes an electrically heated, covered water container. During the operation of the cooker the amount of heat supplied to the container is regulated by an adjustable thermostat operating essentially as an infinite switch. This thermostat regulates the heat supplied so that the cooking time is varied in accordance with the rate at

which water is boiled in the container and escapes from the container past the lid as steam. A fixed thermostat is pro-




vided to shut off the power to the heating element used when all water has been evaporated.

3,577,909 AUTOMATIC STRAPPING MACHINE

Masatoshi Takano, No. 377 Higashi Narashino-machi 1-chome, Chiba-ken, Narashino-shi; Hiroshi Arita, No. 135 Otake, Sanbu-gun, Chiba-ken, Oami-Machi, and Hayao Omori, No. 13, 11-go. Oshima-machi, Ko-to-ku, Tokyo-To, Japan
Filed Nov. 12, 1968, Ser. No. 774,711
Claims priority, application Japan, Dec. 29, 1967, 42/84512
Int. Cl. B65B 13/04

U.S. Cl. 100-4

3 Claims




In an automatic strapping machine in which a strapping band is advanced in one direction in a guide to encircle an article and is then advanced in the opposite direction to engage the article, apparatus for increasing the tension in the band before the ends of the band are fastened together. The apparatus comprises a frame mounted for displacement in both directions along the path of movement of the band, feed rolls carried by the frame to engage the band in the path, drive means for rotating the feed rolls to advance the band first in the one direction and then in the opposite direction, and control means for operating the feed rolls and the frame. The control means causes the band to advance around the article in the first direction until the article is surrounded by the band, then clamps the leading end of the band upon encirclement of the article and interruption of the first means, then drives the feed rolls in the opposite direction and to cause the frame to be displaced along the path toward the article which arrests the feed rolls, and finally operates to forcibly displace the frame away from the article to apply additional tension to tighten the band around the article.

3,577,910 PLASTIC STRAPPING MACHINE

John G. Feldkamp, 481 Hamilton Road, Homewood, Ill.
Filed Apr. 16, 1969, Ser. No. 816,737
Int. Cl. B65b 13/24

U.S. Cl. 100-17

11 Claims




Apparatus for applying plastic strapping comprises a base which defines a work platform and a joint-forming station. A complementary strap supply includes a source of strapping and a strap-feeding arrangement mounted in the base for controllably advancing strapping material toward the joint-forming station. Cooperative joint-forming heads are mounted for converging movement toward the work station, one of the heads including a strap-gripping arrangement and the other head including guide means for controllably feeding the strapping material. In addition, joint-forming means are provided and include a transfer member mounted in the base and an outlet member mounted in one of the heads to cooperate in forming joints in the strapping.

3,577,911 CONTROL FOR THE OPERATION OF THE RAM OF A BALER

Stanley A. Morse, Hammond, Ind., assignor to American Hoist and Derrick Company, St. Paul, Minn.
Filed Apr. 14, 1969, Ser. No. 815,752
Int. Cl. B30b 15/00

U.S. Cl. 100-53

2 Claims




A control mechanism for balers providing for the full cycling of a baler ram through a compression stroke, through a retraction stroke, and to a stop, upon a single initial manual actuation of a hand control on the control mechanism.

3,577,912 HORIZONTAL SCRAP METAL PRESS

Giovanni Busi, Piazzale Kossut, Brescia, Italy
Filed Oct. 1, 1968, Ser. No. 764,167
Claims priority, application Italy, Oct. 3, 1967, 814,006
Int. Cl. B30b 15/32

U.S. Cl. 100-218

4 Claims




A horizontal press is provided for forming compressed scrap metal briquettes that can be charged to electric furnace crucibles. Scrap metal is introduced into an elongated casing having a conical shape and a concave bottom. The scrap metal is compressed through the action of a fluid actuated cylinder and piston assembly.

3,577,913 TYPE CARRIER DEVICE

Herbert J. Hinze, Detroit, Mich., assignor to Burroughs Corporation, Detroit, Mich.
Filed July 24, 1969, Ser. No. 844,453
Int. Cl. B41j 1/20

U.S. Cl. 101-93

6 Claims



The disclosure embodies a printing mechanism having a number of separable type carrying blocks successively arranged for travel along an endless path. Along a linear portion of the endless path between a pair of spaced-apart sprockets is a printing station where the blocks are guided. The blocks are separable in the sense that they are not physically joined by connectors. Instead they are pushed along their path of travel by a gear which meshes with the blocks. An endless belt connects the sprockets and passes through the blocks. Coupling means on the blocks couple with the belt to provide its drive between the sprockets, the belt in turn dragging the blocks around the sprockets.

3,577,914 SCREEN PRINTING MACHINE EMPLOYING A RECIPROCATING PRINTING AND FEED PLATE


Heinrich Ronge, 115 Bergerhude, Wuppertal-E, Germany
Continuation-in-part of application Ser. No. 723,678, Apr. 24, 1968, now abandoned. This application Nov. 28, 1969, Ser. No. 880,791
Int. Cl. B41i 27/06

U.S. Cl. 101-124

10 Claims

A screen printing machine has a reciprocating printing and feed plate and retractable stops combined and cooperating with said plate so that the material to be printed moves forward over the plate in a stepwise manner. The screen is

mounted over this plate and reciprocates with it so that the material passes under the screen. While it is under the screen



a relatively stationary printing squeegee is lowered into its operative position and printing is thereby effected.

3,577,915

HOT SCREEN PRINTING WITH THERMOPLASTIC INK

Stanley P. Thompson, and Don L. Shofer, Bartlesville, Okla., assignors to Phillips Petroleum Company

Division of Ser. No. 602,551, Dec. 19, 1966, filed May 1, 1969, Ser. No. 821,081

Int. Cl. B41m 1/12

U.S. Cl. 101-129

5 Claims

A hot screen printing process is disclosed wherein a thermoplastic ink comprising polyethylene, a colorant, and either an ester of rosin or a wax is used at a temperature in the range from about 200-450° F. for screen printing on polyolefin.

3,577,916

DUPLICATOR PROGRAM CONTROL ASSEMBLY


Kenneth J. Tonkin, Glenview, and John P. Gallagher, Park Ridge, Ill., assignors to A. B. Dick Company, Niles, Ill.

Division of Ser. No. 633,866, Apr. 26, 1967, filed Apr. 8, 1969, Ser. No. 836,183

Int. Cl. B41l 25/02

U.S. Cl. 101-148

2 Claims



An etcher assembly for etching a master cylinder of a duplicating machine supported between the side plates of the

duplicating machine. The etcher assembly includes a rotatably mounted metering roller that is partially disposed within a fountain mounted on the duplicating machine, and an etch applicator roller rotatably supported between two parallel support arms that are adapted to swing about the shaft of the metering roller. A pair of return springs constantly urge the etch applicator roller into contact with the metering roller.

3,577,917
PRINTING MACHINES WITH SHIFTING ROLLER PLATEN


Jack G. Nantz, Euclid, Ohio, assignor to Addressograph-Multigraph Corporation, Cleveland, Ohio

Filed Aug. 4, 1969, Ser. No. 847,178

Int. Cl. B41f 3/04

U.S. Cl. 101-269

7 Claims



Imprinting of forms with fixed and variable data from printing elements comprising two distinct groups of characters. A bed retains the printing elements and the form, and a roller platen moves from a home position in a first path across the form to an actuated position and back to home position in a second path across the form to perform a printing cycle. The roller platen is shiftable between the first and the second path such that as the platen is moved in the first path it is operative to imprint a single line only of one group of characters, and as it is moved in the opposite direction in the second path it is operative to imprint a single line only of the other group of characters, to thereby compensate for imprinting pressure as a result of rolling line contact of the platen with only a single line of characters without the platen reaching any adjacent line of characters.

3,577,918

MARKING-MEASURING DEVICES


David John Wayfield, (Freeland, Md.), Box 188, Tivoli, N.Y.

Continuation-in-part of application Ser. No. 500,866, Oct. 22, 1965, now abandoned. This application Oct. 3, 1967, Ser. No. 672,506

Int. Cl. B41k 1/22

U.S. Cl. 101-328

26 Claims



A portable, hand-operated tool which includes a printing pressure roller for marking a surface in precise linear segments, each of the segments being of a length greater than the circumference of the printing pressure roller.

3,577,919
METHOD AND APPARATUS FOR POSITIONING
ARTICLES


Alexander J. Usko, Wapping, Conn., assignor to Monsanto Company, St. Louis, Mo.

Filed Mar. 13, 1969, Ser. No. 807,013

Int. Cl. B23q 5/22; B65g 47/24

U.S. Cl. 101-426

13 Claims



A method of handling elongated articles such as plastic bottles being transported to and from a vertically oriented work station, which involves transporting the articles on their sides, pivoting each article upright at the work station and striking each article in a controlled manner on leaving the work station to return it to its side. Apparatus includes a pivotally mounted loading device, a reciprocally mounted arm at the discharge of the work station for knocking the bottom of each article onto a conveyor and a bumper adjacent the arm to prevent the upper article portion from moving in the same direction as the arm when the article is contacted thereby.

3,577,920

METALLIC LITHOGRAPHIC PLATE AND METHOD OF MAKING THE SAME

Melvyn London, Deerfield; Guy Robert Smetters, Downers Grove, and George Eugene Beck, Prospect Heights, Ill., assignors to London Litho-Aluminum Company, Incorporated, Lincolnwood, Ill.

Filed July 10, 1967, Ser. No. 651,986

Int. Cl. B41n 1/08; B23k 21/00

U.S. Cl. 101-459

3 Claims

Metallic lithographic plate for use in the copperized lithographic printing process, comprising a base layer of magnesium-aluminum alloy and a surface layer sheet of aluminum metallurgically bonded thereto under conditions of temperature and pressure which bring about both physical and chemical changes in said surface layer and place it in a hard tempered condition, the resulting "activated" aluminum surface improving the ease of depositing copper thereon and the durability and tenacity of the copper so deposited in image areas subsequent to development, and also preventing the decomposition of light sensitive diazo compounds in contact with said surface layer.

3,577,921

CASELESS AMMUNITION FOR FIREARMS AND THE LIKE

Jules Edmond Van Langenhoven, Benton County, Ark., assignor to Victor Comptometer Corporation, Chicago, Ill.


Division of Ser. No. 473,556, July 7, 1965, abandoned, filed July 18, 1968, Ser. No. 760,108

Int. Cl. F42b 9/16

U.S. Cl. 102-38

10 Claims

There is herein disclosed caseless ammunition for firearms comprising a projectile portion and an associated caseless



one-piece solid porous ungranulated propellant portion.

3,577,922

COMBUSTIBLE SHELL BASE

Paul Zehfeld, Huttenstrasse 82, Dusseldorf, and Hans-Dieter Harnau, Feldstrasse 2, Gevelsberg, Germany


Continuation-in-part of application Ser. No. 594,565, Nov. 15, 1966. This application Feb. 6, 1969, Ser. No. 796,956

Claims priority, applications Germany, Nov. 17, 1965, May 14, 1966, P 12 91 262.8-15, P 15 78 204.4

Int. Cl. F42b 9/28

U.S. Cl. 102-44

4 Claims



A combustible cartridge with an electric primer in which the bottom portion of the cartridge composed of combustible synthetic material with a plurality of annular surfaces arranged in different planes relative to one another and a primer is provided in the bottom portion.

3,577,923

PERCUSSION-ELECTRIC PRIMER AND RADIATION SHIELD


William E. Perkins, Runnenede, N.J., and Allen F. Schlack, Churchville, Pa., assignors to the United States of America as represented by the Secretary of the Army

Filed Jan. 16, 1969, Ser. No. 791,598

Int. Cl. F42b 9/08

U.S. Cl. 102-46

6 Claims



A combined percussion-electric primer having an electrically insulated rimfire cap is centrally positioned at the rearward end of a cartridge, and an electromagnetic radiation shield having a weakened central portion adapted to yield upon firing pin impact is positioned rearwardly of the primer.

3,577,924 SHOTSHELLS


Donald Urquhart Findlay; Francis Hamnet Garland McCaffrey, Brownsburg, Quebec, and George David Taylor, Lachute, Quebec, Canada, assignors to Canadian Industries Limited, Montreal, Quebec, Calif.

Filed Feb. 14, 1969, Ser. No. 799,276

Claims priority, application Canada, Mar. 26, 1968, 015936
Int. Cl. F42b 7/08, 9/26

U.S. Cl. 102-42R

4 Claims



The present invention provides a novel shotshell basead construction by which the useful life of reloadable shotshells may be increased. The basead comprises two interlocking components of molded thermoplastic material which are pressed into the bottom end of a shotshell tube. The basead construction provides increased durability and improved gas sealing properties over earlier known types.

3,577,925


HOUSING FOR BALLISTIC TELEMETERING SONDE
Louis A. Schmidt, Hyattsville, Md.

Filed Nov. 26, 1965, Ser. No. 510,453

Int. Cl. F42b 11/00; H05k 13/04, 13/00

U.S. Cl. 102-70.2

4 Claims



An improved housing for standardizing the assembly, packaging and potting of various combinations of operational components for a radio sonde into a highly flexible and interchangeable unit.

3,577,926

VARIABLE VOLUME SAFE AND ARM MECHANISM
Wilfred C. Schuermann, Rawlins, Md., assignor to Hercules, Incorporated, Wilmington, Del.

Filed Dec. 31, 1968, Ser. No. 789,058


Int. Cl. F42c 15/32, 15/04, 15/06

U.S. Cl. 102-76

7 Claims

A safe and arm mechanism is provided employing in combination a pressure-responsive diaphragm and a variable volume chamber which are adaptable to change the mechanism from the "safe" configuration to the "armed" configuration. In the "safe" configuration gas pressure resulting from accidental ignition of a squib is insufficient to rupture the pressure-responsive diaphragm protecting the device in which the safe and arm mechanism is employed. In the

"armed" configuration the available volume of the variable volume chamber is reduced and ignition of a squib within the



mechanism ruptures the pressure-responsive diaphragm allowing the squib gases to initiate an igniter.

3,577,927

ARRANGEMENT FOR CONFINING A VOLUME OF FLUID


Jean Henri Bertin, Neuilly-sur-Seine, France, assignor to Bertin & Cie, Plaisir, France

Filed Apr. 4, 1968, Ser. No. 718,764

Claims priority, application France, Apr. 5, 1967, Aug. 20, 1967, 101,643; 119,166
Int. Cl. B60v 1/04, 1/16

U.S. Cl. 104-23

10 Claims



An arrangement for reducing leaks in machines, chiefly, ground-effect machines such as vehicles running over or under a fluid cushion, this being obtained by providing a friction reduced to a minimum between the free edges of walls which peripherally confine the fluid cushion and the cooperating vertical or horizontal track surfaces as provided by laying a trail of lubricant in the gap between said free edges and the track surface, preferably through distributing channels extending inside the walls and opening into registry with said gap.

3,577,928

LINEAR INDUCTION MOTOR DRIVE SYSTEM
Marcel Victorri, Grenoble, France, assignor to Merlin Gerin, Societe Anonyme, Grenoble, France


Filed Apr. 18, 1969, Ser. No. 817,488

Claims priority, application France, May 6, 1968, 150757

Int. Cl. B61b 13/00

U.S. Cl. 104-148LM

5 Claims



A linear induction motor drive system comprising a stationary magnetic stator structure 28,30 having an airgap 32 in which a magnetic traveling field drives the armature plates

3,577,931

DAMPENED RAILWAY CAR TRUCK


James A. Shafer, East Cleveland, Ohio, assignor to Midland-Ross Corporation

Filed Dec. 9, 1966, Ser. No. 600,486

Int. Cl. B61f 5/06, 5/08, 5/12

U.S. Cl. 105-197

3 Claims



A railway car truck which includes a bolster supported at each end on load springs which are in turn supported by the side frames of the truck. The load springs are of length which exceeds that of conventional load springs to attain softer, full-load cushioning. To avoid mispositioning of the car coupler at a greater height than allowed, the car truck includes cushioning devices between the bolster and the upper part of each side frame.

3,577,932

EXTERIOR COVER ENCLOSING HOPPER GATE AND ACTUATING MECHANISM


Frank C. Pulcrano, and Dallas W. Rollins, St. Charles, Mo., assignors to ACF Industries, Inc., New York, N.Y.

Filed Mar. 25, 1969, Ser. No. 810,197

Int. Cl. B61d 5/04, 5/08, 7/22

U.S. Cl. 105-253

7 Claims



A lower generally pan-shaped cover for fitting around the entire bottom discharge structure of a railway hopper car, such as a discharge structure having a gravity gate and a combination rack-and-pinion drive for the gravity gate. The cover seals the entire bottom outlet structure against the entrance of foreign matter including the drive means. Means mount the cover for movement between a covering position with respect to the bottom outlet and a position removed from beneath the bottom discharge outlet to permit the discharge of lading. The cover is formed of fiber glass and resin binder to insulate the bottom discharge structure for minimizing heat losses from an insulated car. The capstans for rotating the pinion shaft are mounted for folding to an inoperative position in order for the cover to cover the drive means while remaining within clearance limits and without being of an unduly long length.

24 secured to the driven vehicles 10. The armature plates are pivotally connected at 22 to the vehicles in order to allow rolling movements of the vehicles and overlapping of the armature plates in vertical inflexion zones.

3,577,929

ELECTRIC VEHICLE DRIVING AND CONTROLLING APPARATUS

Yoshimitsu Onoda, and Hisakatsu Kiwaki, Katsuta-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 7, 1968, Ser. No. 774,052

Claims priority, application Japan, Nov. 10, 1967, 42/71991

Int. Cl. B60l 13/00

U.S. Cl. 104-148

8 Claims



An electric vehicle driving and controlling apparatus, wherein during the low-speed operation, single-phase AC power is supplied to a synchronous motor type rotary machine through a thyristor group to thereby control the rotation of said rotary machine, and during the ultra-high-speed operation, three-phase AC power available at the armature terminals of said rotary machine is also applied to a linear motor to thereby accelerate the latter.

3,577,930

MONORAIL SYSTEM


Jack Rooklyn, Northridge, Calif., assignor to Republic Corporation, Beverly Hills, Calif.

Filed Nov. 24, 1967, Ser. No. 685,561

Int. Cl. B61b 31/00; B65g 17/24; E01b 25/22

U.S. Cl. 104-173

9 Claims



An overhead conveyor system having a trolley rolling along a pair of spaced bars and a pendant for carrying goods, the pendant suspended from the trolley and passing downwardly between the rods. The trolley comprises a pair of hemispheres, one hemisphere rolling along each rod, and the hemispheres are pivotally connected to rotate independently of each other.

3,577,933

LIGHTWEIGHT RAILWAY CONTAINER CAR


Ray L. Ferris, Thornton, Ill.; William R. Shaver, Munster, Ind., and William P. Manos, Chicago, Ill., assignors to Pullman Incorporated, Chicago, Ill.

Filed Dec. 5, 1968, Ser. No. 781,337

Int. Cl. B65j 1/22

U.S. Cl. 105-366

18 Claims



A railway car of lightweight design consisting of a skeletal fishbelly structure having at opposite ends an end frame structure including a boxlike center sill. A boxlike transition structure connects the end frame structure to an intermediate structure which includes a pair of longitudinally extending spaced-apart webs having relatively narrow horizontal top and bottom flanges providing side sill members. The end structures include crossmembers which provide end sill platforms which support container brackets. Additional container brackets are supported alongside the side sill members for supporting containers of various lengths and a latticework structure replaces the conventional deck plate structure and is connected to the top and bottom flanges to stabilize the container brackets and the structure at the loading points.

3,577,934

TRANSITION REINFORCEMENT FOR FISHBELLY UNDERFRAME


Jack E. Gutridge, Dyer, Ind.; Kent N. Johnson, South Holland, and John H. Spence, Chicago Heights, Ill., assignors to Pullman Incorporated, Chicago, Ill.

Filed Aug. 28, 1968, Ser. No. 755,880

Int. Cl. B61f 1/02

U.S. Cl. 105-414

7 Claims



A railway car underframe of the fishbelly type wherein transition sections connected between the end section and a center section include a reinforcement structure in the area of the transverse bend line of the bottom plate, the structure comprising upright plates located between and connected to spaced vertical webs of the underframe, with the plates extending longitudinally with the webs, and having their lower edges connected to the bottom plates on longitudinally spaced opposite sides of the bend line, said structure improving the stress distribution on the transition section bottom plate.

3,577,935

EXTRUSION APPARATUS

Richard D. Reinhart, and Robert O. Straughn, Minneapolis, Minn., assignors to General Mills, Inc.

Filed Feb. 1, 1967, Ser. No. 613,254


Int. Cl. A21c 1/16

U.S. Cl. 107-14

12 Claims

An apparatus and method for extruding an elongated, tubular, corrugated product having a plurality of longitudinally extending indentations or depressions on its surface. Extrud-

ble material is forced through an extrusion apparatus having an annular extrusion orifice formed by a die opening in the extrusion apparatus, and a mandrel having its projecting end positioned in the opening. Either the shape of the die opening or the shape of the mandrel is formed in such a manner that the thickness of the space surrounding the mandrel varies at a number of different points. A product made by using this apparatus has a somewhat coblike appearance.



ing or the shape of the mandrel is formed in such a manner that the thickness of the space surrounding the mandrel varies at a number of different points. A product made by using this apparatus has a somewhat coblike appearance.

3,577,936

STOOL OR LEG REST


William M. Emery, 44 Pittsford Way, New Providence, N.J.

Filed Jan. 10, 1969, Ser. No. 790,348

Int. Cl. A47c 7/50

U.S. Cl. 108-8

1 Claim



A stool or leg rest widely adjustable as to height and angle having but few simplified basic parts, i.e. 3 similar 1/4-inch plywood platens coinciding when adjacent, their ends interjoined by hinges, two sets of plywood diecut and inwardly directed ratchet teeth made integral with the upper side of two platens to coincide with the longer edges thereof and two U-pawls nested intermediate of said ratchets when platens are adjacent, journaled on the undersides of two of the platens facing the ratchets, and gravity responsive when the leg rest is being Z-extended.

3,577,937

CORNER POST SUPPORT, PREFERABLY FOR LOAD PALLETS

Ake E. Sjoblom, Orebro, Sweden, assignor to Aktiebolaget Grythyttans Stalmobler, Grythyttan, Sweden


Filed Apr. 8, 1969, Ser. No. 814,316

Claims priority, application Great Britain, Apr. 8, 1968, 4,700/1968

Int. Cl. B65d 19/18

U.S. Cl. 108-53

10 Claims



A detachable corner post support for a load pallet. A bracket is bent at an angle to fit against the two vertical sides of the pallet which form the corner, and the bracket extends

above the load supporting surface of the pallet. A corner plate attached to the inside of the bracket lies against the top of the load supporting surface and forms with the inside of the bracket a three-sided mounting for a corner post. Two attachment wings are attached to the bracket and extend one along each of the vertical sides which form the corner and in a direction away from the corner. Hook-formed elements extend from each wing inwardly beneath the load supporting surface and generally perpendicular to its respective vertical side, each hook-formed element engaging a side of the corner foot of the pallet which lies at an angle to its respective vertical side. The hook-formed element of at least one attachment wing is movable out from its position perpendicular to its respective vertical side to facilitate assembling the corner post support onto the pallet.

3,577,938

INCINERATORS

Duncan Ronald Muirhead, Narrow Lane, near Ferriby, and John Francis Richardson, Swansea, South Wales, England, assignors to Rose, Downs & Thompson Limited, Kingston-upon-Hull, Yorkshire, England


Filed May 8, 1969, Ser. No. 822,975

Claims priority, application Great Britain, May 10, 1968, 22,424/68

Int. Cl. F23g 5/00

U.S. Cl. 110-8

8 Claims



In a method of disposing of town refuse the refuse is burnt in an incinerator whilst supported on a nonfluidized mass of refractory granular material and the granular material is periodically fluidized to allow the noncombustible content of the refuse to pass therethrough and be removed from the incinerator through an outlet. The mass of refractory granular material serves as a valve for permitting the noncombustible content of the refuse which collects on the surface of the granular material to pass therethrough and be removed from the incinerator.

3,577,939

INCINERATORS

Duncan Ronald Muirhead, Narrow Lane, near Ferriby, England, assignor to Rose, Downs & Thompson Limited, Kingston-upon-Hull, Yorkshire, England

Filed May 8, 1969, Ser. No. 822,977

Claims priority, application Great Britain, May 10, 1968, 22,412/68


Int. Cl. F23g 5/00

U.S. Cl. 110-8

8 Claims

In a method of disposing of town refuse, the refuse is burnt whilst supported in an incinerator by a fluidized bed of refractory granular material and the bed is separated from an outlet of the incinerator container by a mass of refractory granular material which is periodically fluidized to allow the noncombustible content of the refuse to pass therethrough and be removed from the incinerator through the outlet. The mass of refractory granular material may form an extension

of the bed which supports the refuse whilst it is burnt with the mass of granular material positioned between the part of



the bed which supports the refuse and an outlet from the incinerator container.

3,577,940

INCINERATOR


Robert Joel Hasselbring, Shelbyville, and Robert Loren Shields, Rushville, Ind., assignors to General Electric Company

Filed Oct. 27, 1969, Ser. No. 869,823

Int. Cl. F23g 5/12

U.S. Cl. 110-8

23 Claims



An incinerator for burning waste material includes a combustion chamber having spaced end walls and a sidewall through which a mixture of waste material and air is introduced under pressure tangentially for establishing a vortical movement of the waste material toward one of the end walls. The waste material is ignited during its vortical movement and the chamber includes a discharge flue at the one end wall which is concentric with the central axis of the chamber and which has an open end in the chamber spaced axially of the one end wall. A second discharge port adjacent the one end wall extends tangentially through the sidewall for discharging from the chamber products residual combustible material and noncombustible material entrained in the outer region of the vortex. The discharged material is conveyed through a conduit to a separator which separates the discharged gases and solid material. The separated gases and any solid particles suspended therein are introduced back into the chamber. A baffle is mounted on the flue adjacent its open end for deflecting outwardly toward the sidewall solid material which moves from adjacent the one end wall toward the open end of the flue.

3,577,941

INCINERATOR

Fritz Schoppe, Ebenhausen, Germany, assignor to Aqua-Chem, Inc.

Filed May 19, 1969, Ser. No. 825,865

Claims priority, application Germany, June 21, 1968, P 17 51 574.1


Int. Cl. F23g 5/06

U.S. Cl. 110-14

6 Claims

An improved maintenance system in a pyrometric cone incinerator having a conical basketlike hollow body located in

a housing and having perforated walls. The basketlike hollow body is positioned rotatably about an axis inclined at an angle to the horizontal line and has an obliquely upwardly directed large feed opening and an obliquely downwardly directed smaller discharge opening. The discharge opening is aligned with a bar cage attached to the lower end of the conical body and coaxial therewith. The outer end of the bar



cage is rotatably supported on a suitable bearing which supports the body and the bar cage on a portable frame. An access door is provided in the lower axial discharge opening of the conical body. An operating means including an operating shaft extends axially outwardly from the access door through the bar cage, drive means and bearing means to an external operating handle.

3,577,942

APPARATUS FOR CLOSING HOSIERY TOES AND EVERTING HOSIERY AND METHOD


Dalton O. Hulin, Lexington, N.C., assignor to Sliver Knit Hosiery Mills, Inc., High Point, N.C.

Filed July 30, 1969, Ser. No. 846,051

Int. Cl. D05b 7/00; A41h 43/00

U.S. Cl. 112-25

11 Claims



A method and apparatus for turning socks wherein open-toe socks are everted to wrong side out condition and impaled upon points of a rotary dial for the formation of a toe closure. Means are provided to evert the toe-closed socks to their original right side out condition after the toe-closing operation.

3,577,943

DENSE PILE TUFTING MACHINES

Charles William Watkins, Hixson, Tenn., assignor to The Singer Company, New York, N.Y.

Filed Apr. 3, 1969, Ser. No. 813,130


Int. Cl. D05c 15/28

U.S. Cl. 112-79

16 Claims

This disclosure relates to tufting machines for producing dense pile fabrics and more particularly those of the cut pile type. In general, the machine includes apparatus for shifting the backing fabric used in the tufting process relative to the needles, loopers, and cutting mechanism. Through the novel

arrangement of the shifting mechanism and the tufting components, as set forth in this disclosure, a dense pile fabric is produced having rows of pile tufts which are spaced less than the distance of the spacing between adjacent needles as viewed in the direction of the backing fabric feed. As is known in the art, the gauge of the machine is measured by



the transverse spacing between adjacent needles. The longitudinal rows of tufting produced through the apparatus of the present disclosure are spaced less than the gauge distance. The disclosure further presents a commercially desirable machine of the so-called sliding needle plate type which produces a cut pile fabric.

3,577,944

UNDERTRIMMER MECHANISM FOR SEWING MACHINES


Erich M. Willenbacher, Karlsruhe; Ulrich Schmedtkord, Badenwuerttemberg, and Dieter K. Gabler, Neudorf, Germany, assignors to The Singer Company, New York, N.Y.

Filed Oct. 7, 1969, Ser. No. 864,447

Int. Cl. D05b 37/02

U.S. Cl. 112-127

11 Claims



A trimming mechanism for a sewing machine for severing the marginal edge of the lower ply of material being seamed. Oscillatory movement is imparted to the trimming blade by a series of arms driven off an eccentric on the sewing machine bed shaft. An operator-controlled cam member is operatively connected through its follower to mechanism which changes the relative position of the arms to vary the stroke of the trimming blade and also change its vertical elevation so that the blade at the bottom of its cutting stroke is at the same elevation for any stroke selected.

3,577,945

ADJUSTABLE GAGE FOR SEWING MACHINES


Arthur Kalish, 64-10 Dieterle Crescent, Rego Park, N.Y.

Filed Jan. 16, 1969, Ser. No. 791,713

Int. Cl. D05b 35/10

U.S. Cl. 112-153

2 Claims



A sewing machine gage for controlling the distance between a stitch and edge of thin, delicate fabric, as well as heavier fabrics. The gage comprises a frame member provided with a magnetized bar for securing the gage against lateral displacement on a sewing machine table. A pair of pins secured to the frame are received in the sewing machine table to prevent the lateral displacement of the gage. A ferrous gage member is slidably and pivotably mounted on the frame to permit its adjustment at a desired position. The gage member is provided with a gage foot and a magnetized element for holding down the gage foot in intimate engagement with the table surface of the sewing machine. The magnetized bar holds the ferrous gage member in a selected position at a selected distance from the stitch.

3,577,946

STABLE MARINE CONSTRUCTION


Edward E. Horton, Portuguese Bend, Calif., assignor to Deep Oil Technology, Inc., Long Beach, Calif.

Filed Feb. 6, 1969, Ser. No. 797,121

Int. Cl. B63b 35/44; E02b 17/00

U.S. Cl. 114-0.5

10 Claims



A marine construction and a mooring system therefor for supporting an above surface working platform wherein the marine construction comprises a stable determinate structure held by anchor means and by tension means interconnecting the anchor means and structure for positioning the marine structure a selected distance below the surface of the water. The submerged marine structure includes a plurality of main buoyant members forming a continuous peripheral buoyant means of selected cross-sectional configuration whereby cyclic stresses imparted to the structure and tension means by wave action are minimized and reduced. The submerged buoyant means also includes internal buoyant members symmetrically disposed with respect to the main buoyant members and arranged to interconnect corresponding portions of main members for enhancing stability of the construction under different conditions.

3,577,947

MULTIPLE HULL BOAT

Gordon L. Draeseke, 1599 Angus Drive 9, Vancouver, British Columbia, Canada


Filed Apr. 28, 1969, Ser. No. 819,603

Claims priority, application Great Britain, May 17, 1968, 23484/68

Int. Cl. B63b 1/10

U.S. Cl. 114-61

7 Claims



A water craft having a rigid superstructure supported by three deep draft pontoons arranged in a triangular configuration with two forward and one aft, the aft pontoons are elongated in both fore-and-aft and vertical directions and have sidewalls extending in a substantially straight line configuration from top to bottom so as to have a substantially linear depth-buoyancy ratio.

3,577,948

STABILIZER TRIM ATTACHMENT FOR POWER BOATS


Ellsworth J. Frey, Logan, Ohio, assignor to Star Tab, Inc., Logan, Ohio

Filed Apr. 11, 1969, Ser. No. 815,404

Int. Cl. B63b 1/22

U.S. Cl. 114-66.5

1 Claim



An attachment for a power boat which fits on the transom or stern of the boat and comprises a pair of trim tabs hinged at the transom and extending rearwardly therefrom, and which may be swung vertically simultaneously to different angular positions to trim the boat so that it operates at the proper attitude regardless of its loading. The tabs are so formed that they also bring about lateral stability as well as impart the proper attitude to the boat. Furthermore, the tabs are positively moved vertically up or down to their selected angular positions.

3,577,949

EXPLOSIVELY PROPELLED UNDERWATER EMBEDMENT ANCHOR ASSEMBLY

Kenneth E. Mueller, Baltimore City; John L. Critcher, Cockeysville; Franklin A. Monson, Glenarm; William H. Turnbaugh, Cockeysville, and John E. Kosloski, Timonium, Md., assignors to the United States of America as represented by the Secretary of the Navy

Filed June 19, 1968, Ser. No. 740,817


Int. Cl. B63b 21/28, 21/26; F41c 27/00

U.S. Cl. 114-206

12 Claims

An explosively propelled underwater embedment anchor assembly having a barrel with a smooth bore therethrough except for an internal flange near the muzzle extremity; a

breech at the other end of the barrel; an explosive propellant cartridge within the barrel and adjacent the breech; a piston also within the barrel and adjacent the breech but on the muzzle side thereof, the piston having an outside diameter approximately equal to the diameter of the smooth bore; and



a harpoon adjacent the piston and extending out of the barrel, the harpoon having a maximum outside diameter approximately equal to the inside diameter of the flange. A spring-biased firing pin is restrained by a plurality of ball lock detents held in place by a resiliently biased tube.

3,577,950

UNDERWATER MOORING RELEASE DEVICE


William Gordon, 1173 Fountain Way, Anaheim, Calif.

Filed July 7, 1969, Ser. No. 839,266

Int. Cl. B63b 21/24; A44b 13/00

U.S. Cl. 114—206

13 Claims



An underwater mooring release device having an explosive-charge-actuated piston to shear a diaphragm and release toggle-type load retainer means. Control for the explosive charge is enclosed in a housing which remains sealed after detonation of the explosive charge and release of the tethered load. Simple clamping means releases the components for servicing and reconditioning after a use cycle.

3,577,951

APPARATUS FOR STOWING AND DROPPING AN ANCHOR

Erwin M. Smith, Rte. 1, Box 355, Camas Valley, Oreg.

Filed Mar. 19, 1969, Ser. No. 808,529


Int. Cl. B63b 21/22

U.S. Cl. 114—210

4 Claims

An apparatus is disclosed located on the forward deck of a boat and operable to position an anchor from a stowed location over the deck to a dropping position. An anchor carriage

is mounted for travel along a rail structure having a curved segment located adjacent the boat's prow whereat the carriage discharges the anchor and oppositely receives the anchor during stowing of same. The anchor carriage is posi-



tionable forward to an anchor discharge position by spring means which means is loaded by powered retrieval of the anchor and the anchor carriage to a rearward stowed position. Powered winch means are also disclosed.

3,577,952

EXHAUST SYSTEM OF PROPELLER FOR SHIPS

Hiroshi Tado, Suita-shi, Japan, assignor to Yanmar Diesel Engine Co. Ltd., Kita-ku, Osaka, Japan


Filed Sept. 22, 1969, Ser. No. 859,744

Claims priority, application Japan, Sept. 30, 1968, 43/85326

Int. Cl. B63h 21/34

U.S. Cl. 115—17

1 Claim



An exhaust tube is mounted in an exhaust pipe connected to the exhaust port of the engine of a propeller apparatus. A deflector member defining obliquely radially extending channels and having a concave outer surface is provided at the lower end of the exhaust tube integrally therewith, so as to divert the path of gas flow in the exhaust pipe and also repulse the water particles sucked up by being entrained by the wave of negative pressure of the engine reflecting on the surface of water present in the lower portion of the exhaust pipe.

3,577,953

LIFTING APPARATUS FOR OUTBOARD MOTORS

Siegfried Braun, and Heinz Hieber, Friedrichshafen, Germany, assignors to Zahnradfabrik Friedrichshafen, Aktiengesellschaft, Friedrichshafen, Postfach, Germany

Filed May 20, 1969, Ser. No. 826,100


Claims priority, application Germany, Jan. 8, 1969,

P 19 00 710.4

Int. Cl. B63h 5/12

U.S. Cl. 115—41

8 Claims



An outboard motor is conventionally supported to swing on vertical and horizontal axes. A pressure fluid cylinder and piston is arranged between the motor and the support which carries it. A latch device is likewise provided between the motor and support which automatically locks them together when the motor is in normal operating position. However, the latch device is automatically released via a lost motion device when the cylinder is initially pressurized. Continued pressurization raises the motor through takeup of lost motion in the device, for operation in shallow water or for any other purpose.

3,577,954

TILT LATCHING AND LOCKING MEANS FOR TILTABLE STERN DRIVES FOR BOATS


Kjell Borgersen, Gothenburg, Sweden, assignor to AB Volvo Penta, Gothenburg, Sweden

Filed July 7, 1969, Ser. No. 839,219

Int. Cl. B63k 5/12

U.S. Cl. 115—41

8 Claims



A tilt lock for motor boat stern drives of the type comprising a downwardly extending leg having propeller means at its lower end portion and pivotally connected to the boat at its upper portion on an axis extending laterally of the boat keel for tilting upwardly and rearwardly. The tilt lock comprises pivoted arms preferably carried by the leg having notches therein for receiving a pin preferably carried by the boat in a

selectable position. The notches are provided with cam surfaces which engage the pin during forward propulsion in a direction to force the arms away from the pin, whereby sudden tilting of the leg moves the arms away from the pin before biasing means are effective to swing the arms into position to nest the pin in the notches. A latch member is arranged for selective swinging into the path of yielding movement of the latch, and the lock member is operably connected to reverse gear shifting means to lock the latch member in retaining position during reverse operation of the propeller means.

3,577,955

DISCONTINUITY SENSOR


Charles G. Palmer, Orange, Calif. (1628 E. Stafford, Santa Ana, Calif. 92667)

Filed June 19, 1968, Ser. No. 738,251

Int. Cl. G01d 21/00

U.S. Cl. 116—114

13 Claims



This invention relates to discontinuity or surface irregularity sensors. Three embodiments are illustrated and described. All three illustrate application of the invention to the task of counting articles, such as newspapers, being conducted along a conveyor. Each of these three embodiments includes two surface or contour follower elements spaced apart in the direction of conveyor movement and individually mounted for movement in a degree corresponding to the value of that dimension in which discontinuities or surface irregularities are to occur. Means are provided for sensing the difference in movement of the follower elements and for providing a signal upon the occurrence of a selected difference.

3,577,956

PARTITION WALL FOR SHEDS HAVING AUTOMATIC DUNG SCRAPER

Adolf G. Forster, Augsburg, Germany, assignor to Alfa-Laval AB, Tumba, Sweden

Filed May 16, 1969, Ser. No. 825,160


Claims priority, application Germany, May 17, 1968,

A29790/45hGhm

Int. Cl. A01k 1/00

U.S. Cl. 119—15

11 Claims



The shed floor includes a cleaning area along which a scraper is movable automatically to remove dung. A partition wall has an opening located above the cleaning area and so dimensioned as to permit a reclining animal to pass through the opening in the event that the animal is entrained by the

scraper. While thus passing through the opening, the reclining animal displaces a yieldable barrier means from its normal position extending across the opening, the barrier means having a lower edge spaced above the cleaning area a sufficient distance to permit the scraper to pass freely under the barrier means.

3,577,957

ANIMAL FEEDER HAVING ADJUSTABLE TIMING MEANS

Henry Sandig, 38 Park Row, New York, N.Y.
Filed Sept. 9, 1969, Ser. No. 856,357
Int. Cl. A01k 5/02

U.S. Cl. 119-51.11

3 Claims



An automatic animal feeder comprising upper and lower container elements, the upper container element being adapted to contain food, the lower container element containing a meltable solid or solids and having drainage means for the resultant melted fluid after said solids have melted. Resilient means urge the containers into mutually telescoped relation. Each container includes an opening alignable with an opening in the other container to provide a passage through which food may be discharged, whereby with the melting of the meltable solids in the lower container and melting fluid discharged therefrom, the lightening of the effective weight and the diminishing of the space between the containers permits the resilient means to progressively telescope the container elements to align the openings for this purpose.

3,577,958

STEAM BOILER HEATED BY WASTE HEAT

Shozo Narita, Masaki Ojima, and Asahiko Shiraishi, Kobe City, Japan, assignors to Kawasaki Jukogyo Kabushiki Kaisha, Kobe City, Japan

Filed Feb. 12, 1969, Ser. No. 798,681

Claims priority, application Japan, Feb. 14, 1968, 43/9283

Int. Cl. F22b 1/18

U.S. Cl. 122-7

6 Claims



Process gas of high temperature and under high pressure

from naphtha reformers or the like is used in a heat-exchanging steam boiler for generating steam for the use in the reforming process itself and for other purposes such as in steam turbines whereby the hot gas is cooled at the same time.

3,577,959

SATURATED STEAM SUPPLY SYSTEM FOR A STEAM COOLED FAST BREEDER REACTOR


Robert Owen Barratt, Parsippany, and John Polcer, Florham Park, N.J., assignors to Foster Wheeler Corporation, Livingston, N.J.

Filed Aug. 5, 1968, Ser. No. 750,185

Int. Cl. F23b 1/08

U.S. Cl. 122-31

16 Claims



A saturated steam supply system for a steam cooled fast breeder reactor power plant having mechanical spray desuperheaters for the first and second stage of desuperheating the reactor core superheated coolant steam and a bubble-through steam washing and final desuperheater contact boiler. The contact boiler having a vertically extending cylindrical vessel with a steam inlet at its lower level for receiving the two-stage desuperheated steam and directing it through a plurality of vertical concentric tube manifolds of ascending reduced cylindrical sizes which distribute the steam in bubble trays has bubble caps. The vessel also has a feed water inlet at its upper level for feed water which cascades from bubble tray to bubble tray for steam washing and final desuperheating of the steam. The steam is directed through mechanical separators and dryers and then leaves the contact boiler at the upper level of the vessel to be used as saturated steam coolant for the fast breeder reactor.

3,577,960

ROTARY ENGINE

John Wiley, Seattle, Wash., assignor to Skrob, Inc., Seattle, Wash.

Continuation of application Ser. No. 773,562, Nov. 5, 1968, now abandoned. This application Apr. 20, 1970, Ser. No. 302,286


Int. Cl. F02b 55/00

U.S. Cl. 123-8.09

7 Claims

A rotary internal combustion engine of the type having a central combustion rotor containing peripheral combustion chambers, a planetary piston means having at least one piston revolvable around the combustion rotor in an annular piston chamber, and at least one cutoff rotor cooperable with the piston and combustion rotor to provide compression and expansion zones in the annular piston chamber is provided

with a through power output shaft, internal liquid cooling r.p.m. for all conditions of engine temperature and the and a pressurized air accumulation chamber, and additional number of actuated engine driven accessories. The system



combustion chambers designed to enhance engine stability, fuel injection and efficiency.

also opens the throttle blade slightly during engine deceleration to improve exhaust emissions.

3,577,961

LIQUID-COOLED SUPERCHARGED INTERNAL COMBUSTION ENGINE

Herbert Deutschmann, Stuttgart-Bad Cannstatt, and Ulrich Conrad, Ludwigsburg-Ossweil, Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart-Unterturkheim, Germany


Filed Mar. 14, 1968, Ser. No. 713,177

Claims priority, application Germany, Mar. 17, 1967, D525581a

Int. Cl. F02b 29/04; F01p 1/06; F16l 27/12

U.S. Cl. 123-52

15 Claims



A liquid-cooled super-charged internal combustion engine in which the line for the compressed combustion air and the line for the cooling liquid are connected, prior to entry into the engine, to an elbow-housing that has two channels with a common separating wall for the heat-exchange between cooling liquid and air.

3,577,962

THROTTLE BLADE CONTROL SYSTEM FOR MINIMIZING VARIATIONS IN IDLING SPEED

William K. Ojala, Dearborn Heights, Mich., assignor to Ford Motor Company, Dearborn, Mich.


Filed Oct. 20, 1969, Ser. No. 867,474

Int. Cl. F02d 11/08

U.S. Cl. 123-103

12 Claims

A cam having an effectively V-shaped cam surface is positioned by engine intake manifold pressure modulated according to engine speed above a predetermined value to control the idling position of the carburetor throttle blade. Engine idling speed resulting from the system is constant within 60



3,577,963

CONTROL FOR INTERNAL COMBUSTION ENGINES

Rudolf Bechmann, Wolfsburg, Germany, assignor to Volkswagenwerk Aktiengesellschaft, Wolfsburg, Germany


Filed May 17, 1968, Ser. No. 730,053

Claims priority, application Germany, May 27, 1967, P 15 76 689.9

Int. Cl. F02b 5/00

U.S. Cl. 123-117.1

1 Claim



A distributor for internal combustion engines having a centrifugally operated and a vacuum operated spark timing control with a switch in the primary circuit of an ignition coil operated by a throttle valve and the switch connected to a circuit breaker system controlled by centrifugal operation and a further circuit breaker system connected and influenced by a vacuum operated control.

3,577,964

CONTROL APPARATUS

Jeffrey M. Lazar, Rosemount, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Apr. 17, 1968, Ser. No. 721,994


Int. Cl. F02m 17/04

U.S. Cl. 123-119

8 Claims

A fluidic fuel control system wherein mass fuel flow into a

mixing chamber is controlled in response to volumetric flow of idling fuel to the engine for a time period sufficient to stop engine dieseling. An electrical solenoid valve connected to



rate, temperature and pressure of air entering the chamber.

3,577,965

FUEL ATOMIZATION SYSTEM HAVING A COMPRESSOR DRIVE MEANS


Jack G. Sundberg, Meriden, Conn., assignor to Chandler Evans Inc., West Hartford, Conn.

Filed Aug. 8, 1969, Ser. No. 848,557

Int. Cl. F02p 5/04

U.S. Cl. 123-119

3 Claims



A boost compressor for aiding the atomization of fuel supplied through a nozzle to the combustor of a variable speed power source is provided with a pair of gears fixed for independent coaxial rotation about a driven member slideably connected to the boost compressor. Each of the gears is driven at a different rotational speed by a gear train directly connected to said variable speed power source. A separate clutch independently engages and disengages each of said gears and said driven member in response to axial movement of said driven member caused by pressurized fluid directed to a piston connected to said driven member by a speed responsive fluid transfer switch.

3,577,966

ENGINE ANTIDIESELING DEVICE

Wilford R. Collingwood, Dearborn; William M. Hutchison, Allen Park, and Frank E. Mangas, Southfield, Mich., assignors to Ford Motor Company, Dearborn, Mich.


Filed Dec. 12, 1969, Ser. No. 884,444

Int. Cl. F02m 7/06; F02d 31/00, 13/08

U.S. Cl. 123-124B

7 Claims

A container stores a small quantity of air and pumps the air into the idling system of a carburetor when the engine ignition system is turned off. The air reduces the supply of



the engine ignition system controls the injection of the air into the idling passage.

3,577,967

CONTROL DEVICE FOR FUEL INJECTION PUMPS

Heinrich Staudt, Markgroningen-Talhausen, Germany, assignor to Robert Bosch GmbH, Stuttgart, Germany


Filed June 9, 1969, Ser. No. 831,470

Claims priority, application Germany, July 13, 1968, P 17 51 701.0

Int. Cl. F02d 31/00

U.S. Cl. 123-140

9 Claims



A fuel quantity control device for fuel injection pumps, wherein the maximum "open" position of a fuel quantity regulating member is limited by an abutment member movable by a piston which is displaceable by hydraulic pressure against a return spring. The said hydraulic pressure is admitted to the piston by a control shuttle disposed within said piston and displaceable with respect thereto by a sensor responsive to a variable.

3,577,968

CENTRIFUGAL R.P.M. REGULATOR FOR INTERNAL COMBUSTION ENGINES

Heinrich Staudt, Markgroningen-Talhausen; Eberhard Hoffmann, Kirchberg/Murr, Neuhof, and Rolf Muller, Stuttgart-Zuffenhausen, Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

Filed Oct. 1, 1969, Ser. No. 862,877

Claims priority, application Germany, Oct. 17, 1968, P 18 03 564.8


Int. Cl. F02d 1/04, 1/06

U.S. Cl. 123-140(R)

8 Claims

In a centrifugal r.p.m. regulator for internal combustion engines, the governor sleeve is connected to a fuel quantity

control member through a linkage assembly that includes an intermediate lever coupled to a manually operable lever to arbitrarily adjust said fuel quantity control member. The r.p.m. regulator includes a spring-loaded support arm against which the governor sleeve is adapted to abut after traveling a



predetermined distance under the force exerted by the centrifugal weights as the engine r.p.m. increases. Beyond a predetermined r.p.m. the last-named force overcomes the force of the support lever spring thus permitting the governor sleeve to be further displaced, shifting thereby said control member to lessen the injected fuel quantities.

3,577,969

VARIABLE GOVERNOR LIMITING MECHANISM


Stanley J. Kranc, Morton, and Ziedonis I. Krauja, East Peoria, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed June 23, 1969, Ser. No. 835,413

Int. Cl. F02d 1/04, 1/06; F02b 41/10

U.S. Cl. 123-140

3 Claims



A variable limiting mechanism in combination with an engine governor having a movable control rod for establishing an optimum rate of fuel flow, the limiting mechanism being effective to vary the optimum governor setting according to the amount of pressure available within the air inlet manifold for the engine. The limiting mechanism includes a diaphragm member arranged for movement within a housing and defining a first chamber in communication with the air inlet manifold and a second hermetically sealed chamber. A link is secured for movement with the diaphragm member and includes means for limiting motion of the control rod in one direction.

ERRATUM

For Class 123-140 see:
Patent No. 3,577,978

3,577,970

INTERNAL COMBUSTION ENGINE IGNITION SYSTEMS

Maurice King, and Trevor Leslie Barber, Maulden, England, assignors to General Motors Corporation, Detroit, Mich.


Filed Sept. 22, 1969, Ser. No. 859,648

Claims priority, application Great Britain, Sept. 27, 1968, 45,922/68

Int. Cl. F02p 1/00

U.S. Cl. 123-146.5

3 Claims



An ignition distributor is mounted on the front end of an overhead camshaft, the latter carrying a drive gear member which is recessed to house the centrifugal time control mechanism of the distributor and also having secured thereto a carrier member in which is journaled the housing of the distributor, the main shaft of which has a coaxial driving connection with the gear member and camshaft, and the housing being secured against rotation about the camshaft axis by a steady plate.

3,577,971

CONTACTLESS AND DISTRIBUTORLESS IGNITION SYSTEM


David T. Cavil, Menomonee Falls, Wis., assignor to Outboard Marine Corporation, Waukegan, Ill.

Filed Nov. 18, 1968, Ser. No. 776,379

Int. Cl. F02p 3/02


U.S. Cl. 123-148

13 Claims




Disclosed herein is a contactless and distributorless capacitor discharge ignition circuit which is designed for an internal combustion engine and which employs a rotary pulse generator with a rotor which can be connected directly to the engine crankshaft for rotation therewith and which includes two circumferentially aligned magnet pole pieces in the form of circular ring sectors having a total angular span of slightly less than 360°. The ends of the pole pieces are spaced by narrow high reluctance gaps. The rotor induces one positive and one negative pulse in an adjacent trigger coil for each revolution to alternately make conducting two semiconductor switches to discharge a capacitor and create sequential ignition pulses in each of two ignition coils to fire spark plugs connected to the ignition coils.

3,577,972
ADJUSTABLE VALVE STEM OIL SEAL FOR INTERNAL COMBUSTION ENGINES
 Forest J. Moray, 1513 Brooks Ave., Renton, Wash.
 Filed July 6, 1970, Ser. No. 52,175
 Int. Cl. F01I 3/00; F16k 41/02
 U.S. Cl. 123—188P 15 Claims




The disclosed valve stem seal in the head of an internal combustion engine comprises a packing around a valve stem with a packing gland thereon. The latter comprises a sleeve screwed in the head and slideable around the valve stem with gripping means on the upper end of the packing gland. Various gripping means include several different types of circular plates fitting around the packing gland and keyed thereto. The several plates have on their periphery either recesses, straight radial projections, or arcuate projections for the rotation thereof. Also one packing gland has radial projections formed around the upper surface thereof for being rotated for adjustment and another packing gland is keyed to the valve stem and a gripping surface formed on the top of the valve stem for being rotated. All gripping means permit rotation of the packing gland for adjusting the pressure on the packing as the latter wears with friction and without requiring the removal of the valve spring, resulting in a great saving in time and expense. This provides greater inducement for maintaining the valve seals tight and leak proof for the elimination of the smog problem, carbon monoxide, engine sludge, and excess oil usage.

3,577,973
OVEN DOOR WINDOW UNIT
 Joseph W. Katona, Walled Lake, Mich., assignor to Mills Products, Inc., Farmington, Mich.
 Filed Feb. 25, 1970, Ser. No. 14,107
 Int. Cl. F23m 7/00
 U.S. Cl. 126—200 4 Claims




Window unit for an oven door in which a one-piece spacing and clamping member is disposed between a pair of glass panels to maintain the panels in sealed, spaced-apart relation, the spacing and clamping member having integral flanges extending across the peripheral edges of the panels with portions of the flanges crimped over the outer edges of the panels to clamp the latter to the spacer. Molding strips are clamped between the glass and the crimped portions of the flanges and are engaged by flanges on the oven door to locate the unit within the door opening.

3,577,974
SELF-CONTAINED HANDLE HEATER
 Alvin M. Boldt, 820 Lariat Drive, Eugene, Oreg.
 Filed June 27, 1969, Ser. No. 837,276
 Int. Cl. A61f 7/06; F23q 1/02
 U.S. Cl. 126—208 6 Claims




A handle heater fueled with liquefied petroleum gas contained in a cylinder secured in or on the handle with the flow of gas controlled by a hand-actuated valve. Means are provided for lighting the flame with a flint-type igniter. Accidental flow of fluid from the cylinder is prevented by the path of the conduit extending from the cylinder to the burner. Means extending through the handle provides a tortuous path for the products of combustion to evenly heat the handle. The handles are disclosed as fishing pole handles and golf cart handles.

3,577,975
SNOW MELTER
 John F. Farsbetter, 2215 7th Ave., Rockford, Ill.
 Filed May 2, 1969, Ser. No. 821,388
 Int. Cl. E01h 5/10; F24h 1/00
 U.S. Cl. 126—343.5 7 Claims




A snow melting container having as its bottom a rectangular steam jacket and as its sides vertically extending steam jackets. The side steam jackets are L-shaped and are mounted on the bottom jacket to form one end wall and two sidewalls leaving the other end of the container open. To increase the heating area of the bottom steam jacket, a number of vertically extending holes are formed through the jacket, and a baffle plate is suspended beneath the bottom jacket to catch any snow which might fall through the holes and to hold the snow until the latter melts. To divide the container into two compartments, a steam jacket is placed parallel with and midway between the portions of the L-shaped jackets forming the sides. The container is supported between the sides of a large tank and is located a predetermined distance above the bottom of the tank. A steam boiler generates steam which is piped to all the jackets under pressure and, through a valving system, the steam in the jackets is maintained at predetermined pressures.

3,577,976
HEATED ASPHALT STORAGE UNIT
 Anton H. Heller, Levittown, N.Y., assignor to Poweray Infrared Corporation, Farmingdale, N.Y.
 Filed July 23, 1969, Ser. No. 844,090
 Int. Cl. E01c 19/45
 U.S. Cl. 126—343.5A 4 Claims




A unit for storing and maintaining asphalt at an elevated temperature as is necessary to facilitate making road repairs with this material, even in cold weather. Instead of applying heat insulation to the walls defining the asphalt storage compartment in an attempt to minimize heat loss therethrough, the storage compartment is enveloped within a body of heated air flowing at a controlled rate and the outer wall bounding the passage for this convection flowing heated air is insulated against heat loss. Thus, what would be an impractical insulated wall construction, both from the standpoint of the thickness and cost, in order to effectively minimize heat loss from a stationary heated body, such as the stored asphalt, is rendered well within practical requirements when it is applied and used for the continuously moving body of heated air. The enveloping heated air results in an optimum heat gradient about the heated asphalt and thus minimizes heat loss therefrom.

3,577,977
CARDIOVASCULAR CONDITIONING DEVICE AND PORTABLE RESPIRATOR
 Frederick R. Ritzinger, Jr., Williams, Ariz.; Henry B. Whitmore, San Antonio; Paul M. Stevens, Houston; Gerald Gardner, Alvin; Leonard Harris, and Arnott A. Moore, San Antonio, Tex.
 Filed Nov. 13, 1968, Ser. No. 775,406
 Int. Cl. A61b 19/00
 U.S. Cl. 128—1 1 Claim




A positive pressure vest and helmet assembly is pressurized by introducing gases thereto to produce pooling of blood in the subject's extremities causing the vascular muscles to exercise in order to compensate for conditions resulting from body changes which occur under zero gravity conditions.

3,577,978
A REGULATOR DEVICE FOR A VARIABLE RATE OF FLOW FOR A FUEL INJECTION PUMP FOR AN INTERNAL COMBUSTION ENGINE
 Giampaolo Garcea, Milan, Italy, assignor to Alfa Romeo S.p.A., Milan, Italy
 Filed Apr. 1, 1969, Ser. No. 811,789
 Claims priority, application Italy, Apr. 6, 1968, 14918A/68
 Int. Cl. F02d 1/04
 U.S. Cl. 123—140 1 Claim



Regulator unit for a gasoline injection pump, which provides the automatic control of the idle running speed when the internal combustion engine has not reached its working temperature, comprising a thermostatic device which automatically moves a catch forming the limiting stop, which in turn controls the angle of opening of the throttle (or throttles).

3,577,979
DISPOSABLE SURGICAL SKIN PUNCH
 Harry van der Gaast, 289 N. Hibiscus Drive, Miami Beach, Fla.
 Filed Feb. 6, 1968, Ser. No. 703,286
 Int. Cl. A61b 5/10
 U.S. Cl. 128—2 6 Claims



A disposable skin biopsy punch manufactured by forming a piece of sheet metal into a tubular member having a handle end and a cutting end. The cutting end terminates into an undulating cutting edge and includes means for retaining the skin plug within it and preferably having graduations or circumferential grooves for indicating the depth of cut or penetration. The skin punch is further provided with an axially extending scoop to allow observation of the cutting operation and may be produced with various size diameter cutting ends.

the diver, and a gas propulsion mechanism is disposed between the two canisters. This results in sucking atmosphere through one canister and pushing it through the other, which reduces the channelling of gas in the carbon dioxide absorber chemical. Also it isolates the sound of the gas moving mechanism so that very little noise reaches the diver's helmet, making it easier to use the diver's microphone and earphones. The carbon dioxide absorber is prepackaged in removable cartridges to improve the quality of the packing of the absorbing chemical and to make removal and replacement of the chemical quicker and easier.

3,577,989


DISPOSABLE PLASTIC, ELIMINATION-TRAPPING BAG FOR INCONTINENT PATIENTS

Jean O. Anderson, 169 S. Catalina St., Los Angeles, Calif.
Filed Oct. 31, 1968, Ser. No. 772,189

Int. Cl. A61f 5/44

U.S. Cl. 128—283

5 Claims



A disposable plastic elimination-trapping bag for incontinent patients or the like, including a sack having an open-top portion, and a thin resilient annular oval-shaped flange secured to the sack around the open-top portion to extend outwardly therefrom with the sack extending downwardly from the flange. The flange and the sack are sized to be attached to and positioned below the patient in the vicinity of the anus or in the vicinity of the anus extending to the vicinity of the urinary duct. The flange is shaped to conform to the contour of the patient. The sack may include a forward and a rearward edge one of which extends below the flange a greater distance than the other. The sack may be attached to the flange at acute angles to the axes of the flange.

3,577,990

URINARY APPLIANCE


Henry E. Borgerson, and Lewis K. Borgerson, 1926 Cambridge Ave., Flint, Mich. 48053

Filed Mar. 13, 1968, Ser. No. 712,669

Int. Cl. A61f 5/44

U.S. Cl. 128—295

8 Claims



A urine-holding appliance for use by males comprising an elongate receptacle with a flange near one end which may be attached to the wearer's clothing, and a forwardly extending, elastic penis-fitting tube on the receptacle, having stops preventing undue telescoping of the tube into the receptacle.

3,577,991 SEWING TISSUE INSTRUMENTS OR THE LIKE

Guilbert Roland Wilkinson, 10 Arran Road, Hamilton, New Zealand


Filed Feb. 10, 1969, Ser. No. 797,971

Claims priority, application New Zealand, Nov. 12, 1968, 154,454

Int. Cl. A61b 17/04; B25b 7/06

U.S. Cl. 128—340

1 Claim



A forceps or like instrument having a covering shield attached to each member or leg at its pivoted end so as to cover any opening between engaging surfaces or projection at or about where each member or leg pivots, so that thread or the like employed with the forceps will be prevented from dropping into an opening between the surfaces or about the projections on the forceps.

3,577,992

VALVE FOR USE WITH A CONDUIT HAVING A LUMEN


Jack D. Merry, Minnetonka, Minn., and Fritz Deuschle, St. Louis, Mo., said Merry assignor to Brunswick Corporation

Filed Aug. 31, 1967, Ser. No. 664,716

Int. Cl. A61m 25/00

U.S. Cl. 128—349

7 Claims



A valve adapter for use with a tubular conduit, such as an inflation-type catheter, having a lumen in the wall thereof. The adapter is arranged to receive the tapered end of a fluid flow duct, such as a hypodermic needle for conducting pumped air through the inflation lumen. The catheter is provided at its inner end with a balloon structure which is enlarged by the air pumped through the lumen to retain the catheter in a body cavity.

3,577,993

HOSE RETAINING PANTY GARMENT

Gerald W. Gluckin, Rye, and William Kurland, Sands Point, N.Y., assignors to William Gluckin & Co., Inc., New York, N.Y.

Filed Feb. 10, 1969, Ser. No. 798,099


Int. Cl. A41c 1/08

U.S. Cl. 128—535

21 Claims

A hose-retaining panty garment comprising a panty with leg extensions having, at least at the lower extremities thereof, longitudinally and circumferentially yieldable portions, a first circumferential band of circumferentially yieldable material joined in foldable edge to edge relation to each yieldable portion, a second band of circumferentially yieldable material joined in foldable edge to edge relation to each of said first bands, said bands being of essentially the same

width, and said second band being adapted to be disposed in an upwardly folded juxtaposed position within said first band with a stocking edge extending upwardly between said assemblage and the leg of a wearer and downwardly between the juxtaposed bands, at least two of the four surfaces provided



by the juxtaposed bands and interposed stocking edge carrying a circumferential deposit of resilient friction material, and at least the second named inwardly disposed of said circumferential bands having means for stiffening the same in its transverse dimension without impairing its circumferential yieldability.

3,577,994

METHOD FOR PRODUCING SMOKING PRODUCT OF OXIDIZED CELLULOSIC MATERIAL


Howard F. Keller, Jr., Los Angeles, and Geoffrey R. Ward, Beverly Hills, Calif., assignors to Sutton Research Corporation, Los Angeles, Calif.

Filed Nov. 7, 1968, Ser. No. 774,064

Int. Cl. A24b 15/00; A24d 1/18

U.S. Cl. 131—2

13 Claims



The method for rapidly and uniformly effecting selective oxidation of cellulosic materials used in the preparation of a smokable product embodying the sequence of steps of soaking the cellulosic material with liquid nitrogen dioxide and then exposing the cellulosic material to hot gaseous nitrogen dioxide for oxidation reaction and wherein the liquid nitrogen dioxide may contain up to 8 percent by weight water.

3,577,995

FILTER

Jackie L. White, Pfafftown, N.C., assignor to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.

Filed Mar. 31, 1970, Ser. No. 24,081


Int. Cl. A24d 1/04; A24f 1/08, 1/16

U.S. Cl. 131—10.5

10 Claims

A tobacco smoke filter element comprising a solid smoke barrier having a smoke passageway extending between a forward end wall and a sidewall wherein the sidewall is covered with a thin smoke impermeable membrane provided with a plurality of orifices so that the smoke passing through the

passageway must escape from the orifices. The several orifices direct the smoke radially from the membrane against an



impingement surface which may take the form of a smoke impervious sheet material supported by the barrier plug.

3,577,996

TOBACCO SMOKE FILTER


Joseph H. Sherrill, Winston-Salem, N.C., assignor to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.

Filed June 30, 1969, Ser. No. 837,669

Int. Cl. A24d 1/04; A24f 1/08, 1/16

U.S. Cl. 131—10.5

10 Claims



A filter is provided which is adapted to the affixed to one end of a tobacco rod. The filter is formed of three laminae defining a sleeve unit which is in sealing encompassing relation with a smoke barrier piece. The outer lamina is of smoke impervious thin sheet material, the intermediate lamina is of thin sheet material with a plurality of longitudinally extending elongated slots formed therein, and the inner lamina is of thin sheet material provided with a plurality of perforations arranged in sleeve-encircling relation and in registration with the slots of the intermediate lamina. As smoke is drawn through the filter, it is caused to pass through the perforations at a high velocity whereupon it impinges against an obstructing surface disposed in close proximity to the perforations.

3,577,997

TOBACCO TREATMENT WITH CITRIC ACID AND DEUTERIUM OXIDE

Max August Helmut Bindig, Munich, Germany, assignor to American Chemosol Corporation

Continuation-in-part of application Ser. No. 662,299, Aug.

22, 1967, now abandoned, Continuation-in-part of

application Ser. No. 533,631, Mar. 11, 1966, now abandoned.

This application Mar. 20, 1969, Ser. No. 809,004

Int. Cl. A24b 15/02

U.S. Cl. 131—17

12 Claims

Treatment of tobacco to render smoking of the same safer. Reduction of the quantity of various undesirable constituents, particularly benzo(a)pyrene, in smoke resulting from the pyrolysis of such tobaccos in cigarettes and the like is shown as well as biological studies indicating such smoke condensates to be physiologically less dangerous. A mixture of citric acid and deuterium oxide is utilized to effect the foregoing modification of the combustion products of tobacco treated therewith.


3,577,998 IMPACT METHOD

Jesse R. Pinkham, Winston-Salem, N.C., assignor to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.
Continuation-in-part of application Ser. No. 529,424, Feb. 23, 1965, now abandoned, Division of Ser. No. 615,792, Feb. 13, 1967, abandoned. Filed June 23, 1969, Ser. No. 851,119

U.S. Cl. 131-96

Int. Cl. A24c 5/36

9 Claims U.S. Cl. 132-79R



A method of striking an article, particularly a wrapper enclosed product such as a cigarette, by striking the article and achieving a clear impact without cutting the wrapper to create a blast of air upon impact so as to force the product out of the wrapper by an air pump action.

3,577,999


IMPACT APPARATUS AND METHOD

Jesse R. Pinkham, Winston-Salem, N.C., assignor to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.
Continuation of application Ser. No. 615,792, Feb. 13, 1967, now abandoned, which is a continuation-in-part of application Ser. No. 529,424, Feb. 23, 1965, now abandoned. This application July 14, 1969, Ser. No. 852,144

U.S. Cl. 131-96

Int. Cl. A24c 5/36

4 Claims



Apparatus for reclaiming tobacco from cigarette filters and wrappers includes a vertical casing with a top inlet and a bottom outlet. Vertically spaced and radially extending rods are secured to the inner periphery of the casing. A rotor with vertically spaced and radially extending rods secured thereto is rotatably mounted within the casing. The feed is struck as it passes downwardly between the intermeshing stationary and rotating rods and tobacco is disassociated from the filters and wrappers for subsequent separation by pneumatic or screen type separators.


3,578,000 COMBINATION MANICURING AND HAIR-DRYING APPLIANCE

Stanley V. Horecky, Oak Park, Ill., and Thomas Howe Hayes, Indianapolis, Ind., assignors to Sunbeam Corporation, Chicago, Ill.

Filed Jan. 29, 1968, Ser. No. 701,347

Int. Cl. A45d 29/18

14 Claims



A compact, portable hair dryer and manicure appliance having a housing for a motor-driven blower unit with compartments provided for storing an air delivery hose, a collapsible hair-drying hat, and a manicure attachment including a flexible drive shaft and nail-treating implements. The housing is formed by three molded plastic parts which form the housing with its storage compartments and a closure for two of the compartments.

3,578,001

AUTOMATIC ELECTRO-PNEUMATIC CONTROL APPARATUS FOR CAR WASHING SYSTEM


Thomas J. Attaway, 50 S.E. 14th St., Dania, Fla.

Filed Aug. 29, 1969, Ser. No. 854,064

Int. Cl. B60s 3/04

U.S. Cl. 134-45

10 Claims



Apparatus for automatic control of a vehicle washing system includes a flexible pad wider than the bearing surface of a vehicle wheel. The pad containing gas or liquid is connected via a hose to a pneumatically or hydraulically operated timer switch. The pad is provided with means such as suction and or a weight to prevent displacement when a vehicle rolls over it. The timer switch automatically opens a circuit keeping an electrically controlled valve closed to stop discharge of a detergent solution on the vehicle.

3,578,002 APPARATUS AND METHOD FOR PROCESSING WORKPIECES


Henry A. Rowan, Watchung, and Donald H. Shiffner, Branchburg, N.J., assignors to Economics Laboratory, Inc., St. Paul, Minn.

Filed Sept. 25, 1969, Ser. No. 860,957

Int. Cl. B08b 3/06

U.S. Cl. 134-25R

23 Claims



Apparatus for processing (e.g., cleaning, degreasing) workpieces which are supplied to the apparatus in containers or tote boxes includes a frame for removably engaging the tote box and means for continuously rotating the frame so that the workpieces are progressively and gently dumped into a perforated processing chamber and subsequently returned to the tote box. The processing chamber comprises a first inclined surface for receiving and spreading the dumped workpieces into a less confined area upon the partial rotation of the frame (whereupon the processing of parts may be commenced) and a second inclined surface for returning the processed workpieces to the tote box upon the further rotation of the frame. Methods for such processing, as well as carousel and conveyor systems incorporating such apparatus, are also disclosed.

3,578,003

PORTABLE PLATFORM AND SHELTER


Lucille G. Everett, 229 Pine, Dumas, Tex.

Filed Apr. 1, 1969, Ser. No. 812,151

Int. Cl. A45f 1/16, 1/12

U.S. Cl. 135-4

3 Claims



A portable platform and a compact tentlike shelter providing a safe, cozy, comforting and snug hiding place for a child. The platform is characterized by a low-lying rigid but lightweight frame suspending a canvas floor. Both ends of the tent embody readily openable and closable flaps having suitable flap-tying tapes which permit the child to crawl through, back and forth at will. The applicable and removable tent material is washable, is draped over a rigid shaped-imparting framework and the lower lengthwise edges are preferably provided with anchorable holddown straps. Thus and amply ventilated, this unique shelter permits concealment, prevents stuffiness and permits playful freedom for the child.

3,578,004


METHOD AND DEVICE FOR FLOW CONTROL OF LIQUOR BY VORTEX MOVEMENT OF THE LIQUOR
Le Roy A. Bromley, Moraga, and Stanley M. Read, Occidental, Calif., assignors to The Regents of the University of California

Continuation-in-part of application Ser. No. 534,012, Mar. 14, 1966, now abandoned. This application June 12, 1969, Ser. No. 832,710

Int. Cl. B01d 1/22

U.S. Cl. 137-1

18 Claims



A method of controlling the flow of volatile liquor from a container in a manner to (1) maximize the ratio of liquor flow relative to vapor flow, (2) distribute the flow of liquor evenly to a series of parallel disposed tubes although the inlets thereto are not in the same horizontal plane, (3) distribute the flow evenly against the interior walls of the tubes, and (4) accelerate the flow along the interior walls of the tubes to increase heat exchange with the environment about the tubes. The controller for carrying out the method includes a tubular element having (1) a portion provided with an inlet in the upper part thereof for the flow of fluid thereto from the container, (2) a portion having a passage leading from the container downstream of the inlet and disposed for causing vortical movement to be imparted to the liquor entering the second mentioned portion through the passage, and (3) a throat downstream of the second mentioned portion.

3,578,005

WATER TREATMENT APPARATUS

Roland Jurion, Bobigny, and Andre Leblanche, Saint-Denis, France, assignors to Societe D'Etudes Chimiques pour L'Industrie et L'Agriculture, Paris, France


Filed Mar. 1, 1968, Ser. No. 709,748

Claims priority, application France, Mar. 1, 1967, 96908

Int. Cl. G05d 11/00

U.S. Cl. 137-3

11 Claims



A water treatment apparatus having a fluid mixing device for injecting an aqueous solution of a treating fluid into the

water to be treated. Storage vessels for the treating fluid communicate with a dilution vessel for dilution of the treating fluid. Dilution water is transmitted to the device through valved lines communicating in parallel with the storage vessel and with the dilution vessel. A control is provided to alternately direct dilution water through the storage vessel to the dilution vessel or directly to the dilution vessel as determined by the chemical makeup of the water to be treated.

3,578,006

ACCELERATION AND PRESSURE RESPONSIVE FLUID VALVE


Andrew J. Betz, Jr., Adelphi, Md.

Filed Apr. 25, 1969, Ser. No. 819,286

Int. Cl. F16k 17/36

U.S. Cl. 137-38

10 Claims



An acceleration and pressure responsive fluid valve for a conduit having a fluid blocking body held in place in the conduit by ball detents. The balls are held in locking position by a spring loaded piston which under high fluid pressure, moves against the spring out of ball locking position to allow the balls to pop into the body out of locking position which frees the body to be pushed out of blocking position in the conduit. The fluid which operates the piston enters the body through fluid spiracles which are closed during acceleration by an inertia operated valve, but opened again by a biasing spring when the acceleration decreases below a given value, thereby permitting fluid to flow through the spiracles to operate the piston and unlock the valve.

3,578,007

DELAYED GOVERNOR CUTOFF VALVE


William W. Blake, Wyoming, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Filed Dec. 10, 1969, Ser. No. 883,839

Int. Cl. G05d 13/66

U.S. Cl. 137-51

3 Claims



A delayed governor cutoff valve system is provided in a transmission control system for temporarily blocking hydraulic

pressure signals which are normally transmitted from a governor to a group of automatic transmission shift selector valves. By blocking off the governor from the automatic shift selector valves the governor is prevented from sending erroneous pressure signals to the selector valves during certain phases of the transmission shifting cycle.

3,578,008

FAST OPENING PLATE VALVE SHOCK TUBE SYSTEM


Robert O. Clark, Albuquerque, N. Mex.

Filed Jan. 24, 1969, Ser. No. 793,760

Int. Cl. F16k 31/12; G01n 3/02

U.S. Cl. 137-68

1 Claim



A thin aluminum plate is positioned over one end of a shock tube to seal the passage between high and low pressure regions. Upon sudden reduction of the pressure on one side of the plate, a low pressure rarefaction passes toward the plate causing the plate to move rapidly away from the shock tube opening and allow high pressure gas to enter the tube and form a chock wave therein.

3,578,009

DISTRIBUTED CONTROL FLUERIC AMPLIFIER


Chris E. Spyropoulos, Washington, D.C.

Filed Oct. 24, 1968, Ser. No. 770,184

Int. Cl. F15c 1/08, 1/14

U.S. Cl. 137-81.5

4 Claims



A flueric amplifier with two control ports for each control channel. Each control channel is split to operate both ports. The control flow is split and applied to the power jet through the two separate control ports. This separate application is called distributed control and results in greater flow recovery and pressure recovery as well as improved switching time. One of the control ports comprises an entrainment control port for introducing positive pressure control fluid to the attachment bubble existing along the attachment wall, and the other one of the control ports constitutes a momentum exchange control port for creating a momentum impact force on the power stream.

3,578,010

FLUERIC VELOCITY DISCRIMINATOR


Carl J. Campagnuolo, and Fernando Villarroel, Chevy Chase, Md.

Filed Dec. 19, 1968, Ser. No. 785,152

Int. Cl. F15c 1/04

U.S. Cl. 137-81.5

3 Claims



The discriminator includes a housing having an inlet passage and a pair of outlet passages opposite the inlet passage, the inlet passage having a reduced diameter passageway for creating a high velocity fluid stream. A pair of lateral passages communicate with the junction of the inlet and outlet passages and a bias passage communicates between the inlet passage and one of the lateral passages to create a low-pressure condition on one side of the fluid stream and thereby direct it through one of the outlet passages. A feedback passage communicates between the one outlet passage and the one lateral passage and deflects the fluid stream from the one outlet to the other outlet passage in response to a predetermined minimum pressure. A flow maintaining passage communicates with the other outlet passage and the other lateral passage to create a low-pressure condition on the other side of the fluid stream and thereby maintains fluid communication between the inlet and other outlet passages.

3,578,011


PYRO FLUIDIC RELAY

Allen B. Holmes, Rockville, Md., assignor to the United States of America as represented by the Secretary of the Army

Int. Cl. F15c 1/08, 4/00

U.S. Cl. 137-81.5

8 Claims



A pyro fluidic relay device which is capable of generating thermal energy at a predetermined time. A pure supersonic fluid amplifier is initially in an inactive mode of operation whereby the supply flow is discharged to atmosphere. At the predetermined time a control pressure is used to switch the fluid amplifier to an active mode of operation causing a resonator tube in an output channel thereof to generate thermal

energy. In one application, the thermal energy so generated may be applied to a primer for detonating an explosive.

3,578,012

FLUERIC DEVICE


Cheng-Kuo Weng, Fair Lawn, N.J., assignor to Singer-General Precision, Inc., Little Falls, N.J.

Filed Apr. 2, 1969, Ser. No. 812,730

Int. Cl. F15c 1/04

U.S. Cl. 137-81.5

4 Claims



A flueric device comprising a deflection chamber having at least two outlet receivers and a supply nozzle adapted to introduce supersonic fluid flow into said deflection chamber. Control means are provided to selectively deflect the fluid flow in the chamber between the two outlet receivers.

3,578,013

VORTICES, PARTICULARLY TO THEIR OUTLET
Guy Brochard, Asnieres, France, assignor to Societe Anonyme D.B.A.


Filed May 2, 1969, Ser. No. 821,312

Claims priority, application France, May 8, 1968, 150,983

Int. Cl. F15c 1/16, 3/06

U.S. Cl. 137-81.5

18 Claims



A fluid vortex includes: a cylindrical chamber; a first inlet for the main fluid into the chamber; a control inlet for the tangential introduction of a control fluid into the chamber in order to impart to the main fluid travelling inside the chamber a rotary motion; and an axial outlet for the fluid escaping from the chamber. According to the present invention, a body having substantially a revolution shape and without any rigid mechanical connection with the vortex is placed in the vortex outlet as a load therefor.

3,578,014

PRESSURE REGULATOR FOR PRESSURIZED-FLUID CIRCUITS

Jean Gachot, 179 Avenue de la Division Leclerc, Enghien, (Val d'Oise), France

Filed May 1, 1969, Ser. No. 821,006

Claims priority, application France, May 9, 1968, Nov. 28, 1968, 151,139; 175,674


Int. Cl. G05d 16/06

U.S. Cl. 137-115

9 Claims

Regulator for a pressurized-fluid circuit supplied by a pressure-elevating apparatus such as a compressor, said regulator

comprising a measuring chamber which communicates with the fluid circuit and is provided with a pressure-gauge element for measuring the pressure within said fluid circuit, and a regulating chamber which is connected to the pressure-elevating apparatus and has an orifice for the admission of the fluid in the direction of the measuring chamber, a low-pressure discharge orifice and means actuated by the pressure-gauge element in order to shut off the discharge orifice when the pressure of the reservoir is lower than a minimum value and to open said orifice when the pressure of the reservoir is higher than a maximum value. The admission orifice and discharge orifice are located in oppositely-facing relation



and the regulating chamber comprises a two-position obturator which is connected directly to the pressure-gauge element and selectively closes the admission orifice or the discharge orifice according as the pressure within the fluid circuit attains either the maximum or minimum value.


According to a preferred embodiment, the discharge orifice of the regulating chamber opens into a reaction chamber having an orifice which provides a communication with the atmosphere, means being additionally provided for producing a time lag between connection of said reaction chamber to the atmosphere and opening of the discharge orifice of the regulating chamber.

3,578,015 AUTOMATIC CHANGE-OVER REGULATOR FOR BOTTLED GAS SYSTEMS WITH TWO GAS CONTAINERS

Frede Reinholdt Andersen, Niverod, Denmark, assignor to Teknova A/S, Nivaa, Denmark
Continuation of application Ser. No. 560,502, June 27, 1966, now abandoned. This application June 3, 1969, Ser. No. 833,868
Int. Cl. G05d 11/00

U.S. Cl. 137-113

11 Claims




An automatic changeover regulator for selecting which of two gaseous fluid sources will supply a gas-consuming apparatus. The regulator has a casing with two inlets each of which has an associated valve controlled by a discharge fluid pressure responsive means and a switchover device including

manual means operable to select one source as the service source, the other source being in reserve, and which, in either position, is automatically operable by the valve controlling means to indicate whether gas is actually being admitted from the service or reserve source.

3,578,016
ANTISIPHON FLUID INLET MEANS
Gerald J. Kushner, Louisville, Ky., assignor to General Electric Company
Filed Dec. 26, 1968, Ser. No. 787,045
Int. Cl. F16l 55/06; E03c 1/10
U.S. Cl. 137-216

10 Claims




An antisiphon fluid inlet means is provided to minimize the possibility of reverse flow of washing liquid from an automatic washer into the water piping of the building in which the washer is installed. The means comprises a housing defining an arcuate chamber therein having a tangential inlet and a tangential outlet thereto, and a vent to the atmosphere formed centrally within the housing. A flow direction means, which, in one embodiment includes a cusp formed adjacent the outlet opening from the chamber, directs a substantial portion of the fluid circulating within the chamber to the outlet opening, and directs the remainder of the fluid into the chamber for continued circulation therein. The vent is positioned out of the path of fluid circulating within the chamber and is adapted to admit air from the exterior of the housing should a suction force be exerted on the inlet, and to drain to the exterior of the housing a sufficient amount of any fluid which may backflow through the outlet to prevent fluid discharge from the chamber back through the inlet and into the water supply connected thereto.

3,578,017 AUTOMATIC ACTUATION OF AIR CLEANER SELECTOR VALVE

Harry B. Rath, Allentown, Pa., assignor to Mack Trucks, Inc., Allentown, Pa.
Filed Nov. 26, 1968, Ser. No. 779,194
Int. Cl. F16k 31/46, 31/52
U.S. Cl. 137-344

10 Claims




A preferred embodiment of this invention comprises a cam rotatably carried by the drive shaft of a motor that operates

the windshield wipers of a vehicle. The cam carries one end of a cable, which is connected to an extension of an air cleaner selector valve that is normally held in a position allowing the passage of air from outside by a spring connected thereto. As the shaft oscillates, the cam is rotated and tensions the cable to move the selector valve to a position allowing the passage of air from under the hood. In order to hold the valve in this latter position, a lever operated by the motor engages a shoulder on the cam and holds it in place until the motor is turned off.

3,578,018
RATE OF PRESSURE RISE LIMITING VALVE
Leo H. Dillon, Columbus, Ohio, and William F. Weese, Lawndale, Calif., assignors to Abex Corporation, New York, N.Y.
Filed Apr. 18, 1969, Ser. No. 817,447
Int. Cl. F16k 17/10

U.S. Cl. 137-489

23 Claims




A valve for preventing pressures in a fluid line from exceeding a preset value by venting fluid to a reservoir whenever the rate of pressure increase in the line exceeds some predetermined value or rate of gain. The valve is operative to open and spill fluid to relieve the increasing pressure condition whenever it detects an excessive rate of pressure increase, irrespective of the pressure at which the increase is initiated.

3,578,019
RELIEF VALVE UNIT FOR HYDRAULIC PRESSURE
LINES
Marco Turolla, 213, Via Toscana, Bologna, Italy
Filed Dec. 24, 1968, Ser. No. 786,606
Claims priority, application Italy, Jan. 4, 1968, 6704A/68
Int. Cl. F16k 17/10

U.S. Cl. 137-491

5 Claims




A differential-piston relief valve provided with a shock and vibration-absorbing plunger and a spring-urged pilot vent valve for operating the relief valve are mounted in a single cylindrical hollow body in which the cylinders for the relief

valve and attached plunger and the housing for the vent valve are bored. The hollow body is closed at one end by a screw plug, acting also as vent valve spring-adjusting means, and with external screw threads for mounting the whole as a unit in a blind bore of a block forming a part of the hydraulic pressure line. The hollow body is provided with inlet- and outlet ports which come to be in front of corresponding ports opening within the blind bore of said block, thus completing the hydraulic circuit.

3,578,020
VALVE ASSEMBLY
Jerry E. Rochte, Seal Beach, and Larry S. McDavid, Fullerton, Calif., assignors to Beckman Instruments, Inc.
Filed Aug. 20, 1968, Ser. No. 754,012
Int. Cl. F16k 15/14
U.S. Cl. 137-512


3 Claims



A check-type valve assembly in which an annular channel is formed in a valve body. A port is formed in the inner surface of the channel and is closed by an elastic band which is positioned under tension in the channel so as to bear tightly against the inner surface thereof. The elastic band functions as a valve element for controlling the flow of fluid through passages communicating with said port and the annular channel.

3,578,021
FROST HEAVE-RESISTANT PUMP INLET ASSEMBLY
August Milo, 1015 Schliefer Drive, Hillside, N.J.
Filed Dec. 23, 1969, Ser. No. 887,524
Int. Cl. F16l 27/12
U.S. Cl. 137-515

3 Claims



A frost heave-resistant inlet assembly for a pump designed for pumping inflammable liquid, and disposable above the ground, and connectable to a tank outlet disposed underground, consists in a sleeve, the lower portion of which is connected in sealed sliding relation to the tank outlet. The sleeve is extendable over the tank outlet for a distance adequate to accommodate the tank outlet in the event of a

frost heave causing the outlet to rise above the ground. A coupling is connected over the upper portion of the sleeve in outside sealable relation, and it has an inwardly projecting circumferential lip having a bevel on its lower portion. A valve section, having a lower nipple portion and an upper portion, and having a seating means on its upper portion, has a valve mounted therein, the valve being seatable on the seating means when the pump is idle, and being in raised position when the pump is running. The nipple portion of this valve section has a circumferential groove and a broken ring is seated in the groove and projecting out of it so as to serve as locking means for the beveled edge of the coupling. A connecting means, such as a coupling, is mounted on the upper portion of the valve section to connect it in outside sealing relation with the pump inlet.

3,578,022

DIRECTIONAL CONTROL VALVE


George W. Jahrstorfer, Wapping, Conn., assignor to Chandler Evans, Inc., West Hartford, Conn.

Filed Dec. 8, 1969, Ser. No. 883,154

Int. Cl. F16k 11/02, 11/10

U.S. Cl. 137—596

6 Claims



A directional control valve has a supply pressure chamber in communication with a source of pressurized air and a vent pressure chamber in communication with the surrounding environment. Three ducts in respective communication with three ports, each interconnect the supply pressure chamber and the vent pressure chamber. Two rotors, each including two arcuate cuts, are fixedly secured to a rotatable shaft which extends between the chambers. Positioned within the ends of the ducts are spring-loaded carbon seals which are adapted to sealingly engage the inboard faces of the rotors. The cuts in the rotors are arranged so that the ports are pressurized and vented in a predetermined sequence as the shaft is rotated.

3,578,023

WALL-MOUNTED PIVOTABLE FLOW-DIRECTING ASSEMBLY

Joseph Diamond, Simsbury; Melvin Y. Gershman, West Hartford, Conn., and Fred A. Ravreby, Framingham, Mass., assignors to Coleco Industries, Inc., Hartford, Conn.

Filed Apr. 10, 1969, Ser. No. 815,034


Int. Cl. E04h 3/16

U.S. Cl. 137—592

9 Claims

An assembly adapted for mounting on a wall of a pool or the like for directing the flow of water thereinto includes a socket portion defining a generally spherical chamber and a generally spherical flow-directing member seated therein. The flow-directing member has an axial passageway and is pivotable in the chamber to position the passageway between the inlet and outlet openings of the chamber in a multiplicity

of angular attitudes to control the direction of flow. A resilient gasket in the chamber has a circular aperture therein



which is configured and dimensioned to snugly seat the flow-directing member to restrain movement thereof and form a seal therewith.

3,578,024

SUPPLY AND EXHAUST CONTROL VALVE


Jennings Paul Hill, 9861 Memphis Ave., Apt. 9A6, Cleveland, Ohio 44144

Filed Oct. 31, 1968, Ser. No. 776,850

Int. Cl. F16k 11/10

U.S. Cl. 137—627.5

10 Claims



A fluid control valve of the supply and exhaust type including a slidable valve cartridge having a valve face normally sealing access of fluid to a work port and having an interior passage providing communication from said work port to exhaust normally sealed by a valve face on a plunger slidably movable within said cartridge, said plunger being movable against spring resistance to open said communication to exhaust or to allow fluid flow to said work port and sealing means to prevent leakage.

3,578,025

FLUID-CONTROLLED, IN PARTICULAR HYDRAULICALLY OR PNEUMATICALLY CONTROLLABLE SLIDE VALVE ARRANGEMENT

Eduard Furrer, Zurich, Switzerland, assignor to Contraves AG, Zurich, Switzerland

Filed Dec. 18, 1968, Ser. No. 784,678

Claims priority, application Switzerland, Dec. 22, 1967,

18131/67

Int. Cl. F16k 11/07

U.S. Cl. 137—625.66

5 Claims

There is disclosed a fluid-controlled slide valve arrangement, in particular a pneumatically or hydraulically controlled slide valve arrangement, for alternately connecting an outflow conduit with a pressure conduit and return flow conduit of a fluid-operating system. This slide valve arrangement embodies a sleeve valve member displaceably mounted in a slide valve housing, such sleeve valve member incorporating at one end a piston extension of larger diameter. Fluid-

operated control means alternately apply a pneumatic or hydraulic overpressure to the end faces of the piston extension in order to displace the sleeve valve member. The pneumatic or hydraulic control overpressure is only maintained

3,578,027



SEALING PLUGS OR CLOSURES

William L. Zopfi, 593 Pleasant, Ferndale, Mich.
Filed July 30, 1969, Ser. No. 846,148

Int. Cl. F16l 55/10

U.S. Cl. 138—89

1 Claim



A molded rubberlike sealing plug or closure formed of a semihard rubberlike material for closing a pipe end or the like is formed with tapered ribs on its peripheral surface.

3,578,028

REINFORCED HOSE AND METHOD OF MAKING THE SAME

Robert E. Roberts, Wilton, Conn., assignor to Fred T. Roberts & Company, Wilton, Conn.

Filed July 16, 1969, Ser. No. 842,122

Int. Cl. F16l 11/08

U.S. Cl. 138—123

8 Claims

during a portion of the switching operation. Relief channel means provided at the slide valve arrangement communicate with the outside, whereby the control pressure drops during the latter part of the switching operation as soon as the relief channel means are freed by the enlarged piston extension.

3,578,026

JACKET FOR FLEXIBLE HOSE


Howard F. Meyer, Jr., Northville, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Feb. 24, 1969, Ser. No. 801,397


Int. Cl. F16l 11/12, 57/00

U.S. Cl. 138—110

8 Claims



A hose jacket of acetal resin and designed to bend a flexible hose approximately 90° is formed in two partial semitoroidal sections joined together at the outer radius by a flexible hinge portion of the resin. The sections have an annular cavity conforming approximately to the size and shape of the hose. Folding the sections around the hose and latching the arcuate edges together at each end and the middle bends the hose sharply without kinking or damaging the hose walls. Forces exerted on the jacket by the hose assist in maintaining the latch elements in engagement with each other.



A tubular flexible hose of elastomeric material and the method of making the same, said hose having a reinforcing layer of warp knit net fabric. It can have a helical spring wire under the fabric. The hose is highly resistant to bursting under internal pressure, and has substantially no axial extension and only slight radial stretch and can be readily manufactured.

3,578,029

PIPE


Roy H. Cullen; Charles H. Elliott; Jimmie R. Aker, and Harvey O. Mohr, Houston, Tex., assignors to Youngstown Sheet and Tube Company, Youngstown, Ohio

Continuation-in-part of application Ser. No. 648,039, June 22, 1967, now abandoned, and a continuation-in-part of 712,163, Mar. 11, 1968, now Patent No. 3,499,668. This application June 27, 1969, Ser. No. 837,245

Int. Cl. F16l 11/16

U.S. Cl. 138—133

13 Claims



This invention discloses a flexible pipe suitable for use as a drill string. The construction of the pipe is such that it will

withstand high internal and external pressures, will sustain a leg and the free leg of the gripper point. A spring operated substantial longitudinal load, and a substantial torque.


3,578,030

ABLATIVE AND INSULATIVE STRUCTURES

Donald M. Hatch, Harbor City, Calif., assignor to Hitco Division of Ser. No. 450,076, Apr. 27, 1965, Pat. No. 3,449,189.
Filed Sept. 27, 1967, Ser. No. 679,281
Int. Cl. F16I 9/14

U.S. Cl. 138-141

11 Claims



flap in the main leg holds a yarn against the free leg, and hence against the said edge.


3,578,032

LOOM HAVING A JACQUARD MECHANISM AND A WEFT CHANGING MECHANISM

Erwin Pfarrerwall, Winterthur, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland
Filed Sept. 11, 1968, Ser. No. 758,976
Claims priority, application Switzerland, Sept. 15, 1967, 12952/67
Int. Cl. D03d 47/24

U.S. Cl. 139-126

2 Claims



An ablatively structure in the form of a relatively thick-walled body of revolution is prepared by laying up, substantially side-by-side successive panels of high temperature resistant materials impregnated with a thermally curable resin within a female mold, disposing between certain panels removable aperture-defining plugs out of communication with the interior and exterior surface of the body, curing the resin and densifying the structure under radially outwardly exerted pressure and removing the plugs from the structure.

3,578,031

HOOK-SHAPED GRIPPER POINT

Heinz Maassen, Dulken, Germany, assignor to The Firm of Jean Gusken, Dulken, Rhineland, Germany
Filed Sept. 29, 1969, Ser. No. 861,558
Claims priority, application Germany, Sept. 27, 1968, P 17 85 467.0
Int. Cl. D03d 47/20

U.S. Cl. 139-122

3 Claims

A hook-shaped yarn take-up gripper point having a protuberance formed on a first side of the free leg of the hook, the end of the protuberance away from the tip of the gripper point forming a trailing edge which extends substantially perpendicular to a central plane passing through both the main

3,578,033

WOOD PULP AND CHIPPING CHAIN SAW APPARATUS

Gerald R. Wood, Cross City, Fla.
Filed Sept. 20, 1968, Ser. No. 761,165
Int. Cl. B27b 17/00


U.S. Cl. 143-32

5 Claims

A wood pulp and chipping apparatus for cutting and chipping logs into pulpwood comprising a frame with a forward conveyor means and a rear conveyor means disposed to receive logs from said forward conveyor means, and said conveyor means being disposed at an inclined angle with respect to a horizontal plane so as to feed logs carried thereby



to a chipping and pulping means comprising an endless chain drive with cutter and chipping teeth thereon, which teeth are disposed in directions so as to cover the top of the endless



chain and the opposite sides thereof, and with the chipping and cutting means disposed to receive the logs after they have been fed rearwardly by said rear conveyor means.


3,578,034

APPARATUS FOR AUTOMATICALLY WINDING CONCENTRIC DYNAMOELECTRIC MACHINE COILS

Robert J. Eminger, Fort Wayne, Ind., assignor to Fort Wayne Tool & Die, Inc., Fort Wayne, Ind.
Filed Mar. 27, 1969, Ser. No. 811,016
Int. Cl. B21f 3/00

U.S. Cl. 140-1

20 Claims



Apparatus for automatically winding a set of at least two concentric dynamoelectric machine coils upon a coil form having at least two progressively small steps. A flyer for winding wire on the coil form steps is rotatably supported by a block, and a two-speed electric motor is connected to rotate the flyer. A slide supports the block and flyer for longitudinal movement parallel with the axis of the flyer between forward and rear positions, and latches selectively retain the block and flyer at the forward and at least one intermediate position thereby to locate the flyer in winding relationship with each of the coil form steps. The slide with the block and flyer supported thereon is mounted for longitudinal movement thereby to traverse the flyer across the coil form steps. In one embodiment the slide is oscillated by the motor thereby to level-wind the wire on each of the coil form steps; and in another embodiment the slide is continuously moved from a forward to a rear position by a lead screw driven by the motor. A control circuit is provided which automatically actuates the motor to its low speed a predetermined number of turns in advance of completion of a given coil; and which upon completion of the coil actuates a latch to permit the block and flyer to move rearwardly by one incremental step when the flyer is in a predetermined rotational position with respect to the coil form, thereby to move the flyer into winding relationship with the next coil form step, and actuates the motor to its high speed to initiate

winding of the next coil. The motor is preferably a multiphase, two-speed, constant torque induction motor, thus providing very rapid acceleration and deceleration between its high and low speeds, and the latches are preferably electromagnetically actuated from a source of substantially ripple-free direct current, thus providing nearly instantaneous stepping of the flyer, to the end that a set of concentric coils may be automatically wound at high speed without stopping the flyer and with the connections between adjacent coils accurately located.


3,578,035

SUCCESSIVE WIRE LOOP TWISTER

Orval Parker, 3719 Seminole St., Houston, Tex.
Filed Feb. 25, 1969, Ser. No. 802,051
Int. Cl. B21f 3/00, 1/06, 7/00

U.S. Cl. 140-102.5

8 Claims



The disclosure is to a tool or device installable on a running length of wire at a distance from an end thereof and at the point installed adapted to be manipulated to twist the wire several times around itself leaving a bight or loop. The twister may then bend the running length of wire to extend substantially in initial direction; and then the tool device or twister can be deftly removed and reinstalled, further along upon the aforesaid running length, and a second series of twists made in the length, leaving a second loop, and on successively.


3,578,036

LATTICE FOR THE REINFORCEMENT OF TUBULAR CONCRETE ELEMENTS HAVING A SOCKET METHOD FOR PRODUCING SAID LATTICE AND THE PRODUCTS OBTAINED

Maurice Francois, Saint Dizier, France, assignor to Trefilun, Paris, France
Filed Mar. 18, 1969, Ser. No. 808,252
Claims priority, application France, Mar. 22, 1968, 144,908
Int. Cl. B21f 27/22

U.S. Cl. 140-107

1 Claim



Method for producing a reinforcement having a socket for a reinforced concrete tubular element having a socket. The method comprises forming a prereinforcement from lattice in which some of the warp wires have successive deformed non-rectilinear portions whereas the other warp wires and all the weft wires are rectilinear. The deformed warp wires are bent in the form of welded rings and the rest of the lattice is bent in the form of a cylinder. The part of the prereinforcement intended for the socket part of the tubular element is radially

expanded to the desired diameter by at least partially straightening the deformation of the deformed warp wires.

3,578,037

METHOD FOR FILLING A SYRINGE


Thomas J. Flynn, 112 White Cap Ave., Daytona Beach, Fla.

Filed Sept. 11, 1969, Ser. No. 857,089

Int. Cl. B65b 1/04, 3/04; B67c 3/00

U.S. Cl. 141—2

4 Claims



An apparatus and method for preventing foreign material from entering syringes during the filling of the syringes from containers and thus preventing foreign material from being injected into a patient. The apparatus provides a liquid container, such as a vial, having a pierceable self-sealing stopper for inserting the syringe needle for filling the syringe. A filter material is attached to the top of the container so that the needle can be extended therethrough and adapted to filter out foreign material such as coring that breaks loose as the needle pierces the top of the container. A method is provided including drawing air into a syringe prior to inserting the syringe cannula through a pierceable self-sealing stopper of a container. The air in the syringe is then injected into the container freeing any coring material that has broken from the container stopper either into the filtering material or into the liquid in the container. The cannula tip is then withdrawn or extended to place the tip either in the liquid or the filter material where the coring material has not been deposited and drawing the required amount of liquid from the container into the syringe.

3,578,038

RECEPTACLE FILLING METHOD


Chester O. Burford, King of Prussia, Pa., assignor to Federal Mfg. Co., Milwaukee, Wis.

Filed Sept. 15, 1967, Ser. No. 668,091

Int. Cl. B65b 3/18

U.S. Cl. 141—7

9 Claims



A rotary type filling machine having a plurality of filling heads spaced about its periphery. The filling heads have vent

tubes for communicating the interior of flexible walled containers, which are to be filled by the machine, with a gas storage area within the machine. This area is subjected to a pulsing vacuum which vacuum is communicated to the containers via the vent tubes and which operates on said containers to prevent overfilling of the same.

3,578,039

AUTOMATIC PROPORTIONER ASSEMBLY


Edward P. Marbach, Los Angeles, Calif., assignor to Baxter Laboratories, Inc.

Filed Oct. 15, 1968, Ser. No. 767,676

Int. Cl. B65b 1/04, 3/04

U.S. Cl. 141—18

9 Claims



An automatic proportioner for proportioning a sample and a diluent for subsequent chemical analysis including a syringe driven by an actuator and controlled by a control system, a valve for selectively connecting the syringe to either a source of diluent in a receptacle or a source of sample, with diluent receptacle and valve being formed in a unitary assembly selectively removable from the main housing supporting the syringe and the control system components so that the receptacle, valve and syringe may be removed easily and replaced by another set.

3,578,040

CARTON FILLER


J. Robert Galloway, 908 Georgian Drive, Danville, Ill.

Filed Dec. 20, 1968, Ser. No. 785,531

Int. Cl. B65b 57/02

U.S. Cl. 141—142

10 Claims



A filler for use with a carton filling machine having an improved no carton-no fill mechanism arranged such that the capacity of the volumetric filling mechanism thereof can be changed without making a number of additional adjustments. Also, the hopper and the cup support for the filler is adapted to be vibrated, to provide improved carton fill.

3,578,041

AUTOMATIC APPARATUS FOR PACKAGING POWDERED MATERIAL WITH UNIFORM BAG WEIGHT AND WITH DUST-FREE OPERATION


Katsuji Obara, Yokohama, Kanagawa, Japan, assignor to Nippon Jido Fukurozumei Mfg. Co., Ltd., Tokyo, Japan

Filed Sept. 23, 1968, Ser. No. 761,441

Int. Cl. B65b 1/18, 1/34

U.S. Cl. 141—59

9 Claims



An automatic packaging apparatus for powdered material in which such material is fluidized in an air chamber and delivered by air to a filling means associated with a receiving bag. Flow control means are provided responsive to automatic weighing means, and recirculation means are provided for returning the dust from the air chamber and the region of the filling means for recirculation.

3,578,042

VAPORIZER FOR ANESTHETIC

Hans Georg Breiling, Lubeck, Germany, assignor to Dragerwerke, Heinrich & Bernh. Drager, Lubeck, Germany


Filed Dec. 24, 1968, Ser. No. 786,621

Claims priority, application Germany, Jan. 2, 1968,

P 16 16 191.4

U.S. Cl. 141—301

5 Claims



Narcosis apparatus comprising a vaporizer equipped with a filler assembly consisting essentially of a horizontal member and a member rotatable thereon to a filling position and is provided with bore holes that align themselves only when in filling position, the exterior opening of the bore holes when aligned being at the same level as the preselected maximum liquid level within the vaporizer so that the latter will automatically be prevented from overfilling.

3,578,043

LUMBER CUTTING APPARATUS


Donald C. Menge, Warren, Mich., assignor to Troy Steel Corporation, Troy, Mich.

Filed Aug. 15, 1968, Ser. No. 752,918

Int. Cl. B27b 5/20

U.S. Cl. 143—6

24 Claims



A rotatable adjustable pedestal support to which is mounted a circular saw for horizontal movement back and forth along a straight line across a piece of lumber and for rotation about a vertical axis to a desired cutting pitch. In a further embodiment a pair of rotatable adjustable pedestal supports are mounted on a longitudinal table slide for adjustment toward and away from each other between selected positions accommodating the finished length of a wooden stud or truss element.

3,578,044

CARRIAGE FOR SAWING SHAKE BOLTS INTO WEDGES


Norman E. Norlander, Longview, and Robert A. Knowles, Tacoma, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

Filed Feb. 26, 1969, Ser. No. 802,609

Int. Cl. B27b 13/00; B27m 3/02

U.S. Cl. 143—12

2 Claims



A shake bolt is supported on a carriage for movement relative to a cutting saw. The carriage has grasping rollers which engage the ends of the bolt and feed it into the plane of the saw. Each roller is driven by a stepped drive to provide alternate larger and smaller rotation step movements for the rollers on opposite ends of the bolt. While the roller at the first end rotates the larger rotation step, feeding the first end of the bolt a greater distance beyond the saw plane to produce a butt cut, the roller at the other end rotates a smaller rotation step, feeding the other end a lesser distance beyond the saw plane, to produce a tip cut. This cycle alternates with a second cycle wherein the roller at the first end rotates the smaller rotation step for a tip cut while the other roller rotates the larger step for a butt cut. The system for aligning the grasping rollers with the end surfaces of the bolts and the two-step drive system are disclosed in detail.

3,578,045

EXPANDING TIRE-SUPPORTING WHEEL APPARATUS


John B. Lundberg; Richard J. Beck, and James N. Locke, Lodi, Calif., assignors to Super Mold Corporation, Lodi, Calif.

Filed May 26, 1969, Ser. No. 827,692

Int. Cl. B60c 25/00

U.S. Cl. 144-288

7 Claims



An expanding wheel apparatus for temporarily supporting a pneumatic tire during operations such as buffing, grinding, smoothing and dressing preparatory to recapping or retreading the tire. The apparatus includes a rotatable shaft to which is keyed a scroll wheel. A jaw support is rotatably supported by the shaft, with a plurality of jaws being carried by such jaw support for radial movement relative thereto. Engaged helically extending teeth are carried by the jaws and the scroll wheel. When the jaw support is locked in place, the rotation of the scroll wheel will extend or retract the jaws. The jaws support a radially expandable band assembly that receives the tire when such assembly is in a contracted position. The wheel assembly is radially expanded when the jaws undergo radial movement relative to the scroll wheel.

3,578,046

TOOL

Joseph W. Curran, 22 St. Mary's Place, Denville, N.J.

Filed Dec. 20, 1968, Ser. No. 785,528

Int. Cl. B25b 15/00

U.S. Cl. 145-50

4 Claims



A bifurcated screwdriver for torquing a threaded fastener having a drive slot interrupted by a borehole. The tines for torquing the fastener have a first pair of linear thrust surfaces and a second pair of nonlinear thrust surfaces along the termination thereof, together with two pair of torquing surfaces adjacent thereto. In addition, the tines have axially-extending, arcuate surfaces for position-orienting the tool relative to the borehole upon the borehole having an element in penetration thereof. The tool has a hexagonal shank for engagement with a mechanically-advantaged torquing source.

3,578,047

RECIPROCATING NUT SHELLER


Bernard W. Diggs, 571B Meadowlark Drive, Little Rock, Ark.

Filed Mar. 13, 1969, Ser. No. 806,792

Int. Cl. A23n 5/02

U.S. Cl. 146-16

1 Claim



A swingably movable handle, functioning as a second order lever, is connected to actuate the reciprocable jaw of a piston-type nut sheller through a swingably movable connecting rod releasably latched to the handle. The connection is selectively effected by the seating of a latch pin mounted on the handle into one of a plurality of linearly spaced notches disposed along the underside of the connecting rod, to thereby alter the position of the reciprocable path of the movable jaw as may be required to shell nuts differing in size, the continued connection of the handle to the connecting rod as the handle is swung in either direction being assured by a distinctive configuration of the notches.

3,578,048

POTATO DICER


Harrison M. Von Duyke, P.O. Box 842, Wilmington, Del.

Filed June 3, 1969, Ser. No. 830,000

Int. Cl. B26d 1/06, 3/20

U.S. Cl. 146-78

8 Claims



Apparatus for dicing cooked potatoes which includes a base, support members for supporting the potatoes, tracks on the base carrying a pair of opposed cutting frames, which frames have metallic cutting wires thereon, and a drive connecting the frames to provide horizontal motion to the frames to cut the potatoes into strips so that they can be further diced by a vertically movable blade.

3,578,049

MEANS FOR COMMUNUTING STALK OR LEAF VEGETABLE

Ernst Weichel, Bahnhofstr.1, Heiningen, Kreis, Goppingen, Germany

Filed Feb. 26, 1968, Ser. No. 708,244

Int. Cl. A01d 55/00; B02c 18/06

U.S. Cl. 146-98

19 Claims

A comminuting arrangement for the cutting or crushing of stalk or leaf vegetables has a conveyor and a conveyor chute

3,578,051

CYLINDER COVER


George L. Hammon, Oakland, Calif., assignor to Chemetron Corporation, Chicago, Ill.

Filed Apr. 1, 1969, Ser. No. 811,844

Int. Cl. B65d 87/36

U.S. Cl. 150-52

4 Claims



forming the discharge of the conveyor and comprising walls in the zone of a cutting device. The cutting device comprises at least two groups of cutting discs, and the discs of each group are arranged on a respective common shaft. The shafts carrying the cutting discs are mounted exteriorly of the conveying chute and rotate at a low speed. The distance between

the two shafts arranged in opposition to each other is less than the sum of the radii of the opposed cutting discs, and the cutting discs extend through opposite walls of the chute and only partially into the chute. The device is arranged for mounting on a self-loading vehicle or for stationary operation.

Cover for enclosing the valved end of a container for gas material. At least a portion of the cover is resilient and has an open end which is engageable about the cylinder end by hand pressure.

3,578,050

COLLAPSIBLE AIRCARGO CONTAINER


Joseph L. Weingarten (1927 Oak Tree Drive, East Kettering, Ohio 45440), and Stephen R. Mehaffie, Dayton, Ohio (1596 Beaver Ridge Road, Kettering, Ohio 45429)

Filed May 12, 1969, Ser. No. 823,643

Int. Cl. B65d 19/18, 11/18

U.S. Cl. 150-0.5

4 Claims



A collapsible aircargo container is disclosed which is particularly adapted for aircraft transportation. The container is secured at its lower edges to a pallet on which the products rest within the container. The latter is formed of a double walled airtight rubberized material having a passageway between the walls to receive air under pressure. One or more spring loaded air valves are inserted in the material of the container and communicate with the compartment formed between the double walls. A frame member is also provided, made of a double walled material, to provide an entrance to the interior of the container. The frame, when charged with air under pressure, will stand upright to support the container material and, when devoid of air, can be moved around hinges to be against the pallet. Adjustable straps of webbing material are secured to the outer surface of the container and the frame member so as firmly to secure the contained product to the pallet and to be protected by the container. After the products have been stowed within the container, the pressure of air in the double walls of the container and frame member is reduced to cause the container material to hug or settle down onto the aggregate contour of the products. The container and frame member can be collapsed by complete removal of air pressure when not in use, to occupy a space no greater than the physical dimensions, i.e. thickness and size of the container material and the attached pallet.

3,578,052
REPLACEABLE TREAD ON AN EXPANDING DIAMETER CAR CARCASS TIRE


Aivars V. Petersons, 1925 Little York Road, Dayton, Ohio

Filed Sept. 19, 1968, Ser. No. 760,931

Int. Cl. B60c 11/02

U.S. Cl. 152-187

2 Claims



A vehicle tire which provides a simple means of mounting, dismounting, or exchanging tire treads. The tire carcass is designed in such a manner that the diameter increases by 15 percent or more when the tire is inflated to operating or operable pressure. On the carcass, in place of the conventional integral tread there is a wide annular groove or channel having spaced sidewalls. The tread comprises an annular nonstretchable flexible band or belt which snugly fits in the channel between the sidewalls. When the tire is inflated and expands radially outwardly, the nonexpandable tread is securely and firmly held in place in the channel, but it can be removed and replaced when the tire is deflated. The interengaging inner annular surface of the tread member or band and the outer surface or bottom of the tread receiving channel may be formed with complementary, interengaging means or lugs which are forced into interengagement with each other when the annular tread band is fitted into the channel and the tire is inflated to resist relative slippage between the tire and the annular belt tread member.

3,578,053

TIRE STUD

Paul E. Milliken, Massillon, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

Filed Sept. 5, 1969, Ser. No. 855,540


Int. Cl. B60c 11/16

U.S. Cl. 152-210


12 Claims

A tire stud having increased traction characteristics due to increased edge contact with the road achieved by the cross-

sectional contour of the traction portion of the stud. In one embodiment, the traction portion is X-shaped in cross section and in another embodiment, the traction portion is L-shaped in cross section. The stud may be inserted directly in



and secured in position thereby, the marker comprising, at least in part, material which may be distinguished either



visually or audibly upon rotation of the tire on a hard surface for indicating a degree of tread wear which has occurred in the rubber adjacent the marker.

3,578,056

RUN-FLAT COMBAT TIRE


Walter P. Wynbelt, Royal Oak, Mich., assignor to the United States of America as represented by the Secretary of the Army

Filed May 20, 1969, Ser. No. 826,119

Int. Cl. B60c 17/04

U.S. Cl. 152-340

4 Claims



To provide an improved military run-flat combat tire, a conventional tubular tire casing is equipped with a smaller diameter, pressureless, filament wound, reinforced fiberglass toroid capable of supporting the vehicle at relatively high sustained speeds after the tubeless tire has been punctured.

3,578,057

SYNTHETIC RESIN PNEUMATIC TIRE

Ulrich Knipp, Leverkusen; Eckhard Boigk, Leichlingen, and Erwin Weinbrenner, Opladen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany


Filed May 27, 1968, Ser. No. 732,155

Claims priority, application Germany, June 2, 1967, F52579

Int. Cl. B60c 9/02

U.S. Cl. 152-356

3 Claims



A pneumatic tire made from a synthetic resin is produced using a mold and an annular mold core and has a spacing layer arranged between the windings of a reinforcing insert and the internal surface of the tire.

3,578,054

TIRE COVERS

Jacques Boileau, Clermont-Ferrand, France, assignor to Compagnie Generale Des Etablissements Michelin, raison sociale Michelin & Cie, Clermont-Ferrand (Puy-de-Dome), France


Filed Feb. 2, 1968, Ser. No. 702,564

Claims priority, application France, Feb. 6, 1967, 93886

Int. Cl. B60c 19/00

U.S. Cl. 152-330

4 Claims



A series of tires for an automotive vehicle is manufactured in accordance with an identical model, on identical machines and under identical conditions. Because of manufacturing tolerances, the tires have a pseudocamber the magnitude of which is an aleatory variable. The pseudocamber is measured for each tire, and those tires having a pseudocamber producing a lateral thrust, when the tires roll at 10 km./h at normal load and pressure on level ground, beyond 0 percent to 6 percent and, preferably, 1 percent to 4 percent of the rated load of tire, are rejected. The remaining tires are marked by any arbitrary symbols the meaning of which is understood by users, to indicate the direction of mounting on a rim. The tires are mounted on their respective rims so that the lateral thrust is outward on the front wheels and inward on the rear wheels.

3,578,055

TREAD WEAR INDICATOR

Tom French, and Vernon E. Gough, Sutton Coldfield, England, assignors to The Dunlop Company Limited, London, England

Filed Oct. 11, 1968, Ser. No. 837,961

Claims priority, application Great Britain, Oct. 18, 1967, 47346/67

Int. Cl. B60c 11/00

U.S. Cl. 152-330

3 Claims

A pneumatic tire having a recess formed in the tread rubber thereof by cutting or moulding a recess shoulder portion formed in the rubber bounding the recess, and a tread wear marker located in the recess having at least a part thereof located radially inwardly of the said shoulder portion

3,578,058

PNEUMATIC TIRE DISMOUNTING APPARATUS


Chester W. Allen, 635 N. Flora, Wichita, Kans.

Filed July 24, 1969, Ser. No. 844,461

Int. Cl. B60c 25/06

U.S. Cl. 157-1.17

21 Claims U.S. Cl. 160-172



Apparatus for use in dismounting a tire from a wheel comprising an elongated hollow frame having a bifurcated lip at its lower end adapted to be forced between the bead of the tire and the wheel rim. A clamp movably mounted on the frame for movement toward and away from the bifurcated lip to force the latter between the bead and the rim. A foot member slidably mounted in the hollow frame for telescopic downward extension from a retracted position in the frame, with the foot member having a lip portion coextensive with and disposed within the bifurcated lip when the foot member is retracted. Power operable means movable within the frame from an upper to a lower position for initially actuating the clamp toward the bifurcated lips and thence moving the foot member downwardly so that the lip of the latter forces the bead from the rim.

3,578,059

BEAD SPREADER FOR TRUCK TIRES


James R. Uhen, Burlington, and David L. Olson, Racine, Wis., assignors to Tenneco, Inc., Houston, Tex.

Filed Nov. 4, 1968, Ser. No. 773,101

Int. Cl. B60c 25/12

U.S. Cl. 157-1.21

5 Claims



A device for expanding the beads of tubeless tires so as to facilitate filling them with air under pressure comprises a flexible strap that may be looped around the outside of the tire and a device for receiving the ends of the strap and applying tension to the strap. The device preferably includes a frame having a guide neck with rollers through which the strap ends extend with one end being anchored to the frame and the other end extending through a ratchet takeup mechanism mounted on the frame, tension being applied by means of a hydraulic ram assembly connected through rollers to the two end sections of the strap. The hydraulic assembly has a special relief valve to preclude the application of excessive pressure.

3,578,060


VERTICALLY MOVABLE SELF-LOCKING SHUTTER

Lloyd Spencer, 220 Patrician Way, Pasadena, Calif.

Filed Apr. 18, 1969, Ser. No. 817,360

Int. Cl. E06b 9/30

18 Claims



An exposed shutter having horizontally disposed slats movable between a raised, stacked condition and a lowered, spaced condition; the slats being provided with end fittings slidable on fixed vertical guides and linkage arranged to tilt and lock each slat in a predetermined angular position as it reaches its spaced condition, and further includes a final locking mechanism operable, when the shutter is extended, to secure all the slats so as to resist windloads; the shutter being raised and lowered by tapes which also function to release the locking mechanism.

3,578,061

COVERING DEVICE FOR PROTECTING THE GUIDING

PATHS OF MACHINE TOOLS

Friedrich Hascheck, Weidenau, and Kurt Loos, Dreis-Tiefenbach, Germany, assignors to Kabelschlepp G.m.b.H., Siegen (Westphalia), Germany


Filed Dec. 2, 1968, Ser. No. 780,340

Claims priority, application Germany, Dec. 14, 1967, P1,650,983.4

Int. Cl. E05d 15/06

U.S. Cl. 160-202

10 Claims



In combination with guideway means of a machine tool for protecting said guideway means, a slide cover which includes: a plurality of box-shaped members telescopically movable into and out of each other; each of said box-shaped members comprising a top plate and two sideplates extending in the longitudinal direction of said guideway means, each of said box-shaped members also comprising supporting plate means adapted to engage and to be supported by said guideway means, one of the outer ones of said box-shaped


members being provided with an end face wall and being adapted to be connected to a reciprocable member of said machine tool; and coupling means between at least two adjacent box-shaped members and between said end face wall and the next box-shaped member, said coupling means being operable automatically to couple the respective adjacent box-shaped members to each other in response to the said respective box-shaped members with the coupling means therebetween having been telescoped into each other to their possible maximum extent to thereby permit all box-shaped members when telescoped into each other to move beyond the end of said guideway so as to form a cantilever.

3,578,062

METHOD OF AND APPARATUS FOR CONTINUOUS CASTING WITH IMMERSION-TYPE LONG NOZZLES
Shigeki Soeda, Yokohama-shi; Hidetaro Nemoto, Hasegawa; Tomohiro Hasegawa, and Yasuhiro Kaneko, Yokohama-shi, Japan, assignors to Nippon Kokan Kabushiki Kaisha
Filed Feb. 25, 1969, Ser. No. 802,118
Claims priority, application Japan, Mar. 5, 1968, 43/13858
Int. Cl. B22d 11/00

U.S. Cl. 164-82

2 Claims




A single tundish is used provided with two or more immersion-type long (submerged extended) nozzles of different length. The tundish is lowered to immerse the longest immersion-type nozzle to a predetermined depth below the surface of the molten steel in a casting mold, the tundish is elevated to cut off the longest nozzle before it is subjected to erosion, and again the tundish is lowered to immerse the next longest immersion-type nozzle to said predetermined depth to continue the casting operation.

3,578,063

DEVICE FOR SETTING TUNDISH ABOVE MOULD OF MACHINE FOR CONTINUOUS CASTING OF METAL
Vitaly Maximovich Niskovskikh, Ulitsa Festivalnaya, 21, KV. 60, Sverdlovsk; Alexei Ivanovich Varaxin, Khimki-khovrino, Ulitsa Dyben KO, 22, Korpus 5, KV. 374, Moscow; Evgeny Jukhimovich Gelfenbein, Ulitsa 40 Let Oktyabrya, 28, KV. 51; Lev Isaevich Safronovich, Ulitsa Kirovograd Skaya, 71, KV. 2, and Leonid Georgievich Kuznetsov, Ulitsa Pobedy, 59, KV. 5, Sverdlovsk, U.S.S.R.
Filed July 12, 1968, Ser. No. 744,520
Int. Cl. B22d 11/10

U.S. Cl. 164-281

5 Claims



A device for positioning a tundish above a continuous casting mold during the casting process, the device consisting of


a carriage movably mounted on rails, which carriage carries the tundish in cantilever fashion. Specifically, the carriage has mounted thereon a lifting mechanism which actuates a lever system, connected to a support means holding the tundish. The lever system takes the form of four links, two links being mounted at either end of the tundish between the support means and the carriage, and each pair of links being in the shape of a parallelogram, especially when considering an imaginary line drawn between the pivot axes at each end of each pair of links.

3,578,064

CONTINUOUS CASTING APPARATUS
Norman T. Mills, Highland; Charles R. Jackson, Hammond, and James W. Halley, Chesterton, Ind., assignors to Inland Steel Company, Chicago, Ill.
Filed Nov. 26, 1968, Ser. No. 779,088
Int. Cl. B22d 11/10

U.S. Cl. 164-281

10 Claims




A continuous casting process whereby objectionable surface inclusions are substantially eliminated from the continuous casting and wherein molten steel is introduced into a continuous casting mold by an injection means which discharges the molten metal into the mold below the surface of the molten metal pool maintained in the upper end of the mold through controlled streams having an upwardly and outwardly flowing component which contacts the solidifying casting surfaces to wash away objectionable inclusions normally frozen into the casting and concentrates the objectionable inclusions on the surface of the molten metal where they can be readily removed. Injection nozzles adapted for use with rectangular and square continuous casting molds comprise tubular sections having circumferentially spaced lateral discharge openings for introducing the molten metal into the mold so as to uniformly contact those surfaces of the casting from which objectionable inclusions must be substantially excluded.

3,578,065

MANDREL HOLDER FOR HORIZONTAL PIPE CASTING APPARATUS
Reinhold Langer, Garbsen, Germany, assignor to Kabel-und Metallwerke Gutehoffnung-shutte Aktiengesellschaft, Hannover, Germany
Filed Aug. 28, 1969, Ser. No. 853,896
Claims priority, application Germany, Aug. 31, 1968, P1,758,902.5
Int. Cl. B22d 11/10

U.S. Cl. 164-281

7 Claims



A holder for a mandrel mounted in a metal casting crucible to continuously form pipe; the casting operation being of


the horizontal type and the holder accurately centering the mandrel in respect to the tube mold.

3,578,066

APPARATUS FOR THE HEATING AND COOLING OF MOULDS FOR THE PRODUCTION OF PLASTIC BODIES
Anton J. Vox, Ruit, Germany, assignor to Thermovox G.m.b.H. Kunststoffmaschinen, Ruit, Germany
Filed Jan. 31, 1969, Ser. No. 795,569
Claims priority, application Germany, Feb. 2, 1968, P1704375.3; P1704376.4
Int. Cl. F25b 29/00

U.S. Cl. 165-27

15 Claims




In combination with a mould having an outer and an inner wall defining a space therebetween for the flow of cooling or heating fluid therethrough, fluid circuit means including a pressure pump for circulating fluid under pressure through the space and bypass means connected to the circuit means for bypassing part of the fluid pumped by the pump past the mould to avoid overpressure in the space and possible deformation of the mould walls.

3,578,067

SELF-COOLING MECHANICAL SEAL LUBRICATOR
Seymour Schlosberg, East Brunswick, N.J., assignor to R. Gelb & Sons, Inc.
Filed July 10, 1970, Ser. No. 53,808
Int. Cl. B60h 1/00

U.S. Cl. 165-39

7 Claims



Apparatus for lubricating a mechanical seal between a rotatable shaft and its housing comprises a fluidtight reservoir. A tubular member is disposed within the reservoir and is secured to an upper end wall of the reservoir to define therewithin a lubricant-cooling chamber. The lower end portion of the tubular member is disposed sufficiently above a lower end wall of the reservoir to permit circulation of lubri-


cant between the reservoir and the cooling chamber. A lubricant return conduit extends upwardly through the lower end wall into the cooling chamber and terminates at a point sufficiently below the upper end wall to permit circulation of returned lubricant throughout the cooling chamber. Means are provided for cooling the returned lubricant as it circulates downwardly within the cooling chamber. In operation, the reservoir is filled and gas under pressure is introduced therein to force the lubricant within the cooling chamber upwardly to a level sufficient to provide adequate heat transfer from the returned lubricant to the cooling means.

3,578,068

TEMPERATURE RESPONSIVE PASSIVE VARIABLE THERMAL CONDUCTANCE DEVICE
Daniel L. Elliott, Southington, and Gary D. Burr, Berlin, Conn., assignors to United Aircraft Corporation, East Hartford, Conn.
Filed June 11, 1969, Ser. No. 832,263
Int. Cl. B60h 1/00

U.S. Cl. 165-39

9 Claims




Heat conductivity through a device in a given direction is achieved by a pair of relatively rotatable thermal anisotropies having mutual interfacing surfaces of constant area. The overall thermal conductance of the assembly varies with the relative angular position of the elements in response to a temperature responsive element such as a bimetallic spring or a fluid-charged bellows.

3,578,069

APPARATUS FOR FIRING CARBON-CONTAINING PRODUCTS
Paul Morel, Le Vesinet; Jean-Pierre Givry, Ville D'Avry, and Philippe Voisin, Saint-Jean de Maurienne, France, assignors to Compagnie Pechiney, Paris, France
Filed Feb. 10, 1969, Ser. No. 797,738
Claims priority, application France, Feb. 19, 1968, 140,305
Int. Cl. F25b 29/00

U.S. Cl. 165-61

7 Claims




Method and apparatus for firing carbon-containing products which involve processing the products through four zones, including a heating zone, a zone for release and combustion of volatile materials, a final heating zone, and a cooling zone, and in which the final heating zone provides for the heating of the products from the inside out thereby to achieve uniform temperature distribution in this stage of the operation to provide a more efficient process and a more desirable product.

3,578,070

APPARATUS FOR SALVAGING BLUE POWDER FROM ZINC ORE FURNACES AND THE LIKEIve L. Martin, P.O. Box 2256, Modesto, Calif.
Filed Aug. 19, 1968, Ser. No. 753,380
Int. Cl. C22b 19/02

U.S. Cl. 165-61

9 Claims



A material smelting and processing plant which is usable for smelting zinc ore or also glass materials. It includes a main housing, the upper portion of which contains ore or glass smelting containers or pots, with heating means for raising their temperature to the smelting point, so that the zinc ore is smelted into liquid metallic zinc which is decanted from the pots, while the remaining blue powder containing richly zinc is reamed out and dropped into a compartment in the basement of the main housing and onto conveyors for carrying it to an end receptacle for further smelting and processing. The remaining zinc ore slag is then reamed out of the pots and dropped into a waste compartment in the basement and onto conveyors for removal as waste. Cooling sprays are in the basement for reducing the temperature of the materials and to protect the conveyors and compartments from the intense heat. The plant when used to produce glass also has means for removing the glass from the containers, dropping it into the basement onto conveyors and refrigeration for cooling the spray fluid below freezing to cool the hot glass. It is then conveyed to end receptacles for further processing such as crushing, etc.

3,578,071

CONCENTRIC EVAPORATION-CONDENSATION, ROTARY, THIN FILM, HEAT TRANSFER APPARATUS

Arthur K. Johnston, New Lambton, New South Wales, Australia, assignor to The University of Newcastle, Newcastle, New South Wales, Australia

Filed Apr. 8, 1969, Ser. No. 814,352


Claims priority, application Australia, Apr. 11, 1968,

36388/68

Int. Cl. F28f 5/00

U.S. Cl. 165-66

9 Claims



The invention relates to an apparatus for transfer of heat between solids, liquids and vapors and for transfer of mass between and within liquids and vapors, the apparatus com-

prising a rotatable, substantially cylindrical film carrier onto which a thin film of a material to be vaporized is deposited by stationary depositing means, a vaporizing zone surrounding the film carrier, and a condensation zone within the film carrier into which a vaporized component of the material deposited on the film carrier is directing for condensing. The film carrier constitutes a common heat transfer boundary between the vaporizing and condensation zones and latent heat emitted from material during condensation passes through the film carrier to effect the vaporization of the material on the outside of the film carrier. The invention has particular application as a desalination apparatus.

3,578,072

HEAT EXCHANGE APPARATUS


Henry H. Kolm, Wayland, Mass., assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Continuation-in-part of application Ser. No. 761,048, Sept. 20, 1968. This application Aug. 11, 1969, Ser. No. 849,127

Int. Cl. F28d 1/106

U.S. Cl. 165-84

3 Claims



Heat exchange apparatus is disclosed in which the heat exchange surfaces are vibrated by electric eddy current means to enhance heat transfer between said surfaces and a medium.

3,578,073

HEAT EXCHANGE APPARATUS WITH INTEGRAL FORMATION OF HEAT EXCHANGERS AND SEPARATORS

Maurice Bosquain, Paris, France, assignor to L'Air Liquide Societe Anonyme Pour L'Etude Et L'Exploitation Des Procédés Georges Claude


Filed Mar. 27, 1968, Ser. No. 716,486

Claims priority, application France, Mar. 3 1, 1967, 100919

Int. Cl. F25j 1/00, 5/00, 3/00

U.S. Cl. 165-111

2 Claims



An indirect heat exchange assembly comprises superimposed heat exchangers with nests of tubes and liquid separators disposed between the exchangers. The nests of tubes open onto the walls of the separators, which thus serve the purpose of headers or collectors. Further features are that the separators can have their bases common to those of ad-

3,578,074

WARM WATER PRODUCER

Otto Domok, Luzern, Switzerland, assignor to Strelbelwerk AG, Rothrist, Switzerland

Filed Mar. 5, 1969, Ser. No. 804,461


Claims priority, application Switzerland, Mar. 14, 1968,

3757/68

Int. Cl. F24h 1/46; F28d 1/06

U.S. Cl. 165-132

7 Claims



A series of pipes in the space between the outer casing and the inner lining carry water to be heated back and forth until it is finally emptied into the interior of the lining which acts as a reservoir from which the heated water can be drawn off. Hot heating water flows in the space between the outer casing and the inner lining.

3,578,075

CORRUGATED TUBING

Joseph Winter, New Haven, Conn., assignor to Olin Corporation

Continuation-in-part of application Ser. No. 679,459, Oct. 31, 1967, now abandoned. This application Oct. 29, 1969, Ser.

No. 872,154

Int. Cl. F28f 1/06, 1/10

U.S. Cl. 165-177

4 Claims



The disclosure teaches an improved corrugated metal tubing having improved corrosion resistance and heat transfer characteristics. The tubing is characterized by having a plurality of lands and grooves extending helically along the circumference thereof and having in cross section a plurality of uniform, symmetrical, wavelike indentations.

3,578,076

THAWING-OUT MEANS FOR REFRIGERATORS

Luis Camejo, Union City, New Jersey, assignor of one-third to Jose Bovantes, Fort Lee, New Jersey, and one-third to Orlando Martinez, Union City, New Jersey

Filed May 19, 1969, Ser. No. 825,546


Int. Cl. F25d 21/00

U.S. Cl. 165-63

4 Claims

The invention relates to refrigerator structure embodying means therein for thawing out frozen or refrigerated

foodstuffs within selected time intervals and comprises an accessible chamber within the interior of the refrigerator, provided with adjustable and controlled heating means to effectuate an accelerated defrosting operation. Means are



provided to cause air circulation within the said chamber for oxygenation and prevention of heat build-up to approximate defrosting under the normal ambient conditions present in conventional defrosting.

3,578,077

FLOW CONTROL SYSTEM AND METHOD


Edwin E. Glenn, Jr., Dallas, Vasek R. Slover, and Malcolm K. Strubhar, Irving, Tex., assignors to Mobil Oil Corporation

Filed May 27, 1968, Ser. No. 732,460

Int. Cl. E21b 43/00

U.S. Cl. 166-68

9 Claims



This specification discloses a method and apparatus for controlling flow of a multiphase fluid stream from a partially depleting supply source such as a pumping oil well so that the flow rate of the liquid phase thereof is maintained substantially constant. Where said source is an oil well, the multiphase fluid is pumped from the well into a separator where it is separated into its liquid and gas phases. A constant volume pump withdraws liquid from the separator at a set flow rate. A conduit connects the separator back to the well and has a valve therein which is controlled by the liquid level in the separator whereby a portion of the liquid in the separator can be returned to the well to maintain sufficient fluid in the well for the well pump to operate at its capacity.

3,578,078

EARTH BOREHOLE TOOL

Harold E. Shillander, Albuquerque, N. Mex., assignor to General Oil Tools, Inc., Phoenix, Ariz.

Filed Jan. 12, 1970, Ser. No. 2,115


Int. Cl. E21b 23/00

U.S. Cl. 166-152

20 Claims

An oil well drill string or stem having a tubular mandrel fast on its lower end and a drive sleeve assembly telescoped onto the mandrel. A resilient packer fastened at its upper end to the mandrel is slidable on the mandrel above the drive sleeve assembly, and a retractor secured to the lower end of the packer with a lost-motion connection is alternately

latched to the mandrel when the packer is extended, unlatched by the drive sleeve assembly as the latter moves upwardly relative to the mandrel to compress the packer longitudinally and thus expand it radially, and latched to the drive sleeve assembly for positive longitudinal extension and



radial collapse of the packer as it is returned to the latched condition. Circulation ports in the drive sleeve assembly are opened only when the packer is expanded, and a driving spline connection between the drive sleeve assembly and the mandrel has squared spline elements for increased bearing strength.

3,578,079


APPARATUS FOR PLUGGING WELL BORES WITH HARDENABLE FLUENT SUBSTANCES

Carl V. Alexander, Houston, Tex., assignor to Schlumberger Technology Corporation, New York, N.Y.
Filed Nov. 12, 1969, Ser. No. 875,877

Int. Cl. E21b 33/127

U.S. Cl. 166—187

17 Claims



As a preferred embodiment of the present invention disclosed herein, a tubular bag is sealingly mounted around an elongated body and operatively arranged to be expanded into engagement with the walls of a well bore by discharging thereinto an initially fluent hardenable substance contained in a selectively-operable displacement assembly releasably coupled to the body. After the fluent substance has expanded

the bag, one end of the bag is secured to the body, selectively released biasing means are operatively arranged for imposing opposed axial forces against the expanded bag to depress the ends of the bag toward one another. In this manner, unbalanced pressure forces acting on the tool will only further urge the bag radially outwardly against the walls of the well bore with an added force for securely anchoring the tool against longitudinal movement until the fluent substance has solidified.

3,578,080

METHOD OF PRODUCING SHALE OIL FROM AN OIL SHALE FORMATION


Philip J. Closmann, Houston, Tex., assignor to Shell Oil Company, New York, N.Y.

Filed June 10, 1968, Ser. No. 735,684

Int. Cl. E21b 43/24, 43/26, 43/27

U.S. Cl. 166—248

4 Claims



A method of producing shale oil from a subterranean oil shale formation by exploding a relatively high energy explosive device therein thereby forming a chimney of rubble within the formation having fractures extending from the chimney into the formation. A plurality of spaced wells are extended into the formation radially outwardly from the chimney and adjacent to at least some of the fractures. Fluid flow paths are formed from the wells through the fractures into the chimney and fluid is circulated from the wells through these fluid flow paths and into the chimney at rates creating a pressure drop from the wells to the chimney. Oil shale-reactive properties are imparted to the circulating fluid whereby the fluid reacts with the oil shale thereby moving solid components thereof into void spaces formed within the chimney thereby increasing the permeability of the oil shale formation relative to the permeability of the chimney in regions surrounding the chimney.

3,578,081

SONIC METHOD AND APPARATUS FOR AUGMENTING THE FLOW OF OIL FROM OIL BEARING STRATA


Albert G. Bodine, 7877 Woodley Ave., Van Nuys, Calif.

Filed May 16, 1969, Ser. No. 825,142

Int. Cl. E21b 43/25

U.S. Cl. 166—249

6 Claims



A source of sonic vibrational energy is tightly coupled to the walls of an oil well casing, this energy source being

adapted to vibrationally distort the casing in an elliptical pattern. The casing is sonically energized in this manner, the sonic energy being transferred to the surrounding oil bearing strata to induce the migration of the oil particles therein into the well. The energy source may be two pairs of piezoelectric crystals oriented on axes normal to each other, or a pair of rollers driven around the longitudinal axis of the casing.

3,578,082

AROMATICITY INFLUENCING THE THERMOSTABILITY OF MICELLAR DISPERSIONS


John A. Davis Jr., and William J. Kunzman, Littleton, Colo., assignors to Marathon Oil Company, Findlay, Ohio

Continuation-in-part of application Ser. No. 746,391, July 22, 1968, now Patent No. 3,495,660. This application Nov. 6, 1969, Ser. No. 870,244

Int. Cl. E21b 43/22

U.S. Cl. 166—252

15 Claims



An improved process of recovering hydrocarbon from a hydrocarbon-bearing subterranean formation wherein a micellar dispersion comprised a hydrocarbon, surfactant and aqueous medium is injected into and displaced through the formation to recover hydrocarbon through a production means, the improvement comprising determining the temperature of the formation, mixing with the surfactant and aqueous medium a hydrocarbon having sufficient aromaticity to obtain a stable micellar dispersion at the temperature of the formation. The micellar dispersion can optionally contain cosurfactant and/or electrolyte. Such a process is especially useful to recover crude oil in a secondary or tertiary oil recovery process wherein the formation is at a temperature in excess of ambient temperature.

3,578,083

METHODS AND APPARATUS FOR PLUGGING WELL BORES WITH HARDENABLE FLUENT SUBSTANCES

Ronald A. Anderson, and Nevel G. Owens, Houston, Tex., assignors to Schlumberger Technology Corporation, New York, N.Y.

Filed Nov. 12, 1969, Ser. No. 875,681

Int. Cl. E21b 33/127

U.S. Cl. 166—285

20 Claims

As a preferred embodiment of the apparatus of the present invention disclosed herein, a tubular bag is sealingly mounted around an elongated body and operatively arranged to be expanded into engagement with the walls of a well bore by discharging thereinto an initially fluent hardenable substance contained in a selectively operable displacement assembly releasably coupled to the body. Biasing means are operatively arranged for imposing opposed axial forces against the expanded bag to depress the ends of the bag toward one another. In this manner, unbalanced pressure forces acting on the tool will only further urge the bag radially outwardly against the walls of the well bore with an added force for securely anchoring the tool against longitudinal movement until the fluent substance has solidified. In practicing the methods of the present invention, a yieldable enclosed con-



Thereafter, unbalanced pressure differentials acting across the container will be effective for further increasing the pressure of the fluent substance for firmly urging the container outwardly against the walls of the well bore with a correspondingly increasing frictional force to secure the container in position until the fluent material therein has hardened.

3,578,084

THERMAL WELL COMPLETION METHOD AND APPARATUS


Caurino C. Bombardieri, Calgary, Alberta, and James F. Tod, Edmonton, Alberta, Canada, assignors to Esso Production Research Company

Filed Jan. 23, 1969, Ser. No. 835,386

Int. Cl. E21b 33/14, 17/10

U.S. Cl. 166—288

14 Claims



A method and apparatus for attaching subsurface cementing devices to the periphery of free moving casing for use in thermal wells. Centralizers, wall scratchers, cement baskets, and the like are secured to the free-moving casing by means of a fusible material which is rigid at normal subsurface temperatures and which is deformable at thermal treatment temperatures.

3,578,085

METHOD OF RESTORING FORMATION PERMEABILITY

William G. Halbert, Butte, Mont., assignor to Tenneco Oil Company, Houston, Tex.

Filed Jan. 15, 1970, Ser. No. 3,230

Int. Cl. E21b 43/27

U.S. Cl. 166—307

5 Claims

A method for restoring original permeability to a subterranean oil producing formation penetrated by a well. The

method includes the steps of injecting into the formation a slug of pressurized gasiform fluid, then a slug of aqueous silicate solution, retaining the solution in the formation for 2-24 hours, then removing the solution by the force of the pressurized fluid. These steps accomplish dispersal of clay particles blocking formation permeability and restoration of the formation's original permeability.

3,578,086

RUBBER HORSESHOE

Kenneth M. Giles, Chesterville, Ontario, Canada


Filed Nov. 4, 1968, Ser. No. 772,978

Claims priority, application Canada, Nov. 2, 1967, 004,099

Int. Cl. A011 03/00

U.S. Cl. 168-18

12 Claims



A reusable unitary horseshoe formed from a hard resilient natural or synthetic resinous material which may be readily fitted to and removed from a horse's hoof, said shoe having a lip extending from its outer edge shaped to accommodate the lower part of the hoof and being provided with means adapted to releasably reduce the distance between the free ends of the shoe against the natural resilience of the shoe whereby to adjust the shape of the shoe for fitting to the horse's hoof.

3,578,087
HORSESHOE


Max B. Kirkpatrick, Anchorage, Alaska (P.O. Box 1509, Wickenburg, Ariz. 85358); Andrew Harvey, and John M. Sparks, III, P.O. Box 1509, Wickenburg, Ariz.

Filed Dec. 6, 1968, Ser. No. 781,717

Int. Cl. A01j 01/02

U.S. Cl. 168-24

8 Claims



A horseshoe made of a single piece of metal or the like has a peripheral side surface that is inclined in substantial conformity with the hoof wall and a relatively smooth continuous bottom ground engaging surface that is concave inwardly from a relatively sharp edged intersection with the side surface.

3,578,088

PLANT HARVESTING MACHINE

Roedolf Johannes Raath, 286 Deverish Street, Pretoria, Transvaal Province, South Africa

Filed Apr. 24, 1969, Ser. No. 819,024

Claims priority, application South Africa, Apr. 26, 1968, 68-2696

Int. Cl. A01d 17/10


U.S. Cl. 171-62

6 Claims

The invention relates to a machine for the harvesting of plants and more particularly pulling groundnut plants from

the soil and gathering such plants according to an orderly arrangement.

The machine according to the invention provides a beltlike conveyor, disposed at an angle to the direction of travel of the machine, spaced fingers projecting from an edge of the conveyor, and plant guide means forwardly divergently disposed relative to the conveyor for directing and holding



the plants between fingers and against the conveyor so that the plants are pulled upwardly at the position when the conveyor commences upward movement. With the conveyor means are provided to remove extracted plants for orderly side by side collection on a surface. In addition means are provided for discharge of the plants with the root ends directed in the same directions.

3,578,089


ADJUSTABLE IMPLEMENT-CARRYING ASSEMBLY
Ronald J. Fischer, Wapakoneta; Wilbur E. Groeneveld, Celina, and Gerald O. Irvine, Coldwater, Ohio, assignors to Avco Corporation, Coldwater, Ohio

Filed Feb. 4, 1969, Ser. No. 796,459

Int. Cl. A01b 59/048, 63/32

U.S. Cl. 172-277

7 Claims



The disclosure illustrates an implement-carrying assembly for use with a wheeled transport vehicle. A tool bar is secured to the forward end of the transport vehicle by a pair of laterally adjustable parallel lift linkages. Each of the parallel lift linkages has a provision for detachable mounting of a hydraulic actuator for raising and lowering the tool bar through a linkage arrangement connected to the lifting links. The lift linkages are laterally adjustable relative to one another and to the tool bar to facilitate the mounting of implements for various row spacings. The tool bar is stiffened by truss rods supported in such a manner that they provide support irrespective of the relative positions of the tool bar and the lifting linkages.

3,578,090

SUBSOILER CHISEL PLOW


Ted L. Cline, P.O. Box 38, Rush Springs, Okla.

Filed Feb. 4, 1969, Ser. No. 796,477

Int. Cl. A01b 13/08, 59/043

U.S. Cl. 172-439

5 Claims



A subsoiler chisel plow including a horizontal, perforated or apertured frame having a plurality of downwardly and forwardly extending chisel teeth secured to the frame. The frame has pairs of horizontally spaced hitch brackets on the forward side thereof and has a special angle of attack adjustment structure projecting upwardly therefrom and adapted for connection to the central hitch of a towing vehicle having a three-point hitch connection.

3,578,091

POWER-OPERATED IMPACT WRENCH OR SCREWDRIVER

Ronald Frederick States, London, England, assignor to Desoutter Brothers Limited, Hendon, London, England


Filed Sept. 29, 1969, Ser. No. 861,898

Claims priority, application Great Britain, Nov. 29, 1968, 56653/68

Int. Cl. B25b 23/14

U.S. Cl. 173-12

10 Claims



A power-operated impact wrench, screwdriver or like rotary tool with relatively movable hammer and anvil members and means for automatically causing them to become engaged and disengaged cyclically in which there is means for causing disengagement of the hammer members from the anvil members at a value of torque above a predetermined value comprising an inertia means which is coupled to the hammer member by resilient means the values of which are so chosen that values of torque below the predetermined cut-off value the inertia means is constrained by the resilient means from moving relative to the hammer means and the tool operates in a normal manner while at a value of torque above the predetermined value inertia means move against the action of the resilient means thereby to allow the amount of disengagement movement of members to increase and operate control means to interrupt a supply of power to the tool.

3,578,092

DRILLING TOOLS

Hans-Jurgen Tesch, Hannover; Gunther Haverkamp, Hamburg; Herbert Becker; Alexander Wacker, Frankfurt, Main, and Hans Gotte, Kelkheim, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt, Main, Germany


Filed Feb. 11, 1966, Ser. No. 526,740

Claims priority, application Germany, Feb. 16, 1965, F45,256

Int. Cl. E21b 13/00

U.S. Cl. 175-39

10 Claims



A drilling tool has been provided which has a gastight cavity therein, the entrance of which cavity is preferably positioned away from a wear surface of the tool and which cavity contains krypton as a wear indicating means either for a bearing wear surface or for an abrasive drilling wear surface. The indicating means are activated when, because of wear, the cavity is punctured and krypton escapes or is expelled by means of auxiliary agents. The method of marking the tools as well as the tools thus marked are within the scope of the invention. Further, the improvement in the method of drilling deep bore holes with a tool possessing these indicating means is similarly within the scope of the disclosed invention.

3,578,093

METHOD FOR DRILLING AND CORING


Wayland D. Elenburg, P. O. Box 1588, Monahans, Tex.

Division of Ser. No. 714,551, Mar. 20, 1968, Pat. No. 3,473,517, Oct. 21, 1969, application May 19, 1969, Ser. No. 825,524

Int. Cl. E21b 9/20, 49/00

U.S. Cl. 175-60

12 Claims



A method of drilling bore holes which enables a cylindrical solid core sample to be obtained from a formation. A coring bit together with a core barrel and concentrically arranged drill pipe provides central and annular passageways. The annular passageway is used for circulating fluid to the bit and back up the bore hole annulus while the central passageway


provides for the return of drilling fluid and cores. The circulating fluid is forced down through the drill string annulus to the drill bit, and back up through the hole annulus to thereby remove debris and cool the bit in an improved manner. The cores which have been cut by the bit are accumulated within the core barrel and from time to time the pressure of the drilling fluid is increased while the central passageway is opened to the flow of fluid, thereby forcing the fluid to flow into and up through the central passageway, carrying the accumulated cores therewith. A predetermined pressure drop is maintained across the face of the diamond bit by adjusting the bearing pressure thereof with respect to the formation to thereby enable the bit to cooperate with the formation in a manner analogous to the action of a valve.

3,578,094

FEEDING SYSTEM FOR CONSTANT PRODUCT FLOW
Nelson R. Henry, and Donald R. Middour, Decatur, Ga., assignors to The Woodman Company, Inc., Decatur, Ga.
Filed Sept. 13, 1968, Ser. No. 759,567
Int. Cl. G01g 13/16

U.S. Cl. 177-108

4 Claims



A feeding system including a plurality of in-line vibratory conveyors in which bulk feed is transformed into uniform single-file or column feed whereby product in flight from the system at any given time is equal. A hopper conveyor transfers multiple layers of product to a primary vibratory feeder in response to the demand as gauged by the total weight of the product in said feeder. The primary feeder subcombination employs horizontal section and a contiguous inclined section with a feeding step in between to form a wedge-shaped body of product for regulation of product flow and for thinning out of the product to a single layer with multiple rows. The product then enters a secondary vibratory feeder having its vibrator unit attached at an acute angle to the longitudinal axis of the feeder pan whereby the multirow flow is converted into the single-file flow against a side guide wall of the feeder pan.

3,578,095

COMPACT SNOW VEHICLE


Hans Hauser, Fredericktown, Ohio, assignor to The J. B. Foote Foundry Co., Fredericktown, Ohio
Division of Ser. No. 724,692, Apr. 29, 1968, Pat. No. 3,507,346, this application Mar. 3, 1969, Ser. No. 803,552
1969, Ser. No. 803,552
Int. Cl. B62m 27/02

U.S. Cl. 180-5R

5 Claims

A snow vehicle or snowmobile is provided which is especially designed for children and yet can still carry a fully grown man. The snowmobile is small, of a simple, relatively inexpensive design, and is intended to sell for a fraction of the cost of conventional snowmobiles so as to reach a wide

market. The snow vehicle, the components of which are in a



compact arrangement, features a unique ski structure and also a unique belt driving and supporting unit.


3,578,096

AUTOMATIC THROTTLE CONTROL FOR AUXILIARY MOTORS DRIVING DRAWBAR-TOWED VEHICLES
Chester T. Pearson, 1102 S. W. Stephenson St., Portland, Ore.

Filed June 25, 1968, Ser. No. 739,807
Int. Cl. B62d 59/04

U.S. Cl. 180-14

7 Claims



An automatic throttle control for auxiliary motors driving drawbar-towed trailing vehicles comprises means mounting the drawbar resiliently for longitudinal movement, a throttle control motor and link means operatively linking the throttle control motor to the throttle. Actuating means for the throttle control motor are connected to the drawbar and adjust the throttle proportionately to longitudinal movement of the drawbar. Accordingly, as the vehicle is towed up a hill, movement of the drawbar adjusts the throttle setting to accelerate the auxiliary drive motor. As the vehicle descends the hill, the reverse drawbar movement and throttle adjustment occur.

3,578,097

SYSTEM FOR CONTROLLING THE STEERING OF VEHICLE WHEELS


Jean-pierre Guilbaud, Jouars Ponchartrain, and Jean Vertut, Paris, France, assignors to Commissariat A L'Energie Atomique, Paris, France
Filed Apr. 1, 1969, Ser. No. 812,037
Claims priority, application France, Apr. 9, 1968, 147,453
Int. Cl. B62d 5/04

U.S. Cl. 180-79.1

12 Claims

In a steering control system for vehicle wheels in which rotational axis of the wheels are disposed in a plane at the vertices of a polygon which can be inscribed within a circle referred to as a base circle, the direction of the axes of rotation of the wheels is caused to converge continuously towards a common point referred to as the center of rotation of the vehicle and the circle which circumscribes the base polygon in the base plane corresponds by means of a geomet-

rical transformation to a reference circle in a reference plane, said center of rotation being related alternately its



transformed point in said reference plane and to the harmonic conjugate of said point with respect to said reference circle.

3,578,098


OPERATOR STATION AND SUPPORT

Lawrence F. Clancy, Peoria; Frank A. Grooss, and Richard W. Luttrell, Morton, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed Feb. 28, 1969, Ser. No. 803,279
Int. Cl. B62d 33/06

U.S. Cl. 180-89

6 Claims



A rigid support structure, formed as an integral part of a vehicle such as a large earthmoving machine. The structure incorporates the lower half of an operator's station safety cab, the upper portion of the cab being removable therefrom.

3,578,099


SKIRTING ARRANGEMENTS FOR GROUND-EFFECT MACHINES

Francois Louis Giraud, Plaisir, France, assignor to Societe De L'Aerotraine, Paris, France
Filed Apr. 4, 1969, Ser. No. 813,659
Claims priority, application France, Apr. 5, 1968, 147,271
Int. Cl. B60v 1/16

U.S. Cl. 180-119

11 Claims

The present invention relates to improvements in ground-effect machines of the kind comprising a structure located opposite a bearing surface at a variable distance therefrom, the skirting arrangements which delimit the plenum chamber being associated with means which sense the height of the leakage gap between bearing surface and skirt edge in order



effect machine, the purpose being to prevent premature wear of said skirting edge.

3,578,100

DEVICE FOR CONFINING PRESSURE-FLUID CUSHIONS, MORE PARTICULARLY FOR WATERBORNE GROUND-EFFECT MACHINES


Charles Joseph Marchetti, Neuilly-sur-Seine, and Guy Marcel Neplaz, Meudon-la-Forêt, France, assignors to Societe D'Etudes Et De Developpement Des Aeroglisateurs Marins Ferrestres Et Amphibies S.E.D.A.M., Paris, France
Filed Dec. 19, 1968, Ser. No. 785,302

Claims priority, application France, Dec. 22, 1967, 133598

Int. Cl. B60v 1/04

U.S. Cl. 180-126

11 Claims



A pressure-fluid cushion device for a ground-effect machine movable opposite a surface, which device comprises two sidewall structures extending substantially parallel to and on each side of the longitudinal medial plane of the machine and having a front end portion and a rear end portion, the sidewall structures having sufficient rigidity to resist deformation as a result of variable external forces acting on them during displacement of the machine and laterally defining a space between the machine and the said surface, chambers obstructing the space at the front and rear and extending between the sidewall structures, these chambers being bounded by flexible skirts deformable by such external forces, and means for supplying pressure fluid to the chambers and space.

3,578,101

CHARGE LOADER DEVICE, SYSTEM, AND METHOD FOR UNDERWATER SEISMIC EXPLORATION

Richard R. Larson, Ulster Park, N.Y., assignor to Hercules Incorporated, Wilmington, Del.
Continuation-in-part of application Ser. No. 818,475, Apr. 21, 1969. This application Nov. 4, 1969, Ser. No. 873,875
Int. Cl. F42d 3/06


U.S. Cl. 181-.5XC

22 Claims

A device for loading small explosive charges for delivery to an underwater seismic shooting site over prolonged periods with greater regularity of sequence and higher rate of delivery than possible heretofore is provided which comprises a housing, and an open passageway extending therethrough and including a constricted throat portion and

steps for use as a means to step up into a mobile home or the like. One or more of the treads may be adapted to be easily

inlet being connected to a supply of lubricant and the outlet being communicated with the selected area. The power press includes an improved lubricating system comprising: first lubrication control means operative when the press is operat-



opened by hinges or the like so that the interior of the structure may be used as a handy storage space.

3,578,111


MULTIPLE BEARING RECIRCULATING LUBRICATION SYSTEM

Harold J. Miller, Durand, Mich., assignor to Simplicity Engineering Company, Durand, Mich.
Filed Oct. 18, 1968, Ser. No. 768,804

Int. Cl. F01m 1/12

U.S. Cl. 184-6

12 Claims



A system for lubricating two or more bearing structures which are eccentrically mounted on a common shaft. The system is comprised of structure which enables a fluid lubricant and coolant to be continuously circulated therethrough.

3,578,112

POWER PRESS LUBRICATING SYSTEM

Edward J. Freeland, Hastings, Mich., assignor to Gulf & Western Industrial Products Company, Grand Rapids, Mich.

Filed Aug. 21, 1969, Ser. No. 852,013

Int. Cl. F01m 9/12

U.S. Cl. 184-6

5 Claims

In a power press of the type having at least two relatively movable components in interfriictional contact at a selected area during relative movement of these components, means for selectively operating the press in one of two modes, and means for lubricating the selected area, the lubricating means including a lubricant injector having an inlet and outlet, the

ing in one of the modes for actuating the lubricant injector; and second lubrication control means operative when the press is operating in the other of the modes for actuating the lubricant injector.

3,578,113

OIL SHIELD FOR RAILROAD JOURNAL BOX


Don A. Dozier, 11141 Joymeadow, Dallas, Tex.

Filed Aug. 8, 1969, Ser. No. 848,662

Int. Cl. F16n 33/00

U.S. Cl. 184-106

8 Claims



An oil shield for attachment to the jacking pad of a plain or solid type-railroad journal box for catching and diverting oil leaking from the journal box away from the wheels and rails to a point toward the edge of the track.

3,578,114

MECHANICAL PNEUMATIC DELAY TIMER

Jay N. Hopps, Minneapolis, Minn., and Norman F. Green, Plymouth Village, Minn., assignors to the United States of America as represented by the Secretary of the Air Force

Filed Jan. 9, 1969, Ser. No. 790,517


Int. Cl. F16f 9/02

U.S. Cl. 188-311

1 Claim

A mechanical pneumatic time delay device has an actuating arm attached to a piston located within a housing. A spring and a bellows for sealing the housing surrounds the actuating arm. A chamber within the housing adjacent the piston is filled with CO₂ under pressure to compress the spring. A porous restrictor is positioned in a passageway in

one wall of the housing. Support discs are provided on both sides of the restrictor. A puncture diaphragm is positioned



adjacent the restrictor on the side remote from the pressure chamber. Puncture of the diaphragm initiates the time cycle.

3,578,115

UTILITY BAG


Marvin Schneider, Bryn Mawr, Pa., assignor to Rapid-American Corporation, Clayton, Del.

Filed Oct. 21, 1968, Ser. No. 769,313

Int. Cl. A45c 3/00

U.S. Cl. 190-48

17 Claims



A general utility bag is provided, major components of which are rotationally cast or molded, as an integral monolithic unit, with bottom and closure units being secured thereto by radio frequency heat sealing and wherein other heat sealing operations may be of the radio frequency type. Detail, trim and graining along with simulated stitching is provided as part of the integral molding or casting operation to give the general appearance of a bag constructed of multiple components. Handles are then attached to the bag.

3,578,116

DEVICE FOR SELECTIVE COMBUSTION IN A MULTICYLINDER ENGINE

Yasuo Nakajima, and Yoshimasa Hayashi, Yokohama, Japan, assignors to Nissan Jidsha Kabushiki Kaisha, Yokohama City, Japan


Filed Nov. 13, 1968, Ser. No. 775,239

Claims priority, application Japan, Jan. 25, 1968, 43/3986

Int. Cl. F16d 21/04; F02d 9/00

U.S. Cl. 192-.062

7 Claims



A device for saving fuel and cleansing exhaust gas in a multicylinder automobile engine, by interrupting fuel supply

to selected cylinders of the engine during deceleration and coasting of the automobile. The device comprises valves mounted in the selected cylinders of the engine, a pressure-sensing means to sense the negative pressure at the intake manifold of the engine, and a connecting means to operative-ly connect said pressure-sensing means to said valves. The valves are closed by the pressure-sensing means when the negative pressure at the engine intake manifold exceeds a certain predetermined level due to deceleration or slow running of the automobile.

3,578,117

VEHICLE TRANSMISSIONS

Karl Gustav Ahlen, Stockholm K, Sweden, assignor to S. R. M. Hydromekanik, AB, Sweden


Filed Dec. 6, 1968, Ser. No. 781,855

Claims priority, application England, Dec. 11, 1967, 56293

Int. Cl. F16h 37/00, 47/08, 67/00

U.S. Cl. 192-3.51

23 Claims



A transmission for vehicles including a hydrodynamic torque converter wherein the torque multiplication range of the torque converter is increased by a power shift gear device having a release clutch interposed between input and output of the shift gear. The output side of the shift gear is connected to a synchromesh gear transmission, the arrangement being such that the shift gear the release clutch and the synchromesh gear can be connected in series.

3,578,118

CAM OPERATED POSITIVE CLUTCH AND BRAKE


Lewis K. Wetzel, South Burlington, Vt., assignor to General Electric Company

Filed Oct. 1, 1969, Ser. No. 862,656

Int. Cl. F16d 67/02

U.S. Cl. 192-16

9 Claims




A clutch and brake mechanism includes a constantly rotating drive gear mounted for rotation about the driven shaft. A clutch hub is keyed to the shaft for rotation therewith and axial movement thereon, and has a lug which is to be engaged with either the drive gear or a stationary stop. A guide vane is mounted on the hub for axial movement therewith and rotation thereon, and is keyed to the drive gear for rotation therewith and axial movement thereon. The vane has a lug with a constantly rotating knife or cam blade. A non-rotatable control knife or cam blade is translated between the vane and the gear or the vane and the stationary stop to cam the vane directly and thereby shift the hub lug into engagement with either the gear or the stop.

3,578,119


MULTIDISC CLUTCHES

Jean G. M. Auriol, Billancourt, France, assignor to Regie Nationale Des Usines Renault, Billancourt, France
 Filed May 14, 1969, Ser. No. 824,428
 Claims priority, application France, May 22, 1968, 152779
 Int. Cl. F16d 13/38, 69/00
 U.S. Cl. 192-70.14 2 Claims



Clutch mechanisms comprising a plurality of axially movable discs alternatively rotatably solid with two concentric members, wherein a thrust element coacts with the pressure plate of the discs, characterized in that the registering faces of two adjacent discs are formed with cooperating surface portions concentric to the disc axis but not parallel to the opposite face of the same disc.

and coupled to said annular plates by elastic means, the retention in position of the elastic means is ensured by pressed-



out portions, formed alternately as dished portions and relief portions in said annular plates.


3,578,122

GROOVED SINTERED METAL SYNCHROMESH RING
 Roger Magnier, Billancourt, France, assignor to Regie Nationale des Usines Renault and Automobiles Peugeot, Paris, France

Filed Mar. 5, 1969, Ser. No. 806,778
 Int. Cl. F16d 13/66, 13/72

U.S. Cl. 192-107

5 Claims



Splined synchromesh ring of sintered metal for transmission mechanism wherein relatively narrow splines are disposed in the direction of the generatrices of the inner tapered surface, characterized in that said nonmachined splines are compression-calibrated and arranged by groups, and that a relatively shallow depression is provided between two adjacent splines of the same group.

3,578,123

DUAL CLUTCH VALVE INTERLOCKING
 Edward J. Freeland, Hastings, Mich., assignor to Gulf & Western Industries Products Company, Grand Rapids, Mich.

Filed Apr. 17, 1969, Ser. No. 817,101
 Int. Cl. F16p 3/18

U.S. Cl. 192-131

11 Claims

An improved pneumatic-electrical interlocking arrangement for presses comprising an electrical run circuit; a pair of contacts in series in said run circuit; a pneumatic clutch circuit including dual solenoid actuated poppet valves arranged so that if one of said valves should fail the other valve

3,578,121


FRICTION DISC WITH TORSIONAL DAMPENER

Jean Maurice, Paris, France, assignor to Societe Anonyme Francaise Du Ferodo, Paris, France
 Filed Apr. 7, 1969, Ser. No. 814,047
 Claims priority, application France, Apr. 9, 1968, PU147,428
 Int. Cl. F16d 47/02, 3/14

U.S. Cl. 192-106.2


19 Claims

In a clutch friction-unit of the kind comprising a friction disc mounted between two annular plates fixed to each other




Power transmitting devices, such as friction clutches including disengageable friction plates, and having means for sensing the deceleration or acceleration of relatively moving parts and which can be utilized to control the slippable friction clutch and thereby limit the torque peaks transmitted by the clutch and aid in control of input or output speed.

prevents the inadvertent flow of air in said pneumatic circuit; stopping of said mechanical parts until completion of the the solenoids of said poppet valves being connected in said phase of one cycle and control circuit for preventing the flow run circuit; and switch means responsive to the positions of



plunger has been deposited in the vending machine and recorded on the totalizer. If the correct amount of money has

the carriage, means driven by a command signal to fixedly locate the carriage, a braking means driven by a command signal to apply a braking force to the carriage and a control



been inserted, a latch will be released and the plunger will be permitted to continue a full stroke operation, thereby dispensing a commodity from its associated magazine.

3,578,128


TYPE ACTION HAVING LOST MOTION

Kenneth R. Frechette, and Daniel J. Rosborg, Bristol, Conn., assignors to Litton Business Systems, Inc., New York, N.Y.
Filed Oct. 8, 1968, Ser. No. 765,755

Int. Cl. B41j 23/06

U.S. Cl. 197-17

2 Claims



An efficient type action for an electric typewriter characterized by an economy of parts, having a pawl adapted to be pulled into the tooth of a snatch roll by key lever depression, which is coupled to a type bar sublever by a lost motion pin and slot connection. The action is also associated with a resilient energy storing and controlled motion transmitting connection between a power source and the snatch roll.

3,578,129

CONTROL DEVICE FOR POSITIONING CARRIAGES OF BUSINESS MACHINES


Yoshiaki Kato, and Hideya Watanabe, Kamakura-shi, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha
Filed July 22, 1968, Ser. No. 746,406

Claims priority, application Japan, Aug. 30, 1967, 55675/67
Int. Cl. B41j 5/30

U.S. Cl. 197-19

6 Claims

A control device for positioning a carriage of a business machine such as an accounting machine or a typewriter comprises means to detect the present position of the carriage, means to compare a signal produced by the detecting means with a position signal representing a predetermined carriage position a driving means driven by a command signal to drive



means to generate said position signal and to selectively send a control signal to respective ones of said detecting means, comparing means, driving means, locating means and braking means, to locate the carriage in a desired final position.

3,578,130

CARRIAGE RETURN ENERGY ABSORBER


Kenneth R. Frechette, Bristol, Conn., assignor to Litton Business Systems, Inc., New York, N.Y.

Filed Feb. 17, 1969, Ser. No. 799,568

Int. Cl. B41j 19/02, 19/68

U.S. Cl. 197-64

3 Claims



A carriage return drawband load cushioning device having a carriage return drawband guide supported on a pivotally mounted bell crank, the position of which is determined by a spring adapted to yield in response to carriage load at the commencement of carriage return movement and revert to a normal condition only after the termination of carriage return movement.

3,578,131

TYPEWRITER WITH EXTENDED WRITING LINE

William A. Heidt; Leon E. Palmer, and John O. Schaefer, Lexington, Ky., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Nov. 8, 1968, Ser. No. 774,276

Int. Cl. B41j 19/00

U.S. Cl. 197-82

5 Claims

The writing line of a typewriter is extended by combining movements of the paper and of a type element carrier. Incremental letter feed is accomplished by movement of the type element carrier along a writing line past the paper which is normally stationary. Upon reaching an advanced position, the type element carrier is restored in the reverse direction and the paper is advanced to present the next letter space to the type element in its restored position. Continued typing advances the type element carrier incrementally to the end of

the writing line. Operation of a line-return key restores the carrier directly to a new line left-hand margin position, in-

3,578,133

NONREPEAT MECHANISM FOR KEYBOARD



John O. Schaefer, Lexington, Ky., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 15, 1969, Ser. No. 791,420

Int. Cl. B41j 5/08

U.S. Cl. 197-98

11 Claims



dexes the paper to a new line and restores the paper to its original beginning-of-line position.

3,578,132

HALF-SPACE CARRIAGE RETURN MECHANISM FOR TYPEWRITERS

Venanzio Micheletti Cremasco, Banchette, and Domenico Roano, Parella, Italy, assignors to Ing. C. Olivetti & C. S. P. A., Ivrea (Torino), Italy


Filed Feb. 2, 1968, Ser. No. 702,568

Claims priority, application Italy, Feb. 6, 1967, 50454/67

Int. Cl. B41j 19/62

U.S. Cl. 197-91

4 Claims



A half-space carriage return mechanism for typewriters, having a rack secured to the carriage and normally engaged by an escapement dog adapted to be disengaged momentarily from the rack to letter space the carriage, comprises a pawl movable in a first direction to engage the rack and to return the carriage half a space, and means actuatable for momentarily disengaging the pawl from the rack simultaneously with disengagement of the escapement dog when and only when the pawl is in the position in which it has backspaced the carriage through half a space, to cause said carriage to be advanced offset half a space with respect to normal letter spaced positions.

An encoding keyboard having individual reciprocal key-selected interposers, is constructed to eliminate the usual nonrepeat linkage while retaining the nonrepeat function. Each interposer is yieldably guided for movement within a plane, but is permitted limited lateral movement out of the plane to accomplish the nonrepeat function. Each keylever is provided with a laterally inclined cam portion. An operating interposer restores past a "still depressed" key by tilting laterally and thereby prevents an undesired second selection of the same interposer.

3,578,134

FINE ADJUSTMENT MEANS FOR INCREMENTAL FEED MECHANISMS


Ralph L. Parker, Rockville, Conn., assignor to Litton Business Systems, Inc., New York, N.Y.

Filed Oct. 16, 1968, Ser. No. 768,006

Int. Cl. B41j 19/76

U.S. Cl. 197-114

5 Claims



An incremental feed mechanism having a fine or incremental feed control wheel is connected in driving relationship with a drive transmitting hub which is rotatably mounted on a typewriter platen shaft. The hub is formed to provide an eccentric surface for rotatably supporting and transmitting rotary movement to a pair of integrally formed or connected axially spaced spur gears adapted to engage a first inner ring gear formed in a normally stationary line feed indexing ratchet and a second inner ring gear secured to a cylindrical typewriter platen, to thereby drive the cylindrical typewriter platen through minute and irregular arcs proportional to rotary movement of the incremental feed control wheel.

3,578,135


WEB SEVERING AND EJECTION DEVICE

Walter H. Husing, Walnut Creek, Calif., assignor to Shell Oil Company, New York, N.Y.

Filed July 23, 1968, Ser. No. 746,888

Int. Cl. B41j 15/00

U.S. Cl. 197-133



An apparatus for detaching or separating completed multiply copy printed forms as they are discharged from an automatic printing or billing machine. The apparatus includes a main frame for supporting the printed forms and to which is attached a tension-applying pair of rollers at one end and a carriage at the other. The carriage moves transversely across the main frame and severs the printed forms by pulling a cutting line therethrough as it moves across the main frame. The operation of the apparatus is synchronized with the operation of the printing machine and will route the detached form to a designated location.

3,578,136


TYPEWRITER PRINTING MEANS FOR SYMBOLS IN CODED INKS

Robert H. Postal, Clifton, N.J., assignor to American Cyanamid Company, Stamford, Conn.

Filed Sept. 11, 1969, Ser. No. 856,959

Int. Cl. B41j 33/14, 31/05, 35/04

U.S. Cl. 197-151



Symbols in coded inks in which the code in the presence or absence of photoluminescent constituents is effected on a modified teletypewriter mechanism by clipping onto the back of a standard teletypewriter type head a portion of ribbon with separate areas registering with the type heads, each area being impregnated with a coded ink having the proper presence or absence of coded photoluminescent components corresponding to the symbol of the type head. The areas are separated from each other somewhat, as is always the case with the teletypewriter head, and so contamination of the coded ink impregnated in one area with that in another area cannot take place. The teletypewriter head is provided with a

clip frame and the inked ribbon portions are in suitable disposable frames which slide into the clip and are self-registering.

3,578,137

DEVICE FOR GUIDING A RIBBON IN A TYPEWRITER OR SIMILAR MACHINE

Rinaldo Salto, Ivrea, Turin, Italy, assignor to Ing. C. Olivetti & C.S.P.A., Ivrea, Turin, Italy


Filed Sept. 26, 1968, Ser. No. 762,788

Claims priority, application Italy, Oct. 12, 1967, 53320-A/67

Int. Cl. B41j 35/04

U.S. Cl. 197-170

9 Claims



A ribbon vibrator body carries in association with each of two opposite lateral recesses an arm to provide therewith normally two closed ribbon guiding eyes. Said arms are pivotally carried on said body above said recesses for forward swinging movement from closed eye to open eye positions but are under bias to closed eye positions. The arrangement is such that if a ribbon is lowered behind said body at said recesses and then at each side of the body is drawn forwardly, said arms will first yield out of the way of the ribbon and thus will open said eyes to receive the ribbon and then will by the seated bias move to closed eye positions to entrap the ribbon.

3,578,138

PAPER ADJUSTING MECHANISM


Gill Cantwell, Los Angeles, Calif., assignor to Data Products Corporation, Culver City, Calif.

Filed July 18, 1968, Ser. No. 745,796

Int. Cl. B41j 15/16; G03b 1/30

U.S. Cl. 197-133

1 Claim



Apparatus for use with a high speed printer which has four tractors that engage sprocket holes in the paper, to adjust for different paper widths or to adjust the lateral position of the paper. The apparatus comprises a pair of lead screws on each side of the printer, each lead screw coupled to one tractor. A pair of timing belts couple together the two lead screws on each side of the printer so that the tractors on each side move laterally together. A handwheel on the printer can be engaged either with only one belt to laterally move only the pair of tractors on one side of the printer, or with both belts to move all four tractors together.

3,578,139

ARTICLE HANDLING MACHINE UNLOADING MECHANISM


Ronald A. Pearce, Jefferson City, Colo., assignor to Coors Porcelain Company, Golden, Colo.

Filed Sept. 8, 1969, Ser. No. 856,091

Int. Cl. B65g 47/74

U.S. Cl. 198-28

13 Claims



Article handling and unloading mechanism comprising a traveling endless belt having an article supporting surface on which articles are carried to an unloading position, a rotating roller having means thereon for engaging the belt and extending through openings in the belt to project beyond the article carrying surface and to constitute lifting surfaces for lifting articles from the supporting surface when the belt approaches unloading position and transfer them to an article receiving curved plate which is pivotally mounted adjacent the unloading position of the belt for automatically assuming an article receiving position overlying the unloading area of the belt.

3,578,140

CLOSURE FEEDING APPARATUS


Caleb H. Myer, Columbia, and Gregory L. Nicklaus, Lancaster, Pa., assignors to Kerr Glass Manufacturing Corporation, Los Angeles, Calif.

Filed Sept. 16, 1968, Ser. No. 759,847

Int. Cl. B65g 47/24

U.S. Cl. 198-33

8 Claims



Apparatus for feeding and orienting closure caps. Caps in random arrangement on a rotary disc are centrifugally forced to the periphery thereof where they are plowed off into a single layer. Small magnets in the periphery of the disc hold the outermost row of caps which are fed into a discharge chute in single file. Selector means in the discharge chute allow passage of properly oriented caps and discharges the remainder to an orienting means attached to an opening in the chute directly below the selector means. The orienting means turns the caps and passes them to a magnetic conveyor belt which discharges them, properly oriented, onto the periphery of the rotary disc from which they are again fed into the discharge chute.

3,578,141

FILLED BAG SHIFTING DEVICE WITH BAG TURNER


Robert T. Sheehan, 31530 Myrna Road, Livonia, Mich.

Filed Sept. 20, 1968, Ser. No. 761,053

Int. Cl. B65g 47/24

U.S. Cl. 198-33

3 Claims



Pivotally mounted above the framework of a power-driven horizontal endless belt conveyor is a power-driven vertical endless belt bag shifting device adapted to be swung over the horizontal belt conveyor for engagement with filled bags proceeding therealong. Such engagement causes the bag shifting belt to carry the bags across the horizontal conveyor to a discharge ramp or other points of disposal or further transfer. Where it is desired to turn vertically standing bags around their vertical axes as they proceed along the horizontal conveyor, a bag turner is mounted above and on the opposite side of the horizontal conveyor from the vertical bag shifting belt device, the ribbed or otherwise roughened surface of which acts as a fulcrum engaging and retarding the forward travel of one side of the bag while the endless vertical bag shifting belt swings the other side of the bag in a forward direction so as to turn the bag through an angle of approximately 90°.

3,578,142

TOOLING FOR VIBRATABLE BOWL


Warren C. Burgess, Jr., Avon Lake, Ohio, assignor to Burgess & Associates, Inc., Lakewood, Ohio

Filed Mar. 5, 1969, Ser. No. 804,477

Int. Cl. B65g 47/24

U.S. Cl. 198-33AA

1 Claim



There is provided, for use with a vibratable bowl adapted to feed parts from a supply of randomly disposed parts in said bowl, such parts being similarly geometrically configured and having an enlarged portion, e.g. a headed bolt, means coaxing with a track portion of said bowl characterized by adjustability in an axial direction to define an axially adjustable slot adapted to receive a narrower portion of the part and to retain the enlarged portion and to guide the parts to a discharge gate which is characterized by adjustability in a radial direction. Thus, the bowl is adjustable to accommodate parts of varying sizes.

3,578,143

CONTROL SYSTEM


Benjamin W. Woodward, Kenmore, N.Y., assignor to Sperry Rand Corporation, New York, N.Y.

Filed Aug. 22, 1969, Ser. No. 852,232

Int. Cl. B65g 43/00

U.S. Cl. 198—40

9 Claims



A system for automatically controlling mechanized filing equipment including a conveyor for moving one or more article carriers along a predetermined path. Selective carrier positioning for access at a work station is effected by entering appropriate input commands. Corresponding control signals are accordingly initiated that ultimately determine the interval during which the conveyor drive is operative. To this end, coarse and fine control arrangements are interrelated to energize motor drive circuitry and achieve accurate carrier positioning.

3,578,144

CONVEYING ARTICLES


John M. Punzak, West Hartford, Conn., assignor to Monsanto Company, St. Louis, Mo.

Filed Feb. 26, 1969, Ser. No. 802,540

Int. Cl. B65g 17/46

U.S. Cl. 198—41

2 Claims



In a system for transporting articles, such as packaging containers, between work stations by means of an endless conveyor having spaced supports thereon and holders for the articles mounted either directly on the conveyor or on the supports attached to the conveyor, the improvement of utilizing permanent magnets for securing the holders in a readily

releasable manner. A method is provided which requires that the magnetic field be sufficient to resist gravity separation but insufficient to prevent manual separation of the holders from their supports.

3,578,145

TRANSPORT DEVICE


Guenther L. Kuehl, Peekskill, N.Y., assignor to Guenther Systems, Inc., Buchanan, N.Y.

Filed Feb. 11, 1969, Ser. No. 798,366

Int. Cl. B65g 21/12, 67/00

U.S. Cl. 198—115

8 Claims



In the several embodiments of the invention described herein, an adjustable transport device is provided which includes a multiple chain drive system for transporting unit loads of material between a number of vertically and laterally displaced locations. In one embodiment, the device is provided as a truck attachment, and in a second embodiment, the vertical lift is permanently installed in a truck dock. In the third embodiment, a transport device for aircraft and the like carriers is provided with self-adjusting features and a unique platform construction. In a fourth embodiment, a transport device provides perpetual motion bridging for transporting people or material across obstacles and in the fifth and sixth embodiments, telescoping transport devices are provided. In a seventh embodiment, an inverted transport system is provided for transporting unit loads of material between at least three locations.

3,578,146

FILLER FOR BINS


James J. Mehlschau, Davis, Calif., assignor to The Regents of the University of California, Berkeley, Calif.

Filed Oct. 14, 1968, Ser. No. 767,073

Int. Cl. B65g 65/30

U.S. Cl. 198—121

6 Claims



A filler for bins has a supply conveyor with a stationary initial portion and an end portion movable on said stationary portion to lift and lower in a bin in response to a jack con-

3,578,149

BELT CONVEYORS

Charles Thomson, Wokingham, England, assignor to Solar Thomson Engineering Company Limited, Surrey, England


Filed Dec. 1, 1969, Ser. No. 876,201

Claims priority, application Great Britain, Oct. 12, 1967, 16885/67

Int. Cl. B65g 15/62

U.S. Cl. 198—201

4 Claims



A belt conveyor having an endless carrier belt, and endless drive belt in frictional driving engagement with the inner surface of the carrier belt, and support means traveling with the carrier belt, and support along the load carrying flight thereof for supporting the carrier belt in a troughed configuration.

3,578,150

CONVEYING MEMBER FOR INCOHERENT OR POWDERY MATERIALS, ESPECIALLY FOOD FOR POULTRY OR LIKE ANIMALS, AND DEVICE FOR THE MANUFACTURE THEREOF

Camillo Pirovano, Via Monza, 51, Cernusco Lombardone, (Como), and Costante Radaelli, Via Ardigo, 38, Monza, (Milan), Italy

Filed Apr. 22, 1968, Ser. No. 723,199

Claims priority, application Italy, Apr. 22, 1967, Apr. 9, 1968, 15289A/67; 15001A/68

Int. Cl. B65g 33/00

U.S. Cl. 198—213

6 Claims



A conveying member for dispensing food to poultry and like animals is disclosed, which comprises a flexible core made by a steel rope and a helical sheath applied to the exterior of said rope by concurrent extrusion of a thermoplastic material. The helical sheath may comprise a single helix or a plural helix, the helical web being possibly interrupted by notches in order to improve the flexibility. The conveying member is used by placing it, in closed loop, within a tubular casing which is properly perforated at the dispensing points to feed the underlying troughs.

3,578,147

CHAIN CONVEYOR

Robert Benjamin Bolton, 14, Middle Drive, Ponteland, Northumberland, England


Filed Jan. 28, 1969, Ser. No. 794,549

Claims priority, application Great Britain, Jan. 31, 1968, 5002/68

Int. Cl. B65g 45/00

U.S. Cl. 198—171

6 Claims



Improvements in chain conveyors of the type comprising a trough to receive the materials being conveyed, and endless chain to one side of the trough extending therealong between end sprockets, a series of flights spaced along and below the chain and pivotally attached at one end to the chain, there being means adapted to maintain the flights transversely to the trough throughout the driving run of the chain whereby the working parts of the flights cause the materials to flow along the trough and further adapted to cause or permit rotation of the flights about their pivots at the completion of each driving run so that they assume a trailing attitude relative to their pivots during the return run.

The improvements include the provision of a scraper edge arranged at the discharge end of the conveyor so as to closely overlie the flat upper surface of each oncoming flight in a region adjacent its pivot. The flights are withdrawn underneath the scraper edge so that the flat upper surface of each flight passes progressively beneath the scraper edge from said region adjacent the pivot point to the end remote from the pivot.

3,578,148

TRAY AND CONVEYOR ASSEMBLY


Charles P. Pinckard, 1301 E. Morehead St. Suite 15, Charlotte, N.C.

Filed Jan. 27, 1969, Ser. No. 794,302

Int. Cl. B65g 15/00

U.S. Cl. 198—181

10 Claims



A multitiered conveyor tray for facilitating serving tray assembly having a base, side and end walls for retaining articles on each tier level for travel along a directed path of travel on a conveyor to expose selected tiers to various treatment.

3,578,151

SHEET CONVEYOR SYSTEM


John H. Crawford, Corvallis, Oreg., assignor to Leading Plywood, Corvallis, Oreg.

Filed Nov. 29, 1968, Ser. No. 780,061

Int. Cl. B65g 45/00

U.S. Cl. 198-230

3 Claims



A conveyor system is disclosed for the transfer of sheet material. The traveling components comprise a multitude of replaceable elastic members each identically entrained about powered roller means. The system presently disclosed is adapted for conveying sheet material which is to be treated while being conveyed with additional structure being disclosed for cleaning of the elastic conveyor components. Toward this end a rinse is provided for the conveyor components along with means for removing water particles from said components prior to their again receiving delivered sheet material to be treated.

3,578,152

SHELL CARTON


Daniel W. Hartley, 1820 Bexley St., North Charleston, S.C.

Filed July 2, 1969, Ser. No. 838,510

Int. Cl. F42b 39/00

U.S. Cl. 206-3

10 Claims



A carton for packaging articles such as shells for shotguns comprising a pair of complementary half sections of plastic material detachably interconnected to form a carton with a plurality of shells removably supported on each half section and with tie straps on the ends of each half section for tying a detached half section around a wearer's waist thereby exposing the shells for convenient access and removal by the wearer.

3,578,153

DRILL HOLDER DEVICE

John L. Olson, 1300 Birch St., North Branch, Minn. 55056

Filed Aug. 7, 1969, Ser. No. 848,305


Int. Cl. A45c 11/26

U.S. Cl. 206-17

6 Claims

A drill holder device includes a bracket which is attachable to the inside surface of the cover of a tool box. A drill container is pivoted to the bracket and the container has a plurality of openings therein, each opening receiving a different

size drill therein. Each drill projects exteriorly from the container, and a retainer is pivotally mounted on the drill container and prevents the drills from falling from the container when the tool box cover is closed. However, the drill con-



tainer will swing away from the retainer when the tool box cover is in the fully open position, thereby permitting ready removal and replacement of the drills with respect to the container.

3,578,154

SHADOW BOX WITH LOCKING DUST FLAPS


Homer Martelli, Westwood, N.J., assignor to Union Camp Corporation, New York, N.Y.

Filed Apr. 7, 1969, Ser. No. 813,842

Int. Cl. B65d 5/50, 5/10

U.S. Cl. 206-45.14

1 Claim



A carton is formed from a precut and prescored blank to provide a hollow body having front and rear panels joined by side panels, and ends closed by interlocking flap means. One end, usually the top, is closed by two infolded dust flaps and an overlying tuck-in flap means. Each of the dust flaps has a recess cut into the edge facing the front panel so as to form inner and outer tabs along that edge. The tuck-in portion of the overlying flap has a recess or opening cut into it to provide two tab formations. When the flaps are infolded to close the carton, each of the tab formations on the tuck-in portion fits into the recess of its associated dust flap. A locking slit is formed at each end of the score line which hinges the tuck-in portion of the overlying flap, which slits interlock with the outer tab on each of the dust flaps upon full insertion of the tuck-in portion. The erected carton may be converted into a shadow box for displaying the merchandise by separating the front panel into two portions and folding such portions and the top locked flap means inwardly, whereby a mitered frame effect is formed in back of the displayed merchandise.

3,578,155

DISPOSABLE PRODUCT

Rudolph E. Small, and John J. Bradley, Green Bay, Wis., assignors to Paper Converting Machine Company, Green Bay, Wis.

Filed Feb. 24, 1969, Ser. No. 801,407


Int. Cl. B65d 85/67

U.S. Cl. 206-56

4 Claims

A disposable product such as a diaper characterized by having a generally trapezoidal configuration and made up of

outer sheets confining a generally rectangular fluff pad, the product sheets being united to confine the pad and per-



forated along generally straight lines to define detachable products.

3,578,156

CONTAINER FOR A REEL

Carl J. Norby, Boulder, Colo., assignor to International Business Machines Corporation, Armonk, N.Y.

Continuation of application Ser. No. 692,337, Dec. 21, 1967,


now abandoned. Filed Sept. 29, 1969, Ser. No. 869,438

869,438

Int. Cl. B65d 85/67

U.S. Cl. 206-52F

8 Claims



A container having a base member, a cover member and a locking mechanism for releasably locking the members together. A locking mechanism having a keeper, latching fingers for releasably engaging the keeper, and a pushbutton to release the fingers from the keeper.

3,578,157

DISPENSING CARTRIDGE


Laszlo Hidassy, Elizabeth, N.J., assignor to Thomas & Betts Corporation, Elizabeth, N.J.

Division of Ser. No. 705,046, Feb. 13, 1968, Pat. No. 3,515,178. Filed Oct. 24, 1969, Ser. No. 869,303

Int. Cl. B65d 83/00

U.S. Cl. 206-56AC

7 Claims



The cartridge of the invention is composed of two arcuate portions joined at their longer arcuate length and open at

their shorter arcuate end to allow the articles stored therein to extend beyond the cartridge and to permit a feed mechanism to enter the cartridge and eject the articles therein. Expanded areas permit acceptance of the wider head portion of the articles and removable plugs placed therein provide for article alignment and packing as well as a simple way to permit removal of the articles in the cartridge.

3,578,158

ARTIFICIAL FINGERNAILS FOR WEAR

Eric Victor Aylott, Welwyn Garden City, England, assignor to Eylure Limited, Welwyn Garden City, England


Filed Mar. 3, 1970, Ser. No. 16,248

Claims priority, application Great Britain, Mar. 4, 1969, 11,395

Int. Cl. B65d 71/00

U.S. Cl. 206-65K

6 Claims



A unit of self adhesive fingernails connected to a stepped base member by a neck only the arrangement being such that several units may be stacked one on top of the other without the nails coming into close contact with one another.

3,578,159

DOCUMENT-HANDLING APPARATUS


Everet F. Lindquist, and George E. Carsner, Iowa City, Iowa, assignors to Westinghouse Learning Corporation

Filed Feb. 18, 1969, Ser. No. 800,110

Int. Cl. B07c 5/00

U.S. Cl. 209-74

13 Claims



An arrangement for identifying particular documents, which are selected according to predetermined criteria, from other documents contained in a stack at the output end of an apparatus through which the documents were separately conveyed for processing or other purposes. The arrangement permits immediate identification in the output stack of the documents so selected without physically removing them from the stack and without disturbing the order of the documents as originally fed to the apparatus.

3,578,160

PROCESS AND APPARATUS FOR SEPARATING ARTICLES

Peter Albert Martini, Naupliastrasse 7, Munich, Germany

Filed Oct. 10, 1968, Ser. No. 780,924


Int. Cl. B07c 5/344

U.S. Cl. 209-81

10 Claims

Process and device for separating potatoes from impurities such as clods and stones. The process consists of contacting

the items to be examined by a pair of spaced feelers which are connected with a measuring device for determining capacity and ohmic conductivity of the items being tested.



Various mechanical arrangements are provided for sequentially presenting test articles and for mechanically sorting or distributing the test articles responsive to the test results.

3,578,161

MACHINE FOR SIZE-GRADING WALNUTS


Hugh Perry Barton, Modesto, Calif., assignor to R. P. Barton & Company, Escalon, Calif.

Filed July 3, 1969, Ser. No. 838,761

Int. Cl. B07c 5/06

U.S. Cl. 209-86

9 Claims



A machine, for size-grading walnuts (i.e. separating one size from another), comprising a plurality of rotary sizing reels or grate-bar-type trommels arranged on a supporting frame in a manner such that—selectively—any one of the trommels can be brought to a working position between a feed chute and carry-off conveyors mounted on such frame; the individual trommels, each relative to the others, having different spacing between the grate-bars whereby the machine can be set to size-grade walnuts which have different average sizes depending on the variety being processed.

3,578,162

BENEFICIATION OF MAGNESIAN ORES OR THE LIKE

Tage L. B. Jepsen, Gabbs, Nev., assignor to Basic Incorporated, Cleveland, Ohio

Continuation of application Ser. No. 725,526, Apr. 30, 1960, now abandoned. Filed Oct. 1, 1969, Ser. No. 862,979

Int. Cl. B03b 3/44

U.S. Cl. 209-172

8 Claims

Beneficiation of magnesian ores and similar derivative mixtures for concentrating or upgrading the magnesium content, usually by removal of the undesired constituents. Such mixtures after size reduction to obtain desired liberation of constituents are subjected to float and sink separations in heavy media having a gravity intermediate the float and sink constituents. Mixtures include magnesite, brucite, hydromag-

nesite and dolomite ores and synthetic mixtures of CaCO_3 and hydrated magnesium carbonates with tetrabromoethane, methylene bromide, trichloroethylene, carbon tetrachloride and methylene iodide as heavy media diluted with lighter organic liquids as necessary to establish optimum specific gravity. Movement of material in separation zone causes lighter fraction to float to surface of media while heavier fraction penetrates media and is recovered as an underflow product.

3,578,163

METHOD AND APPARATUS FOR PRECOATING FILTER LEAVES


Theodore J. Warning, Walnut, Calif., assignor to U. S. Filter Corp., Whittier, Calif.

Filed Mar. 24, 1969, Ser. No. 809,757

Int. Cl. B01d 37/02

U.S. Cl. 210-75

19 Claims



A layer of precoat material is applied to a rotary filter leaf prior to the filtration process. Filter cake accumulates on the leaf during filtering operations, and at the end of the filtration cycle the cake is removed by an adjustable knife blade so that the precoat layer remains on the leaf. The precoat material is then sluiced from the leaf, reslurried, and reapplied to the leaf to serve as the precoat layer for the next filtration cycle.

3,578,164

WATER SOFTENING CONTROL


Jonas Weiss, Plainfield, and William Hodes, Edison, N.J., assignors to American Standard Inc., New York, N.Y.

Filed May 14, 1968, Ser. No. 728,937

Int. Cl. B01d 15/04, 19/06

U.S. Cl. 210-96

4 Claims



In a water-treating apparatus comprising in combination cation-exchange means for removing divalent cations from water to be treated and substituting for the divalent cations, cations selected from the group consisting of hydrogen ions and sodium ions, anion-exchange means for removing divalent anions from the water and substituting for the

anions, anions selected from the group consisting of hydroxyl ions and chloride ions, sensing means consisting of a contractile fiber having a length dependent on the concentration of calcium ions in the water and located in the apparatus in the flow stream of the water at a point downstream of at least a portion of the cation-exchange means, the sensing means being sensitive to the concentration of calcium ions in the water, means for regenerating the cation-exchange means and the anion-exchange means, and means responsive to the sensing means for activating the regenerating means in response to a predetermined level of calcium ion concentration in the water, the improvement in the water-treating apparatus comprising as the sensing means a water insoluble contractile fiber composed of polymers containing non-hydrolyzable groups which groups are selected from the group consisting of carboxy, primary, secondary and tertiary amines and imine.

3,578,165

METHOD AND APPARATUS FOR MANUFACTURING RADIALLY FINNED HEAT EXCHANGE TUBING


Robert C. Boose, Pryor, Okla., assignor to Escro Fintube Corporation, Pryor, Okla.

Filed Mar. 3, 1969, Ser. No. 803,598

Int. Cl. B23k 9/02

U.S. Cl. 219-107

14 Claims



A method and apparatus are disclosed for manufacturing radially finned heat exchange tubing. In accordance with the method, one end of a solid metal L-shaped strip is initially secured to the outer periphery of the tube. The foot of the strip is directly urged against the tube at a plurality of points in advance of a welding station, as for example, by forming rollers. The welding station is energized to continuously weld the foot of the strip to the tube while the tube is rotated and advanced longitudinally. The apparatus disclosed includes a plurality of adjustable forming rollers mounted approximately in the plane of the welding station. Each of the forming rollers includes an annular slot for receiving and guiding the leg of the metal strip in a plane perpendicular to the axis of the tube. The edges of the rollers are disposed adjacent the outer periphery of the tube so that the foot of the strip is forced against the tube as it travels over the guide rollers.

3,578,166

SEPTIC TANK FOR WASTE DISPOSAL SYSTEM


Peter V. Paulus, Port Clinton, Ottawa, and Harry W. Green, North Olmsted, Ohio, assignors to The Standard Products Company, Cleveland, Ohio

Filed Mar. 17, 1969, Ser. No. 807,627

Int. Cl. C02c 1/26

U.S. Cl. 210-110

2 Claims



An improved septic tank having a pair of waste receiving chambers with one chamber being connected to the other by

a drain pipe whereby liquid wastes from one chamber may drain over to the other after the bacteriological treatment has been completed.

3,578,167

MULTIPLE-TANK WATER CONDITIONING SYSTEM AND VALVE THEREFOR


Willis E. Clack; Clifford Kay, and Charles E. Nygren, Madison, Wis., assignors to Clack Corporation, Madison, Wis.

Filed Nov. 19, 1968, Ser. No. 776,925

Int. Cl. B01d 29/08

U.S. Cl. 210-134

2 Claims



A pair of water conditioning tanks each having a service port. The service ports are connected to each other and to a service outlet conduit. A pair of semibalanced, direct-acting control valves are provided, each having an inlet port, a tank port connected to one of the conditioning tanks, and a drain port. Each valve has a pressure responsive piston engaging the valve stem and a conduit for supplying line pressure to the piston to assist in operating the valve. Timed motor operators alternately maintain one of the valves in service position and the other in backwash position whereby each tank can be backwashed with conditioned water from the other.

3,578,168

REFRIGERATING APPARATUS HAVING OIL-SEPARATING MEANS


Whitney I. Grant, Muskego, Wis., assignor to Vilter Manufacturing Corporation, Milwaukee, Wis.

Filed June 25, 1969, Ser. No. 836,390

Int. Cl. B01d 50/00

U.S. Cl. 210-167

6 Claims



A refrigerating system having a compressor which delivers refrigerant to a condenser and an oil separator is interposed between the compressor and condenser. The oil separator includes a layer of asbestos and a screen mesh layer, the mesh layer functioning as a channel or path in which the oil can flow downwardly by gravity to thereby be separated from the vapor.

3,578,169

REVERSE-FLOW AQUARIUM FILTER DEVICE

Eugene B. White, Oak Park, Ill., assignor to Ken-Flo Products Corporation, Palos Heights, Ill.

Filed Mar. 7, 1969, Ser. No. 805,274


Int. Cl. E04h 3/20

U.S. Cl. 210-169

20 Claims

An aquarium water purification system employing a tertiary filter cycle utilizing a shallow gravel-trickling filter with

underwater aeration and sedimentation followed by anaerobic action and final tertiary cycle, in a filter structure having



the filter material thereof disposed in a removable replaceable cartridge.

3,578,170

APPARATUS FOR DETECTING INCLINATION OF FILTER PLATES IN TRANSIT


Ken-Ichiro Kurita, 36-4, 5-chome, Senriyama-nishi, Suita, Osaka Prefecture, Japan

Filed Jan. 12, 1970, Ser. No. 002,267

Int. Cl. B01d 25/00

U.S. Cl. 210-230

4 Claims U.S. Cl. 210-321



A prevention apparatus is for use in a filter press provided with a group of filtering elements supported between a stationary end plate and a movable end plate and adapted to be released horizontally for the removal of cake or to be compressed together for filtration. Disposed at least along one side of the group of filtering elements is a detecting line employing a light beam, lead wire or wire rope which has linearity in parallel with the direction of movement of the filtering elements. A blocking member is mounted on each of the filtering elements in corresponding relationship with the detecting line. When the filtering element is inclined due to some trouble during transit, the detecting line is interfered with by the blocking member to halt the transport of the filtering elements or give a warning.

3,578,171

APPARATUS FOR REMOVING FLOATING POLLUTANTS


David Usher, 9010 Roselawn Ave., Huntington Woods, Detroit, Mich. 48204

Filed Apr. 2, 1969, Ser. No. 812,780

Int. Cl. B01d 21/00

U.S. Cl. 210-242

3 Claims



Apparatus for removing oil and other floating pollutants from a body of water employing a barge which consists of means for encompassing a slick and confining it to prevent lateral spreading, skimming and withdrawing the pollutant under vacuum to a storage area on a barge, pumping into settling tanks and simultaneously siphoning off the water; and

transporting a barge and its pollutant removal equipment by one from the group consisting of air, truck and rail, to any remote point for emergency use.

3,578,172

APPARATUS FOR REMOVING TOXIC SUBSTANCES AND EXCESS WATER FROM THE BLOOD

Maria Gavrilovna Sirotkina, Prospekt Mira, 180, Kv. 193, Moscow; Jury Gotlibovich Kozlov, Khoroshevskoe shosse, 11, kv. 47; Alevtina Vasilievna Alexeeva, Botanichesky proezd, 3a, kv. 16; Ljudmila Alexeevna Afanasieva, Anadyrsky proezd, 1, kv. 78; Galina Nikolaevna Benyash, Khutorskaya ulitsa, 7, kv. 28; Efim Bentsionovich Gorbovitsky, 4 Vishnyakovsky proezd, 5, korpu, 4, kv. 27; Ljudmila Alexeevna Levitskaya, Kotelnicheskaya naberezhnaya, 25 kv. 5; Galina Konstantinovna Lisitsina, Ulitsa Molditsova, 9, kv. 7; Anatoly Stepanovich Tkachenko, ulitsa Iva Tolstogo, 5, kv. 7, Pushkino, Moskovskaya obl., and Adolf Iserovich Khaitlin, Bolshevistsky pereulok, 13/3, kv. 13, U.S.S.R.


Filed June 7, 1968, Ser. No. 735,322

Claims priority, application U.S.S.R., Sept. 25, 1967, 1,186,150

Int. Cl. B01d 31/00

U.S. Cl. 210-321

4 Claims



An apparatus for removing toxic substances and excess water from blood being intended for treating chronic cases of renal insufficiency. In contrast to the devices known in the art, the present apparatus provides an effective normalization of aqueous-electrolytic balance and elimination of toxic products of metabolism when it is not necessary to introduce the donor blood for the initial filling of the blood conveying system. In said apparatus, the resistance of the blood conveying system of the dialyzer is reduced. The elements of the blood conveying system are sterilized by oil boiling or treating in an autoclave.

3,578,173

FOLDED SEMIPERMEABLE MEMBRANE

Robert John William Streeton, Harwell, England, assignor to United Kingdom Atomic Energy Authority, London, England


Filed Nov. 21, 1968, Ser. No. 777,784

Claims priority, application Great Britain, Nov. 24, 1967, 53565/67

Int. Cl. B32b 3/04; B01d 39/16

U.S. Cl. 210-321

4 Claims



A semipermeable membrane is made by casting on a ridged casting plate so that the rear surface of the membrane

is grooved and it can be supported by a rigid impervious backing plate. Alternatively the membrane may be folded (at an angle to the grooves) so as to be self-supporting.

3,578,174

FLUID-FLOW PUMP


Susanna Mikhailovna Karpacheva, 2 Schulinsky proezd, 2, kv. 88; Leonid Solomonovich Raginsky, Nikitinskaya ulitsa, 16 korpus kv. 29; Valerian Matveevich Muratov, Astakhovskiy pereulok, 1/2, kv. 1; Vladimir Dmitrievich Ivanov, 2, Schulinsky proezd 11, kv. 6, Moscow, and Jury Nikolaevich Baulin, ulitsa Parkovaya, 5, kv. 120, Balashikha Moskovskoi oblasti, U.S.S.R.

Filed July 19, 1968, Ser. No. 746,092

Int. Cl. B01d 35/26

U.S. Cl. 210-416

3 Claims



A pump comprises a pulsation chamber from which liquid is ejected through a nozzle apparatus into a discharge chamber and a discharge pipe. A fluid inlet pipe opens into the discharge chamber beneath the nozzle apparatus and coaxially therewith to supply liquid under suction pressure. The nozzles of the nozzle apparatus are placed tangentially so that the liquid from the pulsation chamber moves with rotary motion from a center to the periphery. The pump is used in a filter apparatus by placing the pump in a body containing a filter element, the body forming the discharge chamber and the discharge pipe.

3,578,175

HELICALLY WOUND SEMIPERMEABLE MEMBRANE


Serop Manjikian, Del Mar, Calif., assignor to Universal Water Corporation, Del Mar, Calif.

Filed Apr. 23, 1969, Ser. No. 818,514

Int. Cl. B01d 31/00

U.S. Cl. 210-489

11 Claims



A membrane element, useful in treatment of a solution by osmosis or reverse osmosis, comprises a porous support structure around which is a semipermeable membrane preferably formed by helically winding a strip of semipermeable membrane material. The edges of adjacent turns of membrane strip are preferably overlapped and the overlapped portions are bonded together as by use of adhesive, or solvent bonding. An intermediate layer of porous backing material may be employed between the support structure and the membrane, and this can be formed by helically winding a strip, for example, of nylon cloth, preferably with contiguous edges abutted. The support structure may be of circular cross section outline, or may be of polygonal outline. A helically wound backing layer may be employed with a membrane cast on its surface.

3,578,176

FILTER DISC


Kenneth W. Cuyler, Deerfield, Ill., assignor to William W. Nugent & Company, Inc., Skokie, Ill.

Filed May 8, 1969, Ser. No. 823,098

Int. Cl. B01d 29/34

U.S. Cl. 210-492

4 Claims



For use in a stack of axially aligned and axially compressed discs of filtering material having circumferentially spaced and alternating inlet and outlet openings communicating through inlet and outlet passageways respectively with the outer peripheries and central apertures of the discs, a disc in which the inlet and outlet openings are shaped and sized to avoid collapse of adjacent discs into the outlet openings and the outlet passageways and to provide a large sealing pressure at the overlapping surfaces of adjacent discs to prevent liquid being filtered from passing between the discs of filter material.

3,578,177

STORAGE RACK FOR LEVELING JACKS


Ray Wellington Paden, R. D. #1, Nescopeck, Pa.

Filed Feb. 19, 1970, Ser. No. 12,674

Int. Cl. A47f 7/00

U.S. Cl. 211-49

10 Claims



A special rack for storing a set of leveling jacks of the type including a hollow tapered stand with side openings and a top aperture removably receiving an adjusting screw. The rack consists of a base with a vertical shaft, a set of jack stands being nested on the base so that the shaft passes through the top apertures thereof and a retaining nut on the shaft serves to hold the nested stands against the base. Supporting elements for the jack adjusting screws are provided on the base around the shaft and support the screws which extend upwardly and outwardly through the side openings of the nested stands.


3,578,178

ADJUSTABLE OUTFEED ASSEMBLY FOR STATIONERY BURSTER

Howard K. Absler, Skokie, and Leonard M. Narel, Cary, Ill., assignors to Uarco Incorporated
Division of Ser. No. 645,262, June 12, 1967, Pat. No. 3,493,156. Filed May 2, 1969, Ser. No. 862,538
Int. Cl. A47f 7/00

U.S. Cl. 211—50

3 Claims



A stacking tray for use with a stationery burster, the stacking tray having a fixed medial portion flanked by portions movable with respect to the remainder thereof to accommodate uneven marginal areas of stationery dispensed thereon.

3,578,179


PORTABLE JIB CRANE

Richard T. Fujioka, Oxford, Mich., assignor to Fruehauf Corporation, Detroit, Mich.

Filed Jan. 16, 1969, Ser. No. 791,589
Int. Cl. B66c 23/02

U.S. Cl. 212—61

10 Claims



A support portion includes depending pins at the upper end thereof for fitting within a hole in a corner casting of an associated structure such as a container or the like. A locking bar and a spaced retainer member are carried at the lower part of the support portion and engage a corner post portion of the associated structure for holding the support portion in place. A load-carrying portion is swingably carried by said support portion, the load-carrying portion including a horizontally extending member having means at the outer end for carrying a load.


3,578,180

CAR COUPLER CENTERING DEVICE

William J. Metzger, Cleveland, and Kenneth L. DePenti, Mayfield Heights, Ohio, assignors to Midland-Ross Corporation, Cleveland, Ohio
Filed Dec. 19, 1968, Ser. No. 785,225
Int. Cl. B61g 7/12

U.S. Cl. 213—20

18 Claims



A railway car coupler centering device for maintaining an uncoupled car coupler centered in relation to the associated vehicle body center sill structure. The device automatically returns the shank of the coupler to a central position within the coupler housing after the coupler has been shifted laterally in either direction. The device includes a release mechanism which, when actuated, inactivates the centering units of the device when coupler alignment requires an uncoupled coupler to be manually moved to an off-center position for car coupling operations, as on a curved section of track. The device also includes mechanism for automatically reengaging the centering units, after they have been inactivated, once the shank of a laterally displaced coupler is returned to its central position.

3,578,181


PARTS STACKER

Francis H. Hughes, and Douglas J. Crawford, Troy, N.Y., assignors to Cluett Peabody & Co., Inc., Troy, N.Y.

Filed Mar. 24, 1969, Ser. No. 809,628
Int. Cl. B65g 57/06

U.S. Cl. 214—6

2 Claims



A parts stacker particularly useful for handling limp fabrics, especially garments parts such as shirt sleeves, and including relatively narrow supports having low friction surfaces. The supports are retractable and cooperate with belts which engage the surfaces and feed the parts onto them.


3,578,182

LUMBER CART HAVING CRADLE WITH VARIABLE HEIGHT

Edward M. Harvey, 200 Meadowbrook, Hot Springs, Ark.
Filed Oct. 2, 1969, Ser. No. 863,061
Int. Cl. B65g 57/03

U.S. Cl. 214—6

4 Claims



A lumber cart for use in the lumber industry such as a sawmill for receiving lumber pieces one at a time from a conveyor such as a lumber sorter, which categorizes lumber into categories having identical dimensions. The cart includes a rectangular frame supported on four wheels adapted to ride on rails, four stanchions positioned one at each corner and a winchlike mechanism having two spools for winding wire rope cable onto and a brake band and drum portion which creates holding action of the spools stopping rotation of the spool assembly when the brake band is allowed to engage the brake drum. The wire rope cable is arranged between the two forward stanchions and the two rearward stanchions in such a manner that the slack in the suspended cable forms a cradle for receiving the lumber pieces at an elevation near the uppermost portion of the stanchions and the winchlike mechanism enables the cradling portion of the cables to slipingly change elevation downwardly to variable heights. Two of the stanchions, one fore and one aft both being on the same side of the cart, are pivotally attached to the frame allowing them to articulate outwardly facilitating unloading.

3,578,183


METHOD AND APPARATUS FOR CONVEYING MATERIAL

Nelson N. Larger, Salisbury, Md., assignor to A. W. Perdue & Son, Inc., Salisbury, Md.

Filed Mar. 3, 1969, Ser. No. 803,584
Int. Cl. B65g 65/42

U.S. Cl. 214—17

17 Claims



Unloading material such as ice from a storage room by gradually moving a vertical conveyor horizontally against a

supply of ice to raise portions of the ice and deposit the same at the top of the conveyor into a chute mounted on the conveyor to convey the ice downwardly onto a horizontal conveyor which leads out of the storage room. A plurality of bucket members are secured to vertically movable endless drive members in the vertical conveyor for picking up, raising and then discharging portions of the ice into the chute, the bucket members also having a plurality of prongs for scarifying the ice. The vertical conveyor is moved against the ice by means of an overhead trolley from which the conveyor is suspended, the overhead trolley being movable along a horizontal track under the power of a motor which also is employed to drive the endless members. In one embodiment, an agitating mechanism is mounted on the top of the vertical conveyor to be movable therewith by means of the trolley.


3,578,184

ARTICLE HANDLING METHOD AND APPARATUS
Wilbur A. Schaich, Maumee, Ohio, assignor to Owens-Illinois, Inc.

Filed Mar. 20, 1969, Ser. No. 808,887
Int. Cl. B65g 67/02

U.S. Cl. 214—38

8 Claims



Methods and apparatus for transporting and handling relatively large articles of uniform size, as for example, loaded pallets. A boxlike unit load container, of a size corresponding generally to that of the cargo portion of a conventional semitrailer, is constructed with an open framed gridlike bottom having openings of lesser dimensions than those of the bottoms of the individual articles or pallets so as to support the articles with a major portion of the bottom surface of the article overlying and exposed through one or more of the openings in the container bottom. A shipping or receiving dock platform is provided with a conveyor system with a terminal group of conveying elements arranged in a pattern corresponding to that of the openings in the unit load container bottom so that the conveying elements can project or be projected upwardly through the openings in the container bottom to an elevation above the article supporting surface of the bottom when the container is at rest on the dock platform. The conveying elements thus enable the articles or loaded pallets to be conveyed into or out of the unit load container. The container is provided with means for detachably securing it onto the bed of a trailer frame for over-the-road transport and the securing means can also be employed to secure the container to a lifting sling.

3,578,185

MECHANIZED VEHICLE SYSTEM


David F. Black, Salt Lake City, Utah
Filed Sept. 9, 1969, Ser. No. 856,409
Int. Cl. B60p 1/52

U.S. Cl. 214—38

7 Claims

A mechanized system for the automatic loading and unloading of a vehicle of the front loading type. The vehicle is provided with a cab which will swing 90° to the left thereof

and a bed which is movable longitudinally on the vehicle's chassis. Powered rollers on the floor of the bed move the cargo into or out of the vehicle. A switch in front of the vehicle's cab will activate means to open the door of a warehouse when the cab is in close proximity to the



warehouse dock. The cab is swung to the left of the vehicle and the bed moved onto the dock to the warehouse door. All operations are controlled by the driver and he is protected from inclement weather at all times. The system eliminates the need for fork lifts in loading or unloading.

3,578,186

VEHICLE UNLOADER


Henry D. Thomas, 16180 Markese Ave., Allen Park, Mich.

Filed Apr. 10, 1969, Ser. No. 815,136

Int. Cl. B60p 1/36

U.S. Cl. 214-83.22

14 Claims



A pusher and a floor belt in a dump box of a vehicle for unloading or dumping material from the dump box. The pusher and the belt are moved longitudinally through the dump box by a winch and interconnecting cables. Batch boards and a tailgate are also carried by tracks connected to the dump box to provide separate compartments for carrying individual batches of material. In one modification the tracks are arranged so that the tailgate and sequentially each batch board can be moved to the rear of the dump box beyond the floor belt so that the material on the belt will be discharged from the dump box as the pusher is moved toward the rear of the box.

3,578,187

INSTALLATION FOR THE PREFABRICATION OF CONSTRUCTION ELEMENTS

Jean Charles Stribick, 7, Cours, Hippolyte Saiezea, Saint-Etienne, Loire, France

Filed Mar. 19, 1968, Ser. No. 808,451

Claims priority, application France, Mar. 21, 1968, 68143


Int. Cl. B23g 5/22

U.S. Cl. 214-89

4 Claims

An installation for the prefabrication of construction elements is provided with translating elements such as rails forming in a base plane various conveyor lines for pallets carrying elements and molds for the elements. At operating stations along the conveyor lines is a lifting device for raising the pallets to upper operating stations and lowering them. The lifting device has a shoe for each corner of a pallet. The shoe is fixed to a nut screwed on a vertical screw which is rotated by a horizontal shaft and bevel gears, driven by a central motor. Operations of long duration can thereby be

performed at upper stations while pallets not requiring such operations can continue to circulate along the conveyor



3,578,188

BUCKET ACTUATED MEANS FOR EXCAVATOR

Gotthardt Drieschner, Dortmund-Wellinghofen, Germany, assignor to Orenstein-Koppel Aktiengesellschaft, Dortmund-Dorstfeld, Germany

Filed Oct. 22, 1968, Ser. No. 769,653


Claims priority, application Germany, Oct. 26, 1967,

P 16 34 921.6

Int. Cl. E02f 3/74

U.S. Cl. 214-138

9 Claims



A power transfer mechanism for excavator bucket operation by fluid actuator means effective upon a working point, to which a rocker arm is journaled from a dipper arm pivot located above the turning axis of the bucket and to which a coupling member is journaled from a bucket pivot located below the turning axis of the bucket. A bucket front portion is tiltable during bucket opening and closing with respect to a turning point shaft in radial alignment with semicircular formed guide slot means of a box-formed housing of the bucket back portion. A housing cover provides access to parts including fluid actuator means protected in the box-formed housing and used to effect tiltable movement of the front portion with respect to the back portion of the bucket.

3,578,189

METHOD FOR ORIENTING AND ASSEMBLING SMALL PARTS

John L. Yonkers, 2030 Sunset Ridge Road, Northbrook, Ill. Division of Ser. No. 498,710, Oct. 20, 1965, Pat. No. 3,468,024. Filed Dec. 26, 1968, Ser. No. 839,738


Int. Cl. B65g 1/00

U.S. Cl. 214-152

3 Claims

This invention relates to a method of orienting and gauging the internal and external diameters of small hollow parts. To carry out this method, a gauge plate having a plurality of up-standing gauge pins is provided. An orienting plate having a plurality of openings is placed over the gauge plate with the pins extending through a respective one of said openings. A random supply of said parts is placed over the said orienting plate which is then vibrated to simultaneously fill a majority

of said openings with the hollow parts fitted over the gauge pins. The orienting plate is then removed and a transfer plate having a plurality of transfer cavities is assembled against the gauge plate with the parts supported on the gauge pins being



received in said transfer cavities. The assembly of said transfer plate and said gauge plate is inverted so that the parts move into the transfer cavities and the assembly is then separated.

3,578,190

MULTIPURPOSE TRAILER

Joe C. May, 139 Calhoun St., Biloxi, Miss., and James D. Lowery, Jr., 127 T Pass Road, Jackson, Miss.

Filed July 7, 1969, Ser. No. 839,485

Int. Cl. B60p 3/10

U.S. Cl. 214-505

13 Claims



A multipurpose trailer particularly adapted for use as a combination boat and dog/utility trailer in which a separable frame is provided for supporting a boat on a running gear for the transporting thereof, as well as independently of the running gear for the storage thereof. A method for mounting and dismounting the separable frame from the running gear with a boat thereon is also disclosed.

3,578,191

LOADER LINKAGE

Rodolf Horsch, Burlington, Iowa, assignor to J. I. Case Company

Filed Oct. 13, 1969, Ser. No. 865,819


Int. Cl. B66f 9/00

U.S. Cl. 214-771

9 Claims

In a material handling device of the type in which lift arms are pivotally mounted on a support and pivotally carry a bucket controlled by a hydraulic circuit including a bucket cylinder arranged to provide maximum hydraulic force for break out or rollback of the bucket and maximum speed for the dumping or forward roll of the bucket, an automatic self-leveling and antirollback linkage connected between the bucket and the support including a first member pivotally connecting the cylinder to the lift arms and a second portion including three members pivotally connected end to end and having one end pivotally connected to the bucket, the other end pivotally connected to the support and the middle member pivotally connected to the cylinder. The linkage connects the bucket to the bucket cylinder to effect pivoting

of the bucket upon operation of the bucket cylinder, levels the bucket relative to the ground and prevents rollback of



the bucket past its level position when the lift arms are raised.

3,578,192

TAMPERPROOF CAP FOR RECEPTACLE

Hans Sonne, 4534 Horve, Denmark

Filed June 25, 1969, Ser. No. 836,321

Claims priority, application Denmark, Jan. 31, 1969, 545/69

Int. Cl. A61j 1/00; B65d 55/02

U.S. Cl. 215-9

5 Claims



The invention relates to tamperproof receptacles provided with a rotatable cap, the latter having an annular recess for reception of a flexible band that includes a latch and a manual control therefor, said latch cooperating with dimples on the neck of the receptacle to permit either free relative movement of the cap on the receptacle for complete removal or prevent movement thereof depending upon the position of the manual control.

3,578,193

SAFETY STOPPER

Maurice Steiner, 40bis avenue de Suffren, 75 Paris 15, France


Filed June 17, 1969, Ser. No. 834,039

Claims priority, application France, June 19, 1968, 155,633

Int. Cl. A61j 1/00; B65d 55/02, 39/00

U.S. Cl. 215-9

4 Claims



Safety stopper having a recess of the general shape of a glove finger so that the user may insert his finger therein and an outer wall adapted to be introduced into the top portion of the container to be closed and provided with at least one element adapted to cooperate with a corresponding element provided on the inner wall of said top portion of said container in order to lock the stopper within said portion, said

locking elements being so arranged as to ensure that the neck. Locking means extends between a shoulder on the in-
stopper is released as a result of action exerted within the
recessed portion of said stopper.

3,578,194

THROW-AWAY BEVERAGE BOTTLES


Richard T. Cornelius, Minneapolis, Minn., assignor to The
Cornelius Company, Anoka, Minn.

Filed Sept. 20, 1968, Ser. No. 761,086

Int. Cl. B65d 11/04, 11/22

U.S. Cl. 215-13

7 Claims



Low cost, large capacity, lightweight plastic bottles, espe-
cially suitable for carbonated beverages, have burst-resistant
construction in which an upright wall and a concave-convex
bottom wall may have the thinnest practicable wall section;
and a combination label and a bottle-supporting skirt is af-
fixed to the lower end portion of the bottle.

3,578,195

LYOFLO-STOPPER


Robert W. Ogle, Newport Beach, Calif., assignor to Lyoflo-
Stopper Corporation, Wilmington, Del.

Filed Jan. 16, 1969, Ser. No. 791,727

Int. Cl. B65d 39/04, 51/16

U.S. Cl. 215-47

1 Claim



This patent describes a novel resilient lyophilizing stopper
for use in a vial or other medicament container having an
open end, said stopper comprising an upper portion having
one or more sealing rings adapted to form a seal on the inside
walls of said vial and act as a piston therein, and a lower por-
tion comprising a series of interruptions around the periphery
of the lower portion, said interruptions forming a force com-
pression fit with the walls of the vial and the spaces between
the interruptions being adapted to provide a gas passage from
the interior of the vial to the exterior when said sealing rings
are held beyond the end of the vial by said interruptions.

3,578,196

BOTTLE-LOCK

Lee Ender, 1509 Madison St., Madison, Dane County, Wis.


Filed Jan. 21, 1969, Ser. No. 800,797

Int. Cl. B65d 45/02

U.S. Cl. 215-88

1 Claim

A bottle has a threaded neck and a cap threaded on the



terior of the bottle and the cap to prevent unauthorized
removal of the cap.

3,578,197

POROUS MASS AND A CONTAINER THEREFOR


Leslie G. Taylor, Wimbledon, and Donald S. Withey,
Beddington, England, assignors to The British Oxygen
Company Limited

Division of Ser. No. 641,914, May 9, 1967, abandoned. Filed
Feb. 20, 1969, Ser. No. 817,206

Int. Cl. B65d 25/00

U.S. Cl. 220-16

2 Claims



A porous mass having a high absorptive capacity for a
liquefied gas is housed in a vented thermally insulated con-
tainer, the porous mass having recesses therein for the recep-
tion of materials requiring refrigeration by said liquefied gas
has been inserted.

3,578,198

STOPPER FOR SELF-OPENING CAN


Dan Blechman, 1200 N. State St., Los Angeles, Calif.

Filed Aug. 30, 1968, Ser. No. 756,524

Int. Cl. B65d 45/00

U.S. Cl. 220-25

4 Claims



A stopper for a metal beverage can provided with an easy
opening or ring-pull top. The stopper includes an inner clamp
member adapted at one rotated position to be insertable
through the opening in the can and upon being rotated and
being brought up tight against the underside of the top of the
can to bring an upper seal member into sealing engagement
with the top of the can to seal the opening.

3,578,199

PORTABLE CARRIER FOR BEVERAGE CONTAINERS


Allen B. Duncan, 327 W. Wooster St., Bowling Green, Ohio

Filed Apr. 9, 1969, Ser. No. 814,624

Int. Cl. B65d 25/14, 43/16

U.S. Cl. 220-31

5 Claims



A lightweight portable insulated carrier adapted to carry
drink containers, such as cans, consisting of an elongate hol-
low tubular insulated body with closure members attached to
each end thereof, the closure members being hinged and
adapted to be moved between open and closed positions for
access to the interior of the body and releasable means are
carried by the body for mounting the carrier on a suitable
supporting member such as the handle of a golf cart for ex-
ample, the closure members being insulated and locking
means being provided so that the interior of the container
can be securely closed off and insulated.

3,578,200

PORT PROTECTORS


Harry Hetzer, Depew, N.Y., assignor to GTI Corporation,
Meadville, Pa.

Filed Nov. 3, 1969, Ser. No. 873,584

Int. Cl. B65d 39/04; F16i 57/00; B65d 59/02

U.S. Cl. 220-42B

5 Claims



A port closure is provided for threaded ports comprising a
resilient cylindrical member adapted to slidably fit within
said port and having an interrupted thread on the exterior
thereof intermediate the ends engaging the threads in said
port, a circular end cap covering one end of said cylindrical
member and extending beyond the periphery forming an an-
nular radial flange, a depending ring at the outer periphery of
the flange spaced from the cylinder and engaging the surface
surrounding the port and spacing the flange therefrom when
the cylinder is in place in said port whereby the cylinder is
under axial tension between the thread and end cap.

3,578,201

VENT VALVE ASSEMBLY

Charles W. Smith, Jr., Erie, Pa., assignor to Autoclave En-
gineers, Inc., Erie, Pa.

Filed Sept. 30, 1969, Ser. No. 862,262


Int. Cl. B65d 51/16

U.S. Cl. 220-44

7 Claims

A vent and drain valve useful for venting a pressure
chamber and draining displaced fluid from within the
chamber, as in an isostatic press, including a housing sup-
porting independently biased, vertically slideably upper and
lower plungers having cooperating working faces. The valve,
which is positioned in a base in the cover for the chamber,
provides an opening through the cover to permit flow of fluid

upwardly through the valve from within the chamber. As
pressure is increased in the chamber, the lower plunger is



moved upwardly to cause the plunger faces to seal against
one another to prevent leakage through the valve.

3,578,202

SEALING ASSEMBLY AND METHOD


Maurice Mainet, Asnieres, France, assignor to Produits
Chimiques Pechiney-Saint-Gobain, Neuilly-sur-Seine,
France

Filed Nov. 4, 1969, Ser. No. 873,986

Claims priority, application France, Nov. 8, 1968, 173,070
Int. Cl. B65d 53/00

U.S. Cl. 220-46

30 Claims



Sealing elements and method for their assembly wherein
the assembly comprises a first element having a body with at
least one projection fixed thereto, wherein the projection is
formed of a material which is deformable and which has an
elastic memory, and a second element having at least one
groove therein which is adapted to receive the projection of
the first element whereby said projection is urged toward a
sealing relation with the groove in response to the combina-
tion of forces generated by the elastic memory of the projec-
tion and by the internal pressures exerted on the sealing ele-
ments.

3,578,203

SEALING ASSEMBLY

Maurice Mainet, Asnieres, France, assignor to Produits
Chimiques Pechiney Saint-Gobain, Neuilly-sur-Seine,
France

Filed Nov. 4, 1969, Ser. No. 873,914

Claims priority, application France, Nov. 8, 1968, No.
173,071


Int. Cl. B65d 53/00

U.S. Cl. 220-46

18 Claims

A sealing assembly for forming a tight sealing relationship
between at least two elements which comprises a spline
member having two lateral faces having at least one convex
relief element on each face, a first element and a second ele-
ment, each of which have at least one wall with a recess
formed therein which is adapted to receive the relief element
on each lateral face of the spline member, and wherein one
of the elements defines a cavity adapted to receive the other

element and the spline member whereby the spline member may be interposed between the walls of the elements to form a tight seal there between when the relief elements of the



spline member are engaged with the recess in each of the walls to thereby prevent movement of one of the elements to the other.


3,578,204

CONTAINER WITH FLEXIBLE REINFORCED WALL MEMBERS

Roy W. Bloch, Northbrook, and Donald K. Jewell, Chicago, Ill., assignors to Ekco Products, Inc., Wheeling, Ill.
Filed May 28, 1969, Ser. No. 828,542
Int. Cl. B65d 7/42

U.S. Cl. 220-72

6 Claims



A relatively flexible container comprising a bottom wall and sidewalls extending upwardly therefrom. The bottom wall contains rib means which provide for the downward bulging of the bottom wall when opposing sidewalls of the container are pressed inwardly.


3,578,205

CORNER SUSPENDABLE PAIL AND HANGER

Jose F. Ballester, 5 Suchville R.F.D. 52, Bayamon, P.R.
Filed Oct. 21, 1968, Ser. No. 769,263
Int. Cl. B65d 25/00

U.S. Cl. 220-85

13 Claims



A corner suspendable pail and hanger wherein the pail is supported by a downturned lip on its top edge engaged with

an upstanding flange on the bottom of the hanger as well as by a handle, pivotally mounted to the top edge of the pail, detachably secured to the top of the hanger by means of a slidable lockpin.


3,578,206

PHONOGRAPH RECORD VENDING MACHINE

Jack C. Moore, 1238 Brown St., Alton, Ill.
Filed May 14, 1968, Ser. No. 729,132
Int. Cl. B65g 59/00

U.S. Cl. 221-124

4 Claims



A vending dispenser for phonograph records wherein a plurality of spindles are supported in alignment along a common vertical axis for releasably storing a plurality of records each, the spindles being supported adjacent their uppermost ends by V-shaped brackets having a horizontal portion attached to a vertical wall and supporting the spindle, and an inclined portion also attached to the vertical wall and joining the horizontal portion at an apex spaced from another vertical wall paralleling the first vertical wall, whereby records released from any of the spindles are guided into the space between the apex and the other vertical wall by the inclined bracket portion and are then gravitationally discharged to the lower part of a record case for discharge externally therefrom.


3,578,207

ADJUSTABLE BREAD DISPENSER WITH EJECTOR-CONTROLLED CLOSURE

James F. Danow, 2163 Vine St., Apt. A, Berkeley, Calif.
Filed Oct. 21, 1968, Ser. No. 769,316
Int. Cl. B65h 1/08

U.S. Cl. 221-232

11 Claims



A bread dispenser comprises a container adapted to retain a stack of sliced bread therein. Spring means are disposed at one end of the container to urge the bread towards a dispensing means mounted at the other end thereof. The dispensing means comprises a guillotinlike plunger reciprocally

cally mounted on the container to dispense one or more bread slices.

which includes a plurality of reserve chambers for the propellant gas which are adapted to sequentially release their con-

3,578,208

WATCH BAND STRAP WITH RELEASABLE END CONNECTION

Hilmar Herzog, Nottingen, Germany, assignor to Firma Gustav Bauer, Otto-Maurer Str., Germany
Filed Feb. 18, 1969, Ser. No. 800,217
Int. Cl. A44c 5/00

U.S. Cl. 224-4

12 Claims



A tubular element of elastic temporarily deformable, preferably thermoplastic material is bonded to the watch strap, for example by fusion if the watch strap is likewise of plastic material; the tubular element has a transverse slit so that, upon deformation of the tubular element in the region of the slit, the cross pin of a wrist watch case can be snapped through the slit into the hollow of the tube.

tained reserve gas supply as the pressure of the propellant gas in the main chamber drops below a predetermined level.


3,578,211

LOADER FOR RECIPROCATING HOPPER

Richard T. Coapman, and Gary D. Ginther, Troy, Mich., assignors to Clyde Corporation, Troy, Mich.
Filed Dec. 31, 1968, Ser. No. 788,270
Int. Cl. B67d 5/08

U.S. Cl. 222-56

25 Claims




3,578,209

TIMED FEEDING MECHANISM


James K. Fraser, 1356 Clairmont Road, Decatur, Ga.
Filed Dec. 10, 1968, Ser. No. 782,539
Int. Cl. B67d 5/06

U.S. Cl. 222-23

2 Claims



A timed feeding mechanism suitable for dispensing food or other granular material to fish or other pets or larger animals at predetermined time intervals and in prescribed quantities, comprising a housing defining an inlet opening and an outlet opening, a receptacle movable between the inlet and outlet openings, a hopper communicating with the inlet opening of the housing for supplying the granular material to the housing, and a timing mechanism for moving the receptacle back and forth between the inlet and outlet openings of the housing to dispense the granular material from the hopper through the housing.



A flexible band forms a chute by which articles are delivered to a vertically oscillating hopper from an elevated container while the hopper is in motion. A spring-supported pressure plate within the hopper is depressed by impacts of the articles within the hopper thereon only until the supply falls below a predetermined minimum and thereafter remains undepressed, thereby actuating a motor which causes transfer of additional articles from the elevated container onto the chute for automatically replenishing the supply of articles in the hopper.

3,578,212

LIQUID DOSAGE APPARATUS

Rudolf Greiner, and Rudolf Oberli, Langenthal, Switzerland, assignors to Greiner Electronic AG, Langenthal, Switzerland

Filed Nov. 14, 1969, Ser. No. 876,782
Claims priority, application Sweden, Mar. 31, 1969, 4833/69
Int. Cl. B67d 5/16

U.S. Cl. 222-71

8 Claims

Liquid dosage dispensing apparatus, characterized by the combination of means for pumping a selected quantity of liquid from constant liquid level container means to a discharge nozzle, and nozzle positioning means for displacing the nozzle from an initial storage position in which the nozzle

3,578,210

AEROSOL DISPENSING CONTAINER WITH RESERVE PROPELLANT CHAMBERS


Thomas B. Pitroff-Szabo, 728 Belmont St., Watertown, Mass. 02172
Filed Jan. 12, 1970, Ser. No. 2,276
Int. Cl. B67d 5/08

U.S. Cl. 222-52

6 Claims

An aerosol dispensing container of the gas-propelled type

is partially submerged in the container liquid to a dispensing position relative to a liquid receiver. The dosage pump means include reciprocatory piston means alternately operable to draw, by suction, a desired volume of liquid into a chamber



and to discharge this desired volume from the chamber. Slide valve means are provided that are operable in synchronism with the piston to connect the chamber alternately with the container and with the nozzle means, respectively.

3,578,213

CONTAINER WITH DISPENSING MEANS FOR TRANSPORTING BULK MATERIALS


Edwin E. Clarke, 651 S. 31st St., Allentown, Pa., and Albert J. Florig, 1549 Yost St., Norristown, Pa.

Filed Jan. 28, 1969, Ser. No. 794,591

Int. Cl. B65d 35/30

U.S. Cl. 222-95

32 Claims



A container for transporting bulk materials including a rigid enclosure means, partition means disposed in the rigid enclosure means, and being movable along a length of the rigid enclosure means to provide a variable volume chamber, a flexible enclosure means disposed in the variable volume chamber, the rigid enclosure means having discharge means and the flexible enclosure means having outlet means communicating with the discharge means of the rigid enclosure means.

3,578,214

CARBONATOR

Frank M. Iannelli, 5 Penwood Road, Livingston, N.J.

Filed Feb. 7, 1969, Ser. No. 797,462


Int. Cl. B67d 5/56

U.S. Cl. 222-129.1

5 Claims

Liquid to be carbonated flows under its normal pressure into a combined reservoir and precarbonating chamber and is forced from said chamber by carbonating gas into a combined mixing and dispensing chamber. The supply of carbonating gas to said reservoir and carbonating chamber is controlled by an electromagnetic valve which is actuated by a float-operated switch in accordance with variations in the

liquid level in the mixing and dispensing chamber. Constant gas pressure is supplied through a restricted duct to the mixing and dispensing chamber so that if the chamber empties and the switch cuts off the gas supply, resumption of the flow



3,578,215

POWDER DELIVERY ARRANGEMENTS

Roger B. Bushnell, Ashford, Middlesex, England, assignor to Controsion Electrostatic Limited, London, England

Filed July 7, 1969, Ser. No. 839,502


Claims priority, application Great Britain, July 15, 1968,

33637/68

Int. Cl. B67d 5/54

U.S. Cl. 222-193

5 Claims



This invention relates to a powder delivery arrangement, for example for the delivery of powdered paint to a spray gun for the spray coating of surfaces, and comprises a hopper into which the powder is introduced, a stirring device in the hopper for preventing clogging of the powder, a worm shaft in the hopper for driving the powder received from the stirring device out from the hopper into a chamber containing a centrifugal fan which sucks the powder received from the hopper and drives it through a delivery pipe. The powder expelled from the hopper may conveniently be delivered into an intermediate compartment having an air inlet preferably provided with a filter device, the centrifugal fan acting to suck a mixture of powder and air from such compartment. The hopper together with the stirring device and worm shaft within it is preferably removably mounted for interchange with alternative hoppers. The stirring device and the worm shaft are preferably driven by a variably speed motor.

3,578,216

PREVENTION OF ARCHING COMPACTION OF DISCRETE MATERIAL IN GRAVITY FEED HOPPERS

William S. Pearson, 225 N. First St., Hampstead, Md.

Filed Dec. 3, 1968, Ser. No. 780,708

Int. Cl. B65g 3/12, 69/06

U.S. Cl. 222-195

10 Claims

Arching compaction of discrete material in gravity feed

hoppers is prevented by directing a stream of fluid upwardly



from adjacent to the discharge outlet of the hopper.

3,578,217

FLUENT MATERIAL DISPENSING DEVICE HAVING ROTARY TRAP CHAMBERS WITH RADIALLY MOVABLE EJECTOR


Roland E. Miller, Orangeville, Ill., assignor to Kraftco Corporation

Filed May 15, 1968, Ser. No. 729,356

Int. Cl. G01f 11/00

U.S. Cl. 222-218

19 Claims



A device is provided for dispensing metered quantities of material and includes a wheel defining circumferentially spaced chambers extending radially inwardly from the periphery of the wheel, a plunger within each of the chambers, and means for selectively adjusting the extent of radial movement of the plungers within the chambers so as to permit selective control of the amount of material dispensed from each chamber.

3,578,218

VACUUM SEAL FOR DOUGH DIVIDERS

Harold Thomas Atwood, Chicago, Ill. (14152 Irving Ave., Dolton, Ill. 60419)

Filed Mar. 6, 1969, Ser. No. 804,858


Int. Cl. B67d 5/40

U.S. Cl. 222-383

1 Claim

A vacuum seal is provided in an open top tubular cylinder by a pair of sealing rings mounted respectively on a piston

that is reciprocated in the cylinder, and in an annular groove in the upper edge of the cylinder. The sidewall of the cylinder is provided with an inlet opening in flow communication with a hopper from which material, such as dough, for example, is fed into the cylinder above the top of the piston. A metal plate having a flat bottom slides laterally of the cylinder with its flat bottom held in the plane of the open



upper end of the cylinder. The metal plate fits against the upper edge of the cylinder and covers its upper end during the downward movement of the piston. The two sealing rings cooperate to seal the cylinder above and below the inlet opening, so that as the piston moves downwardly in the cylinder, it produces sufficient suction to force the dough from the hopper through the inlet opening into the cylinder.

3,578,219

QUICK-CONNECT COUPLING CONVERSION MEANS FOR BEER KEGS


Harry E. Berry, 3510 S. W. 32nd Ave., Hollywood, Fla.

Filed May 1, 1969, Ser. No. 821,057

Int. Cl. B65d 83/00

U.S. Cl. 222-394

5 Claims



A keg having a lower liquid dispensing tapping opening provided with a removable adapter mounted in a valve body cup and having a downwardly extending radial conduit on its innermost end with the conduit having an inlet opening adjacent the bottom of the keg on one end and communicating with a male quick-connect coupling member on its other end for the discharge of liquid through the coupling for enabling a maximum efficiency in the discharge of the keg contents.

3,578,220

AEROSOL VALVE ACTUATOR AND CAP COMBINATION

Derek Bernard Green, Bedford, N.H., and Gordon Edwin Kaye, South Salem, N.Y., assignors to Scovill Manufacturing Company, Waterbury, Conn.

Filed Mar. 17, 1969, Ser. No. 807,618



Int. Cl. B65d 83/14

U.S. Cl. 222-402.13

4 Claims

An aerosol valve actuator button is held in preliminary assembly with an overcap so that the button is maintained cor-

rectly oriented with respect to features of the cap intended to restrict the operation of the button to one direction only. In the preliminary assembly, the button is in a raised position al-



chamber above the piston serving to swing the door vertically.

3,578,223

CONTAINER WITH CLOSURE


Donald F. Armour, Bloomfield, Conn., assignor to Monsanto Company, St. Louis, Mo.

Filed Aug. 27, 1968, Ser. No. 755,693

Int. Cl. B67d 3/00

U.S. Cl. 222-521

4 Claims



A container closure assembly including a fitment secured to the outside of the neck of a resilient plastic bottle having a dispensing channel therein communicating with an outlet passage in a cap which is threaded onto the neck over the fitment. The assembly has dual seals against leakage and a self-cleaning outlet achieved by means of a wiping type of contact between a pin on the fitment and the surface of the cap opening as the cap is rotated toward its closed position. The outlet passage may be provided with channels to augment its size and provide for varying the discharge rate.

3,578,224

CONTAINER AND CLOSURE CAP


Marvin S. Greenhut, Massapeque, N.Y., assignor to Grow Chemical Corp., New York, N.Y.

Filed July 25, 1968, Ser. No. 747,510

Int. Cl. B65d 47/00

U.S. Cl. 222-546

4 Claims



The invention contemplates a plastic bottle or container for the storage and selective dispensing of fluent material, such as liquid adhesive, through a dispensing opening at the end of an outwardly projecting neck. Interfitting cap and neck parts establish and assure sealing when the container is closed. The cap includes a central projecting stem which achieves a sealing interference fit with the opening, and the skirt of the cap is relied upon to engage and secure the cap to the base of the neck.

ERRATUM

For Class 224-4 see:
Patent No. 3,578,208

3,578,222

HOPPER WITH BOTTOM DOOR ACTUATOR

Hendrik Pot, Kinderdijk, Netherlands, assignor to N. V. Industriele Handelscombinatie Holland, Rotterdam, Netherlands

Filed Aug. 22, 1969, Ser. No. 852,179

Claims priority, application Netherlands, Aug. 23, 1968, 68.12073

Int. Cl. B67d 3/00

U.S. Cl. 222-504

3 Claims

A hopper has a bottom door which is pivoted intermediate its length about a horizontal axis. That portion of the hopper door which is on the side of the pivot axis opposite the hold

3,578,225

CONCEALED PURSE: HIDE-A-PURSE


Stella Mae Schroeder, 141 W. 4th St., Davenport, Iowa

Filed Apr. 4, 1969, Ser. No. 813,596

Int. Cl. A45c 1/04

U.S. Cl. 224-5-R

1 Claim



band of metal longitudinally tensioned and positioned in alignment with and below the shaft.

In accordance with my invention a strap is adapted to be detachably secured to the shoulder of a wearer and worn under a coat or jacket. The strap extends downwardly toward the waist and at its lowest point is provided with one or more fastener means. A purse, which can be hand carried in conventional manner, is provided with a like plurality of fastening means which are adapted for detachable engagement with the fastener means. As a result, the purse can be held next to the waist by the straps, out of sight, and inaccessible to would-be thieves and purse snatchers.

3,578,228

APPARATUS FOR FEEDING TWO WIRES SIMULTANEOUSLY


Charles Dale Steiner, Harrisburg, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Nov. 6, 1969, Ser. No. 874,430

Int. Cl. B65h 17/42

U.S. Cl. 226-109

4 Claims



Wire feeding means comprises a pair of feed wheels mounted on parallel spaced-apart axes. One of the wheels has two tires mounted in side-by-side relationship on its periphery, each tire being adapted to engage one of two wires being fed. The tires are supported on the periphery of the wheel by means of helical springs which extend radially with respect to the axis of the wheel. These springs can be compressed and also can be deflected laterally thereby to permit the tires to feed different sizes of wires and to provide a resilient coupling between the tires and the wheel on which they are mounted.

3,578,229

BOOSTER ROLL FOR INTERMITTENT FEEDS

James Keith Macomber, Rockville Centre, N.Y., assignor to Consolidated Educational Publishing, Inc., Long Island, N.Y.

Filed Apr. 5, 1968, Ser. No. 719,028

Int. Cl. B65h 17/36

U.S. Cl. 226-114

11 Claims

This invention relates to supply means for web or ribbon feed machines where the ribbon is unreel from a storage supply means such as a reel in substantially continuous motion, and is fed through the mechanism of the machine by an intermittent motion. The purpose of the invention is to pro-

3,578,227

METHOD OF BREAKING DICE

Aime A. Gehri, Beverly, Mass., assignor to Transiron Electronic Corporation, Wakefield, Mass.

Continuation of application Ser. No. 696,433, Jan. 8, 1968,

now abandoned. This application Oct. 1, 1969, Ser. No.

868,961


Int. Cl. B26f 3/00

U.S. Cl. 225-2

9 Claims

A means for breaking a semiconductor wafer that has been scored into a plurality of individual dice consisting of a roller

vide mechanical filter means cooperating with a booster assist drive connected to the main drive of the device to translate the intermittent motion of the feed of the machine to a smooth, continuous motion at the supply means or reel for the ribbon. In the preferred form of the invention, the booster is a cylindrical roll in the ribbon pathway adapted to



frictionally engage the ribbon, and the mechanical filter comprises a ribbon holding means, or brake, to prevent the ribbon from reversing its motion, and a coercing member, such as a tension member, spring urged against the ribbon within the ribbon pathway, between the ribbon holding means and the booster roll, as will be more fully described and claimed hereinbelow.

3,578,230

PRESS FEED CONTROL


Joseph W. Baldyga, Utica, Mich., assignor to Diamond Die & Mold Co., Mount Clemens, Mich.

Filed Sept. 8, 1969, Ser. No. 855,847

Int. Cl. B65h 17/04

U.S. Cl. 226—162

11 Claims



A press feed control comprising a pair of interconnected hydraulic cylinders, a piston in one cylinder mechanically operated by press actuation to displace fluid which in turn displaces the piston in the timing cylinder, which piston is connected to feed mechanism. Resilient means urge the feed mechanism in the direction tending to move the piston in the timing cylinder to return fluid to the first cylinder. A check valve and an adjustable metering valve are provided in the connection between the cylinders.

3,578,231

FASTENER DRIVING TOOL WITH PNEUMATICALLY CLAMPED NOSEPIECE STRUCTURE

Edward J. Novak, Franklin Park, Ill., assignor to Fastener Corporation, Franklin Park, Ill.

Filed Feb. 5, 1970, Ser. No. 8,915


Int. Cl. B25c 5/06

U.S. Cl. 227—123

14 Claims

A pneumatic fastener driving tool using a compressed air driven fastener driver includes a housing supplied with compressed air. A nosepiece on the housing forms a drive track for the driver to which fasteners are supplied below the driver. An opening through the nosepiece into the drive track is closed by a movable closure held in place by a pneumatic clamping assembly. This assembly includes a piston and cylinder supplied with compressed air from the housing for biasing a lever engaging the closure. A manually actuated

release valve in the piston releases the bias to permit movement of the closure to clear jams. A fulcrum for the lever is



3,578,232

HYDRAULICALLY LOADED THRUST BEARING ARRANGEMENT FOR A FRICTION WELDING MACHINE


Calvin D. Loyd, Peoria; Theodore L. Oberle, Washington, and Ronald L. Satzler, Metamora, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed Dec. 20, 1968, Ser. No. 785,644

Int. Cl. B23k 27/00

U.S. Cl. 228—2

8 Claims



A thrust bearing arrangement for use with a shaft which is subject to high rotational speeds and high axial thrust relative to a supporting housing. A number of angular contact thrust bearings are arranged in tandem between the shaft and housing and are independently pressurized by hydraulic fluid for developing equal internal counterbalancing pressure in the bearings. The internal counterbalancing force developed within each bearing is preferably somewhat in excess of the axial force transmitted between the shaft and housing with resilient backup means absorbing at least a portion of the internal counterbalancing force and axially stabilizing the shaft relative to the housing. The bearing arrangement is adaptable to a friction welding machine for use with its spindle and spindle housing with working fluid from a common source delivered both to the bearing and to a hydraulic load cylinder for developing the axial load.

3,578,233

APPARATUS FOR REMOTELY JOINING UNDERWATER PIPELINES


Robert P. Meister; James S. Glasgow; Donald J. Hackman; Milton D. Randall, Columbus, Ohio, and John K. McCarron, Houston, Tex., assignors to Shell Oil Company, New York, N.Y.

Filed July 11, 1968, Ser. No. 744,161

Int. Cl. B23k 1/20

U.S. Cl. 228—5

24 Claims



A technique for joining pipelines underwater comprising joint preparation and completion apparatus that is either remotely operated or automatically sequenced. The apparatus is adapted to be used with three alternate embodiments of joining means: (1) a mechanical connection, (2) thermit welding, or (3) a combination of explosive-forming and mechanical joining.

3,578,234

LINED SHIPPING CONTAINER


Joseph Marchisen, Hightstown, N.J., assignor to Union Camp Corporation, New York, N.Y.

Filed Aug. 1, 1969, Ser. No. 846,750

Int. Cl. B65d 5/56

U.S. Cl. 229—14BA

1 Claim



A shipping container comprising a carton and a liner bag therein. The open end of the bag extends above the horizontal plane of the closing flaps of the carton to an extent exceeding the width of a flap. The top of the bag is closed by elongating and bringing together opposite sides to form a flexible body longitudinally parallel to and extending between two opposing flaps of a pair. The carton and bag are simultaneously closed and a substantially tight seal for the bag is formed by first infolding one of the flaps of the pair, and thereby the body. Thereafter, the opposing flap of the pair is infolded, which also folds the body again and interleaves the body between the two flaps to form two longitudinal closure folds. The body may be of sufficient length to be folded over the second flap to form an additional closure fold. Finally, the flaps of the other pair are infolded whereby the folded body projecting over these flaps is infolded to form transverse closure folds.

3,578,235

TRAY FOR CARMELS


Hugh R. Weiss, Montclair, N.J. (c/o The Pantasote Co., 26 Jefferson St., Passaic, N. J. 07055)

Filed Nov. 5, 1969, Ser. No. 874,240

Int. Cl. B65d 1/36, 1/00

U.S. Cl. 229—15

1 Claim



A one-piece multicavity tray suitable for receiving, supporting and displaying high density candies which tend to flow in warm climates, has smooth bottom surface cavities, partitions of inverted U-shape section separating cavities, a continuous lateral peripheral flange terminating in a fluted skirt for supporting the peripheral cavities well off the bottom of the box in which to loaded trays are placed, and in place of the rippling or ribbing usually used in the bottoms of the cavities, internal support for the tray is provided by forming a plurality of distributed steps which extend downwardly from intermediate portions of the partitions below the plane of the bottom of the cavities to bear against the bottom of the said box.

3,578,236

PAPER BAG OF SIMPLIFIED STRUCTURE ADAPTED TO BE RETAINED IN EACH OF THE OPENED AND THE FOLDED CONFIGURATIONS

Masayuki Arai, Tokyo, Japan, assignor to Lyric Kabushiki Kaisha, Tokyo, Japan


Filed Mar. 21, 1969, Ser. No. 809,291

Claims priority, application Japan, July 16, 1968, 43/61141

Int. Cl. B65d 33/02

U.S. Cl. 229—55

3 Claims



A paper bag having a substantially rectangular cross section and made of a single tough but cheap paper material and provided with a flexible and tough reinforcement wire or band lined along the entire open top edges and also with intermediate vertical folding lines in the side panels, at least one horizontal folding line extending around the vertical panels in the lower portions of these panels, inclined folding lines extending inwardly from the corners of the bottom side edges to join the point of intersection of said intermediate vertical folding line and said horizontal folding line, and at least one longitudinal central folding line in the bottom panel, whereby said paper bag may be retained in each of the opened and the closed configurations by virtue of said reinforcement means.


3,578,237

TRAY FOR DISPLAYING AND PROTECTING CANDY AND THE LIKE

Hugh R. Weiss, Montclair, N.J. (c/o The Pantasote Company, 26 Jefferson St., Passaic, N.J. 07055)
Filed Nov. 5, 1969, Ser. No. 874,241
Int. Cl. B65d 1/36, 1/00

U.S. Cl. 229-15

2 Claims



A one-piece multicompartment tray for protecting fragile cookies or candy has a plurality of rectangular compartments surrounded by a continuous relatively thick peripheral lip, ribs formed by adjacent walls of adjacent compartments and having a relatively thick upper portion separate adjacent compartments, some of the ribs extending to and intersecting with said peripheral lip, each of the compartments is fitted with a boss attached to two adjacent walls of the compartment, an upper surface of said boss is tilted downwards toward a boss-free wall of the cavity and toward the nearest peripheral edge of the tray that is parallel to the boss-free wall of the cavity.

3,578,238


CONTAINER WHICH COMPLETELY ENCLOSES ARTICLES

Joseph F. Schillinger, Chicago, and Thomas B. Moser, Glen Ellyn, Ill., assignors to Weyerhaeuser Company, Tacoma, Wash.
Continuation of application Ser. No. 710,120, Mar. 4, 1968, now abandoned. This application July 28, 1969, Ser. No. 848,402

Int. Cl. B65d 5/02, 85/00

U.S. Cl. 229-40

11 Claims



A carton or container which fully encloses the contained articles. The carton has finger holes placed along one side edge of the carton allowing one of the articles to be grasped when the carton is carried by use of the finger holes. There are no cutouts for the caps or base of the articles, so that the container tightly encloses them. The container has a design which allows the container blanks to be nested on the web prior to cutting.


3,578,239

BAG STRUCTURE

Sol J. Perlman, Baltimore, Md., assignor to Vac Pac Manufacturing Company, Inc., Baltimore, Md.
Continuation-in-part of application Ser. No. 630,961, Apr. 14, 1967, now Patent No. 3,478,952. This application July 17, 1969, Ser. No. 842,570
Int. Cl. B65d 31/00, 33/00

U.S. Cl. 229-53

6 Claims



An improved method of adhering the bottom of polyalkylene terephthalate film bags, such as those used to shrink package frozen turkeys, is disclosed. The bags are adhered on at least one side with two distinct adhesive bands. The inner band is a thermoplastic adhesive which allows a measure of "peelability and shock absorbability," whereas the outer adhesive band is a high strength thermosetting adhesive. The contained product may even be cooked within the bag.


3,578,240

RECEPTACLE HOLDER FOR CENTRIFUGES

Gunter Eberle, Gartenstrasse 100, Postrach 391, 72 Tuttlingen, Germany
Filed Apr. 14, 1969, Ser. No. 815,912
Claims priority, application Germany, Apr. 13, 1968, P 17 73 198.5
Int. Cl. B04b 9/12

U.S. Cl. 233-26

5 Claims



A holder for a receptacle such as a blood-containing receptacle which is to be centrifuged. The holder includes an outer wall structure which is lined by an inner flexible lining. The outer wall structure is formed with axial bores in which hydraulic pistons are respectively slidable. The outer wall structure and the flexible liner define between themselves a chamber of a predetermined configuration for receiving a compensating hydraulic liquid which is acted upon by the pistons which slide in the bores in response to centrifugal forces which are present during the centrifuging operations. With this construction the configuration of the chamber is

such that the hydraulic liquid is displaced by the pistons during centrifuging in such a way that horizontal and radial forces which otherwise would act on the receptacle during centrifuging thereof are eliminated with the compensating hydraulic liquid.


3,578,241

SLIDE RULE FOR SCUBA DIVERS

Philip J. Wombough, 4255 Ocean Blvd., and Charles E. Tal-
lerino, 3717 Yosemite, Pacific Beach, Calif.
Filed Oct. 16, 1969, Ser. No. 866,806
Int. Cl. G06c 3/00

U.S. Cl. 235-88

11 Claims



A circular slide rule for use by scuba divers which coordinates the variables of air tank pressure, depth of submergence, breathing rate, and time and with which a variable may be determined when the others are known. The time available at depth is disposed on a scale formed as two separate parts, the first being from surface to an intermediate depth and the other from the intermediate depth to maximum depth which provides greater accuracy at greater depths, where it is most needed. The discs of the slide rule are flexible and of various diameters permitting the selective locking together of different combinations of same by the fingers of the user.


3,578,242

PNEUMATIC AIR-CONDITIONING CONTROL SYSTEM

Donald H. Spethmann, Arlington Heights, Ill., assignor to Honeywell, Inc., Minneapolis, Minn.
Filed Sept. 3, 1969, Ser. No. 854,937
Int. Cl. G05d 23/19

U.S. Cl. 236-1

5 Claims



A pneumatic control system controlling sequentially operable valves, including a pressure-responsive pneumatic switch operable in response to the operation of the central fan or blower of the air-conditioning system. This switch connects the thermostat to the valves when the blower or fan is operat-


3,578,243

STEPPED-FLOW GAS VALVE

John J. Love, St. Louis, Mo., assignor to Emerson Electric Co., St. Louis, Mo.
Filed June 13, 1969, Ser. No. 833,113
Int. Cl. G05d 23/185

U.S. Cl. 236-80

6 Claims



Two, series arranged, biased closed valves in a fuel passageway and a bypass around the downstream valve to provide a partial flow when the upstream valve is open and the downstream valve is closed, the downstream valve being opened by the fluid pressure in the passageway between the valves when the upstream valve is open and the opening of the downstream valve being delayed so as to provide a partial flow of fuel for a short period following the opening of the upstream valve.


3,578,244

INTERMITTENT SPRINKLER IRRIGATION SYSTEM

Lennart G. Erickson, San Mateo, Calif., assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
Filed Apr. 14, 1969, Ser. No. 815,596
Int. Cl. A01g 25/02

U.S. Cl. 239-1

6 Claims




Irrigation apparatus and method utilizing substantially constant waterflow through a lateral and sequential operation of sprinkler heads mounted on and in selective fluid communication with the lateral to provide cyclic irrigation at each of a number of operative locations along the lateral. The constant waterflow and sequential operation of the heads allows for reductions in cross section of the lateral and permits fewer but larger heads to be used, whereby equipment costs are reduced and greater land areas can be irrigated. The heads are selectively placed in fluid communication with the lateral by the use of remotely controlled valves.

3,578,245 ELECTRICALLY CONTROLLED FLUID DISTRIBUTION SYSTEM

Glover B. Brock, 3709 8th St. South, Arlington, Va.
Filed July 29, 1969, Ser. No. 845,740
Int. Cl. A01g 25/02

U.S. Cl. 239—66

17 Claims U.S. Cl. 239—29




A fluid distribution system is shown which includes a plurality of electrically actuated valves. Each valve is associated with a selectively activated switching device responsive to a particular control signal of preselected frequency. A band-pass filter is connected between each switching device and a source of control signals having differing frequencies and preselected durations for activating the switching devices. The source of control signals may be a source of prerecorded signals, such as a replacable cassette, or a preprogrammed oscillator arrangement.

3,578,246 SPRAYING PROCESS

Orvis A. Davis, Sr., Gibsonia, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
Division of Ser. No. 687,236, Dec. 1, 1967, abandoned, which is a division of Ser. No. 524,672, Feb. 3, 1966, Pat. No. 3,373,941. Filed Oct. 16, 1969, Ser. No. 866,935
Int. Cl. B05b 7/06

U.S. Cl. 239—8

6 Claims




A spray having a generally circular cross section is modified into one having an oblong cross section. A pair of pressurized fluid streams are charged in a collision course directly into each other on one side of said spray while a second pair of pressurized fluid streams are charged in a collision course directly into each other on the diametrically opposite side of said spray. Said pairs of fluid streams compress the circular cross section of said spray into an oblong cross-sectional configuration.

3,578,247 SPHERICAL WATER FOUNTAIN

Allen C. Wright, Moraga, Calif., assignor to Haws Drinking Faucet Company, Berkeley, Calif.
Filed Nov. 21, 1968, Ser. No. 777,650
Int. Cl. E03b 9/20

5 Claims



A water fountain comprising a pedestal supporting a spherical head thereon having spaced ports along the surface thereof respectively adapted to have a valve-controlled stream of water discharge therefrom. Water issuing from the ports falls downwardly onto the convex spherical surface of the head and is carried thereby into a bowl or receiver located beneath the head and within the pedestal. Substantially all of the functional components of the fountain are concealed within the hollow spherical head and hollow pedestal so as to minimize vandalism of such components and misuse of the fountain.

3,578,248 FLUID SPRINKLER HAVING MEANS FOR DRIVING AND REVERSING AN OSCILLATING DISTRIBUTING TUBE OF UNIFORM SPEED


George L. Congdon, Fort Atkinson, and Fred W. Kufirin, Janesville, Wis., assignors to Western Industries, Inc., Milwaukee, Wis.

Filed July 16, 1969, Ser. No. 842,124

Int. Cl. B05b 3/16

U.S. Cl. 239—242

6 Claims




A fluid sprinkler having an oscillating water tube that moves with a uniform velocity through an arc of adjustable length, including a fluid turbine connected to the distributing tube for oscillating the tube of a uniform velocity and depositing a predetermined amount of water per unit area of ground regardless of water pressure or the length of oscillatory swinging movement of the water tube. The means for oscillating the tube includes a directional flow valve means connected to the tube for instantly reversing the direction of swing of the tube.

3,578,249 FLAT SPRAY ASPIRATING NOZZLE

Orvis A. Davis, Sr., Gibsonia, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
Filed Mar. 5, 1969, Ser. No. 804,450
Int. Cl. B05b 1/28

U.S. Cl. 239—296



A flat spray nozzle utilizing two flows, which may be of two different fuels, or of a fuel and air, and one or both of which may be pressurized. The nozzle includes a front end nosepiece which creates a region of low pressure in its exit orifice, and the exit end of the liquid fuel supply is located at that low-pressure region to thereby cause aspiration of the fuel into the gas as it exits from the nozzle in a flat, fan-shaped spray.

3,578,250 PULPING APPARATUS


William H. Combs, Wayne; Sam N. Craig, Devon; Ellis R. Warner, Jr., West Chester, and Wayne T. Buckman, Pipersville, Pa., assignors to Wascon Systems, Incorporated, Harrisburg, Pa.

Filed Aug. 9, 1968, Ser. No. 751,536

Int. Cl. B02c 18/12, 18/22, 18/40

U.S. Cl. 241—46.02

16 Claims



A pulping apparatus is provided, adapted to receive therein solid debris for comminution to a desired size in a liquid medium, such as water. Water and debris are received in the bottom of a tank having a disklike impeller rotatably driven at the bottom thereof and a sizing ring disposed at the bottom of the tank about the impeller whereby, during rotation of the impeller, there is effected a size reduction of solid particles by means of teeth carried by the impeller. Debris which is sufficiently sized passes through holes in the sizing ring and is discharged from the pulping tank. A particularly novel structure is provided for effecting a scissorslike cutting action by means of cutting elements carried by each of the tank and the rotatable impeller. A novel configuration is also provided for the outermost edge of the impelling disc, relative to the sizing ring such that fluid and debris in the tank is driven across their common running clearances passage, rather than through the passage. A ramp is also provided,


centrally located relative to the impeller, for preventing balling-up of rags and the like at the center of the impeller.

3,578,251 BAR-TYPE ROTARY CRUSHERS

Leonel Beudin, Paris, France, assignor to Bureau De Recherches Geologiques Et Minières, Paris, France
Filed May 24, 1968, Ser. No. 731,848
Claims priority, application France, May 26, 1967, 108,129
Int. Cl. B02c 17/02, 17/10, 17/22

U.S. Cl. 241—74

7 Claims




The crusher has a rotary, generally cylindrical structure, of substantially horizontal axis, which contains free cylindrical or prismatic bars adapted to crush the products introduced into this cylindrical structure. Two girdles are disposed on the interior lateral wall of the cylindrical structures. These girdles form the runway for the bars, and separate the bars from the lateral wall of the cylindrical structure, this separation being greater than the dimensions of the large particles of the products to be crushed.

3,578,252 INDUSTRIAL SHREDDING APPARATUS

John C. Brewer, Salt Lake City, Utah, assignor to Garbalizer Corporation of America, Salt Lake City, Utah
Filed Dec. 13, 1968, Ser. No. 783,665
Int. Cl. B02c 18/06

U.S. Cl. 241—141

22 Claims




The present invention comprises an industrial shredding apparatus which is usable in shredding many types of industrial waste, garbage, trash, and so forth. The shredding apparatus incorporates a pair of oppositely revolving shafts upon which are mounted respective sets of knives or cutting blades disposed such that the tips thereof form, compositely, a helixlike configuration relative to each of the respective shafts. The blades are so arranged that they serve both in holding debris for cutting by adjacent blades, and, additionally, for cutting themselves in their own turn. The shredding mechanism is designed such that the cutting is done centrally of the apparatus, with associated structure being designed for urging debris falling thereon toward a central position relative to the apparatus. The device is ideally

suited for shearing and/or cutting debris and allowing the same to pass through the shredder onto a transport conveyor, for example.

3,578,253 DUAL ROTATION MILL

Arthur Brilliant, Jr., 18 W. 480 Edward, Lombard, Ill.
Filed Oct. 14, 1968, Ser. No. 768,220
Int. Cl. A47j 42/34; B02c 19/12
U.S. Cl. 241-168

5 Claims




A comminuting apparatus particularly adaptable for use in comminuting seeds such as pepper seeds and coffee beans. The apparatus includes a tubular housing including a comminution member coaxially and rotatably disposed therein. The comminution member is constructed to permit clockwise or counterclockwise rotation.

3,578,254 IMPACT CRUSHER

Bruce V. Wood, 10945 S.E. Clay St., Portland, Oreg.
Filed Sept. 23, 1968, Ser. No. 761,508
Int. Cl. B02c 19/00
U.S. Cl. 241-275

5 Claims




An impact crusher having impeller shoes and anvils capable of easy replacement and furthermore capable of repositioning individually in the crusher as wear occurs. The impeller shoes are triangular in shape for operation in forward or reverse directions of rotation without shifting their position. The anvils are supported on a crusher housing by means of brackets capable of adjustment radially in the housing for repositioning the anvils.

3,578,255 PRODUCTION OF A TWISTLESS PAYOUT PACKAGE WITH MEANS FOR DRAWING OUT THE INNER END OF THE MATERIAL

William F. Gordon, Yonkers, and James W. Newman, Scarsdale, N.Y., assignors to Windings, Inc.
Filed Apr. 23, 1969, Ser. No. 818,731
Int. Cl. B65h 54/02, 49/26
U.S. Cl. 242-18

6 Claims



In winding a package of flexible material formed of a plurality of layers each composed of a number of figure-eight lights in which the crossovers progress around the package therein, in which a radial hole is provided opening into the central core space of the package through which the inner end of the material can be led out for twistless payout, an arrangement is provided for facilitating the withdrawal of the free inner end of the package through the opening after winding. This may be a means for holding a loop or elongated piece of the flexible material in a position where it can be easily fished out through the hole when the package is finished; or an arrangement for feeding a pin to which the inner end of the material is attached out through the hole as the package is wound; or to an arrangement for projecting a member out through the hole from the interior of the mandrel.


When a pin is fed out through the hole as the package is wound, this pin may protrude beyond the periphery of the package far enough to aid in or to accomplish the formation of the radial hole without the need for speed variations between the spindle and the guide.

3,578,256 YARN BRAKE OF THE SLING TYPE

Geert J. Vermeulen, Deurne, Netherlands, assignor to N. V. Machinefabriek L. te Strake, Deurne, Netherlands
Filed July 29, 1968, Ser. No. 748,341
Claims priority, application Netherlands, Sept. 12, 1967, 6712482

Int. Cl. B65h 63/00, 59/26
U.S. Cl. 242-36

6 Claims




A yarn brake of the sling type comprising a pair of yarn guides each having yarn guide formations. One of the yarn guides is movable and biased for movement away from the other by suitable means such as a coil mechanically coupled to the guide, to which coil direct current is applied and which is suspended in a magnetic field. A second coil in a magnetic field is mechanically coupled to the movable yarn guide for generating a voltage according to the velocity of movement of the guide. The voltage can be applied to a detector which in turn signals undesirably large fluctuations or movements in the guide.

3,578,257 TAPE HANDLING APPARATUS FOR DATA RECORDER

George R. Cogar, Frankfort; Torkjell Sekse, Marcy; Walter Banziger; Joseph W. Ming, Utica, and Laszlo Horvath, Ilion, N.Y., assignors to Mohawk Data Sciences Corporation, Herkimer, N.Y.
Division of Ser. No. 541,450, Mar. 30, 1966, Pat. No. 3,483,523. Filed Nov. 18, 1968, Ser. No. 786,526

U.S. Cl. 242-68.3

5 Claims




A tape handling system for a data recorder wherein a taper reel is engaged by a holder comprising a pair of circular plates mounted in side-by-side relation and having their edges encircled by a resilient band. One of the plates is fixed on a rotatable shaft with which the other plate is axially movable. The edge of the movable plate tapers outwardly away from the fixed plate so that outward movement of the movable plate causes the resilient band to become disengaged from the movable plate at its maximum dimension. This allows the hub opening of the reel to slip past this maximum dimension and encircle the band and plates. Subsequent inward movement of the movable plate expands the band and causes the reel to slip past this maximum dimension and encircle the band and plates. The tape handling system also includes means for controlling the rotation of the reel to keep the proper amount of tension on the tape when it is being drawn from the reel. The tape is looped around a guide roller mounted on a pivotable tension arm so that the angular position of the arm indicates the amount of tension on the tape. The arm is connected to a brake band passed around a brake drum located on the reel's shaft to regulate the ease with which the reel may rotate and, thereby, the tension on the tape.

3,578,258 RIBBON SPOOL

Wolfgang Fred Heine, Gronton, and Kenneth D. Vought, Owego, N.Y., assignors to SCM Corporation, New York, N.Y.
Filed Jan. 21, 1969, Ser. No. 792,394
Int. Cl. B65h 75/28

U.S. Cl. 242-74.1

7 Claims



A ribbon spool for a fabric ribbon, carbon ribbon, magnetic ribbon or the like molded from a synthetic material as a single unit including a ribbon attaching element. The ribbon attaching element is integral with the spool by a living hinge construction thereby providing the capability of repetitive


movement from a nonribbon attaching position to a ribbon attaching position. The element in cooperation with the spool has a snap-fit construction in the ribbon attaching position to securely attach the ribbon to the spool.

3,578,259 COILABLE RULE LOCKING MECHANISM

Charles Zelnick, Saginaw, and Erwin Schmidt, Bay City, Mich., assignors to Cooper Industries, Inc., Houston, Tex.
Filed May 13, 1968, Ser. No. 728,465
Int. Cl. B65h 75/48

U.S. Cl. 242-107.2

15 Claims




A measuring or like device having a casing with a front wall opening adjacent a bottom wall and a tapeline coilable in the casing and movable out the opening to various projected positions, and wherein an actuator projecting from the front wall of the casing and journaled for pivotal movement from a first pivoted position to a second pivoted position moves a vertically slideable tapeline lock from a position out of braking engagement with the tapeline down to a position in which it resiliently clamps the tapeline against the bottom wall of the casing and holds it in a particular position of extension, cams interconnecting the lock and actuator being operable to cam the lock down to clamp the tapeline when the actuator is pivoted from the first to the second position and to lift the lock up to release the tapeline when the actuator is returned.

3,578,260 INERTIA REEL MECHANISMS

John Kell, Carlisle, Cumberland, England, assignor to Kangel Magnet Limited, London, England
Filed June 25, 1969, Ser. No. 836,502
Claims priority, application Great Britain, June 27, 1968, 30,816/68

U.S. Cl. 242-107.4

8 Claims



In a vehicle-sensitive inertia reel device of the pendulum type, the pendulum is arranged to cause a subsidiary pawl to


move from a first position in which it does not engage with a subsidiary ratchet wheel mounted on the reel to a second position in which it does so engage, rotation of the reel in the direction resisted by the main pawl when the subsidiary pawl is in its second position being operative to move the subsidiary pawl from its second position to a third position and movement of the subsidiary pawl from its second position to its third position being arranged to cause the main pawl to move from a first position in which it engages in one direction and a second position in which it does not so engage.

3,578,261

TAPE RECORDER OF MAGAZINE TYPE
Kozo Yamamoto, Hirakata-shi, and Toshio Kawada, Neyagawa-shi, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan
Filed Feb. 26, 1968, Ser. No. 708,312
Int. Cl. G11b 23/10

U.S. Cl. 242-199

16 Claims




A tape recorder of the magazine type adapted to operate with a magazine of the kind in which a magnetic tape supplied from one reel is taken up on the other. In the tape recorder, the reel shafts and the capstan are mounted on a movable body which is pivotally and linearly movable in response to the insertion of the magazine into the recorder casing whereby the reel shafts and capstan are brought into driving engagement with the corresponding elements in the magazine.

3,578,262

CASSETTE CHANGER WITH FAST TAPE WIND
George C. Mandell, Des Plaines, Ill., assignor to Ampex Corporation

Filed Nov. 10, 1969, Ser. No. 875,208
Int. Cl. G03b 1/04; G11b 15/32, 23/04
U.S. Cl. 242-199

7 Claims




A cassette changer is provided with a tape drive system a portion of which is disabled, preferably whenever the cassette changer shifts to a pause position to space tape drive components and a sound transducer head from the tape, to permit the tape to be driven in either a forward or reverse direction at a speed faster than the operational speed.

3,578,263

VERTICALLY STARTING AND LANDING AIRPLANE
Siegfried Gunter, deceased late of Munich, Ruth Gunter, Executrix, Munich, Germany, assignors to Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung, "Weser" Flugzeugbau/Focke-Wulf/Heinkel Flugzeugbau, Bremen, Germany
Filed July 24, 1969, Ser. No. 870,207
Claims priority, application Germany, July 29, 1968, P 17 56 894.4
Int. Cl. B64c 27/28

U.S. Cl. 244-7

3 Claims



A vertically starting and landing airplane with pivotable propellers in front and behind the center of gravity of the airplane, in which the propellers located in front of the center of gravity of the airplane have a greater number of blades than the propellers located behind the center of gravity of the airplane.


3,578,264

BOUNDARY LAYER CONTROL OF FLOW SEPARATION AND HEAT EXCHANGE

Arnold M. Kuethe, Ann Arbor, Mich., assignor to The Battelle Development Corporation, Columbus, Ohio
Filed July 9, 1968, Ser. No. 743,350
Int. Cl. B64c 21/10, 23/06

U.S. Cl. 244-41

23 Claims



Boundary layer control for delay or prevention of flow separation and/or increase in rate of heat exchange between a surface and a fluid by an arrangement of surface elements which may take the form of either crests or discreet concave depressions in the surface, having effective depths or dimensions of less than that of the adjacent boundary layer thickness, to cause the formation of vortices with succeeded surface elements being positioned to cause vortex amplification, for effective boundary layer mixing with less drag, weight penalty, noise, and energy loss than that of conventional vane-type generators.

3,578,265

AERODYNAMIC STRUCTURES
John W. Paterno, Huntington Beach; Vernon L. White, Los Angeles; Haig Asdurian, and Hans W. Grellmann, Torrance, Calif., assignors to Northrop Corporation, Beverly Hills, Calif.


Filed Oct. 6, 1969, Ser. No. 864,034
Int. Cl. B64c 3/00

U.S. Cl. 244-42

3 Claims

A jet-type aircraft the wings of which define slots or passageways passing through root portions of the wings and

opening on the upper and lower surfaces thereof functioning (1) to divert fuselage boundary layer air from side mounted inlets located below the wings and (2) to reduce adverse



fuselage boundary layer pressure gradients and prevent boundary layer thickening ahead of the engine inlets at high angles of attack or sideslip.


3,578,266

WING AREA ENLARGEMENT SYSTEM
Gerald G. Upton, Seattle, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed June 16, 1969, Ser. No. 833,394
Int. Cl. B64c 3/50

U.S. Cl. 244-43

5 Claims



An aircraft wing provided with at least one pivotally connected section which upon inversion enlarges the width of the wing surface. The section fits preferably against the under surface of the wing and is made of a plurality of segments, disposed somewhat like venetian blinds parallel to the length of the wing. Upon foldout the entire section will swing about a pivot point for approximately 180° while at all times the individual surfaces of the segments are maintained parallel to the main wing surface so that a minimum of air disturbance is experienced upon movement of the section.

3,578,267

CONTROL SYSTEM WITH MULTIPLE FUNCTION CAPABILITY


Edward Kazmarek, Reseda, Calif., assignor to Lear Siegler, Inc., Santa Monica, Calif.

Filed Nov. 21, 1968, Ser. No. 777,798
Int. Cl. B64c 13/24

U.S. Cl. 244-77

22 Claims

A first force-transmitting mechanism is adapted to move relative to a stationary frame responsive to a servoactuator. An element to be controlled is coupled to the first mechanism such that it moves with the first mechanism relative to the frame. A second force-transmitting mechanism is adapted to move relative to the frame in response to a manual input device. Mechanical coupling between the first and second mechanisms enables operation in one of two modes. In one mode, the mechanisms are coupled to move in a mutually independent manner relative to the frame within predetermined limits beyond which they move together. In addition to its normal function, the servoactuator operates responsive to a transducer that senses the displacement between the first and second mechanisms and returns the



to move together relative to the frame without appreciable play.


3,578,268

AUTOMATIC PITCH CONTROL SYSTEM
Kenneth C. Kramer, Thousand Oaks, Calif., assignor to Lear Siegler, Inc., Santa Monica, Calif.

Filed Jan. 21, 1969, Ser. No. 792,366
Int. Cl. B64c 13/08

U.S. Cl. 244-77

3 Claims



The elevator of an aircraft and a tab associated with the elevator are positioned by servoactuators both of which are driven by a common servoamplifier. In an automatic pitch-manuever mode of operation, a constant pitchup trim bias signal is additively combined with the signal from the servoamplifier that drives the trim servoactuator. Prior to the execution of the pitch maneuver, the high-gain servoloop formed by the system overpowers the trim bias signal, thereby nullifying its effect. During the execution of the maneuver, the trim bias provides the added pitchup authority and a pitchup command in case of passive failure. The trim bias signal shifts the response of the aircraft to the pitch maneuver command so this response is unsymmetrical, having greater authority in the pitchup direction.

3,578,269

AUTOMATIC FLARE AND ALTITUDE HOLD SYSTEM
Kenneth C. Kramer, Thousand Oaks; Richard L. Davis, Pacific Palisades, and Otto H. Boe, Saugus, Calif., assignors to Lear Siegler, Inc., Santa Monica, Calif.
Continuation-in-part of application Ser. No. 631,972, Apr. 17, 1967, now abandoned. This application June 11, 1969, Ser. No. 839,766
Int. Cl. B64c 13/18

U.S. Cl. 244-77

27 Claims

The invention disclosed by one representative embodiment herein includes an automatic pitch control system for an aircraft wherein a manual setting at any selected altitude produces a signal which is nulled out by a radar altimeter signal so as to automatically engage a pitch control flare circuit. Altitude error and altitude rate input signals are

remainder of the mold. Wedge shaped members may be formed on the exterior surface of the detachable sidewall to cooperate with the supporting member in fastening the detachable sidewall tightly.

3,578,277

LOCKING ASSEMBLY FOR ELECTRIC OUTBOARD FISHING MOTORS


Ralph C. Osborn, Bloomington, Ill., assignor to Osborn Engineering Corporation

Filed Nov. 3, 1969, Ser. No. 873,186

Int. Cl. B63h 21/26

U.S. Cl. 248-4

4 Claims



A locking assembly for electric outboard fishing motors with a manually actuated and spring-biased rod received within an aperture on the clamping cradle of the assembly when the propeller column supporting bracket and column are substantially horizontally disposed (a storage position) or disposed substantially perpendicularly to the clamping face of said cradle. The rod is part of an angular adjustment mechanism for the motor.

3,578,278

VIBRATION-ISOLATED SELF-LEVELING PLATFORM AND METHOD


Norman C. Pickering, Sag Harbor, N.Y., and Joseph P. Roberts, Arleta, Calif., assignors to ROBINTECH Incorporated

Filed June 16, 1969, Ser. No. 833,570

Int. Cl. A47b 9/02

U.S. Cl. 248-20

19 Claims



A pneumatically supported, load-carrying platform that is precisely controlled against minute excursions from a predetermined position while being cushioned against shock and vibration. The platform structure preferably is pendulously supported by a group of spaced pneumatically pres-

surized mounts or air springs, having individual sensors responsive to incipient deviations in the platform position and which control the pressure applied to the respective mounts so as to restore or maintain the platform within normal limits. Sensitivity of response, and adjustment of the system stability results from regulating the supply of air available to the mounts, and furnishing preestablished incremental pressures above the pressures needed for proper operation of the mounts, which incremental pressures are substantially independent of both the mount pressure and the pressure from the source of supply.

3,578,279

RESILIENT MOUNTING MEANS


Owen H. Scheldorf, Louisville, Ky., assignor to General Electric Company

Filed Sept. 10, 1969, Ser. No. 856,536

Int. Cl. F16f 15/00

U.S. Cl. 248-20

3 Claims



Resilient mounting means comprising an open coil, helical spring and a spring-anchoring means comprising a stud of a smaller diameter than the spring and having a tapered end. The stud has a circumferential groove thereon which is square with the axis of the stud and the end of the spring which is anchored on the stud has an end turn portion which is also square with the spring axis and of a reduced diameter so that when slipped over the tapered end of the stud and positioned within the groove, it grips the stud through an angle of more than 180° to form the sole means for anchoring the spring on the stud. From this anchoring portion, the spring spirals tangentially outwardly from the groove and thereafter, within the first complete turn of the spring, extends helically to clear the tip of the spring end turn.

3,578,280

TWIST TO MOUNT CONDENSER MOUNTING GROMMET FOR REFRIGERATOR


James P. Laughlin, and Everett Worman, Evansville, Ind., assignors to Whirlpool Corporation

Filed Oct. 13, 1969, Ser. No. 865,761

Int. Cl. F16l 3/08

U.S. Cl. 248-54

9 Claims



A vibration isolation mounting for the tubular coils of a refrigerator condenser having a resilient rubbery block for both mounting the condenser on a support structure and absorbing vibrations in the condenser so that these will not be significantly transferred to the support structure.

3,578,281

PRECISION ALIGNMENT FIXTURE


James C. Nielsen, Charleston, S.C., and John J. Turner, Amsterdam, N.Y., assignors to General Electric Company

Filed Feb. 13, 1970, Ser. No. 11,201

Int. Cl. F16m 13/00


U.S. Cl. 248-346

3 Claims



A precision alignment fixture which has a base member and a floating disc between which is situated a pad of grease is described and may be utilized to align heavy workpieces to close tolerances. An O-ring is situated between the base member and floating disc in order to prevent leakage of the grease. The greasing system is of the type which utilizes a spring, ball, and pin together with a feedback arrangement for shutting off the flow of grease. Jack bolts are provided to instigate and control the horizontal aligning movements of the floating disc in any direction.

ing of an integral inwardly projecting protuberance serving to prevent particles of the granular material from lodging



3,578,284

SOLENOID VALVE


Leo A. Martini, Garland, Tex., assignor to Telsco Industries, Garland, Tex.

Filed Mar. 28, 1969, Ser. No. 811,303

Int. Cl. F16k 31/06

U.S. Cl. 251-88

5 Claims



A solenoid valve useable as a pilot for actuating a flow control valve of the pressure responsive type, the solenoid valve having a coaxial valve ball and seat and means upstream of and reciprocable axially of the valve seat for actuating the valve ball which includes a portion for holding said valve ball engaged with the valve seat, a portion spaced from the seated ball for unseating said ball and a valve cage portion in spaced surrounding relation to said valve ball. The valve ball actuating means has at least a portion of magnetic material adapted to function as an armature for a solenoid so as to be attracted thereby for unseating the valve ball, the solenoid including an electromagnetic coil having multifilar windings of fine gauge wire of the order of 0.004 of an inch whereby the coil is of reduced volume and increased efficiency and said solenoid is relatively minute.

3,578,282

HANGER FOR OUTDOOR LIGHT SOCKETS


Carl J. Olsen, 1610 Belmont Ave., Ontario, Canada

Filed Oct. 1, 1969, Ser. No. 862,806

Int. Cl. E04b 7/18; F21v 33/00

U.S. Cl. 248-214

5 Claims



An integral hanger for attaching outdoor light sockets to eave troughs. The hanger has a hooked upper portion for gripping the upper outer edge of an eave trough, and an outwardly protruding portion at its lower end with an aperture for receiving the clip of an outdoor light socket.

3,578,283

ARCuate BLADE GATE VALVE

William H. Jones, Toronto, Ontario, Canada, assignor to Armstrong Jones Limited, Toronto, Ontario, Canada

Filed Apr. 24, 1969, Ser. No. 818,889

Int. Cl. F16k 1/20

U.S. Cl. 251-31

10 Claims

A gate valve of the type commonly used to control the flow of pulverulent or granular material moving by gravity from hoppers and the like. The valve has an arcuate valve plate and the valve casing is formed with a deflector consist-

3,578,285

SAMPLE AND BLEED VALVE

Sydney E. Carlton, 240 W. Hereford St., Gladstone, Oreg.

Filed June 26, 1969, Ser. No. 836,926


Int. Cl. F16k 31/50

U.S. Cl. 251-218

4 Claims

The bleed valve of the present invention has a fixed body member for installation through the wall of the particular pressure vessel involved so as to be in direct communication with the cavity. The main valve portion moves axially from the closed to the open position for bleeding or sampling and is restrained from going beyond the full open position. The


slidable portion is sealed against leakage of fluid pressure by an O-ring which has its own housing in the slidable portion and so remains in position at all times. It is always positioned beyond the fully open position so that no pressure or sample



3,578,288
BUTTERFLY VALVE WITH A SEALING RING HAVING A DOUBLE SWALLOWTAIL SHAPE IN CROSS SECTION
Erik Rishovd, Gelthus, Modum, Norway, assignor to A/S Westad Armaturfabrik, Gelthus, Modum, Norway
Filed Mar. 24, 1969, Ser. No. 809,570
Claims priority, application Norway, Mar. 29, 1968, 1211/68
Int. Cl. F16k 1/22
U.S. Cl. 251-306


4 Claims

escapes beyond the intended outlet. The valve is useful for bleeding air or fluid under pressure in a pressure vessel, pump, or valve, particularly as a means for checking seals, sampling the contents, or reducing internal pressures.



3,578,286
DRAIN VALVE
Boleslaw Klimek, Des Plaines, Ill., assignor to Berg Mfg. & Sales Co., Des Plaines, Ill.
Filed Aug. 19, 1969, Ser. No. 851,205
Int. Cl. F16k 1/16; B21d 53/10
U.S. Cl. 251-303


5 Claims



A fitting part has a flared slot in which is received the open end portion of a cup-shaped closure, the fitting and closure forming a chamber. A valve member is tiltable in an opening in the closure and yieldingly urged thereagainst. A seal is carried by the fitting part adjacent the flared slot.


3,578,287
BUTTERFLY VALVE
Paul G. Salerno, Glenview, and Steven J. Wilson, Chicago, Ill., assignors to Vapor Corporation, Chicago, Ill.
Filed Nov. 5, 1968, Ser. No. 773,458
Int. Cl. F16k 1/228
U.S. Cl. 251-306

5 Claims



Butterfly valve for controlling fluid flow in conduits, and including a butterfly coacting with a seating bore in a casing having a peripherally mounted, solid sealing ring for engage-

ment with a seating bore, wherein the sealing ring is mounted on the butterfly for radial movement to conform to the seating bore when the valve is closed.




3,578,289
SPHERICAL VALVE PLUG
Max Thevignot, Chancenay, and Robert M. Schwebel, Saint-Dizier-Le-Neuf, France, assignors to Etablissements Thevignot
Filed Jan. 28, 1969, Ser. No. 794,595
Claims priority, application France, Jan. 18, 1968, 881
Int. Cl. F16k 5/06
U.S. Cl. 251-309

2 Claims


3,578,290
PORTABLE LOAD-HANDLING DEVICE WITH WINCH
Mohammed S. Gof, 89 Haledon Ave., Paterson, N.J.
Filed Feb. 18, 1969, Ser. No. 800,172
Int. Cl. B66c 23/60
U.S. Cl. 254-139.1

3 Claims



3,578,292
PORTABLE MIXER
Aubrey V. Montague, 1190 Atwater Ave., Port Credit, Ontario, Canada
Filed Jan. 21, 1969, Ser. No. 792,393
Int. Cl. B01f 9/04
U.S. Cl. 259-177

8 Claims




A portable, manually operated winch fabricated of welded-together steel tubing and channel members for economy of manufacture, and comprising wheeled, relatively adjustable and detachable front and rear frame assemblies, the front frame assembly of which has a relatively adjustable and detachable boom subassembly and the rear frame assembly of which has a relatively adjustably and detachable extension support member subassembly. A manually operated crank, ratchet wheel and drum mechanism is provided on the rear frame assembly for controlling a boom-lifting cable.

A lightweight and portable mixing machine having a two-stage speed reduction system wherein a cylindrical vessel is supported for rotation by a drive shaft for a one-stage speed reduction and said drive shaft is operatively connected to a prime mover by a pulley-belt arrangement for a second-stage speed reduction.

3,578,291
TEST TUBE HAVING INTEGRAL MIXING MEANS
Rudolf Oberli, Langenthal, Switzerland, assignor to Greiner Electronic AG, Langenthal, Switzerland
Filed Sept. 26, 1969, Ser. No. 861,251
Claims priority, application Switzerland, Jan. 22, 1969, 876/69
Int. Cl. B01f 11/00
U.S. Cl. 259-75


7 Claims



A test tube for mixing liquids, characterized by the provision of integral stirring means extending longitudinally from the bottom wall in spaced relation to the sidewall of the tube. The stirring means preferably is of knifelike configuration including a longitudinal edge adjacent and spaced from the internal surface of the sidewall whereby upon oscillation of the test tube about its longitudinal axis, a vortex is formed adjacent the edge to effect rapid thorough mixing. Preferably the test tube has a capacity of between about 0.5 and 5 milliliters and is designed for disposal after a single use.

3,578,293
AUTOMATIC CHOKE ACTUATOR FOR SMALL ENGINES
John D. Santi, West Allis, Wis., assignor to Briggs & Stratton Corporation, Wauwatosa, Wis.
Filed Dec. 6, 1968, Ser. No. 781,940
Int. Cl. F02m 1/14
U.S. Cl. 261-64

4 Claims




In an automatic choke actuator wherein the choke is spring-biased toward closed position and is opened by suction in a suction chamber acting on a pressure responsive actuator linked to the choke, the suction chamber is communicated with the fuel induction zone of the carburetor induction passage through a duct controlled by a pressure responsive throttling valve opened by suction in the induction passage and which closes to restrict flow of air back into the suction chamber.

3,578,294
SMOKE ELIMINATOR
Metody Chruniak, 27 Carlton St., Salem, Mass.
Filed June 19, 1969, Ser. No. 834,667
Int. Cl. B01f 3/04
U.S. Cl. 261-90

2 Claims

This invention consists of a horizontally disposed metal drum in the top of which water is piped under pressure through one or more nozzles. A horizontally disposed paddle wheel is located within the drum which is provided with end plates. The paddle wheel is rotated by an electric motor as smoke, from any desired type of burner or furnace, is piped horizontally into one end of the drum where the smoke dis-

appears on mixing with the churned water. Two or more of the aforesaid drums can be connected end to end depending on the amount of smoke to be eliminated. The paddle wheel of each drum is driven by a separate electric motor, while the grate whose upper surface slopes toward a central opening and receives material from a rotary distributor. Products of combustion are fed into the vessel below the grate so that the ascending gas fluidizes the material above the grate. The material travels toward and into the opening of the grate and



smoke from the first drum will be fed on into the second drum and so on until all of the smoke disappears. The water is drained from the opposite and lower end of each drum from which the smoke enters the drum.

3,578,295

SELF-CONTAINED ABSORPTION GAS CHARGER FOR LIQUIDS


James L. Hudson, 5950 Yorkshire Road, Detroit, Mich.

Filed July 29, 1969, Ser. No. 845,749

Int. Cl. B01f 3/04

U.S. Cl. 261-122

7 Claims



is evacuated by way of a central conduit to enter an adjustable pneumatic conveyor which classifies treated material according to size. A revolving scraper is employed to prevent clogging of the grate and/or caking of material along its upper surface.

3,578,297

APPARATUS FOR COOLING PARTICLES


Lee H. Niems, 2702 Brassie, Flossmoor, Ill.

Filed June 23, 1969, Ser. No. 835,696

Int. Cl. F27b 7/02

U.S. Cl. 263-32

16 Claims



A pressure-tight receptacle contains the water or other liquid to be saturated with gas, such as carbon dioxide gas supplied to it from a conventional carbon dioxide cylinder, through an elongated capillary tube leading to a porous sintered powdered metal diffuser which creates a myriad of small bubbles of the gas which, passing upward through the liquid, saturates the liquid with gas. The elongated capillary tube retards the flow of gas to the diffuser and thereby prevents the gas bubbles from being discharged therefrom too rapidly for the liquid to absorb them. The surplus gas not absorbed by the liquid collects in the top space above the liquid level and serves as a pressurized chamber to dispense the carbonated liquid through a dispensing pipe leading to the bottom of the receptacle. The diffuser is supported by a pipe through which the capillary tube extends and is protected thereby.

3,578,296

APPARATUS FOR TREATING PARTICULATE MATERIALS

Michel Boucraut, Metz; Imre Toth, Longeville les Metz, and Jean Pierre Reyter, Maizieres les Metz, France, assignors to Institut De Recherches De La Siderurgie Francaise, St. Germain-en-Laye, Yvelines, France

Filed June 27, 1969, Ser. No. 837,101

Claims priority, application France, July 10, 1968, 158562

Int. Cl. F27b 15/08

U.S. Cl. 263-21A

10 Claims

Apparatus for drying particulate materials having particles of different sizes comprises an upright vessel provided with a

Apparatus for cooling heated pieces of matter and particularly calcined lime pebbles or particles, wherein cool air is injected under positive pressure into the path of and counter to the downwardly moving mass of pebbles with a coincident partial downward flow of air which is automatically balanced and prevented from blowing free particles of dust from the mass into the surrounding atmosphere by sucking the downward flowing air and coincident dust particles into a negative pressure recirculating path also generated by the positive pressure means.

This invention is directed to a method and apparatus for air cooling high temperature masses of particles continuously discharged from pyroprocessing apparatus here exemplified by calcined lime pebbles such as are produced from a limestone calcining operation in a kiln. The invention is not limited to cooling of lime pebbles alone, however, since it

may be applied to cooling other heated pieces of matter such as deadburned dolomite, cement, expanded shale and the like. The term particles are used herein refers to the many forms of such materials including large and small pieces, pebbles, granules, broke solids, fragments, clinkers etc. In this regard, lime particles cooled in the apparatus herein described may, for example, range in size from dust less than 60 mesh to 1 inch to 2 1/2 inch pebbles or larger.

3,578,298

METHOD AND APPARATUS FOR CEMENT KILN CONTROL


Myron Robert Hurlbut, Peabody, Mass.; Robert Arthur Phillips, and Leland Chester Tupper, Schenectady, N.Y., assignors to General Electric Company

Filed Sept. 26, 1969, Ser. No. 861,424

Int. Cl. F27b 7/20

U.S. Cl. 263-32

19 Claims



A rotary cement kiln control system and method. Burning zone temperature and torque measurements generate a total process error apportioned to fuel and speed control for the kiln. The control system responds to short-term process disturbances to maintain thermal stability in the kiln and the contributions of the burning zone temperature and torque measurements are modified in accordance with thermal stability. Feedback representing expected variations in the measurements is provided. Unusual or adverse conditions are sensed to generate override signals. The effect of torque in the chain section of the wet kiln is also considered in control.

3,578,299

METHOD AND APPARATUS FOR CEMENT KILN CONTROL


Myron R. Hurlbut, Peabody, Mass., assignor to General Electric Company

Filed Sept. 26, 1969, Ser. No. 861,425

Int. Cl. F27b 7/20

U.S. Cl. 263-32

10 Claims



A method and apparatus for controlling the operation of a rotary cement kiln which is fed with an incoming slurry. The

fuel rate set point and the exit gas rate set point are controlled. The control of fuel rate set point is based upon kiln drive motor torque measurements in conjunction with feedback signals generated by a dynamic kiln model which stores a record of past control actions and a calculated effect of the slurry drying characteristics in the kiln. Control of the exit gas rate set point is based upon measurements of gas temperature at the feed end of the kiln. Oxygen content of the exit gas is monitored and employed to exercise overriding control to insure that no combustibles which might cause an explosion appear in the exit gas.

3,578,300

BAKING FURNACE


Allen C. Goodrich, East Aurora, N.Y., assignor to The Carborundum Company, Niagara Falls, N.Y.

Filed Dec. 20, 1968, Ser. No. 785,519

Int. Cl. F27b 5/00

U.S. Cl. 263-41

7 Claims



A baking furnace for carbonaceous bodies, such as electrodes for the steel industry, having metal flues extending therethrough for conveying the baking heat to the baking media that surrounds the bodies. Inserts of heat conductive material are strategically placed in the media so as to facilitate the distribution of heat from the flues to the area of the bodies and to obtain a uniformity of baking temperature therearound.

3,578,301

FURNACE SUPPORT FOR RESINOID PREFORMS


Gardner E. Alden, Fayville, and George M. Herterick, West-boro, Mass., assignors to Avco Corporation, Cincinnati, Ohio

Filed Nov. 6, 1969, Ser. No. 874,610

Int. Cl. F27b 21/00

U.S. Cl. 263-47

9 Claims



The invention relates to a support used in combination with a resinoid preform for maintaining the shape of the preform as it is cured in a furnace. More particularly, the invention relates to a furnace batt used to support a preform of a resinoid grinding wheel while the wheel is cured in a furnace at elevated temperature, usually over prolonged period of times. Broadly, the invention comprises a substrate which conforms very closely to the shape of the preform. The top and bottom surface of the substrate is coated with a hard metal coating. Preferably the exposed surface of the coating has a textured or roughened surface. The hard metal coating is, in turn, covered with a fluorocarbon composition. In the preferred embodiment an aluminum substrate is coated with molybdenum, the latter having a textured surface. A fluorocarbon coating is applied over the molybdenum.

3,578,302

GAS CUPOLA FURNACE WITH A SPECIAL SUPERHEAT HEARTH

Anatoly Alexeevich Cherney, ulitsa Tsiolkovskogo, 41, kv.; Vladimir Alexandrovich Grachev, ulitsa Uritskogo, 74, kv. 9, Penza; Lev Mikhailovich Marienbakh, ulitsa Bolshaya Cherkizovskaya, Korpus, 1, kv. 73, Moscow; Ivan Lukich Kurbatsky, ulitsa Volodarskogo, 70, kv. 4; Efim Davidovich Sosnovsky, ulitsa Sbornaya, 7, kv. 35, and Nikolai Semenovitch Pavlenko, ulitsa Dokuchaeva, 1, kv. 18, Penza, U.S.S.R.

Filed May 15, 1967, Ser. No. 638,204


Claims priority, application U.S.S.R., June 27, 1966,

1088005

Int. Cl. C22b 9/12

U.S. Cl. 266-11

8 Claims



A gas cupola furnace for making metals, said furnace having a hearth comprising various chemical reagents which contact the molten metals for the purpose of changing the chemical composition thereof.

3,578,303

OLEO-PNEUMATIC SHOCK ABSORBERS


John P. Fullam, Baie O'Urfe, Quebec, Canada, assignor to Abex Industries of Canada Ltd., Montreal, Quebec, Canada

Filed Apr. 2, 1969, Ser. No. 812,652

Int. Cl. F16f 5/00

U.S. Cl. 267-64

8 Claims



A two-stage oleo-pneumatic shock absorber incorporating an overload relief valve for instantaneous damping of transient loads. A cylindrical oil chamber is separated by a movable orifice plate into high- and low-pressure stages which are connected by a hollow metering pin passing through the orifice. The relief valve comprises a high-pressure air chamber separated from the oil in the high-pressure stage by an annular floating piston which encircles and nor-

mally covers large holes in the metering pin. When a transient load increases the oil pressure in the shock absorber, the floating piston moves, compresses the air, uncovers the holes and "dumps" high-pressure oil down the hollow metering pin to the low-pressure side of the orifice plate.

3,578,304

APPARATUS FOR DAMPING OSCILLATIONS

Wolfgang Hasselbach, Königstein, and Heinz Heim, Egel-sbach, Germany, assignors to Braun Aktiengesellschaft, Frankfurt, Main, Germany

Filed Dec. 10, 1968, Ser. No. 782,530


Claims priority, application Germany, Dec. 14, 1967,

P 15 72 419.3

Int. Cl. F16f 5/00

U.S. Cl. 267-121

9 Claims



A shock absorber for electroacoustical instruments such as record players also suppresses oscillations in the audible frequency range which interfere with the quality of the reproduced sound. The dual function of the shock absorber is carried out by a combination of dampers in a system providing three-dimensional freedom of motion. The shock absorber thus is an acoustic filter for periodic and aperiodic oscillations with varying amplitude-frequency characteristics.

3,578,305

SPRING


Otto Muelhauser, Berghausen, Germany, assignor to Gesellschaft Fur Kernforschung G.m.b.H.

Filed Aug. 28, 1968, Ser. No. 764,366

Int. Cl. F16f 1/34

U.S. Cl. 267-165

5 Claims



A novel spring composed of a multiplicity of doubly arcuate plates (preferably hyperbolic paraboloids) which are attached together into a stack. The particular attachment means is for next adjacent plates to be attached to each other along a pair of opposite edges with each plate being attached to the plate before it and the plate after it by alternating opposite edge pairs (preferably 90° apart).

3,578,306

AIR PRESSURE OPERATED CLAMP


Kenneth C. Smith, 35 Harbord Drive, Bloomington, Ill.

Filed June 5, 1969, Ser. No. 830,704

Int. Cl. B23q 3/08

U.S. Cl. 269-24

14 Claims



A workpiece is clamped to a supporting surface by slidable extension and pivotable displacement of a lever element relative to a mounting body. An air operated piston extends the lever element from the body against the bias of a retraction spring. When the piston reaches a limit position, the lever element is automatically pivoted under a larger clamping force transversely of the piston to clamp the workpiece at its outer engaging end.

3,578,307

PIPE WRENCH CONSTRUCTION


Coy B. Lock, Alice, Tex., assignor to Clemens N. Freybig, Alice and Paul Racusin, Corpus Christi, Tex., a fractional part interest to each

Filed May 6, 1969, Ser. No. 822,139

Int. Cl. B34q 3/02; B25b 13/16

U.S. Cl. 269-96

8 Claims



A wrench construction including an elongated handle having an endwise facing stationary jaw at one end and defining a short sleeve disposed to one side of the stationary jaw. An elongated threaded shank is slidably received through the sleeve and includes a second laterally outwardly projecting movable jaw facing toward, opposing and aligned with the stationary jaw. A thrust nut is threaded on the shank and opposes the sleeve end remote from the movable jaw. Further, an overcenter lever assembly is connected between the handle and the nut for shifting the shank relative to the handle.

3,578,308

WISE


John Jesionowski, 1437 Chrysler Ave., Schenectady, N.Y.

Filed May 27, 1968, Ser. No. 732,313

Int. Cl. B25b 1/12

U.S. Cl. 269-212

1 Claim



A quick-acting precision vise including a movable jaw movable rectilinearly toward and away from a stationary or immovable jaw along an anchored vise rack or power bar

whereby the jaws may be first manually and quickly brought into contact with two opposite sides of a workpiece, and may be secondly forced into accurate tight locked gripping contact therewith by application of the power of a comparatively fine screw and without causing stress or distortion of the workpiece or of the workholder.

3,578,309

MULTIPURPOSE CONCRETE FORM CLAMP


Albert Freedman, 7451 N.W. 63rd St., Miami, Fla.

Filed Aug. 4, 1969, Ser. No. 847,120

Int. Cl. E04g 17/06, 13/02

U.S. Cl. 269-287

4 Claims



A multipurpose form clamp for use in forming concrete beams and columns is described. Each clamp is fabricated of a pair of angle-iron leg members held in spaced relation by an end angle-iron member at one end and a pair of intermediate, mutually spaced transverse angle-iron members defining therebetween an opening for the reception of an interconnecting bolt for securing a pair of clamps against the outsides of spaced, parallel column forms. The clamps are also usable as beam-forming clamps by straddling the open ends of their leg members over the upper ends of beam form boards. Each clamp is provided with a right-angular bracket member projecting from one side, which serves as a locating slot for the reception of continuous wales upon use of the clamps in beam forming, and which provide means for hookingly interengaging the clamps when used for the support of corner column form boards.

3,578,310

SIGNATURE OR SHEET COLLATING SYSTEM


Joseph R. Carson, Jr., Lancaster, N.Y., assignor to J. W. Clement Company, Depew, N.Y.

Filed June 25, 1969, Ser. No. 836,453

Int. Cl. B65h 39/02

U.S. Cl. 270-54

10 Claims



In a signature or sheet collating system having N groups of feeders delivering signatures out of phase one to another onto a collating conveyor and caliper devices serving to detect a malfunction in the delivery of signatures by the feeders, the improvement comprising an electrical monitoring device including a shift register adapted to receive signals from the caliper devices in accordance with the position at which a malfunction occurs along the conveyor and being effective to reject a book rendered imperfect by a malfunction at a station beyond the last feeder, the shift register being formed of N banks of functional elements driven in synchronization one with each group of feeders. The N banks are serially interconnected by spacer functional elements permitting delay in driving of a succeeding bank, so as to per-

mit spacing between adjacent groups of feeders to exceed the spacing between individual feeders forming such groups.

3,578,311

FOLDING METHOD AND APPARATUS THEREFOR


Philip W. Wood, Larchmont, N.Y.; Terry L. Carter, Jr., and Terry L. Carter, III, Sparta, N.J., assignors to Cities Service Company

Filed May 29, 1969, Ser. No. 828,828

Int. Cl. B65h 45/14

U.S. Cl. 270—69

7 Claims



A method and apparatus for forming multitransverse folds in limp sheets, preferably polyethylene bags, is disclosed. The method consists essentially of placing the sheet intermediate its ends opposite a pair of adjacent counterrotating rolls having their adjacent surfaces moving away from the sheet, and tucking the sheet into the rolls by applying jets of high velocity air against the sheet in the area opposite the rolls. The pair of rolls draw the sheet between themselves, folding it over itself at the point the sheet enters the space between the rolls. Similarly, a second transverse fold is made by positioning the folded sheet intermediate its folded and unfolded ends opposite a second pair of counterrotating rolls having adjacent surfaces moving away from the sheet, tucking the folded sheet into the second pair of rolls by applying jets of high velocity air against the sheet and drawing the sheet into the second pair of rolls, folding it over itself a second time. The twice-folded sheets are then counted and a predetermined number of sheets are stacked on top of each other before being removed. A machine for accomplishing the method of this invention comprises a frame a first nip roll mounted horizontally on the frame, a second nip roll mounted adjacent the first roll, a third nip roll mounted directly below the second nip roll, all three nip rolls being driven counterrotationally to each other by a motor and suitable gears. A first set of air nozzles are positioned on the frame above the space between the first and second nip rolls and is supplied with air in response to the presence of a sheet in position on the nip rolls. Similarly, a second set of air nozzles are mounted on the frame and directed towards the juxtaposed second and third nip rolls, and are supplied with air in response to the presence of the fold sheet opposite the rolls. Additionally a counter, program timer, counting conveyor, pivoted elevator and holding conveyor are mounted on the frame to count and stack the folded sheets.

3,578,312

SHEET FEEDING APPARATUS

Franz Kocourek, Munich, Germany, assignor to Agfa-Gevaert Aktiengesellschaft, Leverkusen, Germany

Filed Apr. 1, 1969, Ser. No. 811,741

Claims priority, application Germany, Apr. 4, 1968,

P 17 72 141.4


Int. Cl. B65h 3/08

U.S. Cl. 271—20

7 Claims

The foremost sheet of a pile of smooth-surfaced sheets abuts against a roller with its upper portion, and is located behind an upwardly extending stop with its lower edge prior

to separation from the next following sheet. Such separation is brought about by a suction head which moves a portion of the foremost sheet away from the next-following sheet so that the foremost sheet is flexed between the roller and the stop and permits air to penetrate between its rear surface and the



front surface of tee next-following sheet. After a predetermined period of dwell in a position corresponding to maximum flexing of tee foremost sheet, the suction head causes the lower edge of the foremost sheet to clear the stop and to move downwardly into the range of driven advancing rolls.

3,578,313

RECORD CARD HOPPER LOAD-REDUCING DEVICE


Rolf H. Eppinger, Detroit, Mich., assignor to Burroughs Corporation, Detroit, Mich.

Filed Feb. 24, 1969, Ser. No. 801,553

Int. Cl. B65h 3/42

U.S. Cl. 271—41

3 Claims



The disclosure embodies a card stack hopper, a card feeder to feed cards singly from the bottom of the stack, and a card baffle which precludes the descent of cards from an upper portion of the stack to a lower portion of the stack until the height of the latter is decreased to a predetermined level.

3,578,314

BRUSH FEEDER FOR WARPED SHEETS

Henry D. Ward, Jr., Phoenix, Md., assignor to The Ward-Turner Machinery Company, Baltimore, Md.

Filed Nov. 25, 1968, Ser. No. 778,629


Int. Cl. B65h 1/06, 5/16

U.S. Cl. 271—44

21 Claims

This invention pertains generally to sheet feeding apparatus wherein a bottom feeder is provided for bottom feeding of sheets from a stack in a hopper. The hopper is provided with sheet retaining and aligning vertical means. A reciprocating feeder bar with spring clips works beneath the hopper. A revolving friction brush positioned to wipe against

the trailing edges of the stack of sheets continuously brushes against movement when uncoupled, and control means limiting uncoupling of the shuttle to a predetermined shuttle operating position.



**3,578,317
SHEET CONVEYOR APPARATUS FOR AUTOMATIC COPYING MACHINE**


Edward H. Burnham, and Edward J. Lavander, Rochester, N.Y., assignors to Xerox Corporation, Rochester, N.Y.

Filed May 14, 1969, Ser. No. 824,543

Int. Cl. B65h 29/68

U.S. Cl. 271—69

6 Claims



lowermost sheet for engagement by an extractor ledge as it rests upon an extended ledge of lips.

3,578,315

OVERLAPPED DOCUMENT DETECTOR


Richard E. Milford, Phoenix, Ariz., assignor to Honeywell Information Systems Inc.

Filed Oct. 4, 1968, Ser. No. 765,062

Int. Cl. B65h 7/12

U.S. Cl. 271—47

10 Claims



A document handling system is disclosed in which the documents are serially-fed along a predetermined path. The system further includes a sensor apparatus to detect any overlapped feeding of the documents.

3,578,316

DRIVING APPARATUS FOR ARTICLE FEEDERS


Donald W. Watson, Arlington Heights, and Herbert C. Artelt, Jr., Wildwood, Ill., assignors to Xerox Corporation, Rochester, N.Y.

Filed Nov. 12, 1968, Ser. No. 774,956

Int. Cl. B65h 7/18

U.S. Cl. 271—54

5 Claims



A driving apparatus for shuttle type article feeders, the apparatus including a latch mechanism adapted to couple the shuttle with a reciprocating driving element, abutment means selectively interposed in the path of movement of the latch mechanism and contactable with an operating arm of the latch mechanism to cause release of the latch mechanism and uncoupling of the shuttle, means to restrain the shuttle

**3,578,318
PNEUMATIC AMUSEMENT AND EDUCATIONAL DEVICE**

James V. Young, Clayton, Mo., assignor to Monsanto company, St. Louis, Mo.

Filed Feb. 20, 1969, Ser. No. 800,953

Int. Cl. A63g 31/00

U.S. Cl. 272—1R

17 Claims



A pneumatic amusement and educational device consisting of at least two bellows structures and an interconnecting hose


which affords an action similar to a seesaw for two or more riders.

3,578,319 MARBLE PICKUP GAME WITH FLEXIBLE MANIPULATOR

Frank Kohner, New York, N.Y.; Albert Stubbman, Franklin Lakes, N.J., and Natalie Donna, New York, N.Y., assignors to Kohner Bros., Inc., East Paterson, N.J.

Filed Dec. 20, 1968, Ser. No. 785,471
Int. Cl. A63f 9/00

U.S. Cl. 273-1(R)



A dish-shaped concave base is provided with a plurality of open-ended upright tubular goal seats adjacent the outer periphery thereof. Several marbles are placed within the base and a manipulator is employed to carry a single marble from the central portion of the base to a seated position on the open end of one of the tubular goal seats. The manipulator is an elongated member having a handle at one end and at the other end, a pickup member with a cut out portion suitable for sliding under the major spherical diameter of a marble resting on the base and lifting the marble. Intermediate its ends, the manipulator is formed of a plurality of segments joined by hinges, the pivotal axes of which are all parallel. The hinges permit movement of the segments with respect to one another while maintaining all of the moving segments within the same plane transverse to the pivotal hinge axes and ideally horizontal when the game is being played. A player lifts one of the marbles from the base by the pickup member in the front of the manipulator and places the marble over and onto one of the tubular goal seats to score a point in the game.


3,578,320 GAME STRUCTURE AND METHOD

Adolph E. Goldfarb, 7427 Varna St., and Rene Soriano, Los Angeles, Calif.

Filed Feb. 19, 1968, Ser. No. 706,439
Int. Cl. A63f 7/02

U.S. Cl. 273-1

10 Claims



A game comprising a hollow upright transparent conduit having a plurality of apertures in an intermediate section to releasably receive and support a plurality of rods which form a variable interdependent network barrier across the conduit. The rods support a plurality of discrete objects such as marbles, and the players of the game remove the rods one at a time, with each endeavoring to remove a rod in accordance with a game objective such as not permitting any marbles to

fall through the barrier. The objects are of such a size with respect to the conduit that at least two rods are necessary to prevent passage of the objects. A method of playing a game comprising positioning a plurality of rods to form a network barrier across a flow path; positioning a plurality of objects upstream of the flow path above the barrier; and selectively removing the rods successively to control the passage of objects past the barrier.


3,578,321 PUTTER-POOL GAME DEVICE

Charles M. Skully, 10 N. Main St., Akron, Ohio, and Richard W. LaConte, 320 S. O. M. Road, Cleveland, Ohio

Filed Apr. 15, 1968, Ser. No. 721,456
Int. Cl. A63g 31/00

U.S. Cl. 273-2

6 Claims



A game device which is a portable package having a smooth carpeted playing surface and edges to define a pool table configuration, with pockets and bumpers, where the package unfolds to lay flat on the floor to stretch the carpet tight because of the abutment of the carrying base when the device is unfolded. Golf balls are utilized as the balls and putted with a putter to achieve the combination of putting with pool. The device is portable and can be folded to store all the balls and clubs inside between the carpeted surfaces in the folded condition. A carrying handle also serves to retain the device in the folded condition.

3,578,322 RAMP STRUCTURE

John T. Kerr, 1343 W. 42nd St., Baltimore, Md.

Filed Oct. 13, 1969, Ser. No. 865,640
Int. Cl. A63d 5/00

U.S. Cl. 273-54R

6 Claims



A ramp structure is provided. It consists of a lap board for a sitting player and parallel rails for launching a rolling ball. The flat undersurface of the lap board rests on the thighs of the sitting player. Spaced apertures on the board are provided for storage of bowling balls.


3,578,323 PORTABLE RUNNING CHUTE

James T. Coleman, and James W. Fox, Paducah, Ky., assignors to Coleman-Fox, Inc., Paducah, Ky.

Filed June 27, 1968, Ser. No. 740,558
Int. Cl. A63b 67/00

U.S. Cl. 273-55

9 Claims



A training device for runners is provided wherein an elongated framework is positioned above the ground at a height lower than the normal height of the runner so that an extended overhead obstruction is provided. The framework includes crossmembers at spaced intervals and a plurality of resilient crosslines at spaced intervals different from said crossmembers with the latter being at a lower position so that a multilevel obstruction is provided to simulate spaced obstacles along the chute. The framework is supported by upright U-shaped stands at each end of the chute that also serve as indicating devices as to the relative position of the overhead obstruction. Further, adjusting means is provided to allow varying the height of the framework for different exercises and different height runners.


3,578,324 FOOTBALL BLOCKING APPARATUS

George H. Alvey, 2805 N. Garvin St.; Paul E. McDaniels, 1100 N. Kelsey Ave., Ind., and Roy T. Pease, Jr., 3301 Cave Ave., Evansville, Ind.

Filed Dec. 2, 1968, Ser. No. 780,473
Int. Cl. A63b 67/00

U.S. Cl. 273-55

1 Claim



An athletic practice apparatus having particular adaptability for the game of football characterized by the movement of a blocking structure from a first position to a second position by reason of body contact, and when at such second position, a thrust member is released to move the blocking structure in the direction of the first position.


3,578,325 A BALL AND IMPACT Mallet

Roy K. Teas, 1100 Bluemont, Manhattan, Kans.

Filed Oct. 17, 1969, Ser. No. 867,142
Int. Cl. A63b 59/10, 67/00

U.S. Cl. 273-56

4 Claims



This invention is a game structure to be played on a given course area with the use of lifter structures, ball members usable with respective ones of the lifter structures, and various configurations of wicket members. More particularly, this invention relates to a lifter structure having a handle member connected to a head member whereupon the head member is provided with an outer inclined impact end section having a central groove to achieve two point contact with the ball member when striking and lifting the same.


3,578,326 AIR OPERATED AMUSEMENT DEVICE

Richard L. Brown, 1812 Pelton Ave., Bellevue, Nebr.

Filed Feb. 27, 1969, Ser. No. 803,005
Int. Cl. A63b 71/00

U.S. Cl. 273-101

24 Claims



This invention relates to an amusement apparatus for use in amusement parks and like places in which a number of successive contestants may try their skill in the operation thereof. The air operated amusement device comprises a compressed air source adapted to direct an airstream through a specially mounted upright elongate nozzle to propel a lightweight spherical body located within an enclosure toward one or more elevated targets located therewithin. The amusement device is a preferred form further comprises a pair of manual-controls including a first control-lever adapted to control the airflow rate through the nozzle and including a second control-lever adapted to position the nozzle axis within a continuous plurality of conical loci of selectable slopes with a common apex surrounding a vertical datum axis whereby simultaneous manipulation of the two control levers permits tridirectional aerodynamic movement of the spherical ball toward the several targets including targets horizontally offset from the vertical datum axis.

3,578,327


TARGET PROVIDING AN INDICATING SIGNAL UPON IMPACT BY A PROJECTILE OF A PARTICULAR PORTION OF THE TARGET

Calvin D. Pickell, Woodland Hills, and Maury Klevens, Los Angeles, Calif., assignors to Marksman Manufacturing Corporation

Filed Sept. 18, 1968, Ser. No. 760,411
Int. Cl. F41j 5/04

U.S. Cl. 273—102.2

9 Claims



There is disclosed herein an improved target arrangement for providing a preselected indicating signal upon impact of a projectile upon particular portions of the target. A plurality of target rings, each having a projective impingeable area, are pivotally mounted in a spaced apart relationship so that apertures in the first and all intermediate target rings provide a projectile passageway therethrough. A device to stop the target is provided behind each target ring to limit the pivotal angular movement of the target ring when that particular target ring is struck by a projectile. The pivotal motion of each of the target rings is highly damped, and when the target ring contacts the stop device there is generated an indicating signal unique to that particular target ring so that it may be easily determined which target ring was struck by the projectile.

3,578,328


ARROWHEAD WITH PIVOTED BLADES

Donald H. Rickey, 1521 Carlisle Ave., Richmond, Va.
Filed Aug. 9, 1968, Ser. No. 751,410

Int. Cl. F41b 5/02

U.S. Cl. 273—106.5(B)

3 Claims



An arrow head having sharpened blades pivotally mounted in a slot in the head and constructed and arranged, in response to impact with and penetration into a target, to automatically pivot outwardly from a first position wherein the forwardly directed points of the blades are confined within the slot, to a second position wherein they are fully extended. Each blade is essentially planar and is provided with an integral radial extension or lug which in first position projects outwardly from the confines of the slot, and which may not only assist in pivoting it from first to second position, but also in cooperation with stop means fixed with the head, positively limit movement thereof to second position while permitting ready withdrawal of the head.

3,578,329

A WIRE LOOP AMUSEMENT GAME


Louis Biedny, 27 Patton Drive, Somerset, N.J. 08873

Filed May 26, 1969, Ser. No. 827,629

Int. Cl. A63f 7/00

U.S. Cl. 273—119

4 Claims



An amusement device including a base element, a wirelike guide element supported by said base element and extending upwardly therefrom, the guide element having a downwardly extending loop. A compressible resilient means surrounds the guide element and rests on the base element, said resilient means supporting selectively a plurality of weighted members which slide on the guide element, whereby depending upon the degree of compression of said resilient element, upon release, one or more of said weighted members are urged past the downwardly extending loop portion of the guide element.

3,578,330

JIGSAW PUZZLE OF A SIZE REQUIRING LARGE MUSCLE EXERCISE


Irving Brambier, 841 Duncan Drive, Westbury, N.Y.

Filed May 1, 1968, Ser. No. 725,781

Int. Cl. A63f 9/12

U.S. Cl. 273—157

3 Claims



A jigsaw puzzle formed by a plurality of relatively large interlocking pieces providing for large muscle activity, with the assembled puzzle having an upper surface bearing a pictorial scene having an area for occupancy by a participant in the pictorial scene, so that the player may assume a position on said puzzle when the pieces are in assembled relationship with the player forming a part of the assembled scene.

3,578,331

THREE DIMENSIONAL PUZZLES

Hilaire G. DeGast, 1508 N. Quinn St., Arlington, Va.

Filed Feb. 20, 1969, Ser. No. 800,858


Int. Cl. A63f 9/12

U.S. Cl. 273—157R

3 Claims

Three-dimensional puzzles are disclosed for forming a hollow ornamental object having a surface of revolution. The surface is formed, for the most part, of a plurality of substantially identical puzzle pieces each of which has projections

and complementary recesses about its periphery for cooperation with corresponding complementary recesses and projections on a contiguous piece. In one embodiment, the surface



is a sphere, and the pieces are arranged in sets forming triangular and pentagonal portions of the spherical surface. In a second embodiment, the surface of revolution is cylindrical. A pair of such cylindrical surfaces intersect to form a cross.

3,578,332

GOLF PUTTER WITH CENTRALLY LOCATED SPHEROIDAL ENLARGEMENT

Stanley Benson Caldwell, The Royd, Meols Drive, Hoylake, England

Filed Sept. 3, 1968, Ser. No. 756,955


Claims priority, application Great Britain, Sept. 9, 1967,

41266/67

Int. Cl. A63b 53/04

U.S. Cl. 273—164

2 Claims



This invention relates to a putter which comprises a head formed with a medial, upwardly and rearwardly extending spheroidal enlargement having its center of curvature in line with the upper edges of the heel and toe of said head, and a shaft the axis whereof intersects the transverse axis of said spheroidal enlargement.

3,578,333

PRACTICE GOLF GREEN INCLUDING UNDULATED AREA AND THICKENED TAPERED CUP RECEIVING END PORTION


Joseph Elesh, Skokie, Ill., assignor to International Recreation Products, Inc., Skokie, Ill.

Filed Mar. 24, 1969, Ser. No. 809,540

Int. Cl. A63b 67/02

U.S. Cl. 273—176R

1 Claim



The disclosure describes a golf game for both indoor and outdoor use comprising a mat with a clipping tee and a driving tee thereon and an artificial golf green having a cup and

flag, with indicia on the surface of the green marking off areas progressively further away from the cup, with values assigned to the green areas for evaluating golf shots to the green. The green includes an undulated area and a thickened tapered end portion including an integral molded cup of regulation size. The mat and green are separable so that the distance between them can be varied at will depending on the space available. The device can be used with either a practice ball or a regular golf ball.

3,578,334

AUTOMATIC PLAYING APPARATUS UTILIZING PLURALITY OF ENDLESS TAPE CARTRIDGES

Itsuki Ban, 829, Higashi-Oizumimachi, Nerima-ku, Tokyo-to, Japan

Filed Mar. 18, 1968, Ser. No. 713,656


Claims priority, application Japan, Mar. 18, 1967, Mar. 23,

1967, Apr. 14, 1967, 42/16625; 42/17679; 42/23425

Int. Cl. G11b 5/54, 15/28; B65h 19/06

U.S. Cl. 274—4

9 Claims



An automatic playing apparatus for use with a plurality of endless tape cartridges comprising a planar base radially carrying and rotatably moving the plurality of the cartridges, a mechanism arresting movement of the casing to position the indexed cartridge in the play position, a pivotally movable deck including a magnetic head, and a capstan engageable and disengageable with the tape, a pinch roller therethrough when the cartridge in the play position, and so provided that the deck is moved from the base by deck driving means which are actuated upon searching an end mark signal on the tape for which time movement of the casing is effected to bring the next indexed cartridge into the play position or to change over a sound track on the tape.

3,578,335

SOUND TRACK CHANGEOVER DEVICE FOR AUTOMATIC PLAYING APPARATUS HAVING A PLURALITY OF ENDLESS TAPE CARTRIDGES

Itsuki Ban, 829, Higashi-Oizumimachi, Nerima-ku, Tokyo-to, Japan

Filed Mar. 18, 1968, Ser. No. 713,657

Claims priority, application Japan, Mar. 18, 1967, Mar. 23,

1967, Apr. 11, 1967, Apr. 14, 1967, Apr. 14, 1967, Apr. 14,


1967, 42/16625; 42/17679; 42/23425; 42/22612; 42/23426;

42/23429

Int. Cl. B65h 19/00; G11b 15/66; G03b 21/04

U.S. Cl. 274—4

9 Claims



A sound track changeover device for an automatic playing apparatus having a plurality of endless tape cartridges


wherein a plurality of pushbutton rods are provided, corresponding to each of the cartridges and are adapted to index not only the cartridges in the play position but also the sound track when said pushbutton rod is depressed while movement of a housing is arrested at the same time the sound track is indexed when the depressed pushbutton rod is engaged with the stop member to depress an operating rod for a switch and the like which is provided to correspond to each sound track.

3,578,336

AUTOMATIC PLAYING APPARATUS UTILIZING PLURALITY OF ENDLESS TAPE CARTRIDGES
Itsuki Ban, 829, Higashi-Oizumimachi, Nerima-ku, Tokyo-to, Japan

Filed Apr. 12, 1968, Ser. No. 720,848
Claims priority, application Japan, Apr. 14, 1967, 42/23425; 42/23428
Int. Cl. G11b 5/54, 15/28; B65h 19/06
U.S. Cl. 274-4

5 Claims




An automatic playing apparatus utilizing a plurality of endless tape cartridges, comprising a movable housing within which a plurality of endless tape cartridges are arranged in a manner that each of them is inclined to a radius drawn from the center of rotation of the housing thereof, means for arresting movement of the housing to bring a preselected endless tape cartridge into the play position, a swingable deck including a magnetic head and a capstan adapted to abut against the endless tape and a pinch roller in the cartridge, respectively, when the cartridge is in the play position, whereby said deck is swung away from the selected cartridge when reproduction of the endless tape within the cartridge is completed, and a capstan into abutment with a pinch roller or out of abutment therewith is effected, movement of the housing is admitted when the pinch roller is away from the capstan to bring a next preselected cartridge into the play position and to change over a sound track when desired.

3,578,337

REVERSIBLE DRIVE FOR TRANSDUCER USED IN A RECORDING AND REPRODUCING APPARATUS
Walter F. Klein, Lexington, Ky., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Nov. 20, 1968, Ser. No. 777,327
Int. Cl. G11b 5/02

U.S. Cl. 274-4

8 Claims



A transducer is driven in reciprocating motion relative to a recording medium for scanning the medium by attaching a

band having apertures therein to the transducer. Rotating means has means to engage the apertures in the band to provide positive engagement between the rotating means and the band. The direction of rotation of the rotating means is reversed at each end of scanning by the transducer. The change in direction of rotation of the rotating means is accomplished through a pivotally mounted member that locks a ball retaining member against rotation.


3,578,338

TAPE CARTRIDGE REJECTION APPARATUS
Yoshihiro Ueno, Hujisawa, Japan, assignor to Victor Company of Japan, Limited, Moriya-cho Kanagawa-Ku, Yokohama, Japan

Filed Dec. 16, 1968, Ser. No. 784,163
Claims priority, application Japan, Dec. 19, 1967, 42/105912
Int. Cl. G11b 5/78

U.S. Cl. 274-4

7 Claims



A tape cartridge rejection apparatus having a plunger mainly operable by a discharge current of a condenser for rejecting and pushing out a tape cartridge, a normally-opened switch being closed when said tape cartridge is loaded in the tape player unit before rejection, resistor such as an incandescent lamp greatly variable in value corresponding to the flowing time of electric current, and a power source which charges electricity in said condenser through said resistance. The resistance serves to limit the electric current supplied to said plunger when said tape cartridge is not rejected although the plunger is energized and to prevent the burning of said plunger.

3,578,339


TOPE ARM ASSEMBLY IN A TOY SOUND REPRODUCING DEVICE

William F. Summerfield, Huntington Beach, Calif., assignor to Mattel, Inc., Hawthorne, Calif.

Filed Feb. 17, 1969, Ser. No. 805,942
Int. Cl. G11b 3/00, 3/62, 3/10

U.S. Cl. 274-9

12 Claims



A tone arm assembly, including a stylus which is supported in a rolling block, for use in a toy sound reproducing device, of the type in which a sequence of sounds, representing a saying or the like is reproduced during Play, when the stylus follows in a sound groove in a record, rotatable in a Play direction. The rolling block is shaped and the stylus supported therein, so that when the record is rotated in the Re-

wind direction, opposite the Play direction, the moving record causes the block to pivot so that a rounded part thereof, rather than the stylus, engages the record as the arm is pivoted toward a Start of Play position. When the record starts turning in the Play direction, it pivots the block so that when the stylus finally engages a groove, the block is locked in a Play direction to enable the stylus to follow the engaged groove.

3,578,340


RECORD PLAYERS

Henry James Fortune, Swindon, England, assignor to The Plessey Company Limited, Ilford, England

Filed Dec. 16, 1968, Ser. No. 783,883
Claims priority, application Great Britain, Dec. 22, 1967, 58387/67
Int. Cl. G11b 17/08

U.S. Cl. 274-15

10 Claims



A record player employs parallel tracking by having an arm extending across the playing surface during play with a pickup cartridge arranged to run along a track along the arm while its position is measured or determined according to the point in the changing cycle by a low mass swinging arm extending more or less at right angles to the track. The arm carrying the track is arranged to be swung to a position clear of the record during the actual record changing operation of the cycle.

3,578,341


SEAL ASSEMBLY FOR A HYDRAULICALLY OPERATED CYLINDER

Arthur H. Le Fevre, Washington Township, N.J., assignor to Singer-General Precision, Inc., Little Falls, N.J.

Filed May 21, 1968, Ser. No. 730,801
Int. Cl. F16j 15/00

U.S. Cl. 277-3

10 Claims



A seal assembly for a hydraulically operated cylinder comprising a pair of sealing members acting between the cylinder end cap and the operating shaft to seal the hydraulic operating fluid from the ambient fluid. A pressurized fluid is disposed between the sealing members and acts on the shaft to control the pressure differentials across each of the sealing members.

3,578,342


SHAFT SEAL

James Glenn Satterthwaite, 5001 Dogwood Trail, Portsmouth, Va., and James B. Macy, Jr., 107 River Drive, Morehead City, N.C. 28557

Filed Jan. 14, 1969, Ser. No. 791,082
Int. Cl. F16j 9/00, 15/46

U.S. Cl. 277-9

6 Claims



There is a shaft seal characterized by an inflatable seal and compressible packing seal means arranged in tandem about a shaft and including between the two sealing means, fluid inlet means for admission of lubricating fluid for a stern tube bearing. The inflatable seal is constructed and arranged to insure it does not contact the shaft excepting when its operation as a seal is desired. These devices are particularly useful as journal seals in marine installations for shafts extending through a vessel or hull.

3,578,343


ANNULAR SHOULDER ASSEMBLY FOR A ROTATING SEAL

Ernest J. Taschenberg, Baltimore, Md., assignor to Koppers Company, Inc.

Filed Apr. 24, 1969, Ser. No. 818,963
Int. Cl. F16j 15/00, 15/40

U.S. Cl. 277-16

7 Claims



This disclosure relates to an annular shoulder assembly for a rotating seal. The shoulder assembly has an annular reservoir connected to an annular cooling chamber. An annular orifice is provided between the reservoir and the cooling chamber to control the distribution of coolant supplied to the cooling chamber from the reservoir. The annular cooling chamber extends rearwardly from the front planar surface and the coolant fluid, by the centrifugal force exerted during rotation of the annular shoulder assembly, forms a uniform film on the annular walls of the chamber to cool the annular shoulder assembly.

3,578,344

CARTRIDGE TYPE SEAL HAVING IMPROVED ANTI-ROTATION MEANS


Kermit D. Yost, Skokie, Ill., assignor to Rex Chainbelt, Inc., West Milwaukee, Wis.

Filed Nov. 5, 1969, Ser. No. 874,131

Int. Cl. F16j 9/00, 15/40

U.S. Cl. 277-40

12 Claims



A cartridge-type seal having an annular stator of carbon or the like running in engagement with a rotor on a shaft in which the stator has an antirotation arm secured to its rear end surface and which extends to a position alongside the stator. The arm cooperates with antirotation lugs mounted inside the cylindrical wall of the seal housing to block rotation while permitting the stator to move endwise in the housing free of any possibility of localized chafing at the stator surfaces. In a preferred embodiment two of such antirotation arms are used arranged at diametrical points on a flat annular yoke which is keyed at spaced points to the rear end surface of the stator.

3,578,345

MECHANICAL SEAL INSERTS


John C. Copes, 2750 McConnell Drive, Baton Rouge, La.

Continuation-in-part of application Ser. No. 423,203, Jan. 4, 1965, now abandoned. This application Feb. 3, 1969, Ser. No. 804,044

Int. Cl. F16j 15/16

U.S. Cl. 277-81

16 Claims



Split critically tapered inserts adapted for relatively rotatable in radial face-to-face contact to form a sealing surface when one is carried in a stationary member as the hub part of a frame, and the other carried by a holder on the shaft. Special critically dimensioned grooves convey pressurized fluid to the inserts which act through the effective radial component of area thus provided, easily to eject the inserts. The inserts have contact rings of specially hardened, more expensive material bonded therein to be ground and lapped for final finish contact in rotation.

3,578,346

SEALED JOINT AND GASKET THEREFOR

Jerry G. Jelinek, Whittier, Calif., assignor to Parker-Hannifin Corporation, Cleveland, Ohio

Filed Jan. 29, 1969, Ser. No. 794,935

Int. Cl. F16j 15/08, 15/10

U.S. Cl. 277-180

21 Claims

A joint and a gasket therefor in which the gasket comprises a resilient member attached to an offset portion of a first

rigid plate. A second rigid plate is adjacent the first plate and surrounds the resilient member but is unattached to either so



that it may be reused with a new first plate and elastometric member if the latter becomes worn out or damaged.

3,578,347

INSTRUMENT PANHEAD SEAL


Chadwell O'Connor, 1596 Mountain St., Pasadena, Calif.

Filed July 17, 1969, Ser. No. 842,451

Int. Cl. F16j 15/32

U.S. Cl. 277-205

1 Claim



A rotary seal for instrument panheads in which the seal is a unitary annular body of Teflon formed with two seating surfaces in contact with the sides of a sealing region and one sealing surface in light resilient contact with a relatively rotatable surface against which the seal must be made. In one form, the annular seal body is U-shaped in cross section with a lip being formed on one leg of the U to define the sealing surface. In another form, the seal is shaped as a Belleville washer. In each case, pressure within the chamber being sealed acts to urge the sealing surfaces more tightly against the sides of the sealing recess.

3,578,348

FERTILIZER TRAILER


Richard F. Reinke, P.O. Box 272, Deshler, Nebr.

Filed Dec. 10, 1968, Ser. No. 782,624

Int. Cl. B60p 3/22

U.S. Cl. 280-5

8 Claims



A wheeled fertilizer trailer wherein the tank is mounted within a wheeled frame to present a low profile and lower the center of gravity of the trailer. The frame having a relatively high location relative to growing crops and having very small projections on the bottom thereof, the clearance for crops is higher than conventional fertilizer trailers wherein the tank is mounted on top of the wheeled trailer.

3,578,349

SAFETY SKI BINDING


James Mitchell Edmund, 6404 Ridge Drive, Washington, D.C.

Filed May 26, 1969, Ser. No. 827,558

Int. Cl. A63c 9/086

U.S. Cl. 280-11.35

22 Claims



A safety ski binding in which the boot is secured to the ski by means of a plate fastened to the boot sole intermediate its heel and toe.

3,578,350

SAFETY HEEL SKI BINDING

Willy Suhner, Aarauerstr. 38, Brugg, Switzerland


Filed June 26, 1969, Ser. No. 836,840

Claims priority, application Switzerland, Nov. 14, 1968, 16998/68

Int. Cl. A63c 9/00

U.S. Cl. 280-11.35T

21 Claims



A step-in safety heel ski binding wherein a heel-holding link is movable by the ski boot from a raised position to a lower position and is moved into engagement with parts fixed to the ski in a first intermediate position which is nearer to the lower position than a second intermediate position in which the link is released from such parts on forcible movement from lower position toward raised position. A spring is stressed during movement of the link from raised position to first intermediate position and biases the link from first intermediate position to lower position.

3,578,351

AUXILIARY SLIDE MEMBER FOR MOUNTING ON SLED RUNNER


Regis Aloysius McAtee, R.D. 5, Box 356, Latrobe, Pa.

Filed Apr. 9, 1969, Ser. No. 814,679

Int. Cl. B62b 17/02

U.S. Cl. 280-28

14 Claims



The invention relates to an auxiliary slide member for mounting on a sled runner, characterized in that the slide

member has substantially greater width than the sled runner and is flexible so as to conform to the contour of the sled runner, and has a channel formed on top for receiving the sled runner, whereby the auxiliary member can be telescoped over the sled runner from the back and then fixed thereto.

3,578,352

VEHICLE WITH FRAME ADAPTED TO BE RAISED AND LOWERED

Franz Heine, Essen, Germany, assignor to Fried. Krupp Gesellschaft mit beschränkter Haftung, Essen, Germany


Filed Feb. 14, 1969, Ser. No. 799,247

Claims priority, application Germany, Feb. 16, 1968, P 16 80 141.5

Int. Cl. B62d 21/18

U.S. Cl. 280-43.23

7 Claims



A vehicle with a plurality of axles or axle groups supported by angle levers in which said angle levers are adapted to be interconnected by coupling rod means which have associated therewith hydraulically operable cylinder piston means operable to act upon said angle lever means so as selectively to raise and lower the vehicle body relative to the wheels supported by the axles or axle groups.

3,578,353

HANDTRUCK APPARATUS


Robert J. Lockhart, 552-C, East Central Park Ave., Anaheim, Calif.

Filed May 19, 1969, Ser. No. 825,723

Int. Cl. B62b 3/02

U.S. Cl. 280-47.2

10 Claims



A handtruck apparatus comprising a vertical frame supported on a pair of support wheels and including a pair of support handles at its upper extremity. A brace is pivotally supported on its upper end from the frame and includes a third wheel carried from its bottom extremity. A spring is connected between the brace and the frame in an over-the-center-type arrangement to normally bias such brace to its retracted position adjacent the frame and, when the brace is pivoted to an intermediate position, to bias such brace to its extended supporting position. A transverse pivot rod is carried from the frame and includes a first lever arm connected with an upwardly projecting actuating handle disposed adjacent one of said support handles and a second lever arm

pivotaly connected with a strut which engages the lower extremity of the brace whereby raising of the actuating handle kicks the lower extremity of the strut rearwardly to pivot the brace rearwardly to said intermediate position to enable the spring to pivot it to its supporting position.

3,578,354


VEHICLE SUSPENSION

Lawrence A. Schott, 15940 Warwick, Detroit, Mich.
Continuation-in-part of application Ser. No. 718,639, Apr. 3, 1968, now abandoned. This application Nov. 12, 1969, Ser. No. 875,953

Int. Cl. B60g 3/00

U.S. Cl. 280-96.2

3 Claims



A vehicle suspension system wherein each wheel of the vehicle is supported on a spindle rotatably carried within a hub housing provided with a pair of radially extending pins having a common axis perpendicular to the axis of the spindle. A pair of frame supporting arms rigidly connected to the frame of the vehicle are slidably engaged by the pins for relative vertical and rotational movements respectively along and about the pin axis. A coil spring wound around the upper pin intermediate the hub housing and the upper frame supporting arm absorbs shock loads received by the wheel as it travels over irregularities in a road surface. A tie bar connected to the hub housing and adapted to be displaced in a horizontal plane by a suitable steering mechanism rotates the hub housing and the pins relative to the frame supporting arms to permit steering of the vehicle.

3,578,355


AIR SUSPENSION SYSTEM

Carl E. Oeder, 256 Shawhand Road, Morrow, Ohio
Filed Jan. 29, 1969, Ser. No. 795,118

Int. Cl. B60g 1/146

U.S. Cl. 280-124

6 Claims



An air suspension leaf spring assembly for drop center axles used on vehicles, such as trucks and the like. The leaf spring is secured to the axle at its center and suspended from the vehicle frame at an intermediate point by an air spring, with the ends of said leaf spring being free to move in a restricted vertical path.

3,578,356


DETACHABLE GOOSENECK

Maurice Moiriat, 8490 Clark St., Montreal, Quebec, Canada
Filed May 2, 1969, Ser. No. 821,397

Int. Cl. B62d 53/06

U.S. Cl. 280-425

5 Claims



A trailer wherein a depressed load bed is coupled at one end to a gooseneck which is mounted at the rear of a tractor. The depressed load bed comprises at least two spaced-apart and longitudinally disposed beams. A pair of hydraulic pistons are horizontally mounted underneath the load bed, either longitudinally or transversely with respect to the beams and each of the hydraulic piston are connected at each end thereof to the articulation of a toggle mechanism. The toggle mechanism is pivotally connected at one end thereof to one of the beams and at the other end thereof to a ground-engaging footplate. The hydraulic pistons are dimensioned to fit within an enclosure defined by the upper and lower surfaces of the beams and are movable from a retracted position within said enclosure to an extended position whereby the end of the trailer may be uncoupled from the gooseneck and lowered to any desired position.

3,578,357


FIFTH WHEEL LOCK ASSEMBLY

Clarence N. Bouman, Holland, and Fred Bakker, West Olive, Mich., assignors to Holland Hitch Company, Holland, Mich.
Filed Dec. 27, 1968, Ser. No. 787,482

Int. Cl. B62d 53/12

U.S. Cl. 280-434

2 Claims



A kingpin lock assembly for a vehicular-hauling hitch, especially the fifth-wheel type, using overlapping retention jaws giving full peripheral pin engagement, the jaws sliding laterally together in retention tracks generally transverse to the usual direction of the hauling force.

3,578,358

FRAME HITCH AND STEP BUMPER

Donald F. Reynolds, 4415 E. Textile Road, Ypsilanti, Mich.
Filed Aug. 19, 1969, Ser. No. 851,212


Int. Cl. B60d 1/14

U.S. Cl. 280-500

6 Claims

An accessory for mounting on the frame of a motor vehicle, to provide a frame hitch assembly adapted to be used with the original equipment bumper of the vehicle or which is adapted to support an accessory step bumper. The frame

hitch assembly has mounting end plates and reinforcing upon the stud within a sleeve press-fitted on the boss, the torque bars adapted for mounting the hitch assembly on the sleeve and liner pipe being crimped to engage between the



frame without altering the physical characteristics of the frame.

3,578,359


RIGID REFLECTIVE HEAT INSULATION

James E. Smith, and Carl W. Schulz, Lancaster, Ohio, assignors to Diamond Power Specialty Corporation
Filed Sept. 4, 1969, Ser. No. 855,271

Int. Cl. F16l 59/14

U.S. Cl. 285-47

4 Claims



Sectional prefabricated thermal insulating elements for projecting portions of large structures having inaccurately positioned components, such as the nozzles of reactor vessels, are formed in semicylindrical parts of different diameters held together against longitudinal separation by overlapping sheet metal parts which permit them to move transversely of each other and of the longitudinal axis. The parts are buckled together and separable both longitudinally and transversely of the axis.

3,578,360

FITTING FOR A LINER PIPE FORMED OF POLYETHYLENE

Sol S. Eliot, Chicago, Ill., assignor to Perfex Plastics, Inc., Chicago, Ill.


Filed July 16, 1969, Ser. No. 842,248

Int. Cl. F16l 9/14, 33/20

U.S. Cl. 285-55

1 Claim

A fitting for a liner pipe formed of plastic material such as polyethylene, the fitting having an enlarged shoulder, a boss, and a stud with circumferentially extending spaced-apart steps or ribs insertable in the end of the liner pipe. The shoulder is circumferentially beveled at one edge. A pliable compression ring is forced and compressed against the adjacent walls of a pipe within which the liner pipe is arranged and the fitting, to provide an effective seal and connection between the fitting and the pipe. The liner pipe is inserted



steps to provide connection between the liner pipe and the stud.

3,578,361

ROTARY COUPLING AND SEAL COMBINATION


John E. Corrigan, Evanston, Ill., assignor to The Roy M. Moffitt Company

Filed May 12, 1969, Ser. No. 823,914

Int. Cl. F16l 17/00

U.S. Cl. 285-98

8 Claims



A rotary coupling having a seal member between members movable with respect to each other said seal member being composed of a nonporous, slippery, compressibly deformable and abrasive-resistant material and having a flange element extending radially inwardly into deflective engagement with a sealing face of the member rotating with respect to said seal member to define a fluidtight seal between the members of the coupling.

3,578,362


PIPE ADAPTER

Brian R. Cauthery, R.R. #1, Caledon, Ontario, Canada
Filed Feb. 27, 1969, Ser. No. 802,801

Int. Cl. F16l 17/02

U.S. Cl. 285-110

4 Claims



An adapter for sealing a plastic pipe to a cast iron bell fitting is provided with an internal dynamic seal to receive the plastic pipe in entered peripheral sealing relation within the adapter, and an axial end seal, with a compression shoulder to accept axial closing forces providing precise positioning of the end seal against a tapered inner surface of the bell fitting.

3,578,363


LOCKING KEY FOR COUPLING

Donald E. De Rocker, Ramsey, and Andrew J. Vaccaro, Little Falls, N.J., assignors to Sier-Bath Gear Co., Inc., Bergen, N.J.

Filed Apr. 28, 1969, Ser. No. 819,917
Int. Cl. F16d 1/06

U.S. Cl. 287—52.05

9 Claims



A rotatable coupling includes a sleeve engaging a shaft having an end provided with opposite parallel flats, which end is received in the bore of the sleeve. The sleeve has a recess in its inner face with a flat base at a transverse angle to the confronting shaft flat and a wedge-shaped key is located in the recess with opposite converging faces engaging the shaft flat and recess base. Screws accessible externally of the sleeve engage tapped traverse bores communicating with the recess and bear on opposite ends of the key to permit its transverse adjustment. The opposite shaft flat is engaged by a confronting flat on the sleeve. A compression spring urges the key toward the deep side of the recess.

3,578,364


CONNECTING ARRANGEMENT

Hermann Ehrenberg, Lagen, Hessen, Germany, assignor to Fouquet-Werk Frauz & Planck, Rottenburg, Neckar, Germany

Filed Mar. 27, 1969, Ser. No. 811,145
Claims priority, application Germany, Dec. 30, 1968,
P 18 17 398.3
Int. Cl. F16d 1/06

U.S. Cl. 287—52

16 Claims



A substantially cylindrical inner member is surrounded with clearance by an annular outer member. Connecting means is located in this clearance in form of one or several axially consecutive annular members which in axial section are of substantially Z-shaped or substantially Y-shaped configuration and which, when subjected to axial stress, are spread radially into engagement with the opposed surfaces on the inner and outer member, thereby connecting the members against movement relative to one another.

3,578,365

BALL AND SOCKET JOINT

Rudolf Gottschald, deceased late of Osterath by Erika Gottschald, sole heir, Osterath, Germany, assignors to A. Ehrenreich & Cie, Dusseldorf-Oberkassel, Germany


Filed Sept. 11, 1968, Ser. No. 759,827
Claims priority, application Germany, Sept. 14, 1967,
P 16 25 532.6
Int. Cl. F16c 11/06

U.S. Cl. 287—87

3 Claims

A ball and socket joint, particularly for the steering and tie

rods of motor vehicles, comprising a housing having a cover



with a tear-off strip for facilitating removal of said cover.

3,578,366


BALL JOINT SELF-SEALING BEARING

Edward A. Snidar, Ann Arbor, Mich., assignor to O & S Bearing & Mfg. Co., Whitmore Lake, Mich.

Filed Nov. 28, 1969, Ser. No. 880,646
Int. Cl. F16c 11/06

U.S. Cl. 287—90

8 Claims



A long-life, self-lubricating, self-sealing bearing which utilizes a plastic insert assembly for carrying the bearing load backed up by a lubricant-impregnated material to serve as a resilient compression force in the bearing assembly and as a source of lubricant during the life of the bearing, the plastic assembly being formed of interlocking parts which provide a substantial body of load-carrying material at the equatorial surface of the joint and at the same time provides a resilient lip seal at each end of the joint to exclude contaminant material.

3,578,367

FASTENER INCLUDING EXPANDER MEANS AND JOINT INCLUDING THE SAME

Leonard A. Harvill, Santa Ana, and William E. Duncan, Garden Grove, Calif., assignors to Hi-Shear Corporation, Torrance, Calif.

Continuation of application Ser. No. 713,658, Mar. 18, 1968, now abandoned. This application Sept. 3, 1969, Ser. No. 857,293

Int. Cl. F16b 5/02


U.S. Cl. 287—189.36

11 Claims

This invention relates to a fastener pin for making an interference fit with the cylindrical wall of a hole in a metal workpiece, and to a joint produced by this fastener pin together with the metal workpiece. During the insertion of the fastener pin into the hole, a temporary and localized expansion of the wall to a diameter greater than that of the shank with which the interference fit will be formed is caused. This temporary and localized expansion is to such an extent that the metal immediately surrounding the hole where the localized expansion occurs is compressed beyond its compressive yield point, after which at least a portion of the axial extent of the wall of the hole is permitted to return toward its original diameter, thereby to embrace in an interference fit at

least a portion of the pin. The joint produced by this technique enjoys the benefits of having worked the material surrounding the pin in its plastic range, after which it is permitted to return to make the interference fit. This enables the

which is driven home by gear means operated by a cam engaged by the active door. Thermal-responsive means may



wall of the hole to be burnished, to be made more truly cylindrical, and to reduce the compressive hoop force on the fastener pin with the correlative effects of reducing stress corrosion in the joint and of reducing galling and damage to the plating on the shank of the pin.

3,578,368


SAFETY COVER LOCK FOR THE CASE OF AN ELECTRICALLY OPERATED DEVICE

Guy-Louis Dupuis, Ilot C. Caudebec En Caux, France, assignor to Burroughs Corporation, Detroit, Mich.

Filed Jan. 6, 1969, Ser. No. 789,161
Int. Cl. E05c 3/26

U.S. Cl. 292—45

11 Claims



The base and cover portions of a container intended for housing an electrically operated device are provided with latching means effective for securing the cover to the base when the device is in an operating state, and for conveniently removing the cover from the base for maintenance and repair purposes. The latching means cooperates with the electrical supply cord of the housed device in such manner as to require its disconnection therefrom, at its point of entry into the case, before the cover can be removed from the base, and to prevent its reconnection therewith until the latched relationship between the cover and the base is reestablished.

3,578,369

SELF-OPERATING EXTENSION FLUSH BOLT

Leo Coopersmith, Ivoryton, Conn., assignor to The H.B. Ives Company, New Haven, Conn.

Filed Apr. 2, 1969, Ser. No. 812,671
Int. Cl. E05c 5/00

U.S. Cl. 292—58

15 Claims

There is disclosed a self-operating extension flush bolt mechanism for latching the inactive one of a pair of swinging doors, which is operated to latch the door, once the latter is closed, by swinging movement of the other or active door to the closed position. The latch mechanism includes a bolt

be provided to inhibit retraction of the bolt when the latter is subjected to high temperatures, as during a fire, such as those likely to cause buckling of the doors.

3,578,370


MAGNETIC DOOR STOP

James J. Greytok, 1123 Ashbridge Road, Rosemont, Pa.

Filed Apr. 11, 1969, Ser. No. 815,412
Int. Cl. E05c 19/16; E05d 13/00

U.S. Cl. 292—251.5

11 Claims



A door stop is provided with a magnetically susceptible element that may be aligned in cooperative relationship with a magnetically susceptible element of a door to provide magnetic means to secure the door in the open position. The magnetically susceptible element of the door stop may be moved, when desired, into a nonoperating position. In one optional form of this invention, provision is made for adjustably aligning the operating face of the magnetically susceptible element of the door stop to make planar contact with the door while in its open position.

3,578,371

DISK TUMBLER CYLINDER AND KEY FOR A LOCK


Ernst Keller, 6, Querstrasse, 8805 Richterswil, Switzerland

Filed Feb. 10, 1969, Ser. No. 797,733
Claims priority, application Switzerland, Feb. 9, 1969,
1929/68

Int. Cl. E05b 15/14, 29/12

U.S. Cl. 292—364

7 Claims



The lock plug has several slots, each holding three disc tumblers spring biased into locking positions, two of which

tumblers are moved up and the remaining one down by the key and its camming shoulders to release the rotatable plug.


3,578,372

SUCTION CUP STRUCTURE

Jacob Pieter Schuler, Soest, Netherlands, assignor to Handelsmaatschappij Othene N.V., Soest, Netherlands
Filed Apr. 28, 1969, Ser. No. 819,667
Claims priority, application Netherlands, Apr. 29, 1968, Nov. 18, 1968, 6806080; 6816396
Int. Cl. B66c 1/02

U.S. Cl. 294-64

5 Claims




A suction cup structure for use in a lifting device to lift structural building elements, which is to be connected to a vacuum source and comprises a rubber sealing ring mounted in a circular groove around the opening of the suction cup, the configuration of which cup conforms to the relevant surface portion of the object to be lifted, said ring consisting of a plurality of layers of foam rubber succeeding each other from the inside to the outside about the opening of the cup, said layers being separated from each other by impenetrable layers of glue interconnecting the rubber layers.

3,578,373

POWER OR MANUALLY RELEASED CARGO LATCH

John R. Metz, Ridgefield, Conn., assignor to Norco, Inc., Ridgefield, Conn.
Filed Feb. 19, 1969, Ser. No. 800,475
Int. Cl. B64d 1/00; B66c 1/00
U.S. Cl. 294-83

13 Claims



A cargo latch releasable either electrically or at remote or proximal points manually, comprising a slide bolt movable across the mouth of the latch body. Control of the bolt movement is effected by a series of sears and levers arranged in a unique, compact and advantageous manner to give positive action, great strength and at the same time easy release.

3,578,374

CONTAINER COUPLER ARRANGEMENT


John J. Glassmeyer, Covington, Ky., assignor to Pullman Incorporated, Chicago, Ill.
Filed May 22, 1969, Ser. No. 826,852
Int. Cl. B66c 1/10

U.S. Cl. 294-67

31 Claims

For tandem coupling together of cargo containers of the highway trailer-type attendant to hoisting of the containers

between land, sea or air transport means, an upper between-the-containers compression spacer block and a lower tension coupler between the containers wherein the lower coupler comprises a housing carrying a pair of longitudinally spaced rotatable container tandem locking clamps receivable in the corner fittings of tandem containers in locked and unlocked positions, key means slidable inwardly and outwardly of the housing and contained thereby for each clamp for rotating



each clamp about an axis and moving each clamp independently of the other clamp along such axis between locked and unlocked positions and including complementary tooth means on the clamp and on the key means for clamp rotation and the key means having key wedge portions for moving each clamp axially and for limiting rotation of each locked clamp, and, key holder means for retaining the key means in the locked position in the housing.


3,578,375

CUSHIONING LINER FOR VEHICLES OR THE LIKE

Donald W. Finefrock, Massillon, Ohio, assignor to The Johnson Rubber Company, Middlefield, Ohio
Filed Feb. 24, 1969, Ser. No. 801,561
Int. Cl. B62d 33/00

U.S. Cl. 296-39

14 Claims



A cushioning liner is disclosed which combines a plurality of elongated elastomeric sheet members and a plurality of elongated elastomeric rib members mounted between adjacent edges of sheet members. The ribs are provided with T-shaped longitudinal slots along which metal plates extend to distribute clamping loads. Bolt fasteners are mounted in the plate at spaced intervals therealong to bolt the ribs to the supporting surface and in turn clamp the sheets in position. The ribs and sheets are provided with mating interlocking surface arranged so that they provide mutual lateral support.


3,578,376

SEAT CONSTRUCTION OF A VEHICLE

Tatsuo Hasegawa, Okazaki-shi; Kohichi Yoshie, and Yasuhiro Kamijima, Toyota-shi, Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota-shi, Japan
Filed Aug. 7, 1969, Ser. No. 848,302
Claims priority, application Japan, Sept. 20, 1968, 43/67598
Int. Cl. B60r 21/10; B60n 1/02

U.S. Cl. 296-65

6 Claims



A seat assembly for a vehicle is composed of a floor, a seat, a movable support member supporting the seat to permit the seat to move relative to the floor, a pin or stationary member fixing the seat on the floor to prevent the seat from moving relative to the floor which includes a weak link or releasable section, and an energy absorbing member disposed between the floor and the seat. When an impact in the forward direction is applied to the seat by a rear-end-collision with a following car, if the impact force exceeds a predetermined permissible value, the stationary member is released to permit the seat to move rearwards relative to the floor by the inertia of the seat and passengers, and, simultaneously the energy absorbing member is deformed so as to reduce the impact imposed on the passengers and prevent them from being injured.

3,578,377

TILT OVER ROLL PROTECTOR FRAME WITH POWER TILTING MEANS


John H. Babbitt, Jr.; Max E. Butterfield, Peoria; Grant L. Nelson, Bartonville; Hugh V. Piper, Peoria, and Sheldon L. Stark, Bloomington, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed Jan. 13, 1969, Ser. No. 790,797

Int. Cl. B62d 25/06

U.S. Cl. 296-102

17 Claims



A roll protection frame, for mounting on a tractor or similar machine, which is fabricated to provide a maximum cross-sectional area of material in critical locations for adequate strength to protect the vehicle operator if the vehicle should roll over, and which has a reduced cross section in locations requiring less strength to eliminate excessive weight. The front of the frame is wider than the rear portion thereof so as to provide a more even distribution of impact forces when the vehicle is overturned. The frame is detachable and pivotally mounted on the machine and a hydraulic cylinder arrangement may be removably attached thereto for pivoting the frame, together with the operator's seat and console, to provide access to the machine components beneath the frame. The provision of a double holding valve within the

removable tilting cylinder will allow the protection frame to be tilted and maintained in any desired position, without allowing it to fall over when it passes the center of gravity.


3,578,378

TELESCOPIC AND PIVOTAL COVER ASSEMBLY FOR OPEN BED VEHICLES

Edwin G. Anderson, 804 Northey Drive, Sacramento, Calif.
Continuation-in-part of application Ser. No. 618,099, Feb. 23, 1967, now abandoned. Filed Apr. 11, 1969, Ser. No. 815,309
Int. Cl. B60j 7/10

U.S. Cl. 296-137

40 Claims



A telescopic cover assembly for open bed vehicles comprising a plurality of cover segments at least one of which is longitudinally movable. The movable segment carries wheel assemblies engageable with a guide rail along which the segment is movable. The guide rail is constructed to elevate the movable segment during movement towards an extended position. Cutouts are provided in the guide rail in which the wheel assemblies are engageable for maintaining the movable segment in predetermined locations. Improved mounting means for the guide rail, and improved gate closure structure also are included in the cover assembly. In a preferred embodiment, the cover is pivotal upwardly to permit unrestricted access to the vehicle bed.

3,578,379


ADJUSTABLE CHAIR

Norris O. Taylor, Swarthmore, Pa.; Wilmer P. Uhler, Tottenville, Staten Island; John M. Gardella, Staten Island, N.Y., and Jim C. Cahlik, Parma, Ohio, assignors to Pennwalt Corporation

Division of Ser. No. 475,181, July 27, 1965, Pat. No. 3,414,324. Filed Dec. 28, 1967, Ser. No. 722,504
Int. Cl. A47c 1/037, 1/04

U.S. Cl. 297-7.1

18 Claims



A dental chair is equipped with a cushion roll between the backrest and the seat rest to provide a continuous supporting surface extending from the backrest to as far as the bottom of the leg rest. Single or dual controls are provided on the backrest, preferably along the opposite side edges of the backrest. Where dual controls are employed, a signal from a dental assistant's control will not operate the chair except in


the absence of a signal from the dentist's control, which preferably overrides the assistant's control. A shroud connected to the seat rest is biased into engagement with the backrest adjacent the pivotal connection of the backrest and seat rest. Continuous return of the backrest to upright position may be effected by a holding device incorporated in the control unit, with provision for deactivation when a control switch for reclining the backrest is subsequently actuated. During movement of the backrest to various angular inclinations the arm rest is maintained in substantially parallel relation to the seat rest.

3,578,380

SANITARY COVER FOR SHOPPING CART SEAT
Rosalind R. Jacobus, 1730 Gumwood Drive, Concord, Calif.
Filed Mar. 7, 1969, Ser. No. 805,194
Int. Cl. A47c 4/30

U.S. Cl. 297-229

6 Claims




A thin sheet of pliable material configured to removably fit the seat of a conventional shopping cart in covering relation to all cart surfaces forming a portion of and adjacent to such seat. The sheet is formed of a double back portion slidable onto the back of a shopping cart seat, a central portion fitting the sides, bottom and front of the seat with openings in the front to match the cart seat openings and an edge portion disposable over the top cart bars and handle with elastic or tie means for securing the cover in position.

3,578,381

CONTROLLED MOTION AMUSEMENT DEVICE
James V. Young, Clayton, Mo., assignor to Monsanto Company, St. Louis, Mo.
Filed Feb. 20, 1969, Ser. No. 800,920
Int. Cl. A47d 1/00

U.S. Cl. 297-300

10 Claims




A pneumatic amusement device consisting of a resilient bellows and offering controlled but varied motion responses to the rider.

3,578,382
AUTOMATIC SAFETY SEAT CLAMP
Robert Servadio, 3721 Parkview Ave., Pittsburgh, Pa. 15213
Filed Mar. 5, 1969, Ser. No. 804,423
Int. Cl. B60r 21/10; A47c 31/00

U.S. Cl. 297-390

11 Claims




An automatic safety seat clamp adapted to be moved in front of an occupant of a vehicle seat, to restrain him from being thrown forwardly during an accident. The safety clamp is automatically raised from a low retracted position in response to the occupant's body pressure which actuates a switch on the seat backing. The clamp encircles the occupant in response to foot pedal action. The clamp is retracted by motor power in response to another foot pedal action.

3,578,383

PILLOW UNIT FOR A SEAT
Thad J. Earl, 1132 E. Second St., Defiance, Ohio 43512
Filed Mar. 3, 1969, Ser. No. 803,564
Int. Cl. A47c 7/36, 7/42

U.S. Cl. 297-391

7 Claims



A pillow unit for the head of a person in a chair or in a vehicle seat is attached to the back of the seat and supports the head when the person is in a relaxed, sitting position. The pillow unit includes a pillow extending outwardly from the seat back a sufficient distance and at a proper angle to adequately support the head, and means for affixing the pillow to the seat at the level of the head and to one side of the center of the seat back. In a preferred form, the pillow is affixed to a base sheet which, in turn, is attached to the seat back by elastic straps or by means of Velcro, by way of example. Also in a preferred form, the pillow includes a cover and a removable pillow insert which can be removed for the purpose of cleaning the cover and the base sheet. If desired, two of the pillows can be employed with the base sheet spaced apart a distance sufficient to receive the person's head to support either or both sides thereof.


3,578,384
ADJUSTABLE HEADREST FOR VEHICLE SEATS
Ludwig Leichtl, Emmaus, Pa., assignor to McCord Corporation, Detroit, Mich.

Filed Nov. 25, 1968, Ser. No. 778,464

Int. Cl. A47c 7/36, 7/42

U.S. Cl. 297-410

16 Claims



A headrest for a vehicle seat wherein the cushioned headrest pad has one or more vertically depending support arms thereon which are vertically slideable in support brackets mounted within the seat cushion. Each support bracket is formed with a guideway for receiving the associated support arm. Each support bracket has a pair of inclined tabs thereon, an upper tab inclining upwardly and away from the guideway and a lower tab inclining downwardly and away from the guideway to form with an axially extending surface portion of the support arm a pair of acute angle cavities. Cylindrical members are arranged in the


cavities to form friction wedges and springs are connected with the cylindrical members to urge them into tangential contact with the tabs and with the support arm so that vertical movement of the support arm is yieldably resisted by the frictional wedge action of spring-biased cylindrical members.

3,578,385

DEMOUNTABLE SOFA OR CHAIR CONSTRUCTION
Karen R. Stiglitz, 4804 Chevy Chase Blvd., Chevy Chase, Md.
Filed Mar. 4, 1970, Ser. No. 16,350
Int. Cl. A47c 17/40, 4/02

U.S. Cl. 297-440

11 Claims



The outer rigid frame is demountably fastened together by pins inserted in transverse openings formed in the outer exposed ends of tongues which are rigid with the ends of the front and back walls of the frame and which protrude through openings formed in the sidewalls of the outer frame. The cushion support is formed of strong fabric detachably connected to three parallel, elongated dowels removably mounted on the sidewalls of the frame.

CHEMICAL

3,578,386

DYEING HUMAN HAIR WITH BENZOTHAZOLE AZO COMPOUNDS

Gregoire Kalopissis, Paris, and Andree Bugaut, Boulogne-sur-Seine, France, assignors to L'Oreal, Paris, France

No Drawing. Filed Feb. 16, 1968, Ser. No. 705,925




Claims priority, application Luxembourg, Feb. 22, 1967, 53,050

Int. Cl. A61k 7/12

U.S. Cl. 8—10

3 Claims

This invention relates to methods of dyeing and dyes for keratinic fibers, especially human hair with benzothiazole compounds corresponding to one of the following formulae:



In each of these formulae R, R₁ and R₂ may be lower alkyl radicals, but in some of the formulae they may be H or acyl radicals instead, as set forth in detail in the specification. Preferably R₁ and R₂ are combined with an adjacent N to form a heterocyclic radical falling within the group consisting of morpholino, piperidino and pyrrolidino radicals.

3,578,387

DYEING HAIR WHILE SIMULTANEOUSLY LIGHTENING ITS COLOR

Charles Zviak, Franconville, and Giuliana Ghilardi, Paris, France, assignors to L'Oreal, Paris, France

No Drawing. Filed Feb. 13, 1967, Ser. No. 615,330

Claims priority, application Luxembourg, Feb. 15, 1966, 50,461; Aug. 22, 1966, 51,804

Int. Cl. A61k 7/12

U.S. Cl. 8—10.1

6 Claims

This invention relates to a process for simultaneously dyeing hair and lightening its color and to specific compositions for use in carrying out that process. These compositions contain in combination a water-soluble dye which is either an anthraquinone dye or a nitrated derivative of benzene, together with an azo dye or an anthraquinone dye which are insoluble in water, and hydrogen peroxide.

3,578,388

AQUEOUS DYESTUFF COMPOSITIONS CONTAINING 2,2'-(AZO-DIPHENYLENE)-BISBENZOTHAZOLES AND ONE OR MORE DISPERSING AGENTS

Chi K. Dien, Buffalo, N.Y., assignor to Allied Chemical Corporation, New York, N.Y.

No Drawing. Original application Nov. 16, 1966, Ser. No. 594,662, now Patent No. 3,510,241, dated May 5, 1970. Divided and this application May 14, 1969, Ser. No. 842,054

Int. Cl. C09b 33/12; D06p 1/18, 3/36

U.S. Cl. 8—41

2 Claims

Dyestuff compositions comprising aqueous dispersions of 2,2'-(azo-diarylene)-bis-benzo thiazoles intimately mixed with one or more dispersing agents useful in coloring in yellow to orange shades aromatic polyester materials and especially those of the polyalkylene terephthalate type possessing excellent sublimation, washing and light fastness properties.

3,578,389

FIBER REACTIVE PHOTOCHROMIC DYES

John Kazan, Jr., Somerville, and Walter Henry Foster, Jr., Freehold, N.J., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Original application Jan. 26, 1967, Ser. No. 611,840, now Patent No. 3,505,306, dated Apr. 7, 1970. Divided and this application June 3, 1969, Ser. No. 830,150

Int. Cl. D06p 1/10

U.S. Cl. 8—163

5 Claims

Process of dyeing a textile material containing reactive hydrogen atoms, e.g., nylon, which comprises applying as dispersed dyes, fiber-reactive dye compounds comprising photochromic mercury dithizonates containing fiber-reactive groups to said textile material from an aqueous dispersion and subsequently fixing the dye with an alkali after-treatment. The dyed materials exhibit photochromic properties.

3,578,390

METHOD OF REMOVING SULFUR DIOXIDE FROM GASES CONTAINING THE SAME

Martin Kruehl, Essen-Bergerhausen, Harald Juentgen, Essen-Heisingen, and Heinrich Drwatwa, Rheinhausen, Germany, assignors to Bergwerksverband GmbH, Essen, Germany

No Drawing. Continuation of application Ser. No. 739,902, June 13, 1968. This application May 27, 1969, Ser. No. 828,815

Claims priority, application Germany, Sept. 16, 1965, B 83,755

Int. Cl. B01d 47/00

U.S. Cl. 23—2

14 Claims

Sulfur dioxide is removed from gases containing the same, particularly steam and oxygen-containing waste gas, by intimately contacting such gas and an adsorbent material consisting essentially of a porous carbonaceous material which is impregnated with an ammonium or alkali metal iodide or iodate. The contacting is carried out at an elevated temperature which may be up to 200° C. and preferably is at least as high as 100° C.

MAY 11, 1971

CHEMICAL

349

3,578,391

YTTRIUM PURIFICATION

Vincent Chiola, Joseph J. Cleveland, George J. Kamin, and Tai K. Kim, Towanda, Pa., assignors to Sylvania Electric Products Inc.

Filed Sept. 16, 1969, Ser. No. 858,341

Int. Cl. C22b 59/00; C01f 17/00

U.S. Cl. 23—22

8 Claims

A continuous process useful for the purification of yttrium from an aqueous solution containing light rare earths, heavy rare earths and yttrium comprising:

- (a) an extraction step having a plurality of stages wherein an organic extractant solution consisting essentially of specific alkyl phosphoric acids in specific amounts, tributyl phosphates in specific amounts and a hydrocarbon solvent,
- (b) a scrubbing step having a plurality of stages wherein the organic phase from the extraction step is scrubbed with an acidic aqueous scrub solution and the aqueous solution is thereafter recycled to the extractant step,
- (c) a stripping step having a plurality of stages wherein the organic phase from the scrubbing step is stripped with an aqueous nitric acid solution to remove yttrium and the heavy rare earths from the organic phase,
- (d) a washing step having a plurality of stages wherein the stripped organic phase is contacted with deionized water, and
- (e) recycling the organic phase to the extraction step and processing the yttrium bearing aqueous solution to separate yttrium from the heavy rare earths.

3,578,392

MOLYBDENUM PURIFICATION PROCESS

Joseph E. Ritsko, Towanda, Pa., assignor to Sylvania Electric Products Inc.

No Drawing. Filed June 30, 1969, Ser. No. 837,940

Int. Cl. C22b 59/00; C01g 39/00

U.S. Cl. 23—22

4 Claims

The process, wherein an aqueous molybdenyl sulfate feed solution is formed from sulfuric acid and an impure molybdenum source and is contacted with an organic extractant phase to selectively extract molybdenum into the organic phase and thereafter the molybdenum values are recovered by using an aqueous ammonium stripping agent to contact the molybdenum-containing organic solution, is improved by adding the steps of (1) forming a molybdenyl sulfate solution containing a molybdenum concentration of from about 120 to about 180 grams/liter MoO₃ basis; (2) filtering the molybdenyl sulfate solution to remove undissolved impurities; (3) maintaining the temperature of the molybdenyl sulfate feed solution at from about 70° C. to about 90° C. for about 3 hours, thereby forming a high purity solid molybdenum trioxide and (4) separating the solid molybdenum trioxide from the aqueous feed solution that now has a reduced molybdenum concentration but is suitable as the aqueous feed solution to the organic extraction step.

3,578,393

PREPARATION OF CALCIUM HYPOCHLORITE FROM HYPOCHLOROUS ACID SOLUTIONS

John A. Wojtowicz, Cheshire, Conn., Milton Lapkin, Barrington, R.I., and Mohindar S. Puar, East Brunswick, N.J., assignors to Olin Corporation

No Drawing. Continuation-in-part of application Ser. No. 792,761, Jan. 21, 1969. This application Aug. 25, 1969, Ser. No. 852,895

Int. Cl. C01b 11/04, 11/06

U.S. Cl. 23—86

6 Claims

Solutions of hypochlorous acid (HOCl), free from chloride, which are prepared by extraction of aqueous

chlorination mixtures containing HOCl and chloride using an extraction solvent selected from the group consisting of lower alkyl ketones, lower alkyl cyanides and lower alkyl esters of lower alkanic acids, are reacted with lime to produce a slurry of calcium hypochlorite in the solvent. The solid is separated from the solvent to obtain the calcium hypochlorite product in excellent yields of high quality material.

3,578,394

PREPARATION OF AQUEOUS MANGANOUS CHLORIDE SOLUTIONS


Jay W. Palmer, Crystal Lake, Ill., assignor to Morton International, Inc., Chicago, Ill.

Filed Dec. 5, 1969, Ser. No. 882,558

Int. Cl. C01g 45/06

U.S. Cl. 23—87

15 Claims



A process for preparing aqueous solutions of manganous chloride essentially free from heavy metal contaminants by the reaction of manganese ore with an aqueous solution of ferrous chloride followed by removal of iron and heavy metals by treatment with sulfide ion. The manganous chloride solutions so prepared are suitable for further chemical processing or may be used to prepare pure manganese metal by electrolysis or other methods. Iron hydroxide may be recovered separately as a by-product of this process for use in pigments or as a raw material charge for the production of steel.

3,578,395

RECOVERY OF METALS

Harris E. Klusdahl, San Rafael, and James R. Hopkins, Sonoma, Calif., assignors to Chevron Research Company, San Francisco, Calif.

No Drawing. Filed Dec. 26, 1967, Ser. No. 693,193

Int. Cl. C01g 49/00

U.S. Cl. 23—20

8 Claims

A catalyst containing rhenium in the oxidized state supported on a porous solid carrier is treated with an excess of an ionic solution at a pH from 0—12 to recover rhenium from the catalyst without dissolving the carrier.

3,578,396

FLUIDIZED BED TREATMENT OF SPENT PULP DIGESTION LIQUOR

Robert J. Priestley, Westport, Conn., assignor to Dorr-Oliver Incorporated, Stamford, Conn.

Filed Aug. 13, 1968, Ser. No. 752,334


Int. Cl. D21c 11/12

U.S. Cl. 23—48

7 Claims

The reclaiming of chemicals from spent wood pulp digestion liquors by reacting the liquor in a thermal oxidizing, fluidized bed, then feeding the product to a fluidized cooling bed, SO₂ from a sulfur burner being fed di-

rectly into the cooling bed and thence to the oxidizing bed to form additional sulphate material, without formation



of objectionable SO_3 and scale formation which tends to result from introducing hot SO_2 into the hot bed.

3,578,397

PREPARATION OF ANHYDROUS CUPROUS CHLORIDE OR BROMIDE

Harold E. Doorenbos, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.
No Drawing. Filed Nov. 26, 1969, Ser. No. 880,423

Int. Cl. C01g 3/04

U.S. Cl. 23—97

2 Claims

Essentially anhydrous cuprous chloride or bromide is prepared by reacting cupric chloride or bromide with an alkyl hydrogen phosphonate.

3,578,398

SYNTHETIC CRYSTALLINE ZEOLITE AND PREPARATION THEREOF

Edwin Earl Jenkins, Elmer, N.J., assignor to Mobil Oil Corporation
No Drawing. Filed Apr. 1, 1968, Ser. No. 717,978

Int. Cl. C01b 33/28

U.S. Cl. 23—113

19 Claims

As a new zeolite, a crystalline aluminosilicate having a definite repetitive crystalline structure similar to offretite and containing tetramethylammonium ions. It is prepared from a mixture of silica, alumina, water, sodium oxide, potassium oxide, and tetramethylammonium oxide. Hydrocarbon conversion utilizing a catalyst comprising the new zeolite.

3,578,399

PRODUCTION OF CRYSTALLINE POTASSIUM SULFATE

Albert F. Boeglin, Carlsbad, N. Mex., assignor to International Minerals & Chemicals Corporation
No Drawing. Filed Oct. 23, 1968, Ser. No. 770,069

Int. Cl. C01d 5/10

U.S. Cl. 23—121

7 Claims

The metathetical reaction of langbeinite with potassium chloride to produce crystalline potassium sulfate proceeds slowly and with considerable foaming when a small amount of surface active agent has been added for the purpose of increasing the average size of the potassium sulfate crystals. The reaction can be made to proceed to completion more quickly and foaming can be controlled by adjusting the pH of the reaction mixture at a time when the reaction has proceeded about 35% to

about 50% to completion. The pH is adjusted from an initial value of about 7 to a value between 2 and 6 by addition of acid.

3,578,400

PREPARATION OF CHLORIDE-FREE HYPOCHLOROUS ACID SOLUTIONS

John A. Wojtowicz, Cheshire, Milton Lapkin, Woodbridge, and Mohindar S. Puar, Hamden, Conn., assignors to Olin Corporation
No Drawing. Filed Jan. 21, 1969, Ser. No. 792,761

Int. Cl. C01b 11/04

U.S. Cl. 23—152

8 Claims

Solutions of hypochlorous acid (HOCl), free from chloride and chlorine are prepared by extraction of aqueous chlorination mixtures containing HOCl and chloride using an extraction solvent selected from the group consisting of lower alkyl ketones, lower alkyl cyanides and lower alkyl esters of lower alkanic acids. The lower alkyl suitably contains 1 to 5 carbon atoms and the lower alkanic acids suitably contain 1 to 5 carbon atoms. The resulting solutions, containing from about 0.5 to about 50 percent by weight of HOCl , are useful for chlorohydrination reactions where the presence of chloride or chlorine is deleterious.

3,578,401


PROCESS OF PRODUCING HYDROHALIC ACIDS AND METAL OXIDES

Dieter Ueberle and Ernst Heinz, Frankfurt am Main, Germany, assignors to Metallgesellschaft Aktiengesellschaft, Frankfurt am Main, Germany
Filed Jan. 29, 1969, Ser. No. 794,964

Claims priority, application Germany, Jan. 31, 1968, P 16 67 195.7
Int. Cl. C01b 7/00, 7/08

U.S. Cl. 23—154

13 Claims



A process of producing hydrohalic acid and metal oxide from a metal halide solution, wherein metal halide is precipitating from the metal halide solution in a precipitation step, and the precipitated halide is separated from the mother liquor and is thermally decomposed with oxygen, steam or a mixture thereof, to yield a hot hydrohalic acid containing gas and metal oxide, characterized in that:

- mother liquid is recycled to the precipitation step,
- said recycle mother liquor, prior to the precipitation step being subjected to direct heat exchange with said hot hydrohalic acid-containing gas,
- the mother liquor recycle stream is recycled so often that the throughput of recycle mother liquor per unit of time amounts to 4 to 20 times the amount of metal halide solution which is fed to the process per unit of time.

3,578,402

METHOD FOR INHIBITING THE FOAMING TENDENCIES OF PHOSPHORIC ACID

Olen L. Riggs, Jr., Ponca City, Okla., assignor to Continental Oil Company, Ponca City, Okla.
No Drawing. Filed Feb. 9, 1968, Ser. No. 704,215

Int. Cl. C01b 25/18

U.S. Cl. 23—165

2 Claims

The foaming tendencies of phosphoric acid are inhibited by addition thereto of the reaction product of an iodide such as hydrogen iodide and an organic amine such as aliphaticalkyl mono and diamines, imidazolines, and guanidines.

3,578,403


RECRYSTALLIZATION OF PYROLYTIC BORON NITRIDE

Arthur W. Moore, Parma, Ohio, assignor to Union Carbide Corporation
Filed July 5, 1968, Ser. No. 742,614

Int. Cl. C01b 21/06

U.S. Cl. 23—191

6 Claims



A method for structurally transforming pyrolytic boron nitride into a product closely related to a single crystal hexagonal boron nitride structure by subjecting a disc or plate of the starting material to a simultaneous temperature of at least 2250°C . and pressure of 5000 p.s.i. in a non-reactive atmosphere. The pressure is applied uniaxially in the predominant direction of the C-axes and applied so as to place the material in compression.

3,578,404

AUTOMATIC REACTION RATE APPARATUS


Wilhelm E. Walles, Midland, Mich., and William F. Touseignant, Elm Grove, Wis., assignors to The Dow Chemical Company, Midland, Mich.

Filed Dec. 4, 1967, Ser. No. 687,707

Int. Cl. G01n 7/02, 7/18

U.S. Cl. 23—230

25 Claims



Method and apparatus for ascertaining the rate of reaction that evolves or consumes a gas; comprising a closed, circuitous duct a first upstream end of which

originates at a downstream portion of a reaction vessel, proceeds through valve means, pump means, and pressure sensing means, means for sensing at least one kind of influence upon the rate of a reaction in said reaction vessel, and optionally other means, returning to terminate at a second, downstream end at an upstream portion of said reaction vessel which, in turn, communicates with said first end. By control under provided timing means, confined gas pressure is sensed in increments, along with increments of reaction-rate influences such as heat; during operation the interior of the duct and vessel are returned to reference pressure after each sensing increment and are subject to substantially continuous movement of gas.

3,578,405

METHOD AND APPARATUS FOR ANALYSIS OF FLUID MIXTURES


Robert A. Woodle, Nederland, Tex., assignor to Texaco Inc., New York, N.Y.

Filed July 22, 1968, Ser. No. 746,488

Int. Cl. G06f 15/46; G01n 25/00

U.S. Cl. 23—230

16 Claims




A method and apparatus for continuously monitoring a component of a fluid mixture, such as the naphthene content of a hydrocarbon mixture. The apparatus includes an adiabatic selective micro-reactor, such as a dehydrogenation micro-reactor, in which the fluid mixture is reacted to alter a component by conversion to another chemical component having different physical properties such as the heat of formation thereof, and means for sensing the altered physical property such as thermocouples, thereby enabling detection of the fluid component of interest in accordance with the altered physical property. In a further embodiment a unique computer is provided for calculating the concentration in the mixture of the fluid component of interest in response to the sensed heat of the reaction. The method of the invention includes reacting the fluid mixture to alter at least one component of the fluid mixture to a different chemical component having a different physical property thereby rendering the altered fluid component distinguishable, and detecting the fluid component of interest. In one aspect of the method the detecting step includes the steps of sensing the heat of the reaction by sensing the fluid temperature before and after the reaction, and generating signals corresponding to the sensed temperatures, and in response to these signals generating a further signal corresponding to the concentration in the mixture of the fluid component of interest in accordance with a predetermined relationship between the heat of said reaction and said concentration.

3,578,406

SULFUR DIOXIDE MEASUREMENT SYSTEM
Boong Y. Cho and Larry B. Anderson, Columbus, Ohio,
assignors to the United States of America as represented by the United States Atomic Energy Commission
Filed Mar. 3, 1969, Ser. No. 803,642
Int. Cl. G01n 23/00

U.S. Cl. 23-232

10 Claims



A quantitative determination of relatively small or trace amounts of gaseous sulfur dioxide involves a reaction between mercurous chloride and sulfurous acid, the latter formed when sulfur dioxide is dissolved in water. One of the reaction products is a water soluble bis-sulfite-mercurate complex, the mercurate being easily removable from the remainder of the reaction mixture. The conversion of sulfur dioxide to the bis-sulfite-mercurate complex is about 95% complete. By nucleonically detecting the amount of the bis-sulfite-mercurate complex, which contains a metal having a high Z number (atomic number), using a monoenergetic source of nuclear radiation in the range of 15 to 25 kev., the amount of the complex is determinable and easily compared against a known standard sample either electronically or visually. The present system may be used on a continuously flowing gas such as stack gas, in which event it is unnecessary to scrub the gas, and permitting accurate determination of trace amounts of sulfur dioxide by monitoring or controlling the gas flow rate.

3,578,407


HIGH-PRESSURE CLOSURE APPARATUS
Lloyd C. Arnold, Texas City, and George A. Mortimer, La Marque, Tex., assignors to Monsanto Company, St. Louis, Mo.

Filed Oct. 14, 1968, Ser. No. 767,079

Int. Cl. B65d 25/54; G01f 23/02

U.S. Cl. 23-252

12 Claims



An apparatus for use in high pressure applications comprising a solid body having a partially ellipsoidal shape,


said solid body being of a material having high compressive strength and low tensile strength and a means for uniformly supporting said body. The apparatus is especially suitable as a window and a support for said window which can be mounted in a reaction vessel for visual observation of very high pressure chemical reactions.

3,578,408

TITRATING APPARATUS
Louis L. Sirois, Albert A. Winer, and Gordon E. Alexander, Ottawa, Ontario, and Arthur P. Page, Stittsville, Ontario, Canada, assignors to Canadian Patents and Development Limited, Ottawa, Ontario, Canada
Filed Oct. 7, 1969, Ser. No. 864,488
Int. Cl. G01n 27/56, 31/16; G01r 5/28

U.S. Cl. 23-253

6 Claims



An automated potentiometric titrating apparatus for successively adding quantities of titrant to a mineral suspension when the pH recovery is at equilibrium, comprising electrodes in the suspension and connected to a pH meter and strip chart recorder, a meter relay for operating a titrant adding device, a capacitor for operating the meter relay, a programmable power supply for charging the capacitor, a variable resistance coupled to the recording pen of the strip chart recorder for operating the programmable power supply in response to changes in the pH of the suspension, and a motor driven cam operated micro-switch assembly, for controlling the quantities of titrant added and the response of the meter relay, so that it is responsive to the systems indicating pH recovery of suspension.

3,578,409


SENSORS UNAFFECTED BY HUMIDITY CHANGES TO DETECT TOXIC OXIDIZING VAPORS
Herbert P. Silverman, Orange, and Gino A. Giarrusso, Long Beach, Calif., assignors to TRW Inc., Redondo Beach, Calif.

Filed Aug. 23, 1967, Ser. No. 662,663

Int. Cl. G01n 31/00, 31/06

U.S. Cl. 23-254

5 Claims



A thin film of a metal such as iron, silver or copper being oxidizable to the extent of corrosion bonded to a non-corrodible backing and having a thin layer of a compound such as potassium chloride on at least a portion of the metal, the compound being adapted to prevent the formation of a passivating layer on the metal when exposed to oxidizing vapors and being adapted to permit

continued oxidation of the metal; and an additive to said compound of a hygroscopic organic composition such as glycerol having been mixed with the compound in solution before coating the metal therewith.

3,578,410


AMMONIA DETECTION, FOLLOWING ULTRAVIOLET RADIATION
Frank W. Van Luik, Jr., Schenectady, N.Y., assignor to General Electric Company

Filed July 1, 1968, Ser. No. 741,529

Int. Cl. G01n 21/26, 33/00; H01j 37/00

U.S. Cl. 23-232

4 Claims




If a gas such as air containing small amounts of ammonia is exposed to ultraviolet radiation prior to being contacted with an acid to form ammonia compound condensation nuclei, about 1000 times more nuclei are formed than if such radiation is omitted.

3,578,411

BUBBLER ASSEMBLY FOR BLOOD TREATING APPARATUS
Donald J. Bentley, Newport Beach, Calif., and Richard A. De Wall, Dayton, Ohio; said De Wall assignor to Bentley Laboratories, Inc., Santa Ana, Calif.
Filed July 22, 1969, Ser. No. 843,558
Int. Cl. A61m 1/03

U.S. Cl. 23-258.5

11 Claims



A bubbler assembly for use in a blood treating apparatus such as a blood oxygenator for forming films of blood in bubble form by directing oxygen into a stream of venous blood to effectuate transfer of oxygen to the blood film and release of carbon dioxide from the blood film. The bubbler assembly is characterized by an improved arrangement of the blood passageway which is generally S-shaped in nature; by a completely smooth interior which eliminates sharp edges; by an improved


outlet structure whereby blood bubbles empty outwardly and downwardly on a deflector plate for more uniform distribution of blood through an enveloping defoamer unit; and by an improved exterior configuration having recessed side portions relative to adjacent top and bottom structure by means of which a greater portion of the defoamer sleeve is held relatively spaced from the bubbler structure to eliminate obstructions to the flow of bubbles passing out of the bubbler unit and to expose a greater area of the defoamer sleeve to the blood.

3,578,412

AUTOMATED TRANSPORT SYSTEM
Donald N. Martin, Whittier, Calif., assignor to Beckman Instruments, Inc.
Filed Jan. 22, 1968, Ser. No. 699,617
Int. Cl. G01n 1/10; B65g 47/00

U.S. Cl. 23-259

15 Claims



A transport system for use in an automated chemical analyzer having a pair of horizontal rails on which a plurality of individual sample capsules are adapted to be supported and conveyed by means of a pair of serrated members or racks, in intermittent stop and go fashion, past a series of processing stations where various analytical steps are performed, the rails being mounted for up and down movement by means of a vertical air cylinder, the racks being mounted for reciprocal horizontal movement by a horizontal air cylinder, the action of rails and racks being synchronized or coordinated so that a capsule on the rails in the down position thereof is disposed in engagement with a pair of teeth on the racks which then slides the capsule along the rails a distance equal to about the width of a capsule, after which the vertical air cylinder is triggered to raise the rails and trigger return of the racks, each cycled downward movement of the rails engaging the capsule with the next downstream pair of teeth of the racks during each succeeding cycle and in such manner conveying the capsule the length of the rails.


3,578,413

APPARATUS FOR THE PRODUCTION OF MELAMINE FROM UREA
Victor A. M. G. Vorage, Beek, Netherlands, assignor to Stamicarbon N.V., Heerlen, Netherlands
Filed Nov. 21, 1968, Ser. No. 777,705
Claims priority, application Netherlands, Nov. 21, 1967, 6715751

Int. Cl. B01j 9/20; C07d 55/28

U.S. Cl. 23-260

2 Claims



Apparatus for producing melamine from urea which includes in combination a reactor and separating devices in communication therewith for removing melamine from

the reaction product and recovering NH_3 from the essentially melamine-free reaction product. The recovered NH_3 is recycled to the reactor to fluidize the catalyst bed therein and to atomize the urea fed thereto for conversion into melamine. Venting conduit means and supplemental ammonia conduit means are also provided. Means for sensing the pressure in the reactor and separating devices and for sensing the amount of ammonia introduced into the reactor to fluidize the catalyst bed are employed and in response to the sensed pressure and quantity values. The pressure and amount of ammonia utilized are controlled to maintain the reactor in operational condition.

3,578,414

APPARATUS FOR GROWTH OF LARGE CRYSTALS IN GELS


Alton F. Armington, Lexington, and John J. O'Connor, Arlington, Mass., assignors to the United States of America as represented by the Secretary of the Air Force

Filed Oct. 24, 1967, Ser. No. 677,791

Int. Cl. B01d 9/02

U.S. Cl. 23-273

3 Claims



An apparatus for growing single crystals of a relatively large size having first and second reactant containing reservoirs respectively possessing relatively large volumes in relation to the volume of a crystal growing chamber positioned in a horizontal relationship between the reservoirs and interconnected thereto. Crystal growth is effected in a gel matrix positioned within the crystal growing chamber with the first and second reservoirs containing the required crystal growing solutions needed to bring about crystal growth.

3,578,415

DRY HYDROGEN GENERATOR


Ralph H. Hiltz, Pittsburgh, Pa., assignor to the United States of America as represented by the Secretary of the Army

Continuation-in-part of application Ser. No. 681,965, Nov. 8, 1967. This application Oct. 13, 1969, Ser. No. 865,712

Int. Cl. B01j 7/00



U.S. Cl. 23-281

2 Claims




A telescopically expandable container for dry materials which produce hydrogen when heated by a squib or other means. The expandable container allows for cooling of the liberated gas and removal of moisture therefrom.

3,578,416
HIGH TEMPERATURE REACTOR
Bill J. Pope, Department of Chemical Engineering,
Brigham Young University, Provo, Utah 48601
Filed Dec. 19, 1968, Ser. No. 785,156
Int. Cl. F27d 11/04
U.S. Cl. 23-277 3 Claims



A high temperature gas reactor is provided for carrying out high temperature chemical reactions. The reactor includes a porous member, having electrical resistance properties, mounted in a gas introduction chamber. A first gas is introduced into the chamber and is heated as it passes through the porous member. A second gas communicates with the heated first gas at a Venturi passage which Venturi passage is adapted to draw the heated first gas from the gas introduction chamber through the porous member. In an embodiment, an auxiliary reaction chamber is positioned between the porous member and the Venturi passage and a third gas is supplied to said auxiliary chamber.


3,578,417
VAPORIZING SULFUR FROM ORE BY DIRECT CONTACT WITH HEATED PEBBLES
John M. Dale, San Antonio, Tex., assignor to Pan American Sulphur Company, Houston, Tex.
Filed June 30, 1969, Ser. No. 837,655
Int. Cl. B01d 7/00; C01b 17/08
U.S. Cl. 23-294 11 Claims



The continuous method of and apparatus for recovering sulfur from ores by feeding surface sulfur ore into a closed conveyor and simultaneously heating the ore with

heated pebbles while slowly mixing and conveying the mixture through the conveyor and heating the ore above the boiling point of sulfur to vaporize the sulfur in which the vaporized sulfur is passed through a condenser for recovery. The depleted ore and pebbles are discharged from the conveyor and separated with the pebbles being conveyed to a heater for reheating and reuse. For greater efficiency the hot exhaust gases from the pebble heater are flowed in a counterflow heat exchange relationship with the container to heat the mixture. The conveyor having an elongate power shaft positioned longitudinally in the container for rotative movement with a plurality of paddles positioned adjacent the interior walls of the container and connected by the shaft for rotative movement to mix the ore and pebbles, move the mixture along the conveyor, and keep the interior walls of the container cleaned for greater heat transfer. The volume of pebbles being greater than the volume of ore in the container to more easily convey the mixture through the conveyor.

3,578,418
SULFUR EXTRACTION USING HALOGENATED HYDROCARBONS INCLUDING WASHING THE RECOVERED SULFUR WITH METHANOL, ACETONE, OR ETHYLENE GLYCOL
Robert R. Cantrell, Baltimore, and Vernon F. Swanson, Ellicott City, Md., assignors to W. R. Grace & Co., New York, N.Y.
Filed May 27, 1968, Ser. No. 732,294
Int. Cl. C01b 17/08, 17/14; B01d 9/02
U.S. Cl. 23-299 11 Claims




A solvent-extraction process for recovering sulfur from sulfur-bearing ores not amenable to treatment by the Frasch hot-water process. Sulfur-bearing ore is dried and contacted with a solvent, such as tetrachloroethylene, at a temperature above the melting of the sulfur. The gangue is separated from the loaded solvent by filtration, and the loaded solvent is cooled to a temperature to permit crystallization of the sulfur. The solid sulfur is separated from the solvent and the sulfur cake is passed through a countercurrent washing system to remove residual solvent and to provide sulfur in essentially pure form.

3,578,419
SCRAP NUCLEAR FUEL MATERIAL RECOVERY PROCESS
Richard K. Welty, Murrsville, Pa., assignor to General Electric Company
Filed Dec. 14, 1967, Ser. No. 690,635
Int. Cl. C01g 1/02, 43/02
U.S. Cl. 23-317 4 Claims

An improved process for recovering hard scrap nuclear reactor fuel material is disclosed. In the preparation of fuel pellets, a significant quantity of scrap nuclear fuel material which has been pressed and sintered is produced. In the disclosed process, the scrap is first oxidized in a

fluidized bed method which simultaneously oxidizes and comminutes the scrap, then, if desired, the oxidized ma-



terial is reduced back to the original chemical form with improved sinterability.

3,578,420
METAL FILM RESISTOR
Yasuro Nishimura, Machida-shi, and Masao Tanaka, Tokyo, Japan, assignors to Fujitsu Limited, Kawasaki, Japan
Filed Sept. 20, 1968, Ser. No. 761,050
Claims priority, application Japan, Sept. 23, 1967, 42/61,093
Int. Cl. B32b 15/04; H01c 7/00
U.S. Cl. 29-195 2 Claims

Our invention relates to a metal film resistor comprising evaporated thin films of small specific resistance and temperature coefficient of resistance. The metal film resistor comprises a first evaporated thin film including nickel, chromium and gold and, when necessary, other metals and an electrically stable second evaporated thin film provided on said first evaporated thin film. The second film prevents diffusion and precipitation of gold in the first evaporated thin film and protects the first evaporated thin film.

3,578,421
LIQUID HYDROCARBON COMPOSITIONS CONTAINING REACTION PRODUCTS OF AN AMINE AND METHYL VINYL ETHER-MALEIC ANHYDRIDE COPOLYMERS AS ANTI-STATIC AGENTS
Harry J. Andress, Jr., Pitman, and Henry Ashjian, East Brunswick, N.J., assignors to Mobil Oil Corporation
No Drawing. Filed July 26, 1968, Ser. No. 747,808
Int. Cl. C101 1/18, 1/22
U.S. Cl. 44-62 17 Claims

Liquid hydrocarbon compositions are provided containing, in an amount sufficient to impart anti-static properties, the reaction product of an amine and a methyl vinyl ether-maleic anhydride copolymer.

3,578,422
EMULSION RESISTANT FUEL COMPOSITIONS
Casper John Dorer, Jr., Lyndhurst, Ohio, assignor to The Lubrizol Corporation, Wickliffe, Ohio
No Drawing. Filed Mar. 3, 1969, Ser. No. 804,015
Int. Cl. C101 1/18, 1/22
U.S. Cl. 44-63 14 Claims

Fuel compositions containing additive combinations consisting of at least (1) one ashless dispersant, (2) an ammonium or amine salt of sulfonic acid, and (3) an oil-soluble polyether. A typical fuel could contain at least one acylated nitrogen material prepared by reacting a hydrocarbon substituted succinic acid anhydride and an ethylene polyamine, at least one ammonium salt of a petrosulfonic acid, and a polyglycol.

3,578,423
PROCESS FOR CATALYTICALLY SPLITTING ISOBUTYRALDEHYDE TO PRODUCE CARBON MONOXIDE AND HYDROGEN

Jürgen Falbe, Dinslaken, and Heinz-Dieter Hahn, Oberhausen-Sterkrade-Nord, Germany, assignors to Ruhrchemie A.G.

No Drawing. Filed Apr. 14, 1969, Ser. No. 816,108
 Claims priority, application Germany, Apr. 20, 1968, P 17 67 281.0
 Int. Cl. C01b 2/14

U.S. Cl. 48—197 11 Claims

Process for catalytically splitting isobutyraldehyde with formation of a gas mixture consisting essentially in carbon monoxide and hydrogen which comprises contacting isobutyraldehyde and water vapor in amount of at least 3 moles water vapor per g-atom aldehyde carbon, at temperatures of about 600–900° C. at ordinary atmospheric or elevated pressure, with a nickel containing catalyst.


3,578,424
ABRADING MACHINE FOR A PREFORMED ORTHODONTIC BAND

Frank R. Miller, Bradbury, and Raymond E. Dillberg, Temple City, Calif., assignors to Ormco Corporation, Glendora, Calif.

Filed Aug. 9, 1968, Ser. No. 751,555
 Int. Cl. B24b 5/00

U.S. Cl. 51—89

5 Claims



A machine for forming an orthodontic incisor, cuspid, bicuspid or molar band is provided. The machine is provided with opposed peripheral abrading wheels which are pendantly supported with drive motors on the lower ends of the pendant arms and a conveyor means moves the bands into grinding position.

3,578,425
DIAMOND AND BORON NITRIDE PARTICLES COATED WITH A POLYMERIZED DIANHYDRIDE

Archibald N. Wright, Schenectady, N.Y., and Wilfred F. Mathewson, Jr., Franklin, Mich., assignors to General Electric Company


Filed Mar. 14, 1967, Ser. No. 622,944
 Int. Cl. B24b 1/00; C08 51/12

U.S. Cl. 51—295

4 Claims

A thin, continuous film is formed on a substrate by ultraviolet surface photopolymerization of a material in the gaseous phase. The material is selected from various anhydrides and dianhydrides. Such films, which can be selectively formed as electrically insulating or electrically conductive, are useful as coatings on metallic and non-metallic substrates, and for corrosion protection. The electrically insulating films are useful further as capacitor

dielectrics, cryogenic device insulation, insulation for microelectric devices, and primer or insulation on electric



cally conductive wire, while the electrically conductive films can also be employed as conductive layers in microelectric devices.

3,578,426
METHOD FOR MAKING GLASS FIBER STRAND FOR RESIN REINFORCEMENT

Thomas E. Philipps, Granville, and James C. Belue, Sylvania, Ohio, assignors to Owens-Corning Fiberglass Corporation

Continuation-in-part of application Ser. No. 493,505, Oct. 6, 1965. This application Jan. 8, 1968, Ser. No. 696,172

The portion of the term of the patent subsequent to Mar. 3, 1987, has been disclaimed
 Int. Cl. C03c 25/02, 25/06

U.S. Cl. 65—3

11 Claims

Bundles of glass fibers and method of producing same wherein the fibers are etched and are held together along generally line contacts by a brittle binder formed by the deposition in situ of the material leached from the fibers.

3,578,427
PROCESS FOR FABRICATING GLASS MULTIPLE GLAZED UNITS

Robert A. Jansson, Pittsburgh, and Raymond J. Mickellic, Springdale, Pa., assignors to PPG Industries, Inc., Pittsburgh, Pa.

Filed Dec. 16, 1968, Ser. No. 784,130
 Int. Cl. C03b 23/24

U.S. Cl. 65—58

10 Claims



A process for the manufacture of welded all-glass multiple glazed window units having a stepped edge configuration such that the spacing of the glass sheets about the marginal edges of the unit is less than the spacing of the glass sheets throughout the remainder of the unit. A multiple glazed unit is heated inwardly of the marginal

fused edge of one of its glass sheets, and then the portion of the glass sheet within the heated circumscribing portion is moved relative to the other glass sheet.


3,578,428
METHODS OF PRODUCING CERAMIC MATERIAL IN ROD OR TUBE FORM

William Stanley Lee, South Shields, England, assignor to James A. Jobling & Company Limited, Sunderland, England

Filed Nov. 4, 1968, Ser. No. 773,108
 Int. Cl. C03c 17/00; C03b 5/22

U.S. Cl. 65—60

3 Claims



A method of producing ceramic material in rod or tube form comprising the steps of feeding lengths of ceramic material of specific desired composition to a melting chamber, melting the lengths of ceramic material in the chamber and continuously drawing ceramic material of rod or tube form from the chamber.

3,578,429
APPARATUS FOR MAKING MINIATURE INCANDESCENT LAMPS

Donald J. Belknap, 302 Patterson Court, Takoma Park, Md. 20012

Filed Sept. 19, 1968, Ser. No. 760,852
 Int. Cl. C03c 27/02; H01j 9/00

U.S. Cl. 65—154

17 Claims

Miniature incandescent lamp envelopes are formed seriatim by feeding the components by gravity-feed chutes to an assembly station where the envelope sleeves are supported on a table having aligned grooves for receiving the sleeves. The end sleeves are partially inserted into the central sleeve by pusher members. The resulting assemblies are then conveyed by a rotating member to a sealing station. Filaments are formed and inserted into the envelopes by pulling a length of wire through a tubular sleeve, inserting an envelope over the sleeve and winding a filament coil from the end of the filament wire projecting from the sleeve. The coil winder comprises a mandrel about which the coil is formed, and a wire guide for engaging the wire at locations spaced laterally from the mandrel. A solenoid is supported for rotation about the axis of the mandrel. The solenoid has two jaws which grip the wire. Both the jaws and the mandrel are rotated with the solenoid. The mandrel is also mounted for axial reciprocation.


3,578,430
SEALED FLOAT GLASS PLANTS
 Günter Labrot, Porz, Germany, assignor to Erste Deutsche Floatglas G.m.b.H. & Co. OHG., Porz, Cologne, Germany

Filed Mar. 27, 1968, Ser. No. 716,483
 Claims priority, application Germany, Mar. 29, 1967, E 33,696
 Int. Cl. C03b 18/02

U.S. Cl. 65—157

9 Claims

The specification describes means for preventing the access of air to molten glass passing from a container



one of which is of a gas-imperious nature, and a masonry channel having gas-imperious external sheathing structure.


3,578,431
METHOD FOR AUTOMATICALLY SUPPLYING NUTRITIVE COMPOSITIONS TO PLANTS IN OPTIMUM AMOUNTS

Nils Torsten Ingestad, Stockholm, and Ernst Göran von Haartman, Lund, Sweden, assignors to Aktiebolaget Wallico, Stockholm, Sweden

Filed Sept. 30, 1966, Ser. No. 583,163
 Claims priority, application Sweden, Oct. 1, 1965, 12,722
 Int. Cl. A01g 9/00, 31/00

U.S. Cl. 71—1

4 Claims



Constant nutrient composition corresponding to predetermined nutrient proportions at optimum growth is automatically maintained in an aqueous cultivation medium for plants without the need for replacing the medium with a fresh solution. Mineral nutrient is supplied to the cultivation medium consisting essentially of water and a nutrient salt mixture in response to variations in hydrogen ion concentration and conductivity from at least three nutrient solutions, the first solution being alkaline and containing a portion of the nutrients, the second solution being acidic and containing a second portion of the nutrients, and the third solution containing the remainder of the nutrients.

3,578,432
METHOD OF IRRIGATION

Vernon E. Stiles, 1012 Brookdale Place, Fullerton, Calif.


Filed Mar. 22, 1968, Ser. No. 715,208
 Int. Cl. A01g 25/00

U.S. Cl. 71—1

19 Claims

Irrigation water is contacted with ion exchange resins charged with ions of plant nutrients, e.g., ammonium, nitrate, sulfate, potassium, to replace the ions of the salts

contained in the irrigation water with ions of nutrient value. This treatment obviates the difficulties encountered in arid and semi-arid areas with irrigation water containing a high content of dissolved salts which otherwise tend to accumulate in the soil to phytotoxic levels. In a typical embodiment, a column of mixed anion and cation exchange resins charged with nitrate and ammonium, respectively, and having a size of about 1.5 feet in diameter and about 10 feet in length is used to treat irrigation water having a total of about 300 p.p.m. hardness at a




liquid hourly space velocity of about 50 liquid volumes per volume per hour. This bed within a four-hour period treats a sufficient quantity of water to irrigate one acre one inch in depth and results in the addition of about 210 parts per million of ammonium nitrate to the irrigation water. When this is practiced over a year's irrigation involving approximately 3 acre feet of water per acre of irrigated land, the amount of nitrogen supplied is from about 400 to 850 pounds nitrogen, ample to supply all of the nutrient requirements of the plants.

3,578,433
METHOD FOR UREA-AMMONIUM POLYPHOSPHATE PRODUCTION
Gabriele A. Bottai, Florence, and John M. Stinson, Sheffield, Ala., assignors to Tennessee Valley Authority
Filed Aug. 5, 1968, Ser. No. 750,277
Int. Cl. C05b 1/00

U.S. Cl. 71—1

7 Claims



Prilling processes for the production of high-analysis fertilizers composed of urea and ammonium polyphosphate which involve combining concentrated urea solution with molten ammonium polyphosphate, forming droplets of said mixtures, and solidifying said droplets by allowing them to fall through liquid medium. Alternatively, product fines and crushed oversize or supplemental fertilizer materials such as potassium chloride or micro-nutrient sources may be incorporated prior to droplet formation.


3,578,434
2,6-DICYANOTRICHOROPYRIDINE SEED TREATMENT
Robert L. Noeroske, Walnut Creek, and Helen K. Tobol, Concord, Calif., assignors to The Dow Chemical Company, Midland, Mich.
No Drawing. Filed July 23, 1968, Ser. No. 746,730
Int. Cl. A01c 1/06; A01n 21/02
U.S. Cl. 71—77
2 Claims
Compositions containing 2,6-dicyanotrichloropyridine are applied to seeds to enhance and accelerate growth of the plant and to protect the seeds from pesticidal attack.

3,578,435
METHOD FOR PROMOTING GROWTH OF AGRICULTURAL PLANT
Tsunezo Ushioda, Tokyo, and Katsuhiko Nonaka, Minoru Yasuhara, Katsuya Sato, Takeshi Inoi, and Hiroaki Ishibashi, Yokohama-shi, Kanagawa-ken, Japan, assignors to Chisso Corporation, Osaka, Japan
No Drawing. Filed Dec. 29, 1966, Ser. No. 605,541
Claims priority, application Japan, Jan. 27, 1966, 41/4,732; Mar. 26, 1966, 41/18,595; Nov. 17, 1966, 41/75,715
Int. Cl. A01n 9/22


U.S. Cl. 71—92
7 Claims
A method for promoting the growth of agricultural plant by contacting said plant with 2-oxo-4-methyl-6-ureido-hexahydropyrimidine (which is a condensation product of urea and acetaldehyde or crotonaldehyde) and/or 2-oxo-4-methyl-6-hydroxy-hexahydropyrimidine (which is a hydrolyzate of the former), especially in soilless culture or in foliage application.

3,578,436
PROCESS FOR PRODUCING ALUMINUM
Warren E. Becker, Baton Rouge, La., and Paul Kobetz, Southfield, Mich., assignors to Ethyl Corporation, New York, N.Y.
No Drawing. Filed Aug. 20, 1968, Ser. No. 766,013
Int. Cl. B22f 9/00; C22b 21/00

U.S. Cl. 75—5
25 Claims
Aluminum is produced by thermocatalytic disproportionation of dialkylaluminum hydride into aluminum, trialkylaluminum and hydrogen. The amount of olefin liberated, if any, is very small. Unitary operations using the disproportionation reaction for converting crude aluminum into purified aluminum are described. One such operation involves the following:



which reduces to




3,578,437
METHOD OF SINTERING ORES
Masaaki Higuchi, Teiji Shibuya, Koichi Onoue, and Seiji Fujii, Fukuyama-shi, Hiroshima-ken, Japan, assignors to Nippon Kokan Kabushiki Kaisha, Tokyo, Japan
Filed Sept. 25, 1968, Ser. No. 762,565
Claims priority, application Japan, Oct. 2, 1967, 42/63,214
Int. Cl. C22b 1/20

U.S. Cl. 75—5
8 Claims
In a method of sintering ores, the temperature distribution pattern of the fracture of sintered cakes is measured and the measured value is compared with a predetermined reference temperature distribution pattern to derive a deviation signal which is used to control one or more of the factors that influence the sintering property.

3,578,438
PROCESS FOR FLAME REFINING OF COPPER SMELTS
Horst Dieter Iken, Dusseldorf, and Wolfgang Hans Trappmann, Heiligenhaus, Germany, assignors to Messer Griesheim GmbH, Frankfurt am Main, Germany
Filed Oct. 10, 1967, Ser. No. 674,188
Claims priority, application Germany, Oct. 19, 1966, M 71,328
Int. Cl. C22b 15/06

U.S. Cl. 75—73


2 Claims



In a flame refining process of copper smelts in a rotary calciner wherein oxygen is blown through an individual nozzle or lance to the flame burning in the furnace, the oxygen is blown so that its effect on the smelting charge is to oxidize a considerable portion of the charge during smelting, with the highest flame temperature being on the underside of the flame.

3,578,439
AMALGAMATION PROCESS
Maximillian R. Merriman, Upper Hibernia Road, Rockaway, N.J. 07866
No Drawing. Filed July 2, 1968, Ser. No. 741,891
Int. Cl. C22c 5/00, 7/00, 35/00
U.S. Cl. 75—129
10 Claims
Methods for amalgamating iron, platinum, and ferrous alloys, by acid cleaning the material to be amalgamated and permitting moisture to remain or form on the cleaned metal prior to dipping in amalgam.

3,578,440
NICKEL-COPPER ALLOY
Herbert L. Eiselstein and Carl B. Haeberle, Huntington, W. Va., assignors to The International Nickel Company, Inc., New York, N.Y.
Filed Mar. 25, 1968, Ser. No. 715,898
Int. Cl. C22c 19/00
U.S. Cl. 75—170
5 Claims



An age hardenable nickel-copper alloy having markedly improved weldability and machinability which alloy

contains not more than about 0.1% carbon, not more than about 0.5% titanium, about 2.5% to about 3.5% aluminum, about 63% to about 70% nickel and the balance, except for incidental elements and impurities, essentially copper.


3,578,441
ALLOY
Otto Knotek, Lausanne, Switzerland, assignor to Eutectic Corporation, Flushing, N.Y.
No Drawing. Filed Nov. 4, 1968, Ser. No. 773,285
Int. Cl. C22c 19/02

U.S. Cl. 75—171
4 Claims
This invention relates to an alloy capable of being polished to a mirrorlike finish. The alloy is very hard having a hardness of up to 1200 on the Vickers scale and comprises a nickel base with high boron content, up to nine percent by weight, with chromium.

3,578,442
METHOD OF MAKING MEANS FOR VENTING HELIUM FROM A RADIOISOTOPE CONTAINER
Charles G. Anderson, Carlisle, Ohio, assignor to the United States of America as represented by the United States Atomic Energy Commission
Filed Oct. 15, 1968, Ser. No. 768,225
Int. Cl. C22c 1/04

U.S. Cl. 75—206

4 Claims



Filter means and method of making the same for venting helium gas through a radioisotope container wall and preventing or minimizing escape of radioisotopes and radioactivity, comprising a porous tablet forming a part of the wall including a pressed and sintered particulate blend of a refractory metal and a heat resistive material to provide porosity and strength at elevated temperatures.

3,578,443
METHOD OF PRODUCING OXIDE-DISPERSION-STRENGTHENED ALLOYS
Nicholas J. Grant, Winchester, and William F. Schilling, Boston, Mass., assignors to Massachusetts Institute of Technology, Cambridge, Mass.
No Drawing. Filed Jan. 21, 1969, Ser. No. 792,817
Int. Cl. C22c 1/04

U.S. Cl. 75—206
18 Claims
A method is disclosed for producing an alloy having a fine uniformly dispersed hard refractory oxide material in a ductile matrix metal. The alloy is made from an alloy powder, the individual particles of which each contain the metal of which the refractory oxide is formed and the matrix metal, the oxide-producing reactive metal being one that has a much greater affinity for oxygen than the matrix metal and is soluble in the matrix metal. The powder particles are formed preferably into thin flakes,

of the order of 5 microns or less thick, in a controlled oxygen containing environment to oxidize the surfaces of both the reactive metal and the matrix metal in a thin film. The alloy powder flakes produced are thin enough to allow oxidation of a substantial portion of the reactive metal and a portion of the matrix metal to some predetermined degree. The oxidized flakes are then placed in a neutral or inert environment at an elevated temperature to remain a sufficient time to allow the matrix oxides to react with the matrix and thereby to supply oxygen to the reactive metal to oxidize the reactive metal within the interior of the flakes. The flake powders, now free of matrix oxide or oxygen in solution, are compacted, heat is applied to bring the temperature of the compact to a hot working temperature while maintaining the inert environment, and the compact is extruded or otherwise hot worked to a wrought alloy form. Favorable results for some purposes have been obtained by reducing the surface matrix metal oxides without the internal oxidation step, and then following the further steps mentioned to provide the wrought alloy.

3,578,444

METHOD OF MAKING POSITIVE-WORKING LITHOGRAPHIC PLATES BY ELECTROSTATIC IMAGE

Julius L. Silver, Franklin Township, Somerset, N.J., assignor to Union Carbide Corporation

No Drawing. Filed June 13, 1968, Ser. No. 736,554

Int. Cl. G03g 13/22

U.S. Cl. 96—1

9 Claims

Method for making positive-working lithographic plates by electrostatic imaging which involves coating an insolubilized oleophilic, hydrophobic substrate having admixed therewith a chromium trioxide component with a thin coating of a photoconductive material suspended in a binder, electrostatically charging the coating in the dark, and exposing the charged surface to a light image generated by projection or reflection. Thereupon, the image is developed by the application of a suitable toner. A solution of a photosensitizing agent is then applied. Exposure of this surface to actinic light causes the light struck areas of the plate to become hydrophilic and oleophobic. The photoconductive material-binder coating can then be removed.

3,578,445

XEROGRAPHIC PLATE FABRICATION


John J. Elchisak, Webster, William D. Hope, Rochester, and Edward M. Van Wagner, Webster, N.Y., assignors to Xerox Corporation, Rochester, N.Y.

Original application Sept. 26, 1963, Ser. No. 311,872, now Patent No. 3,341,681. Divided and this application June 22, 1967, Ser. No. 648,166

Int. Cl. G03g 5/04

U.S. Cl. 96—1.5

4 Claims



A xerographic drum and method for fabricating the same wherein a flexible, conductive, sheet-like substrate having a photoconductive surface thereon is bonded to

the surface of a drum blank. A lateral fold is formed in the flexible substrate along one edge thereof which edge becomes the trailing edge when the substrate is placed on the drum blank. The leading or non-folded edge of the flexible substrate is bonded to the drum surface and as the drum blank is rotated, the flexible substrate is held taut to produce a tightly wrapped relationship therebetween. The trailing or folded edge is placed in overlapping relationship to the bonded leading edge and the trailing portion of the substrate bonded to the drum blank at a point preceding the fold. After bonding of the trailing portion of the substrate, the fold, as a result of the resiliency of materials, produces a tight, flexible seal which prevents developer material from accumulating between the drum blank and the substrate.

3,578,446

ELECTROPHOTOGRAPHIC REPRODUCTION EMPLOYING BI-CHARGING AND NEGATIVE-CHARGING ZINC OXIDE

Meyer L. Sugarman, Northbrook, Ill., assignor to The Firestone Tire & Rubber Company, Akron, Ohio

No Drawing. Filed July 26, 1967, Ser. No. 657,471

Int. Cl. G03g 5/00

U.S. Cl. 96—1.8

4 Claims

Direct electrostatic duplication processes are often plagued with problems of background printing. The inclusion of bi-charging zinc oxide, and/or of polyvinyl alcohol in the coating composition applied to the paper or other substrate will greatly reduce this problem.

3,578,447

DYE DEVELOPER COLOR DIFFUSION TRANSFER PROCESSES AND ELEMENTS COMPRISING ALPHA AND GAMMA HYDROXY AND GAMMA AMINO SUBSTITUTED PYRIDINES


Myron S. Simon, West Newton, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed May 2, 1969, Ser. No. 821,191

Int. Cl. G03c 5/54, 7/00

U.S. Cl. 96—3

19 Claims



Dye-developer diffusion transfer color processes and elements and compositions for employment therein, comprising a compound selected from alpha and gamma hydroxy and gamma amino substituted pyridines adapted to react with the oxidation products of the dye developers

to provide during processing a product which is less diffusible in the processing composition than the said dye developer oxidation products.

3,578,448

DIFFUSION TRANSFER DYE DEVELOPER PROCESSES AND PRODUCTS EMPLOYING ORTHO AND PARA HYDROXY AND PARA AMINO SUBSTITUTED PYRIDINES


Stanley M. Bloom, Waban, Myron S. Simon, West Newton, and Jeanne A. Ward, Lexington, Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Dec. 20, 1968, Ser. No. 785,624

Int. Cl. G03c 7/20

U.S. Cl. 96—3

19 Claims



The present invention relates to photographic diffusion transfer dye developer processes employing ortho and para hydroxy and para amino substituted pyridines and film units specifically adapted for the performance of such processes.

3,578,449

TRANSFER IMAGE PROCESS UTILIZING AN ORGANIC PHOSPHINE AS SILVER HALIDE SOLVENT

Stanley M. Bloom, Waban, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

No Drawing. Filed Jan. 22, 1968, Ser. No. 699,300

Int. Cl. G03c 5/54

U.S. Cl. 96—29

10 Claims

Organic derivatives of the trihydrides of trivalent elements in Group V-A of the Periodic Table having an atomic number greater than 7 and less than 83 are used as silver halide solvents in photographic processing compositions. Specifically, organic phosphines, arsines, stibines and mixtures thereof are used in photographic processing compositions which find particular utility in silver diffusion transfer techniques.

3,578,450

DIFFUSION TRANSFER PRODUCTION OF REFLECTION POSITIVE WITH ALUMINUM STEARATE IN RECEPTIVE STRATUM

Edgar W. Miller, Newton Center, and Harry A. Smith, Concord, Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Apr. 22, 1968, Ser. No. 723,003


Int. Cl. G03c 5/54

U.S. Cl. 96—29

12 Claims

Photographic products for forming a composite print viewable as a positive silver image, including a silver

halide emulsion layer, an opacifying material in the emulsion layer and/or in an overlying layer, and an outer developer oxidation products.



layer comprising a silver-receptive stratum, wherein the silver-receptive stratum includes a reagent comprising essentially aluminum stearate.

3,578,451

INTEGRAL NEGATIVE TYPE POSITIVE PHOTOLITHOGRAPHIC PLATE


Towers Doggett, Westbrook, Maine, assignor to Scott Paper Company, Delaware County, Pa.

Filed Mar. 29, 1967, Ser. No. 626,874

Int. Cl. G03f 7/02

U.S. Cl. 96—33

2 Claims



A normally negative-working lithographic plate is coated with a conventional silver halide emulsion, an intermediate water-barrier coating being used to prevent co-mingling of the sensitized layers. The resulting plate is image-wise exposed to a positive original and developed to form as in-situ mask or integral negative for a subsequent exposure of the diazo layer. Following the second exposure the emulsion layer is removed and the resulting plate used to reproduce the original positive pattern.

3,578,452

DEVELOPING COMPOSITIONS FOR DIAZOTYPE MATERIALS

Konrad Parker, Park Ridge, Ill., assignor to Addressograph-Multigraph Corporation, Mount Prospect, Ill.


No Drawing. Continuation-in-part of application Ser. No. 440,752, Mar. 18, 1965. This application Sept. 12, 1968, Ser. No. 759,503

Int. Cl. G03c 1/58

U.S. Cl. 96—49

8 Claims

Diazotype developing compositions comprising a liquid organic amine such as morpholine, alkylmorpholine, piperidine, alkylpiperidine, or an amine of the formula



wherein R₁ is hydroxyalkyl, cycloalkyl or aralkyl dissolved in a polyhydric alcohol, a glycol ether or a monohydric alcohol containing at least six carbon atoms with water in an amount not greater than the weight of the organic solvent.

3,578,453

COLOR PHOTOGRAPHIC PROCESSING WITH WATER SOLUBLE AMINES AND SALTS THEREOF


Hiroyuki Amano, Haruhiko Iwano, Kazuo Shirasu, and Reiichi Ohi, Kanagawa, Japan, assignors to Fuji Shashin Film Kabushiki Kaisha, Kanagawa, Japan
No Drawing. Filed Jan. 5, 1968, Ser. No. 695,892
Claims priority, application Japan, Jan. 6, 1967, 42/1,306

Int. Cl. G03c 5/32

U.S. Cl. 96—60

16 Claims

The present invention relates to a method of processing color photographic light sensitive elements and particularly to a bleaching process for color photographic light sensitive elements by processing them in a bleaching solution containing at least one member selected from the group consisting of an aliphatic primary amine, an aliphatic secondary amine, an aliphatic tertiary amine, and a salt thereof, said amine being represented by the general formula



wherein R₁, R₂ and R₃ represent a member selected from the group consisting of a hydrogen atom, an unsubstituted alkyl group, a substituted alkyl group, an unsubstituted aliphatic group, a substituted aliphatic group, and a heterocyclic ring with another group, the total number of carbon atoms in R₁, R₂ and R₃ being less than 12.

3,578,454

COLOR PHOTOGRAPHIC PROCESSING

Hiroyuki Amano, Reiichi Ohi, Haruhiko Iwano, and Kazuo Shirasu, Kanagawa, Japan, assignors to Fuji Shashin Film Kabushiki Kaisha, Kanagawa, Japan
No Drawing. Filed Dec. 13, 1967, Ser. No. 690,068
Claims priority, application Japan, Dec. 14, 1966, 41/81,967

Int. Cl. G03c 5/32, 5/38

U.S. Cl. 96—60

12 Claims

A method of color processing for a photographic light-sensitive color element comprising, at least, development, stop-fixing, and bleach-fixing, the improvement which comprises processing the light-sensitive element in a bath containing a water-soluble iron complex salt and a compound represented by the general formula:



wherein A represents an alkylene group having from 2 to 4 carbon atoms and n is a positive integer, the bath being a bleach-fixing bath or a separate bath in which the element is processed, after color development, but no later than bleach-fixing.

3,578,455

INCREASED SPEED IN R—C—X₃/COLOR FORMER LIGHT SENSITIVE SYSTEM BY ALKALI TREATMENT

Victor P. Petro, Brecksville, James M. Lewis, Cleveland, and Robert D. Fox, University Heights, Ohio, assignors to Horizons Incorporated, a Division of Horizons Research Incorporated
No Drawing. Filed Mar. 11, 1968, Ser. No. 711,832

Int. Cl. G03c 1/72

U.S. Cl. 96—90

25 Claims

Photosensitive compositions consisting essentially of (1) an organic halogen compound which produces free

radicals when exposed to a suitable dose of radiant energy and (2) a styryl quinoline or other dye base are found to be improved by treatment of the dye base with an alkali metal hydroxide, whereby the resulting composition has more speed, i.e., it can be developed for longer intervals before the amount of fogging becomes objectionable.

3,578,456

NON-SILVER PHOTOSENSITIVE COMPOSITION SENSITIZED WITH RUBRENE

Victor P. Petro, Brecksville, James R. Cable, Macedonia, and Eugene Walner, Shaker Heights, Ohio, assignors to Horizons Incorporated, a Division of Horizons Research Incorporated
Filed May 9, 1968, Ser. No. 728,002

Int. Cl. G03c 1/72

U.S. Cl. 96—90

8 Claims

Non-silver photosensitive compositions adapted to be developed by optical means, said compositions being provided with sensitivity extending into the red by the addition thereto of merocarbocyanines or a merocyanine.

3,578,457

PHOTOSENSITIVE DIAZOTHIETHER MATERIAL

Harke Jan Houtman, Cornelis Johannes Schoot, Jan Boven, and Leendert Klaas Hellings van Beek, Emmasingel, Eindhoven, Netherlands, assignors to U.S. Phillips Corporation, New York, N.Y.
No Drawing. Filed Feb. 10, 1969, Ser. No. 798,127


Claims priority, application Netherlands, Feb. 13, 1968, 6802059

Int. Cl. G03c 1/52, 1/62, 1/76

U.S. Cl. 96—91

4 Claims

A photosensitive material which consists of a support which is electrically non-conductive at least at its surface with a photosensitive layer, the active compound of which consists of an aromatic diazothioether of the type



in which Formula X is one or more substituents, preferably 4-nitro or 3,5-dichloro - 4 - dimethylamino, and in which Formula R is a branched or non-branched alkyl group or aralkyl group.

3,578,458

IONICALLY CROSS-LINKED PHOTOPOLYMERIZED ADDITION POLYMERS

Lloyd D. Taylor, Everett, Mass., assignor to Polaroid Corporation, Cambridge, Mass.
No Drawing. Filed Oct. 5, 1966, Ser. No. 584,353

Int. Cl. G03c 1/68

U.S. Cl. 96—115

1 Claim

Unsaturated monomers containing ionic sites are photopolymerized and, further, ionically cross-linked through these sites. Examples of unsaturated monomers containing ionic sites are zwitterions.

3,578,459

FOOD PRODUCT

James E. Corbin, Webster Groves, Mo., assignor to The Ralston Purina Company, St. Louis, Mo.
No Drawing. Filed July 18, 1968, Ser. No. 745,682

Int. Cl. A23l 1/10

U.S. Cl. 99—1

16 Claims

The method of producing a novel food product comprising coating the surfaces of a substantially dry food

product with an edible, chemically reactive composition which, when contacted with an aqueous liquid, forms an exothermic reaction, thereby producing a resulting heated food product.

3,578,460

PROCESS FOR THE PREPARATION OF PROTEINACEOUS MATERIALS

Lloyd E. Weeks, Creve Coeur, and Bernard S. Wildi, Kirkwood, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Dec. 12, 1968, Ser. No. 783,391

Int. Cl. A23j 3/00

U.S. Cl. 99—7

8 Claims

An edible proteinaceous material having nutritional value is prepared by digesting non-edible protein materials from domestic animals, for example, feathers, in a liquid medium comprising water, keratinase and a reductive-type disulfide splitting agent. Reductive-type disulfide splitting agents are exemplified by mercaptoethanol and sodium sulfite. The procedure is typically carried out at a temperature in the range of from about 10° to about 70° C. The proteinaceous material is useful in animal feed compositions.

3,578,461

PROCESS FOR THE PREPARATION OF PROTEINACEOUS MATERIALS

Lloyd E. Weeks, Creve Coeur, and Bernard S. Wildi, Kirkwood, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Dec. 12, 1968, Ser. No. 783,408

Int. Cl. A23j 3/00

U.S. Cl. 99—7

12 Claims

An edible proteinaceous material having nutritional value is prepared by digesting non-edible protein materials from domestic animals, for example, feathers, in a liquid medium comprising water and an enzyme selected from the group consisting of alkaline protease, neutral protease and mixtures of said enzymes. Optionally a reductive-type disulfide splitting agent as exemplified by mercaptoethanol may be included. The procedure is typically carried out at a temperature in the range of from about 10° to about 70° C. The proteinaceous material is useful in animal feed compositions.

3,578,462

YEAST LEAVENED BREAD DOUGH COMPOSITION AND PROCESS OF MANUFACTURE

Louis J. Smerak, Wayne, and Jason A. Miller, Dover, N.J., assignors to Caravan Products Co., Inc., Passaic, N.J.

No Drawing. Continuation-in-part of application Ser. No. 566,212, July 19, 1966. This application Dec. 2, 1969, Ser. No. 881,609

The portion of the term of the patent subsequent to Feb. 10, 1987, has been disclaimed
Int. Cl. A21d 2/02, 2/04, 8/04

U.S. Cl. 99—90

26 Claims

A yeast leavened bread dough containing a composition consisting essentially of about 0.0005 to 0.010 part by weight per 100 parts of flour employed in the dough of an oxidizing agent, about 0.03 to 1.0 part by weight of calcium salt per 100 parts flour employed in the dough, and catalytically active quantities of enzyme selected from the class consisting of fungal amylase and fungal protease, wherein the fungal alpha amylase enzyme is sufficient to provide between 3,000 and 150,000 SKB units for 100 pounds of flour employed in the dough and the fungal protease enzyme is sufficient to provide between 3,000 and 500,000 hemoglobin units for 100 pounds of flour employed in the dough.

3,578,463

MICROWAVE BLANCHING

Franklin J. Smith, Diablo, and L. G. Williams, Martinez, Calif., assignors to Cryodry Corporation, San Ramon, Calif.

Filed Mar. 8, 1967, Ser. No. 621,645

Int. Cl. A23b 7/06; A23l 3/18

U.S. Cl. 99—103

4 Claims

Treating vegetables by successively hot water blanching with water above 185° F. or atmospheric steam, finish blanching with the application of microwave energy to the point of enzyme deactivation and finish blanching with hot water above 185° F. Optionally, a final quench in cold water may be used.

3,578,464

METHOD OF RIPENING FRUIT

Christos C. Mpelkas, Lynn, Mass., assignor to Sylvania Electric Products Inc.

Filed May 18, 1967, Ser. No. 639,459

Int. Cl. A23l 1/00

U.S. Cl. 99—103

4 Claims

Ripening fruit that is detached from the vine unripened by exposing the fruit intermittently to periods of several hours of light being followed by several hours of darkness, the light being confined substantially to the blue, red and far red regions of the spectrum and maintaining the temperature lower during the dark period than during the light period.

3,578,465

FLAVOURING COMPOSITIONS

Antonie Simon Maria van der Zijden, deceased, late of Duiven, Netherlands, by Regina Christina Maria van der Zijden-Willemsse, legal representative of the heirs, Duiven, Netherlands, assignor to Lever Brothers Company, New York, N.Y.

No Drawing. Filed May 22, 1968, Ser. No. 731,338
Claims priority, application Netherlands, May 25, 1967, 6707232

Int. Cl. A23l 1/22

U.S. Cl. 99—140

21 Claims

An artificial flavouring composition comprising pyrrolidone carboxylic acid or a precursor thereof such as glutamine and succinic acid. The weight ratio of the acids, calculated as the free acid, is pyrrolidone carboxylic acid 1 part to succinic acid 0.01 up to 5 parts. The compositions can also include glutamic acid and then the weight ratio, of pyrrolidone carboxylic acid to glutamic acid is 1 to 0.02 up to 50 parts, and may also include a 5'-ribonucleotide, the weight ratio of pyrrolidone carboxylic acid to 5'-ribonucleotide being 1 to 0.01 up to 10 parts.

3,578,466

PICKLED VEGETABLE PRODUCT AND PROCESS OF PREPARATION

Frederick Hugo Luckmann, Westfield, and Daniel Melnick, Teaneck, N.J., assignors to CPC International Inc.
No Drawing. Filed May 21, 1968, Ser. No. 730,953

Int. Cl. A23b 7/10

U.S. Cl. 99—156

5 Claims

The present invention relates to enhancing on aging the flavor, color, and texture of pickled vegetables by the addition of an edible alkylenediaminetetracarboxylic acid component in minor proportions. The alkylenediaminetetracarboxylic acid component is added either in a brine solution in which the vegetables to be pickled are treated, or in the pickling syrup solution during the manufacture of vegetable pickles. The alkylenediaminetetracarboxylic acid component is present in amounts ranging from 0.004% to 0.04%. There is a synergistic reaction between the alkylenediaminetetracarboxylic acid component and calcium chloride, the latter in 0.04 to 0.1% concentration, in providing aged products of improved crispness.

3,578,467
VARIABLE VOLUME COFFEE CONTAINER
 Richard R. Huber, 853 Rincon Lane,
 Palos Verdes Estates, Calif. 94306
 Filed Sept. 5, 1968, Ser. No. 757,596
 Int. Cl. B65b 25/00

U.S. Cl. 99—182

3 Claims




A coffee container apparatus including an open top can which receives a plunger type cover that closely fits the wall of the can and is insertable downwardly thereinto to force the air there out of to come to rest on the top of the coffee and hermetically seal air from contact therewith whereby the coffee aroma will be maintained. The cover may include an upwardly and outwardly flared, resilient, peripheral lip which deforms to conform to the can wall configuration for assuring positive hermetic sealing.

3,578,468
SOLUTION FOR DEPOSITING AN ELECTROLESS COBALT ALLOY
 Fred Pearlstein and Robert F. Weighman, Philadelphia, Pa., assignors to the United States of America as represented by the Secretary of the Army
 Filed Mar. 1, 1968, Ser. No. 709,620
 Int. Cl. C23c 3/02

U.S. Cl. 106—1

6 Claims



Additions to an electroless cobalt solution of sodium tungstate, potassium perrhenate, nickel sulfate or phenylthiourea yielded electroless cobalt alloy deposits having a variety of improved magnetic properties.

3,578,469
REMOVAL OF FERROUS SULFATE FROM NICKEL BATHS
 Richard N. Hudd, Wheaton, and Heinz Seller, Cicero, Ill., assignors to Eagle-Picher Industries, Inc., Cincinnati, Ohio
 No Drawing. Filed Mar. 24, 1969, Ser. No. 810,012
 Int. Cl. C23c 3/02

U.S. Cl. 106—1

8 Claims

Process for the removal of ferrous sulfate from nickel plating solutions which involves adding hydrogen peroxide to the solution and adjusting the pH to a value of

about 3.1 to 3.3 to thereby precipitate ferric sulfate in a form which can be readily removed from the remainder of the solution by filtration.

3,578,470
BaO-Al₂O₃-SiO₂ GLASS-CERAMIC MATERIALS
 Dov Bahat, 77 E. 1st St., Corning, N.Y. 14830, and
 Gordon P. K. Chu, 1 Overbrook Road, Painted Post, N.Y. 14870

Filed Nov. 12, 1968, Ser. No. 774,687
 Int. Cl. C03c 3/22

U.S. Cl. 106—39

2 Claims

This invention relates to the production of glass-ceramic materials in the composition field BaO-Al₂O₃-SiO₂ nucleated with Ta₂O₅ and/or Nb₂O₅ which are especially suitable for sealing to tungsten and/or molybdenum metal and their alloys.

3,578,471
THERMAL SHOCK RESISTANT CERAMIC MATERIAL

Irwin M. Lachman, Corning, N.Y., assignor to
 Corning Glass Works, Corning, N.Y.

Continuation-in-part of application Ser. No. 668,067,
 Sept. 15, 1967. This application Nov. 10, 1969, Ser.
 No. 875,174

Int. Cl. C04b 35/00, 35/44

U.S. Cl. 106—39

12 Claims

Ceramic bodies composed of a plurality of phases having markedly different coefficients of thermal expansion. The ceramic bodies are characterized by grain boundary and intracrystalline cracking. The ceramics have compositions analytically defined by and selected from the groups consisting of: (1) first compositions in the area and along the boundaries defined by the letters A, B, C, D, E, F, G, M, N in FIG. 1 of the drawing; (2) second compositions in the area and along the boundaries defined by the letters A', B', C', D', E', F', G', M', N' in FIG. 2 of the drawing, and (3) mixtures of said first and second compositions.

3,578,472
CARBONACEOUS BONDING SYSTEM FOR REFRACTORIES
 George R. Henry, Bethel Park, and Ernest P. Weaver, Pittsburgh, Pa., assignors to Dresser Industries, Inc., Dallas, Tex.
 No Drawing. Filed Nov. 3, 1967, Ser. No. 680,320
 Int. Cl. C04b 35/02, 35/52

U.S. Cl. 106—56

9 Claims

Carbonaceous bonding system for refractories, especially basic refractories, of increased storage life, which system does not normally require heating for use. Said system being mainly comprised of unsaturated fatty acid pitch plus an effective amount of that portion of pitches generally referred to as asphaltenes.

3,578,473
BASIC FUSED REFRACTORY WITH RARE EARTH OXIDE
 Allen M. Alper and Robert N. McNally, Corning, N.Y., assignors to Corhart Refractories Company, Louisville, Ky.
 No Drawing. Filed May 17, 1968, Ser. No. 729,894
 Int. Cl. C04b 35/40

U.S. Cl. 106—58

5 Claims

Basic fused refractory material analytically composed of, by weight, at least 70% MgO, 1 to 25% rare earth oxide, 0 to 20% FeO, 0 to less than 15% of TiO₂, ZrO₂, Cr₂O₃ and mixtures thereof, 0 to less than 10% of SiO₂, Al₂O₃, B₂O₃, fluorine and mixtures thereof, 0 to 3.5%

P₂O₅, and 0 to 3% ThO₂. Material can be in form of either fused cast articles or fused grain or rebonded fused grain article.

3,578,474
FUSED REBONDED BASIC BRICK
 Dwight S. Whittemore, Bethel Park, Pa., assignor to
 Dresser Industries, Inc., Dallas, Tex.
 No Drawing. Filed Oct. 3, 1967, Ser. No. 672,455
 Int. Cl. C04b 35/42

U.S. Cl. 106—59

7 Claims

Ceramically bonded basic brick made from a batch comprising at least two chemically different fused magnesite-chrome ore grains being in different size fractions of the batch.

3,578,475
CATIONIC CEREAL FLOURS AND A METHOD FOR THEIR PREPARATION
 Richard J. Alexander, Wauwatosa, and Robert G. Cumisford, Brookfield, Wis., assignors to Krause Milling Company, Milwaukee, Wis.
 No Drawing. Filed Dec. 9, 1968, Ser. No. 782,438
 Int. Cl. C13l 1/08

U.S. Cl. 106—150

6 Claims

A series of novel cationic cereal flours are described in which the protein portion of the flour is modified by certain tertiary amines or quaternary ammonium salts.

3,578,476
DYESTUFFS FOR ORNAMENTAL COATINGS OR THE LIKE
 Robert J. Perkel, R.D. 3, Lamington Road, Branchburg Township, Somerset County, N.J. 07826
 No Drawing. Filed Apr. 3, 1969, Ser. No. 813,282
 Int. Cl. C08h 17/02

U.S. Cl. 106—193

10 Claims

The specification describes a dyestuff useful for ornamental coatings. The dyestuff is produced by reacting an organic titanate with a phenolic substance, conveniently a phenolic resin. The product is soluble in most organic finishes and produces a metallic gold finish on neutral-colored metal surfaces.

3,578,477
PAPER SIZING COMPOSITION COMPRISING A CATIONIC WAX EMULSION, AN ANIONIC ROSIN AND AN ACID AMINE CONTAINING EMULSIFYING AGENT
 Donald R. Cushman, Wenonah, N.J., assignor to
 Mobil Oil Corporation
 No Drawing. Filed July 17, 1969, Ser. No. 842,724
 Int. Cl. C08h 9/10

U.S. Cl. 106—230

16 Claims

A paper sizing composition is provided comprising a mixture of an aqueous cationic wax emulsion and an anionic rosin size.

3,578,478
SLIP CASTING OF TUNGSTEN
 Craig T. Waldo, Towanda, Pa., assignor to
 Sylvania Electric Products Inc.
 No Drawing. Filed Sept. 16, 1968, Ser. No. 762,327
 Int. Cl. C08h 17/24; B22f 3/22

U.S. Cl. 106—286

6 Claims

An improved method of making a tungsten slip casting slurry is disclosed. The slurry may contain only water as the suspending agent due to the controlled density and size of the tungsten powder.

3,578,479
METHOD OF SEALING LEAKS IN VESSELS AND JOINTS
 Joseph J. Packo, 3043 N. Federal Highway,
 Fort Lauderdale, Fla. 33306
 No Drawing. Filed Oct. 29, 1968, Ser. No. 771,622
 Int. Cl. B23p 7/00

U.S. Cl. 117—2


11 Claims

The invention relates to a method for sealing leaks in pipes, conduits, gas lines, closed containers, tanks and the like. The interior of such equipment is first purged with a non-reactive dry gas, such as nitrogen, to remove any moisture and/or oxygen which may be present. Then a selected sealant agent is introduced into the interior of the equipment in a suitable inert gas vehicle under pressure. The sealant and gas mixture will escape from any leaks present in the equipment into the outer ambient atmosphere. The sealant reacts with oxygen and/or moisture to form in the situs of the leak a solid reaction product which may be a metal oxide compound. The sealant agents used are normally gaseous or volatile metal hydrides, metal alkyls, metal alkyl halides, and metal alkyl hydrides. Examples of these sealant agents are silicon hydrides, alkyl aluminum halides, zinc alkyls such as diethyl zinc. The sealants are supplied to the interior of the apparatus or vessel which may contain leaks in sufficient concentration and suitable pressure so that upon escape from the leaks a solid seal will form in situ.

3,578,480
METHODS OF ORNAMENTING PLIABLE SHEET MATERIAL
 Sydney A. Vinter, Leicester, England, assignor to USM Corporation, Fleming, N.J.
 Filed Oct. 1, 1968, Ser. No. 764,089
 Claims priority, application Great Britain, Oct. 5, 1967, 45,336/67
 Int. Cl. B44d 1/52, 5/00

U.S. Cl. 117—4

3 Claims



In ornamenting pliable sheet material, a surface area thereof is provided with a layer of masking material and subjected to pressure from a cutting die to sever the layer and indent the sheet material along lines defining area portions to be colored. The masking layer is removed from the area portions which are then spray coated, and thereafter the remaining masking layer is removed. The materials adjacent the edge of the cutting die are heated during pressure thereof to promote severance of the layer and the fixation of the embossment so that the area portions are sharply defined and stand out handsomely. The

heating is effected by emanations from the die, suitably in the form of a heat flux or an RF field but preferably both.

3,578,481

SUEDE-LIKE SHEET MATERIAL OF STYRENE/BUTADIENE POLYMER CONTAINING AN ADDITIVE

Charles A. Young, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Filed June 18, 1968, Ser. No. 737,824
Int. Cl. B44f 9/00, 9/12


U.S. Cl. 117—8 11 Claims
An improved supple, synthetic, microporous vapor permeable suede-like sheet material of a non-woven synthetic flexible fibrous web that is impregnated with a polymeric binder of styrene and butadiene and the polymeric binder contains about 0.1–10 parts of a silicone oil additive per 100 parts of polymeric.

3,578,482

METHOD OF COATING A SUBSTRATE WITH CAPSULES

John G. Whitaker, Englewood, and Victor A. Crainich, Jr., Dayton, Ohio, assignors to The National Cash Register Company, Dayton, Ohio
Filed May 5, 1969, Ser. No. 821,737
Int. Cl. B05c 1/16; B44d 1/14

U.S. Cl. 117—38 14 Claims



A process in which a dispersion containing an inert liquid vehicle, for example, water, a binder such as polyvinyl alcohol and a profusion of capsules having elastic, readily distorted walls containing liquid internal core material such as an odoriferous substance are coated through a screen onto a substrate by the application of pressure to the capsular dispersion. The capsule walls are subsequently hardened. The walls may then be ruptured by the application of pressure to the capsules to release the internal core material.

3,578,483

PROCESS FOR IMPROVING THE PRINTABILITY OF THE SURFACE OF α -CELLULOSE PAPER TO BE USED AS THE DECORATIVE SHEET IN A DECORATIVE LAMINATE

Leonardo Medrano Garcia, Lawrence, Mass., assignor to Formica Corporation, Cincinnati, Ohio
No Drawing. Filed May 14, 1969, Ser. No. 824,689
Int. Cl. B44d 5/02, 5/03

U.S. Cl. 117—38 5 Claims
A process for improving the printability of α -cellulose paper which is to be used as the decorative sheet in a decorative laminate comprising placing thereon a discontinuous coating from an organic solvent solution of a mixture of certain acrylic copolymers with an inorganic pigment.

3,578,484

SURFACE PREPARATION AND ELECTROSTATIC SPRAY COATING OF PLASTIC ARTICLE

Wilhelm E. Walles and Arnett L. Bird, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Continuation-in-part of application Ser. No. 732,871, May 29, 1968. This application Feb. 13, 1969, Ser. No. 799,078

Int. Cl. B05b 5/02; B44d 1/092
U.S. Cl. 117—47 12 Claims
Process for the spray coating of plastic articles wherein the articles are surface sulfonated before they are electrostatic spray coated. The articles can be neutralized after sulfonation if desired. A degree of sulfonation of at least about 0.001 milligram sulfur trioxide or equivalents thereof per square centimeter of plastic surface is required to give the desired uniform coating and good adhesion. The sprayed coatings can be liquid paints or lacquers, powdered plastics and liquid coatings containing filamentary reinforcing agents which are normally cured by drying, heating and drying, or heating.

3,578,485

METHOD OF PRODUCING A COATED PAPER

Saburo Imoto, Sakazu Kurashiki-shi, Kyoichiro Ikari, Yasue Kurashiki-shi, and Tatsuki Hattori, Sakazu Kurashiki-shi, Japan, assignors to Kuraray Co., Ltd., Sakazu, Kurashiki-shi, Japan

No Drawing. Filed July 26, 1968, Ser. No. 747,797
Claims priority, application Japan, Aug. 3, 1967, 42/50,241

Int. Cl. B44d 1/44 10 Claims
U.S. Cl. 117—62
A process for producing a coated, paper, having improved water-resistance and superior printability characterized by treating the coated surface of a paper coated with a color composition containing as the principal constituent a pigment and a polyvinyl alcohol with a solution containing a boric compound having an electron accepting structure selected from the group consisting of boric acid and boric salts, a water-soluble amino compound having one or more of primary, secondary, tertiary or quaternary amino groups in its molecule, an electron donating structure and a boiling point in excess of about 100° C., and a surface active agent which reduces the surface tension of the treating solution.


3,578,486

ELECTROSTATIC COATING MATERIAL RECOVERY DEVICE

Joseph E. Fenton, Grimsby, Ontario, Canada, assignor to H. G. Fischer & Co.

Filed Oct. 9, 1967, Ser. No. 673,750

Int. Cl. B05b 5/02 13 Claims
U.S. Cl. 117—93.41



In electrostatic spray coating systems a barrier of electrical conductive aperture material is placed beyond the

work to be coated to recover overspray. The barrier is either connected to the work to be coated so that it remains at the same potential or an auxiliary power supply is provided to increase the potential difference between a charging electrode and the barrier over the potential difference between the electrode and work being coated.

3,578,487

METHOD FOR RENDERING SUBSTRATES SOIL REPELLENT

Martin Knell, Ossining, and Eduard Karl Kleiner, Dobbs Ferry, N.Y., assignors to Gelgy Chemical Corporation, Ardsley, N.Y.

No Drawing. Filed July 1, 1968, Ser. No. 741,298

Int. Cl. D06m 15/36; B44d 1/02 6 Claims
U.S. Cl. 117—121
Substrates, particularly textiles, are rendered soil, oil, and water repellent by the application thereto of compositions comprising polymers of N-(perfluoroalkanoylethyl) aminoethyl acrylate or N-(perfluoroalkanoylethyl)-N-lower alkyl-aminoethyl acrylates.


3,578,488

METHOD FOR RENDERING SUBSTRATES WATER REPELLENT

Howard Gary Ohlhausen, 82 Graymoor Lane, Olympia Fields, Ill. 60461

No Drawing. Filed June 21, 1968, Ser. No. 738,787

Int. Cl. C09d 3/48 16 Claims
U.S. Cl. 117—123
A method for rendering substrates water repellent by treating the same with a composition containing a poly alkyl vinyl ether/maleic anhydride having the following formula:



wherein R is an alkyl radical having sufficient number of carbon atoms to render the polymer water insoluble, and n is an integer greater than 1. The polymer is preferably present in the composition in an amount 0.5–40% by weight. Other water repellent compounds or additives are advantageously included in the composition.


3,578,489

RESIN COATED FILAMENTARY MATERIAL

Leonard L. Gelb, Cumberland, Md., assignor to Hercules Incorporated, Wilmington, Del.

Filed Nov. 13, 1968, Ser. No. 775,254

Int. Cl. B44d 1/42; H01b 3/36; B32b 27/12 16 Claims
U.S. Cl. 117—128.4



The invention provides (1) boron filament coated with a phenolic-polyvinyl acetal resin as a medium for bonding the filament to an epoxy type matrix material, (2) process for manufacture of the above coated boron filaments involving contact of bare boron filaments with a solution of said resins to wet the filament, regulating thickness of the resulting solution layer to provide the residual resin coating sought, removing solvent from the wetting layer, and partially curing residual solid resin as the resin coating, (3) broad goods comprising mat

product of filamentary winding of the above described resin coated boron filaments, (4) method for forming a specific coating solution for the bare filaments, involving forming a separate solution of each of the resins in predetermined resin proportions and concentrations, and then admixing the two separate solutions to form the product solution and (5) resulting coating solution of 5–20 weight percent total resin content, in a phenolic resin to polyvinyl acetal resin weight ratio of from about 0.25:1 to 18:1.

3,578,490

MOLDED ARTICLES AND COATINGS BASED ON ORGANOPOLYSILOXANES

Ignaz Bauer, Rudolf Riedle, and Siegfried Nitzsche, Burg-hausen, Upper Bavaria, Germany, assignors to Wacker-Chemie G.m.b.H., Munich, Bavaria, Germany

No Drawing. Filed Feb. 7, 1968, Ser. No. 703,549
Claims priority, application Germany, Nov. 15, 1967, W 45,165

Int. Cl. B32b 27/28, 27/06 4 Claims
U.S. Cl. 117—138.8
Molded articles and coatings prepared from organo-polysiloxanes having olefinically unsaturated organic substituents bonded to silicon are coated with organosilicon compounds having SiN groups thereby reducing or eliminating the surface tackiness heretofore encountered.

3,578,491

WOOL-POLYESTER TEXTILE ARTICLES HAVING A POLYMERIC FINISH

James W. Dowd, Robert D. Jacobs, and Harry L. Mercer, Cheraw, S.C., assignors to J. P. Stevens & Co., Inc., New York, N.Y.

No Drawing. Filed May 23, 1968, Ser. No. 731,612
Int. Cl. B32b 27/36; D06m 13/02, 3/02

U.S. Cl. 117—138.8 1 Claim
This invention relates to woolen textile articles containing synthetic yarns, impregnated with a polymeric composition comprising
(1) a copolymer of vinyl acetate (40 to 60% by weight) and an ethylenically unsaturated acid (60 to 40% by weight) and
(2) an alkyd resin
and having substantially improved wash-wear properties.

3,578,492

SIZED TWISTLESS YARNS

Edgar D. Bolinger, 113 Lanford Road, Spartanburg, S.C. 29301

Application Nov. 23, 1966, Ser. No. 596,657, now Patent No. 3,512,232, dated May 19, 1970, which is a continuation of application Ser. No. 250,320, Jan. 9, 1963. Divided and this application June 13, 1969, Ser. No. 832,953

Int. Cl. D02j 3/18 5 Claims
U.S. Cl. 117—139.5
A twistless yarn containing at least some fibers having interlocking characteristics is described. The yarn is sized with a sizing agent comprising a frictioning agent, a binding agent and, optionally, an insolubilizing agent. An example of a frictioning agent is colloidal silica.

3,578,493


HIGH SOLIDS COATING COMPOSITION

Johanna Wilhelmina v.O. Smith, Cape Elizabeth, Maine, assignor to The Scott Paper Company, Delaware County, Pa.

Filed May 29, 1968, Ser. No. 733,173

Int. Cl. D21h 1/28 3 Claims
U.S. Cl. 117—155
Disclosed is an aqueous paper coating composition having a solids content of at least 70 percent by weight with

said solids being comprised of a coarse ground substantially spherical pigment, a finely divided pigment and coating binder; said coarse ground pigment comprising from 25 to 90 percent of the total pigment content with



the finely divided pigment comprising the remainder of the pigment composition. Also disclosed is a process for applying the new paper coating composition and a glossy coated paper product.

3,578,494

ZINC PLATING BY CHEMICAL REDUCTION
Billy J. Williams and Charles M. Starks, Ponca City, Okla., assignors to Continental Oil Company, Ponca City, Okla.

No Drawing. Filed Apr. 9, 1969, Ser. No. 814,797
Int. Cl. C23c 17/02


U.S. Cl. 117—160 7 Claims
Thin films of zinc can be plated onto substrates at ambient temperatures by first coating the substrate with an organo zinc compound and then contacting the wetted substrate with an aluminum compound having at least one hydrogen bonded directly to the aluminum. The aluminum hydride serves to reduce the zinc compound, and good adhesive thin films of zinc on the substrate are formed.

3,578,495

METHOD OF PRECIPITATING INSULATING PROTECTIVE LAYERS COMPRISED OF INORGANIC MATERIAL UPON THE SURFACES OF SEMICONDUCTOR WAFERS

Erich Pammer, Munich, and Helmuth Kirschner, Unterhaching, Germany, assignors to Siemens Aktiengesellschaft, Berlin and Munich, Germany
Filed Jan. 13, 1969, Ser. No. 790,725
Claims priority, application Germany, Jan. 15, 1968, S 113,723

Int. Cl. H01l 7/36
U.S. Cl. 117—201 9 Claims



Described is a method of precipitating insulating protective layers of inorganic material at the surface of heated semiconductor wafers from a reaction gas which precipitates the material. The wafers are heated by the reaction chamber wall, comprised of highly pure quartz or similar material. The method is characterized in that the reaction gas which is introduced into the reaction chamber fresh and having a temperature of at least 100° C. below the semiconductor wafers to be coated, is directed by at least one impediment positioned along its path toward the semi-


conductor wafers to be coated, radially toward the wall of the reaction chamber which has a temperature of at most 50° C. below the temperature of the semiconductor wafers to be coated and then passes quickly to the semiconductor wafers which are located at a distance behind said impediment, that in spite of the now high temperatures of the reaction gas, precipitation takes place only at the location of the semiconductor wafers.

3,578,496

METHOD OF IMPROVING THE SUPERCONDUCTIVITY OF NIOBIUM-TIN LAYERS PRECIPITATED ON A CARRIER
Günther Ziegler, Erlangen, and Barbara Wirth, Altenfurt, near Nuremberg, Germany, assignors to Siemens Aktiengesellschaft, Munich and Berlin, Germany

Filed Mar. 28, 1968, Ser. No. 716,948
Claims priority, application Germany, Mar. 30, 1967, S 109,081

Int. Cl. C23c 11/02; H01v 11/00
U.S. Cl. 117—227 6 Claims



Described is a method of improving the superconductive properties of layers of the intermetallic compound niobium-tin (Nb_3Sn) which are precipitated on a heated carrier by hydrogen reduction of halides of the elements niobium and tin. The method is characterized in that the coated carrier is subjected to a heat processing, under protective gas, which lowers the hydrogen content of the niobium-tin layer.

3,578,497

POTATO STARCH PROPERTIES BY CONTROLLED HEATING IN AQUEOUS SUSPENSION

Erling T. Hjermstad, Cedar Rapids, Iowa, assignor to Penick & Ford, Limited, Cedar Rapids, Iowa
No Drawing. Filed May 19, 1969, Ser. No. 826,026

Int. Cl. C13l 1/08
U.S. Cl. 127—32 6 Claims
Improved paste and gel properties and a higher swelling temperature are imparted to potato starch by heating an aqueous suspension of potato starch at temperatures which are at least initially below the natural gelatinization temperature of the starch, but always below the higher gelatinization temperature attained by the starch due to said heating.

3,578,498

DESOLVENTIZING OF STARCH
Francis E. Kite, Riverside, and Joseph F. Stejskal, Brookfield, Ill., assignors to CPC International Inc., New York, N.Y.

No Drawing. Filed June 12, 1967, Ser. No. 645,528
Int. Cl. C13l 1/08, 1/00, 1/04

U.S. Cl. 127—71 12 Claims
Starch which has been treated with a hydrophilic organic solvent such as a low molecular weight alcohol, ketone, or the like, and which, as a result, retains relatively large quantities of the solvent, is desolventized by contacting it with a hot humid gas, such as, for example, steam or moist air, while maintaining the starch at a temperature of from about 160° F. to about 320° F. and at a moisture level of from about 1% to about 15%. The process is applicable to any type or variety of

starch, in either non-gelatinized or pregelatinized form; the process does not alter or otherwise affect the properties of the starch.

3,578,499

GELLING COMPOSITION FOR GENERAL PURPOSE CLEANING AND SANITIZING

Homer E. Crotty and Charles R. Coffey, Cincinnati, and Thomas C. Tesdahl, Forest Park, Ohio, assignors to W. R. Grace & Co., New York, N.Y.
No Drawing. Filed Aug. 2, 1968, Ser. No. 749,585

Int. Cl. B08b 7/00; C11d 3/48
U.S. Cl. 134—4 6 Claims

The disclosed invention includes a powder gelling composition containing a gelling agent, a neutral diluent, a wetting agent, and desirably a dye or coloring additive. The powder gelling composition when added to water forms a gel. To this gel may be added acid or alkaline materials for cleaning, biocidal agents for sanitizing, or other materials to produce a desired effect. The significant advantage of this method is the increased residence time and hence contact time between agents in the gel and the surface to be acted on.

3,578,500

NONAQUEOUS ELECTRO-CHEMICAL CURRENT PRODUCING CELL HAVING SOLUBLE CATHODE DEPOLARIZER

Donald Leonard Maricle, Ridgefield, and Arthur Kentaro Hoffmann, New Canaan, Conn., assignors to American Cyanamid Company, Stamford, Conn.
No Drawing. Filed July 8, 1968, Ser. No. 743,005


Int. Cl. H01m 17/00
U.S. Cl. 136—6 9 Claims

A primary and secondary electrochemical cell which comprises in combination an anode of a metal capable of reducing a cathode depolarizer, sulfur dioxide alone or in a co-solvent, an electrolyte salt, and soluble depolarizers.

3,578,501

FUEL CELL SYSTEM AND METHOD USING LITHIUM AND LITHIUM HYPOCHLORITE TO PRODUCE HYDROGEN AND OXYGEN
Sammy C. Honeycutt, Gastonia, N.C., assignor to Lithium Corporation of America, New York, N.Y.

Filed Nov. 13, 1968, Ser. No. 775,455
Int. Cl. H01m 27/14
U.S. Cl. 136—86 9 Claims



Regenerative hydrogen-oxygen fuel cell system in which gaseous hydrogen and oxygen are separately generated and conveyed to a hydrogen-oxygen fuel cell associated with the system. Hydrogen is generated by the action of water on lithium metal. Oxygen is generated by heating an aqueous solution containing lithium hypochlorite. The system is regenerated by converting the lithium chloride, resulting from the thermal decomposition of lithium hypochlorite, to lithium metal, and by converting the lithium hydroxide monohydrate, obtained from the action of water on the lithium metal, to lithium hypochlorite.

3,578,502

STABILIZED ZIRCONIUM OXIDE ELECTRODE FOR SOLID ELECTROLYTE FUEL CELL

Helmut Tannenberger, Geneva, and Paul Kovacs, Carouge, Geneva, Switzerland, assignors to Compagnie Francaise de Raffinage, Paris, France

Filed July 18, 1968, Ser. No. 760,394
Claims priority, application Switzerland, July 19, 1967, 10,254/67

Int. Cl. H01m 27/04, 27/16
U.S. Cl. 136—120 8 Claims

An electrode has been provided for a solid electrolyte containing fuel cell suitable for high temperature operations, comprising a first porous layer and a second porous layer, said first porous layer comprising at least one layer of granules of a ceramic material capable of conducting oxygen ions and electrons generated in said fuel cell, said granules being in contact with the electrolyte with at least a part of surfaces of said granules, at least a part of other surfaces of said granules being in contact with a material possessing good electron conductivity, said material being in turn in contact with a second porous layer, said second porous layer being a good conductor of electrons and in an electrical contact with said granules, said layers constituting an electrode which in the cell allows the ready access to said granules of fuel or comburant gas.


3,578,503

DEVICES FOR THE ELECTROCHEMICAL GENERATION OF ELECTRICAL CURRENT

Moshe R. Bloch, Chaim Forgacs, and Ronald V. Bobker, Beersheba, Israel, assignors to State of Israel represented by the Prime Minister's Office, Jerusalem, and Dead Sea Works Ltd., Beer Sheva, Israel

Filed Sept. 19, 1967, Ser. No. 668,783
Claims priority, application Israel, Aug. 11, 1967, 28,488

Int. Cl. H01m 17/00
U.S. Cl. 136—102 7 Claims



A fuel cell comprising a cathode system and an anode system disposed in a chamber and separated by a permselective membrane. A liquid catholyte is continuously introduced into and circulated through the catholyte compartment, and an anolyte is continuously introduced into and circulated through the anolyte compartment. The anode system preferably includes a slurry of zinc particles dispersed in a zinc-bromide solution (the anolyte), and the cathode preferably includes a carbon electrode, bromine, and a zinc-bromide solution (the catholyte).

3,578,504

METHOD OF ACTIVATING A SILVER OXIDE-ZINC PRIMARY CELL

Robert P. Hamlen, Scotia, and Elihu C. Jerabek, Delmar, N.Y., assignors to General Electric Company

Filed July 1, 1969, Ser. No. 838,066
Int. Cl. H01m 17/00

U.S. Cl. 136—102 2 Claims
A silver oxide-zinc primary cell is disclosed which comprises a casing, a zinc anode positioned in the casing, a

separator on each side of the anode, a silver oxide cathode on each side of the anode adjacent each separator and spaced from the anode, and magnesium oxide powder contained within the cell. A method is disclosed for activating such a cell which does not contain the magnesium oxide powder which comprises mixing together 5 to 40 weight percent of magnesium oxide powder in an aqueous alkaline electrolyte thereby forming a pourable electrolytic solution, filling the assembled cell with the electrolytic solution, and allowing the viscosity of the solution to increase prior to discharging the cell. A method is also disclosed for forming such a cell wherein magnesium oxide powder is added to the cell during assembly, and the assembled cell is filled with an aqueous alkaline electrolyte prior to use. In both of these methods upon activation of the previously assembled cell, a high viscosity electrolytic solution results thereby preventing silver migration to the anode and other cell components.

3,578,505

PROCESS FOR PREPARING A FUEL CELL ELECTRODE

Edward S. Rogers, Hinsdale, Richard V. Hardin II, Harvey, Benjamin C. Harrison, Hazel Crest, and Robert A. Sanford, Homewood, Ill., assignors to Atlantic Richfield Company

No Drawing. Filed July 8, 1966, Ser. No. 563,685

Int. Cl. H01m 13/00

U.S. Cl. 136—120

6 Claims

A process whereby a catalytically-active metal may be applied to a porous substrate in the preparation of a fuel cell electrode wherein the catalytically-active metal is applied as an aqueous liquid and it is desired to exclude the catalytically-active metal from pores having radii smaller than a predetermined minimum. Particularly, the process comprises blocking the smaller pores with a water-immiscible liquid having a boiling point above that of water prior to the treating of the substrate whereby the blocking is accomplished by contacting the porous substrate with the water-immiscible liquid, and then evaporating the water-immiscible liquid from substrate pores having radii larger than the predetermined minimum. The evaporation is conducted so that the water-immiscible liquid remains in substrate pores having radii smaller than the predetermined minimum. Then an aqueous solution of the catalytically-active metal is applied to the porous substrate. Evaporation of the aqueous solution deposits the catalytically-active metal in the substrate pores having radii larger than the predetermined minimum. Often the porous substrate contains pores of inordinate size and in this case the porous substrate is first treated with an aqueous solution and the largest pores are evacuated. Then the porous substrate is treated with a water-immiscible liquid containing a polymerizable monomer polymerized in said larger pores and decreasing their size accordingly.

3,578,506

SEALING ARRANGEMENT FOR TERMINALS OF ELECTROCHEMICAL GENERATORS

René Chassoux, Talence, France, assignor to Société des Accumulateurs Fixes et de Traction (Société Anonyme), Romainville, France

Filed Apr. 7, 1969, Ser. No. 813,885

Claims priority, application France, May 30, 1968; 153,442


Int. Cl. H01m 1/02

U.S. Cl. 136—168

15 Claims

Sealed electrochemical generators and a sealing arrange-

ment for the terminals of electrochemical generators which project outwardly of a metallic cover which provides



effective sealing as well as electrical insulation of the terminals from the metallic cover.

3,578,507

METHOD OF PRODUCING NON-OPAQUE P-TYPE WIDE BAND GAP SEMICONDUCTOR MATERIALS

Kang-rong Chiang, Chicago, Zoltan K. Kun, Skokie, and Robert J. Robinson, Park Ridge, Ill., assignors to Zenith Radio Corporation, Chicago, Ill.

No Drawing. Filed Apr. 28, 1969, Ser. No. 819,962

Int. Cl. H01l 7/62

U.S. Cl. 148—1.5

10 Claims

To produce a non-opaque p-conductivity type wide band gap semiconductor material, a crystalline semiconductor material comprising a zinc chalcogenide is simultaneously doped with zinc atoms and with atoms of a Group V element in non-stoichiometric proportions, with an excess of the Group V atoms. Preferably, the starting material is a hybrid crystalline semiconductor material comprising II-VI compound and III-V compound constituents. P-type conductivity with specific resistivities of 1.0 ohm centimeter or less without opaque darkening is obtained with this process.

3,578,508

TREATMENT OF FERROUS METAL SURFACES TO PREVENT CORROSION

Martin B. Pearlman, New York, N.Y.

(78—05 141st St., Flushing, N.Y. 11367)

No Drawing. Filed Apr. 12, 1967, Ser. No. 630,187

Int. Cl. C23f 5/02

U.S. Cl. 148—6.14

6 Claims

Ferrous metal is corrosion-proofed with a solution obtained by treating chromite ore or other oxide with gallic acid. Other chelating agents may replace the gallic acid. The solutions can also be used for the deposition of oxides on inexpensive mineral material to form attrition-resistant supported catalysts.

3,578,509

CONDITIONING FERROUS METAL SUBSTRATES

Bert E. Palm, Mentor, and William Wayne Warner, Painesville, Ohio, assignors to Diamond Shamrock Corporation, Cleveland, Ohio

No Drawing. Filed May 17, 1968, Ser. No. 729,933

Int. Cl. C23f 7/10

U.S. Cl. 148—6.16

7 Claims

To prepare a ferrous metal surface for receiving a hexavalent-chromium-containing coating composition, the surface is first contacted with an aqueous solution having a pH of between about 2-6 and containing up to about 50 weight percent of ammonium dihydrogen phosphate and/or alkali metal dihydrogen phosphate. The resulting contacted surface is then rinsed and may be dried. The solution may also contain, for example, oxidizing ions and surface active agents. After this preparation and the establishment of the above-noted coating, substrates exhibit weldability and enhanced paint adhesion.

3,578,510

CONDITIONING FERROUS METAL SUBSTRATES

Bert E. Palm, Mentor, and William Wayne Warner, Painesville, Ohio, assignors to Diamond Shamrock Corporation, Cleveland, Ohio

No Drawing. Filed May 17, 1968, Ser. No. 729,931

Int. Cl. C23f 7/10, 7/26

U.S. Cl. 148—6.16

5 Claims

To prepare a ferrous metal surface for receiving a hexavalent-chromium-containing coating composition there is first established on the surface a partially autogenous, loose dry powder. This powder is formed by contacting the surface with an aqueous solution having a pH below about 2.6 and containing up to about 30 weight percent of an acid of phosphorous and usually 0.25-10 volume percent of surface active agent, and then drying the resulting contacted surface. The solution is typically more acid than a conversion coating solution and weaker in acid strength than a pickling bath. Resulting articles exhibit weldability and enhanced paint adhesion.

3,578,511

SOLID METAL MOLDING


Daniel L. Mehl, Lexington, Ky., Delbert T. Willson, Austin, Tex., and Richard J. Young, Lexington, Ky., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 13, 1968, Ser. No. 783,675

Int. Cl. C22f 1/16

U.S. Cl. 148—11.5

8 Claims



The superplastic eutectoid alloy of zinc and aluminum is deformed in a die having a temperature substantially in excess of the critical temperature limit for the alloy without detrimental effect. After forming, the temperature of the resulting part exceeds the critical limit and to thus enable the part to be handled without distortion. In addition, the part temperature after forming is sufficiently high to permit immediate heat treatment for room temperature structural property enhancement as part of the forming cycle simply by controlling the cooling rate of the part.

3,578,512

METHOD OF HEAT TREATMENT OF A STEEL PRODUCT

Shinnosuke Funakubo, Tokyo, Japan, assignor to Funakubo Seikyo Kabushiki Kaisha, Tokyo, Japan


Filed May 17, 1968, Ser. No. 730,120

Claims priority, application Japan, May 25, 1967, 42/32,789

Int. Cl. C21d 9/32

U.S. Cl. 148—147

6 Claims



A method of heat-treating and hardening a steel product such as a toothed wheel and similar structural ele-

ments, requiring a hardness and abrasion resistance on portions of its working surfaces increased in comparison to the hardness and abrasion resistance of the remaining portions comprising the steps of providing on the surface of said product at least one groove separating the said surfaces of portions of required increased hardness from the remaining surfaces; locally heat-treating the said portions of the surfaces requiring an increased hardness as they are divided by said at least one groove and subsequently hardening by quenching the heat-treated portions leaving the remaining portions with its original hardness and abrasion resistance.

3,578,513

METHOD OF FABRICATING SOLUTION GROWN EPITAXIAL PN-JUNCTIONS IN GALLIUM PHOSPHIDE


Manfred H. Pilkuhn, Braunschweig, Germany, and Max R. Lorenz, Mahopack, N.Y., assignors to the United States of America as represented by the Secretary of the Navy

Filed Sept. 22, 1967, Ser. No. 669,978

Int. Cl. H01l 7/46, 7/00

U.S. Cl. 148—171

7 Claims



The invention is a method of fabricating epitaxial grown p-n junctions from solution and comprises the steps of preparing a gallium phosphide crystal substrate, placing the crystal substrate in one end of a graphite boat, placing a gallium-saturated gallium phosphide solution in the other end of the graphite boat, adding a dopant to the solution, placing the graphite boat in a receptacle, passing a forming gas through the receptacle, heating the receptacle and the graphite boat to about 1140° C. in about 45 minutes, tipping the graphite boat so that the solution covers the substrate, cooling the receptacle and boat to about 700° C. in about 40 minutes and then to near room temperature from about 700° C. by shutting off the heating apparatus, separating the epitaxially overgrown substrate crystal from the mixture, cleaving the crystal at right angles to the overgrowth, etching the cleavage plane, lapping the substrate side of the crystal and alloying ohmic contacts simultaneously on the substrate side and the overgrowth of the crystal.

3,578,514

METHOD FOR MAKING PASSIVATED FIELD-EFFECT TRANSISTOR


Israel Arnold Lesk, Scottsdale, Ariz., assignor to Motorola, Inc., Franklin Park, Ill.

Continuation-in-part of abandoned application Ser. No. 368,212, May 18, 1964. This application July 9, 1967, Ser. No. 655,265

Int. Cl. H01l 7/36, 3/00; B01j

U.S. Cl. 148—175

5 Claims



A method of making a field effect transistor in a semiconductor wafer of one conductivity type semiconductor

material which includes initially forming an epitaxial layer of opposite conductivity type semiconductor material on the surface of the wafer to form a first gate PN junction. The epitaxial layer is then coated with a film of diffusion resistant material, and a portion of this film is removed to expose a selected area of the epitaxial layer. An impurity of one conductivity type semiconductor material is then diffused through the exposed area of the epitaxial layer and into the epitaxial layer to a depth less than the first PN junction to thereby form a second gate region of the field effect transistor. This gate region divides the epitaxial layer into source, drain and channel regions of opposite conductivity type semiconductor material. The relatively high resistivity epitaxial channel provides a high gain characteristic and the step of diffusing the second gate provides excellent channel width control.

3,578,515

PROCESS FOR FABRICATING PLANAR DIODES IN SEMI-INSULATING SUBSTRATES


Sebastian Ronald Borrello, Richardson, and Charles Grady Roberts, Dallas, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Apr. 5, 1967, Ser. No. 628,613

Int. Cl. H01L 3/00, 5/00, 7/34

U.S. Cl. 148—175

13 Claims



A planar diode comprising a body of p-type indium arsenide (InAs) formed in a pocket in a substrate of semi-insulating gallium arsenide (GaAs) with the faces of the two semiconductors coplanar. A p-type cadmium (Cd) diffused region is formed in only a portion of the indium arsenide which extends to one edge of the body of InAs. A first expanded contact is disposed directly on the GaAs substrate and extends onto the p-type Cd diffused region of the InAs body, and a second expanded contact is formed directly on the GaAs substrate and extends onto the InAs body that is still n-type.

The diode is fabricated by selectively etching a pocket in the GaAs substrate through a silicon dioxide (SiO₂) mask, epitaxially filling the pocket with InAs, removing the SiO₂ and lapping the surface of the GaAs substrate and InAs smooth, diffusing Cd through an SiO₂ diffusion mask, and forming the expanded contact by evaporation and photolithographic patterning.

3,578,516

HIGH ENERGY FUEL COMPRISING BERYLLIUM HYDRIDE AND PENTABORANE

Robert N. Sanders, Baton Rouge, La., assignor to Ethyl Corporation, New York, N.Y.

No Drawing. Filed Aug. 6, 1968, Ser. No. 752,731

Int. Cl. C06b 21/00

U.S. Cl. 149—22

10 Claims

Heterogeneous compositions, stable against sedimentation, are made by suspending an insoluble solid component in a liquid mixture of two components, one more and the other less dense than the solid component, in such proportions that the density of the liquid mixture approximates closely that of the solid component. Exemplary compositions are suspensions of beryllium hydride in (1) 82 volume percent pentaborane, 18 volume percent trimethylaluminum, and (2) 93 volume percent pentaborane, 7 volume percent decaborane.

3,578,517

GYPSUM BOARD FORMING


Leon R. Lapp and Edward A. Burkard, East Amherst, N.Y., assignors to National Gypsum Company, Buffalo, N.Y.

Filed Aug. 26, 1968, Ser. No. 755,149

Int. Cl. B32b 13/04

U.S. Cl. 156—40

10 Claims



A method and machine for forming wrapped edges of paper-enclosed gypsum board, wherein the bottom cover sheet side edges are folded upward and inward, underlapping the side edges of the top cover sheet, and containing therewithin the unset gypsum slurry. The contacting surfaces of the lapped edges are kept clean and free of adhesive until forming is complete, after which they are slightly separated, a contact adhesive is applied and they are then firmly adhered, one to another.

3,578,518

METHOD AND APPARATUS FOR MONITORING THE BONDING OF PAPER-WRAPPED WIRE


Alvin L. Gregg and Charles E. Koons, Harrisonville, Mo., assignors to Anaconda Wire and Cable Company

Filed June 27, 1968, Ser. No. 740,563

Int. Cl. H01b 13/10

U.S. Cl. 156—64

4 Claims



In a device for applying adhesive to the longitudinal edge of a paper tape being wrapped around an advancing wire, interruptions in adhesive flow to the tape are sensed from a decrease in electrical conductivity at a point immediately downstream of the applicator.

3,578,519

PROCESS FOR THE ASSEMBLY OF SHEETS AND APPARATUS FOR SAME

Bernard Baumann, Paris, France, assignor to L'Aluminium Francais, Balzac, France

Continuation-in-part of abandoned application Ser. No. 503,842, Oct. 23, 1965. This application Mar. 10, 1969, Ser. No. 816,143

Int. Cl. B65b 7/00

U.S. Cl. 156—69

8 Claims

A system for joining flat portions of sheets with a joint blank formed of thermoplastic material. The joint

blank initially defines first and second flat sides extending substantially perpendicularly one from the other. One flat side is disposed in overlying relationship with the flat edge portions of the sheets and the other side in overhanging relationship with respect to the flat edge



portions. A rotating roller die is provided for engagement with the overhanging portion of the joint blank, and the roller die is gradually displaced for deforming the overhanging portion for molding this portion into engagement with the flat edge portions of the sheets.

3,578,520


THERMAL INSULATION AND BOND FOR SOLID FUEL MOTORS AND METHOD OF MAKING SAME

Calvin M. Dolan, King of Prussia, and John S. Axelson, Levittown, Pa., assignors to General Electric Company
Original application Oct. 10, 1966, Ser. No. 588,003,
Divided and this application July 17, 1968, Ser. No. 745,638

Int. Cl. B32b 5/20

U.S. Cl. 156—79

7 Claims



Improved means for bonding a rocket propellant grain to its casing and thermally insulating the grain from the casing comprises the interposition between the grain and casing of a room-temperature curing and foaming elastomeric material with char retention additives. The preferred elastomeric materials are silicones and silicone epoxies. Generally, a thin layer of the insulative-adhesive foaming material is first applied either to the outer surface of the preformed rocket grain or to the inner surface of the rocket grain casing. The grain and casing are then assembled and the elastomer is allowed to foam, filling the space between the rocket grain and the casing.

3,578,521

METHOD FOR MAKING FILM CLAD PANELS

Wayne Evans, Raytown, Mo., assignor to Butler Manufacturing Company, Kansas City, Mo.

Filed July 26, 1967, Ser. No. 656,209

Int. Cl. B32b 31/06

U.S. Cl. 156—84

3 Claims

An improvement in the continuous method of fabricating polyvinyl fluoride clad fiber reinforced plastic panels wherein fine wrinkles in the surface of the panels

resulting from variations in shrinkage characteristics are removed by subjecting the film to infrared heat after ini-



tiation of cure of the plastic and prior to final forming and cure.

3,578,522

VENEER DEFECT FILLING METHOD


August H. Rauch, Lebanon, Oreg., assignor to U.S. Plywood-Champion Papers Inc., New York, N.Y.

Filed July 6, 1966, Ser. No. 563,268

Int. Cl. B32b 19/08, 35/00

U.S. Cl. 156—94

8 Claims



The present invention and apparatus covers a two-stage method for patching surface discontinuities in wood panels such as veneers and the like. In an initial stage, aggregate is added to the discontinuity by means of a vacuum. The aggregate is then compacted. In a second stage additional aggregate is added in the voids of the aggregate added in the initial stage by imposing a vacuum through said voids.

3,578,523

EXTRUSION MOLDING OF PARTICLE BOARD HAVING PARTICULAR SURFACE CHARACTERISTIC

Georg Ohse, Neuenbeken, Paderborn, Germany, assignor to Alfred Graf zu Erbach-Furstenau, Schloss Furstenau, Michelstadt, Germany

Filed May 18, 1967, Ser. No. 639,492


Claims priority, application Germany, May 21, 1966,

E 23,490, E 31,712

Int. Cl. B32b 31/08

U.S. Cl. 156—164

16 Claims



Particled board made by extrusion moulding, in which the chips located adjacent to the surfaces of the board are oriented or bent into a plane substantially parallel to the plane of the board to produce isotropic strength characteristics.

3,578,524

PROCEDURE DURING THE PRODUCTION OF A PACKAGING CONTAINER COMPRISING AN OUTER SLEEVE AND A LINING WITH AN OUTWARD-TURNED FLANGE

Rolf Lennart Ignell, Lund, Sweden, assignor to Sobrefina SA, Fribourg, Switzerland


Filed Oct. 16, 1967, Ser. No. 675,540

Claims priority, application Sweden, Nov. 18, 1966, 15,788/66

Int. Cl. B32b 1/10

U.S. Cl. 156—196

2 Claims



A method for forming a container having an inner liner with a radial flange extending outwardly therefrom adjacent its upper portion and being inserted in a sleeve up to the flange and the flange being folded down about the sleeve to secure the sleeve and liner together.

3,578,525

METHOD OF MARKING TEXTILE ARTICLES

Roger Mueller, Syracuse, N.Y., assignor to Textile Marking Machine Co., Inc., Syracuse, N.Y.

Filed June 5, 1968, Ser. No. 742,112

Int. Cl. B41m 3/00

U.S. Cl. 156—238

3 Claims

A dry transfer is applied to the textile article by a heating iron and simultaneously, additional indicia is printed on the article by selected type fixedly located relative to the iron. The transfers are provided at areas spaced along a carrier strip and print ink is provided on the same strip, or on another strip. By using interchangeable type, any form of additional indicia may be printed on the article simultaneously with the application of the transfer thereto.

3,578,526

METHOD OF MAKING REINFORCED HONEYCOMB SANDWICH


Howard H. Harding, Bridgeport, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed Jan. 22, 1968, Ser. No. 701,528

Int. Cl. B29c 27/00


U.S. Cl. 156—242

23 Claims



A lightweight, sandwich construction comprising a honeycomb core member with end-grain balsa wood impressed thereinto to fill the cells thereof at selected positions for the purpose of strengthening the honeycomb

for machining or load carrying such as bolt retention and preferably including plastic impregnated fiber glass sheets adhesively bonded to the opposite sides of the end-grain



balsa wood impressed honeycomb core to form a sandwich construction thereof and the method of so fabricating such sandwich construction.

3,578,527

METHOD OF PRODUCING A LAMINATED ARTICLE EMPLOYING EXTRUSION AND AN INERT GAS

Rikita Sakata, Kohei Masuda, Taku Uchigaki, and Masakazu Arai, Yokkaichi-shi, Japan, assignors to Mitsubishi Petrochemical Industry Co., Ltd., Tokyo, Japan

Filed Mar. 11, 1968, Ser. No. 712,113

Claims priority, application Japan, Mar. 10, 1967, 42/14,921

Int. Cl. B29c 23/00

U.S. Cl. 156—244

17 Claims

A method for producing composite laminated articles by extruding a thin film of melted resin such as polyethylene, polypropylene, and the like, onto a base material such as paper, metallic foil and the like, the melted resin being extruded at its oxidizing temperature whereby the surface opposite to the surface to be bonded to the base material of the extruded film is covered by inert gas while the bonding surface is oxidized by the air such that the non-bonding surface is prevented from being oxidized by the air. By this method, a laminated composite article having superior adhering properties between the resin film and the base and having superior heat sealing properties, without offensive odors, is obtained.

Apparatus for carrying out the above-mentioned method wherein means providing an apparatus for issuing inert gas is provided adjacent to the mouth piece of the resin extruder.

3,578,528

APPARATUS FOR FORMING HANDLES ON PAPER BAGS


Peter Weissbuh, 204—1985 Bellevue Ave., Vancouver, British Columbia, Canada

Filed May 9, 1967, Ser. No. 642,999

Int. Cl. B29c 23/00

U.S. Cl. 156—380

9 Claims



Apparatus and method for forming handles on paper bags wherein a running paper web, partially severed transversely at intervals, is passed together with an extruded

sheet of thermo-plastic material in a flowing condition, through a nip between a chilling roller and pressure roller—thus effecting a bond. The chilling roller has depressions formed in its surface which provides unbonded thermo-plastic sections overlying lines of partial severance of the paper web so that when the web is completely severed at said intervals the unbonded sections of thermo-plastic material form bag handles.

3,578,529

APPARATUS FOR PRODUCING REINFORCED PLASTICS MATERIAL ARTICLES


Arthur Kenneth Baker, Woodlands, Cut-a-Thwart Lane, Woodham Walter, Maldon, Essex, England

Filed May 27, 1968, Ser. No. 732,211

Int. Cl. B32b 23/02

U.S. Cl. 156—393

6 Claims



The invention is particularly applicable to the production of comparatively long hollow reinforced tubular components such as tapering masts or spars, the invention covering an apparatus comprising a carrier for spools of strands of reinforcing material, means for uniformly distributing and laying said strands progressively longitudinally on a former or shell whilst the latter is supported in a vertical position, a bath for containing synthetic resin surrounding said former or shell and through which said strands are adapted to pass during laying and thus become impregnated with resin, said bath at its lower end including a tubular resilient neck portion adapted to fit closely around said strands as they are laid on said shell or former to consolidate said strands and control the resin content and means for moving said bath vertically upwardly throughout the length of said shell or former until the laying process is completed.

3,578,530

ARRANGEMENT FOR CONSOLIDATING TIRE BUILDING COMPONENTS

Ernest G. Nicholls, Balsall Common, near Coventry, England, assignor to The Dunlop Company Limited, London, England

Filed Mar. 8, 1968, Ser. No. 711,725


Claims priority, application Great Britain, Mar. 17, 1967, 12,612/67

Int. Cl. B29h 17/18

U.S. Cl. 156—410

6 Claims

A device for consolidating tire building components e.g. breakers, tread strips, on to a shaped carcass comprising a pair of freely rotatable rollers, pivotally mounted on a framework, and locatable symmetrically with respect to the mid-circumferential plane of the carcass. In use the



mounts and successive parts of the roller peripheries engage with the parts of the component at gradually increasing distances from the mid-circumferential plane.

3,578,531

MANDREL

Dominique Carlini, Rousset, France, assignor to Recherches et Applications des Plastiques dans l'Industrie et le Bâtiment, S.A., Rousset, France


Filed Apr. 25, 1968, Ser. No. 723,986

Claims priority, application France, Aug. 17, 1967, 118,049

Int. Cl. B65h 67/00, 81/00, 81/02

U.S. Cl. 156—425

10 Claims



A cylindrical mandrel comprised of a plurality of segments, the arc transcribed by each segment being adjustable to vary the circumference of the mandrel. The mandrel segments comprise frame members which support, from the center thereof, flexible rectangular blanks and means are provided for adjusting the bending of the blanks.

3,578,532

WINDING APPARATUS FOR FORMING T-SHAPED FITTINGS

Herbert V. Thaden, 1101 N. Main St., High Point, N.C. 27262

Filed Nov. 4, 1968, Ser. No. 772,924


Int. Cl. B65h 81/02; B31c 1/00

U.S. Cl. 156—431

8 Claims

Winding apparatus for forming T-shaped fittings from continuous resin-impregnated glass fiber stock, characterized in that means are provided for winding "figure 8"

turns about the crotch areas between the stem and arm portions of a T-shaped mandrel. In accordance with the invention, first control means are provided for vertically displacing the mandrel relative to the continuously driven



winding table, and second control means serve to vertically adjust the roving guide means relative to winding table, whereby an improved structurally strengthened T-shaped object is produced.


3,578,533

APPARATUS FOR DRAFTING AND DEPOSITING MULTIPLE FIBER WEBS ON A CARRIER SHEET
James Loynd, Neenah, Wis., assignor to Kimberly-Clark Corporation, Neenah, Wis.

Filed June 23, 1969, Ser. No. 835,630
Int. Cl. D04h 3/00; B65h 5/04

U.S. Cl. 156—436

5 Claims



An apparatus for forming a non-woven material including a web of highly-drafted fibers and a layer of cellulosic wadding is disclosed. The wadding sheet is printed with a spaced pattern of adhesive and moved along a path disposed to intersect the discharge path of the drawn web. A vacuum is drawn through the wadding sheet opposite the point of fiber impingement to pull the highly-drafted fibers against the sheet and partially embed the fibers in the adhesive. The wadding sheet may be substantially wider than the web of highly-drafted fibers and multiple draw frames are provided with adjacent ones of the draw frames disposed in laterally offset and vertically staggered relation such that adjacent webs are successively deposited on the sheet in substantially abutting side-by-side relation.

3,578,534

CARPET SEAMER

Leo R. Johnson, 7026 NE. Grand Ave.,
Portland, Oreg. 97211

Filed Aug. 30, 1968, Ser. No. 756,527


Int. Cl. B31f 5/06

U.S. Cl. 156—461

13 Claims

An apparatus for seaming carpets face-up on the floor having a support for a roll of carpet tape, means for fold-

ing the tape along a longitudinal centerline thereof, and means for feeding the tape to the underside of two abutting pieces of carpet lying face-up on the floor, whereby the tape and the carpet are in position for the carpet to be



3,578,535

MACHINE FOR FOLDING EDGES OF A PLASTICS SHEET FACING ABOUT A DOOR PANEL, OR THE LIKE

Gerhard Göhlfenn, Imstiege 10, and Roland Spicka,
Bahnhofstr. 13, both of Gildehaus, Germany


Filed July 22, 1968, Ser. No. 746,549

Claims priority, application Germany, July 22, 1967,
G 50,720; Nov. 7, 1967, P 16 25 549.5; July 3,
1968, P 17 79 066.8

Int. Cl. B65c 9/36; B30b 15/34

U.S. Cl. 156—493

13 Claims



A machine for applying plastics sheet material facing to a door panel or the like, in which the door panel is advanced on a table where mechanism operates first to align it, and then other mechanism clamps it firmly in place, bears for the clamping device being guided between parallel guide members. Thereafter, presses in the form of gas-filled flexible tubes apply pressure to the facing material at the corners. Sequentially, tools apply the facing material to other parts of the door, including the rabbeted edge portion. Finally the clamping device is released to enable the finished door panel to make way for an unfinished door panel.

3,578,536

APPARATUS FOR CURING LABELS


Arthur C. Peck, Hazardville, and Alexander J. Usko,
Wapping, Conn., assignors to Monsanto Company, St.
Louis, Mo.

Original application Nov. 21, 1966, Ser. No. 595,796, now
Patent No. 3,510,341, dated May 5, 1970. Divided
and this application Apr. 24, 1969, Ser. No. 841,172

Int. Cl. B32b 31/20

U.S. Cl. 156—497

2 Claims



This invention is directed toward glossing the surface of wax release decals on plastic containers by shock melting the wax without appreciably raising the temperature of the plastic, in order to smooth the wax, followed by immediate shock chilling of the heated surface to maintain the gloss.

3,578,537

APPARATUS FOR THE PREPARATION OF WALLED STRUCTURES


Donald R. Wright, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Filed Sept. 25, 1967, Ser. No. 670,055

Int. Cl. B44c 7/02; E04b 1/345

U.S. Cl. 156—577

7 Claims



A structure is prepared by the spiral generation technique employing a flattened plastic tube which is inflated by means of internal fluid pressure and deposited in a generally helical manner. Adjacent turns of the helix are adhered to each other to provide a walled structure.

3,578,538

LAMINATED INDICATOR PLAQUES

Kenneth Wheatley Prosser and John Vipond Wallace,
Luton, England, assignors to The English Electric Company Limited, London, England


Filed June 12, 1968, Ser. No. 736,380

Claims priority, application Great Britain, June 15, 1967,
27,650/67

Int. Cl. B32b 3/10; G09f 13/06, 13/08

U.S. Cl. 161—6

15 Claims



A laminated indicator plaque has V-shaped indicia cut through an opaque layer and into a translucent layer so

that light from a source behind the translucent layer is reflected from the walls of the indicia in the opaque layer.

3,578,539

PICTURE RECORDS

Alec Lash, Corner House, York St., Sydney,
New South Wales, Australia

Filed July 5, 1968, Ser. No. 742,546

Claims priority, application Australia, July 19, 1967,
24,769

Int. Cl. G11b 3/84; B29d 17/00

U.S. Cl. 161—6

10 Claims



This application discloses the construction of a picture record being a musical or sound recording disc having a transparent playing surface superimposed over a paper disc bearing a picture, design and/or printed matter visible through the transparent playing surface and a method of manufacturing such picture records with avoidance of damage to the paper discs bearing a picture or other indicia.

3,578,540

COLOR PHOTOGRAPHIC PRODUCT FORMED BY DIFFUSION TRANSFER


Edwin Land, Cambridge, Mass., assignor to
Polaroid Corporation, Cambridge, Mass.

Continuation-in-part of application Ser. No. 622,283,
Mar. 10, 1967. This application July 22, 1968, Ser.
No. 746,554

Int. Cl. B44f 1/00; G03c 5/54



U.S. Cl. 161—6

8 Claims



A laminated photographic product including an image-containing layer protectively sandwiched between outer support layers and formed by utilizing an integral film unit including a photosensitive image-recording medium and a liquid reagent for processing the recording medium

following exposure thereof to produce a visible image and laminate said layers to one another to form an integral unit. The product is especially designed to resist



distortion due to physical changes, particularly the quantity and distribution of moisture in laminae comprising the product.

3,578,541

THERMALLY INSULATED RECEPTACLE FOR A CRYOGENIC FLUID

Henri Tarel, Grenoble, France, assignor to L'Air Liquide Anonyme pour l'Etude et l'Exploitation des Procédés Georges Claude

Filed Dec. 16, 1966, Ser. No. 602,324

Claims priority, application France, Nov. 2, 1966, 82,152

Int. Cl. B32b 3/26, 5/18; B65d 81/38

U.S. Cl. 161—7

3 Claims



Cryogenic insulation is provided, comprising Klegecell G300, which is foamed plastic formed from polyvinyl chloride, a copolymer of a vinylidene monomer and an ethylenically unsaturated carboxylic acid anhydride, and a polyisocyanate having at least two $-N=C=O$ groups per molecule. It is impervious to atmospheric gases and thus protects the insulation. It can be used in combination with superinsulation, and can be covered with a protective and/or ablative coating.

3,578,542

SIMULATED GRASS MAT FOR DRIVING GOLF BALLS

Steven Migitz, 17 Whistler Hill Lane, Huntington, N.Y. 11743

Filed Oct. 21, 1968, Ser. No. 769,183


Int. Cl. A41g 1/00

U.S. Cl. 161—21

9 Claims

A simulated grass mat having substantially perpendicularly extending blades or stems wherein the blades

are anchored in a cavity so that they bend and deflect the head of a golf club rather than being sheared off;



the material of the mat being selected to simulate normal turf.

3,578,543

SEAL FOR PLASTIC SHEETING


Charles A. Cook and David H. Campbell, Baton Rouge, La., assignors to Ethyl Corporation, New York, N.Y.

Filed Sept. 28, 1967, Ser. No. 671,263

Int. Cl. B32b 3/22

U.S. Cl. 161—38

5 Claims



An overlap seal for joining together two edges of reinforced thermoplastic material. A plurality of strands or bands of hot melt adhesive are applied adjacent the edge of the one sheet of thermoplastic reinforced material and the edge of another sheet is positioned above the first sheet. The sheets are brought together and pressure is applied so that the heat contained in the hot melt adhesive causes a fusion of the two edges of thermoplastic to create a high strength bond. Some of the bands of thermoplastic material flow together to form a wide band with narrower bands on each side to provide an overlapped seal having increased strength.

3,578,544

REINFORCED MICROPOROUS LAMINATES


Agmund K. Thorsrud, Brussels, Belgium, assignor to Phillips Petroleum Company

Filed Jan. 18, 1968, Ser. No. 698,831

Int. Cl. B32b 5/12, 5/18

U.S. Cl. 161—59

6 Claims



A reinforced microporous sheet is formed by distributing fibers and blowing agent in a softened elastomeric or thermoplastic material, forming a sheet of material having unidirectionally oriented fibers, laminating two or more sheets such that the fibers in each sheet are at an angle to those in adjacent sheet(s), and foaming during or subsequent to the preparation of the sheet or laminate.

3,578,545

FLEXIBLE ODOR-LIBERATING LAMINATE

Richard M. Carson and Reuben R. Saeks, Dayton, Ohio, assignors to Carson-Saeks, Inc., Dayton, Ohio

No Drawing. Continuation-in-part of application Ser. No. 433,991, Feb. 19, 1965. This application Aug. 19, 1968, Ser. No. 753,704

Int. Cl. A61l 9/04

U.S. Cl. 161—86

8 Claims

The present invention relates to laminates of flexible, transparent, porous plastic films to which is cemented absorbent fabric or felt impregnated with an odoriferous material, such as a perfume, which slowly passes through the pores of the plastic film thus giving objects in contact therewith an agreeable odor over relatively long periods of time.

3,578,546

SPANDEX FABRIC AND METHOD OF MAKING THE SAME


William F. Morancy, Cumberland, R.I., assignor to Lawson Products, Inc., Pawtucket, R.I.

Filed Apr. 28, 1967, Ser. No. 634,535

Int. Cl. B32b 5/04, 7/04

U.S. Cl. 161—89

9 Claims



Fabric having concatenated loops of spandex yarn and of at least one other yarn is made non-run and given true shape stability without loss of elasticity, stretchability, flexibility and fitability, by being autoclaved in the presence of steam to produce fusion between contacting portions of the spandex yarn only.

ERRATUM

For Class 161—102 see: Patent No. 3,578,173

3,578,547

LAMINATED FIBER-REINFORCED SHEET OF POLYMERIC MATERIAL

George Leonard Wicker, Lancashire, England, assignor to Turner Brothers Asbestos Company Limited, Manchester, England

Application June 15, 1965, Ser. No. 464,149, now Patent No. 3,461,012, dated Aug. 12, 1969, which is a continuation-in-part of abandoned application Ser. No. 237,195, Nov. 13, 1962. Divided and this application Apr. 28, 1969, Ser. No. 819,631

Claims priority, application Great Britain, Nov. 13, 1961, 40,520/61; June 15, 1964, 24,749/64


Int. Cl. B32b 5/16

U.S. Cl. 161—156

6 Claims

A rigid sheet of a polymeric material having loose fibers dispersed throughout the sheet and randomly oriented and

predominantly lying in the plane of the sheet is produced by feeding a homogeneous dough-like mass formed from a solution or emulsion of the polymeric material and the



loose fibers into the nip between two calender bowls, one of which is heated, and building the material up in laminations on one of the bowls.

3,578,548

PREFORMED RESINOUS COVERINGS ADHERED TO ARCHITECTURAL SURFACES

George L. Wesp, Ballwin, Mo., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed July 14, 1969, Ser. No. 842,086

Int. Cl. B32b 3/12, 27/08, 27/30

U.S. Cl. 161—160

15 Claims

A resinous covering material is adhered to a surface with a pressure-sensitive adhesive which, upon contact after drying, develops an immediate bond of high cohesive strength between the surface and the covering that becomes a permanent moisture-resistant bond. The adhesive compositions comprise a latex and a transient tackifier which comprises an epoxy resin and a curing agent. Some adhesive compositions may be foamed to provide a conformable smooth supporting surface for a high modulus preformed resinous covering. The architectural surface, preformed resinous covering and pressure-sensitive adhesive containing a transient tackifier comprise a used architectural surface composite for residential and commercial installations.

3,578,549

EXPANDABLE PLASTIC ARTICLES

Kenneth J. Cleereman and Lowell S. Thomas, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Original application Aug. 26, 1966, Ser. No. 575,282.

Divided and this application Nov. 24, 1969, Ser. No. 877,594

Int. Cl. B32b 3/02, 5/18

U.S. Cl. 161—160

8 Claims

Expandable synthetic resinous sheets are provided which have major expansion in only one direction. The limited expansion is obtained by employing axially oriented sheets.

3,578,550

FOIL-BACKED NON-SKID SHEET

Alfred J. Hoerner, St. Paul, and George M. Seiter, Golden Valley Village, Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jan. 31, 1969, Ser. No. 795,455

Int. Cl. B32b 5/16; C09j 7/02


U.S. Cl. 161—162

8 Claims

Foil-backed non-skid sheet material suitable for installation on rough, irregular, and curved surfaces with

which it maintains intimate contact over extended periods of time. An "open coat" single layer of frictional particles is adhered in a regular manner to an annealed aluminum

sandwich containing the thermosetting core between the face sheets may be cold-formed into shaped articles and such shape as is imparted to it is retained by the thermo-



foil backing by a flexible, elastoplastic, silane-containing polyurethane binder. The rear face of the foil is coated with a normally tacky and pressure-sensitive adhesive.

3,578,551

SPLITTABLE TOW

Jack N. Gray, Columbia, S.C., and George A. Watson, Davidson, N.C., assignors to Celanese Corporation and Fiber Industries, Inc., both of New York, N.Y.
Original application July 13, 1964, Ser. No. 382,017, now Patent No. 3,439,394, dated Apr. 22, 1969. Divided and this application Apr. 18, 1969, Ser. No. 817,508
Int. Cl. D02g 3/00

U.S. Cl. 161-173

5 Claims



A crimped tow comprising a ribbon of crimped parallel continuous filaments readily splittable by pulling opposite sides of the band.

3,578,552

THERMOSETTING LAMINATES


Dusan C. Prevorsek, Morristown, Hsin L. Li, Parsippany, Paul J. Koch, Mount Freedom, Hendrikus J. Oswald, Morristown, and George J. Schmitt, Madison, N.J., assignors to Allied Chemical Corporation, New York, N.Y.
Continuation-in-part of application Ser. No. 604,255, Dec. 23, 1966. This application Apr. 4, 1968, Ser. No. 718,858
Int. Cl. B32b 15/08, 27/36, 27/40

U.S. Cl. 161-214

9 Claims

A cold formable sandwich structure which has a thermosetting resinous core between face sheets comprising laminae of a thermoplastic sheet which incorporates a metallic foil. The metal foil-thermoplastic resin facing sheets are of sufficient thickness and strength so that the

plastic face sheets without external constraint on the shape as the thermosetting core is subsequently cured at relatively high temperatures.




3,578,553

NITROGEN DIOXIDE PULPING PROCESS

Madhu P. Godsay and Donald M. MacDonald, Hawkesbury, Ontario, Canada, assignors to Canadian International Paper Company, Montreal, Quebec, Canada
Filed Sept. 10, 1968, Ser. No. 758,841
Int. Cl. D27c 3/16

U.S. Cl. 162-14

9 Claims



A primary pulping process in which raw ligno-cellulosic material is contacted with nitrogen dioxide gas at atmospheric pressure and ambient temperature to produce cellulosic pulp and useful by-products, for example lignin nitrates and nitrites, without air or other pollution.

3,578,554

METHOD FOR COMMON DIGESTION OF TWO DIFFERENTLY PRE-TREATED FRACTIONS OF WOOD CHIPS


Johan C. F. C. Richter, St. Jean Cap Ferrat, France, assignor to Aktiebolaget Kamyr, Karlstad, Sweden
Filed Sept. 18, 1968, Ser. No. 760,486
Claims priority, application Sweden, Sept. 18, 1967, 12,803
Int. Cl. D21c 3/26

U.S. Cl. 162-19

2 Claims

A continuous digester is charged with wood chips divided by screening into two fractions, viz a larger fraction of coarser particles and a smaller fraction of finer

particles. The fractions are digested in common but are pre-treated differently. The pre-treatment of the coarser fraction consists in steaming and thorough impregnation with digesting liquor, and the pre-treatment of the finer fraction consists in merely steaming or steaming and im-



pregnation during a shorter time. The two fractions are conveyed to the digester top in different ways, the coarser chips being suspended in circulating liquid, and the finer chips may be blown by steam, preferably steam later used for heating the digester to digesting temperature.

3,578,555

SILICONE-ALUM TREATMENT OF PERLITE FIBER INSULATION BOARD AND PRODUCT THEREOF

Otto A. Oshida and Jon P. Gilmore, Albuquerque, N. Mex., assignors to Grefco, Inc., Philadelphia, Pa.
No Drawing. Filed Dec. 12, 1968, Ser. No. 783,434
Int. Cl. D21h 3/36

U.S. Cl. 162-164

8 Claims

A high degree of water repellency is conferred on perlite-cellulose fiber insulation board by uniformly incorporating both a silicone and an acid aluminum salt in the aqueous board forming mix.

3,578,556

VERTICAL PAPER MACHINE WHEREIN STOCK IMPINGES BELOW THE BREAST ROLLS

Willard C. Notbohm and Paul M. Schaffrath, Watertown, N.Y., assignors to The Black Clawson Company, Hamilton, Ohio
Filed Aug. 27, 1968, Ser. No. 755,602
Int. Cl. D21f 1/06

U.S. Cl. 162-203

9 Claims

In a two-wire vertical paper machine, opposed downwardly traveling reaches of the two wires are guided in converging relation to define a forming zone of predetermined dimensions, and a free standing sheet-like stock jet of a thickness less than the width of the mouth of the forming zone is delivered into the forming zone in such manner that it does not impinge on either of the wires until it reaches a level sufficiently below the breast rolls to avoid their pumping action. The relative speeds of the wires and the stock jet are regulated to produce desired characteristics in the paper sheet i.e., such as the ratio of tear strength in the cross machine direction to the machine direction.


3,578,557

SUPPORT STRUCTURE FOR FOURDRINIER WIRE ADJACENT THE HEADBOX CONSISTING OF A SMALL DIAMETER ROLL SUPPORTED BY A LARGER DIAMETER MASTER ROLL

Gordon Thomas Tidbury, Beaconsfield, Quebec, Canada, assignor to Dominion Engineering Works, Limited, Lachine, Quebec, Canada
Filed Dec. 9, 1968, Ser. No. 782,362
Claims priority, application Canada, Dec. 26, 1967, 8,443
Int. Cl. D21f 1/40

U.S. Cl. 162-301

4 Claims



A twin-wire paper-web forming machine uses a headbox discharging stock between two forming wires, one of the wires being supported adjacent the headbox by a rider breast roll. The rider breast roll is in turn directly supported by a relatively stiff master roll, the breast roll having a diameter significantly less than the diameter of the master roll which result in the breast roll being flexible with respect to the master roll. The profile of the master roll is reflected in the surface of the breast roll thereby resulting in controlled deflection.


3,578,558

TWIN WIRE PAPER MAKING ASSEMBLY

Terence E. McCarrick and Olaf S. Antonsen, Watertown, N.Y., assignors to The Black Clawson Company, Hamilton, Ohio
Filed Feb. 19, 1968, Ser. No. 706,514
Int. Cl. D21f 1/00

U.S. Cl. 162-303

3 Claims




Apparatus for making paper in a twin wire paper making machine. A pair of endless forming webs looped around a pair of spaced parallel breast rolls forms a nip of predetermined width. Deflector assemblies in contact with the forming webs downstream of the breast rolls guide the webs into gradually converging relation. An adjustable regulator bar, positioned in contact with one of the webs between the breast rolls and deflector assemblies, forces the one web into predetermined relation with the other web, thus establishing a preset distance therebetween.

3,578,559
ENDLESS BELT WITH POCKETS FOR COLLECTING
WATER DRAINED THROUGH A FOURDRINIER
WIRE

Ralph A. Beck, Beloit, Wis., assignor to Beloit Corporation, Beloit, Wis.
 Filed Aug. 29, 1969, Ser. No. 854,180
 Int. Cl. D21f 1/36
 U.S. Cl. 162—303

6 Claims




The surface of a paper forming wire opposite the paper-making stock carried thereby runs in contact with a portion of an endless moving drainage belt provided with enclosed pockets which have openings facing an adjacent wire to collect water drained from the stock through the adjacent wire and which are subsequently emptied by gravity along a portion of the belt path remote from the wire. Such apparatus is particularly suitable for use in twin wire vertical formation machines in which a separate drainage belt is provided in contact with each forming wire in close proximity to the headbox slice.

3,578,560
HEADBOX FOR TWIN WIRE PAPER
MAKING APPARATUS

Willard C. Notbohm, Charles A. Lamb, and J. Leslie Hanson, Watertown, N.Y., assignors to The Black Clawson Company, Hamilton, Ohio
 Filed Feb. 6, 1968, Ser. No. 703,299
 Int. Cl. D21f 1/06

U.S. Cl. 162—344

11 Claims



A headbox for use in a twin wire vertical paper making machine comprising a downwardly extending slice having elongated parallel side walls which form the stock


into a high speed jet directed into the area between twin breast rolls. One of the lips of the slice is adjustable in such a manner that it always remains parallel to the opposite lip so that the thickness of the jet can be varied without the creation of turbulence or pressure variation within the jet as it is formed between the lips. In another embodiment, one slice lip is simultaneously adjusted with one breast roll to change the width of the forming zone and the slice at the same time.

3,578,561
PAPER FORMING APPARATUS
 Terence E. McCarrick and Olaf S. Antonsen, Watertown, N.Y., assignors to The Black Clawson Company, Hamilton, Ohio

Filed Mar. 8, 1968, Ser. No. 711,583
 Int. Cl. D21g 9/00

U.S. Cl. 162—352

11 Claims




A machine for forming paper from stock between a pair of vertically traveling spaced forming wires which extend between upper breast rolls to lower couch rolls. The water is removed from the stock to a drainage system by deflectors mounted on opposite sides of the forming zone in contact with the wires which cause the wires to exert a squeezing action on the stock and which remove water from the rear side of the wires. The deflectors are individually adjustable so that the wire engaging surfaces move horizontally in a plane parallel to the wires without any vertical movement. Separate apparatus is also provided for adjusting the angular position of each wire engaging surface.

3,578,562
METHOD AND APPARATUS FOR CONTINUOUS
MONITORING AND CONTROL OF NEUTRON
ABSORPTION PROPERTIES OF CHEMICAL SHIM
 Loering M. Johnson, Tariffville, and Arthur M. Yulle, Windsor, Conn., assignors to Combustion Engineering, Inc., Windsor, Conn.

Filed Oct. 23, 1968, Ser. No. 769,778
 Int. Cl. G21c 17/00, 1/22; G01t 3/00

U.S. Cl. 176—22

7 Claims



An apparatus, and method of operation thereof, to continuously monitor and control the neutron absorption properties of chemical shim used in regulating reactivity of a pressurized water nuclear reactor. Coolant-moderator fluid, including the soluble neutron absorption property in the chemical shim, is continuously passed

through a chamber having plural neutron detectors surrounding a neutron source of known strength. Utilizing the neutron absorptiometry principle, a signal representative of the concentration of the absorption properties of the chemical shim in the coolant-moderator is derived. This signal is then applied through signal conditioning means to a readout and alarm device so that constant monitoring of the shim concentration absorption properties may be accomplished; additionally, the signal may be applied to maintain the concentration of neutron absorption properties of the chemical shim in the coolant-moderator at a desired level.


3,578,563
FLUID COOLANT APPARATUS FOR A
NUCLEAR REACTOR

Charles Strohmeier, Jr., Bern Township, Berks County, Pa., assignor to Electrodyne Research Corporation, Reading, Pa.
 Continuation-in-part of application Ser. No. 653,475, July 14, 1967. This application Dec. 22, 1967, Ser. No. 693,004

U.S. Cl. 176—51

Int. Cl. G21c 15/02

6 Claims



The invention provides an apparatus for cooling a nuclear reactor wherein there are two systems for flowing a coolant fluid, one system having multiple conduits in parallel relationship with and individually encompassing a portion of the longitudinally disposed nuclear fuel elements, the other system cooling the exterior walls of the multiple conduits and wherein means are provided for controlling fluid flow selectively in each of the two systems.

3,578,564
DOUBLE CONTAINER REACTOR VESSEL
 William D. Fletcher III, Hartford, Conn., assignor to Combustion Engineering, Inc., Windsor, Conn.
 Filed Oct. 31, 1968, Ser. No. 772,304


U.S. Cl. 176—87

Int. Cl. G21c 13/02

4 Claims

Means for suspendedly mounting a double container reactor vessel within a vessel cavity formed in a foundation structure in a manner such that, in the event of failure of the outer vessel in any location, the inner vessel will remain secured to the foundation structure. The means comprises the provision of radial flanges on the shells and closure covers of the inner and outer container vessels arranged such that the inner vessel flanges are retained in sandwiched relation between the opposing faces of the

outer vessel flanges. Annular shoulder means are provided on the foundation wall to vertically support the assembled vessel structure by engagement with the outer vessel shell flange. An annular lock ring releasably attached to the



foundation presents a bearing face adapted to engage the outer vessel closure cover flange to prevent upward movement of the retained flanges in the event of a reactor accident.

3,578,565
PROCESS FOR THE MANUFACTURE OF STEROIDS
OF THE ANDROSTANE SERIES

Arno Johannes Schocher, Benken, Andor Furst, Basel, Hans Els, Binningen, and Elisabeth Becher and Gisela Gross, Basel, Switzerland, assignors to Hoffmann-La Roche Inc., Nutley, N.J.
 No Drawing. Filed Oct. 1, 1968, Ser. No. 766,021
 Claims priority, application Switzerland, Oct. 5, 1967, 13,930/67

U.S. Cl. 195—51

17 Claims

Microbiological process for preparing 17-oxygenated androstanes by subjecting 20-oxygenated pregnanes to the action of a culture of the fungus *Gliocladium roseum*. The steroids prepared are known compounds which are pharmaceutically useful as androgenic agents and as intermediates which can be converted to known compounds which are progestational agents.

3,578,566
PROCESS OF TREATING OIL CONTAINING
FERMENTATION DISCHARGES

Manfred Rudel, Markleeberg, and Anton Gabert, Ulrich Behrens, and Dieter Pohland, Leipzig, Manfred Ringpfeil, Holzhausen, and Karl Sattler, Leipzig, Germany, assignors to Deutsche Akademie der Wissenschaften zu Berlin, Berlin-Aldershof, Germany
 No Drawing. Filed Dec. 28, 1967, Ser. No. 694,120

U.S. Cl. 195—82

12 Claims

An oil containing fermentation discharge such as obtained in the aerobic fermentation of petroleum fractions and petroleum-like paraffinic products is subjected in the form of a dispersion of the oil and microorganisms in the nutrient medium to a gravitational field of a sufficient magnitude and for a time sufficient to effect a phase inversion, the fermentation medium and microorganisms in the inverted phase being dispersed in the oil so that the latter forms the external phase of the dispersion, and then effecting the separation of at least part of the oil from the microorganisms. Preferably the microorganism is yeast and the gravitational force is applied by means of a centrifugal field having an acceleration in excess of $10^3 g$; g being the gravity acceleration.

3,578,567

PROCESS AND APPARATUS FOR THE CONTINUOUS FLOW, IN-LINE FRACTIONATION AND EXCHANGE OF VOLATILE SOLVENTS


Harry H. Malvin, Houston, Tex. (585 Carriage Way, Deerfield, Ill. 60015), and Marion J. Stansell, San Antonio, Tex. (8260-H Jamboree Circle, Colorado Springs, Colo. 80907)

Filed Oct. 31, 1968, Ser. No. 772,337

Int. Cl. B01d 3/34, 11/02

U.S. Cl. 203—49

9 Claims



A method for separating the individual solvent components from a mixture of miscible solvents present together in a single solvent system. This method also provides for the continuous flow, in-line fractionation and exchange of miscible liquids of differing volatilization characteristics. A solvent mixture is introduced into a heated, inclined, perforated conduit. As the solvent mixture descends the heated conduit, a countercurrent stream of heated inert gas, saturated with vapors of the same solvent component to be retained in the conduit, is passed over the perforations. Preferential evaporation of the more volatile solvent components occurs, resulting in near complete removal of these components by the time the solvent mixture exits at the bottom of the conduit with the less volatile solvent component remaining within the conduit for subsequent collection.

3,578,568

PURIFICATION OF LOW MOLECULAR WEIGHT EPOXIDES BY EXTRACTIVE DISTILLATION WITH A GLYCOL OR GLYCOL ETHER


Thomas A. Washall, Wilmington, Del., assignor to Atlantic Richfield Company, New York, N.Y.

Filed Nov. 29, 1968, Ser. No. 779,738

Int. Cl. B01d 3/34

U.S. Cl. 203—64

4 Claims



Method for the purification of C₃ to C₅ monoepoxides by extractive distillation with ethylene glycol, propylene

glycol, ethylene glycol monomethyl ether or diethylene glycol monomethyl ether.

3,578,569

ANODE POLARIZATION DETECTOR


Robert A. Lewis, Los Altos, Calif., assignor to Kaiser Aluminum & Chemical Corporation, Oakland, Calif.

Filed Sept. 18, 1967, Ser. No. 668,360

Int. Cl. B01k 1/00; C22d 3/12

U.S. Cl. 204—1

6 Claims



This invention describes a method and a system for indicating the alumina requirements of the molten bath in an electrolytic cell for the production of aluminum so as to maintain stable operation. A reference electrode is inserted into the molten bath of the cell and an instrument for measuring potential is connected between the reference electrode and the operating anode system of the cell so as to measure the potential difference between the reference electrode and the operating system of the cell. Increasing potential difference indicates increasing polarization of the operating anode system and decreasing alumina content in the molten bath. Decreasing potential difference indicates decreasing polarization of the operating anode system and increasing alumina content of the bath. In accordance with the indication received, the alumina content in the bath is adjusted as needed to maintain stable operation of the electrolytic reduction cell.

3,578,570

ALUMINUM CAPACITOR FOIL

Gerald Harvey Kissin, Spokane, Wash., assignor to Kaiser Aluminum & Chemical Corporation, Oakland, Calif.

No Drawing. Filed Sept. 25, 1967, Ser. No. 670,402

Int. Cl. C23b 3/00

U.S. Cl. 204—33

2 Claims

A capacitor foil alloy and a method for making capacitor foil by constituting an aluminum alloy of high purity aluminum containing from 0.02 to 0.1% magnesium, and less than 0.002% sodium, preferably preheating the alloy to a temperature above 950° F., rolling to a foil, electrolytically etching the foil and anodizing the etched foil.

3,578,571

METHOD OF ELECTRODEPOSITING A MAGNETIC ALLOY AND ELECTROLYTE THEREFOR

Paul E. McQuaid, Canoga Park, and Anthony J. Kolk, Jr., Palos Verdes Peninsula, Calif., assignors to General Precision Systems Inc.

Filed Sept. 9, 1968, Ser. No. 758,548

Int. Cl. C23b 5/32

U.S. Cl. 204—43

13 Claims

Magnetically responsive coatings affording high coercivity properties and a very high squareness ratio are achieved by electrodeposition of Co, Ni and P from a bath in which the ratio of Co to Ni is approximately 1.5.

3,578,572

ELECTRODES FOR USE IN AQUEOUS ALKALI METAL CHLORIDE ELECTROLYTES

Denis Lee, Runcorn, England, assignor to Imperial Chemical Industries Limited, London, England

No Drawing. Filed Oct. 21, 1968, Ser. No. 769,400

Claims priority, application Great Britain, Nov. 10, 1967, 51,219/67

Int. Cl. C01b 11/26; C23b 5/24, 5/48

U.S. Cl. 204—95

9 Claims

The invention relates to a platinum metal coated titanium electrode for use in electrolysis of brine. By electroplating the platinum group metal from an electrolyte containing a polybasic, hydroxy organic acid the resulting plated electrode is "activated."

3,578,573

PROCESS OF FINISHING PARTS OF ZIRCONIUM ALLOYS SUCH AS FOR USE WITH NUCLEAR REACTOR PLANTS

Friedrich Schwelger, Nuremberg, and Horst Bertholdt, Erlangen, Germany, assignors to Siemens Aktiengesellschaft, Berlin and Munich, Germany

No Drawing. Filed May 7, 1968, Ser. No. 727,365

Claims priority, application Germany, May 10, 1967, S 109,810

Int. Cl. C23b 3/06

U.S. Cl. 204—140.5

5 Claims

Finished parts of zirconium alloys, such as envelope tubes for nuclear fuel, are surface treated by electrolytic polishing. Preferably used is a polishing bath composed of acetic acid of about 99 to 100% concentration, perchloric acid of 40% concentration and hydrochloric acid of 37% concentration in a mixing ratio of about 300:1 to 10:10 to 40 parts.

3,578,574

ELECTROLYTIC MATERIAL REMOVAL PROCESS AND APPARATUS


Charles J. Trzyna, Long Grove, Ill., and Thaddeus S. Trzyna, Pasadena, Calif., assignors to Electronic Precision Industries Corporation, Inc.

Filed Oct. 18, 1965, Ser. No. 497,089

Int. Cl. B23p 1/00

U.S. Cl. 204—143

5 Claims



A process for removing material from metal articles and for perforating metal articles using an electrolytical material removal technique.

3,578,575

PHOTONITROSATION OF NORMAL PARAFFINS

Orville W. Rigdon, Groves, and Robert S. Edwards and Edward H. Holst, Nederland, Tex., assignors to Texaco Inc., New York, N.Y.

Filed Oct. 11, 1967, Ser. No. 674,612

Int. Cl. B01j 1/00; C07c 131/00

U.S. Cl. 204—162

12 Claims

A process for producing normal paraffin oximes and, in particular, normal paraffin oximes having from 10 to 13 carbon atoms wherein a C₁₀ to C₁₃ normal paraffin is photochemically reacted with a gaseous nitrosating agent, the nitrosating agent partial pressure being at least 125 mm. Hg and the photolytic reaction conducted under the influence of light excluding wave-lengths below 200 millimicrons. The process is admirably suited for the production of normal paraffin oximes from mixtures of C₁₀ to C₁₃ normal paraffins.

3,578,576

POLYPEPTIDE SYNTHESIS FROM AMMONIA AND METHANE USING HIGH ENERGY RADIATION

Robert M. Kliss, Marblehead, Mass., and Clifford N. Matthews and Robert E. Moser, St. Louis, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Apr. 25, 1967, Ser. No. 641,723

Int. Cl. B01j 1/10

U.S. Cl. 204—162

7 Claims

A process for synthesis of polypeptides by subjecting ammonia and methane to high energy radiation and then treating the resulting product with water.

3,578,577

SURFACER TREATING PROCESS FOR BLEMISHED ELECTROCOAT SUBSTRATES

Allan E. Gilchrist, Westlake, Ohio, assignor to SCM Corporation, Cleveland, Ohio

No Drawing. Filed Oct. 11, 1967, Ser. No. 674,639

Int. Cl. B01k 5/02; C23b 13/00

U.S. Cl. 204—181

5 Claims

This patent application sets forth a process for surface treating an electrode substrate used in electrocoating, specifically, one which has surface imperfections or blemishes, and a surfacer composition therefor. The surfacer composition is a curable mixture comprising binder resin and sufficient electrically conductive filler mixed therewith for at most insignificantly changing, in cured thin final section on a blemished surface region of said substrate, the electrical resistance of said region relative to that of the untreated adjacent substrate to be coated. In accordance with the process surfacer composition is applied in thin layer to the blemished region of the substrate, cured (and when appropriate further and finally finished as by wet sanding), then the thus-treated substrate is electrocoated with paint.

3,578,578

MEASURING MEANS FOR MEASURING THE OXYGEN CONTENT IN LIQUID AND GASEOUS MEDIA

Otto Von Krusenstierna, Vasteras, Sweden, assignor to Allmänna Svenska Elektriska Aktiebolaget, Vasteras, Sweden

Filed Sept. 30, 1968, Ser. No. 763,760

Claims priority, application Sweden, Sept. 28, 1967, 13,306/67

Int. Cl. G01n 27/46

U.S. Cl. 204—195

10 Claims

Measuring means for measuring the oxygen content in a liquid or gaseous medium, comprising a solid oxygen

ion conducting electrolyte arranged in contact with a reference system having known oxygen potential and consisting of a metal and its oxide which is arranged in contact with a current collector. The current collector is



designed as a carrying element for the reference system and the electrolyte which are both arranged as layers on the current collector with the electrolyte outside the reference system.


3,578,579

ELECTROCHEMICAL APPARATUS

Normand C. Hebert and Martin E. Nordberg, Corning, N.Y., assignors to Corning Glass Works, Corning, N.Y.
Filed Sept. 11, 1967, Ser. No. 666,843
Int. Cl. G01n 27/36

U.S. Cl. 204—195

8 Claims



An electrochemical apparatus for determining the concentration of cations in solution and more particularly, an improved glass electrode for determining the activity of alkaline earth metal ions in an aqueous solution.

3,578,580


ELECTROLYTIC CELL APPARATUS

Wolfgang Schmidt-Hatting and Sebastian Huwyler, Sierre, Switzerland, assignors to Swiss Aluminium Ltd., Chippis, Switzerland

Filed Oct. 17, 1967, Ser. No. 675,881
Claims priority, application Switzerland, Apr. 28, 1967, 6,145/67

Int. Cl. C22d 1/02; B01k 3/04
U.S. Cl. 204—243

8 Claims



Apparatus for the electrolysis of molten oxides, especially of alumina, in which the anode is separated from the melt being electrolysed by a layer of oxygen-ion-conducting material, for example cerium oxide stabilised with calcium oxide or other oxides, which is resistant to the melt at the temperature of the electrolysis, and correlated inventions and discoveries appertaining thereto.

3,578,581

AROMATICS RECOVERY WITH CARBON MONOXIDE-CUPROUS FLUOROBORATE AND CARBON MONOXIDE-CUPROUS FLUOROPHOSPHATE COMPLEXES

George F. Davis, Creve Coeur, Herbert J. Gebhart, Jr., Ferguson, and Earle C. Makin, Jr., St. Louis, Mo., assignors to Monsanto Company, St. Louis, Mo.
No Drawing. Filed Feb. 12, 1969, Ser. No. 798,778
Int. Cl. B01d 17/00; C07c 7/16

U.S. Cl. 208—308

10 Claims

A process for the separation of aromatic hydrocarbons from admixture with aliphatic hydrocarbons or vinylaromatic hydrocarbons wherein separation is effected by selective complex formation with a complex comprising cuprous fluoroborate or cuprous fluorophosphate and carbon monoxide.

3,578,582

STARTUP PROCEDURE FOR CYCLIC REGENERATIVE PLATINUM-RHENIUM REFORMING PROCESS

Robert L. Jacobson, Pinole, Calif., assignor to Chevron Research Company, San Francisco, Calif.
No Drawing. Filed June 9, 1969, Ser. No. 831,773
Int. Cl. C10g 35/08

U.S. Cl. 208—138

9 Claims

In a cyclic regenerative reforming process wherein a substantially sulfur-free naphtha fraction is contacted with a platinum group component-rhenium component catalyst at reforming conditions and in the presence of hydrogen to produce a high octane gasoline product, the process is started up by sulfiding the catalyst in situ with from 0.05 to 2 moles of sulfur per mole of the platinum group component and rhenium component, calculated as the metals.

3,578,583

REFORMING PROCESS WITH PROMOTED LOW PLATINUM CONTENT CATALYST

Waldeen C. Buss, Richmond, Calif., assignor to Chevron Research Company, San Francisco, Calif.

No Drawing. Continuation-in-part of application Ser. No. 758,673, Sept. 10, 1968, which is a continuation-in-part of application Ser. No. 753,165, Aug. 16, 1968. This application Aug. 1, 1969, Ser. No. 846,971
Int. Cl. C10g 35/08; B01j 11/12

U.S. Cl. 208—138

11 Claims

Reforming a naphtha in the presence of hydrogen with a catalyst composition of a porous solid carrier and 0.01 to 0.3 weight percent platinum, 0.01 to 0.3 weight percent rhenium, and 0.001 to 0.1 weight percent iridium, and the novel supported platinum-rhenium-iridium catalyst.

3,578,584

HYDROCARBON CONVERSION PROCESS AND PLATINUM-GERMANIUM CATALYTIC COMPOSITE FOR USE THEREIN

John C. Hayes, Palatine, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.

No Drawing. Filed May 28, 1969, Ser. No. 828,762
Int. Cl. B01j 11/08; C10g 35/08

U.S. Cl. 208—139

20 Claims

A catalytic composite, comprising a combination of a platinum group component, a germanium component, and a halogen component with a porous carrier material in amounts sufficient to result in the composite containing, on an elemental basis, about 0.01 to about 2.0 wt. percent of the platinum group metal, about 0.01 to about 5.0 wt. percent germanium, and about 0.5 to about 3.5 wt. percent halogen, is disclosed. Key feature of the subject composite is the use of the germanium component, which is prepared and maintained in an oxidation state above that of the elemental metal, to promote the platinum group component. The principal utility of the subject composite is in the conversion of hydrocarbons, particu-

larly in the reforming of a gasoline fraction. A specific example of the catalyst disclosed is a combination of platinum, germanium oxide, and chloride with an alumina carrier material in amounts sufficient to result in the composite containing, on an elemental basis, about 0.05 to about 1.0 wt. percent platinum, about 0.05 to about 2.0 wt. percent germanium, and about 0.6 to about 1.2 wt. percent chlorine.

3,578,585


METHOD OF REMOVING FLOATING OIL FROM THE SURFACE OF A BODY OF WATER

Robert L. Yahnke, Munster, Ind., assignor to Standard Oil Company, Chicago, Ill.

Continuation of application Ser. No. 672,294, Oct. 2, 1967. This application Mar. 24, 1969, Ser. No. 809,524
Int. Cl. B01d 15/02, 33/02

U.S. Cl. 210—30

4 Claims



A rotating cylinder covered with a layer of porous polyurethane absorbs oil flowing on a body of water, and a roller squeezes absorbed oil from the layer into a collecting trough.

3,578,586

TREATMENT OF SLURRIES

István Gál, János Hollo, Jenő Toth, and István Zagayvai, Budapest, Hungary, and Béla Galgoczi, deceased, late of Budapest, Hungary, by Katalin Galgaczi, trustee, Budapest, Hungary, assignors to Simonacco Limited, Cumberland, England


Continuation-in-part of application Ser. No. 624,331, Mar. 20, 1967. This application June 20, 1969, Ser. No. 835,315

Claims priority, application Hungary, Mar. 24, 1966, GA-803

Int. Cl. B01d 21/01

U.S. Cl. 210—49

7 Claims



A method and equipment for treatment and dewatering of aqueous suspensions containing finely divided mineral solids having a particle size not greater than 30 microns wherein the aqueous suspensions is treated with a polyelectrolyte having a molecular weight of from

10,000 to 10,000,000 in at least two steps which comprises diluting the solids content of the suspension with water to a solids content to 2 to 5% by weight, treating the suspension under vigorous stirring with an aqueous solution of an amphoteric polyelectrolyte, conducting the treated suspension under continuous flow to a first settling zone and adding a further amount of polyelectrolyte for increasing the structural viscosity of the settled phase to an extent of at least 10,000 centipoises, separating water, then diminishing the structural viscosity of the settled phase to an extent of not more than 2000 centipoises, separating further water, conducting the settled phase while intermixing a further amount of polyelectrolyte to a second settling zone, and finally dewatering it.

3,578,587

COLOR REMOVAL PROCESS

Frank N. Kemmer, La Grange, Ill., assignor to Nalco Chemical Company, Chicago, Ill.

No Drawing. Filed Jan. 5, 1970, Ser. No. 815

Int. Cl. C02c 5/02

U.S. Cl. 210—52

4 Claims

The amount of lime necessary to remove color from paper mill waste waters can be substantially reduced when the lime is used in combination with certain water-soluble anionic polymers.

3,578,588

POLYHYDROXYL COAGULANT COMPOUNDS

Andrew G. Tsuk, Laurel, Md., assignor to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed July 22, 1969, Ser. No. 843,814

Int. Cl. B01d 21/01

U.S. Cl. 210—52

12 Claims

Compositions of polyhydroxyl compounds of the polygalactomannans such as guar gum or locust bean gum with borax are good flocculants for cellulosic substances. These compositions readily flocculate cellulose suspensions having a pH of 7 or more. The gums comprise cationically modified gums as well as the unmodified gums.

3,578,589

METHOD FOR TREATING COOLING WATER

Chih Ming Hwa, Arlington Heights, Ill., and Gary J. Antony, Burnsville, Minn., assignors to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed Mar. 17, 1969, Ser. No. 807,964

Int. Cl. C02b 5/06

U.S. Cl. 210—58

6 Claims

Accumulated deposits of scale, and of mud, silt, sludge and other foulants, are removed from cooling water systems; and further deposition is inhibited; by incorporating into the water flowing through such systems a mixture of a nonionic surface active agent and from 0.01 to 10 parts by weight, per part by weight of the surface active agent, of an acrylic or methacrylic acid polymer or a water soluble salt of such polymer having a weight average molecular weight of from 400 to 95,000. The mixture is added to the cooling water system in amounts up to 500 parts per million.

3,578,590

FIRE-EXTINGUISHING COMPOSITION COMPRISING ETHOXYLATED ALKYLPHENOL AND ETHYLENE GLYCOL MONO LOWER ALKYL ETHER

Darle Lee Nieneker, Austin, and Leslie Preston Williams, Groves, Tex., assignors to Jefferson Chemical Company, Inc., Houston, Tex.

No Drawing. Filed Aug. 19, 1968, Ser. No. 753,714

Int. Cl. A62d 1/00; B01f 17/42

U.S. Cl. 252—8.05

3 Claims

An improved fire-fighting composition of an ethoxylated alkylphenol and an ethylene glycol mono lower alkyl

ether has been discovered. This improved fire-extinguishing composition is useful as a wetting agent, emulsifying agent, low-expansion or high-expansion foam and performs exceptionally well in the presence of both fresh and salt water.

3,578,591

FABRIC SOFTENER COMPOSITION

Christina Nicholson Lazaridis, Piscataway, and Harold Eugene Wixon, New Brunswick, N.J., assignors to Colgate-Palmolive Company, New York, N.Y.
No Drawing. Filed Nov. 13, 1967, Ser. No. 682,592
Int. Cl. D06m 13/28, 13/40

U.S. Cl. 252—8.7

13 Claims

A non-yellowing fabric-softening composition comprising a mixture of a sulfonate and an aliphatic alkanol which is designed for use in conjunction with anionic, cationic, and nonionic detergent compositions.

3,578,592

IMIDAZOLINE QUATERNARY SALTS AS SOIL RETARDANTS

Joseph John Pontelandolfo, Piscataway Township, Middlesex County, N.J., assignor to American Cyanamid Company, Stamford, Conn.
No Drawing. Filed Oct. 3, 1967, Ser. No. 672,461
Int. Cl. D06m 13/40, 13/46

U.S. Cl. 252—8.8

1 Claim

The use of imidazolium halides as soil retardants for non-cellulosic textile materials, the treated textile materials and a stabilized composition containing said halide and a formaldehyde-bisulfite addition product.

3,578,593

LIQUID ELECTROSTATIC DEVELOPING MEDIUM HAVING A MIXTURE OF NON-ESTERIFIED TRICYCLIC DITERPENE CARBOXYLIC ACID AND POLYHYDRIC ALCOHOL

Lauren L. Hulse, Lexington, Ky., assignor to Addressograph-Multigraph Corporation, Mount Prospect, Ill.
No Drawing. Filed Sept. 1, 1967, Ser. No. 664,957
Int. Cl. G03g 9/04

U.S. Cl. 252—62.1

12 Claims

A liquid electrostatic developer having toner particles dispersed in an insulating, nonpolar organic liquid carrier is used for the development of zinc oxide coated copy sheets and the like. A tricyclic diterpene carboxylic acid or heat blended mixture of a tricyclic diterpene carboxylic acid and a polyhydric alcohol absorbed on the toner particles orients the polarity and controls the magnitude of the charge on the toner particles. Suitable acids are levopimaric acid, abietic acid, neoabietic acid, dehydroabietic acid, dihydroabietic acid, tetrahydroabietic acid, dextropimaric acid, and isodextropimaric acid. Suitable polyhydric alcohols are ethylene glycol, triethylene glycol, glycerol, and pentaerythritol.

3,578,594

FIBER TREATING COMPOSITIONS

Bernard A. Dombrow, Teaneck, N.J., assignor to Diamond Shamrock Corporation, Cleveland, Ohio
No Drawing. Filed Nov. 24, 1967, Ser. No. 685,335
Int. Cl. D06m 13/20, 13/18

U.S. Cl. 252—8.9

8 Claims

Fiber treating compositions containing from about 10% by weight to about 75% by weight of an ester of an ethoxylated arylphenol and from about 90% by weight to about 25% by weight of an ester of an ethoxylated aliphatic alcohol have reduced high temperature volatilities and enhanced high temperature stability. A useful fiber treating composition contains 25% by weight of an ester of an ethoxylated benzylphenol and 75% by weight of an ester of an ethoxylated aliphatic alcohol having from about 11 to about 15 carbon atoms. Also, fibers can

be treated with esters of linear secondary alcohols or esters of ethoxylated secondary linear alcohols having low pour points. A typical example is fiber treated with the ester of an ethoxylated secondary linear alcohol having from about 11 to about 15 carbon atoms.

3,578,595


ZINC DI-3-ALKYLPHENOXY-2,2-DIALKYLPROPYL DITHIOPHOSPHATE AND AUTOMATIC TRANSMISSION FLUID CONTAINING SAME

Raymond C. Schlicht and Arthur W. Godfrey, Fishkill, N.Y., assignors to Texaco Inc., New York, N.Y.
Filed July 28, 1969, Ser. No. 845,445
Int. Cl. C09k 3/00

U.S. Cl. 252—75

5 Claims

Zinc di-3-alkylphenoxy-2,2-dialkylpropyl dithiophosphate represented by the formula:



in which each R represents an alkyl radical having from 1 to 4 carbon atoms, R₁ is an alkyl radical having from 6 to 18 carbon atoms, R₂ is hydrogen or an alkyl radical having from 6 to 18 carbon atoms and the total number of carbon atoms in R₁ and R₂ is from 6 to 24 and a hydraulic fluid or automatic transmission fluid containing same.

3,578,596

PENETRATING OIL FORMULATION

David D. Conway, Littleton, Colo., assignor to Marathon Oil Company, Findlay, Ohio
No Drawing. Filed June 25, 1968, Ser. No. 739,667
Int. Cl. C10m 1/50

U.S. Cl. 252—49.6

8 Claims

Lubricating oil composition having penetrating, residual lubricating properties, and release characteristics is obtained by mixing 40–95% of hydrocarbon carrier (e.g. mixture of naphtha and kerosene), 5–40% of an alkyl ester of a carboxylic acid containing about 8–24 carbon atoms, and about 0.1% of dialkyl polysiloxane.


3,578,597

MIXTURES OF PERFLUORODIMETHYLCYCLOBUTANE AND TRICHLOROTRIFLUOROETHANE

Bernhardt J. Eiseman, Jr., Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
Filed Apr. 17, 1969, Ser. No. 816,995
Int. Cl. H01b 3/24; C09k 3/06

U.S. Cl. 252—66

4 Claims



A mixture of perfluorodimethylcyclobutane with 1,1,2-trichloro-1,2,2-trifluoroethane, said mixture containing

MAY 11, 1971

about 26 to 42 weight percent 1,1,2-trichloro-1,2,2-trifluoroethane and having an essentially constant boiling point of about 40° C.

3,578,598

STABILIZATION OF N-CHLORO-IMIDES

Richard L. Burke, Madison, N.J., assignor to Colgate-Palmolive Company, New York, N.Y.
No Drawing. Filed May 29, 1968, Ser. No. 732,844
Int. Cl. C11d 7/54

U.S. Cl. 252—102

12 Claims

Cleansing compositions containing an N-chloro-imide and a stabilizing amount of a mercaptan compound of the following structural formula:



wherein R is selected from the group consisting of alkyl containing from 4–12 carbon atoms, phenyl and benzyl.

3,578,599


STABILIZATION OF N-CHLORO-IMIDES

Richard L. Burke, Madison, N.J., assignor to Colgate-Palmolive Company, New York, N.Y.
No Drawing. Filed May 29, 1968, Ser. No. 732,875
Int. Cl. C11d 7/54

U.S. Cl. 252—102

13 Claims

Cleansing compositions containing an N-chloro-imide and a stabilizing amount of a dialkyl sulfoxide of the following structural formula:



wherein R and R₁ independently represent alkyl groups, the combined carbon content of such groups falling within the range of from 2 to 14.

3,578,600

STABILIZATION OF N-CHLORO-IMIDES

Richard L. Burke, Madison, N.J., assignor to Colgate-Palmolive Company, New York, N.Y.
No Drawing. Filed May 29, 1968, Ser. No. 732,878
Int. Cl. C11d 7/54

U.S. Cl. 252—102

11 Claims

Cleansing compositions containing an N-chloro-imide and a stabilizing amount of a disulfide compound of the following structural formula:



wherein R and R₁ are independently selected from the group consisting of alkyl, aryl, aralkyl, and alkaryl the combined carbon content of such groups falling within the range of from 4–14.

3,578,601


DETERGENT COMPOSITIONS CONTAINING SULFONIO CARBOXYLATES

Arnon O. Snoddy, Cincinnati, and Francis L. Diehl and Howard F. Drew, Wyoming, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
No Drawing. Original application Aug. 23, 1966, Ser. No. 574,469. Divided and this application Nov. 12, 1968, Ser. No. 794,448
Int. Cl. C11d 3/04, 1/18

U.S. Cl. 252—135

8 Claims

Detergent compositions containing sulfonio carboxylates, having the formula set forth below, and alkaline builder salts are especially useful in cool water detergency:

R₁ is C₁₀–C₁₈ alkylR₂ is C₁–C₄ alkyl or hydroxyalkyl

n is 1–12.


3,578,602

PHOTOCHROMIC COMPOUND


Hisatake Ono, Tiaki Osada, and Kuniko Kosuge, Asaka-shi, Japan, assignors to Fuji Shashin Film Kabushiki Kaisha, Kanagawa, Japan
Filed Aug. 29, 1968, Ser. No. 756,180
Claims priority, application Japan, Aug. 30, 1967, 42/55,662
Int. Cl. G02b 5/24

U.S. Cl. 252—300

7 Claims



A photochromic compound represented by the formula:



in which R can be hydrogen, a halogen, a cyan group, a nitro group, an alkyl group (1–8 carbons), an alkoxy group (1–8 carbons) or an alkoxy carbonyl group (1–8 carbons). Various resin and solvent systems which form photochromic compositions with the above compound are described in the specification. The compound or composition will vary from colorless (non-excited) to blue (under ultraviolet), and exhibits high reversibility.

3,578,603

PROCESS FOR THE PREPARATION OF PHOSPHATE PHOSPHORS

Ernest A. Dale, Hamilton, Richard A. Fowler, Danvers, and Martha J. B. Thomas, Winchester, Mass., assignors to Sylvania Electric Products Inc.
No Drawing. Filed Mar. 20, 1969, Ser. No. 809,037
Int. Cl. C09k 1/36

U.S. Cl. 252—301.4

3 Claims

A process of making calcium phosphate-type phosphors including the use of vaterite form of calcium carbonate as one of the starting materials.

3,578,604

PREPARATION OF MIXED GELS OF ACRYLAMIDE AND AGAROSE OR AGAR-AGAR


José Uriel, Paris, France, assignor to Etablissement Public: Centre National de la Recherche Scientifique, Paris, France
Filed Nov. 29, 1966, Ser. No. 597,713
Claims priority, application France, Nov. 30, 1965, 40,338; Oct. 3, 1966, 78,576, 78,578
Int. Cl. B01j 13/00

U.S. Cl. 252—316

8 Claims

Mixed gels of acrylamide and a substance selected from the group consisting of agarose and agar-agar, which gels are especially suitable in the electrophoretic separation of natural products as molecular sieves and filters, are prepared by providing heated, buffered solutions of (1) melted agarose or agar-agar, and (2) acrylamide with N,N'-methylene-bisacrylamide, adding ammonium persulfate and N,N',N'-tetramethyl-ethylene diamine to solu-

tion (1), rapidly mixing so-treated solution (1) and solution (2), immediately casting the mixture in an oven at a



temperature above 50° C., and letting the acrylamide gel form and cool to room temperature.

3,578,605

PROCESS FOR MAKING DUAL WALLED MICROCAPSULES

George Baxter, Font Hill, Ontario, Canada, assignor to Moore Business Forms, Inc., Niagara Falls, N.Y.
No Drawing. Filed Aug. 2, 1968, Ser. No. 749,600
Int. Cl. B01j 13/02; B44d 1/16; A61k 9/04

U.S. Cl. 252—316 10 Claims
A method of forming dual walled microcapsules around core particles or nuclei of oily or solvent material in which the oily or solvent material containing a dibasic or long-chain organic acid chloride is dispersed in an aqueous solution of a hydrophilic colloidal protein and a second hydrophilic colloid which is adapted to undergo coacervation with the colloidal protein upon a reduction in the pH of the aqueous solution. The acid chloride reacts with the protein to form a thin film of insolubilized protein around the core particles or nuclei, releasing hydrochloric acid as a reaction by-product which lowers the pH of the aqueous solution to the point at which coacervation of the colloids takes place, depositing an outer shell of complex coacervate. The dual-walled capsules can be given a hardening treatment, using formaldehyde or the like. The resultant capsules retain even relatively volatile matter for long periods of time.

3,578,606

ALKYLLEAD ANTIKNOCK FLUIDS

Martin B. Smith and Norman G. Adams, Baton Rouge, La., assignors to Ethyl Corporation, New York, N.Y.
No Drawing. Filed May 27, 1968, Ser. No. 732,094
Int. Cl. C09k 3/00; C10I 1/20

U.S. Cl. 252—386 14 Claims
Incorporation of small amounts of methyl bromide or ethyl bromide, or both, into tetraethyllead-containing antiknock fluids having a scavenger combination of ethylene dibromide and ethylene dichloride wherein the latter scavenger predominates. The flash point by Tag closed cup (ASTM designation: D 56-64) is raised to above 100° F.

3,578,607

CORROSION INHIBITED PHOSPHORIC ACID COMPOSITION

Olen L. Riggs, Jr., and David W. Barnett, Ponca City, Okla., assignors to Continental Oil Company, Ponca City, Okla.
No Drawing. Filed Feb. 9, 1968, Ser. No. 704,251
Int. Cl. C23f 11/00

U.S. Cl. 252—389 4 Claims
A corrosion inhibited phosphoric acid composition comprising a phosphoric acid solution having added thereto

an effective amount of the reaction product of an acidic fluoride with an organic amine having a molecular weight between about 50 and about 500.

3,578,608

REGENERATING A PLATINUM OXIDE DEACTIVATED CATALYST RESULTING FROM USE IN ELIMINATING OXIDES OF NITROGEN FROM GASES

Kamran Aykan, Woodbury, N.J., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Filed Sept. 24, 1968, Ser. No. 762,142
Int. Cl. B01j 11/18, 11/02

U.S. Cl. 252—411 6 Claims
Regenerating a deactivated platinum catalyst by heating a platinum oxide deactivated catalyst on a carrier and passing gas inert in the system under conditions of regeneration over the deactivated catalyst for a time and at a temperature sufficient to cause dissociation of a platinum oxide and reform platinum in metallic form on the carrier.

3,578,609

ION EXCHANGE RESIN CONTAINING ZERO-VALENT METAL

Werner O. Haag, Trenton, and Darrell Duayne Whitehurst, Raritan, N.J., assignors to Mobil Oil Corporation
No Drawing. Filed Oct. 2, 1967, Ser. No. 672,007
Int. Cl. C07c 5/02

U.S. Cl. 252—430 4 Claims
This specification discloses an ion exchange resin containing zero-valent metal. In the preparation thereof, an ion exchange resin is contacted with a reducing agent to fix the reducing agent in the resin. Thereafter, the resin is contacted with a soluble metal compound, the metal being from Groups VIII, I-B, II-B, III-B, IV-B, V-B, VI-B, and VII-B of the Periodic Table. The metal of the compound is thereby reduced to the zero-valent state in situ in the resin. The resulting product may be employed as a catalyst.

3,578,610

PROCESS FOR FABRICATION OF STOICHIOMETRIC URANIUM MONOCARBIDE

Bruce M. Johnson, Michael A. De Crescenti, and James G. Darrah, Wethersfield, Conn., assignors to United Aircraft Corporation, East Hartford, Conn.
No Drawing. Filed Nov. 30, 1960, Ser. No. 72,798
Int. Cl. G21c 21/02; C01g 43/00

U.S. Cl. 264—5 8 Claims
1. In a process for fabrication of stoichiometric uranium monocarbide, the steps of cold-pressing UC in a die in a vacuum under pressures from 40 to 120 tons per square inch, said UC having a carbon content between 4.70% and 4.88% and having less than 0.2% oxygen, and sintering the cold-pressed UC in a vacuum at temperatures between 3500 and 3800° F. for two to four hours in a vacuum between 10⁻⁵ to 10⁻⁶ mm. of Hg.

3,578,611

AROMATIC POLYMERS AND METHOD

Norman Bilow, Los Angeles, and Leroy J. Miller, Canoga Park, Calif., assignors to Hughes Aircraft Company, Culver City, Calif.
No Drawing. Filed Sept. 5, 1967, Ser. No. 665,267
Int. Cl. C08g 33/00, 49/00

U.S. Cl. 260—2 8 Claims
The method of providing commercially useful new aromatic polymer compositions from fused aromatic ring

compounds as anthracene, naphthalene and phenanthrene, and mixtures thereof, including mixtures of same with monomers and/or polymers of biphenyl, terphenyls, quaterphenyls, and other aromatic monomers and phenylene oligomers and polyphenyls with not more than 5 aromatic rings, and the products thereof which are heat curable resins in combination with monofunctional and preferably polyfunctional curing agents which produce reactive electrophilic intermediates, including such products.

3,578,612

POLYURETHANE FOAMS BASED ON DIMER FATTY ACID POLYALKANOLAMIDES

Christian Burba, Lunen, Manfred Drawert, Werne, and Eugen Griebisch, Unna, Germany, assignors to Schering A.G., Berlin and Bergkamen, Germany
No Drawing. Continuation-in-part of applications Ser. No. 700,001, Jan. 24, 1968, and Ser. No. 743,958, July 11, 1968. This application July 24, 1969, Ser. No. 844,650
Claims priority, application Germany, Jan. 31, 1967, P 17 95 024.02

Int. Cl. C08g 22/08, 22/46, 51/72
U.S. Cl. 260—2.5 4 Claims

Foams of a synthetic amide group-containing polyurethane resin formed by reacting and foaming a polymeric fatty acid alkanolamide, or an alkoxylated polymeric fatty acid alkanolamide, with a polyisocyanate. The polymeric fatty acid alkanolamide is made typically by condensing dimerized fatty acid with mono- or di-alkanolamines. The foams have excellent resistance to hydrolysis.

3,578,613

ADHESIVE DIP COMPRISING A RUBBER LATEX AND TRIS(DIPHENYLBENZYL) PHENOL

Wun T. Tai, Monroeville, Pa., assignor to Koppers Company, Inc.
No Drawing. Filed Nov. 29, 1968, Ser. No. 780,278
Int. Cl. C08c 9/16; C08d 9/10


U.S. Cl. 260—3 5 Claims
Adhesive dips containing tris(dihydroxybenzyl)phenol are used to bond textile cords to rubber. The adhesive dips are useful for the bonding of nylon, rayon, and the especially difficult to bond polyester tire cords to rubber, giving excellent adhesive properties.

3,578,614

ALPHA-HYDROXY-CARBOXYLIC ACIDS AS CURING RATE ACCELERATORS FOR CURABLE POLYMER SYSTEMS

Walter R. Wszolek, Sykesville, Md., assignor to W. R. Grace & Co., New York, N.Y.
No Drawing. Filed Oct. 21, 1968, Ser. No. 778,368
Int. Cl. C08d 9/02; C08f 27/06; C08g 22/00

U.S. Cl. 260—13 21 Claims
This invention relates to accelerated curing of a liquid composition comprising a polyene containing at least two reactive unsaturated carbon to carbon bonds per molecule and a polythiol containing at least two thiol groups per molecule, the total combined functionality of (a) the reactive unsaturated carbon to carbon bonds per molecule in the polyene and (b) the thiol groups per molecule in the polythiol being greater than four, in the presence of a novel class of curing rate accelerators from the group consisting of oxalic acid and an α -hydroxy carboxylic acid of the formula



wherein R and R' are independently selected from the group consisting of —CH₂COOH, —CHOHCOOH, hydrogen, aryl, alkyl containing 1–18 carbon atoms.

3,578,615

EPOXY RESIN COATINGS HAVING IMPROVED CATHODIC DISBONDING RESISTANCE

Robert J. Moore, Short Hills, and Roy A. Allen, Iselin, N.J., assignors to Shell Oil Company, New York, N.Y.
No Drawing. Filed Apr. 8, 1968, Ser. No. 719,719
Int. Cl. C08g 30/12

U.S. Cl. 260—18 10 Claims
Epoxy resin powder coatings having improved cathodic disbonding resistance and which can be efficiently applied by fluidized bed techniques comprise (1) a polyepoxide, (2) an epoxy curing agent, (3) a catalyst, and (4) a suitable bonding additive hereinafter more fully described (e.g., barium sulfate, strontium chromate, o-nitrophenol, phosphoric acid, and aminosilanes).

3,578,616

PROCESS FOR CURING POLYEPOXIDES AND RESULTING PRODUCT

Lawrence D. Harry, Midland, Mich., and George A. Sweeney, Erlenbach, Switzerland, assignors to The Dow Chemical Company, Midland, Mich.
No Drawing. Continuation-in-part of application Ser. No. 682,646, Nov. 13, 1968, which is a continuation-in-part of applications Ser. No. 480,128, Aug. 16, 1965, and Ser. No. 657,059, July 31, 1967. This application July 17, 1968, Ser. No. 745,364
Int. Cl. C08g 30/12

U.S. Cl. 260—18 9 Claims
A process for curing a polyepoxide to obtain a clear colorless casting adaptable for optical applications comprising reacting:

- (A) a mixture of (1) epoxy resin and (2) hexahydrophthalic anhydride and
- (B) a curing catalyst composition comprising
 - (1) an equal weight mixture of
 - (a) a metal carboxylate e.g. Zn oleate, Zn or Sn-II 2-ethyl hexoate and Na salicylate
 - (b) triphenyl phosphite
 - (2) the product of reaction at 40 to 100° C. of H₃PO₄ with an aliphatic glycidyl ether in the presence of a solvent such as glycerine, polyethylene glycol or a glycerine initiated polypropylene glycol
 - (3) an amount of hexahydrophthalic anhydride sufficient to bring the total in the system up to 40 to 100 parts by weight of polyepoxide.

3,578,617

COLD WATER-DISPERSIBLE EMULSIONS OF WATER REPELLENT COMPOSITIONS CONTAINING TRIAZINE-FORMALDEHYDE CONDENSATION PRODUCTS

Kwok Toy Louis, Wyckoff, Donald W. Wurmser, Jackson, and Herbert Zaritsky, Toms River, N.J., assignors to Ciba Corporation, Summit, N.J.
No Drawing. Filed Apr. 17, 1969, Ser. No. 817,180
Int. Cl. C08g 9/30

U.S. Cl. 260—21 9 Claims
Cold water-dispersible aqueous emulsions of water repellent compositions containing triazine-formaldehyde condensation products are provided which are comprised of the water repellent composition, a higher molecular weight polyethyleneglycol-alkylphenyl ether, a solvent for the water repellent composition which is water-immiscible, and a second solvent which is miscible with the water-immiscible solvent and soluble in water. The emulsions of this invention are especially useful for imparting water repellence to textiles.

3,578,618

**VINYL ACETATE-ETHYLENE COPOLYMER
AQUEOUS PAINT COMPOSITIONS**

Herbert P. Beardsley, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Continuation-in-part of application Ser. No. 664,285, Aug. 30, 1967. This application July 7, 1969, Ser. No. 839,710

Int. Cl. C08f 37/00

U.S. Cl. 260—17

1 Claim

Aqueous paint compositions containing vinyl acetate-ethylene copolymers having 5–40 percent ethylene are disclosed. Also, there are disclosed paint compositions wherein the copolymers contain small quantities of carboxylic acids, such as acrylic and methacrylic, which have improved freeze-thaw stability.

3,578,619

**PROCESS OF PREPARING METAL CHELATES
OF β -KETOESTERS**

James A. Reeder, Poland, Ohio, assignor to
British Columbia Research Council

No Drawing. Filed Feb. 28, 1969, Ser. No. 803,471
Int. Cl. C07c 11/26; C07d 107/00, 3/64

U.S. Cl. 260—22

23 Claims

An improved process for preparing metal chelates of β -ketoesters derived from higher alcohols, glycols, polyols or polymers containing hydroxyl groups which comprises reacting a higher alcohol, glycol, polyol or polymer containing hydroxyl groups with a metal chelate of a β -ketoester derived from a volatile alcohol, so that a transesterification takes place with elimination of the volatile alcohol.

3,578,620

**COLOR STABILIZED UNSATURATED
INTERPOLYMERS**

Paul J. Prucnal, Monroeville, Pa., assignor to
PPG Industries, Inc., Pittsburgh, Pa.

No Drawing. Filed Apr. 2, 1969, Ser. No. 812,888
Int. Cl. C08f 45/58

U.S. Cl. 260—23.7

15 Claims

This invention relates to the stabilization and especially the color stabilization of certain unsaturated hydrocarbon polymers which are non-rubbery interpolymers of a cyclic polyene and at least one monoolefin, said interpolymer having an essentially saturated carbon chain containing a substantial proportion of the total carbon atoms in the polymer molecule and containing sufficient ethylenically unsaturated groups in the polymer molecule to permit substantial curing of films thereof by an oxidative mechanism, said interpolymers having an intrinsic viscosity of 0.6 or less. The stabilizers, which do not prevent oxidative cure, are a combination of epoxides such as epoxidized soybean oil or epoxidized higher fatty acid esters and tri-(alkylphenyl)phosphites.

3,578,621

**DIESTERS EXHIBITING INTERNAL-EXTERNAL
LUBRICATING PROPERTIES IN STRUCTURAL
RESINS**

Christian H. Stapfer, Newtown, Pa., assignor to Carlisle Chemical Works, Inc., Reading, Ohio

No Drawing. Filed Aug. 27, 1968, Ser. No. 755,736
Int. Cl. C08f 45/36; C08g 51/36

U.S. Cl. 260—31.6

10 Claims

Esters, which have a formula corresponding to



wherein R is an alkyl radical having 15 to 30 straight chain carbon atoms and R_1 is an alkylene radical or alkenylene radical having 2 to 12 straight chain carbon atoms, have been found to unexpectedly act as combined internal and external lubricants for structural resins.

3,578,622

SPRAYABLE ADHESIVE

Francis W. Brown, West St. Paul, and Leon V. Kremer, Cottage Grove, Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.
No Drawing. Continuation-in-part of application Ser. No. 702,807, Feb. 5, 1968. This application Sept. 12, 1969, Ser. No. 857,536

Int. Cl. C08f 45/30

U.S. Cl. 260—33.8

20 Claims

A sprayable adhesive composition is provided which contains a higher concentration of acrylate polymer than was previously possible in sprayable formulations, the acrylate being an elastomeric, crosslinked polymer further characterized as having an organic solvent soluble portion and a predominating organic solvent insoluble portion.

3,578,623

**COMPOSITIONS OF SATURATED POLYESTERS,
INORGANIC SOLIDS, AND CYCLIC CARBONATES**

Klaus Weissner, Kelkheim, Taunus, and Rudolf Uebe, Eschborn, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Filed Mar. 21, 1969, Ser. No. 809,432
Claims priority, application Germany, Apr. 6, 1968, P 17 69 119.9

Int. Cl. C08g 51/04

U.S. Cl. 260—40

15 Claims

Thermoplastically processible moulding compositions of linear saturated polyesters of aromatic dicarboxylic acids, inert inorganic solid substances and cyclic carbonates that yield shaped articles free from flash.

3,578,624

**CLAY FILLED, SULFUR-CURED ELASTOMERS
COMPOUNDED WITH HYDROXYL-TERMI-
NATED BUTADIENE POLYMERS**

Edward Fuller Cluff, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Filed Apr. 1, 1969, Ser. No. 812,289
Int. Cl. C08c 11/14; C08d 13/26

U.S. Cl. 260—41.5

10 Claims

An elastomeric composition comprising (a) a copolymer of at least one α -monoolefin, and at least one nonconjugated diene having at least one readily polymerizable double bond, (b) a hydroxyl-terminated liquid polymer containing at least 60% by weight of butadiene units, (c) a clay filler and (d) a sulfur curing system. The hydroxyl-terminated liquid polymer improves the physical properties of the vulcanizate produced therefrom.

3,578,625

**STABILIZED COMPOSITION OF
POLYPHENYLENE OXIDE**

Seizo Nakashio, Nishinomiyashi, and Isao Maruta, Ibaragi-shi, Japan, assignors to Sumitomo Chemical Company, Ltd., Osaka, Japan
No Drawing. Filed Aug. 29, 1968, Ser. No. 756,317
Claims priority, application Japan, Sept. 2, 1967, 42/56,507

Int. Cl. C08g 51/62

U.S. Cl. 260—45.75

8 Claims

The present composition of polyphenylene oxide has an improved stability against deterioration of quality and in discoloration, and comprises a polyphenylene oxide, 0.005 to 5% by weight of at least one kind of hindered phenol and 0.005 to 5% by weight of at least one member selected from the group consisting of trialkyl phosphites, triaryl phosphites, trialkyl thiophosphites, triaryl thiophosphites, thiophosphites, thioethers of carboxylic acid esters, thioethers, metal alkylthiocarbamates and metal arylthiocarbamates.

3,578,626

**PROCESS FOR THE POLYMERIZATION OF
ACETYLENE COMPOUNDS**

Walter A. Kornicker, Brookline, Mass., assignor to
Monsanto Company, St. Louis, Mo.
Original application July 30, 1965, Ser. No. 475,918.
Divided and this application Feb. 24, 1969, Ser. No. 832,516

Int. Cl. C08f 9/00, 9/02

U.S. Cl. 260—94.1

1 Claim

As a new composition of matter solid linear crystalline trans-polyacetylene having nickel therein. The product is produced by a process of polymerizing acetylene or acetylenic compounds by subjecting to electrolysis the complex compound of a nickel dihalide and an electron donor and acetylene or an acetylenic compound or mixtures thereof in the presence of an inert polar solvent.

3,578,627

**PROCESS FOR TREATING HIGH VINYL LIQUID
POLYBUTADIENE WITH SULFURIC ACID**

Stephen Boutsicaris, Akron, Ohio, assignor to The Firestone Tire & Rubber Company, Akron, Ohio
No Drawing. Filed June 16, 1969, Ser. No. 833,689
Int. Cl. C08d 5/02; C08f 27/00

U.S. Cl. 260—94.4

12 Claims

The process disclosed herein comprises the treatment of a high-vinyl liquid polybutadiene with concentrated sulfuric acid to convert the liquid polybutadiene to a tough thermoplastic elastomer. The liquid polybutadiene has at least 60% of the repeating units therein of the pendent vinyl type, and has an average molecular weight of 2,000–10,000. The polybutadiene is treated while in dilute solution in a hydrocarbon solvent which is inert to sulfuric acid, such as toluene, benzene, xylene, etc. The sulfuric acid is of at least 80% concentration, preferably at least 95%, and is used in a proportion of 5–15 parts by weight per 100 parts of polymer.

3,578,628

**PROCESS FOR TREATING CELLULOSIC DIGEST-
ING LIQUOR CONTAINING SOAP**

Sun W. Chun, Pittsburgh, Pa., and William H. Friend, Edison, N.J., assignors to Union Camp Corporation, New York, N.Y.
No Drawing. Filed Apr. 21, 1969, Ser. No. 818,049
Int. Cl. C09f 1/00

U.S. Cl. 260—97.7

3 Claims

Process for treating a cellulosic digesting liquor containing soap with a liquid hydrocarbon and alcohol to separate the soap from the liquor.

3,578,629


**PROCESS FOR PREPARING REINFORCED
POLYOLEFINS**

Robert J. McManis, Des Peres, Mo., assignor to
Monsanto Company, St. Louis, Mo.
No Drawing. Filed May 21, 1968, Ser. No. 730,896
Int. Cl. C08f 45/04, 45/14

U.S. Cl. 260—41

19 Claims

Process for preparing reinforced polyolefins by a Ziegler-type low pressure polymerization process comprising conducting the polymerization of a monomeric α -olefin in the presence of a filler which has been pretreated and prereacted with an organosilane of the formula



where X is a hydrolyzable group capable of reacting with a hydroxyl group, Y is a monovalent hydrocarbon group, R is a divalent hydrocarbon group, Z is a group containing ethylenic unsaturation, a is an integer from 1 to 3, b is an integer from 0 to 2, and c is an integer from 1 to 3 provided that the sum of $a+b+c$ equals 4.

3,578,630

**GLASS FILLED RANDOM COPOLYMERS OF AN
OLEFIN AND AN UNSATURATED ACID**

James K. Rieke and Frank H. Justin, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.
No Drawing. Continuation-in-part of application Ser. No. 531,381, Mar. 3, 1966. This application Feb. 14, 1969, Ser. No. 799,486

Int. Cl. C08f 45/10

U.S. Cl. 260—41

8 Claims

Polymer compositions having improved tensile properties and improved impact resistance comprising a blend of between about 10 and about 40 weight percent glass fibers and between about 60 and about 90 weight percent of a random copolymer of an olefin such as ethylene and an ethylenically unsaturated carboxylic acid such as acrylic acid. The polymer compositions can be molded or extruded to produce useful articles of manufacture including gears, sprockets, washing machine agitators, gear housings, and the like.

3,578,631

**METHOD OF PRODUCING MODIFIED
POLYARYLATES**

Vasily Vladimirovich Korshak, Ulitsa Gubkina 4, kv. 81; Svetlana Vasilievna Vinogradova, Jugo-Zapad kvartal 42-a, korpus 1, kv. 35; and Dzidra Rudolfovna Tur, Ulitsa Vavilova 30-a, kv. 120, all of Moscow, U.S.S.R.
No Drawing. Filed Mar. 1, 1967, Ser. No. 619,560
Claims priority, application U.S.S.R., Mar. 1, 1966, 1,058,760

Int. Cl. C08g 33/04

U.S. Cl. 260—47

1 Claim

Modified polyarylates which are polyhydrazide-polyarylates are produced by condensing dicarboxylic acyl chlorides with bisphenols and hydrazine or dihydrazides of dicarboxylic acids. The modified polyarylates may be further converted to poly-1,3,4-oxadiazol polyarylates by heating in vacuum to 250–350° C.

3,578,632

**CURING POLYEPOXIDES WITH MIXED
CATALYSTS**


Alfred Kuhlkamp, Hofheim, Taunus, and Edgar Fischer and Ernst Nolken, Frankfurt am Main, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Filed Aug. 8, 1968, Ser. No. 751,031
Claims priority, application Germany, Aug. 23, 1967, F 53,308

Int. Cl. C08g 30/10

U.S. Cl. 260—47

8 Claims

Liquid polyepoxides or solvent solutions of solid polyepoxides having 2 to 10 epoxy groups and preferably epoxide equivalents of 100 to 300 are cured without application of external heat by mixing them with a catalyst system consisting essentially of a mixture of a Lewis acid and a phosphorus compound of the formula



in which R and R' represent alkyl, aryl, cycloalkyl, alkylaryl, aralkyl, alkoxyalkyl, alkoxyaryl, hydroxyalkyl, hydroxyaryl, hydroxyaralkyl or alkenyl. Epoxide resins are thus obtained by a room temperature cure which exhibit good resistance to alkalies. The products may be used for making glass fiber reinforced articles and for coating such materials as paper, metals, wood, textiles and plastics.

wherein R is a divalent aliphatic, cycloaliphatic or aromatic group; and R' is divalent aliphatic. This patent further describes the procedures for the preparation of these novel polymers and uses of these polymers.

3,578,645

LACTONE POLYMERS AND PROCESS OF PREPARING

William Lee Hergenrother, Akron, Ohio, assignor to The Firestone Tire & Rubber Company, Akron, Ohio
No Drawing. Filed Sept. 25, 1969, Ser. No. 861,190
Int. Cl. C08f 15/28

U.S. Cl. 260—78.5

12 Claims


This invention relates to polymers produced from vinyl halide or vinylidene halide by reaction with a dialkyl maleate or fumarate, with pyrolysis of the polymer to form gamma lactone groups in the polymer chain. The invention includes the product and the process.

3,578,646

VINYL MONOMER POLYMERIZATION PROCESS
Charles W. Moberly and Gerald R. Kahle, Bartlesville, Okla., assignors to Phillips Petroleum Company
Continuation-in-part of application Ser. No. 778,709, Nov. 25, 1968. This application Oct. 29, 1969, Ser. No. 872,137
Int. Cl. C08f 1/04, 15/30, 45/00

U.S. Cl. 260—85.7

9 Claims



Pourability of polymers of vinyl monomers is improved by catalytic vapor phase polymerization of vinyl monomers in the absence of substantial amounts of solvent or diluent and in the presence of certain pourability modifiers, which may also improve the color of the product polymer. The pourability of polymers formed by liquid phase bulk polymerization of vinyl monomers can be improved by these modifiers.

3,578,647

CHEMICAL CROSSLINKING SCORCH PREVENTING ADDITIVES AND PROCESS THEREFOR

Razmic S. Gregorian, Silver Spring, and Charles C. Kirk, Laurel, Md., assignors to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed May 6, 1968, Ser. No. 727,008
Int. Cl. C08f 27/00

U.S. Cl. 260—86.7

4 Claims

This invention relates to the prevention of scorch in a process for chemically crosslinking ethylene-containing

homopolymers and copolymers by free radical generating crosslinking agents by the addition of chain transfer agents to the system.

3,578,648

PROCESS FOR THE PREPARATION OF VINYL CHLORIDE POLYMERS

Susumu Taima and Shigeo Nakada, Uozu-shi, Japan, assignors to Nippon Carbide Kogyo Kabushiki Kaisha, Tokyo, Japan

No Drawing. Filed Nov. 22, 1968, Ser. No. 778,299

Claims priority, application Japan, June 18, 1968, 43/41,661

Int. Cl. C08f 1/13, 3/30, 15/00

U.S. Cl. 260—87.5

8 Claims

Emulsion type polymerization of vinyl chloride in an aqueous medium in the presence of a polymerization initiator is divided into two steps: the first step of polymerizing monomers to prepare polymers suitable as seeds and the second step of polymerizing fresh monomers using the above polymers as seeds to produce the final product polymers. And in each of the both steps respectively, is used a specified emulsifier system comprising (a) a higher fatty acid of carbon number of 10–18, (b) a high molecular surface active agent represented by the formula



and (c) disodium phosphate or sodium bicarbonate. The final product polymers require no salting-out procedure and can be readily dehydrated. And the polymers can form a plastisol which shows a very low viscosity and is excellent in age stability, heat-stability and transparency. Thus the polymers are quite suitable for paste resins.

3,578,649

PREPARATION OF VINYL POLYMERS

Leon Badguerhanian, Montlignon, and Thomas Kemp, Bois-Colombes, France, assignors to Produits Chimiques Pechiney Saint-Gobain, Paris, France


Filed June 23, 1964, Ser. No. 377,230

Claims priority, application France, Mar. 10, 1964, 966,799

Int. Cl. C08f 1/11, 3/00, 3/30

U.S. Cl. 260—92.8

6 Claims



Vinyl monomers, of which vinyl chloride is exemplary, are polymerized in suspension in aqueous medium and the conditions of polymerization produce superior products by withdrawing vaporized product, condensing it, and returning it to the suspension, producing, by aid of exterior heat exchange, equality of internal and external temperature. The product has notable superiority, especially in its acceptance of plasticizers and other modifiers.

3,578,650

METHOD FOR CARRYING OUT REACTIONS OF UNSATURATED HYDROCARBONS AT LOW TEMPERATURES

Maurice M. Mitchell, Jr., Wallingford, Pa., Harold M. Fisher, Redstone Arsenal, Ala., and Edward S. J. Tomezko, Media, Pa., assignors to Atlantic Richfield Company, New York, N.Y.

No Drawing. Filed Feb. 20, 1969, Ser. No. 801,205

Int. Cl. C07c 5/10, 15/00; C08f 29/00

U.S. Cl. 260—93.7

3 Claims

Method for carrying out alkylation, polymerization or hydrogenation reactions of unsaturated hydrocarbons by contacting the unsaturated hydrocarbon such as an olefin or aromatic or combination thereof with tungsten hexafluoride at temperatures between 0° C. and 50° C.

3,578,651

ACYLATED LIGNOSULFONATES

Charles H. Ludwig, Bellingham, Wash., assignor to Georgia-Pacific Corporation, Portland, Oreg.

No Drawing. Filed May 6, 1968, Ser. No. 727,053

Int. Cl. C07g 1/00

U.S. Cl. 260—124

15 Claims

A process for the acylation of lignosulfonate by the reaction, in an organic solvent, of a trialkylammonium lignosulfonate salt with a halide of carboxylic or sulfonic acid and products thereof.

3,578,652

RED PHENYLAZO NAPHTHOL DYESTUFF

Gustav E. Rast, Hamburg, and Russell I. Steiner, Williamsburg, N.Y., assignors to Allied Chemical Corporation, New York, N.Y.

No Drawing. Filed Oct. 20, 1967, Ser. No. 676,741

Int. Cl. C09d 45/00, 29/16

U.S. Cl. 260—151

10 Claims

Monoazo dyestuffs are prepared by coupling a 3-diazo-6-alkoxybenzene sulfonic acid and an α -naphthol disulfonic acid and precipitating the dye, either as the free acid or as an ammonium or metal salt. The trisodium salts are preferred because of their low toxicity to warm-blooded animals. The dyestuffs are useful as colorants for foods, pharmaceuticals, cosmetics, and the like, and form aluminum lakes useful as pigments for plastics.

3,578,653

MONOAZONAPHTHOTRIAZOSTILBENE DYESTUFFS

William E. Wallace, R.D. 1, Box 190A, Rensselaer, N.Y. 12144


No Drawing. Filed Dec. 18, 1967, Ser. No. 691,141

Int. Cl. C07c 7/06; C09b 43/00; D21h 1/46

U.S. Cl. 260—157

5 Claims

A monoazonaphthotriazolostilbene dyestuff, especially useful for dyeing paper, having in free acid form the formula



where n has a value of 1 or 2, R¹ is alkyl or phenyl, R² is R¹, alkoxy or phenoxy, or R¹ and R² jointly represent —NHCONH—. Use of these dyes results in dyeings having bright, pure and strong reddish to greenish-yellow shades with good fastness properties.

3,578,654

MONOAZO AND DISAZO DISPERSION DYESTUFFS CONTAINING A 2-HYDROXY - 5- β -CYANO-, β -LOWER ALKOXYCARBONYL- OR β -CARBOXY-AMIDOETHYL BENZENE GROUP

François Favre, Basel, Switzerland, assignor to J. R. Geigy A.G., Basel, Switzerland

No Drawing. Filed Nov. 6, 1967, Ser. No. 680,992


Claims priority, application Switzerland, Nov. 10, 1966, 16,196/66

Int. Cl. C09b 29/00, 29/12, 31/06

U.S. Cl. 260—186

8 Claims

Monoazo and disazo dyestuffs are described which are characterized by a novel coupling component of the formula



wherein Y represents the cyano group or a functional derivative of the carboxyl group, which does not dissociate acid in water and the benzene ring may contain further substituents; these novel dyestuffs must be free from water-solubilizing groups that dissociate acid in water, and are useful as dispersion dyestuffs for the dyeing of hydrophobic and particularly of polyglycol terephthalate and cellulose ester fibres. Their affinity for polyester fibers, particularly polyglycol terephthalate, is strong and the dyed fibers have good fastness to light and sublimation, their coloration being generally yellow, greenish yellow, orange or yellow-brown.

3,578,655

CARBOHYDRATE AGENT OF HIGH WATER RETENTION POWER, PROCESS OF MAKING SAME, AND COMPOSITION CONTAINING SAME

Joachim König and Günter Padberg, Hamburg-Rahlstadt, Germany, assignors to Chemische Fabrik Promonta GmbH, Hamburg, Germany


Filed Aug. 16, 1967, Ser. No. 661,110

Claims priority, application Germany, Aug. 19, 1966, C 39,914

Int. Cl. C07c 47/18

U.S. Cl. 260—209

11 Claims



The reaction product of a carbohydrate such as a sugar, with an alkaline agent such as an alkali metal hydroxide solution has a high water retention power which is about as high as that of the neutral skin sugar fraction obtained by extraction of the stratum corneum and far superior to that of hygroscopic compounds such as glycerol, glycols, the water-soluble amino acid fraction of the skin and others which, although they attract water, permit rapid evaporation thereof.

3,578,656

METHOD OF MAKING ALLANTOIN POLY-GALACTURONIC ACID COMPOUNDS

Sebastian B. Mecca, Abington, Pa., assignor to Schuylkill Chemical Company, Philadelphia, Pa.
No Drawing. Filed Feb. 24, 1969, Ser. No. 801,763
Int. Cl. C07c 95/04

U.S. Cl. 260—209 8 Claims
Allantoin polygalacturonic acid compounds are prepared by dissolving a salt of allantoin and a salt of polygalacturonic acid in water containing a base, lowering the pH of the resulting solution with an acid or an aluminum salt to precipitate allantoin polygalacturonic acid when an acid is used or aluminum allantoin polygalacturonate when an aluminum salt is used, and recovering the precipitate.

3,578,657

ANTILIPAEMIC SULPHATED POLYSACCHARIDE

René Ricard, Jesus y Maria 27, and Miguel Margarit Tayá, Manuel Girona 56, both of Barcelona, Spain
No Drawing. Filed July 29, 1968, Ser. No. 748,204
Claims priority, application Spain, Aug. 9, 1967, 343,957
Int. Cl. C07c 69/32

U.S. Cl. 260—234 4 Claims
An antilipaemic sulphated polysaccharide active under oral administration, which consists of a salt, preferably an alkaline salt, of a sulphated hydrodextran, with an average content of from 1 to 3 —SO₃— groups per monosaccharide groups and being essentially non-reducing as determined by the Somogyi method, having preferably an intrinsic viscosity of between 0.02 and 0.07 at 25° C. and containing a proportion of sulphur of from 10 to 20% by weight.

3,578,658

N'-SUBSTITUTED N-ARYLSULFONYL UREAS

Henri Dietrich, Arlesheim, Basel-Land, Switzerland, assignor to Geigy Chemical Corporation, Ardsley, N.Y.
No Drawing. Filed Aug. 21, 1967, Ser. No. 661,823
Claims priority, application Switzerland, Aug. 25, 1966, 12,360/66
Int. Cl. C07d 41/04

U.S. Cl. 260—239 16 Claims
N - arylsulfonyl - decahydro - 1H - 3 - benzazepine - 3 - carboxamides and pharmaceutically acceptable salts thereof with bases, which compounds have useful hypoglycaemic action, as well as starting materials for their production; therapeutic compositions containing these carboxamides or their pharmaceutically acceptable salts and processes of producing hypoglycaemic effects in mammals. As illustrative embodiment is N-(p-tolylsulfonyl)-decahydro-1H-3-benzazepine-3-carboxamide.

3,578,659

18-NOR-14β-PREGNANO-[13,14-f]-HEXAHYDRO-1,4-OXAZEPINES

Hans-Detlef Berndt, Berlin, Germany; Paul Buchschacher, Arlesheim, Switzerland, Ulrich Eder, Berlin, Germany, Andre Furlenmeier and Andor Furst, Basel, Switzerland, Ulrich Kerb, Berlin, Germany, Marcel Muller, Frenkendorf, Switzerland, and Rudolf Wiechert, Berlin, Germany, assignors to Hoffmann-La Roche Inc., Nutley, N.J.
No Drawing. Filed Mar. 28, 1969, Ser. No. 811,626
Claims priority, application Germany, Apr. 6, 1968, P 17 68 162.8
Int. Cl. C07c 173/00

U.S. Cl. 260—239.55 28 Claims
18 - nor - 14β - pregnano - [13,14-f] - hexahydro - 1,4 - oxazepines and methods for their preparation are described. These compounds are valuable pharmaceuticals in that they exhibit blood pressure reducing and diuretic

effects. They also possess a positive inotrope and myotrope activity, promote the blood flow to blood vessels surrounding the heart and also the stroke minute volume of the heart.

3,578,660

2-ACYLOXYCEPHALOSPORIN COMPOUNDS

Robin D. G. Cooper, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,686
Int. Cl. C07d 99/24

U.S. Cl. 260—243 19 Claims
Reaction of a 7-(protected amino)cephalosporin ester with a lead tetraacylate compound, followed by deesterification, to yield the corresponding 2-acyloxy-7-(protected amino)cephalosporin compound which is useful as an antibiotic.

3,578,661

PROCESS FOR THE PREPARATION OF 7-[α-(4-PYRIDYLTHIO)ACETAMIDO]CEPHALOSPORANIC ACIDS

Robert Edward Havranek, Liverpool, and Leonard Bruce Crast, Jr., Clay, N.Y., assignors to Bristol-Myers Company, New York, N.Y.
No Drawing. Filed June 2, 1969, Ser. No. 829,707
Int. Cl. C07d 99/24

U.S. Cl. 260—243 6 Claims
7-[α-(4-pyridylthio)acetamido]cephalosporanic acid and related compounds having the same side chain and the pharmaceutically acceptable salts thereof are valuable antibacterial agents for use in mammals, including man. This disclosure relates to a new process for the preparation of such compounds, an example of which comprises reacting 7-aminocephalosporanic acid with 1-oxo-4-pyridylmercaptoacetyl chloride followed by mild reduction to produce 7-[α-(4-pyridylthio)acetamido]cephalosporanic acid.

3,578,662

ISOCYANURATE MANUFACTURE

John H. Cornell, Jr., Arlington, Mass., assignor to Monsanto Research Corporation, St. Louis, Mo.
No Drawing. Continuation-in-part of application Ser. No. 165,249, Jan. 9, 1962. This application Oct. 10, 1967, Ser. No. 675,011
Int. Cl. C07d 55/38

U.S. Cl. 260—248 9 Claims
A process for producing trimers of isocyanates which involves contacting a monoisocyanate mixture thereof with a catalyst system comprising a basic compound and a hydrocarbon carbonylic compound of from 1-12 carbon atoms. These trimers are useful for the manufacture of resins, adhesives, impregnants, and cast or molded materials.

3,578,663

PREPARATION OF CYANURIC CHLORIDE

Wilhelm Gruber and Wolfgang Kleine-Doepke, Darmstadt, Germany, assignors to Rohm & Haas G.m.b.H., Darmstadt, Germany
No Drawing. Filed Dec. 3, 1968, Ser. No. 780,911
Claims priority, application Germany, Dec. 15, 1967, P 16 95 658.4
Int. Cl. C07d 55/42


U.S. Cl. 260—248 3 Claims
The yield of cyanuric chloride is increased and the life of an activated charcoal catalyst used in preparing cyanuric chloride by contact of cyanogen and chlorine in the gas phase at a temperature of from about 350° C. to about 750° C. is considerably lengthened by pretreatment of the activated charcoal catalyst for removal therefrom of metal compounds, preferably with a metal-solubilizing acid such as aqueous hydrochloric acid, formic acid, acetic acid or dilute nitric acid.

3,578,664

PROCESS FOR THE RECOVERY OF MELAMINE FROM A SYNTHESIS GAS MIXTURE CONTAINING HOT MELAMINE VAPOUR

Petrus J. C. Kaasenbrood, Sittard, Netherlands, assignor to Stamicarbon N.V., Heerlen, Netherlands
Filed June 30, 1969, Ser. No. 837,479
Claims priority, application Netherlands, June 29, 1968, 6809253
Int. Cl. C07d 55/24

U.S. Cl. 260—249.7 4 Claims



group at the 4 position to a hydroxy substituent and then to an acyloxy group. The thus formed N - t - butyl - 1 - acyl - 4 - acyloxyhexahydronicotinamide is then treated with a noble metal to effect the simultaneous removal of the substituents in the 1,4 position and aromatization of the ring to form N - t - butylnicotinamide, the latter which upon hydrolysis yields nicotinamide.

3,578,671 OXAZOLES

Kevan Brown, Woodley, England, assignor to John Wyeth & Brothers Limited, Taplow, Maidenhead, Berkshire, England

No Drawing. Filed Nov. 6, 1967, Ser. No. 680,990
Int. Cl. C07d 85/44, 99/02

U.S. Cl. 260—307

13 Claims

A class of oxazole-2-polycarbon aliphatic monocarboxylic acids arylated at the 4- and/or 5-positions in the oxazole ring is described. Compounds of this class are active anti-inflammatory agents.

3,578,672

2-PROPARGYLAMINO-5-PHENYL-2-OXAZOLIN-4-ONE AND DERIVATIVES

Cheuk Man Lee and Bruce Wayne Horrom, Waukegan, Ill., assignors to Abbott Laboratories, North Chicago, Ill.

No Drawing. Filed Nov. 3, 1969, Ser. No. 873,688

Int. Cl. C07d 85/40

U.S. Cl. 260—307

12 Claims

2-propargylamino-5-phenyl-2-oxazolin-4-one and derivatives thereof were found to be effective anti-depressants when administered in oral dosages of 0.5–20 mg./kg. to warm-blooded animals. The new compounds are prepared by condensing 2-amino-5-phenyl-2-oxazolin-4-one with propargylamine or the corresponding N- and/or 1-mono- or disubstituted alkyl derivatives thereof in the presence or absence of an inert reaction medium.

3,578,673

3-NITROARYL-4-HALOISOXAZOLES AND METHOD FOR PREPARING SAME

Herman A. Bruson, Woodbridge, and Howard L. Plant, Milford, Conn., assignors to Olin Corporation


No Drawing. Filed Sept. 30, 1968, Ser. No. 775,972

Int. Cl. C07d 85/22

U.S. Cl. 260—307

2 Claims

The nitration of aryl-2,2-dihalocyclopropanes in the presence of higher oxides of nitrogen, principally dinitrogen tetroxide, gives 3-nitroaryl-4-haloisoxazoles by a new reaction which can be formulated as follows:



where R is a substituted aryl radical and X is chlorine or bromine. These new compounds are useful as fungicides, insecticides or herbicides, and as intermediates for dye-stuffs.

3,578,674

DERIVATIVES OF TETRAZOLYL ALKANOIC ACIDS

Robert Thomas Buckler, Elkhart, Ind., assignor to Miles Laboratories, Inc., Elkhart, Ind.

No Drawing. Filed Dec. 24, 1969, Ser. No. 888,069

Int. Cl. C07d 55/56

U.S. Cl. 260—308

5 Claims

A series of bifunctional amide derivatives of omega-5-aryl-2-tetrazolylalkanoic acids. These compounds are useful as anti-inflammatory agents.

3,578,675

2-(3'-FLUORO-2'-NAPHTHYL)-BENZIMIDAZOLES

Dale R. Hoff, Cranford, and Louis H. Peterson, Woodbridge, N.J., assignors to Merck & Co., Inc., Rahway, N.J.

No Drawing. Continuation of application Ser. No. 527,520, Feb. 15, 1966. This application June 9, 1969, Ser. No. 834,593

Int. Cl. C07d 49/38

U.S. Cl. 260—309.2

3 Claims

Anthelmintically active benzimidazoles having an o-fluoronaphthyl group at the 2-position are prepared by a variety of processes including reaction of an o-nitroaniline or o-phenylenediamine with 3-fluoro-2-naphthoic acid or an equivalent thereof wherein the carboxylic acid radical is derivatized to a radical such as an ester, imidoester, amide, carbonyl halide or nitrile.

3,578,676

BENZIMIDAZOLE-2-CARBAMATES SUBSTITUTED ON THE BENZENE RING WITH AN ACYLOXY-ALKYL GROUP

George L. Dunn, Wayne, Pa., assignor to Smith Kline & French Laboratories, Philadelphia, Pa.

No Drawing. Filed June 21, 1968, Ser. No. 738,842

Int. Cl. C07d 49/38

U.S. Cl. 260—309.2

9 Claims

Benzimidazolyl carbamic acids and substituted on the benzene nucleus by carboxylated alkyl and alkoxy groups are disclosed as having activity against helminthiasis in animals. They may be prepared synthetically starting with an appropriate p-aminophenyl alkyl alcohol, proceeding through the alcoholic phenylene diamine to a hydroxy-alkyl-2-carbomethoxyaminobenzimidazole.

3,578,677

PROCESS FOR PREPARING 2,3,5,9b-TETRAHYDRO-1H-IMIDAZO[2,1-a]ISOINDOL-5-OLS

Theodore S. Sulkowski, Narberth, Pa., assignor to American Home Products Corporation, New York, N.Y.

No Drawing. Filed May 24, 1968, Ser. No. 731,740

Int. Cl. C07d 49/34

U.S. Cl. 260—309.7

3 Claims

This invention concerns 2,3,5,9b - tetrahydro - 1H - imidazo[2,1-a]isoindol - 5 - ols which are pharmacologically active as anorexants and to a process for their preparation.

3,578,678

HYDROXYCARBAZOLE DIONES

Ruddy Littell, Rivervale, and George Rodger Allen, Jr., Old Tappan, N.J., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed May 9, 1969, Ser. No. 823,512

Int. Cl. C07d 27/68

U.S. Cl. 260—315

4 Claims

The preparation of 4a,7,8,9a-tetrahydro-9a-hydroxycarbazole-3,4-(4H,6H)-diones by reaction of a 2-trifluoromethyl-1,4-benzoquinone with an amino or lower alkyl-amino-2-cyclohexen-1-one, is described. The compounds are physiologically active on the central nervous system and are useful as tranquilizers.

3,578,679

DECENYLSUCCINAMIC ACID AND IMIDE FROST AND FREEZE PREVENTATIVE COMPOUNDS

Paul J. Caruso, Philadelphia, Pa., and Pieter J. C. Kuiper, Riverside, Calif., assignors to Amchem Products, Inc., Ambler, Pa.

Filed Aug. 3, 1967, Ser. No. 658,179

Int. Cl. C07c 101/24; C07d 27/10

U.S. Cl. 260—326.5

4 Claims

Decenylsuccinamic acid and imide frost and freeze preventative compounds and method of use involving the

compounds N,N-dimethyl-decenylsuccinamic acid; N-dimethylamino - decenylsuccinamic acid; and N - dimethylamino-decenylsuccinimide. The application to crops of any of these compounds in sufficient amounts as present in aqueous solution by conventional spray equipment enables such crops to become resistant to the damaging effects of cold temperatures.

3,578,680

PHOTOCHROMIC COMPOUND

Hisatake Ono and Chiaki Osada, Saitama, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed June 10, 1968, Ser. No. 735,896


Claims priority, application Japan, June 9, 1967, 42/36,877

Int. Cl. C07d 27/38

U.S. Cl. 260—326.11

7 Claims

A photochromic compound which exhibits the ability to change color under the influence of exciting radiation represented by the general formula



R₁ can be hydrogen, a halogen, a cyan group, an alkoxy group having from 1 to 8 carbon atoms and an alkyl group having from 1 to 8 carbon atoms. R₂ may be either hydrogen or a halogen.

Several specific compounds are also described in the disclosure.

3,578,681

SYNTHESIS OF THIOXANE

Clifford H. Mihm, deceased, late of Borger, Tex., by Adeline M. Mihm, administratrix, Borger, Tex., assignor to Phillips Petroleum Company

No Drawing. Filed Nov. 1, 1968, Ser. No. 773,978

Int. Cl. C07d 89/14

U.S. Cl. 260—327

3 Claims

Thioxane is synthesized by reaction of beta-mercaptoethanol and 1,2-ethanedithiol employing a silicone catalyst. The silicone catalyst is a silicone rubber or grease on a solid support disposed in a column.

3,578,682

2,5-BIS-(2-N-LOWER ALKYL AMINO ISOPROPYL)-1,3,4-TRITHIOLANES AND PROCESS FOR THE PREPARATION THEREOF

Arthur B. Ash, Lathrup Village, and Calvin L. Stevens and Anica Markovac, Detroit, Mich., assignors to Ash Stevens, Inc., Detroit, Mich.


No Drawing. Filed Mar. 20, 1969, Ser. No. 809,012

Int. Cl. A61k 27/00; C07d 77/00


U.S. Cl. 260—327

3 Claims

Dimercapto compounds characterized as alpha,alpha-dimethyl-beta,beta-dimercapto-N-lower alkyl-(phenyl and substituted phenyl) ethylamines of the structural formula:




where R is phenyl and substituted phenyl and R₁ is lower alkyl containing 1 to 8 carbon atoms are described. Tri-thiolane condensation derivatives of the dimercapto compounds (I) prepared by oxidation with the elimination of hydrogen sulfide are also described. The dimercapto compounds (I) are generally prepared by reacting an alpha, alpha-dimethyl-beta-N-lower alkyl imine-(phenyl and substituted phenyl) ethylamine of the structural formula:



(III)

where R and R₁ are as in the dimercapto compounds (I) and R₂ is a lower alkyl group containing 1 to 8 carbon atoms with hydrogen sulfide in an inert anhydrous polar organic solvent for the imino compounds (III) at temperatures less than the decomposition temperature of the dimercapto compounds (I) and until (I) is formed and precipitates from the reaction mixture. The imino compounds (III) are preferably prepared by reacting a compound of the structural formula:



(II)

with a lower alkyl amine (R₂-NH₂) containing 1 to 8 carbon atoms. The product dimercapto compounds (I) and trithiolanes are particularly useful as antimalarials in mammals.

3,578,683

1,4-DISUBSTITUTED-1-HYDROXY-2,2,3-TRICYANO-1,2-DIHYDROXANTHONES

Myrna Loy, Philadelphia, Pa., and Kenneth Robert Huffman and Edwin Fisher Ullman, Stamford, Conn., assignors to American Cyanamid Company, Stamford, Conn.


No Drawing. Original application Dec. 14, 1964, Ser. No. 418,337. Divided and this application Nov. 2, 1967, Ser. No. 703,491

Int. Cl. C07d 7/44

U.S. Cl. 260—335

5 Claims

Cyclohexadiene compounds, of which the following is exemplary.



These compounds are photochromic and may be used in information display or recording, and in other optical applications such as light filtering.

3,578,684

PERFLUORO- β -OXA- δ -VALEROLACTONE

James R. Throckmorton, St. Paul, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Mar. 21, 1969, Ser. No. 809,397
Int. Cl. C07d 7/06

U.S. Cl. 260—340.2

5 Claims

Perfluoro- β -oxa- δ -valerolactone, and a process for its preparation comprising heating a perfluorooxydiacetyl halide in the presence of an alkali metal fluoride, the compound being useful as a chemical intermediate.

3,578,685

3-(CYCLOPROPYLALKYL) - 2 - HYDROXY-1,4-NAPHTHOQUINONES AND THEIR PREPARATION

Sydney Archer, Bethlehem, N.Y., assignor to Sterling Drug Inc., New York, N.Y.

No Drawing. Filed Apr. 26, 1968, Ser. No. 724,618
Int. Cl. C07c 49/66

U.S. Cl. 260—396

9 Claims

3 - [cyclopropyl - (CH₂)_n] - 2 - hydroxy - 1,4 - naphthoquinones, where n is an integer from 6 to 12 inclusive, having antimalarial properties, are prepared: (a) by heating 2 - hydroxy - 1,4 - naphthoquinone with a diacyl peroxide of the formula [cyclopropyl - (CH₂)_n - CO]₂O₂ where n is 6 to 12 inclusive to produce said naphthoquinones where n is 6 to 12, respectively; (b) by oxidizing under alkaline conditions 3 - [cyclopropyl - (CH₂)_n] - 2 - hydroxy - 1,4 - naphthoquinone where n is 7 to 12 inclusive to produce the corresponding compound where n is 6 to 11, respectively; and (c) by the steps of oxidizing the corresponding 2-[cyclopropyl-(CH₂)_n] - 1 - naphthol where n is 6 to 12 inclusive to form 2 - [cyclopropyl-(CH₂)_n] - 1,4 - naphthoquinone, reacting the latter with a peroxide under alkaline conditions to form 2 - [cyclopropyl-(CH₂)_n] - 1,4 - naphthoquinone - 2,3 - oxide and hydrolyzing the 2,3 - oxide under acidic conditions to yield 2 - hydroxy - 3 - [cyclopropyl-(CH₂)_n] - 1,4 - naphthoquinone. Intermediates include compounds of the formula cyclopropyl - (CH₂)_x - COOH where x is an integer from 5 to 12 inclusive.

3,578,686

2-HYDROXY - 3-[(3,3,5-TRIMETHYLCYCLOHEXYL)-ALKYL] - 1,4-NAPHTHOQUINONES AND THEIR PREPARATION

Benjamin F. Tullar, Chatham, and Roman R. Lorenz, Greenbush, N.Y., assignors to Sterling Drug Inc., New York, N.Y.

No Drawing. Filed Apr. 26, 1968, Ser. No. 724,617
Int. Cl. C07c 49/00

U.S. Cl. 260—396

10 Claims

2-hydroxy - 3 - [(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1,4-naphthoquinones where n is an integer from 4 to 12 inclusive, having antimalarial properties, are prepared: (a) by heating 2-hydroxy-1,4-naphthoquinone with a diacyl peroxide of the formula [(3,3,5-trimethylcyclohexyl)-(CH₂)_n-CO]₂O₂ where n is 4 to 12 inclusive to produce said naphthoquinones where n is 4 to 12, respectively; (b) by oxidizing under alkaline conditions 2-hydroxy-3-[(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1,4 - naphthoquinone where n is 5 to 12 inclusive to produce the corresponding compound where n is 4 to 11, respectively; and, (c) by the steps of oxidizing 2-[(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1-naphthol where n is 4 to 12 inclusive to form 2 - [(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1,4-naphthoquinone, reacting the latter with a peroxide under alkaline conditions to form 2 - [(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1,4-naphthoquinone-2,3-oxide and hydrolyzing the 2,3-oxide under acidic conditions to yield 2-hydroxy-3-[(3,3,5-trimethylcyclohexyl)-(CH₂)_n] - 1,4 - naphtho-

quinone. Novel intermediates include compounds of the formula (3,3,5-trimethylcyclohexyl) - (CH₂)_x - COOH where x is an integer from 3 to 12 inclusive.

3,578,687

PROCESS FOR PRODUCING 4-NITROALKANOIC ACIDS


John M. Larkin, Hopewell Junction, and Kenneth L. Kreuz, Fishkill, N.Y., assignors to Texaco Inc., New York, N.Y.

No Drawing. Filed Jan. 30, 1968, Ser. No. 701,562
Int. Cl. C09f 7/02; C07c 51/28


U.S. Cl. 260—404

11 Claims

A method for preparing a 4-nitroalkanoic acid by contacting a dinitroalcohol having at least 5 carbon atoms corresponding to the formula:



with an acidic oxidizing agent at a pH not exceeding 4 thereby forming a 4-nitroalkanoic acid of the formula:



The contemplated 4-nitroalkanoic acids are useful as plasticizers, bacteriocides, lubricant additives, fuel additives, anti-rust agents and as precursors for the preparation of 2-pyrrolidinone.

3,578,688

ISOMERIZATION OF ACIDS

Donald M. Fenton, Anaheim, Calif., assignor to Union Oil Company of California, Los Angeles, Calif.

No Drawing. Filed May 3, 1968, Ser. No. 726,581
Int. Cl. C07c 3/14, 61/00, 53/00

U.S. Cl. 260—405.6

18 Claims

A process for isomerization of carboxylic acids or anhydrides comprising contacting the acid or anhydride at elevated temperature in an essentially closed system with a complex catalyst comprising a Group VIII noble metal and a biphilic ligand from the group consisting of organic phosphines, arsines and stibines, for a time sufficient to form an isomer of the acid or anhydride. The product acids and anhydrides are useful for preparation of a wide variety of products such as plasticizers, ester solvents, detergents, etc.

3,578,689

ESTER PURIFICATION PROCESS

Eugie A. Martin and Robert J. Fanning, Baton Rouge, La., assignors to Ethyl Corporation, New York, N.Y.

No Drawing. Filed Jan. 10, 1969, Ser. No. 790,471
Int. Cl. C07c 69/00

U.S. Cl. 260—410.9

18 Claims

A process is disclosed whereby esters are purified to remove contaminants such as alcohol, fatty acid and residual esterification catalyst by a selected sequence of contacting operations under selected conditions while avoiding conditions found to be conducive to the formation of emulsions and gels and while avoiding conditions that require the manipulation of large quantities of various washing streams conducive to losses of esters.

3,578,690

PROCESS FOR PREPARING MOLYBDENUM ACID SALTS

Mitchell Becker, Teaneck, N.J., assignor to Halcon International, Inc.

No Drawing. Filed June 28, 1968, Ser. No. 740,975
Int. Cl. C08h 17/36

U.S. Cl. 260—414

9 Claims

This invention relates to the preparation of molybdenum acid salts by directly reacting the carboxylic acid with a molybdenum compound while removing the water that is formed. These molybdenum acid salts are useful as catalysts in such processes as in the epoxidation of olefins.

3,578,691

ORGANIC 1,3,2,4-DIAZADISILETIDINES AND PROCESS


Walter Fink, Zurich, Switzerland, assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Nov. 25, 1968, Ser. No. 778,798
Int. Cl. C07f 7/02; C07d 103/02

U.S. Cl. 260—448.2

5 Claims

Organic 1,3,2,4-diazadisiletidines of the formula



and process for making by gradually adding the corresponding halo compound wherein the hydroxyl groups are replaced by reactive halogen atoms to a mixture or solution comprising water and an acid-binding agent.

3,578,692

1,3-DISILYL-1,3,2,4-DIAZADISILETIDINES AND PROCESS


Walter Fink, Zurich, Switzerland, assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Nov. 25, 1968, Ser. No. 778,841
Int. Cl. C07f 7/02


U.S. Cl. 260—448.2

11 Claims

The invention is a process for preparing 1,3-bis-disilyl-1,3,2,4-diazadisiletidines of the formula



where n is 1 to 100, by reacting a compound of the formula



where M is a metal atom linked through an oxygen atom, with a compound of the formula XR^3 where X is a reactive halogen atom, and new compounds of the first formula above where n is an integer of 1 to 100.

The compounds prepared in this manner find utility as temperature resistant products.

3,578,693

CYCLODISILAZANYLSILOXANES


Walter Fink, Zurich, Switzerland, assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Dec. 6, 1968, Ser. No. 781,955
Int. Cl. C07f 7/02

U.S. Cl. 260—448.2


3 Claims

The invention relates to new compounds having the formula



886 O.G.—16

and



useful as temperature resistant functional fluids, such as heat transfer fluids, hydraulic fluids and lubricants.

3,578,694

ALKYL CARBALKOXYALKYL AND ALKYL ALKANLOYLOXYALKYL SULFITES


Rupert A. Covey, Wolcott, and Bogislav von Schmeling and Charles E. Crittendon, Hamden, Conn., assignors to Uniroyal, Inc., New York, N.Y.

No Drawing. Filed Dec. 26, 1967, Ser. No. 693,117
Int. Cl. A01n 9/14; C07c 137/00

U.S. Cl. 260—456

7 Claims

Novel sulfite esters having the formula



wherein R is an alkyl or monohaloalkyl group having up to 12 carbon atoms and R' is a carbalkoxy alkyl or alkanoyloxyalkyl group or a monohalosubstituted derivative thereof having 3 to 9 carbon atoms, useful as herbicides, insecticides and nematocides.

3,578,695

OLEFINIC NITRILES BY THE CATALYTIC OXIDATION OF OLEFINS USING HYDROGEN CYANIDE

Ernest C. Milberger, Solon, and Wilfrid G. Shaw, Lyndhurst, Ohio, assignors to The Standard Oil Company, Cleveland, Ohio

No Drawing. Filed July 26, 1967, Ser. No. 655,993
Int. Cl. C07c 121/32, 121/00

U.S. Cl. 260—465.3

8 Claims

The instant application deals with a process for the manufacture of monoolefinically unsaturated aliphatic nitriles by the catalytic oxidation of olefin using cyanide and a molecular oxygen-containing gas, but no ammonia.

3,578,696

METHOD FOR PRODUCING MALONONITRILE

Joachim Hillard Blanck, 260—16 69th Ave., Glen Oaks, N.Y. 11004, and Martin Prince, 58 Darlington Drive, Wayne, N.J. 07470

No Drawing. Filed Aug. 5, 1968, Ser. No. 749,936
Int. Cl. C07c 121/22, 121/02

U.S. Cl. 260—465.3

11 Claims

Malononitrile is produced by direct vapor phase reaction of allene and ammonia in the presence of oxygen at a temperature in the range of 650° F. to 1000° F. and preferably in the presence of a catalyst such as bismuth phosphomolybdate or bismuth phosphotungstate on a catalytic support. Water may be advantageously used to be premixed with the reactants before passing over the catalyst to effect the vapor phase reaction.

3,578,697

CHELATING POLYMER


Nelson S. Marans, Silver Spring, Md., assignor to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed Oct. 10, 1968, Ser. No. 766,645
Int. Cl. C07c 97/02


U.S. Cl. 260—465.4

14 Claims


In abstract this invention is directed to a process for preparing a final polymer having the formula




wherein (i) n is 2-4,000; (ii) each of R_1 and R_2 is separately a member selected from the group consisting of




and




the mole ratio of carboxyl groups to amide groups being about 1:0.1-10; (iii) G is an alkylene group having about 2-12 carbon atoms; (iv) R_3 is a member selected from the group consisting of




and




(v) R_4 is a member selected from the group consisting of




and



wherein R_5 is a member selected from the group consisting of



(vi) Z is a member selected from the group consisting of



comprising reacting a dihydric alcohol or an amino alcohol, or a diamine with an acid having the formula $\text{NC}-\text{A}-\text{N}=(\text{CH}_2\text{COOH})_2$ wherein A is an alkylene group having 1-2 carbon atoms to form a first intermediate polymer, treating the first intermediate polymer with hot aqueous alkali to form a second intermediate polymer, and treating the second aqueous polymer with a strong mineral acid to form the final polymer which is recovered, all as recited hereinafter.

3,578,698

PREPARATION OF ESTERS FROM OLEFINS IN THE PRESENCE OF AN OXIME

Percy Hayden, Norton-on-Tees, England, assignor to Imperial Chemical Industries Limited, London, England
No Drawing. Filed Dec. 15, 1966, Ser. No. 601,868
Claims priority, application Great Britain, Dec. 24, 1965, 54,840/65; May 5, 1966, 19,853/66; Dec. 24, 1966, 28,201/66

Int. Cl. C07c 67/04

U.S. Cl. 260-475

18 Claims

There is provided a process for the oxidation of an unsaturated organic compound in the presence of a palladium catalyst and a nucleophilic compound. The oxidation is carried out in the presence of an oxime or in a solution to which has been added a nitrate, nitrite, nitrosyl, nitro or nitroso compound. The reaction is thus accomplished in the essential absence of halide ions.

3,578,699
p-(1,5-DIMETHYL-1,5-DIHALOHEXYL) BENZOIC ACID ESTERS, COMPOUNDS FOR COMBATING INSECT PESTS OF THE GENUS DYSDERCUS
Frantisek Sorm and Milos Suchy, Prague, Czechoslovakia, assignors to Ceskoslovenska Akademie Ved, Prague, Czechoslovakia

Filed June 20, 1968, Ser. No. 738,397
Claims priority, application Czechoslovakia, June 21, 1967, 4,548/67

Int. Cl. C07c 69/76; A01n 9/24

U.S. Cl. 260-476

5 Claims

Insect pests of the genus Dysdercus are combatted by contacting insects, larvae or eggs of the genus Dysdercus with an effective amount of a compound of the formula



wherein R is 1,5-dimethyl-1,5-dihaloheptyl wherein dihaloheptyl is dichloroheptyl or dibromoheptyl and R_1 is alkyl with one or two carbon atoms or an aralkyl with up to 9 carbon atoms. The above compound is produced by reacting a compound of the formula



wherein R_1 is an alkyl group with one or two carbon atoms or an aralkyl group with up to 9 carbon atoms, and R_2 is a 1,5-dimethylhexa-1,4-dienyl group, with a hydrogen halide selected from the group consisting of HCl and HBr, and recovering the thus-produced compound.

3,578,700

PROCESS FOR PREPARING POLY (BETA-LACTONE) PREPOLYMERS

Arie Klootwijk, deceased, late of Amsterdam, Netherlands, by Johanna Maria Klootwijk, representative, Purmerend, and Willem Bergwerf and Willem M. Wagner, Amsterdam, Netherlands, assignors to Shell Oil Company, New York, N.Y.

No Drawing. Filed Mar. 29, 1968, Ser. No. 717,472

Int. Cl. C08g 17/017

U.S. Cl. 260-484

7 Claims

Poly(beta-lactone) prepolymers having a molecular weight of from about 200 to about 10,000 and which are especially suitable as initiators for the polymerization of poly(beta-lactones) are prepared by reacting a beta-lactone and preferably an alpha, alpha-dialkyl-beta-propiolactone with a nucleophilic agent as hereinafter more fully described such as the tertiary phosphines, in a molar ratio of 20:1 to 1:40.

3,578,701

FLUORINATED ACIDS AND ESTERS

Kenneth C. Smeltz, Graylyn Crest, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Original application July 26, 1967, Ser. No. 656,076, now Patent No. 3,478,116, dated Nov. 11, 1969. Divided and this application Feb. 28, 1969, Ser. No. 803,469

Int. Cl. C07c 55/08, 69/62

U.S. Cl. 260-485

11 Claims

Perfluoroalkyl-terminated alkyl malonic acids and esters of the formula $(R_1-R')_2\text{CH}_2-\text{C}(\text{COOR})_2$ prepared from

the corresponding malonic acid ester and $R_1-R'-Z$. The esters are useful to prepare perfluoroalkyl-terminated alkyl-1,3-propanediols of the formula



by reduction. The esters and diols can be used to prepare polyesters and polyurethanes which are in general useful as fabric coatings to impart oil- and water-repellency thereto.

3,578,702

PROCESS FOR PRODUCING α,β -UNSATURATED ORGANIC COMPOUNDS

Thomas Carter Snapp, Jr., Alden E. Blood, and Hugh John Hagemeyer, Jr., Longview, Tex., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Dec. 3, 1965, Ser. No. 511,327

Int. Cl. C07c 69/52, 69/54, 121/30

U.S. Cl. 260-486

7 Claims

A process for producing α,β -unsaturated organic compounds which comprises contacting formaldehyde and a saturated organic ester, aldehyde, ketone or nitrile in the vapor phase in the presence of one or more inorganic oxides of rare earth metals of the lanthanide series impregnated on an inert support such as silica gel.

3,578,703

PROCESS FOR PRODUCING METHYL FORMATE FROM ALKALI OR ALKALINE EARTH FORMATE

Erwin F. Schoenbrunn, Ridgefield, and Edward H. Durell, Monroe, Conn., assignors to Escambia Chemical Corporation, Pace, Fla.

No Drawing. Filed Apr. 23, 1968, Ser. No. 723,603

Int. Cl. C07c 67/00

U.S. Cl. 260-488

9 Claims

A process for the production of methyl formate from alkali or alkaline earth formate by reaction with at least an equivalent quantity of methanol and strong acid in the presence of sufficient water to keep the reactant formate in solution, followed by distillation of the methyl formate produced. Sodium formate and sulfuric acid are preferred reactants. Methanol may be recovered by increasing the distillation temperature to at least the boiling point of methanol.

3,578,704

SUCCINATES SUBSTITUTED IN THE ALPHA POSITION BY ALKYL BENZENE SULFONATES

Stephen E. McGuire and Eugene F. Kennedy, Ponca City, Okla., assignors to Continental Oil Company, Ponca City, Okla.


No Drawing. Filed Aug. 1, 1969, Ser. No. 846,928

Int. Cl. C07c 143/52

U.S. Cl. 260-507

3 Claims

Novel surface active agents are provided having the general formula:



wherein X is a linear alkyl group containing from about 0 to about 35 carbon atoms, with the provision that when

X contains 0 carbon atoms the phenyl nucleus is attached directly to the carbon atom bearing the succinyl group; Y is hydrogen or a linear alkyl group containing from about 1 to about 35 carbon atoms; Z is hydrogen or a linear alkyl group containing from about 1 to about 35 carbon atoms; A is hydrogen or a linear or branched alkyl group containing from about 1 to about 15 carbon atoms; M is a cation selected from the group consisting of Li, Na, K, Rb, Cs, Ca, Mg, NH_4 and substituted ammonium; B is hydrogen or $-\text{SO}_3\text{M}$, with M being defined as before; and the sum of the carbon atoms X , Y , Z and A being from about 8 to about 35.

3,578,705

PROCESS FOR THE PREPARATION OF HOMOPHTHALIC ACID

Norman L. Wendler, Summit, Harry L. Slates, Florham Park, and Stuart Weber, Colonia, N.J., assignors to Merck & Co., Inc., Rahway, N.J.

No Drawing. Filed July 26, 1967, Ser. No. 656,001

Int. Cl. C07c 65/00

U.S. Cl. 260-521

10 Claims

3,5-diloweralkoxy homophthalic acids are prepared from 5,7-diloweralkoxy-1-indanones via the corresponding 2-oximo-1-indanones and 1,2-indandiones and are employed as intermediates in the total synthesis of d,l-Zearalenones.

3,578,706

REMOVAL OF BROMINE-CONTAINING IMPURITIES FROM AQUEOUS ACETIC ACID

Ferdinand List and Helmut Alfs, Marl, Germany, assignors to Chemische Werke Huels A.G., Marl, Germany

No Drawing. Filed Oct. 18, 1967, Ser. No. 676,022

Claims priority, application Germany, Oct. 27, 1966, C 40,534

Int. Cl. C07c 63/02

U.S. Cl. 260-524

7 Claims

In the working-up of acetic-acid-containing byproducts mixtures derived from processes directed to the liquid-phase air oxidation of alkyl aromatics in the presence of bromide anions, the improvements of treating such mixtures with metals or inorganic compounds thereof having electrochemical potentials ranging from magnesium to iron in order to convert organically bound bromide to bromide anions, and then subjecting the reaction mixture to ion exchange to remove substantially all the bromide ions, thereby eliminating the corrosiveness of the mixture and permitting the utilization of considerably less expensive materials of construction for the distillation system and other apparatus.

3,578,707

PRODUCTION OF UNSATURATED ALIPHATIC ACIDS

James Robert Bethell and David James Hadley, Epsom Downs, Surrey, England, assignors to BP Chemicals (U.K.) Limited, London, England

No Drawing. Continuation-in-part of application Ser. No. 497,496, Oct. 18, 1965, which is a division of application Ser. No. 4,221, Jan. 25, 1960. This application July 19, 1967, Ser. No. 654,372

Claims priority, application Great Britain, Feb. 17, 1959, 5,396/59; Apr. 15, 1959, 12,881/59

Int. Cl. C07c 57/04

U.S. Cl. 260-530

7 Claims

Process for producing unsaturated aliphatic acids such as acrylic acid and methacrylic acid from the corresponding aldehyde or compounds giving rise to them under the reaction conditions by passing the starting material over a catalyst comprising cobalt molybdate and optionally a quantity of tellurium or an oxide of tellurium.

3,578,708

METAL SEQUESTERANT

Ronald H. Carlson, Lewiston, N.Y., assignor to Hooker Chemical Corporation, Niagara Falls, N.Y.

No Drawing. Filed Nov. 2, 1967, Ser. No. 680,040

Int. Cl. C07c 101/26; C07f 9/50; C11d 3/36

U.S. Cl. 260—534 12 Claims

This invention relates to novel compounds useful as a sequesterant, and as a stabilizer for hydrogen peroxide, against contaminating catalyst ions such as cupric, ferric and manganous ions which cause decomposition of hydrogen peroxide for example.

Although the novel compounds included within this invention are of broad scope, representative compounds include: hexasodium tris(N,N-diacetatoaminomethyl)phosphine; trisodium tris(N-acetatoaminomethyl)phosphine; tris(N,N - diacetatoaminomethyl)phosphine; tetrasodium mono(hydroxymethyl)bis(N,N - diacetatoaminomethyl)phosphine; and disodium bis(hydroxymethyl)N,N-diacetatoaminomethyl phosphine.

3,578,709

PREPARATION OF ALKALI METAL SALTS OF NITRILOTRIACETIC ACID

John J. Bishop, Northford, Conn., and Albert W. Jache, Wauwatosa, Wis., assignors to Olin Corporation

No Drawing. Filed Aug. 28, 1968, Ser. No. 755,837

Int. Cl. C07c 101/20

U.S. Cl. 260—534

3 Claims

Alkali metal salts of nitrilotriacetic acid are advantageously produced by heating triethanolamine in the presence of a zinc oxide or a cadmium oxide catalyst at 150° to 300° C. with a mixture of sodium hydroxide and a minor proportion of potassium hydroxide.

3,578,710

DIHALOCYCLOPROPANE DERIVATIVES

Herman A. Bruson, Woodbridge, and Howard L. Plant, Milford, Conn., assignors to Olin Corporation

No Drawing. Filed Sept. 30, 1968, Ser. No. 763,910

Int. Cl. C07c 143/70

U.S. Cl. 260—543

2 Claims

Novel halosulfonyl derivatives are prepared by reacting a halosulfonic acid with a 1,1-dihalo-2-phenylcyclopropane compound. These derivatives are useful as pesticides and, in addition, may be utilized in preparing a variety of valuable pharmaceutical products.

3,578,711

N-(3,4-DICHLOROPHENYL) - 3-[N'-(3,4-DICHLOROPHENYL)CARBAMOYL]METHYL - 2,2-DIMETHYLCYCLOBUTANE CARBOXAMIDE

Theodore Largman, Morristown, N.J., and Peter E. Newallis, Leawood, Kans., assignors to Allied Chemical Corporation, New York, N.Y.

No Drawing. Filed July 18, 1968, Ser. No. 745,664

Int. Cl. C07c 103/33

U.S. Cl. 260—558

1 Claim

N - (3,4 - dichlorophenyl) - 3 - [N'-(3,4-dichlorophenyl) carbamoyl]methyl - 2,2-dimethylcyclobutanecarboxamide is prepared by reaction of 3,4-dichloroaniline with pinic acid chloride in the presence of base. The product is useful as an insecticide and chemosterilant.

3,578,712

BIS(SUBSTITUTED PHENYL)ACETALS

Albert J. Frey, Essex Fells, and Mario G. Buzzolini, Morristown, N.J., assignors to Sandoz-Wander, Inc., Hanover, N.J.

No Drawing. Filed Feb. 7, 1969, Ser. No. 797,661

Int. Cl. C07c 103/30

U.S. Cl. 260—559

2 Claims

The compounds are para-substituted bis-phenylacetals of N-amidinoglyoxylamide, and non-toxic acid addition

salts thereof, e.g., bis(p-chlorophenyl)acetal of N-amidinoglyoxylamide, are useful theapeutically. They are obtainable by reaction of an appropriate lower alkyl ester of bis(p-halophenoxy)acetic acid with guanidine.

3,578,713

PROCESS FOR PREPARING TOLUIDINES

John A. Scott, North Haven, Conn., assignor to

Olin Corporation

No Drawing. Filed Nov. 22, 1968, Ser. No. 778,297

Int. Cl. C07c 85/10

U.S. Cl. 260—580

7 Claims

The process for preparing nitrotoluidines by reacting an aromatic nitro compound with carbon monoxide in the presence of a catalyst comprised of a mixture of an oxide of copper and an oxide of manganese.

3,578,714

PROCESS FOR PREPARING ANILINE FROM PHENOL

Joseph L. Russell, Ridgewood, N.J., assignor to

Halcon International, Inc.

No Drawing. Filed Oct. 28, 1968, Ser. No. 771,342

Int. Cl. C07c 85/06

U.S. Cl. 260—581

4 Claims

A process for preparing aniline by the direct amination of phenol with ammonia in the vapor phase in the presence of a solid, heterogeneous catalyst. It has been discovered that significant process improvements are obtained if the phenol feed to the reaction is vaporized in the absence of substantial amounts of ammonia.

3,578,715

NOVEL DIKETONES AND DERIVATIVES THEREOF

Bernard Pierre Corbier and Paul Jose Teisseire, Grasse, France, assignors to S.A. des Etablissements Roure-

Bertrand Fils & Justin Dupont, Grasse, France


No Drawing. Filed Oct. 10, 1966, Ser. No. 585,259
Claims priority, application Switzerland, Oct. 14, 1965, 14,216/65

Int. Cl. C07c 49/30

U.S. Cl. 260—586

3 Claims

Novel diketones, illustrative of which are lower enol-ethers such as those of the formula



where R represents a lower alkyl group, and process for preparing the same wherein certain particular intermediate ketones are reacted with lower alkylorthoformates in the presence of an acid catalyst.

3,578,716

PROCESS FOR AROMATIC SUBSTITUTION

Robert E. Robinson, Columbia, S.C., assignor to National Distillers and Chemical Corporation, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 631,917, Apr. 19, 1967, which is a continuation-in-part of applications Ser. No. 282,559, Ser. No. 282,594, and Ser. No. 282,595, all filed May 23, 1963. This application Mar. 21, 1969, Ser. No. 809,406

Int. Cl. C07c 25/06, 25/18

U.S. Cl. 260—650

12 Claims

Substituted aromatic derivatives are prepared by reacting an aromatic compound with a Group VIII platinum

metal salt wherein the substituent introduced is derived from the anion portion of said Group VIII platinum metal salt.

3,578,717

PERFLUOROALKYL VINYL SULFONES AND PROCESS FOR PRODUCING SAME

Ronald A. Mitsch, St. Paul, and Robert J. Koshar, Lincoln Township, Washington County, Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed May 29, 1968, Ser. No. 732,865

Int. Cl. C07c 147/04; C08f 13/00

U.S. Cl. 260—607

4 Claims

Perfluoroalkyl vinyl sulfones, $\text{CF}_3\text{SO}_2\text{CH}=\text{CH}_2$ and higher, are provided which are homopolymerized to oligomers in the presence of tertiary amine basic catalysts.

3,578,718

PROCESS FOR THE PREPARATION OF ISOMERIC MIXTURES OF DI-THIO-BENZENE COMPOSED ESSENTIALLY OF THE PARA ISOMER

Max Schmidt, Wurzberg, Germany, assignor to Research Corporation, New York, N.Y.

No Drawing. Filed May 17, 1968, Ser. No. 729,915

Claims priority, application France, May 19, 1967, 107,109

Int. Cl. C07c 149/32

U.S. Cl. 260—609

4 Claims

A process for producing di-thio-benzene is disclosed, wherein polyphenylene-disulfide is subjected to the action of a reducing agent, and the resultant compound is acidified to produce the free mercaptan.

3,578,719

SURFACE ACTIVE AGENTS

Gregoire Kalopissis, Paris, and Guy Vanlerberghe, Montjay-la-Tour, France, assignors to Societe Anonyme dite: L'Oreal, Paris, France

No Drawing. Continuation-in-part of application Ser. No. 544,095, Apr. 21, 1966. This application Nov. 29, 1968, Ser. No. 780,300


Claims priority, application Luxembourg, Apr. 23, 1965, 48,458; Nov. 22, 1965, 49,902; Apr. 6, 1966, 50,850; France, Dec. 1, 1967, 130,713

Int. Cl. C07c 41/00, 43/04

U.S. Cl. 260—611

9 Claims

Non-ionic surface active agents having the formula



in which R is a lipophile group, X is OH or halogen and n is 2-10.

3,578,720

REDUCTION OF AROMATIC NITROCOMPOUNDS

David Dodman and John Mathers, Woolley, Manchester, England, assignors to Imperial Chemical Industries Limited, London, England

No Drawing. Filed Nov. 14, 1968, Ser. No. 775,895
Claims priority, application Great Britain, Nov. 24, 1967, 53,636/67; Mar. 29, 1968, 15,392/68

Int. Cl. C07c 81/02, 107/06

U.S. Cl. 260—647

14 Claims

Reducing aromatic nitrocompounds to nitroso-, azoxy- or azo-compounds with carbon monoxide in presence of a catalyst comprising oxygenated compounds of at least two heavy metals.

3,578,721

PROCESS FOR REDUCING THE FORMATION OF POLYMER ATTENDANT THE PYROLYSIS OF TETRAFLUOROETHYLENE

Maurice Joseph Couture, Parkersburg, W. Va., and Hans M. B. Gerner and Hugh H. Gibbs, Wilmington, Del., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed Dec. 14, 1967, Ser. No. 690,398

Int. Cl. C07c 17/26, 17/28, 23/06

U.S. Cl. 260—648

6 Claims

The pyrolysis of tetrafluoroethylene to higher molecular weight perfluorocarbon compounds, e.g., hexafluoropropylene, is accompanied by polymer formation which, according to the present invention, is suppressed by intimately contacting the pyrolyzate before it cools sufficiently for polymerization to occur with such compounds as HCl, HF, KF or NaF.

3,578,722

CHEMICAL PROCESS

Robert Nell Fraser, Horsham, England, assignor to BP Chemicals (U.K.) Limited, London, England

No Drawing. Filed Oct. 28, 1968, Ser. No. 771,271

Claims priority, application Great Britain, Nov. 16, 1967, 52,207/67

Int. Cl. C07c 3/50

U.S. Cl. 260—671

7 Claims

1:2:4:5 tetra-alkyl benzenes are produced from the reaction of propylene and xylene in mole ratio less than 2.

3,578,723

ISOMERIZATION AND DISPROPORTIONATION OF AROMATIC HYDROCARBONS

Emmerson Bowes, Media, and John J. Wise, Philadelphia, Pa., assignors to Mobil Oil Corporation

No Drawing. Filed Apr. 18, 1968, Ser. No. 722,162

Int. Cl. C01b 33/28; C07c 3/58, 5/22

U.S. Cl. 260—672

12 Claims

A new and unusual family of crystalline zeolites identified as zeolite ZSM-4 are used as catalysts for the isomerization and disproportionation of aromatic hydrocarbons.

3,578,724

MIGRATION AND ISOMERIZATION OF ACETYLENES

Andre Jules Hubert, Brussels, Belgium, assignor to Union Carbide Corporation

No Drawing. Filed Mar. 4, 1968, Ser. No. 709,942

Int. Cl. C07c 5/22, 11/12, 11/22

U.S. Cl. 260—678

4 Claims

Process for the migration of acetylenic bonds and a process for the isomerization of hydrocarbons containing acetylenic bonds to hydrocarbons containing conjugated unsaturation, by contacting a compound containing one or two acetylenic bonds with potassium amide on alumina. The unsaturated compounds produced by the process of the invention are useful as ultraviolet light absorbers, as cross-linking agents for polyolefinic elastomers, and as intermediates in the synthesis of new compounds.

3,578,725

NOVEL CATALYST SYSTEM FOR ISOMERIZING HYDROCARBONS

Donald E. Jost, Media, Edward J. Janoski, Havertown, and Abraham Schneider, Philadelphia, Pa., assignors to Sun Oil Company, Philadelphia, Pa.

No Drawing. Filed Aug. 9, 1968, Ser. No. 751,378

Int. Cl. C07c 5/28

U.S. Cl. 260—683.75

9 Claims

In the isomerization of C_4 - C_7 paraffins with an aluminum halide catalyst, it has been found that higher yields are obtainable and at lower temperatures, when the reaction is carried out in the presence of both a support and a solvent for the aluminum halide catalyst.

3,578,726 CONDENSATION METHOD FOR MAKING MULTIPLE SEQUENCE ORGANOPOLY- SILOXANE BLOCK POLYMERS

Edgar E. Bostick, Scotia, and William A. Fessler, Albany, N.Y., assignors to General Electric Company
No Drawing. Filed Oct. 13, 1969, Ser. No. 866,002
Int. Cl. C08g 31/34, 47/02

U.S. Cl. 260—825 5 Claims
A condensation method is provided for making branched and multiple sequence block polymers. A silane having at least two hydrolyzable radicals attached to silicon is employed to couple active polydiorganosiloxane having at least one terminal alkali metal silanolate radical. The polydiorganosiloxane can be in the form of a binary or ternary block and the alkali metal silanolate is complexed with hexamethylphosphoramide to provide a stable non-randomizing activated site. The multiple sequence block polymers exhibit improved physical properties over the corresponding binary or ternary block polymers.

3,578,727 TWO-ROD HOT-MELT ADHESIVES FROM POLY- EPOXIDES OR POLYURETHANE SYSTEMS

William R. Battersby, Lexington, Robert P. Follett, Lowell, Timothy D. MacGrandle, Lynn, Conrad Rossitto, Andover, and Paul Taylor, North Andover, Mass., assignors to Uulted Shoe Machinery Corporation, Flemington, N.J.

No Drawing. Continuation-in-part of application Ser. No. 699,357, Jan. 22, 1968. This application July 1, 1968, Ser. No. 741,266

Int. Cl. C08g 45/12 8 Claims
An adhesive or stiffening agent supply comprising at least two flexible slender rods of synthetic polymer resin of different mutually reactive compositions adapted to be melted in predetermined length ratio to supply molten material for mixing to give a curing adhesive or stiffening agent composition for application to a surface.

3,578,728 LIQUID UNSATURATED POLYESTERS AND POLY- ESTER URETHANES CONTAINING CROSS- LINKED PARTICLES OF THE SAME RESINS

Wendell A. Ehrhart, Hellam, and Clarence E. Rohrer, Lititz, Pa., assignors to Armstrong Cork Company, Lancaster, Pa.

No Drawing. Filed Nov. 18, 1968, Ser. No. 784,955
Int. Cl. C08g 41/04

U.S. Cl. 260—859 8 Claims
Blends of particles of cross-linked unsaturated polyester resins and fluid unsaturated polyester resins. The blends possess properties unique to unsaturated polyester resins in that they may be readily processed using a variety of techniques not commonly associated with unsaturated polyester resins and the blends are readily curable to form useful articles. The cross-linked particles used in forming the blends are conveniently produced by subjecting the unsaturated polyester resin to mastication during or after polymerization.

3,578,729 THERMOPLASTIC POLYESTER MOLDING COMPOSITIONS

Ludwig Brinkmann and Walter Herwig, Frankfurt am Main, and Harald Cherdron, Wiesbaden, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Filed July 11, 1968, Ser. No. 743,925
Claims priority, application Germany, July 20, 1967, F 53,013

Int. Cl. C08g 39/10 15 Claims
Molding compositions which can be processed thermoplastically are prepared from a mixture of linear satu-

rated polyesters and α -olefin-acrylic acid ester copolymers and are distinguished by a high impact strength.

3,578,730 THERMOPLASTIC POLYESTER-POLY-3-METHYL- BUTENE-1 MOULDING COMPOSITIONS

Walter Herwig and Ludwig Brinkmann, Frankfurt am Main, and Klaus-Dieter Asmus, Hofheim, Taunus, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Filed Sept. 26, 1968, Ser. No. 763,012
Claims priority, application Germany, Oct. 7, 1967, P 16 94 199.4


Int. Cl. C08f 29/10; C08g 39/20, 51/58 10 Claims
Thermoplastic moulding compositions comprising linear saturated polyesters and poly-3-methylbutene-1 of which at least 80% of the particles are 10 microns or less and from which moulded articles of high dimensional stability can be made.

3,578,731 LINEAR POLYMERIC PHOSPHORUS- CONTAINING ESTERS

Franklin E. Mange, Rudolf S. Buriks, and Patrick M. Quinlan, St. Louis, Mo., assignors to Petrolite Corporation, Wilmington, Del.


No Drawing. Filed Dec. 1, 1967, Ser. No. 687,127
Int. Cl. C07f 9/38; A01n 9/36; B01d 17/04

U.S. Cl. 260—929 6 Claims
Linear polyesters of a phosphorus-containing acid and a diol as illustrated by a polyester having repetitive units of the formula:



where X is oxygen or sulfur; B is a diol residue; Z is hydrogen in the case of a phosphite ester i.e. H; a hydrocarbon or a substituted hydrocarbon group in the case of a phosphonate ester i.e. R; an oxyhydrocarbon or a substituted oxyhydrocarbon group in the case of a phosphate ester i.e. —OR; a thiohydrocarbon or a substituted thiohydrocarbon group in the case of thiophosphate ester i.e. —SR.

The preferred polyester has repeating units of the formula



where OA is the residue of an alkylene oxide or a substituted alkylene oxide; n is an integer, for example 1–300 or more, such as about 2–250, for example about 3–200, but advantageously about 5–130, and Z is hydrogen, a substituted group (R), for example, alkyl, aryl, cycloalkyl, alkaryl, aralkyl, heterocyclic including substituted derivatives thereof, etc.; alkoxy or aryloxy group (OR) for example methoxy, propoxy, isopropoxy, 2-ethylhexoxy, etc., phenoxy, etc.

These polyesters are employed as demulsifiers as well as for other uses.


3,578,732 METHOD OF FORMING BUILDING WALLS

Graham C. Lount, 744 South Drive, and William D. Lount, 101 Grenfell Blvd., both of Winnipeg, Manitoba, Canada

Filed Oct. 21, 1968, Ser. No. 769,344
Int. Cl. E04b 1/16; E04g 21/00

U.S. Cl. 264—34 12 Claims
This method of forming walls is primarily for multi-storied, column supported buildings and consists of placing a plurality of vertically situated spaced and parallel

tendons or cables through the wall opening, then prestressing same, and then attaching a wire grid or equivalent to the tendons or cables. Under certain circumstances a form is then placed in spaced and parallel relationship from the




tendons or cables and the grid and then a wall material that sets up by chemical action is sprayed or trowelled through and around the tendons or cables and the grid so that the said tendons or cables and grid are fully embedded in the material.

3,578,733 METHOD FOR MAKING JOINTED CONCRETE STRUCTURES

John Hurst, London, England, assignor to W. R. Grace & Co., New York, N.Y.

Filed May 23, 1968, Ser. No. 731,374
Claims priority, application Great Britain, May 26, 1967, 24,716/67

Int. Cl. E04b 1/16 8 Claims
U.S. Cl. 264—35



Concrete is cast with a dummy joint sealed by a flexible water stop embedded by keying formations into the concrete, by a method in which a crack is formed as the dummy joint, a crack-inducing body, e.g., a piece of wood being fixed in position, e.g., by spring clips, opposite the centre line of each water stop. The invention also includes a novel assembly of a water stop and a spring clip for holding the crack-inducing body.


3,578,734 METHOD FOR TREATING THE FLANGES OF CONTAINERS

Charles Elbert Woodard, 14 Elizabeth St., South Windsor, Conn. 06074, and Richard James Morcom, 44 High Farms Road, West Hartford, Conn. 06107

Filed Nov. 19, 1968, Ser. No. 777,030
Int. Cl. B29c 25/00; B29f 5/00

U.S. Cl. 264—80 12 Claims
Containers of synthetic plastic material having an outwardly extending flange about at least a portion of their

periphery are stacked in nested relationship with a relatively small spacing between their flanges and are subjected to a flame treatment by an angularly disposed




flame along the outer edge of the flange to eliminate jagged edges and whiskers. The heating produces a bead of increased thickness at the flange edge to provide a smooth surface.

3,578,735 METHOD AND APPARATUS FOR MOLDING PLASTIC ARTICLES

Sidney Cholmar and Robert H. Peters, Bloomfield, Conn., assignors to Monsanto Company, St. Louis, Mo.

Filed Dec. 30, 1968, Ser. No. 787,654
Int. Cl. B29c 17/03, 17/04

U.S. Cl. 264—89 6 Claims



Method and apparatus for simultaneously forming a plurality of articles from thermoplastic sheet material. The sheet from which the articles are formed is clamped against a mold containing rows of mold cavities. The clamping is within the periphery of the sheet solely in a direction perpendicular to that of advancement of the sheet such that it is uninterrupted across the sheet intermediate each row of cavities. The clamping member has a reciprocally mounted frame having laterally extending ribs joined to sides of the frame. The ribs are aligned opposite a front face of the mold between the rows of cavities therein.

ERRATUM

For Class 219—107 see:
Patent No. 3,578,165

DESIGNS

MAY 11, 1971

220,674

BATHING-CAP

Carlos Capella Nogue, Calle Roman Macaya 18,
Barcelona 6, Spain

Filed Jan. 5, 1970, Ser. No. 20,769

Claims priority, application Spain July 12, 1969

Term of patent 14 years

Int. Cl. D2-03

U.S. Cl. D2-237



220,676

TORQUE WRENCH


Bosko Grabovac, Altadena, Calif. (% Consolidated
Devices, Inc., 818 E. Broadway, San Gabriel, Calif.
91776)

Filed May 22, 1969, Ser. No. 17,280

Term of patent 14 years

Int. Cl. D8-02

U.S. Cl. D8-24



220,677

HANDSAW

Arne Erkers, Hallebergsvagen 18, Bromma, Sweden

Filed Feb. 10, 1970, Ser. No. 21,395

Claims priority, application Sweden Sept. 26, 1969

Term of patent 14 years

Int. Cl. D8-02

U.S. Cl. D8-96



220,675

NECKTIE OR THE LIKE

Louis J. Schultze, 102 E. Oak St., Chicago, Ill. 60611

Continuation-in-part of design application Ser. No. 19,239,
Sept. 22, 1969. This application July 29, 1970, Ser.
No. 24,212

Term of patent 14 years

Int. Cl. D2-06

U.S. Cl. D2-351



220,678

HANDLE


William J. Horgan, Jr., Pittsburgh, Pa., assignor to
Blumcraft of Pittsburgh, Pittsburgh, Pa.

Filed Oct. 8, 1969, Ser. No. 19,457

Term of patent 14 years

Int. Cl. D8-03

U.S. Cl. D8-166



MAY 11, 1971

U. S. PATENT OFFICE

411

220,679

BOTTLE OR THE LIKE


Henry Finkel, Westmount, Quebec, Canada, assignor to
Quality Oil Corporation, Montreal, Quebec, Canada

Filed May 12, 1970, Ser. No. 22,941

Term of patent 14 years

Int. Cl. D9-01

U.S. Cl. D9-44



220,680

BOTTLE


Van H. Neher, Mauricetown, N.J., assignor to Wheaton
Glass Company, Millville, N.J.

Filed Feb. 18, 1970, Ser. No. 21,477

Term of patent 14 years

Int. Cl. D9-01

U.S. Cl. D9-62



220,681

BOTTLE

Robert H. Knies, Fullerton, Calif., assignor to Hunt-
Wesson Foods, Inc., Fullerton, Calif.

Filed Aug. 5, 1970, Ser. No. 24,315

Term of patent 14 years

Int. Cl. D9-01

U.S. Cl. D9-103



220,682

COMBINED PACKAGING TRAY AND COVER

Kenneth W. Artz, Mohnton, Pa., assignor to


W. R. Grace & Co., Duncan, S.C.

Filed Dec. 17, 1968, Ser. No. 15,026

Term of patent 14 years

Int. Cl. D9-04

U.S. Cl. D9-219



220,683

PACKAGING TRAY FOR A LOBSTER


Allan Ray Clouston, 6845 Monkland Ave.,
Montreal 28, Quebec, Canada

Filed Jan. 20, 1970, Ser. No. 21,010

Term of patent 14 years

Int. Cl. D9-04

U.S. Cl. D9-222



220,684

BUILDING STRUCTURE INCLUDING UNDER-WATER LIVING ACCOMMODATIONS

William S. Page, 12862 Sylvan St., Garden Grove, Calif.
92641, and Lauren W. Anderson, Newport Beach, Reid

A. Kawai, Pasadena, and Paul B. Kraus, Sunset Beach,
Calif., and George C. Oyama, Mount Clemens, Mich.;


said Anderson, Kawai, Kraus, and Oyama assignors to
said Page

Filed Jan. 21, 1970, Ser. No. 21,016

Term of patent 14 years

Int. Cl. D25-04

U.S. Cl. D13-1




220,685

AIR-SUPPORTED STRUCTURE

James Scott Stineman, 615 W. Civic Center Drive,
Suite 215, Santa Ana, Calif. 92701
Filed Feb. 17, 1970, Ser. No. 21,474
Term of patent 14 years
Int. Cl. D25—04

U.S. Cl. D13—1




220,686

AIR-SUPPORTED STRUCTURE

James Scott Stineman, 615 W. Civic Center Drive,
Suite 215, Santa Ana, Calif. 92701
Filed May 11, 1970, Ser. No. 22,911
Term of patent 14 years
Int. Cl. D25—04

U.S. Cl. D13—1




220,687

CAMPING AND UTILITY TRAILER

Nathan E. Spiese, East Petersburg, Pa., assignor to
Wheel Mate Corporation, East Petersburg, Pa.
Filed Dec. 12, 1969, Ser. No. 20,472
Term of patent 14 years
Int. Cl. D12—10

U.S. Cl. D14—3




220,688

TRUCK RACK

James G. Zulim, 911 King St., Santa Cruz, Calif. 95060,
and Louis J. Zulim, 604 Townsend Ave., Aptos, Calif.
95003

Filed Mar. 26, 1970, Ser. No. 22,061
Term of patent 14 years
Int. Cl. D12—09

U.S. Cl. D14—3




220,689

MOTOR COACH

Maurice E. Moore, 315 Continental Ave.,
Dallas, Tex. 75207

Filed Apr. 3, 1970, Ser. No. 22,229
Term of patent 14 years
Int. Cl. D12—08

U.S. Cl. D14—3




220,690

CHAIR

Arthur Charles Ferro, St. Louis, Mo., assignor to Contour
Chair-Lounge Co., Inc., St. Louis, Mo.
Filed Mar. 16, 1970, Ser. No. 21,920

Term of patent 14 years
Int. Cl. D6—02

U.S. Cl. D15—11




220,691

GUNSTOCK GRIP

Charles R. Peterson, 7839 Craner Ave.,
Sun Valley, Calif. 91352
Filed Mar. 3, 1969, Ser. No. 16,005
Term of patent 14 years
Int. Cl. D22—02

U.S. Cl. D22—6




220,692

MODULE EXTENDER

Ira Morris, Framingham, Mass. (% Digital Equipment
Corp., 146 Main St., Maynard, Mass. 01754)

Filed Apr. 27, 1970, Ser. No. 22,653
Term of patent 14 years
Int. Cl. D13—99

U.S. Cl. D26—1



220,693

DATA TERMINAL OR SIMILAR ARTICLE

Pierre L. Crease, Kettering, and James C. Kaufman, Day-
ton, Ohio, and Dean E. Wilson, Glendale, Mo., as-
signors to The National Cash Register Company,
Dayton, Ohio

Filed Apr. 30, 1970, Ser. No. 22,731
Term of patent 14 years
Int. Cl. D14—02

U.S. Cl. D26—5




220,694

DATA TERMINAL OR SIMILAR ARTICLE

Pierre L. Crease, Kettering, Donald L. Forsythe, Dayton,
and Dean E. Wilson, Kettering, Ohio, assignors to The
National Cash Register Company, Dayton, Ohio

Filed Apr. 30, 1970, Ser. No. 22,732
Term of patent 14 years
Int. Cl. D14—02

U.S. Cl. D26—5



220,695

CONTROL ENCLOSURE

Stephen Lazzo III, Park Forest, Ill., assignor to
General Electric Company

Filed Oct. 24, 1969, Ser. No. 19,699
Term of patent 14 years
Int. Cl. D13—03

U.S. Cl. D26—13



220,696

CONTROL ENCLOSURE

Stephen Lazzo III, Park Forest, Ill., assignor to
General Electric Company
Filed Oct. 24, 1969, Ser. No. 19,700
Term of patent 14 years
Int. Cl. D13—03

U.S. Cl. D26—13





220,697

FISHING MOTOR FOOT PEDAL CONTROL

Ralph C. Osborn, Bloomington, Ill., assignor to
Osborn Engineering Corporation
Filed Oct. 27, 1969, Ser. No. 19,746
Term of patent 7 years
Int. Cl. D13—03

U.S. Cl. D26—13





220,698

TELEPHONE TERMINAL

Henry Kapper, Raleigh, N.C., assignor to International
Business Machines Corporation, Armonk, N.Y.
Filed Dec. 31, 1969, Ser. No. 20,928
Term of patent 14 years
Int. Cl. D14—03

U.S. Cl. D26—14




220,699

CONTROL UNIT FOR A TWO-WAY RADIO OR SIMILAR ARTICLE

Martin C. Stessel, Schaumburg, Rudolph W. Krolopp,
Palatine, and Karl Miklas, Park Ridge, Ill., assignors to
Motorola, Inc., Franklin Park, Ill.
Filed Feb. 24, 1970, Ser. No. 21,630
Term of patent 14 years
Int. Cl. D14—03

U.S. Cl. D26—14




220,700

STEREO-TAPE PLAYER

Robert P. Maniaci, Downey, Calif., assignor to California
Auto Radio Inc., Downey, Calif.
Filed Mar. 9, 1970, Ser. No. 21,798
Term of patent 14 years
Int. Cl. D14—03

U.S. Cl. D26—14




220,701

CHRISTIAN MEDALLION OR SIMILAR ARTICLE

Joseph A. Honzik, 2120 34th St.,
Two Rivers, Wis. 54241
Filed Oct. 28, 1969, Ser. No. 19,756
Term of patent 14 years
Int. Cl. D11—02

U.S. Cl. D29—23




220,702

SHELF UNIT FOR STORING BLUE PRINTS OR SIMILAR ARTICLES

Frank R. Sweet, Jr., 56 Fayerweather,
Cambridge, Mass. 02138
Filed Oct. 30, 1968, Ser. No. 14,226
Term of patent 14 years
Int. Cl. D6—01

U.S. Cl. D33—2




220,703

COMBINED DESK AND BOOK RACK

Yoshio Deguchi, Tokyo, and Fumio Yanaguchi, Yokohama,
Japan, assignors to Okamura Manufacturing
Company Limited, Yokohama, Japan


Filed Dec. 11, 1969, Ser. No. 20,449
Claims priority, application Japan June 23, 1969
Term of patent 14 years
Int. Cl. D6—06

U.S. Cl. D33—7

220,704
TABLE


Edward James Kramer, Edmonds, Wash., assignor to
Magna Design, Inc., Lynnwood, Wash.
Filed Dec. 12, 1969, Ser. No. 20,479
Term of patent 14 years
Int. Cl. D6—03

U.S. Cl. D33—14

220,705
FILING CABINET


Charles M. Huck, New Brunswick, N.J., assignor to
Estey Corporation, Red Bank, N.J.
Original design application Sept. 25, 1968, Ser. No. 13,713,
now Patent No. 215,307, dated Sept. 23, 1969. Divided
and this application Sept. 18, 1969, Ser. No. 19,205
Term of patent 14 years
Int. Cl. D6—04

U.S. Cl. D33—19




220,706
COMBINED CABINET AND ACCESSORY
TRAY UNIT
 Essie M. Reid, 12 Rita Lane,
 North Syracuse, N.Y. 13212
 Filed Nov. 7, 1969, Ser. No. 19,979
 Term of patent 14 years
 Int. Cl. D6—01

U.S. Cl. D33—19



220,708
COMBINED LIQUID AND CUP DISPENSER
 Rodney J. Brott, 1340 Yale Ave. NW.,
 Canton, Ohio 44703
 Filed Jan. 21, 1970, Ser. No. 21,020
 Term of patent 14 years
 Int. Cl. D6—01

U.S. Cl. D33—26




220,707
COMBINED LIQUID AND CUP DISPENSER
 Rodney J. Brott, 1340 Yale Ave. NW.,
 Canton, Ohio 44703
 Filed Jan. 21, 1970, Ser. No. 21,019
 Term of patent 14 years
 Int. Cl. D6—01

U.S. Cl. D33—26




220,709
GAME BOARD
 William B. Burke, Springfield, Mass., assignor to Milton
 Bradley Company, Springfield, Mass.
 Filed July 24, 1969, Ser. No. 18,368
 Term of patent 14 years
 Int. Cl. D21—01

U.S. Cl. D34—5




220,710
RING TOSS GAME TARGET BOARD
 Elwood T. Stricklin, Lima, Peru
 (374 Santa Isabel Ave., Costa Mesa, Calif. 92627)
 Filed Aug. 13, 1969, Ser. No. 18,673
 Term of patent 14 years
 Int. Cl. D21—01

U.S. Cl. D34—5



220,711
FOOD CUTTER
 James B. Swett, Barrington, R.I., assignor to
 Dart Industries, Inc., Los Angeles, Calif.
 Filed Feb. 18, 1970, Ser. No. 21,478
 Term of patent 14 years
 Int. Cl. D7—99

U.S. Cl. D44—1





220,712
CUP
 Neils Refsgaard, Ishøj per Taastrup, Denmark, assignor
 to Dansk Designs, Ltd., Mount Kisco, N.Y.
 Filed Jan. 26, 1970, Ser. No. 21,085
 Term of patent 14 years
 Int. Cl. D7—01

U.S. Cl. D44—9





220,713
CANDELABRA
 Jens H. Quistgaard, Copenhagen, Denmark, assignor to
 Dansk Designs, Ltd., Mount Kisco, N.Y.
 Filed Mar. 9, 1970, Ser. No. 21,805
 Term of patent 14 years
 Int. Cl. D26—05

U.S. Cl. D48—2



220,714
CANDELABRA
 Bertil Vallien, Afors, Sweden, assignor to Dansk
 Designs, Ltd., Mount Kisco, N.Y.
 Filed May 26, 1970, Ser. No. 23,150
 Term of patent 14 years
 Int. Cl. D26—05


U.S. Cl. D48—2



220,715

COMBINED LAMP SHADE AND MIRROR
 Alme Trudeau, 227 NE. 26th St., Miami, Fla. 33127
 Filed Jan. 14, 1970, Ser. No. 20,921
 Term of patent 14 years
 Int. Cl. D26-06


U.S. Cl. D48-16



220,716

DESIGN FOR A LAMP BASE
 Vine B. Miller, 1414 S. Shipley St., Muncie, Ind. 47302
 Filed Apr. 13, 1970, Ser. No. 22,419
 Term of patent 14 years
 Int. Cl. D26-02

U.S. Cl. D48-20



220,717

HIGH INTENSITY LAMP
 Dan M. Andre, 8843 Kostner Terrace,
 Skokie, Ill. 60076
 Filed Apr. 29, 1970, Ser. No. 22,713
 Term of patent 3½ years
 Int. Cl. D26-02



U.S. Cl. D48-20



220,718

COMBINED COIN HOLDER AND CALENDAR
 David M. Pallet, 3239 Bishop St.,
 Cincinnati, Ohio 45220
 Filed Apr. 10, 1969, Ser. No. 16,683
 Term of patent 14 years
 Int. Cl. D20-99


U.S. Cl. D52-4



220,719

CASH REGISTER OR SIMILAR ARTICLE
 Claudio G. Gomez and Francisco Kvapil, Buenos Aires,
 Argentina, assignors to The National Cash Register
 Company, Dayton, Ohio
 Filed Apr. 9, 1970, Ser. No. 22,351
 Term of patent 14 years
 Int. Cl. D20-99


U.S. Cl. D52-4



220,720

CASH REGISTER
 Isao Kitai, Nara, Japan, assignor to Sharp Kabushiki
 Kaisha, Osaka, Japan
 Filed Apr. 16, 1970, Ser. No. 22,458
 Claims priority, application Japan Dec. 5, 1969
 Term of patent 14 years
 Int. Cl. D20-99


U.S. Cl. D52-4



220,721

TURNING CENTER
 Brooks Stevens, Fox Point, Wis., assignor to Kearney &
 Trecker Corporation, West Allis, Wis.
 Filed Jan. 22, 1970, Ser. No. 21,037
 Term of patent 14 years
 Int. Cl. D15-05


U.S. Cl. D54-6



220,722

**ROLL FORMING MACHINE FOR MAKING
 GUTTERS**
 Gary A. Knudson, 1280 Willow Lane,
 Golden, Colo. 80401
 Filed June 23, 1969, Ser. No. 17,816
 Term of patent 14 years
 Int. Cl. D15-05

U.S. Cl. D55-1



220,723

RADIO RECEIVER
 Edward Abbo, 6 Ronald Drive, Monsey, N.Y. 10952
 Filed June 2, 1970, Ser. No. 23,258
 Term of patent 3½ years
 Int. Cl. D14-03


U.S. Cl. D56-4



220,724

HAND MAGNIFIER
 St. Barth Alaska, 3811 S. Scoville Ave.,
 Berwyn, Ill. 60402
 Filed Mar. 3, 1969, Ser. No. 16,016
 Term of patent 14 years
 Int. Cl. D16-08

U.S. Cl. D57-1



220,725

DESIGN FOR A PAIR OF SPECTACLES
 Roger L. McCracken, Chill, N.Y., assignor to Bausch &
 Lomb Incorporated, Rochester, N.Y.
 Filed Sept. 23, 1969, Ser. No. 19,260
 Term of patent 14 years
 Int. Cl. D16-08

U.S. Cl. D57-1



220,726

PORTABLE TYPEWRITER
 John Cuccio, Westport, Conn., assignor to
 Ing. C. Olivetti & C., S.p.A., Ivrea, Italy
 Filed Feb. 20, 1970, Ser. No. 21,563
 Term of patent 14 years
 Int. Cl. D18-01


U.S. Cl. D64-11



220,727
AIRCRAFT

Ralph V. Sawyer, 45432 Leatherwood,
Lancaster, Calif. 93534
Filed Jan. 5, 1970, Ser. No. 20,767
Term of patent 14 years
Int. Cl. D12—07


U.S. Cl. D71—1



220,729
BOAT ENGINE

William P. Kitovich, Chicopee, Mass., assignor to
K & P Products Inc., Chicopee Falls, Mass.
Filed June 30, 1969, Ser. No. 17,964
Term of patent 14 years
Int. Cl. D12—14

U.S. Cl. D71—1



220,728
BOW-MOUNTED STEERING CONSOLE
FOR BOATS

Joseph G. Cox, Jr., 2611 Gilmer Road,
Longview, Tex. 75601
Filed Mar. 2, 1970, Ser. No. 21,682
Term of patent 14 years
Int. Cl. D12—99


U.S. Cl. D71—1



220,730
HIGH RAM AUTOMOTIVE INTAKE MANIFOLD

Philip Weiland, 2737 San Fernando Road,
Glendale, Calif. 90065
Filed Dec. 15, 1969, Ser. No. 20,513
Term of patent 14 years
Int. Cl. D15—01


U.S. Cl. D77—1



220,731
GAS GRILL

Lewis H. Herr, Lansdale, Pa., assignor to
Caloric Corporation, Topton, Pa.
Filed Dec. 19, 1969, Ser. No. 20,568
Term of patent 14 years
Int. Cl. D7—04


U.S. Cl. D81—10



220,732
NIPPLE SEAT FOR BABY BOTTLE

Michael C. Ritsl, 7950 SW. 16th St., Miami, Fla. 33155
Filed Mar. 23, 1970, Ser. No. 22,026
Term of patent 14 years
Int. Cl. D24—05


U.S. Cl. D83—8



220,733
JEWEL CASE

Kenneth G. Niblack, 395 Linwood Ave.,
Buffalo, N.Y. 14209
Filed Oct. 1, 1968, Ser. No. 13,825
Term of patent 14 years
Int. Cl. D3—99


U.S. Cl. D87—1



220,734
FISHING TACKLE BOX

Gary Wallazy, 14860 Lyons, Livonia, Mich. 48154
Filed Jan. 16, 1970, Ser. No. 20,951
Term of patent 14 years
Int. Cl. D3—99


U.S. Cl. D87—1



220,735
TYPEWRITER CARRYING CASE

Ettore Sottsass, Jr., Milan, Italy, assignor to Ing. C.
Olivetti & C. S.p.A., Ivrea, Turin, Italy
Filed Feb. 11, 1970, Ser. No. 21,401
Claims priority, application Italy Aug. 20, 1969
Term of patent 14 years
Int. Cl. D3—01

U.S. Cl. D87—1




220,736
COMBINED UMBRELLA AND SHEATH

Manfred Bremshey, 350 Simcoe Ave.,
Mount Royal, Quebec, Canada
Continuation-in-part of design application Ser. No. 14,442,
Nov. 13, 1968. This application Dec. 29, 1969, Ser.
No. 20,659

Term of patent 14 years
Int. Cl. D3—99


U.S. Cl. D87—1



220,737
VEGETABLE PEELER

Louis H. Loeffler, 1247 Minerva Ave.,
West Islip, N.Y. 11795
Filed Feb. 17, 1970, Ser. No. 21,473
Term of patent 14 years
Int. Cl. D7—05


U.S. Cl. D89—1



220,738
TIRE

Robert W. Floyd, Atwater, Ohio, assignor to The
B. F. Goodrich Company, New York, N.Y.
Filed Oct. 8, 1969, Ser. No. 19,465
Term of patent 14 years
Int. Cl. D12—14


U.S. Cl. D90—20



220,739
TIRE

Eric C. Bartlett, Birmingham, England, assignor to The
Dunlop Company Limited, Birmingham, England
Filed Apr. 1, 1970, Ser. No. 22,171
Claims priority, application Great Britain Oct. 23, 1969
Term of patent 14 years
Int. Cl. D12—14


U.S. Cl. D90—20



220,740

INFORMATION PLATE FOR A HOSPITAL PATIENT
Roger V. Larson, Murray, Utah, assignor to
Bio-Logics, Inc., Salt Lake City, Utah
Filed Aug. 7, 1969, Ser. No. 18,573
Term of patent 14 years
Int. Cl. D20—99

U.S. Cl. D96—13



LIST OF PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 11TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- AB Volvo Pentax: See—
Borgersen, Kjell, 3,577,954.
- Abbott Laboratories: See—
Lee, Cheuk Man; and Horrom, Bruce Wayne, 3,578,672.
- Abex Corporation: See—
Dillon, Leo H.; and Weese, William F., 3,578,018.
- Abex Industries of Canada Ltd.: See—
Fullam, John P., 3,578,303.
- Absler, Howard K.; and Narel, Leonard M., to Uarco Incorporated.
Adjustable outfeed assembly for stationery burster. 3,578,178, Cl. 211-50.
- ACF Industries, Incorporated: See—
McConnell, Charles Knapp, 3,578,108.
Pulcrano, Frank C.; and Rollins, Dallas W., 3,577,932.
- Adams, David M., to Conzing Riotinto of Australia Limited Mel-
bourne. Hot and cold liquid dispenser with frand alarm. 3,578,126,
Cl. 194-16.
- Adams, Norman G.: See—
Smith, Martin B.; and Adams, Norman G., 3,578,606.
- Addressograph-Multigraph Corporation: See—
Hulse, Lauren L., 3,578,593.
Nantz, Jack G., 3,577,917.
Parker, Konrad, 3,578,452.
- Aerospace Systems Company: See—
Kriesel, Marshall S.; Anderson, Lawrence; and Ericson, Paul E.,
3,578,275.
- Afanasieva, Ljudmila Alexeevna: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva,
Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash,
Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levit-
skaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna;
Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf
Iserovich, 3,578,172.
- Agfa-Gevaert Aktiengesellschaft: See—
Kocourek, Franz, 3,578,312.
- Agonic Engineering, Inc.: See—
Jones, Richard F., 3,577,988.
- Ahlen, Karl Gustav, to S.R.M. Hydromekanik AB. Vehicle transmis-
sions. 3,578,117, Cl. 192-3.5
- Aker, Jimmie R.: See—
Cullen, Roy H.; Elliott, Charles H.; Aker, Jimmie R.; and Mohr,
Harvey O., 3,578,029.
- Aktiebolaget Grythyttans Stalmoelers: See—
Sjoberg, Ake E., 3,577,937.
- Aktiebolaget Kamyr: See—
Richter, Johan C. F. C., 3,578,554.
- Aktiebolaget Wallen: See—
Ingestad, Nils Torsten; and von Haartman, Ernst Goran,
3,578,431.
- Alden, Gardner E.; and Herterick, George M., to Avco Corporation.
Furnace support for resinoid preforms. 3,578,301, Cl. 263-47.
- Alexander, Carl V., to Schlumberger Technology Corporation. Appa-
ratus for plugging well bores with hardenable fluent substances.
3,578,079, Cl. 166-187.
- Alexander, Gordon E.: See—
Sirois, Louis L.; Winer, Albert A.; Alexander, Gordon E.; and
Page, Arthur P., 3,578,408.
- Alexander, Richard J.; and Cummisford, Robert G., to Krause Milling
Company. Cationic cereal flours and a method for their preparation.
3,578,475, Cl. 106-150.
- Alexeeva, Alevtina Vasilievna: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva,
Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash,
Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levit-
skaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna;
Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf
Iserovich, 3,578,172.
- Alfa Romeo S.p.A.: See—
Garcea, Giampaolo, 3,577,978.
- Alfa-Laval AB: See—
Forster, Adolf G., 3,577,956.
- Alfred Graf zu Erbach-Furstenau: See—
Ohse, Georg, 3,578,523.
- Alfs, Helmut: See—
List, Ferdinand; and Alfs, Helmut, 3,578,706.
- Allen, Chester W. Pneumatic tire dismounting apparatus. 3,578,058,
Cl. 157-1.47
- Allen, George Rodge, Jr.: See—
Littell, Ruddy; and Allen, George Rodge, Jr., 3,578,678.
- Allen, Roy A.: See—
Moore, Robert J.; and Allen, Roy A., 3,578,615.
- Allied Chemical Corporation: See—
Dien, Chi K., 3,578,388.
Largman, Theodore; and Newallis, Peter E., 3,578,711.
Prevorsek, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hen-
drikus J.; and Schmitt, George J., 3,578,552.
Rast, Gustav E.; and Steiner, Russell I., 3,578,652.
Twilley, Ian C.; Coli, Guido John, Jr.; and Roth, David W. H., Jr.,
3,578,640.
- Allmanna Svenska Elektriska Aktiebolaget: See—
Von Krusenstierna, Otto, 3,578,578.
- Alper, Allen M.; and Mc Nally, Robert N., to Corhart Refractories
Company. Basic fused refractory with rare earth oxide. 3,578,473,
Cl. 106-58.
- Alpma Alpenland-Maschinenbaugesellschaft Hain & Co., KG: See—
Hain, Gottfried M.; and Leonard, Wolfgang B., 3,577,865.
- Alvey, George H.; McDaniels, Paul E.; and Pease, Roy T., Jr. Football
blocking apparatus. 3,578,324, Cl. 273-55.
- Amano, Hiroyuki; Iwano, Haruhiko; Shirasu, Kazuo; and Ohi, Reiichi,
to Fuji Shashin Film Kabushiki Kaisha. Color photographic
processing with water soluble amines and salts thereof. 3,578,453,
Cl. 96-60.
- Amano, Hiroyuki; Ohi, Reiichi; Iwano, Haruhiko; and Shirasu, Kazuo,
to Fuji Shashin Film Kabushiki Kaisha. Color photographic
processing. 3,578,454, Cl. 96-60.
- Amchem Products, Inc.: See—
Caruso, Paul J.; and Kuiper, Pieter J. C., 3,578,679.
- American Chemosol corporation: See—
Bindig, Max August Helmut, 3,577,997.
- American Cyanamid Company: See—
Kazan, John, Jr.; and Foster, Walter Henry, Jr., 3,578,389.
Littell, Ruddy; and Allen, George Rodge, Jr., 3,578,678.
- Loy, Myrna; Huffman, Kenneth Robert; and Ullman, Edwin
Fisher, 3,578,683.
- Maricle, Donald Leonard; and Hoffmann, Arthur Kentaro,
3,578,500.
- Pontelandolfo, Joseph John, 3,578,592.
- Postal, Robert H., 3,578,136.
- American Hoist and Derrick Company: See—
Morse, Stanley A., 3,577,911.
- American Home Products Corporation: See—
Sulkowski, Theodore S., 3,578,677.
- American Standard Inc.: See—
Weiss, Jonas; and Hodes, William, 3,578,164.
- AMP Incorporation: See—
Steiner, Charles Dale, 3,578,228.
- Ampex Corporation: See—
Mandell, George C., 3,578,262.
- Anaconda Wire and Cable Company: See—
Gregg, Alvin L.; and Koons, Charles E., 3,578,518.
- Andersen, Frede Reinholdt, to Teknova A/S. Automatic change-over
regulator for bottled gas systems with two gas containers. 3,578,015,
Cl. 137-113.
- Anderson, Charles G., to United States of America, Atomic Energy
Commission. Method of making means for venting helium from a
radioisotope container. 3,578,442, Cl. 75-206.
- Anderson, Edwin G. Telescopic and pivotal cover assembly for open
bed vehicles. 3,578,378, Cl. 296-137.
- Anderson, Jean O. Disposable plastic, elimination-trapping bag for in-
continent patients. 3,577,989, Cl. 128-283.
- Anderson, Larry B.: See—
Cho, Boong Y.; and Anderson, Larry B., 3,578,406.
- Anderson, Lawrence: See—
Kriesel, Marshall S.; Anderson, Lawrence; and Ericson, Paul
E., 3,578,275.
- Anderson, Ronald A.; and Owens, Nevel G., to Schlumberger
Technology Corporation. Method and apparatus for plugging well
bores with hardenable fluent substances. 3,578,083, Cl. 166-285.
- Andress, Harry J., Jr.; and Ashjian, Henry, to Mobil Oil Corporation.
Liquid hydrocarbon compositions containing reaction products of an
amine and methyl vinyl ether-maleic anhydride copolymers as anti-
static agents. 3,578,421, Cl. 44-62.
- Anglo American Corporation of South Africa Limited: See—
Leslie, George W. D., 3,577,880.
- Antonsen, Olaf S.: See—
McCarriek, Terence E.; and Antonsen, Olaf S., 3,578,558.
McCarriek, Terence E.; and Antonsen, Olaf S., 3,578,561.
- Antony, Gary J.: See—
Hwa, Chih Ming; and Antony, Gary J., 3,578,589.
- Aqua-Chem, Inc.: See—
Schoppe, Fritz, 3,577,941.

- Arai, Masakazu: *See—*
Sakata, Rikita; Masuda, Kohei; Uchigaki, Taku; and Arai, Masakazu, 3,578,527.
- Arai, Masayuki, to Lyric Kabushiki Kaisha. Paper bag of simplified structure adapted to be retained in each of the opened and the folded configurations. 3,578,236, Cl. 229-55.
- Archer, Sydney, to Sterling Drug Inc. 3-(Cyclopropylalkyl)-2-hydroxy-1,4-naphthoquinones and their preparation. 3,578,685, Cl. 260-396.
- Arita, Hiroshi: *See—*
Takano, Masatoshi; Arita, Hiroshi; and Omori, Hayao, 3,577,909.
- Armington, Alton F.; and O'Connor, John J., to United States of America, Air Force. Apparatus for growth of large crystals in gels. 3,578,414, Cl. 23-273.
- Armour, Donald F., to Monsanto Company. Container with closure. 3,578,223, Cl. 222-521.
- Armstrong Cork Company: *See—*
Ehrhart, Wendell A.; and Rohrer, Clarence E., 3,578,728.
- Armstrong Jones Limited: *See—*
Jones, William H., 3,578,283.
- Arnold, Lloyd C.; and Mortimer, George A., to Monsanto Company. High-pressure closure apparatus. 3,578,407, Cl. 23-252.
- Aron, Jerome: *See—*
Hardy, John F.; Rivin, Donald; and Aron, Jerome, 3,578,635.
- Artelt, Herbert C., Jr.: *See—*
Watson, Donald W.; and Artelt, Herbert C., Jr., 3,578,316.
- A/S Westad Armaturfabrik: *See—*
Rishovd, Erik, 3,578,288.
- Asanari, Shigeyuki: *See—*
Hosokawa, Tomoyuki; Tsugeki, Toshii; and Asanari, Shigeyuki, 3,577,869.
- Asdurian, Haig: *See—*
Paterno, John W.; White, Vernon L.; Asdurian, Haig; and Grollmann, Hans W., 3,578,265.
- Ash, Arthur B.; Stevens, Calvin L.; and Markovac, Anica, to Stevens, Ash, Inc. 2,5-Bis (2-N-lower alkyl amino isopropyl)-1,3,4-trithiolanes and process for the preparation thereof. 3,578,682, Cl. 260-327.
- Ashjian, Henry: *See—*
Andress, Harry J., Jr.; and Ashjian, Henry, 3,578,421.
- Asmus, Klaus-Dieter: *See—*
Herwig, Walter; Brinkmann, Ludwig; and Asmus, Klaus-Dieter, 3,578,730.
- Atlantic Richfield Company: *See—*
Mitchell, Maurice M., Jr.; Fisher, Harold M.; and Tomezsko, Edward S. J., 3,578,650.
- Rogers, Edward S.; Hardin, Richard V., II; Harrison, Benjamin C.; and Sanford, Robert A., 3,578,505.
- Washall, Thomas A., 3,578,568.
- Attaway, Thomas J. Automatic electro-pneumatic control apparatus for car washing system. 3,578,001, Cl. 134-45.
- Atwood, Harold Thomas. Vacuum seal for dough dividers. 3,578,218, Cl. 222-383.
- Auriol, Jean G. M., to Regie Nationale des Usines Renault, and Automobiles Peugeot. Multi-disk clutches. 3,578,119, Cl. 192-70.14.
- Autoclave Engineers, Inc.: *See—*
Smith, Charles W., Jr., 3,578,201.
- Automobiles Peugeot: *See—*
Auriol, Jean G. M., 3,578,119.
- Magnier, Roger, 3,578,122.
- Avco Corporation: *See—*
Alden, Gardner E.; and Herterick, George M., 3,578,301.
- Fischer, Ronald J.; Groeneveld, Wilbur E.; and Irvine, Gerald O., 3,578,089.
- Aviroland Maatachappij voor Vliegtuigbouw N.V.: *See—*
van Marle, Nicolaas Gradus Jan Willem, 3,577,838.
- Awrath, Rudolf, to Bayerische Motoren Werke Aktiengesellschaft. Self-locking differential gear, especially for motor vehicles. 3,577,888, Cl. 74-711.
- Axelsson, John S.: *See—*
Dolan, Calvin M.; and Axelsson, John S., 3,578,520.
- Aykan, Kamran, to Du Pont de Nemours, E. I., and Company. Regenerating a platinum oxide deactivated catalyst resulting from use in eliminating oxides of nitrogen from gases. 3,578,608, Cl. 252-411.
- Aylott, Eric Victor, to Eylure Limited. Artificial fingernails for wear. 3,578,158, Cl. 206-65.
- Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., to Caterpillar Tractor Company. Tilt over roll protection frame with power tilting means. 3,578,377, Cl. 296-102.
- Bader, Karl F., Jr. Subdermal tendon implant. 3,577,837, Cl. 3-1.
- Badgerahanian, Leon; and Kemp, Thomas, to Produits Chimiques Pechiney Saint-Gobain. Preparation of vinyl polymers. 3,578,649, Cl. 260-92.8.
- Baessler, Lee R., to Humetrics Corporation. Method and apparatus for automatically screening variably recurrent waveforms such as an electrocardiac signal. 3,577,983, Cl. 128-2.06.
- Bahat, Dov; and Chu, Gordon P. K. BaO-Al₂O₃-SiO₂ glass-ceramic materials. 3,578,470, Cl. 106-39.
- Baker, Arthur Kenneth. Apparatus for producing reinforced plastics material articles. 3,578,529, Cl. 156-393.
- Bakker, Fred: *See—*
Bouman, Clarence N.; and Bakker, Fred, 3,578,357.
- Baldyga, Joseph W., to Diamond Die & Mold Co. Press feed control. 3,578,230, Cl. 226-162.
- Ballester, Jose F. Corner suspendable pail and hanger. 3,578,205, Cl. 220-85.
- Ban, Itsuki. Automatic playing apparatus utilizing plurality of endless tape cartridges. 3,578,334, Cl. 274-4.
- Ban, Itsuki. Sound track changeover device for automatic playing apparatus having a plurality of endless tape cartridges. 3,578,335, Cl. 274-4.
- Ban, Itsuki. Automatic playing apparatus utilizing plurality of endless tape cartridges. 3,578,336, Cl. 274-4.
- Banziger, Walter: *See—*
Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, 3,578,257.
- Barber, Trevor Leslie: *See—*
King, Maurice; and Barber, Trevor Leslie, 3,577,970.
- Barnett, David W.: *See—*
Riggs, Olen L., Jr.; and Barnett, David W., 3,578,607.
- Barratt, Robert Owen; and Poleer, John, to Foster Wheeler Corporation. Saturated steam supply system for a steam cooled fast breeder reactor. 3,577,959, Cl. 122-31.
- Barrere, Clem A., Jr., to Continental Oil Company. Method for cooling heated adsorbent beds. 3,577,867, Cl. 55-62.
- Barton, Hugh Perry, to Barton, R. P., & Company. Machine for size-grading walnuts. 3,578,161, Cl. 209-86.
- Barton, R. P., & Company: *See—*
Barton, Hugh Perry, 3,578,161.
- Basic Incorporated: *See—*
Jepsen, Tage L. B., 3,578,162.
- Battelle Development Corporation, The: *See—*
Kuethe, Arnold M., 3,578,264.
- Battersby, William R.; Follett, Robert P.; MacGranule, Timothy D.; Rossitto, Conrad; and Taylor, Paul, to United Shoe Machinery Corporation. Two-rod hot-melt adhesives from polycapoxides or polyurethane systems. 3,578,727, Cl. 260-830.
- Bauer, Ignaz; Riedle, Rudolf; and Nitzsche, Siegfried, to Wacker-Chemie G.m.b.H. Molded articles and coatings based on organopoly-siloxanes. 3,578,490, Cl. 117-138.8.
- Baulin, Jury Nikolaevich: *See—*
Karpacheva, Susanna Mikhailovna; Raginsky, Leonid Solomonovich; Muratov, Valerian Matveevich; Ivanov, Vladimir Dmitrievich; and Baulin, Jury Nikolaevich, 3,578,174.
- Baum, Lloyd. Jaw hinge axis locator. 3,577,855, Cl. 33-174.
- Baumann, Bernard, to L'Aluminium Francais. Process for the assembly of sheets and apparatus for same. 3,578,519, Cl. 156-69.
- Baxter, George, to Moore Business Forms, Inc. Process for making dual walled microcapsules. 3,578,605, Cl. 252-316.
- Baxter Laboratories, Inc.: *See—*
Marbach, Edward P., 3,578,039.
- Bayerische Motoren Werke Aktiengesellschaft: *See—*
Awrath, Rudolf, 3,577,888.
- Beardsley, Herbert P., to Du Pont de Nemours, E. I., and Company. Vinyl acetate-ethylene copolymer aqueous paint compositions. 3,578,618, Cl. 260-17.
- Becher, Elisabeth: *See—*
Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, 3,578,565.
- Beck, George Eugene: *See—*
London, Melvyn; Smetters, Guy Robert; and Beck, George Eugene, 3,577,920.
- Beck, Ralph A., to Beloit Corporation. Endless belt with pockets for collecting water drained through a fourdrinier wire. 3,578,559, Cl. 162-303.
- Beck, Richard J.: *See—*
Lundberg, John B.; Beck, Richard J.; and Locke, James N., 3,578,045.
- Becker, Herbert: *See—*
Tesch, Hans-Jurgen; Haverkamp, Gunther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, 3,578,092.
- Becker, Mitchell, to Halcon International, Inc. Process for preparing molybdenum acid salts. 3,578,690, Cl. 260-414.
- Becker, Warren E.; and Kobetz, Paul, to Ethyl Corporation. Process for producing aluminum. 3,578,436, Cl. 75-0.5.
- Beckman Instruments, Inc.: *See—*
Martin, Donald N., 3,578,412.
- Rochte, Jerry E.; and McDavid, Larry S., 3,578,020.
- Beckmann, Rudolf, to Volkswagenwerke Aktiengesellschaft. Control for internal combustion engines. 3,577,963, Cl. 123-117.1.
- Behrens, Ulrich: *See—*
Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfeil, Manfred; and Sattler, Karl, 3,578,566.
- Belknap, Donald J. Apparatus for making miniature incandescent lamps. 3,578,429, Cl. 65-154.
- Beloit Corporation: *See—*
Beck, Ralph A., 3,578,559.
- Beluc, James C.: *See—*
Philipps, Thomas E.; and Beluc, James C., 3,578,426.
- Bender, David L.; and Moore, Robert E., to Kayex Corporation. Transfer device for cutting apparatus. 3,577,861, Cl. 51-73.
- Bentley, Donald J.; and De Wall, Richard A., said DeWall assor. to Bentley Laboratories, Inc. Bubbler assembly for blood treating apparatus. 3,578,411, Cl. 23-258.5.
- Bentley Laboratories, Inc.: *See—*
Bentley, Donald J.; and De Wall, Richard A., 3,578,411.

- Benyash, Galina Nikolaevna: *See—*
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Iserovich, 3,578,172.
- Berg Mfg. & Sales Co.: *See—*
Klimek, Boleslaw, 3,578,286.
- Bergwerf, Willem: *See—*
Klootwijk, Arie; Bergwerf, Willem; and Wager, Willem M., 3,578,700.
- Bergwerksverband GmbH: *See—*
Krucl, Martin; Juentgen, Harald; and Drwatwa, Heinrich, 3,578,390.
- Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, to Hoffmann-La Roche Inc. 18-Nor-14 β -pregnano-[13,14- η]-hexahydro-1,4-oxazepines. 3,578,659, Cl. 260-239.55.
- Berry, Harry E. Quick-connect coupling conversion means for beer kegs. 3,578,219, Cl. 222-394.
- Bertholdt, Horst: *See—*
Schweigert, Friedrich; and Bertholdt, Horst, 3,578,573.
- Bertin & Cie: *See—*
Bertin, Jean Henri, 3,577,927.
- Bertin, Jean Henri, to Bertin & Cie. Arrangement for confining a volume of fluid. 3,577,927, Cl. 104-23.
- Bethell, James Robert; and Hadley, David James, to BP Chemicals (U.K.) Limited. Production of unsaturated aliphatic acids. 3,578,707, Cl. 260-530.
- Betz, Andrew J., Jr., to United States of America, Navy. Acceleration and pressure responsive fluid valve. 3,578,006, Cl. 137-38.
- Beudin, Leonel, to Bureau de Recherches Geologiques et Minieres. Bar-type rotary crushers. 3,578,251, Cl. 241-74.
- Bialous, Charles A.; Jaquiss, Donald B. G.; and Keane, John J., to General Electric Company. Thermally stable copolycarbonate phosphite. 3,578,634, Cl. 260-47.
- Biedny, Louis. Wire loop amusement game. 3,578,329, Cl. 273-119.
- Bilow, Norman; and Miller, Leroy J., to Hughes Aircraft Company. Aromatic polymers and method. 3,578,611, Cl. 260-2.
- Bindig, Max August Helmut, to American Chemosol corporation. Tobacco treatment with citric acid and deuterium oxide. 3,577,997, Cl. 131-17.
- Bird, Arnett L.: *See—*
Walles, Wilhelm E.; and Bird, Arnett L., 3,578,484.
- Bishop, John J.; and Jache, Albert W., to Olin Corporation. Preparation of alkali metal salts of nitrilotriacetic acid. 3,578,709, Cl. 260-534.
- Black Clawson Company, The: *See—*
McCarrick, Terence E.; and Antonsen, Olaf S., 3,578,558.
- McCarrick, Terence E.; and Antonsen, Olaf S., 3,578,561.
- Notbohm, Willard C.; Lamb, Charles A.; and Hanson, J. Leslie, 3,578,560.
- Black Clawson Company, The: *See—*
Notbohm, Willard C.; and Schaffrath, Paul M., 3,578,556.
- Black, David F., to United States of America, Army. Mechanized vehicle system. 3,578,185, Cl. 214-38.
- Blake, William W., to Caterpillar Tractor Company. Delayed governor cut-off valve. 3,578,007, Cl. 137-51.
- Blanc, Joachim Hillard; and Prince, Martin. Method for producing malononitrile. 3,578,696, Cl. 260-465.3.
- Blaw-Knox Company: *See—*
Cerutti, Henry P., 3,577,862.
- Blechman, Dan. Stopper for self-opening can. 3,578,198, Cl. 220-25.
- Bloch, Moshe R.; Forgaes, Chaim; and Bobker, Ronald V., to Israel, Prime Minister Office, and Dead Sea Works Ltd. Devices for the electrochemical generation of electrical current. 3,578,503, Cl. 136-102.
- Bloch, Roy W.; and Jewell, Donald K., to Ekco Products, Inc. Container with flexible reinforced wall members. 3,578,204, Cl. 220-72.
- Blood, Alden E.: *See—*
Snapp, Thomas Carter, Jr.; Blood, Alden E.; and Hagemeyer, Hugh John, Jr., 3,578,702.
- Bloom, Stanley M., to Polaroid Corporation. Transfer image process utilizing an organic phosphine as silver halide solvent. 3,578,449, Cl. 96-29.
- Bloom, Stanley M.; Simon, Myron S.; and Ward, Jeanne A., to Polaroid Corporation. Diffusion transfer dye developer processes and products employing ortho and para hydroxy and para amino substituted pyridines. 3,578,448, Cl. 96-3.
- Bobker, Ronald V.: *See—*
Bloch, Moshe R.; Forgaes, Chaim; and Bobker, Ronald V., 3,578,503.
- Bodine, Albert G. Sonic method and apparatus for laying and repairing asphalt material. 3,577,897, Cl. 94-48.
- Bodine, Albert G. Sonic method and apparatus for augmenting the flow of oil from oil bearing strata. 3,578,081, Cl. 166-249.
- Boe, Otto H.: *See—*
Kramer, Kenneth C.; Davis, Richard L.; and Boe, Otto H., 3,578,269.
- Boeglin, Albert F., to International Minerals & Chemicals Corporation. Production of crystalline potassium sulfate. 3,578,399, Cl. 23-121.
- Boeing Company, The: *See—*
Upton, Gerlad G., 3,578,266.
- Boigk, Eckhard: *See—*
Knipp, Ulrich; Boigk, Eckhard; and Weinbrenner, Erwin, 3,578,057.
- Boileau, Jacques, to Compagnie Generale des Etablissements Michelin, raison sociale Michelin & Cie. Tire covers. 3,578,054, Cl. 152-330.
- Boldt, Alvin M. Self-contained handle heater. 3,577,974, Cl. 126-208.
- Bolinger, Edgar D. Sized twistless yarns. 3,578,492, Cl. 117-139.5.
- Bolton, Robert Benjamin. Chain conveyor. 3,578,147, Cl. 198-171.
- Bombardieri, Caurino C.; and Tod, James F., to Esso Production Research Company. Thermal well completion method and apparatus. 3,578,084, Cl. 166-288.
- Boose, Robert C., to Escoa Fintube Corporation. Method and apparatus for manufacturing radially finned heat exchange tubing. 3,578,165, Cl. 219-107.
- Borgersen, Kjell, to AB Volvo Penta. Tilt latching and locking means for tiltable stern drives for boats. 3,577,954, Cl. 115-41.
- Borgerson, Henry E.; and Borgerson, Lewis K. Urinary appliance. 3,577,990, Cl. 128-295.
- Borgerson, Lewis K.: *See—*
Borgerson, Henry E.; and Borgerson, Lewis K., 3,577,990.
- Borrello, Sebastian Ronald; and Roberts, Charles Grady, to Texas Instruments, Incorporated. Process for fabricating planar diodes in semi-insulating substrates. 3,578,515, Cl. 148-175.
- Bosch, Robert, GmbH: *See—*
Staudt, Heinrich, 3,577,967.
- Staudt, Heinrich; Hofmann, Eberhard; and Muller, Rolf, 3,577,968.
- Bosquin, Maurice, to L'Air Liquide Societe Anonyme pour l'Etude et l'Exploitation des Procédes Georges Claude. Heat exchange apparatus with integral formation of heat exchangers and separators. 3,578,073, Cl. 165-111.
- Bostick, Edgar E.; and Fessler, William A., to General Electric Company. Condensation method for making multiple sequence organopolysiloxane block polymers. 3,578,726, Cl. 260-825.
- Bottai, Gabriele A.; and Stinson, John M., to Tennessee Valley Authority. Method for urea-ammonium polyphosphate production. 3,578,433, Cl. 71-1.
- Boucaut, Michel; Toth, Imre; and Reyter, Jean Pierre, to Institut de Recherches de la Siderurgie Francaise. Apparatus for treating particulate materials. 3,578,296, Cl. 263-21.
- Bouman, Clarence N.; and Bakker, Fred, to Holland Hitch Company. Fifth wheel lock assembly. 3,578,357, Cl. 280-434.
- Bourns/Cai, Inc.: *See—*
Gray, Earl E., 3,577,901.
- Boutsicaris, Stephen, to Firestone Tire & Rubber Company, The. Process and composition. 3,578,627, Cl. 260-94.4.
- Boven, Jan: *See—*
Houtman, Harke Jan; Schoot, Cornelis Johannes; Boven, Jan; and van Beek, Leendert Klaas Hellinga, 3,578,457.
- Bowes, Emmerson; and Wise, John J., to Mobil Oil Corporation. Isomerization and disproportionation of aromatic hydrocarbons. 3,578,723, Cl. 260-672.
- BP Chemicals (U.K.) Limited: *See—*
Bethell, James Robert; and Hadley, David James, 3,578,707.
- Fraser, Robert Neil, 3,578,722.
- Bradley, John J.: *See—*
Small, Rudolph E.; and Bradley, John J., 3,578,155.
- Bragg, Herbert E., to Twentieth Century-Fox Film Corporation. Supplemental illuminating of film plane in photographic cameras. 3,577,898, Cl. 95-11.
- Brambier, Irving. Jigsaw puzzle of a size requiring large muscle exercise. 3,578,330, Cl. 273-157.
- Braun Aktiengesellschaft: *See—*
Hasselbach, Wolfgang; and Heim, Heinz, 3,578,304.
- Braun, Siegfried; and Hieber, Heinz, to Zahnradfabrik Friedrichshafen Aktiengesellschaft. Lifting apparatus for outboard motors. 3,577,953, Cl. 115-41.
- Breiling, Hans Georg, to Dragerwerke, Heint. & Bernh. Vaporizer for anesthetic. 3,578,042, Cl. 141-301.
- Brewer, John C., to Garbalizer Corporation of America. Industrial shredding apparatus. 3,578,252, Cl. 241-141.
- Briggs & Stratton Corporation: *See—*
Santi, John D., 3,578,293.
- Brilliant, Arthur, Jr. Dual rotation mill. 3,578,253, Cl. 241-168.
- Brinkmann, Ludwig; Herwig, Walter; and Cherdron, Harald, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Brunn. Thermoplastic polyester molding compositions. 3,578,729, Cl. 260-873.
- Brinkmann, Ludwig: *See—*
Herwig, Walter; Brinkmann, Ludwig; and Asmus, Klaus-Dieter, 3,578,730.
- Bristol-Myers Company: *See—*
Havranek, Robert Edward; and Crast, Leonard Bruce, Jr., 3,578,661.
- British Columbia Research Council: *See—*
Reeder, James A., 3,578,619.
- British Oxygen Company Limited, The: *See—*
Taylor, Leslie G.; and Withey, Donald S., 3,578,197.
- Brochard, Guy, to Societe Anonyme D.B.A. Vortices, particularly to their outlet. 3,578,013, Cl. 137-81.5.
- Brock, Glover B. Electrically controlled fluid distribution system. 3,578,245, Cl. 239-66.

- Bromley, Le Roy A.; and Read, Stanley M., to Regents of the University of California, The. Method and device for flow control of liquor by vortex movement of the liquor. 3,578,004, Cl. 137-1.
- Bronnenkant, Paul H., to Hallmark Plastics, Inc. Article having an integral elongated appendage, and method of manufacturing the same. 3,577,987, Cl. 128-130.
- Brown, Francis W.; and Kremer, Leon V., to Minnesota Mining and Manufacturing Company. Sprayable adhesive. 3,578,622, Cl. 260-33.8.
- Brown, James D.: See—
Mueller, Francis X., Jr.; and Brown, James D., 3,578,642.
- Brown, Kevan, to Wyeth, John, & Brothers Limited mesne. Oxazoles. 3,578,671, Cl. 260-307.
- Brown, Richard L. Air operated amusement device. 3,578,326, Cl. 273-101.
- Bruson, Herman A.; and Plant, Howard L., to Olin Corporation. 3-Nitroaryl-4-haloisoxazoles and method for preparing same. 3,578,673, Cl. 260-307.
- Bruson, Herman A.; and Plant, Howard L., to Olin Corporation. Dihaloacyclopropane derivatives. 3,578,710, Cl. 260-543.
- Buberniak, Harry P. Self-holding hinge. 3,577,840, Cl. 16-142.
- Buchschacher, Paul: See—
Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.
- Buckler, Robert Thomas, to Miles Laboratories, Inc. Derivatives of tetrazolylalkanoic acids. 3,578,674, Cl. 260-308.
- Buckman, Wayne T.: See—
Combs, William H.; Craig, Sam N.; Warner, Ellis R., Jr.; and Buckman, Wayne T., 3,578,250.
- Budd Company, The: See—
Eggert, Walter S., Jr., 3,577,903.
- Bugaut, Andre: See—
Kalopissis, Gregoire; and Bugaut, Andre, 3,578,386.
- Bunker-Ramo Corporation: See—
Flum, Herman H., 3,578,124.
- Burba, Christian; Drawet, Manfred; and Griesch, Eugen, to Schering AG. Polyurethane foams based on dimer fatty acid polyalkanolamides. 3,578,612, Cl. 260-2.5.
- Bureau de Recherches Geologiques et Minières: See—
Beudin, Leonel, 3,578,251.
- Burford, Chester O., to Federal Mfg. Co. Receptacle filling method. 3,578,038, Cl. 141-7.
- Burg, Frederick J., to Salton, Inc. Egg cooker. 3,577,908, Cl. 99-333.
- Burgess & Associates, Inc.: See—
Burgess, Warren C., Jr., 3,578,142.
- Burgess, Warren C., Jr., to Burgess & Associates, Inc. Tooling for vibratable bowl. 3,578,142, Cl. 198-33.
- Buriks, Rudolf S.: See—
Mange, Franklin E.; Buriks, Rudolf S.; and Quinlan, Patrick M., 3,578,731.
- Burkard, Edward A.: See—
Lapp, Leon R.; and Burkard, Edward A., 3,578,517.
- Burke, Richard L., to Colgate-Palmolive Company. Stabilization of N-chloro-imides. 3,578,598, Cl. 252-102.
- Burke, Richard L., to Colgate-Palmolive Company. Stabilization of N-chloro-imides. 3,578,599, Cl. 252-102.
- Burke, Richard L., to Colgate-Palmolive Company. Stabilization of N-chloro-imides. 3,578,600, Cl. 252-102.
- Burnham, Edward H.; and Lavander, Edward J., to Xerox Corporation. Sheet conveyor apparatus for automatic copying machine. 3,578,317, Cl. 271-69.
- Burr, Gary D.: See—
Elliott, Daniel L.; and Burr, Gary D., 3,578,068.
- Burroughs Corporation: See—
Dupuis, Guy-Louis, 3,578,368.
- Eppinger, Rolf H., 3,578,313.
- Hinze, Herbert J., 3,577,913.
- Bushnell, Roger B., to Controsion Electrostatic Limited. Powder delivery arrangements. 3,578,215, Cl. 222-193.
- Busi, Giovanni. Horizontal scrap metal press. 3,577,912, Cl. 100-218.
- Buss, Waldeen C., to Chevron Research Company. Reforming process with promoted low platinum content catalyst. 3,578,583, Cl. 208-138.
- Butler Manufacturing Company: See—
Evans, Wayne, 3,578,521.
- Butterfield, Max E.: See—
Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., 3,578,377.
- Buzzolini, Mario G.: See—
Frey, Albert J.; and Buzzolini, Mario G., 3,578,712.
- Cable, James R.: See—
Petro, Victor P.; Cable, James R.; and Wainer, Eugene, 3,578,456.
- Cahlk, Jim C.: See—
Taylor, Norris O.; Uhler, Wilmer P.; Gardella, John M.; and Cahlk, Jim C., 3,578,379.
- Caldwell, Stanley Benson. Golf putter with centrally located spheroidal enlargement. 3,578,332, Cl. 273-164.
- Campagnuolo, Carl J.; and Villarroel, Fernando, to United States of America, Army. Fluoric velocity discriminator. 3,578,010, Cl. 137-81.5.
- Campbell, David H.: See—
Cook, Charles A.; and Campbell, David H., 3,578,543.
- Canadian Industries Limited: See—
Findlay, Donald Urquhart; McCaffrey, Francis Hamnet Garland; and Taylor, George David, 3,577,924.
- Canadian International Paper Company: See—
Godsay, Madhu P.; and Mac Donald, Donald M., 3,578,553.
- Canadian Patents and Development Limited: See—
Sirois, Louis L.; Winer, Albert A.; Alexander, Gordon E.; and Page, Arthur P., 3,578,408.
- Cantrell, Robert R.; and Swanson, Vernon F., to Grace, W. R., & Co. Sulfur extraction using halogenated hydrocarbons including washing the recovered sulfur with methanol, acetone, or ethylene glycol. 3,578,418, Cl. 23-299.
- Cantwell, Gill, to Data Products Corporation. Paper adjusting mechanism. 3,578,138, Cl. 197-133.
- Caravan Products Co., Inc.: See—
Smerak, Louis J.; and Miller, Jason A., 3,578,462.
- Carborundum Company, The: See—
Goodrich, Allen C., 3,578,300.
- Carlin, Eunice A. Slide construction. 3,577,895, Cl. 94-7.
- Carlini, Dominique, to Recherches et Applications des Plastiques Dans l'Industrie et le Batiment, S.A. Mandrel. 3,578,531, Cl. 156-425.
- Carlisle Chemical Works, Inc.: See—
Stapfer, Christian H., 3,578,621.
- Carlson, Ronald H., to Hooker Chemical Corporation. Metal sequestrant. 3,578,708, Cl. 260-534.
- Carlton, Sydney E. Sample and bleed valve. 3,578,285, Cl. 251-218.
- Carsner, George E.: See—
Lindquist, Everett F.; and Carsner, George E., 3,578,159.
- Carson, Joseph R., Jr., to Clement, J. W., Company. Signature or sheet collating system. 3,578,310, Cl. 270-54.
- Carson, Richard M.; and Sacks, Reuben R., to Carson-Sacks, Inc. Flexible odor-liberating laminate. 3,578,545, Cl. 161-86.
- Carson-Sacks, Inc.: See—
Carson, Richard M.; and Sacks, Reuben R., 3,578,545.
- Carter, Terry L., III: See—
Wood, Philip W.; Carter, Terry L., Jr.; and Carter, Terry L., III, 3,578,311.
- Carter, Terry L., Jr.: See—
Wood, Philip W.; Carter, Terry L., Jr.; and Carter, Terry L., III, 3,578,311.
- Caruso, Paul J.; and Kuiper, Pieter J. C., to Amchem Products, Inc. Decenylsuccinamic acid and imide frost and freeze preventative compounds. 3,578,679, Cl. 260-326.5.
- Case, J. I., Company: See—
Horsch, Rudolf, 3,578,191.
- Caterpillar Tractor Company: See—
Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., 3,578,377.
- Blake, William W., 3,578,007.
- Clancy, Lawrence F.; Grooss, Frank A.; and Luttrell, Richard W., 3,578,098.
- Kranc, Stanley J.; and Krauja, Ziedonis I., 3,577,969.
- Loyd, Calvin D.; Oberle, Theodore L.; and Satzler, Ronald L., 3,578,232.
- Cauthery, Brian R. Pipe adapter. 3,578,362, Cl. 285-110.
- Cavil, David T., to Outboard Marine Corporation. Contactless and distributorless ignition system. 3,577,971, Cl. 123-148.
- Celanese Corporation and Fiber Industries, Inc.: See—
Gray, Jack N.; and Watson, George A., 3,578,551.
- Cerutti, Henry P., to Blaw-Knox Company. Composite precompressed grating structure. 3,577,862, Cl. 52-223.
- Ceskoslovenska akademie ved: See—
Sorm, Frantisek; and Suchy, Milos, 3,578,699.
- Chandler Evans Inc.: See—
Jahrstorfer, George W., 3,578,022.
- Sundberg, Jack G., 3,577,965.
- Charvat, Vernon K.; and Jarvi, Robert E., to Sherwin-Williams Company, The, mesne. Brush and brush material. 3,577,839, Cl. 15-179.
- Chassoux, Rene, to Societe des Accumulateurs Fixes et de Traction (Societe Anonyme). Sealing arrangement for terminals of electrochemical generators. 3,578,506, Cl. 136-168.
- Chemotron Corporation: See—
Hammon, George L., 3,578,051.
- Chemische Fabrik Promonta GmbH: See—
Konig, Joachim; and Padberg, Gunter, 3,578,655.
- Chemische Werke Huels A.G.: See—
List, Ferdinand; and Alfs, Helmut, 3,578,706.
- Cherdron, Harald: See—
Brinkmann, Ludwig; Herwig, Walter; and Cherdron, Harald, 3,578,729.
- Cherny, Anatoly Alexeevich; Vladimir Alexandrovich; Lev Mikhailovich; Kurbatsky, Ivan Lukich; Sosnovsky, Efim Davidovich; and Pavlenko, Nikolai Semenovich. Gas cupola furnace with a special superheat hearth. 3,578,302, Cl. 266-11.
- Chevron Research Company: See—
Buss, Waldeen C., 3,578,583.
- Jacobson, Robert L., 3,578,582.
- Kluksdahl, Harris E.; and Hopkins, James R., 3,578,395.
- Chiang, Kang-Rong; Kun, Zoltan K.; and Robinson, Robert J., to Zenith Radio Corporation. Method of producing non-opaque P-type wide band gap semiconductor materials. 3,578,507, Cl. 148-1.5.
- Chiola, Vincent; Cleveland, Joseph J.; Kamin, George J.; and Kim, Tai K., to Sylvania Electric Products, Inc. Yttrium purification. 3,578,391, Cl. 23-22.

- Chisso Corporation: See—
Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishihashi, Hiroaki, 3,578,435.
- Cho, Boong Y.; and Anderson, Larry B., to United States of America, Atomic Energy Commission. Sulfur dioxide measurement system. 3,578,406, Cl. 23-232.
- Cholmar, Sidney; and Peters, Robert H., to Monsanto Company. Method and apparatus for molding plastic articles. 3,578,735, Cl. 264-89.
- Chruniak, Metody. Smoke eliminator. 3,578,294, Cl. 261-90.
- Chu, Gordon P. K.: See—
Bahat, Dov; and Chu, Gordon P. K., 3,578,470.
- Chun, Sun W.; and Friend, William H., to Union Camp Corporation. Process for treating collulosic digesting liquor containing soap. 3,578,628, Cl. 260-97.7.
- Ciba Corporation: See—
Louis, Kwok Toy; Wurmser, Donald W.; and Zaritsky, Herbert, 3,578,617.
- Cities Service Company: See—
Wood, Philip W.; Carter, Terry L., Jr.; and Carter, Terry L., III, 3,578,311.
- Clack Corporation: See—
Clack, Willis E.; Kay, Clifford; and Nygren, Charles E., 3,578,167.
- Clack, Willis E.; Kay, Clifford; and Nygren, Charles E., to Clack Corporation. Multiple-tank water conditioning system and valve therefor. 3,578,167, Cl. 210-134.
- Clancy, Lawrence F.; Grooss, Frank A.; and Luttrell, Richard W., to Caterpillar Tractor Company. Operator station and support. 3,578,098, Cl. 180-89.
- Clark, Robert O., to United States of America, Air Force. Fast opening plate valve shock tube system. 3,578,008, Cl. 137-68.
- Clark-Aiken Company, The: See—
Moore, Clark A., 3,577,892.
- Clarke, Edwin E.; and Florig, Albert J. Container with dispensing means for transporting bulk materials. 3,578,213, Cl. 222-95.
- Cleereman, Kenneth J.; and Thomas, Lowell S., to Dow Chemical Company, The. Expandable plastic articles. 3,578,549, Cl. 161-160.
- Clement, J. W., Company: See—
Carson, Joseph R., Jr., 3,578,310.
- Cleveland, Joseph J.: See—
Chiola, Vincent; Cleveland, Joseph J.; Kamin, George J.; and Kim, Tai K., 3,578,391.
- Cline, Ted L. Subsoiler chisel plow. 3,578,090, Cl. 172-439.
- Closmann, Philip J., to Shell Oil Company. Method of producing shale oil from an oil shale formation. 3,578,080, Cl. 166-248.
- Cluett Peabody & Co., Inc.: See—
Hughes, Francis H.; and Crawford, Douglas J., 3,578,181.
- Cluff, Edward Fuller, to Du Pont de Nemours, E. I., and Company. Clay filled, sulfur-cured elastomers compounded with hydroxyl-terminated butadiene polymers. 3,578,624, Cl. 260-41.5.
- Clyde Corporation: See—
Coapman, Richard T.; and Ginther, Gary D., 3,578,211.
- Coapman, Richard T.; and Ginther, Gary D., to Clyde Corporation. Loader for reciprocating hopper. 3,578,211, Cl. 222-56.
- Coates, Joseph F.: See—
Wakeman, Reginald L.; and Coates, Joseph F., 3,578,667.
- Coffey, Charles R.: See—
Crotty, Homer E.; Coffey, Charles R.; and Tesdahl, Thomas C., 3,578,499.
- Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, to Mohawk Data Sciences Corporation. Tape handling apparatus for data recorder. 3,578,257, Cl. 242-68.3.
- Cohen, Milton J. Fluid extraction device. 3,577,980, Cl. 128-2.
- Coleco Industries, Inc.: See—
Dicmond, Joseph; Gershman, Melvin Y.; and Ravreby, Fred A., 3,578,023.
- Coleman, James T.; and Fox, James W., to Coleman-Fox, Inc. Portable running chute. 3,578,323, Cl. 273-55.
- Coleman, Lester E., to Lubrizol Corporation, The. Polymers of aromatic N-3-oxohydrocarbon- substituted acrylamides. 3,578,637, Cl. 260-63.
- Coleman-Fox, Inc.: See—
Coleman, James T.; and Fox, James W., 3,578,323.
- Colgate Palmolive Company: See—
Schnettler, Richard A.; and Suh, John T., 3,578,668.
- Colgate-Palmolive Company: See—
Burke, Richard L., 3,578,598.
- Burke, Richard L., 3,578,599.
- Burke, Richard L., 3,578,600.
- Lazaridis, Christina Nicholson; and Wixon, Harold Eugene, 3,578,591.
- Coli, Guido John, Jr.: See—
Twilley, Ian C.; Coli, Guido John, Jr.; and Roth, David W. H., Jr., 3,578,640.
- Collingwood, Wilford R.; Hutchison, William M.; and Mangas, Frank E., to Ford Motor Company. Engine antidiesselling device. 3,577,966, Cl. 123-124.
- Combs, William H.; Craig, Sam N.; Warner, Ellis R., Jr.; and Buckman, Wayne T., to Wascos Systems, Incorporated. Pulping apparatus. 3,578,250, Cl. 241-46.02.
- Combustion Engineering, Inc.: See—
Fletcher, William D., III, 3,578,564.
- Johnson, Loering M.; and Yuile, Arthur M., 3,578,562.
- Commissariat a l'Energie Atomique: See—
Guilbaud, Jean-Pierre; and Vertut, Jean, 3,578,097.
- Compagnie Francaise de Raffinage: See—
Tannenberger, Helmut; and Kovacs, Paul, 3,578,502.
- Compagnie Generale des Etablissements Michelin, raison sociale Michelin & Cie: See—
Boileau, Jacques, 3,578,054.
- Compagnie Pechiney: See—
Morel, Paul; Givry, Jean-Pierre; and Voisin, Philippe, 3,578,069.
- Congdon, George L.; and Kufrin, Fred W., to Western Industries, Inc. Fluid sprinkler having means for driving and reversing an oscillating distributing tube of uniform speed. 3,578,248, Cl. 239-242.
- Conrad, Ulrich: See—
Deutschmann, Herbert; and Conrad, Ulrich, 3,577,961.
- Consolidated Educational Publishing, Inc.: See—
Macomber, James Keith, 3,578,229.
- Continental Oil Company: See—
Riggs, Olen L., Jr.; and Barnett, David W., 3,578,607.
- Continental Oil Company: See—
Barrere, Clem A., Jr., 3,577,867.
- McGuire, Stephen E.; and Kennedy, Eugene F., 3,578,704.
- Riggs, Olen L., Jr., 3,578,402.
- Williams, Billy J.; and Starks, Charles M., 3,578,494.
- Continental/Moss-Gordin, Inc.: See—
Towery, Jack D., 3,577,844.
- Contraves AG: See—
Furrer, Eduard, 3,578,025.
- Controsion Electrostatic Limited: See—
Bushnell, Roger B., 3,578,215.
- Conway, David D., to Marathon Oil Company. Penetrating oil formulation. 3,578,596, Cl. 252-49.6.
- Conzring Riotinto of Australia Limited Melbourne: See—
Adams, David M., 3,578,126.
- Cook, Charles A.; and Campbell, David H., to Ethyl Corporation. Seal for plastic sheeting. 3,578,543, Cl. 161-38.
- Cooper Industries, Inc.: See—
Zelnick, Charles; and Schmidt, Erwin, 3,578,259.
- Cooper, Robin D. G., to Lilly, Eli, and Company. 2-Acyloxyccephalosporin compounds. 3,578,660, Cl. 260-243.
- Coopersmith, Leo, to Ives, H. B., Company, The. Self-operating extension flush bolt. 3,578,369, Cl. 292-58.
- Coors Porcelain Company: See—
Pearce, Ronald A., 3,578,139.
- Copes, John C. Mechanical seal inserts. 3,578,345, Cl. 277-81.
- Corbier, Bernard Pierre; and Teisseire, Paul Jose, to S.A. des Etablissements Roure-Bertrand fils & Justin Dupont. Novel diketones and derivatives thereof. 3,578,715, Cl. 260-586.
- Corbin, James E., to Ralston Purina Company, The. Food product. 3,578,459, Cl. 99-1.
- Corhart Refractories Company: See—
Alper, Allen M.; and McNally, Robert N., 3,578,473.
- Cornelius Company, The: See—
Cornelius, Richard T., 3,578,194.
- Cornelius, Richard T., to Cornelius Company, The. Throw-away beverage bottles. 3,578,194, Cl. 215-13.
- Cornell, John H., Jr., to Monsanto Research Corporation. Isocyanurate manufacture. 3,578,662, Cl. 260-248.
- Corning Glass Works: See—
Hebert, Normand C.; and Nordberg, Martin E., 3,578,579.
- Lachman, Irwin M., 3,578,471.
- Corrigan, John E., to Moffitt, Roy M., Company, The. Rotary coupling and seal combination. 3,578,361, Cl. 285-98.
- Couture, Maurice Joseph; Gerner, Hans M. B.; and Gibbs, Hugh H., to Du Pont de Nemours, E. I., and Company. Process for reducing the formation of polymer attendant the pyrolysis of tetrafluoroethylene. 3,578,721, Cl. 260-648.
- Covey, Rupert A.; von Schmeling, Bogislav; and Crittendon, Charles E., to Uniroyal, Inc. Alkyl carbalkoxyalkyl and alkyl alkanoyloxyalkyl sulfites. 3,578,694, Cl. 260-456.
- CPC International Inc.: See—
Kite, Francis E.; and Stejskal, Joseph F., 3,578,498.
- Luckmann, Frederick Hugo; and Melnick, Daniel, 3,578,466.
- Craig, Sam N.: See—
Combs, William H.; Craig, Sam N.; Warner, Ellis R., Jr.; and Buckman, Wayne T., 3,578,250.
- Crainich, Victor A., Jr.: See—
Whitaker, John G.; and Crainich, Victor A., Jr., 3,578,482.
- Craut, Leonard Bruce, Jr.: See—
Havranek, Robert Edward; and Craut, Leonard Bruce, Jr., 3,578,661.
- Crawford, Douglas J.: See—
Hughes, Francis H.; and Crawford, Douglas J., 3,578,181.
- Crawford, John H., to Leading Plywood, Sheet conveyor system. 3,578,151, Cl. 198-230.
- Cremasco, Venanzio Micheletti; and Roano, Domenico, to Olivetti, Ing., C., & C., S.p.A. Half-space carriage return mechanism for typewriters. 3,578,132, Cl. 197-91.
- Critcher, John L.: See—
Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., 3,577,949.
- Crittendon, Charles E.: See—
Covey, Rupert A.; von Schmeling, Bogislav; and Crittendon, Charles E., 3,578,694.
- Crotty, Homer E.; Coffey, Charles R.; and Tesdahl, Thomas C., to Grace, W. R., & Co. Gelling composition for general purpose cleaning and sanitizing. 3,578,499, Cl. 134-4.

Cryodry Corporation: *See—*
Smith, Franklin J.; and Williams, L. G., 3,578,463.
Cullen, Roy H.; Elliott, Charles H.; Aker, Jimmie R.; and Mohr, Harvey O., to Youngstown Sheet and Tube Company. Pipe. 3,578,029, Cl. 138-133.
Cummisford, Robert G.: *See—*
Alexander, Richard J.; and Cummisford, Robert G., 3,578,475.
Curran, Joseph W. Tool. 3,578,046, Cl. 145-50.
Cushman, Donald R., to Mobil Oil Corporation. Paper sizing composition comprising a cationic wax emulsion, an anionic resin and an acid amine containing emulsifying agent. 3,578,477, Cl. 106-230.
Cuyler, Kenneth W., to Nugent, William & Co., Inc. Filter Disc. 3,578,176, Cl. 210-492.
Daimler-Benz Aktiengesellschaft: *See—*
Deutschmann, Herbert; and Conrad, Ulrich, 3,577,961.
Dale, Ernest A.; Fowler, Richard A.; and Thomas, Martha J. B., to Sylva Electric Products, Inc. Process for the preparation of phosphate phosphors. 3,578,603, Cl. 252-301.4
Dale, John M., to Pan American Sulphur Company, mesne. Vaporizing sulfur from ore by direct contact with heated pebbles. 3,578,417, Cl. 23-294.
Danow, James F. Adjustable bread dispenser with ejector controlled closure. 3,578,207, Cl. 221-232.
Darrah, James G.: *See—*
Johnson, Bruce M.; DeCrescenti, Michael A.; and Darrah, James G., 3,578,610.
Data Products Corporation: *See—*
Cantwell, Gill, 3,578,138.
Davidson, William E., to General Electric Company. Combination flatiron and integral creaser. 3,577,859, Cl. 38-71.
Davis, George F.; Gebhart, Herbert J., Jr.; and Makin, Earle C., Jr., to Monsanto Company. Aromatics recovery with carbon monoxide-cuprous fluoroborate and carbon monoxide-cuprous fluorophosphate complexes. 3,578,581, Cl. 208-308.
Davis, John A., Jr.; and Kunzman, William J., to Marathon Oil Company. Aromaticity influencing the thermostability of micellar dispersions. 3,578,082, Cl. 166-252.
Davis, Orvis A., Sr., to Gulf Research & Development Company. Spraying process. 3,578,246, Cl. 239-8.
Davis, Orvis A., Sr., to Gulf Research & Development Company. Flat spray aspirating nozzle. 3,578,249, Cl. 239-296.
Davis, Richard L.: *See—*
Kramer, Kenneth C.; Davis, Richard L.; and Boc, Otto H., 3,578,269.
Davison, William B.: *See—*
Towner, Robert L., 3,577,893.
Dead Sea Works Ltd.: *See—*
Bloch, Moshe R.; Forgacs, Chaim; and Bohker, Ronald V., 3,578,503.
DeCrescenti, Michael A.: *See—*
Johnson, Bruce M.; DeCrescenti, Michael A.; and Darrah, James G., 3,578,610.
Deep Oil Technology, Inc.: *See—*
Horton, Edward E., 3,577,946.
De Gast, Hilaire G. Three dimensional puzzles. 3,578,331, Cl. 273-157.
De Pentti, Kenneth L.: *See—*
Metzger, William J.; and De Pentti, Kenneth L., 3,578,180.
De Rucker, Donald E.; and Vaccaro, Andrew J., to Sier-Bath Gear Co., Inc. Locking key for coupling. 3,578,363, Cl. 287-52.05
Desoutter Brothers Limited: *See—*
States, Ronald Frederick, 3,578,091.
Detheridge, John Stanley; and March, John William, to Lucas, Joseph, (Industries) Limited. Method of making dynamo electric machines. 3,577,851, Cl. 29-596.
Deuschle, Fritz: *See—*
Merry, Jack D.; and Deuschle, Fritz, 3,577,992.
Deutsche Akademie der Wissenschaften Zu Berlin: *See—*
Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfeil, Manfred; and Sattler, Karl, 3,578,566.
Deutschmann, Herbert; and Conrad, Ulrich, to Daimler-Benz Aktiengesellschaft. Liquid-cooled super-charged internal combustion engine. 3,577,961, Cl. 123-52.
De Wall, Richard A.: *See—*
Bentley, Donald J.; and De Wall, Richard A., 3,578,411.
Diamond Die & Mold Co.: *See—*
Baldyga, Joseph W., 3,578,230.
Diamond Power Specialty Corporation: *See—*
Smith, James E.; and Schulz, Carl W., 3,578,359.
Diamond Shamrock Corporation: *See—*
Dombrow, Bernard A., 3,578,594.
Palm, Bert E.; and Warner, William Wayne, 3,578,509.
Palm, Bert E.; and Warner, William Wayne, 3,578,510.
Dick, A. B., Company: *See—*
Tonkin, Kenneth J.; and Gallagher, John P., 3,577,916.
Diehl, Francis L.: *See—*
Snoddy, Arnon O.; Diehl, Francis L.; and Drew, Howard F., 3,578,601.
Diamond, Joseph; Gershman, Melvin Y.; and Ravreby, Fred A., to Coleco Industries, Inc. Wall mounted pivotable flow directing assembly. 3,578,023, Cl. 137-592.
Dien, Chi K., to Allied Chemical Corporation. Aqueous dyestuff compositions containing 2,2'-(azo-diphenylene)-bisbenzothiazoles and one or more dispersing agents. 3,578,388, Cl. 8-41.

Dietrich, Henri, to Geigy Chemical Corporation. N'-substituted N-aryl-sulfonyl ureas. 3,578,658, Cl. 260-239.
Diggs, Bernard W. Reciprocating nut sheeler. 3,578,047, Cl. 146-16.
Dillberg, Raymond E.: *See—*
Miller, Frank R.; and Dillberg, Raymond E., 3,578,424.
Dillon, Leo H.; and Weese, William F., to Abex Corporation. Rate of pressure rise limiting valve. 3,578,018, Cl. 137-489.
Dodman, David; and Wooley, John Mathers, to Imperial Chemical Industries Limited. Reduction of aromatic nitrocompounds. 3,578,720, Cl. 260-647.
Doehel, Karl J.; and Francis, John E., to Geigy Chemical Corporation. 3-Hydrazino-1,2,8,9-tetraazaphenolones. 3,578,665, Cl. 261-250.
Doggett, Towers, to Scott Paper Company, mesne. Integral negative type positive photolithographic plate. 3,578,451, Cl. 96-33.
Dolan, Calvin M.; and Axelson, John S., to General Electric Company. Thermal insulation and bond for solid fuel motors and method of making same. 3,578,520, Cl. 156-79.
Dombrow, Bernard A., to Diamond Shamrock Corporation. Fiber treating compositions. 3,578,594, Cl. 252-8.9
Dominion Engineering Works, Limited: *See—*
Tidbury, Gordon Thomas, 3,578,557.
Domok, Otto, to Strebelwerk AG. Warm water producer. 3,578,074, Cl. 165-132.
Donna, Natalie: *See—*
Kohner, Frank; Stubbman, Albert; and Donna, Natalie, 3,578,319.
Donti Research Development Manufacturing: *See—*
Levy, Donald; and Rusz, Tibor, 3,577,984.
Doorenbos, Harold E., to Dow Chemical Company. The. Preparation of anhydrous cuprous chloride or bromide. 3,578,397, Cl. 23-97.
Dorer, Casper John, Jr., to Lubrizol Corporation. The. Emulsion resistant fuel compositions. 3,578,422, Cl. 44-63.
Dorr-Oliver Incorporated: *See—*
Priestley, Robert J., 3,578,396.
Douglass Industries, Inc.: *See—*
Engler, Anthony R., 3,577,871.
Dow Chemical Company, The: *See—*
Cleerehan, Kenneth J.; and Thomas, Lowell S., 3,578,549.
Doorenbos, Harold E., 3,578,397.
Harry, Lawrence D.; and Sweeney, George A., 3,578,616.
Noeroske, Robert L.; and Tobol, Helen K., 3,578,434.
Rieke, James K.; and Justin, Frank H., 3,578,630.
Walles, Wilhelm E.; and Tousignant, William F., 3,578,404.
Walles, Wilhelm E.; and Bird, Arnett L., 3,578,484.
Wright, Donald R., 3,578,537.
Dowd, James W.; Jacobs, Robert D.; and Mercer, Harry L., to Stevens, J. P., & Co., Inc. Wool-polyester textile articles having a polymeric finish. 3,578,491, Cl. 117-138.8
Dozier, Don A. Oil shield for railroad journal box. 3,578,113, Cl. 184-106.
Draeseke, Gordon L. Multiple hull boat. 3,577,947, Cl. 114-61.
Dragerwerke, Heintz & Bernh.: *See—*
Breiling, Hans Georg, 3,578,042.
Drawert, Manfred: *See—*
Burha, Christian; Drawert, Manfred; and Griebisch, Eugen, 3,578,612.
Dresser Industries, Inc.: *See—*
Henry, George R.; and Weaver, Ernest P., 3,578,472.
Whittemore, Dwight S., 3,578,474.
Drew, Howard F.: *See—*
Snoddy, Arnon O.; Diehl, Francis L.; and Drew, Howard F., 3,578,601.
Drieschner, Gotthardt, to Orenstein-Koppel Aktiengesellschaft. Bucket actuated means for excavator. 3,578,188, Cl. 214-138.
Drummond, Warren W., to PPG Industries, Inc. Method and apparatus for coating textile material. 3,577,872, Cl. 57-35.
Drwatwa, Heinrich: *See—*
Kruel, Martin; Juentgen, Harald; and Drwatwa, Heinrich, 3,578,390.
Ducrocq, Roger Eugene, to Pneumatiques, Caoutchouc Manufacture et Plastiques Kleber-Colombes. Floating barrier means. 3,577,879, Cl. 61-1.
Duncan, Allen B. Portable carrier for beverage containers. 3,578,199, Cl. 220-31.
Duncan, William E.: *See—*
Harvill, Leonard A.; and Duncan, William E., 3,578,367.
Dunlop Company Limited, The: *See—*
French, Tom; and Gough, Vernon E., 3,578,055.
Nicholls, Ernest G., 3,578,530.
Dunn, George L., to Kline, Smith & French Laboratories. Benzimidazole-2-carbamates substituted on the benzene ring with an acyloxyalkyl group. 3,578,676, Cl. 260-309.2
Du Pont de Nemours, E. I., and Company: *See—*
Beardsley, Herbert P., 3,578,618.
Du Pont de Nemours, E. I., and Company: *See—*
Aykan, Kamran, 3,578,608.
Cluff, Edward Fuller, 3,578,624.
Couture, Maurice Joseph; Gerner, Hans M. B.; and Gibbs, Hugh H., 3,578,721.
Eiseman, Bernhardt J., Jr., 3,578,597.
Fang, James C., 3,578,638.
Smeltz, Kenneth C., 3,578,701.
Young, Charles A., 3,578,481.
Dupuis, Guy-Louis, to Burroughs Corporation. Safety cover lock for the case of an electrically operated device. 3,578,368, Cl. 292-45.

Durell, Edward H.: *See—*
Schoenbrunn, Erwin F.; and Durell, Edward H., 3,578,703.
Dyckerhoff & Widmann Kommanditgesellschaft: *See—*
Finsterwalder, Ulrich; and Finsterwalder, Klemens, 3,577,896.
Eagle-Picher Industries, Inc.: *See—*
Hudd, Richard N.; and Seiler, Heinz, 3,578,469.
Earl, Thad J. Pillow unit for a seat. 3,578,383, Cl. 297-391.
Eastman Kodak Company: *See—*
Peterson, Dean M.; Pickering, Charles E.; and Mindler, Fredric A., 3,577,900.
Snapp, Thomas Carter, Jr.; Blood, Alden E.; and Hagemeyer, Hugh John, Jr., 3,578,702.
Eberle, Gunter. Receptacle holder for centrifuges. 3,578,240, Cl. 233-26.
Economics Laboratory, Inc.: *See—*
Rowan, Henry A.; and Shiffner, Donald H., 3,578,002.
Eder, Ulrich: *See—*
Berndt, Hans-Dietlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.
Edmund, James Mitchell. Safety ski binding. 3,578,349, Cl. 280-11.35
Edwards, Robert S.: *See—*
Rigdon, Orville W.; Edwards, Robert S.; and Holst, Edward H., 3,578,575.
Eggert, Walter S., Jr., to Budd Company, The. Handrail and air conditioning duct support. 3,577,903, Cl. 98-2.
Ehrenberg, Hermann, to Fouquet-Werk Franz & Planck. Connecting arrangement. 3,578,364, Cl. 287-52.
Ehrenfried, John F.; and Gardner, Charles M., to Goodyear Tire & Rubber Company, The. Packaging apparatus and package. 3,577,866, Cl. 53-184.
Ehrenreich, A., & Cie: *See—*
Gottschald, Rudolf, 3,578,365.
Ehrhart, Wendell A.; and Rohrer, Clarence E., to Armstrong Cork Company. Liquid unsaturated polyesters and polyester urethanes containing crosslinked particles of the same resins. 3,578,728, Cl. 260-859.
Eichenberger, Hansulrich; and Schwengeler, Peter, to Rieter Machine Works, Ltd. Apparatus for guiding a fleece. 3,577,845, Cl. 19-231.
Eiselstein, Herbert L.; and Haeberle, Carl B., to International Nickel Company, Inc. The. Nickel-copper alloy. 3,578,440, Cl. 75-170.
Eiseman, Bernhardt J., Jr., to Du Pont de Nemours, E. I., and Company. Mixtures of perfluorodimethylcyclohexane and trichlorotrifluoroethane. 3,578,597, Cl. 252-66.
Ekco Products, Inc.: *See—*
Bloch, Roy W.; and Jewell, Donald K., 3,578,204.
Elchisak, John J.; Hope, William D.; and Van Wagner, Edward M., to Xerox Corporation. Xerographic plate fabrication. 3,578,445, Cl. 96-1.5
Electrodyn Research Corporation: *See—*
Strohmeyer, Charles, Jr., 3,578,563.
Electronic Precision Industries Corporation: *See—*
Trzyna, Charles J.; and Trzyna, Thaddeus S., 3,578,574.
Elenburg, Wayland D. Method for drilling and coring. 3,578,093, Cl. 175-60.
Elesh, Joseph, to International Recreation Products, Inc. Practice golf green including undulated area and thickened tapered cup receiving end portion. 3,578,333, Cl. 273-176.
Eliot, Sol S., to Perfex Plastics, Inc. Fitting for a liner pipe formed of polyethylene. 3,578,360, Cl. 285-55.
Elliott Brothers (London) Limited: *See—*
Ellis, Stafford Malcolm, 3,578,270.
Elliott, Charles H.: *See—*
Cullen, Roy H.; Elliott, Charles H.; Aker, Jimmie R.; and Mohr, Harvey O., 3,578,029.
Elliott, Daniel L.; and Burr, Gary D., to United Aircraft Corporation. Temperature responsive passive variable thermal conductance device. 3,578,068, Cl. 165-39.
Ellis, Peter H., to Rohr Corporation. Turbo-fan propulsion silencing apparatus. 3,578,106, Cl. 181-33.
Ellis, Stafford Malcolm, to Elliott Brothers (London) Limited. Aircraft manual control members. 3,578,270, Cl. 244-83.
Els, Hans: *See—*
Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, 3,578,565.
Emerson, Dean, Jr.; and Wood, Sidney B., Jr. Playing court. 3,577,894, Cl. 94-7.
Emerson Electric Co.: *See—*
Love, John J., 3,578,243.
Emery, William M. Stool or leg rest. 3,577,936, Cl. 108-8.
Eminger, Robert J., to Fort Wayne Tool & Die, Inc. Apparatus for automatically winding concentric dynamoelectric machine coils. 3,578,034, Cl. 140-1.
Ender, Lee. Bottle-lock. 3,578,196, Cl. 215-88.
Engler, Anthony R., to Douglass Industries, Inc., mesne. Chain curtain. 3,577,871, Cl. 56-25.4
English Electric Company Limited, The: *See—*
Prosser, Kenneth Wheatley; and Wallace, John Vipond, 3,578,538.
Eppinger, Rolf H., to Burroughs Corporation. Record card hopper load-reducing device. 3,578,313, Cl. 271-41.
Erickson, Lennart G., to Goodyear Tire & Rubber Company, The. Intermittent sprinkler irrigation system. 3,578,244, Cl. 239-1.

Ericson, Paul E.: *See—*
Kriesel, Marshall S.; Anderson, Lawrence; and Ericson, Paul E., 3,578,275.
Eriksen, Herluf N., to Keene Corporation. Method and apparatus for slitting and trimming pipe covering. 3,577,889, Cl. 83-7.
Erste Deutsche Floatglass GmbH, & Co., OHG: *See—*
Labrot, Gunter, 3,578,430.
Escambia Chemical Corporation: *See—*
Schoenbrunn, Erwin F.; and Durell, Edward H., 3,578,703.
Escoa Fintube Corporation: *See—*
Boose, Robert C., 3,578,165.
Esso Production Research Company: *See—*
Bombardieri, Caurino C.; and Tod, James F., 3,578,084.
Etablissement Public: Centre National de La Recherche Scientifique: *See—*
Uriel, Jose, 3,578,604.
Etablissements Thevignot: *See—*
Thevignot, Max; and Schwebelen, Robert M., 3,578,289.
Ethyl Corporation: *See—*
Becker, Warren E.; and Kohetz, Paul, 3,578,436.
Cook, Charles A.; and Campbell, David H., 3,578,543.
Martin, Eugie A.; and Fanning, Robert J., 3,578,689.
Sanders, Robert N., 3,578,516.
Smith, Martin B.; and Adams, Norman G., 3,578,606.
Eutectic Corporation: *See—*
Knotek, Otto, 3,578,441.
Evans, Wayne, to Butler Manufacturing Company. Method for making film clad panels. 3,578,521, Cl. 156-84.
Everett, Lucille G. Portable platform and shelter. 3,578,003, Cl. 135-4.
Everett, Wilhelm S.; and Floyd, James K., to Pulsation Controls Corporation. Pulsation dampener using non-linear decoupling means. 3,578,107, Cl. 181-57.
Eylure Limited: *See—*
Aylott, Eric Victor, 3,578,158.
Falbe, Jürgen; and Hahn, Heinz-Dieter, to Ruhrchemie AG. Process for catalytically splitting isobutyraldehyde to produce carbon monoxide and hydrogen. 3,578,423, Cl. 48-197.
Fang, James C., to Du Pont de Nemours, E. I., and Company. Aromatic poly(carbamic-anhydride-amide-ester) and a process for preparing the same. 3,578,638, Cl. 260-77.5
Fanning, Robert J.: *See—*
Martin, Eugie A.; and Fanning, Robert J., 3,578,689.
Farbenfabriken Bayer Aktiengesellschaft: *See—*
Knipp, Ulrich; Boigk, Eckhard; and Weinbrenner, Erwin, 3,578,057.
Farwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning: *See—*
Brinkmann, Ludwig; Herwig, Walter; and Cherdron, Harald, 3,578,729.
Herwig, Walter; Brinkmann, Ludwig; and Asmus, Klaus-Dieter, 3,578,730.
Kuhkamp, Alfred; Fischer, Edgar; and Nolken, Ernst, 3,578,632.
Tesch, Hans-Jürgen; Haverkamp, Günther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, 3,578,092.
Weissermel, Klaus; and Uebe, Rudolf, 3,578,623.
Farrel, James M.: *See—*
Nussdorfer, W. R.; and Farrel, James M., 3,577,905.
Farsbeter, John F. Snow melter. 3,577,975, Cl. 126-343.5
Fastener Corporation: *See—*
Novak, Edward J., 3,578,231.
Favre, Francois, to Geigy, J. R., A.G. Monoazo and disazo dispersion dyestuffs containing 2-hydroxy-5-β-cyano-, Blower alkoxycarbonyl- or β-carboxamidoethyl benzene group. 3,578,654, Cl. 260-186.
Federal Mfg. Co.: *See—*
Burford, Chester O., 3,578,038.
Feldkamp, John G. Plastic strapping machine. 3,577,910, Cl. 100-17.
Felix, Ernst, to Zellweger Ltd. Method of representing the dial settings of an electronic yarn smoother. 3,577,854, Cl. 33-1.
Fenton, Donald M., to Union Oil Company of California. Isomerization of acids. 3,578,688, Cl. 260-405.6
Fenton, Joseph E., to Fischer, H. G., & Co., mesne. Electrostatic coating material recovery device. 3,578,486, Cl. 117-93.41
Ferris, Ray L.; Shaver, William R.; and Manos, William P., to Pullman Incorporated. Lightweight railway container car. 3,577,933, Cl. 105-366.
Fessler, William A.: *See—*
Bostick, Edgar E.; and Fessler, William A., 3,578,726.
Findlay, Donald Urquhart; McCaffrey, Francis Hamnet Garland; and Taylor, George David, to Canadian Industries Limited. Shotshells. 3,577,924, Cl. 102-42.
Finefrock, Donald W., to Johnson Rubber Company, The. Cushioning liner for vehicles or the like. 3,578,375, Cl. 296-39.
Fink, Walter, to Monsanto Company. Organic 1,3,2,4-diazadistilenes and process. 3,578,691, Cl. 260-448.2
Fink, Walter, to Monsanto Company. 1,3-Disilyl-1,3,2,4-diazadistilenes and process. 3,578,692, Cl. 260-448.2
Fink, Walter, to Monsanto Company. Cyclodisilazanylsiloxanes. 3,578,693, Cl. 260-448.2
Finsterwalder, Klemens: *See—*
Finsterwalder, Ulrich; and Finsterwalder, Klemens, 3,577,896.
Finsterwalder, Ulrich; and Finsterwalder, Klemens, to Dyckerhoff & Widmann Kommanditgesellschaft. Method for producing structure components of reinforced concrete subjected to tensile stress. 3,577,896, Cl. 94-24.

Firestone Tire & Rubber Company, The: See—
Boutsicaris, Stephen, 3,578,627.
Hergenrother, William Lee, 3,578,645.
Sugarman, Meyer L., 3,578,446.

Fischer, Edgar: See—
Kuhlkamp, Alfred; Fischer, Edgar; and Nolken, Ernst, 3,578,632.

Fischer, H. G., & Co.: See—
Fenton, Joseph E., 3,578,486.

Fischer, Ronald J.; Groeneveld, Wilbur E.; and Irvine, Gerald O., to Avco Corporation. Adjustable implement-carrying assembly. 3,578,089, Cl. 172-277.

Fisher, Harold M.: See—
Mitchell, Maurice M., Jr.; Fisher, Harold M.; and Tomezko, Edward S. J., 3,578,650.

Fletcher, William D., III, to Combustion Engineering, Inc. Double container reactor vessel. 3,578,564, Cl. 176-87.

Florig, Albert J.: See—
Clarke, Edwin E.; and Florig, Albert J., 3,578,213.

Floyd, James K.: See—
Everett, Wilhelm S.; and Floyd, James K., 3,578,107.

Flum, Herman H., to Bunker-Ramo Corporation. Automatic fare collecting system. 3,578,124, Cl. 194-4.

Flynn, Thomas J. Method for filling a syringe. 3,578,037, Cl. 141-2.

Follett, Robert P.: See—
Battersby, William R.; Follett, Robert P.; MacGrandle, Timothy D.; Rossitto, Conrad; and Taylor, Paul, 3,578,727.

Foot, J. B., Foundry Co., The: See—
Hauser, Hans, 3,578,095.

Ford Motor Company: See—
Collingwood, Wilford R.; Hutchison, William M.; and Mangas, Frank E., 3,577,966.
Meyer, Howard F., Jr., 3,578,026.
Ojala, William K., 3,577,962.

Forgacs, Chaim: See—
Bloch, Moshe R.; Forgacs, Chaim; and Bobker, Ronald V., 3,578,503.

Formica Corporation: See—
Garcia, Leonardo Medrano, 3,578,483.

Forster, Adolf G., to Alfa-Laval AB. Partition wall for sheds having automatic dung scraper. 3,577,956, Cl. 119-15.

Fort Wayne Tool & Die, Inc.: See—
Eminger, Robert J., 3,578,034.

Fortune, Henry James, to Plessey Company Limited, The. Record players. 3,578,340, Cl. 274-15.

Foster, Walter Henry, Jr.: See—
Kazan, John, Jr.; and Foster, Walter Henry, Jr., 3,578,389.

Foster Wheeler Corporation: See—
Barratt, Robert Owen; and Polcer, John, 3,577,959.

Fouquet-Werk Franz & Planck: See—
Ehrenberg, Hermann, 3,578,364.

Fowler, John H., to Rockwell Manufacturing Company. Remote underwater flowline connection. 3,578,076, Cl. 166-06.

Fowler, Richard A.: See—
Dale, Ernest A.; Fowler, Richard A.; and Thomas, Martha J. B., 3,578,603.

Fox, James W.: See—
Coleman, James T.; and Fox, James W., 3,578,323.

Fox, Robert D.: See—
Petro, Victor P.; Lewis, James M.; and Fox, Robert D., 3,578,455.

Francis, John E.: See—
Doebel, Karl J.; and Francis, John E., 3,578,665.

Francis, Maurice, to Trefilunio. Lattice for the reinforcement of tubular concrete elements having a socket method for producing said lattice and the products obtained. 3,578,036, Cl. 140-107.

Fraser, James K. Timed feeding mechanism. 3,578,209, Cl. 222-23.

Fraser, Robert Neil, to BP Chemicals (U.K.) Limited. Chemical process. 3,578,722, Cl. 260-671.

Frechette, Kenneth R., to Litton Business Systems, Inc. Carriage return energy absorber. 3,578,130, Cl. 197-64.

Frechette, Kenneth R.; and Rosborg, Daniel J., to Litton Business Systems, Inc. Type action having lost motion. 3,578,128, Cl. 197-17.

Freedman, Albert. Multi-purpose concrete form clamp. 3,578,309, Cl. 269-287.

Freeland, Edward J., to Gulf & Western Industrial Products Company, Inc. Power press lubricating system. 3,578,112, Cl. 184-6.

Freeland, Edward J., to Gulf & Western Industrial Products Company. Dual clutch valve interlocking. 3,578,123, Cl. 192-131.

French, Tom; and Gough, Vernon E., to Dunlop Company Limited, The. Tread wear indicator. 3,578,055, Cl. 152-330.

Frey, Albert J.; and Buzzolini, Mario G., to Sandoz-Wander, Inc. Bis (substituted phenyl) acetals. 3,578,712, Cl. 260-559.

Frey, Ellsworth J., to Star Tab, Inc. Stabilizer trim attachment for power boats. 3,577,948, Cl. 114-66.5.

Fried, Krupp Gesellschaft mit beschränkter Haftung: See—
Heine, Franz, 3,578,352.

Friend, William H.: See—
Chun, Sun W.; and Friend, William H., 3,578,628.

Fruehauf Corporation: See—
Fujioka, Richard T., 3,578,179.

Fuji Photo Film Co., Ltd.: See—
Ono, Hisatake; and Osada, Chiaki, 3,578,680.

Fuji Shashin Film Kabushiki Kaisha: See—
Amano, Hiroyuki; Iwano, Haruhiko; Shirasu, Kazuo; and Ohi, Reiichi, 3,578,453.

Amano, Hiroyuki; Ohi, Reiichi; Iwano, Haruhiko; and Shirasu, Kazuo, 3,578,454.

Ikegami, Yoshizo, 3,577,899.

Ono, Hisatake; Osada, Tiaki; and Kosuge, Kuniko, 3,578,602.

Fujii, Seiji: See—
Higuchi, Masaaki; Shibuya, Teiji; Onoue, Koichi; and Fujii, Seiji, 3,578,437.

Fujioka, Richard T., to Fruehauf Corporation. Portable jib crane. 3,578,179, Cl. 212-61.

Fujita, Takashi, to Matsushita Electric Industrial Co., Ltd. Pressure measuring device. 3,577,884, Cl. 73-141.

Fujitsu Limited: See—
Nishimura, Yasuro; and Tanaka, Masao, 3,578,420.

Fullam, John P., to Abex Industries of Canada Ltd. Oleo-pneumatic shock absorbers. 3,578,303, Cl. 267-64.

Funakubo, Shinnosuke: See—
Funakubo, Shinnosuke, 3,578,512.

Funakubo, Shinnosuke, to Funakubo, Shinnosuke. Method of heat treatment of steel product. 3,578,512, Cl. 148-147.

Furlenmeier, Andre: See—
Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.

Furrer, Eduard, to Contraves AG. Fluid-controlled, in particular hydraulically or pneumatically controllable slide valve arrangement. 3,578,025, Cl. 137-625.66.

Furst, Andor: See—
Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.

Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, 3,578,565.

Futterer, Bodo, to Gillette Company, The. Cutting head for motor driven shavers. 3,577,852, Cl. 30-43.92.

Gabert, Anton: See—
Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfel, Manfred; and Sattler, Karl, 3,578,566.

Gabler, Dieter K.: See—
Willebacher, Erich M.; Schmedtkord, Ulrich; and Gabler, Dieter K., 3,577,944.

Gachot, Jean. Pressure regulator for pressurized-fluid circuits. 3,578,014, Cl. 137-108.

Gagnon, Marcel. Apparatus for picking apples or the like fruits. 3,578,109, Cl. 182-129.

Gal, Istvan; Hollo, Janos; Toth, Jenő; and Galgoczi, Bela, deceased (by Galgoczi, Katalin; trustee), to Simonaco Limited. Treatment of slurries. 3,578,586, Cl. 210-49.

Galgoczi, Bela: See—
Gal, Istvan; Hollo, Janos; Toth, Jenő; and Galgoczi, Bela, 3,578,586.

Galgoczi, Katalin: See—
Gal, Istvan; Hollo, Janos; Toth, Jenő; and Galgoczi, Bela, 3,578,586.

Gallagher, John P.: See—
Tonkin, Kenneth J.; and Gallagher, John P., 3,577,916.

Galloway, J. Robert. Carton filler. 3,578,040, Cl. 141-142.

Garbalizer Corporation of America: See—
Brewer, John C., 3,578,252.

Garcia, Giampaolo, to Alfa Romeo S.p.A. Regulator device for a variable rate of flow for an internal combustion engine. 3,577,978, Cl. 123-140.

Garcia, Leonardo Medrano, to Formica Corporation. Process for improving the printability of the surface of α -cellulose paper to be used as the decorative sheet in a decorative laminate. 3,578,483, Cl. 117-38.

Gardella, John M.: See—
Taylor, Norris O.; Uhler, Wilmer P.; Gardella, John M.; and Cahlik, Jim C., 3,578,379.

Gardner, Charles M.: See—
Ehrenfried, John F.; and Gardner, Charles M., 3,577,866.

Gardner, Thomas E., to United Aircraft Corporation. Digital integrator. 3,577,902, Cl. 98-1.5.

Garnder, Gerald: See—
Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Garnder, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.

Gebhart, Herbert J., Jr.: See—
Davis, George F.; Gebhart, Herbert J., Jr.; and Makin, Earle C., Jr., 3,578,581.

Gehri, Aime A., to Transiron Electric Corporation. Method of breaking dice. 3,578,227, Cl. 225-2.

Geigy Chemical Corporation: See—
Dietrich, Henri, 3,578,658.

Doebel, Karl J.; and Francis, John E., 3,578,665.

Knell, Martin; and Kleiner, Eduard Karl, 3,578,487.

Geigy, J. R., A.G.: See—
Favre, Francois, 3,578,654.

Gelb, Leonard L., to Hercules Incorporated. Resin coated filamentary material. 3,578,489, Cl. 117-128.4.

Gelb, R., & Sons, Inc.: See—
Schlosberg, Seymour, 3,578,067.

Gelfenbein, Evgeny Jukhimovich: See—
Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Safronovich, Lev Isaevich; and Kuznetsov, Leonid Georgievich, 3,578,063.

General Electric Company: See—
Bialous, Charles A.; Jaquiss, Donald B. G.; and Keane, John J., 3,578,634.

Bostick, Edgar E.; and Fessler, William A., 3,578,726.

Davidson, William E., 3,577,859.

Dolan, Calvin M.; and Axelson, John S., 3,578,520.

Hamlen, Robert P.; and Jerabek, Elihu C., 3,578,504.

Hasselbring, Robert Joel; and Shields, Robert Loren, 3,577,940.

Hurlbut, Myron R., 3,578,299.

Hurlbut, Myron Robert; Phillips, Robert Arthur; and Tupper, Leonard Chester, 3,578,298.

Kunz, Raymond W., 3,577,907.

Kushner, Gerald J., 3,578,016.

Nielsen, James C.; and Turner, John J., 3,578,281.

Scheldorf, Owen H., 3,578,279.

Van Luik, Frank W., Jr., 3,578,410.

Welty, Richard K., 3,578,419.

Wetzel, Lewis K., 3,578,118.

Wright, Archibald N.; and Mathewson, Wilfred F., Jr., 3,578,425.

General Mills, Inc.: See—
Reinhart, Richard D.; and Straughn, Robert O., 3,577,935.

General Motors Corporation: See—
King, Maurice; and Barber, Trevor Leslie, 3,577,970.

General Oil Tools, Inc.: See—
Shillander, Harold E., 3,578,078.

General Precision Systems Inc.: See—
McQuaid, Paul E.; and Kolk, Anthony J., Jr., 3,578,571.

Georgia-Pacific Corporation: See—
Ludwig, Charles H., 3,578,651.

Gerner, Hans M. B.: See—
Couture, Maurice Joseph; Gerner, Hans M. B.; and Gibbs, Hugh H., 3,578,721.

Gershman, Melvin Y.: See—
Diamond, Joseph; Gershman, Melvin Y.; and Ravreby, Fred A., 3,578,023.

Gesellschaft für Kernforschung mbH: See—
Mühlhauser, Otto, 3,578,305.

Ghilardi, Giuliana: See—
Zviak, Charles; and Ghilardi, Giuliana, 3,578,387.

Giarrusso, Gino A.: See—
Silverman, Herbert P.; and Giarrusso, Gino A., 3,578,409.

Gibbs, Hugh H.: See—
Couture, Maurice Joseph; Gerner, Hans M. B.; and Gibbs, Hugh H., 3,578,721.

Gilchrist, Allan E., to SCM Corporation. Surfactant treating process for blemished electrocoat substrates. 3,578,577, Cl. 204-181.

Giles, Kenneth M. Rubber horseshoe. 3,578,086, Cl. 168-18.

Gillette Company, The: See—
Futterer, Bodo, 3,577,852.

Gilmore, Jon P.: See—
Oshida, Otto A.; and Gilmore, Jon P., 3,578,555.

Ginn, David L.; and Hilmer, Donald A., to McDonnell Douglas Corporation. Pallet assembly. 3,578,274, Cl. 244-118.

Ginther, Gary D.: See—
Coapman, Richard T.; and Ginther, Gary D., 3,578,211.

Giraud, Francois Louis, to Societe De L'Aerotrain. Skirting arrangements for ground-effect machines. 3,578,099, Cl. 180-119.

Givry, Jean-Pierre: See—
Morel, Paul; Givry, Jean-Pierre; and Voisin, Philippe, 3,578,069.

Glasgow, James S.: See—
Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and McCarron, John K., 3,578,233.

Glassmeyer, John J., to Pullman Incorporated. Container coupler arrangement. 3,578,374, Cl. 294-67.

Glenn, Edwin E., Jr.; Slover, Vasek R.; and Strubhar, Malcolm K., to Mobil Oil Corporation. Flow control system and method. 3,578,077, Cl. 166-68.

Gluckin, Gerald W.; and Kurland, William, to William Gluckin & Co., Inc. Hose retaining panty garment. 3,577,993, Cl. 128-535.

Godfrey, Arthur W.: See—
Schlicht, Raymond C.; and Godfrey, Arthur W., 3,578,595.

Godsay, Madhu P.; and Mac Donald, Donald M., to Canadian International Paper Company. Nitrogen dioxide pulping process. 3,578,553, Cl. 162-14.

Gof, Mohammed S. Portable load handling device with winch. 3,578,290, Cl. 254-139.1.

Gohlfenn, Gerhard; and Spicka, Roland. Machine for folding edges of a plastics sheet facing about a door panel, or the like. 3,578,535, Cl. 156-493.

Goldfarb, Adolph E.; and Soriano, Rene, said Soriano assor. to said Goldfarb. Game structure and method. 3,578,320, Cl. 273-1.

Good, Frederick H. Hand tote device for garments on clothes hangers. 3,578,226, Cl. 224-45.

Goodrich, Allen C., to Carborundum Company, The. Baking furnace. 3,578,300, Cl. 263-41.

Goodyear Tire & Rubber Company, The: See—
Ehrenfried, John F.; and Gardner, Charles M., 3,577,866.

Erickson, Lennart G., 3,578,244.

Milliken, Paul E., 3,578,053.

Gorbovitsky, Efim Bentsionovich: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alekzina Vasilievna; Afanasiev, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Iserovich, 3,578,172.

Gordon, William F.; and Newman, James W., to Windings, Inc. Production of a twistless payout package with means for drawing out the inner end of the material. 3,578,255, Cl. 242-18.

Gordon, William. Underwater mooring release device. 3,577,950, Cl. 114-206.

Gotte, Hans: See—
Tesch, Hans-Jürgen; Haverkamp, Gunther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, 3,578,092.

Gottschald, Erika: See—
Gottschald, Rudolf, 3,578,365.

Gottschald, Rudolf, deceased (by Gottschald, Erika; sole heir), to Ehrenreich, A., & Cie. Ball and socket joint. 3,578,365, Cl. 287-87.

Gough, Vernon E.: See—
French, Tom; and Gough, Vernon E., 3,578,055.

Grace, W. R., & Co.: See—
Cantrell, Robert R.; and Swanson, Vernon F., 3,578,418.

Crotty, Homer E.; Coffey, Charles R.; and Tesdahl, Thomas C., 3,578,499.

Gregorian, Razmic S.; and Kirk, Charles C., 3,578,647.

Hurst, John, 3,578,733.

Hwa, Chih Ming; and Antony, Gary J., 3,578,589.

Marans, Nelson S., 3,578,697.

Tsuk, Andrew G., 3,578,588.

Wood, Louis L.; and Hamilton, Richard A., 3,578,643.

Wszolek, Walter R., 3,578,614.

Grant, Nicholas J.; and Schilling, William F., to Massachusetts Institute of Technology. Method of producing oxide-dispersion-strengthened alloys. 3,578,443, Cl. 75-206.

Grant, Whitney I., to Vilter Manufacturing Corporation. Refrigerating apparatus having oil separating means. 3,578,168, Cl. 210-167.

Gray, Earl E., to Bourns/Cai, Inc. Remotely controlled focal plane shutter. 3,577,901, Cl. 95-57.

Gray, Jack N.; and Watson, George A., to Celanese Corporation and Fiber Industries, Inc. Splittable tow. 3,578,551, Cl. 161-173.

Green, Derek Bernard; and Kaye, Gordon Edwin, to Scovill Manufacturing Company. Aerosol valve actuator and cap combination. 3,578,220, Cl. 222-402.13.

Green, Harry W.: See—
Paulus, Peter V.; and Green, Harry W., 3,578,166.

Green, Norman F.: See—
Hopps, Jay N.; and Green, Norman F., 3,578,114.

Greenhut, Marvin S., to Grow Chemical Corporation. Container and closure cap. 3,578,224, Cl. 222-546.

Greenwood, Kenneth; Heaton, Alban; Harrison, Alwin; and Jackson, Squire Ronald, to Lucas, Joseph, (Industries) Limited. Flame tubes for gas turbine engines. 3,577,878, Cl. 60-39.65.

Grefco, Inc.: See—
Oshida, Otto A.; and Gilmore, Jon P., 3,578,555.

Gregg, Alvin L.; and Koons, Charles E., to Anaconda Wire and Cable Company. Method and apparatus for monitoring the bonding of paper-wrapped wire. 3,578,518, Cl. 156-64.

Gregorian, Razmic S.; and Kirk, Charles C., to Grace, W. R., & Co. Chemical crosslinking scorch preventing additives and process therefor. 3,578,647, Cl. 260-86.7.

Greiner Electronic AG: See—
Greiner, Rudolf; and Oberli, Rudolf, 3,578,212.

Oberli, Rudolf, 3,578,291.

Greiner, Rudolf; and Oberli, Rudolf, to Greiner Electronic AG. Liquid dosage apparatus. 3,578,212, Cl. 222-71.

Grellmann, Hans W.: See—
Patierno, John W.; White, Vernon L.; Asdurian, Haig; and Grellmann, Hans W., 3,578,265.

Greytak, James J. Magnetic door stop. 3,578,370, Cl. 292-251.5.

Griebsch, Eugen: See—
Burba, Christian; Drawert, Manfred; and Griebsch, Eugen, 3,578,612.

Griff, Allan L. Acoustical tile. 3,578,105, Cl. 181-33.

Groeneveld, Wilbur E.: See—
Fischer, Ronald J.; Groeneveld, Wilbur E.; and Irvine, Gerald O., 3,578,089.

Gronemeyer, Erich W.: See—
Kutik, Louis F.; and Gronemeyer, Erich W., 3,577,843.

Grooss, Frank A.: See—
Clancy, Lawrence F.; Grooss, Frank A.; and Luttrell, Richard W., 3,578,098.

Gross, Gisela: See—
Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, 3,578,565.

Grow Chemical Corporation: See—
Greenhut, Marvin S., 3,578,224.

Gruber, Wilhelm; and Kleine-Doepke, Wolfgang, to Rohm & Haas G.m.b.H. Preparation of cyanuric chloride. 3,578,663, Cl. 260-248.

GTI Corporation: See—
Hetzer, Harry, 3,578,200.

Guenther Systems, Inc.: See—
Kuehl, Guenther L., 3,578,145.

Guffin, Margaret Alice. Massaging and washing device. 3,577,985, Cl. 128-57.
 Guilbaud, Jean-Pierre; and Vertut, Jean, to Commissariat a l'Energie Atomique. System for controlling the steering of vehicle wheels. 3,578,097, Cl. 180-79.1
 Gulf & Western Industrial Products Company: *See—*
 Freeland, Edward J., 3,578,112.
 Thompson, Charles S., Jr., 3,578,271.
 Thompson, Charles S., Jr., 3,578,272.
 Gulf & Western Industries Products Company: *See—*
 Freeland, Edward J., 3,578,123.
 Gulf Research & Development Company: *See—*
 Davis, Orvis A., Sr., 3,578,246.
 Davis, Orvis A., Sr., 3,578,249.
 Gunter, Ruth, executrix: *See—*
 Gunter, Siegfried, 3,578,263.
 Gunter, Siegfried, deceased (by Gunter, Ruth, executrix, Germany), to Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung fruher (Weser! Flugzeugbau/ Focke-Wulf/Heinkel-Flugzeugbau. Vertically starting and landing airplane. 3,578,263, Cl. 244-7.
 Gusken, Jean, The firm of: *See—*
 Maassen, Heinz, 3,578,031.
 Gustav Bauer, Firma: *See—*
 Herzog, Hilmar, 3,578,208.
 Gutridge, Jack E.; Johnson, Kent N.; and Spence, John H., to Pullman Incorporated. Transition reinforcement for fishbelly underframe. 3,577,934, Cl. 105-414.
 Haag, Werner O.; and Whitehurst, Darrel Duayne, to Mobil Oil Corporation. Ion exchange resin containing zero-valent metal. 3,578,609, Cl. 252-430.
 Hackman, Donald J.: *See—*
 Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and Mc Carron, John K., 3,578,233.
 Hadley, David James: *See—*
 Bethell, James Robert; and Hadley, David James, 3,578,707.
 Haerberle, Carl B.: *See—*
 Eiselstein, Herbert L.; and Haerberle, Carl B., 3,578,440.
 Hagemeyer, Hugh John, Jr.: *See—*
 Snapp, Thomas Carter, Jr.; Blood, Alden E.; and Hagemeyer, Hugh John, Jr., 3,578,702.
 Hahn, Heinz-Dieter: *See—*
 Falbe, Jürgen; and Hahn, Heinz-Dieter, 3,578,423.
 Hain, Gottfried M.; and Leonard, Wolfgang B., to Alpa Alpenland-Maschinenbaugesellschaft Hain & Co., KG. Wrapping machine method. 3,577,865, Cl. 53-25.
 Halbert, William G., to Tenneco Oil Company. Method of restoring formation permeability. 3,578,085, Cl. 166-307.
 Halcon International, Inc.: *See—*
 Becker, Mitchell, 3,578,690.
 Russell, Joseph L., 3,578,714.
 Halley, James W.: *See—*
 Mills, Norman T.; Jackson, Charles R.; and Halley, James W., 3,578,064.
 Hallmark Plastics, Inc.: *See—*
 Bronnenkant, Paul H., 3,577,987.
 Hamilton, Richard A.: *See—*
 Wood, Louis L.; and Hamilton, Richard A., 3,578,643.
 Hamlen, Robert P.; and Jerabek, Elihu C., to General Electric Company. Method of activating a silver oxide-zinc primary cell. 3,578,504, Cl. 136-102.
 Hammon, George L., to Chemetron Corporation. Cylinder cover. 3,578,051, Cl. 150-52.
 Handelsmaatschappij Othene N.V.: *See—*
 Schuler, Jacob Pieter, 3,578,372.
 Hanson, J Leslie: *See—*
 Notbohm, Willard C.; Lamb, Charles A.; and Hanson, J Leslie, 3,578,560.
 Hardin, Richard V., II: *See—*
 Rogers, Edward S.; Hardin, Richard V., II; Harrison, Benjamin C.; and Sanford, Robert A., 3,578,505.
 Harding, Howard H., to United Aircraft Corporation. Method of making reinforced honeycomb sandwich. 3,578,526, Cl. 156-242.
 Hardy, John F.; Rivin, Donald; and Aron, Jerome. Lacquer compositions comprising halogenated carbon black. 3,578,635, Cl. 260-22.
 Harnau, Hans-Dieter: *See—*
 Zehfeld, Paul; and Harnau, Hans-Dieter, 3,577,922.
 Harris, Leonard: *See—*
 Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Gardner, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.
 Harris, Rano J., Sr., to Precision Sampling Corporation. Method of forming seals. 3,577,850, Cl. 29-510.
 Harrison, Alwin: *See—*
 Greenwood, Kenneth; Heaton, Alban; Harrison, Alwin; and Jackson, Squire Ronald, 3,577,878.
 Harrison, Benjamin C.: *See—*
 Rogers, Edward S.; Hardin, Richard V., II; Harrison, Benjamin C.; and Sanford, Robert A., 3,578,505.
 Harry, Lawrence D.; and Sweeney, George A., to Dow Chemical Company. The Process for curing polyepoxides and resulting product. 3,578,616, Cl. 260-18.
 Hartley, Daniel W. Shell carton. 3,578,152, Cl. 206-3.

Harvey, Andrew: *See—*
 Kirkpatrick, Max B.; Harvey, Andrew; and Sparks, John M., III, 3,578,087.
 Harvey, Edward M. Lumber cart having cradle with variable height. 3,578,182, Cl. 214-6.
 Harvill, Leonard A.; and Duncan, William E., to Hi-Shear Corporation. Fastener including expander means and joint including the same. 3,578,367, Cl. 287-189.36
 Haschek, Friedrich; and Loos, Kurt, to Kabelschlepp GmbH. Covering device for protecting the guiding paths of machine tools. 3,578,061, Cl. 160-202.
 Hasegawa, Tatsuo; Yoshie, Kohichi; and Kamijima, Yasuhiro, to Toyota Jidosha Kogyo Kabushiki Kaisha. Seat construction of a vehicle. 3,578,376, Cl. 296-65.
 Hasselbach, Wolfgang; and Heim, Heinz, to Braun Aktiengesellschaft. Apparatus for damping oscillations. 3,578,304, Cl. 267-121.
 Hasselbring, Robert Joel; and Shields, Robert Loren, to General Electric Company. Incinerator. 3,577,940, Cl. 110-8.
 Hatch, Donald M., to Hiteco. Ablative and insulative structures. 3,578,030, Cl. 138-141.
 Hattori, Tatsuaki: *See—*
 Imoto, Saburo; Ikari, Kyoichiro; and Hattori, Tatsuaki, 3,578,485.
 Hauser, Hans, to Foote, J. B., Foundry Co., The. Compact snow vehicle. 3,578,095, Cl. 180-5.
 Haverkamp, Gunther: *See—*
 Tesch, Hans-Jürgen; Haverkamp, Gunther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, 3,578,092.
 Havranek, Robert Edward; and Crast, Leonard Bruce, Jr., to Bristol-Myers Company. Process for the preparation of 7-[a-(4-pyridylthio)acetamido]-cephalosporanic acids. 3,578,661, Cl. 260-243.
 Haws Drinking Faucet Company: *See—*
 Wright, Allen C., 3,578,247.
 Hayashi, Yoshimasa: *See—*
 Nakajima, Yasuo; and Hayashi, Yoshimasa, 3,578,116.
 Hayden, Percy, to Imperial Chemical Industries Limited. Preparation of esters from olefins in the presence of an oxime. 3,578,698, Cl. 260-475.
 Hayes, John C., to Universal Oil Products Company. Hydrocarbon conversion process and platinum-germanium catalytic composite for use therein. 3,578,584, Cl. 208-139.
 Hayes, Thomas Howe: *See—*
 Horecky, Stanley V.; and Hayes, Thomas Howe, 3,578,000.
 Heaton, Alban: *See—*
 Greenwood, Kenneth; Heaton, Alban; Harrison, Alwin; and Jackson, Squire Ronald, 3,577,878.
 Hebert, Normand C.; and Nordberg, Martin E., to Corning Glass Works. Electrochemical apparatus. 3,578,579, Cl. 204-195.
 Heckler & Koch GmbH: *See—*
 Jestrabek, Leopold, 3,577,860.
 Heeb, Dieter: *See—*
 Lukesch, Heinz; Krakowsky, Hans; and Heeb, Dieter, 3,578,221.
 Heidt, William A.; Palmer, Leon E.; and Schaefer, John O., to International Business Machines Corporation. Typewriter with extended writing line. 3,578,131, Cl. 197-82.
 Heim, Heinz: *See—*
 Hasselbach, Wolfgang; and Heim, Heinz, 3,578,304.
 Heine, Franz, to Fried. Krupp Gesellschaft mit beschränkter Haftung. Vehicle with frame adapted to be raised and lowered. 3,578,352, Cl. 280-43.23
 Heine, Wolfgang Fred; and Vought, Kenneth D., to SCM Corporation. Ribbon spool. 3,578,258, Cl. 242-74.1
 Heinz, Ernst: *See—*
 Ueberle, Dieter; and Heinz, Ernst, 3,578,401.
 Heller, Anton H., to Poweray Infrared Corporation. Heated asphalt storage unit. 3,577,976, Cl. 126-343.5
 Henry, George R.; and Weaver, Ernest P., to Dresser Industries, Inc. Carbonaceous bonding system for refractories. 3,578,472, Cl. 106-56.
 Henry, Nelson R.; and Middour, Donald R., to Woodman Company, Inc. The. Feeding system for constant product flow. 3,578,094, Cl. 177-108.
 Hercules Incorporated: *See—*
 Gelb, Leonard L., 3,578,489.
 Larson, Richard R., 3,578,101.
 Schuermann, Wilfred C., 3,577,926.
 Hergenrother, William Lee, to Firestone Tire & Rubber Company. The. Lactone polymers and process for preparing. 3,578,645, Cl. 260-78.5
 Herterick, George M.: *See—*
 Alden, Gardner E.; and Herterick, George M., 3,578,301.
 Herwig, Walter: *See—*
 Brinkmann, Ludwig; Herwig, Walter; and Cherdron, Harald, 3,578,729.
 Herwig, Walter; Brinkmann, Ludwig; and Asmus, Klaus-Dieter, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Thermoplastic polyester-poly-3-methyl butene-1 moulding compositions. 3,578,730, Cl. 260-873.
 Herzog, Hilmar, to Gustav Bauer, Firma. Watch band strap with releasable endconnection. 3,578,208, Cl. 224-4.
 Hetzer, Harry, to GTI Corporation. Port protectors. 3,578,200, Cl. 220-42.
 Hi-Shear Corporation: *See—*
 Harvill, Leonard A.; and Duncan, William E., 3,578,367.

Hidassy, Laszlo, to Thomas & Betts Corporation. Dispensing cartridge. 3,578,157, Cl. 206-56.
 Hieber, Heinz: *See—*
 Braun, Siegfried; and Hieber, Heinz, 3,577,953.
 Higuchi, Masaaki; Shibuya, Teiji; Onoue, Koichi; and Fujii, Seiji, to Nippon Kokan Kabushiki Kaisha. Method of sintering ores. 3,578,437, Cl. 75-5.
 Hill, Jennings Paul. Supply and exhaust control valve. 3,578,024, Cl. 137-627.5
 Hilmer, Donald A.: *See—*
 Ginn, David L.; and Hilmer, Donald A., 3,578,274.
 Hilpert, Conrad R., to Twin Disc, Incorporated. Torque transmission housing acceleration responsive fluid control means. 3,578,120, Cl. 192-103.
 Hiltz, Ralph H., to United States of America, Army. Dry hydrogen generator. 3,578,415, Cl. 23-281.
 Hinz, Herbert J., to Burroughs Corporation. Type carrier device. 3,577,913, Cl. 101-93.
 Hirooka, Masaaki: *See—*
 Nakaguchi, Kohji; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, 3,578,636.
 Hitachi, Ltd.: *See—*
 Nemoto, Mamoru; and Tani, Seiji, 3,577,891.
 Onoda, Yoshimitsu; and Kiwaki, Hisakatsu, 3,577,929.
 Hitco: *See—*
 Hatch, Donald M., 3,578,030.
 Hjermstad, Erling T., to Penick & Ford, Limited. Potato starch properties by controlled heating in aqueous suspension. 3,578,497, Cl. 127-32.
 Hodes, William: *See—*
 Weiss, Jonas; and Hodes, William, 3,578,164.
 Hoerner, Alfred J.; and Seiter, George M., to Minnesota Mining and Manufacturing Company. Foil-backed non-skid sheet. 3,578,550, Cl. 161-162.
 Hoff, Dale R.; and Peterson, Louis H., to Merck & Co., Inc. 2-(3'-Fluoro-2'-naphthyl)-benzimidazoles. 3,578,675, Cl. 260-309.2
 Hoffmann, Arthur Kentaro: *See—*
 Maricle, Donald Leonard; and Hoffmann, Arthur Kentaro, 3,578,500.
 Hoffmann-La Roche Inc.: *See—*
 Berndt, Hans-Dietlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wicbert, Rudolf, 3,578,659.
 Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, 3,578,565.
 Hofmann, Eberhard: *See—*
 Staudt, Heinrich; Hofmann, Eberhard; and Muller, Rolf, 3,577,968.
 Holland Hitch Company: *See—*
 Bouman, Clarence N.; and Bakker, Fred, 3,578,357.
 Hollo, Janos: *See—*
 Gal, Istvan; Hollo, Janos; Toth, Jenő; and Galgoczi, Bela, 3,578,586.
 Holmes, Allen B., to United States of America, Army. Pyro fluidic relay. 3,578,011, Cl. 137-81.5
 Holst, Edward H.: *See—*
 Rigdon, Orville W.; Edwards, Robert S.; and Holst, Edward H., 3,578,575.
 Honeycutt, Sammy C., to Lithium Corporation of America. Fuel cell system and method using lithium and lithium hypochlorite to produce hydrogen and oxygen. 3,578,501, Cl. 136-86.
 Honeywell Inc.: *See—*
 Lazar, Jeffrey M., 3,577,964.
 Spethmann, Donald H., 3,578,242.
 Honeywell Information Systems Inc.: *See—*
 Milford, Richard E., 3,578,315.
 Hooker Chemical Corporation: *See—*
 Carlson, Ronald H., 3,578,708.
 Hope, William D.: *See—*
 Elchisak, John J.; Hope, William D.; and Van Wagner, Edward M., 3,578,445.
 Hopkins, James R.: *See—*
 Kluksdahl, Harris E.; and Hopkins, James R., 3,578,395.
 Hopps, Jay N.; and Green, Norman F., to United States of America, Air Force. Mechanical pneumatic delay timer. 3,578,114, Cl. 188-311.
 Horecky, Stanley V.; and Hayes, Thomas Howe, to Sunbeam Corporation. Combination manicuring and hair drying appliance. 3,578,000, Cl. 132-79.
 Horizons Incorporated: *See—*
 Petro, Victor P.; Lewis, James M.; and Fox, Robert D., 3,578,455.
 Petro, Victor P.; Cable, James R.; and Wainer, Eugene, 3,578,456.
 Horrom, Bruce Wayne: *See—*
 Lee, Cheuk Man; and Horrom, Bruce Wayne, 3,578,672.
 Horsch, Rudolf, to Case, J. I., Company. Loader linkage. 3,578,191, Cl. 214-771.
 Horton, Edward E., to Deep Oil Technology, Inc. Stable marine construction. 3,577,946, Cl. 114-0.5
 Horvath, Laszlo: *See—*
 Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, 3,578,257.
 Hosokawa, Tomoyuki; Tsugeki, Toshii; and Asanari, Shigeyuki, to Matsushita Electric Industrial Co., Ltd. Electric vacuum cleaner. 3,577,869, Cl. 55-361.

Houdet, Claude: *See—*
 Stcherbatcheff, Georges; and Houdet, Claude, 3,577,875.
 Houtman, Harko Jan; Schoot, Cornelis Johannes; Boven, Jan; and van Beck, Leendert Klaas Hellinga, to U.S. Philips Corporation. Photosensitive diazotheother material. 3,578,457, Cl. 96-91.
 Huber, Richard R. Variable volume coffee container. 3,578,467, Cl. 99-182.
 Hubert, Andre Jules, to Union Carbide Corporation. Migration and isomerization of acetylenes. 3,578,724, Cl. 260-678.
 Hudd, Richard N.; and Seiler, Heinz, to Eagle-Picher Industries, Inc. Removal of ferrous sulfate from nickel baths. 3,578,469, Cl. 106-1.
 Hudnall, Frederiek W., to Textron Inc. Trench duct connecting device with vertical adjustment means. 3,577,863, Cl. 52-220.
 Hudson, James L. Self-contained absorption gas charger for liquids. 3,578,295, Cl. 261-122.
 Huffman, Kenneth Robert: *See—*
 Loy, Myrna; Huffman, Kenneth Robert; and Ullman, Edwin Fisher, 3,578,683.
 Hughes Aircraft Company: *See—*
 Bilow, Norman; and Miller, Leroy J., 3,578,611.
 Hughes, Francis H.; and Crawford, Douglas J., to Cluett Peabody & Co., Inc. Parts stacker. 3,578,181, Cl. 214-6.
 Hulin, Dalton O., to Silver Knit Hosiery Mills, Inc. Apparatus for closing hosiery toes and everting hosiery and method. 3,577,942, Cl. 112-25.
 Hulse, Lauren L., to Addressograph-Multigraph Corporation. Liquid electrostatic developing medium having a mixture of non-esterified tricyclic diterpene carboxylic acid and polyhydric alcohol. 3,578,593, Cl. 252-62.1
 Humetrics Corporation: *See—*
 Baessler, Lee R., 3,577,983.
 Hurlbut, Myron Robert; Phillips, Robert Arthur; and Tupper, Leland Chester, to General Electric Company. Method and apparatus for cement kiln control. 3,578,298, Cl. 263-32.
 Hurlbut, Myron R., to General Electric Company. Method and apparatus for cement kiln control. 3,578,299, Cl. 263-32.
 Hurst, John, to Grace, W. R., & Co. Method for making jointed concrete structures. 3,578,733, Cl. 264-35.
 Husing, Walter H., to Shell Oil Company. Web severing and ejection device. 3,578,135, Cl. 197-133.
 Hutchison, William M.: *See—*
 Collingwood, Wilford R.; Hutchison, William M.; and Mangas, Frank E., 3,577,966.
 Huwylar, Sebastian: *See—*
 Schmidt-Hatting, Wolfgang; and Huwylar, Sebastian, 3,578,580.
 Hwa, Chih Ming; and Antony, Gary J., to Grace, W. R., & Co. Method for treating cooling water. 3,578,589, Cl. 210-58.
 Iannelli, Frank M. Carbonator. 3,578,214, Cl. 222-129.1
 Ignell, Rolf Lennart, to Sobrefina SA, mesne. Procedure during the production of a packaging container comprising an outer sleeve and a lining with an outward-turned flange. 3,578,524, Cl. 156-196.
 Ikari, Kyoichiro: *See—*
 Imoto, Saburo; Ikari, Kyoichiro; and Hattori, Tatsuaki, 3,578,485.
 Ikegami, Yoshizo, to Fuji Shashin Film Kabushiki Kaisha. Flash system for a photographic camera. 3,577,899, Cl. 95-11.
 Iken, Horst Dieter; and Trappmann, Wolfgang Hans, to Messer Griesheim GmbH. Process for flame refining of copper smelts. 3,578,438, Cl. 75-73.
 Imoto, Saburo; Ikari, Kyoichiro; and Hattori, Tatsuaki, to Kuraray Co., Ltd. Method of producing a coated paper. 3,578,485, Cl. 117-62.
 Imperial Chemical Industries Limited: *See—*
 Dodman, David; and Wooley, John Mathers, 3,578,720.
 Hayden, Percy, 3,578,698.
 Lee, Denis, 3,578,572.
 Waters, Graham Thomas, 3,577,873.
 Ingestad, Nils Torsten; and von Haartman, Ernst Goran, to Aktiebolaget Walco. Method for automatically supplying nutritive compositions to plants in optimum amounts. 3,578,431, Cl. 1.
 Inland Steel Company: *See—*
 Mills, Norman T.; Jackson, Charles R.; and Halley, James W., 3,578,064.
 Inoi, Takeshi: *See—*
 Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishibashi, Hiroaki, 3,578,435.
 Institut de Recherches de la Siderurgie Francaise: *See—*
 Boucraut, Michel; Toth, Imre; and Reyter, Jean Pierre, 3,578,296.
 International Business Machines Corporation: *See—*
 Heidt, William A.; Palmer, Leon E.; and Schaefer, John O., 3,578,131.
 Klein, Walter F., 3,578,337.
 Mehl, Daniel L.; Wilson, Delbert T.; and Young, Richard J., 3,578,511.
 Norby, Carl J., 3,578,156.
 Schaefer, John O., 3,578,133.
 International Minerals & Chemicals Corporation: *See—*
 Boeglin, Albert F., 3,578,399.
 International Nickel Company, Inc., The: *See—*
 Eiselstein, Herbert L.; and Haerberle, Carl B., 3,578,440.
 International Recreation Products, Inc.: *See—*
 Elesh, Joseph, 3,578,333.
 Intong Aktiebolag: *See—*
 Soderlund, Per-Erik, 3,578,276.
 Iowa State University Research Foundation: *See—*
 Schuster, Donald H.; and Vaught, Russ S., 3,577,857.

- Irvine, Gerald O.: See—
Fischer, Ronald J.; Groeneveld, Wilbur E.; and Irvine, Gerald O., 3,578,089.
- Ishihashi, Hiroaki: See—
Ushioda, Tsuneo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishibashi, Hiroaki, 3,578,435.
- Israel, Prime Minister Office: See—
Bloch, Moshe R.; Forgacs, Chaim; and Bobker, Ronald V., 3,578,503.
- Ivanov, Vladimir Dmitrievich: See—
Karpacheva, Susanna Mikhailovna; Raginsky, Leonid Solomonovich; Muratov, Valerian Matveevich; Ivanov, Vladimir Dmitrievich; and Baulin, Jury Nikolaevich, 3,578,174.
- Ives, H. B., Company, The: See—
Coopersmith, Leo, 3,578,369.
- Iwano, Haruhiko: See—
Amano, Hiroyuki; Iwano, Haruhiko; Shirasu, Kazuo; and Ohi, Reichi, 3,578,453.
- Amano, Hiroyuki; Ohi, Reichi; Iwano, Haruhiko; and Shirasu, Kazuo, 3,578,454.
- Jache, Albert W.: See—
Bishop, John J.; and Jache, Albert W., 3,578,709.
- Jackson, Charles R.: See—
Mills, Norman T.; Jackson, Charles R.; and Halley, James W., 3,578,064.
- Jackson, Squire Ronald: See—
Greenwood, Kenneth; Heaton, Alban; Harrison, Alwin; and Jackson, Squire Ronald, 3,577,878.
- Jacobs, Robert D.: See—
Dowd, James W.; Jacobs, Robert D.; and Mercer, Harry L., 3,578,491.
- Jacobson, Robert L.: See—
Chevron Research Company. Startup procedure for cyclic regenerative platinum-rhenium reforming process, 3,578,582, Cl. 208-138.
- Jacobus, Rosalind R.: See—
Sanitary cover for shopping cart seat, 3,578,380, Cl. 297-229.
- Jahrstorfer, George W.: See—
Chandler Evans Inc. Directional control valve, 3,578,022, Cl. 137-597.
- Janoski, Edward J.: See—
Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,578,725.
- Jansson, Robert A.: See—
Mickelie, Raymond J., to PPG Industries, Inc. Process for fabricating glass multiple glazed units, 3,578,427, Cl. 65-58.
- Jaquiss, Donald B. G.: See—
Bialous, Charles A.; Jaquiss, Donald B. G.; and Keane, John J., 3,578,634.
- Jarvi, Robert E.: See—
Charvat, Vernon K.; and Jarvi, Robert E., 3,577,839.
- Jefferson Chemical Company, Inc.: See—
Nieneker, Darle Lee; and Williams, Leslie Preston, 3,578,590.
- Jelinek, Jerry G.: See—
Parker-Hannifin Corporation. Sealed joint and gasket therefor, 3,578,346, Cl. 277-180.
- Jenkins, Edwin Earl: See—
Mobil Oil Corporation. Synthetic crystalline zeolite and preparation thereof, 3,578,398, Cl. 23-113.
- Jepsen, Tage L. B.: See—
Basic Incorporated. Beneficiation of magnesians ores or the like, 3,578,162, Cl. 209-172.
- Jerabek, Elihu C.: See—
Hamlen, Robert P.; and Jerabek, Elihu C., 3,578,504.
- Jesionowski, John: See—
Vise, 3,578,308, Cl. 269-212.
- Jestrabek, Leopold: See—
Heckler & Koch GmbH. Magazine for firearms, 3,577,860, Cl. 42-50.
- Jewell, Donald K.: See—
Bloch, Roy W.; and Jewell, Donald K., 3,578,204.
- Jobling, James A., & Co., Limited: See—
Lee, William Stanley, 3,578,428.
- Johnson, Bruce M.; DeCrescenti, Michael A.; and Darrah, James G.: See—
United Aircraft Corporation. Process for fabrication of stoichiometric uranium monocarbide, 3,578,610, Cl. 264-0.5.
- Johnson, John H.: See—
Monsanto Company. Resinous esters of polymeric N-hydroxyimides, 3,578,641, Cl. 260-78.
- Johnson, Kent N.: See—
Gutridge, Jack E.; Johnson, Kent N.; and Spence, John H., 3,577,934.
- Johnson, Leo R.: See—
Carpet seamer, 3,578,534, Cl. 156-461.
- Johnson, Loering M.; and Yuile, Arthur M.: See—
Combustion Engineering, Inc. Method and apparatus for continuous monitoring and control of neutron absorption properties of chemical shim, 3,578,562, Cl. 176-22.
- Johnson Rubber Company, The: See—
Finerock, Donald W., 3,578,375.
- Johnston, Arthur K.: See—
University of Newcastle, The. Concentric evaporation-condensation, rotary, thin film, heat transfer apparatus, 3,578,071, Cl. 165-66.
- Jones, Richard F.: See—
Agonic Engineering, Inc. Dual canister recirculator, 3,577,988, Cl. 128-142.7.
- Jones, William H.: See—
Armstrong Jones Limited. Arcuate blade gate valve, 3,578,283, Cl. 251-31.
- Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham: See—
Sun Oil Company. Novel catalyst system for isomerizing hydrocarbons, 3,578,725, Cl. 260-683.75.
- Juentgen, Harald: See—
Kruel, Martin; Juentgen, Harald; and Drwatwa, Heinrich, 3,578,390.
- Jurion, Roland; and Leblanche, Andre: See—
Societe d'Etudes Chimiques pour L'Industrie et. Water treatment apparatus, 3,578,005, Cl. 137-3.
- Justin, Frank H.: See—
Rieke, James K.; and Justin, Frank H., 3,578,630.
- Kaasenbrood, Petrus J. C.: See—
Stamicarbon N.V. Process for the recovery of melamine from a synthesis gas mixture containing hot melamine vapour, 3,578,664, Cl. 260-249.7.
- Kabel- und Metallwerke Gutehoffnungshutte Aktiengesellschaft: See—
Langer, Reinhold, 3,578,065.
- Kabelschlepp GmbH: See—
Haseck, Friedrich; and Loos, Kurt, 3,578,061.
- Kahle, Gerald R.: See—
Moberly, Charles W.; and Kahle, Gerald R., 3,578,646.
- Kaiser Aluminum & Chemical Corporation: See—
Kissin, Gerald Harvey, 3,578,570.
- Kewis, Robert A.: See—
Lewis, Robert A., 3,578,569.
- Kalish, Arthur: See—
Adjustable gage for sewing machines, 3,577,945, Cl. 112-153.
- Kalopissis, Gregoire; and Bugaut, Andree: See—
L'Oreal. Dyeing human hair with benzothiazole azo compounds, 3,578,386, Cl. 8-10.
- Kalopissis, Gregoire; and Vanlerberghe, Guy: See—
Societe Anonyme dite: L'Oreal. Surface active agents, 3,578,719, Cl. 260-611.
- Kamijima, Yasuhiro: See—
Hasegawa, Tatsuo; Yoshie, Kohichi; and Kamijima, Yasuhiro, 3,578,376.
- Kamin, George J.: See—
Chiola, Vincent; Cleveland, Joseph J.; Kamin, George J.; and Kim, Tai K., 3,578,391.
- Kancko, Yasuhiro: See—
Soeda, Shigeki; Nemoto, Hidetaro; and Kancko, Yasuhiro, 3,578,062.
- Kangel Magnet Limited: See—
Kell, John, 3,578,260.
- Karpacheva, Susanna Mikhailovna; Raginsky, Leonid Solomonovich; Muratov, Valerian Matveevich; Ivanov, Vladimir Dmitrievich; and Baulin, Jury Nikolaevich: See—
Fluid-flow pump, 3,578,174, Cl. 210-416.
- Kato, Yoshiaki; and Watanabe, Hideya: See—
Mitsubishi Denki Kabushiki Kaisha. Control device for positioning carriages of business machines, 3,578,129, Cl. 197-19.
- Katona, Joseph W.: See—
Mills Products Inc. Oven door window unit, 3,577,973, Cl. 126-200.
- Kaufman, Cut E.: See—
Ro-Search, Incorporated. Footwear, 3,577,858, Cl. 36-2.5.
- Kawada, Toshio: See—
Yamamoto, Kozo; and Kawada, Toshio, 3,578,261.
- Kawasaki Jukogyo Kabushiki Kaisha: See—
Narita, Shozo; Ojima, Masaki; and Shiraishi, 3,577,958.
- Kawasumi, Shohachi: See—
Nakaguchi, Kohci; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, 3,578,636.
- Kay, Clifford: See—
Clack, Willis E.; Kay, Clifford; and Nygren, Charles E., 3,578,167.
- Kaye, Gordon Edwin: See—
Green, Derek Bernard; and Kaye, Gordon Edwin, 3,578,220.
- Kayex Corporation: See—
Bender, David L.; and Moore, Robert E., 3,577,861.
- Kazan, John, Jr.; and Foster, Walter Henry, Jr.: See—
American Cyanamid Company. Fiber reactive photochromic dyes, 3,578,389, Cl. 8-163.
- Kazmarek, Edward: See—
Lear Siegler, Inc. Control system with multiple function capability, 3,578,267, Cl. 244-77.
- Keane, John J.: See—
Bialous, Charles A.; Jaquiss, Donald B. G.; and Keane, John J., 3,578,634.
- Keene Corporation: See—
Eriksen, Herluf N., 3,577,889.
- Kell, John: See—
Kangel Magnet Limited. Inertia reel mechanisms, 3,578,260, Cl. 242-107.4.
- Keller, Ernst: See—
Disk tumbler cylinder and key for a lock, 3,578,371, Cl. 292-364.
- Keller, Howard F., Jr.; and Ward, Geoffrey R.: See—
Sutton Research Corporation. Method for producing smoking product of oxidized cellulosic material, 3,577,994, Cl. 131-2.
- Kemmer, Frank N.: See—
Nalco Chemical Company. Color removal process, 3,578,587, Cl. 210-52.
- Kemp, Thomas: See—
Badguerhanian, Leon; and Kemp, Thomas, 3,578,649.
- Ken-Flo Products Corporation: See—
White, Eugene B., 3,578,169.
- Kennedy, Eugene F.: See—
McGuire, Stephen E.; and Kennedy, Eugene F., 3,578,704.
- Kerb, Ulrich: See—
Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.
- Kerr Glass Manufacturing Corporation: See—
Myer, Caleb H.; and Nicklaus, Gregory L., 3,578,140.
- Kerr, John T.: See—
Ramp structure, 3,578,322, Cl. 273-54.
- Khaitlin, Adolf Iserovich: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna;

- Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Iserovich, 3,578,172.
- Kim, Tai K.: See—
Chiola, Vincent; Cleveland, Joseph J.; Kamin, George J.; and Kim, Tai K., 3,578,391.
- Kimberly-Clark Corporation: See—
Loynd, James, 3,578,533.
- King, Maurice; and Barber, Trevor Leslie: See—
General Motors Corporation. Internal combustion engine ignition systems, 3,577,970, Cl. 123-146.5.
- Kirk, Charles C.: See—
Gregorian, Razmic S.; and Kirk, Charles C., 3,578,647.
- Kirkpatrick, Max B.; Harvey, Andrew; and Sparks, John M., III: See—
Horseshoe, 3,578,087, Cl. 168-24.
- Kirschner, Helmut: See—
Pammer, Erich; and Kirschner, Helmut, 3,578,495.
- Kissin, Gerald Harvey: See—
Kaiser Aluminum & Chemical Corporation. Aluminum capacitor foil, 3,578,570, Cl. 204-33.
- Kite, Francis E.; and Stejskal, Joseph F.: See—
CPC International Inc. Desolvating starch, 3,578,498, Cl. 127-71.
- Kiwaki, Hisakatsu: See—
Onoda, Yoshimitsu; and Kiwaki, Hisakatsu, 3,577,929.
- Klein, Walter F.: See—
International Business Machines Corporation. Reversible drive for transducer used in a recording and reproducing apparatus, 3,578,337, Cl. 274-4.
- Kleine-Doecke, Wolfgang: See—
Gruber, Wilhelm; and Kleine-Doecke, Wolfgang, 3,578,663.
- Kleiner, Eduard Karl: See—
Kneil, Martin; and Kleiner, Eduard Karl, 3,578,487.
- Klevens, Maury: See—
Pickell, Calvin D.; and Klevens, Maury, 3,578,327.
- Klimek, Boleslaw: See—
Berg Mfg. & Sales Co. Drain valve, 3,578,286, Cl. 251-303.
- Kline, Smith & French Laboratories: See—
Dunn, George L., 3,578,676.
- Kliss, Robert M.; Matthews, Clifford N.; and Moser, Robert E.: See—
Monsanto Company. Polypeptide synthesis from ammonia and methane using high energy radiation, 3,578,576, Cl. 204-162.
- Klootwijk, Arie: See—
deceased (by Klootwijk, Johanna Maria, representative); Bergwerf, Willem; and Wager, Willem M., to Shell Oil Company. Process for preparing poly(beta-lactone) perpolymers, 3,578,700, Cl. 260-484.
- Kluskdahl, Harris E.; and Hopkins, James R.: See—
Chevron Research Company. Recovery of metals, 3,578,395, Cl. 23-20.
- Knell, Martin; and Kleiner, Eduard Karl: See—
Geigy Chemical Corporation. Method for rendering substrates soil repellent, 3,578,487, Cl. 117-121.
- Knipp, Ulrich; Boigk, Eckhard; and Weinbrenner, Erwin: See—
Farbenfabriken Bayer Aktiengesellschaft. Synthetic resin pneumatic tire, 3,578,057, Cl. 152-356.
- Knotek, Otto: See—
Eutectic Corporation. Alloy, 3,578,441, Cl. 75-171.
- Knowles, Robert A.: See—
Norlander, Norman E.; and Knowles, Robert A., 3,578,044.
- Kobetz, Paul: See—
Becker, Warren E.; and Kobetz, Paul, 3,578,436.
- Koch, Paul J.: See—
Prevorseck, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hendrikus J.; and Schmitt, George J., 3,578,552.
- Kocourek, Franz: See—
Agfa-Gevaert Aktiengesellschaft. Sheet feeding apparatus, 3,578,312, Cl. 271-20.
- Kohner Bros. Inc.: See—
Kohner, Frank; Stubbman, Albert; and Donna, Natalie, 3,578,319.
- Kohner, Frank; Stubbman, Albert; and Donna, Natalie: See—
Kohner Bros. Inc. Marble pickup game with flexible manipulator, 3,578,319, Cl. 273-1.
- Kolk, Anthony J., Jr.: See—
McQuaid, Paul E.; and Kolk, Anthony J., Jr., 3,578,571.
- Kolm, Henry H.: See—
Massachusetts Institute of Technology. Heat exchange apparatus, 3,578,072, Cl. 165-84.
- Konig, Joachim; and Padberg, Gunter: See—
Chemische Fabrik Promonta GmbH. Carbohydrate agent of high water retention power, process of making same, and composition containing same, 3,578,655, Cl. 260-209.
- Koons, Charles E.: See—
Gregg, Alvin L.; and Koons, Charles E., 3,578,518.
- Koppers Company, Inc.: See—
Tai, Wun T., 3,578,613.
- Taschenberg, Ernest J.: See—
Taschenberg, Ernest J., 3,578,343.
- Kornicher, Walter A.: See—
Monsanto Company. Process for the polymerization of acetylene compounds, 3,578,626, Cl. 260-94.1.
- Korshak, Vasily Vladimirovich; Vinogradova, Svetlana Vasilievna; and Tur, Dzidra Rudolfovna: See—
Method of producing modified polyarylates, 3,578,631, Cl. 260-47.
- Koshar, Robert J.: See—
Mitsch, Ronald A.; and Koshar, Robert J., 3,578,717.
- Kosloski, John E.: See—
Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., 3,577,949.
- Kosuge, Kuniko: See—
Ono, Hisatake; Osada, Tiaki; and Kosuge, Kuniko, 3,578,602.
- Kovacs, Paul: See—
Tannenberger, Helmut; and Kovacs, Paul, 3,578,502.
- Kozlov, Jury Gotlibovich: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna;

Lambert, Guy; and Macaire, Marcel, to Merlin Gerin. Energy storage control device, in particular for electric circuit breakers. 3,577,887, Cl. 74-2.

Lambert, Robert R. Suspended ceiling integrated air distribution system. 3,577,904, Cl. 98-40.

Land, Edwin, to Polaroid Corporation. Color photographic product formed by diffusion transfer. 3,578,540, Cl. 161-6.

Langer, Reinhold, to Kabel- und Metallwerke Gutehoffnungshutte Aktiengesellschaft. Mandrel holder for horizontal pipe casting apparatus. 3,578,065, Cl. 164-281.

Lapkin, Milton: See—
Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,393.
Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,400.

Lapp, Leon R.; and Burkard, Edward A., to National Gypsum Company. Gypsum board forming. 3,578,517, Cl. 156-40.

Larger, Nelson N., to Perdue, A. W., & Son, Inc. Method and apparatus for conveying material. 3,578,183, Cl. 214-17.

Largman, Theodore; and Newall, Peter E., to Allied Chemical Corporation. N-(3,4-dichlorophenyl)-3-[N'-(3,4-dichlorophenyl) carbamoyl]methyl-2,2-dimethylcyclobutane-carboxamide. 3,578,711, Cl. 260-558.

Larkin, John M.; and Kreuz, Kenneth L., to Texaco Inc. Process for producing 4-nitroalkanoic acids. 3,578,687, Cl. 260-404.

Larson, Richard R., to Hercules Incorporated. Charge loader device, system, and method for underwater seismic exploration. 3,578,101, Cl. 181-05.

Lash, Alec. Picture records. 3,578,539, Cl. 161-6.

Laughlin, James P.; and Worman, Everett, to Whirlpool Corporation. Twist to mount condenser mounting grommet for refrigerator. 3,578,280, Cl. 248-54.

Lavander, Edward J.: See—
Burnham, Edward H.; and Lavander, Edward J., 3,578,317.

Lawson Products, Inc.: See—
Morancy, William F., 3,578,546.

Lazar, Jeffrey M., to Honeywell Inc. Control apparatus. 3,577,964, Cl. 123-119.

Lazaridis, Christina Nicholson; and Wixon, Harold Eugene, to Colgate-Palmolive Company. Fabric softener composition. 3,578,591, Cl. 252-87.

Leading Plywood: See—
Crawford, John H., 3,578,151.

Lear Siegler, Inc.: See—
Kazmarck, Edward, 3,578,267.
Kramer, Kenneth C., 3,578,268.
Kramer, Kenneth C.; Davis, Richard L.; and Boc, Otto H., 3,578,269.

Leblanche, Andre: See—
Jurion, Roland; and Leblanche, Andre, 3,578,005.

Ledoux, Claude; and Neuville, Bernard, to Produits Chimiques Pechiney-Saint-Gobain. Extruders with rotating plate. 3,577,841, Cl. 18-12.

Lee, Cheuk Man; and Horrom, Bruce Wayne, to Abbott Laboratories. 2-propargylamino-5-phenyl-2-oxazolin-4-one and derivatives. 3,578,672, Cl. 260-307.

Lee, Denis, to Imperial Chemical Industries Limited. Electrodes for use in aqueous alkali metal chloride electrolytes. 3,578,572, Cl. 204-95.

Lee, William Stanley, to Jobling, James A., & Co., Limited. Methods of producing ceramic material in rod or tube form. 3,578,428, Cl. 65-60.

Leeds & Northrup Company: See—
Wiese, John R., 3,577,886.

Le Febvre, Arthur H., to Singer-General Precision, Inc. Seal assembly for a hydraulically operated cylinder. 3,578,341, Cl. 277-3.

Leichtl, Ludwig, to McCord Corporation. Adjustable headrest for vehicle seats. 3,578,384, Cl. 297-410.

Lennox, John B. Speaker enclosure. 3,578,103, Cl. 181-31.

Leonard, Wolfgang B.: See—
Hain, Gottfried M.; and Leonard, Wolfgang B., 3,577,865.

Le Par, Edwin. Equipment for delivering a liquid into a body stoma. 3,577,982, Cl. 128-2.

Leak, Israel Arnold, to Motorola, Inc. Method for making passivated field-effect transistor. 3,578,514, Cl. 148-175.

Leslie, George W. D., to Anglo American Corporation of South Africa Limited. Means for varying the physical conditions of a gas. 3,577,880, Cl. 62-86.

Lev Mikhailovich: See—
Cherny, Anatoly Alexeevich; Vladimir Alexandrovich; Lev Mikhailovich; Kurbatsky, Ivan Lukich; Sosnovsky, Efim Davidovich; and Pavlenko, Nikolai Semenovich, 3,578,302.

Lever Brothers Company: See—
van der Zijden, Antonie Simon Maria; and of the heirs, 3,578,465.

Levitkaya, Ljudmila Alexeevna: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Iserovich, 3,578,172.

Levy, Donald; and Ruz, Tibor, to Donti Research Development Manufacturing. Spirometer. 3,577,984, Cl. 128-208.

Lewis, James M.: See—
Petro, Victor P.; Lewis, James M.; and Fox, Robert D., 3,578,455.

Lewis, Robert A., to Kaiser Aluminum & Chemical Corporation. Anode polarization detector. 3,578,569, Cl. 204-1.

Li, Hsin L.: See—
Prevorsek, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hendrikus J.; and Schmitt, George J., 3,578,552.

Lilly, Eli, and Company: See—
Cooper, Robin D. G., 3,578,660.

Lindquist, Everett F.; and Carsner, George E., to Westinghouse Learning Corporation. Document handling apparatus. 3,578,159, Cl. 209-74.

Lisitsina, Galina Konstantinovna: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Iserovich, 3,578,172.

List, Ferdinand; and Alfs, Helmut, to Chemische Werke Huels A.G. Removal of bromine-containing impurities from aqueous acetic acid. 3,578,706, Cl. 260-524.

Lithium Corporation of America: See—
Honeycutt, Sammy C., 3,578,501.

Littell, Ruddy; and Allen, George Rodge, Jr., to American Cyanamid Company. Hydroxycarbazonol diones. 3,578,678, Cl. 260-315.

Litton Business Systems, Inc.: See—
Frechette, Kenneth R.; and Rosborg, Daniel J., 3,578,128.
Frechette, Kenneth R., 3,578,130.
Parker, Ralph L., 3,578,134.

Lock, Coy B., 1/4 each to Treybig, Clemens N., and Racusin, Paul. Pipe wrench construction. 3,578,307, Cl. 269-96.

Locke, James N.: See—
Lundberg, John B.; Beck, Richard J.; and Locke, James N., 3,578,045.

Lockhart, Robert J. Hand truck apparatus. 3,578,353, Cl. 280-47.2

Lombard Corporation: See—
Lombard, Daniel L., 3,577,882.

Lombard, Daniel L., to Lombard Corporation. Hydraulic forging press. 3,577,882, Cl. 72-450.

London Litho-Aluminum Company, Incorporated: See—
London, Melvyn; Smetters, Guy Robert; and Beck, George Eugene, 3,577,920.

London, Melvyn; Smetters, Guy Robert; and Beck, George Eugene, to London Litho-Aluminum Company, Incorporated. Metallic lithographic plate and method of making the same. 3,577,920, Cl. 101-459.

Loos, Kurt: See—
Haschek, Friedrich; and Loos, Kurt, 3,578,061.

L'Oreal: See—
Kalopissis, Gregoire; and Bugaut, Andre, 3,578,386.
Zviak, Charles; and Ghilardi, Giuliana, 3,578,387.

Lorenz, Max R.: See—
Pilkun, Manfred H.; and Lorenz, Max R., 3,578,513.

Lorenz, Roman R.: See—
Tullar, Benjamin F.; and Lorenz, Roman R., 3,578,686.

Louis, Kwok Toy; Wurms, Donald W.; and Zaritsky, Herbert, to Ciba Corporation. Cold water-dispersible emulsions of water repellent compositions containing triazine-formaldehyde condensation products. 3,578,617, Cl. 260-21.

Lount, Graham C.; and Lount, William D. Method of forming building walls. 3,578,732, Cl. 264-34.

Lount, William D.: See—
Lount, Graham C.; and Lount, William D., 3,578,732.

Love, John J., to Emerson Electric Co. Stepped flow gas valve. 3,578,243, Cl. 236-80.

Lowery, James D., Jr.: See—
May, Joe C.; and Lowery, James D., Jr., 3,578,190.

Loy, Myrna; Huffman, Kenneth Robert; and Ullman, Edwin Fisher, to American Cyanamid Company. 1,4 Disubstituted-1-hydroxy-2,3-tricyano-1,2-dihydroanthrones. 3,578,683, Cl. 260-335.

Loyd, Calvin D.; Oberle, Theodore L.; and Satzler, Ronald L., to Caterpillar Tractor Company. Hydraulically loaded thrust bearing arrangement for a friction welding machine. 3,578,232, Cl. 228-2.

Loynd, James, to Kimberly-Clark Corporation. Apparatus for drafting and depositing multiple fiber webs on a carrier sheet. 3,578,533, Cl. 156-436.

Lubrizol Corporation, The: See—
Coleman, Lester E., 3,578,637.
Dorer, Casper John, Jr., 3,578,422.

Lucas, Joseph, (Industries) Limited: See—
Detheridge, John Stanley; and March, John William, 3,577,851.
Greenwood, Kenneth; Heaton, Alban; Harrison, Alwin; and Jackson, Squire Ronald, 3,577,878.
Warne, Eugene Harold, 3,577,877.

Luckmann, Frederick Hugo; and Melnick, Daniel, to CPC International Inc. Pickled vegetable product and process of preparation. 3,578,466, Cl. 99-156.

Ludwig, Charles H., to Georgia-Pacific Corporation. Acylated lignosulfonates. 3,578,651, Cl. 260-124.

Lukesch, Heinz; Krakowsky, Hans; and Heeb, Dieter, to Schwarzkopf, Hans, Firma. Aerosol container with push-on closure and nozzle. 3,578,221, Cl. 222-402.22

Lundberg, John B.; Beck, Richard J.; and Locke, James N., to Super Mold Corporation. Expanding tire-supporting wheel apparatus. 3,578,045, Cl. 144-288.

Luttrell, Richard W.: See—
Clancy, Lawrence F.; Grooss, Frank A.; and Luttrell, Richard W., 3,578,098.

Lyofo-Stopper Corporation: See—
Ogle, Robert W., 3,578,195.

Lyric Kabushiki Kaisha: See—
Arai, Masayuki, 3,578,236.

Maassen, Heinz, to Gusken, Jean, The firm of. Hook shaped gripper point. 3,578,031, Cl. 139-122.

Macaire, Marcel: See—
Lambert, Guy; and Macaire, Marcel, 3,577,887.

MacDonald, Donald M.: See—
Godsay, Madhu P.; and Mac Donald, Donald M., 3,578,553.

MacGrandle, Timothy D.: See—
Battersby, William R.; Follett, Robert P.; MacGrandle, Timothy D.; Rossitto, Conrad; and Taylor, Paul, 3,578,727.

Mack Trucks, Inc.: See—
Rath, Harry B., 3,578,017.

Macomber, James Keith, to Consolidated Educational Publishing, Inc. Booster roll for intermittent feeds. 3,578,229, Cl. 226-114.

Macy, James B., Jr.: See—
Satterthwaite, James Glenn; and Macy, James B., Jr., 3,578,342.

Magnier, Roger, to Regie Nationale des Usines Renault, and Automobiles Peugeot. Grooved sintered metal synchro mesh ring. 3,578,122, Cl. 192-107.

Mainet, Maurice, to Produits Chimiques Pechiney Saint-Gobain. Sealing assembly and method. 3,578,202, Cl. 220-46.

Mainet, Maurice, to Produits Chimiques Pechiney Saint-Gobain. Sealing assembly. 3,578,203, Cl. 220-46.

Makin, Earle C., Jr.: See—
Davis, George F.; Gebhart, Herbert J., Jr.; and Makin, Earle C., Jr., 3,578,581.

Malvin, Harry H.; and Stansell, Marion J. Process and apparatus for the continuous flow, in-line fractionation and exchange of volatile solvents. 3,578,567, Cl. 203-49.

Mandell, George C., to Ampex Corporation. Cassette changer with fast tape wind. 3,578,262, Cl. 242-199.

Mangas, Frank E.: See—
Collingwood, Wilford R.; Hutchison, William M.; and Mangas, Frank E., 3,577,966.

Mange, Franklin E.; Buriks, Rudolf S.; and Quinlan, Patrick M., to Petrolite Corporation. Linear polymeric phosphorus-containing esters. 3,578,731, Cl. 260-929.

Manjikian, Serop, to Universal Water Corporation. Helically wound semipermeable membrane. 3,578,175, Cl. 210-489.

Manning, Robert E., to Sandoz-Wander, Inc. Substituted imidazolines pyrimidines and diazcpines. 3,578,666, Cl. 260-256.5

Manos, William P.: See—
Ferris, Ray L.; Shaver, William R.; and Manos, William P., 3,577,933.

Marans, Nelson S., to Grace, W. R., & Co. Chelating polymer. 3,578,697, Cl. 260-465.4

Marathon Oil Company: See—
Conway, David D., 3,578,596.

Davis, John A., Jr.; and Kunzman, William J., 3,578,082.

Marbach, Edward P., to Baxter Laboratories, Inc. Automatic proportioner assembly. 3,578,039, Cl. 141-18.

March, John William: See—
Detheridge, John Stanley; and March, John William, 3,577,851.

Marchetti, Charles Joseph; and Neplaz, Guy Marcel, to Societe d'Etudes et de Developpement des Aeroglisseurs Marins Terrestres et Amphibies S.-E.D.A.M. Device for confining pressure-fluid cushions, more particularly for waterborne ground-effect machines. 3,578,100, Cl. 180-126.

Marchisen, Joseph, to Union Camp Corporation. Lined shipping container. 3,578,234, Cl. 229-14.

Margarit Taya, Miguel: See—
Ricard, Rene; and Margarit Taya, Miguel, 3,578,657.

Maricle, Donald Leonard; and Hoffmann, Arthur Kentaro, to American Cyanamid Company. Non-aqueous electro-chemical current producing cell having soluble cathode depolarizer. 3,578,500, Cl. 136-6.

Markovac, Anica: See—
Ash, Arthur B.; Stevens, Calvin L.; and Markovac, Anica, 3,578,682.

Markovics, Eugene J. Portable highway crash rescue unit. 3,577,881, Cl. 72-302.

Marksman Manufacturing Corporation: See—
Pickell, Calvin D.; and Klevens, Maury, 3,578,327.

Marlet Barbera, Jose. Coffee-making and vending machine. 3,578,125, Cl. 194-13.

Martelli, Homer, to Union Camp Corporation. Shadow box with locking dust flaps. 3,578,154, Cl. 206-45.14

Martin, Donald N., to Beckman Instruments, Inc. Automated transport system. 3,578,412, Cl. 23-259.

Martin, Eugie A.; and Fanning, Robert J., to Ethyl Corporation. Ester purification process. 3,578,689, Cl. 260-410.9

Martin, Ivo L. Apparatus for salvaging blue powder from zinc ore furnaces and the like. 3,578,070, Cl. 165-61.

Martini, Leo A., to Telco Industries. Solenoid valve. 3,578,284, Cl. 251-88.

Martini, Peter Albert. Process and apparatus for separating articles. 3,578,160, Cl. 209-81.

Maruta, Isao: See—
Nakashio, Seizo; and Maruta, Isao, 3,578,625.

Massachusetts Institute of Technology: See—
Grant, Nicholas J.; and Schilling, William F., 3,578,443.

Kolm, Henry H., 3,578,072.

Masuda, Kohei: See—
Sakata, Rikita; Masuda, Kohei; Uchigaki, Taku; and Arai, Masakazu, 3,578,527.

Mathewson, Wilfred F., Jr.: See—
Wright, Archibald N.; and Mathewson, Wilfred F., Jr., 3,578,425.

Matsushita Electric Industrial Co., Ltd.: See—
Fujita, Takashi, 3,577,884.
Hosokawa, Tomoyuki; Tsugeki, Toshii; and Asanari, Shigeyuki, 3,577,869.
Nakai, Miyoji; Nakajima, Akira; Watanabe, Makoto; and Sanukiya, Toshio, 3,577,842.
Yamamoto, Kozo; and Kawada, Toshio, 3,578,261.

Mattel, Inc.: See—
Summerfield, William F., 3,578,339.

Matthews, Clifford N.: See—
Kliss, Robert M.; Matthews, Clifford N.; and Moser, Robert E., 3,578,576.

Maurice, Jean, to Societe Anonyme Francaise Du Ferodo. Friction disc with torsional dampener. 3,578,121, Cl. 192-106.2

May, Joe C.; and Lowery, James D., Jr. Multipurpose trailer. 3,578,190, Cl. 214-505.

McAttee, Regis Aloysius. Auxiliary slide member for mounting on sled runner. 3,578,351, Cl. 280-28.

McCaffrey, Francis Hamnet Garland: See—
Findlay, Donald Urquhart; McCaffrey, Francis Hamnet Garland; and Taylor, George David, 3,577,924.

McCarrick, Terence E.; and Antonsen, Olaf S., to Black Clawson Company. The Twin wire paper making assembly. 3,578,558, Cl. 162-303.

McCarrick, Terence E.; and Antonsen, Olaf S., to Black Clawson Company. The Paper forming apparatus. 3,578,561, Cl. 162-352.

Mc Carron, John K.: See—
Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and Mc Carron, John K., 3,578,233.

McConnell, Charles Knapp, to ACF Industries, Incorporated. Automotive cruise control system having fluidic control devices. 3,578,108, Cl. 180-106.

McCord Corporation: See—
Leichtl, Ludwig, 3,578,384.

McDaniels, Paul E.: See—
Alvey, George H.; McDaniels, Paul E.; and Pease, Roy T., Jr., 3,578,324.

McDavid, Larry S.: See—
Roche, Jerry E.; and McDavid, Larry S., 3,578,020.

McDonnell Douglas Corporation: See—
Ginn, David L.; and Hilmer, Donald A., 3,578,274.

McGuire, Stephen E.; and Kennedy, Eugene F., to Continental Oil Company. Succinates substituted in the alpha position by alkyl benzene sulfonates. 3,578,704, Cl. 260-507.

Mc Manime, Robert J., to Monsanto Company. Process for preparing reinforced polyolefins. 3,578,629, Cl. 260-41.

Mc Nally, Robert N.: See—
Alper, Allen M.; and Mc Nally, Robert N., 3,578,473.

Mc Quaid, Paul E.; and Kolk, Anthony J., Jr., to General Precision Systems Inc. Method of electrodepositing a magnetic alloy and electrolyte therefor. 3,578,571, Cl. 204-43.

Mecca, Sebastian B., to Schuykill Chemical Company. Method of making allantoin polygalacturonic acid compounds. 3,578,656, Cl. 260-209.

Mchaffie, Stephen R.: See—
Weingarten, Joseph L.; and Mchaffie, Stephen R., 3,578,050.

Mehl, Daniel L.; Wilson, Delbert T.; and Young, Richard J., to International Business Machines Corporation. Solid metal molding. 3,578,511, Cl. 148-11.5

Mehlshau, James J., to University of California, The Regents of the. Filler for bins. 3,578,146, Cl. 198-121.

Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and Mc Carron, John K., to Shell Oil Company. Apparatus for remotely joining underwater pipelines. 3,578,233, Cl. 228-5.

Melnick, Daniel: See—
Luckmann, Frederick Hugo; and Melnick, Daniel, 3,578,466.

Menge, Donald C., to Troy Steel Corporation. Lumber cutting apparatus. 3,578,043, Cl. 143-6.

Mengle, Robert C. Method of extracting O-rings from recessed grooves. 3,577,848, Cl. 29-427.

Mercer, Harry L.: See—
Dowd, James W.; Jacobs, Robert D.; and Mercer, Harry L., 3,578,491.

Merck & Co., Inc.: See—
Hoff, Dale R.; and Peterson, Louis H., 3,578,675.

Wendler, Norman L.; Taub, David; and Kuo, Chan Hwa, 3,578,670.

Wendler, Norman L.; Slates, Harry L.; and Weber, Stuart, 3,578,705.

Merlin Gerin: See—
Lambert, Guy; and Macaire, Marcel, 3,577,887.

Merlin Gerin, Societe Anonyme: See—
Victorri, Marcel, 3,577,928.

Merriman, Maximilian R. Amalgamation process. 3,578,439, Cl. 75-129.

- Merry, Jack D.; and Deuschle, Fritz, to Said Merry assor. to Brunswick Corporation. Valve for use with a conduit having a lumen. 3,577,992, Cl. 128-349.
- Messer Griesheim GmbH: See—
Iken, Horst Dieter; and Trappmann, Wolfgang Hans, 3,578,438.
- Metallgesellschaft Aktiengesellschaft: See—
Uehler, Dieter; and Heinz, Ernst, 3,578,401.
- Metz, Joseph R., to Norco, Inc. Power or manually released cargo latch. 3,578,373, Cl. 294-83.
- Metzger, William J.; and De Penti, Kenneth L., to Midland-Ross Corporation. Car coupler centering device. 3,578,180, Cl. 213-20.
- Meyer, Howard F., Jr., to Ford Motor Company. Jacket for flexible hose. 3,578,026, Cl. 138-110.
- Mickelic, Raymond J.: See—
Jansson, Robert A.; and Mickelic, Raymond J., 3,578,427.
- Middour, Donald R.: See—
Henry, Nelson R.; and Middour, Donald R., 3,578,094.
- Midland-Ross Corporation: See—
Shafer, James A., 3,577,931.
- Midland-Ross Corporation: See—
Metzger, William J.; and De Penti, Kenneth L., 3,578,180.
- Migitz, Steven. Simulated grass mat for driving golf balls. 3,578,542, Cl. 161-21.
- Mihm, Adeline M.: See—
Mihm, Clifford H., deceased; and Mihm, Adeline M.; administrator, 3,578,681.
- Mihm, Clifford H., deceased; and Mihm, Adeline M.; administrator, to Phillips Petroleum Company. Synthesis of thioxane. 3,578,681, Cl. 260-327.
- Milberger, Ernest C.; and Shaw, Wilfrid G., to Standard Oil Company, The (Ohio). Olefinic nitriles by the catalytic oxidation of olefins using hydrogen cyanide. 3,578,695, Cl. 260-465.3
- Miles Laboratories, Inc.: See—
Buckler, Robert Thomas, 3,578,674.
- Milford, Richard E., to Honeywell Information Systems Inc., mesne. Overlapped document detector. 3,578,315, Cl. 271-47.
- Miller, Edgar W.; and Smith, Harry A., to Polaroid Corporation. Diffusion transfer production of reflection positive with aluminum stearate in receptive stratum. 3,578,450, Cl. 96-29.
- Miller, Frank R.; and Dillberg, Raymond E., to Ormco Corporation. Abrading machine for a pre-formed orthodontic band. 3,578,424, Cl. 51-89.
- Miller, Harold J., to Simplicity Engineering Company. Multiple bearing recirculating lubrication system. 3,578,111, Cl. 184-6.
- Miller, Jason A.: See—
Smerak, Louis J.; and Miller, Jason A., 3,578,462.
- Miller, Leroy J.: See—
Bilow, Norman; and Miller, Leroy J., 3,578,611.
- Miller, Roland E., to Kraftco Corporation. Fluent material dispensing device having rotary trap chambers with radially movable ejector. 3,578,217, Cl. 222-218.
- Milliken, Paul E., to Goodyear Tire & Rubber Company, The. Tire stud. 3,578,053, Cl. 152-210.
- Millmaster Onyx Corporation: See—
Wakeman, Reginald L.; and Coates, Joseph F., 3,578,667.
- Mills, Norman T.; Jackson, Charles R.; and Halley, James W., to Inland Steel Company. Continuous casting apparatus. 3,578,064, Cl. 164-281.
- Mills Products Inc.: See—
Katona, Joseph W., 3,577,973.
- Milo, August. Frost heavy-resistant pump inlet assembly. 3,578,021, Cl. 137-515.
- Mindler, Fredric A.: See—
Peterson, Dean M.; Pickering, Charles E.; and Mindler, Fredric A., 3,577,900.
- Ming, Joseph W.: See—
Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, 3,578,257.
- Minnesota Mining and Manufacturing Company: See—
Brown, Francis W.; and Kremer, Leon V., 3,578,622.
- Hoerner, Alfred J.; and Seiter, George M., 3,578,550.
- Mitsch, Ronald A.; and Koshar, Robert J., 3,578,717.
- Throckmorton, James R., 3,578,684.
- Mitchell, Maurice M., Jr.; Fisher, Harold M.; and Tomezsko, Edward S. J., to Atlantic Richfield Company. Method for carrying out reactions of unsaturated hydrocarbons at low temperatures. 3,578,650, Cl. 260-93.7
- Mitsch, Ronald A.; and Koshar, Robert J., to Minnesota Mining and Manufacturing Company. Perfluoroalkyl vinyl sulfones and process for producing same. 3,578,717, Cl. 260-607.
- Mitsubishi Denki Kabushiki Kaisha: See—
Kato, Yoshiaki; and Watanabe, Hideya, 3,578,129.
- Mitsubishi Petrochemical Industry Co., Ltd.: See—
Sakata, Rikita; Masuda, Kohji; Uchigaki, Taku; and Arai, Masakazu, 3,578,527.
- Moberly, Charles W.; and Kahle, Gerald R., to Phillips Petroleum Company. Vinyl monomer polymerization process. 3,578,646, Cl. 260-85.7
- Mobil Oil Corporation: See—
Andress, Harry J., Jr.; and Ashjian, Henry, 3,578,421.
- Bowes, Emmerson; and Wise, John J., 3,578,723.
- Cushman, Donald R., 3,578,477.
- Glenn, Edwin E., Jr.; Slover, Vasek R.; and Strubhar, Malcolm K., 3,578,077.
- Haag, Werner O.; and Whitehurst, Darrel Duayne, 3,578,609.
- Jenkins, Edwin Earl, 3,578,398.
- Moffitt, Roy M., Company, The: See—
Corrigan, John E., 3,578,361.
- Mohawk Data Sciences Corporation: See—
Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, 3,578,257.
- Mohr, Harvey O.: See—
Cullen, Roy H.; Elliott, Charles H.; Aker, Jimmie R.; and Mohr, Harvey O., 3,578,029.
- Moiriat, Maurice. Detachable gooseneck. 3,578,356, Cl. 280-425.
- Monsanto Company: See—
Armour, Donald F., 3,578,223.
- Arnold, Lloyd C.; and Mortimer, George A., 3,578,407.
- Cholmar, Sidney; and Peters, Robert H., 3,578,735.
- Davis, George F.; Gebhart, Herbert J., Jr.; and Makin, Earle C., Jr., 3,578,581.
- Fink, Walter, 3,578,691.
- Fink, Walter, 3,578,692.
- Fink, Walter, 3,578,693.
- Johnson, John H., 3,578,641.
- Kliss, Robert M.; Matthews, Clifford N.; and Moser, Robert E., 3,578,576.
- Kornicher, Walter A., 3,578,626.
- Mc Manime, Robert J., 3,578,629.
- Peck, Arthur C.; and Usko, Alexander J., 3,578,536.
- Punzak, John M., 3,578,144.
- Usko, Alexander J., 3,577,919.
- Weeks, Lloyd E.; and Wildi, Bernard S., 3,578,460.
- Weeks, Lloyd E.; and Wildi, Bernard S., 3,578,461.
- Wesp, George L., 3,578,548.
- Young, James V., 3,578,318.
- Young, James V., 3,578,381.
- Monsanto Research Corporation: See—
Cornell, John H., Jr., 3,578,662.
- Monson, Franklin A.: See—
Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., 3,577,949.
- Montague, Aubrey V. Portable mixer. 3,578,292, Cl. 259-177.
- Moore, Arnott A.: See—
Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Gardner, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.
- Moore, Arthur W., to Union Carbide Corporation. Recrystallization of pyrolytic boron nitride. 3,578,403, Cl. 23-191.
- Moore Business Forms, Inc.: See—
Baxter, George, 3,578,605.
- Moore, Clark A., to Clark-Aiken Company, The. Spraying device and method. 3,577,892, Cl. 93-93.
- Moore, Jack C. Phonograph record vending machine. 3,578,206, Cl. 221-124.
- Moore, Robert E.: See—
Bender, David L.; and Moore, Robert E., 3,577,861.
- Moore, Robert J.; and Allen, Roy A., to Shell Oil Company. Epoxy resin coatings having improved cathodic disbonding resistance. 3,578,615, Cl. 260-18.
- Morancy, William F., to Lawson Products, Inc. Spandex fabric and method of making the same. 3,578,546, Cl. 161-89.
- Moray, Forest J. Adjustable valve stem oil seal for internal combustion engines. 3,577,972, Cl. 123-188.
- Morcom, Richard James: See—
Woodard, Charles Elbert; and Morcom, Richard James, 3,578,734.
- Morel, Paul; Givry, Jean-Pierre; and Voisin, Philippe, to Compagnie Pechincy. Apparatus for firing carbon-containing products. 3,578,069, Cl. 165-61.
- Morse, Stanley A., to American Hoist and Derrick Company, mesne. Control for the operation of the ram of a baler. 3,577,911, Cl. 100-53.
- Mortimer, George A.: See—
Arnold, Lloyd C.; and Mortimer, George A., 3,578,407.
- Morton International, Inc.: See—
Palmer, Jay W., 3,578,394.
- Moser, Robert E.: See—
Kliss, Robert M.; Matthews, Clifford N.; and Moser, Robert E., 3,578,576.
- Moser, Thomas B.: See—
Schillinger, Joseph F.; and Moser, Thomas B., 3,578,238.
- Motorola, Inc.: See—
Lesk, Israel Arnold, 3,578,514.
- Mpelkas, Christos C., to Sylvania Electric Products, Inc. Method of ripening fruit. 3,578,464, Cl. 99-103.
- Mueller, Francis X., Jr.; and Brown, James D., to Phillips Petroleum Company. Polymerization of alkene oxides with an organo-alkaline earth complex and an organoaluminum catalyst system. 3,578,642, Cl. 260-78.3
- Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., to United States of America, Navy. Explosively propelled underwater embedment anchor assembly. 3,577,949, Cl. 114-206.
- Mueller, Roger, to Textile Marking Machine Co., Inc. Method of marking textile articles. 3,578,525, Cl. 156-238.
- Muhlhauser, Otto, to Gesellschaft fur Kernforschung mbH. Spring. 3,578,305, Cl. 267-165.

- Muirhead, Duncan Ronald, to Rose, Downs & Thompson Limited. Incinerators. 3,577,939, Cl. 110-8.
- Muirhead, Duncan Ronald; and Richardson, John Francis, to Rose, Downs & Thompson Limited. Incinerators. 3,577,938, Cl. 110-8.
- Mulgrave, Thomas P., to United States of America, Navy. Reusable holdback release device. 3,578,273, Cl. 244-115.
- Muller, Hans. Device for separating foam into its liquid and gaseous phases. 3,577,868, Cl. 55-178.
- Muller, Marcel: See—
Berndt, Hans-Detlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wicbert, Rudolf, 3,578,659.
- Muller, Rolf: See—
Staudt, Heinrich; Hofmann, Eberhard; and Muller, Rolf, 3,577,968.
- Muller-Schlenker: See—
Mutter, August, 3,577,874.
- Muratov, Valerian Matveevich: See—
Karpacheva, Susanna Mikhailovna; Raginsky, Leonid Solomonovich; Muratov, Valerian Matveevich; Ivanov, Vladimir Dmitrievich; and Baulin, Jury Nikolaevich, 3,578,174.
- Mutter, August, to Muller-Schlenker. Electric clocks with magnetic drives. 3,577,874, Cl. 58-23.
- Myer, Caleb H.; and Nicklaus, Gregory L., to Kerr Glass Manufacturing Corporation. Closure feeding apparatus. 3,578,140, Cl. 198-33.
- Nakada, Shigeo: See—
Tiama, Susumu; and Nakada, Shigeo, 3,578,648.
- Nakaguchi, Kohji; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, to Sumitomo Chemical Company, Ltd. Method for manufacturing alternating copolymers of conjugated vinyl compounds and olefinic unsaturated compounds. 3,578,636, Cl. 260-63.
- Nakai, Miyoji; Nakajima, Akira; Watanabe, Makoto; and Sanukiya, Toshio, to Matsushita Electric Industrial Co., Ltd. Apparatus for compression molding a powder within a container. 3,577,842, Cl. 18-20.
- Nakajima, Akira: See—
Nakai, Miyoji; Nakajima, Akira; Watanabe, Makoto; and Sanukiya, Toshio, 3,577,842.
- Nakajima, Yasuo; and Hayashi, Yoshimasa, to Nissan Jidsha Kabushiki Kaisha. Device for selective combustion in a multi-cylinder engine. 3,578,116, Cl. 192-0.062
- Nakashio, Seizo; and Maruta, Isao, to Sumitomo Chemical Company, Ltd. Stabilized composition of polyphenylene oxide. 3,578,625, Cl. 260-45.75
- Nalco Chemical Company: See—
Kemmer, Frank N., 3,578,587.
- Nantz, Jack G., to Addressograph-Multigraph Corporation. Printing machines with shifting roller platen. 3,577,917, Cl. 101-269.
- Narel, Leonard M.: See—
Absler, Howard K.; and Narel, Leonard M., 3,578,178.
- Narita, Shozo; Ojima, Masaki; and Shiraishi, to Kawasaki Jukogyo Kabushiki Kaisha. Steam boiler heated by waste heat. 3,577,958, Cl. 122-7.
- National Cash Register Company, The: See—
Whitaker, John G.; and Crainich, Victor A., Jr., 3,578,482.
- National Distillers and Chemical Corporation: See—
Robinson, Robert E., 3,578,716.
- National Gypsum Company: See—
Lapp, Leon R.; and Burkard, Edward A., 3,578,517.
- Nelson, Grant L.: See—
Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., 3,578,377.
- Nemoto, Hidetaro: See—
Soeda, Shigeki; Nemoto, Hidetaro; and Kaneko, Yasuhiro, 3,578,062.
- Nemoto, Mamoru; and Tani, Seiji, to Hitachi, Ltd. Swash plate compressor. 3,577,891, Cl. 92-72.
- Neplaz, Guy Marcel: See—
Marchetti, Charles Joseph; and Neplaz, Guy Marcel, 3,578,100.
- Neuville, Bernard: See—
Ledoux, Claude; and Neuville, Bernard, 3,577,841.
- Newallis, Peter E.: See—
Largman, Theodore; and Newallis, Peter E., 3,578,711.
- Newman, James W.: See—
Gordon, William F.; and Newman, James W., 3,578,255.
- Nicholls, Ernest G., to Dunlop Company Limited, The. Arrangement for consolidating tire building components. 3,578,530, Cl. 156-410.
- Nicklaus, Gregory L.: See—
Myer, Caleb H.; and Nicklaus, Gregory L., 3,578,140.
- Nielsen, James C.; and Turner, John J., to General Electric Company. Precision alignment fixture. 3,578,281, Cl. 248-346.
- Niems, Lee H. Apparatus for cooling particles. 3,578,297, Cl. 263-32.
- Nieneker, Darle Lee; and Williams, Leslie Preston, to Jefferson Chemical Company, Inc. Fire-extinguishing composition comprising ethoxylated alkylphenol and ethylene glycol mono lower alkyl ether. 3,578,590, Cl. 252-8.05
- Nippon Carbide Kogyo Kabushiki Kaisha: See—
Tiama, Susumu; and Nakada, Shigeo, 3,578,648.
- Nippon Gakki Seizo Kabushiki Kaisha: See—
Sotome, Hiromi, 3,578,104.
- Nippon Jido Fukurozumei Mfg. Co. Ltd.: See—
Obara, Katsuji, 3,578,041.
- Nippon Kokan Kabushiki Kaisha: See—
Higuchi, Masaaki; Shibuya, Teiji; Onoue, Koichi; and Fujii, Seiji, 3,578,437.
- Soeda, Shigeki; Nemoto, Hidetaro; and Kaneko, Yasuhiro, 3,578,062.
- Nishimura, Yasuo; and Tanaka, Masao, to Fujitsu Limited. Metal film resistor. 3,578,420, Cl. 29-195.
- Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Safronovich, Lev Isaevich; and Kuznetsov, Leonid Georgievich. Device for setting tundish above mould of machine for continuous casting of metal. 3,578,063, Cl. 164-281.
- Nissan Jidsha Kabushiki Kaisha: See—
Nakajima, Yasuo; and Hayashi, Yoshimasa, 3,578,116.
- Nitzsche, Siegfried: See—
Bauer, Ignaz; Riedel, Rudolf; and Nitzsche, Siegfried, 3,578,490.
- Noeroske, Robert L.; and Tobol, Helen K., to Dow Chemical Company, The. 2,6-Dicyanotrichloropyridine seed treatment. 3,578,434, Cl. 71-77.
- Nolken, Ernst: See—
Kuhkamp, Alfred; Fischer, Edgar; and Nolken, Ernst, 3,578,632.
- Nonaka, Katsuhiko: See—
Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishihashi, Hiroaki, 3,578,435.
- Norby, Carl J., to International Business Machines Corporation. Container for a reel. 3,578,156, Cl. 206-52.
- Norco, Inc.: See—
Metz, Joseph R., 3,578,373.
- Nordberg, Martin E.: See—
Hebert, Normand C.; and Nordberg, Martin E., 3,578,579.
- Norlander, Norman E.; and Knowles, Robert A., to Weyerhaeuser Company. Carriage for sawing shake bolts into wedges. 3,578,044, Cl. 143-12.
- Northrop Corporation: See—
Patierno, John W.; White, Vernon L.; Asdurian, Haig; and Grellmann, Hans W., 3,578,265.
- Notbohm, Willard C.; Lamb, Charles A.; and Hanson, J. Leslie, to Black Clawson Company, The. Headbox for twin wire paper making apparatus. 3,578,560, Cl. 162-344.
- Notbohm, Willard C.; and Schaffrath, Paul M., to Black Clawson Company, The. Vertical paper machine wherein stock impinges wire below the breast rolls. 3,578,556, Cl. 162-203.
- Novak, Edward J., to Fastener Corporation. Fastener driving tool with pneumatically clamped nosepiece structure. 3,578,231, Cl. 227-123.
- Nugent, William & Co., Inc.: See—
Cuyler, Kenneth W., 3,578,176.
- Nussdorfer, W. R.; and Farrel, James M., to White Consolidated Industries, Inc. Air guide structure. 3,577,905, Cl. 98-94.
- N.V. Industriële Handelscombinatie: See—
Pot, Hendrik, 3,578,222.
- N.V. Machinefabriek L. te Strake: See—
Vermeulen, Geert J., 3,578,256.
- Nygren, Charles E.: See—
Clack, Willis E.; Kay, Clifford; and Nygren, Charles E., 3,578,167.
- Obara, Katsuji, to Nippon Jido Fukurozumei Mfg. Co. Ltd. Automatic apparatus for packaging powdered material with uniform bag weight and with dust-free operation. 3,578,041, Cl. 141-59.
- Oberle, Theodore L.: See—
Lloyd, Calvin D.; Oberle, Theodore L.; and Satzler, Ronald L., 3,578,232.
- Oberli, Rudolf, to Greiner Electronic AG. Test tube having integral mixing means. 3,578,291, Cl. 259-75.
- Oberli, Rudolf: See—
Greiner, Rudolf; and Oberli, Rudolf, 3,578,212.
- O'Connor, Chadwell. Instrument panhead seal. 3,578,347, Cl. 277-205.
- O'Connor, John J.: See—
Armington, Alton F.; and O'Connor, John J., 3,578,414.
- Oeder, Carl E. Air suspension system. 3,578,355, Cl. 280-124.
- of the heirs: See—
van der Zijden, Antonie Simon Maria; and of the heirs, 3,578,465.
- Ogle, Robert W., to Lyoflo-Stopper Corporation. Lyoflo-stopper. 3,578,195, Cl. 215-47.
- Ohi, Reiichi: See—
Amano, Hiroyuki; Iwano, Haruhiko; Shirasu, Kazuo; and Ohi, Reiichi, 3,578,453.
- Amano, Hiroyuki; Ohi, Reiichi; Iwano, Haruhiko; and Shirasu, Kazuo, 3,578,454.
- Ohlhausen, Howard Gary. Method for rendering substrates water repellent. 3,578,488, Cl. 117-123.
- Ohse, Georg, to Alfred Graf zu Erbach-Furstenau. Extrusion molding of particle board having particular surface characteristic. 3,578,523, Cl. 156-164.
- Oil City Iron Works: See—
Roberts, Dan T., 3,577,849.
- Ojala, William K., to Ford Motor Company. Throttle blade control system for minimizing variations in idling speed. 3,577,962, Cl. 123-103.
- Ojima, Masaki: See—
Narita, Shozo; Ojima, Masaki; and Shiraishi, 3,577,958.
- Olin Corporation: See—
Bishop, John J.; and Jache, Albert W., 3,578,709.
- Bruson, Herman A.; and Plant, Howard L., 3,578,673.
- Bruson, Herman A.; and Plant, Howard L., 3,578,710.
- Scott, John A., 3,578,713.

Winter, Joseph, 3,578,075.
 Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,393.
 Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,400.
 Olivetti, Ing. C., & C., S.p.A.: See—
 Cremasco, Venanzio Micheletti; and Roano, Domenico, 3,578,132.
 Salto, Rinaldo, 3,578,137.
 Olsen, Carl J. Hanger for outdoor light sockets. 3,578,282, Cl. 248-214.
 Olson, David L.: See—
 Uhen, James R.; and Olson, David L., 3,578,059.
 Olson, John L. Drill holder device. 3,578,153, Cl. 206-17.
 Omori, Hayao: See—
 Takano, Masatoshi; Arita, Hiroshi; and Omori, Hayao, 3,577,909.
 Ono, Hisatake; and Osada, Chiaki, to Fuji Photo Film Co., Ltd. Photochromic compound. 3,578,680, Cl. 260-326.11.
 Ono, Hisatake; Osada, Tiaki; and Kosuge, Kuniko, to Fuji Shashin Film Kabushiki Kaisha. Photochromic compound. 3,578,602, Cl. 252-300.
 Onoda, Yoshimitsu; and Kiwaki, Hisakatsu, to Hitachi, Ltd. Electric vehicle driving and controlling apparatus. 3,577,929, Cl. 104-148.
 Onoue, Koichi: See—
 Higuchi, Masaaki; Shibuya, Teiji; Onoue, Koichi; and Fujii, Seiji, 3,578,437.
 Orenstein-Koppel Aktiengesellschaft: See—
 Drieschner, Gotthardt, 3,578,188.
 Ormco Corporation: See—
 Miller, Frank R.; and Dillberg, Raymond E., 3,578,424.
 O&S Bearing & Mfg., Co.: See—
 Snidar, Edward A., 3,578,366.
 Osada, Chiaki: See—
 Ono, Hisatake; and Osada, Chiaki, 3,578,680.
 Osada, Tiaki: See—
 Ono, Hisatake; Osada, Tiaki; and Kosuge, Kuniko, 3,578,602.
 Osborn Engineering Corporation: See—
 Osborn, Ralph C., 3,578,277.
 Osborn, Ralph C., to Osborn Engineering Corporation. Locking assembly for electric outboard fishing motors. 3,578,277, Cl. 248-4.
 Oshida, Otto A.; and Gilmore, Jon P., to Grefco, Inc. Silicoalum treatment of perlite fiber insulation board and product thereof. 3,578,555, Cl. 162-164.
 Oswald, Hendrikus J.: See—
 Prevorsek, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hendrikus J.; and Schmitt, George J., 3,578,552.
 Outboard Marine Corporation: See—
 Cavil, David T., 3,577,971.
 Owens, Nevyl G.: See—
 Anderson, Ronald A.; and Owens, Nevyl G., 3,578,083.
 Owens-Corning Fiberglas Corporation: See—
 Philipps, Thomas E.; and Belue, James C., 3,578,426.
 Owens-Illinois, Inc.: See—
 Schaich, Wilbur A., 3,578,184.
 Packo, Joseph J. Method of sealing leaks in vessels and joints. 3,578,479, Cl. 117-2.
 Padberg, Gunter: See—
 Konig, Joachim; and Padberg, Gunter, 3,578,655.
 Paden, Ray Wellington. Storage rack for leveling jacks. 3,578,177, Cl. 211-49.
 Page, Arthur P.: See—
 Sirois, Louis L.; Winer, Albert A.; Alexander, Gordon E.; and Page, Arthur P., 3,578,408.
 Palm, Bert E.; and Warner, William Wayne, to Diamond Shamrock Corporation. Conditioning ferrous metal substrates. 3,578,509, Cl. 148-6.16.
 Palm, Bert E.; and Warner, William Wayne, to Diamond Shamrock Corporation. Conditioning ferrous metal substrates. 3,578,510, Cl. 148-6.16.
 Palmer, Charles G. Discontinuity sensor. 3,577,955, Cl. 116-114.
 Palmer, Jay W., to Morton International, Inc. Preparation of aqueous manganous chloride solutions. 3,578,394, Cl. 23-87.
 Palmer, Leon E.: See—
 Heidt, William A.; Palmer, Leon E.; and Schaefer, John O., 3,578,131.
 Pammer, Erich; and Kirschner, Helmuth, to Siemens Aktiengesellschaft. Method of precipitating insulating protective layers comprised of inorganic material upon the surfaces of semiconductor wafers. 3,578,495, Cl. 117-201.
 Pan American Sulphur Company: See—
 Dale, John M., 3,578,417.
 Paper Converting Machine Company: See—
 Small, Rudolph E.; and Bradley, John J., 3,578,155.
 Parker, Konrad, to Addressograph-Multigraph Corporation. Developing compositions for diazotype materials. 3,578,452, Cl. 96-49.
 Parker, Orval. Successive wire twister. 3,578,035, Cl. 140-102.5.
 Parker, Ralph L., to Litton Business Systems, Inc. Fine adjustment means for incremental feed mechanisms. 3,578,134, Cl. 197-114.
 Parker-Hannifin Corporation: See—
 Jelinek, Jerry G., 3,578,346.
 Patierno, John W.; White, Vernon L.; Asduran, Haig; and Grellmann, Hans W., to Northrop Corporation. Aerodynamic structures. 3,578,265, Cl. 244-42.

Paulus, Peter V.; and Green, Harry W., to Standard Products Company, The. Septic tank for waste disposal system. 3,578,166, Cl. 210-110.
 Pavlenko, Nikolai Semenovich: See—
 Cherny, Anatoly Alexeevich; Vladimir Alexandrovich; Lev Mikhailovich; Kurbatsky, Ivan Lukich; Sosnovsky, Efim Davidovich; and Pavlenko, Nikolai Semenovich, 3,578,302.
 Pearce, Ronald A., to Coors Porcelain Company. Article handling machine unloading mechanism. 3,578,139, Cl. 198-28.
 Pearlman, Martin B. Treatment of ferrous metal surfaces to prevent corrosion. 3,578,508, Cl. 148-6.14.
 Pearlstein, Fred; and Weightman, Robert F., to United States of America, Army. Solution for depositing an electroless cobalt alloy. 3,578,468, Cl. 106-1.
 Pearson, Chester T. Automatic throttle control for auxiliary motors driving drawbar-towed vehicles. 3,578,096, Cl. 180-14.
 Pearson, William S. Prevention of arching compaction of discrete material in gravity feed hoppers. 3,578,216, Cl. 222-195.
 Pease, Roy T., Jr.: See—
 Alvey, George H.; McDaniels, Paul E.; and Pease, Roy T., Jr., 3,578,324.
 Peck, Arthur C.; and Usko, Alexander J., to Monsanto Company. Apparatus for curing labels. 3,578,536, Cl. 156-497.
 Penick & Ford, Limited: See—
 Hjermstad, Erling T., 3,578,497.
 Pennwalt Corporation: See—
 Taylor, Norris O.; Uhler, Wilmer P.; Gardella, John M.; and Cahlik, Jim C., 3,578,379.
 Perdue, A. W., & Son, Inc.: See—
 Larger, Nelson N., 3,578,183.
 Perflex Plastics, Inc.: See—
 Eliot, Sol S., 3,578,360.
 Perkel, Robert J. Dyestuffs for ornamental coatings or the like. 3,578,476, Cl. 106-193.
 Perkins, William E.; and Schlack, Allen F., to United States of America, Army. Percussion-electric primer and radiation shield. 3,577,923, Cl. 102-46.
 Perlman, Sol J., to Vac Pac Manufacturing Company, Inc. Bag structure. 3,578,239, Cl. 229-53.
 Perrin, Badger, to United-Carr Incorporated. Three-piece tack button. 3,577,846, Cl. 24-95.
 Peters, Robert H.: See—
 Cholmar, Sidney; and Peters, Robert H., 3,578,735.
 Peterson, Aivars V. Replaceable tread on an expanding diameter car carcass tire. 3,578,052, Cl. 152-187.
 Peterson, Dean M.; Pickering, Charles E.; and Mindler, Fredric A., to Eastman Kodak Company. Film metering and double exposure prevention mechanism for photographic camera. 3,577,900, Cl. 95-31.
 Peterson, Louis H.: See—
 Hoff, Dale R.; and Peterson, Louis H., 3,578,675.
 Petro, Victor P.; Cable, James R.; and Wainer, Eugene, to Horizons Incorporated. Non silver photosensitive composition sensitized with rubrene. 3,578,456, Cl. 96-90.
 Petro, Victor P.; Lewis, James M.; and Fox, Robert D., to Horizons Incorporated. Increased speed in R-C-X₂ color former light sensitive system by alkali treatment. 3,578,455, Cl. 96-90.
 Petrolite Corporation: See—
 Mange, Franklin E.; Buriks, Rudolf S.; and Quinlan, Patrick M., 3,578,731.
 Pfarrwallner, Erwin, to Sulzer Brothers Limited. Loom having a jacquard mechanism and a weft changing mechanism. 3,578,032, Cl. 139-126.
 Philipps, Thomas E.; and Belue, James C., to Owens-Corning Fiberglas Corporation. Method for making glass fiber strand for resin reinforcement. 3,578,426, Cl. 65-3.
 Phillips Petroleum Company: See—
 Mihm, Clifford H., deceased; and Mihm, Adeline M.; administrator, 3,578,681.
 Moberly, Charles W.; and Kahle, Gerald R., 3,578,646.
 Mueller, Francis X., Jr.; and Brown, James D., 3,578,642.
 Thompson, Stanley P.; and Shofer, Don L., 3,577,915.
 Thorsrud, Agmund K., 3,578,544.
 Wells, Johnny L., 3,577,885.
 Phillips, Robert Arthur: See—
 Hurlbut, Myron Robert; Phillips, Robert Arthur; and Tupper, Leeland Chester, 3,578,298.
 Pickell, Calvin D.; and Klevens, Maury, to Marksman Manufacturing Corporation. Target providing an indicating signal upon impact by a projectile of a particular portion of the target. 3,578,327, Cl. 273-102.2.
 Pickering, Charles E.: See—
 Peterson, Dean M.; Pickering, Charles E.; and Mindler, Fredric A., 3,577,900.
 Pickering, Norman C.; and Roberts, Joseph P., to ROBINTECH Incorporated. Vibration-isolated self-leveling platform and method. 3,578,278, Cl. 248-20.
 Pilkuhn, Manfred H.; and Lorenz, Max R., to United States of America, Navy. Method of fabricating solution grown epitaxial PN-junctions in gallium phosphide. 3,578,513, Cl. 148-171.
 Pinckard, Charles P. Tray and conveyor assembly. 3,578,148, Cl. 198-181.
 Pinkham, Jesse R., to Reynolds, R. J., Tobacco Company. Impact method. 3,577,998, Cl. 131-96.

Pinkham, Jesse R., to Reynolds, R. J., Tobacco Company. Impact apparatus and method. 3,577,999, Cl. 131-96.
 Piper, Hugh V.: See—
 Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., 3,578,377.
 Pirovano, Camillo; and Radaelli, Costante. Conveying member for incoherent or powdery materials, especially food for poultry or like animals, and device for the manufacture thereof. 3,578,150, Cl. 198-213.
 Pitroff-Szabo, Thomas B. Aerosol dispensing container with reserve propellant chambers. 3,578,210, Cl. 222-52.
 Plant, Howard L.: See—
 Bruson, Herman A.; and Plant, Howard L., 3,578,673.
 Bruson, Herman A.; and Plant, Howard L., 3,578,710.
 Plessey Company Limited, The: See—
 Fortune, Henry James, 3,578,340.
 Pneumatiques, Caoutchouc Manufacture et Plastiques Kleber-Colombes: See—
 Ducrocq, Roger Eugene, 3,577,879.
 Pohland, Dieter: See—
 Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfel, Manfred; and Sattler, Karl, 3,578,566.
 Polaroid Corporation: See—
 Bloom, Stanley M.; Simon, Myron S.; and Ward, Jeanne A., 3,578,448.
 Bloom, Stanley M., 3,578,449.
 Land, Edwin, 3,578,540.
 Miller, Edgar W.; and Smith, Harry A., 3,578,450.
 Simon, Myron S., 3,578,447.
 Taylor, Lloyd D., 3,578,458.
 Polcer, John: See—
 Barratt, Robert Owen; and Polcer, John, 3,577,959.
 Pontelandolfo, Joseph John, to American Cyanamid Company. Imidazoline quaternary salts as soil retardants. 3,578,592, Cl. 252-88.
 Pope, Bill J. High temperature reactor. 3,578,416, Cl. 23-277.
 Postal, Robert H., to American Cyanamid Company. Typewriter printing means for symbols in coded inks. 3,578,136, Cl. 197-151.
 Pot, Hendrik, to N.V. Industriele Handelscombinatie. Hopper with bottom door actuator. 3,578,222, Cl. 222-504.
 Poweray Infrared Corporation: See—
 Heller, Anton H., 3,577,976.
 PPG Industries, Inc.: See—
 Drummond, Warren W., 3,577,872.
 Jansson, Robert A.; and Mickelic, Raymond J., 3,578,427.
 Prucnal, Paul J., 3,578,620.
 Precision Sampling Corporation: See—
 Harris, Rano J., Sr., 3,577,850.
 Preuss, John K. Grease catching device. 3,577,906, Cl. 99-234.
 Prevorsek, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hendrikus J.; and Schmitt, George J., to Allied Chemical Corporation. Thermosetting laminates. 3,578,552, Cl. 161-214.
 Priestley, Robert J., to Dorr-Oliver Incorporated. Fluidized bed treatment of spent pulp digestion liquor. 3,578,396, Cl. 23-48.
 Prince, Martin: See—
 Blanck, Joachim Hillard; and Prince, Martin, 3,578,696.
 Procter & Gamble Company, The: See—
 Snoddy, Arnon O.; Diehl, Francis L.; and Drew, Howard F., 3,578,601.
 Produits Chimiques Pechiney Saint-Gobain: See—
 Badgueranahian, Leon; and Kemp, Thomas, 3,578,649.
 Mainet, Maurice, 3,578,202.
 Mainet, Maurice, 3,578,203.
 Produits Chimiques Pechiney-Saint-Gobain: See—
 Ledoux, Claude; and Neuville, Bernard, 3,577,841.
 Prosser, Kenneth Wheatley; and Wallace, John Vipond, to English Electric Company Limited, The. Laminated indicator plaques. 3,578,538, Cl. 161-6.
 Prucnal, Paul J., to PPG Industries, Inc. Color stabilized unsaturated interpolymers. 3,578,620, Cl. 260-23.7.
 Puar, Mohindar S.: See—
 Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,393.
 Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., 3,578,400.
 Pulcrano, Frank C.; and Rollins, Dallas W., to ACF Industries Incorporated. Exterior cover enclosing hopper gate and actuating mechanism. 3,577,932, Cl. 105-253.
 Pullman Incorporated: See—
 Ferris, Ray L.; Shaver, William R.; and Manos, William P., 3,577,933.
 Glasmeier, John J., 3,578,374.
 Gutridge, Jack E.; Johnson, Kent N.; and Spence, John H., 3,577,934.
 Pulsation Controls Corporation: See—
 Everett, Wilhelm S.; and Floyd, James K., 3,578,107.
 Punzak, John M., to Monsanto Company. Conveying articles. 3,578,144, Cl. 198-41.
 Quinlan, Patrick M.: See—
 Mange, Franklin E.; Buriks, Rudolf S.; and Quinlan, Patrick M., 3,578,731.
 Raath, Roedolf Johannes. Plant harvesting machine. 3,578,088, Cl. 171-62.
 Racusin, Paul: See—
 Lock, Coy B., 3,578,307.
 Radaelli, Costante: See—
 Pirovano, Camillo; and Radaelli, Costante, 3,578,150.
 Raginsky, Leonid Solomonovich: See—
 Karpacheva, Susanna Mikhailovna; Raginsky, Leonid Solomonovich; Muratov, Valerian Matveevich; Ivanov, Vladimir Dmitrievich; and Baulin, Jury Nikolaevich, 3,578,174.
 Ralston Purina Company, The: See—
 Corbin, James E., 3,578,459.
 Randall, Milton D.: See—
 Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and McCarron, John K., 3,578,233.
 Rapid-American Corporation: See—
 Schneider, Marvin, 3,578,115.
 Rast, Gustav E.; and Steiner, Russell L., to Allied Chemical Corporation. Red phenylazo naphthol dyestuff. 3,578,652, Cl. 260-151.
 Rath, Harry B., to Mack Trucks, Inc. Automatic actuation of air cleaner selector valve. 3,578,017, Cl. 137-344.
 Rauch, August H., to U.S. Plywood-Champion Papers Inc. Veneer defect filling method. 3,578,522, Cl. 156-94.
 Ravreby, Fred A.: See—
 Diamond, Joseph; Gershman, Melvin Y.; and Ravreby, Fred A., 3,578,023.
 Read, Stanley M.: See—
 Bromley, Le Roy A.; and Read, Stanley M., 3,578,004.
 Recherches et Applications des Plastiques Dans l'Industrie et Le Bâtiment, S.A.: See—
 Carlini, Dominique, 3,578,531.
 Reeder, James A., to British Columbia Research Council. Process of preparing metal chelates of β -ketoesters. 3,578,619, Cl. 260-22.
 Regent, Leslie K., to Surgical Developments Limited. Hernial support device. 3,577,986, Cl. 128-96.
 Regents of the University of California, The: See—
 Bromley, Le Roy A.; and Read, Stanley M., 3,578,004.
 Regie Nationale des Usines Renault: See—
 Auriol, Jean G. M., 3,578,119.
 Magnier, Roger, 3,578,122.
 Reinhart, Richard D.; and Straughn, Robert O., to General Mills, Inc. Extrusion apparatus. 3,577,935, Cl. 107-14.
 Reinke, Richard F. Fertilizer trailer. 3,578,348, Cl. 280-5.
 Republic Corporation: See—
 Rooklyn, Jack, 3,577,930.
 Research Corporation: See—
 Schmidt, Max, 3,578,718.
 Rex Chainbelt Inc.: See—
 Yost, Kermit D., 3,578,344.
 Reynolds, Donald F. Frame hitch and step bumper. 3,578,358, Cl. 280-500.
 Reynolds, R. J., Tobacco Company: See—
 Pinkham, Jesse R., 3,577,998.
 Pinkham, Jesse R., 3,577,999.
 Sherrill, Joseph H., 3,577,996.
 White, Jackie L., 3,577,995.
 Reyter, Jean Pierre: See—
 Boucraut, Michel; Toth, Imre; and Reyter, Jean Pierre, 3,578,296.
 Ricard, Rene; and Margarit Taya, Miguel. Antilipemic sulphated polysaccharide. 3,578,657, Cl. 260-234.
 Richardson, John Francis: See—
 Muirhead, Duncan Ronald; and Richardson, John Francis, 3,577,938.
 Richter, Johan C. F. C., to Aktiebolaget Kamyr. Method for common digestion of two differently pre-treated fractions of wood chips. 3,578,554, Cl. 162-19.
 Rickey, Donald H. Arrowhead with pivoted blades. 3,578,328, Cl. 273-106.5.
 Riedle, Rudolf: See—
 Bauer, Ignaz; Riedle, Rudolf; and Nitzsche, Siegfried, 3,578,490.
 Rieke, James K.; and Justin, Frank H., to Dow Chemical Company, The. Glass filled random copolymers of an olefin and an unsaturated acid. 3,578,630, Cl. 260-41.
 Rieter Machine Works, Ltd.: See—
 Eichenberger, Hansulrich; and Schwengeler, Peter, 3,577,845.
 Rigdon, Orville W.; Edwards, Robert S.; and Holst, Edward H., to Texaco Inc. Photoreduction of normal paraffins. 3,578,575, Cl. 204-162.
 Riggs, Olen L., Jr., to Continental Oil Company. Method for inhibiting the foaming tendencies of phosphoric acid. 3,578,402, Cl. 23-165.
 Riggs, Olen L., Jr.; and Barnett, David W., to Continental Oil Company. Corrosion inhibited phosphoric acid composition. 3,578,607, Cl. 252-389.
 Ringpfel, Manfred: See—
 Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfel, Manfred; and Sattler, Karl, 3,578,566.
 Rishovd, Erik, to A/S Westad Armaturfabrik. Butterfly valve with a sealing ring having a double shallow-tail shape in cross section. 3,578,288, Cl. 251-306.
 Ritsko, Joseph E., to Sylvania Electric Products, Inc. Molybdenum purification process. 3,578,392, Cl. 23-22.
 Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Garnder, Gerald; Harris, Leonard; and Moore, Arnett A., to United States of America, Air Force. Cardiovascular conditioning device and portable respirator. 3,577,977, Cl. 128-1.
 Rivin, Donald: See—
 Hardy, John F.; Rivin, Donald; and Aron, Jerome, 3,578,635.
 Ro-Search, Incorporated: See—
 Kaufman, Cut E., 3,577,858.

Roano, Domenico: *See—*
Cremasco, Venanzio Micheletti; and Roano, Domenico, 3,578,132.
Roberts, Charles Grady: *See—*
Borrello, Sebastian Ronald; and Roberts, Charles Grady, 3,578,515.
Roberts, Dan T., to Oil City Iron Works. Method and materials for welding. 3,577,849, Cl. 29-495.
Roberts, Fred T., & Company: *See—*
Roberts, Robert E., 3,578,028.
Roberts, Harold D. Dental implant and method of mounting the same. 3,577,853, Cl. 32-10.
Roberts, Joseph P.: *See—*
Pickering, Norman C.; and Roberts, Joseph P., 3,578,278.
Roberts, Robert E., to Roberts, Fred T., & Company. Reinforced hose and method of making the same. 3,578,028, Cl. 138-123.
Robinson, Robert E., to National Distillers and Chemical Corporation. Process for aromatic substitution. 3,578,716, Cl. 260-650.
Robinson, Robert J.: *See—*
Chiang, Kang-Rong; Kun, Zoltan K.; and Robinson, Robert J., 3,578,507.
ROBINTeCH Incorporated: *See—*
Pickering, Norman C.; and Roberts, Joseph P., 3,578,278.
Roche, Jerry E.; and McDavid, Larry S., to Beckman Instruments, Inc. Valve assembly. 3,578,020, Cl. 137-512.
Rockwell Manufacturing Company: *See—*
Fowler, John H., 3,578,076.
Rogers, Edward S.; Hardin, Richard V., II; Harrison, Benjamin C.; and Sanford, Robert A., to Atlantic Richfield Company. Process for preparing a fuel cell electrode. 3,578,505, Cl. 136-120.
Rohm & Haas G.m.b.H.: *See—*
Gruber, Wilhelm; and Kleine-Doecke, Wolfgang, 3,578,663.
Rohr Corporation: *See—*
Ellis, Peter H., 3,578,106.
Rohrer, Clarence E.: *See—*
Ehrhart, Wendell A.; and Rohrer, Clarence E., 3,578,728.
Rollins, Dallas W.: *See—*
Pulcrano, Frank C.; and Rollins, Dallas W., 3,577,932.
Ronge, Heinrich. Screen printing machine employing a reciprocating printing and feed plate. 3,577,914, Cl. 101-124.
Rooklyn, Jack, to Republic Corporation. Monorail system. 3,577,930, Cl. 104-173.
Rosborg, Daniel J.: *See—*
Frechette, Kenneth R.; and Rosborg, Daniel J., 3,578,128.
Rose, Downs & Thompson Limited: *See—*
Muirhead, Duncan Ronald; and Richardson, John Francis, 3,577,938.
Muirhead, Duncan Ronald, 3,577,939.
Rosemont Engineering Company: *See—*
Werner, Frank D., 3,577,883.
Ross, Frederick W.; Van Horn Serrell, Peter; and Shatto, Howard L., to Shell Oil Company. Seismic generator. 3,578,102, Cl. 181-0-5.
Rossa, Gerd, to Shell Oil Company. Process for curing polycyepoxides with polycarboxylic acid anhydrides in presence of alkaline metal salts or carboxylic acids. 3,578,633, Cl. 260-47.
Rossitto, Conrad: *See—*
Battersby, William R.; Follett, Robert P.; MacGrandie, Timothy D.; Rossitto, Conrad; and Taylor, Paul, 3,578,727.
Roth, David W. H., Jr.: *See—*
Twilley, Ian C.; Coli, Guido John, Jr.; and Roth, David W. H., Jr., 3,578,640.
Rowan, Henry A.; and Shiffner, Donald H., to Economics Laboratory, Inc. Apparatus and method for processing work pieces. 3,578,002, Cl. 134-25.
Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfel, Manfred; and Sattler, Karl, to Deutsche Akademie der Wissenschaften Zu Berlin. Process of treating oil containing fermentation discharges. 3,578,566, Cl. 195-82.
Ruhchemie AG: *See—*
Falbe, Jürgen; and Hahn, Heinz-Dieter, 3,578,423.
Russell, Joseph L., to Halcon International, Inc. Process for preparing aniline from phenol. 3,578,714, Cl. 260-581.
Rusz, Tibor: *See—*
Levy, Donald; and Rusz, Tibor, 3,577,984.
S.A. des Etablissements Roure-Bertrand fils & Justin Dupont: *See—*
Corbier, Bernard Pierre; and Teisseire, Paul Jose, 3,578,715.
Sacks, Reuben R.: *See—*
Carson, Richard M.; and Sacks, Reuben R., 3,578,545.
Safronovich, Lev Isaevich: *See—*
Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Safronovich, Lev Isaevich; and Kuznetsov, Leonid Georgievich, 3,578,063.
Said Merry assor, to Brunswick Corporation: *See—*
Merry, Jack D.; and Deuschle, Fritz, 3,577,992.
Sakata, Rikita; Masuda, Kohei; Uchigaki, Taku; and Arai, Masakazu, to Mitsubishi Petrochemical Industry Co., Ltd. Method of producing a laminated article employing extrusion and an inert gas. 3,578,527, Cl. 156-244.
Salerno, Paul G.; and Wilson, Steven J., to Vapor Corporation. Butterfly valve. 3,578,287, Cl. 251-306.
Salto, Rinaldo, to Olivetti, Ing., C., & C., S.p.A. Device for guiding a ribbon in a typewriter or similar machine. 3,578,137, Cl. 197-170.
Salton, Inc.: *See—*
Burg, Frederick J., 3,577,908.

Sanders, Robert N., to Ethyl Corporation. High energy fuel comprising beryllium hydride and pentaborane. 3,578,516, Cl. 149-22.
Sandig, Henry. Animal feeder having adjustable timing means. 3,577,957, Cl. 119-51.11.
Sandoz-Wander, Inc.: *See—*
Frey, Albert J.; and Buzzolini, Mario G., 3,578,712.
Manning, Robert E., 3,578,666.
Sanford, Robert A.: *See—*
Rogers, Edward S.; Hardin, Richard V., II; Harrison, Benjamin C.; and Sanford, Robert A., 3,578,505.
Santi, John D., to Briggs & Stratton Corporation. Automatic choke actuator for small engines. 3,578,293, Cl. 261-64.
Sanukiya, Toshio: *See—*
Nakai, Miyoji; Nakajima, Akira; Watanabe, Makoto; and Sanukiya, Toshio, 3,577,842.
Sato, Katsuya: *See—*
Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishibashi, Hiroaki, 3,578,435.
Satterthwaite, James Glenn; and Macy, James B., Jr. Shaft seal. 3,578,342, Cl. 277-9.
Sattler, Karl: *See—*
Rudel, Manfred; Gabert, Anton; Behrens, Ulrich; Pohland, Dieter; Ringpfel, Manfred; and Sattler, Karl, 3,578,566.
Satzler, Ronald L.: *See—*
Lloyd, Calvin D.; Oberle, Theodore L.; and Satzler, Ronald L., 3,578,232.
Schaefer, John O.: *See—*
Heidt, William A.; Palmer, Leon E.; and Schaefer, John O., 3,578,131.
Schaefer, John O., to International Business Machines Corporation. Non-repeat mechanism for keyboard. 3,578,133, Cl. 197-98.
Schaffrath, Paul M.: *See—*
Nothohm, Willard C.; and Schaffrath, Paul M., 3,578,556.
Schaich, Wilbur A., to Owens-Illinois, Inc. Article handling method and apparatus. 3,578,184, Cl. 214-38.
Scheldorf, Owen H., to General Electric Company. Resilient mounting means. 3,578,279, Cl. 248-20.
Schenectady Chemicals, Inc.: *See—*
Sheffer, Howard E., 3,578,639.
Schering AG: *See—*
Burba, Christian; Drawert, Manfred; and Griebisch, Eugen, 3,578,612.
Schilling, William F.: *See—*
Grant, Nicholas J.; and Schilling, William F., 3,578,443.
Schilling, Joseph F.; and Moser, Thomas B., to Weyerhaeuser Company. Container which completely encloses articles. 3,578,238, Cl. 229-40.
Schlack, Allen F.: *See—*
Perkins, William E.; and Schlack, Allen F., 3,577,923.
Schlight, Raymond C.; and Godfrey, Arthur W., to Texaco Inc. Zinc di-3-alkylphenoxy-2, 2-dialkylpropyl dithiophosphate and automatic transmission fluid containing same. 3,578,595, Cl. 252-75.
Schlosberg, Seymour, to Gelb, R., & Sons, Inc. Self-cooling mechanical seal lubricator. 3,578,067, Cl. 165-39.
Schlumberger Technology Corporation: *See—*
Alexander, Carl V., 3,578,079.
Anderson, Ronald A.; and Owens, Nevel G., 3,578,083.
Schmedtkord, Ulrich: *See—*
Willebacher, Erich M.; Schmedtkord, Ulrich; and Gabler, Dieter K., 3,577,944.
Schmidt, Erwin: *See—*
Zelnick, Charles; and Schmidt, Erwin, 3,578,259.
Schmidt-Hatting, Wolfgang; and Huwyler, Sebastian, to Swiss Aluminium Ltd. Electrolytic cell apparatus. 3,578,580, Cl. 204-243.
Schmidt, Louis A., to United States of America, Navy. Housing for ballistic telemetering sonde. 3,577,925, Cl. 102-70.2.
Schmidt, Max, to Research Corporation, mesne. Process for the preparation of isomeric mixtures di-thio-benzene composed essentially of the para isomer. 3,578,718, Cl. 260-609.
Schmitt, George J.: *See—*
Prevorsek, Dusan C.; Li, Hsin L.; Koch, Paul J.; Oswald, Hendrikus J.; and Schmitt, George J., 3,578,552.
Schneider, Abraham: *See—*
Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,578,725.
Schneider, Marvin, to Rapid-American Corporation, mesne. Utility bag. 3,578,115, Cl. 190-48.
Schnettler, Richard A.; and Suh, John T., to Colgate Palmolive Company. 1-Aminoalkylamino-benzo[b]quinolizines. 3,578,668, Cl. 260-288.
Schocher, Arno Johannes; Furst, Andor; Els, Hans; Becher, Elisabeth; and Gross, Gisela, to Hoffmann-La Roche Inc. Process for the manufacture of steroids of the androstane series. 3,578,565, Cl. 195-51.
Schoenbrunn, Erwin F.; and Durell, Edward H., to Escambia Chemical Corporation. Process for producing methyl formate from alkali or alkaline earth formate. 3,578,703, Cl. 260-488.
Schoot, Cornelis Johannes: *See—*
Houtman, Harke Jan; Schoot, Cornelis Johannes; Boven, Jan; and van Beek, Leendert Klaas Hellinga, 3,578,457.
Schoppe, Fritz, to Aqua-Chem, Inc. Incinerator. 3,577,941, Cl. 110-14.
Schott, Lawrence A. Vehicle suspension. 3,578,354, Cl. 280-96.2.
Schroeder, Stella Mae. Concealed purse: hide-a-purse. 3,578,225, Cl. 224-5.

Schueemann, Wilfred C., to Hercules Incorporated. Variable volume safe and arm mechanism. 3,577,926, Cl. 102-76.
Schuler, Jacob Pieter, to Handelsmaatschappij Othene N.V. Suction cup structure. 3,578,372, Cl. 294-64.
Schulz, Csarl W.: *See—*
Smith, James E.; and Schulz, Csarl W., 3,578,359.
Schuster, Donald H.; and Vaught, Russ S., to Iowa State University Research Foundation. Driver trainer simulator head unit. 3,577,857, Cl. 35-11.
Schuykill Chemical Company: *See—*
Mecca, Sebastian B., 3,578,656.
Schwarzkopf, Hans, Firma: *See—*
Lukesch, Heinz; Krakowsky, Hans; and Heeb, Dieter, 3,578,221.
Schweblen, Robert M.: *See—*
Thevignot, Max; and Schweblen, Robert M., 3,578,289.
Schweigert, Friedrich; and Bertholdt, Horst, to Siemens Aktiengesellschaft. Process of finishing parts of zirconium alloys such as for use with nuclear reactor plants. 3,578,573, Cl. 204-140.5.
Schwengeler, Peter: *See—*
Eichenberger, Hansulrich; and Schwengeler, Peter, 3,577,845.
SCM Corporation: *See—*
Gilchrist, Allan E., 3,578,577.
Heine, Wolfgang Fred; and Vought, Kenneth D., 3,578,258.
Scott, John A., to Olin Corporation. Process for preparing toluidines. 3,578,713, Cl. 260-580.
Scott Paper Company: *See—*
Doggett, Towers, 3,578,451.
Scott Paper Company, The: *See—*
Smith, Johanna Wilhelmina v. o., 3,578,493.
Scovill Manufacturing Company: *See—*
Green, Derek Bernard; and Kaye, Gordon Edwin, 3,578,220.
Scranton, Ronald A. Component part inserter for circuit board. 3,577,847, Cl. 29-203.
Seagraves, David. Step for mobile homes and the like. 3,578,110, Cl. 182-129.
Seiler, Heinz: *See—*
Hudd, Richard N.; and Seiler, Heinz, 3,578,469.
Seimens Aktiengesellschaft: *See—*
Schweigert, Friedrich; and Bertholdt, Horst, 3,578,573.
Seiter, George M.: *See—*
Hoerner, Alfred J.; and Seiter, George M., 3,578,550.
Sekse, Torkjell: *See—*
Cogar, George R.; Sekse, Torkjell; Banziger, Walter; Ming, Joseph W.; and Horvath, Laszlo, 3,578,257.
Servadio, Robert. Automatic safety seat clamp. 3,578,382, Cl. 297-390.
Shafer, James A., to Midland Ross Corporation. Dampened railway car truck. 3,577,931, Cl. 105-197.
Shatto, Howard L.: *See—*
Ross, Frederick W.; Van Horn Serrell, Peter; and Shatto, Howard L., 3,578,102.
Shaver, William R.: *See—*
Ferris, Ray L.; Shaver, William R.; and Manos, William P., 3,577,933.
Shaw, Wilfrid G.: *See—*
Milberger, Ernest C.; and Shaw, Wilfrid G., 3,578,695.
Sheehan, Robert T. Filled bag shifting device with bag turner. 3,578,141, Cl. 198-33.
Sheffer, Howard E., to Schenectady Chemicals, Inc. Polyamide-imide-ureas and method of preparation. 3,578,639, Cl. 260-77.5.
Shell Oil Company: *See—*
Closmann, Philip J., 3,578,080.
Husing, Walter H., 3,578,135.
Klootwijk, Arie; Bergwerf, Willem; and Wager, Willem M., 3,578,700.
Meister, Robert P.; Glasgow, James S.; Hackman, Donald J.; Randall, Milton D.; and Mc Carron, John K., 3,578,233.
Moore, Robert J.; and Allen, Roy A., 3,578,615.
Ross, Frederick W.; Van Horn Serrell, Peter; and Shatto, Howard L., 3,578,102.
Rossa, Gerd, 3,578,633.
Sherrill, Joseph H., to Reynolds, R. J., Tobacco Company. Tobacco smoke filter. 3,577,996, Cl. 131-10.5.
Sherwin-Williams Company, The: *See—*
Charvat, Vernon K.; and Jarvi, Robert E., 3,577,839.
Shibuya, Teiji: *See—*
Higuchi, Masaaki; Shibuya, Teiji; Onoue, Koichi; and Fujii, Seiji, 3,578,437.
Shields, Robert Loren: *See—*
Hasselbring, Robert Joel; and Shields, Robert Loren, 3,577,940.
Shiffner, Donald H.: *See—*
Rowan, Henry A.; and Shiffner, Donald H., 3,578,002.
Shillander, Harold E., to General Oil Tools, Inc. Earth borehole tool. 3,578,078, Cl. 166-152.
Shiraishi: *See—*
Narita, Shozo; Ojima, Masaki; and Shiraishi, 3,577,958.
Shirasu, Kazuo: *See—*
Amano, Hiroyuki; Iwano, Haruhiko; Shirasu, Kazuo; and Ohi, Reiichi, 3,578,453.
Amano, Hiroyuki; Ohi, Reiichi; Iwano, Haruhiko; and Shirasu, Kazuo, 3,578,454.
Shofer, Don L.: *See—*
Thompson, Stanley P.; and Shofer, Don L., 3,577,915.
Siemens Aktiengesellschaft: *See—*
Pammer, Erich; and Kirschner, Helmuth, 3,578,495.

Ziegler, Gunther; and Wirth, Barbara, 3,578,496.
Sier-Bath Gear Co., Inc.: *See—*
De Rucker, Donald E.; and Vaccaro, Andrew J., 3,578,363.
Silver, Julius L., to Union Carbide Corporation. Method of making positive-working lithographic plates by electrostatic image. 3,578,444, Cl. 96-1.
Silver Knit Hosiery Mills, Inc.: *See—*
Hulin, Dalton O., 3,577,942.
Silverman, Herbert P.; and Giarrusso, Gino A., to TRW Inc. Sensors unaffected by humidity changes to detect toxic oxidizing vapors. 3,578,409, Cl. 23-254.
Simon, Myron S.: *See—*
Bloom, Stanley M.; Simon, Myron S.; and Ward, Jeanne A., 3,578,448.
Simon, Myron S., to Polaroid Corporation. Dye developer color diffusion transfer processes and elements comprising alpha and gamma hydroxy and gamma amino substituted pyridines. 3,578,447, Cl. 96-3.
Simonaco Limited: *See—*
Gal, Istvan; Hollo, Janos; Toth, Jeno; and Galgoczi, Bela, 3,578,586.
Simplicity Engineering Company: *See—*
Miller, Harold J., 3,578,111.
Singer Company, The: *See—*
Watkins, Charles William, 3,577,943.
Willebacher, Erich M.; Schmedtkord, Ulrich; and Gabler, Dieter K., 3,577,944.
Singer-General Precision, Inc.: *See—*
Le Febvre, Arthur H., 3,578,341.
Weng, Cheng-Kuo, 3,578,012.
Sirois, Louis L.; Winer, Albert A.; Alexander, Gordon E.; and Page, Arthur P., to Canadian Patents and Development Limited. Titrating apparatus. 3,578,408, Cl. 23-253.
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaeвна; Gorbiovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khahtin, Adolf Isacovich. Apparatus for removing toxic substances and excess water from the blood. 3,578,172, Cl. 210-321.
Sjoberg, Ake E., to Aktiebolaget Grythyttans Stalmobler. Corner post support, preferably for load pallets. 3,577,937, Cl. 108-53.
Skrob Inc.: *See—*
Wilcy, John, 3,577,960.
Skully, Charles M.; and LaConte, Richard W. Putter-pool game device. 3,578,321, Cl. 273-2.
Slates, Harry L.: *See—*
Wendler, Norman L.; Slates, Harry L.; and Weber, Stuart, 3,578,705.
Slover, Vasek R.: *See—*
Glenn, Edwin E., Jr.; Slover, Vasek R.; and Strubhar, Malcolm K., 3,578,077.
Small, Rudolph E.; and Bradley, John J., to Paper Converting Machine Company. Disposable product. 3,578,155, Cl. 206-56.
Smeltz, Kenneth C., to Du Pont de Nemours, E. I., and Company. Fluorinated acids and esters. 3,578,701, Cl. 260-485.
Smerak, Louis J.; and Miller, Jason A., to Caravan Products Co., Inc. Yeast leavened bread dough composition and process of manufacture. 3,578,462, Cl. 99-90.
Smetters, Guy Robert: *See—*
London, Melvyn; Smetters, Guy Robert; and Beck, George Eugene, 3,577,920.
Smith, Charles W., Jr., to Autoclave Engineers, Inc. Vent valve assembly. 3,578,201, Cl. 220-44.
Smith, Erwin M. Apparatus for stowing and dropping an anchor. 3,577,951, Cl. 114-210.
Smith, Franklin J.; and Williams, L. G., to Cryodry Corporation. Microwave blanching. 3,578,463, Cl. 99-103.
Smith, Harry A.: *See—*
Miller, Edgar W.; and Smith, Harry A., 3,578,450.
Smith, James E.; and Schulz, Csarl W., to Diamond Power Specialty Corporation. Rigid reflective heat insulation. 3,578,359, Cl. 285-47.
Smith, Johanna Wilhelmina v. o., to Scott Paper Company, The. High solids coating composition. 3,578,493, Cl. 117-155.
Smith, Kenneth C. Air pressure operated clamp. 3,578,306, Cl. 269-24.
Smith, Martin B.; and Adams, Norman G., to Ethyl Corporation. Alkyl-lead antiknock fluids. 3,578,606, Cl. 252-386.
Snapp, Thomas Carter, Jr.; Blood, Alden E.; and Hagemeyer, Hugh John, Jr., to Eastman Kodak Company. Process for producing alpha, beta-unsaturated organic compounds. 3,578,702, Cl. 260-486.
Snidar, Edward A., to O&S Bearing & Mfg., Co. Ball joint self-sealing bearing. 3,578,366, Cl. 287-90.
Snoddy, Arnon O.; Diehl, Francis L.; and Drew, Howard F., to Procter & Gamble Company, The. Detergent compositions containing sulfonic carboxylates. 3,578,601, Cl. 252-135.
Sobrefina SA: *See—*
Ignell, Rolf Lennart, 3,578,524.
Societe Anonyme D.B.A.: *See—*
Brochard, Guy, 3,578,013.
Societe Anonyme dite: L'Oreal: *See—*
Kalopissis, Gregoire; and Vanlerberghe, Guy, 3,578,719.
Societe Anonyme Francaise Du Ferodo: *See—*
Maurice, Jean, 3,578,121.

- Societe De L'Aerotraine: See—
Giraud, Francois Louis, 3,578,099.
- Societe de Recherches en Matiere de Mercromoteurs Electriques Socrem: See—
Stcherbatcheff, Georges; and Houdet, Claude, 3,577,875.
- Societe des Accumulateurs Fixes et de Traction (Societe Anonyme): See—
Chassoux, Rene, 3,578,506.
- Societe d'Etudes et de Developpement des Aeroglisseurs Marins Terrestres et Amphibies S.-E.D.A.M.: See—
Marchetti, Charles Joseph; and Neplaz, Guy Marcel, 3,578,100.
- Soderlund, Per-Erik, to Intong Aktiebolag. Cellular concrete mold. 3,578,276, Cl. 249-165.
- Soeda, Shigeki; Nemoto, Hidetaro; and Kaneko, Yasuhiro, to Nippon Kokan Kabushiki Kaisha. Method of and apparatus for continuous casting with immersion-type long nozzles. 3,578,062, Cl. 164-82.
- Sommerfeld, Louis. Frame with deformable locking means. 3,577,864, Cl. 52-473.
- Sonne, Hans. Tamperproof cap for receptacle. 3,578,192, Cl. 215-9.
- Soriano, Rene: See—
Goldfarb, Adolph E.; and Soriano, Rene, 3,578,320.
- Sorm, Frantisek; and Suchy, Milos, to Ceskoslovenska akademie ved. Dimethyl-1,5 dihalohexyl benzoic acid esters, compounds for combating insect pests of the genus dysdercus. 3,578,699, Cl. 260-476.
- Sosnovsky, Efim Davidovich: See—
Cherny, Anatoly Alexeevich; Vladimir Alexandrovich; Lev Mikhailovich; Kurbatsky, Ivan Lukich; Sosnovsky, Efim Davidovich; and Pavlenko, Nikolai Semenovitch, 3,578,302.
- Sotome, Hiromi, to Nippon Gakki Seizo Kabushiki Kaisha. Loud-speaker. 3,578,104, Cl. 181-32.
- Spadini, Paolo. Watertight alarm wrist-watch. 3,577,876, Cl. 58-57.5.
- Sparks, John M., III: See—
Kirkpatrick, Max B.; Harvey, Andrew; and Sparks, John M., III, 3,578,087.
- Spence, John H.: See—
Gutridge, Jack E.; Johnson, Kent N.; and Spence, John H., 3,577,934.
- Spencer, Lloyd. Vertically movable self-locking shutter. 3,578,060, Cl. 160-172.
- Sperry Rand Corporation: See—
Woodward, Benjamin W., 3,578,143.
- Spethmann, Donald H., to Honeywell Inc. Pneumatic air conditioning control system. 3,578,242, Cl. 236-1.
- Spicka, Roland: See—
Gohlffennel, Gerhard; and Spicka, Roland, 3,578,535.
- Spyropoulos, Chris E., to United States of America, Army. Distributed control fuzeic amplifier. 3,578,009, Cl. 137-81.5.
- S.R.M. Hydromeknik AB: See—
Ahlen, Karl Gustav, 3,578,117.
- Stamicarbon N.V.: See—
Kaasenbrood, Petrus J. C., 3,578,664.
- Vorage, Victor A. M. G., 3,578,413.
- Standard Oil Company (Indiana): See—
Yahnke, Robert L., 3,578,585.
- Standard Oil Company, The (Ohio): See—
Milberger, Ernest C.; and Shaw, Wilfrid G., 3,578,695.
- Standard Products Company, The: See—
Paulus, Peter V.; and Green, Harry W., 3,578,166.
- Stansell, Marion J.: See—
Malvin, Harry H.; and Stansell, Marion J., 3,578,567.
- Stapfer, Christian H., to Carlisle Chemical Works, Inc. Diesters exhibiting internal-external lubricating properties in structural resins. 3,578,621, Cl. 260-31.6.
- Star Tab, Inc.: See—
Frey, Ellsworth J., 3,577,948.
- Stark, Sheldon L.: See—
Babbitt, John H., Jr.; Butterfield, Max E.; Nelson, Grant L.; Piper, Hugh V.; and Stark, Sheldon L., 3,578,377.
- Starks, Charles M.: See—
Williams, Billy J.; and Starks, Charles M., 3,578,494.
- States, Ronald Frederick, to Desoutter Brothers Limited. Power-operated impact wrench or screwdriver. 3,578,091, Cl. 173-12.
- Staudt, Heinrich, to Bosch, Robert, GmbH. Control device for fuel injection pumps. 3,577,967, Cl. 123-140.
- Staudt, Heinrich; Hofmann, Eberhard; and Muller, Rolf, to Bosch, Robert, GmbH. Centrifugal RPM regulator for internal combustion engines. 3,577,968, Cl. 123-140.
- Stcherbatcheff, Georges; and Houdet, Claude, to Societe de Recherches en Matiere de Mercromoteurs Electriques Socrem. Clockwork movement cased by a rotary stepping electric motor having two motive phases succeeding one another in time. 3,577,875, Cl. 58-28.
- Steiner, Charles Dale, to AMP Incorporation. Apparatus for feeding two wires simultaneously. 3,578,228, Cl. 226-109.
- Steiner, Maurice. Safety stopper. 3,578,193, Cl. 215-9.
- Steiner, Russell I.: See—
Rast, Gustav E.; and Steiner, Russell I., 3,578,652.
- Stejskal, Joseph F.: See—
Kite, Francis E.; and Stejskal, Joseph F., 3,578,498.
- Sterling Drug Inc.: See—
Archer, Sydney, 3,578,685.
- Tullar, Benjamin F.; and Lorenz, Roman R., 3,578,686.
- Zenitz, Bernard L., 3,578,669.
- Stevens, Ash, Inc.: See—
Ash, Arthur B.; Stevens, Calvin L.; and Markovac, Anica, 3,578,682.
- Stevens, Calvin L.: See—
Ash, Arthur B.; Stevens, Calvin L.; and Markovac, Anica, 3,578,682.
- Stevens, J. P., & Co., Inc.: See—
Dowd, James W.; Jacobs, Robert D.; and Mercer, Harry L., 3,578,491.
- Stevens, Paul M.: See—
Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Garnder, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.
- Stiglitz, Karen R. Demountable sofa or chair construction. 3,578,385, Cl. 297-440.
- Stiles, Vernon E. Method of irrigation. 3,578,432, Cl. 71-1.
- Stinson, John M.: See—
Bottai, Gabriele A.; and Stinson, John M., 3,578,433.
- Straughn, Robert O.: See—
Reinhart, Richard D.; and Straughn, Robert O., 3,577,935.
- Strebelwerk AG: See—
Domok, Otto, 3,578,074.
- Strepton, Robert John William, to United Kingdom Atomic Energy Authority. Folded semi-permeable membrane. 3,578,173, Cl. 161-102.
- Stribick, Jean Charles. Installation for the prefabrication of construction elements. 3,578,187, Cl. 214-89.
- Strohmeyer, Charles, Jr., to Electrodyne Research Corporation. Fluid coolant apparatus for a nuclear reactor. 3,578,563, Cl. 176-51.
- Strubhar, Malcolm K.: See—
Glenn, Edwin E., Jr.; Slover, Vasek R.; and Strubhar, Malcolm K., 3,578,077.
- Stubbman, Albert: See—
Kohner, Frank; Stubbman, Albert; and Donna, Natalie, 3,578,319.
- Suchy, Milos: See—
Sorm, Frantisek; and Suchy, Milos, 3,578,699.
- Sugarman, Meyer L., to Firestone Tire & Rubber Company, The. Electrophotographic reproduction employing BI-charging and negative-charging zinc oxide. 3,578,446, Cl. 96-1.8.
- Suh, John T.: See—
Schnettler, Richard A.; and Suh, John T., 3,578,668.
- Suhner, Willy. Safety heel ski binding. 3,578,350, Cl. 280-11.35.
- Sulkowski, Theodore S., to American Home Products Corporation. Process for preparing 2,3,5-9b-tetrahydro-1H-imidazo [2,1-a] isindol-5-ols. 3,578,677, Cl. 260-309.7.
- Sulzer Brothers Limited: See—
Pfarrwaller, Erwin, 3,578,032.
- Sumitomo Chemical Company, Ltd.: See—
Nakaguchi, Kohei; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, 3,578,636.
- Nakashio, Seizo; and Maruta, Isao, 3,578,625.
- Summerfield, William F., to Mattel, Inc. Tone arm assembly in a toy sound reproducing device. 3,578,339, Cl. 274-9.
- Sun Oil Company: See—
Jost, Donald E.; Janoski, Edward J.; and Schneider, Abraham, 3,578,725.
- Sunbeam Corporation: See—
Horecky, Stanley V.; and Hayes, Thomas Howe, 3,578,000.
- Sundberg, Jack G., to Chandler Evans Inc. Fuel atomization system having compressor drive means. 3,577,965, Cl. 123-119.
- Super Mold Corporation: See—
Lundberg, John B.; Beck, Richard J.; and Locke, James N., 3,578,045.
- Surgical Developments Limited: See—
Regent, Leslie K., 3,577,986.
- Sutton Research Corporation: See—
Keller, Howard F., Jr.; and Ward, Geoffrey R., 3,577,994.
- Swanson, Vernon F.: See—
Cantrell, Robert R.; and Swanson, Vernon F., 3,578,418.
- Sweeney, George A.: See—
Harry, Lawrence D.; and Sweeney, George A., 3,578,616.
- Swiss Aluminium Ltd.: See—
Schmidt-Hatting, Wolfgang; and Huwyler, Sebastian, 3,578,580.
- Sylvania Electric Products, Inc.: See—
Chiola, Vincent; Cleveland, Joseph J.; Kamin, George J.; and Kim, Tai K., 3,578,391.
- Dale, Ernest A.; Fowler, Richard A.; and Thomas, Martha J. B., 3,578,603.
- Mpelkas, Christos C., 3,578,464.
- Ritsko, Joseph E., 3,578,392.
- Waldo, Craig T., 3,578,478.
- Tado, Hiroshi, to Yanmar Diesel Engine Co., Ltd. Exhaust system of propeller for ships. 3,577,952, Cl. 115-17.
- Tai, Wun T., to Koppers Company, Inc. Adhesive dip comprising a rubber latex and tris (dihydroxybenzyl) phenol. 3,578,613, Cl. 260-3.
- Takano, Masatoshi; Arita, Hiroshi; and Omori, Hayao. Automatic strapping machine. 3,577,909, Cl. 100-4.
- Takao, Hiroyoshi: See—
Nakaguchi, Kohei; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, 3,578,636.
- Tallerino, Charles E.: See—
Wombough, Philip J.; and Tallerino, Charles E., 3,578,241.
- Tamura, Raymond M. Armored garment. 3,577,836, Cl. 2-2.5.

- Tanaka, Masao: See—
Nishimura, Yasuro; and Tanaka, Masao, 3,578,420.
- Tani, Seiji: See—
Nemoto, Mamoru; and Tani, Seiji, 3,577,891.
- Tannenberger, Helmut; and Kovacs, Paul, to Compagnie Francaise de Raffinage. Stabilized zirconium oxide electrode for solid electrolyte fuel cell. 3,578,502, Cl. 136-120.
- Tariel, Henri, to L'Air Liquide Anonyme Pour l'Etude et l'Exploitation des Proceder Georges Claude. Thermally insulated receptacle for a cryogenic fluid. 3,578,541, Cl. 161-7.
- Taschenberg, Ernest J., to Koppers Company, Inc. Annular shoulder assembly for a rotating seal. 3,578,343, Cl. 277-16.
- Tauh, David: See—
Wendler, Norman L.; Taub, David; and Kuo, Chan Hwa, 3,578,670.
- Taylor, George David: See—
Findlay, Donald Urquhart; McCaffrey, Francis Hamnet Garland; and Taylor, George David, 3,577,924.
- Taylor, Leslie G.; and Withey, Donald S., to British Oxygen Company Limited. The Porous mass and a container therefor. 3,578,197, Cl. 220-16.
- Taylor, Lloyd D., to Polaroid Corporation. Ionically cross-linked photopolymerized addition polymers. 3,578,458, Cl. 96-115.
- Taylor, Norris O.; Uhler, Wilmer P.; Gardella, John M.; and Cahlik, Jim C., to Pennwalt Corporation, mesne. Adjustable chair. 3,578,379, Cl. 297-71.
- Taylor, Paul: See—
Battersby, William R.; Follett, Robert P.; MacGrandle, Timothy D.; Rossitto, Conrad; and Taylor, Paul, 3,578,727.
- Teas, Roy K. Ball and impact mallet. 3,578,325, Cl. 273-56.
- Teisseire, Paul Jose: See—
Corbier, Bernard Pierre; and Teisseire, Paul Jose, 3,578,715.
- Teknova A/S: See—
Andersen, Frede Reinholdt, 3,578,015.
- Telco Industries: See—
Martini, Leo A., 3,578,284.
- Tenneco Inc.: See—
Uhen, James R.; and Olson, David L., 3,578,059.
- Tenneco Oil Company: See—
Halbert, William G., 3,578,085.
- Tennessee Valley Authority: See—
Bottai, Gabriele A.; and Stinson, John M., 3,578,433.
- Tesch, Hans-Jurgen; Haverkamp, Gunther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Drilling tools. 3,578,092, Cl. 175-39.
- Tesdahl, Thomas C.: See—
Crotty, Homer E.; Coffey, Charles R.; and Tesdahl, Thomas C., 3,578,499.
- Texaco Inc.: See—
Larkin, John M.; and Kreuz, Kenneth L., 3,578,687.
- Rigdon, Orville W.; Edwards, Robert S.; and Holst, Edward H., 3,578,575.
- Schlight, Raymond C.; and Godfrey, Arthur W., 3,578,595.
- Woodle, Robert A., 3,578,405.
- Texas Instruments, Incorporated: See—
Borrello, Sebastian Ronald; and Roberts, Charles Grady, 3,578,515.
- Textile Marking Machine Co., Inc.: See—
Mueller, Roger, 3,578,525.
- Textron Inc.: See—
Hudnall, Frederick W., 3,577,863.
- Thaden, Herbert V. Winding apparatus for forming T-shaped fittings. 3,578,532, Cl. 156-431.
- Thermovox GmbH: See—
Vox, Anton J., 3,578,066.
- Thevignot, Max; and Schweblen, Robert M., to Etablissements Thevignot. Spherical valve plug. 3,578,289, Cl. 251-309.
- Thomas & Betts Corporation: See—
Hidassy, Laszlo, 3,578,157.
- Thomas, Henry D. Vehicle unloader. 3,578,186, Cl. 214-83.22.
- Thomas, Lowell S.: See—
Clecreman, Kenneth J.; and Thomas, Lowell S., 3,578,549.
- Thomas, Martha J. B.: See—
Dale, Ernest A.; Fowler, Richard A.; and Thomas, Martha J. B., 3,578,603.
- Thompson, Charles S., Jr., to Gulf & Western Industrial Products Company, mesne. Aircraft arresting device. 3,578,271, Cl. 244-110.
- Thompson, Charles S., Jr., to Gulf & Western Industrial Products Company. Aircraft arresting device. 3,578,272, Cl. 244-110.
- Thompson, Stanley P.; and Shofer, Don L., to Phillips Petroleum Company. Hot screen printing with thermoplastic ink. 3,577,915, Cl. 101-129.
- Thomson, Charles, to Thomson, Solar Engineering Company. Belt conveyors. 3,578,149, Cl. 198-201.
- Thomson, Solar Engineering Company: See—
Thomson, Charles, 3,578,149.
- Thorsrud, Agmund K., to Phillips Petroleum Company. Reinforced microporous laminates. 3,578,544, Cl. 161-59.
- Throckmorton, James R., to Minnesota Mining and Manufacturing Company. Perfluoro- β -oxa- δ -valerolactone. 3,578,684, Cl. 260-340.2.
- Tiama, Susumu; and Nakada, Shigeo, to Nippon Carbide Kogyo Kabushiki Kaisha. Process for the preparation of vinyl chloride polymers. 3,578,648, Cl. 260-87.5.
- Tidbury, Gordon Thomas, to Dominion Engineering Works, Limited. Support structure for fourcinier wire adjacent the headbox consisting of a small diameter roll supported by a large diameter master roll. 3,578,557, Cl. 162-301.
- Tkachenko, Anatoly Stepanovich: See—
Sirotkina, Maria Gavrilovna; Kozlov, Jury Gotlibovich; Alexeeva, Alevtina Vasilievna; Afanasieva, Ljudmila Alexeevna; Benyash, Galina Nikolaevna; Gorbovitsky, Efim Bentsionovich; Levitskaya, Ljudmila Alexeevna; Lisitsina, Galina Konstantinovna; Tkachenko, Anatoly Stepanovich; and Khaitlin, Adolf Isacovich, 3,578,172.
- Tobol, Helen K.: See—
Noeroske, Robert L.; and Tobol, Helen K., 3,578,434.
- Tod, James F.: See—
Bombardieri, Caurino C.; and Tod, James F., 3,578,084.
- Tomezsko, Edward S. J.: See—
Mitchell, Maurice M., Jr.; Fisher, Harold M.; and Tomesko, Edward S. J., 3,578,650.
- Tonkin, Kenneth J.; and Gallagher, John P., to Dick, A. B., Company. Duplicator program control assembly. 3,577,916, Cl. 101-148.
- Toth, Imre: See—
Boucaut, Michel; Toth, Imre; and Reyter, Jean Pierre, 3,578,296.
- Toth, Jenő: See—
Gal, Istvan; Hollo, Janos; Toth, Jenő; and Galgoczi, Bela, 3,578,586.
- Tousignant, William F.: See—
Walles, Wilhelm E.; and Tousignant, William F., 3,578,404.
- Towery, Jack D., to Continental/Moss-Gordin, Inc. Apparatus for preparing fibrous material for a carding machine. 3,577,844, Cl. 19-105.
- Towner, Robert L., to Davison, William B. Insulation method and constructions. 3,577,893, Cl. 94-4.
- Toyota Jidosha Kogyo Kabushiki Kaisha: See—
Hasegawa, Tatsuo; Yoshie, Kohichi; and Kamijima, Yasuhiro, 3,578,376.
- Transitron Electric Corporation: See—
Gehri, Aime A., 3,578,227.
- Trappmann, Wolfgang Hans: See—
Iken, Horst Dieter; and Trappmann, Wolfgang Hans, 3,578,438.
- Treflunion: See—
Francois, Maurice, 3,578,036.
- Treybig, Clemens N.: See—
Lock, Coy B., 3,578,307.
- Trischler, Floyd D., to Whittaker Corporation. Hydroxyl modified polybenzimidazoles. 3,578,644, Cl. 260-78.4.
- Troy Steel Corporation: See—
Menge, Donald C., 3,578,043.
- TRW Inc.: See—
Silverman, Herbert P.; and Giarrusso, Gino A., 3,578,409.
- Trzyna, Charles J.; and Trzyna, Thaddeus S., to Electronic Precision Industries Corporation. Electrolytic material removal process and apparatus. 3,578,574, Cl. 204-143.
- Trzyna, Thaddeus S.: See—
Trzyna, Charles J.; and Trzyna, Thaddeus S., 3,578,574.
- Tsugeki, Toshi: See—
Hosokawa, Tomoyuki; Tsugeki, Toshi; and Asanari, Shigeyuki, 3,577,869.
- Tsuk, Andrew G., to Grace, W. R., & Co. Polyhydroxyl coagulant compounds. 3,578,588, Cl. 210-52.
- Tullar, Benjamin F.; and Lorenz, Roman R., to Sterling Drug Inc. 2-Hydroxy 3-[3-(3,5-trimethylcyclohexyl)-alkyl]-1, 4-naphthoquinones and their preparation. 3,578,686, Cl. 260-396.
- Tupper, Leland Chester: See—
Hurlbut, Myron Robert; Phillips, Robert Arthur; and Tupper, Leland Chester, 3,578,298.
- Tur, Dzidra Rudolfovna: See—
Korshak, Vasily Vladimirovich; Vinogradova, Svetlana Vasilievna; and Tur, Dzidra Rudolfovna, 3,578,631.
- Turnbaugh, William H.: See—
Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., 3,577,949.
- Turner Brothers Asbestos Company Limited: See—
Wicker, George Leonard, 3,578,547.
- Turner, John J.: See—
Nielsen, James C.; and Turner, John J., 3,578,281.
- Turolia, Marco. Relief valve unit for hydraulic pressure lines. 3,578,019, Cl. 137-491.
- Twentieth Century-Fox Film Corporation: See—
Bragg, Herbert E., 3,577,898.
- Twilliey, Ian C.; Coli, Guido John, Jr.; and Roth, David W. H., Jr., to Allied Chemical Corporation. Method for the production of thermally stable polycaprolactam. 3,578,640, Cl. 260-78.
- Twin Disc, Incorporated: See—
Hilpert, Conrad R., 3,578,120.
- Uarco Incorporated: See—
Absler, Howard K.; and Narel, Leonard M., 3,578,178.
- Uchigaki, Taku: See—
Sakata, Rikita; Masuda, Kohei; Uchigaki, Taku; and Arai, Masakazu, 3,578,527.
- Uebe, Rudolf: See—
Weissmehl, Klaus; and Uebe, Rudolf, 3,578,623.
- Ueberle, Dieter; and Heinz, Ernst, to Metallgesellschaft Aktiengesellschaft. Process of producing hydrohalic acids and metal oxides. 3,578,401, Cl. 23-154.

- Ueno, Yoshihiro, to Victor Company of Japan, Limited. Tape cartridge rejection apparatus. 3,578,338, Cl. 274-4.
- Uhen, James R.; and Olson, David L., to Tenneco Inc., mesne. Bead spreader for truck tires. 3,578,059, Cl. 157-1.21
- Uhler, Wilmer P.: *See—*
Taylor, Norris O.; Uhler, Wilmer P.; Gardella, John M.; and Cahlik, Jim C., 3,578,379.
- Ullman, Edwin Fisher: *See—*
Loy, Myrna; Huffman, Kenneth Robert; and Ullman, Edwin Fisher, 3,578,683.
- Ultrasonic Systems, Inc.: *See—*
Kuris, Arthur, 3,577,981.
- Union Camp Corporation: *See—*
Chun, Sun W.; and Friend, William H., 3,578,628.
Marchisen, Joseph, 3,578,234.
Martelli, Homer, 3,578,154.
- Union Carbide Corporation: *See—*
Hubert, Andre Jules, 3,578,724.
Moore, Arthur W., 3,578,403.
Silver, Julius L., 3,578,444.
- Union Oil Company of California: *See—*
Fenton, Donald M., 3,578,688.
- Uniroyal, Inc.: *See—*
Covey, Rupert A.; von Schmeling, Bogislav; and Crittendon, Charles E., 3,578,694.
- United Aircraft Corporation: *See—*
Elliott, Daniel L.; and Burr, Gary D., 3,578,068.
Gardner, Thomas E., 3,577,902.
Harding, Howard H., 3,578,526.
Johnson, Bruce M.; DeCrescenti, Michael A.; and Darrah, James G., 3,578,610.
- United Kingdom Atomic Energy Authority: *See—*
Streeton, Robert John William, 3,578,173.
- United Shoe Machinery Corporation: *See—*
Battersby, William R.; Follett, Robert P.; MacGrandle, Timothy D.; Rossitto, Conrad; and Taylor, Paul, 3,578,727.
- United States of America
Air Force: *See—*
Armington, Alton F.; and O'Connor, John J., 3,578,414.
Clark, Robert O., 3,578,008.
Hopps, Jay N.; and Green, Norman F., 3,578,114.
Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Garnder, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.
- Army: *See—*
Black, David F., 3,578,185.
Campagnuolo, Carl J.; and Villarreal, Fernando, 3,578,010.
Hiltz, Ralph H., 3,578,415.
Holmes, Allen B., 3,578,011.
Pearlstein, Fred; and Weightman, Robert F., 3,578,468.
Perkins, William E.; and Schlack, Allen F., 3,577,923.
Spyropoulos, Chris E., 3,578,009.
Wynbelt, Walter P., 3,578,056.
- Atomic Energy Commission: *See—*
Anderson, Charles G., 3,578,442.
Cho, Boong Y.; and Anderson, Larry B., 3,578,406.
- Navy: *See—*
Betz, Andrew J., Jr., 3,578,006.
Mueller, Kenneth E.; Critcher, John L.; Monson, Franklin A.; Turnbaugh, William H.; and Kosloski, John E., 3,577,949.
Mulgrave, Thomas P., 3,578,273.
Pilkun, Manfred H.; and Lorenz, Max R., 3,578,513.
Schmidt, Louis A., 3,577,925.
- United-Carr Incorporated: *See—*
Perrin, Badger, 3,577,846.
- Universal Oil Products Company: *See—*
Hayes, John C., 3,578,584.
- Universal Vendors, Inc.: *See—*
Verbeke, Henry, 3,578,127.
- Universal Water Corporation: *See—*
Manjikian, Serop, 3,578,175.
- University of California, The Regents of the: *See—*
Mehlschau, James J., 3,578,146.
- University of Newcastle, The: *See—*
Johnston, Arthur K., 3,578,071.
- Updegraff, Edward R. Apparatus for offset printing. 3,577,856, Cl. 33-184.5
- Upton, Gerlad G., to Boeing Company, The. Wing area enlargement system. 3,578,266, Cl. 244-43.
- Uriel, Jose, to Etablissement Public: Centre National de La Recherche Scientifique. Preparation of mixed gels of acrylamide and agarose or agar-agar. 3,578,604, Cl. 252-316.
- U.S. Filter Corporation: *See—*
Warning, Theodore J., 3,578,163.
- U.S. Philips Corporation: *See—*
Houtman, Harke Jan; Schoot, Cornelis Johannes; Boven, Jan; and van Beek, Leendert Klaas Hellinga, 3,578,457.
- U.S. Plywood-Champion Papers Inc.: *See—*
Rauch, August H., 3,578,522.
- Usher, David. Apparatus for removing floating pollutants. 3,578,171, Cl. 210-242.
- Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishibashi, Hiroaki, to Chisso Corporation. Method for promoting growth of agricultural plant. 3,578,435, Cl. 71-92.
- Usko, Alexander J., to Monsanto Company. Method and apparatus for positioning articles. 3,577,919, Cl. 101-426.
- Usko, Alexander J.: *See—*
Peck, Arthur C.; and Usko, Alexander J., 3,578,536.
- USM Corporation: *See—*
Vinter, Sydney A., 3,578,480.
- Vac Pac Manufacturing Company, Inc.: *See—*
Perlman, Sol J., 3,578,239.
- Vaccaro, Andrew J.: *See—*
De Rucker, Donald E.; and Vaccaro, Andrew J., 3,578,363.
- van Beek, Leendert Klaas Hellinga: *See—*
Houtman, Harke Jan; Schoot, Cornelis Johannes; Boven, Jan; and van Beek, Leendert Klaas Hellinga, 3,578,457.
- Van Der Gaast, Harry. Disposable surgical skin punch. 3,577,979, Cl. 128-2.
- Van Der Lely, Cornelis. Mowing machines. 3,577,870, Cl. 56-6.
- van der Zijden, Antonie Simon Maria, deceased (by van der Zijden-Willemsse, Regina Christina Maria, legal representative); and of the heirs, to Lever Brothers Company. Flavouring compositions. 3,578,465, Cl. 99-140.
- Van Horn Serrell, Peter: *See—*
Ross, Frederick W.; Van Horn Serrell, Peter; and Shatto, Howard L., 3,578,102.
- Van Langenhoven, Jules Edmond, to Victor Comptometer Corporation. Caseless ammunition for firearm and the like. 3,577,921, Cl. 102-38.
- Vanlerberghe, Guy: *See—*
Kalopissis, Gregoire; and Vanlerberghe, Guy, 3,578,719.
- Van Luik, Frank W., Jr., to General Electric Company. Ammonia detection, following ultraviolet radiation. 3,578,410, Cl. 23-232.
- van Marle, Nicolaas Gradus Jan Willem, to Avirolanda Maatschappij voor Vliegtuigbouw N.V. Airport gangway. 3,577,838, Cl. 14-71.
- Van Wagner, Edward M.: *See—*
Elchisak, John J.; Hope, William D.; and Van Wagner, Edward M., 3,578,445.
- Vapor Corporation: *See—*
Salerno, Paul G.; and Wilson, Steven J., 3,578,287.
- Varaxin, Alexei Ivanovich: *See—*
Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Safronovich, Lev Isaacovich; and Kuznetsov, Leonid Georgievich, 3,578,063.
- Vaught, Russ S.: *See—*
Schuster, Donald H.; and Vaught, Russ S., 3,577,857.
- Verbeke, Henry, to Universal Vendors, Inc. Vending machine with adjustable price setting. 3,578,127, Cl. 194-71.
- Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung. *See—*
Gunter, Siegfried, 3,578,263.
- Vermeulen, Geert J., to N.V. Machinefabriek L. te Strake. Yarn brake of the sling type. 3,578,256, Cl. 242-36.
- Vertut, Jean: *See—*
Guilbaud, Jean-Pierre; and Vertut, Jean, 3,578,097.
- Victor Company of Japan, Limited: *See—*
Ueno, Yoshihiro, 3,578,338.
- Victor Comptometer Corporation: *See—*
Van Langenhoven, Jules Edmond, 3,577,921.
- Victorri, Marcel, to Merlin Gerin, Societe Anonyme. Linear induction motor drive system. 3,577,928, Cl. 104-148.
- Villarreal, Fernando: *See—*
Campagnuolo, Carl J.; and Villarreal, Fernando, 3,578,010.
- Vilter Manufacturing Corporation: *See—*
Grant, Whitney L., 3,578,168.
- Vinogradova, Svetlana Vasilievna: *See—*
Korshak, Vasily Vladimirovich; Vinogradova, Svetlana Vasilievna; and Tur, Dzidra Rudolfovna, 3,578,631.
- Vinter, Sydney A., to USM Corporation. Methods of ornamenting pliable sheet material. 3,578,480, Cl. 117-4.
- Vladimir Alexandrovich: *See—*
Cherny, Anatoly Alexeevich; Vladimir Alexandrovich; Lev Mikhailovich; Kurbatsky, Ivan Lukich; Sosnovsky, Efim Davidovich; and Pavlenko, Nikolai Semenovich, 3,578,302.
- Voisin, Philippe: *See—*
Morel, Paul; Givry, Jean-Pierre; and Voisin, Philippe, 3,578,069.
- Volkswagenwerke Aktiengesellschaft: *See—*
Bockmann, Rudolf, 3,577,963.
- Von Duyke, Harrison M. Potato dicer. 3,578,048, Cl. 146-78.
- von Haartman, Ernst Goran: *See—*
Ingstad, Nils Torsten; and von Haartman, Ernst Goran, 3,578,431.
- Von Krusenstierna, Otto, to Allmänna Svenska Elektriska Aktiebolaget. Measuring means for measuring the oxygen content in liquid and gaseous media. 3,578,578, Cl. 204-195.
- von Schmeling, Bogislav: *See—*
Covey, Rupert A.; von Schmeling, Bogislav; and Crittendon, Charles E., 3,578,694.
- Vorage, Victor A. M. G., to Stamicarbon N.V. Apparatus for the production of melamine from urea. 3,578,413, Cl. 23-260.
- Vought, Kenneth D.: *See—*
Heine, Wolfgang Fred; and Vought, Kenneth D., 3,578,258.

- Vux, Anton J., to Thermovox GmbH. Apparatus for the heating and cooling of moulds for the production of plastic bodies. 3,578,066, Cl. 165-27.
- Wacker, Alexander: *See—*
Tesch, Hans-Jürgen; Haverkamp, Gunther; Becker, Herbert; Wacker, Alexander; and Gotte, Hans, 3,578,092.
- Wacker-Chemie G.m.b.H.: *See—*
Bauer, Ignaz; Riedle, Rudolf; and Nitzsche, Siegfried, 3,578,490.
- Wager, Willem M.: *See—*
Klootwijk, Aric; Bergwerf, Willem; and Wager, Willem M., 3,578,700.
- Wainer, Eugene: *See—*
Petro, Victor P.; Cable, James R.; and Wainer, Eugene, 3,578,456.
- Wakeman, Reginald L.; and Coates, Joseph F., to Millmaster Onyx Corporation. Quaternary ammonium alicyclic carboxylates. 3,578,667, Cl. 260-286.
- Waldo, Craig T., to Sylvania Electric Products, Inc. Slip casting of tungsten. 3,578,478, Cl. 106-286.
- Walker, Edgar F.; and Walker, Montez A. Musical teaching aid. 3,577,890, Cl. 84-472.
- Walker, Montez A.: *See—*
Walker, Edgar F.; and Walker, Montez A., 3,577,890.
- Wallace, John Vipond: *See—*
Prosser, Kenneth Wheatley; and Wallace, John Vipond, 3,578,538.
- Wallace, William E. Monoazonaphthotriazostilbene dyestuffs. 3,578,653, Cl. 260-157.
- Wallis, Wilhelm E.; and Bird, Arnett L., to Dow Chemical Company. The. Surface preparation and electrostatic spray coating of plastic article. 3,578,484, Cl. 117-47.
- Wallis, Wilhelm E.; and Tousignant, William F., to Dow Chemical Company. The. Automatic reaction rate apparatus. 3,578,404, Cl. 23-230.
- Ward, Geoffrey R.: *See—*
Keller, Howard F., Jr.; and Ward, Geoffrey R., 3,577,994.
- Ward, Henry D., Jr., to Ward-Turner Machinery Company, The. Brush feeder for warped sheets. 3,578,314, Cl. 271-44.
- Ward, Jeanne A.: *See—*
Bloom, Stanley M.; Simon, Myron S.; and Ward, Jeanne A., 3,578,448.
- Ward-Turner Machinery Company, The: *See—*
Ward, Henry D., Jr., 3,578,314.
- Warne, Eugene Harold, to Lucas, Joseph, (Industries) Limited. Fuel control systems for dual fuel gas turbine engines. 3,577,877, Cl. 60-39.28
- Warner, Ellis R., Jr.: *See—*
Combs, William H.; Craig, Sam N.; Warner, Ellis R., Jr.; and Buckman, Wayne T., 3,578,250.
- Warner, William Wayne: *See—*
Palm, Bert E.; and Warner, William Wayne, 3,578,509.
Palm, Bert E.; and Warner, William Wayne, 3,578,510.
- Warning, Theodore J., to U.S. Filter Corporation. Method and apparatus for precoating filter leaves. 3,578,163, Cl. 210-75.
- Wascon Systems, Incorporated: *See—*
Combs, William H.; Craig, Sam N.; Warner, Ellis R., Jr.; and Buckman, Wayne T., 3,578,250.
- Washall, Thomas A., to Atlantic Richfield Company. Purification of low molecular weight epoxides by extractive distillation with a glycol or glycol ether. 3,578,568, Cl. 203-64.
- Watanabe, Hideya: *See—*
Kato, Yoshiaki; and Watanabe, Hideya, 3,578,129.
- Watanabe, Makoto: *See—*
Nakai, Miyoji; Nakajima, Akira; Watanabe, Makoto; and Sanukiya, Toshio, 3,577,842.
- Waters, Graham Thomas, to Imperial Chemical Industries Limited. Core yarns and methods for their manufacture. 3,577,873, Cl. 57-144.
- Watkins, Charles William, to Singer Company, The. Dense pile tufting machines. 3,577,943, Cl. 112-79.
- Watson, Donald W.; and Artelt, Herbert C., Jr., to Xerox Corporation. Driving apparatus for article feeders. 3,578,316, Cl. 271-54.
- Watson, George A.: *See—*
Gray, Jack N.; and Watson, George A., 3,578,551.
- Wayfield, David John. Marking-measuring devices. 3,577,918, Cl. 101-328.
- Weaver, Ernest P.: *See—*
Henry, George R.; and Weaver, Ernest P., 3,578,472.
- Weber, Stuart: *See—*
Wendler, Norman L.; Slaters, Harry L.; and Weber, Stuart, 3,578,705.
- Weeks, Lloyd E.; and Wildi, Bernard S., to Monsanto Company. Process for the preparation of proteinaceous materials. 3,578,460, Cl. 99-7.
- Weeks, Lloyd E.; and Wildi, Bernard S., to Monsanto Company. Process for the preparation of proteinaceous materials. 3,578,461, Cl. 99-7.
- Weese, William F.: *See—*
Dillon, Leo H.; and Weese, William F., 3,578,018.
- Weichel, Ernst. Means for comminuting stalk or leaf vegetable. 3,578,049, Cl. 146-98.
- Weightman, Robert F.: *See—*
Pearlstein, Fred; and Weightman, Robert F., 3,578,468.
- Weinbrenner, Erwin: *See—*
Knipp, Ulrich; Boigk, Eckhard; and Weinbrenner, Erwin, 3,578,057.
- Weingarten, Joseph L.; and Mehaffie, Stephen R. Collapsible air cargo container. 3,578,050, Cl. 150-0.5
- Weiss, Hugh R. Tray for caramels. 3,578,235, Cl. 229-15.
- Weiss, Hugh R. Tray for displaying and protecting candy and the like. 3,578,237, Cl. 229-15.
- Weiss, Jonas; and Hodes, William, to American Standard Inc. Water softening control. 3,578,164, Cl. 210-96.
- Weissermel, Klaus; and Uebe, Rudolf, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Compositions of saturated polyesters, inorganic solids, and cyclic carbonates. 3,578,623, Cl. 260-40.
- Weissuhm, Peter. Apparatus for forming handles on paper bags. 3,578,528, Cl. 156-380.
- Wells, Johnny L., to Phillips Petroleum Company. Paper coating composition. 3,577,885, Cl. 73-150.
- Welly, Richard K., to General Electric Company. Scrap nuclear fuel material recovery process. 3,578,419, Cl. 23-317.
- Wendler, Norman L.; Slaters, Harry L.; and Weber, Stuart, to Merck & Co., Inc. Process for the preparation of homophthalic acid. 3,578,705, Cl. 260-521.
- Wendler, Norman L.; Taub, David; and Kuo, Chan Hwa, to Merck & Co., Inc. Nicotinamide intermediates and process for preparing same. 3,578,670, Cl. 260-294.
- Weng, Cheng-Kuo, to Singer-General Precision, Inc. Fluoric device. 3,578,012, Cl. 137-81.5
- Werner, Frank D., to Rosemont Engineering Company. Capacitive strain sensor. 3,577,883, Cl. 73-88.5
- Wesp, George L., to Monsanto Company. Preformed resinous coverings adhered to architectural surfaces. 3,578,548, Cl. 161-160.
- Western Industries, Inc.: *See—*
Congdon, George L.; and Kufin, Fred W., 3,578,248.
- Westinghouse Learning Corporation: *See—*
Lindquist, Everett F.; and Carsner, George E., 3,578,159.
- Wetzel, Lewis K., to General Electric Company. Cam operated positive clutch. 3,578,118, Cl. 192-16.
- Weyerhaeuser Company: *See—*
Norlander, Norman E.; and Knowles, Robert A., 3,578,044.
- Schillinger, Joseph F.; and Moser, Thomas B., 3,578,238.
- Whirlpool Corporation: *See—*
Laughlin, James P.; and Worman, Everett, 3,578,280.
- Whitaker, John G.; and Crainich, Victor A., Jr., to National Cash Register Company, The. Method of coating a substrate with capsules. 3,578,482, Cl. 47-38.
- White Consolidated Industries, Inc.: *See—*
Nussdorfer, W. R.; and Farrel, James M., 3,577,905.
- White, Eugene B., to Ken-Flo Products Corporation. Reverse-flow aquarium filter device. 3,578,169, Cl. 210-169.
- White, Jackie L., to Reynolds, R. J., Tobacco Company. Filter. 3,577,995, Cl. 131-10.5
- White, Vernon L.: *See—*
Patierno, John W.; White, Vernon L.; Asdurian, Haig; and Grellmann, Hans W., 3,578,265.
- Whitchurst, Darrel Duayne: *See—*
Haag, Werner O.; and Whitchurst, Darrel Duayne, 3,578,609.
- Whitmore, Henry B.: *See—*
Ritzinger, Frederick R., Jr.; Whitmore, Henry B.; Stevens, Paul M.; Garnder, Gerald; Harris, Leonard; and Moore, Arnott A., 3,577,977.
- Whittaker Corporation: *See—*
Trischler, Floyd D., 3,578,644.
- Whittemore, Dwight S., to Dresser Industries, Inc. Fused rebonded basic brick. 3,578,474, Cl. 106-59.
- Wicker, George Leonard, to Turner Brothers Asbestos Company Limited. Laminated fiber-reinforced sheet of polymeric material. 3,578,547, Cl. 161-156.
- Wiechert, Rudolf: *See—*
Berndt, Hans-Dietlef; Buchschacher, Paul; Eder, Ulrich; Furlenmeier, Andre; Furst, Andor; Kerb, Ulrich; Muller, Marcel; and Wiechert, Rudolf, 3,578,659.
- Wiese, John R., to Leeds & Northrup Company. Device for immersion in molten material to sample and/or measure temperature. 3,577,886, Cl. 73-425.4
- Wildi, Bernard S.: *See—*
Weeks, Lloyd E.; and Wildi, Bernard S., 3,578,460.
Weeks, Lloyd E.; and Wildi, Bernard S., 3,578,461.
- Wiley, John, to Skrob Inc. Rotary internal combustion engine. 3,577,960, Cl. 123-8.09
- Wilkinson, Guilbert Roland. Sewing tissue instruments or the like. 3,577,991, Cl. 128-340.
- Willebacher, Erich M.; Schmedtkord, Ulrich; and Gabler, Dieter K., to Singer Company, The, mesne. Undertrimmer mechanism for sewing machines. 3,577,944, Cl. 112-127.
- William Gluckin & Co., Inc.: *See—*
Gluckin, Gerald W.; and Kurland, William, 3,577,993.
- Williams, Billy J.; and Starks, Charles M., to Continental Oil Company. Zinc plating by chemical reduction. 3,578,494, Cl. 117-160.
- Williams, L. G.: *See—*
Smith, Franklin J.; and Williams, L. G., 3,578,463.
- Williams, Leslie Preston: *See—*
Nieneker, Darle Lee; and Williams, Leslie Preston, 3,578,590.
- Wilson, Delbert T.: *See—*
Mehl, Daniel L.; Wilson, Delbert T.; and Young, Richard J., 3,578,511.
- Wilson, Steven J.: *See—*
Salerno, Paul G.; and Wilson, Steven J., 3,578,287.

- Windings, Inc.: *See—*
Gordon, William F.; and Newman, James W., 3,578,255.
- Winer, Albert A.: *See—*
Sirois, Louis L.; Winer, Albert A.; Alexander, Gordon E.; and Page, Arthur P., 3,578,408.
- Winter, Joseph, to Olin Corporation. Corrugated tubing. 3,578,075, Cl. 165-177.
- Wirth, Barbara: *See—*
Ziegler, Gunther; and Wirth, Barbara, 3,578,496.
- Wise, John J.: *See—*
Bows, Emmerson; and Wise, John J., 3,578,723.
- Withey, Donald S.: *See—*
Taylor, Leslie G.; and Withey, Donald S., 3,578,197.
- Wixon, Harold Eugene: *See—*
Lazaridis, Christina Nicholson; and Wixon, Harold Eugene, 3,578,591.
- Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., to Olin Corporation. Preparation of calcium hypochlorite from hypochlorous acid solutions. 3,578,393, Cl. 23-86.
- Wojtowicz, John A.; Lapkin, Milton; and Puar, Mohindar S., to Olin Corporation. Preparation of chloride-free hypochlorous acid solutions. 3,578,400, Cl. 23-152.
- Wombough, Philip J.; and Tallerino, Charles E. Slide rule for scuba divers. 3,578,241, Cl. 235-88.
- Wood, Bruce V. Impact crusher. 3,578,254, Cl. 241-275.
- Wood, Gerald R. Wood pulp and chipping chain saw apparatus. 3,578,033, Cl. 143-32.
- Wood, Louis L.; and Hamilton, Richard A., said Wood assor. to Grace, W. R., & Co. Polymers from nitrilotriacetonitrile and iminodiacetonitrile. 3,578,643, Cl. 260-78.4.
- Wood, Philip W.; Carter, Terry L., Jr.; and Carter, Terry L., III, to Citics Service Company. Folding method and apparatus therefor. 3,578,311, Cl. 270-69.
- Wood, Sidney B., Jr.: *See—*
Emerson, Dean, Jr.; and Wood, Sidney B., Jr., 3,577,894.
- Woodard, Charles Elbert; and Morcom, Richard James. Method for treating the flanges of containers. 3,578,734, Cl. 264-80.
- Woodle, Robert A., to Texaco Inc. Method and apparatus for analysis of fluid mixtures. 3,578,405, Cl. 23-230.
- Woodman Company, Inc. The: *See—*
Henry, Nelson R.; and Middour, Donald R., 3,578,094.
- Woodward, Benjamin W., to Sperry Rand Corporation. Control System. 3,578,143, Cl. 198-40.
- Woolley, John Mathers: *See—*
Dodman, David; and Woolley, John Mathers, 3,578,720.
- Worman, Everett: *See—*
Laughlin, James P.; and Worman, Everett, 3,578,280.
- Wright, Allen C., to Haws Drinking Faucet Company. Spherical water fountain. 3,578,247, Cl. 239-29.
- Wright, Archibald N.; and Mathewson, Wilfred F., Jr., to General Electric Company. Diamond and boron nitride particles coated with a polymerized dianhydride. 3,578,425, Cl. 51-295.
- Wright, Donald R., to Dow Chemical Company, The. Apparatus for the preparation of walled structures. 3,578,537, Cl. 156-577.
- Wszolek, Walter R., to Grace, W. R., & Co. Alpha-hydroxy-carboxylic acids as curing rate accelerator for curable polymer systems. 3,578,614, Cl. 260-13.
- Wurmser, Donald W.: *See—*
Louis, Kwok Toy; Wurmser, Donald W.; and Zaritsky, Herbert, 3,578,617.
- Wyeth, John, & Brothers Limited: *See—*
Brown, Kevan, 3,578,671.
- Wynbelt, Walter P., to United States of America, Army. Run-flat combat tire. 3,578,056, Cl. 152-340.
- Xerox Corporation: *See—*
Burnham, Edward H.; and Lavander, Edward J., 3,578,317.
- Elchisak, John J.; Hope, William D.; and Van Wagner, Edward M., 3,578,445.
- Watson, Donald W.; and Artelt, Herbert C., Jr., 3,578,316.
- Yabuuchi, Hiroshi: *See—*
Nakaguchi, Kohci; Kawasumi, Shohachi; Hirooka, Masaaki; Yabuuchi, Hiroshi; and Takao, Hiroyoshi, 3,578,636.
- Yahnke, Robert L., to Standard Oil Company (Indiana). Method of removing floating oil from the surface of a body of water. 3,578,585, Cl. 210-30.
- Yamamoto, Kozo; and Kawada, Toshio, to Matsushita Electric Industrial Co., Ltd. Tape recorder of magazine type. 3,578,261, Cl. 242-199.
- Yanmar Diesel Engine Co., Ltd.: *See—*
Tado, Hiroshi, 3,577,952.
- Yasuhara, Minoru: *See—*
Ushioda, Tsunezo; Nonaka, Katsuhiko; Yasuhara, Minoru; Sato, Katsuya; Inoi, Takeshi; and Ishibashi, Hiroaki, 3,578,435.
- Yonkers, John L. Method for orienting and assembling small parts. 3,578,189, Cl. 214-152.
- Yoshie, Kohichi: *See—*
Hasegawa, Tatsuo; Yoshie, Kohichi; and Kamijima, Yasuhiro, 3,578,376.
- Yost, Kermit D., to Rex Chainbelt Inc. Cartridge type seal having improved anti-rotation means. 3,578,344, Cl. 277-40.
- Young, Charles A., to Du Pont de Nemours, E. I., and Company. Suede-like sheet material of styrene/butadiene polymer containing an additive. 3,578,481, Cl. 117-8.
- Young, James V., to Monsanto Company. Pneumatic amusement and educational device. 3,578,318, Cl. 272-1.
- Young, James V., to Monsanto Company. Controlled motion amusement device. 3,578,381, Cl. 297-300.
- Young, Richard J.: *See—*
Mehl, Daniel L.; Wilson, Delbert T.; and Young, Richard J., 3,578,511.
- Youngstown Sheet and Tube Company: *See—*
Cullen, Roy H.; Elliott, Charles H.; Aker, Jimmie R.; and Mohr, Harvey O., 3,578,029.
- Yuile, Arthur M.: *See—*
Johnson, Loering M.; and Yuile, Arthur M., 3,578,562.
- Zahnradfabrik Friedrichshafen Aktiengesellschaft: *See—*
Braun, Siegfried; and Hieber, Heinz, 3,577,953.
- Zaritsky, Herbert: *See—*
Louis, Kwok Toy; Wurmser, Donald W.; and Zaritsky, Herbert, 3,578,617.
- Zehfeld, Paul; and Harnau, Hans-Dieter. Combustible shell base. 3,577,922, Cl. 102-44.
- Zellweger Ltd.: *See—*
Felix, Ernst, 3,577,854.
- Zelnick, Charles; and Schmidt, Erwin, to Cooper Industries, Inc. Coiled rule locking mechanism. 3,578,259, Cl. 242-107.2.
- Zenith Radio Corporation: *See—*
Chiang, Kang-Rong; Kun, Zoltan K.; and Robinson, Robert J., 3,578,507.
- Zenitz, Bernard L., to Sterling Drug Inc. 1-[(2-substituted-3-indolyl)-lower-alkanoyl]-cycloalkyl-lower-alkylpiperidines and 1-[(2-hydroxymethyl-3-indolyl)-lower-alkyl]-cycloalkyl-lower-alkylpiperidines. 3,578,669, Cl. 260-294.
- Ziegler, Gunther; and Wirth, Barbara, to Siemens Aktiengesellschaft. Method of improving the super conductivity of niobium-tin layers precipitated on a carrier. 3,578,496, Cl. 117-227.
- Zopf, William L. Sealing plugs or closures. 3,578,027, Cl. 138-89.
- Zviak, Charles; and Ghilardi, Giuliana, to L'Oreal. Dyeing hair while simultaneously lightening its color. 3,578,387, Cl. 8-10.1.

LIST OF DEFENSIVE PUBLICATIONS

APPLICANTS TO WHOM

DEFENSIVE PUBLICATIONS WERE ISSUED ON THE 11TH DAY OF MAY, 1971

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O. G. 687.

- Craven, Robert L., and J. F. Hesselberth, to E. I. du Pont de Nemours and Co. Process for distributing aqueous dispersions through a pneumatic cell. T886,010, 5-11-71, Cl. 117-65.2.
- Du Pont de Nemours, E. I., and Co.: *See—*
Craven, Robert L., and Hesselberth, T886,010.
- Wollnski, Leon E. T886,011.
- Schubert, Kenneth E. T886,013.
- Dykstra, Thomas K. Gelatin with improved chemical setting properties. T886,014, 5-11-71, Cl. 96-114.8.
- Hesselberth, John F.: *See—*
Craven, Robert L., and Hesselberth, T886,010.
- Imperial Chemical Industries Limited: *See—*
Small, William B. T886,012.
- Rees, William W.: *See—*
Stahr, Richard W., and Rees, T886,015.
- Schubert, Kenneth E., to E. I. du Pont de Nemours and Co. Two-phase glass systems and resistor compositions containing the same. T886,013, 5-11-71, Cl. 252-514.
- Small, William B., to Imperial Chemical Industries Limited. Pallets. T886,012, 5-11-71, Cl. 108-51.
- Stahr, Richard W., and W. W. Rees. Flexible transparent contact charging element for electrophotography. T886,015, 5-11-71, Cl. 250-49.5.
- Wollnski, Leon E., to E. I. du Pont de Nemours and Co. Surface static reduction. T886,011, 5-11-71, Cl. 117-46.

LIST OF DESIGN PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 11TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- Abbo, Edward. Radio receiver. 220,723, 5-11-71, Cl. D36-4.
- Alaska, St. Barth. Hand magnifier. 220,724, 5-11-71, Cl. D57-1.
- Anderson, Lauren W.: *See—*
Page, William S., Anderson, Kawai, Kraus, and Oyama. 220,684.
- Andre, Dan M. High intensity lamp. 220,717, 5-11-71, Cl. D48-20.
- Artz, Kenneth W., to W. R. Grace and Co. Combined packaging tray and cover. 220,682, 5-11-71, Cl. D9-219.
- Bartlett, Eric C., to The Dunlop Co. Ltd. Tire. 220,739, 5-11-71, Cl. D90-20.
- Bausch & Lomb Inc.: *See—*
McCracken, Roger L. 220,725.
- Bio-Logics, Inc.: *See—*
Larson, Roger V. 220,740.
- Blumcraft of Pittsburgh: *See—*
Horgan, William J., Jr. 220,678.
- Bremshy, Manfred. Combined umbrella and sheath. 220,736, 5-11-71, Cl. D87-1.
- Brott, Rodney J. Combined liquid and cup dispenser. 220,707, 5-11-71, Cl. D33-26.
- Brott, Rodney J. Combined liquid and cup dispenser. 220,708, 5-11-71, Cl. D33-26.
- Burke, William B., to Milton Bradley Co. Game board. 220,709, 5-11-71, Cl. D34-5.
- California Auto Radio Inc.: *See—*
Maniaci, Robert P. 220,700.
- Caloric Corp.: *See—*
Herr, Lewis H. 220,731.
- Capella Nogue. Bathing-cap. 220,674, 5-11-71, Cl. D2-237.
- Clouston, Allan R. Packaging tray for a lobster. 220,683, 5-11-71, Cl. D9-222.
- Contour Chair-Lounge Co., Inc.: *See—*
Ferro, Arthur C. 220,690.
- Cox, Joseph G., Jr. Bow-mounted steering console for boats. 220,728, 5-11-71, Cl. D71-1.
- Crease, Pierre L., J. C. Kaufman, and D. E. Wilson, to The National Cash Register Co. Data terminal or similar article. 220,693, 5-11-71, Cl. D26-5.
- Crease, Pierre L., D. L. Forsythe, and D. E. Wilson, to The National Cash Register Co. Data terminal or similar article. 220,694, 5-11-71, Cl. D26-5.
- Cuccio, John, to Olivetti, Ing., C. & C., S.p.A. Portable typewriter. 220,728, 5-11-71, Cl. D64-11.
- Dansk Designs, Ltd.: *See—*
Niels, Refsgaard. 220,712.
- Quistgaard, Jens H. 220,713.
- Vallien, Bertil. 220,714.
- Dart Industries, Inc.: *See—*
Swett, James B. 220,711.
- Deguchi, Yoshio, and F. Yanaguchi, to Okamura Mfg. Co. Ltd. Combined desk and book rack. 220,703, 5-11-71, Cl. D33-7.
- Dunlop Co. Ltd., The: *See—*
Bartlett, Eric C. 220,739.
- Erkers, Arne. Handsaw. 220,677, 5-11-71, Cl. D8-96.
- Estey Corp.: *See—*
Huck, Charles M. 220,705.
- Ferro, Arthur C., to Contour Chair-Lounge Co., Inc. Chair. 220,690, 5-11-71, Cl. D15-11.
- Finkel, Henry, to Quality Oil Corp. Bottle or the like. 220,679, 5-11-71, Cl. D9-44.
- Floyd, Robert W., to The B. F. Goodrich Co. Tire. 220,738, 5-11-71, Cl. D90-20.
- Forsythe, Donald L.: *See—*
Crease, Pierre L., Forsythe, and Wilson. 220,694.
- General Electric Co.: *See—*
Lazzo, Stephen, III. 220,695.
- Lazzo, Stephen, III. 220,696.
- Gomez, Claudio G., and F. Kvapil, to The National Cash Register Co. Cash register or similar article. 220,719, 5-11-71, Cl. D52-4.
- Goodrich, B. F. Co., The: *See—*
Floyd, Robert W. 220,738.
- Grabovac, Bosko. Torque wrench. 220,676, 5-11-71, Cl. D8-24.
- Grace, W. R., & Co.: *See—*
Artz, Kenneth W. 220,682.
- Herr, Lewis H., to Caloric Corp. Gas grill. 220,731, 5-11-71, Cl. D81-10.
- Honzik, Joseph A. Christian medallion. 220,701, 5-11-71, Cl. D29-23.
- Horgan, William J., Jr., to Blumcraft of Pittsburgh. Handle. 220,678, 5-11-71, Cl. D8-166.
- Huck, Charles M., to Estey Corp. Filing cabinet. 220,705, 5-11-71, Cl. D33-19.
- Hunt-Wesson Foods, Inc.: *See—*
Kules, Robert H. 220,681.
- International Business Machines Corp.: *See—*
Kapper, Henry. 220,698.
- KI & PO Corp.: *See—*
Kltovich, William P. 220,729.
- Kapper, Henry, to International Business Machines Corp. Telephone terminal. 220,698, 5-11-71, Cl. D26-14.
- Kaufman, James C.: *See—*
Crease, Pierre L., Kaufman, and Wilson. 220,693.
- Kawal, Reid A.: *See—*
Page, William S., Anderson, Kawai, Kraus, and Oyama. 220,684.
- Kearney & Trecker Corp.: *See—*
Stevens, Brooks. 220,721.
- Kital, Isao, to Sharp Kabushiki Kaisha. Cash register. 220,720, 5-11-71, Cl. D52-4.
- Kltovich, William P., to KI & Po Corp. Boat engine. 220,729, 5-11-71, Cl. D71-1.
- Kules, Robert H., to Hunt-Wesson Foods, Inc. Bottle. 220,681, 5-11-71, Cl. D9-103.
- Knudson, Gary A. Roll forming machine for making gutters. 220,722, 5-11-71, Cl. D55-1.
- Kramer, Edward J., to Magna Design, Inc. Table. 220,704, 5-11-71, Cl. D33-14.
- Kraus, Paul B.: *See—*
Page, William S., Anderson, Kawai, Kraus, and Oyama. 220,684.
- Krolopp, Rudolph W.: *See—*
Stessel, Martin C., Krolopp, and Miglas. 220,699.
- Kvapil, Francisco: *See—*
Gomez, Claudio G., and Kvapil. 220,719.
- Larson, Roger V., to Bio-Logics, Inc. Information plate for a hospital patient. 220,740, 5-11-71, Cl. D96-13.
- Lazzo, Stephen, III, to General Electric Co. Control enclosure. 220,695, 5-11-71, Cl. D26-13.
- Lazzo, Stephen, III, to General Electric Co. Control enclosure. 220,696, 5-11-71, Cl. D26-13.
- Loeber, Louis H. Vegetable peeler. 220,737, 5-11-71, Cl. D89-1.
- Magna Design, Inc.: *See—*
Kramer, Edward J. 220,704.
- Maniaci, Robert P., to California Auto Radio Inc. Stereo-tape player. 220,700, 5-11-71, Cl. D26-14.
- McCracken, Roger L., to Bausch & Lomb Inc. Design for a pair of spectacles. 220,725, 5-11-71, Cl. D57-1.

Miklas, Karl: *See*—
 Stessel, Martin C., Krolopp, and Miklas, 220,699.
 Miller, Vline B. Design for a lamp base. 220,716, 5-11-71, Cl. D48—20.
 Milton Bradley Co.: *See*—
 Burke, William B. 220,709.
 Moore, Maurice E. Motor coach. 220,689, 5-11-71, Cl. D14—3.
 Morris, Ira. Module extender. 220,692, 5-11-71, Cl. D26—1.
 Motorola, Inc.: *See*—
 Stessel, Martin C., Krolopp, and Miklas, 220,699.
 National Cash Register Co., The: *See*—
 Crease, Pierre L., Forsythe, and Wilson, 220,694.
 Crease, Pierre L., Kautman, and Wilson, 220,693.
 Gomez, Claudio G., and Kvapil, 220,719.
 Neher, Van H., to Wheaton Glass Co. Bottle. 220,680, 5-11-71, Cl. D9—62.
 Niblack, Kenneth G. Jewel case. 220,733, 5-11-71, Cl. D87—1.
 Nield, Retsgaard, to Dansk Designs, Ltd. Cup. 220,712, 5-11-71, Cl. D44—9.
 Okamura Mfg. Co. Ltd.: *See*—
 Deguchi, Yoshio, and F. Yanaguchi, 220,703.
 Olivetti, Ing. C. & C., S.p.A.: *See*—
 Cuccio, John, 220,726.
 Sottsass, Ettore, Jr. 220,735.
 Osborn Engineering Corp.: *See*—
 Osborn, Ralph C. 220,697.
 Osborn, Ralph C., to Osborn Engineering Corp. Fishing motor foot pedal control. 220,697, 5-11-71, Cl. D26—13.
 Oyama, George C.: *See*—
 Page, William S., Anderson, Kawai, Kraus and Oyama, 220,684.
 Page, William S., L. W. Anderson, R. A. Kawai P. B. Kraus, and G. C. Oyama, said Anderson, Kawai, Kraus and Oyama assignors to said Page. Building structure including underwater living accommodations. 220,684, 5-11-71, Cl. D13—1.
 Pallet, David M. Coin-holder and dispenser. 220,718, 5-11-71, Cl. D52—4.
 Peterson, Charles R. Gun stock grip. 220,691, 5-11-71, Cl. D22—6.
 Quality Oil Corp.: *See*—
 Finkel, Henry, 220,679.
 Quistgaard, Jens H., to Dansk Designs, Ltd. Candelabra. 220,713, 5-11-71, Cl. D48—2.
 Reid, Essie M. Combined cabinet and accessory tray. 220,706, 5-11-71, Cl. D33—19.
 Ritsl, Michael C. Nipple seat for baby bottle. 220,735, 5-11-71, Cl. D83—8.

Sawyer, Ralph V. Aircraft. 220,727, 5-11-71, Cl. D71—1.
 Sawyer, Ralph V. Aircraft. 220,767, 5-11-71, Cl. D71—1.
 Schultze, Louis J. Necktie or the like. 220,675, 5-11-71, Cl. D2—351.
 Sottsass, Ettore, Jr., to Ing. C. Olivetti & C., S.p.A. Type-writer carrying case. 220,735, 5-11-71, Cl. D87—1.
 Spiese, Nathan E., to Wheel Mate Corporation. Camping and utility trailer. 220,687, 5-11-71, Cl. D14—3.
 Stessel, Martin C., R. W. Krolopp, and K. Miklas, to Motorola, Inc. Control unit for a two-way radio or similar article. 220,699, 5-11-71, Cl. D26—14.
 Stevens, Brooks, to Kearney & Trecker Corp. Turning center. 220,721, 5-11-71, Cl. D54—6.
 Stinemann, James S. Air-supported structure. 220,685, 5-11-71, Cl. D13—1.
 Stinemann, James S. Air-supported structure. 220,686, 5-11-71, Cl. D13—1.
 Stricklin, Elwood T. Ring toss game target board. 220,710, 5-11-71, Cl. D34—5.
 Sharp Kabushiki Kaisha: *See*—
 Kitai, Isao, 220,720.
 Sweet, Frank R., Jr. Shelf unit for storing blue prints or similar articles. 220,702, 5-11-71, Cl. D33—2.
 Swett, James B., to Dart Industries, Inc. Food cutter. 220,711, 5-11-71, Cl. D44—1.
 Trudeau, Aime. Combined lamp shade and mirror. 220,715, 5-11-71, Cl. D48—16.
 Vallien, Bertil, to Dansk Designs Ltd. Candelabra. 220,714, 5-11-71, Cl. D48—2.
 Wallazy, Gary. Fishing tackle box. 220,734, 5-11-71, Cl. D87—1.
 Weland, Philip. High ram automotive intake manifold. 220,730, 5-11-71, Cl. D77—1.
 Wheaton Glass Co.: *See*—
 Neher, Van H. 220,680.
 Wheel Mate Corp.: *See*—
 Spiese, Nathan E. 220,687.
 Wilson, Dean E.: *See*—
 Crease, Pierre L., Forsythe, and Wilson, 220,694.
 Crease, Pierre L., Kaufman, and Wilson, 220,693.
 Yanaguchi, Fumio: *See*—
 Deguchi, Yoshio, and Yanaguchi, 220,703.
 Zulim, James G., and L. J. Zulim. Truck rack. 220,688, 5-11-71, Cl. D14—3.
 Zulim, Louis J.: *See*—
 Zulim, James G., and Zulim, 220,688.

CLASSIFICATION OF PATENTS

ISSUED MAY 11, 1971

NOTE.—First number, class; second number, subclass; third number, patent number

2- 2.5 : 3.577.836	70-364 : 3.578.371	105-366 : 3.577.933	128-349 : 3.577.992	156-164 : 3.578.523	181- 33 : 3.578.105
3- 1 : 3.577.837	71- 1 : 3.578.431	414 : 3.577.934	535 : 3.577.993	196 : 3.578.524	57 : 3.578.107
8- 10 : 3.578.386	72- 1 : 3.578.432	106- 1 : 3.578.468	131- 2 : 3.577.994	238 : 3.578.525	182-129 : 3.578.109
.1 : 3.578.387	73- 1 : 3.578.433	39 : 3.578.470	10.5 : 3.577.995	242 : 3.578.526	3.578.110
41 : 3.578.388	77 : 3.578.434	56 : 3.578.471	17 : 3.577.997	244 : 3.578.527	184- 6 : 3.578.111
163 : 3.578.389	92 : 3.578.435	58 : 3.578.472	96 : 3.577.998	380 : 3.578.528	3.578.112
14- 71 : 3.577.838	72-302 : 3.577.881	59 : 3.578.473	132- 79 : 3.577.999	393 : 3.578.529	106 : 3.578.113
15-179 : 3.577.839	450 : 3.577.882	150 : 3.578.475	134- 4 : 3.578.499	410 : 3.578.530	188-311 : 3.578.114
16-142 : 3.577.840	73- 88.5 : 3.577.883	193 : 3.578.476	25 : 3.578.000	425 : 3.578.531	9 : 48 : 3.578.115
18- 12 : 3.577.841	141 : 3.577.884	230 : 3.578.477	45 : 3.578.001	431 : 3.578.532	192- .062 : 3.578.116
20 : 3.577.842	150 : 3.577.885	286 : 3.578.478	135- 4 : 3.578.003	436 : 3.578.533	3.51 : 3.578.117
42 : 3.577.843	425.4 : 3.577.886	107- 14 : 3.577.935	136- 6 : 3.578.500	461 : 3.578.534	16 : 3.578.118
19-105 : 3.577.844	74- 2 : 3.577.887	108- 8 : 3.577.936	86 : 3.578.501	493 : 3.578.535	70.14 : 3.578.119
231 : 3.577.845	711 : 3.577.888	53 : 3.577.937	102 : 3.578.503	497 : 3.578.536	103 : 3.578.120
23- 2 : 3.578.390	75- 5 : 3.578.436	110- 8 : 3.577.938	120 : 3.578.502	537 : 3.578.537	106.2 : 3.578.121
20 : 3.578.395	5 : 3.578.437	112- 14 : 3.577.939	168 : 3.578.506	157- 1.17 : 3.578.538	107 : 3.578.122
22 : 3.578.391	73 : 3.578.438	127 : 3.577.944	169 : 3.578.507	21 : 3.578.539	131 : 3.578.123
3.578.392	129 : 3.578.439	153 : 3.577.945	170 : 3.578.508	202 : 3.578.540	194- 4 : 3.578.124
48 : 3.578.396	170 : 3.578.440	154 : 3.577.946	171 : 3.578.509	3 : 3.578.541	13 : 3.578.125
86 : 3.578.393	171 : 3.578.441	155 : 3.577.947	172 : 3.578.510	38 : 3.578.542	16 : 3.578.126
87 : 3.578.394	206 : 3.578.442	156 : 3.577.948	173 : 3.578.511	59 : 3.578.543	71 : 3.578.127
97 : 3.578.397	3.578.443	157 : 3.577.949	174 : 3.578.512	68 : 3.578.544	195- 51 : 3.578.565
113 : 3.578.398	83- 7 : 3.577.889	158 : 3.577.950	175 : 3.578.513	81.5 : 3.578.009	82 : 3.578.566
121 : 3.578.399	84-472 : 3.577.890	159 : 3.577.951	176 : 3.578.514	3.578.010	197- 17 : 3.578.128
152 : 3.578.400	92- 72 : 3.577.891	160 : 3.577.952	177 : 3.578.515	3.578.011	19 : 3.578.129
154 : 3.578.401	93- 93 : 3.577.892	161 : 3.577.953	178 : 3.578.516	3.578.012	64 : 3.578.130
165 : 3.578.402	94- 4 : 3.577.893	162 : 3.577.954	179 : 3.578.517	3.578.013	82 : 3.578.131
191 : 3.578.403	7 : 3.577.894	163 : 3.577.955	180 : 3.578.518	3.578.014	91 : 3.578.132
230 : 3.578.404	24 : 3.577.895	164 : 3.577.956	181 : 3.578.519	3.578.015	98 : 3.578.133
232 : 3.578.406	48 : 3.577.897	165 : 3.577.957	182 : 3.578.520	3.578.016	114 : 3.578.134
3.578.410	95- 11 : 3.577.898	166 : 3.577.958	183 : 3.578.521	3.578.017	133 : 3.578.135
252 : 3.578.407	31 : 3.577.899	167 : 3.577.959	184 : 3.578.522	3.578.018	3.578.138
253 : 3.578.408	57 : 3.577.901	168 : 3.577.960	185 : 3.578.523	3.578.019	151 : 3.578.136
254 : 3.578.409	57 : 3.577.901	169 : 3.577.961	186 : 3.578.524	3.578.020	170 : 3.578.137
258.5 : 3.578.411	8 : 3.578.444	170 : 3.577.962	187 : 3.578.525	3.578.021	198- 28 : 3.578.139
259 : 3.578.412	.5 : 3.578.445	171 : 3.577.963	188 : 3.578.526	3.578.022	33 : 3.578.140
260 : 3.578.413	.8 : 3.578.446	172 : 3.577.964	189 : 3.578.527	3.578.023	3.578.142
273 : 3.578.414	3 : 3.578.447	173 : 3.577.965	190 : 3.578.528	3.578.024	40 : 3.578.143
277 : 3.578.416	29 : 3.578.448	174 : 3.577.966	191 : 3.578.529	3.578.025	41 : 3.578.144
281 : 3.578.415	33 : 3.578.451	175 : 3.577.967	192 : 3.578.530	3.578.026	115 : 3.578.145
294 : 3.578.417	49 : 3.578.452	176 : 3.577.968	193 : 3.578.531	3.578.027	121 : 3.578.146
299 : 3.578.418	60 : 3.578.453	177 : 3.577.969	194 : 3.578.532	3.578.028	171 : 3.578.147
317 : 3.578.419	60 : 3.578.454	178 : 3.577.970	195 : 3.578.533	3.578.029	181 : 3.578.148
24- 95 : 3.577.846	90 : 3.578.455	179 : 3.577.971	196 : 3.578.534	3.578.030	201 : 3.578.149
29-195 : 3.578.420	91 : 3.578.456	180 : 3.577.972	197 : 3.578.535	3.578.031	203 : 3.578.150
203 : 3.577.847	91 : 3.578.457	181 : 3.577.973	198 : 3.578.536	3.578.032	230 : 3.578.151
427 : 3.577.848	115 : 3.578.458	182 : 3.577.974	199 : 3.578.537	3.578.033	203- 49 : 3.578.567
495 : 3.577.849	115 : 3.578.458	183 : 3.577.975	200 : 3.578.538	3.578.034	64 : 3.578.568
510 : 3.577.850	88- 1.5 : 3.577.902	184 : 3.577.976	201 : 3.578.539	3.578.035	204- 1 : 3.578.569
596 : 3.577.851	2 : 3.577.903	185 : 3.577.977	202 : 3.578.540	3.578.036	33 : 3.578.570
30- 43.92 : 3.577.852	40 : 3.577.904	186 : 3.577.978	203 : 3.578.541	3.578.037	43 : 3.578.571
32- 10 : 3.577.853	94 : 3.577.905	187 : 3.577.979	204 : 3.578.542	3.578.038	95 : 3.578.572
33- 1 : 3.577.854	99- 1 : 3.578.459	188 : 3.577.980	205 : 3.578.543	3.578.039	140.5 : 3.578.573
174 : 3.577.855	7 : 3.578.460	189 : 3.577.981	206 : 3.578.544	3.578.040	143 : 3.578.574
184.5 : 3.577.856	90 : 3.578.462	190 : 3.577.982	207 : 3.578.545	3.578.041	162 : 3.578.575
35- 11 : 3.577.857	103 : 3.578.463	191 : 3.577.983	208 : 3.578.546	3.578.042	3.578.576
36- 2.5 : 3.577.858	133 : 3.578.464	192 : 3.577.984	209 : 3.578.547	3.578.043	181 : 3.578.577
38- 71 : 3.577.859	140 : 3.578.465	193 : 3.577.985	210 : 3.578.548	3.578.044	195 : 3.578.578
42- 50 : 3.577.860	156 : 3.578.466	194 : 3.577.986	211 : 3.578.549	3.578.045	3.578.579
44- 62 : 3.578.421	182 : 3.578.467	195 : 3.577.987	212 : 3.578.550	3.578.046	243 : 3.578.580
63 : 3.578.422	234 : 3.577.906	196 : 3.577.988	213 : 3.578.551	3.578.047	206- 3 : 3.578.152
48-197 : 3.578.423	329 : 3.577.907	197 : 3.577.989	214 : 3.578.552	3.578.048	17 : 3.578.153
51- 73 : 3.577.861	333 : 3.577.908	198 : 3.577.990	215 : 3.578.553	3.578.049	45.14 : 3.578.154
89 : 3.578.424	100- 4 : 3.577.909	199 : 3.577.991	216 : 3.578.554	3.578.050	52 : 3.578.156
295 : 3.578.425	17 : 3.577.910	200 : 3.577.992	217 : 3.578.555	3.578.051	56 : 3.578.157
52-220 : 3.577.863	53 : 3.577.911	201 : 3.577.993	218 : 3.578.556	3.578.052	58 : 3.578.158
223 : 3.577.862	218 : 3.577.912	202 : 3.577.994	219 : 3.578.557	3.578.053	65 : 3.578.159
473 : 3.577.864	101- 93 : 3.577.913	203 : 3.577.995	220 : 3.578.558	3.578.054	208-138 : 3.578.582
53- 25 : 3.577.865	124 : 3.577.914	204 : 3.577.996	221 : 3.578.559	3.578.055	139 : 3.578.583
184 : 3.577.866	129 : 3.577.915	205 : 3.577.997	222 : 3.578.560	3.578.056	139 : 3.578.584
55- 62 : 3.577.867	148 : 3.577.916	206 : 3.577.998	223 : 3.578.561	3.578.057	308 : 3.578.581
178 : 3.577.868	269 : 3.577.917	207 : 3.577.999	224 : 3.578.562	3.578.058	209- 74 : 3.578.159
361 : 3.577.869	328 : 3.577.918	208 : 3.577.999	225 : 3.578.563	3.578.059	81 : 3.578.160
56- 6 : 3.577.870	426 : 3.577.919	209 : 3.577.999	226 : 3.578.564	3.578.060	86 : 3.578.161
255 : 3.577.871	459 : 3.577.920	210 : 3.577.999	227 : 3.578.565	3.578.061	172 : 3.578.162
57- 35 : 3.577.872	102- 38 : 3.577.921	211 : 3.577.999	228 : 3.578.566	3.578.062	210- 30 : 3.578.585
144 : 3.577.873	42 : 3.577.924	212 : 3.577.999	229 : 3.578.567	3.578.063	49 : 3.578.586
58- 23 : 3.577.874	44 : 3.577.922	213 : 3.577.999	230 : 3.578.568	3.578.064	52 : 3.578.587
28 : 3.577.875	46 : 3.577.923	214 : 3.577.999	231 : 3.578.569	3.578.065	3.578.588
57.5 : 3.577.876	70.2 : 3.577.925	215 : 3.577.999	232 : 3.578.570	3.578.066	58 : 3.578.589
60- 39.28 : 3.577.877	76 : 3.577.926	216 : 3.577.999	233 : 3.578.571	3.578.067	75 : 3.578.163
.65 : 3.577.878	104- 23 : 3.577.927	217 : 3.577.999	234 : 3.578.572	3.578.068	96 : 3.578.164
61- 1 : 3.577.879	148 : 3.577.928	218 : 3.577.999	235 : 3.578.573	3.578.069	110 : 3.578.166
62- 86 : 3.577.880	173 : 3.577.930	219 : 3.577.999	236 : 3.578.574	3.578.070	134 : 3.578.167
65- 3 : 3.578.426	105-197 : 3.577.931	220 : 3.577.999	237 : 3.578.575	3.578.071	167 : 3

210-321 : 3,578,172	227-123 : 3,578,231	252-8.7 : 3,578,591	260-94.4 : 3,578,627	260-534 : 3,578,709	273-56 : 3,578,325
416 : 3,578,173	228-2 : 3,578,232	8 : 3,578,592	97.7 : 3,578,628	543 : 3,578,710	101 : 3,578,326
489 : 3,578,174	5 : 3,578,233	9 : 3,578,594	124 : 3,578,651	558 : 3,578,711	102.2 : 3,578,327
492 : 3,578,175	229-14 : 3,578,234	49.6 : 3,578,596	151 : 3,578,652	559 : 3,578,712	106.5 : 3,578,328
50 : 3,578,176	15 : 3,578,235	62.1 : 3,578,593	157 : 3,578,653	580 : 3,578,713	119 : 3,578,329
211-49 : 3,578,177	3,578,237	66 : 3,578,597	186 : 3,578,654	581 : 3,578,714	157 : 3,578,330
50 : 3,578,178	40 : 3,578,238	75 : 3,578,595	209 : 3,578,655	586 : 3,578,715	3,578,331
212-61 : 3,578,179	53 : 3,578,239	102 : 3,578,598	3,578,656	607 : 3,578,717	164 : 3,578,332
213-20 : 3,578,180	55 : 3,578,236	3,578,599	234 : 3,578,657	609 : 3,578,718	176 : 3,578,333
214-6 : 3,578,181	233-26 : 3,578,240	3,578,600	239 : 3,578,658	611 : 3,578,719	274-4 : 3,578,334
17 : 3,578,182	235-88 : 3,578,241	135 : 3,578,601	55 : 3,578,659	647 : 3,578,720	3,578,335
38 : 3,578,183	236-1 : 3,578,242	300 : 3,578,602	243 : 3,578,660	648 : 3,578,721	3,578,336
83.22 : 3,578,184	80 : 3,578,243	301.4 : 3,578,603	3,578,661	650 : 3,578,726	3,578,337
89 : 3,578,185	239-1 : 3,578,244	316 : 3,578,604	248 : 3,578,662	671 : 3,578,722	3,578,338
138 : 3,578,186	8 : 3,578,246	3,578,605	3,578,663	672 : 3,578,723	9 : 3,578,339
152 : 3,578,187	29 : 3,578,247	386 : 3,578,606	249.7 : 3,578,664	678 : 3,578,724	15 : 3,578,340
505 : 3,578,188	66 : 3,578,245	389 : 3,578,607	250 : 3,578,665	683.75 : 3,578,725	277-3 : 3,578,341
771 : 3,578,189	242 : 3,578,248	411 : 3,578,608	256.5 : 3,578,666	825 : 3,578,726	9 : 3,578,342
215-9 : 3,578,190	296 : 3,578,249	430 : 3,578,609	286 : 3,578,667	830 : 3,578,727	16 : 3,578,343
13 : 3,578,191	241-46.02 : 3,578,250	254-139.1 : 3,578,290	288 : 3,578,668	859 : 3,578,728	40 : 3,578,344
47 : 3,578,192	74 : 3,578,251	259-75 : 3,578,291	294 : 3,578,669	873 : 3,578,729	81 : 3,578,345
88 : 3,578,193	141 : 3,578,252	177 : 3,578,292	3,578,670	3,578,730	180 : 3,578,346
107 : 3,578,194	168 : 3,578,253	260-2 : 3,578,611	307 : 3,578,671	929 : 3,578,731	205 : 3,578,347
219-107 : 3,578,195	275 : 3,578,254	5 : 3,578,612	3,578,672	261-64 : 3,578,732	280-5 : 3,578,348
220-16 : 3,578,196	242-18 : 3,578,255	3 : 3,578,613	3,578,673	90 : 3,578,733	11.35 : 3,578,349
31 : 3,578,197	36 : 3,578,256	13 : 3,578,614	308 : 3,578,674	122 : 3,578,734	3,578,350
42 : 3,578,198	68.3 : 3,578,257	17 : 3,578,615	309.2 : 3,578,675	263-21 : 3,578,735	28 : 3,578,351
44 : 3,578,199	74.1 : 3,578,258	18 : 3,578,616	3,578,676	32 : 3,578,736	43.23 : 3,578,352
46 : 3,578,200	107.2 : 3,578,259	3,578,617	7 : 3,578,677	3,578,677	47.2 : 3,578,353
72 : 3,578,201	4 : 3,578,260	21 : 3,578,617	315 : 3,578,678	3,578,678	96.2 : 3,578,354
85 : 3,578,202	199 : 3,578,261	22 : 3,578,619	326.11 : 3,578,680	41 : 3,578,731	124 : 3,578,355
221-124 : 3,578,203	244-7 : 3,578,262	23.7 : 3,578,620	327 : 3,578,681	264-5 : 3,578,732	425 : 3,578,356
232 : 3,578,204	41 : 3,578,264	31.6 : 3,578,621	335 : 3,578,682	34 : 3,578,733	434 : 3,578,357
222-23 : 3,578,205	42 : 3,578,265	33.8 : 3,578,622	340.2 : 3,578,683	35 : 3,578,734	500 : 3,578,358
52 : 3,578,206	43 : 3,578,266	40 : 3,578,623	396 : 3,578,684	80 : 3,578,735	285-47 : 3,578,359
56 : 3,578,207	77 : 3,578,267	41 : 3,578,624	3,578,685	89 : 3,578,736	55 : 3,578,360
71 : 3,578,208	3,578,268	404 : 3,578,625	3,578,686	266-11 : 3,578,737	110 : 3,578,361
95 : 3,578,209	83 : 3,578,269	405.6 : 3,578,626	3,578,687	267-64 : 3,578,738	287-52 : 3,578,362
129.1 : 3,578,210	110 : 3,578,270	410.9 : 3,578,627	406.6 : 3,578,688	121 : 3,578,739	05 : 3,578,363
193 : 3,578,211	115 : 3,578,271	47 : 3,578,628	410.9 : 3,578,689	165 : 3,578,740	87 : 3,578,364
195 : 3,578,212	118 : 3,578,272	448.2 : 3,578,629	414 : 3,578,690	269-24 : 3,578,741	90 : 3,578,365
218 : 3,578,213	152 : 3,578,273	3,578,630	448.2 : 3,578,691	96 : 3,578,742	189.36 : 3,578,366
383 : 3,578,214	118 : 3,578,274	3,578,631	3,578,692	212 : 3,578,743	292-45 : 3,578,367
394 : 3,578,215	152 : 3,578,275	3,578,632	3,578,693	287 : 3,578,744	58 : 3,578,368
402.13 : 3,578,216	248-4 : 3,578,276	63 : 3,578,633	456 : 3,578,694	270-54 : 3,578,745	251.5 : 3,578,369
22 : 3,578,217	20 : 3,578,277	3,578,634	465.3 : 3,578,695	69 : 3,578,746	294-64 : 3,578,370
504 : 3,578,218	3,578,278	77.5 : 3,578,635	3,578,696	271-20 : 3,578,747	67 : 3,578,371
521 : 3,578,219	54 : 3,578,279	78 : 3,578,636	3,578,697	41 : 3,578,748	83 : 3,578,372
546 : 3,578,220	214 : 3,578,280	3 : 3,578,637	475 : 3,578,698	44 : 3,578,749	296-39 : 3,578,373
224-4 : 3,578,221	346 : 3,578,281	4 : 3,578,638	476 : 3,578,699	47 : 3,578,750	65 : 3,578,374
45 : 3,578,222	249-165 : 3,578,282	5 : 3,578,639	484 : 3,578,700	54 : 3,578,751	102 : 3,578,375
225-2 : 3,578,223	251-31 : 3,578,283	85.7 : 3,578,640	485 : 3,578,701	69 : 3,578,752	137 : 3,578,376
226-109 : 3,578,224	88 : 3,578,284	86.7 : 3,578,641	486 : 3,578,702	272-1 : 3,578,753	297-71 : 3,578,377
114 : 3,578,225	218 : 3,578,285	87.5 : 3,578,642	488 : 3,578,703	2 : 3,578,754	229 : 3,578,378
162 : 3,578,226	303 : 3,578,286	92.8 : 3,578,643	507 : 3,578,704	54 : 3,578,755	300 : 3,578,379
	306 : 3,578,287	93.7 : 3,578,644	521 : 3,578,705	55 : 3,578,756	390 : 3,578,380
	309 : 3,578,288	94.1 : 3,578,645	524 : 3,578,706		391 : 3,578,381
	252-8.05 : 3,578,289		530 : 3,578,707		410 : 3,578,382
			534 : 3,578,708		440 : 3,578,383

CLASSIFICATION OF DESIGNS

D 2-237 : 220,674	D13-1 : 220,686	D26-13 : 220,697	D33-26 : 220,708	D52-4 : 220,719	D77-1 : 220,730
351 : 220,675	D14-3 : 220,687	14 : 220,698	D34-5 : 220,709	220,720	D81-10 : 220,731
D 8-96 : 220,677	220,688	220,699	220,710	D54-6 : 220,721	D83-8 : 220,732
166 : 220,678	220,689	220,700	D44-1 : 220,711	D55-1 : 220,722	D87-1 : 220,733
D 9-44 : 220,679	D15-11 : 220,690	D29-23 : 220,701	9 : 220,712	D56-4 : 220,723	220,734
62 : 220,680	D22-6 : 220,691	D33-2 : 220,702	D48-2 : 220,713	D57-1 : 220,724	220,735
103 : 220,681	D26-1 : 220,692	7 : 220,703	16 : 220,714	220,725	220,736
219 : 220,682	5 : 220,693	14 : 220,704	20 : 220,715	D64-11 : 220,726	D89-1 : 220,737
222 : 220,683	13 : 220,694	19 : 220,705	220,716	D71-1 : 220,727	D90-20 : 220,738
D13-1 : 220,684	220,695	26 : 220,706	220,717	220,728	220,739
	220,696		220,718	220,729	D96-13 : 220,740

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

1 : 3.578,126	6 : 3.578,274	9 : 3.578,396	17 : 3.578,169	18 : 3.578,660	24 : 3.578,697
3.578,433	3.578,320	3.578,400	3.578,176	3.578,674	25 : 3.577,892
2 : 3.578,087	3.578,327	3.578,500	3.578,178	19 : 3.577,857	3.578,072
4 : 3.577,977	3.578,339	3.578,526	3.578,189	3.578,159	3.578,210
3.578,110	3.578,346	3.578,536	3.578,204	3.578,191	3.578,227
3.578,315	3.578,347	3.578,562	3.578,206	3.578,225	3.578,294
3.578,514	3.578,353	3.578,564	3.578,217	3.578,497	3.578,298
5 : 3.577,921	3.578,367	3.578,610	3.578,218	20 : 3.578,058	3.578,299
3.578,047	3.578,378	3.578,673	3.578,231	3.578,325	3.578,301
3.578,182	3.578,380	3.578,694	3.578,232	21 : 3.578,016	3.578,414
6 : 3.577,855	3.578,395	3.578,703	3.578,238	3.578,131	3.578,443
3.577,859	3.578,409	3.578,709	3.578,242	3.578,133	3.578,447
3.577,897	3.578,411	3.578,710	3.578,253	3.578,279	3.578,448
3.577,902	3.578,412	3.578,713	3.578,262	3.578,323	3.578,449
3.577,904	3.578,424	3.578,734	3.578,277	3.578,337	3.578,450
3.577,930	3.578,432	3.578,735	3.578,286	3.578,374	3.578,458
3.577,955	3.578,434	10 : 3.578,048	3.578,287	3.578,511	3.578,464
3.577,983	3.578,463	3.578,481	3.578,297	3.578,593	3.578,483
3.577,988	3.578,467	3.578,568	3.578,306	3.578,642	3.578,540
3.577,989	3.578,569	3.578,597	3.578,316	22 : 3.577,850	3.578,576
3.577,994	3.578,571	3.578,618	3.578,333	3.578,345	3.578,603
3.578,004	3.578,582	3.578,624	3.578,344	3.578,436	3.578,626
3.578,020	3.578,583	3.578,701	3.578,360	3.578,516	3.578,635
3.578,030	3.578,611	11 : 3.577,980	3.578,361	3.578,543	3.578,662
3.578,039	3.578,644	3.578,009	3.578,377	3.578,606	3.578,727
3.578,045	3.578,688	3.578,349	3.578,394	3.578,689	26 : 3.577,840
3.578,051	7 : 3.577,950	12 : 3.577,843	3.578,446	23 : 3.578,451	3.577,905
3.578,060	8 : 3.577,900	3.577,906	3.578,452	3.578,493	3.577,913
3.578,070	3.578,082	3.577,979	3.578,469	24 : 3.577,856	3.577,962
3.578,081	3.578,139	3.578,037	3.578,488	3.577,918	3.577,964
3.578,102	3.578,156	3.578,219	3.578,498	3.577,925	3.577,966
3.578,106	3.578,596	3.578,309	3.578,505	3.577,926	3.577,973
3.578,107	9 : 3.577,846	3.578,479	3.578,507	3.577,949	3.577,990
3.578,135	3.577,907	13 : 3.578,001	3.578,574	3.578,006	3.578,026
3.578,138	3.577,919	3.578,094	3.578,584	3.578,010	3.578,027
3.578,146	3.577,952	3.578,209	3.578,587	3.578,011	3.578,043
3.578,161	3.577,965	15 : 3.577,836	3.578,589	3.578,183	3.578,056
3.578,163	3.578,022	17 : 3.577,837	3.578,672	3.578,216	3.578,111
3.578,175	3.578,023	3.577,847	18 : 3.577,911	3.578,239	3.578,112
3.578,195	3.578,028	3.577,901	3.577,933	3.578,314	3.578,123
3.578,198	3.578,068	3.577,910	3.577,934	3.578,322	3.578,141
3.578,207	3.578,075	3.577,916	3.577,940	3.578,343	3.578,171
3.578,226	3.578,128	3.577,920	3.578,033	3.578,385	3.578,179
3.578,241	3.578,130	3.577,969	3.578,034	3.578,418	3.578,186
3.578,244	3.578,134	3.577,975	3.578,064	3.578,429	3.578,211
3.578,247	3.578,144	3.578,000	3.578,103	3.578,489	3.578,230
3.578,265	3.578,223	3.578,007	3.578,280	3.578,588	3.578,259
3.578,267	3.578,369	3.578,040	3.578,324	3.578,614	3.578,264
3.578,268	3.578,373	3.578,098	3.578,585	3.578,643	3.578,295
3.578,269	3.578,393	3.578,120	3.578,634	3.578,647	3.578,313

26 : 3,578,354	34 : 3,578,214	36 : 3,578,200	39 : 3,577,948	42 : 3,577,881	48 : 3,577,844
3,578,357	3,578,224	3,578,229	3,578,018	3,577,886	3,577,849
3,578,358	3,578,234	3,578,255	3,578,024	3,577,893	3,577,871
3,578,366	3,578,235	3,578,257	3,578,050	3,577,903	3,577,894
3,578,397	3,578,237	3,578,258	3,578,052	3,577,982	3,578,003
3,578,404	3,578,271	3,578,278	3,578,053	3,578,017	3,578,029
3,578,484	3,578,272	3,578,300	3,578,089	3,578,038	3,578,035
3,578,549	3,578,290	3,578,308	3,578,095	3,578,115	3,578,076
3,578,616	3,578,329	3,578,310	3,578,142	3,578,140	3,578,077
3,578,630	3,578,341	3,578,311	3,578,166	3,578,177	3,578,079
3,578,682	3,578,363	3,578,317	3,578,180	3,578,201	3,578,080
27 : 3,577,883	3,578,389	3,578,319	3,578,184	3,578,213	3,578,083
3,577,895	3,578,398	3,578,330	3,578,199	3,578,228	3,578,090
3,577,935	3,578,421	3,578,388	3,578,321	3,578,246	3,578,093
3,577,992	3,578,439	3,578,410	3,578,355	3,578,249	3,578,113
3,578,114	3,578,444	3,578,425	3,578,359	3,578,250	3,578,284
3,578,194	3,578,462	3,578,445	3,578,375	3,578,273	3,578,307
3,578,275	3,578,466	3,578,470	3,578,383	3,578,351	3,578,405
3,578,550	3,578,473	3,578,471	3,578,403	3,578,370	3,578,407
3,578,622	3,578,476	3,578,487	3,578,406	3,578,379	3,578,417
3,578,684	3,578,477	3,578,504	3,578,422	3,578,382	3,578,515
3,578,717	3,578,552	3,578,508	3,578,426	3,578,384	3,578,567
28 : 3,578,190	3,578,591	3,578,517	3,578,442	3,578,391	3,578,575
29 : 3,577,932	3,578,592	3,578,525	3,578,455	3,578,415	3,578,590
3,578,108	3,578,594	3,578,542	3,578,456	3,578,419	3,578,681
3,578,153	3,578,598	3,578,556	3,578,482	3,578,427	3,578,702
3,578,243	3,578,599	3,578,558	3,578,499	3,578,468	49 : 3,578,185
3,578,318	3,578,600	3,578,560	3,578,501	3,578,472	3,578,252
3,578,381	3,578,608	3,578,561	3,578,509	3,578,474	3,578,416
3,578,459	3,578,609	3,578,579	3,578,510	3,578,478	50 : 3,578,118
3,578,460	3,578,615	3,578,595	3,578,545	3,578,520	51 : 3,577,863
3,578,461	3,578,617	3,578,639	3,578,577	3,578,537	3,578,245
3,578,518	3,578,666	3,578,652	3,578,601	3,578,563	3,578,328
3,578,521	3,578,670	3,578,653	3,578,619	3,578,613	3,578,331
3,578,548	3,578,675	3,578,661	3,578,627	3,578,620	3,578,342
3,578,581	3,578,690	3,578,665	3,578,637	3,578,621	3,578,640
3,578,629	3,578,705	3,578,669	3,578,645	3,578,628	53 : 3,577,960
3,578,641	3,578,711	3,578,678	3,578,695	3,578,638	3,577,972
3,578,731	3,578,712	3,578,685	40 : 3,577,885	3,578,650	3,578,044
30 : 3,578,085	3,578,714	3,578,686	3,577,915	3,578,656	3,578,266
31 : 3,578,326	35 : 3,578,008	3,578,687	3,578,165	3,578,667	3,578,570
3,578,348	36 : 3,577,861	3,578,696	3,578,402	3,578,676	3,578,651
32 : 3,578,162	3,577,864	3,578,708	3,578,494	3,578,677	54 : 3,578,440
33 : 3,578,220	3,577,898	3,578,726	3,578,607	3,578,679	3,578,721
34 : 3,577,889	3,577,908	37 : 3,577,858	3,578,646	3,578,683	55 : 3,577,971
3,577,923	3,577,945	3,577,942	3,578,704	3,578,723	3,578,059
3,577,936	3,577,957	3,577,995	41 : 3,577,853	3,578,725	3,578,155
3,577,959	3,577,976	3,577,996	3,577,951	3,578,728	3,578,167
3,578,002	3,577,981	3,577,998	3,577,974	43 : 3,578,205	3,578,168
3,578,012	3,577,984	3,577,999	3,578,096	44 : 3,578,233	3,578,196
3,578,021	3,577,985	3,578,148	3,578,151	45 : 3,578,546	3,578,248
3,578,046	3,577,987	3,578,532	3,578,254	3,578,152	3,578,293
3,578,067	3,577,993	39 : 3,577,839	3,578,285	3,578,281	3,578,475
3,578,127	3,578,101	3,577,848	3,578,522	3,578,491	3,578,533
3,578,136	3,578,105	3,577,866	3,578,534	3,578,492	3,578,559
3,578,154	3,578,143	3,577,882	42 : 3,577,862	3,578,551	3,578,668
3,578,157	3,578,145	3,577,917	3,577,867	3,578,716	56 : 3,577,946
3,578,164	3,578,181	3,577,931	3,577,872	47 : 3,577,943	

Design Patents

5 : 220,721	6 : 220,727	17 : 220,697	26 : 220,734	37 : 220,698	42 : 220,687
6 : 220,677	220,730	220,699	29 : 220,690	39 : 220,693	44 : 220,731
220,681	8 : 220,722	220,717	34 : 220,680	220,694	48 : 220,711
220,684	9 : 220,726	220,724	36 : 220,705	220,707	49 : 220,728
220,685	12 : 220,715	18 : 220,716	220,706	220,708	53 : 220,740
220,686	220,732	25 : 220,692	220,723	220,718	55 : 220,704
220,688	17 : 220,675	220,702	220,725	42 : 220,738	
220,691	220,695	220,709	220,733	220,678	
220,700	220,696	220,729	220,737	220,682	

U.S. GOVERNMENT PRINTING OFFICE: O—1971

OFFICIAL GAZETTE of the UNITED STATES PATENT OFFICE

May 18, 1971

Volume 886

Number 3

CONTENTS

Issue of May 18, 1971	423
Patents and Trademark Notices	
Appeal Briefs Under Rules 192 and 193(b)	424
Title 37—Patents, Trademarks, and Copyrights—Conflicting Claims	424
Patent Suits	424
Patent Notices	
Patents Available for Licensing or Sale	426
Registration to Practice	426
Certificates of Correction for the Week of May 18, 1971	426
Condition of Patent Applications	427
Reissue Patents Granted	428
Patents Granted	
General and Mechanical	429
Chemical	565
Design Patents Granted	626
Index of Patentees	PI 1
Indices of Reissues and Designs	PI 30
Classification of	
Patents (Including Reissues)	PI 33
Designs	PI 34
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 35
Designs	PI 36

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENTS SECTION), issued weekly, subscription \$89.00 per annum, foreign mailing \$22.25 additional; single copies \$2.00 each.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$17.00 per annum, foreign mailing \$4.25 additional; single copies 40 cents each.

CIRCULARS OF GENERAL INFORMATION concerning PATENTS or TRADEMARKS, price 15 cents each.

PRINTED COPIES OF PATENTS are furnished by the Patent Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS and DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents, Washington, D.C., 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S. Code P.O.

PATENT OFFICE NOTICES

Appeal Briefs Under Rules 192 and 193(b)

Appellants are reminded that their briefs in appealed cases must be responsive to every ground of rejection stated by the examiner, including new grounds stated in his answer.

Where an appellant fails to respond by way of brief or reply brief to any ground of rejection, and it appears that the failure is inadvertent, appellant shall be notified that he is allowed one month to correct the defect by filing a supplemental brief. Where this procedure has not been followed, the Board of Appeals should remand the application to the examiner for compliance. When the record clearly indicates intentional failure to respond by brief to any ground of rejection, for example, by failure to file a supplemental brief within the one-month period allowed for that purpose, the examiner should inform the Board of Appeals of this fact in his answer and merely specify the claims affected.

Where the failure to respond by brief appears to be intentional, the Board of Appeals may dismiss the appeal as to the claims involved. Oral argument at a hearing will not remedy such deficiency of a brief.

This notice supersedes the notices of May 4, 1966, 826 O.G. 1060, and of Oct. 20, 1966, 833 O.G. 1.

WILLIAM E. SCHUYLER, Jr.,
Commissioner of Patents.

Apr. 26, 1971.

TITLE 37—PATENTS, TRADEMARKS, AND COPYRIGHTS

Chapter I—Patent Office, Department of Commerce

PART 1—RULES OF PRACTICE IN PATENT CASES

PART 3—FORMS FOR PATENT CASES

Conflicting Claims

These rule changes are intended to provide: (1) a basis for requiring a determination of priority without an interference by the common owner of a plurality of applications, or patent and applications, containing conflicting claims, and (2) a basis for requiring inclusion of a common ownership clause in all terminal disclaimers filed to obviate a double patenting rejection.

The proposal to amend Title 37, Code of Federal Regulations, by revising §§ 1.78 and 1.321 and by adding a new § 3.53 was published in the December 31, 1970, issue of the Federal Register (35 F.R. 20011).

All interested persons were given an opportunity to participate in the rule making process by submission of comments in writing and in person at an oral hearing held on February 19, 1971. Changes have been made in the text of the original proposal as a result of these comments.

In consideration of the comments received and pursuant to the authority contained in section 6 of the Act of July 19, 1952 (66 Stat. 793; 35 U.S.C. 6), Parts 1 and 3 of Title 37, Code of Federal Regulations, are hereby amended as follows:

1. In § 1.78, paragraph (b) has been revised and paragraph (c) has been added to read as follows:

§ 1.78 *Cross-references to other applications.*

(b) Where two or more applications filed by the same applicant contain conflicting claims, elimination of such claims from all but one application may be required in the absence of good and sufficient reason for their retention during pendency in more than one application.

(c) Where two or more applications, or an application and a patent naming different inventors and owned by the same party contain conflicting claims, the assignee may be called upon to state which named inventor is the prior inventor. In addition to making said statement, the assignee may also explain why an interference should be declared or that no conflict exists in fact.

2. Section 1.321 is revised to read as follows:

§ 1.321 *Statutory disclaimer.*

(a) A disclaimer under 35 U.S.C. 253 must identify the patent and the claim or claims which are disclaimed, and be signed by the person making the disclaimer, who shall state therein the extent of his interest in the patent. A disclaimer which is not a disclaimer of a complete claim or claims may be refused recordation. A notice of the disclaimer is published in the OFFICIAL GAZETTE and attached to the printed copies of the specification. In like manner any patentee or applicant may disclaim or dedicate to the public the entire term, or any terminal part of the term, of the patent granted or to be granted.

(b) A terminal disclaimer, when filed in an application to obviate a double patenting rejection, must include a provision that any patent granted on that application shall be enforceable only for and during such period that said patent is commonly owned with the application or patent which formed the basis for the rejection. See § 1.21 for fee.

3. A new § 3.53 is added, which reads as follows:

§ 3.53 *Terminal disclaimers in applications.*

To the Commissioner of Patents:

Your petitioner, _____, residing at _____ in the county of _____ and State of _____ represents that he is (here state exact interest of the disclaimant and, if he is an assignee, set out the libel and page or reel and frame where the assignment is recorded) of application Serial No. _____, filed on the _____ day of _____, 19____ for _____. Your petitioner, _____, hereby disclaims the terminal part of any patent granted on the above-identified application, which would extend beyond the expiration date of Patent No. _____ and hereby agrees that any patent so granted on the above-identified application shall be enforceable only for and during such period that the legal title to said patent shall be the same as the legal title to United States Patent No. _____, this agreement to run with any patent granted on the above identified application and to be binding upon the grantee, its successors or assigns.

Effective date. This revision shall become effective on April 30, 1971.

WILLIAM E. SCHUYLER, Jr.,
Commissioner of Patents.

Approved: April 12, 1971.

JAMES H. WAKELIN, Jr.,
Assistant Secretary for
Science and Technology.

[FR Doc. 71-5418; Filed 4-16-71; 8:51 am]

Published in 36 F.R. 7312; Apr. 17, 1971

Patent Suits

Notices under 35 U.S.C. 290; Patent Act of 1952

2,809,092, Zimmerley and Malouf, EXTRACTION OF RHEINIUM INCIDENTAL TO MANUFACTURE OF MOLYBDENUM OXIDE, filed Dec. 8, 1970, D.C. Colo. (Denver), Doc. C-2763, Kennecott Copper Corporation v. The S. W. Shattuck Chemical Co., Inc. and Engelhard Minerals and Chemical Corporation.

2,828,449, I. L. Kerper, SAFETY FEATURE FOR ELECTRIC WATERTIGHT DOOR SYSTEMS, filed Dec. 11, 1970, D.C., C.D. Calif. (Los Angeles), Doc. 70-2777-F, Irving L. Kerper v. Grace Line, Continental Equipment Corp. et al.

2,895,003, G. M. Rapata, STRAIN RELIEF GROMMET; 2,930,840, F. Klumpp, Jr., STRAIN RELIEF BUSHING, filed May 12, 1967, D.C., N.D. Ill. (Chicago), Doc. 67c801, Heyman Manufacturing Company v. Richlock Corporation et al. Order on stipulation, dismissed and judgment by consent, Dec. 4, 1970.

MAY 18, 1971

U. S. PATENT OFFICE

425

2,907,585, Sornberger and Wakeman, MANIFOLDING ASSEMBLIES, filed Aug. 6, 1968, D.C., S.D. Fla. (Miami), Doc. 68-934-TC, Moore Business Forms, Inc. v. Gulfstream Press, Inc. Judgment by consent, patent valid and infringed by defendant. Defendant's counterclaim dismissed with prejudice, Nov. 18, 1970.

2,930,840. (See 2,895,003.)

3,045,910, H. M. McLearn, AUTOMATIC COUNTING MACHINE, filed Dec. 3, 1970, D.C., N.D. Fla. (Jacksonville), Doc. 70-249-Orl-C, American Machinery Corporation v. FMC Corporation.

3,096,048, P. E. Yost, HEATED GAS GENERATOR FOR BALLOON; 3,131,889, same, BALLOON STRUCTURE WITH RELEASE MECHANISM; 3,229,932, same, MANEUVERING VALVE FOR HOT AIR BALLOON, filed Dec. 17, 1970, D.C., C.D. Calif. (Los Angeles), Doc. 70-2841-DWW, Raven Industries, Inc. v. Donald L. Piccard.

3,111,691, Luger and Luger, SECTIONAL BOAT STRUCTURE, filed Nov. 18, 1970, D.C. Minn. (Minneapolis), Doc. 4-70-C-497, Luger Industries, Inc. v. Commodore Kits and Donald Simerson.

3,131,889. (See 3,096,048.)

3,146,319, W. O. Stanton, MAGNETIC PHONOGRAPH PICKUP WITH COMPENSATING POLE PIECE ARRANGEMENT; 3,297,831, same, MAGNETIC STEREOGRAPHIC PHONOGRAPH PICKUP, filed Oct. 8, 1970, D.C., S.D.N.Y., Doc. 70-C-4372, Pickering & Company Inc. v. Qualitone Industries, Inc. Consent order, defendant perpetually enjoined, Dec. 7, 1970.

3,150,216, W. Z. Saleer, METHOD FOR MAKING PLASTIC ARTICLES; 3,248,757, same, APPARATUS FOR MAKING PLASTIC ARTICLES, filed Dec. 8, 1970, D.C. Conn. (Bridgeport), Doc. B-226-C, American Universal, Inc. v. Susemihl Magnesium Etching Co., Inc. and Swan Engineering Co., Inc.

3,157,157, Clay and Letson, METHOD AND APPARATUS FOR DISPENSING FEED TO LIVESTOCK, filed Mar. 23, 1970, D.C., N.D. Ill. (Chicago), Doc. 70c6S7, Clay Equipment Corporation v. The De Laval Separator Company. Consent judgment, case dismissed, Dec. 15, 1970.

3,161,908, P. Walach, HYDRAULIC DOOR CLOSER, filed Nov. 10, 1970, D.C., N.D. Ill. (Chicago), Doc. 70c2804, Monterey Manufacturing Co. v. Hartzell Manufacturing, Inc. et al.

3,229,932. (See 3,096,048.)

3,248,757. (See 3,150,216.)

3,296,052, A. M. Bechtold, MEANS AND METHOD FOR POSTFORMING PLASTIC LAMINATED PRODUCTS, filed Dec. 16, 1970, D.C., M.D. Fla. (Tampa), Doc. 70-572-C, Roberts Consolidated Industries Inc. v. Stewart Lochr, doing business as Stewart Lochr Laminate Tool Mfg.

3,297,831. (See 3,146,319.)

3,325,018, L. A. Wright, ARTICULATING CRANE, filed Dec. 7, 1970, D.C., W.D. Wash. (Seattle), Doc. 9371, Star Iron & Steel Co. and International Terminal v. Freuhauf Corporation.

3,343,375, L. K. Quick, LATENT HEAT REFRIGERATION DEFROSTING SYSTEM, filed Oct. 28, 1970, D.C. Del. (Wilmington), Doc. 4002, Hussman Refrigerator Co., and Pet Incorporated v. Hillman Coal & Coke Company, and Melchior, Armstrong, Dessau, Inc.

3,359,116, L. L. Little, PROCESS OF MAKING SOUR CREAM TYPE PRODUCTS AND CREAM CHEESE; 3,378,375, same, METHOD OF PREPARING ACIDIFIED DAIRY PRODUCTS, filed Dec. 3, 1970, D.C., S.D. Ohio (Cincinnati), Doc. 7771, The Battelle Development Corp. v. Diamond-Shamrock Corp.

3,378,375. (See 3,359,116.)

3,409,000, Brader and Tanasse, SYSTEM FOR HEATING LARGE VOLUMES OF AIR, filed Dec. 2, 1970, D.C., E.D. Wash. (Yakima), Doc. 2676-C, Redi-Fire Heating, Inc. v. Orchard Rite, Inc.

3,439,452, O. Kain, MIRRORED DOOR APPARATUS, filed Dec. 11, 1970, D.C., C.D. Calif. (Los Angeles), Doc. 70-2781-EC, Oscar Kain v. Manufacturers Mirror Door Co., Inc.

3,444,621, E. C. Fletcher, ORTHODONTIC APPLIANCE, filed May 15, 1970, D.C.N.J. (Newark), Doc. 616-70, G.A.C. International, Inc. v. Unitek Corporation. Consent judgment dismissing complaint, Dec. 10, 1970.

3,458,102, Zanger and Szasz, SEMICONDUCTOR WAFER PICKUP AND BONDING TOOL, filed Nov. 30, 1970, D.C., C.D. Calif. (Los Angeles), Doc. 70-2681-CC, Kulicke & Soffa Industries, Inc. v. Gaiser Tool Company.

3,491,446, Griffiths and Martin, EXTENSION DEVICE, filed May 13, 1970, D.C., N.D. Calif. (San Francisco), Doc. C70-1011-AJZ, Keith K. Griffiths and James D. Martin v. Kalabar, Inc. Consent judgment, plaintiff owner of patent and defendant has infringed, June 17, 1970.

3,494,253, Hood and Trulitt, METALLIC STRIP MILLING MACHINE, filed Dec. 15, 1970, D.C., E.D.N.Y. (Brooklyn), Doc. 70-C-1517, Metals Engineering Company v. North American Specialties Corporation.

Patents Available for Licensing or Sale

- D. 217,444. WHEELED CARRIER. Leo Stein, Box 1063, F.D.R. station, New York, N.Y., 10022.
- 3,191,513. FOLDING BELLOWS WITH INTERLOCKING CORNERS FOR PHOTOGRAPHIC DEVICES. Correspondence to: Central Trust Company Rochester N.Y., 44 Exchange St., Rochester, N.Y., 14614. Attn: William K. Sjea, Asst. Vice Pres.
- 3,225,761. FATIGUE SUPPORT. Robert Swensen, 120 Poincianna Drive, Martinez, Ga., 30907.
- 3,420,503. DEVICE FOR MAKING A CONTROLLED DESCENT. T/Sgt. Otto Stangl, Lot 23, Trailer Park, Langley A.F.B., Va., 23365.
- 3,535,667. ELECTRICAL SAFETY DEVICE. Henry C. Harnish, Jr., and Anthony J. Osello, Elcock Ave., Boonton, N.J., 07005.
- 3,559,328. LINE-CASTER ATTACHMENT FOR FISHING ROD. Royal B. Leshar, 3200 W. 29th Turnagain S., Anchorage, Alaska, 99503.
- 3,559,988. SPRING TYPE ARM EXERCISING DEVICE. Russell C. Greenlees, 316 E. Shadbolt St., Lake Orion, Mich., 48035.
- 3,568,355. SLIDING FISHING SINKER. Jack V. Hassell, 902 Del Paso Blvd., Space #3, Sacramento, Calif., 95815.
- 3,570,176. TOY MACHINE GUN. Henry J. Palmer, 699 N. Broad St., Philadelphia, Pa., 19123.
- 3,570,793. FISH POLE HOLDER FOR CASTING-SPINNING-DEEP SEA FISHING ROD. Joseph T. Shackel, 14636 Bringard, Detroit, Mich., 48205.
- 3,577,386. PROTECTIVE HEADGEAR. Norma E. Fisher, Rte. #1, Cedar, Minn., 55011.

The following 2 patents are offered by: Russell W. Weidenbacker, Box 153, Haverford, Pa., 19041.

- 3,558,149. ELASTOMERIC-BONDED ICE SKATE.
- 3,545,778. SAFETY AND DECORATIVE COVER FOR ICE SKATES.

The following 2 patents are offered by: Zed Cunningham, 4101 Green Court, Cleveland, Ohio, 44104.

- 3,038,528. TIRE MOUNTING APPARATUS.
- 3,347,998. TELEPHONE HANDSET HOLDER.
- The following 3 patents are offered by: John W. Barnd, 32 Hollybrook Road, Paramus, N.J.
- 3,351,128. MULTI-ZONE TEMPERATURE CONTROL.
- 3,496,991. FLUID TEMPERATURE REGULATING METHOD AND APPARATUS.
- 3,515,345. MULTI-ZONE TEMPERATURE CONTROL.

General Electric Company is prepared to grant non-exclusive licenses under the following 19 patents upon reasonable terms to domestic manufacturers.

Applications for license under the following 2 patents may be addressed to: Patent Counsel, Mobile Radio Department, General Electric Co., Lynchburg, Va., 24502.

- 3,054,966. CRYSTAL CONTROLLED OSCILLATOR WITH TEMPERATURE COMPENSATING MEANS.
- 3,543,053. ELECTRONIC SINGLE-POLE, DOUBLE-THROW SWITCH.

Applications for license under the following 3 patents may be addressed to: Department Patent Counsel, Apollo & Ground Systems, General Electric Co., P.O. Box 2500, Daytona Beach, Fla., 32015.

- 3,550,114. PREWIRED ADDRESS SEQUENCER FOR SUCCESSIVE APPROXIMATION ANALOG TO DIGITAL CONVERTER.
- 3,555,298. ANALOG TO PULSE DURATION CONVERTER.
- 3,564,538. MULTIPLE SLOPE ANALOG TO DIGITAL CONVERTER.

Applications for license under the following 14 patents may be addressed to: Patent Counsel, Audio Electronics Business Department, Bldg. 1, Electronics Park, General Electric Company, Syracuse, N.Y., 13201.

- 3,561,766. SWITCH ACTUATING MECHANISM FOR RECORD PLAYER.
- 3,560,001. TURNTABLE AND TONE ARM MECHANISM FOR RECORD PLAYER.

- 3,492,004. GUIDING STRUCTURE FOR PHONOGRAPH TONE ARMS.
- 3,495,836. PORTABLE RECORDING APPARATUS.
- 3,495,839. TURNTABLE RECESS FOR RECORD REMOVAL.
- 3,501,214. LID LATCH FOR PHONOGRAPH.
- 3,500,219. AUDIO AMPLIFIER.
- 3,521,889. RECORDING APPARATUS.
- 3,527,530. SLIDE VIEWER.
- 3,531,130. PIVOTAL SUPPORT ASSEMBLY FOR PHONOGRAPH RECORD AND PLAYBACK ARMS.
- 3,417,322. SIMPLIFIED PIEZORESISTIVE FORCE SENSING DEVICE.
- D. 218,911. PORTABLE PHONOGRAPH OR SIMILAR ARTICLE.
- 3,498,659. MULTISECTION CASING AND LATCH MECHANISM THEREFOR.
- 3,534,180. PHONOGRAPH PREAMPLIFIER WITH DIRECT DC BIAS COUPLING BETWEEN THE TRANSISTOR AND PIEZORESISTIVE PICKUP.

Registration to Practice

The following list contains the names of applicants for registration to practice before the United States Patent Office who attained passing grades in the examinations of March 31, and September 15, 1970, respectively. Information tending to affect the eligibility of any of said applicants on moral or ethical grounds should be furnished the Commissioner of Patents on or before June 14, 1971.

ROBERT GOTTSCHALK,
Chairman, Committee on Enrollment.

LIST OF APPLICANTS

- Baehr, Fred J., Jr., 212 Monticello Drive, Export, Pa. 15632
- Blodgett, Gerry A., 39 Highland St., Worcester, Mass. 01608
- Elpper, Eugene B., 233 Grandview Ave., Pitman, N.J. 08071
- Fleming, Frederick A., 1860 Highland Parkway, St. Paul, Minn. 55116
- Hagopian, Robert W., 109 Hemenway Ct., Boston, Mass. 02115
- Keller, John J., 111 S. 4th St., Bethpage, N.Y. 11714
- Krawitz, Willie, 3001 Chapel Hill Rd., Orange, Calif. 92667
- Lloyd, Lewis L., 80 Main St., Landisville, Pa. 17538
- O'Reilly, David, 327 Riley St., Falls Church, Va. 22046
- Penland, Raphael B., 1305 Parkington Lane, Bowie, Md. 20715
- Skinkiss, Ralph J., 1255 Flicker Drive, Florissant, Mo. 63031
- Spicer, James M., 273 East Drive, Oak Ridge, Tenn. 37830
- Stott, Ronald A., 206 Helen St., North Syracuse, N.Y. 13212
- Thomas, Gilbert A., 14711 Mimosa Lane, Tustin, Calif. 92680
- Walpert, Gary A., 1321 Worcester Road, Framingham, Mass. 01701
- Wildenstelter, Otto, 2207 Seminary Road, Silver Spring, Md. 20910

Certificates of Correction for the Week of May 18, 1971

- | | | | |
|------------|-----------|-----------|-----------|
| Re. 26,963 | 3,544,327 | 3,556,147 | 3,560,396 |
| 3,240,799 | 3,544,610 | 3,556,220 | 3,560,535 |
| 3,372,414 | 3,544,695 | 3,556,314 | 3,560,572 |
| 3,375,414 | 3,546,194 | 3,556,512 | 3,560,576 |
| 3,440,051 | 3,546,199 | 3,556,904 | 3,560,639 |
| 3,485,797 | 3,546,980 | 3,556,923 | 3,560,751 |
| 3,496,244 | 3,547,684 | 3,557,109 | 3,560,793 |
| 3,499,008 | 3,549,592 | 3,557,117 | 3,561,108 |
| 3,503,758 | 3,549,608 | 3,557,207 | 3,561,369 |
| 3,509,211 | 3,550,434 | 3,557,460 | 3,561,665 |
| 3,517,558 | 3,551,429 | 3,557,473 | 3,561,773 |
| 3,521,672 | 3,551,525 | 3,557,648 | 3,562,160 |
| 3,523,768 | 3,551,593 | 3,557,881 | 3,562,282 |
| 3,534,404 | 3,551,688 | 3,557,916 | 3,562,338 |
| 3,535,134 | 3,552,409 | 3,558,335 | 3,562,348 |
| 3,536,137 | 3,552,764 | 3,558,418 | 3,562,580 |
| 3,536,749 | 3,553,428 | 3,558,585 | 3,562,785 |
| 3,537,852 | 3,553,614 | 3,558,624 | 3,563,448 |
| 3,538,184 | 3,554,046 | 3,558,692 | 3,563,604 |
| 3,539,366 | 3,554,404 | 3,558,747 | 3,563,738 |
| 3,539,461 | 3,554,430 | 3,558,811 | 3,563,966 |
| 3,542,818 | 3,554,502 | 3,558,985 | 3,565,165 |
| 3,542,926 | 3,554,624 | 3,559,094 | 3,565,671 |
| 3,543,704 | 3,555,097 | 3,559,546 | |
| 3,543,735 | 3,556,081 | 3,560,177 | |

PATENT EXAMINING CORPS

R. A. WAHL, Assistant Commissioner
F. H. BRONAUGH, Deputy Assistant Commissioner

CONDITION OF PATENT APPLICATIONS AS OF MAY 4, 1971

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—M. STERMAN, Director..... Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	1-02-70
GENERAL ORGANIC CHEMISTRY, GROUP 120—I. MARCUS, Director..... Heterocyclic; Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carbonylic Acid Esters; Acid Anhydrides; Acid Halides.	9-02-69
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—L. J. BERCOVITZ, Director..... Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Natural Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g.: Coating; Molding; Ink; Adhesive and Abrading Compositions; Molding, Shaping, and Treating Processes.	2-10-70
COATING AND LAMINATING, BLEACHING, DYEING AND PHOTOGRAPHY, GROUP 160—A. P. KENT, Director..... Coating; Processes and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; Bleaching; Dyeing and Photography.	2-03-70
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—W. B. KNIGHT, Director..... Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	10-17-69
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS AND RELATED ELEMENTS, GROUP 210—N. ANSHER, Director..... Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Miscellaneous.	8-17-70
SECURITY, GROUP 220—R. L. CAMPBELL, Director..... Ordnance, Firearms and Ammunition; Radar, Underwater Signaling, Directional Radio, Torpedoes, Seismic Exploring, Radio-Active Batteries; Nuclear Reactors, Powder Metallurgy, Rocket Fuels; Radio-Active Material.	12-11-69
INFORMATION TRANSMISSION, STORAGE AND RETRIEVAL, GROUP 230—J. F. COUCH, Director..... Communications; Multiplexing Techniques; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	3-13-70
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—W. L. CARLSON, Director..... Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	3-03-70
PHYSICS, GROUP 280—R. L. EVANS, Director..... Photography; Sound and Lighting; Indicators and Optics; Measuring and Testing; Geometrical Instruments.	1-21-70
DESIGNS, GROUP 290—R. L. CAMPBELL, Director..... Industrial Arts; Household, Personal and Fine Arts.	6-03-70
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—A. BERLIN, Director..... Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet and Web Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Railways and Railway Equipment; Brakes; Rigid Flexible and Special Receptacles and Packages.	3-09-70
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—D. J. STOCKING, Director..... Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion—Bonding, Metal Founding; Metallurgical Apparatus; Plastics Working Apparatus; Plastic Block and Earthenware Apparatus; Machine Tools for Shaping or Dividing; Work and Tool Holders Woodworking; Tools; Cutlery; Jacks.	1-02-70
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—A. RUEGG, Director..... Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Butchering; Earth Working and Excavating; Fishing, etc.; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Stationery; Information Dissemination.	2-02-70
HEAT, POWER AND FLUID ENGINEERING, GROUP 340—C. F. GAREAU, Director..... Power Plants; Combustion Engines; Fluid Motors; Pumps; Turbines; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Vaporizing; Temperature and Humidity Regulation; Machine Elements; Power Transmission; Fluid Handling; Lubrication; Joint Packing.	6-08-70
CONSTRUCTIONS, SUPPORTS, TEXTILES, CLEANING, GROUP 350—T. J. HICKEY, Director..... Joints; Fasteners; Rod, Pipe and Electrical Connectors; Miscellaneous Hardware; Locks; Building Structures; Closure Operators; Bridges; Closures; Earth Engineering; Drilling; Mining; Furniture; Receptacles; Supports; Cabinet Structures; Centrifugal Separations; Cleaning; Coating; Pressing; Agitating; Foods; Textiles; Apparel and Shoes; Sewing Machines; Winding and Reeling.	1-06-70

Expiration of patents: The patents within the range of numbers indicated below expire during May 1971, except those which may have expired earlier due to shortened terms under the provisions of Public Law 600, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents..... Numbers 2,677,129 to 2,679,644, inclusive
Plant Patents..... Numbers 1,274 to 1,281, inclusive

REISSUES

MAY 18, 1971


Matter enclosed in heavy brackets **[]** appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

27,123
EXTRUDING FIBERS HAVING OXIDE SKINS
Norman E. Alber, Mentor, Ohio, and Walter E. Smith, Hingham, Mass., assignors to Clevite Corporation
Original No. 3,216,076, dated Nov. 9, 1965, Ser. No. 191,340, Apr. 30, 1962. Application for reissue May 26, 1969, Ser. No. 835,867
Int. Cl. B22d 11/00
U.S. Cl. 164-86

melt and a minor portion of a metal the oxide of which is insoluble in the melt. The oxide skin formed by extrusion into air stabilizes the molten jet pending solidification.

27,124
WOOD DRYING METHOD
Robert W. Erickson, St. Paul, Minn., assignor to The Regents of the University of Minnesota, Minneapolis, Minn.
No Drawing. Original No. 3,309,778, dated Mar. 21, 1967, Ser. No. 523,869, Feb. 1, 1966. Application for reissue Dec. 29, 1969, Ser. No. 888,180
Int. Cl. F26b 5/06
U.S. Cl. 34-5

4 Claims
A method of accelerating the drying rate of lumber, such as redwood, which is normally susceptible to damage if subjected to rapid drying at elevated temperatures. Such high moisture content lumber is subject to damage in the form of collapse and honeycombing and to shrinkage. It has been discovered that lumber may be upgraded and damage minimized when the lumber in green condition is pretreated by thorough freezing of its liquid fraction and then the pretreated lumber is dried rapidly by subjecting to conditions of low relative humidity and high temperature at least 30° F. above the critical temperature at which damage normally occurs, 110° to 120° F. in the case of redwood. Preferably at least a substantial portion of the pretreated lumber is permitted to thaw by returning to ambient temperature before rapid drying.



Metallic fibers and filaments made by extrusion of certain molten alloys into air, said alloys containing a major portion of a metal the oxide of which is soluble in the

428


PATENTS

GRANTED MAY 18, 1971

GENERAL AND MECHANICAL

3,578,736
HAT AND SWEATBAND INSERT THEREFOR
Norman L. Dootson, San Francisco, Calif., assignor to Winifred M. Colombo, Mill Valley, Calif., fractional part interest
Filed Oct. 20, 1969, Ser. No. 870,431
Int. Cl. A42b 1/02
U.S. Cl. 2-181

5 Claims




A hat having a sweatband and an elongated readily insertable and discardable insert. The insert includes a perspiration absorbent face portion and a moisture impervious back portion with an upstanding central member. The central member extends above a sweatband to expose the absorbent portion to facilitate perspiration evaporation therefrom and to provide a grasping portion whereby the insert can be readily inserted or removed.

3,578,737
MONOLITHIC SINK AND VANITY TOP COMBINATION
Kay L. Ruggles; Dale B. Gunnerson, and Howard S. Clark, Salt Lake City, Utah, assignors to American Standard Inc., New York, N.Y. Division of Ser. No. 635,477, May 2, 1967, Pat. No. 3,496,612.
Filed July 15, 1969, Ser. No. 870,995
Int. Cl. A47k 1/04

U.S. Cl. 4-166

2 Claims




An integral sink and vanity top combination of a thermosetting synthetic plastic composition, preferably of a polyester resin type, wherein the bowl area is integrally formed with the vanity top area. The bowl area is provided with an overflow passageway that extends along the sidewall of the bowl. An improved combination having one or more sink bowls is disclosed and which is manufactured by a method which includes the steps of applying appropriate

coating to the mold and thereafter applying an initial pour of the polyester resin into the mold, mounting an overflow tube in proximity to the bowl mold area, then applying a bonnet over the overflow tube and bowl area after the first pour has become tacky, and then making a second pour of the same material into the interior of the bonnet area over the first pour to form the bowl area to shape in integral assembly with the vanity top area. A mineral filler may be added to the resin for the initial pour to produce different desired finishes on the sink and vanity top combination. As the material is permitted to gel the mold is vibrated to permit entrapped gasses to escape to insure a product essentially free of pockets of entrapped air.

3,578,738
FLOOR MAT
Martin Robert Hughes, Grand Rapids, Mich., assignor to Bissell Inc., Grand Rapids, Mich.
Filed Feb. 25, 1969, Ser. No. 802,147
Int. Cl. A47l 23/22; A47g 27/02
U.S. Cl. 15-215


6 Claims



A floor mat having a thin perforate water-absorbent top layer for wiping the feet on. An intermediate spongy layer receives water, but no appreciable dirt, from the top layer and also reinforces the top layer against side loads. An imperforate tray supports both layers and serves as a water receptacle. Ribs on the tray assist in preventing sliding of the intermediate layer thereon. The tray is snap fit onto a clamping frame which also holds the edge portions of both layers in place.

3,578,739
APPARATUS FOR APPLYING ELECTROSTATIC CHARGE TO FIBROUS STRUCTURE
Henry H. George, Berkeley Heights, N.J., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
Filed May 13, 1969, Ser. No. 824,183
Int. Cl. D01d 9/00
U.S. Cl. 18-8

8 Claims



An apparatus for electrostatically charging fibrous material being forwarded in a linear path that includes an ion gun and an opposed grounded target electrode positioned on opposite sides of the path. The electrode has a surface facing the ion gun that is covered by a dielectric material having a re-

429

sistance measured at about 65° C. of between about 1×10^6 and 10^{10} ohms. Covering materials with resistances in this range minimize the disruptive effect on continuity of operation of polymer buildup on the target electrode.


3,578,740

DEWATERING PELLETIZER APPARATUS

Billy J. Redding; John T. Steadman, and Lorel J. Bragg, St. Albans, W. Va., assignors to Goodrich Gulf Chemicals, Inc.
Filed Oct. 8, 1968, Ser. No. 765,758
Int. Cl. B29f 3/00

U.S. Cl. 18-12

10 Claims



Disclosed is a dewatering pelletizer apparatus and method for dewatering and reducing the size of wet polymeric material.

The apparatus is comprised of an elongated barrel housing having an input end and an output end. Escape passages are provided in the barrel wall to permit the escape of liquid from the interior of the housing. A rotatable shaft having screw flights therein is disposed axially within the housing with one end of the shaft disposed within the output end of the housing. A bearing boss is supported within the housing and provides a bearing support for the shaft end. A generally annular screw flight section is secured to the shaft end and is defined by external and internal screw flights. The annular space between the external screw flight and the internal wall of the housing defines a discharge passage for polymeric material. The internal screw flight of the annular screw flight section is disposed closely adjacent the bearing boss thereby preventing polymeric material from entering the bearing chamber. An oil seal is provided adjacent the bearing and extends from the bearing boss into contact with the shaft. A secondary internal screw flight member is secured to the shaft closely adjacent an annular sealing wall extending from the bearing boss. The secondary internal screw flight member and the internal screw flight of the annular screw flight section cooperate to prevent polymeric material from entering the bearing chamber. A generally circular die plate is secured to said housing in blocking relationship to the output end thereof. A plurality of circumferentially spaced apertures are defined in the die plate. A high-speed cutting blade is disposed adjacent the die plate and is adapted to cut the extruded polymeric material into flakes as it emerges from the die plate.

3,578,741

VALVE FOR A PLASTIFYING DEVICE


Armin Blumer, Schwanden, Switzerland, assignor to Maschinenfabrik und Giesserei Netstal AG, Netstal, Switzerland
Filed May 27, 1969, Ser. No. 828,117
Claims priority, application Switzerland, May 31, 1968, G8198/68
Int. Cl. B29f 1/00

U.S. Cl. 18-30

11 Claims

In a plastifying device, a valve member is provided on the leading end of a worm for regulating flow to an injection head. The valve is displaceable in the axial direction of the worm and it has a head portion on its leading end, the axis of

which is offset from the axis of the worm so that, as the worm rotates, the head continuously affords a partial closure for



the end of the bore containing the worm and effects a mixing action as the material is fed to the injection head.

3,578,742

THROW-AWAY TOOL INSERT


William J. Manthei, Detroit, Mich., assignor to Kelsey-Hayes Company

Filed Feb. 27, 1969, Ser. No. 802,993

Int. Cl. B26d 1/00, 1/12

U.S. Cl. 29-96

2 Claims



A machining tool for forming a surface and including a plurality of removable tool holders each of which holds one or more throwaway tool inserts. The tool holders are constructed so as to rigidly hold the tool inserts for precluding damage to the cutting edges of these inserts. In addition, the tool holders accurately locate the individual tool inserts.

3,578,743

ALUMINUM COATED COLUMBIUM BASE ALLOYS


Elihu F. Bradley, West Hartford, Conn.; Edwin S. Bartlett, Worthington; Horace R. Ogden, and Robert I. Jaffee, Columbus, Ohio, assignors to United Aircraft Corporation, East Hartford, Conn.

Continuation of application Ser. No. 502,650, Oct. 22, 1965, now abandoned. This application Jan. 13, 1969, Ser. No. 791,880

Int. Cl. B32b 15/18

U.S. Cl. 29-194

20 Claims



PHOTOMICROGRAPH IN PLAIN LIGHT OF TRIALUMINIDE COATING OVER UNALLOYED CB

This invention provides protective coatings for columbium alloys. The coatings comprise columbium aluminide modified

by titanium and one or more of the following comodifiers Cr-, V-, Mo-, and Mo-Ta. The coatings can be provided by coating with aluminum a substrate consisting of columbium alloyed with these modifiers. The modified columbium aluminide coatings may remain on the substrate on which they are produced, or they can be removed from the original substrate and applied to other Cb-alloy substrates. Exemplary of the protective coatings of this invention are (a) a coating consisting essentially of columbium aluminide modified by 7 percent of Ti and 9 percent Mo, (b) a coating consisting essentially of columbium aluminide modified by 7 percent of Ti and 4 percent of V, (c) a coating consisting essentially of columbium aluminide modified by 8 percent of Ti and 4 percent of Cr, and (d) a coating consisting essentially of columbium aluminide modified by 8 percent of Ti, 11 percent of Ta, and 11 percent of Mo.

3,578,744

METHOD AND APPARATUS FOR ORTHODONTIC TREATMENT


Alexander J. Wildman, Eugene, Oreg., assignor to Alexo, Corp., Eugene, Oreg.

Filed Sept. 12, 1969, Ser. No. 857,351

Int. Cl. A61c 7/00

U.S. Cl. 32-14

9 Claims



After securement of brackets of novel design to teeth of a patient to be treated, impression is taken of the mouth. The impression is removed, replicas of brackets are inserted in impression and casting made of teeth which are then separated and positioned in ideal location in a model. Arch wires are then preformed to fit brackets on ideal model and after preforming, arch wire transferred to mouth of patient. Brackets have groove to receive arch wire which is locked in place by follower and snap ring.

3,578,745

DENTAL INSTRUMENT


Marcel Garnier, 6 Rue St. Antoine, Besancon, and Roger Blanc, Chambéry, France

Continuation-in-part of application Ser. No. 438,364, Mar. 3, 1965, and a continuation-in-part of 494,629, Oct. 11, 1965. This application May 6, 1968, Ser. No. 726,777

Int. Cl. A61c 5/02

U.S. Cl. 32-57

5 Claims



In a dental instrument for the treatment of dental roots by dental instruments such as broaches or reamers, means are provided for causing the instrument to alternately rotate in one direction and in the opposite direction, the means causing an angle of rotation of the instrument which is at the

most equal to the angle which corresponds to its yield strength, or elastic limit.

3,578,746

GAGING APPARATUS AND METHOD


John H. Walker, Dayton, Ohio, assignor to The Bendix Corporation

Filed Feb. 13, 1969, Ser. No. 799,047

Int. Cl. G01b 13/02

U.S. Cl. 33-174

23 Claims



An apparatus for and method of controlling the force exerted by a gaging probe against a workpiece wherein gaging movement of such probe is provided along a rectilinear path coinciding with a longitudinal axis of the probe and the force exerted by the probe is kept substantially constant at all angles of inclination of the longitudinal axis of the probe relative to a reference plane.

3,578,747

SHRINK TUNNEL WITH TURNABLE


Richard F. Schramm, St. Louis, Mo., assignor to Speed Equipment Incorporated, St. Louis, Mo.

Filed Jan. 3, 1968, Ser. No. 695,408

Int. Cl. F26b 11/00

U.S. Cl. 34-184

6 Claims



A portable shrink tunnel with turntable means for heat shrinking plastic film about various objects to be wrapped. The shrink tunnel is provided with a turntable disc having a loading station in which the objects are wrapped and placed on the turntable, a heat-shrinking station within an overlying shrink tunnel that may be expandable to cover one-quarter to one-half of the turntable, and a discharge station on the turntable which is adjacent the receiving station. The turntable is constantly rotated and carries the objects to be wrapped 360° from the receiving station, through the shrink tunnel, and the discharge station. The shrink tunnel is composed of two arcuate housing sections telescopically adjustable to vary the tunnel length, and provide a means for controlling the tunnel heat supplied in the tunnel and also to vary the area of the loading or receiving station. A heating element may be positioned underneath the turntable disc at the receiving station to heat the disc which aids in maintaining the wrapping film about the article to be wrapped before it is charged to the heat shrink tunnel.


3,578,748

ICE FISHING HOLE COVER

Raymond M. Hurd, 2548 S. 78th St., Milwaukee, Wis.
 Filed Feb. 11, 1969, Ser. No. 798,396
 Int. Cl. A01k 93/00, 97/12

U.S. Cl. 43-44.9

7 Claims



A buoyant cover for an ice fishing hole is formed as a centrally split, two-piece plate member having recesses defining a fishing line opening. The opposed edges of the pieces are releasably connected by an adhesive greaselike substance. The plate member is covered with a water-repellent material and has a black coating on its top surface to absorb heat.


3,578,749

SELF-LOCKING DROP-DOOR

Homer G. Woten, 912 Perrin Ave. N. W., Winter Haven, Fla.
 Filed May 5, 1969, Ser. No. 821,714
 Int. Cl. E05f 1/00

U.S. Cl. 49-387

4 Claims



A drop-door hinged at the bottom to an enclosure, and having support bars pivotally connected to the door and slidable through slots in the enclosure adjacent the opening closed by the door. The support bars are angular, with short arms adjacent the door to move into the slots in the enclosure, and counterweight arms to move about the bottoms of the slots in the enclosure as fulcrums to assume downwardly depending self-locking positions.

ERRATUM

For Class 52-156 see:
 Patent No. 3,578,156


3,578,750

CROP GUIDING AND ARRANGING MEANS FOR A SELF-PROPELLED HARVESTING MACHINE

Lawrence M. Halls, New Holland; Henry N. Lausch, Leacock, and Bruce D. Schwalm, Leola, Pa., assignors to Sperry Rand Corporation, New Holland, Pa.
 Filed Apr. 3, 1969, Ser. No. 813,219
 Int. Cl. A01d 43/00

U.S. Cl. 56-23

11 Claims



Crop guiding and arranging means are mounted on two suspension assemblies supporting a wide header on a narrower self-propelled tractor and on the tractor for guiding and deflecting crops cut by a header into windrows or swaths.

3,578,751


APPARATUS FOR DRIVING SPINDLE FOR EFFECTING FALSE TWISTING OF YARNS

Nobuhisa Kodaira, 7-10, Kami-Renjiyaku 2-chome, Mitaka, and Norio Motegi, 2-8, Sakura 1-chome, Norio, Tokyo, Japan

Filed July 14, 1969, Ser. No. 841,438
 Claims priority, application Japan, Aug. 21, 1968, 43/59192
 Int. Cl. D01h 7/92

U.S. Cl. 57-77.45

5 Claims



An apparatus for driving a spindle for effecting false twisting of yarns in which a drive roller frictionally contacts a spinner to rotate it with high speed. Said spinner loosely fits in the grooves formed in the ends of a fixed magnet.

The portions of the spinner loosely fit in grooves of a fixed magnet having a polarity the same as the polarity of corresponding grooves of the fixed magnet respectively whereby due to repulsion produced between the polarities, said spinner is urged to abut said drive roller and also its rocking motion is avoided. In front of respective poles of said fixed magnet, a metal plate of high permeability is provided with an airgap therebetween to increase magnetic flux density of said polarity portions.


3,578,752

SEGMENTED BULKHEAD FOR TUNNELS AND THE LIKE

Richard W. Stevens, Oconomowoc, Wis., assignor to Milwaukee Boiler Manufacturing Company, Milwaukee, Wis.
 Filed Sept. 23, 1968, Ser. No. 761,770
 Int. Cl. E02d 23/00

U.S. Cl. 61-83

4 Claims



A circular bulkhead is formed of a pair of segments and is capable of assembly and erection within the confines of a tunnel. The generally semicircular segments include means for joining the segments together to form the completed bulkhead.


3,578,753

LIQUEFIED PETROLEUM VAPORIZER WITH AUTOMATIC VAPORIZER BYPASS

William P. Freeman, Jr., Dallas, Tex., assignor to John E. Mitchell Company, Dallas, Tex.
 Filed Feb. 28, 1969, Ser. No. 803,185
 Int. Cl. F17c 9/02

U.S. Cl. 62-51

6 Claims



A liquid petroleum vaporizer with means to supply vapor from a storage tank under conditions of demand in excess of the capacity of the vaporizer and with an automatically operable valve-controlled line bypassing the vaporizer when the vapor in the storage tank is adequate to supply the demand.

3,578,754

DEFROSTING CONTROLLER FOR ELECTRIC REFRIGERATOR

Zenji Kusuda, Ibaragi-shi, and Takeji Kobayashi, Kyoto, Japan, assignors to Matsushita Electronics Corporation, Osaka, Japan


Filed Feb. 25, 1969, Ser. No. 802,035
 Claims priority, application Japan, Mar. 1, 1968, 43/13925
 Int. Cl. F25d 21/06

U.S. Cl. 62-156

4 Claims

A defrosting controller for electric refrigerators which is operated under control of a first transistor adapted for triggering a silicon-controlled rectifier depending upon the result detected by a temperature detector in the freezer of the refrigerator and under control of a second transistor for keeping the first transistor in one state during the defrosting operation so that the defrosting operation is automatically stopped as soon as the temperature within the freezer reaches a predetermined temperature after starting the

defrosting operation. Thus, frost accumulated within the freezing compartment can completely be removed and an un-



necessary temperature rise within the freezing and provisions compartments can be prevented.

3,578,755


RESPONSE ANALYZER FOR SENSORS

Bobby G. Bynum, and Drayton H. Talley, Huntsville, Ala., assignors to the United States of America, as represented by the Administrator of the National Aeronautics and Space Administration

Filed July 30, 1969, Ser. No. 845,991
 Int. Cl. G01f 25/00

U.S. Cl. 73-1R

7 Claims



The invention is an apparatus for measuring the performance of liquid level sensors under dynamic conditions. The apparatus includes a motor driven cam having a cam groove formed therein. A cam follower riding in the cam groove drives a pivotally mounted lift rod which in turn drives a slide rod to which a sensor being tested is attached. The slide rod is positioned with respect to a container such that the attached sensor is moved in and out of a liquid in the container. A first signal generating means is provided that indicates when the sensor actually first enters the liquid and another signal is generated by the sensor when it senses entering the liquid. By monitoring the time lapse between the signals it is possible to determine the response characteristics of the sensor upon entry into a liquid. A camera and light source are utilized to photograph conditions within the container during test of a sensor.

3,578,756

AUTOIGNITION TEST CELL

Fred D. Evans, Oviedo; Carlos L. Springfield, Titusville, and Coleman J. Bryan, Merritt Island, Fla., assignors to the United States of America as represented by the Administrator of the National Aeronautics and Space Administration
 Filed July 30, 1969, Ser. No. 845,971
 Int. Cl. G01n 25/00


U.S. Cl. 73-15

1 Claim

A chamber for analyzing test samples of materials, such as used in spacecrafts, under certain predetermined environmental conditions in order to determine autoignition temperatures and degree of decomposition is controlled atmospheres. The apparatus includes an elongated hermetically sealed cylindrical chamber which has a plurality of couplings

carried thereon. A vacuum pump, a source of gas, a bubbler system which bubbles through a mercury bath, a valve and other various items may be coupled to the couplings in order

helium gas is introduced into the previously purged sample chamber. Helium gas effusing from a leaking specimen flows



to produce predetermined environmental conditions within the chamber. The chamber is also provided with a viewing port and a thermocoupled probe for measuring the temperature of the test sample.

3,578,757

CHROMATOGRAPH FOR DETERMINATION OF ADMIXTURES IN GASES


Viktor Ivanovich Samuilov, oblast, Leninsky Raion doma Uniigaz, 4A, Kv.59, Moskovskaya Oblst; Jury Markovich Genkin, ulitsa Usacheva, 62, Kv.254, and Maria Dmitrievna Suvorova, Simonovsky val., 12, Kv. 171, Moscow, U.S.S.R.

Filed July 12, 1968, Ser. No. 744,517

Int. Cl. G01n 31/08; B01d 15/08

U.S. Cl. 73—23.1

6 Claims



A chromatograph for the determination of admixtures in gases, comprises a chromatographic column bent in the form of at least a single helix coil or an arc of circle and which is rigidly secured on the shaft of a drive device in a plane perpendicular to the axis of the shaft. The shaft is mounted in stationary supports so that at the same time one portion of the chromatographic column is immersed in a refrigerant bath and the other portion of the column is in a heater, and during the rotation of the shaft said portions of the column subsequently pass through the cooling and heating zones.

3,578,758

ORIFICE GROSS LEAK TESTER

Thomas L. Altshuler, West Concord, Mass. assignor to the United States of America as represented by the Administration of the National Aeronautics and Space Administration.


Filed May 7, 1969, Ser. No. 822,519

Int. Cl. G01m 3/16

U.S. Cl. 73—40.7

3 Claims

An orifice leak tester for use with a helium mass spectrometer is disclosed. The leak tester comprises a sample chamber, wherein an article to be tested is supported on a wire screen; an orifice formed in a wall common to the sample chamber and mass spectrometer specimen chamber; and means for directing a purging gas over the orifice and through the sample chamber. A specimen pressurized with



3,578,759

FOOT-OPERATED HAND-RELEASED BRAKE OF THE VEHICLE

Takeo Yamazaki, Anjo-shi, Japan, assignor to Aisin Seiki Kabushiki Kaisha, Kariya, Japan


Filed July 28, 1969, Ser. No. 845,436

Claims priority, application Japan, Aug. 3, 1968, 43/55048

Int. Cl. G05g 1/14

U.S. Cl. 74—540

5 Claims



A foot-operated and hand-released brake of the vehicle in which a pedal is oscillatably pivoted by a shaft rotatably mounted on a bracket and an internal gear is carried on the shaft rotatably and eccentrically to the shaft. The rotation of the shaft swings the internal gear in mesh with an external gear provided on the pedal concentrically to the shaft, and rotating the internal gear with a speed largely reduced due to the slight difference in the number of teeth in the gears. An arm fixed to the internal gear releases the brake cable depending on the amount of the rotation of the shaft.

3,578,760

POWER TRANSMISSION APPARATUS

Kimino Shinmura, Tokyo, Japan, assignor to Kabushiki Kaisha Honda Gijutsu Kenkyusho, Saitama-ken, Japan

Filed Dec. 27, 1968, Ser. No. 787,404

Claims priority, application Japan, Jan. 17, 1968, 43/2147

Int. Cl. F16h 37/00; B60k 17/06


U.S. Cl. 74—701

4 Claims

A power transmission apparatus in which an input shaft driven by a prime mover is provided with respective driving gears for low-speed and high-speed operation and with spaced, respective hydraulic-operated frictional clutches for selectively connecting the gears to the shaft, there being an output shaft extending parallel to the input shaft and pro-

vided with spaced driven gears in mesh with respective driving gears and with an output gear partly projecting into the

flutes extending therefrom. These drilling and reaming sections are designed to give a positive round hole of the proper diameter so that the threaded section can engage the sides of the hole and distort the sheet metal enough so that a firm



space formed between the two clutches and directly driving an adjacent differential gear apparatus.

3,578,761

SEVERING APPARATUS


Albert J. Sarka, Fairview Park, Ohio, assignor to Harris-Intertype Corporation, Cleveland, Ohio

Filed Sept. 12, 1968, Ser. No. 759,275

Int. Cl. B23d 25/12; B26d 1/56

U.S. Cl. 83—343

13 Claims



Apparatus for severing material at selected locations comprises first and second dies. Each of the dies has sheet-severing elements in the form of narrow projections extending above the surface of the main body of the respective die. The sheet-severing elements define a layout of the selected material locations to be severed. At least one of the dies comprises a plurality of separate discrete die sections. An additional die section is provided as a replacement for each die section in the event of damage thereto.

3,578,762

SELF-DRILLING, REAMING AND TAPPING SCREW

George Siebol, Orange, and Robert F. Kolec, Whittier, Calif., assignors to Armco Steel Corporation, Middletown, Ohio


Filed Apr. 14, 1969, Ser. No. 815,825

Int. Cl. F16b 25/00

U.S. Cl. 85—41

2 Claims

A fastener comprising a screw having a head adapted to be engaged by means whereby it may be rotated so as to force it into a workpiece or the like at one end and a workpiece-engaging point at the other end. This fastener is designed to have the maximum tensile strength in the total fastener. To this end the shank of the screw, between the point and head, is formed into three sections. The first section, moving from the point towards the head, is of relatively small diameter and is provided with a pair of cutting edges having flutes extending therefrom whereby this section functions as a pilot drill. The next or intermediate section is of larger diameter. The aforementioned grooves or flutes extend into this section and define a second pair of cutting edges. Additionally, however, this intermediate section is provided with other cutting edges and flutes whereby this intermediate section constitutes a reaming section having multiple cutting edges with



3,578,763

FLOATABLE CORDS


Jan Hendrik Platou, Birkelundsbk 76, Paradis, near Bergen, Norway

Filed Mar. 12, 1968, Ser. No. 712,445

Int. Cl. D04c 1/12

U.S. Cl. 87—6

6 Claims



A flexible floatable cord for use in fishing nets, trawls, water skiing and the like, which comprises a braided sleeve, a core of continuous filament threads incorporated therein and particles of an expanded plastic material disposed between said sleeve and said core, said particles being only attached to one another and to the sleeve and the core and forming a continuous cord in which the core is embedded. Further a process and an apparatus for producing said flexible floatable cord.

3,578,764

OVEN DOOR SEAL AND METHOD OF MAKING SAME

Robert L. Nunnally, Valley Forge, and Thomas L. Weil, Paoli, Pa., assignors to Bentley-Harris Manufacturing Company, Conshohocken, Pa.

Filed July 23, 1969, Ser. No. 844,083


Int. Cl. D04c 1/06

U.S. Cl. 87—6

9 Claims

A heat-resistant gasket is provided for sealing a space between a door and a jamb around an access opening in an oven of the self-cleaning type. The gasket has a braided fiberglass jacket which has a line of juncture extending longitudinally to dispose a resilient metal mesh tubular sealing element and a tubular mounting element in spaced parallel relation therein, the mounting element being engaged by clamping means on the door which secures it thereto to dispose the sealing element in the space to be sealed. In addition, there is disclosed a method for fabricating the gasket which includes the steps of braiding the fiberglass jacket around both a knitted wire mesh core in the tubular sealing element and a paper core in the tubular mounting element as the elements advance in spaced parallel relation and joining

the braided jacket longitudinally between the elements by stitching, then shaping the sealing element, and heating the



gasket assembly to an elevated temperature to disintegrate the paper core and to set its shape.

3,578,765 ELECTRIC EYE CAMERA

Tatsuo Kobayashi, Kaizuka, and Kayoshi Tsujimoto, Higashi, Osaka, Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Apr. 10, 1968, Ser. No. 720,091

Claims priority, application Japan, Apr. 12, 1967, Apr. 13, 1967, Apr. 28, 1967, 42/23064; 42/30516; 42/27300

Int. Cl. G03b 7/12, 9/00

U.S. Cl. 95—10

13 Claims



An electric eye camera to be operated either in a programmed exposure control mode or in an automatic exposure control with priority on shutter speed mode. The camera has a changeover ring to facilitate selection of the mode by simple operation. A lens aperture control ring is used to inhibit the mode of operation with priority on shutter speed as long as the lens aperture control ring is away from its initial position.

3,578,766 VARIABLE PRESSURE EMBOSING MACHINE

Lucien Diolot, Neuilly Sur Seine, France, assignor to Societe Nouvelle Spidem, Paris, France

Filed Apr. 4, 1967, Ser. No. 628,325

Claims priority, application France, Apr. 4, 1966, 56353


Int. Cl. B44b 5/00; B30b 3/04

U.S. Cl. 101—23

8 Claims

An embossing machine having means to vary the pressure of the cooperating embossing rolls employing hydraulic power cylinders to provide the substantially constant main force pressing the embossing cylinders together. Control hydraulic jacks are placed operatively between the cylinders to press them apart with a predetermined selected pressure to thereby selectively vary the resultant engaging pressure of the cylinders. Preferably, the jacks and power cylinders receive their hydraulic fluid from the same supply and the

jacks are provided with motor reducer control units that may be coupled together for simultaneous adjustment of the jacks on each axial end of the cylinders or uncoupled for separate



adjustment. Also, the jacks are retractable along with the upper cylinder supporting structure so that the cylinders may be easily removed and replaced.

3,578,767

SAFETY AND ARMING DEVICE


John T. M. Lee, Tamaqua, Pa., assignor to Atlas Chemical Industries, Inc., Wilmington, Del.

Filed Dec. 11, 1968, Ser. No. 782,886

Int. Cl. F42c 15/32

U.S. Cl. 102—70.2

4 Claims



A safety and arming device activated by contact with a liquid activator and armed by the evaporation of the liquid. An element of the device expands when contacted by the liquid activator and contracts when the liquid evaporates; the expansion of this element collapses a member and the element's subsequent contraction activates a switch which arms the device.

3,578,768

PARTITIONING SYSTEM FOR FLUID CUSHIONS IN GROUND EFFECT MACHINES

Francois L. Giraud, Plaisir, France, assignor to Societe De L'Aerotraine, Paris, France


Filed June 27, 1968, Ser. No. 740,498

Claims priority, application France, Oct. 4, 1967, June 19, 1968, 123,278; 155,691

Int. Cl. B61b 13/08

U.S. Cl. 104—23

15 Claims



An arrangement for partitioning the compressed fluid cushion of ground effect vehicles and the like machines, said

arrangement including dihedral-shaped partitions extending across the cushions and facing one of the walls along which the machine is guided and sustained, said dihedral defining a compartment on either side of same; the outer edges of the elementary partitions facing said wall and normally oblique with reference thereto are separated by a clearance from said wall and by reason of the pivotal securing of the dihedral to the machine along the ridge of said dihedral, any leak of fluid in one of the compartments produces a shifting of the elementary partition bounding the opposite compartment so as to throttle the corresponding clearance and to cut off the leaking compartment.

3,578,769

DIFFERENTIAL FEED ATTACHMENT MEANS FOR SHIRTING


Edward L. Seaman, 65 Harvard St., Garden City, N.Y.

Filed May 1, 1969, Ser. No. 820,995

Int. Cl. D05b 27/08

U.S. Cl. 112—208

4 Claims



A differential feed attachment means for a drop feed sewing machine, said attachment being intended to replace the conventional feed dogs and consisting of two feed dogs arranged in tandem with the front feed dog being adjustable through a lever system relatively to the rear feed dog so that the amount of travel of the front feed dog can be in unison with the rear feed dog and may be quickly and easily varied by the operator while the machine is in motion to continuously or intermittently gather or shirr material being operated upon.

3,578,770

SEWING MACHINE

Johannes Franciscus Van Hazendonk, Zwaneburg, Netherlands, assignor to "De Jong & De Vliet Machinehandel N.V.", Zwaneburg/Halfweg, Netherlands

Filed Dec. 18, 1968, Ser. No. 784,770


Claims priority, application Netherlands, Dec. 29, 1967, 6717780

Int. Cl. D05b 69/26, 65/02

U.S. Cl. 112—219

5 Claims

A sewing machine is disclosed having a treadle-operated main clutch, an electromagnetic clutch and brake unit, a thread cutoff and an electric control circuit comprising a rotating needle positioning device. On pressing the treadle forwardly the main clutch is actuated whereby the driving motor of the machine drives the latter at the full operating speed and on subsequent disengagement of the treadle the electromagnetic clutch is actuated whereby the drive motor drives the machine through a reduction gear at a reduced needle positioning speed until the needle has reached its lowest position and is stopped by the actuation of the electromagnetic brake. When the treadle is moved from its forward position through its rest position to a rear position, the



stopped. The thread cutoff is electrically actuated during the movement of the needle from its lowest to its highest position.

3,578,771

COATING APPARATUS INCLUDING PLURAL, SEQUENTIAL CONVEYING MEANS


John W. Black, Prairieville Township, Barry County, Mich., assignor to Pemco Wheel Company, Kalamazoo, Mich.

Filed Mar. 22, 1967, Ser. No. 625,123

Int. Cl. B05c 11/00

U.S. Cl. 118—6

13 Claims



Plural treating stations comprise two downwardly opening ovens facing respectively an upwardly opening fluidized bed coating tank and a quench tank. An endless conveyor means conveys the article to be treated into and out of the first oven and delivers same to a second endless conveyor means which conveys the article into and out of the fluidized coating tank. Third endless conveyor means transfers the article from said second to a fourth endless conveyor means which conveys same into and out of the second oven and the quench tank.


3,578,772

APPARATUS FOR APPLYING A COATING TO SHEET MATERIAL

Robert B. Taylor, and Robert G. Walker, Fort Wayne, Ind., said Walker assignor to Allan W. Pedden, Fort Wayne, Ind. Division of Ser. No. 462,506 June 9, 1965, Pat. No. 3,436,232. Filed Mar. 13, 1969, Ser. No. 840,860
Int. Cl. B05c 1/00, 11/00

U.S. Cl. 118—33

1 Claim



An apparatus for applying a coating of paraffin to one side of a sheeting material having an applicator roll which is rotatable mounted in a container of liquid paraffin so that a lamination of paraffin is transferred to the face of the sheeting material and an adjustable brake having a pivotable crossbar provided with a friction pad for engagement with the supply roll for controlling the tension of the sheet material as it is drawn through the apparatus.


3,578,773

SUPPORTIVE ORTHOPEDIC DEVICE

August L. Schultz, 214 N. Harmon Drive, Mitchell, S. Dak. Filed Oct. 28, 1968, Ser. No. 771,140
Int. Cl. A61f 5/02

U.S. Cl. 128—78

1 Claim



An orthopedic appliance including a flexible and elastic body-engageable and conformable belt having a pressure pad slidably mounted on the inner side thereof for application to the torso of the wearer to provide support and pressure in any preselected position on the circumference of the torso between the lower scapular area and the sacroiliacs.

3,578,774

UROLOGICAL ENDOSCOPIC IRRIGATION MACHINE

Harold P. McDonald, Jr., Garden City, N.Y. (University of Tenn. College of Medicine, Urology Dept. 858 Madison Ave., Memphis, Tenn. 38103)

Filed Aug. 7, 1969, Ser. No. 848,170


Int. Cl. A61m 7/00

U.S. Cl. 128—227

8 Claims

A urological endoscopic irrigation machine which consists of a cabinet for holding tank of irrigation fluid which is pumped through a tube into a reservoir bag at an elevated height. A membrane filter is connected on the input of the bag to filter out bacteria from the irrigant pumped from the tank. The bag is supported from a weight-sensitive switch which is responsive to the weight of the bag and its contents

so that, as the fluid level in the bag drops, the weight-sensitive switch will automatically operate the pump to refill the



bag to a predetermined level so as to maintain its constant supply of irrigation fluid for the patient.

3,578,775

VEHICLE-WASHING APPARATUS


James W. McMillen, 2011 Belmont Blvd., Nashville, Tenn.

Filed Feb. 20, 1969, Ser. No. 800,904

Int. Cl. B60s 3/04

U.S. Cl. 134—45

10 Claims



A vehicle-washing apparatus having a longitudinally disposed overhead spray frame supporting longitudinally spaced spray heads for reciprocable movement transversely above a vehicle to be washed, and a pair of vertically disposed side frames supporting vertically spaced side spray heads and mounted for reciprocable movement longitudinally along opposite sides of the vehicle. The overhead frame may include depending end frames having vertically spaced end spray heads for washing the opposite ends of the vehicle, and the overhead spray heads may be arranged at different elevations to define the contour of the vehicle.

3,578,776

CHEMICAL FEEDER

Thomas E. Schneider, Jr.; Marion R. Carstens, Atlanta, and Homer J. Bates, Roswell, Ga., assignors to Tesco Chemicals, Inc., Atlanta, Ga.

Continuation-in-part of application Ser. No. 579,253, Sept. 14, 1966, now Patent No. 3,057,624, which is a continuation-in-part of application Ser. No. 403,968, Oct. 12, 1964, now Patent No. 3,323,539. This application Aug. 22, 1968, Ser. No. 754,535


Int. Cl. B01d 11/02

U.S. Cl. 137—268

9 Claims

A chemical feeder for feeding a chemical from a solid chemical compound into a stream of water. The feeder in-

cludes a housing divided into upper and lower chambers, a chemical container positioned in the upper chamber for receiving a solidified chemical compound, a liquid inlet conduit communicating with the upper chamber, a liquid exhaust conduit communicating with the lower chamber, valves controlling both conduits, and a float positioned in the lower chamber for operating both valves. The chemical container



includes a plurality of apertures at spaced intervals about its lower end, and a nozzle extending inwardly from its lower end for flowing liquid from the upper chamber into contact with the solidified chemical compound and eroding the compound from its lower end. The mixture of the liquid and chemical compound flows from the upper chamber to the lower chamber.

3,578,777

CORRUGATED TUBING


William J. DeGain, Warren, Mich., assignor to Koppy-Tool Corporation, Ferndale, Mich.

Filed June 11, 1969, Ser. No. 832,352

Int. Cl. F16l 9/06, 11/12

U.S. Cl. 138—121

28 Claims



A corrugated tubing in which either the corrugation peak or root portions respectively and selectively are provided with longitudinal annularly spaced depressions or bulges connecting adjacent corrugation surfaces and in which selected peak or root diameters selectively may be different than the remaining peak or root diameters, such tubing when used as an energy-absorbing device having thereby a predetermined resistance of the corrugations to axial collapse loads and producing controlled degree and order of their collapse on subjecting the tubing to such axial loads.

3,578,778

PACKAGING APPARATUS FOR FILLING INDIVIDUAL CONTAINERS

Ernest L. Matthews, and Ralph E. Matthews, Decatur, Ala., assignors to Matthew Machine Company, Inc., Decatur, Ala.

Filed Mar. 7, 1969, Ser. No. 805,149


Int. Cl. B65b 43/42; B67c 3/00

U.S. Cl. 141—144

3 Claims

A high productivity packaging apparatus and method are based on utilization of a container and a plurality of circular

arranged valves which are connected to and rotate with the container. During rotation each valve draws a unit of material to be packaged from the container at one station, holds the



unit of material in the valve during continuing rotation and then discharges the unit of material at a discharge station to which empty containers are fed successively in synchronism with successive valves being discharged.

3,578,779

BAR FOR A CHAIN SAW


Kan Ishizaki, Tokyo, Japan, assignor to Shingu Shoko, Ltd., Otaru, Hokkaido, Japan

Filed Jan. 28, 1969, Ser. No. 794,659

Int. Cl. B27b 17/02, 17/12

U.S. Cl. 143—32

1 Claim



The present invention discloses a bar for a chain saw comprising a pair of parallel guide rails for a saw chain, a circumferential groove provided between said pair of guide rails and extending therealong, and an oil supply means having one or more ports facing said groove, wherein a cover plate extending from one of said openings to a top portion of the bar is fixedly mounted within said groove and along a bottom portion thereof, thereby forming an oil passage, and oil supplied into the oil passage through said opening by the oil supply means can be discharged into the guide groove at the top portion of the bar.

3,578,780

APPARATUS FOR COMMUNUTING MATERIALS

Norman J. Peters, Fond Du Lac, Wis., assignor to DEC International, Inc., Madison, Wis.

Filed Dec. 30, 1968, Ser. No. 787,805

Int. Cl. B02c 18/00; B26d 9/00


U.S. Cl. 146—79

16 Claims

An apparatus for comminuting and blending materials such as food products. The materials to be blended are initially fed into a shredder unit and the shredded materials are discharged to a comminuting or grinding unit.

The grinding unit includes a rotor which rotates within a perforated drum having a generally U-shaped cross section

and open ends. The material is introduced into the drum through the longitudinally extending opening and is forced outwardly through the perforations by the rotor and discharged to a hopper.



The drum is adapted to be slipped longitudinally over the rotor and rotor bearings and is retained within a fixed cage. The drum can be readily removed from the unit without removing the rotor or disassembling the bearings for the rotor shaft.

3,578,781

CLAY TREATING AND OIL-WETTING DISPERSION AND METHOD OF USE THEREOF

Albert Abrams; Harold J. Hill, and David R. Thigpen, Houston, Tex., assignors to Shell Oil Company, New York, N.Y.

Filed Dec. 31, 1968, Ser. No. 789,002
Int. Cl. E21b 43/25

U.S. Cl. 166—305

6 Claims

Permeability characteristics of a subterranean earth formation are improved by permeating them with a clay treating and oil-wetting dispersion of a surface active salt of a surface active cation and a surface active anion in an aqueous liquid solution containing electrolyte and water-soluble surfactant.

3,578,782


APPARATUS FOR THE RETRACTION OF A STEERING WHEEL OF A VEHICLE IN THE EVENT OF A FRONT END COLLISION THEREOF

Takeomi Miyoshi, Tokyo, Japan, assignor to Honda Giken Kogyo Kaisha, Tokyo, Japan

Filed Oct. 29, 1969, Ser. No. 872,302
Int. Cl. B62d 1/18

U.S. Cl. 180—82

11 Claims



A steering wheel is connected to a shaft which in turn is connected to a steering mechanism in a housing so as to provide a steering connection, the housing being supported on a support frame which extends forwardly from the car body frame and is connected therewith along an inclined surface so that if the support frame is displaced rearwardly in the event of front end collision, the support frame is lowered where it is connected with the housing to cause the latter to be lowered and in turn cause the steering shaft to be retracted from the passenger compartment. The support frame may also be provided with a downwardly bent portion to achieve lowering of the housing and retraction of the shaft and steering wheel.


3,578,783 EXTRACTOR FOR AN UMBILICAL CONNECTOR OF A ROCKET

Pierre Loustalet, and Guy Roujas, Tarbes, France, assignors to The French State, France

Filed Nov. 5, 1969, Ser. No. 874,344
Claims priority, application France, Nov. 5, 1968, 172,592
Int. Cl. F03g 1/00; F15b 15/26

U.S. Cl. 185—37

10 Claims



An extractor for an umbilical connector of a rocket comprises a hook of a piston rod engaging the connector, the piston rod being connected to a piston which is loosely fitted in a cylinder. A lock member engages the piston to hold the same in a ready or armed position in which a spring is compressed between the piston and cylinder. In a first mode of operation, a command signal is given to retract the lock member whereupon the piston is displaced by the spring and the hook pulls the umbilical connector to separate it from the rocket. In a second mode of operation, the hook remains in place and during rocket lift-off the umbilical connector tilts the piston past the lock member whereupon the piston is displaced by the spring to pull the umbilical connector and separate it from the rocket.

3,578,784


SPREADING SPRING FOR SPEED SELECTION AND SYNCHRONIZING DEVICES FOR MOTOR VEHICLES

Karl Ashauer, 318 Wolfsburg, Rabenhorst 2, and Dieter Manthey, 318 Wolfsburg, An der Kirchmesse 14, Wolfsburg, Germany

Filed Nov. 26, 1969, Ser. No. 880,120
Int. Cl. F16d 23/02

U.S. Cl. 192—53R

4 Claims



An annular-shaped spreading spring for speed selection and synchronizing devices for motor vehicles consisting of an integral wire with two winding loops interconnected by a crossover sector.


3,578,785 OUTLET PLUG AND CONDUIT FOR CHROMATOGRAPH

James A. Patterson, Los Altos, Calif., assignor to Sondell Research & Development Co., Palo Alto, Calif.

Filed Feb. 12, 1968, Ser. No. 707,016
Int. Cl. B01d 15/08

U.S. Cl. 210—198

11 Claims U.S. Cl. 212—59



A chromatographic conduit forming a channel through which a continuous stream of eluate or classified fluids pass with minimal destruction of the classified state. The conduit commences at the output of a chromatographic classifying column and comprises reactors for processing the classified fluids, interconnecting tubes for transporting the classified fluids, and plugs for accommodating unavoidable changes in overall conduit cross section. The reactor and plugs define fluid-containing volumes, which volumes are packed with spherical particles to define intercommunicating spaces therein. These defined intercommunicating spaces prevent the fluid interfaces contained within the eluate from being dispersed over large and unobstructed areas wherein mixing due to turbulence and molecular migration may freely take place. The conduit, including the interconnecting tubing and reactor, is provided throughout with an essentially constant, effective cross-sectional area for fluid flow, which area permits uniform velocity in the fluid stream and gradual and uniform pressure drop therethrough.

3,578,786


DISCHARGE DEVICE FOR THE BOTTOM FRACTION AT A VORTEX-TYPE SEPARATOR

Ake Karl Gustaf Cras, Karlskoga, Sweden, assignor to Karl Arvid Skardal, Stockholm, Sweden

Filed July 3, 1969, Ser. No. 838,891
Claims priority, application Sweden, July 9, 1968, 9460
Int. Cl. B04c 5/16

U.S. Cl. 210—512

5 Claims



A device is provided for discharging the heavy bottom or reject fraction from a vortex-type separator and the device comprises a cylindrical vortex chamber which is connected to a bottom fraction outlet of the separator so as to receive the reject fraction therefrom in a manner producing a vortex flow in the vortex chamber. The vortex chamber is provided with an outlet port for the reject fraction and a flow-deflecting member is disposed within the vortex chamber for deflecting the vortex flow away from the circumferential wall of the vortex chamber at the location of the outlet port. The flow-deflecting member has an adjustable position in the vortex chamber so that the degree of deflection of the vortex flow from the location of the outlet port is determined by the position of the flow-deflecting member.


3,578,787 CONTROL SYSTEM

Alan E. Brickett, and Everett R. Windahl, Green Bay, Wis., assignors to Northwest Engineering Corporation, Green Bay, Wis.

Filed Nov. 12, 1968, Ser. No. 774,772
Int. Cl. B66c 23/06

11 Claims U.S. Cl. 212—59

5 Claims



A control system for a convertible pullshovel-crane wherein a plurality of hydraulic cylinders and/or hydraulic motors are actuated by a combination of air cylinders and hydraulic valves. In one embodiment, booster means for some of the hydraulic cylinders are provided with interlocks to prevent booster operation under certain conditions. In another embodiment, a plurality of hoist drums are controlled by the hydraulic motors, with the drums having both friction brakes as well as friction clutches to provide flexibility of cable control. Various bypasses and interconnections in the pneumatic circuit permit varying or fixing certain drum speeds.

3,578,788


GAS LIQUID WITHDRAWAL VALVE

John J. Potter, Jr., and William J. Hamel, St. Albans, W. Va., assignors to Union Carbide Corporation, New York, N.Y.

Filed Nov. 13, 1968, Ser. No. 775,427
Int. Cl. B67b 7/24

U.S. Cl. 222—4

5 Claims



A device is provided for attachment to the opening on top of a pressurized container and adapted to selectively


withdraw liquid or gas therefrom. It comprises a valve body adapted to be fitted to the opening of a container. The valve body is fitted with a disc valve having one or more openings which may be selectively rotated to vent either a tubular member extending from the valve body into the container so as to withdraw liquid, or an opening in the base of the valve body communicating with the gas above the liquid. A plunger, biased by a double-acting resilient member such as a spring, is provided in the top of the valve in order to externally vent the valve after the disc has been rotated to withdraw either liquid or vapor from the container. The double-acting resilient member is additionally biased against a pressure relief member in a housing within the valve body and an externally venting conduit is provided in the housing. In a preferred embodiment the housing coacts with the plunger and venting conduits are provided in the base of the plunger.

3,578,789 TOY GUN

Giampiero Ferri, Via Stoppani 38, Florence, Italy
Filed Apr. 11, 1969, Ser. No. 815,375
Claims priority, application Italy, Apr. 26, 1968, 4540A/68
Int. Cl. A63h 3/18

U.S. Cl. 222—79

13 Claims



A water pistol which includes a main liquid reservoir formed in a part of the casing, a trigger-actuated pump for withdrawing liquid from the main reservoir, and a pressurized liquid reservoir mounted within the main reservoir. A three-way valve is connected between the pump and the pressurized reservoir to selectively supply liquid from the pump to the pressurized liquid reservoir, from the pump to the nozzle of the gun and to the pressurized liquid reservoir, or from the pressurized liquid reservoir to the nozzle.

3,578,790 CABINET PANTS PRESS

David L. Radford; Paul W. Frisby, Salt Lake City, and Francisco Muniz Filho, Taylorsville, Utah, assignors to McGraw-Edison Company, Elgin, Ill.


Filed Mar. 10, 1970, Ser. No. 18,215
Int. Cl. D06c 15/10; D06f 59/00, 71/00

U.S. Cl. 223—73

24 Claims

A one lay cabinet pants press comprising nested outer and inner bucks about which the pants waist portion can be dressed and held by overlying lap clamps, the lap clamps having a nominal clamping force for quick and accurate pants dressing under the clamps and a large clamping force for securely holding the dressed pants, the inner buck having a single intermediate support whereupon separation of the inner and outer bucks automatically expands the pants uniformly across the upper waist and lower seat portions thereof, cuff grippers and supporting parallel arm linkage therefor suitable to move the grippers to a dressing position near the waist bucks and an inspection position and a pressing position each further spaced from the waist bucks where the pants legs are drawn lengthwise and a brake device across the linkage effective to hold the pants legs as drawn, carriage support for the waist bucks, another parallel arm linkage supporting the grippers aligned with the waist bucks, structure connecting the carriage support and other linkage

together suitable for moving them as aligned in unison between an outer dressing position and an inner pressing position, a fly press carried by the waist bucks to move



3,578,791 ENVELOPE OPENER AND ADVERTISING PIECE

George W. Davis, 1379 Venetian Way, Miami, Fla.

Filed Mar. 2, 1970, Ser. No. 15,604

Int. Cl. B65d 27/32; B43m 7/00

U.S. Cl. 229—85

3 Claims



The combination of an envelope having a triangular cutout at one corner defining a slit into the interior at the corner, and an insert within the envelope with a tab extending out of the corner. The insert has a slice edge extending at an angle from the tab so that when the insert is pulled from the envelope by the tab extending through the slit in the corner as it is pulled relative to the envelope, the slice edge which extends downwardly from the tab will slice the edge of the envelope. The insert also has a hooked portion to loosely captivate a piece of planar material in the hooked portion to be dragged from the envelope when the insert is removed from the envelope to drop free and to catch the attention of the recipient of the envelope as it falls.

3,578,792 DECADE COUNTER OR THE LIKE

John J. Affel, Canoga Park, Calif., assignor to International Telephone and Telegraph Corporation

Filed May 20, 1969, Ser. No. 826,131


Int. Cl. G06c 15/42

U.S. Cl. 235—144

9 Claims

The invention includes, for example, a number wheel and a gearwheel. Both wheels have a star-shaped ratchet around

which a leaf spring fits. The spring holds the wheels together. The number wheel, thus, normally advances with the




3,578,793 VARIABLE FLAME OXY-FUEL BURNER

Robert D. Jones, and Keith A. Miller, Allentown, Pa., assignors to Air Products and Chemicals, Inc., Allentown, Pa.
Filed May 29, 1968, Ser. No. 733,100

Int. Cl. B05b 15/00

U.S. Cl. 239—132.3

6 Claims



An oxy-fuel burner for use in a metallurgical furnace is disclosed which can be controlled to regulate the configuration of the burner flame to provide a flame shape varying from a wide "umbrella" shaped flame to a narrow "pencil" shaped flame. Several methods of using such burners in metallurgical furnaces are also disclosed.

3,578,794 SPOOLING APPARATUS


Edward E. Laird, 18 Pine Orchard Road, Branford, Conn.

Filed Jan. 16, 1969, Ser. No. 791,585

Int. Cl. B65h 54/00

U.S. Cl. 242—25

11 Claims



Unitary apparatus for precisely winding wirelike material from a large payoff reel to a takeup spool having an arrange-

ment of operating elements and control circuits to enable a battery of these units to be operated by a single operator. The arrangement of elements permits of a treating means such as cleaning being interposed between the payoff reel and takeup spool.


3,578,795

COP WINDER WITH CONTROLLED YARN TENSION
Gaspere Polese, Padua, Italy, assignor to Utita Officine E Fonderie Di Este S.P.A., Padua, Italy

Continuation-in-part of application Ser. No. 563,440, July 7, 1966, now Patent No. 3,412,949. This application July 12, 1968, Ser. No. 744,429
Int. Cl. B65h 59/38

U.S. Cl. 242—45

8 Claims



A yarn feeler means for a yarn winder includes a dancer pulley carried by a pivotally supported arm pivotal about the axis of a mounting shaft, the dancer pulley being engaged in a loop of the yarn in advance of the yarn-winding means. Spring means are connected to the shaft to apply an essentially uniform torque thereto and tension to the looping arm. The yarn winder is driven from a variable speed motor supplied by a supply circuit including supply adjusting means operable responsive to the actual position of the dancer pulley and arm to provide a supply proportional to the actual position to compensate for differences between the yarn-feeding speed and the yarn-winding speed. An auxiliary supply control circuit is effective, when closed, to boost the adjustment of the supply, and includes a movable contact supported by an arm fixedly connected to the shaft and movable within an arc of small amplitude, the movable contact, upon movement of the dancer pulley and arm in one given direction, engaging a fixed contact to close the auxiliary control circuit to boost the motor supply, such as the motor voltage, to counteract any tendency to increasing the difference between the yarn-feeding and yarn-winding speeds.

ERRATUM

For Class 243—797 see:
Patent No. 3,579,244

3,578,796

SPINNING AND STABILIZING SYSTEM FOR SOLID PROPELLANT ROCKET OR MISSILES

Travis J. Hagler, Huntsville; William R. Puckett, Trinity, and Bobby G. Tanner, Huntsville, Ala., assignors to Thiokol Chemical Corporation, Bristol, Pa.

Filed Sept. 25, 1968, Ser. No. 762,491


Int. Cl. F42b 13/32

U.S. Cl. 244—3.23

3 Claims

A system for imparting a spin force to a solid propellant rocket while it is in a launch tube, and to stabilize the solid

propellant rocket to discontinue the spin force after it leaves out of contact with gaseous products of combustion used to provide heat for the reaction.



the launch tube.

ERRATUM

For Class 251—41.9 see:
Patent No. 3,579,270

3,578,797


FUSING METHOD AND APPARATUS

Howard T. Hodges, and Claire F. Hodges, Executrix, Perinton, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Sept. 26, 1969, Ser. No. 861,510
Int. Cl. F27b 9/28

U.S. Cl. 263—3

9 Claims



A toner image is fused to a receiver sheet without substantial heating of the sheet by placing the sheet, image side down, on an endless heat-conductive web extending around at least two spaced rotatable supports. One or more of these rotatable supports may include a heating element to heat the endless web at or adjacent to the point where the receiver sheet is brought into contact therewith. A corona charger may be used to tack the receiver to the endless web to assure positive contact therebetween.

3,578,798


CYCLONIC FLUID BED REACTOR

Walter C. Lapple, and Edward M. Poole, Alliance, Ohio, assignors to The Babcock & Wilcox Company, New York, N.Y.

Filed May 8, 1969, Ser. No. 823,056
Int. Cl. F27b 15/02

U.S. Cl. 263—21

9 Claims



A high capacity fluidized bed unit is formed of single or multiple stages where reaction products may be maintained

out of contact with gaseous products of combustion used to provide heat for the reaction.

ERRATUM

For Class 263—52 see:
Patent No. 3,579,616

3,578,799


DEVICES FOR SECURING OR POSITIONING WORKPIECES FOR MACHINING OPERATIONS

Peter Grant Davis, Deptford, London, England, assignor to The Molins Machine Company Limited, London, England
Filed Apr. 4, 1968, Ser. No. 718,885

Claims priority, application Great Britain, Apr. 14, 1967, 17,248/67
Int. Cl. B23q 3/02; F16b 41/00

U.S. Cl. 269—51

3 Claims



A device for securing a workpiece to a pallet comprises a hollow support element, which can be screwed to the pallet, and which contains a screw urged by a spring to project from a support surface on that side of the support element remote from the pallet. The projecting end of the screw has a hexagonal recess which can receive a key inserted through a hole in the workpiece to rotate the screw and thread it up into the workpiece.

3,578,800


FOLDABLE BICYCLE-TYPE EXERCISING DEVICE

Paolo DiNepi, Via Crocefisso 6, Milan, Italy

Filed Oct. 8, 1968, Ser. No. 765,894
Claims priority, application Italy, Oct. 13, 1967, 815,374
Int. Cl. A63b 21/00, 23/04

U.S. Cl. 272—73

7 Claims



A foldable frame provided with a seat and a handlebar. The lower portion of the frame carries a step-up gear transmission having a pedal-operated drive shaft. The transmission drives a flywheel which is coaxial with the drive shaft and is equipped with a friction brake. A speedometer on the handlebar is operatively connected to the transmission. The foldable frame includes pairs of downwardly convergent frame members and leg members pivotally connected to the frame members, and a pair of transversely spaced straps straddling the frame and leg members. One leg member is rigidly secured to the straps at one end thereof, the other end portions of the straps are provided with longitudinal slots, a

pivot extends through the slots and connects the other leg member and one of the frame members to the straps, and a second pivot connects the other frame member to the straps.

position in which it is held by a latch which may be released by energizing a coil.

3,578,801

PRACTICE BASEBALL BAT

Raymond Piazza, 15402 Flagstaff St., La Puente, Calif.
Filed Dec. 30, 1968, Ser. No. 787,670

Int. Cl. A63b 59/06, 69/40

U.S. Cl. 273—26

4 Claims



A hollow bat for baseball practice having an internal longitudinal rod and movable weight which will increase the inertia of the bat during the swing.

3,578,802

VERTICALLY ADJUSTABLE BUMPER FOR BALL ROLLING GAMES


Frank T. Murphy, Chicago; Norman R. Clark, Oak Lawn, and William E. Casey, Chicago, Ill., assignors to Williams Electronic Manufacturing Corporation, Chicago, Ill.

Filed Feb. 25, 1969, Ser. No. 802,160

Int. Cl. A63b 71/00

U.S. Cl. 273—129

3 Claims



In order to provide for random or controlled variations in ball-rolling games, which include a ballfield and means for causing balls to enter upon the field and engage elements permitting scoring depending upon the skill of the player, this application discloses a bumper which is normally flush with the surface of the field, but which may be moved by that surface in order to impede the passage of balls used in the game. The bumper may be arranged to have its movement controlled in a random fashion or may be arranged to be subject to the ability of a game player to direct the passage of the ball. A solenoid is used to retract the bumper to its flush

3,578,803

SLIDE-RING SEAL


Dieter Karl Wilhelm Huhn, Lagmansuagen 9, Vallentuna, Sweden

Filed Feb. 13, 1969, Ser. No. 798,869

Claims priority, application Sweden, Feb. 15, 1968, 1,981/68
Int. Cl. F16j 15/34

U.S. Cl. 277—85

5 Claims



A slide-ring seal for rotating shafts seals two spaces separated by a transverse wall. The seal comprises a seal ring rotating with the shaft and a counter-ring in the said wall. A helical spring urges the seal ring towards the counter-ring. An O-ring or sleeve seals the ring against the periphery of the shaft. The cross section of the spring wire is substantially greater in its radial direction than in its axial direction, the spring transmitting to the shaft the entire or a substantial part of the slide friction between the slide surfaces. The spring is of conical shape and exerts both axial and radial forces so as to effect sealing between the sleeve and the periphery of the shaft also.

3,578,804

SAFETY ABUTMENT OF SKI BINDING


Jean Joseph Alfred Beyl, 10, blvd. Victor Hugo, Nevers, France

Filed Dec. 16, 1968, Ser. No. 783,843

Claims priority, application France, Dec. 29, 1967, 134,220
Int. Cl. A63c 9/00

U.S. Cl. 280—11.35T

3 Claims



A safety abutment of a front ski safety binding for coacting with the rounded toe end of a ski boot upper instead of with the sole portion thereof, the abutment device being so designed that it can coact with ski boots of different designs and sizes.

3,578,805

TUBE COUPLING

Lloyd K. Dutton, West Paterson, N.J., assignor to Mooney Brothers Corporation, Little Falls, N.J.

Filed Mar. 5, 1969, Ser. No. 804,581


Int. Cl. F16l 9/14

U.S. Cl. 285—55

4 Claims

A tube coupling for coupling tubes capable of carrying corrosive fluids, the tube coupling employing an outer body of relatively rigid, high strength material, an inner tubular member of a resiliently deformable, generally inert, corrosion resistant material such as a fluorocarbon resin received within the outer body and having a bore for receiving a tube therein, an annulus of elastomeric material having a first por-

tion placed around the inner tubular member adjacent an end thereof and a second portion extending beyond the end of the inner tubular member, the annulus retaining the inner tubular member within the outer body against inadvertent removal therefrom, a nut threaded onto the outer body and means coupling the nut and the annulus such that upon threading the nut along the outer body the coupling means



will axially contract the annulus to radially contract the inside diameter of the first portion of the annulus and thereby deform the inner tubular member radially inwardly to grip the tube therein and establish a seal between the inner tubular member and the tube therein and to radially contract the inside diameter of the second portion of the annulus and thereby grip the tube therein in response to axial movement of the threaded member.

3,578,806

TRAILER AND UNDERCARRIAGE THEREFOR


Roger R. Tonelli, Chicago, Ill., assignor to Radio Steel & Mfg. Co., Chicago, Ill.

Filed Feb. 14, 1969, Ser. No. 799,179

Int. Cl. B60p 1/24

U.S. Cl. 298-2

5 Claims



A trailer having an undercarriage formed from flat strip material which has an adjustable hitch on its front end and carries a self-dumping dump body is provided. A latch on the dump body is engageable with a cooperating member and need not be accurately registered therewith.

3,578,807

METHOD OF STEERING

Arthur Lee Barrett, 2928 Lothair Way, Michigan City, Ind.

Original application July 11, 1966, Ser. No. 570,109, now

Patent No. 3,421,796, which is a continuation-in-part of application Ser. No. 202,642, June 11, 1962, now abandoned

, which is a continuation-in-part of application Ser. No.

751,316, June 28, 1958, now abandoned. Divided and this

application Nov. 5, 1968, Ser. No. 773,584


Int. Cl. E21c 35/08

U.S. Cl. 299-1

10 Claims

A method of maintaining a desired distance between a steerable earth strata mining means and a laterally adjacent bore. A signal-reflecting means is placed at a known location along the bore. The mining means includes means to emit signals toward the reflecting means and another means to

receive a portion of the original signal which is reflected by the reflecting means. The mining means is steered in



response to the reflected signal received by the receiving means.

3,578,808

SOLUTION MINING METHOD AND APPARATUS


Byron P. Edmonds, and Douglas C. Ruse, Saskatchewan, Canada, assignors to Kolium Chemicals Limited, Regina, Saskatchewan, Canada

Filed Jan. 14, 1969, Ser. No. 790,935

Int. Cl. E21b 43/28

U.S. Cl. 299-4

12 Claims



A method of solution mining soluble subterranean deposits is shown in which a bore hole is cased to the depth equivalent to a desired height of a cavity to be developed in a deposit. Into the cased bore hole a tubing string is introduced with a liner rigidly mounted thereon. The tubing is passed through the casing and into the soluble deposit a substantial distance below the end of the casing set in the deposit. A fixed distance is provided between the end of the tubing and the end of the liner attached thereto. Solvent is then introduced into the soluble deposit and cavity development begun by dissolution of the minerals in the deposit with a suitable solvent. When lateral development of the cavity has proceeded to the desired extent, roof raises are made by moving the tubing string in a vertical direction upward from ground level. The fixed liner moves with the tubing string since it is rigidly mounted thereto. Thus, a fixed mining distance is maintained between the influent point for the solvent entering the soluble deposit and the effluent or withdrawal point. Roof raises can be accomplished in this manner as fixed distances until the liner is finally introduced into the casing by the vertical movement of the tubing toward the ground surface. The apparatus involved in conducting the novel method of the invention is also disclosed.

3,578,809

METHOD AND APPARATUS FOR FORMING SUBTERRANEAN STRUCTURES


Vernon Cunningham, P.O. Box 9337 Springhill Station, South Charleston, W. Va.

Filed May 9, 1969, Ser. No. 823,407

Int. Cl. E21d 23/00

U.S. Cl. 299-33

4 Claims



A multisection shield incorporates means for subterranean excavation and for conveyance of excavated materials and provides for the installation of the lining planks within the shield. This apparatus is employed in a system of tunnel or conduit lining wherein floor and roof planks are prepositioned and sidewall planks are wedged in place therebetween.

3,578,810

CABLE HANDLER TROUGHS

Gordon Newstead, Moorside, Durham, England, assignor to R. B. Bolton (Mining Engineers) Limited, Durham, England

Filed July 24, 1969, Ser. No. 844,279


Claims priority, application Great Britain, July 30, 1968,

36316/68

Int. Cl. E21c 35/20

U.S. Cl. 299-43

4 Claims



The present invention relates to chain conveyors for conveying bulk material, wherein the conveyor has mounted to it and extending along its length a trough for cables used in the operation of the conveyor. A tongue and an upstanding pin are provided on a fixed portion of the conveyor, and a slot to receive the tongue is provided on the trough. A locking plate extends through an aperture in an upright portion of the trough and over the pin. Shoulders on the plate engage the sides of the portion adjacent the aperture. A split dowel passes through the pin to retain the plate on the pin. The plate holds the trough in position on the tongue, but can be easily removed without disturbing the trough. The invention is particularly applicable to a conveyor used at a mining face, wherein the open-top trough contains power cables for the travelling cutter.

3,578,811

ROLLER CUTTER

Friedrich-Karl Bassler, Eppinghoven/Uber, Dinslaken, and Hans Tekathen, Dinslaken Niederrhein, Germany, assignors to Gebr. Eickhoff, Maschinenfabrik und Eisengiesserei m.b.H., Bochum, Germany

Filed Aug. 6, 1969, Ser. No. 847,964


Claims priority, application Germany, Aug. 10, 1968,

P 17 58 809.9

Int. Cl. E21c 27/24, 35/20

U.S. Cl. 299-45

3 Claims



A mining machine having a cutting roller supported by a pivotable supporting arm and rotatable about a horizontal axis, in which said cutting roller is equipped with a conveying shield pivotable about the axis of said roller while a ramp is connected to the machine carriage and ascends from the floor of the seam of the rock being mined to the upper edge of the long wall conveying means, both ends of said ramp carrying confining walls curved in conformity with the curvature of the conveying shield and arranged adjacent one edge of said shield, said confining walls in either one of two end positions of said conveying shield closing off the space between the conveying shield and the long wall conveying means.

3,578,812

SUPPORT WHEEL AND METHOD OF MAKING SAME


Frederick Taussig, Ladue, and Robert Gene Tanner, St. Charles, Mo., assignors to Arundale Manufacturers, Inc., St. Louis, Mo.

Filed Mar. 3, 1969, Ser. No. 803,853

Int. Cl. B60b 5/02

U.S. Cl. 301-63

10 Claims



The inventions are a support wheel assembly and a method of making it. The support wheel comprises a central bearing, a circular elastic tire, and a plastic wheel interposed between the bearing and tire. The tire has opposite circular clincher grooves on its sides and locking knobs on its inner wall. The plastic wheel is molded around the bearing, into the grooves, and around the knobs.

The method involves locating the tire, and usually the bearing, as inserts in a mold cavity, the tire being compressed at opposite sides adjacent the rim, causing it to be temporarily reduced in width, and to bulge inward at the clincher grooves. Plastic to form the wheel is injected under pressure through at least three equally spaced gates in the hub portion of the mold cavity. The plastic flows around the bearing insert, if present, then outwardly to form a wheel web, until it strikes an arcuate inner wall of the tire. It is thereby evenly divided to flow outwardly and laterally to form the wheel rim. At the edge of the rim it is deflected laterally into the clincher grooves of the precompressed tire to form a circular clincher bead therein, and also around the edge of the rim to

form a peripheral outer ridge. It flows around the knobs, or similar projections, on the inner wall of the tire and interlocks therewith.

The inward compression of the walls of the tire aids in preventing flow of the plastic up the sides of the tire, and, if the mold is designed in a manner herein disclosed, permits the formation of the ridges around the wheel rim adjacent the sides of the tire. A two-piece core and cavity mold is employed, the separations being located at the maximum outward extremes of the wheel, to vent air from the mold. Upon removal from the mold, the tire is snug on the wheel, and the wheel is shrunk or bonded to the bearing, if present.

3,578,813

DEVICE FOR IMPARTING A PRE-ARRANGED ARRAY TO AND CARRYING AN ORDERLY TRAIN OF ELONGATED BODIES, THE BARYCENTRE OF WHICH BEING ADJACENT AND END THEREOF

Tomaso Ruscitti, Via Amedeo D'Aosta, 11, Milan, Italy


Filed July 17, 1968, Ser. No. 745,527

Claims priority, application Italy, Aug. 5, 1967, 19277/67

Int. Cl. B65g 53/30

U.S. Cl. 302-14

6 Claims



Device for imparting a vertical array and conveying along guide means drawing tubes applied on valves to be attached on aerosol containers, the device comprising a container from which the tubes are caused to randomly drop on a moving belt provided with perforated housings or slots. Prior to dropping on the belt, the tubes orientate in a vertical direction due to friction encountered with the fluid in which they move and, once having dropped into the belt housing or slot, they are retained therein due to suction exerted below the belt and then conveyed to collecting guides.

3,578,814

METHOD AND APPARATUS FOR CONVEYING DUST


Percy E. Todd, Apison, Tenn., assignor to Percy Todd Manufacturing Company, Cleveland, Tenn.

Filed Sept. 3, 1968, Ser. No. 756,820

Int. Cl. B65g 53/40

U.S. Cl. 302-40

5 Claims



A method and apparatus for conveying particulate material from a silo to a container in which material is transferred to a surge container that is substantially at atmospheric pressure, pressurized fluid is then directed into the surge container to entrain the particulate material and convey it along the path, the path having a trap to assure that the particulate material is conveyed by the fluid.

3,578,815 MATERIAL DISCHARGE ARRANGEMENT FOR HOPPER STRUCTURES


William D. Mundinger, Highland, Ernest J. Nagy, Munster, Ind., assignor to Pullman, Incorporated, Chicago, Ill.

Filed Sept. 30, 1968, Ser. No. 763,745

Int. Cl. B65g 53/40

U.S. Cl. 302-52

14 Claims



A discharge arrangement for hopper structures including a sliding gravity gate which is movable to open and closed positions relative to the hopper structure with the gate being movable by a manually operable mechanism. A pneumatic discharge pan is positioned beneath the gate and may be selectively interconnected by an indexing arrangement with the gate to move therewith to the open and closed positions. The manually selectable indexing arrangement by movement of a single rotating shaft is adapted to connect the discharge pan to the gate for movement therewith, to lock the pan in position underneath the discharge opening of a hopper with the gate moved to an out-of-the-way position, and to lock both the gate and the discharge pan in a closed position.

3,578,816

METHOD OF FACILITATING THE RESUSPENSION OF THE SOLID PHASE OF A SLURRY IN A SHUTDOWN PIPELINE


Junn-Ling Chao, Houston, Tex., assignor to Shell Oil Company, New York, N.Y.

Filed Feb. 26, 1969, Ser. No. 802,615

Int. Cl. B65g 53/04

U.S. Cl. 302-66

3 Claims



Method for facilitating the resuspension of settled solids in a shutdown slurry pipeline. As flow in the pipeline is terminated a bladder or bag in the line is inflated in those locations where plug formation by slumping slurry solids is likely to occur. In this manner the settling solids will only occupy the space in the line not occupied by the bladder. Upon restart, the bladder is deflated to allow lateral movement of the solids in the line, thereby facilitating resuspension thereof.

3,578,817

CONTROL OF MINE HOIST BRAKING

Peter De Hertel Eastcott, Peterborough, Ontario, Canada, assignor to Canadian General Electric Company Limited, Toronto, Ontario, Canada

Filed Sept. 19, 1969, Ser. No. 859,272

Claims priority, application Canada, Oct. 26, 1968, 33617


Int. Cl. B60t 7/12

U.S. Cl. 303-16

4 Claims

The safety controller for a mine hoist usually incorporates some means for giving a warning of an impending emergency stop when the speed of the hoist exceeds the speed called for by the operating program. Instead of an abrupt emergency

stop, this invention enables the hoist to make an emergency stop at a controlled rate of slowdown giving about the same smoothness as obtained during normal operation. According to the invention, a brake deceleration regulator, which exercises no control over the hoist while it obeys the program, is placed in control of braking by the warning means on the safety controller when the speed of the hoist exceeds the speed called for by the program by the amount necessary to



activate the warning means. The deceleration regulator then brings the hoist to a smooth stop at a fully controlled rate. Since the warning means becomes active at a speed somewhat lower than the speed necessary to bring on a full emergency stop, unregulated emergency stopping will seldom if ever occur. In practice, the deceleration regulator introduces another level of safety into the braking system, a level which produces a smooth stop and reserves the emergency stop for the most extreme conditions conceivable.

3,578,818

PNEUMATIC ENGINE FOR MINE HOIST BRAKING


Peter De Hertel Eastcott, Peterborough, Ontario, Canada, assignor to Canadian General Electric Company Limited, Toronto, Ontario, Canada

Filed Sept. 19, 1969, Ser. No. 859,345

Int. Cl. B60x 7/12

U.S. Cl. 303-16

13 Claims



Instead of using a single large pneumatic actuator for driving the brake shoes against the rotating brake surface, this invention uses a number of smaller pneumatic actuators, controlled individually and collectively by means of a regulator, for driving the shoes against the braking surfaces. The actuators are coupled with the brake shoes and the pneumatic fluid is controlled by the regulator such that one actuator normally applies the brakes for a medium or light braking effort and it is assisted by one or more of the other actuators

3,578,819

SKID CONTROL SYSTEM


Thomas M. Atkins, Ann Arbor, Mich., assignor to Kelsey-Hayes Company, Romulus, Mich.

Filed Sept. 23, 1968, Ser. No. 761,709

Int. Cl. B60t 8/08

U.S. Cl. 303-21

31 Claims



A skid control system for fluid-actuated brakes of a wheeled vehicle including a modulating valve for modulating the fluid pressure to the fluid-actuated brakes and a control circuit for controlling the valve in response to indications of wheel speed and/or wheel deceleration.

3,578,820

TWO-WHEEL SKID CONTROL BY MODULATION OF BRAKE POWER BOOSTER


Hugh E. Riordan, Ann Arbor, Mich., assignor to Kelsey-Hayes Company, Romulus, Mich.

Filed Aug. 18, 1969, Ser. No. 850,933

Int. Cl. B60t 8/12, 13/10

U.S. Cl. 303-21

8 Claims



A skid control system for a vehicle having front and rear wheels in which the brakes of the rear wheels are to be skid controlled and with a system utilizing a power booster, this system including means for locking in the pressure to the front brakes upon the occurrence of a skid control signal, at which time the power booster is relieved whereby the pressure to the rear brakes is relieved.


3,578,821

BRAKE LIMITERS

Michel Guettier, Billancourt, France, assignor to Regie Nationale Des Usines Renault, Billancourt (Hauts de Seine), France and Automobiles Peugeot, Paris, France
 Filed Mar. 14, 1969, Ser. No. 807,369
 Claims priority, application France, Mar. 27, 1968, 145,645
 Int. Cl. B60t 15/00, 8/18

U.S. Cl. 303—22

1 Claim



The braking effort-limiting device comprises two closely interfitting valve bodies each enclosing a valve and a single control member engaging directly the valve of one body, said valve being adapted in turn to drive directly the valve of the second body responsive to the action of an antagonistic spring.

3,578,822

DYNAMICALLY BALANCED POWER TRANSMISSION

Arthur J. Stemmons, Los Gatos, Calif., assignor to FMC Corporation, San Jose, Calif.

Filed Aug. 12, 1969, Ser. No. 849,404
 Int. Cl. B62d 55/08

U.S. Cl. 305—24

11 Claims



A rotating power transmission member engaged with a segmented power transmission means is balanced to counteract vibratory torques and forces by three tuned pendulum balance weights spaced 120° apart. A specific application is to a crawler vehicle with tuned pendulums in the track drive, bogey and idler wheel assemblies to balance and counteract vibratory forces and torques transmitted to the wheels by the track. The balance weights are built into each wheel assembly and are tuned to the same order as the number of teeth on the track drive wheel so that the balance weights produce counterforces and counter torques, per revolution, equal to those from the number of track segments, per revolution, causing the imbalance forces and torques. In the case of the idler and bogey wheels, the tuning order is the effective pitch circumference divided by the track pitch.

3,578,823

LINKS FOR THE ENDLESS TRACKS OF TRACK-LAYING VEHICLES

Frank Clymer, Lichfield, England, assignor to Lloyds (Burton) Limited, Burton-on-Trent, England
 Filed Nov. 21, 1968, Ser. No. 777,754
 Claims priority, application Great Britain, Nov. 28, 1967, 54,107/67


Int. Cl. B62d 55/20

U.S. Cl. 305—42

2 Claims

A track link having at each end at least one bush which is formed of elastomeric material and which is located in a recess formed in the link, the exterior of the bush being of

noncircular configuration in cross section whilst the interior of the bush is provided with a sleeve-like insert which is formed of rigid material, the interior of said insert being of noncircular configuration in cross section and being adapted



to receive in use a pin of corresponding cross section which will extend through the bush or bushes at the end of one link and an aligned bush or aligned bushes at the adjacent end of an adjacent link.

3,578,824


ENDLESS TRACK TREAD

Earl R. Woodward, Jr., Mars, Pa., assignor to Woodward, Inc., Mars, Pa.

Filed Mar. 24, 1969, Ser. No. 809,587
 Int. Cl. B62d 55/26

U.S. Cl. 305—54

2 Claims



An endless track tread involving the use of two pieces of plate which are welded together in offset relationship at both ends and drilled, or the use of a unitary section of plate of similar offset outline, for use as one of the plurality of overlapping and nesting treads of a self-propelled tractor vehicle.

3,578,825

HAND TOOL

George W. Merrow, Bloomfield, and Robert F. West, Simsbury, Conn., assignors to The Stanley Works, New Britain, Conn.

Filed June 26, 1968, Ser. No. 740,178
 Int. Cl. B25g 3/10

U.S. Cl. 306—32

12 Claims

A hammer is provided with a glass fiber reinforced handle having a tenon-shaped end portion in pressurized engagement with the eye of the hammer head. The handle, which is securely connected to the hammer head without the necessity for separate wedging members or materials, is spaced from the head at the inner end of the eye while being in intimate surface contact therewith along the plane of percussion for a distance of approximately two-thirds the axial length of the eye. The shank and grip portions of the glass fiber reinforced handle are dimensioned to permit mounting of the handle by

passing the shank and handle portions through the eye. Additionally, the handle is self-aligning within the eye by means of

but not made to the same close tolerances so that some deviations exist. Air bearings are held adjacent these surfaces with ball-and-socket mountings to allow universal movement



a pair of opposed handle aligning ribs which also serve to confine an auxiliary bonding material.


3,578,826
OILER BUSHING

Kasimir Janiszewski, 5426 W. Andover Road, Milwaukee, Wis.

Filed Sept. 23, 1969, Ser. No. 860,370
 Int. Cl. F16c 17/00, 33/10

U.S. Cl. 308—4

9 Claims



A conventional bushing has an oiler extension of very slightly increased interior diameter attached to it by a sleeve having pressed-fit connection externally with the bushing and extension. The oiler section is spool shaped, providing an oil-retaining well between it and the sleeve, and it has a shoulder proximate the bushing to seat an annular wick which has extensions downwardly into the well. Both the bushing and this extension are hardened and the bushing provides an extremely tight fit upon the leader pin, the pin being guided by the extension in entering the bushing.

3,578,827

ARRANGEMENT FOR PROVIDING PRECISE MOVEMENT


Joseph E. Smith, Torrance, Calif., assignor to Excellon Industries, Torrance, Calif.

Filed Feb. 19, 1969, Ser. No. 800,488
 Int. Cl. F16c 17/00

U.S. Cl. 308—5

19 Claims

This arrangement for providing precision motion includes two relatively movable members, one of which is provided with a surface accurately defining a predetermined path, opposite which is a surface approximately parallel to the first,



of the bearings. The bearings adjacent the irregular surface are held by a resilient means, which allows them to move when inaccuracies are encountered.

3,578,828


SPLIT-RACE BEARING CONSTRUCTION

Stanley S. Orkin, Rockville, Conn., and Richard W. Hartswick, Granby, Conn., assignors to Kaman Aerospace Corporation, Bloomfield, Conn.

Filed Feb. 18, 1969, Ser. No. 800,143
 Int. Cl. F16c 17/10

U.S. Cl. 308—37

20 Claims



A dry, self-lubricating bearing comprises an outer and an inner race with coengaging bearing surfaces with the bearing surfaces on one race being made of a solid lubricant material and the bearing surfaces on the other race being made of a hardened material such as a thin ceramic coating on a metal substrate. In one embodiment, the outer race comprises a single member while the inner race comprises two separate members slidably carried within opposed seats of the outer race with the bearing being capable of absorbing radial, axial and moment loading individually or in combination. In other embodiment, the outer race is split comprising two members and/or the outer race is carried within concave seats of the inner race.

3,578,829

BOTTOM BRACKET FOR BICYCLE

Kotaro Hata, Nara-shi, and Toshikazu Fujii, Yao-shi, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Nov. 21, 1969, Ser. No. 878,796
 Claims priority, application Japan, Nov. 26, 1968, Apr. 1, 1969, 43/86784; 44/26382


Int. Cl. F16c 3/06

U.S. Cl. 308—179.5

7 Claims

A bottom bracket for bicycle having a pair of ball bearings for supporting a crankshaft, at least one of the bearings having an inner race slidable with respect to the crankshaft, and a coil spring urging the inner race of said one bearing against

the steel balls to avoid chattering of the elements due to localized or irregular wear which would otherwise be produced




on these members thereby to facilitate smooth rotation of the crankshaft.

3,578,830 NEEDLE BEARINGS

Alfred Pitner, Paris, France, assignor to Rueil Nadella, Malmaison, France, fractional part interest
Filed Aug. 26, 1969, Ser. No. 853,075
Claims priority, application France, Aug. 30, 1968, 164,658
Int. Cl. F16c 35/06

U.S. Cl. 308-207

9 Claims



A needle bearing in which the space for circulation of the needles between the two races is reduced in a plurality of angularly spaced zones around the bearing. To this end the ring forming one of the races is radially deformed in one direction in the region of each of the zones and is supported by an auxiliary resilient member, either the ring or the auxiliary member or both having a variable peripheral profile so that when subjected to axial compression, radial deformation is obtained both of the auxiliary member and the ring in accordance with the peripheral variations to thereby give raised appearance in the zones around the bearing. Furthermore the axial compression of the auxiliary member is adjustable during manufacture to produce a desired radial deformation and this axial compression is subjected into the bearing to maintain this radial deformation permanently during the life of the bearing.

3,578,831 COMPOSITE TAPERED ROLLER BEARING AND METHOD OF MAKING THE SAME

Hudson B. Scheifele, 30165 Ponds View Road, Franklin, Mich. 48025
Division of Ser. No. 685,525, Nov. 24, 1967, abandoned, filed Feb. 13, 1969, Ser. No. 798,931
Int. Cl. F16c 33/34


U.S. Cl. 308-214

3 Claims

This composite tapered roller bearing has outer and inner races, each of which is built up by a method which includes forming annular inner and outer tapered or frustoconical load-bearing roller path members formed from unheated butt-welded strips of steel, subsequently heat-treating and final grinding these annular members, welding to the large end of the annular inner roller path member a finished side ring, forming an annular roller retainer with circumferentially spaced pocket openings, assembling a complement of tapered rollers in these circumferentially spaced pocket

openings of this annular roller retainer, these tapered rollers having spherical surfaces on their larger diameter ends, placing the thus-formed assembly on the thus partially built-up inner race, and welding a smaller side ring to the other end of the annular inner roller path member.

These tapered rollers engage a tapered or frustoconical annular inner load-bearing surface on the annular central roller path member of this composite tapered roller bearing inner race, the larger diameter side ring of which has an annular




inner surface of spherical curvature mating with the spherically curved surfaces on the larger ends of the tapered rollers. Before welding, the inner roller path member and the side rings are preferably case hardened in the areas actually engaged by the side and end surfaces respectively of the rollers, the remaining area of each ring not so engaged being selectively excluded from the case hardening. This enables the bearing components to be case hardened and precision ground and honed before assembling and welding, preferably by electronic or laser welding to precisely localize the welds.

3,578,832 STABILIZED ELEVATOR FILING DEVICE

Lloyd M. Toms, Crozet, Va., assignor to Acme Visible Records, Inc., Crozet, Va.
Filed Apr. 29, 1969, Ser. No. 820,213
Int. Cl. A47b 47/00

U.S. Cl. 312-268

2 Claims



Stabilizer means for a vertically disposed elevator-type filing apparatus comprising a cabinet having a front opening and wherein a plurality of trays disposed therein are adapted to be moved in an elliptical path and presented at said opening for access to said trays on the links of a sprocket chain, comprising closed path elliptical stabilizer means in the form of channel members embracing said sprocket chains and defining spaced vertical components and a pair of double arch components at the top and bottom of said vertical components and merging and communicating with each other and with said vertical components and triangular stabilizers pivoted at one corner to swivel pins carried by support means secured to said trays and carrying rollers at its two remaining corners disposed to slide in and retained by said channel members.

3,578,833 DRAWER SUSPENSION


Philip Frederick, Brooklyn, N.Y., assignor to Supreme Equipment & Systems Corp.

Filed Mar. 14, 1969, Ser. No. 807,291

Int. Cl. A47b 88/00

U.S. Cl. 312-330

6 Claims



A suspension system for a cabinet or the like having at least one drawer comprising upper and lower rollers on each side of the drawer with a cable having both ends affixed to the cabinet (directly or indirectly) threaded in front of the upper roller and in back of the lower roller on each side, each of the cables being under tension, and an adjusting means for each of the cables comprising a block slidable in a direction parallel to the length of the cable, one end of the cable affixed to the block, and a screw means adapted to cause the block to move in its direction of motion and to maintain the block in the position to which it has been moved, whereby the tension on the cable can be adjusted.

A track in the foregoing device mounted immediately beneath the lower roller and extending in the direction of movement of the drawer and so positioned as to be in support relationship with the lower roller when the tension in the cable is insufficient to support the lower roller and the drawer without assistance.

3,578,834 GENERATION OF ALKALI METALS

Paolo Della Porta, and Elio Rabusin, Milan, Italy, assignors to S.A.E.S. Getters S.p.A., Milan, Italy
Continuation-in-part of application Ser. No. 690,125, Dec. 13, 1967. This application Feb. 12, 1969, Ser. No. 798,785
Claims priority, application Italy, Dec. 15, 1966, and Oct. 12, 1967, 31040/66 and 21538A/67
Int. Cl. H01j 9/38, 7/12

U.S. Cl. 316-16

20 Claims

Compositions of matter which release alkali metal vapors comprising an alkali metal compound and a reducing agent for the compound wherein the reducing agent is an alloy of 5 to 30 weight percent aluminum balance zirconium. These compositions are useful in processes for the release of alkali metal vapors used in the production of photosensitive surfaces in vacuum tubes.

3,578,835 ART OF MAKING VACUUM ENVELOPES

Lowell A. Noble, Hillsborough, and Robert B. Hanley, Campbell, Calif., assignors to Varian Associates

Filed July 28, 1960, Ser. No. 46,026


Int. Cl. H01j 7/18

U.S. Cl. 316-25

7 Claims

1. A bakeout process for a vacuumtight tube containing materials which liberate gases at a given bakeout temperature and a metal which sorbs gases at said bakeout temperature, said process comprising the steps of heating said tube to said bakeout temperature to remove occluded gases, evacuating said tube during said bakeout step, cooling said gas sorbing metal during said bakeout step to maintain the

gas sorbing metal at a temperature at which it is substantially ineffective to sorb gases, heating said gas sorbing metal after



said bakeout step, introducing a hydrogen isotope into said tube, and cooling said tube.

3,578,836 RETRIEVAL OF HOLOGRAPHICALLY RECORDED DATA


William J. Hannan, Pennington, N.J., assignor to RCA Corporation

Filed Oct. 16, 1968, Ser. No. 767,991

Int. Cl. G03b 27/10, 27/32

U.S. Cl. 350-3.5

3 Claims



A two-step process for retrieving holographically recorded pages of information. In the first step, a low power laser is employed to reconstruct the image stored in a small hologram and to record this image in a small area of recording medium. In the second step, a high power incoherent light source and optical means are employed to derive from the small image an enlarged hard copy.

3,578,837 DOUBLE-DIFFUSER HOLOGRAPHIC SYSTEM

Robert E. Brooks, Redondo Beach, Calif., assignor to TRW Inc., Redondo Beach, Calif.

Filed Apr. 1, 1969, Ser. No. 811,805


Int. Cl. G02b 27/00

U.S. Cl. 350-3.5

6 Claims

A holographic system for recording holograms of an object in transmission. In order to make more uniform the spatial coherence and the intensity of the light beam of a laser, a light diffuser is disposed in the path of the scene beam. In addition a second light diffuser is also disposed in the path of the diffused and enlarged scene beam. Preferably the second diffuser has a certain directivity which may be achieved by coating the diffusing surface with a transparent lacquer. In order to further improve the directivity of the second diffuser there may be provided a Fresnel lens having one of its focal points in the first diffuser and the other focal point in the recording material for the hologram. The second diffuser

may be replaced by a diffusing and reflecting ellipsoidal section which serves simultaneously the purpose of diffusing the



scene beam and directing it from the first diffuser to the recording material.

3,578,838


MULTIPLE HOLOGRAM RECORDING AND READ OUT SYSTEM

James N. Hallock, Watertown, Mass.

Filed Aug. 28, 1969, Ser. No. 853,856
Int. Cl. G02b 27/22

U.S. Cl. 350—3.5

4 Claims



An information recording and readout system is presented wherein multiple holograms are recorded in a single hologram recording medium by the use of three intersecting light beams and a lens system. Hologram patterns are formed by adding a third intersecting light beam to the two intersecting light beams normally used in hologram formation. The location of the third beam is changed for each different hologram to be formed on the medium. Readout, for the case of pattern identification, is accomplished by presenting patterns to the holographic medium and recreating and sensing the position of the third beam.

3,578,839


AUTOMATED DEVICE FOR PROTECTING LENS SYSTEMS

Grant C. Riggle, Bethesda, and James P. White, Bradbury, Md.

Filed Oct. 24, 1968, Ser. No. 770,344
Int. Cl. G02b

U.S. Cl. 350—61

8 Claims



The automated device for protecting lens systems in lasers includes a motor driven protective film which advances across the laser lens after each light flash. A mechanical sen-

sor operative in response to film position selectively connects the film driving motor to an electro-optical control system which energizes the motor in response to light flashes.

3,578,840

REVOLVING REFLECTOR


John O. Richards, 5715 Stumph Road, Parma, Ohio

Filed Jan. 26, 1970, Ser. No. 5,507

Int. Cl. G02b 5/12

U.S. Cl. 350—99

4 Claims



A revolving reflector having three prismatic-shaped blades attached to a bushing through which a central shaft is inserted. The device, due to the position and shape of the prismatic blades, will rotate regardless of the wind direction or its position on a moving object. The various blade surfaces are coated with different reflecting and nonreflecting materials and provide a flashing effect by reflecting light when revolving. The device can be utilized in various ways, as a safety device, on a child's bicycle, or as an indicating marker for a driveway, etc. The revolving reflector is of simple design and can be produced inexpensively, yet is sturdy and durable.

3,578,841

REAR PROJECTION SCREEN


William B. Elmer, 113 Pinckney St., Thornton, N.H. 02114

Filed Dec. 15, 1967, Ser. No. 690,970

Int. Cl. G03b 21/60

U.S. Cl. 350—127

11 Claims



A rear projection screen has a rear surface that provides lens action for collimating incident light rays on essentially the entire screen surface into parallel rays directed essentially perpendicular to the front surface. The front surface is formed with a number of generally parallel closely spaced ribs that diverge incident light rays over a prescribed viewing angle so that anyone within the prescribed viewing angle sees the image projected on the screen with essentially equal brightness. For wide viewing angles the ribs are preferably arranged in clusters so that respective ribs in a cluster direct light rays to respective angular sectors of the viewing region.

3,578,842

EXPLODING MIRROR FOR OPTICAL VIEWING SYSTEM


Richard J. Holland; Zoltan G. Sztankay, Washington, D.C., and Timothy J. Kilduff, Greenbelt, Md., assignors to the United States of America as represented by the Secretary of the Army

Filed Oct. 8, 1968, Ser. No. 766,383

Int. Cl. G02b 5/08

U.S. Cl. 350—160

4 Claims



An exploding mirror for an optical viewing system which will partially self-destruct when a laser beam of a minimum predetermined energy density impinges thereon. Using an epoxy encapsulation method, an explosive charge is placed adjacent a thin film mirror on a glass slide. The opposite side of the mirror is part of the optical sight path of the viewing system. A laser beam of sufficient energy density will cause the explosive charge to detonate, thus blowing out a critical section of the mirror and disrupting the optical sight path, thereby protecting the viewer.

3,578,843

CONTROL OF LIGHT REFLECTED FROM A MIRROR


George Augustus Castellion, Stamford, Conn., assignor to American Cyanamid Company, Stamford, Conn.

Filed Sept. 25, 1968, Ser. No. 773,690

Int. Cl. G02f 1/28

U.S. Cl. 350—160

7 Claims



Electro-optical device useful in modulation of reflected light, and the like, typically comprising an electrochromic device and a reflecting layer in sandwiched arrangement, said electrochromic device itself being a sandwich arrangement of a pair of transparent electrodes, and a film of a transition metal compound and an insulating film disposed between the electrodes. The electrochromic device exhibits coloration and bleaching thereof at ambient temperature by control of the polarity of an applied electric field, whereby light reaching the reflecting layer is modulated in intensity, thus modulating, in turn, the reflected light.

3,578,844

RADIATION SENSITIVE DISPLAY DEVICE CONTAINING ENCAPSULATED CHOLESTERIC LIQUID CRYSTALS


Donald Churchill, Kettering, and James V. Cartmell, Dayton, Ohio, assignors to The National Cash Register Company, Dayton, Ohio

Filed Feb. 23, 1968, Ser. No. 707,823

Int. Cl. B01g 13/00; H01j 29/10; G02f 1/34

U.S. Cl. 350—160

17 Claims



This disclosure is directed to articles of manufacture, chiefly display devices, containing encapsulated cholesteric liquid crystals which change color or shade of color not only upon application of an electric potential but also upon removal of the field. The image produced has a comparable outline to that of the path of the electric field. Three chromatic states are evident, the normal color (before the electric potential is applied), the color given off when the electric field is applied, and the color observed when the electric field is removed. All three chromatic states are readily discernible from one another. The encapsulation of the cholesteric liquid crystal provides an unusual advantage regarding electric field behavior because the third chromatic state (electric potential removed) has a much greater longevity with the encapsulated material versus unencapsulated material of identical composition. Other advantages are also discussed.

3,578,845

HOLOGRAPHIC FOCUSING DIFFRACTION GRATINGS FOR SPECTROSCOPES AND METHOD OF MAKING SAME


Robert E. Brooks, Redondo Beach; Lee O. Heflinger, Torrance, and Ralph F. Wuerker, Palos Verdes, Calif., assignors to TRW Inc., Redondo Beach, Calif.

Filed Feb. 12, 1968, Ser. No. 704,884

Int. Cl. G02b 5/18; G01j 3/18

U.S. Cl. 350—162R

4 Claims



A method making a focusing diffraction grating including casting a diverging beam of coherent light on a photographic plate, casting a convergent beam of coherent light on the same plate so that the beams interfere with each other on the light-sensitive plane of the plate, and then developing the plate. A holographic focusing diffraction grating having a plurality of curved, spaced grating lines on the face of the grating, the lines having specific curves and spacing relating to specific predetermined wavelengths of light for diffracting specific wavelengths of light at predetermined angles. A spectroscope, spectrograph, or spectrometer having a holographic focusing diffraction grating.

3,578,846

MULTIPLE-STAGE OPTICAL INFORMATION PROCESSING SYSTEM


Wu Chen, Royersford, Pa., assignor to Sperry Rand Corporation, New York, N.Y.

Filed Jan. 31, 1969, Ser. No. 795,617

Int. Cl. G02b 27/38

U.S. Cl. 350-162

2 Claims



An optical pattern recognition system is disclosed which has multiple reference-pattern capability and materially decreases the space occupied as compared with the prior art. These advantages flow from the use of a zigzag optical path employing concave mirrors in the system and a novel observation plane which allows cascaded multistage operation. An additional advantage is that the mirrors used may be made of metal or other material and force cooled allowing the use of higher intensity sources.

3,578,847

THREE ELEMENT OBJECTIVE LENS


David S. Grey, Lexington, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Continuation-in-part of application Ser. No. 687,167, Dec. 1, 1967. This application Oct. 3, 1969, Ser. No. 863,562

Int. Cl. G02b 7/04, 9/16

U.S. Cl. 350-226

1 Claim



A telephoto triplet objective lens is disclosed wherein the first element facing the longer conjugate is a positive meniscus lens of relatively high power and thickness. The second element is a negative, biconcave, relatively thick, lens. The third element is a relatively thin biconvex positive lens. Lens elements two and three are made from the same material. This lens is designed to be molded from polymer materials.

3,578,848

METHOD OF MAKING AN INTERFERENCE FILTER

Robert R. Austin, Ridgefield, Conn., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed Jan. 26, 1968, Ser. No. 700,928


Int. Cl. G02b/00

U.S. Cl. 350-320

1 Claim

A Fabry-Perot type interference filter in which the two reflectors are identical high reflection coatings and are separated by a spacer element made of solid glass. The

coatings are formed on individual substrates which are optically contacted to the ends of the spacer. The coated ends of the substrates are optically contacted to the spacer element



in sequence. After the first substrate is joined to the spacer element, the thickness of the spacer element is adjusted. Once the size of the spacer element is precisely that required, the other substrate is joined to it.

3,578,849

DIAPHRAGM FOR A LASER AMPLIFIER CHAIN

Hubert Guillet, Saint Germain-les-Arpajon, France, assignor to Commissariat A L'Energie Atomique, Paris, France


Filed July 10, 1969, Ser. No. 840,813

Claims priority, application France, July 23, 1968, 160311

Int. Cl. G02b 27/00

U.S. Cl. 350-321

1 Claim



A diaphragm for a laser amplifier chain, comprising an element operable as a transparent divergent lens to an incident laser beam and including an aperture disposed centrally of the lens and of a size to permit a substantially part of a laser beam to pass from a driver laser to a laser amplifier. The element has a planar face on the side of the driver laser and a concave recess surrounding the aperture on its other side.

3,578,850

ANTI-FLARE CONTACT LENS

Alan H. Grant, 3208 Woodhollow Drive, Chevy Chase, Md.


Continuation of application Ser. No. 707,784, Feb. 23, 1968,

now abandoned. This application Feb. 11, 1970, Ser. No. 10,592

Int. Cl. G02c 7/04

U.S. Cl. 351-160

2 Claims



Contact lens, together with process and apparatus for making the contact lens, which has an annular surface area of ir-

3,578,853

MOTION PICTURE CAMERA


Johann Roth, Schwabhausen; Alfred Roppel, Munich, and Theodor Steibl, Maisach, Germany, assignors to Niezoldi & Kramer GmbH, Munich, Germany

Filed Nov. 26, 1968, Ser. No. 779,051

Int. Cl. G03b 7/14, 21/36

U.S. Cl. 352-91

19 Claims



3,578,851

AUTOMATICALLY THREADED FILM APPARATUS INCORPORATING A PROJECTION APPARATUS AND A PRE-THREADED FILM CARTRIDGE ASSEMBLY


Christian Jensen, Oslo, Norway, assignor to MPO Videotronics, Inc., New York, N.Y.

Filed May 24, 1967, Ser. No. 641,039

Int. Cl. G03b 23/02

U.S. Cl. 352-72

10 Claims



An automatically threaded film apparatus having a projection apparatus and a prethreaded film cartridge assembly intended to be detachably mounted at the projection apparatus. Owing to the synchronous feeding out, running and winding up of the film on the same shaft the film is not exposed to friction, wear and tear. Moreover, mechanism is provided to insure that the film automatically adjusts itself to a desired frame separation between a film gate assembly and a sound head. Simple operation of the unit is insured for by the overall arrangement wherein a common control knob or the like initiates various operations required for reliable visual and/or sound reproduction.

A motion picture camera with an adjustable rotary shutter and a diaphragm which is adjustable as a function of scene brightness. A lever is pivotable about a fixed axis to adjust the shutter and is movable radially of the axis to adjust the diaphragm independently of scene brightness as a function of the corresponding adjustment of the shutter.

3,578,854

MOTION PICTURE PROJECTOR

Johann Roth, Schwabhausen, Germany, assignor to Niezoldi & Kramer G.m.b.H., Munich, Germany

Filed Oct. 15, 1968, Ser. No. 767,748


Claims priority, application Germany, Oct. 18, 1967,

P 15 97 341.8

Int. Cl. B65h 17/42; G03b 1/58

U.S. Cl. 352-158

25 Claims



3,578,852

MOTION PICTURE APPARATUS HAVING SENSING MEANS FOR FILM CARRIED CUE SIGNALS


Charles A. Aldridge, Barrington, Ill., assignor to Bell & Howell Company, Chicago, Ill.

Filed June 10, 1968, Ser. No. 735,861

Int. Cl. G03b 21/50

U.S. Cl. 352-92

4 Claims



An apparatus for projecting motion picture films has a sensing station located adjacent the path of each margin of the film for sensing control marks on the film. The sensing stations may be selectively actuated to respond to markings on either of the marginal areas or to respond only to the simultaneous occurrence of markings on both marginal areas.

A motion picture projector wherein the leading end of motion picture film is initially engaged by a first sprocket and thereupon advances along a first fixed loop former, through the film gate and along a second fixed loop former to move into the range of a second sprocket which advances it around

a pivotable deflecting roll and into engagement with the core of a driven takeup reel so that the latter subjects the film to tension. Such tension is utilized to impart to the sprockets additional movements in directions to move the loops of film away from engagement with the loop formers. This is achieved by rotating the first sprocket counter to its normal direction of rotation and by effecting short-lasting additional rotary movement of the second sprocket in its normal direction of rotation. Such movements are superimposed upon normal movements of the sprockets in response to axial movement of two worms each of which drives one of the sprockets by way of a worm wheel, or in response to appropriate displacement of an endless belt which is trained around pulleys rigid with the sprockets.

3,578,855

PROJECTOR FRAME CONTROL


Angelo Boudouris, Sylvania, Ohio, assignor to Eprad Incorporated, Toledo, Ohio

Filed Feb. 20, 1969, Ser. No. 801,010

Int. Cl. G03b 21/46

U.S. Cl. 352-163

4 Claims



A frame control device for aligning frames on film with a projection lens. A control sleeve is coaxially mounted for limited movement on a driven axle and a film drive sprocket is coaxially mounted on the sleeve for limited movement of the sleeve with respect to the sprocket. Thrust bearings prevent axial movement of the axle and the film sprocket. The sleeve is keyed to the axle and the sprocket such that the phase relationship between the sprocket and the axle may be adjusted by changing the axial position of the sleeve on the axle, thereby aligning the film frame with the lens.

3,578,856

MOTION PICTURE CAMERA WITH FOOTAGE COUNTER

Kurt Thate, Munich; Friedrich Winkler, Unterhaching, and Anton Theer, Munich, Germany, assignors to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Germany


Filed Apr. 30, 1969, Ser. No. 820,491

Claims priority, application Germany, May 18, 1968, A 29 797

Int. Cl. G03b 1/60

U.S. Cl. 352-172

13 Claims



A motion picture camera wherein the film transporting mechanism drives a worm in response to insertion of a film

magazine, and the worm moves a pointer with reference to a graduated footage counter scale to indicate the length of exposed and/or unexposed part of the film. The worm is pivoted away from engagement with the pointer in response to removal of the magazine whereby a spring resets the pointer to zero position. The scale transmits light and has an arm which is observable in the view finder. When the pointer moves all the way from starting position, it completely shields the scale from ambient light whereby the operator is informed that the entire film is exposed.

3,578,857

PLURAL UNIT PROJECTION SYSTEM


Edwin Busch, 214 S. Hamilton St., Saginaw, Mich.

Continuation-in-part of application Ser. No. 697,201, Jan. 11, 1968. This application Jan. 27, 1970, Ser. No. 886,420

Int. Cl. G03b 21/26

U.S. Cl. 353-94

22 Claims



A multiple unit projection system for transmitting images to a remote screen wherein a plurality of projectors selectively project an image on the screen along a common image projecting path. At least a pair of the projectors are individually movable from a remote inoperative position to an image projecting position and apparatus is provided for shifting at least one of the movable projectors from the remote inoperative position to an image projecting position and to simultaneously automatically shift at least one of the other movable projectors to its remote position. Mirror means is provided to transmit the image emanating from one of the projectors to the screen along the image projecting path.

3,578,858

SLIDE MOUNT AND TAPE GUIDE


Wesley A. LeMarr, New York, N.Y., assignor to Montage Production Inc., New York, N.Y.

Filed Jan. 31, 1969, Ser. No. 795,487

Int. Cl. G03b 21/64, 31/04

U.S. Cl. 353-120

7 Claims



A combined transparency slide mount and magnetic tape guide having conventional means for mounting a visual transparency and having means for guiding a continuous loop of magnetic tape material through four 90° turns around the edges of said mount. The mount is for use in a slide projector which has both projection equipment and a magnetic tape head and tape drive means so that a transparency can be pro-

jected and correlated audio information can be played at the same time.

3,578,859

MECHANICAL STRIPPING APPARATUS


William K. Stillings, Penfield, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Filed July 3, 1969, Ser. No. 838,902

Int. Cl. G03g 15/08

U.S. Cl. 355-3

13 Claims



Apparatus to remove an insulating copy sheet from a moving photoconductive surface, the copy sheet being electrostatically tacked to the surface prior to removal by a corona discharge device during a xerographic image transfer operation. A stripping finger is arranged to lift the leading edge of a sheet being advanced on the photoconductive surface and to direct the sheet upwardly away from the surface. A stationary transport having a smooth flat platen to receive a stripped copy sheet in sliding relation therewith is positioned to intercept the leading edge of the stripped sheet and direct the sheet towards a subsequent processing station. Suction ports in the platen located behind the point of contact of the leading edge of the sheet lift the body of the sheet from the stripper finger and hold the sheet in sliding contact with the platen. Lifting means raise the stripper finger away from the moving surface and further stripping of the sheet is accomplished as the sheet slides along the platen and is lifted from the drum surface.

3,578,860

APPARATUS FOR CONTINUOUS DODGING PRINTING


Jacob Louis Breitbord, Framingham, and Richard Donald MacDougall, Arlington, Mass., assignors to Itek Corporation, Lexington, Mass.

Filed Mar. 4, 1968, Ser. No. 710,296

Int. Cl. G03b 27/76

U.S. Cl. 355-80

25 Claims



Apparatus is disclosed for continuously dodging a series of photographic reproductions as they are being printed, includ-

ing an ultraviolet light source for producing a narrow zone of ultraviolet energy to excite a fluorescent surface on the internal wall of a transparent cylinder to emit actinic light, drive means for rotating the cylinder relative to the narrow zone of ultraviolet energy to sweep that zone, which extends transverse to the direction of rotation of the cylinder, along the fluorescent surface to successively excite narrow portions of that surface, and a near infrared light source fixed relative to the ultraviolet light source for directing near infrared light through a transparency onto excited narrow portions of the surface to quench the surface to form a luminous image, unquenched actinic light from the surface being simultaneously directed to a photosensitive medium to expose narrow sections of that medium, and second drive means for moving the transparency and photosensitive medium relative to the narrow zone of energy, for continuously subjecting unexposed sections of the photosensitive medium and companion segments of the transparency to such exposure.

3,578,861

COPY PAPER FEEDING DEVICE FOR USE WITH PHOTOCOPYING MACHINE

Yugoro Kobayashi, Tokyo, Japan, assignor to Kabushiki Kaisha Ricoh, Tokyo, Japan


Filed Aug. 27, 1968, Ser. No. 755,564

Claims priority, application Japan, Aug. 31, 1967, 42/74669

Int. Cl. G03b 27/20

U.S. Cl. 355-91

3 Claims



A photocopying machine having an adjustment mechanism for correcting misalignment of the original. Lateral misalignment of the original is corrected by axial movement of a driving belt unit. Longitudinal misalignment of the original is corrected by pivoting movement of the driving belt unit.

3,578,862

PHOTOGRAPHIC EXPOSING APPARATUS


Edward P. Hudock, Santurce, P.R.; Irving G. Russell, and Robert L. Sorensen, Westport, Conn., assignors to Time, Incorporated, New York, N.Y.

Filed Oct. 7, 1968, Ser. No. 765,300

Int. Cl. G03b 27/22


U.S. Cl. 355-104

19 Claims



A photographic exposing apparatus which includes a housing, a light source within the housing and a drum carrying a

and efficient transfer of the ink thereto and to provide a series of apertures. An elastomeric ring encircled by the rim swivel mounting for the writing end of the nib for maintain- acts to close the apertures when the ring is expanded by centrifugal force into contact with the rim, so that maximum



ing full face-to-face contact with the surface to be marked, and insuring uniformity of width of the ink line.

3,578,871


CONTROL DEVICE FOR AN OBJECT SUCH AS A ROTOR IN A PRIME MOVER OR THE LIKE

Tetsuzo Sakamoto, Yokohama-shi, Japan, assignor to Tokyo Shibaura Electric Co. Ltd., Kawasaki-shi, Japan
Filed Feb. 6, 1969, Ser. No. 797,131

Claims priority, application Japan, Feb. 9, 1968, 43/7746
Int. Cl. F01b 25/00; H02p 1/54

U.S. Cl. 415-10

14 Claims



A fail-safe control device for controlling an object such as a rotor of a turbine comprising first and second control systems and a low value gate selecting the output from either of the two control systems which has a safer value. The output of the low value gate is used to control the object, such as the rotor. A change ratio detecting circuit is provided for locking the function of the low value gate when the change ratio of the variable being controlled exceeds a predetermined value.

3,578,872

SPEED AND TORQUE CONTROL FOR SURGICAL TURBINE

Thomas W. McBurnie, Santa Barbara, Calif., assignor to Air Instruments, Inc., Santa Barbara, Calif.


Filed Nov. 14, 1969, Ser. No. 876,841

Int. Cl. F01b 25/02

U.S. Cl. 415-25

5 Claims

A turbine-driven rotary tool has a rotary member mounted to turn within a stationary housing, and a rotary torque plate is mounted within the housing. The torque plate has a flange carrying a peripheral rim, and the flange is provided with a



speed of the rotary member is limited by flow of motive fluid around the outside of the rim, and whereby maximum torque is determined by flow of motive fluid through the apertures.

3,578,873

COUNTER-ROTARY PUMPS FOR CHEMICAL LIQUIDS AND PARTICULARLY DYES AND THE LIKE

Guillermo Federico Baez, Jujuy St. 759, Buenos Aires, Argentina


Filed May 26, 1969, Ser. No. 827,789

Claims priority, application Argentina, Nov. 13, 1968, 217,760

Int. Cl. F01d 1/24, 25/18

U.S. Cl. 415-68

3 Claims



The improvements in counter-rotary pumps for chemical liquids and particularly dyes and the like are characterized in that the blades which are integral parts of their rotors and substantially helicoidal and opposed, include respective flat surfaces which have a constant pitch. The form and placing of these blades constitute the basic means for the reversibility of the pump. Their respective carrier shafts are supported by individual bellmouths being in engagement with a block which, inserted between each bellmouth and each integral portion of the casing of the pump, constitute refrigeration and mounting jackets hydraulically sealing the passage of the said shafts.

3,578,874

REMOVABLE RUNNER SEAL

Robert Stanley Sproule; Feodor Kanger, Montreal, Quebec, and Hugh Laurie Seybold, Lachine, Quebec, Canada, assignors to Dominion Engineering Works, Limited, Lachine, Quebec, Canada

Filed Aug. 29, 1969, Ser. No. 854,071

Claims priority, application Canada, Sept. 26, 1968, 30,953


Int. Cl. F01d 11/08, 1/20

U.S. Cl. 415-170

8 Claims

A hydraulic turbomachine such as a pump, pump turbine or Francis turbine having a shrouded runner is provided with sheared seals to minimize leakage through the shroud spaces,

and seal access means, to permit servicing of the seals without removal of the runner from its housing, in the form



of a service housing adjacent the throat and a crown service housing, permitting disassembly of the seals from within.

3,578,875

ROTARY WING ASSEMBLY

Yoshiyuki Oguri, 9-7, Minami Aoyama 7-chome, Minato-Ku, Tokyo, Japan


Filed Oct. 24, 1968, Ser. No. 770,162

Claims priority, application Japan, July 9, 1968, 43/47525

Int. Cl. B64c 27/74

U.S. Cl. 416-109

3 Claims



An improved rotary wing assembly is disclosed, in which a tilted bearing body is provided around a principal rotary shaft to which are fixedly secured base end portions of rotary tractive rods, while base portions of rotary following rods are pivotably secured to said tilted bearing body. At the rigid base portion of each wing are drilled two bearing bores extending towards the tip of the wing, and into these respective bearing bores are slidably fitted said rotary tractive rod and rotary following rod respectively. As said principal rotary shaft rotates the angles of attack of the wings are varied to generate lift and an advancing force when the wing moves down.

3,578,876

MIXER

Andrew Stratienko, Philadelphia, Pa., assignor to King of Prussia Research and Development Corporation, King of Prussia, Pa.


Filed June 6, 1969, Ser. No. 831,117

Int. Cl. B01f 7/24

U.S. Cl. 416-121

13 Claims

A mixer is provided with a plurality of impellers which are mounted to hang vertically in a tank. The upper impeller is



3,578,877

ROTOR CONSTRUCTION WITH ELASTIC INTERCONNECTION OF OPPOSITE BLADES

Karlheinz Mautz, Munich, Germany, assignor to Bolkow Gesellschaft mit beschränkter Haftung, Ottobrunn bei Munich, Germany


Filed June 4, 1968, Ser. No. 735,956

Claims priority, application Germany, July 11, 1967, B93415

Int. Cl. B64c 27/48

U.S. Cl. 416-134

9 Claims




A four blade rotor construction for helicopters includes means for rotatably mounting each blade at equally spaced angular locations around the rotor hub. Diametrically opposed rotor blades are connected with each other by torsion elastic bands or endless members which are stretched across the center of the rotor head with one of the bands being arranged to pass through and intersect the other. The endless bands are formed of laminations of torsion elastic bands and the laminations of one of the bands which connects one pair of blades are arranged in a substantially vertical orientation and the laminations of the other band which interconnects the two adjacent blades are arranged in a substantially horizontal plane. The clearance between the two band loops at the center of the rotor head is such that collective and cyclic pitch controls are possible.

3,578,878

BLOWER WHEEL AND METHOD OF MAKING SAME
 Richard V. Ross, Parma Heights, Ohio, assignor to Morrison Products, Inc., Cleveland, Ohio
 Filed Aug. 19, 1969, Ser. No. 851,319
 Int. Cl. F04d 29/28; B21k 3/04; B23p 15/04
 U.S. Cl. 416-178

13 Claims




A centrifugal blower wheel is formed from a sheet metal strip having opposite side edges including marginal rim portions extending continuously along the side edges of the strip. The strip has a plurality of longitudinally spaced transverse blades formed therein between the side edges. The blades are connected with the rim portions by integral webs. The blades are formed into an arcuate shape in successive steps. An initial step partially curves the blades and leaves the end portions of the blades adjacent the webs flat. The flat portions are curved in a subsequent step so that the end portions of the blades are work hardened less than if they are successively bent in a plurality of steps. The rim portions are folded between adjacent blades in order to decrease the longitudinal spacing of the blades. The folds are specially formed so that a plurality of bends in each fold are smoothly curved to prevent fracturing of the metal at the bends. The blades have notches formed in their inner edges for receiving the peripheral edges of a pair of discs. The discs have circumferential protuberances adjacent their outer peripheral edges. The protuberances are deformed into contact with one another at their centers to provide each disc with a pair of radially spaced protuberances which are under bending stress and continuously bias the peripheral edges of the discs into firm engagement with the notches.

3,578,879

SPRING ACTUATED FUEL PUMP FOR FUEL INJECTION SYSTEMS

Emile David Long, Elmira, and Kenneth Donald Aumick, Pine City, N.Y., assignors to Gillett Tool Co., Buffalo, N.Y.
 Filed Jan. 22, 1969, Ser. No. 793,088
 Int. Cl. F04b 23/04, 27/04
 U.S. Cl. 417-62

19 Claims



A motor-driven fuel pump for precision fuel-metering systems of the fuel injection type wherein a plurality of radially disposed reciprocating pistons are actuated during the


pumping stroke by a pumping spring after the spring has been cocked by means of a motor-driven eccentric motor coupled to the radially disposed pistons. The plurality of pistons can be staged to provide either series or parallel operation by means of a feed manifold which can provide any desired relationship between inlet and outlet connection depending upon the desired output pressure and/or delivery requirements.

3,578,880

DIAPHRAGM OPERATED PRIMING DEVICE FOR CENTRIFUGAL IMPELLER PUMP
 John E. Cygnor, Middletown, Conn., assignor to Chandler Evans Inc., West Hartford, Conn.
 Filed July 24, 1969, Ser. No. 844,591
 Int. Cl. F04d 9/00

U.S. Cl. 417-203

5 Claims




A shaft driven centrifugal impeller pump has a priming arrangement associated with its collector section and drive shaft. A continuously operated diaphragm-type positive displacement pump is operatively connected to a cam mounted on the drive shaft to cause air to flow out of the collector section, into a chamber of the positive displacement pump, out of the chamber and through a conduit connected to the impeller pump's discharge line. A spring loaded shutoff valve prevents a flow from the collector section to the discharge line until the fluid pressure in the collector section forces the valve open. A passage interconnects the chamber of the displacement pump and the collector section to pressure balance the diaphragm.

3,578,881

LIQUID FUEL PUMPING APPARATUS FOR SUPPLYING FUEL TO AN INTERNAL COMBUSTION ENGINE
 Dorian Farrar Mowbray, Burnham, and Kenneth Albert Walters Kemp, Ealing, England, assignors to C.A.V. Limited, London, England

Filed Jan. 31, 1969, Ser. No. 796,315
 Claims priority, application Great Britain, Feb. 1, 1968, 5138/68
 Int. Cl. F04b 23/12, 25/00, 39/10
 U.S. Cl. 417-206

6 Claims



A fuel injection pump having a plurality of pumping plungers mounted in separate bores and actuated by individual


cams the plungers being moved inwardly by the lobes of the cams to discharge fuel from the pumping chambers through valve controlled outlets, each bore having a spill opening which at a predetermined position during the inward movement of each plunger, communicates with the pumping chamber to terminate the flow of fuel through the outlet. Each spill opening is closable by a valve for the purpose of providing an excess of fuel and the flow of fuel into each pumping chamber is controlled by a common throttle valve.

3,578,882

INJECTOR

Leonard F. Janssen, Des Moines, Iowa, assignor to Delavan Manufacturing Co.
 Filed Sept. 10, 1968, Ser. No. 758,722
 Int. Cl. F04b 25/00, 17/00, 23/06
 U.S. Cl. 417-245

11 Claims



A proportioning injector for injecting a fluid in a positive displacement pump cavity. A passage extends through the injector housing between an inlet for supplying the injection fluid and an outlet for discharging the fluid to the cavity. A chamber is located in the passage and a double-headed piston member having piston surfaces exposed to the chamber and to the pump cavity is located in the chamber to vary the volume of the chamber. The fluid is injected into the pump cavity during the intake cycle of the pump and the chamber is filled with fluid to be injected during the discharge cycle of the pump.


3,578,883

UNLOADER FOR MULTICYLINDER REFRIGERATION COMPRESSORS

Lawrence W. Cheney, Sidney, Ohio, assignor to Copeland Refrigeration Corporation
 Filed May 14, 1969, Ser. No. 824,627
 Int. Cl. F04b 49/00

U.S. Cl. 417-286

3 Claims



Means are disclosed for controlling the output and reducing the driving load of a multicylinder refrigeration compres-

sor comprising valve means for closing off the inlet to one or more cylinders motivated by the fluid pressure discharge of the compressor and controlled by a solenoid-operated servo valve.

3,578,884


ORAL HYGIENE APPARATUS

Chester F. Jacobson, Scotia, N.Y., assignor to General Electric Company

Filed May 8, 1969, Ser. No. 823,086
 Int. Cl. F04d 21/02; A61h 9/00

U.S. Cl. 417-317

9 Claims



The disclosure herein concerns an improvement for oral hygiene apparatus of the variable pressure pulsed liquid jet type. The oral hygiene apparatus has a single control that regulates the amount of liquid pressure and actuates the motor switch only when the pressure setting is on low, thus permitting the use of a motor that has a lower starting than run torque, such as a shaded pole motor, with a minimum starting torque capacity.


3,578,885

PUMPING APPARATUS

Kelly F. Alton, Malibu, Calif., assignor to James D. Earle, Los Angeles, Calif., fractional part interest
 Filed Mar. 5, 1969, Ser. No. 804,512
 Int. Cl. F04b 21/00, 43/00, 11/00

U.S. Cl. 417-454

7 Claims



A valve mechanism useful in a pump for pumping concrete comprising a valve member which alternately squeezes closed each of two flexible hoses leading from a hopper which holds concrete to be pumped, and which alternately squeezes closed a pair of flexible hoses leading to two outlets which discharge concrete under pressure. The valve member squeezes the hoses against anvils that are supported on springs, so that a hose is not damaged when a large rock is present therein at the point where the hose is being squeezed.

3,578,886

DOWNHOLE PRODUCING PUMP

Victor J. Nino, Bogota, Colombia, assignor to Texas Petroleum Company, New York, N.Y.

Filed Sept. 11, 1968, Ser. No. 759,177

Int. Cl. F04b 7/00, 34/10, 39/07

U.S. Cl. 417-495

7 Claims



Improved downhole piston pump for production of well fluids involving a multiplicity of quick-acting ports adapted to accelerate handling of heavy or gassy fluids.

3,578,887

GEARED PUMPS

Marco Turolla, 213, Via Toscana, Bologna, Italy


Filed Nov. 12, 1969, Ser. No. 875,710

Claims priority, application Italy, Nov. 15, 1968, 7473A/68

Int. Cl. F04c 5/00; F01c 19/08

U.S. Cl. 418-132

7 Claims



A gear pump has, on the outer face of each bearing plate, four annular symmetrical and symmetrically arranged packings, comprising a central packing which is disposed around the gear wheel pivots and which may be of approximately 8-shaped form, two intermediate packings one on each side of and closely adjacent the central packing, and a peripheral packing encircling both the central packing and the intermediate packing and closely adjacent the latter.

A vane rotary-type engine having vanes with a main body portion and a telescoping tip seal with separate means being provided to support the main part and support the tip seal so that neither places a radial load on the housing in which the vane rotates. The main portion has cam rollers which ride in cam tracks so that as the vane rotates the radial load is taken through the rollers. The tip seal is supported at each end by two large ball bearing units which are fixed in the housing and have carriers which abut the ends of the tip seal.

3,578,888

FLUID PUMP HAVING INTERNAL RATE OF PRESSURE GAIN LIMITING DEVICE


Cecil E. Adams, Columbus, Ohio, assignor to Abex Corporation, New York, N.Y.

Filed Apr. 18, 1969, Ser. No. 817,475

Int. Cl. F04c 15/00

U.S. Cl. 418-133

34 Claims



A fluid pressure energy-translating device such as a fluid pump or motor, having a pressure-loaded element, such as a bushing, port plate or cheek plate, held in position in the device by fluid under pressure, which pressure is relieved by a rate of pressure gain control mechanism whenever pressure surges or peaks occur in the pressure loading.

3,578,889

ROTARY ENGINE VANE SEALING MEANS


Louis C. Dagne, Juno; Howard J. McLean, North Palm Beach, and George A. Bonner, Palm Beach Gardens, Fla., assignors to United Aircraft Corporation, East Hartford, Conn.

Filed Dec. 23, 1969, Ser. No. 887,472

Int. Cl. F01c 19/02

U.S. Cl. 418-147

8 Claims



3,578,890

ROTARY STEAM ENGINE


Oluf F. Jensen, 929-6th Ave., Council Bluffs, Iowa

Filed Apr. 9, 1970, Ser. No. 26,985

Int. Cl. F01c 11/00; F04c 11/00; F04b 49/00

U.S. Cl. 418-199

3 Claims



A rotary steam engine comprising a housing including at least first and second power units mounted therein. Each of power units include a pair of cylinders in communication with each other and having two rotors rotatably mounted therein. The rotors have peripheral gear teeth extending therefrom which are in mesh with the gear teeth of the other rotor. A rotary valve is centrally positioned in the housing with respect to the rotors and is adapted to successively supply steam to the power units to cause the rotation of the rotors therein. Each of the rotors have a drive shaft connected thereto which extend outwardly of the housing. A gear is mounted on the outer ends of each of the drive shafts. The gears on the drive shafts of the first power unit are in mesh with each other with the gears on the rotors of the second power unit also being in mesh with each other. The rotary valve has a drive shaft connected thereto which extends outwardly from the housing with a drive gear being secured to the outer end of the drive shaft. The drive gear is in operative engagement with one of the gears of the first power unit and in operative engagement with a gear of the second power unit. Rotation of the rotors causes the rotary valve to be rotated so as to admit and cut off the steam supply to the rotors at the proper times. The rotary valve is provided with a steam discharge opening which has an increasing opening area from one end thereof to the other end thereof to permit the rotary valve to be longitudinally moved with respect to oppositely disposed steam passageways to permit the amount of steam passing therethrough to be varied.

3,578,891

CROSSOVER LIGHTER STRUCTURE FOR GAS BURNERS


Adrian V. Cavestany, Pasadena; Donald R. Smith, Diamond Bar, and Harold R. Bissell, Jr., Hacienda Hts., Calif., assignors to Carrier Corporation, Syracuse, N.Y.

Filed Nov. 28, 1969, Ser. No. 880,602

Int. Cl. F23d 13/02

U.S. Cl. 431-191

5 Claims



The crossover lighting structure is formed with open-ended gas passages extending along opposite sides thereof. The gas

passages communicate at their inner ends with a gas discharge passage in the burner, and they diverge therefrom toward the inlet end of the burner. The outer ends of the passages terminate in close adjacency to the outer ends of the passages of the crossover structures mounted on adjacent burners. The passages decrease in cross-sectional area toward their outer ends. The outer wall structure of each passage if formed with an opening of controlled area extending lengthwise thereof. Preferably, the openings increase in width toward the outer ends of the passages.

3,578,892

GASEOUS SEALING DEVICES

Ronald D. Wilkinson, Pinner, Middlesex, England, assignor to Airol Burner Company (GB) Limited, West Drayton, Middlesex, England


Filed Mar. 12, 1969, Ser. No. 806,584

Claims priority, application Great Britain, Mar. 21, 1968, 13721/68

Int. Cl. F23b 5/00; F23c 9/00

U.S. Cl. 431-202

10 Claims



A gaseous sealing device intended particularly for use with flare stacks. The device is composed of two hollow members disposed one within another and a number of walls extending between the members to form first and second chambers communicating with one another, the second chamber communicating with the interior of the innermost member open to the atmosphere. The first chamber receives a waste gas from the flare stack and the gas passes through the first chamber in one direction, through the second chamber in the reverse direction and finally through the innermost member again in said one direction. When the gas flow ceases air is prevented from passing into the first chamber by waste gas trapped in the device.

3,578,893

ELECTRICAL COMPONENT CLAMPING DEVICE IN AN ELECTROMELTING INSTALLATION FOR METALS

Otmar Kleinhagauer; Wolfgang Holzgruber; Peter Cerwenka, and Wolfgang Hladny, Kapfenberg, Austria, assignors to Gebr. Böhler & Co. Aktiengesellschaft, Vienna, Austria

Filed Nov. 18, 1968, Ser. No. 776,401

Claims priority, application Austria, Nov. 20, 1967, Nov. 20, 1967, A10398; A10397



Int. Cl. H05b 7/10

U.S. Cl. 13-16

4 Claims

A device for establishing an electrical connection with a component to be used, for example, in the continuous casting of metal. The device includes a pair of electrically conductive clamping members which are adapted to clamp the component between themselves. A pair of swing-lever means are respectively swingable about predetermined axes and carry the clamping members. A fluid-pressure means coacts with

these swing-lever means to act on them in one direction for pressing the clamping members against the component in an opposite direction for retracting the clamping members away from the component.



sleeve constituting a socket for receiving and holding a connector or a terminal lead wire.

3,578,894


RADIO FREQUENCY KEYING PULSE IN ELECTRONIC ORGAN

Harold O. Schwartz, and Anthony C. Ippolito, North Tawanda, N.Y., assignors to The Wurlitzer Company, Chicago, Ill.

Filed Oct. 20, 1969, Ser. No. 867,742
Int. Cl. G10h 1/00

U.S. Cl. 84-1.01

22 Claims



A radio frequency signal is placed on the pickup bus of an audio-keyed electronic organ. The connection is through a resistor and capacitor which form with the input resistors of the audio switches a voltage divider, whereby the level of radio frequency voltage on the bus changes upon closure of any key switch. The radio frequency is amplified and applied to a rectifier to produce a DC potential proportional to the level of the radio frequency, and this is applied through a capacitor to a utilization circuit. Hence as the DC level changes through the capacitor, it appears as a pulse or spike at the utilization circuit, and this pulse or spike is used to key rhythm or other accompaniment effects.

3,578,895

LEAD TERMINAL

Eugene J. Caires, Newtown, Conn., assignor to Vitramon, Incorporated, Monroe, Conn.

Filed June 9, 1969, Ser. No. 831,612
Int. Cl. H02g 15/02

U.S. Cl. 174-74R

1 Claim

The present invention relates to improved terminals for electrical components having bodies of thermoshrinkable material. More particularly, the present invention relates to a resilient sleeve adapted to be disposed within the body and electrically connected to elements therein and held in posi-


3,578,896 ELECTRICAL CONNECTOR WITH FUSIBLE PLUG MEANS AND HEATING MATERIAL

Leslie S. Lynch, Martinsville, N.J., assignor to Thomas & Betts Corporation, Elizabeth, N.J.

Filed Oct. 10, 1969, Ser. No. 865,346
Int. Cl. H02g 15/08

U.S. Cl. 174-84R

10 Claims



A connector for coupling at least one electrical conductor to a further conductor, or other element, comprising an outer insulating sleeve containing within a longitudinal passage therethrough a fusible plug of material for joining such elements. A heating member may be imbedded within the insulating sleeve about the fusible plug or external to the insulating sleeve and will upon operation cause fusion of the fusible plug. Ports may be provided from the outer surface of the sleeve to the heating member for external operation thereof and for the insertion of temperature sensing probe within the fusible plug. Seals for the various ports are provided to insure the integrity of the outer insulating sleeve.

3,578,897

ARRANGEMENT AND PROCESS FOR REPRODUCING COLOR PATTERNS ELECTRONICALLY

Hans Joachim Stock, Freiburg im Breisgau, Germany, assignor to Franz Morat GmbH, Stuttgart-Vaihingen, Germany


Filed Dec. 27, 1967, Ser. No. 694,032
Claims priority, application Germany, Dec. 27, 1966, 72187/67

U.S. Cl. 178-5.2

17 Claims

An arrangement whereby a given unscreened color pattern is scanned by an electronic scanning head. The pattern or design being scanned is stationarily mounted upon a coordinatograph. The scanning head is moved by the carriage of the coordinatograph in a line-wise manner so as to cover the entire surface of the color design. The scanning head generates electronic signals representative of the colors scanned and transmits them to a signal processing circuit for modifying the signals suitable for transmission to a remote location. A printing head mounted on another coordinatograph

is moved synchronously with the scanning head and receives the signal from the signal processing circuit. The printing television receiver is disclosed in which the grid leak current



head prints out a color pattern to a desired scale as a reproduction of the design being scanned.

3,578,898


AUTOMATIC GAIN CONTROL FOR MULTICHANNEL TELEVISION SYSTEMS

Irving Kuzminsky, Silver Spring, and Ray B. Kauffman, Seabrook, Md., assignors to Entron, Inc., Silver Spring, Md.

Filed July 1, 1968, Ser. No. 741,497
Int. Cl. H04n 7/08

U.S. Cl. 178-5.2

6 Claims



Automatic gain control means for a wide-band multichannel color television system, such as a community antenna TV system of the type in which the level of the pilot carrier controls the gain of the trunkline amplifiers. The invention is characterized in that the pilot carrier is modulated by a modulating signal that is a function of the sync signal stripped from the information signal of a given channel (specifically, channel 5). The pilot carrier signal is so modulated that the gain control is effected during the retrace time of the channel 5 signal, whereby any interference produced by the pilot carrier signal will not be visible on a television receiver and will therefore, not be objectionable.

3,578,899

AUTOMATIC CHROMA CONTROL CIRCUIT


James M. Yongue, Indianapolis, Ind., assignor to RCA Corporation

Filed May 29, 1967, Ser. No. 641,759
Int. Cl. H04n 9/48

U.S. Cl. 178-5.4

4 Claims

A closed loop automatic chroma control circuit for a color



of an injection locked color reference oscillator is supplied to a transistor so as to produce an amplified ACC voltage.

3,578,900


VIDEO AMPLIFIER CIRCUIT

Donald H. Willis, Indianapolis, Ind., assignor to RCA Corporation

Filed May 13, 1968, Ser. No. 728,567
Int. Cl. H04n 9/48

U.S. Cl. 178-5.4

6 Claims



A video signal processing channel for use in a color television receiver employing a positively poled detector, a first amplifying stage coupled to the detector and a second amplifying stage coupled to the first for amplifying composite color television video signals. The output of the first stage is coupled by means of separate alternating current and direct current coupling means to the input of the second stage. The DC coupling path comprises a variable impedance which provides means for compensating for variations in characteristics of devices employed in the first and second stages, for selectively adjusting the DC level of the video signals applied to the second stage and for selecting an operating threshold for an automatic gain control circuit, the input of which is derived from the output of the second stage. The second stage provides input signals to each of the chrominance, AGC and synchronizing circuits of the receiver while furnishing a low impedance source of signals for the luminance delay line.

3,578,901

VIDEO AMPLIFIER FOR DRIVING A DELAY LINE BETWEEN GROUNDED COLLECTOR AND GROUNDED BASE

Dal F. Griepentrog, Indianapolis, Ind., assignor to RCA Corporation


Filed May 20, 1968, Ser. No. 730,335

Claims priority, application France, Oct. 3, 1967, 123101

Int. Cl. H04n 9/18

U.S. Cl. 178-5.4R

11 Claims



Transistorized luminance channel of a color television receiver includes emitter follower coupled to input of luminance delay line and common base amplifier coupled to delay line output. Low output impedance of emitter follower and low input impedance of common base amplifier permits reliable termination of both ends of delay line with resistors substantially matching characteristic impedance of delay line. Common emitter amplifier serves to amplify and invert output of common base amplifier, and inverted signal is applied to power output stage via common collector stage providing a low impedance output circuit. Negative feedback established by path between emitters of common collector and common base amplifiers ensures low source impedance required to adequately drive output stage; feedback path provides convenient facility for frequency response control.

3,578,902

APPARATUS FOR SYNCHRONIZED GENERATION OF A SIGNAL FROM A COMPOSITE COLOR VIDEO SIGNAL SUBJECT TO SIGNAL PERTURBATIONS


John Monsay, Malvern, Pa., assignor to RCA Corporation

Filed Aug. 28, 1968, Ser. No. 755,895

Int. Cl. H04n 5/44; H04n 7/00

U.S. Cl. 178-5.4

3 Claims



A technique is disclosed for providing a local reference signal in response to a composite color video signal. The frequency and phase of the reference signal are determined by certain signal portions of the composite signal. The nominal frequency of the reference signal is made to conform to a multiple of the horizontal synchronizing signal frequency portion of the composite signal. The reference signal is further influenced by the presence of the color burst signal portion of the composite signal, to synchronize the reference signal in phase and frequency to the burst signal.

CONTROL CIRCUITS FOR PREVENTING KINESCOPE COLOR SATURATION DURING BLOOMING


Donald H. Willis, Indianapolis, Ind., assignor to RCA Corporation

Filed Dec. 18, 1968, Ser. No. 784,730

Int. Cl. H04n 9/48

U.S. Cl. 178-5.4

9 Claims



In a color television receiver a condition arises where the load demands on deflection circuitry causes blooming during a color transmission. These increasing load demands are detected in the receiver and the detected signal is used to reduce the gain and therefore the drive supplied by the chroma amplifier to the kinescope. The result is to decrease the load demands on the deflection circuitry by decreasing the chroma drive to the kinescope.

3,578,904

FEATURE COUNTER WITH FEATURE DISCRIMINATION AND/OR MASKING


Raymond D. Dewey, Bon Air; Robert S. Mapes, and Garth S. Jones, Richmond, Va., assignors to Reynolds Metals Company, Richmond, Va.

Filed Oct. 15, 1968, Ser. No. 767,614

Int. Cl. G01n 15/02, 21/22; H04n 7/00

U.S. Cl. 178-6

23 Claims



In the disclosed system a specimen is scanned by a video camera and the resulting video signals are applied to a digital logic circuit. The logic circuit is manually settable so that it produces signals only when the video camera scans features

of the specimen that are greater than a preselected width and darker (or lighter) than a preselected grey level. The logic system includes a delay line and an anticoincidence detector for comparing the signals developed during two consecutive line scans so that only a single count pulse is produced for each feature. A scaler is provided for counting the features scanned. Either the features counted or the count pulses may be displayed on a video monitor or the count pulses and features may be displayed simultaneously. A variable electronic mask is provided so that an operator may select any portion of a specimen for analysis.

3,578,905

SIGNATURE AUTHORIZATION AND VERIFICATION EQUIPMENT AND SYSTEM


Walter G. Anders, and Henry W. Kumpf, Jr., Canton, Ohio, assignors to Diebold, Incorporated, Canton, Ohio

Filed Jan. 14, 1969, Ser. No. 790,977


Int. Cl. A47b 81/06; H04n 7/18

U.S. Cl. 178-6

23 Claims



tical image in either a vertical direction or a horizontal direction for use in printed circuit manufacture wherein line-



width and line-spacing measurements of printed circuits are made before and after etch.

3,578,907

OPTICAL-ELECTRONIC PICTURE STORAGE APPARATUS

Hans Joachim Stock, Freiburg Im Breisgau, and Gernot Gottschall, Boblingen, Germany, assignors to Franz Morat GmbH, Stuttgart-Vaihingen, Germany

Filed Sept. 13, 1967, Ser. No. 667,397


Claims priority, application Germany, Sept. 13, 1966,

M70919/67

Int. Cl. H04n 3/22

U.S. Cl. 178-6.8

6 Claims



Banking service equipment is provided to permit one of a number of bank tellers to transmit a picture of a signature on a check by closed-circuit television to a monitor for one of a number of file clerks at a bank department where signature cards are filed, so that a file clerk can compare the signatures on the check and card, verify the authenticity of the signature on the check, and actually stamp the check to signify that the signature has been verified and that a banking transaction based on the check is authorized. The stamping is accomplished by an approval stamp located at the teller station actuated by pressing a button at the file clerk station. The equipment also is provided with means for signaling the teller in event that the file clerk determines that the signatures are not believed to be the same. This system enables entire responsibility for authorization to be placed on the file clerk.

3,578,906

CLOSE CIRCUIT TELEVISION MEASUREMENT SYSTEM

Larry W. Holmstrom, Vestal; James A. Tuttle, Endicott, and Harold J. Young, Vestal, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Nov. 24, 1969, Ser. No. 879,482

Int. Cl. H04n 7/18

U.S. Cl. 178-6

10 Claims

A system designed to make linear measurements of an op-

ERRATA

For Classes 178-6, 6.6, 7.3, 7.85 see:
Patent Nos. 3,579,249 thru 3,579,252

3,578,908

AUTOMATIC PEAK VIDEO CONTROL SYSTEM

William R. Tompkins, Pacific Beach, Calif., assignor to Cohu Electronics, Inc., San Diego, Calif.

Filed Dec. 5, 1968, Ser. No. 781,557


Int. Cl. H04n 5/19

U.S. Cl. 178-7.2

14 Claims

An automatic peak video control system for vidicon tubes in which the peak level of the video signal is detected and

stored during each field scan of the vidicon. The detected signal is sampled, compared with a reference voltage, and applied to the input of an integrating amplifier which controls



the target voltage of the vidicon in a manner such that the error between the peak video signal and the reference voltage will be reduced toward zero.

3,578,909

PAPER FEED CABLE INDEXING SYSTEM


Eric A. Von Hippel, Weston, Mass., and Charles C. Stimus, Jr., Danbury, Conn., assignors to Graphic Sciences, Inc., Danbury, Conn.

Filed Aug. 19, 1968, Ser. No. 753,542

Int. Cl. H04n 3/04

U.S. Cl. 178-7.6

18 Claims



A portable facsimile transmitter and receiver has a rotatable, cylindrical drum for receiving a document which is to be reproduced by means of reading and reproducing heads adjacent the drum. Flexible crossbands bridged across cables wound helically around opposite edges of the drum hold the document on the drum during a reproduction cycle; the cables unwind from the drum during loading and unloading. For ease of loading, the drum is spring wound; a safety stop is provided to prevent premature reverse rotation of the drum during loading or unloading. A margin control enables adjustment of the reproduction cycle to accommodate documents of differing length. An arm extends against the drum when the drum rotation is to be stopped and locks the drum in a reference position at the end of each reproduction cycle to facilitate loading and unloading.

3,578,910

SIGNAL RESPONSIVE FUNCTION PERFORMING MECHANISM


Robert E. Arko, Mount Prospect, Ill., assignor to Teletype Corporation, Skokie, Ill.

Filed July 1, 1968, Ser. No. 741,460

Int. Cl. H04l 15/26

U.S. Cl. 178-23

10 Claims



A function mechanism for producing an output upon receipt of any signal except a designated signal comprising a

universal function bar responsive to all signals, a universal function pawl responsive to the universal function bar, a coded function bar responsive to the designated signal and means responsive to the coded function bar for preventing the universal function pawl from responding to the universal function bar.

3,578,911

TELEPHONE WIRE PAIR COMPENSATOR UTILIZING NEGATIVE CAPACITANCE CIRCUIT


Warren G. Bender, Wellesley, and Robert C. MacKenzie, Franklin, Mass., assignors to Communication Technology, Inc., Burlington, Mass.

Filed Feb. 12, 1970, Ser. No. 10,849

Int. Cl. H04b 3/18; H03h 11/00

U.S. Cl. 178-45

11 Claims



Apparatus is disclosed for compensating a telephone wire pair to alleviate transmission degradation caused by wiring capacitance. A negative capacitance effect is provided by employing positive capacitive feedback around each of two complementary transistor pairs. The pairs are also complementary in conductivity types with respect to each other and are connected effectively in series across a DC potential source so as to operate efficiently and in a balanced manner in a telephone environment.

3,578,912

SOUND GENERATOR


William E. Beavers, Jr., Maryland City, and William H. Sturdevant, Bladensburg, Md., assignors to Singer-General Precision, Inc.

Filed Feb. 23, 1968, Ser. No. 707,615

Int. Cl. G10l 1/00

U.S. Cl. 179-1

9 Claims



This invention comprises a system for digitally generating desired sounds under the control of a digital computer. The

sound generator of this invention can be used to duplicate or synthesize available sounds. To accomplish this, the sound to be duplicated is analyzed to indicate which frequency bands are present in the sound and the relative amplitudes for each band. The actual generation of the sound is by a transducer, such as a loudspeaker, which is fed by the output of a flip-flop. The time duration of a complete cycle of the flip-flop determines the frequency of the signal being generated, and the duty cycle determines the amplitude of that signal. There are many different ways to achieve a duplicate of a known sound. For example, if the sound to be duplicated contains a fundamental frequency and primarily odd harmonics, then the output of the flip-flop, a rectangular wave, can be fed directly to the transducer. Other shaped waves, such as triangular waves, sine waves, etc., can be produced by the use of differentiating circuits, integrating circuits, filters, and the like. In addition, the harmonics can be generated and supplied simultaneously by using duplicate apparatus, or they can be generated in sequence using a single apparatus if they are sufficiently close in time to create the impression of a single, composite sound.

3,578,913

TRANSISTOR AMPLIFIER WITH NEGATIVE FEEDBACK VOLUME CONTROL

Pieter Johan Ufkes, Emmasingel, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed May 13, 1968, Ser. No. 728,701

Claims priority, application Netherlands, June 9, 1967, 6708111

Int. Cl. H03f 3/00

U.S. Cl. 179-1

7 Claims



A hearing aid amplifier comprising a capacitor and a microphone in series across the amplifier input terminals and a volume control potentiometer in shunt with the microphone. A resistor connected between the amplifier output terminal and the movable arm of the potentiometer provides, at the input terminals, a DC negative feedback voltage and an AC negative feedback signal that varies with the adjustment of the Pot arm to provide volume control for the hearing aid.

3,578,914

EQUALIZER WITH AUTOMATIC LINE BUILD-OUT


Richard A. Simonelli, San Francisco, Calif., assignor to Lynch Communication Systems, Inc., San Francisco, Calif.

Filed Apr. 9, 1969, Ser. No. 814,680

Int. Cl. H04b 3/14

U.S. Cl. 179-15

5 Claims



Automatic line build-out is provided in the equalizer stage of a PCM telephone repeater to correctly and continuously

match the repeater automatically to any line length and to varying line parameters. To reduce the power requirements to a minimum, the circuit utilizes the equalized signal itself to determine the amount of degradation and to derive therefrom a control voltage which controls, without power consumption, the amount of series resistance inserted by the line build-out network between the cable and the equalizing circuit. The control is achieved by means of a field-effect transistor passively connected as a variable resistance.

3,578,915

TELEPHONE SWITCHING SYSTEM EMPLOYING TIME DIVISION AND DELTA-MODULATION

Yves H. Le Goffic, Pavillon 3, Saint-Roch, Lannion; Maurice F. Le Dorh, 34 rue Branly, Perros-Guirec, and Fernand R. Arnouat, Pen an Ru, Lannion, France


Filed June 19, 1969, Ser. No. 834,798

Claims priority, application France, June 21, 1968, 156,176

Int. Cl. H04m 3/24

U.S. Cl. 179-15BY

3 Claims



Telephone switching system employing delta-modulation which comprises a time-division switching network, a plurality of subscriber's telephone sets and, in the switching network, an equal plurality of subscriber's equipments connected to the subscriber's sets by four-wire subscriber's lines. Each subscriber's set comprises a delta-modulator for converting the analog signals produced by the telephone set into delta-coded pulses, a delta demodulator for converting delta-coded pulses coming from said switching network into analog signals applied to the telephone set, a timer and means for synchronizing said timer by said delta demodulator. The switching network comprises a timer defining sampling periods. Each subscriber's equipment comprises means for receiving delta-coded signals from the telephone subscriber's sets, a pulse converter and stretcher converting each delta-coded pulse received from a subscriber's set into a long pulse of the same binary value, having a duration equal to one sampling period and coincident with the full sampling period just following said delta-coded pulse occurrence time, means for sampling said long pulse during the time slots allocated to the subscribers and comprised within said sampling period, and means for transmitting delta-coded signals to said telephone subscriber's sets.

ERRATA

For Classes 179-6.3, 179-17, 179-18, 179-100 see: Patent Nos. 3,579,253 thru 3,579,256

3,578,916

TELEPHONE SWITCHING SYSTEMS

Pierre M. Lucas, 20 rue tarel, Issy-Les-Moulineaux, and Michel M. Rouzier, 15 Chemin de la Sabliere, Vauhallan, France

Filed Apr. 18, 1969, Ser. No. 817,403

Claims priority, application France, Apr. 19, 1968, 148,810


Int. Cl. H04q 3/42

U.S. Cl. 179-18GE

2 Claims

Device for detecting in a switching system including crosspoint matrices, those of said matrices which have faulty crosspoints. The switching system comprises crosspoint matrices interlaced with junctor stages whose junctors are in-

serted in the subscriber's lines connected to the outer matrices and in the intermatrix junction lines. The junctor stages are associated with identification markers capable of applying a pulse to a selected junctor and with identifiers capable of detecting said pulse response signal. When an



identification pulse in a first junctor gives rise to more than one pulse response signal in a second junctor, the matrices inserted between said first and second junctors are considered as faulty. They are withdrawn from the switching system when they are freed.

3,578,917

SECURITY CIRCUIT FOR MULTI-EXCHANGE TELECOMMUNICATIONS NETWORK

Charles Henri Emile Grandjean, Villejuif, (Val-de-Marne), and Jean Perrault, Port-Marly, (Yvelines), France, assignors to International Standard Electric Corporation, New York, N.Y.


Filed June 16, 1969, Ser. No. 833,579

Claims priority, application France, June 18, 1968, 155361

Int. Cl. H04q 3/56

U.S. Cl. 179-18

5 Claims



In a telephone exchange comprising a central processor serving several satellite exchanges, a satellite is completely blocked when the cable which connects it to the processor is out of order. According to the invention, each pair of satellites is interconnected by means of a single communication channel so that the transfer of data between the processor and the satellite whose cable is out of order may be effected via another satellite.

3,578,918

COMPUTER CONTROLLED SWITCHING SYSTEM USING FLIP-FLOPS FOR CONTROL OF REPETITIVE OPERATIONS

Pierre M. Lucas, 20 rue Tariel, Issy-Les-Moulineaux; Jean F. Duquesne, 120 rue de Javel; Jean-pierre L. Berger, 124 boulevard Auguste Blanqui, Paris, and Roger L. Courtois, 65 avenue Paul Vaillant-Couturier, Gentilly, France

Filed Aug. 6, 1969, Ser. No. 848,063

Claims priority, application France, Aug. 8, 1968, 162,411


Int. Cl. H04q 3/54

U.S. Cl. 179-18ES

2 Claims

Digital computer for controlling telephone switching systems. The computer can be controlled selectively by two

control circuits: a program permanent store and a group of flip-flops. The program permanent store has written therein contingent instructions relative to telephone communication establishment and release processing operations and is associated with a readout instruction register, an instruction address register and an auxiliary instruction address register. A multiregister has written therein register words containing data relative to the actual state of a telephone communication being processed, and this multiregister is associated with a readout register and a write-in register. The group of flip-flops controls repetitive operations, such as reading out from the readout register the register words, testing the potentials of points located in said switching system and rewriting in the write-in register the register words selectively modified according to the test results. A first means and a second means



for jumping from the control of the computer by said group of flip-flops to the control thereof by said program permanent store and vice versa are provided. The first means comprises means for comparing the results of two consecutive potential tests, means for counting the number of consecutive tests with unchanged results and means, controlled by both said comparing means and said counting means, for inhibiting said flip-flops, transferring in the instruction address register the address contained in the auxiliary instruction address register and activating the program permanent store. The second means comprises means for detecting a jump instruction in the readout instruction register, transferring in the auxiliary instruction address register the address of the jump instruction, inhibiting the program permanent store and activating the group of flip-flops.

3,578,919

TIME COMPRESSION TONE DETECTOR


John F. O'Neill, Eatontown, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Dec. 30, 1968, Ser. No. 787,876

Int. Cl. H04m 1/50; H04q 5/10

U.S. Cl. 179-84

15 Claims



In a frequency detection device time compression techniques are utilized for detecting the presence of a predetermined tone on any one of a plurality of communication channels. Signals appearing on the plurality of channels are sequentially sampled and stored in digital form. Information relating to individual channels is read out of storage and

sent to the frequency detection device at a rate greater than the rate at which the individual channels are sampled.

3,578,920

FERRITE MAGNETIC HEAD WITH GAP SPACER OF SILICON OXIDE AND METAL OXIDES

Noriaki Okamoto, Kanagawa-ken; Teruo Wakabe, Tokyo, and Kazuo Nozawa, Chiba-ken, Japan, assignors to Sony Corporation, Tokyo, Japan


Filed Mar. 12, 1969, Ser. No. 806,477

Claims priority, application Japan, Mar. 15, 1968, 43/16853

Int. Cl. G11b 5/24, 5/42

U.S. Cl. 179-100.2C

3 Claims



A magnetic head has a gap spacer between magnetic core members thereof, which spacer is constituted by at least one layer of a nonmagnetic metal oxide formed over a protective layer, such as, silica dioxide, on a gap-defining surface of the magnetic core members. The metal oxide layer is formed over the protective layer by heating on the latter an acid solution of a nonmagnetic metal halide or a solution of an organic metal salt, during which heating the protective layer prevents oxidation and etching of the underlying gap-defining surface.

3,578,921

MINIATURE MULTIPLE-DIAPHRAGM ACOUSTIC MECHANOELECTRIC TRANSDUCER DEVICE


William F. Knauert, Yonkers, N.Y., assignor to Sonotone Corporation, Elmsford, N.Y. Continuation of Ser. No. 634,736, Apr. 28, 1967, abandoned

Filed Jan. 26, 1970, Ser. No. 6,035

Int. Cl. H04r 7/00

U.S. Cl. 179-139

5 Claims



A miniature size electroacoustic signal transducer device has an elongated mechanoelectric transducer connected to a plurality of diaphragms for multiplying the transduced signal output.

ERRATA

For Classes 200-11, 200-148 see:
Patent Nos. 3,579,257 and 3,579,258

3,578,922

IGNITION DISTRIBUTOR

Roger Habert, Paris, France, assignor to Ducellier & Cie, Paris, France

Filed July 25, 1969, Ser. No. 845,019

Claims priority, application France, Aug. 1, 1969, 161489


Int. Cl. H01h 19/00

U.S. Cl. 200-19R

2 Claims

The advance curve of an ignition distributor is tailored to provide a desired degree of advance at cranking speed, a

desired degree of retardation at low or engine idling speed, and thereafter a normal advance curve as the engine speed increases. The desired curve is obtained by the use of two



3,578,923

ELECTROMAGNETICALLY CLUTCHED RESET TIMER


Fred E. Morey, III, and George B. Mork, Baraboo, Wis., assignors to Gulf & Western Industries, New York, N.Y.

Filed Jan. 16, 1969, Ser. No. 791,702

Int. Cl. H01h 7/08, 43/10, 3/32

U.S. Cl. 200-38

13 Claims



An adjustable reset timer comprising: a frame, a motor, and electromagnetic clutch assembly, drive means for interconnecting said motor and said clutch assembly, a clutch armature axially movable into and out of magnetically locked engagement with said clutch assembly and adapted to rotate in an operative direction from an initial preselected position to a final position, at least one switch affixed to said frame at a point corresponding to said final position, means for actuating said switch when said armature is in said final position, and means for selecting the initial position.

3,578,924

METAL CLAD SWITCH GEAR FOR HIGH VOLTAGES

Rintje Boersma, Harmelen, Netherlands, assignor to N. V. "COQ" Utrecht, Netherlands

Filed Apr. 11, 1969, Ser. No. 815,345

Claims priority, application Netherlands, Apr. 23, 1968, 6,805,720


Int. Cl. H01h 31/00

U.S. Cl. 200-48

10 Claims

Metal clad switch gear for high voltages, all switches and accessories belonging to the same phase of a switching unit of the switch gear being accommodated in a common metal

vessel which consists of a base member supporting said depressed, the side rails pass the pivot point of the tongue switches and accessories and a hood which is detachably and cause the contact carrying end of the blade to snap



secured with its lower rim to said base member and encloses said switches and accessories while remaining clear thereof.

3,578,925

DRAWOUT-TYPE SWITCHGEAR


John L. Drown, Monroeville, and Nagar J. Patel, East McKeesport, Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Nov. 24, 1969, Ser. No. 879,189

Int. Cl. H01h 9/20

U.S. Cl. 200—50

8 Claims



Drawout-type switchgear comprises a levering-in mechanism for levering a circuit-interrupting unit into a connected position in a cell with improved means stopping movement of the circuit-interrupting unit when the circuit-interrupting unit reaches the connected position.

3,578,926

SNAP SWITCH

George Obermann, Niles, Ill., assignor to Controls Company of America, Melrose Park, Ill.


Filed Dec. 4, 1969, Ser. No. 882,080

Int. Cl. H01h 13/36

U.S. Cl. 200—67

3 Claims

The compressed tongue of the switch blade is pivoted on the fixed support member while the side rails are under tension. The actuated end of the blade has integral pivot arms bent at 90° from the plane of the blade and pivoted on ears projecting from the support member. When the plunger is



downwardly. The construction affords considerable over-travel with no adverse effect on contact pressure. The switch provides a high degree of contact wiping.

ERRATUM

For Class 200—83 see:
Patent No. 3,579,284

3,578,927

HIGH VOLTAGE SWITCHING ASSEMBLY

Adrian W. Roth, Aarau, Switzerland, assignor to Sprecher & Schuh AG, Aarau, Switzerland


Filed Feb. 26, 1969, Ser. No. 802,604

Claims priority, application Switzerland, Feb. 29, 1968, Mar. 21, 1968, 3073/68;4413/68

Int. Cl. H01h 33/64, 9/40

U.S. Cl. 200—145

7 Claims



A high-voltage, fluid insulation switching station for a ring bus bar arrangement built up on a separate phase basis, having switching assemblies including three individually enclosed circuit breakers, earthing switches, instrument transformers and voltage transformers, cable dividing boxes and outdoor lead-throughs, the three circuit breakers with associated earthing switches and current transformers required for each connecting point of the bus bar arrangement being arranged within a T-shaped metal housing, wherein the individually enclosed circuit breakers of any one phase in parallel rows form, in sequence with T-shaped housings, a ring arranged, with like parts of the three phases being disposed on axes perpendicular to said parallel rows of circuit breakers.

3,578,928

SPRING MOUNTED ARC DEFLECTOR

John C. Schuessler, West Covina, and Roman J. Capol, Norwalk, Calif., assignors to Leach Corporation, South Pasadena, Calif.

Filed Nov. 22, 1968, Ser. No. 778,109

Int. Cl. H01h 9/34, 33/04


U.S. Cl. 200—144

3 Claims

An improved arc deflector having a backing plate, a plurality of spaced-apart walls, and a recessed partition, which

members define compartments having an end wall and opposed sidewalls. A set of contacts of an electrical relay are enclosed within each compartment, the walls acting to

project into respective recesses for engagement by the ball when the latter enters the recess, to operate the associated switch contacts. The multiple switch may be a rotary switch, a linear switch or a band switch, and the band switch may be



prevent arcing from one set of contacts to another. A retaining spring seats on a shelf of the backing plate and biases the compartmented enclosure against the relay container to hold the arc deflector immobile during use.

3,578,929

SLIDER SWITCH WITH ADJUSTABLE ABUTMENT ON FRAME, AND STATIONARY CONTACT FACES WITH AN ANGLE GREATER THAN 180° THEREBETWEEN BRIDGED BY A FORK SHAPED BRIDGING CONTACT

Horst Prieb, Bielefeld, Germany, assignor to Anker-Werke Aktiengesellschaft, Bielefeld, Germany


Filed Jan. 15, 1968, Ser. No. 697,885

Claims priority, application Germany, Jan. 17, 1967, A54637

Int. Cl. H01h 1/20, 1/18, 3/46

U.S. Cl. 200—153

7 Claims



A switch slider of an electric switch is linked with an actuating member and is reciprocally movable by the actuating member. A spring applies a force to the switch slider to position an electrically conductive bridge member pivotally mounted on the switch slider in electrical bridging contact with a pair of spaced electrical contacts positioned in fixed relation to each other and to maintain good electrical contact between the bridge member and the contacts by relative motion of the bridge member and the contacts.

3,578,930

MULTIPLE ELECTRIC SWITCH

Wolfgang Tiefenthaler, Rosenheim, Wehrle, Germany, assignor to Messerschmitt-Bolkow Gesellschaft mit beschränkter Haftung, Munich, Germany

Filed Apr. 1, 1969, Ser. No. 811,799


Claims priority, application Germany, Apr. 6, 1968, Oct. 22, 1968, B75308;G6803301

Int. Cl. H01h 3/00

U.S. Cl. 200—153

7 Claims

A multiple electric switch includes a spring-biased ball mounted as a locking element in a member connected to a switch shaft, and a plate formed with locking positions in the form of recesses and with guiding means to guide the ball relative to the recesses. Individual sets of switch contacts, such as microswitches, having respective operating members, are mounted as part of the switch and the operating members



3,578,931

SELF-CLEANING ELECTRICAL SWITCH CONTACT


Frank W. Murphy, and Frank W. Murphy, Jr., 3131 S. Sheridan P.O. Box 45248, Tulsa, Okla. 74145

Filed Jan. 15, 1970, Ser. No. 003,112

Int. Cl. H01h 1/18

U.S. Cl. 200—166BD

10 Claims



An electrical switch including a movable switch arm, a switch contact engageable and movable with said switch arm to close an electric circuit, and wherein the contact is spring-biased to constantly engage within a seat and to wipe therein upon engagement and disengagement of said switch arm, and to return the contact to its original position.

3,578,932

REVERSIBLY MOUNTABLE LIMIT SWITCH CONSTRUCTION

Ronald W. Holmes, Freeport, Ill., assignor to Robertshaw Controls Company, Richmond, Va.

Filed June 17, 1968, Ser. No. 737,658


Int. Cl. H01h 9/02

U.S. Cl. 200—168

6 Claims

This application discloses a limit switch having a cup-shaped switch-supporting casing with an open rim, and a cup-shaped switch cover casing with an open rim. Either of these casings may be mounted on a support wall with its rim exposed. Then the other casing may cover the supported casing, rim to rim, to form a combined closed casing. The switch-supporting casing has an operator head at the top and a powerline-receiving notch at the bottom. The switch cover casing has a powerline-receiving notch at the bottom. Prong receptacle means may be added to the switch cover casing so

that the powerline terminals may be attached thereto and prongs may be added to the switch support casing, when the



switch cover casing is attached to the support wall as a plug-in installation.

3,578,933

CORROSION-RESISTANT ENCLOSURE


Woodrow A. De Smidt, and Edward H. Kuhn, Milwaukee, Wis., assignors to Allen-Bradley Company, Milwaukee, Wis.

Filed Sept. 12, 1969, Ser. No. 857,512

Int. Cl. H01h 9/04

U.S. Cl. 200-168

7 Claims



A corrosion-resistant enclosure is disclosed for electrical switches, such as across the line motor starters and safety disconnect switches, that is made of a reinforced resin. The enclosure has a unitary backplate with a backwall and forwardly turned flange, a four-sided body open at the back to receive the backplate and fit snugly about the backplate flange, a sealing material bonding the backplate and body together, and a cover hinged to the body by integral hinge straps that retain the sealed integrity of the enclosure. The components of the enclosure are of molded, reinforced resin having a high degree of resistance to corrosive environments.

ERRATA

For Classes 219-56, 219-98, 219-154, 219-295, 219-486 see:

Patent Nos. 3,579,259 thru 3,579,264

3,578,934

WIRE CONDENSER MAT WELDER AND METHOD OF FORMING

Rene G. Beauvais, 1614-3rd St., Bay City, Mich. 48706
Division of Ser. No. 582,042, Sept. 26, 1966, Pat. No. 3,460,225.

Filed Feb. 24, 1969, Ser. No. 825,468


Int. Cl. B23k 11/00; B63h 9/04

U.S. Cl. 219-56

17 Claims

Apparatus for manufacturing wire condenser mats wherein at least one rigidifying wire is spot welded to a series of cross-

wisely extending connected loops to rigidify the mat structure and insure proper spacing of the loops. The rigidified



structure is then passed to a second welding station where a wire field is welded to the loops to complete the condenser mats.

3,578,935

AUTOMATIC DRUM-FORMING MACHINE


Clifford T. Deane, St. Albans, W. Va., assignor to Stampco, Inc.

Filed Feb. 10, 1969, Ser. No. 816,137

Int. Cl. B23k 1/16

U.S. Cl. 219-64

15 Claims



Sheet metal stock is initially formed into a cylinder by sequential cutting, bending and seam-welding operations. The cylinder then undergoes necking and flanging operations prior to transfer to a final assembly station at which a lid is applied and seamed to the cylinder as its wall is swaged. The cutting, welding and metal-deforming operations as well as transfer of the workpiece from one station to another is performed automatically by a hydraulic-electrical control system.

3,578,936

CONTAINER BODY SEPARATION UTILIZING RADIATION DISCRIMINATION

Howard L. Gerber, Chicago, Ill., assignor to Continental Can Company, Inc., New York, N.Y.

Filed Apr. 23, 1968, Ser. No. 450,391


Int. Cl. F27b 9/06; F27d 11/00

U.S. Cl. 219-388

45 Claims

An apparatus and method for separating tube portions from a continuous length of tubing is disclosed herein. The tubing is advanced past a marking station wherein a circumferential band of heat absorbent material is applied to the tubing. The tubing is then advanced through a housing supporting radiant energy source provisions which direct radiant energy onto the tubing, the energy being absorbed by the circumferential band to effect severance of the tubing. A second conveyor moving at a slightly higher linear rate than

the tubing engages the severed tubing portion to assist separation at the circumferential band. Increase radiant energy absorption may, alternatively, be achieved by circumferentially scoring the tubing.



gy absorption may, alternatively, be achieved by circumferentially scoring the tubing.

3,578,937

ELECTRICAL DISCHARGE MACHINING POWER SUPPLY CIRCUIT OF THE SUPERIMPOSED VOLTAGE TYPE


Kurt H. Sennowitz, Royal Oak, Mich., assignor to Elox Inc., Troy, Mich.

Filed Aug. 21, 1969, Ser. No. 852,023

Int. Cl. B23p 1/08

U.S. Cl. 219-69

11 Claims



A circuit for providing EDM machining pulses from a pair of different magnitude voltage sources. A pair of electronic switches such as transistors are employed to pulse the sources, either separately or additively to control the magnitude of the machining pulses applied and thereby control the mode of machining from roughing to finishing.

3,578,938

METHOD OF ELECTROSLAG WELDING

Boris Izailevich Medovar, Bulvar Lesi Ukrainki, 2, kv. 8; Daniil Andreevich Dudko, pereulok Mechnikova, 3, kv. 7; Vitaly Mikhailovich Baglai, ulitsa Semanshko, 10, kv. 54/3; Oleg Petrovich Bondarenko, Kreschatik, 15, kv. 34; Albert Nikolaevich Sevruck, ulitsa Ezhena Potie, 9, kv. 89; Rudolf Solomonovich Dublinsky, Brest Litovsky prospekt, 11, kv. 15; Vladimir Prokhorovich Andreev, ulitsa B. Kitaevskaya, 99, kv. 13; Georgy Grigorievich Andrianov, Bulvar Lenina, 30, kv. 26; Valentin Stepanovich Sindeev, Bulvar Druzhby Narodov, 14, kv. 13; Anatoly Nikolaevich Safonnikov, ulitsa Filatova, 1/22, kv. 78, and Igor Ivanovich Suschuk-Slusarenko, ulitsa Vyborgskaya, 80/17, kv. 94, Kiev, U.S.S.R.

Filed Apr. 8, 1969, Ser. No. 814,399


Claims priority, application U.S.S.R., Apr. 8, 1968, 1231246

Int. Cl. B23k 9/18

U.S. Cl. 219-73

5 Claims

A method of electroslog welding, enabling metal parts of great thickness to be welded together, wherein stationary and



movable electrodes being rigid and not bendable along the weld seam being made as they are immersed into a slag bath.

3,578,939

BACKING GAS ATTACHMENT SAVING DEVICE FOR HELIARC WELDING


Randolph E. Green, 8 Woodbine St., Roxbury, Mass. 02119

Filed Oct. 15, 1968, Ser. No. 768,200

Int. Cl. B23k 9/16

U.S. Cl. 219-74

4 Claims



A backing gas attachment for conserving backing gas during heliarc welding provides simultaneous control of the flow of cover gas and backing gas to a piece being welded. This prevents waste of the backing gas when its use is not required.

3,578,940

WELDING PROCESS


Oran J. Sands, Columbus, Ind., assignor to Arvin Industries, Inc., Columbus, Ind.

Filed Feb. 20, 1969, Ser. No. 801,065

Int. Cl. B23k 9/28, 11/10

U.S. Cl. 219-91

2 Claims



A welding apparatus and method for spot welding a first metal workpiece having a plastic-covered surface to a second metal workpiece. The two workpieces are placed in metal-to-metal engagement and clamped between the electrodes of two aligned welding guns, a first electrode engaging the plastic surface of the first workpiece and a second electrode engaging the second workpiece. At a point spaced from the second electrode, the metal of the second workpiece is en-

gaged by a contact member between which and the second electrode an electric current can flow through the metal. The second electrode is connected to one terminal of a welding-current source the other terminal of which is connectable through appropriate switch means alternatively to the contact member or to the first electrode. With the contact member connected to the current source heat generated by current flow through the metal of the workpieces softens the plastic to enable the first electrode to penetrate it and engage the metal substrate. Thereupon, the switch means is operated to disconnect the contact member from the power source and connect the first electrode thereto, thus permitting welding current to flow between the two electrodes through the metal. A timing mechanism is provided to control automatically the supply of current and the operation of the welding guns and switch means.

3,578,941

SURGICAL ELECTRIC WELDING APPARATUS


Jacques Robert Webert, Montrouge, France, assignor to Commissariat a l'Energie Atomique, Paris, France
Filed Mar. 7, 1969, Ser. No. 805,213

Claims priority, application France, Dec. 31, 1968, 182649

Int. Cl. B23k 11/26

U.S. Cl. 219-114

12 Claims



A surgical electric welding apparatus for interconnecting bone implantations, said apparatus comprising a transformer whose primary winding may be connected to an electric energy source, two welding electrodes connected to the terminals of the secondary winding of the transformer by means of a flexible cable and held in a handle, an electronic unit for controlling the closure of the feeding circuit of said primary winding and safety means for preventing said circuit from being improperly closed.

3,578,942

WELDING ELECTRODE ASSEMBLY


Leonard J. Bugaj, Dearborn, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Continuation-in-part of application Ser. No. 769,785, Oct. 23, 1968, now Patent No. 3,525,848. This application Oct. 14, 1969, Ser. No. 866,352

Int. Cl. B23k 9/24, 11/30

U.S. Cl. 219-119

7 Claims



A welding electrode assembly includes a metal-welding electrode and a voltage-sensing wire welded at one end to the

lower portion of the electrode. A layer of insulating material is positioned between the wire and the electrode along at least the portion of the wire which extends along the surface of the electrode. A layer of nonconductive material is placed over the outer surface of the electrode and the wire. A thin layer of conductive paint is placed over the nonconductive material layer. A layer of electrodeposited material is placed on the layer of conductive material. The electrodeposited material is formed from a material highly resistant to scratching and marring when engaged by sharp edges of metal articles.

3,578,943

PROTECTIVE COATING FOR PLASMA APPARATUS

Henry P.J.F.M.C. Schoumaker, Jette, Belgium, assignor to La Soudure Electrique Autogene, Procèdes Arcos, Brussels, Belgium


Filed Aug. 27, 1969, Ser. No. 853,471

Claims priority, application Belgium, Mar. 19, 1969, 71,514

Int. Cl. B23k 9/00

U.S. Cl. 219-121

3 Claims



A plasma nozzle and process for treating plasma nozzles used in operations with reactive gases in which a face of the nozzle, preferably the front face, is provided with means to protect against corrosion from reactive gases, the means consisting of a coating of a metallic element or alloy within the group consisting of gold, platinum, palladium, rhodium, iridium, osmium and or ruthenium.

3,578,944

WELDING ASSEMBLAGE

Arieh Kermen, Dimona, Israel, assignor to The State of Israel, Atomic Energy Commission, Beer-Sheba, Israel


Filed June 18, 1969, Ser. No. 834,363

Claims priority, application Israel, July 4, 1968, 30308

Int. Cl. B23k 9/00

U.S. Cl. 219-130

3 Claims



Welding equipment particularly for arc-welding a junction of two wires, for example, for forming a thermocouple junction.

tion wherein the junction is held by means of a gripping unit of substantial heat capacity, the gripping unit consisting of two constituent elements which can be displaced with respect to each other so as to vary the aperture defined between the elements and designed to receive the junction.

3,578,945

HEATER FOR AEROSOL FOAM-DISPENSING CONTAINERS


John Ayres, Mountainside, and Irving Reich, Princeton Junction, N.J., assignors to Carter-Wallace, Inc., New York, N.Y.

Filed Feb. 20, 1969, Ser. No. 800,982

Int. Cl. B67d 5/62; H05b 5/00

U.S. Cl. 219-214

7 Claims



An electric heating device for heating foam products as they are discharged from an aerosol container by passing the foam in direct contact with the hot surfaces of the secondary winding of a stepdown transformer. The device includes a housing having an inlet admitting pressurized foam from the aerosol container and an outlet for discharge of unpressurized foam. A toroidal shell mounted in the housing forms an annular flow path between the inlet to the outlet. The stepdown transformer includes a multiturn primary wound about the outer surface of the shell and a cylindrical iron core centered within the shell and a single-turn closed secondary winding that is formed by a thin plating of cadmium or copper on the core.

3,578,946

THERMAL PRINT HEAD WAFER AND METHOD OF MAKING THE SAME


William L. Colello, Troy, Ohio, assignor to The National Cash Register Company, Dayton, Ohio

Filed Oct. 27, 1969, Ser. No. 869,700

Int. Cl. H05b 1/00

U.S. Cl. 219-216

17 Claims



A thermal print head wafer including a dielectric substrate having one end whose sharp edges are removed (by grinding) to provide a continuous, blended surface between an intended printing surface of the substrate and opposed flat sides thereof. The blended surface has small grooves in the surface thereof, which grooves are aligned parallel to a direction in which the print wafer moves relative to a thermally responsive record medium with which the printing wafer is used. A layer of semiconductor material is deposited

(by pulse spraying) on the blended surface while a portion of the substrate is heated in a furnace, and the deposited material is separated into discrete, spaced resistive elements by high-pressure spraying of abrasives at the semiconductor material through a slitted U-shaped mask. Electrical conductors (located on the opposed flat sides) of the substrate are connected to the ends of the resistive elements, enabling them to be selectively energized.

3,578,947

ELECTRICALLY HEATED HAIR-CURLING INSTRUMENT


Samuel L. McNair, Overland Park, Kans., assignor to The Songrand Corporation, Kansas City, Mo.

Filed May 3, 1968, Ser. No. 726,620

Int. Cl. A45d 2/36; H05b 3/06

U.S. Cl. 219-226

1 Claim



A hair-curling instrument embodies a heat conductive shell which is internally heated by an electric heating element and which is supported from a hollow handle by means of an arrangement which inhibits the transfer of heat from the heating element to the handle. A tubular rivet extending through an aperture in an end closure on the shell and an opening in the end of the handle holds the handle and shell in axial alignment. The heating element leads pass through the rivet. Thermally nonconductive spacers secured to the handle end and seated in recesses in the shell end closure are interposed between the shell closure and the handle end so as to define an air gap between the confronting surfaces of the handle end and the closure member.

3,578,948

SOLDERING AND DESOLDERING HAND TOOL EMPLOYING AIR BLAST OR SUCTION


Aaron L. Friend; Arthur G. Patterson, and James G. Wilen, Phoenix, Ariz., assignors to General Electric Company

Filed Mar. 19, 1969, Ser. No. 808,573

Int. Cl. B23k 3/06

U.S. Cl. 219-230

24 Claims



A soldering and desoldering device includes a heating unit and a soldering tip having an end for engagement with a sol-

dered joint and having a first passage opening at its end. A second passage is provided having an exit opening and communicating with the first passage such that pressure fluid flowing through the second passage out the exit opening is effective to aspirate air from the first passage. Means including a manually actuatable valve are provided for controllably supplying pressure fluid from a source of pressure fluid to the second passage. An adjustable device is mounted for adjustment between a first position wherein it prevents pressure fluid from leaving the exit opening and causes it to flow through the first passage out the end of the soldering tip, and a second position wherein it permits pressure fluid to flow out the exit opening to aspirate air from the first passage. A container is mounted by the adjustable device to form therewith a unitary structure, the container receiving molten solder which passes through the first passage and the exit opening from the soldered joint in response to actuation of the valve when the adjustable device is in its second position. The container is formed of a thermoplastic material, such as the material known as Teflon, having a nonstick finish to prevent adherence of solder to the inner walls of the container.

3,578,949


COMBINATION BAKE AND AUXILIARY BROIL HEATER FOR A COOKING APPLIANCE

Paul M. Weyrick, Ashland, Ohio, assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Apr. 4, 1969, Ser. No. 813,444

Int. Cl. F27d 11/02; H05b 1/00

U.S. Cl. 219—403



Cooking apparatus having a heater structure which is utilized both as a bake heater and a auxiliary broil element. The heater structure is characterized by its capacity to distribute heat over the entire oven when used as a bake heater and to concentrate the heat when used as a auxiliary broil element, the former being accomplished while the heater structure is positioned adjacent the bottom wall of the oven liner and the latter while the structure is supported closer to the top wall thereof.

3,578,950

ELECTRIC HEAT SEQUENCE CONTROL

Clyde C. Moratz, Brookfield, Wis., assignor to Controls Company of America, Melrose Park, Ill.


Filed July 7, 1969, Ser. No. 839,511

Int. Cl. H05b 3/00

U.S. Cl. 219—486

When the thermostat calls for heat the motor starts and rotates the cam bank to start the fan first and then place the heaters on the line in sequence. After all heaters are on the line the motor circuit is transferred to control by the cold contact of the SPDT thermostat so the motor will stop and keep all heaters on the line until the thermostat is satisfied at which time the heaters are taken off the line in sequence. Once the sequence starts it must be completed notwithstanding changes in the thermostat condition. The only exception

is limit switch opening or power failure causing deenergization of the solenoid allowing the spring biased lever to open



all heater circuits and require homing the control at its starting point before heaters can be put back on the line.

3,578,951

ELECTRIC STOVES


Benedict Ingrao, Elmwood Park, Ill., assignor to John Ingro Jr., Albuquerque, N. Mex., fractional part interest

Filed Dec. 26, 1967, Ser. No. 693,270

Int. Cl. H05b 3/68

U.S. Cl. 219—444

50 Claims



Electric stoves in which the relative vertical movement of a pot support and an electric heating element is controlled to control heat, the heating element and the pot support having surface means in horizontal planes. The surface means of the heating element may include at least one portion interposed between horizontally spaced portions of the surface means of the pot support, the heating element preferably including a plurality of generally annular portions at differing radial distances from a central vertical axis. In another embodiment, the pot support includes a thin flat plate portion. In one type of construction, the heating element is moved vertically while in another the pot support is moved vertically. Important features of the invention relate to means for controlling the relative vertical movement, both manually and automatically, with temperature sensing means being usable in conjunction with the control. The control means may control electrical energization of the heating element while also controlling the relative movement of the heating element and the pot support.

3,578,952

TUBULAR ELECTRICAL HEATING ELEMENT WITH A SEGMENTED HELICAL FIN


Robert C. Boose, Mayes, Okla., assignor to Escoa Fintube Corporation, Pryor, Okla.

Filed June 5, 1969, Ser. No. 838,722

Int. Cl. H05b 3/50

U.S. Cl. 219—540

7 Claims



The disclosure describes a tubular electrical heating element comprising a cylindrical sheath having a helical fin attached thereto. The cylindrical sheath includes a heating coil disposed within the interior of the sheath and a quantity of insulating material compacted between the coil and the sheath. The fin includes a plurality of segmented L-shaped blades having a continuous base that is helically wound around the cylindrical surface of the sheath and is bonded thereto by a plurality of spot welds extending along the length of the base.

3,578,953

SYSTEM FOR READING INTERMIXED MARKS AND SYMBOLS FROM DOCUMENTS


Richard E. Milford, and George Maclean, Phoenix, Ariz., assignors to Honeywell Information Systems Inc.

Filed Oct. 3, 1968, Ser. No. 764,660

Int. Cl. G06r 7/00

U.S. Cl. 235—61.11

12 Claims



A system for automatically reading marks and symbols printed on one or more sides of a document in one or more different formats.

ERRATA

For Classes 235—61, 235—155, 235—189 see: Patent Nos. 3,579,265 thru 3,579,268

3,578,954

HIGH SPEED MAGNETIC COUNTER


James P. Barrett, West Hartford, and John G. Gamble, Westogue, Conn., assignors to Veeder Industries, Inc., Hartford, Conn.

Filed Oct. 4, 1967, Ser. No. 672,786

Int. Cl. G06m 1/04

U.S. Cl. 235—92

12 Claims



A resettable high speed magnetic counter includes a drive mechanism which permits the unidirectional advance of the counter's number wheels by retracting independently mounted verge drive arms. The reset button of the counter is adapted to spread the independent verge arms during the reset operation to thereby disengage the verge from the star wheel and enable the use of a direct driving engagement between the star wheel and the lowest order number wheel. The reset mechanism of the counter provides for delayed withdrawal of the reset fingers from the heart shaped reset cam after reset of the number wheels pending reengagement of the transfer pinions with the gears of the number wheels. The transfer pinions of the counter are suitably contoured to enable only transfer in a single rotatable direction with an interference lock preventing rebound inaccuracies. The magnet employs an E-shaped core limiting the flux path of the magnet to the core and flux plate while eliminating the clapper pivot from the flux path.

3,578,955

TOTALIZER FOR INTEGRATING THE PRODUCT OF TWO VARIABLES WITH DIGITAL REGISTRATION


Gerald P. Kloven, White Bear Lake, Minn., assignor to Ramsey Engineering Company, St. Paul, Minn.

Filed Mar. 18, 1968, Ser. No. 713,758

Int. Cl. H03k 25/02

U.S. Cl. 235—92

15 Claims



A capacitor is charged with a DC current obtained from a voltage signal that is proportional to a first variable, such as the weight of material on a prescribed section of a conveyor belt. Each time that the accumulated charge on the capacitor reaches a specific level, the capacitor is automatically discharged to provide an output pulse. The repetition rate or frequency of these pulses is proportional to the signal voltage and hence the magnitude of the first variable. By causing these pulses, or a percentage of such pulses, to flow to a pulse counter, the count registered during the period of pulse

flow will indicate the time integral of the first variable, and in the conveyor case the amount of conveyed material when the belt is moving at a constant speed.

However, where the integral is influenced by another process variable, such as a variance in the conveyor belt speed, the count that is registered will not be an accurate indication of the total material discharged from the conveyor. Provision is made for modifying the number of pulses reaching the counter so that the total pulse count will reflect therein the variable belt speed. By way of an AC signal having a frequency proportional to the conveyor speed and circuitry controlled thereby, the current for charging the capacitor is alternately directed to the capacitor for a first period and then diverted from the capacitor for a second period. Means are employed for retaining the accumulated charge on the capacitor during each second period. In this way, pulses flow to the counter only during successive first periods and no pulses flow during successive second periods. By making the ratio of pulse flow time to total time, that is, the ratio of each first period to the sum of that first period and the following second period, proportional to the magnitude of the second variable, which is the belt speed in the illustrated situation, the counter registration then indicates the product of the two variables. In other words, there is produced a speed integral in which the counter registration denotes the quantity of material discharged from the conveyor even through both the rate of material and the belt speed vary.

The capacitor is discharged many times each second. Pulse-divider circuitry accurately divides this high pulse rate down to a more usable range, thereby utilizing the above-mentioned percentage of pulses. A rate member is included and provision is made for providing a coarse zero and fine zero setting to indicate both zero rate on the meter and a zero counting rate on the counter for the condition of either (or both) the magnitude of the DC voltage or the frequency of the AC signal being zero. By means of a span adjustment a wide range in magnitudes of the DC input signal can be made to represent full scale on the rate meter.

3,578,956


PHASE MODULATOR OF TWO DYNAMIC COUNTERS
Amiel J. McCall, South Euclid, Ohio, assignor to Allen-Bradley Company, Milwaukee, Wis.

Filed May 13, 1969, Ser. No. 824,065

Int. Cl. G06m 3/08


U.S. Cl. 235-92cc

9 Claims




A digital system controls the relative phase of the outputs of two dynamic counters by modulating the input train of pulses to one counter until the two counters are accurately in phase. In the system, successively releasable coarse, medium, and fine in-phase detectors, operating at successively higher frequencies, are employed to permit modulation to occur until the desired in-phase accuracy is obtained. The coarse in-phase detector first detects an in-phase condition causing release of the medium in-phase detector, which next detects an in-phase condition causing release of the fine in-phase detector which provides the final in-phase detection that terminates the modulation. During the entire modulation period, a lead-lag detector controls the direction in which the input train of pulses to the one counter is modulated.

3,578,957
SAMPLED DATA CONTROLLER
James A. Gatlin, Bowie, Md., assignor to the United States of American as represented by the Administrator of the National Aeronautics and Space Administration
Filed May 29, 1969, Ser. No. 828,984
Int. Cl. G05b 21/02, 11/10; G05d 1/08
U.S. Cl. 235-150.1 13 Claims




A sampled data feedback controller includes means for deriving a plurality of error signals within a single control formulation time interval. The error signals are derived by comparing the response of a plant with a reference input, constant over the interval, in a servo subtraction node. Each of the sampled errors is applied to an accumulator with a weighting factor, having a value selected on a predetermined basis, determined by the plant characteristics, to provide finite plant settling time. At the end of each control formulation interval the previous output of the accumulator is fed back to the accumulator, through a weighting factor network. The output of the accumulator at the end of each formulation interval is applied as a control input to the plant. In a specifically disclosed embodiment, the plant is a spin stabilized, attitude controlled satellite.

3,578,958
DIGITAL AND ANALOG PROCESS CONTROL APPARATUS
David A. Richardson, Sheldonville, Mass., assignor to The Foxboro Company, Foxboro, Mass.
Continuation of application Ser. No. 582,750, Sept. 28, 1966, now abandoned. This application July 8, 1969, Ser. No. 845,642
Int. Cl. G06j 3/00; G06p 11/00
U.S. Cl. 235-150.5 21 Claims




Industrial process control apparatus in which a digital computer is utilized for controlling the process, the controlled process loops of the digital computer system being provided with analog "backup" controllers. In the event of failure, control of the process condition is automatically switched to the analog controller which takes over the functions previously carried out by the digital computer.

3,578,959
DIGITAL RESOLVER WITH ALTERNATELY PHASED DIGITAL DIFFERENTIAL ANALYZERS
Donald W. Perkins, Dewitt, N.Y., and William E. Wickes, Manhattan Beach, Calif., assignors to General Electric Company
Filed Dec. 22, 1967, Ser. No. 692,889
Int. Cl. G06f 7/38, 15/32, 15/24
U.S. Cl. 235-152 8 Claims



A resolver is described for transforming position vectors from polar to Cartesian coordinates and resolving such vectors into orthogonally related components defined by sine and cosine functions of the vector angle. This transformation is accomplished digitally in the systems as described using digital differential analyzers which iteratively sum or extrapolate the sine and cosine functions in steps each taken in response to an input pulse representing a small increment of vector angle. For purposes of optimized accuracy the sine and cosine functions are sequentially incremented by extrapolating a first of the two functions using present values of both and extrapolating the other using the extrapolated value for the first. This sequence is reversed with each input pulse, and is effected by time delay and/or anticipation means operative to differentially phase the sine and cosine extrapolations and to alternate the order or sequence in which they are computed.


3,578,960
RADIATION DETECTION SYSTEM WITH AUTOMATIC SAMPLE COUNTING RATE DETERMINATION
Heinz W. Georgi, San Diego, and Roy E. Nather, Solana Beach, Calif., assignors to Beckman Instruments, Inc.
Filed Apr. 6, 1966, Ser. No. 540,609
Int. Cl. G06f 7/39; G01t 1/16
U.S. Cl. 235-156 11 Claims



A radiation detection system with automatic and continuous online computation of sample count rate is disclosed. Logic circuitry is provided by which count pulses are added to a X register and subtracted from a dividend register. A comparator circuit is provided to detect the condition of identical tally in the X register and a timer register. Upon comparison and tally coincidence of the X register with the timer register, a means to increment a quotient register is provided. Such incrementation is continued until the dividend register is reduced to zero as indicated by the negative detection circuit provided therefor. The quotient register thereby contains the number of times the timer register can be divided into the dividend register. Other circuitry is pro-


vided to transfer the counts from a sample radiation detector into the dividend register. Therefore, at the end of computation the quotient register contains the sample count rate desired. Further logic circuitry and a cycle phase counter circuit are provided to accomplish division in a time substantially less than the elapsed measurement time period. By this logic means the various registers are incremented or decremented, as the case may be, at higher decade levels in the register progressing to lower decade levels as the logic circuitry and cycle phase counter direct, thereby providing a short computational time approaching a continuous presentation of sample count rate. Automatic compensation for undesired background counts is provided by means of digital circuits for subtraction of such count from the quotient register.

3,578,961
PRE-CONDITIONED DIVISOR FOR EXPEDITE DIVISION BY SUCCESSIVE SUBTRACTION
Ming-tzer Miu, Brighton, Mass., assignor to Honeywell, Inc., Minneapolis, Minn.
Filed Mar. 6, 1968, Ser. No. 710,918
Int. Cl. G06f 7/52
U.S. Cl. 235-159 12 Claims



A digital divider wherein the divisor is first preconditioned to a value which renders it more easily divisible into the dividend. Once the divisor has been optimized and the value of the dividend adjusted accordingly, actual division is effected by alternately testing the high order digits of the partial remainder and subtracting multiples of the preconditioned divisor accordingly.

3,578,962
LIGHT PRODUCING DEVICE
Robert L. Gerber, Ridgecrest, Calif.
Filed July 25, 1969, Ser. No. 844,810
Int. Cl. F21v 9/16; C09k 1/02; F21k 2/00
U.S. Cl. 240-2.25 2 Claims



A chemiluminescent light-producing device comprising a glass flask containing an oxalate ester and fluorescer in a solvent and having provided in the neck of said flask a tube

holding hydrogen peroxide which when released by appropriate means reacts with the oxalate ester to produce light.


3,578,963

LIGHTING FIXTURE

Hendrik A. J. De Vos, Wenham, and Thomas Haraden, Ipswich, Mass., assignors to Sylvania Electric Products Inc.
Filed Nov. 1, 1967, Ser. No. 679,758
Int. Cl. F21v 21/00

U.S. Cl. 240—3

3 Claims



A multilamp outdoor lighting luminaire in which the major components thereof are organized about a substantially cylindrical, extruded center post and the auxiliary equipment associated with each light source is mounted on a power tray slidably supported on the center post.

3,578,964

VEHICLE IDENTIFICATION LIGHT

Ralph H. Sherman, 217 Central St., Georgetown, Mass.
Filed Jan. 21, 1969, Ser. No. 792,633
Int. Cl. B60q 1/26

U.S. Cl. 240—8.1

4 Claims



A light attachment to an automotive vehicle for identifying it rapidly in a crowded parking lot, comprises an upwardly telescopic staff carrying a lamp upon the upper end thereof. The lamp is electrically powered by conductor wires extending downwardly through the staff and connected to the automobile battery electrical power.

ERRATUM

For Class 240—10.68 see:
Patent No. 3,579,269


3,578,965

FOLDABLE LUMINAIRE

Joseph N. Tawil, Woodland Hills; George R. Hartz, Canoga Park, and Edmund F. Walsh, Reseda, Calif., assignors to Berkey/Colortran Mfg., Inc., Burbank, Calif.
Filed Sept. 26, 1969, Ser. No. 861,370
Int. Cl. F21v 7/18

U.S. Cl. 240—36

8 Claims



The reflector part of the luminaire is made in sections hinged to the main housing. Each section is foldable from a first extended operative position in which the sections project rearwardly away from the reflector opening to a second position in which all of the sections are located close to the plane of the opening of the reflector.


3,578,966

VEHICLE DRIVING LIGHT

Robert E. Levin, Hamilton, Mass., assignor to Sylvania Electric Products Inc.
Filed Nov. 5, 1969, Ser. No. 874,097
Int. Cl. F21v 5/04, 13/02

U.S. Cl. 240—93

4 Claims



A vehicle headlight or driving light having a light source and optical condensing system producing an image at an aperture, the image being focused into a beam by the lens, which has one aspheric and one plane surface, the aspheric surface conforming to certain stated mathematical equations. The condensing system can be an ellipsoidal reflector with a light source at one focus and the image at the other. The plane surface can have a light control element on it if desired to produce small deviations in the shape of the beam.

3,578,967

PRISMATIC LIGHTING PANEL


Leo G. Stahlhut, Kirkwood, and Leo J. Horvath, St. Louis County, Mo., assignors to K-S-H, Inc., St. Louis, Mo.
Filed Aug. 27, 1969, Ser. No. 853,409
Int. Cl. F21v 5/00; G02b 17/00

U.S. Cl. 240—106

3 Claims

A 1/8-inch plastic lighting panel having recessed conical

prisms on 1/4-inch centers. The cones are one-tenth inch larger diameter rod may extend through the chamber and out the opposite ends. A smaller diameter rod carrying the solid



deep.


3,578,968

MOLECULAR FREQUENCY STANDARD

Helmut W. Hellwig, Oakhurst, N.J.
Filed Apr. 16, 1968, Ser. No. 721,776
Int. Cl. G01n 27/78

U.S. Cl. 250—41.3

2 Claims



A molecular beam tube frequency standard using a barium oxide molecule of the form $Ba^{138}O^{16}$ having spinless atoms and using electrostatic state selection. The beam tube comprises a beam source including a thin-walled refractory electrically conductive oven tube containing $Ba^{138}O^{16}$. The oven tube, which is chemically inert to barium oxide, is surrounded by a thermionic electron emitter which is made negative with respect to the oven tube. Electrons emitted from the electron emitter bombard the oven tube and heat the barium oxide to a temperature at which $Ba^{138}O^{16}$ molecules are evaporated. The beam tube also comprises a cavity resonator supporting a TM mode which includes a cylinder and two end pieces provided with apertures for passage of the beam. Each of the ends of the cylinder is provided with a barbed edge; a flat surface of each end piece is pressed against a corresponding barbed edge of the cylinder by mounting means so that the barbed edges cut slightly into the surface of the end pieces. The beam tube also includes a detector comprising a heated elongated member stretched along the axis of the beam tube and arranged to intercept beam particles over a focal region extending along a portion of the length of the said member. Ions are formed in the vicinity of the elongated member and are collected by electrode means maintained negative with respect to said member.

3,578,969


SOLID SAMPLE INLET SYSTEM FOR A MASS SPECTROMETER

Walter Proskauer, San Francisco, Calif., assignor to Electronic Associates Inc., Long Branch, N.J.
Filed Nov. 25, 1968, Ser. No. 778,602
Int. Cl. H01j 39/34

U.S. Cl. 250—41.9

8 Claims

A system is disclosed for injecting solid material into an evacuated chamber without disturbing the pressure therein. Two rods are slidably mounted for extension into the chamber via sealed apertures at opposite ends thereof. A




3,578,970

VARIABLE WIDTH CORONA DISCHARGE APPARATUS WITH MEANS TO SHIELD OR VARY A PREDETERMINED LENGTH OF A CORONA DISCHARGE WIRE

David E. Michaud, Chicopee, and Nils L. Hakanson, West Springfield, Mass., assignors to The Plastic Coating Corporation, Hampden County, Mass.
Filed May 3, 1968, Ser. No. 726,386
Int. Cl. G03g 15/00

U.S. Cl. 250—49.52C

13 Claims



Variable width corona discharge apparatus for applying an electrostatic charge to a transverse dimension of variable width and position of the surface of strip material moving relative to the apparatus. One embodiment includes a movable shield adapted to mask the corona discharge wires along a predetermined portion of their length. Another embodiment includes a torque biased rotatable element transversely movable relative to the strip material and adapted to wind up the corona discharge wire along a predetermined portion of its length.

3,578,971

MAMMOGRAPHIC X-RAY APPARATUS AND TECHNIQUE


Harold J. Lasky, 55 E. Washington St., Evanston, Ill.
Filed Nov. 21, 1968, Ser. No. 777,923
Int. Cl. G03b 41/16

U.S. Cl. 250—50

5 Claims

A method for radiographic examination of the female

breast comprising X-raying the breast under conditions of gentle compression and concurrent gravitational suspension



of the breast. Apparatus for carrying out the method of the invention.

ERRATUM

For Class 250—51.5 see:
Patent No. 3,579,271

3,578,972

EXTENDED SELF-LUMINOUS LIGHT SOURCES EMPLOYING FIBER OPTICS


Harry H. Dooley; Robert J. Doda, and Arthur F. Mahon, Tucson, Ark., assignors to American Atomics Corporation, Tucson, Ark.

Continuation of application Ser. No. 552,109, May 23, 1966, now abandoned. This application Mar. 6, 1969, Ser. No. 805,041

Int. Cl. F21k 2/02

U.S. Cl. 250—77

15 Claims



A radiation-excited light source having a beta-emitting radioisotope within a sealed tube. Illumination is provided by the impingement of betas upon phosphor material within the tube. "Fiber optic" light transmission media are affixed longitudinally along the exterior of the tube and feed light to a plurality of display locations. In one embodiment a thin layer of phosphor is coated over the entire inner surface of the tube. In another embodiment a thicker layer of phosphor is coated to a metal shell positioned within the tube.

3,578,973

SELF-LUMINOUS LIGHT SOURCES EMPLOYING FIBER OPTICS

Harry H. Dooley; Robert J. Doda, and Arthur F. Mahon, Tucson, Ariz., assignors to American Atomics Corporation, Tucson, Ariz.

Continuation of application Ser. No. 552,108, May 23, 1966, now abandoned. This application Mar. 6, 1969, Ser. No. 805,042


Int. Cl. G01n 23/00

U.S. Cl. 250—71

21 Claims

A self-luminous light source in which "fiber optic" light transmission media are utilized to transmit light from a radiation-excited light source to one or more light display loca-

tions at predetermined distances from the radiation-excited source. In one embodiment the radioactive material within the source is completely surrounded by radiation shielding material such as lead and the "fiber optic" media follow a



curved path within the shield. Other embodiments include apparatus for selectively presenting light of various colors and intensities to the input ends of the "fiber optic" light transmission media.

3,578,974

INFRARED SOURCE UTILIZING AN EXOTHERMIC CHEMICAL CHARGE HAVING STABLE AND NONSEGREGATING REACTION PRODUCTS


Raymond W. Thomas, Phoenix, and Abraham L. Pittinger, Scottsdale, Ariz., assignors to Talley Industries, Inc., Mesa, Ariz.

Filed Mar. 3, 1969, Ser. No. 803,587

Int. Cl. H01j 35/00

U.S. Cl. 250—85

13 Claims



A radiant energy source is described comprising a crucible formed of a refractory material and containing an exothermic charge, the reaction products of which form a stable, non-segregating matrix preventing large scale separation of the reaction products, thereby permitting the energy source to be mounted in a wide variety of attitudes. Cylindrical heat shields of varying lengths may be provided around the crucible permitting a variety of radiation patterns to be achieved, from a very narrow radiation cone up to slightly less than omnidirectional pattern. A valve is provided within the crucible for venting gases generated by the charge while sealing within the crucible any solid or liquid products of the reaction. A liner is disposed between the exothermic charge and the inner wall of the crucible for sealing the crucible wall against leakage of reaction products, thereby preventing deposits which would otherwise reduce the emissivity of the crucible wall.

3,578,975

APPARATUS FOR MONITORING THE GUIDANCE AND FOCUS OF TELESCOPE

Chester C. Wheeler, Altadena, Calif., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed June 14, 1968, Ser. No. 737,181


Int. Cl. G01b 9/00; G01j 1/26

U.S. Cl. 250—203

6 Claims

Guiding and focusing errors in a stellar telescope are detected automatically using photoelectric techniques. Light from a guidestar, collected by the telescope, is directed out of the telescope as a converging focusable beam and impinges on a high-speed chopping element. Guiding errors are detected by measuring the intensity of the emerging chopped light. An AC component in the output signal indicates an error. Focusing errors are detected by measuring the intensity

of the emerging chopped light after it strikes and is partly blocked by a knife edge positioned where the focus should occur. An AC component in the output signal indicates an



error. Both output signals are either read on meters or fed into servosystems which move portions of the telescope to compensate for the errors.

3,578,976

OPTICAL SCANNING DEVICE

Johannes Schunack, Berlin-Lichterfelde, Germany, assignor to Franz Morat G. m. b. H., Stuttgart-Vaihingen, Germany


Filed Aug. 21, 1967, Ser. No. 662,199

Claims priority, application Germany, Dec. 27, 1966, M72186

Int. Cl. G01n 21/30; G01j 3/50

U.S. Cl. 250—219

12 Claims



An arrangement for recording on programming tape the color pattern of, for example, fabric material. A scanning head having photosensitive apparatus scans the color pattern to be recorded on the tape, in a grid fashion. The photosensitive apparatus detects the colors on the pattern and converts the optical signals thus realized into corresponding electrical signals. After amplification, these signals from the photosensitive apparatus are converted into normalized pulses by being passed through pulse shapers. The latter provide pulses of constant amplitude and duration in the form of rectangular-shaped pulses. The latter are then applied to a color recognition circuit which provides a signal permitting recording on the programming tape when all designated colors on the pattern have been recognized. Through a systematic and orderly sequence of scanning and tape recording locations, the pattern and its color information is transferred onto the tape. This programming tape may then be used for controlling various machines, as for example, knitting or weaving

machines for knitting or weaving predetermined color patterns.

3,578,977

REFLECTION TESTS HAVING PHOTOCELL WITH APERTURE


Samuel Natelson, Chicago, Ill., assignor to Rohe Scientific Corporation, Santa Ana, Calif.

Filed Feb. 19, 1968, Ser. No. 706,721

Int. Cl. G01n 21/30

U.S. Cl. 250—219

6 Claims



An instrument with supporting structure for reading relative density of flat spots and the concentration of substances in that spot, comprising in combination, a detector photocell with a small aperture in its center said photocell being supported in a plane parallel to that of the flat spot to be examined and in close proximity thereto, the light sensitive surface of the photocell facing said spot; a light source and lens combination so placed in back of the photocell as to focus a light beam at the aperture in the photocell, said light beam traversing said aperture to form a spreading light beam in front of the photocell so that emission of light from the spot will strike the photocell, causing a change in current in relationship with the density of the spot, and, electrical connecting means from said photocell for connection to readout means to sense the signal from the photocell.

3,578,978

OPTICAL PROJECTOR INCLUDING PHOTO-SENSITIVE DEVICE


Bernard Laurent, Corenc-Montfleury, France, assignor to Cometa S. A. R. L., Montfleury, France

Filed May 5, 1969, Ser. No. 821,669

Int. Cl. G01p 3/68

U.S. Cl. 250—221

5 Claims



This invention relates to an optical projector for use in conjunction with a remote reflector which reflects a light beam from the projector. The projector may incorporate a photoelectric device for detecting variations in the light beam caused by movement of a body with respect to the light beam. The invention provides an optical projector comprising a light source and a lens which may be contained in a flat volume whose dimension in the direction of the optical axis is small with respect to the focal length of the lens.

3,578,979

**ELECTRICAL SIGNAL GENERATING APPARATUS
HAVING A SCALE GRID**

Toshiji Kawaguchi; Takeo Tanaka, Tokyo-to, and Masaru Okada, Kawagoe-shi, Japan, assignors to Kabushiki Kaisha Tajima Seisakusho, Tokyo-to, Japan


Filed Dec. 18, 1968, Ser. No. 784,767

Claims priority, application Japan, Apr. 23, 1968, 43/26999

Int. Cl. G01b 11/04; H01j 39/02

U.S. Cl. 250—237

7 Claims



When a scale grid undergoes movement relative to index grids superposed on and adhering to respective photoelectric devices, the resulting variation in a bright-dark pattern formed by the grids is detected by the photoelectric devices and converted into electrical signals, which are processed and digitally displayed or utilized for control of machines and equipment.

3,578,980

**SPECTRAL ANALYSIS USING MASKS HAVING
DIFFERENT COMBINATIONS OF TRANSMITTING AND
NON-TRANSMITTING PORTIONS**


John A. Decker, Jr., Concord, Mass., and Martin O. Harwit, Ithaca, N.Y., assignors to Comstock & Wescott, Inc., Cambridge, Mass.

Filed June 18, 1969, Ser. No. 834,392

Int. Cl. G06k 9/00

U.S. Cl. 250—237

14 Claims



A light spectrum is projected on a photocell through a movable mask having plural combinations of arrays of light windows and opaque areas which transmit to or mask different portions of the spectral line from the photocell. The combinations of windows and opaque areas in the several arrays are different and distributed according to a set of linearly independent equations forming a matrix. As the mask is advanced stepwise the photocell successively senses all the light transmitted from the spectrum through successively interposed arrays and generates a corresponding group of values with an inverse of the mask matrix so as to derive a series of values representing the distribution of energy along the spectrum. The mask thus analyzes and encodes the spectral energy distribution.

ERRATUM

For Class 250—221 see:
Patent No. 3,579,047

3,578,981

ENGINE STARTER CONTROL CIRCUITS

Claude Edmond Lombard; Jean Henri Maurice, and Jean Piret, Billancourt, France, assignors to Regie National Des Usines Renault, Billancourt (Hauts de Seine), France and Automobiles Peugeot, Paris, France


Filed Dec. 24, 1968, Ser. No. 786,660

Claims priority, application France, Jan. 19, 1968, 136767

Int. Cl. F02n 11/08

U.S. Cl. 290—38

2 Claims



A starter motor control circuit contains a relay having two windings associated in opposed relationship, the first winding being energized through the medium of the ignition key switch and the second winding from the alternator through a special group of rectifying diodes of which the number is proportional to that of the phases of said alternator and the capacity consistent with the current drawn by the winding of the starter relay supplied therethrough.

ERRATUM

For Class 307—10 see:
Patent No. 3,579,285

3,578,982

**CORROSION PROTECTION FOR METAL ENCLOSURES
FOR ELECTRICAL EQUIPMENT**


Rolland D. Nelson, Waukesha, Wis., assignor to RTE Corporation, Waukesha, Wis.

Filed July 30, 1968, Ser. No. 748,798

Int. Cl. H01b 7/28

U.S. Cl. 307—95

6 Claims



Disclosed herein is a metallic enclosure for electrical equipment used in an underground electrical distribution system which is isolated from the electrical distribution system ground and made cathodic by connecting the enclosure to a consumable anode buried in the ground in close proximity to the metallic enclosure.

3,578,983

TRANSISTOR-PROTECTING CIRCUIT

Yoshihiko Kondo, Nagoya, Japan, assignor to Nippon Denso Company Limited, Kariya-shi, Japan


Filed June 5, 1969, Ser. No. 830,646

Claims priority, application Japan, June 25, 1968, 43/44065

Int. Cl. H02h 7/20

U.S. Cl. 307—202

2 Claims



A transistor-protecting circuit comprising a load circuit including a source, a switching transistor and a load. A resistor, a second transistor for receiving an input signal and a capacitor are connected in series between the base of the first transistor and the interconnection of the load and the source. A third transistor and a resistor are further connected in series between the two plates of the capacitor to form a discharging circuit. The third transistor has its base connected to the interconnection of the load and the first transistor whereby when the load is short circuited to keep it in the cutoff state.

ERRATA

For Classes 307—25, 307—218, 307—221, 307—228 see:
Patent Nos. 3,579,272 thru 3,579,275

3,578,984

**MASTER/SLAVE SWITCHING CIRCUIT EMPLOYING
INSULATED-GATE FIELD-EFFECT TRANSISTORS**

John E. Ryley, Ilford, England, assignor to The Plessey Company, Limited, Ilford, England


Filed Dec. 9, 1968, Ser. No. 782,239

Claims priority, application Great Britain, Dec. 14, 1967, 56940/67

Int. Cl. G11c 19/00; H03k 23/08

U.S. Cl. 307—221

11 Claims



A master/slave switching circuit comprising a master bistable defined by a pair of insulated gate field-effect transistors having associated with them load field-effect transistors and a slave bistable switch defined by a further pair of field-effect transistors also having insulated gate field-effect transistor loads connected there to the master bistable and the slave bistable being interconnected by insulated gate field-effect transistors such that if the state of the master bistable is changed in response to a clock pulse applied to a terminal the state of the slave bistable is also changed, the response of the master bistable to input clock pulses being controlled in accordance with the state of input signals applied to terminals.

3,578,985

PARABOLIC WAVEFORM GENERATING CIRCUIT


Alvin W. Edson, Baldwinsville, N.Y., assignor to General Electric Company

Filed Feb. 3, 1969, Ser. No. 795,859

Int. Cl. G06g 7/12

U.S. Cl. 307—229

5 Claims



A parabolic generator circuit for generating a smooth parabolic waveform that is stable and free of distortion, and which circuit is of a relatively simple circuit configuration. The circuit includes a constant current source and a sawtooth current source in combination with a capacitor to which is applied current equal to the difference between the fixed and sawtooth currents, the capacitor integrating the applied current so as to generate said parabolic voltage.

3,578,986

**STACKED PULSE-FORMING NETWORK SWITCHING
CIRCUIT**


August L. McGuffin, Clinton, and Ralph M. Philip, Whitesboro, N.Y., assignors to General Electric Company

Filed Aug. 21, 1968, Ser. No. 754,378

Int. Cl. H03k 17/00, 1/00

U.S. Cl. 307—246

8 Claims



A multiple element switching circuit, including a plurality of controlled unilateral conductive elements such as silicon controlled rectifiers, for connection across a charged pulse-generating circuit and a load in a pulse generator. The switching circuit includes a plurality of SCRs which are each connected in shunt across one of a plurality of serially connected pulse-forming networks. When the SCRs are gated, each pulse-forming network is short circuited. The short-circuited pulse-forming networks provide a step voltage to switch the pulse voltage connected thereacross while providing isolation between each of the conductive elements.

3,578,987

RESISTANCE-SENSING SYSTEM WITH FAIL-SAFE CIRCUIT


Douglas W. De Werth, Cleveland, and Earl J. Weber, Bay Village, Ohio, assignors to Dover Corporation, Louisville, Ky.

Filed Dec. 9, 1968, Ser. No. 782,390

Int. Cl. H03k 17/00

U.S. Cl. 307-252Q

7 Claims



A control circuit suitable for use in a forced-draft gas-fired heating system permits a solenoid gas valve to be turned on only if a blower is operating. The solenoid of the gas valve is controlled by a silicon-controlled rectifier (SCR) which receives its gate signal from a thermistor circuit. The blower, when operating, blows air over the thermistor to limit the extent to which it heats up in response to current passed through it, thereby maintaining the thermistor resistance high enough to operate the SCR and the gas valve so long as the blower operates properly. If the blower does not operate properly, the thermistor warms up further, its resistance decreases markedly, and the signal which it develops and applies to the gate of the SCR becomes too weak to turn on the SCR and the gas valve. To prevent operation of the gas valve should the thermistor become open-circuited, there is employed a second silicon-controlled rectifier circuit comprising a second SCR having anode and cathode electrodes in shunt with the thermistor and having a gate electrode which derives its voltage from across the thermistor by way of a capacitor having a predetermined minimum value sufficient to cause the second SCR to turn on before the first SCR should the thermistor become open-circuited. When the second SCR is thus turned on, the first SCR cannot be turned on, and the solenoid gas valve is thereby prevented from being turned on if the thermistor becomes open-circuited.

3,578,988

DIGITAL PULSE WIDTH SELECTION CIRCUIT

Daniel F. Slowikowski, Newport News, Va.


Filed Nov. 7, 1969, Ser. No. 874,732

The United States of America, as represented by the administrator of the National Aeronautics and Space Administration

Int. Cl. H03k 1/18

U.S. Cl. 307-265

5 Claims



A device that will produce different width pulses. The width of the pulse produced at any given time is selected by a

digital input. The digital input selects one of two or more possible timing circuits for a one-shot multivibrator. Hence, the digital input selects one of two or more possible pulse widths capable of being produced by the multivibrator.

3,578,989

PULSE WIDTH STABILIZED MONOSTABLE MULTIVIBRATOR


Robert Charles Heuner, Bound Brook, N.J., assignor to RCA Corporation

Filed June 17, 1969, Ser. No. 834,019

Int. Cl. H03k 3/26

U.S. Cl. 307-273

7 Claims



A monostable multivibrator comprising two cross-coupled inverters having substantially identical threshold voltage levels. Each cross-coupled path includes a charge storage means and there is also included a discharge path for each charge storage means. In response to complementary input signals to the inverters, the multivibrator switches from a first state to a second state and, in response to the first of either charge storage means discharging to the threshold voltage level, the multivibrator switches back to its first state.

3,578,990

PULSE GENERATOR TIMING CIRCUITS


Henry Naubereit, Brown's Mill, N.J.

Filed Apr. 2, 1969, Ser. No. 812,937

Int. Cl. H03k 17/28

U.S. Cl. 307-293

5 Claims



A detector provides a signal for switching on the power supply of a proximately positioned transmitter upon the detection of desired information. A signal representative of the desired information is transmitted and, at predetermined times thereafter, coded signature signals are produced for transmission, these latter signals being supplied by a code generator upon the receipt thereto of pulses from a one-shot and/or repetitive interval timer. The one-shot timer at a predetermined period of time after receipt of the switching signal provides a single pulse to the code generator. The repetitive interval timer provides recurring pulses to the code generator at predetermined intervals of time after receipt of the switching signal. The system consumes no power in the standby mode.

3,578,991

THERMIONIC CONVERTER WITH CONCENTRIC COLLECTOR AND EMITTER

Franz Gross, Neckargemund, and Rudolf Krapf, Leimen, Germany, assignors to Brown, Boveri & Cie A. G., Kallstadter Str., Germany


Filed Sept. 25, 1967, Ser. No. 670,187

Claims priority, application Germany, Sept. 27, 1966, B89094

Int. Cl. H01j 45/00

U.S. Cl. 310-4

2 Claims



A thermionic converter for converting heat energy directly into electrical energy, the heat being derived from the use in the device of nuclear fuel. In the device the emitter is so disposed as to extend into the mass of nuclear fuel, and has a chamber formed therewithin in which there is disposed the collector electrode element, but spaced from the emitter so as to form a sealed interspace chamber which is filled with a gaseous vapor such as caesium vapor. Electric terminals are provided for carrying outwardly to an electric line the electrical energy from the coupled emitter and collector, and coolant means are provided for conducting coolant fluid into the interior of the collector.

3,578,992

CAVITY EMITTER FOR THERMIONIC CONVERTER


T. O. Paine, Deputy Administrator of the National Aeronautics and Space Administration with respect to an invention of, and Katsunori Shimada, Pasadena, Calif.

Filed Oct. 17, 1968, Ser. No. 768,470

Int. Cl. H01j 45/00

U.S. Cl. 310-4

7 Claims



A thermionic cesium diode incorporating a cavity emitter is disclosed. The emitter defines a plurality of relatively shallow cavities extending inwardly from the surface thereof which faces the interelectrode gap. The depths of the cavities are comparable with the electron-neutral mean-free path and the ratios of the depths of the cavities to their diameters are large enough to neutralize electron space charge from occurring thereat.

3,578,993

VIBRATORY ENERGY GENERATORS

Leslie Tremaine Russell, Canada, assignor to Canadian Patents and Development Limited, Ottawa, Ontario, Canada


Filed Feb. 16, 1970, Ser. No. 11,614

Continuation-in-part of Ser. No. 797,492, Feb. 7, 1969.

Int. Cl. H01v 7/00

U.S. Cl. 310-8.3

4 Claims



Energy emitted in a rearward direction from vibratory energy transducers is conveyed from the rear end of a transducer to another by coupling members of equal length joining similar portions of the rear ends of the transducers.

In the preferred embodiment the coupling members are of steel rods and are stranded in the form of steel rope without a central crown rod.

3,578,994

PIEZOELECTRIC CLAMPED-FREE BEAM TYPE TRANSDUCER


Frank Massa, Cohasset, Mass., assignor to Massa Division, Dynamics Corporation of America, Hingham, Mass.

Filed Oct. 22, 1969, Ser. No. 868,332

Int. Cl. H01v 7/00

U.S. Cl. 310-8.6

7 Claims



A transducer cartridge carries a miniature video recording head on a tiny vibrating platform. The platform is at the end of a piezoelectric reed which undertakes mechanical excursions responsive to an electrical signal. Various designs are illustrated which have been built and found to be satisfactory for use with a home video tape recorder.

3,578,995

ELECTROACOUSTIC TRANSDUCERS OF THE BILAMINAR FLEXURAL VIBRATING TYPE


Frank Massa, Cohasset, Mass., assignor to Massa Division, Dynamics Corporation of America, Hingham, Mass.

Filed Sept. 22, 1969, Ser. No. 859,677

Int. Cl. H01v 7/00

U.S. Cl. 310-8.8

7 Claims



A button transducer comprises a metallic diaphragm concentrically bonded to a piezoelectric ceramic disc. A plurality of types of annular housings are provided for clamping and

terminating the periphery of the diaphragm, each housing type having a central opening with a different diameter therein. The bonded diaphragm-disc assemblies are measured for resonant frequency, and the housing type is selected to tune the bonded assembly to have a predetermined resonant frequency.

3,578,996

ULTRASONIC MOTOR


Lewis Balamuth, New York, N.Y., assignor to Ultrasonic Systems, Inc., Farmingdale, N.Y.

Filed Jan. 7, 1970, Ser. No. 1,125

Int. Cl. H01v 7/00

U.S. Cl. 310—8.7

32 Claims



An ultrasonic motor having a transducer confined at or near a nodal region of vibration sandwiched between two flanged sections, each flanged section consisting of an elongated member whose average cross section is substantially less than the cross section of the transducer, and the transducer is rigidly coupled to the flanged sections.

3,578,997

ELECTRIC GENERATORS

Noel Felici, Grenoble, France, assignor to Tunzini-Sames, Grenoble, France


Filed Oct. 15, 1969, Ser. No. 866,689

Claims priority, application France, Oct. 21, 1968, 170,760

Int. Cl. H02n 3/00

U.S. Cl. 310—10

9 Claims



This invention relates to electric generators employing a gaseous fluid, such as air, which is caused to flow through a passage at high speed. The gaseous fluid is ionized by ionizing means comprising a needle electrode and a counter electrode formed by a convergent-divergent wall portion at the upstream end of the passage, the downstream portion of the passage being formed by an electrically insulating tube. According to this invention means are provided to avoid condensation forming on the outer surface of the insulating tube. The anticondensation means may comprise either thermal insulation, around the outer surface of the insulating tube; or means for heating said outer surface, or yet again means inducing a flow of a gaseous fluid over said outer surface.

3,578,998

POLYPHASE ALTERNATING CURRENT GENERATOR

William C. Euerle, Milton, Mass., assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Filed Nov. 5, 1968, Ser. No. 773,423


Int. Cl. H02n 4/02

U.S. Cl. 310—11

8 Claims

A polyphase alternating current electrical power generator is obtained by interconnecting N direct current power

generators. N is the number of phases to be generated and must be greater than or equal to three. The output of one generator is connected to the input of another generator either serially through a load or in parallel with a load. For rotating or magnetohydrodynamic generators, the output of one generator is connected to the field winding of another generator in a cascaded connection of generators forming a



closed loop. For electrostatic generators the input terminals and output terminals generally have a common ground terminal which restricts the permissible values of N to odd integers. The phasing of the interconnections is such that if the loop is opened at any point, a voltage transfer characteristic corresponding to positive feedback is obtained with a gain of unity and zero phase shift.

3,578,999

MAGNETOHYDRODYNAMIC ENERGY CONVERSION PROCESS


Max Steenbeck, and Fritz Krause, Jena, Germany, assignors to Deutsche Akademie Der Wissenschaften Zu Berlin, Berlin-Adlershof, Germany

Filed July 23, 1969, Ser. No. 843,919

Int. Cl. H02k 45/00; H02m 4/02

U.S. Cl. 310—11

10 Claims



A process for magnetohydrodynamic conversion of mechanical energy in an electrically conducting fluid flowing through a magnetic excitation field. A nonmirror symmetrical flow is applied to the fluid and a main magnetic field is established from the current flow arising from the electromotive force generated parallel to the excitation field. The electromotive force is generated as a result of the alpha-effect. The electrically conducting fluid serves as a conductor for the current flow and, at the same time, removes the heat generated during the process.

3,579,000

SUSPENDED MOTOR VIBRATORY APPARATUS

Joseph W. Mathews, 3762 Swansea Drive, Mobile, Ala.

Filed Nov. 19, 1969, Ser. No. 877,933


Int. Cl. H02k 33/00

U.S. Cl. 310—15

8 Claims

Apparatus for mounting within a case which represents the vibrating load, includes an electric motor assembly and a suspension bracket to which the case is rigidly attached. The motor includes a relatively heavy housing which defines a magnetic stator structure, and a relatively light reciprocating armature structure. The armature oscillates lever arms

pivotaly connected to the motor stator; with the lever arms being coupled to the suspension bracket to effect relative



reciprocating movement between the suspension bracket and motor stator.

3,579,001

LINEAR MOTOR HAVING RADIAL ARMATURE PLATES

Yves F. Pelenc, La Tronche, France, assignor to Merlin Gerin, Societe Anonyme, Grenoble, France


Filed Oct. 16, 1969, Ser. No. 866,911

Claims priority, application France, Nov. 7, 1968, 173,022

Int. Cl. H02k 41/02

U.S. Cl. 310—13

8 Claims



Compact linear motor of high thrust having an annular magnetic field structure with a plurality of radially directed air gaps in which extend armature plates of the motor. The armature plates are subjected to the magnetic flux produced by the field structure resulting in axially directed forces which displace the armature with respect to the field structure.

3,579,002

REVERSING SWITCH FOR POWER TOOLS


John L. Wickham, Glen Arm, Md., assignor to The Black and Decker Manufacturing Company, Towson, Md.

Filed Mar. 31, 1970, Ser. No. 24,308

Int. Cl. H02k 7/14; H01h 9/06

U.S. Cl. 310—50

8 Claims



whereby rotation thereof through an arc causes operation of the switch. The arm portions of the T-bar extend toward the opposite sides of the tool and protrude slightly through apertures in the housing so that, upon engagement of one or the other by the operator's hand, the reversing switch is moved between its forward and reverse positions.

ERRATA

For Classes 310—82, 310—156 see:
Patent Nos. 3,579,276 and 3,579,277

3,579,003

MAGNETIC BRAKING SYSTEM


Robert C. Gray, 280 Clifford St., Blackfoot, Idaho 83221

Filed July 31, 1969, Ser. No. 846,471

Int. Cl. H02k 49/10

U.S. Cl. 310—93

10 Claims



A magnetic braking system for braking the motion of a moving member including first magnet means mounted on the moving member, a support frame positioned proximate the moving member, second magnet means having a polarity opposite the polarity of the first magnet means secured to the support frame, and positioning means for moving the second magnet means on the support frame to a position proximate the first magnet means wherein the magnetic flux between the first and second magnet means brakes the motion of the moving member.

3,579,004

SYNCHRONOUS MOTOR FOR CLOCKS AND THE LIKE


Alan E. Patrick, Statesville, and Kenneth E. Kern, Charlotte, N.C., assignors to General Time Corporation, Stamford, Conn.

Filed Oct. 16, 1969, Ser. No. 866,970

Int. Cl. H02k 21/00

U.S. Cl. 310—164

8 Claims



A portable power tool including a reversible electric motor, a housing having a handle adapted to be grasped by an operator, and a trigger switch adjacent the handle to be grasped by the operator's finger for energizing the motor. The tool also includes a reversing switch. The operating member for the reversing switch comprises a T-shaped operating lever located above the trigger for convenient engagement by the operator. The base portion of the T-bar is connected through a pivot mounting to the reversing switch


A synchronous AC motor for driving clocks or the like having pole structure for producing shaded and unshaded flux in an annular airgap, the airgap being occupied by a rotor having adjacent loops of material of unlike magnetic retentivity, one loop having sufficiently low coercive magnetic intensity to serve, by induction, to start the rotor and bring it up to speed and the second loop having a sufficiently high coercive magnetic intensity as to form durable spots of permanent magnetism for providing torque at synchronous rotor speed. A thick shading ring, to achieve a high shading cur-

rent, is accommodated by a special pole configuration to achieve compact spacing between the shaded and unshaded poles. The first ring is positioned to be subject to the major flux under starting conditions.

3,579,005
HOMOPOLAR DYNAMOELECTRIC APPARATUS
Bruce P. Noble, 2748 Grande Vista Ave., Oakland, Calif.
Filed July 25, 1969, Ser. No. 844,845
Int. Cl. H02k 31/00

U.S. Cl. 310-178


15 Claims



A homopolar dynamoelectric apparatus wherein a field structure is formed with alternately spaced segments of high and low magnetic permeability adjacent a rotating conductive armature for inhibiting undesirable rotation of magnetic flux therewith. The armature is constructed with a plurality of individual sections each adapted to generate a separate voltage potential which may be electrically added to the outputs of each of the other armature sections to produce a resultant output voltage substantially higher than the low output potentials heretofore characteristic of homopolar devices.

3,579,006
LIQUID COOLED COLLECTOR RINGS FOR DYNAMOELECTRIC MACHINE
Fred H. Kindl, Schenectady, and Sterling C. Barton, Scotia, N.Y., assignors to General Electric Company
Filed Nov. 21, 1969, Ser. No. 878,746
Int. Cl. H02k 9/28, 39/00
U.S. Cl. 310-227


5 Claims



In a dynamoelectric machine of the type having brushes transmitting current to a shaft-mounted collector ring, the improvement consists of a liquid dam on one end of the overhanging ring and means to supply liquid into the rotating cavity and collect liquid from the cavity so as to cool the ring and increase the current-transmitting capacity of the brushes.

3,579,007
COMMUTATOR BRUSH STRUCTURE FOR ELECTRIC MOTOR
John Walter, Evergreen Park, Ill., assignor to Sunbeam Corporation, Chicago, Ill.
Filed Oct. 30, 1969, Ser. No. 872,606
Int. Cl. H02k 5/14
U.S. Cl. 310-242


7 Claims



An electric motor having a supporting frame within which the commutator brushes are supported. The brushes are received in channel-shaped recesses and are retained therein by spring clips which snap into engagement with the supporting frame.

3,579,008
COLOR TUBE HAVING ASYMETRICAL ELECTROSTATIC CONVERGENCE CORRECTION SYSTEM
Senri Miyaoka, Kanagawa-ken, Japan, assignor to Sony Corporation, Tokyo, Japan
Filed Apr. 10, 1969, Ser. No. 815,050
Claims priority, application Japan, Apr. 13, 1968, 43/24621
Int. Cl. H01j 3/06, 25/50, 31/20
U.S. Cl. 313-79


4 Claims



In a single-gun, plural-beam color picture tube in which two beams emerge from a focusing lens along paths that diverge from a central beam emerging along the optical axis of the lens by which all of the beams are focused on the color screen, and the divergent beams are deflected to converge with the central beam by passage through respective electrical fields established between first spaced plates, at opposite sides of the central beam path, and second plates spaced outwardly from the first plates; such plates are disposed closely adjacent to the main deflection yoke by which the beams are made to scan the screen so that the length of the tube can be minimized, and the misconvergence of the beams that may result from the magnetic field produced between the first plates by reason of a current flow induced in the first plates by flux change of the magnetic field of the main deflection yoke is corrected by providing the second plates with different dimensional relationships to the first plates, for example, different distances from the first plates or different distances along the first plates, so that the deflecting effects of the electrical fields are correspondingly different.

3,579,009
ELECTRON GUN ASSEMBLY INCLUDING TWO PART THREADED ELECTRODE
Tsutomu Nishino; Kokiti Kinoshita, and Haruo Maeda, Kadoma, Osaka, Japan, assignors to Matsushita Electric Industrial Company Limited, Kadoma, Osaka, Japan
Filed July 3, 1969, Ser. No. 839,015
Claims priority, application Japan, July 10, 1968, 43-49268
Int. Cl. H01j 29/46, 1/00, 8/50
U.S. Cl. 313-83


1 Claim



An electron gun assembly for a cathode-ray tube having a removable cathode-grid assembly which has a plurality of stem leads connected with the respective electrodes and led out to the outside at the stem and which is supported by multihold glass bars, and an anode and focusing electrode assembly which has a plurality of side leads connected with the respective electrodes and led to the outside from the side and which is supported by multihold glass bars.

3,579,010
ELONGATED APERTURE ELECTRON GUN STRUCTURE FOR FLAT CATHODE RAY TUBE
Robert C. Jones, Elkins Park, Pa., assignor to Philco-Ford Corporation, Philadelphia, Pa.
Filed Oct. 31, 1968, Ser. No. 772,232
Int. Cl. H01j 1/46, 29/46
U.S. Cl. 313-86

9 Claims




An electron gun for a flat cathode-ray tube wherein the control electrode and the screen electrode of the gun each have an elliptical aperture therein, and a flat cathode-ray tube employing such a gun. The major axes of the two elliptical apertures lie in a common plane which is oriented with respect to the faceplate of the tube so that an electron beam emitted by the cathode of the gun produces a substantially circular spot on said faceplate.

3,579,011
LIQUID METAL CATHODE WITH SINGLE CAPILLARY FLOW IMPEDANCE
Julius Hyman, Jr., Los Angeles, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.
Filed Jan. 8, 1969, Ser. No. 789,768
Int. Cl. H01j 1/06, 1/10, 13/10
U.S. Cl. 313-29

6 Claims

The liquid metal cathode is employed as a cathodic electron source in arc discharges. A small liquid metal pool serves as the arcing material, and when it is kept small, improved electron-to-atom emission ratios are obtained, as well as gravity independence. However, when such a small pool is employed, feed to the pool must be free of feed rate perturbations. Otherwise, an instability in the level of the mercury in the pool results. The present invention obtains feed rate


stability by providing a feed passage with a diameter which is everywhere larger than that of the feed channel which finally



discharges to the pool. Feed flow impedance is provided by an elongated capillary feed channel.

3,579,012
IMAGING DEVICE WITH COMBINED THIN MONOCRYSTALLINE SEMICONDUCTIVE TARGET-WINDOW ASSEMBLY
Walter K. Zwicker, Scarborough, N.Y., and Alfred Milch, Teaneck, N.J., assignors to U.S. Philips Corporation, New York, N.Y.
Filed Oct. 16, 1968, Ser. No. 767,958
Int. Cl. H01j 31/26; H011 3/12
U.S. Cl. 313-65


10 Claims



An imaging device, especially a vidicon-type camera tube, in which the active target layer is an ultrathin monocrystalline semiconductor grown epitaxially on a thicker supporting monocrystalline substrate which is transparent to the imaging radiation and thus serves as a window for the radiation to enter the tube to be detected by the semiconductor.

3,579,013
CATHODE RAY TUBE HAVING RADIALLY DIRECTED COMMUTATOR ELEMENTS
Elvin E. Herman, Pacific Palisades, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.
Filed Jan. 8, 1969, Ser. No. 789,731
Int. Cl. H01j 31/06, 29/78
U.S. Cl. 313-73

2 Claims



A focused electron beam is circularly deflected. It is directed at a commutator target and passes through a positive collector mesh. The target comprises a plurality of separate, conductive spokes. Alternate spokes are connected together and serve as a shield electrode, which is held slightly

positive with respect to the cathode. The remaining alternating spokes are grouped with three to five of the spokes being connected together to form an input channel. Input channel level ranges are typically from -5 volts to zero, so that when a group is more negative, the electron beam is prevented from landing on the shield electrode, and is returned to the collector grid or mesh. When an input is near zero volts, a large percentage of the electron beam lands on the shield electrode. Thus, between these values, electron beam current returning to the collector mesh is modulated by the input signal levels applied to the various spoke groups. In this manner the voltage levels on the different sets of input spokes are commutated as the electron beam is circularly deflected. The commutated signal can be read as collector mesh current.

3,579,014

SHAPED BEAM TUBE HAVING FINE MESH CLOSELY ADJACENT SUBSTANTIALLY RECTANGULAR TRIM APERTURE


Charles R. Corpew, La Mesa, Calif., assignor to Stromberg Datagraphics Inc., San Diego, Calif.

Filed Aug. 19, 1968, Ser. No. 753,601

Int. Cl. H01j 29/56, 29/70, 29/06

U.S. Cl. 313-86

5 Claims



A shaped beam tube is described wherein a mesh is provided adjacent a trim aperture to diffuse the beam (which is utilized to flood the shaping aperture) and to produce a substantially uniform intensity over the cross section of the beam.

3,579,015

ELECTRON BEAM ADDRESSED PLASMA DISPLAY PANEL


Robert O. Gregory, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

Filed Mar. 18, 1969, Ser. No. 808,195

Int. Cl. H01j 29/10; H05b 33/02

U.S. Cl. 313-89

8 Claims



A combination display and storage tube of the type having gas-filled cells sandwiched between flat insulating sheets. One of the two electrodes for applying the sustaining voltage to the gas-filled cells is provided with apertures so that an electron beam may be used to initiate or extinguish the discharge of selected cells.

3,579,016 POSTDEFLECTION TUBE WITH ALL RARE EARTH PHOSPHORS


Frank C. Palilla, Maspeth, N.Y., assignor to General Telephone & Electronics Laboratories Incorporated

Filed Oct. 23, 1967, Ser. No. 677,198

Int. Cl. H01j 29/32, 31/20

U.S. Cl. 313-92

2 Claims



A color cathode-ray tube of the postdeflection-focusing type (PDF) wherein the phosphor screen exhibits a linear change in brightness with changes in electron beam current density over the entire operating range of the tube. The preferred phosphor screen employs trivalent europium activated yttrium vanadate as the red-emitting phosphor, trivalent terbium activated yttrium phosphate as the green-emitting phosphor and divalent europium activated strontium chlorophosphate as the blue-emitting phosphor. The disclosed screen results in a PDF tube which exhibits a linear increase in brightness, improved contrast and maintenance of color balance for all values of beam current.

3,579,017

HARP ELECTRON MULTIPLIER


Marvin L. Vestal, Baltimore, Md., assignor to Scientific Research Instruments Corporation, Baltimore, Md.

Filed June 17, 1968, Ser. No. 737,490

Int. Cl. H01j 43/00

U.S. Cl. 313-105

12 Claims



An electron multiplier having a plurality of dynodes wherein each dynode includes two wire layers located in staggered relationship with one another and wherein each of the dynodes is located with a first one of its wire layers aligned with the immediately adjacent wire layer of an immediately preceding dynode and with its second wire layer aligned with the immediately adjacent wire layer of an immediately following dynode. The wires in each layer of each of the dynodes are spaced so that the open space between them is less than the diameter of the wires, with the exception of the first wire layer in the first dynode wherein the wires may be of a noncircular cross section or of a smaller diameter and wherein they are spaced apart by a distance greater than the diameters thereof.

3,579,018

LUMINESCENT MATERIALS

Peter Whitten Ranby, and David Richard Palowkar, London, England, assignors to British Lighting Industries Limited, London, England

Filed Apr. 18, 1969, Ser. No. 817,367


Claims priority, application Great Britain, Apr. 30, 1968,

20,505/68

Int. Cl. H01j 63/04

U.S. Cl. 313-109

4 Claims



New phosphors, emitting a red fluorescence and suitable for use in high-pressure mercury vapor lamps, consist of zinc aluminate activated by chromium in which some of the alumina is replaced by boron oxide.

3,579,019

LIGHT CELL MATRIX STRUCTURE


Alfred D. Scarbrough, Northridge, Calif., assignor to The Bunker-Ramo Corporation, Oak Brook, Ill.

Filed Apr. 1, 1969, Ser. No. 812,256

Int. Cl. H01j 5/16

U.S. Cl. 313-109.5

13 Claims



A light cell structure for supporting and conducting energizing signals to a rectangular matrix of ionizable gas-filled light cells. The structure is constructed and arranged so as to permit the emitted light from an energized cell to be directly viewed without first passing through an electrode. Each light cell is typically of the general shape of a rectangular parallelepiped. One pair of opposed surfaces of each parallelepiped light cell serve as energizing surfaces, and one of the remaining surfaces is a light transmitting surface which serves as a viewing surface. The light cells are supported and selectively energized by a row-column arrangement of conductive members to which the light cells are affixed by their energizing surfaces. The row conductive members are typically conductive strips, while the column conductive members are typically conductive strips having uniformly spaced upstanding tabs provided along the length thereof. Each light cell has one of its energizing surfaces affixed to a respective

row strip at a respective one of a plurality of uniformly spaced positions along the length of the row, and the other of its energizing surfaces affixed to a respective one of the upstanding tabs of a respective column strip. Provision is also made for enhancing light emitted from the viewing surface of each parallelepiped light cell by using the remaining surface thereof as a second light transmitting surface whose emitted light passes through a respective appropriately located aperture provided in the column strip to reflective means which reflects light emitted from this second light transmitting surface back up through the light cell and out the viewing surface.

3,579,020

ELECTRON DISCHARGE DEVICE WITH ELECTRODE SPACER HAVING INTEGRAL ELECTRON VIBRATION DAMPENING MEMBER THEREON


William F. Cullen, Philpot, Ky., and Othmar E. Ringeman, St. Meinrad, Ind., assignors to General Electric Company

Filed Dec. 13, 1968, Ser. No. 783,543

Int. Cl. H01j 1/18, 19/12

U.S. Cl. 313-269

4 Claims



An insulative electrode spacer member is provided for an electron discharge device, which spacer comprises a disc of natural mica provided with a cathode dampening arm as an integral part of the spacer. A hole is formed in the mica spacer adjacent the dampening arm for the insertion of a cathode which is properly engaged by a free end of the dampening arm which is positioned on the top of the cathode. The cathode may be notched at the top and the arm so positioned with respect thereto that the arm only engages the bottom of the notch when the cathode expands due to normal operational heating.

3,579,021

INCANDESCENT LAMP HAVING LINEAR OUTPUT


Stephen F. Kimball, Beverly, Mass., assignor to Sylvania Electric Products, Inc.

Filed Apr. 30, 1969, Ser. No. 820,369

Int. Cl. H01j 1/96, 19/52

U.S. Cl. 313-274

5 Claims



The coiled filament of an elongated tubular incandescent lamp is axially mounted and supported therein by spacers bearing against the inside wall of the lamp envelope. The space between filament turns is less at its ends than at its center in order to yield a substantially uniform output of radiational energy from the entire length of the lamp.

3,579,022

ROTARY ANODE FOR X-RAY TUBE

Walter Hennig; Karl Sedlatschek, and Rudolf Machenschalk, Reutte, Tirol, Austria, assignors to Schwarzkopf Development Corporation, New York, N.Y.

Filed Aug. 16, 1968, Ser. No. 753,210

Claims priority, application Austria, Aug. 28, 1967,

A7870/67


Int. Cl. H01j 35/10, 35/26

U.S. Cl. 313-330

2 Claims

A rotary anode for an X-ray tube, the anode body consisting essentially of graphite, and having a target layer bonded

thereto consisting essentially of a tungsten-rhenium alloy; in an alternate embodiment, to improve the bonding between the target layer and the anode body, a thin stratum consisting essentially of rhenium is interposed between the anode body and the tungsten-rhenium target layer;



and processes of uniting the target layer to the anode body, including depositing the tungsten and rhenium layer on the anode body out of a gas phase, and depositing the intermediate rhenium layer between the target layer and the anode body out of a gas phase.

3,579,023

CONTROL APPARATUS


Morton H. Fox, Alhambra, Calif., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Mar. 28, 1969, Ser. No. 811,523

Int. Cl. H01j 27/70

U.S. Cl. 315-18

7 Claims



A high-speed digital deflection switch system incorporating a digital-to-analog conversion circuit comprising a plurality of resistors in a ladder network which are switched into and out of the circuit by digital input signals for providing current changes through a magnetic deflection coil. This circuitry is accompanied by linearizing capacitors to produce a more constant deflection rate and further includes a circuit for changing the character size from large to small letters.

3,579,024

SELECTIVE BLANKING CONTROL CIRCUIT

David A. Sokolov, Fairport, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Division of Ser. No. 700,317, Jan. 2, 1968, Pat. No. 3,459,888, which is a continuation-in-part of application Ser. No. 532,289, Mar. 7, 1966. Filed Feb. 3, 1969, Ser. No. 823,211


Int. Cl. H01j 29/52

U.S. Cl. 315-22

6 Claims

Apparatus for selectively masking graphic material to be recorded on photographic film wherein masking is performed by using a cathode ray tube (CRT) to generate and position a light pattern over an area of the graphic material to be masked thereby overexposing the film in the area of the light pattern when the graphic material is imaged onto the film and wherein a light pattern is formed by selectively blanking

the CRT electron beam in one embodiment by a circuit operating on the CRT horizontal and vertical deflection



signals and in another embodiment by a circuit operating on the CRT horizontal and vertical synchronization pulses.

3,579,025

NUMERICAL INDICATOR TUBE WITH BUILT-IN TRANSLATING CIRCUIT


Harold J. Rayner, Wellesley, Mass., assignor to Raytheon Company, Lexington, Mass.

Filed Feb. 3, 1969, Ser. No. 795,856

Int. Cl. H01j 17/34; H03k 23/38

U.S. Cl. 315-84.6

3 Claims



A numerical indicator tube which includes means for translating coded electrical information such as binary data into decimal readout.

3,579,026

LAMP BALLAST


Frederick W. Paget, Hamilton, Mass., assignor to Sylvania Electric Products Inc.

Filed Jan. 2, 1969, Ser. No. 788,524

Int. Cl. H05b 39/00, 41/02, 41/24

U.S. Cl. 315-99

5 Claims



A solid-state ballast for an electric discharge lamp, the ballast including an unfiltered full-wave rectifier, a transistor inverter for increasing the frequency and a transformer for coupling the lamp.

3,579,027

IGNITING AID FOR HIGH EFFICIENCY PLASMA PRODUCERS

Maximilian Pater, Vienna, Austria, assignor to Gebr. Bohler & Co. Aktiengesellschaft, Vienna, Austria


Filed Mar. 4, 1968, Ser. No. 710,175

Claims priority, application Austria, Mar. 3, 1967, A2031/67

Int. Cl. H01j 7/30

U.S. Cl. 315-111

7 Claims



An igniting device for high efficiency plasma producers, which device precludes the necessity for extremely high voltages to produce the initial ignition of the plasma producer by providing high specific ionic densities between the electrodes thereof. The igniting device consists of an annular passage surrounding a rod electrode and through which ionizable gas is passed. The cylindrical wall which defines the outer periphery of the annulus continues axially beyond the end of the rod electrode to form a first tubular passage. A further cylindrical wall forms a second larger diametered tubular passage beyond said first tubular passage. An arc is struck between the rod electrode and the cylindrical wall forming the second tubular passage, which arc has electric lines of force in the form of a cone with the apex pointing upstream the direction of the flow of the ionizable gas. The cone-shaped arc has an azimuthal magnetic field on the inside and outside thereof, and as the gas goes through the arc it is partially ionized and the opposite charge carriers are radially separated by the azimuthal magnetic field. By virtue of the separation, there is less tendency for the opposite charge carriers to recombine, and consequently there is a higher specific ionic density when the gas is introduced between the electrodes of the high efficiency plasma producer.

3,579,028

CONVERGING-BARREL PLASMA ACCELERATOR


T. O. Paine, Acting Administrator of the National Aeronautics and Space Administration with respect to an invention of, and Dah Yu Cheng, Menlo Park, Calif.

Filed Oct. 23, 1968, Ser. No. 769,998

Int. Cl. H01j 1/50, 7/24; H05b 1/00

U.S. Cl. 315-111

7 Claims



The invention comprises a device for generating and accelerating plasma to extremely high velocity, while focusing the plasma to a decreasing cross section for attaining a very

dense high-velocity plasma burst capable of causing nuclear fusion reactions. A converging coaxial accelerator-electrode configuration is employed with "high-pressure" gas injection in controlled amounts to achieve acceleration by deflagration and focusing by the shaped electromagnetic fields.

3,579,029

MONITORING CIRCUIT FOR A HIGH-INTENSITY GLOW DISCHARGE FOR METALLURGICAL PROCESSES

Gelli Spescha, Winterthur Zurich, Switzerland, assignor to Elektrophysikalische Anstalt Bernhard Berghaus, Vaduz, Liechtenstein


Filed Oct. 24, 1967, Ser. No. 677,660

Claims priority, application Germany, Nov. 9, 1966, J32191

Int. Cl. H02h 7/00

U.S. Cl. 315-127

2 Claims



Monitoring circuit for a glow discharge wherein the voltage and current of the discharge are compared by the circuit and a Schmitt trigger generates a control signal if the voltage-current relationship indicates unsafe operation.

3,579,030

STAGE LIGHTING CONTROL UNIT

Frederick Percy Bentham, Ealing, London; Phillip Robert Sheridan, Bickley, Kent; Joseph Trevor Foreman, Wembley Park, and Ian William Stimpson, Windsor, England, assignors to The Strand Electric & Engineering Company Limited, London, England

Filed May 2, 1968, Ser. No. 726,001


Claims priority, application Great Britain, May 3, 1967,

20,462/67

Int. Cl. H05b 37/00

U.S. Cl. 315-291

12 Claims



A stage lighting control unit in which dimmer line signals are recorded in a memory unit for subsequent recall, and in which an active memory connected between the dimmer lines and the memory store includes a backing store for reading information into and out of the memory unit and also includes a pair of individual active memory elements into which information can be written from the backing store for transmission to the dimmer lines.

3,579,031

ZERO ARC DROP THYRATRON


William J. Kearns, Arcadia, Calif., assignor to Xerox Corporation

Filed June 7, 1967, Ser. No. 644,146

Int. Cl. H01j 17/08, 17/20

U.S. Cl. 315-363

18 Claims



A thyatron has a tubular cathode, preferably made of rhenium and circumscribed by a grid which in turn is circumscribed by an anode tube. The thyatron cavity is filled, e.g., with vapor pressure regulated cesium. The operating parameters can be chosen to establish essentially zero voltage drop across the thyatron. The cathode cavity is contiguous with a cavity of a thermionic converter.

3,579,032

PROCESS FOR IMPROVING THE OLEOPHILIC PROPERTY OF POLYMERS


Robert B. Jacobs, Homewood, Ill., assignor to Standard Oil Company, Chicago, Ill.

Filed Aug. 13, 1968, Ser. No. 752,277

Int. Cl. H05f 3/06

U.S. Cl. 317-2

4 Claims



This invention concerns a process for improving the oleophilic property of polymers, particularly polyethylene, and comprises shaving off the external layer of a polymer in the presence of a hydrocarbon cutting material. Shaving the polymer in this manner presents a new surface which is readily wet by hydrocarbons.

3,579,033

ELECTROSTATIC DISCHARGER WITH INTERNAL RESISTANCE ELEMENT

Larry B. Phillips, Santa Clara, Calif., assignor to Granger Associates, Palo Alto, Calif.

Filed Apr. 22, 1969, Ser. No. 818,265

Int. Cl. H05f 1/00, 3/00

U.S. Cl. 317-2

6 Claims



A discharger for reducing electrostatic discharge interference on objects such as aircraft having an elongated insulating body with an internal resistive element connecting the object to a conductive discharge element at the end of the body via the resistive element.

3,579,034

COMPRESSED GAS SYSTEM FOR ARC EXTINCTION


Otto Jensen, Malvern, Pa., assignor to I-T-E Imperial Corporation

Division of Ser. No. 568,942, July 29, 1966, Pat. No. 3,452,251. Filed Feb. 7, 1969, Ser. No. 817,208

Int. Cl. H02h 3/00, 9/06, 7/24

U.S. Cl. 317-11

14 Claims



A capacitor bank protection system having series-connected spark gaps fired responsive to the firing of a precision spark gap connected in parallel with one of the series gaps. Each pair of spark gaps is disposed at the outer end of a central elongated electrode surrounded by cooperating ring-shaped electrodes at the outer ends of the central electrode. An air blast is introduced into the annular space between the central electrode and outer cooperating electrodes for extinguishing the arc.

3,579,035

SYSTEM FOR DETECTION OF TRANSITION BETWEEN SUPERCONDUCTIVE AND RESISTANT STATE IN SUPERCONDUCTIVE COILS


Pierre Burnier, Thairy, and Jack Moreau, Orsay, France, assignors to Societe Generale de Constructions Electriques et Mecaniques (Alsthom), Paris, France

Filed Sept. 27, 1968, Ser. No. 763,251

Int. Cl. H01h 3/28

U.S. Cl. 317-13

5 Claims



An auxiliary winding is located adjacent the main winding of the superconductive coil, the flux relationship between the flux generated by the main winding and by the auxiliary winding being a predetermined factor, for example unity or a whole number factor of proportionality; upon transition from superconductive to resistant state of any portion of the main winding, the IR drop in the superconductive winding will appear as a signal between the superconductive winding and the auxiliary winding, irrespective of inductive voltages. This signal is compared with a voltage drop across a resistance in the supply of the main winding to obtain an alarm which can be used to disconnect the superconductive coil from a supply.

3,579,036

CROWBAR CIRCUIT FOR VOLTAGE CUTOFF WITH SERIES AND SHUNT SWITCHABLE MEANS


Marion B. McCoy, Centerville, Ohio, assignor to The National Cash Register Company, Dayton, Ohio

Filed Jan. 24, 1969, Ser. No. 793,677

Int. Cl. H02h 3/00, 7/00, 5/00

U.S. Cl. 317-16

14 Claims



A crowbar circuit comprises means sensitive to an overcurrent condition through a load to promptly throw a crowbar across the load, thereby isolating the load from its power supply. To prevent an unreasonable dissipation of power through the crowbar, the same sensing mechanism which throws the crowbar initiates operation of a time delayed mechanism which disconnects the power supply from the crowbar. To further conserve the power supply during the interval following operation of the crowbar and before disconnection of the power supply, the circuit includes energy absorbing means which retards dissipation of power from the power supply.

3,579,037

PORTABLE TOOL


Donald J. Hackman; Ronald L. Legue, Columbus; Jeremy M. Harris, and Donald E. Roop, Worthington, Ohio, assignors to Oceanautic Manufacturing and Research Company, Cincinnati, Ohio

Continuation-in-part of application Ser. No. 754,783, Aug. 23, 1968. This application Nov. 12, 1968, Ser. No. 774,622

Int. Cl. H02h 3/28, 7/26

U.S. Cl. 317-18

29 Claims



An electric motor-driven portable tool for use underwater. The tool and motor are insensitive to water depth and corrosion because of the tool design and choice of materials. To minimize the danger of electrical shock to the human operator, the tool is used in combination with a safety trip circuit which is effective to cut off all power to the tool in less than 30 milliseconds in the event of a short circuit or even a minimal current leak in either the tool or cable supplying current to the tool. Additionally, the tool motor is insulated from the housing, the tool housing is grounded by a third ground or neutral wire in the power cable and the cable has a metal sheath which is also grounded at or near the power source.

3,579,038

ELECTRICAL FAULT PROTECTION SYSTEM


Robert P. Backderf, Franklin, and Douglas R. Kanitz, Middletown, Ohio, assignors to Square D Company, Park Ridge, Ill.

Filed Aug. 14, 1969, Ser. No. 850,212

Int. Cl. H02h 3/28, 7/26

U.S. Cl. 317-18

7 Claims



A normally open relay and a normally closed relay responsive to fault currents in an electrical distribution system control the opening of a disconnect switch incapable of interrupting large fault currents. The contacts of the relays are connected in series in an energizing circuit for an electroresponsive operator of the disconnect switch. Upon occurrence of a small fault, such as a ground fault, the contact of the normally open relay closes after a short time delay to effect opening of the disconnect switch. Upon occurrence of a large fault, the contact of the normally open relay also closes as for a small fault, but the contact of the normally closed relay opens instantaneously to prevent opening of the disconnect switch.

3,579,039

SURGE PROTECTION CIRCUIT


Ivan R. Damon, Tinley Park, Ill., assignor to SCM Corporation, New York, N.Y.

Filed Feb. 17, 1969, Ser. No. 799,678

Int. Cl. H02h 3/22

U.S. Cl. 317-22

16 Claims



A regulated power supply is protected from input potential surges by a transistor and Zener diode input network which shuts down the regulated supply whenever the input potential exceeds a predetermined maximum level. When an input potential surge occurs, current flows through a Zener diode and transistor series circuit connected across the input terminals, and a shutdown current flows from the transistor into a shutdown node within the power supply.

3,579,040

DESENSITIZING CIRCUIT FOR A DIFFERENTIAL RELAY

Nathaniel D. Tenenbaum, Plainfield, N.J., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Feb. 18, 1969, Ser. No. 800,109


Int. Cl. H02h 3/28

U.S. Cl. 317-27

17 Claims

A differential type protective relaying apparatus for a power-transforming device; the relaying apparatus having

first and second switches controlled by first and second operate elements and first and second restraint elements; said first operate element being energized as a function of the difference between the input and output energy of the transferring device and said first restraint element being energized as a function of the amount of energy passed through the transferring device and there is provided a second circuit, energized as a consequence of an overvoltage applied to the transferring device to supply additional energization to the first restraint element; the second operate element being



energized as a function of the magnitude of the fundamental frequency portion of the difference between the input and output energy to and from the transferring device; and the second restraint element being energized as a function of the magnitude of the second harmonic frequency portion of the difference between the input and output energy to and from the transferring device. The relaying apparatus being effective to disconnect the power-transferring device when one or the other of the first or the second operate element overcomes its associated restraint element.

3,579,041


CIRCUIT BREAKER UTILIZING MAGNETIC LATCHING RELAYS

T. O. Paine, Acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; Willard E. Reynolds, and Henry W. Reinhold, Plymouth, Mich.

Filed Oct. 30, 1968, Ser. No. 771,759
Int. Cl. H02h 3/08

U.S. Cl. 317-33

3 Claims



In circuit breakers wherein power consumption is significant, a circuit breaker relay being operably controlled by switching transistors normally biased off, the operation of which is triggered by a magnetic latching relay having a coil sensitive to current flow and requiring current flow only on switching.


3,579,042 PROTECTION CIRCUIT WITH SIMULTANEOUS VOLTAGE AND CURRENT SENSING MEANS

Irving J. Abend, Bergenfield, N.J., assignor to Lear Siegler, Inc., Santa Monica, Calif.

Filed Dec. 23, 1968, Ser. No. 786,027
Int. Cl. H02h 7/00

U.S. Cl. 317-33

17 Claims



Dynamic short circuit and overload protection circuit for transistorized power amplifiers; the circuit is noninstantaneous in operation and comprises means for sensing current through and voltage across a transistor to be protected, means for combining, and integrating with respect to time, signals related to the sensed voltage and current to provide a control signal, and means for shunting the input to the transistor when the control signal reaches a predetermined value.

3,579,043


REVERSE POWER RELAY

Charles P. Goeller, Quincy, Mass., assignor to Allis-Chalmers Manufacturing Company, Milwaukee, Wis.

Filed Nov. 15, 1968, Ser. No. 776,127
Int. Cl. H02h 3/38

U.S. Cl. 317-36

2 Claims



A reverse power relay using semiconductor components is provided to sense the phase relationship between current and voltage in an electric circuit and to trip a circuit breaker controlling that circuit in the event of reverse power conditions. The reverse power relay comprises an amplifier and current multivibrator circuit, an amplifier and potential multivibrator circuit, a comparator circuit, and a timing and output circuit. Current and voltage condition signals from the two multivibrator circuit are compared in the comparator circuit and, if a reverse power condition exists, an output signal from the timing and output circuit operates a trip coil which trips the circuit breaker. The reverse power relay is powered from the same power supply as a known type of overcurrent trip device.

3,579,044 UNIT SUBSTATION WITH TRANSFORMER AND CONTROL COMPARTMENTS


Lawrence Phillips, Jr., 840 Inverness, Pasadena, Calif. 91103

Filed Nov. 13, 1969, Ser. No. 876,465

Int. Cl. H01f 27/06, 27/04

U.S. Cl. 317-103

10 Claims



A frame of the unit substation employs the upper and lower core clamping members of a transformer and a pair of spaced-apart transformer supporting members which support the transformer by carrying the lower clamping members. A barrier of insulating material is mounted within a housing through the bolts used to exert the clamping force of the core clamping members on the core of the transformer. Output terminals from the secondary side of the transformer are connected directly to corresponding horizontally disposed bus bars. The barrier mounts the bus bars and separates the interior of the housing into a transformer compartment and a controller compartment. The substation is constructed such that air can freely circulate through not only the transformer compartment but also the control compartment.

3,579,045

HIGH VOLTAGE AIR TERMINAL CHAMBER FOR INDOOR POWER CENTER WITH INTERLOCKS BETWEEN FUSE DRAWERS AND CIRCUIT BREAKERS, FUSE CLAMPING AND LATCHING MEANS, AND UNIVERSALLY PIVOTAL TERMINAL MEANS


Thomas H. Keogh, Pittsburgh, and Adolph E. Krupit, Allison Park, Pa., assignors to Allis-Chalmers Manufacturing Company, Milwaukee, Wis.

Filed Oct. 18, 1968, Ser. No. 768,811

Int. Cl. H01h 9/20; H02b 1/18

U.S. Cl. 317-114

55 Claims



An indoor unit substation for supplying electrical power at distribution voltage includes an electrical transformer and an air terminal chamber enclosing terminating means for tap cables from a plurality of high-voltage primary feeder sources, a circuit interrupter for each source, and high-voltage fuses between the circuit interrupters and the transformer supported on horizontal drawout drawers in alignment with horizontal insulating bushings on the transformer. Manual fuse clamping means push the fuses into high-pressure contact with universal motion terminals on the transformer-insulating bushings, latching means are provided for the fuse

drawers, and the fuse-clamping means prevent release of the drawer-latching means until clamping pressure is removed from the fuses. Interlock means prevents withdrawal of the fuse drawers if a circuit interrupter is closed, prevents closing of either circuit interrupter if a fuse drawer can be withdrawn, and prevents simultaneous closing of both circuit interrupters.

3,579,046

ELECTRICAL HOUSING ASSEMBLY HAVING A PLURALITY OF CHAMBERS WITH ADJACENT CIRCUIT BOARD ELEMENTS


Charles Edward Jordan, Milwaukee, Wis., assignor to Jordan Controls, Inc., Milwaukee, Wis.

Filed May 2, 1969, Ser. No. 821,263

Int. Cl. H05k 5/02, 1/14

U.S. Cl. 317-120

10 Claims



This disclosure includes a housing assembly which can directly replace the usual electromagnetic contactor. The assembly includes opposed similar end housing sections including inwardly projecting and aligned sidewalls. A shallow intermediate wall is interposed between the opposite end sections. Contact boards are provided with a plurality of contact lugs which project outwardly and upwardly along the opposite side edges. The boards are disposed between the end sections and intermediate wall with the contact lugs mating with recesses in the intermediate wall and firmly clamped in place by the ends of the sidewalls of the end sections.

Components are mounted to the circuit boards facing the end sections with printed connections to the opposite side.

3,579,047

KEYBOARD USING SWITCHES HAVING LIGHT OBSTRUCTING ELEMENTS

Konrad Sturm, Nurnberg; Willy Becker, Behringersdorf; Heinz Timm, Brunn, and Karlheinz Rummel, Nurnberg, Germany, assignors to Firma Diehl, Nurnberg, Germany

Filed Feb. 13, 1969, Ser. No. 798,881

Claims priority, application Germany, Feb. 13, 1968,

P 15 74 554.7

Int. Cl. G06m 7/00


U.S. Cl. 250-221

12 Claims

Keyboard apparatus for producing switch signal combinations in a code used in office machines includes a number of individual light beam producing means corresponding in number to the number of channels used in the code, and a number of individual keys, each of which carries one or more light-obstructing barriers, the number and position of the barriers on a particular key corresponding to the number and position of the channels used in the machine code system to

indicate the signal combination associated with the key so that when a key is depressed the light beams will be selective-

released. The output circuit may include a third relay for applying power to the controlled device, and which actuates a



ly interrupted to thereby form a coded signal representing the depressed key.

3,579,048

ELECTRIC SAFETY-BOX

Rene Auffret, Savigny-sur-Orge, France, assignor to Nord-Aviation Societe Nationale De Constructions Aeronautiques, Paris, France


Filed Apr. 1, 1969, Ser. No. 811,732

Claims priority, application France, Apr. 4, 1968, 147,069

Int. Cl. H01h 47/16

U.S. Cl. 317-135

8 Claims



Safety-box connected to pushbuttons comprising a first line and a second line, a control relay and a safety relay on each line, each relay jointly controlling a main contact and an auxiliary contact, the main contact of the control relay being normally open and the main contact of the safety relay being normally closed in the position of rest of the pushbuttons, the auxiliary contact of the control relay of the first line being connected in parallel with the rest contact of the pushbutton of a second line between a point located downstream of the main relay of the second line and the control winding of the safety relay of the said second line.

3,579,049

SAFETY CONTROL SYSTEM FOR ACTUATING ELECTRICALLY CONTROLLED MECHANICAL DEVICE

Donald D. Kikta, Downers Grove, Ill., assignor to Grayhill, Inc., La Grange, Ill.


Filed Nov. 28, 1969, Ser. No. 880,657

Int. Cl. H01h 47/22

U.S. Cl. 317-135

8 Claims

A control system for an electrically controlled device for applying energy thereto including first and second hand-operated switches positioned to be actuated by the two hands of an operator, and a relay actuated by simultaneous operation of the switches including a contact for controlling the output circuit which energizes the device. A second relay having normally closed contacts connected in series with contacts of the first relay provides a holding circuit for the first relay which is released only when both hand switches are



timer which holds the third relay operated for a predetermined time interval.

3,579,050

HIGH-LOW VOLTAGE DETECTOR


Rabindra N. Basu, and Alfred Dvorak, Ottawa, Ontario, Canada, assignors to Northern Electric Company Limited, Montreal, Quebec, Canada

Filed June 11, 1969, Ser. No. 832,139

Int. Cl. H01h 47/32

U.S. Cl. 317-148.5

3 Claims



A solid-state circuit for monitoring low and high voltage conditions in either direct current or alternating current voltage sources. A single transistor in a current control circuit is biased into or out of current conduction by two sample voltages which are related to the monitored voltage. The current flow is detected. For all values of the first sample voltage which exceed a predetermined minimum value the current control circuit will conduct current, provided also that the second sample voltage does not exceed a predetermined maximum value. Irrespective of the value of the first sample voltage, the current control circuit will cease current conduction when the second sample voltage exceeds the predetermined maximum value. The minimum and maximum sample voltage values define boundary conditions which correspond respectively to the low and high values of the monitored voltage.

3,579,051

SENSITIVE MAGNETIC AMPLIFIER RELAY DRIVER

Robert M. Olsen, Barrington, Ill., assignor to Vapor Corporation, Chicago, Ill.

Filed Oct. 22, 1969, Ser. No. 868,504


Int. Cl. H01h 47/34

U.S. Cl. 317-148

10 Claims

Electronic circuit capable of responding to a low signal input including a preamp magnetic amplifier circuit receiving one or a plurality of input signals and conditioned to deliver an output signal upon overcoming a reference signal, a

second magnetic amplifier circuit for receiving the output signal of the preamp and conditioned to operate as a switch



or as a bistable circuit and thereafter trigger a transistor for operating a relay.

3,579,052

SYSTEM FOR DRIVING A D. C. ELECTROMAGNET

Takaaki Kato, Toyohashi-shi, and Mamoru Kawakubo, Kariya-shi, Japan, assignors to Nippon Denso Kabushiki Kaisha, Kariya-shi, Japan


Filed Aug. 5, 1969, Ser. No. 847,558

Claims priority, application Japan, Sept. 21, 1968, 43/68579

Int. Cl. H02m 7/44, 7/68

U.S. Cl. 317-148.5

7 Claims



A system for driving a DC electromagnet of the kind in which an armature is attracted by the magnetic action of current supplied to an electromagnetic winding, having an attraction starting circuit for generating a DC voltage for a predetermined period of time for completing the attraction of the armature, and an attraction-holding circuit for generating an intermittent voltage. After the voltage generated by the attraction starting circuit is applied to the electromagnetic winding to complete the voltage attraction of the armature, the intermittent voltage generated by the attraction holding circuit is solely applied to the electromagnetic winding for holding the armature in its attracted state. Thus, a large force of attraction is produced by a DC electromagnet having a small physical constitution and heat generated therein can be reduced.

3,579,053

MAGNETIZING AND DEMAGNETIZING APPARATUS AND METHOD

Arthur K. Littwin, 6555 N. Le Mai, Lincolnwood, Ill.


Filed June 26, 1968, Ser. No. 740,052

Int. Cl. H01f 13/00

U.S. Cl. 317-157.5

14 Claims

Apparatus for magnetizing and demagnetizing, including means for adjustable controlling the current and voltage ap-



3,579,054

GRAVIMETER UTILIZING MASS OF IONS


David S. Moulton, 145 E. Center St. Apt. 32, Provo, Utah

Filed June 20, 1969, Ser. No. 835,195

Int. Cl. H01g 9/00; G01m 3/40

U.S. Cl. 317-231

10 Claims



A gravimeter comprising a voltage generator cell and a voltmeter-type instrument responsive to variations of the generated voltages. The cell comprises a tubelike container in which a metal and a solution of its chloride salt cooperate to form the metal ions. The ions form different concentrations at the top and bottom of the tube, and are held in such distribution pattern against the gravitational field force by the electrostatic charge opposing such force. Altitudinal movement of the cell relative to the earth's center changes the gravitational field force with a resulting movement of ions and electrons whereby a variation in the voltage generated by the cell takes place. The change in voltage is generated by the voltage responsive instrument, which may be calibrated to indicate the gravitational field force.

To increase and strengthen the degree of voltage change, a number of cells may be connected serially whereby the voltage variation registered by the voltmeter is the sum of the voltages generated by all the interconnected cells.

ERRATUM —

For Class 317—234 see:
Patent No. 3,579,278

3,579,055**SEMICONDUCTOR LASER DEVICE AND METHOD FOR ITS FABRICATION**


Bernd Ross, Arcadia, Calif., assignor to Bell & Howell Company

Filed Aug. 5, 1968, Ser. No. 750,280

Int. Cl. H01l 15/00

U.S. Cl. 317—234

10 Claims



An integral semiconductor diode laser designed for increased heat-dissipation efficiency. A diode element is sandwiched between, and is integral with, layers of semiinsulating semiconductor material. Opposed cleaved surfaces are provided on the device cutting across the diode PN junction and defining a laser cavity through which the PN junction extends. In preparation, a layer of high conductivity semiconductor material is disposed integral with a layer of semiinsulating semiconductor material and the semiinsulating material is grooved to expose portions of the surface of the high conductivity material. Semiconductor material of one conductivity type is then deposited on the exposed high conductivity material, followed by the provision of semiconductor material of opposite conductivity type to form PN junctions within the grooves. The top surface is then lapped to provide coplanarity between the semiinsulating and diode element materials. Electrical contacts are then disposed on the top, coplanar surface and bottom, high conductivity surface.

3,579,056**SEMICONDUCTOR CIRCUIT HAVING ACTIVE DEVICES EMBEDDED IN FLEXIBLE SHEET**

Ties Siebolt TeVelde, and Albert Schmitz, Emmasingel, Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Oct. 10, 1968, Ser. No. 767,062

Claims priority, application Netherlands, Oct. 21, 1967, 6714336

Int. Cl. H01l 15/00

U.S. Cl. 317—234

8 Claims



A semiconductor device is described comprising a flexible sheet assembly of separate semiconductor components em-

bedded in an electrically insulating flexible sheet. The contact surfaces of the semiconductor components are exposed. Interconnections may be made between the components by providing metal strips on one or both outer surfaces of the flexible sheet assembly, the connections lying on the outer surface of the intervening sheet material.

3,579,057**METHOD OF MAKING A SEMICONDUCTOR ARTICLE AND THE ARTICLE PRODUCED THEREBY**


Arthur Irwin Stoller, North Brunswick, N.J., assignor to RCA Corporation

Filed Aug. 18, 1969, Ser. No. 850,823

Int. Cl. H01l 9/00

U.S. Cl. 317—234

11 Claims



A portion of the surface of a body of single crystalline silicon is etched to provide a wall which is substantially perpendicular to the surface of the body. The body is formed with the surface oriented in a (110) crystallographic plane. The surface is then etched with a crystallographically selective etching solution, such as a hot caustic solution, along a (111) crystallographic plane which extends perpendicularly to the (110) oriented surface.

3,579,058**SEMICONDUCTOR MODULE AND METHOD OF ITS PRODUCTION**


Dietrich Armgarth, Dresden, Germany, assignor to Arbeitss-telle Fur Molekularelektronik, Dresden, Germany

Filed Feb. 2, 1968, Ser. No. 702,754

Int. Cl. H01l 19/00

U.S. Cl. 317—235

7 Claims



A multilayer junction semiconductor device includes one semiconductive layer of a type of conductivity provided on its upper surface with a recess of a rectangular cross section. Vertical walls and corners of this recess are coated with a thin insulating layer, while the bottom thereof is open. Another semiconductive layer of an opposite type of conductivity is disposed within this recess, so that the critical PN junction area extends perpendicularly to the insulated vertical walls.

The method of producing this device is based on the semiconductive layer inside said recess serving as an initial temporary substratum on which subsequent layers are precipitated.

3,579,059**MULTIPLE COLLECTOR LATERAL TRANSISTOR DEVICE**

Robert J. Widlar, Mountain View, Calif., assignor to National Semiconductor Corporation, Santa Clara, Calif.

Filed Mar. 11, 1968, Ser. No. 712,040

Int. Cl. H01l 11/00

U.S. Cl. 317—235

5 Claims

A lateral transistor device constructed to have a single emitter region and a single base region operatively associated with a plurality of collector regions. Each of the various col-

3,579,061**INDIVIDUAL CURRENT-LIMITING FUSE FOR THE ROLLS OF A MULTIPLE ROLL CAPACITOR**


Paul L. Waldon, Fort Edward, N.Y., assignor to General Electric Company

Filed Sept. 23, 1968, Ser. No. 761,437

Int. Cl. H01g 1/11


U.S. Cl. 317—247

6 Claims



base-emitter junction to provide a predetermined portion of the total available collector current.

A multiple roll capacitor is disclosed wherein each individual roll section is protected by an isolated current-limiting fuse as a part of the roll tap strap which passes through a central portion of the roll. The current-limiting fuse operates to remove individual defective rolls from the capacitor circuit without significantly adversely affecting the continued operation of the remaining rolls.

**3,579,060****THYRISTOR WITH IMPROVED CURRENT AND VOLTAGE HANDLING CHARACTERISTICS**



Robert L. Davis, Union Springs, N.Y., assignor to General Electric Company

Filed Mar. 21, 1969, Ser. No. 809,142

Int. Cl. H01l 11/00, 15/00

U.S. Cl. 317—235R

11 Claims



A controlled rectifier is disclosed which is comprised of a main current carrying thyristor which surrounds an integrated gate signal amplifying thyristor. The main thyristor is peripherally beveled to increase the voltage blocking capabilities of the controlled rectifier. The surface of the base layer of the main thyristor is provided with an exposed surface lying at a lower level than the surface of the adjacent emitter layer of the main thyristor, and the exposed base layer surface is interdigitated with the adjacent emitter layer. A metallic contact ohmically connects an emitter layer of the amplifying thyristor to the exposed base layer surface of the main thyristor. The base layer of the main thyristor is also provided with exposed surface portions coplanar with the adjacent emitter layer surface at locations most remote from the fingers of the base layer surface. Additionally, a relatively high resistance current spreading path is provided associated with the emitter layer of the amplifying thyristor, and the amplifying thyristor emitter layer is provided with a minimum spacing from the control lead adjacent the spreading path.

3,579,062**ELECTRICAL CAPACITOR WITH THERMAL FUSE**


Thomas G. Chapman, Hudson Falls, N.Y., assignor to General Electric Company

Filed Nov. 28, 1969, Ser. No. 880,533

Int. Cl. H01g 1/11

U.S. Cl. 317—247

11 Claims



A thermal fuse for a roll capacitor is disclosed wherein a wire lead is joined to a flag of aluminum which is sandwiched between two pieces of insulating material. A narrow strip of a thermal fusible alloy overlies the flag in the sandwich and extends therefrom. This sandwich is positioned in a capacitor roll between a dielectric strip and a foil strip so that the extending fusible alloy strip lies adjacent the capacitor foil strip for electrical connection thereto.

3,579,063**THIN FILM CAPACITOR**

Kiyotaka Wasa, and Shigeru Hayakawa, Osaka, Japan, assignors to Matsushita Electric Industrial Co. Ltd., Osaka, Japan


Filed Mar. 24, 1969, Ser. No. 809,801

Claims priority, application Japan, Mar. 25, 1968, Sept. 13, 1968, Sept. 13, 1968, Sept. 13, 1968, 43/19851; 43/66389; 43/66391

Int. Cl. H01g 1/01

U.S. Cl. 317—258

1 Claim




This invention relates to a thin film capacitor. The capacitor comprises a dielectric layer sandwiched between a top

metal electrode and a base titanium electrode which is oxidized at the surface facing said dielectric layer. The dielectric layer consists essentially of a mixture of lead oxide and titanium oxide.

3,579,064
SOLID-STATE MOTOR CONTROL CIRCUIT USING
TRIAC ELEMENTS
John R. Taylor, North Wales, Pa., assignor to Sperry Rand
Corporation, New York, N.Y.


Filed May 5, 1969, Ser. No. 821,847
Int. Cl. H02p 1/42
U.S. Cl. 318-207



There is disclosed a solid-state control circuit which provides on/off, direction reversal and braking signals for a single-phase motor. The solid-state circuit utilizes a combination of semiconductors which gate AC and DC current through the motor windings in a manner to provide clockwise or counterclockwise shaft rotation as well as on/off and braking signals.

3,579,065
WEB SPEED CONTROL APPARATUS
Joseph F. Laukaitis, Rochester, N.Y., assignor to Eastman
Kodak Company, Rochester, N.Y.


Filed June 28, 1968, Ser. No. 741,184
Int. Cl. H02p 5/08
U.S. Cl. 318—314



A motor operates to drive a web at a predetermined speed. The speed of the motor is automatically adjusted to assure the proper rate of web speed, such motor being under control of a circuit which not only applies a correction signal to such motor for a "time" dependent on the necessary correction, but also applies such correction through a means the operation of which is itself dependent upon a time constant. This technique permits such broadband control of web speed that accelerating to or decelerating from a reference web speed obtains without hunting. As disclosed the invention uses digital techniques, while incorporating the above-mentioned principles, in such a way that digital-to-analog converter apparatus is obviated.

3,579,066
BRAKE MOTOR ATTACHMENT DEVICE
Clair A. Bearfield, and Raymond Cole, Valley City, N. Dak.,
assignors to Tri W-G Inc., Valley City, N. Dak.
Filed Apr. 7, 1969, Ser. No. 813,998
Int. Cl. H02k 23/68


U.S. Cl. 318—372



The invention comprises a mechanical brake for an electric motor with a solenoid mechanically connected to a brakeshoe which upon deactuation of the solenoid automatically engages a brakedrum or the rotor of the electric motor to stop the rotation of the motor. The solenoid and electric motor being actuated and deactuated simultaneously and the brakeshoe engagement preventing coasting of the motor after electric current to the motor has been discontinued.

3,579,067
MOTOR CONTROL SYSTEM
William C. Riester, Williamsville, N.Y., assignor to Trico
Products Corporation, Buffalo, N.Y.
Filed Sept. 16, 1968, Ser. No. 759,839


U.S. Cl. 318-444



An electric motor-driven windshield wiper system for producing timed dwell periods between cycles of wiper operation incorporating a first silicon-controlled rectifier triggered by a timing network which includes a unijunction transistor which is in turn triggered by an RC circuit. A cyclically actuated switch responsive to motor rotation moves between a running and parking contact. When on the running contact a rectifier is connected in circuit with the motor-energizing circuit and also bypasses the silicon-controlled rectifier thus extinguishing it. A dynamic braking circuit is provided which includes a second silicon-controlled rectifier triggered by charging current of a capacitor in the gate circuit when the cyclically actuated switch moves from the running contact to the parking contact. When the cyclical switch moves to the run position the motor continues to be energized through the rectifier until the cyclic switch reaches the park position thereby triggering the second silicon-controlled rectifier in the dynamic braking circuit.

3,579,068
SERVO CONTROLLED HEIGHT CONTROL
 Teh C. Tschang, Springfield, N.J., assignor to Air Reduction
 Company, Incorporated., New York, N.Y.
 Filed Mar. 11, 1968, Ser. No. 712,217
 Int. Cl. G05d 16/00
 U.S. Cl. 318—478
 15 Claims

U.S. Cl. 318-478




A height control unit for maintaining the desired distance between a tool and a substantially flat workpiece on which the tool is working. The control system utilizes fluidic circuitry to measure the reflected pressure of jets of gas directed at the workpiece. The fluidic circuitry develops a signal in response to the reflected pressure which results in the raising or lowering of the tool.

3,579,069
NUMERICAL MACHINE TOOL CONTROL SYSTEM
INCLUDING MEANS TO DIGITALLY SIMULATE A
TEMPLATE FOLLOWER

Johann F. Reuteler, Elmwood, and James A. Warren, Sims-
bury, Conn., assignors to Pratt & Whitney Inc.
Filed Sept. 15, 1967, Ser. No. 668,037
Int. Cl. G05b 19/24

U.S. Cl. 318-571



This disclosure relates to a tracer-controlled machine tool adapted for numerical control. The contact gaps actuated by a tracer stylus to control the movement of a cutting tool is electrically simulated and the simulated tracer contact gap is varied with slide velocity. The gap is simulated by a comparison of a velocity signal with a signal proportional to servo position error or lag and the result of this comparison indicates an open or closed contact and actuates a slide drive means in response thereto. This comparison is further utilized to modify the slide velocity to maintain the servo position lag substantially proportional to slide velocity within predetermined limits.


3,579,070
MACHINE TOOL SERVO SYSTEM INCLUDING FEED-RATE CONTROL

Weyman S. Crocker, Springfield, Vt.; Philip H. White, Caremont, N.H., and William T. McDonald, Wayland, Mass., assignors to Pneumo Dynamics Corporation, Cleveland, Ohio
Filed Apr. 15, 1968, Ser. No. 721,479
Int. Cl. G05b 19/24

U.S. Cl. 318-571

An electronic-hydraulic analog position servomechanism for the automatic actuation of a machine tool of the automatic type having a sequential mode of operation including position and rate control of portions of the traverse of the slide.

A spindle pulse generator and integrator circuit provide a ramp function rate control signal for combination with posi-




tion information for synchronizing slide movement with rotation of the spindle.

3,579,071
ELECTRONIC CIRCUIT ARRANGEMENT FOR
PERFORMING WORK STEPS IN THE PRODUCTION OR
TESTING OF SEMI-CONDUCTOR MEANS

**Kurt Drescher, and Reinhard Springer, Dresden, Germany,
assignors to Arbeitsstelle Fur Molekularelektronik,
Dresden, Haus, Germany**
Filed Dec. 23, 1969, Ser. No. 887,708
Int. Cl. G05b 19/28

U.S. Cl. 318-603



The present invention relates to electronic circuit arrangements for performing predetermined work steps in the production or testing of semiconductor means arranged in rows and columns to form a matrix of said semiconductor means in a coordinate system with individual fields defined at intersections of said rows and columns, wherein row and column measuring and counting means generate coordinate signals which are compared with preselected coordinate digits to produce preselection signals which are channeled through logic circuits to drive means of a positioning apparatus which positions a workpiece support or a tool, for example, in a photorepeater or in a wafer prober, in accordance with the identification of the preselection signals by said logic circuits, whereby any desired extraneous structures may be arranged or tested in said matrix of semiconductor means.

3,579,072
SERVO POSITION CONTROL INCLUDING INTEGRAL
CONTROL IN FORWARD AND FEEDBACK CONTROLS
 Dexter Robert Plummer, Leicester; Keith Lawrence Wright,

Knighton, and Colin Arthur Wild, Stoneygate, England, assignors to The Rank Organisation Limited, London, England


Filed Oct. 21, 1968, Ser. No. 769,087
Claims priority, application Great Britain, Nov. 3, 1967,

50162/67
Int. Cl. G05b 11/36

U.S. Cl. 318-609

A control system for an actuator, for example, a positional control motor for a camera, includes a demand unit which

provides demand signals representative of different positions or energization levels of the actuator. A control signal is generated by an integrator which is responsive to the demand signal and which compares the change in demand with the state of the actuator immediately before the commencement of the change, as indicated by a memory signal provided by a



further integrator. This control signal, and the actuator energization level, changes at a rate dependent upon, and preferably proportional to, the change in demand. Preferably, therefore, the system is such that a given change in actuator energization takes place in a time interval which is independent of the magnitude of the change in demand.

3,579,073


SPINDLE GROWTH COMPENSATOR

Richard Johnstone, 2400 Rockway Lane E., Brookfield, and Richard E. Stobbe, 4221 S. 104th St., Greenfield, Wis. Continuation-in-part of application Ser. No. 726,964, May 6, 1968. This application May 20, 1970, Ser. No. 37,485

Int. Cl. G05d 23/275

U.S. Cl. 318—634

7 Claims



A device for automatically compensating for the expansion and contraction of the spindle of a machine tool due to different operating temperatures. A thermistor, impedance network is utilized to provide a corrective predetermined control signal to the spindle positioning control circuit.

ERRATUM

For Class 318—696 see:
Patent No. 3,579,279

3,579,074

ELECTRONIC POWERED PULSE AMPLIFIER

Clement Michael Richell, Warren, Ohio, assignor to Ray R. Roberts, Warren, Ohio, fractional part interest to each Filed Nov. 2, 1967, Ser. No. 683,760


Int. Cl. H02m 3/00

U.S. Cl. 320—1

22 Claims

A power pulse amplifier comprises a plurality of capacitors, a charging circuit and a discharging circuit. The charging circuit is arranged to connect the capacitors or groups thereof in parallel to a source of charging potential and includes a switching arrangement for charging individual

capacitors or the groups thereof individually and sequentially. The discharge circuit is arranged for discharging all of the capacitors or the groups of capacitors simultaneously after all of the capacitors have been charged sequentially. In



certain embodiments the discharge circuit discharges the capacitors simultaneously in parallel while in other embodiments the discharging circuit discharges the capacitors or the groups thereof simultaneously in series.

3,579,075

COMPACT BATTERY CHARGER FOR RECHARGEABLE BATTERIES OF VARIOUS PHYSICAL SIZES AND ELECTRICAL CAPABILITIES


Linton E. Floyd, Gainesville, Fla., assignor to General Electric Company

Filed Aug. 14, 1968, Ser. No. 752,543

Int. Cl. H02j 7/02

U.S. Cl. 320—2

12 Claims



A portable device for simultaneously charging a plurality of batteries of different electrical and physical characteristics. The input power consists of standard household alternating current which is converted within the device to half-wave rectified current. A plurality of current limiting charging circuits is provided and an included housing is formed with battery retaining recesses sized to mechanically discriminate each battery so that it will connect only with the corresponding circuit which has been designed to provide a proper charging current for the corresponding batteries.

3,579,076

CHARGE CONTROL SYSTEM FOR BATTERIES

John A. Herbst, Morristown, and Victor H. Seliger, North Caldwell, N.J., assignors to Singer-General Precision, Inc., Little Falls, N.J.

Filed Dec. 30, 1968, Ser. No. 787,940


Int. Cl. H02j 7/04

U.S. Cl. 320—36

16 Claims

A battery charging system including means for connecting a voltage source to the battery in a manner to establish a high

current path and a low current path through the battery, and a switching means connected in said paths and responsive to output of the amplifier is applied to the primary of a step up transformer, and the secondary of the transformer is con-



various battery temperatures for providing an open circuit in one or more of the paths.

3,579,077

REGULATED STATIC DC TO DC CONVERTER START-UP MEANS


Douglas R. G. Cameron, Montreal, Quebec, Canada, assignor to Pylon Electronic Development Company, Lachine, Quebec, Canada

Filed May 12, 1969, Ser. No. 823,797

Int. Cl. H02m 3/22, 1/18, 7/52

U.S. Cl. 321—2

6 Claims



A static DC to DC converter having an output converter stage comprising a full-wave bridge with an SCR in each of two adjacent legs of the bridge. The firing times of the SCR's are controlled by a variable phase synchronous pulse generator controlled by an operational amplifier having one input connected to a reference voltage source and another input connected to feedback means across the converter's output so that the converter's output voltage is regulated. Means are provided for delaying, during start-up, the application of voltage to the pulse generator to prevent heavy current surges through the SCR's. An overshoot voltage clipper is connected across the output of the operational amplifier.

3,579,078

CONSTANT CURRENT HIGH VOLTAGE POWER SUPPLY

Donald L. Cronin, Anaheim; Bertrand F. Fraber, Palos Verdes Peninsula, and Charles R. Nockey, Canoga Park, Calif., assignors to TRW Inc., Redondo Beach, Calif.


Filed Oct. 6, 1969, Ser. No. 864,067

Int. Cl. H02m 3/32; H02j 1/04

U.S. Cl. 321—2

1 Claim

A direct current DC source and a square wave voltage source are applied to a bridge type switching amplifier. The



connected to a voltage quadrupler. The output of the voltage quadrupler is the desired DC voltage output.

3,579,079

CURRENT SOURCE MAGNETIC GATING CIRCUIT FOR CONTROLLED RECTIFIERS


Fred W. Kelley, Jr., Media, Pa., assignor to General Electric Company

Filed Nov. 17, 1965, Ser. No. 514,430

Int. Cl. H02m 1/08

U.S. Cl. 321—5

2 Claims



For triggering semiconductor controlled rectifiers, an otherwise conventional gate pulse generator is given the characteristics of a current source by connecting in series therewith a nonlinear impedance comprising a diode poled to block gate current and shunted by the series combination of a source of forward bias voltage and a current limiting resistor.

3,579,080

ZERO DEADBAND REVERSING CONTROL

Donald E. Vollrath, Greenfield, Wis., assignor to The Louis Allis Company

Filed Nov. 13, 1969, Ser. No. 876,470

Int. Cl. H02m 7/68; H02p 1/00


U.S. Cl. 321—5

11 Claims

In a reversible phase controlled rectifier control system, zero deadband response is realized by generating overlapping firing waves for forward current and reverse current conducting controlled switch elements of the phase controlled rectifier and controlling the direction of load current flow substantially instantaneously to provide for current to flow alternately in both directions when the system is in a quiescent state. An oscillator driven flip-flop gates firing between forward current and reverse current conducting controlled switch elements to provide immediate current direction control and lockout. The oscillator is responsive to the state of conduction of the controlled switch elements, permitting the firing signals to pass to forward current conducting controlled switch elements when reverse current conducting controlled

switch elements are nonconductive and vice versa. The oscillator drives the flip-flop between its stable states at a high rate when all controlled switch elements are nonconductive

as thyristors connected in series. Condensers are connected in parallel with the semiconductor valves and the capacitance values of the condensers vary progressively downward in the direction towards the lowest potential point on the chain.



so that the control system is substantially instantaneously responsive to a command for current to flow in either direction.

3,579,081


LOW FREQUENCY SINE WAVE GENERATOR CIRCUIT
James W. Bates, Palos Verdes Estates, Calif., assignor to Gul-ton Industries, Inc., Metuchen, N.J.

Filed Nov. 12, 1968, Ser. No. 774,660

Int. Cl. H02m 1/12, 7/00

U.S. Cl. 321-9

17 Claims



A sinusoidal signal generator circuit comprising at least two bridge circuits each comprising two pairs of series-connected bidirectional current control means connected across a source of direct current DC voltage, each bridge circuit having a pair of output terminals at the juncture of the current control means said pairs of current control means at very low frequencies like 60 cycles per second being connected directly in series. The noncorresponding current control means of the pairs of current control means of each bridge circuit are rendered nonconductive sequentially and in different combinations to produce different rectangular pulse output waveforms at the output terminals of said bridge circuit, each waveform respectively comprising positive and negative going pulses of the same amplitude relative to zero, the pulses of the different waveforms each cycle preferably being different in number and phase and of different magnitude, so the waveforms combine in both additive and subtractive relation to produce a resultant stepped sinusoidal-like resultant waveform.

3,579,082

ARRANGEMENT FOR DIVIDING AND LIMITING THE VOLTAGE FOR A CONVERTER HAVING A PLURALITY OF THYRISTOR VALVES CONNECTED IN SERIES

Hans Jurg Bossi, Nussbaumen, and Werner Faust, Wettingen, Switzerland, assignors to Aktiengesellschaft Brown, Boveri & Cie, Baden, Switzerland

Filed Feb. 10, 1969, Ser. No. 797,994

Claims priority, application Switzerland, Feb. 12, 1968, 2,053


Int. Cl. H02m 7/24

U.S. Cl. 321-11

6 Claims

An electrical converter arrangement comprises a chain of converter valves of the controllable semiconductor type such

This invention is directed to an integrated ferroresonant stabilizer having a regulated constant voltage output and in



3,579,083

PROTECTION MEANS FOR RECTIFIERS UPON THE OCCURENCE OF UNDESIRE DISCHARGE CURRENTS
Lennart Bjork, Ludvika, Sweden, assignor to Allmanna Svenska Elektriska Aktiebolaget, Vasteras, Sweden


Filed Nov. 3, 1969, Ser. No. 873,539

Claims priority, application Sweden, Nov. 4, 1968, 14921/68

Int. Cl. H02m 1/18; H02h 7/10

U.S. Cl. 321-13

6 Claims



For protecting a rectifier unit including a control pulse amplifier composed of a monostable multivibrator and an OR-gate, the gate being controlled by control pulses to cause the amplifier to transmit a signal to the control electrode to render it conducting, a transformer in the conductor for the rectifier is provided which makes the control pulse amplifier operative to emit a control signal in response to a flow of current in the conductor produced by an external flashover occurring when the rectifier is not conducting.

3,579,084


FERRO-RESONANT POWER DEVICE
Elmo E. Moyer, Saratoga Springs, N.Y., assignor to Atto Laboratories, Inc., Rhinebeck, N.Y.

Filed Sept. 10, 1969, Ser. No. 856,570

Int. Cl. H02m 7/06; G05f 3/06; H01f 15/14

U.S. Cl. 321-16

4 Claims



which the secondary windings, of foil interleaved with a dielectric film, provide both inductance and capacitance. A high degree of electrical efficiency is achieved, together with low weight and volume. No external capacitance is required.

power source, reduces circuit complexity, and utilizes power taken directly from the power source output for controlling the polarity switching members. The output voltage of the device may be made proportional to the output frequency, and the device may be utilized in either single- or multi-phase circuits.

3,579,085

POWER SUPPLY FOR PROVIDING MAIN AND STANDBY SOURCES OF POWER


Robert Grodinsky, Skokie, Ill., assignor to Acoustic Research, Inc., Cambridge, Mass.

Filed Sept. 13, 1968, Ser. No. 759,742

Int. Cl. H02m 7/00; H03f 1/00

U.S. Cl. 321-27

5 Claims



A power supply for high-fidelity amplifier and having a pair of full-wave rectifiers, one with its input permanently connected to line power, the other with a switch for connecting and disconnecting it to line power. The output of the auxiliary rectifier is fed to an input terminal for the amplifier so that portions of the latter can be kept energized at low levels. The other or main rectifier is connected to a regulator to provide a regulated supply and the output of the latter is diode connected to the output of the auxiliary rectifier so that when the main rectifier is turned on it will supply all of the necessary power to all portions of the amplifier.

3,579,086

FREQUENCY CONVERSION CYCLOCONVERTER SYSTEM FOR BOTH SINGLE- AND MULTI-PHASE APPLICATIONS


Paul Lebenbaum, Jr., 2531 Blackthorn, Newport Beach, Calif.

Filed June 19, 1969, Ser. No. 834,644

Int. Cl. H02m 5/30

U.S. Cl. 321-60

10 Claims



A device for variably decreasing the frequency of a power source by selectively reversing the polarity of the power source voltage applied to a load, wherein the output of the power source and the output of a signal generator, in conjunction, control the polarity of the voltage applied to the load. Such polarity control avoids short circuiting of the

3,579,087

GENERATOR SEMICONDUCTOR VOLTAGE REGULATOR

Owen E. Reinert, St. Louis County, Mo., assignor to Sperry Rand Corporation, New York, N.Y.


Division of Ser. No. 568,210, July 27, 1966, Pat. No. 3,470,456.

This application Dec. 31, 1968, Ser. No. 840,544

Int. Cl. H02p 9/30

U.S. Cl. 322-28

8 Claims



A silicon controlled rectifier, which is connected to the field winding of a generator, has the firing angle thereof controlled by a firing circuit which includes a capacitor; and a second silicon controlled rectifier stores inhibiting energy in that capacitor to vary the firing angle of the first said silicon controlled rectifier.

3,579,088

FERRORESONANT TRANSFORMER WITH CONTROLLABLE FLUX


Taylor C. Fletcher, 1534 Sunnycrest, Fullerton, Lawrence M. Silva, 4110 Maritime, Portuguese Bend, and Bruce L. Wilkinson, 4604 Sharynne Lane, Torrance, Calif.

Filed Apr. 8, 1969, Ser. No. 814,393

Int. Cl. G05f 1/38, 7/00

U.S. Cl. 323-6

17 Claims



A ferroresonant transformer with means for varying saturation flux capacity for controlling the transformer output. A ferroresonant transformer with at least a portion of the core structure carrying the secondary winding having two separate sections providing parallel magnetic paths for the secondary and resonant flux, with a control winding on one of the sections and a switching circuit for opening and closing the control winding. A low frequency version utilizing E and I laminations with the control winding on one of the outer legs of the E. Another low frequency version utilizing E and I laminations with the control winding encircling a portion of the secondary magnetic circuit. A high frequency version utilizing a plurality of toroid cores with the control winding on one of the cores.

3,579,089

STABILIZED POWER SUPPLY CIRCUITS

Witfried Elmar Giess, Mannheim, Germany, assignor to Brown, Boveri & Cie Aktiengesellschaft, Mannheim-Kafer-tal, Germany


Filed Jan. 7, 1969, Ser. No. 789,565

Claims priority, application Germany, Jan. 11, 1968,

P 16 13 977.8
Int. Cl. G05f 1/56

U.S. Cl. 323-22

6 Claims



A stabilized power supply circuit is provided having a transistor series control circuit, a resistance voltage divider shunting the load, a control circuit with a control amplifier and a reference voltage source as well as a circuit for superposing disturbances derived from input voltage variations.

3,579,090

SWITCHING REGULATOR WITH RAPID SWITCHING DRIVE


Eric V. Madsen, New Shrewsbury, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed May 8, 1969, Ser. No. 823,120

Int. Cl. G05f 1/56

U.S. Cl. 323-22

6 Claims



A switching type regulator reduces switching transition times by increasing the magnitude of the switching control signal at the exact interval of the occurrence of the switching transition. The magnitude of the switching control signal is in turn responsive to the output voltage and hence the circuitry to reduce switching transition times also functions to regulate the output voltage.

3,579,091

SWITCHING REGULATOR WITH RANDOM NOISE GENERATOR

Patrick W. Clarke, Murray Hill, N.J., and Rudolph Scuderi, New York, N.Y., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed May 16, 1969, Ser. No. 825,368


Int. Cl. G05f 1/56, 1/64

U.S. Cl. 323-22

7 Claims

A switching regulator-converter wherein the error detector reference voltage is varied with a random noise signal to per-

mit operation of the switching devices at frequencies in the



audible range without the unacceptable acoustical noise normally accompanying these switching frequencies.

3,579,092

TAP-CHANGING REGULATING TRANSFORMER WITH SOLID-STATE CIRCUITRY

Manfred Matzl, Regensburg, Germany, assignor to Maschin-fabrik Reinhausen Gebruder Scheubeck K.G., Regen-sburg, Germany


Filed Apr. 2, 1970, Ser. No. 24,986

Claims priority, application Germany, Apr. 12, 1969,

P 19 18 606.2
Int. Cl. H01f 29/04

U.S. Cl. 323-43.55

10 Claims



A tap-changing regulating transformer is provided with a tapped winding, a selector switch, a triggerable solid-state circuitry for performing tap-changing operations, trigger pulse generators for triggering said circuitry and automatic control circuitry for controlling said trigger pulse generators. The solid-state circuitry carries the load current permanently, i.e. not only during tap-changing operations, thus dispensing with the provision of current-carrying shunting switches across the solid-state circuitry for carrying load currents during steady state periods when no tap-changing operations are being performed, and further dispensing with operating means for the aforementioned current-carrying shunting switches. The aforementioned trigger pulse generators are controlled to supply the required trigger pulses not only during steady state periods, but also when a noncurrent-carrying movable contact of the selector switch separates from its cooperating fixed contact in order to select another tap of the tapped transformer winding.

3,579,093

VARIABLE MUTUAL COUPLING CIRCUIT EMPLOYING TRANSFORMERS IN AN INDUCTIVE BALANCED CONFIGURATION

Paul R. Johannessen, Lexington, and Thorleif Knutrud, Sud-bury, Mass., assignors to Sylvania Electric Products Inc.

Filed Oct. 29, 1969, Ser. No. 872,312


Int. Cl. H03k 17/18

U.S. Cl. 323-50

7 Claims

A variable mutual coupling circuit employing a plurality of transformers connected in an inductive balanced configuration between an input circuit and an output circuit. Bipolar

switches associated with the transformers are activated in a predetermined sequence to unbalance the inductance and



thereby transfer energy from the input circuit to the output circuit.

3,579,094

VOLTAGE-GENERATING APPARATUS


Otto A. Jorgensen, Centerport, N.Y., assignor to Hazeltine Corporation

Filed Sept. 26, 1969, Ser. No. 861,378

Int. Cl. H03k 5/00

U.S. Cl. 323-100

15 Claims



Apparatus for generating a DC voltage whose amplitude is controlled in accordance with variations in the amplitude of supplied control pulses. In one embodiment a DC control signal is developed whose amplitude varies in proportion to variations in the amplitude of a supplied DC reference signal and a pulse-type difference signal in which the amplitude of each pulse is representative of the difference between the amplitude of corresponding supplied control pulses and an additional supplied DC reference signal. The control signal is coupled to a DC power supply for controlling the output voltage in accordance with variations in the amplitude of the supplied control pulses.

3,579,095

CIRCUITS USING TRANSISTORS TO PROVIDE VARIABLE PHASE SHIFT

Ronald Richard Norley, Indianapolis, Ind., assignor to RCA Corporation


Filed June 3, 1969, Ser. No. 829,970

Int. Cl. H03k 1/12

U.S. Cl. 323-108

8 Claims

A phase shift network for providing a variable shift for a frequency signal while maintaining the amplitude thereof relatively constant. The circuit includes first and second transistors having a common collector network and including first and second reactive networks coupled between the emitter electrodes thereof. A common return path is provided for currents flowing through the transistors and means are coupled to one of the transistor's bases to alter the con-



duction of the transistors, to provide a variable phase change at the collector electrodes, between a first phase angle deter-

3,579,096

PROPORTIONAL POWER CONTROL CIRCUIT


Edward E. Buchanan, Jr., Dallas, Tex., assignor to Electronic Control Corporation, Euless, Tex.

Filed May 1, 1969, Ser. No. 821,003

Int. Cl. G05f 1/40

U.S. Cl. 323-22SC

19 Claims



A proportional power control circuit in which the average power applied to the load is controlled by controlling the number of cycles of power applied to a load in a series of available cycles of power. A proportional gate is generated for controlling the application of power to the load. The proportional gate is generated by a circuit which compares a reference voltage that varies in accordance with the demand for power with a ramp voltage whose potential varies as a function of time.

3,579,097

APPARATUS AND METHOD FOR MEASURING THE AMOUNT OF A SELECTED VAPOR IN AN ATMOSPHERE

Alfred J. Luden, Osseo, Minn., assignor to Bureau of Engraving, Inc., Minneapolis, Minn.

Continuation of application Ser. No. 664,808, Aug. 31, 1967, now abandoned. This application Dec. 30, 1969, Ser. No. 888,128


Int. Cl. G01n 27/42

U.S. Cl. 324-30R

5 Claims

Apparatus and method for detecting and measuring the concentration of a particular gas in a gaseous mixture. A

nonconductive, nonporous probe having a thin film of relatively nonconductive liquid thereon is placed in the gaseous mixture. The liquid film is capable of absorbing the particular gas to thereby change the electrical conductivity of the liquid film. The electrical conductivity of the film is measured to determine the concentration of the particular gas in the mix-



ture. Preferably the probe is a generally U-shaped glass rod having a roughened exterior surface to aid in retaining the thin film of liquid thereon. The apparatus and process is especially effective to detect and measure the amount of ammonia vapor in the air, using distilled water to form the thin liquid film. As a result, ammonia in solution is readily measured by measuring the vapor in proximity to the solution.

3,579,098


METHOD AND COMBINATION WELL-LOGGING APPARATUS FOR CONDUCTING BOTH DEEP AND SHALLOW INVESTIGATION OF THE FORMATIONS SURROUNDING A BOREHOLE

Marcel L. Mougne, Houston, Tex., assignor to Dresser Industries, Inc., Dallas, Tex.

Filed Oct. 24, 1968, Ser. No. 770,221
Int. Cl. G01v 3/18

U.S. Cl. 324-10

9 Claims




The well-logging instrument comprises, essentially, a focus section have a focus upper guard, a center electrode and lower focus guard. The bottom section of the instrument includes a pad device having a minifocus central button electrode and rings around the central button which serve as microguards. The remote electrode of the focus portion of the instrument is the armor surrounding the logging cable. The lower focus guard serves a dual function in that it is also the minifocus remote electrode. Means are provided for measuring the potential between the focus guard and the cable armor and also between the microguard and the lower focus guard, both measurements then being sent up the logging cable to the surface electronics.

3,579,099
IMPROVED FLAW DETECTION APPARATUS USING SPECIALLY LOCATED HALL DETECTOR ELEMENTS
Takayuki Kanbayashi, 552 Niina, Minoo, Japan
Continuation-in-part of application Ser. No. 598,457, Dec. 1, 1966, now abandoned. This application June 5, 1969, Ser. No. 830,624

Int. Cl. G01r 33/12

U.S. Cl. 324-37

7 Claims



A pair of Hall generator elements are symmetrically mounted in the same magnetic plane closely adjacent a material surface of substantially circular cross section, one Hall generator element being mounted on each side of a null plane, to detect the variations in leakage flux emanating from the material surface as the material is spirally rotated past the Hall generator elements. The Hall generator elements are symmetrically mounted on an axis intersecting a line parallel to the longitudinal axis of the material by approximately 5° and a control current provided to each Hall generator element of the same magnitude but different polarity. The Hall generator elements are, alternately, mounted astride the null plane to be substantially nearly aligned with the null plane and the control current to each Hall generator element is of the same magnitude and polarity.

ERRATUM

For Class 324-51 see:
Patent No. 3,579,280


3,579,100 FLASHLIGHT ADAPTED FOR SHORT CIRCUIT TESTING

Palmer R. Lauver, 416 N. Second St., Sunbury, Pa.

Filed May 14, 1969, Ser. No. 824,528
Int. Cl. G01r 31/02

U.S. Cl. 324-53

4 Claims



An apparatus is disclosed comprising a flashlight having two bulbs at the light-emitting end, and equipped with a three-pronged adapter at the rearward end. The two bulbs are wired through the batteries and a two position switch such that a short circuit between any pair of terminals of a three-terminal socket is detected by a specific pattern of energized bulbs.


3,579,101
ALTERNATING CURRENT APPARATUS FOR MEASURING CAPACITANCE OR PHASE ANGLE
Norbert L. Kusters, and William J. M. Moore, Ottawa, Ontario, Canada, assignors to Canadian Patents and Development Limited, Ottawa, Ontario, Canada

Filed Apr. 24, 1969, Ser. No. 819,029

Int. Cl. G01n 11/52

U.S. Cl. 324-60

7 Claims



Apparatus of the current comparator type employs a magnetic core, with detection and compensating windings around the core shielded by a further magnetic core from outer ratio windings. A first series circuit is formed with one ratio winding and a capacitor to be measured; a second series circuit with the second ratio winding, a standard capacitor and a variable resistor. The series circuits are connected in parallel across an alternating potential with the currents in the ratio windings in opposition to generate only a difference flux in the cores. Turns of the compensating winding equal in number to the turns of the second ratio winding are connected in a closed series circuit with a third capacitor and a voltage proportional to the voltage drop across the resistor. Balance is detected by zero output from the detection winding. In-phase adjustment is obtained by varying the number of turns in the second ratio winding and hence in the compensating winding. Quadrature adjustment is achieved by the resistor.


3,579,102
APPARATUS FOR TESTING SUCCESSIVE ONES OF A PLURALITY OF ELECTRICAL COMPONENTS
John F. Keating, Fanwood, and Joseph A. Zutkis, Mountain-side, N.J.

Filed Sept. 30, 1968, Ser. No. 763,690

Int. Cl. G01r 15/12

U.S. Cl. 324-73

2 Claims



A turntable, having a plurality of pairs of test sockets, is moved rotatably through a load station where relays are placed in the sockets. As the turntable is moved rotatably in a first direction, each pair of relays is aligned successively

with a test device, which is then locked against the turntable and connected electrically to the relays to test the relays. After a predetermined rotation of the test device with the turntable, the test device is disengaged from the turntable and is urged in a second direction to engage the next successive pair of relays.


3,579,103
ANALOG-TO-DIGITAL CONVERTER TESTER
Charles H. Russell, Newport News, Va., assignor to the United States of America as represented by the Administrator of the National Aeronautics and Space Administration

Filed Oct. 6, 1969, Ser. No. 863,913

Int. Cl. G01r 15/12

U.S. Cl. 324-73

10 Claims



Apparatus for automatically testing an ADC for open and short circuits. A tester is connected to the contacts on the ADC shaft. The ADC motor turns the ADC shaft to a specific setting and in response to this setting means are provided for stopping the motor and producing a signal having a predetermined duration which is applied to the tester. The tester, in response to this signal, performs the open and short circuit tests for the specific setting of the ADC shaft. If there are no open or short circuits, the tester produces another signal which causes the ADC motor to turn the ADC shaft to another specific setting for testing. If there is an open or short circuit, the tester does not produce said another signal and a buzzer sounds. The operator can then look at lights on the tester to determine where the open or short circuit is located.


3,579,104
DIGITAL PHASE METER WITH COMPENSATING MEANS FOR ASYMMETRIC WAVEFORM DISTORTION
Jean Pignard, Annecy, and Bernard Wintz, Cessenaz, France, assignors to International Standard Electric Corporation, New York, N.Y.

Filed Apr. 21, 1969, Ser. No. 817,968

Int. Cl. G01r 25/00; G04f 9/00, 11/06

U.S. Cl. 324-83D

6 Claims



A phase-measuring instrument for waves of the same frequency is shown in basic form, in which a digital phase shift (or phase delay) reading is obtained and which may be


3,579,111

RADIO FREQUENCY PULSE GENERATOR USING DC CHARGING

Paul R. Johannessen, Lexington, and Thorleif Knutrud, Sundbury, Mass., assignors to Sylvania Electric Products Inc.
Filed Oct. 29, 1969, Ser. No. 872,318
Int. Cl. H04b 1/04

U.S. Cl. 325-141

5 Claims



A radiofrequency generator employing a charging inductor connected to a source of direct current (DC) energy through a charging switch. The capacitor of a radiofrequency (RF) tank circuit cooperates with the charging inductor to achieve resonant charging of the RF tank circuit. A power switch is closed causing the charged tank circuit to oscillate at its natural resonant frequency through a series-connected load.

3,579,112

AUTOMATIC GAIN CONTROL SYSTEMS


Jack R. Harford, Flemington, N.J., assignor to RCA Corporation

Filed Mar. 3, 1969, Ser. No. 803,728

Int. Cl. H03g 3/30

U.S. Cl. 325-319

10 Claims



3,579,119

UNIVERSAL LOGIC CIRCUITRY HAVING MODULES WITH MINIMUM INPUT-OUTPUT CONNECTIONS AND MINIMUM LOGIC GATES


Slk-Sang Yau, and Calvin K. Tang, Evanston, Ill., assignors to Northwestern University, Evanston, Ill.

Filed Apr. 29, 1968, Ser. No. 724,701

Int. Cl. H03k 19/00, 19/12, 19/20

U.S. Cl. 328—92

21 Claims



Universal logic circuitry for a large number of variables using identical universal logic circuits of a small number of variables having a minimal number of logic gates and input-output circuits as modules in a multilevel arrangement.

3,579,120

SELF-TESTING LOGIC GATE


Peter Curran, Hastings-on-Hudson, N.Y., and John Delistovich, Jersey City, N.J., assignors to The Bendix Corporation

Filed Mar. 28, 1969, Ser. No. 812,575

Int. Cl. H03k 19/00, 5/20

U.S. Cl. 328—92

5 Claims



A self-testing logic gate used in redundant control systems performs logic functions on AC coded input signals by means of an input resistor network and a differential amplifier having inverting and noninverting inputs. The amplifier is responsive to the AC inputs for providing a square wave output and when a logic circuit failure occurs, normally balanced DC amplifier inputs are unbalanced so that the amplifier provides a steady state DC output.

3,579,121

APPARATUS FOR DETECTING NONRECURRENT PULSES IN THE NANOSECOND RANGE WITH A DELAY LINE

Eugen Haag, Karlsruhe, Germany, assignor to Siemens Aktiengesellschaft, Berlin and Munich, Germany

Filed Jan. 15, 1969, Ser. No. 791,463

Claims priority, application France, Feb. 16, 1968, 140,140


Int. Cl. G11c 1/26

U.S. Cl. 328—124

11 Claims

An apparatus for obtaining, with a delay, amplitude values of a nonrecurrent signal pulse of a duration in the nanosecond or subnanosecond range. The signal pulse is ap-

plied to a delay line having a plurality of spaced taps, to each of which there is connected a sampling station. Entering the delay line, the signal pulse triggers a scanning signal that travels along a scanning signal path with a speed different from the speed of the signal pulse traveling in the delay line.



Thus, the scanning signal either overtakes or falls behind the signal pulse and during such a relative travel it scans the signal pulse and causes storing of individual amplitude values in said sampling stations from which the stored values may be sequentially picked up for a visible recording of the signal pulse curve.

3,579,122

DIGITAL FILTER FOR REDUCING SAMPLING JITTER IN DIGITAL CONTROL SYSTEMS


Thomas O. Paine, Administrator of the National Aeronautics and Space Administration with respect to an invention of; Tage O. Anderson, Arcadia, and William J. Hurd, La Canada, Calif.

Filed Dec. 23, 1969, Ser. No. 887,701

Int. Cl. H03k 21/18

U.S. Cl. 328—167

10 Claims



A digital filter comprising two up-down counters A and B. Counter A which is responsive to a sampled input signal which is quantized into three levels +1, -1 and 0, is incremented in response to each +1 input, decremented in response to each -1 input, and remains unchanged in response to a 0 input. Counter B, which includes N stages, is incremented at each sampling time when A is positive, decremented when A is negative and remains unchanged when A is zero. When B overflows in a positive direction A is decremented by one while a negative overflow of B results in A being incremented by one. The filter output is $+2^N$ when A is positive, -2^N when A is negative and zero (0) when the count in A is zero.

3,579,123

DC RESTORER APPARATUS

Hirotohi Koga, Tokyo, Japan, assignor to Nippon Electric Company, Limited, Tokyo, Japan

Filed Aug. 21, 1969, Ser. No. 851,991

Claims priority, application Japan, Aug. 23, 1968,

43/59899


Int. Cl. H04b 1/12

U.S. Cl. 328—164

9 Claims

DC restorer apparatus is provided in accordance with the teachings of the present invention for restoring the DC and low frequency components to a pulse train received in a facsimile or data transmission system. The DC restorer ap-

paratus provided comprises adder means for summing first and second input signals applied thereto and for providing an output signal representative of the received pulse train with the DC and low frequency components restored thereto. The adder means is adapted to have the received pulse train applied to the first input thereof while the output of a feedback loop, which includes both bistable circuit means and low-pass



filter means, is applied as the second input thereto. The bistable circuit means is adapted to be driven by the output produced by such adder means and the output of the bistable circuit means is applied through the low-pass filter means to the second input of said adder means. The filtered output of the bistable circuit means is thus added to the received pulse train whereby the DC and low frequency components thereof are restored.

3,579,124

COMPENSATED SWEEP GENERATOR


John Henry O'Hara, Bowie, Md., assignor to The United States of America as represented by the Secretary of the Army

Filed May 12, 1969, Ser. No. 823,911

Int. Cl. H03k 4/10, 4/86

U.S. Cl. 328—181

8 Claims



An apparatus for generating a frequency-compensated sweep. A signal containing wow and flutter deviations is applied to the input of the generator, wherein these deviations are compensated for by increasing or decreasing the instantaneous value of the sweep voltage. An integrator portion of the generator generates the compensated sweep. The output of the integrator is a staircase voltage, the rate of change of voltage varying as the input frequency varies with wow and flutter. The generator compensates for instantaneous variations in the time base due to wow and flutter by generating a time base that is a function of the wow and flutter. Either the number, amplitude, or width of the input pulses may be changed to vary the time base.

3,579,125

APPARATUS FOR RESETTING AN ANALOG INTEGRATOR

Lars A. Lindblad, Klingen, and Rune N. Kahlbom, Uplands Vasby, Sweden, assignors to Junger Instrument Aktiebolag, Stockholm, Sweden

Filed Nov. 25, 1968, Ser. No. 778,658


Int. Cl. G06g 7/18

U.S. Cl. 328—127

1 Claim

Apparatus for resetting an analog integrator with digital readout capability. The resetting signal, which discharges the

integrating capacitor, is terminated when the output of the integrator reaches a level which is proportional to the analog input signal instead of completely discharging the integrating capacitor. This compensates for the errors present in prior art analog integrators caused by ignoring the analog input



signal during the discharge time of the integrating capacitor. During the discharge of the integrating capacitor, an operational amplifier compares the integrator output voltage with a signal proportional to the analog input signal, called the compensating voltage. When two signals are equal the resetting signal is terminated.

3,579,126

DUAL SPEED GATED COUNTER

John J. Paul, Montreal, Quebec, Canada, assignor to Sperry Rand Canada Limited, Toronto, Ontario, Canada


Filed Oct. 17, 1968, Ser. No. 768,487

Claims priority, application Canada, Aug. 29, 1968, 028,840

Int. Cl. H03k 17/28

U.S. Cl. 328—129

4 Claims



Counting apparatus for determining the elapsed time between a reference pulse and the next following positive peak of a delayed sine wave irrespective of the DC level of the sine wave. The apparatus comprises a clock pulse source producing full rate and half rate pulses which are applied through respective gates to a single pulse counter. The first (full rate) gate is turned on by the reference pulse and is turned off upon the first following positive-going crossover of the delayed sine wave. The second (half rate) gate is turned on simultaneously with the termination of the first gate and is turned off upon the next following negative-going crossover of said delayed sine wave.

3,579,127

APPARATUS FOR MONITORING PULSES

Harold A. Thomas, San Diego, Calif., assignor to Gulf Energy & Environmental Systems, Inc., San Diego, Calif.

Filed May 31, 1967, Ser. No. 642,390

Int. Cl. G06g 7/24; G01t 1/15


U.S. Cl. 328—145

5 Claims

Apparatus is described for producing an output signal generally proportional to the log of the rate of random pulses, which rate varies over a total pulse-rate range of sufficient magnitude as to require at least two different monitoring techniques. Means utilizing the respective techniques are provided for producing log signals representing the pulse rate

of the random pulses in lower and upper portions of the total pulse-rate range. The log signals representative of the pulse rate in the respective ranges are adjustable to have the same

sampled or peak voltage for an extended period of time; and a method for holding a peak or sampled voltage for an extended period of time.




proportional relation to the log of the pulse rate. The relative amplitudes of the two log signals are also adjustable such that a continuous and coherent output may be provided over the total pulse-rate range.

3,579,128 PHASE CONTROLLER

Ervin Smith, Timonium, and John O. Wedel, Baltimore, Md.
Filed Feb. 12, 1969, Ser. No. 798,658
Int. Cl. H03b 3/04

U.S. Cl. 328—155

5 Claims




The subject disclosure relates to novel and improved apparatus for detecting and nulling the difference in phase between a pair of electrical operational channels. The apparatus includes a signal generator which applies a test signal to each operational channel, a phase detector coupled to the output of the channels, an analog to digital converter that converts the detected phase difference into a count in and up and down counter circuit and switching devices that in response to the output of the counter couple phase shift elements into one of the channels so as to equalize the phase between the two channels.

3,579,129 VOLTAGE-HOLDING CIRCUIT AND METHOD

Robert G. Irvine, Claremont, Calif., assignor to LTV Ling Altec, Inc., Anaheim, Calif.
Filed Apr. 25, 1969, Ser. No. 819,380
Int. Cl. H03f 3/16, 5/00

U.S. Cl. 330—3

11 Claims




3,579,130 THIN FILM ACTIVE INTERFERENCE FILTER

Vern N. Smiley, San Diego, Calif.
Filed July 18, 1969, Ser. No. 842,917
Int. Cl. H01s 3/05

U.S. Cl. 330—4.3

6 Claims



A thin film of active laser material having a thickness of an integral number of one-half wavelengths of the laser emission energy is disposed between two multilayer films having high reflectance properties relative to the wavelength of energy emitted by the active laser material while offering relatively good transmittance to a source of energy directed to the active laser material to raise its energy level. The multilayer films are each comprised of a number of layers alternating in high and low index of refraction and having a thickness of the order of one-quarter wavelength of the emitted laser energy. The multilayer high reflectance films disposed on either side of the thin film of active laser material may be supported on an appropriate substrate and the assembly is positioned in the path of an input signal which it is desired to filter and amplify as well as in the path of a source of excitation energy to produce an output signal commensurate in frequency with a known or determinable component of the input signal and in amplified form.


3,579,131 OPERATIONAL AMPLIFIER

Toshio Fukuda, Takatsuki, Osaka, Japan, assignor to Shimadzu Seisakusho Ltd., Nakagyo-ku, Kyoto, Kyoto-prefecture, Japan

Filed Oct. 8, 1968, Ser. No. 765,957
Claims priority, application Japan, Oct. 10, 1967, 42/65087
Int. Cl. H03f 1/02, 1/14

U.S. Cl. 330—9

1 Claim



An operational amplifier for constituting an apparatus such as, for instance, an analog computer. The amplifier has a very high input impedance so that only a very low value of signal current is drawn from the signal source. A stationary component in the signal voltage appearing at the signal input terminal is amplified by a chopper-stabilized direct-current amplifier having a chopper and a synchronous demodulator,

A voltage-holding circuit for sampling a signal voltage at a given instant or at the peak of the voltage and for holding the

and then is applied to a feedback point located at the junction between the two operational impedances, after passing through a direct-coupled amplifier. The voltage at the feedback point is equilibrated to the input signal applied to the input signal terminal by feedback action, and in reaction to this equilibrium value, output voltage is taken out at the output terminal. Since the input signal current is not taken directly into the operational impedance, the input impedance can be made extremely high, resulting in increasing the precision of mathematical operations.


3,579,132 CLASS "D" LINEAR AUDIO AMPLIFIER

James A. Ross, La Jolla, Calif., assignor to LTV Ling Altec Inc., Anaheim, Calif.


Filed Nov. 14, 1969, Ser. No. 876,771
Int. Cl. H03f 3/38

U.S. Cl. 330—10

14 Claims



the transconductance of which is adjusted to effect a desired attenuation of applied input signals in response to a controllable direct voltage applied to an included second transistor,



with the control voltage being applied in a manner to introduce a minimum of distortion in the attenuated signal over a wide control range.


3,579,134 SYSTEM FOR STABILIZING AN OPERATIONAL AMPLIFIER

Steven Morrison, Randallstown, Md., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Oct. 17, 1969, Ser. No. 867,321
Int. Cl. H03f 5/00

U.S. Cl. 330—3

8 Claims



An audio frequency amplifier, useful to DC in which a pulse-width modulated signal is formed from the audio frequency signal. Each excursion of the pulse-width signal is cut in half with respect to time by an appropriately timed square-wave and plural logic gates. The resulting waveforms are passed without distortion by pulse transformers. Plural rectifiers and low-pass filters re-form the pulse-width modulated signal. This signal is impressed upon switching power transistors. These give a greatly amplified power output, which is the same type of amplitude-varying waveform as the input audio signal, upon the current flowing through a small choke to the load. The load may have any phase angle without incurring distortion of the output waveform. Half-bridge, quarter-bridge, full-bridge, and plural phase embodiments are described.

Described is a system for direct current stabilizing an operational amplifier by means of a field effect common source differential amplifier with a current sink which drives a matched pair of PNP transistors in the common base configuration.


3,579,135 FILTER NETWORK AND METHOD

Robert K. Anderson, Minneapolis, Minn., assignor to Medtronic, Inc., Minneapolis, Minn.

Filed Dec. 31, 1968, Ser. No. 788,238
Int. Cl. H03f 3/68; H03h 7/10

U.S. Cl. 330—30

1 Claim



3,579,133 SIGNAL TRANSLATING STAGE

Jack R. Harford, Three Bridges, N.J., assignor to RCA Corporation

Filed Jan. 29, 1969, Ser. No. 794,973
Int. Cl. H03f 3/42; H03g 3/30

U.S. Cl. 330—19

9 Claims

A signal translating stage especially suited for fabrication using integrated circuit techniques including a first transistor,

A filter network and method for the rejection of all but a selected band of frequency, the apparatus and method utilizing a pair of notch-type filters such as twin-T filters, with a common input connection and separate outputs connected to different inputs on a differential amplifier.


3,579,136

MULTI-STAGE POWER AMPLIFIER IN WHICH EACH STAGE CONDUCTS FOR ONLY A PREDETERMINED PORTION OF THE INPUT

George A. Machamer, 10401 S. State St., Chicago, Ill.
Filed Dec. 13, 1965, Ser. No. 513,405
Int. Cl. H03f 3/68


U.S. Cl. 330-30

7 Claims



An amplifying circuit made up of a plurality of individual amplifying stages, each of which may have at least three elements. Each of the amplifying stages have a common input and a common output and the stages are so biased that each amplifying stage conducts for a different portion of the input cycle. Although the output wave form is the same as if only a single stage were used, by providing a plurality of stages, each of which conducts for only a portion of the input cycle, a substantially more efficient power amplifier is provided.

detector determine the peak input. A counter is incremented continuously and a reference voltage is developed which increases with the increasing count. The reference voltage is compared with the detected peak voltage and when the reference voltage is equal to or greater than the peak input voltage the counter ceases to increment. A plurality of resistors are connectable in parallel in the feedback path of the



operational amplifier, but each individual resistor is connected in the feedback path only if a respective stage in the counter is in a predetermined state. The gain of the operational amplifier depends upon the total effective feedback impedance. The larger the final count in the counter, corresponding to a larger peak input signal, the smaller the total effective feedback impedance and the lower the gain of the amplifier.


3,579,137

THIN FILM THERMAL DEVICE

Robert H. Walden, Scotch Plains, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.
Filed Oct. 31, 1968, Ser. No. 772,335
Int. Cl. H03f 15/00

U.S. Cl. 330-38

5 Claims




A thin film thermal device comprises an MIS structure fabricated on a low thermal conductivity insulator. A first DC bias and AC signal input are applied across the metal layer and a second DC bias is applied across, and the AC signal output taken from, the semiconductor layer. The device operates as an audio amplifier if the first DC bias current is greater than the second and operates as a frequency doubler if the first DC bias current is zero.

**3,579,139
HORIZONTAL CIRCUITRY FOR TELEVISION RECEIVERS**

Dong Woo Rhee, Williamsville, N.Y., assignor to Sylvania Electric Products Inc.
Filed Aug. 17, 1967, Ser. No. 661,388
Int. Cl. H04i 7/04

U.S. Cl. 331-8

3 Claims



Transistorized horizontal oscillator and drive circuitry for a television receiver including a modified common emitter multivibrator with the emitter electrode of the multivibrator output transistor coupled directly to the base electrode of a drive transistor.

3,579,140

LASER

James M. Anderson, New Milford, and Marvin J. Fenton, Stamford, Conn., assignors to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed Dec. 5, 1967, Ser. No. 688,204
Int. Cl. G01b 11/26; H01s 3/00

U.S. Cl. 331-94.5

3 Claims

A continuous wave laser in which the end mirrors are automatically maintained in alignment. A four-quadrant detector is centered along the path of the emerging light beam. Misalignment of the end mirrors causes an axial shift in the direction of the light beam and produces output signals from

3,579,138

AUTOMATIC GAIN PRESETTING CIRCUIT

George J. Harris, Framingham, and Christopher C. Day, Newtonville, Mass., assignors to American Optical Corporation, Southbridge, Mass.

Filed Aug. 25, 1969, Ser. No. 852,635
Int. Cl. H03g 3/20

U.S. Cl. 330-86

13 Claims

An automatic gain presetting circuit for adjusting the gain of an operational amplifier. A full-wave rectifier and peak


3,579,143

METHOD FOR INCREASING THE EFFICIENCY OF LSA OSCILLATOR DEVICES BY UNIFORM ILLUMINATION

William H. Haydl, Tarzana, Calif., assignor to North American Rockwell Corporation
Filed Nov. 29, 1968, Ser. No. 780,037
Int. Cl. H03b 7/00

U.S. Cl. 331-107G

3 Claims



servocontrol the position of one of the mirrors so as to bring it back into alignment with the other mirror.


3,579,141

GAS LASER TUBE

Masao Miya, Tokyo, Japan, assignor to Nippon Electric Company, Limited, Tokyo, Japan
Filed Jan. 30, 1969, Ser. No. 795,281
Claims priority, application Japan, Feb. 2, 1968, 43/6603
Int. Cl. H01s 3/22

U.S. Cl. 331-94.5

5 Claims



A gas laser device is described wherein a long life is obtained with the employment of a cathode and an anode. A gas filled tube is provided which at oppositely located ends has a cathode and an anode. A short hollow member, preferably of cylindrical shape, is seated on the ends of the gas filled tube. The member is made of a material selected to withstand the bombardment of discharge particles such as positive ions and electrons.

3,579,142


THIN FILM LASER

Vern N. Smiley, San Diego, Calif., assignor to the United States of America as represented by the Secretary of the Navy

Filed July 18, 1969, Ser. No. 842,938
Int. Cl. H01s 3/05

U.S. Cl. 331-94.5

11 Claims



A laser assembly comprises a source of exciting or pumping energy, a thin film of laser material supported to intercept a path of the exciting energy, the film having a thickness of the order of one wavelength of the radiant energy emitted by the laser. The film is positioned at an angle relative to the exciting energy for producing a laser beam which is substantially perpendicular to the plane of the film and therefore a much larger aperture than has been realized with prior thin film lasing materials. In a preferred form, multilayer reflective coatings intensify and enhance the laser beam produced perpendicularly to the plane of the film.


3,579,144

RELAXATION OSCILLATOR SATATED BY TRANSISTOR SWITCH

Michael Rotolo, Jr., Cherry Hill, N.J., assignor to RCA Corporation
Filed Mar. 19, 1969, Ser. No. 808,587
Int. Cl. H03k 3/26

U.S. Cl. 331-111

7 Claims



A unijunction transistor, a switch such as the emitter-to-collector path of a bipolar transistor, connected with the emitter-to-base path of the unijunction transistor, and a charged capacitor connected across the series circuit. When the switch is closed, the capacitor instantaneously discharges through the emitter-to-base diode of the unijunction transistor. Thus, the leading edge of this discharge wave is substantially coincident in time with the closing of the switch, that is, with the turn-on pulse employed to drive the bipolar transistor into conduction.

3,579,145

MODULATOR STABILIZATION CIRCUITS

Owen E. De Lange, Rumson, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.


Filed Mar. 21, 1969, Ser. No. 809,261
Int. Cl. H01s 3/10; H03c 1/06

U.S. Cl. 332-7.51

3 Claims

The operating point of a modulator is stabilized by superimposing a pilot signal upon the information bearing

harmonics. The filter includes an absorptive filter which eliminates spurious passbands resulting from interaction of



components. The absorptive filter includes highpass filters arranged in an L-network.

3,579,155

FILTERED CONNECTOR PIN CONTACT


Jeff Tuchto, Don Mills, Ontario, Canada, assignor to The Bunker-Ramo Corporation, Broadview, Ill.

Filed Feb. 1, 1967, Ser. No. 613,346

Int. Cl. H03h 7/04

U.S. Cl. 333—79

4 Claims



Pin contact for filtered connector, having central metal element surrounded by a ferrite ferrule and an outer ceramic sleeve, and including flexible conductive washers end-loading the ferrule and sleeve, to provide flexibility, and prevent breaking.

3,579,156

SHIELDED FILTER


Peter Parfitt, Hove, England, assignor to Worcester Controls Corporation, West Boylston, Mass.

Filed Aug. 15, 1968, Ser. No. 752,913

Int. Cl. H03h 7/04

U.S. Cl. 333—79

10 Claims



An electrical filter comprises an elongated metallic tube having a pair of open-ended cans inserted into the tube ends with the open ends of the cans being joined to the tube adjacent the tube ends. The interior regions of the tube, divided by the closed ends of the cans, contain inductance and capacitance elements electrically interconnected to one another, said interconnections including conductive tabs carried by the capacitance elements. The ends of the tube are hermetically sealed; and the interior of the tube is filled with a potting compound.

ERRATUM

For Class 333—97 see:
Patent No. 3,579,282

3,579,157
ELECTRIC CROSSBAR SWITCHES

Donald Edward Rowley, Coventry, England, assignor to The General Electric and English Electric Companies Limited, London, England


Filed Nov. 7, 1969, Ser. No. 874,791

Claims priority, application Great Britain, Nov. 8, 1968, 53060/68

Int. Cl. H01h 67/14

U.S. Cl. 335—112

6 Claims



A crossbar switch in which an array of contact sets is formed by a cross-wire matrix. The contact sets are operated by movement of respective 'interposer members' into the plane of the array. The interposer members are operated selectively by coordinate crossbar systems one of which moves a row of interposer members into driving positions underneath the respective contact sets and the other of which, crossing the first, drives the selected one of the positioned interposer members into operative engagement with the selected contact set. The interposer members are carried by, and magnetically located on, the bars of the first coordinate system so that operation of a bar of the first system does not disturb a previous connection made by the same bar, the magnetic coupling accommodating the relative movement of the interposer members.

3,579,158

ARMATURE STRUCTURE FOR REED SWITCHES


John Kutyla, Chicago, Ill., assignor to C. P. Clare & Company, Chicago, Ill.

Filed July 28, 1969, Ser. No. 845,202

Int. Cl. H01h 51/28

U.S. Cl. 335—151


21 Claims



A sealed switch with an elongated glass housing having pole pieces sealed in both ends includes a uniplanar, rigid ar-

mature having a projecting or transversely extending end portion. A flat spring movably mounts said one end on one pole piece with the projection forming a working gap with this pole piece so that the armature has two working gaps and the switch has increased sensitivity. In one switch, a pair of pole pieces are sealed at one end of the housing with the free end of the armature disposed between the pair of pole pieces. In another switch, a single pole piece is provided at each end.

on the stator being selectively magnetized to cause attraction and repulsion with a north pole portion and a south pole portion of the rotor. Two or more spaced permeable bars are



3,579,159

PUSHBUTTON MAGNETIC REED SWITCH


William T. Posey, 608 Knoll Road, Boonton, N.J.

Filed May 3, 1968, Ser. No. 726,391

Int. Cl. H05b 51/28

U.S. Cl. 335—205

7 Claims



A novel reed switch assembly provided with a ceramic bar magnet as the switch actuating means is disclosed. The structure of the novel reed switch is characterized by the arrangement of the ceramic bar magnet with an iron backing plate.

3,579,160

PUSHBUTTON MECHANISM

Harold Jessup Mackway, Haddon Heights, N.J., assignor to RCA Corporation


Division of Ser. No. 707,800, Feb. 23, 1968, Pat. No. 3,519,766.

This application June 2, 1969, Ser. No. 829,530

Int. Cl. H01h 13/12, 13/52


U.S. Cl. 335—206

5 Claims



Pushbutton switches of the type in which, in each bank, the depression of one button releases a previously depressed button. A printed circuit board leading to the electrical contacts of one bank of switches acts also as a sidewall for that bank of switches, and an electric and magnetic field shield member serves as its other sidewall. Additional features of these switches include simple and inexpensive one-piece plungers, simple means for automatically illuminating the depressed buttons, means for automatically electrically indicating whether a pushbutton in a bank is depressed, and means for resetting, in unison, a plurality of banks of switches.

The ducts between adjacent layers of windings are formed into a plurality of longitudinal passageways of generally square cross section. A flat strip of insulating material twisted about the central longitudinal axis thereof is provided in each of the passageways to augment the heat flow from the winding to the coolant flowing in the passageway.



3,579,162

WINDING DUCT CONSTRUCTION FOR POWER TRANSFORMER

Sudhir D. Savkar, Scotia, N.Y., assignor to General Electric Company

Filed Nov. 28, 1969, Ser. No. 880,619

Int. Cl. H01f 27/10

U.S. Cl. 336—57

8 Claims

3,579,161

ELECTROMAGNETIC DEVICE

Sigmunt J. Kremzner, Pompton Plains, and William Pasechnick, Little Ferry, N.J., assignors to Singer-General Precision, Inc., Little Falls, N.J.

Filed Oct. 17, 1969, Ser. No. 867,148

Int. Cl. H01f 7/08

U.S. Cl. 335—272

2 Claims

An electromagnetic device in which a rotor rotates within a stator in response to a plurality of electromagnets formed

3,579,163
LIQUID-FILLED TRANSFORMER WITH FOAMED INSULATION

John C. Cronin, Horsham, Pa., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Sept. 24, 1969, Ser. No. 860,688


Int. Cl. H01f 27/02

U.S. Cl. 336—94

6 Claims

Electrical inductive apparatus of the type containing a magnetic core-winding assembly immersed in a liquid-insulating material. The breakdown voltage of predetermined insulating gaps in the apparatus is increased, while maintaining substantially the same dielectric constant across the gap as that of the liquid-insulating material, by disposing an open

cell-insulating foam material in the predetermined gaps. The open cells of the foam material are impregnated or filled with




the liquid-insulating material, which increases the breakdown voltage in volts per mil across the gap.

3,579,164 NOISE REDUCTION SYSTEMS FOR ELECTRICAL TRANSFORMERS

James L. Rotruck, Sharon, Pa., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.
Filed Nov. 14, 1969, Ser. No. 876,768
Int. Cl. H01f15/00

U.S. Cl. 336—100

8 Claims




A system for reducing noise generated in an electrical transformer due to changing of size and shape of the ferromagnetic core when excited with alternating electric current. The noise reduction system comprises attaching flexible fibers to parts of the ferromagnetic core and parts of the housing or casing of the transformer. The flexible fibers absorb energy from the air column set up by the core when it changes size and shape and reduces the effectiveness of the air column in setting up objectionable audible noise.

3,579,165 WINDING CONNECTION FOR SINGLE PHASE TWO LEG ELECTRIC TRANSFORMER

Wallace M. Johnson, Pittsfield, Mass., assignor to General Electric Company
Filed Sept. 24, 1969, Ser. No. 860,757
Int. Cl. H01f 27/28

U.S. Cl. 336—170

5 Claims




A single phase power transformer having a low power tertiary winding comprises a two-legged core with four concentric coils on each leg. The radially innermost coils are of unequal turns and series connected to constitute the tertiary winding. The high voltage main winding comprises the two radially outermost coils of like formation connected in parallel. The low voltage main winding comprises two series coil circuits in parallel, each series circuit including a radially inner intermediate coil on one leg and a radially outer intermediate coil on the other leg, the radially intermediate coils on each leg having unequal numbers of turns.

3,579,166 ELECTRICAL COIL

Roderick V. Sawyer, Elkhart, Ind., assignor to CTS Corporation, Elkhart, Ind.
Filed Oct. 8, 1968, Ser. No. 765,791
Int. Cl. H01j 15/10

U.S. Cl. 336—192

5 Claims



Strands of material along selected segments of an indeterminate length of stranded conductive material are welded together and severed to provide predetermined lengths of stranded conductive material having the strands at the ends thereof secured together to prevent unraveling. Such pieces of conductive material are secured to one or more coil lead wires to form a pair of terminal leads in a coil assembly. Each strand comprises a pliant fiber core about which is wrapped a conductive foil.

3,579,167 THERMOSTATIC SWITCH WITH IMPROVED HEATER ASSEMBLY AND METHOD OF ASSEMBLING SAME


Jack W. Grable, Lexington, Ky., assignor to Texas Instruments Incorporated, Dallas, Tex.
Continuation of application Ser. No. 566,674, July 20, 1966, now abandoned. This application Nov. 21, 1969, Ser. No. 872,446

U.S. Cl. 337—102

4 Claims

A thermostatically controlled electrical switch having a heater assembly adjacent the thermostatic element. The heater assembly includes ceramic substrate with a resistive coating on the face of the substrate remote from the thermostatic element. First and second spaced conductive contact

layers are provided on the resistive coatings. The resistive coatings are connected to exterior terminals via stiff spring




elements which have coiled end portions biased into firm electrical contact with the respective contact layers.

3,579,168 CYCLIC SWITCH

Alex Vary, North Olmsted, Ohio, assignor to The United States of America as represented by the Administrator of the National Aeronautics and Space Administration
Filed Dec. 31, 1969, Ser. No. 889,387
Int. Cl. H01h 37/36, 87/00

U.S. Cl. 337—114

13 Claims



A switch utilizing a liquid metal in the cavity of a metal chamber connected in a conductor through which current flows from a DC source to a load or vice versa. Abrupt, cyclic decreases in current are effected by the formation of vapor films or vapor cavities which form at the interfaces between the liquid metal and the walls of the chamber due to ohmic heating. A source of pressurized gas communicates with the interior of the chamber. Cooling means for the chamber are provided to extract heat at a predetermined rate. The chamber may also be subjected to ultrasonic waves and heat waves to alter the wetting-dewetting action of the liquid metal.


3,579,169 A VARIABLE RESISTOR FOR DUAL OPERATION

Clarence R. Dickinson, Greendale, Wis., assignor to Allen-Bradley Company, Milwaukee, Wis.
Filed Feb. 5, 1969, Ser. No. 796,686
Int. Cl. H01c 9/02

U.S. Cl. 338—170

7 Claims

A variable resistor providing an integral assembly for dual operation comprising a pair of arcuate resistance track elements in axially spaced, face-to-face relationship and having interposed therebetween a single insulating rotor or brush carrier including oppositely facing cavities, each cavity being recessed relative to a central plane and adapted to in-



contact with the respective resistance elements, as well as individual terminal assemblies for each of the resistance elements.


3,579,170 MODULAR ELECTRICAL CONNECTOR ASSEMBLY

Bruno Baumanis, River Forest, and Robert W. Sebastian, Villa Park, Ill., assignors to Molex Incorporated, Downers Grove, Ill.

Filed May 20, 1968, Ser. No. 730,350

U.S. Cl. 339—17

6 Claims



A modular electrical connector assembly for making connections to printed circuit boards comprising a plurality of male and female terminals. Each of the female terminals includes a circular cylindrically shaped barrel portion having a plurality of resilient contact members integrally formed from the wall thereof and facing inwardly toward the center thereof, and a pair of tab members for insertion into an aperture in a printed circuit board wherein they are bent to secure the terminal thereon. The male terminals each includes at least one circular cylindrical contact end for insertion into either open end of the barrel portion of a female terminal. The male terminals may be used separately or mounted in spaced relation in an insulating terminal block, and may also have a solderless wrap or other type of connector end for making external connection thereto.

3,579,171 SAFETY SOCKET


Arthur S. Woodward, Sylmar, Calif., assignor to Mattel, Inc., Hawthorne, Calif.

Filed Sept. 25, 1969, Ser. No. 860,973

U.S. Cl. 339—34

A socket for an ordinary incandescent lamp which prevents electrical shock if a child sticks his finger into it, comprising an aperture for receiving the base of a lamp and a shuttle which carries an operating arm and a pair of electrical

contacts. The shuttle is spring biased to a position wherein the arm lies within the aperture while the contacts are spaced from the aperture. However, when a lamp is screwed into the



aperture, it pushes the operating arm and shifts the shuttle so that the electrical contacts move to the aperture to contact the base of the lamp.

3,579,172

SOLDERLESS CONNECTOR ASSEMBLY


Marvin A. Clark, 7902 Woodley Ave., Van Nuys, Calif.

Filed June 23, 1969, Ser. No. 835,443

Int. Cl. H01r 9/08, 7/08

U.S. Cl. 339—97

15 Claims



A solderless connector having a main body of insulation formed with at least one pair of wells in side-by-side relation including a threaded well for a deeply threaded conductive member and a nonthreaded well snugly receiving a sheathed conductor with one side of the conductor positioned to intersect and traverse the thread crests of the threaded conductor. The threaded conductor may be shorter than the threaded well or it may have a protruding outer end usable as a terminal lug or as the male end of a service cord plug.

3,579,173

UNDERGROUND CABLE TAP CONNECTOR

Richard G. Greener, Poughkeepsie, N.Y., assignor to Fargo Mfg. Company, Inc., Poughkeepsie, N.Y.

Filed Dec. 23, 1969, Ser. No. 887,652

Int. Cl. H01r 7/04


U.S. Cl. 339—97R

7 Claims




A tap for connecting a line to a cable in an underground application without removing the insulation from the cable and which will provide a moistureproof seal at the point of connection of the tap to the cable.

3,579,174
LAMP-BASE ASSEMBLY
Marcellus N. Gilbert, Jr., Lynnfield, Mass., assignor to Syl-
vania Electric Products, Inc.
Filed June 24, 1968, Ser. No. 739,438
Int. Cl. H01r 13/60
U.S. Cl. 339—144 4 Claims



A lamp-base assembly for a tubular lamp bent into a U-shaped configuration in which the bases on the ends of the lamp are connected to one another by a rod.

3,579,175
ELECTRIC CIRCUIT ADAPTER MEMBER
Larry L. Shroyer, Kendallville, Ind., assignor to Lyall Elec-
tric, Inc., Albion, Ind.
Filed Aug. 13, 1969, Ser. No. 849,645
Int. Cl. H01r 13/50
U.S. Cl. 339—156 5 Claims




The invention relates to an adapter member having a body of electrical insulating material with elements of a male fitting projecting therefrom to permit the adapter to be plugged into a receptacle. The body has elements of a female fitting therein adapted for receiving the male fitting on the end of an electric cable. The female fitting portion of the body may receive a larger male plug than can be received in the receptacle, or a male plug of a different character than can be received in the receptacle. The male fitting portion and female fitting portion of the adapter preferably have their axes parallel and offset so that the female fitting portion can be disposed below the male fitting portion and thereby reduce the load on the receptacle.

3,579,176
MICROMINIATURE PRINTED CIRCUIT CONNECTOR
Michael Bokor, Huntington Beach, and Norbert L. Moulin,
Placentia, Calif., assignors to Hughes Aircraft Company,
Culver City, Calif.
Filed Mar. 3, 1969, Ser. No. 803,896
Int. Cl. H01r 13/64, 13/24
U.S. Cl. 339—176 3 Claims


A connector comprising a connector block with contact elements mounted therein for contacting the leads of a printed-circuit card. The contact elements have tabs for posi-

tioning and locking the contact elements in the connector block. The connector block includes an aperture for receiv-



ing a printed-circuit card and apertures for receiving the contact elements.

3,579,177
TERMINAL BOARD ELECTRICAL CONNECTOR
Robert E. Lawlor, Costa Mesa, Calif., assignor to Electro-
Clamp Corporation, Beverly Hills, Calif.
Continuation-in-part of application Ser. No. 702,411, Feb. 1,
1968, now Patent No. 3,477,060. This application Aug. 21,
1969, Ser. No. 852,060
Int. Cl. H01r 7/06
U.S. Cl. 339—198 2 Claims




A plurality of connectors, mounted in transverse slots in a terminal board, provide connections between respective pairs of axially aligned conductor wires. Each connector is of resilient sheet metal, including a central web secured to the terminal board by a fastener, and spring jaws at each end, each having means for clamping a respective wire end.

ERRATUM

For Class 339—217 see:
Patent No. 3,579,283


3,579,178
ELECTRICAL TERMINAL AND HOUSING THEREFOR
Allen Edwin Travis, Harrisburg, Pa., assignor to AMP Incor-
porated, Harrisburg, Pa.
Filed Dec. 4, 1969, Ser. No. 882,069
Int. Cl. H01r 9/08
U.S. Cl. 339—221 3 Claims



The disclosure relates to terminals for terminating the lead ends of a coil winding and includes provisions for securing


the terminals within apertures located in flanges integral with a coil bobbin with a portion of the terminals extending from the flange for plugging into mating receptacles.

3,579,179
FUSE CONNECTORS
Daniel Dumeige, Pontoise, France, assignor to AMP de
France, Pontoise, France
Filed Sept. 23, 1968, Ser. No. 761,473
Claims priority, application France, Sept. 27, 1967, 122,483
Int. Cl. H01r 11/22; H01h 85/22
U.S. Cl. 339—258 5 Claims



A fuse connector has a fuse contact formed from sheet metal with a body having an apertured extension, a resilient tongue in the aperture engaging an end of a fuse cartridge, side portions along the aperture embracing sides of the cartridge, and a bar joining the side portions serves to limit deflection of the tongue. A housing houses the fuse connectors to provide a connector assembly and it has hinged cover means for access to the fuse; commoning strips may be employed to connect the fuse connectors with other selected connectors of the connector assembly.

3,579,180
BEAM INTERPOLATING SYSTEM
Fausto V. Taddeo, Anaheim, Calif., assignor to Hughes Air-
craft Company, Culver City, Calif.
Filed Aug. 6, 1965, Ser. No. 477,682
Int. Cl. G01s 9/66
U.S. Cl. 340—3 14 Claims



CLAIM 1. In a sonar receiving system including means for effectively forming a plurality of receiving beams, each beam representable by a composite signal comprising signals received from another azimuth range the effective centerline of each beam having an azimuth in the center of said azimuth range, said sonar receiving system further including processing and computing means for processing each composite signal to detect the range of a target having an azimuth within the azimuth range of one of said beams, an improved system for interpolating the composite signal in which a target has been detected to resolve the azimuth of the target with respect to the azimuth of the centerline of said beam comprising: means for splitting a composite signal representative of a receiving beam in which a target has been detected into a pair of signals representative of a pair of beams which are parallel to said centerline and equidistantly disposed with respect thereto; a pair of multibit delay lines, coupled to receive said pair of signals; a plurality of analog storing units, each unit, corresponding to a different azimuth deviation with respect to the azimuth of said centerline, being coupled to two bits of said pair of delay lines; means for integrating in each of said storing units analog signals as a function of the phase correlation of signals

in two different bits of said pair of delay means, the two bits having signals exhibiting a maximum phase correlation being related to the azimuth deviation of said target from the azimuth of said centerline; means for scanning said plurality of storing units to detect the unit coupled to the two bits having signals which exhibit a maximum of phase correlation; and means for providing as a function of the detected unit an output signal which indicates the azimuth deviation of the target from the azimuth of said centerline.

3,579,181


SONAR RANGING SYSTEM FOR LOCATING SUBMERGED OBJECTS

Frank Massa, Cohasset, Mass., assignor to Massa Division Dynamics Corporation of America, Hingham, Mass.
Filed May 14, 1969, Ser. No. 824,407

Int. Cl. G01s 9/66

U.S. Cl. 340-3-R

9 Claims



A pair of narrow-beam directional transducers are mechanically joined together to radiate sonic energy in angular directions which are fixed with respect to each other. Electrical switching means cause the individual transducers to sequentially radiate bursts of sonic energy. Each of the transducers picks up the reflected sonic energy, and electronic means ascertains the azimuth of the object reflecting the energy, responsive to the relative strength of the signals picked up by the two transducers.

3,579,182


ANCHOR DRAGGING ALARM CONTROL BASED ON ANCHOR INCLINATION

Leonard Schneider, Beaver Brook Road, Lyme, Conn.
Filed Mar. 19, 1969, Ser. No. 808,487

Int. Cl. G08g 3/00

U.S. Cl. 340-29

9 Claims



An inclination-sensitive switch is operatively secured to a part of an anchor. The switch is open when the part is oriented such that the anchor grabs the bottom. When the orientation of the anchor part exceeds the horizontal by a predetermined value, corresponding to that orientation when the anchor is freed from the bottom, that switch is closed to actuate an alarm.

3,579,183 SIGNALLING DEVICE TO PREVENT LEAVING A KEY IN A LOCK

Paul Lipschutz, Croissy sur Seine (Yvelines), France, assignor to Societe d'Exploitation des Brevets Neiman S. A., Neuilly-Seine, France


Filed July 25, 1968, Ser. No. 747,670

Claims priority, application France, Oct. 6, 1967, 123,557

Int. Cl. B60q 1/26

U.S. Cl. 340-52

8 Claims



A signalling device to prevent leaving a key in a lock. The device includes a lock which has a number of different positions and a key coacting with the lock to displace it between these positions. An electromechanical means coacts with the key and lock to give a warning signal when the key places the lock in at least one of its positions, such as the position which the lock has when the key is introduced into and removed from the lock. The device is particularly suited for use in connection with ignition switches of vehicles, and the signal which is provided can either be visible, audible, or vibratory so as to be felt by the fingers of the operator.

3,579,184


PORTABLE EXTENDABLE SIGNAL LIGHT PLATFORM

Robert J. Forestal, Indianapolis, Ind., assignor to Dura Corporation, Southfield, Mich.
Filed Apr. 11, 1969, Ser. No. 815,301

Int. Cl. G08b 5/36, 3/00

U.S. Cl. 340-137

12 Claims



A platform for carrying emergency signals having a lazy-tong structure attached to its underside. Said structure is actuable by an electric motor to raise and lower the platform to and from an extended position. The platform serves as a cover for a cabinet which houses the motor and the retracted lazy-tong structure, said cabinet being mountable on the roof of an emergency vehicle.

3,579,185 METHOD AND APPARATUS FOR CHECKING A DATA TRANSFER OPERATION

Wilhelm Spruth, Sindelfingen, Germany, assignor to International Business Machines Corporation, Armonk, N.Y.


Filed Sept. 20, 1968, Ser. No. 761,186

Claims priority, application Germany, Sept. 27, 1967, P1549484.5

Int. Cl. H04i 1/10

U.S. Cl. 340-146.1

12 Claims



The accuracy of a data transfer operation, particularly one which involves loading a micro program into an alterable control storage device for use in a data processing system, is verified by deriving a check number from the transferred data and comparing the desired check number with a predetermined check number known to be correct. A variety of concepts may be used to obtain the derived check number such as successive logical Exclusive OR operations on transferred blocks of data or selected portions of the blocks.

3,579,186

PERSONAL IDENTIFICATION METHOD AND APPARATUS


Robert R. Johnson, Franklin, and Richard L. Dunham, Bloomfield Hills, Mich., assignors to Burroughs Corporation, Detroit, Mich.

Filed June 25, 1968, Ser. No. 739,803

Int. Cl. G06k 5/00

U.S. Cl. 340-146.3

18 Claims



A method and apparatus for positively determining whether an individual is a member of a predetermined group based on unique repeatable characteristics of an electrical waveform generated by a force-responsive transducer whenever the person writes his name or other mark. In accordance with the preferred embodiment of the invention disclosed herein, positive identification of a person as being an authorized member of a predetermined group is made by an apparatus which compares prerecorded authorized signature characterizing information with an electrical waveform generated when the person signs his signature. The comparison may for example comprise a cross or autocorrelation technique in which the identifying apparatus determines

whether the waveform generated by the person in signing his signature correlates within a predetermined degree with the previously recorded signature identifying information.

3,579,187

MUSIC RESPONSIVE LIGHT POWER CURRENT SWITCHING DEVICE


Robert L. Knott, 10406 Leolang Ave., Sunland, Calif., and Donald H. Hadel, 7424 Forbes Ave., Van Nuys, Calif.

Filed Sept. 26, 1967, Ser. No. 670,599

Int. Cl. G08b 5/22

U.S. Cl. 340-148

10 Claims



A music responsive light switching device comprising a music signal pickup which is connected to a control means which regulates the output of a power signal. The regulated power signal is applied to an electrical socket receptacle into which a conventional lamp is electrically plugged. The lamp can then be turned on and off in accordance with the characteristic rhythm of the music.

3,579,188

AUTOMATIC TICKET GATE

Keisuke Osaki, Kyoto, Japan, assignor to Omron Tateisi Electronics Co., Kyoto, Japan


Filed Feb. 5, 1968, Ser. No. 703,074

Claims priority, application Japan, Feb. 6, 1967, 42-7532

Int. Cl. G07f 7/00

U.S. Cl. 340-149

12 Claims



This invention comprises an automatic ticket gate which permits a passenger to pass therethrough only when the ticket he inserted into the slot of the gate for examination of its validity has been recognized as valid. A passenger is prevented from passing through until the ticket is removed from the slot in the gate, even when the ticket is recognized as valid.

3,579,189

COUPLING AND DRIVING CIRCUIT FOR MATRIX ARRAY

Paul K. Weimer, Princeton, N.J., assignor to RCA Corporation

Filed Dec. 13, 1968, Ser. No. 783,591


Int. Cl. H04q 3/00

U.S. Cl. 340-166

7 Claims

A coupling circuit comprising N stages connected in parallel between two conductors. Each stage comprises the con-

duction paths, in series, of two field effect transistors and an output terminal at the connection of the two paths. The output terminals are connected to the respective rows of an array of light sensing circuits. One transistor of one stage is turned on to connect one row of circuits through one con-



ductor to an output circuit to permit the circuits of that row to be read out, in sequence. Concurrently, the other transistor of the following stage is turned on to connect the following row of circuits through the second conductor to ground to permit the circuits of the following row to be precharged. The process is continued until all rows of the matrix are successively precharged and read out.

3,579,190


AUTOMATIC ALARM DETECTOR

Ernest C. Karras, Chicago, Ill., assignor to International Telephone and Telegraph Corporation, New York, N.Y.
Filed May 5, 1967, Ser. No. 636,446

Int. Cl. H04q 9/00

U.S. Cl. 340-167

4 Claims



A system is provided for unattended monitoring of international distress signals. The system employs an RF section which responds to all the signals in the frequency range of interest. The RF signals are fed through two analog-to-digital translators; one of which supplies a control signal to automatic gain control equipment to control amplification in the RF section and the other of which supplies DC pulses according to the intelligence in the original RF signals. The DC pulses are employed by logic circuits which provide an output signal if (1) at least 4 consecutive pulses are present, (2) the pulses are of duration between 3.5 seconds and 6 seconds, and (3) the pulses are separated by time intervals of between 10 milliseconds and 1.5 seconds duration.


3,579,191
NETWORK USING ADAPTIVE ELEMENTS
John Hugh Andreae, Christchurch, New Zealand; Brian Ronald Gaines, Cambridge, and Peter White, Bishop's Stortford, England, assignors to International Standard Electric Corporation

Filed Oct. 27, 1967, Ser. No. 678,589
Claims priority, application Great Britain, Oct. 31, 1966, 48616/66

Int. Cl. G06f 15/18, 15/56

U.S. Cl. 340-172.5

10 Claims



A communication network is provided using information storage control means for selecting a direct path from calling to called portions of the network. The network contains nodes and links therebetween. Each of the links has a switch controlled by an adaptive element therein. The adaptive element includes means for controlling the probability that a signal which emanates from the node traverses the link containing the adaptive element. Means operated in cooperation with the adaptive element are further provided so that any node which receives and passes on a signal is inhibited from receiving a further signal without first being reset.

3,579,192

DATA PROCESSING MACHINE


David Rasche, Bloomfield Hills, Mich.; Bernardo N. Levy, Livingston, N.J.; Bruce L. Ayres, Southfield; Hoy Ying Chang, Westland; Cornelius C. Perkins, and William W. Phillips, Birmingham, Mich., assignors to Burroughs Corporation, Detroit, Mich.

Filed Nov. 2, 1967, Ser. No. 680,184

Int. Cl. G06f 9/16

U.S. Cl. 340-172.5

23 Claims




An improved digital computer having a limited number of hardware elements which can be used to perform varied logical processes on data under the control of macroinstructions, each macroinstruction being implemented through a series of stored microinstructions forming a stored microprogram, each microinstruction corresponding to a control signal for actuating a hardware element in the computer, a series of said microinstructions being used to implement the hardware elements in varied sequences in order to perform different logical processes.

3,579,193
EDITING AND REVISION SYSTEM
Donald R. Bernier, Lake Orion, Mich., assignor to Intercontinental Systems, Inc., Los Angeles, Calif.
Filed May 20, 1968, Ser. No. 730,477

Int. Cl. G06f 3/00

U.S. Cl. 340-172.5

46 Claims



An electronic system for editing and controlling the format of information reproduced on a sheet of paper or other recording device from an automatic input system. The edit control system may be divided into two of the parts, the first of which is the edit control portion and the second is the margin control portion. The edit control portion enables the user to automatically stop the input device after a plurality of preselected information groups have been sensed, as for example a character, a word, a line, a sentence, or a paragraph. The particular group to stop the system is selected by actuating the desired mode switch. This portion of the system may be operated in any one of the print, nonprint or skip modes and the operator may manually enter information onto the recording device after the the automatic input system has been stopped by the edit control. In this way corrections may be easily entered onto the recording device and the information input device may be corrected.

The margin control provides different degrees of control, designated herein as the margin control, the automatic edit control and the tab control modes of operation. The margin control mode of operation controls the right-hand margin of the output printer according to the preset margin stop to insure that information is not printed on the paper beyond a preselected extension of the margin stop, irrespective of the length of the information group being recorded. This preselected extension is designated the right-hand margin zone and is adapted to cause preselected automatic operations of the automatic input device. The automatic edit mode is utilized to specifically control the data printed in the right-hand margin zone to permit the operator to manually control the amount of data printed in the right-hand margin zone.

The tab control mode controls the left side margin or the number of tabs starting from the left-hand margin for a given data group. With the system in the margin and tab control modes, the system counts and stores the number of tabs on the first line of the data group, and generates the same number of tabs after a carrier return is acted upon. This stored number of tabs is skipped from the reader after the first line in the data group.


3,579,194
PROCESS FOR DETERMINING THE SIMPLE CYCLES OF A FINITE DIRECTED GRAPH
Herbert B. Weinblatt, Cambridge, Mass., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed Sept. 4, 1968, Ser. No. 757,315

Int. Cl. G06f 7/00

U.S. Cl. 340-172.5

8 Claims



A machine process based on an algorithm for finding the simple cycles of a finite directed graph wherein each arc of the graph is examined once and only once. Simple cycles are found either when the path of the graph being examined is found to be cyclic or when parts of previously found cycles can be combined with a portion of the path then being examined to form cycles. A general purpose computer program for implementing the algorithm is described.

3,579,195


DATA SYSTEM INCORPORATING METHOD AND APPARATUS FOR REFERENCING MEDIA LOCATIONS
T. Milton Hallmark, and John M. Woodward, Lexington, Ky., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Nov. 5, 1968, Ser. No. 773,471

Int. Cl. G06f 13/04

U.S. Cl. 340-172.5

50 Claims



The invention concerns a data processing system that includes methods and apparatus for establishing accurate

referencing of data locations on a storage media, such as a magnetic tape record media. The system includes a central processor interconnected with a magnetic tape unit having character registers therein and normally operable under command from the processor to read a tape media at relatively high speeds, the data so derived being supplied through the registers to the processor for additional processing. The magnetic tape unit drive is coupled to a disc and photodetection means that supplies coded indications of data locations on the media. The tape unit is operable in a forward direction upon receiving a Read command from the processor and operable in a reverse direction upon receiving a Write-Backspace command, the latter command establishing a pseudowrite operation. In the event the processor does not accept the data characters, or changes commands, or detects an error, provision is made for an overrun operation. During this operation, the last character location not transferred is accurately referenced by counting means while the media is brought to a stop, repositioned in the opposite direction to a point sufficiently removed to insure sufficient acceleration for accurate data reading, and again started in the selected direction during which the overrun occurred. The system inherently provides insurance against mechanical jitter or other mechanical inconsistencies. The system combines counting of character locations on the media with a direction memory to insure that access of characters is accurately maintained.

3,579,196

DATA STORAGE AND DISPLAY SYSTEM


Roland S. Gregg, Jr.; Arnold S. Danberg, and Kenneth N. Larson, Canoga Park, Calif., assignors to The Bunker-Ramo Corporation, Canoga Park, Calif.

Filed Feb. 14, 1969, Ser. No. 799,274

Int. Cl. G11b 13/00

U.S. Cl. 340—172.5

14 Claims



A data storage and display system is provided with a control feature for selectively displaying stored message formats having fields into which data is to be entered by an operator. The feature includes means for insuring that the data entered into each field is of the numeric or alphabetic type if either has been specified on a character-by-character basis. If the operator attempts to enter any other type of character for a given specified character, an error is indicated and a correct character must be entered before proceeding to the next character in the same or different field. There is also provision for determining whether entries in all fields have been completed before the message format can be transferred to a file storage and control unit.

3,579,197

APPARATUS FOR PROGRAMMABLE CONTROL OF ELECTROMECHANICAL DEVICES

Gary N. Stapleford, Nashua, N.H., assignor to Sanders Associates, Inc., Nashua, N.H.

Filed Feb. 28, 1969, Ser. No. 803,371


Int. Cl. G06f 9/00

U.S. Cl. 340—172.5

35 Claims

Instructions having a simple format are used to control several classes of electromechanical devices such as slide projectors, tape recorders, movie projectors, X-Y positioning

devices, etc. The instructions are stored in a recirculating memory and are monitored by a main controller. The main



controller is coupled to one or more subcontrollers, each subcontroller being used to control one of the class devices. When the main controller is activated, an instruction is enabled into a designated subcontroller by means of the main controller. The instruction is then executed by the subcontroller. After execution, the apparatus is recycled by a signal from either of the subcontrollers. In addition, more than one subcontroller may be executing instruction words simultaneously, thereby allowing two or more different class devices to be operating simultaneously. Furthermore, the apparatus may be used in conjunction with a display system, thereby allowing display of text associated with an instruction simultaneously with the execution of the instruction.

3,579,198

MICROPROGRAMMED WIRED LOGIC MEMORY


John A. Giunta, Long Branch, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed Mar. 28, 1969, Ser. No. 811,440

Int. Cl. G06f 9/14

U.S. Cl. 340—172.5

11 Claims



A microprogrammed logic system containing a crossbar switch read-only-store is arranged to control small electromechanical switching networks. The crossbar switch has a discrete voltage potential on each crosspoint representing, in binary format, either a "0" or a "1". Each horizontal row of the switch corresponds to the memory address of one instruction and upon selection enables the operating of a group of hold magnets thereby closing a predetermined number of crosspoints. Upon crosspoint closure, an instruction, containing as many binary bits as there are closed crosspoints, is available for use by the microprogrammed logic system.

3,579,199

METHOD AND APPARATUS FOR FAULT TESTING A DIGITAL COMPUTER MEMORY


Robert A. Anderson; Alfred H. Faulkner, Santa Barbara, Calif., and Edwin L. Hughes, Brookfield, Wis., assignors to General Motors Corporation, Detroit, Mich.

Filed Feb. 3, 1969, Ser. No. 795,938

Int. Cl. G06f 11/04

U.S. Cl. 340—172.5

8 Claims



A digital computer memory is interrogated so as to test its operation. A digital word generator addresses the computer memory with a plurality of test address words identical to a plurality of test data words stored within word storage locations accessed by the test address words. The data words collectively include all coefficients of all powers of the radix of the numerical address code utilized by the digital computer. A digital word comparator detects any noncorrespondence between the test data words retrieved from the accessed word storage locations and the test address words thereby to indicate the presence of a fault within the computer memory.

3,579,200

DATA PROCESSING SYSTEM


Robert H. Davis, Raleigh, and Jerry S. Harris, Cary, N.C., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed July 30, 1969, Ser. No. 846,011

Int. Cl. G06f 11/08; H04I 1/00

U.S. Cl. 340—172.5

45 Claims



A data processing system including a plurality of terminals connected to a transmission medium for sending and receiving data and control signals between terminals is provided, and each terminal includes a master control connected by bus means having data lines and control lines to a plurality of satellite controls and input-output devices. A first parity checking device checks the parity of the signals on the control lines from each satellite to the master control, and a second parity checking device checks the parity of the signals on the control lines from the master control to the satellite controls. Even or odd parity may be used, but odd parity is preferred. Each satellite control includes a plurality of circuits interconnected to perform the control function of such

satellite control, and each one of the plurality of circuits has an output line connected to an odd number of other such circuits, whereby a malfunction in any one of said plurality of circuits affects an odd number of control lines from such satellite control which thereby forces the first parity checking device to detect a malfunction. Each satellite control, for the odd parity case, supplies a control signal on a single given control line when it is not active, whereby the first parity checking device checks the status of each satellite control during both the active and the inactive states.

3,579,201

METHOD OF PERFORMING DIGITAL COMPUTATIONS USING MULTIPURPOSE INTEGRATED CIRCUITS AND APPARATUS THEREFOR


Frank J. Langley, Carlisle, Mass., assignor to Raytheon Company, Lexington, Mass.

Filed Sept. 29, 1969, Ser. No. 861,750

Int. Cl. G06f 1/00

U.S. Cl. 340—172.5

5 Claims



A digital computer, exemplifying a method of organizing and controlling the elements of a general or special purpose computer, incorporating identical multipurpose integrated circuits in the control and/or arithmetic elements, each one of such circuits being responsive to the combination of commonly applied clock pulses and coded function signals and a unique enable signal. With such an arrangement, a basic design of such control and/or arithmetic elements may be changed to expand word length, memory capacity or instruction repertoire by connecting similar multipurpose integrated circuits to existing ones as required.

3,579,202

ELECTROCHEMICAL INHIBIT GATE


Robert M. Stewart, Encino, Calif., assignor to Aerojet-General Corporation, El Monte, Calif.

Filed Oct. 2, 1967, Ser. No. 673,252

Int. Cl. G11c 13/02

U.S. Cl. 340—173CH

7 Claims



An inhibit gate for data processing systems utilizing electrochemical waves of polarization as the basic signalling mechanism employing a pair of electrodes immersed in an electrolyte is disclosed. The inhibit gate employs preferably

iron and gold as the active materials in an electrolyte of nitric acid. Inhibit operation is achieved by the particular composition, size and placement of two electrodes. In one form, the inhibit gate exhibits adaptive properties.

3,579,203

RECIRCULATING BUFFER MEMORY


Michael M. Malmer, Jr., Livonia, Mich., assignor to Burroughs Corporation, Detroit, Mich.

Filed Dec. 12, 1968, Ser. No. 783,252

Int. Cl. G11c 19/00, 21/00

U.S. Cl. 340-173RC

4 Claims



The disclosure embodies a dynamic, first-in-first-out buffer memory and includes means for selectively and sequentially recirculating and advancing the relative positions of the binary encoded data therein.

3,579,204

VARIABLE CONDUCTION THRESHOLD TRANSISTOR MEMORY CIRCUIT INSENSITIVE TO THRESHOLD DEVIATIONS


Andrew James Lincoln, Concord, Mass., assignor to Sperry Rand Corporation

Filed Mar. 24, 1969, Ser. No. 809,899

Int. Cl. G11c 11/40

U.S. Cl. 340-173

5 Claims



A memory circuit for application in a computer memory for storing a binary valued digit. The circuit comprises two insulated gate field effect transistors characterized by electrically controllable conduction thresholds established by potentials applied between the respective gate electrodes and substrates. A binary digit is stored by establishing a difference in threshold between the two transistors and is read by sensing the difference in current flow therebetween in

response to an interrogation potential applied to the gate electrodes thereof. The binary value ONE or ZERO is stored by establishing a higher threshold for one transistor with respect to the other or for the other transistor with respect to the one.

3,579,205

PULSE COUNTING DEVICE WITH MEMORY

Takashi Aga, Akashi-shi, and Masami Yamanaka, Miki-shi, Japan, assignors to Yamato Scale Company, Limited, Akashi-shi, Japan


Filed Sept. 5, 1969, Ser. No. 855,565

Claims priority, application Japan, Nov. 21, 1968, 43/85,415

Int. Cl. G11c 13/04

U.S. Cl. 340-173R

5 Claims



Pulse counting circuit for measuring devices such as scales and the like wherein pulses are produced by motion of the measuring device and fed to a memory element. The memory element produces a second set of pulses which are compared in phase with the original pulses. The phase difference information and pulse count information are used to produce addition and subtraction instruction signals which signals are in turn used to produce a count confirming signal which is fed to the memory element to effect coordination of the original count stored therein with the count confirming signal.

3,579,206

LOW INDUCTANCE INTERCONNECTION OF CRYOELECTRIC MEMORY SYSTEM


Robert A. Grange, Belle Mead, N.J., assignor to RCA Corporation

Filed Dec. 16, 1968, Ser. No. 784,019

Int. Cl. G11c 5/06; H05k 7/06

U.S. Cl. 340-173.1

9 Claims



A length of flexible insulating material such as Mylar or Kapton having parallel conductors on one surface and including a magnetic field shield insulated from the conductors. The parallel conductors are connected at one end to lines at one edge of one cryoelectric memory plane and at the other end either to lines at the corresponding edge of the next adjacent plane, or to a terminal bar whose lines and shield are similar to that of the memory plane. The adjacent plane, in this case, is also connected to the terminal bar but via a second connector such as described. The shield comprises side-by-side discrete conductive sections insulated

from one another, each section registering with, that is, lying under (or over) a pair of conductors. Each adjacent pair of conductors is driven in such manner that one carries current in one direction and the other "simultaneously" carries an equal amount of current in the opposite direction.

3,579,207

LOAD SEQUENCER CONTROLLER


Peter G. Bartlett, Bettendorf, Iowa, and Joseph E. Meschi, Lyons, Ill., assignors to Gulf & Western Industries, New York, N.Y.

Filed Nov. 14, 1967, Ser. No. 682,814

Int. Cl. G11c 11/22

U.S. Cl. 340-173.2

31 Claims



A load sequencer controller is disclosed herein which serves to sequentially allocate and time a plurality of load intervals. The controller includes a plurality of interval time storage memories, each corresponding with an associated load interval to be timed. Each of the memories includes a plurality of electrically alterable and interrogatable bistable memory means which serve to store binary information. The weighted binary content of each memory is a decimal number representative of a desired time duration for an associated load interval. An interrogation circuit serves to sequentially apply interrogation signals to the memories so that when any one memory is interrogated the output of that memory provides a pattern of binary signals. An actuating circuit receives pulses from a source of equi-time-spaced pulses and serves to actuate the interrogation circuit each time the decimal number of the received pulses is equal to the decimal weight of the pattern of binary signals of the memory last interrogated.

3,579,208

CERAMIC MEMORY AMPLIFIER


Peter G. Bartlett, Davenport, Iowa, assignor to Gulf & Western Industries, New York, N.Y.

Filed Feb. 28, 1969, Ser. No. 812,521

Int. Cl. G11c 9/02

U.S. Cl. 340-173.2

9 Claims



There is disclosed herein a ceramic memory system including a ceramic memory matrix comprised of a plurality of

ceramic memory devices each having a first and a second surface respectively connected to a plurality of electrically conductive bit lines and a common line. The bit lines of the ceramic memory device are connected in common to an amplifier having parameters such that when one of the ceramic memory devices is interrogated, the output signal developed by the amplifier is not degraded by the impedance of the remaining ceramic memory devices.

3,579,209

HIGH SPEED CORE MEMORY SYSTEM


Thomas J. Gilligan, Palos Verdes Peninsula, and Arthur T. Nozaki, Torrance, Calif., assignors to Electronic Memories, Incorporated, Hawthorne, Calif.

Filed Sept. 6, 1968, Ser. No. 758,076

Int. Cl. G11c 5/02, 11/06

U.S. Cl. 340-174

17 Claims



A magnetic core memory system is disclosed comprising a rectangular array of magnetic cores. A first plurality of independent wires thread cores along one axis and a second plurality of dependent wires thread cores along the other axis for coincident-current selection of cores to be switched. The second plurality of wires are current dependent in that the current through a selected wire is returned in the opposite direction through unselected wires in parallel. In that manner, a selected core may be overdriven with more than half-select current I_h in one of the first plurality of wires and half-select current I_h in one of the second plurality of wires. The unselected cores threaded by the overdriven wire receive a net current of I_h due to return current through unselected ones of the second plurality of wires.

3,579,210

MATRIX STORAGE DEVICE

Heinrich Eduard Van Bruck, and Theodoor Holtwijk, Emmasingel, Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Mar. 24, 1969, Ser. No. 809,704

Claims priority, application Netherlands, Apr. 10, 1968, 6,805,155


Int. Cl. G11c 7/04, 5/02, 11/06

U.S. Cl. 340-174

4 Claims

In order to reduce stray of the output voltage in reading information from a magnetic matrix store, the information is written as many times in the inverted state as in the noninverted state, on average, so that the heat dissipation on an

average is the same for all cores. The inverted or noninverted state of the written information is recorded by an auxiliary



core joined to each word, which core is read when the information of the word concerned is read.

3,579,211

READ-AFTER-WRITE VERIFICATION OF DATA ON MAGNETIC STORAGE MEDIUM


Raymond B. Larsen, Riverton, Wyo., assignor to Datel Corporation, Falls Church, Va.

Filed Oct. 11, 1968, Ser. No. 766,677

Int. Cl. G11b 5/44

U.S. Cl. 340—174.1

14 Claims



Verification of data recorded on a magnetic storage medium is accomplished by reversibly driving the medium past a common record/reproduce head in order to successively record and play back each character of information and to verify the data recorded by comparing the information played back with the input data supplied for recording.

3,579,212

A REPRODUCING HEAD IN A LIQUID MEDIUM


Andrew Gabor, Bedford, Mass., assignor to Honeywell, Inc., Minneapolis, Minn.

Filed Mar. 5, 1968, Ser. No. 710,506

Int. Cl. G11b 5/60

U.S. Cl. 340—174.1E

6 Claims



High density storage magnetic recording systems are described in which the reproducing transducers must be posi-

tioned in accurately maintained close proximity to the surface of the recording medium. Both transducers and recording medium are immersed in a liquid so that relative motion between the recording surface and the transducers develops a liquid film of controlled thickness for maintaining uniform close spacing.

3,579,213

MAGNETIC HEAD ACCESSING MECHANISM UTILIZING SPRING BIAS


Roy A. Applequist, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 17, 1968, Ser. No. 722,007

Int. Cl. G11b 5/60

U.S. Cl. 340—174.1E

4 Claims



A magnetic head support assembly, particularly useful for noncontact recording, includes a head support arm formed with a spring-loaded portion, and incorporates a ramp that cooperates with a stationary cam to effectuate proper loading of the head to a magnetic record surface. The support arm may be actuated bidirectionally, so that the magnetic transducer is precisely positioned at a desired track and properly spaced from the surface of the record medium or disc during record and playback, or retracted to a rest position.

3,579,214

MULTICHANNEL MAGNETIC HEAD WITH COMMON LEG


Erik R. Solyst, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed June 17, 1968, Ser. No. 737,759

Int. Cl. G11b 5/28

U.S. Cl. 340—174.1F

1 Claim



A read-write head assembly incorporates multiple transducing elements in an integral ferromagnetic structure, all elements being jointed to a common ferromagnetic leg to complete the magnetic circuit. The common leg serves as an air bearing slider for noncontact recording.

3,579,215

METHOD AND APPARATUS FOR CONDUCTING A SIGNAL

Denis R. Brackett, 3313 Croft Drive, St. Anthony Village, Minn.

Filed Sept. 26, 1966, Ser. No. 581,858


Int. Cl. G08c 19/48

U.S. Cl. 340—198

6 Claims

A cablelike device designated as a vector conduit comprised of a plurality of rigid sections coupled together at articulating joints permitting relative angular movement therebetween is utilized to transmit a directional signal from a signal generator on a first space platform, such as an air-

craft fuselage, to a signal receiver located on a second space platform which is not rigidly connected to the first platform,



such as a wing tip of the aircraft. A mechanical device, such as a rocket launcher, on the aircraft wing tip is oriented on the desired directional path by the signal receiver in response to a signal transmitted through the vector conduit from a sighting device on the first space platform. An electromechanical device operatively associated with each of the articulating joints in the vector conduit is utilized to measure or sense the angular displacement between the rigid sections of the vector conduit and to make a corresponding correction in the directional signal, thereby compensating for angular deviation between the first and second space platforms to insure that the signal receiver properly positions and orients the mechanical device, i.e., the rocket launcher, in the desired directional path.

3,579,216


PARTICLE DETECTOR

Alfred W. Vasei, 222 Linwood St., Abington, Mass. 02351
Continuation of application Ser. No. 533,140, Mar. 10, 1966, now abandoned. This application July 8, 1969, Ser. No. 845,646

Int. Cl. G08b 17/10, 19/00

U.S. Cl. 340—237

2 Claims



A smoke detector in which a light for illuminating smoke particles also illuminates a photocell providing a circuit path to maintain an alarm actuating device in a deenergized condition, and means is provided responsive to the detection of smoke to illuminate a second photocell to cause energization of the alarm.

3,579,217

METHOD AND APPARATUS FOR DETECTING AND INDICATING MALFUNCTION OF A TABLETING MACHINE

Thomas J. Casey, Arlington Heights, and George F. Loeffler, Barrington Hills, Ill., assignors to Thomas Machinery Corporation, Hoffman Estates, Ill.

Filed June 10, 1968, Ser. No. 735,737


Int. Cl. G08b 21/00

U.S. Cl. 340—253

5 Claims

Method and means for monitoring a multistation tableting machine with respect to the forces applied by tablet-forming

punch means to tablets successively formed in and ejected from said machine which comprises continuously measuring



3,579,218

ATTITUDE ERROR DETECTION FLUID GAUGING SYSTEM WITHOUT CORRECTION


Arthur M. Forsythe, Jr., Shelburne, Vt., assignor to Simmonds Precision Products, Inc., Tarrytown, N.Y.

Filed Sept. 4, 1968, Ser. No. 757,375

Int. Cl. G08b 21/00

U.S. Cl. 340—253

5 Claims



An aircraft fuel gauging system which is coupled to a standard mass fuel gauge and accepts signals from the aircraft pitch and roll sensors to produce an output signal which indicates whether or not the mass fuel gauge can be accurately read. The output signal may be used to actuate a warning signal flag or a red light at the fuel indicators to signal the pilot that the indicator is unreliable and that the aircraft attitude must be changed to obtain an accurate fuel reading.

3,579,219

LEAKAGE-CURRENT DETECTOR

Bodo M. Wolframm, Claredon Hills, Ill., assignor to Sola Basic Industries, Inc., Milwaukee, Wis.

Filed Nov. 19, 1968, Ser. No. 776,893


Int. Cl. G08b 21/00

U.S. Cl. 340—255

11 Claims

A leakage current or fault detector for isolated power lines in which independent detection circuits each including identical R-C networks operate sequentially from each line to ground. Any fault is fed into a magnetic summing amplifier

which is of the fail-safe type and drives an indicating relay. The fault may be either capacitive or resistive, or both, and is switch (which may operate automatically if he is incapacitated) which, when actuated, causes the alarm




detected on either or both lines, including a symmetrical fault. The detection circuits may be sequentially sampled by electronically operated photosensitive devices.

3,579,220 ALARM SYSTEM

Louis A. Stevenson, Jr., Houston, Tex., assignor to "Automatic" Sprinkler Corporation of America
Filed Mar. 28, 1969, Ser. No. 811,515
Int. Cl. G08b 13/00

U.S. Cl. 340-258

16 Claims



An alarm system having a plurality of disturbance-detecting head means each such head including circuitry for evaluating the disturbance detected and for generating an output when the disturbances detected are alien to the area being monitored. A system circuit capable of assuming different distinct states interconnects the plurality of head means with an alarm. The system circuit changes from one of its states to another of its states in response to the generation of an output from any of the detection heads to thereby trigger the alarm. The alarm may also be triggered as a result of any tampering with the heads or the circuit or as a result of loss of power in the system.


3,579,221 ALARM SYSTEM

John Raymond Ashley, "Kyama" Frome Road, Radstock, Bath, Somerset, and Colin Grahame Douglas, "Stoneybroke" Watergates, Colerne, Wiltshire, England
Filed May 31, 1968, Ser. No. 733,692
Claims priority, application Great Britain, May 31, 1967, 25200/67
Int. Cl. G08b 29/00

U.S. Cl. 340-277

1 Claim

An alarm system for use in conjunction with a radio actuated location system in which a security guard or watchman carries a radio transmitter which transmits signals according to the location of the guard, the alarm system including circuitry to generate an alarm frequency, the guard having a




frequency to be transmitted (or cut off if it is normally being transmitted).

3,579,222 PORTABLE BURGLAR ALARM

Wilbern Marvin Freeman, 907 N.E. 111th St., Miami, Fla.
Filed Jan. 25, 1968, Ser. No. 700,534
Int. Cl. G08b 13/08, 13/00

U.S. Cl. 340-283

6 Claims



The burglar alarm is compact, self-contained and has no significant protrusions, but for a push rod which is pushed in flush with the case when the alarm is supported on its base or when the base is pushed against an object of value. The push rod engages a leaf spring-type switch maintaining it "open;" removal of force from the push rod allows the switch to extend the push rod and close actuating an alarm, for instance a buzzer and a light recessed in the top of the case. This will happen when the burglar alarm is tipped over or the object of value is moved from engagement with the push rod.

The foregoing abstract is not intended to be a comprehensive discussion of all of the principles, possible modes or applications of the invention disclosed in this document and should not be used to interpret the scope of the claims which appear at the end of this specification.

3,579,223 TRANSISTORIZED MONITORING CIRCUIT


Arthur B. McKaig, Bellevue, Wash. (P.O. Box 228, Belfair, Wash. 98528)
Filed June 25, 1968, Ser. No. 739,835
Int. Cl. G08b 21/00

U.S. Cl. 340-248

4 Claims

The invention consists of modifications and improvements to the monitoring circuit of U.S. Pat. No. 3,293,630. These changes increase the sensitivity and accuracy of the monitoring circuit by an improved interconnection with the monitored circuit, provide an adjustment to compensate for manufacturing tolerances in components, provide an adjustment for matching the monitoring circuit to the monitored

circuit, eliminate problems with alternating current waveshape in the monitored circuit, eliminate false indications




tions by effective use of time delay circuits and furnish more usable monitoring information by including a gating circuit.

3,579,224
CHARACTER GENERATOR APPARATUS
John R. Griffin, Portland, and Charles A. Forsberg, Tigard, Oreg., assignors to Tektronix, Inc., Beaverton, Oreg.
Filed Dec. 9, 1968, Ser. No. 782,396
Int. Cl. H01j 29/70

U.S. Cl. 340-324

11 Claims



A character generator apparatus provides deflection signals to a cathode-ray storage tube for causing the electron beam thereof to move through a fixed pattern of dots called a dot matrix. The prospective movement of the electron beam through the dot matrix is very rapid. Input translating means detect when a particular location in the dot matrix is reached at which an elemental portion of the character is to be written by the electron beam. At this time, the electron beam is slowed down and enabled so this elemental portion is displayed and stored by the cathode-ray tube.


3,579,225 LIGHT PROBE CIRCUIT FOR PERSISTENT SCREEN DISPLAY SYSTEM

Robert John Clark, Dorion, Quebec, Canada, assignor to RCA Corporation
Filed Oct. 15, 1969, Ser. No. 866,552
Int. Cl. G06f 3/14

U.S. Cl. 340-324A

8 Claims

The light sensed by a light "probe" or "pen" during each field displayed on a persistent screen causes a signal to be stored for a duration which is a fraction of the field time. The placing of the probe in a light sensing position causes a second signal of a duration at least equal to one field time to be stored and which starts at a time after the pen is placed in




signals produces an output pulse which may be employed to signal the computer associated with the light probe.

3,579,226
MULTIPOINT CONTROL SYSTEM
Robert J. Strehlow, Sunnyvale, Calif., assignor to Wehr Corporation, Milwaukee, Wis.
Filed Nov. 13, 1967, Ser. No. 682,123
Int. Cl. G08b 5/36

U.S. Cl. 340-339

10 Claims



A multipoint control system provides visual display of a message with a matrix of light sources arranged in columns and rows. An input tape is coded with the display information by blacking out certain squares of the tape format which is similar to the display format or punching holes in the tape. The tape is then passed over a column of photosensitive devices and the information transferred to silicon controlled rectifiers which drive triacs coupled to the light sources. A shift register provides for sequential activation of the respective display columns of the light sources. The coded format tape is indexed and synchronized with the activation of the light sources of the various columns.


3,579,227
DIGITAL-TO-ANALOG CONVERTER SYSTEM
James W. Appelgren, Highland Park, Ill., assignor to The Louis Allis Company, Milwaukee, Wis.
Filed May 17, 1968, Ser. No. 730,170
Int. Cl. H03k 13/04

U.S. Cl. 340-347

7 Claims

The D/A converter system includes a positive D/A converter and a negative D/A converter having common outputs connected to ground. Logic circuitry provided for each D/A

converter is responsive to a polarity control signal for disabling one D/A converter from producing an analog output



signal of one polarity while enabling the other D/A converter to produce an analog output signal of the other polarity in response to a digital input signal from a digital controller. Power supplies bias the positive and negative D/A converters to isolate the analog output signal generated by the enabled D/A converter from the disabled D/A converter.

3,579,228

ANALOG-TO-DIGITAL CONVERTER

Kenneth William Cattermole, Harlow, England, assignor to International Standard Electric Corporation, New York, N.Y.


Filed Jan. 26, 1968, Ser. No. 700,874

Claims priority, application Great Britain, Feb. 10, 1967, 6509/67

Int. Cl. H03k 13/17

U.S. Cl. 340-347

10 Claims



An equilibrium type coder comprising an array of multistable and weighted stages interconnected with each other and the analog input to provide an input signal to each stage including the analog signal and weighted functions of the output signal of each stage. The weights of each stage as provided by weighted interconnects, or different biasing of the stages are such that the array has a plurality of stable states each corresponding to a different amplitude of the analog signal. The digital representation of the analog signal is provided by the state of the stages when the array is in a stable state.

3,579,229

PRECISION SWITCHING NETWORK FOR A DIGITAL TO ANALOG CONVERTER

Robert W. Tripp, Tuckahoe, N.Y., assignor to Inductosyn Corporation, Carson City, Nev.

Filed Oct. 30, 1968, Ser. No. 771,748

Int. Cl. H03k 13/04

U.S. Cl. 340-347DA

9 Claims


A system for converting a digital number such as an angle into analog signals representing the sine and cosine of the angle including a plurality of network stages representing binary bits of 360°. A control activates certain stages whereby the sum of the corresponding bits represents the selected angle. The stages of major significance include inputs and trans-

formers for generating output signals to serve as inputs to the stages of minor significance, such output signals being computed by stages in tandem operating in accordance with equations 1 and 2, column 3 of U.S. Pat. No. 2,849,668. The stages of minor significance operate in accordance with the following equations 3 and 4 of the above patent:

$$\sin(a+b) = \tan b \cos a + \sin a \quad (3)$$

$$\cos(a+b) = \cos a - \tan b \sin a \quad (4)$$

In equation 3 the term "cos a" is the output of the last stage of major significance, the term "tan b" being a first transformer having a primary winding common to all of the stages of minor significance, the first transformer having a second-



ry winding individual to each stage of minor significance, the secondary windings connected in series, each secondary winding being activated by a transistor circuit, and the active secondary windings supplying an output to a second transformer. The first transformer has a turns ratio increasing its binary bit value by a certain factor and the second transformer decreases the output by the same factor whereby the signal proportional to "tan b cos a" in the secondary winding of the second transformer is restored to normal prior to being combined with the signal "sin a" from the stages of major significance to form the final sine output. A similar transformer and secondary winding arrangement is provided for the signal according to "tan b sin a" for equation 4 prior to algebraic summing with the term "cos a" from the stages of major significance to form the final cosine output.

3,579,230

DIGITAL TRANSDUCER AND MEMORY SYSTEM THEREFOR


James H. Casterlin, Binghamton, N.Y., assignor to Quantum Devices, Inc., Johnson City, N.Y.

Filed June 17, 1968, Ser. No. 737,714

Int. Cl. G08c 9/04

U.S. Cl. 340-347

6 Claims



A transducer for indicating the extent of rotation of a shaft in digital units consists of several intergearing rotating circuit closure devices coupled to the shaft, each representing a

decade in the numerical system. The closure devices operate, by magnetic attraction, reed switches connected to relay circuits. Each closing and subsequent opening of a circuit connected to the closure devices prepares the eventual actuation of a particular relay designating a digit in each decade. A holding circuit for each relay maintains closure of the relays energized at the time when the rotation of the closure device is momentarily stopped for interrogation of the transducer.

3,579,231

CODE TRANSLATION CIRCUITS


Pioter Bylanski, London, England, assignor to The General Electric and English Electric Companies Limited, London, England

Filed Sept. 17, 1968, Ser. No. 760,269

Int. Cl. H03k 13/17

U.S. Cl. 340-347

4 Claims



A P.C.M. coder using the Waldhauer principle (see U.S. Pat. No. 3,187,325), of incorporating a current-switching decision device in an amplifier feedback loop, in which each coding stage has only a single high-gain amplifier. In each such stage, the input analogue signal to the stage and a reference voltage are supplied to the amplifier and four diode rectifiers are connected in a bridge circuit in a feedback path across the amplifier. The amplifier of each stage supplies a digital signal representing the coding effected by that stage and the analogue output signal for passing onto the next stage is developed across a resistor which is connected across one diagonal of the bridge circuit.

3,579,232

NON-LINEAR DIGITAL TO ANALOG DECODER WITH A SMOOTH CHARACTERISTIC

Pierre Girard, Paris; Claude Paul Henri Lerouge, Maurepas, and Marc Andre Regnier, Aulnay-Sous-Bois, France, assignors to International Standard Electric Corporation, New York, N.Y.


Filed Apr. 23, 1969, Ser. No. 818,554

Claims priority, application France, Apr. 30, 1968, 150085

Int. Cl. H03k 13/04

U.S. Cl. 340-347

6 Claims



A digital to analog decoder or converter is disclosed. The decoder has a smooth nonlinear characteristic of the hyperbolic sine type. This smooth characteristic is contrasted to a nonlinear characteristic approximated by a plurality of straight line segments in the prior art. The decoder of this

case includes a register to store a 7-digit code to be decoded. A first decoder circuit decodes the last four digits of the 7-digit code. Two groups of current generators (a first selection circuit) responding to the output of the first decoder produce two currents. A bipolar inverter (a second selection circuit) responding to the first of the last four digits directs the two currents to a third selection circuit. The third selection circuit responds to the output of a second decoder to direct the two currents to the appropriate one of two ladder attenuators, the outputs of which produce the analog signal. The second decoder responds to the first three digits of the 7-digit code.

3,579,233

AMBIENT NOISE FREQUENCY RESPONSIVE AUDIBLE VEHICLE ALARM


Herbert A. Raschke, Greenbrae, Calif., assignor to E. D. Bulard Company, Sausalito, Calif.

Continuation-in-part of application Ser. No. 571,779, Aug. 11, 1966, now abandoned. This application Jan. 27, 1969, Ser. No. 813,786

Int. Cl. G08b 23/00

U.S. Cl. 340-384E

6 Claims



A vehicle alarm system which has an ambient noise sensor, an alarm signal generator, and a system responsive to the sensor for varying the output frequency of the generator so as to produce a warning signal that has a frequency other than the frequency of the ambient noise.

3,579,234

CHARACTER GENERATOR FOR RADAR DISPLAY

Takao Tsumura; Toshio Kaooka; Keisuke Suzuki; Yoshiaki Ueda, and Naoyoshi Oishi, Tokyo, Japan, assignors to Japan Radio Company, Limited, Tokyo, Japan


Filed May 14, 1969, Ser. No. 824,514

Claims priority, application Japan, May 15, 1968, 43/32655

Int. Cl. G01s 7/12, 7/122

U.S. Cl. 343-5

19 Claims



A character-generating system for use with a radar system wherein coded radial element signals and coded circular ele-

ment signals are generated in response to the trigger and heading signals, respectively, generated by the radar system. The coded radial and circular element signals are combined to form a plurality of pattern signals representing a plurality of characters. The pattern signals are then selected and combined with the video radar information to form a composite signal which is fed to the radar display.

3,579,235


COLLISION AVOIDANCE READOUT ON AIR TRAFFIC CONTROL RADAR BEACON SYSTEMS

Kenneth Luke Straub, Fort Lauderdale, and Wayne Gregory Shear, Pompano Beach, Fla., assignors to The Bendix Corporation

Filed June 18, 1969, Ser. No. 834,432
Int. Cl. G01s 9/56

U.S. Cl. 343-6.5

5 Claims



A system for transmitting collision avoidance maneuvering information together with conventional air traffic control information by the same aircraft transponder. The transponder includes gating apparatus for adding in a serial format both the maneuvering and the control information in order to transmit a single combined response to a single air traffic controller interrogation.

3,579,236

TEMPLATE FOR EVALUATING PHOTOGRAPHS OF DOPPLER RADAR SPEED MEASUREMENTS


Kurt Wilhelm Piechocki, Uster, Switzerland, assignor to Zellweger, Ltd., Uster, Switzerland

Filed Jan. 24, 1969, Ser. No. 793,685

Claims priority, application Switzerland, Feb. 28, 1968, 2915
Int. Cl. G01s 9/44

U.S. Cl. 343-8

9 Claims



A doppler radar vehicle speed measurement template is provided with a representation of the photograph zone intersecting with a horizontal line representing the horizon of the road and a vertical line representing the vertical plane of the optical axis of the camera. The template is laid over the photograph with the vertical and horizontal lines aligned with the center of the photograph and with either the vanishing point of the road or a point at the height of the camera to accurately locate the vehicle in the photograph zone.

3,579,237 METHOD AND APPARATUS FOR AZIMUTH BIAS ERROR CORRECTION OF SEQUENTIAL-OBSERVER DETECTORS


Richard D. Steingart, Dubendorf, Switzerland, and Richard D. Wilmot, Brea, Calif., assignors to Hughes Aircraft Company, Culver City, Calif.

Filed June 24, 1969, Ser. No. 836,010

Int. Cl. G01s 9/02

U.S. Cl. 343-10

22 Claims



A system is disclosed for the correction of azimuth bias error in sequential-observer detectors for surveillance radar systems which assume an average value of azimuth bias in declaring the leading and trailing edges of a target. After normal beam-splitting, the apparent azimuth of the target is corrected by subtracting the effect of half the sweeps that occurred without a video return while searching for the leading edge. Each such sweep has the effect of delaying declaration of a leading edge by one or two sweeps, depending on the pattern of video returns received.

3,579,238

AUTOMATIC POWER CONTROL OF A PULSE MODULATOR


Andrew V. Haeff, Washington, D.C., and Franklin H. Harris, Accokeek, Md.

Filed Feb. 20, 1971, Ser. No. 649,104

Int. Cl. G01s 7/42; H04k 3/00

U.S. Cl. 343-18E

7 Claims



In apparatus receiving periodic radiated pulses and transmitting other periodic radiated pulses responsively to said received pulses and in which the gain of the receiving means in said apparatus is subject to broad variation, means for controlling the output power of the transmitter in said system so that the transmitted pulses fed back through the receiving means do not exceed a selected amplitude, which comprises, a vacuum tube biased so as to be rendered conducting only by the received periodic pulses; a pulse generating means in-

initiated into operation for one pulse only when said vacuum tube is rendered conducting; diode clipping means substantially removing the received periodic pulses from the output of the receiving means and leaving substantially only the portion of the transmitted signal which is fed back through the receiving means; means rectifying the output of the clipping means to form a bias voltage; a variable gain amplifier receiving the output from the pulse generating means, means applying said bias voltage to said variable gain amplifier so as to decrease the gain thereof when the average amplitude of the output of the clipping means increases; rectifier means connected so as to produce a negative direct current potential from an alternating current input; capacitor means coupling the output of the amplifier to the latter rectifier means; a power supply providing a positive and a negative source of potential; a normally conducting cathode loaded vacuum tube having a grid connected across the power supply, the cathode load of said vacuum tube comprising two serially connected resistors, the latter rectifier means being connected so as to operate with reference to the potential of the junction of the two cathode resistors and so that its output is applied to the grid of the cathode loaded vacuum tube; and a vacuum tube having a grid connected in shunt across the power input to the transmitter, the grid of the shunting vacuum tube being connected to the junction of the two cathode resistors.

3,579,239

ANGULARLY SELECTIVE MONOPULSE RECEPTION


William O. Purcell, Jr., Maitland, and Walter D. Trippe, Orlando, Fla., assignors to Martin-Marietta Corporation, Middle River (Baltimore County), Md.

Filed July 13, 1965, Ser. No. 471,523

Int. Cl. G01s 9/22

U.S. Cl. 343-16SD

20 Claims



This invention relates to an angularly selective monopulse system for receiving desired pulse signals, having means for determining whether an incident pulse was received from within a desired angular range. If not so received, the pulse is rejected, but if it was so received, it is further processed and the information it provides is utilized for appropriately adjusting the center of the acceptance sector. This information may also be used for the physical steering of the vehicle or missile upon which it may be mounted.

3,579,240

SELECTIVE RADIO RECEIVER SYSTEM

Andrew F. Deming, Alliance, Ohio, assignor to Alliance Manufacturing Company, Inc.

Filed Apr. 30, 1968, Ser. No. 725,294


Int. Cl. H04b 1/00, 1/06, 7/20

U.S. Cl. 343-228


21 Claims

The disclosure shows a remotely controlled radio receiver circuit which may be used to control a garage door operator, for example, from a low-power remote transmitter. The signal emitted by the transmitter includes a carrier as modulated by a lower frequency, for example an audiofrequency, which signal is amplified in the receiver, detected and supplied to an audiofrequency resonant load and to a resistance load. These two loads are connected in opposition so that if the received signal is of the proper carrier frequency to be


amplified and passed through the first stages of the receiver and if the audiofrequency is of the proper preselected



in the dielectric where it covers the antenna. A plug of the dielectric material is coated around its rim with a metal and formed of a plurality of similar steel members which are mounted in a plane perpendicular to the mast. Within the



then fitted into the hole such that the metal coating extends the conducting surface of the antenna through the dielectric material. The metallic coating minimizes the possibility of surface wave excitation by confining the waves reflected by the dielectric-air interface to the chamber formed by the coating.



mast are cables and auxiliary electrical equipment. The radiating elements, the ground plane elements, and the mast are completely collapsible into a compact package.

3,579,243

WINDSHIELD ANTENNA SYSTEM


Richard T. Dickason, Birmingham, and John A. Richardson, Harper Woods, Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Aug. 11, 1969, Ser. No. 848,799

Int. Cl. H01q 1/32

U.S. Cl. 343-713

8 Claims



An improved windshield antenna system is described in which a pair of laminated glass sheets forming the windshield contains a pair of antenna wires adhered to the laminating interlayer. The wires have free ends which extend out beyond a cutout portion formed in one of the glass sheets. The free ends of the wires are terminated to an attaching area of a conductive terminal which terminal is received in the cutout portion of the glass sheet. An electrical lead is also connected to the conductive terminal at the attaching area. A nonconductive tab is affixed to one surface of the glass sheet away from the cutout portion of the one glass sheet. The tab holds the electrical lead in a relatively stable position with respect to the attaching area of the conductive terminal at which the lead is terminated to the antenna wires. A potting compound overlies the region of the termination of the antenna wires and the electrical lead to the attaching area of the conductive terminal.

3,579,244

COLLAPSIBLE ANTENNA EMPLOYING FLEXIBLE TAPE RADIATORS

Richard C. Dempsey, Chatsworth, and Francis E. Lind, Granada Hills, Calif., assignors to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Aug. 27, 1968, Ser. No. 755,563

Int. Cl. H01q 21/26, 15/20

U.S. Cl. 343-797

5 Claims

A plurality of radiating elements fabricated of flexible thin steel is secured to a telescoping mast. A ground plane is

3,579,245

METHOD OF TRANSFERRING LIQUID


James M. Berry, Princeton, N.J., assignor to Teletype Corporation, Skokie, Ill.

Filed Dec. 7, 1967, Ser. No. 688,947

Int. Cl. G01d 15/18

U.S. Cl. 346-1

9 Claims



An electrostatic printer has a nozzle from which the ink is issued with an accelerating electrode and an intermediate electrode placed between the nozzle and the platen or target. A high voltage potential difference is established between the nozzle and the target with an intermediate potential being applied to the accelerating and intermediate electrodes. A sufficient potential difference exists between the nozzle and the accelerating electrode to draw the ink from the nozzle into a fine stream, and a sinusoidally varying field is superimposed on the field between the nozzle and the accelerating electrode to establish a high frequency vibration in the electrostatically charged ink stream. Droplet formation then takes place in synchronism with the sinusoidally varying field in a region of a weak field between the accelerating and intermediate electrodes which are at the same or only slightly different potentials, with the size and spacing of the droplets being controlled by the frequency of the sinusoidally varying field. As a result, droplets of substantially uniform size, substantially uniformly spaced apart, are formed.

3,579,246

TIME SHARING RECORDER DRIVE CIRCUIT

Theodore Lauer Rhyne, Summit, N.J., and Karl F. McCready, San Pedro, Calif., assignors to Northrop Corporation, Beverly Hills, Calif.

Filed Mar. 4, 1969, Ser. No. 804,079


Int. Cl. G01d 9/00

U.S. Cl. 346-34

4 Claims

Navigational signals having pulse widths in accordance with navigational lines of position are fed to logical gating

circuitry, including a pair of AND gates and an OR gate, the outputs of the AND gates being fed to an OR gate. The AND



gates are alternately gated ON by means of a flip-flop, the OR gate output thus alternately including the signals fed to each of the AND gates. The output of the OR gate is utilized to control a switching circuit which controls the current to the magnetic drive coil of a chart recorder, the writing element of the recorder being successively deflected to positions indicative of the signals fed to each AND gate in accordance with the average current in the drive coil.

3,579,247

MULTISTYLUS PEN RECORDING SYSTEM

Kiyomi Minohara; Hiroshi Ishida, Nishinomiya; Tomoyoshi Miyata; Takeyoshi Takashima, Kobe, and Yoichi Umehara, Nishinomiya, Japan, assignors to Furuno Electric Company, Ltd., Minamitakaki-gu, Nagasaki, Japan


Filed July 14, 1969, Ser. No. 841,437

Claims priority, application Japan, July 15, 1968, Dec. 5, 1968, 43/50142; 43/89453

Int. Cl. G01d 5/247; G01s 7/60

U.S. Cl. 346-35

7 Claims



A multistylus pen recording system having a plurality of styli arranged transversely of and in contact with recording paper, means for generating a series of signal pulses which are applied in sequence to the styli for recording said pulses and means for producing a selectively variable high frequency signal to control the spacing of said pulses and thereby effect a variation in the magnification of the pattern recorded on the paper.

3,579,248

HORIZONTAL Z-FOLD RECORDER

Walter R. McGrath, Jr., Gloucester, Mass., assignor to Hewlett-Packard Company, Palo Alto, Calif.


Filed June 11, 1969, Ser. No. 832,241

Int. Cl. G01d 15/30

U.S. Cl. 346-76

12 Claims

A strip chart recording mechanism unfolds Z-folded paper from a supply stack and guides the paper past a recording station. The paper is then refolded and stacked in a Z manner. The mechanism operates to feed the paper horizontally with respect to a ground plane. The recording station includes two knife edges for engaging opposite surfaces of the



interacts the effect of the first knife edge on the Z-fold creases in the paper.

3,579,249

FEATURE COUNTER HAVING BETWEEN LIMITS AMPLITUDE AND/OR WIDTH DISCRIMINATION



Raymond D. Dewey, Bon Air; Robert S. Mapes, and Garth S. Jones, Richmond, Va., assignors to Reynolds Metals Company, Richmond, Va.

Continuation-in-part of application Ser. No. 767,614, Oct. 15, 1968. This application Aug. 8, 1969, Ser. No. 848,474

Int. Cl. G01n 15/02; H04n 7/18

U.S. Cl. 178-6

16 Claims



A specimen analyzer including a video camera for scanning a specimen and selectively counting features

thereof on the basis of grey level and size. The device may operate in several modes to count only features darker (or lighter) than a selected grey level, to count only features that are darker than a first grey level but lighter than a second grey level, to count only features wider than a selected width, to count only features wider than a first width but not as wide as a second width, or to count features that meet more than one of these tests. A variable electronic mask permits the operator to select any area of the specimen within the view of the camera for feature analysis without moving the specimen. Check spot pulses are generated for each feature counted and these may be displayed on a video motor superimposed on a video display of the specimen.

3,579,250

PRODUCTION OF LATENT IMAGES BY CURIE POINT RECORDING


Alfred M. Nelson, Redondo Beach, Calif., assignor to The Magnavox Company, Torrance, Calif.

Filed Jan. 5, 1967, Ser. No. 607,521

Int. Cl. H04n 5/76; G03g 19/00

U.S. Cl. 178-6.6

16 Claims



A latent magnetic image, positive or negative, is provided on a low Curie point storage carrier by providing concurrently radiation for a line raster and for pictorial information. Depending on the chosen intensity of the thermal radiation energy bias and information, the image will be positive or negative. The image is represented by a series of magnetic pole lines of alternating polarity and variable spacing.

3,579,251

VIDEO SIGNALLING PROCESSING APPARATUS WITH NOISE PROTECTION


Ralph E. Lovelace, North Reading, Mass., assignor to Sylvania Electric Products Inc.

Filed June 24, 1968, Ser. No. 739,323

Int. Cl. H04n 3/16

U.S. Cl. 178-7.3

13 Claims



Video signal-processing apparatus which amplifies the composite video signal from the video detector of a television receiver and charges a capacitance to the peak voltage of the synchronizing pulses. The composite video signal is compared with the voltage stored in the capacitance by a comparator and an output pulse is produced when the voltage of the composite video signal is high enough to indicate the presence of a synchronizing pulse. The composite video signal is also compared with the stored voltage by a second comparator, and a noise-cancelling signal which prevents noise from affecting the voltage stored on the capacitance or the first comparator is generated when the voltage of the composite video signal is high enough to indicate the presence of noise.

3,579,252 COMPUTER DRIVEN DISPLAYS EMPLOYING PATTERN RECOGNITION TECHNIQUES


David M. Goodman, 3843 Debra Court, Seaford, N.Y.

Filed Sept. 30, 1965, Ser. No. 491,673

Int. Cl. H04n 5/72

U.S. Cl. 178-7.85

18 Claims



Different displays are generated on the face of a color cathode ray tube to provide easy-to-interpret patterns representative of input data. The display may be analyzed by human observers, or by automatic means. The patterns are matrixlike in format. Analogue input data is quantized so that the position and/or color of points in the matrix represent a comparison of the input data to reference data. For testing purposes, the data is quantized into five levels and a different color is assigned to each level. Digital input data is transformed into color bits for visually testing the memory bank of a computer. Test data which varies in time is superimposed on data of fixed format to provide a "Blink" effect when the two sets of data do not match. Parity detectors are used to trigger a camera unit which takes photographs of the display screen when mismatch or out-of-tolerance conditions are detected. One such detector consists of an in-line assembly of display screen, photochromic screen, and plastic scintillator.

3,579,253

COIN TELEPHONE CIRCUIT FOR DIAL-TONE-FIRST SERVICE


John E. Edington, and Merville L. Warnock, Indianapolis, Ind., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed Nov. 8, 1968, Ser. No. 774,376

Int. Cl. H04m 17/02

U.S. Cl. 179-6.3

11 Claims



A conventional coin telephone circuit is modified for dial-tone-first service (limited service without a coin deposit) by various interrelated circuit changes which also provide additional features including a shift from an initial rate mode to a subsequent deposit mode in response to battery reversal and a means for indicating that an adjustable initial rate deposit or an overtime deposit has been made.

3,579,254

CALLING SUBSCRIBER PARTY LINE IDENTIFICATION CIRCUIT


Doyle V. Carmody, and John S. Welch, Milan, Tenn., assignors to International Telephone and Telegraph Corporation

Filed Oct. 30, 1967, Ser. No. 678,804

Int. Cl. H04m 13/00

U.S. Cl. 179-17

1 Claim



One party on a two-party line is connected in series with a diode circuit across the tip and ring lines. The diodes have a breakdown voltage above the level of AC tone from a central office and the tone does not pass through. The other party is connected directly across the tip and ring lines and AC tone transmitted to it when the hookswitch is "off" is transmitted through to a control circuit. The control circuit senses the presence or lack of tone and provides appropriate control signals which can be used to supply or control an indication of which is the calling party to the toll center.

3,579,255

OUTGOING TRUNK CONNECTION FOR PABX

Walter Kaiser, Mohrenacker, Germany, assignor to International Standard Electric Corporation, New York, N.Y.


Filed June 18, 1968, Ser. No. 737,925

Claims priority, application Germany, July 14, 1967, ST27136

Int. Cl. H04q 3/42

U.S. Cl. 179-18

1 Claim



A central marker, connected to a PABX, supervises the busy condition of trunk junctors and external registers. If, in an internal register, a call for a trunk line has been detected and all the external registers are busy, but at least one trunk junctor is available, the marker restores the time control of the internal register. As soon thereafter as an external re-

gister becomes available, the marker is requested again and the trunk connection is initiated.

3,579,256

COMBINATION SUBCARRIER FILTER AND BIAS TRAP FOR MAGNETIC TAPE RECORDERS

Gerd Cyrener, and Joachim Fahrendholz, Frankfurt-Main-Seckbach, Germany, assignors to Braun Aktiengesellschaft, Frankfurt, Main, Germany


Filed July 1, 1968, Ser. No. 741,797

Claims priority, application Germany, June 30, 1967, B93256

Int. Cl. G11b 5/00

U.S. Cl. 179-100.2

4 Claims



A recording amplifier receives audio frequency signals having additional undesired high frequency noise and furnishes corresponding amplified signals at a recording output. These are filtered by a low pass filter which passes the audio signals but rejects the high frequency noise. The output of the filter is directly connected to a premagnetization oscillator output and the recording head. Thus it also serves to decouple the premagnetization oscillator output from the recording amplifier, while permitting the full premagnetization oscillator output to be transmitted to the recording head.

3,579,257

MULTIPOSITIONAL SWITCH CONSTRUCTION

Helmuth Spreitzer, Zurich, Switzerland, assignor to Con-traves AG, Zurich, Switzerland


Filed Apr. 15, 1969, Ser. No. 816,257

Claims priority, application Switzerland, May 13, 1968, 7085/68

Int. Cl. H01h 19/58, 21/78, 3/00

U.S. Cl. 200-11

7 Claims



There is disclosed a multipositional switch comprising a rotatably mounted switching wheel equipped with a rotary wiper switch means possessing at least two contact fingers. A circuit board having a plurality of contact tracks, for instance in the form of a number of contact segments and one ring-shaped contact member, cooperate with the rotary wiper switch means such that for each selected position of the switching wheel at least two of the contact tracks are electrically coupled with one another via the contact fingers. The circuit board possesses a plurality of spaced recesses, and cam means are provided for at least one of the contact fingers. The cam means for each switching position of the switching wheel being located in an associated one of said recesses. Upon rotation of said switching wheel into its next switching position, the cam means move out of the associated one recess and along the surface of the circuit board, to thereby rapidly raise the contact finger provided with such cam means from its associated contact track located at the circuit board.


3,579,258

GAS BLAST CIRCUIT BREAKER USING A GENERALLY AXIAL FLOW MAIN BLAST

John W. Beatty, Newtown Square, Pa., assignor to General Electric Company
Filed Sept. 23, 1968, Ser. No. 761,674
Int. Cl. H01h 33/70

U.S. Cl. 200-148

5 Claims



Discloses a gas-blast circuit breaker comprising an upstream electrode, a downstream electrode spaced therefrom, and an orifice having an opening positioned between said electrodes. During interruption, an arc established between the electrodes extends through the orifice opening, and a gas blast is caused to flow through the orifice opening via paths extending along the external surface of the upstream electrode and generally axially of the arc adjacent the upstream electrode. Improved flow conditions adjacent the upstream electrode are produced by providing a series of jets issuing from circumferentially-spaced points about the orifice opening and directed convergently toward the central region of the downstream face of the upstream electrode.


3,579,259

APPARATUS FOR MAKING A DOUBLE-LAYER REINFORCING CAGE FOR CONCRETE PIPES

Shigeru Kato, Koza-gun, Japan, assignor to Nippon Roca Pipes Co., Ltd., Tokyo, Japan
Filed June 23, 1969, Ser. No. 835,681
Int. Cl. B23k 11/00; B21f 15/08

U.S. Cl. 219-56

4 Claims



An apparatus is provided for making a double-layer reinforcing cage for concrete pipes which permits welding of longitudinally oriented steel bars and circumferentially oriented steel bars of an outer reinforcing cage member and simultaneously and respectively the longitudinally oriented steel bars and circumferentially oriented steel bars of an inner reinforcing cage member. The apparatus comprises a rotor and a feed plate for moving the longitudinally oriented steel bars rotatably mounted on a hollow stationary pipe, and two sets of longitudinally oriented steel rod guide lines for the outer reinforcing cage member and the inner reinforcing

cage member respectively are mounted in the periphery of the rotor in such a manner that the two sets of guide lines are spaced apart from each other a predetermined distance, radially of the rotor. A welder for the inner reinforcing cage member and means for supplying circumferentially oriented steel bars to the inner reinforcing cage member are mounted at one end of said hollow stationary pipe.


3,579,260

MACHINE FOR WELDING STUDS TO BEAMS

Lewis J. Logan, 11820 Edgewater Drive, Lakewood, 7, Ohio
Continuation-in-part of application Ser. No. 223,457, Sept. 13, 1962, now abandoned. This application July 28, 1965, Ser. No. 477,652
Int. Cl. B23k 9/20

U.S. Cl. 219-98

8 Claims



A welding machine for simultaneously welding a plurality of studs on a beam (particularly an I-beam) comprising a frame with front and rear wheels for engaging the beam. A plurality of welding heads are mounted on a supporting means and each head includes a chuck for holding a stud; means for moving the chuck away from the beam; means for moving the chuck toward the beam; and, means for supplying electric power to the chuck. The heads are mounted for vertical and horizontal adjustment relative to the frame. Guide means are provided between the machine and the beam to properly orient the machine relative thereto and means are provided for raising and lowering said heads and supporting means as a unit relative to the wheels of the machine.


3,579,261

MAKING OF RIVET HEAD BIMETALLIC ELECTRICAL CONTACTS

Hans Wacker, Heidelberg, Germany, assignor to Renz Wacker & Co., Maschinen- u. Kettenfabrik
Filed Oct. 14, 1968, Ser. No. 767,321
Claims priority, application Germany, Oct. 12, 1967, P 16 26 696.3

Int. Cl. B21j 5/06; H05b 1/00
U.S. Cl. 219-154

7 Claims



A rivet head is formed on a bimetallic electrical contact wire by striking one end of the wire with flat surfaced cam means while retarding the advance of the wire by spring-loaded cam means.


3,579,262

ELECTRIC STEAM VAPORIZER

Donald J. Peeps, Rossford, Ohio, assignor to Champion Spark Plug Company, Toledo, Ohio
Filed May 22, 1968, Ser. No. 731,124
Int. Cl. H05b 3/60

U.S. Cl. 219-295

4 Claims



A safety device for a steam vaporizer having a liquid reservoir base with a removable top. A pair of electrodes depend from the top into the reservoir base for heating a liquid. To remove the top from the base, spaced terminals provided in a terminal block must be disengaged from shorting conductors on the base reservoir, thereby opening the power circuit to the electrodes. In one embodiment, the terminal block is an integral part of the top. In another embodiment, the block is secured to the top by connector cord of such length that the block terminals must be disengaged from the shorting conductors in order to remove the top with its dependent electrodes from the base.


3,579,263

ELECTRIC STEAM VAPORIZER

William H. Corbett, Albert D. Brunell, and George M. Koharchik, Somerset, Pa., assignors to The DeVilbiss Company and Champion Spark Plug Company, Toledo, Ohio
Filed Nov. 25, 1968, Ser. No. 778,685
Int. Cl. H05b 3/60

U.S. Cl. 219-295

9 Claims



An electric steam vaporizer having a liquid reservoir and a removable top. A post member is mounted on the upper part of the liquid reservoir. The top has an opening in one side which receives the post member when the top is placed on the reservoir. The post member actuates a switch which closes an electrical circuit to the vaporizer electrodes. The post also mechanically locks the top to the reservoir thus minimizing possible heated water injuries in the event of vaporizer overturning.

3,579,264


REVERSIBLE PROGRAMMER FOR ELECTRIC CIRCUITS

George B. Mork, Baraboo, Wis., and Donald J. Morse, Davenport, Iowa, assignors to Gulf & Western Industries, New York, N.Y.

Filed Oct. 24, 1968, Ser. No. 770,332
Int. Cl. H05b 1/02

U.S. Cl. 219-486

8 Claims



An improved reversible programmer having a regulated control sequence in both a forward and reverse direction. The programmer includes a plurality of actuatable control switches and a generally arcuate rotatable cam for sequentially actuating the control switches. A thermally controlled motor means is provided to drive the cam in a forward direction thereby actuating the control switches to energize electrical circuits, or to drive the cam in a reverse direction whereby the control switches are disengaged and the circuit deenergized. A pair of limit switch means are employed for deenergizing the motor means when the cam reaches a specific location. In addition, a clutch means is used to drivingly connect the cam to the motor means.


3,579,265

METHOD AND APPARATUS FOR TRANSMITTING INFORMATION

Jozsef Mandzsu, and Erno Csaszar, Budapest, Hungary, assignors to Fok-Gyem Finommechanikai Es Elektronikus Muszergyarto, Budapest, Hungary
Filed May 10, 1968, Ser. No. 728,183
Claims priority, application Hungary, May 10, 1967, Ma-1711

Int. Cl. G06k 7/08; B61 27/04
U.S. Cl. 235-61.11

9 Claims



Method and apparatus for transmitting information between a track bound vehicle and a point on the track whereby the desired information is provided independent of the speed and direction of the travelling vehicle. The signal transmitter is coded according to the desired information, for example, the identifying number of the vehicle, by the selective positioning of a plurality of magnets within a matrix of positions, while the receiver is provided with a plurality of magnetically operated switches, for example, Reed-switches, one for each possible position of the magnet. The transmitter is also provided with an additional gate magnet which is positioned so that it can cooperate with one of a pair of additional magnetic switches provided in the receiver depending on the speed and direction of the travelling vehicle.

on the direction of travel of the vehicle. Actuation of either of these additional magnetic switches causes signals to be simultaneously emitted in parallel from each of the other magnetic switches closed in accordance with the transmitted coded signal. The output signals from the closed magnetic switches are fed to a code converter which, depending on which one of the additional magnetic switches was actuated, provides a binary coded output signal which either represents the actual detected numerical value or its complement. The coded output signals are then either placed in an intermediate store and subsequently read or recorded, for example, by perforating a tape, or are directly recorded.

3,579,266

AUTOMATIC ADDING MACHINE


James E. Berardy, Daly City, and David A. Weinstein, Berkeley, Calif., assignors to Rollin J. Lobaugh, Inc.

Filed May 6, 1968, Ser. No. 726,772

Int. Cl. G06k 15/02; H04q 1/00

U.S. Cl. 235—61.6

33 Claims



An automatic adding machine for reading, accumulating, and printing data from media such as punched tape and cards, magnetic tape and the like. A read and feed mechanism sequentially decodes the data from the media and transmits data responsive signals to a matrix where all data from a set of data such as a punched card is stored. An adding machine or like accumulation device is coupled with the matrix and has a plurality of electrically actuated digit keys. The matrix includes a memory cell for each digit key. Electric command circuits are responsive to data decoded by the read and feed mechanism, are synchronized therewith and include a second memory system which permits storage of command signals from the read and feed mechanism so that the command data can be read prior to the reading of the data stored in the matrix. Upon completion of the reading of the set of data, one of the command circuits is energized to select the operating mode of the adding machine such as the add, subtract, etc. mode. At the same time, data stored in the matrix is fed into the adding machine whereby the data is accumulated therein and printed out. To prevent loss of data due to an asynchronism between the adding machine operating cycle and the operating cycle of the read-feed mechanism the duration of the former is shorter than that of the latter while the commencement of both cycles is interdependent.

3,579,267

DECIMAL TO BINARY CONVERSION

Carl Macey Wright, Cinnaminson, N.J., assignor to RCA Corporation

Filed Sept. 24, 1969, Ser. No. 860,592


Int. Cl. H03k 13/24

U.S. Cl. 235—155

4 Claims

Successive 4-bit numbers representing successive decimal digits in decreasing order of significance are inserted into one portion of a register means. During each period between the insertion of one 4-bit number and the next, the bits are shifted stage-to-stage and an adder serially adds the bit stored in one stage of said one portion of the register means to bits stored in two other stages of the register means. The selection of stages is such as to cause to be added to each new

decimal digit, the two multiple and the eight multiple of a binary number representing all previously applied decimal digits. The successive sum bits produced by the adder are



returned, in serial fashion, to the register means and represent a new binary number equal to the digits inserted, to that point, of the decimal number.

3,579,268

AUTOMATIC QUADRATURE AND AMPLITUDE STABILIZER


Richard J. Steiger, Berkeley, Calif., assignor to Ampex Corporation, Redwood City, Calif.

Filed July 9, 1968, Ser. No. 743,555

Int. Cl. G06g 7/22

U.S. Cl. 235—189

5 Claims



A network adapted to receive two phase related signals and generate two responsive quadrature related signals. One received signal serves as a reference. A servocontrolled percentage of the reference signal is mixed with the other received signal to form a resultant third signal which is quadrature relative to the reference signal.

3,579,269

AUTOCLAVABLE POWER-PAK SEAL

Ralph G. Ostensen, Morton Grove, Ill., assignor to Medical Products Corp., Skokie, Ill.

Filed Nov. 22, 1968, Ser. No. 778,288

Int. Cl. F21l 7/00; A61b 1/06

U.S. Cl. 240—10.68

9 Claims



Autoclavable power-pak having a bore in a stainless steel casing housing a lens-end light bulb with an externally

threaded base, a heat and pressure resistant silicone rubber seal comprising a tubular body surrounding the bulb and an integral annular flange extending inwardly from its upper end for resilient engagement with the lens end of the bulb to effect a sealing action, and a brass sleeve threadedly mounted on the base of the bulb to effect a sealing action, and a brass sleeve threadedly mounted on the base of the bulb and having a lower outwardly extending flange engaging the case for electric current transfer purposes and the lower end of the tubular body to effect a second sealing action between the bulb and the casing.

3,579,270

ENERGY SELECTIVE ION BEAM INTENSITY MEASURING APPARATUS AND METHOD UTILIZING A SCINTILLATOR TO DETECT ELECTRONS GENERATED BY THE BEAM

Norman Richard Daly, Reading, and Royal Edward Powell, Newbury, England, assignors to United Kingdom Atomic Energy Authority, London, England

Filed Oct. 22, 1968, Ser. No. 769,644


Claims priority, application Great Britain, Oct. 31, 1967,

49529/67

Int. Cl. G01t 1/20; B01d 59/44

U.S. Cl. 250—41.9

13 Claims



The apparatus is primarily intended for use with ion beams from mass spectrometers, and has one application in determining metastable ion spectra. It comprises a retarding electrode carrying a scintillator detector and preceded by an apertured electrode. When the retarding electrode voltage equals or exceeds the source accelerating voltage, all ions are repelled to the apertured electrode where secondary electrons are produced which are accelerated to the scintillator and an output is obtained from a photomultiplier located beyond the retarding electrode. When the retarding electrode voltage is less than the source accelerating voltage only ions resulting from metastable fragmentations (which have less energy) are so repelled. The parent ions strike the scintillator but produce no output because the latter is coated with an ion-opaque layer. A second, apertured, retarding electrode can precede the above-described arrangement, to which a lower voltage is applied, thus setting a lower as well as an upper limit to the ion energy detected and making the apparatus of more general application as an energy range selector.

3,579,271

METHOD OF MEASURING COATING WEIGHT BY USING STRONTIUM AS A TRACER

Marc Paul Pomerantz, Old Bridge, N.J., assignor to E.I. du Pont de Nemours and Company, Wilmington, Del.

Filed Mar. 18, 1968, Ser. No. 714,090

Int. Cl. G01n 23/22

U.S. Cl. 250—51.5

6 Claims

A process of measuring the dry coating weight of a gelatin coating by adding a given amount of strontium to the coating solution before coating, then analyzing the dried coating to determine the amount of strontium present, thereby, indicating the coating weight.

3,579,272

LOGIC CIRCUITS

Richard Charles Foss, Ilford, Essex, England, assignor to The Plessey Company Limited, Essex, England

Filed Feb. 12, 1969, Ser. No. 798,714


Claims priority, application Great Britain, Feb. 16, 1968,

7833/68

Int. Cl. H03k 19/20, 1/12

U.S. Cl. 307—218

6 Claims



An emitter coupled logic circuit comprises a long-tailed pair switch defined by transistors connected respectively to output transistors in emitter follower configuration. A V_{BE} variation with temperature of said output transistors being compensated for by further transistors whose bases are provided with a constant voltage supply.

3,579,273

DYNAMIC SHIFT REGISTER


Harold D. Cook, Wheaton, Ill., assignor to Teletype Corporation, Skokie, Ill.

Filed Oct. 1, 1968, Ser. No. 764,247

Int. Cl. G11c 19/00

U.S. Cl. 307—221

6 Claims



A dynamic integrated circuit MOS shift register includes a first storage capacitor which is charged by a first clock signal to a predetermined voltage. This first capacitor then is discharged or remains charged corresponding to an input signal applied to a shunting MOS insulated-gate field-effect transistor connected in series with a control MOS insulated-gate field-effect transistor having a second clock signal applied to it. The control transistor is rendered conductive by the clock signal and the shunting transistor is rendered conductive by an input signal of one type and remains nonconductive for an input signal of a second type. Thus, the capacitor is discharged only when an input signal of said one type occurs. Following the application of the input signal, a transfer MOS insulated-gate field-effect transistor is rendered conductive by the application of a third clock pulse to transfer the charge on the storage capacitor to the distributed gate-to-substrate capacitance present at the gate of the shunting transistor for the next stage. The charge on the distributed capacitance then constitutes the input for the next stage of the shift register and the cycle is repeated.

3,579,274

GENERATOR FOR PRODUCING TRIANGULAR SIGNALS

Arne Jensen, Havnberg, Als, and Tom Kastrup Petersen, Nordborg, Denmark, assignors to Danfoss A/S, Nordborg, Denmark


Filed Aug. 26, 1968, Ser. No. 755,299

Claims priority, application Germany, Aug. 29, 1967, D53955

Int. Cl. H03k 4/06

U.S. Cl. 307—228

9 Claims



A wave generator having an oscillator and a flip-flop generating two square waves of constant frequency and one of which is varied in amplitude in dependence upon the varying amplitude of a control signal received in a control circuit and the other of which is limited in amplitude by a limiter. The two square waves are applied to and added in a summing circuit and integrated in a differentiating amplifier with a limiter and emitter follower feedback circuit.

3,579,275

ISOLATION CIRCUIT FOR GATING DEVICES


Robert W. Polkinghorn, Huntington Beach; Arthur F. Pfeifer, Whittier; Robert F. Hartmann, Santa Ana, and Robert D. Schull, Mission Viejo, Calif., assignors to North American Rockwell Corporation

Filed Jan. 7, 1969, Ser. No. 789,441

Int. Cl. H03k 17/60, 17/60

U.S. Cl. 307—251

7 Claims



Capacitors are charged during a first recurring interval of time to turn a MOS device on for connecting an output terminal to ground. The MOS devices comprise part of a buffer or isolating circuit which is interposed between a multiphase gating circuit and the output terminal. During a second recurring interval, the capacitors are conditionally discharged as a function of inputs to the multiphase gating device.

If the capacitors were discharged during the second interval the output remains at ground during a third interval. However, if the capacitors were not discharged, the output is driven to a voltage level from a clock source. The change in the voltage at the output terminal is fed back through one of the capacitors to the gate electrode of the MOS device for driving the output to approximately the voltage level of the clock source.

Since the MOS device is turned on completely, any positive noise on the output of the circuit is neutralized by the current through the MOS device.

A second MOS device may be connected in parallel with the first device to permit the capacitor to be completely discharged to ground during the second interval.

3,579,276

HARMONIC DRIVE FOR DIGITAL STEP MOTOR


Harold R. Newell, South Newbury, N.H., assignor to Mesur-Matic Electronics Corporation, Warner, N.H.

Filed Mar. 31, 1967, Ser. No. 627,410

Int. Cl. H02k 7/06

U.S. Cl. 310—82

7 Claims



A step motor has first and second circular coaxial gears mounted on a rotor disc for pivoting and rotation relative to a shaft extending through the disc. Third and fourth circular coaxial gears are arranged to mesh with respective ones of the first and second gears but are normally separated along the shaft from the first and second gears so that meshing can occur only in a limited common sector of the gears upon tilting of the disc on the shaft. The third gear is fastened irrotationally relative to the axis and the fourth gear is fastened to the shaft. The disc comprises electromagnetic material and is subjected to an electromagnetic field that rotates about the shaft, in response to sequential energization of electromagnetic actuators disposed in a circular array about the shaft, to produce wobble motion of the disc about the shaft. At least one pair of meshing gears have different numbers of teeth so that wobble of the disc is accompanied by rotation of the fourth gear, and hence, of the shaft, about the axis.

3,579,277

BRUSHLESS DIRECT CURRENT MOTOR

Issei Imahashi, Suwa-shi, Japan, assignor to Kabushiki Kaisha Suwa Seikosha


Filed Apr. 29, 1969, Ser. No. 820,200

Claims priority, application Japan, Apr. 30, 1968, 43/28687

Int. Cl. H02k 21/00

U.S. Cl. 310—156

5 Claims



In brushless direct current motors having pairs of axially spaced permanent magnets radially arranged about and fixed to a rotor shaft, driving coils disposed in the space between said pairs of permanent magnets and detecting means including detecting coils, and a shield ring having cutaway portions in the path of said detecting coil for the operation of each detecting coil when said cutaway portions are aligned therewith for the activation of the driving coil associated with said detecting coil; the improvement of mounting the driving coils in apertures in an insulated board at an angular interval of about 100° and forming said board with a notch extending from the edge thereof to the center of said driving coils to permit removal of said rotor shaft.

3,579,280

SURFACE BARRIER DIODE HAVING A HYPERSENSITIVE η^+ REGION FORMING A HYPERSENSITIVE VOLTAGE VARIABLE CAPACITOR


John Heer, West Newbury, Mass., assignor to Varian Associates, Palo Alto, Calif.

Filed Oct. 12, 1967, Ser. No. 674,821

Int. Cl. H011 3/00

U.S. Cl. 317—234

3 Claims



A surface barrier diode, also known as a Schottky diode, is disclosed having a hypersensitive voltage variable capacitance. The surface barrier diode structure comprises a silicon wafer of n^+ conductivity having an N-type epitaxial layer which is oxidized on its outer surface to form a silicon oxide layer overlaying the epitaxial n -region of the wafer. The silicon oxide coating is relatively thin, as of less than 5000 Å, and is formed relatively quickly i.e., in less than 20 minutes at a temperature within the range of 1150° C. to 1250° C. in order to produce a hypersensitive n^+ impurity accumulation layer immediately adjacent to and underlying the oxide coating. A hole is then opened through the silicon layer and a metal electrode, as of chromium, is deposited directly upon the hypersensitive n^+ region to form the rectifying junction of the diode. The surface barrier diode (Schottky diode) exhibits a hypersensitive voltage variable capacitance effect where "hypersensitive voltage variable capacitance" means that the capacitance is approximately inversely proportional to the first power of the applied voltage as contrasted with normal voltage variable capacitance effects in PN junction devices wherein the capacitance is approximately inversely proportional to the one-half or one-third power of the applied voltage.

3,579,279

STEP MOTOR ACCELERATION-DECELERATION CONTROL SYSTEM

Seiemon Inaba, Kawasaki-shi; Kanryo Shimizu, Tokyo; Yoshihiro Hashimoto, Yokohama-shi, and Kengo Kobayashi, Kawasaki-shi, Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Filed May 15, 1969, Ser. No. 824,897

Claims priority, application Japan, May 16, 1968, 43-33240

Int. Cl. H02v 37/00

U.S. Cl. 318—696

7 Claims



A pulse control circuit is connected between the pulse supply for supplying a train of control pulses to a step motor and the motor. The pulse control circuit gradually increases the frequency of pulses in the beginning of the pulse train and gradually decreases the frequency of pulses in the end of the pulse train thereby enabling proper starting and stopping of a motor operating at high speed.

3,579,280

ELECTRICAL GROUND FAULT DETECTOR WITH TRANSFORMER COUPLING, A BATTERY SUPPLY SOURCE AND BATTERY CHARGING MEANS


Douglas A. Florance, Vestal, and Lloyd P. Nordholm, Binghamton, N.Y., assignors to Flo-Root, Inc., Village of Endicott, N.Y.

Filed May 19, 1969, Ser. No. 825,911

Int. Cl. G01r 31/02

U.S. Cl. 324—51

1 Claim



A ground fault detector applied to an electrical supply system is disclosed. It utilizes a ring-type current transformer, a battery power source, and a solid-state control device operable by preselected current imbalance to energize an alarm. In addition, a modification of the apparatus includes a charging circuit inductively coupled to a branch of the monitored electrical supply to maintain the capability of the battery.

3,579,281

COMBINING NETWORK PROVIDING COMPENSATED TUNING VOLTAGE FOR VARACTOR


George H. Kam, Tonawanda, and Richard J. Hughes, Williamsville, N.Y., assignors to Sierra Research Corporation

Filed June 4, 1969, Ser. No. 830,290

Int. Cl. H03c 3/22

U.S. Cl. 332—30V

9 Claims



A control circuit for an indirect frequency synthesizer which combines a plurality of control functions into a single compensated tuning voltage for the varactor control element of an associated voltage controlled oscillator. The combining circuit includes a resistor network for summing phase control and modulating signals, and a variable resistance circuit for generating a coarse steering signal. The summing network is resistively connected to the variable resistance circuit to form a variable impedance resistor divider operative to attenuate the combined phase control and modulating signals in a manner inversely related to the magnitude of the coarse steering signal and to combine the attenuated control signals with the coarse steering signal and to combine the attenuated control signals with the coarse steering voltage to provide the varactor tuning signal. More specifically, the attenuation provided by the impedance divider is operative to substantially compensate the variation in voltage versus frequency sensitivity of the varactor with changes in the coarse steering voltage.

3,579,282

TRANSMISSION LINE CONNECTOR WITH MEANS INCLUDING CAM SURFACES FOR ALTERING CONNECTOR ELEMENT DIMENSIONS TO COMPENSATE FOR JUNCTION GAPS, AND METHOD THEREFOR


William Dean Couper, Palmyra, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Jan. 3, 1969, Ser. No. 788,812

Int. Cl. H01p 1/00, 5/08

U.S. Cl. 333—97

6 Claims



A microwave coaxial connector structure is disclosed which features mating contact elements shaped to provide automatic compensation for physical discontinuities caused by improper mating. The contact elements include a male portion having a diameter which varies along a segment thereof and a female portion which engages such segment and is displaced radially, more or less depending upon the degree of seating, or relative axial position, of the segment within the female portion. If contact elements are not fully seated a high impedance mismatch is caused by a radial gap therebetween. The invention structure operates to create a counterbalancing low impedance due to the radial expansion of the mating element. The balancing low impedance is made to be physically close to the high impedance relative to signal wavelength. The invention is also taught in a reverse structure for outer conductive mating parts of a connector.

3,579,283

CAM GRIP FLAT CONDUCTOR CONNECTOR

Norman Welburn, Watford, England, assignor to AMP Incorporated, Harrisburg, Pa.


Filed Oct. 4, 1968, Ser. No. 765,221

Claims priority, application Great Britain, Oct. 12, 1967, 46563/67

Int. Cl. H01r 9/08

U.S. Cl. 339—217

2 Claims



An electrical connector primarily for flat conductor cable uses a spring-loaded cam to provide backup pressure between a conductor of the cable and a contact in the connector.

3,579,284

RESET AND ADJUSTMENT MECHANISM FOR A PRESSURE-RESPONSIVE SWITCH


Anthony Mason, Benton Harbor, and Clifton A. Cobb, St. Joseph, Mich., assignors to Whirlpool Corporation, Benton Harbor, Mich.

Filed July 1, 1968, Ser. No. 741,763

Int. Cl. H01h 35/40

U.S. Cl. 200—83

6 Claims



A pressure-responsive switch assembly of the type used, for example, as a liquid level control in washing machines, including a slide means which is operable to automatically reset the diaphragm of the pressure-responsive switch when an adjustment is to be made of the operating point of the switch by advancing to a higher setting.

3,579,285

HYDRAULIC ANTITHEFT SYSTEM FOR VEHICLES

Emile Joseph-Henri Verdier, St. Laurent, Quebec, Canada, assignor to Aktiebolaget Bofors, Bofors, Sweden


Continuation-in-part of application Ser. No. 452,125, Apr. 30, 1965. This application July 18, 1968, Ser. No. 751,668

Claims priority, application Canada, May 8, 1964, 902,304

Int. Cl. B60r 25/08

U.S. Cl. 307—10

12 Claims



An antitheft apparatus for use on a vehicle comprising a key operated valve adapted to retain fluid in the brake lines of the vehicle so that the brakes remain applied. The valve for use in the system being specially formed so that fluid pressure tending to hold the valve closed will not make it difficult to turn the key to open the valve.

CHEMICAL

3,579,286

POLYALKYLENE POLYAMINE THIOSULFONATED SULFUR DYE COMPOSITION AND DYEING THEREWITH

Christian Heid, Frankfurt am Main-Fechenheim, Willi Gunzert, Frankfurt am Main, and Fritz Engelhardt, Frankfurt am Main-Fechenheim, Germany, assignors to Cassella Farbwerke Mainkur Aktiengesellschaft Frankfurt am Main-Fechenheim, Germany

No Drawing. Filed Aug. 23, 1968, Ser. No. 753,998

Claims priority, application Germany, Aug. 27, 1967, P 16 19 404.0

Int. Cl. D06p 1/30

U.S. Cl. 8—37

9 Claims

Thiosulfonate forms of sulfur dyes are fixed on cellulosic fibers by merely drying the fibers after they have been impregnated with the dye and with a polyalkylene polyamide having at least three primary or secondary amine groups and in which the alkylene groups have two to four carbons.

3,579,287

BLEACHING PROCESS

Xavier Kowalski, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed June 11, 1969, Ser. No. 832,437

Int. Cl. D061 3/06

U.S. Cl. 8—108

5 Claims

Textile fibers bleached with solutions of chlorocyanuric acids, salts or complexes are soured by contact with an aqueous acidic solution containing hydroxy ethylidene diphosphonic acid, sodium hexametaphosphate, ethylene diamine tetraacetic acid, nitrilotriacetic acid, alkali metal salts of the foregoing acids or mixtures of these compounds as well as the sulfite salts conventionally utilized in souring solutions. The process provides fibers characterized by improved appearance and reduced heat sensitivity.

3,579,288

PERMSELECTIVE CELLULOSE MEMBRANES REACTED WITH A SULFONATED TRICHLOROPYRIMIDINE DYE, 2,3 - DICHLOROQUINOXALINE DYE OR DICHLORO-s-TRIOZINES

Adalbert Suszer, Jerusalem, Israel, assignor to the State of Israel as represented by the Prime Minister's Office, Jerusalem, Israel

No Drawing. Filed Sept. 20, 1966, Ser. No. 580,595

Int. Cl. D06m 13/34

U.S. Cl. 8—116.2

5 Claims

A process for making permselective membranes comprises reacting a cellulosic film or parchmented cellulosic sheet of about 0.1 mm. thickness with an aqueous solution of a sulfonated compound of the group consisting of a sulfonated trichloropyrimidine dye, a sulfonated 2,3-dichloroquinoxaline reactive dye, and a sulfonated dichloro-s-triazine, in high concentration for a period of time in the order of at least three hours until said cellulosic film or sheet is converted to a permselective membrane exhibiting permselectivity exceeding 14 mv. in a cell containing N/10 to N/20 potassium chloride, and exhibiting an electrical resistance of less than 20 ohms/cm.².

3,579,289

ACID SALT FORM OF DEAE CELLULOSIC FABRIC PROVIDING BUILT-IN CATALYSIS FOR THE REACTION WITH AMINOPLASTS

Donald M. Soignet, Metairie, and Ruth R. Benerito, New Orleans, La., assignors to the United States of America as represented by the Secretary of Agriculture

No Drawing. Filed Jan. 16, 1970, Ser. No. 3,514

Int. Cl. C08b 11/20; D06m 13/40, 13/54

U.S. Cl. 8—116.3

7 Claims

Diethylaminoethylated cellulosic fibers, the diethylaminoethyl groups of which are in an acid salt form, provide a built-in catalyst for the reaction of said fibers with methylolated nitrogen containing cross-linking agents with which said fibers are contacted.

3,579,290

STERILISATION OF SURGICAL INSTRUMENTS

Richard Esdaile Pickstone, 36 Avon Trading Estate, London, W. 4, England

Continuation-in-part of application Ser. No. 713,395, Mar. 15, 1968. This application June 8, 1970, Ser. No. 44,018

Claims priority, application Great Britain, Mar. 16, 1967, 12,419/67

Int. Cl. A61l 1/00, 3/00

U.S. Cl. 21—2

20 Claims



A method of and apparatus for sterilizing articles such as surgical instruments which method comprises suspending the object or instrument in a boiling inert liquid or in a saturated vapor thereof, said liquid having a boiling point within the range of 160° C. to 190° C. until the temperature of the said object has been raised to that of the boiling liquid and then raising it to a zone above the vapor of the boiling liquid until adhering liquid has evaporated under the sensible heat of the instrument.

3,579,291

REMOVING PHENYL AZIDE FROM GASES

Winfried Ludwig and Rudolf Oster, Ludwigshafen, and Hans Urbach, Lampertheim, Germany, assignors to Badische Anilin- & Soda-Fabrik Aktiengesellschaft, Ludwigshafen (Rhine), Germany

No Drawing. Filed Dec. 3, 1969, Ser. No. 881,898

Claims priority, application Germany, Dec. 13, 1968, P 18 14 493.9

Int. Cl. B01d 47/02

U.S. Cl. 23—2

3 Claims

A process for removing phenyl azide from gas by passing the gas containing phenyl azide through 50 to 100 wt. percent sulfuric acid.

3,579,292

PROCESS AND COMPOSITION FOR SEPARATION OF OXYGEN FROM AIR USING STRONTIUM OXIDE-PEROXIDE AS THE CARRIER


Joseph T. Mullhaupt, Tonawanda, and Silviu A. Stern, De Witt, N.Y., assignors to Union Carbide Corporation, New York, N.Y.

Filed Jan. 8, 1969, Ser. No. 789,908

Int. Cl. B01d 53/34; C01b 13/08, 15/04

U.S. Cl. 23—2

22 Claims



By incorporating at least one ion of a metal from Groups I-A, I-B and VIII of the Deming Periodic Table into a strontium oxide-peroxide reaction mass, a great increase in the oxidation and reduction rates of the mass is obtained. This increase in reaction rates makes it feasible to use this system as the oxygen carrier in a cyclic, reversible oxidation-reduction process for the separation of oxygen from air.

3,579,293

REMOVAL OF HYDROGEN SULFIDE FROM GASEOUS MIXTURES

Forrest G. Shultz and Gerald E. Chidester, Morgantown, and Fernand E. Collet, Star City, W. Va., assignors to the United States of America as represented by the Secretary of the Interior

No Drawing. Filed Oct. 10, 1969, Ser. No. 865,535

Int. Cl. B01d 53/14

U.S. Cl. 23—2S

3 Claims

Hydrogen sulfide is removed from gaseous mixtures by contacting the mixtures at elevated temperature with an absorbent comprising iron oxide and fly ash.

3,579,294

PROCESS FOR EXTRACTION OF ALUMINA FROM ORES BY SOLUTION OF CAUSTIC SODA AND SODIUM ALUMINATE

Louis Tamisé, Douvres-la-Delivrande, and Jacques Millet, Versailles, France, assignors to Pechiney-Compagnie de Produits Chimiques et Electrometallurgiques, Paris, and Societe Appareils et Evaporateurs Kestner, Lille, France

Filed Mar. 15, 1968, Ser. No. 713,421

Claims priority, application France, Mar. 20, 1967, 99,393

Int. Cl. C01f 7/02

U.S. Cl. 23—52

10 Claims

Process and equipment for the continuous extraction of alumina from bauxite by dissolution in aqueous caustic soda and sodium aluminate solutions in which use is made of a plurality of autoclaves of increasing temperature through which the suspension flows in series from

one to the next in a sequence of stages and a plurality of expansion vessels of decreasing pressure in series with the autoclaves and through which the suspension flows in series.

3,579,295

PROCESS FOR ATTACK OF BAUXITE WITH ALKALINE SOLUTION

Louis Tamisé, Douvres-la-Delivrande, and Jacques Millet, Versailles, France, assignors to Pechiney Compagnie de Produits Chimiques et Electrometallurgiques, Paris, and Societe Appareils et Evaporateurs Kestner, Lille, France

Filed Mar. 15, 1968, Ser. No. 713,422

Claims priority, application France, Mar. 20, 1967, 99,394

Int. Cl. C01f 7/02

U.S. Cl. 23—52

9 Claims

A process for the continuous attack of ores containing alumina with an aqueous solution of caustic soda and sodium aluminate in which use is made of a series of stages each having an autoclave with the autoclaves increasing in temperature from stage to stage in the direction of flow of the suspension with the autoclave in one stage receiving suspension from the preceding stage and expansion vessels with the expansion vessels decreasing in pressure in countercurrent relation with the autoclaves of increasing temperature.

3,579,296

DUAL CYCLE TREATMENT OF SULFUR DIOXIDE CONTAINING FLUE GAS AND THE LIKE


Everett Douglas Cann, Freeport, Ill., assignor of fractional part interest to William T. Neiman

Filed Nov. 13, 1967, Ser. No. 682,435

Int. Cl. C01b 17/60

U.S. Cl. 23—178

11 Claims



A method is provided for treating flue gas and the like for sulfur dioxide removal and recovery. The gas, containing a minor but polluting amount of sulfur dioxide and substantially no sulfur trioxide, is contacted with ammonia in the presence of water to form an ammonium sulfite. This is separated and, in the absence of oxygen, reacted with an aqueous alkaline earth metal oxide or with zinc oxide to liberate the ammonia for recycle and to form insoluble alkaline earth metal or zinc sulfite. The latter is dried, dehydrated, and thermally decomposed to liberate a concentrated stream of sulfur dioxide and to form alkaline earth metal oxide or zinc oxide for recycle. Procedures are disclosed for efficiently conducting the above processing steps and operations.

3,579,297

PROCESS OF MANUFACTURING AMMONIUM SALTS

Karl Gote Ekblom, Ljungaværk, Sweden, assignor to Fosfatholaget AB, Stockholm, Sweden

Filed June 18, 1968, Ser. No. 738,033

Claims priority, application Sweden, Sept. 15, 1967, 12,742/67

Int. Cl. C01c 1/18, 1/28

U.S. Cl. 23—103

4 Claims

This invention relates to a method for controlling the reaction between ammonia and acid so as to minimize the formation of excess ammonia, which comprises withdrawing some vapor from the reaction zone, dividing said vapor into two streams, contacting it with an acid compound in excess of that needed to neutralize the free ammonia in the stream, cooling each stream to form an aqueous condensate, measuring the conductivity of each condensate, and regulating the introduction of reactants to the reaction zone in accordance with said conductivity measurements.

3,579,298

PRODUCTION OF AMMONIUM NITRATE

George O'Brien and John S. Hubby, Bartlesville, Okla., assignors to Phillips Petroleum Company

Filed Aug. 5, 1968, Ser. No. 750,327

Int. Cl. C01c 1/18

U.S. Cl. 23—103

3 Claims

An aqueous stream comprising essentially water and a minor amount of ammonia is reacted with at least enough nitric acid to produce an ammonia-free water stream containing a minor amount of ammonium nitrate, and then utilizing said ammonium nitrate-containing stream to absorb at least a portion of nitrogen dioxide gas to produce nitric acid containing a minor amount of ammonium nitrate.

3,579,299

POROUS SILICATE

Robert H. Sams, Aldan, and Newton W. McCready, Newtown Square, Pa., assignors to Philadelphia Quartz Company, Philadelphia, Pa.

No Drawing. Continuation-in-part of application Ser. No. 540,204, Apr. 5, 1966. This application July 30, 1968, Ser. No. 748,644

Int. Cl. C01b 33/00; C11d 3/04

U.S. Cl. 23—110A

6 Claims

A low bulk density, crystallized, alkaline sodium silicate or a detergent containing a low bulk density, crystallized, alkaline sodium silicate is formed by the addition of powdered silicon metal to a crystallizing mass of the alkaline sodium silicate to produce a forameniferous product of uniform porosity.

3,579,300

CONTINUOUS PROCESS FOR THE PRODUCTION OF CALCIUM SULPHATE HEMI-HYDRATE FROM GYPSUM

Martin S. Bloom, Norton-on-Tees, and Martin Granger Brown, Runcorn, England, assignors to Imperial Chemical Industries Limited, London, England

Continuation-in-part of abandoned application Ser. No. 414,244, Nov. 27, 1964. This application Aug. 4, 1969, Ser. No. 847,022

Claims priority, application Great Britain, Dec. 3, 1963, 47,675/63

Int. Cl. C01f 11/46

U.S. Cl. 23—122

6 Claims

Process for producing calcium sulphate alpha-hemihydrate by subjecting a slurry of gypsum and water to superatmospheric pressure sufficient to maintain the water in the liquid state at a preselected mean temperature of at least 130° C., continuously passing the said slurry into a reactor having an inlet and an outlet, injecting into said slurry sufficient steam at a pressure and temperature suffi-

cient to maintain said slurry in the reactor at least at said superatmospheric pressure and preselected mean temperature, continuously agitating said slurry in reactor, and continuously withdrawing calcium sulphate alpha-hemihydrate from the outlet without reducing the pressure therein.

3,579,301

CONDENSED PHOSPHORIC ACID HAVING REDUCED VISCOSITY

Robert A. Wiesboeck, Atlanta, and Charles C. Stone, Doraville, Ga., assignors to United States Steel Corporation, Pittsburgh, Pa.

Filed June 28, 1968, Ser. No. 740,918

Int. Cl. C01b 25/24

U.S. Cl. 23—165

7 Claims

To reduce the viscosity of condensed phosphoric acids, so that they can be pumped or otherwise readily handled or treated, the F content of the acids is raised above two percent and preferably above four percent. The fluorine may be added in the form of a fluorine-containing compound, such as fluorophosphoric acid, difluorophosphoric acid, hexafluorophosphoric acid, hydrogen fluoride, etc. The fluorine treatment inhibits crystallization of the acid and, in the case of wet process phosphoric acid containing solids, dissolves solids in the acids.

3,579,302

METHOD OF FORMING SULFUR FROM SO₂-CONTAINING GASES

Verner B. Sefton, Toronto, Ontario, Canada, assignor to Ontario Research Foundation, Sheridan Park, Ontario, Canada

Continuation-in-part of application Ser. No. 722,719, Apr. 19, 1968. This application June 25, 1969, Ser. No. 836,501

Int. Cl. C01b 17/04

U.S. Cl. 23—226

9 Claims

Hydrogen sulphide-containing gases used to react with sulphur dioxide in a waste effluent gas stream to thereby produce sulphur is generated by reaction between sulphur, a hydrocarbon fuel and steam at high temperatures. The high temperatures necessary for the reaction of sulphur, hydrocarbon fuel which may be the same as or different from that used to form the hydrogen sulphide-containing gases. The sulphur used to form the hydrogen sulphide may be that formed in the reaction of the sulphur dioxide and the hydrogen sulphide-containing gases.

3,579,303

SYSTEM FOR HANDLING SPECIMENS AND OTHER SUBSTANCES IN MEDICINE AND PHYSICAL SCIENCES


Donald E. Pickering, 830 NW. St. Helens Ave., Portland, Oreg. 97229

Filed Mar. 6, 1968, Ser. No. 710,974

Int. Cl. G01n 1/00, 33/16

U.S. Cl. 23—230

11 Claims



A method of and apparatus for handling, processing, testing, storing, transporting and otherwise using biomedical, biological, chemical and other specimens, re-

agents and substances from the time of their initial procurement through their transport, storage and ultimate laboratory or other usage and final disposal. The system embodies the use of a length of transparent or translucent, resilient, sterile and disposable tubing divided by heat or other seals into a series of linked and sealed segments. Individual segments are severed from the string of segments as needed, filled with a freshly procured specimen or reagent, and then resealed mechanically with a selectively removable clip to which an identification tag can be attached. Additional temporary or permanent sealing of a tube segment can be achieved as needed for separation of substances through the use of additional clips. A modification of the apparatus includes the use of a swab and transport media to procure, contain and transport or store microbiological specimens.

3,579,304

HEAT SCANNED CHROMATOGRAPHIC DETECTOR

Frederick Bolton Padley, Welwyn Garden City, England, assignor to Lever Brothers Company, New York, N.Y.


Filed Apr. 12, 1968, Ser. No. 720,871

Claims priority, application Great Britain, Apr. 21, 1967, 18,448/67

Int. Cl. G01n 31/12

U.S. Cl. 23—232

8 Claims



A method of detection particularly suitable to thin layer chromatography in which chemically separated materials on a carrier, produced for example by thin layer chromatographic elution, are scanned and detected by a heat source such as the flame of a flame ionization detector.

3,579,305

SCRUBBER APPARATUS


Radhakrishna M. Netti, Brea, Calif., assignor to Beckman Instruments, Inc.

Filed July 25, 1968, Ser. No. 747,721

Int. Cl. C09k 3/00; G01n 31/06

U.S. Cl. 23—232

3 Claims



A solid phase chemical scrubber for selectively removing interferences from an ozone bearing sample gas stream which is to be analyzed for its ozone content. The scrubber contains an alkali or alkaline earth hydroxide, preferably $\text{Ca}(\text{OH})_2$ or KOH , which effectively removes both positive and negative interferences from the gas stream, but does not affect the ozone in the stream.

3,579,306
DIAGNOSTIC TEST DEVICE


Margaret M. Crane, New York, N.Y., assignor to Organon, Inc., West Orange, N.J.

Filed Jan. 22, 1969, Ser. No. 792,936

Int. Cl. A45c 11/00; G01n 21/06, 33/16

U.S. Cl. 23—253

10 Claims



A test kit for the performance of analytical and diagnostic determinations involving visual indication of test results comprises a transparent container having a closure utilizable as a sampling device, a platform supported within the container and having an integral upwardly extending tube supporting a test vial for holding test reagents, and a downwardly extending integral tube guiding and supporting a test dropper, and a mirror set at an angle located in the bottom portion of the container to reflect the results of a test performed within the test vial through the container wall so as to be viewable outside the container.

3,579,307

APPARATUS FOR RECOVERING ACRYLONITRILE MONOMER IN THE PRODUCTION OF A POLYMER

Eiichi Wakita and Kunio Tokumitsu, Fuji-shi, Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan


Original application July 10, 1963, Ser. No. 294,101,

Divided and this application Dec. 31, 1968, Ser. No. 788,188

Int. Cl. B01d 3/10; B01j 1/00; C07c 121/30

U.S. Cl. 23—263

8 Claims



An acrylonitrile polymerizer is connected to an evaporator to recover unpolymerized monomers. A water ejector or jet condenser is connected to the evaporator to recover gaseous monomers therefrom. A tank receives a stream from the ejector or condenser with monomer condensate therein while a filter connected to the evaporator produces a solid filtered material and a filtrate which is fed to the ejector or condenser to form the stream. The tank returns part of the stream and condensate to the polymerizer.

3,579,308
APPARATUS FOR MANUFACTURING HIGH PRESSURE INERT GAS


George H. Gower, Tulsa, Okla., assignor to Inert Gas Corporation, Tulsa, Okla.

Filed Sept. 25, 1969, Ser. No. 860,908

Int. Cl. B01j 7/00

U.S. Cl. 23—281

5 Claims



This invention relates to an apparatus for manufacturing high pressure inert gas utilizing hydrocarbon fuel, the gas being produced by the burning of hydrocarbon fuel in an internal combustion engine, the exhaust gases therefrom being conveyed through a catalytic converter whereby substantially inert gas is derived therefrom, and including means of controllably recycling such inert gas through engine driven compressor stages to vary the loading on the engine and thereby vary the inert gas output in response to the demand.

An additional embodiment of the invention includes means to maintain a positive pressure in all portions of the system, including the engine exhaust manifold and catalytic converter, so that any inadvertent leak in the system will not result in air being drawn into the system.

3,579,309

COLUMN FOR CARRYING OUT ORGANIC CHEMICAL REACTIONS IN CONTACT WITH FINE PARTICULATE CATALYSTS

Kurt Sennewald and Klaus Gehrmann, Knapsack, near Cologne, and Stefan Schafer, Bruhl, near Cologne, Germany, assignors to Knapsack Aktiengesellschaft, Knapsack, near Cologne, Germany


Filed Oct. 7, 1968, Ser. No. 765,337

Claims priority, application Germany, Nov. 18, 1967, P 16 67 139.9

Int. Cl. B01j 9/04; C07c 69/66

U.S. Cl. 23—288

2 Claims



Column for carrying out organic chemical reactions in contact with fine, particulate catalysts, the column being formed with interchangeable, catalyst-receiving reaction vessels, which are arranged outside the column, preferably in staggered relationship to each other, between individual column tray outlet and inlet openings projecting outwardly.

3,579,310

PREPARATION OF ACICULAR RUTILE TiO_2

George L. Lewis, Wilmington, and Carl H. Muendel, Centerville, Del., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Continuation-in-part of application Ser. No. 624,716, Mar. 21, 1967. This application June 28, 1967, Ser. No. 655,984

Int. Cl. B01d 9/00; C01g 23/08

U.S. Cl. 23—301 11 Claims
Pigmentary single acicular rutile TiO_2 crystals, at least 50% by weight of the particles of which have an average cross-sectional dimension of 0.01 to 0.5 micron and a length-to-cross sectional ratio of 3:1 to 50:1, obtained by calcining at 725–1000° C., a blended titania-salt-promoter mixture made up of preformed TiO_2 , a salt comprising sodium chloride, and an oxy-compound of phosphorus (phosphate), and leaching of the calcined product to recover the acicular rutile pigment.

3,579,311

PROCESS AND APPARATUS FOR PRODUCING UO_2 POWDER


John J. McCoy, San Jose, Calif., assignor to General Electric Company

Filed Apr. 25, 1968, Ser. No. 724,119

Int. Cl. C01g 43/02

U.S. Cl. 23—355

12 Claims



An improved process and apparatus for preparing uranium dioxide powder suitable for use in the fabrication of fuel for nuclear reactors. In a process comprising steps of hydrolyzing uranium hexafluoride to form an aqueous uranyl fluoride solution, treating with ammonia to precipitate ammonium diuranate, dewatering and drying the precipitate, and finally calcining the precipitate to form uranium dioxide, the improvement wherein the precipitate is dewatered to about 40% to about 60% by weight, preferably about 50% by weight water and is thereafter directly calcined.

3,579,312

PRINTED CIRCUITS FROM NONMIGRATING SOLDERS

Oliver A. Short, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Original application Mar. 28, 1967, Ser. No. 626,425, now Patent No. 3,472,653, dated Oct. 14, 1969. Divided and this application Apr. 28, 1969, Ser. No. 819,941

Int. Cl. H05k 1/04; C22c 5/00

U.S. Cl. 29—195

5 Claims

Printed circuits of high reliability fabricated with a non-migrating solder comprising an alloy of gold, tin and germanium. The invention is particularly suitable in circuits with non-migrating conductor compositions.

3,579,313

COMPOSITE OF STEEL AND ALUMINUM CONTAINING ZINC AND BORON, AND A CABLE SHEATH MADE THEREFROM


Michael J. Pryor and William H. Anthony, Hamden, Conn., assignors to Olin Mathieson Chemical Corporation

Filed Oct. 25, 1967, Ser. No. 677,955

Int. Cl. B32b 15/00

U.S. Cl. 29—196.2

8 Claims



This invention relates to a novel high strength Al-Zn-B alloy metallurgically bonded to steel and heat treating processes therefore, for use in both aerial and underground cable sheathing.

3,579,314

DUST AND SMOKE REMOVAL IN TIRE BUFFING


John J. Cunningham, Jr., Wilmington, Del., assignor to Quinn Brothers, Incorporated, Philadelphia, Pa.

Filed May 20, 1969, Ser. No. 826,165

Int. Cl. B24b 55/06

U.S. Cl. 51—273

2 Claims



For removing dust and smoke from tire buffing, a cyclone dust collector, a spray chamber and an absolute filter in combination. There is preferably a bypass from a high pressure point in the cyclone dust collector back to a hood adjoining the tire buffing for lengthening the time of a dust and smoke cycle.

3,579,315

METHOD OF PRECISION FORM MILLING


William Rowe Hufendick, Quincy, Ill., assignor to Gardner-Denver Company

Filed May 1, 1968, Ser. No. 725,647

Int. Cl. B24b 1/00

U.S. Cl. 51—288

3 Claims



Precision in form milling processes using arbor-type milling cutters is improved by providing a unitary arbor

and cutter assembly which is mounted on a cutter grinding machine and rotated for individual cutter tooth forming and sharpening thereby establishing an axis and plane of rotation for each point on the cutter profile. After grinding and sharpening of the cutter teeth, the unitary arbor-cutter assembly is transferred to a milling machine and mounted in a manner duplicating the grinder mounting, thereby exactly preserving the axis and plane of rotation of the cutter which was established during the grinding operation.

3,579,316

PROCESS FOR OPTICAL WAVEGUIDE COUPLER

Richard Burnaby Dyott, Chalfont St. Peter, and George Archer Clark, Stanmore, England, assignors to Her Majesty's Postmaster General, London, England

Filed Nov. 4, 1968, Ser. No. 773,195

Claims priority, application Great Britain, Nov. 8, 1967, 50,919/67

Int. Cl. C03c 23/20; G02b 5/14; H01s 3/00

U.S. Cl. 65—4

4 Claims



A method is disclosed of coupling optical waveguides together for energy transfer from one waveguide to another. The waveguide ends are inserted into a glass capillary tube of refractive index lower than that of the waveguide cladding. The closely proximate ends of the waveguides and the capillary are heated to softening point and then pulled out until the diameter of the sleeve approximates to that of a waveguide.

3,579,317

METHOD OF MUTUALLY BONDING PARTS BY USE OF GLASS

Eizo Goto, Chigasaki-shi, Japan, assignor to Tokyo Shibaura Electric Co. Ltd., Kawasaki-shi, Japan


Filed Nov. 4, 1968, Ser. No. 772,891

Claims priority, application Japan, Nov. 9, 1967, 42/71,689; Nov. 11, 1967, 42/72,215

Int. Cl. C03c 27/00

U.S. Cl. 65—43

3 Claims



A method of mutually bonding parts with glass layers which comprises inserting a spacer between those portions of a plurality of assembled parts requiring bonding in a manner to define a very narrow space with said portions. The spacer comprises an angular column of either glass or ceramic material with a metal wire wound around it. Contacting the end faces of said portions of the assembly requiring bonding with the surface of an electrically heated molten glass bath and removing the assembly from the bath. The bonding of the assembled parts being due to the cooling into solid layers of the molten glass filled by capillary action into the spaces of said portions requiring bonding.

3,579,318

METHOD OF AND APPARATUS FOR FORMING GLASS SHEETS BY DRAWING DOWNWARDLY

Cecil R. Ward, Gibsonsia, Pa., assignor to


PPG Industries, Inc., Pittsburgh, Pa.

Filed May 2, 1968, Ser. No. 726,020

Int. Cl. C03b 17/00

U.S. Cl. 65—90

4 Claims



A sheet of glass is drawn downwardly from a contoured nozzle incorporating a trough into which glass is fed through a pipe or conduit from a melter. The glass is extruded upwardly between the inner walls of the nozzle and the feed conduit fills the nozzle and overflows its edges.

3,579,319

ADJUSTABLE SHEAR BLADE AND DROP GUIDE MOUNTING FOR MOLTEN GLASS STRAIGHT LINE SHEARS


Frederick J. Wythe, Hebron, and Harald Hoette, Farmington, Conn., assignors to Emhart Corporation, Bloomfield, Conn.

Filed Apr. 25, 1968, Ser. No. 723,985

Int. Cl. C03b 5/38

U.S. Cl. 65—334

7 Claims



A fixed frame for the shears is mounted beneath the outlet of a feeder bowl, and a pair of horizontally reciprocable carriages are mounted in the frame for movement in opposite directions, and carry opposed pairs of shear blades for severing gobs of glass from a plurality of suspended molten glass columns accumulated at said feeder bowl outlet. One blade in each pair is movably mounted in its associated carriage for vertical adjustment with respect to the other blade, and a hand operated adjustment knob carries a shaft which is slidable in the frame and its inner end is engageable with the blade mounting means when the carriage is retracted for accomplishing these adjustments during operation of the shears. A drop guide is also provided below each adjustable blade in each of said pairs of blades, and said drop guide is adjustable horizontally through another hand knob and shaft located above the shear blade adjusting knob.

3,579,320

PROCESS FOR PRODUCING AND RECOVERING VALUABLE MATERIALS FROM MUNICIPAL WASTE

Marvin Presses, Liberty Township, Trumbull County, Ohio, assignor to General Ecological Systems, Inc., Pittsburgh, Pa.

Filed Aug. 18, 1969, Ser. No. 850,808


Int. Cl. C05f 11/08

U.S. Cl. 71—9

6 Claims

A process for producing and recovering valuable materials from a burden comprising a mixture of organic

and inorganic waste materials comprising the steps of separating large refuse items from the burden and separately recovering same; opening containers of refuse present in the burden and separately recovering the containers; subjecting the burden to a magnetic separation operation and separately recovering the magnetic materials; classifying the non-magnetic materials according to size



ranges; removing discrete items of refuse such as glass, plastic, metals, paper and the like from the large size range material and separately recovering the discrete refuse items; comminuting the large and intermediate size range materials and combining the comminuted material with the small size range material to form an organic mass; composting the organic mass, preferably in a mixture with raw sewage; and recovering a sterile compost.

3,579,321

AMMONIUM PHOSPHATE FERTILIZER COMPOSITION AND METHOD

Jerry H. Stoller, Springfield, Ill., assignor to Brandt Chem. Co., Inc., Pleasant Plains, Ill.

No Drawing. Filed Mar. 9, 1970, Ser. No. 18,402

Int. Cl. C05f 11/00

U.S. Cl. 71—25

10 Claims

A fluid ammonium phosphate composition and method utilizing wet process phosphoric acid or spent phosphoric acid which contain metallic impurities. Lignin sulfonate is added to the acid prior to ammoniation in sufficient quantities to prevent formation of gelatinous precipitate during ammoniation.

3,579,322

RECOVERY OF PHOSPHATE FROM PHOSPHATE CONTAINING POND WATER


Irwin R. Higgins, Oak Ridge, Tenn., assignor to Chemical Separations Corporation, Oak Ridge, Tenn.

Filed Dec. 1, 1966, Ser. No. 598,418

Int. Cl. C05b 7/00

U.S. Cl. 71—34

5 Claims



A continuous process for treating a waste aqueous stream containing phosphate values to recover said phosphate values including initially removing contaminating cations from the waste aqueous stream by contacting the same with a cation exchange resin bed and then contacting the essentially contaminating cation-free aqueous

stream with an anion exchange resin bed to eliminate the phosphate values therefrom and then removing the phosphate values loaded on the anion exchange resin with a regenerating agent. In another embodiment, the waste aqueous stream by-passes the cation exchange resin and is contacted only with a weak-base anion exchange resin which is, thereafter, contacted with a regenerating agent, such as ammonium hydroxide to liberate the phosphate values therefrom.

3,579,323

PROCESS FOR THE MANUFACTURE OF A CHLORIDE-FREE HIGH-STRENGTH POTASSIUM AMMONIUM NITRATE PHOSPHATE FERTILISER

Wolfgang Gauster, Linz (Danube), Walter Muller, Leonding, near Linz (Danube), and Alfred Schmidt and Ferdinand Weinrotter, Linz (Danube), Austria, assignors to Osterreichische Stickstoffwerke Aktiengesellschaft, Linz (Danube), Austria

No Drawing. Filed Sept. 26, 1968, Ser. No. 763,017

Int. Cl. C05b 11/06; C05c 5/02; C05d 1/02

U.S. Cl. 71—35

2 Claims

Process for the manufacture of chloride-free high-strength potassium ammonium nitrate phosphate fertilisers by reaction of potassium chloride with liquid or gaseous N_2O_4 at a temperature of at most $80^\circ C$. The reaction medium used is phosphoric acid or a mixture of phosphoric acid and nitric acid. After removal of the nitrosyl chloride formed and neutralising the resulting acid/potassium nitrate suspension with ammonia the mixture is shaped and dried.

3,579,324

METHOD FOR INDUCTION MELTING OF FINE PARTICLES


Theodore R. Kennedy, Willingboro, and Henry M. Rowan, Moorestown, N.J., assignors to Inductotherm Corporation, Rancocas, N.J.

Filed Nov. 18, 1968, Ser. No. 776,450

Int. Cl. C22d 7/00; H05b 5/08

U.S. Cl. 75—10

1 Claim



The ability of a coreless induction furnace to melt fine particles is enhanced by providing a lower single phase coil which supplies melting currents and an upper polyphase coil which stirs the molten metal so as to lift the outer rim of molten metal adjacent the surface.

3,579,325

STEEL-MAKING PROCESS EMPLOYING AN AUXILIARY COMPOSITION

Joseph K. Stone and Peter J. Beck, Berkeley, and Edward J. Prince, Oakland, Calif., assignors to Kaiser Industries Corporation, Oakland, Calif.

No Drawing. Filed Dec. 26, 1967, Ser. No. 693,123

Int. Cl. C21c 5/28, 5/36

U.S. Cl. 75—51

7 Claims

A composition for charging to a metallurgical furnace, such as an oxygen steel furnace which is a heat- and flux-

producing agent consisting essentially of a granular admixture of from 5% to 95% calcium carbide and from 95% to 5% silicon carbide. Both components provide fuel to enable the use of higher amounts of scrap metal; and in one embodiment the silicon carbide and calcium carbide are admixed in a ratio to give an eventual slag of suitable lime-silica ratio. The admixture of silicon carbide and calcium carbide is advantageously admixed with a minor amount of a hydrocarbon bonding agent which is at least semi-solid at ordinary room temperatures, such as tar or pitch, and formed into compacts, e.g. pellets or briquettes. Powdered aluminum metal can also be incorporated.

3,579,326

PROCESS FOR THE PRODUCTION OF MAGNESIUM


Julian M. Avery, Greenwich, Conn.
(47 Old Orchard Road, Chestnut Hill, Mass. 02167)

Filed June 26, 1967, Ser. No. 648,856

Int. Cl. C22b 45/00

U.S. Cl. 75—67

11 Claims



A process for the production of magnesium by reducing magnesium oxide from an oxidant containing a major proportion of magnesia with reductant containing a metallic aluminum-silicon alloy, having a ratio of silicon to aluminum of at least 0.8 to 1, at a temperature of at least $1400^\circ C$. and in the presence of a molten slag of defined composition and comprising 5-25 percent magnesium oxide, and less than 30 percent calcium oxide. The reductant and slag are preferably chosen having compositions falling within the areas shown in the figures. As a consequence, the reductant and slag are coordinated such that much of the alumina and silica of the slag are derived by the oxidation of the reductant.

3,579,327

COBALT REMOVAL FROM ZINC ELECTROLYTE SOLUTION

Tokushige Hasegawa, Narashino-shi, Kuninobu Makimoto, Aizu-Wakamatsu-shi, and Seiji Nihei and Jiro Takahira, Bandai-machi, Yama-gun, Japan, assignors to Nisso Kinzoku Kabushiki Kaisha, Tokyo-to, Japan

Filed Apr. 9, 1968, Ser. No. 719,951

Int. Cl. C22b 19/32

U.S. Cl. 75—109

6 Claims

Zinc dust containing a small amount of antimony or antimony and lead as alloy elements is added into an electrolyte used in hydrometallurgy of zinc, in order to remove cobalt impurities from the electrolyte of zinc sulfate solution.

3,579,328

PROCESS FOR THE PRODUCTION OF FERROVANADIUM DIRECTLY FROM SLAG OBTAINED FROM VANADIUM-CONTAINING PIG IRON

Helge Aas, Svelgen, and Rolf Nordheim, Oslo, Norway, assignors to Christiania Spigerverk, Oslo, Norway

No Drawing. Filed Apr. 11, 1968, Ser. No. 720,461

Claims priority, application Norway, May 31, 1967,

168,400

Int. Cl. C22c 39/50

U.S. Cl. 75—133.5

5 Claims

A process is provided for the production of ferrovanadium from slag obtained from vanadium-containing pig iron or other vanadium-containing material, characterized in that the reduction of the slag is carried out in two steps: (1) in the first step a reducing agent is added in such amounts that the substantial portion of the iron oxide in the slag is substantially reduced to metallic iron, whereas practically none of the vanadium oxide is reduced; whereupon after removing the metallic iron from the slag, the fluid vanadium-rich slag is subjected to a further final reduction step (2) by adding a powerful reducing agent thereto, such as Si-rich ferro-silicon in such amounts that the remaining iron oxide in the slag and the major part of the vanadium oxide therein is reduced, and whereby the reducing agent is added gradually under continuous agitation to avoid local concentrations of the reducing material and the thus-obtained ferrovanadium is removed from the slag in a conventional manner.

3,579,329

OXIDATION RESISTANT IRON-CHROMIUM-ALUMINUM ALLOYS


Satoru Mito, Yokohama-shi, Mitsuo Kawai, Tokyo, Hiroshi Yoshida, Yokohama-shi, and Kenichiro Ando, Tokyo, Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki-shi, Japan

Filed May 12, 1969, Ser. No. 823,778

Int. Cl. C22c 37/10, 39/02

U.S. Cl. 75—124

4 Claims



Heat resistant and oxidation resistant iron-chromium-aluminum alloys consisting of 15 to 30 percent by weight of chromium, 3 to 7 percent by weight of aluminum, 0.001 to 0.5 percent by weight of one or more of beryllium, magnesium and barium, remainder iron and incidental impurities.

3,579,330

IMAGE-FORMING PROCESS UTILIZING CONTACT ELECTRIFICATION

Robert G. Cunningham, Pittsford, and Harrison P. Hood III, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed May 20, 1968, Ser. No. 730,624

Int. Cl. G03g 13/22

U.S. Cl. 96—1

10 Claims

Electrostatic charge images are produced on a member having an electrically insulating surface when it is inti-

mately contacted with a portion of a second member including originals to be copied that is, at least in part, triboelectrically separated or remote from the insulating surface. After the second member and insulator are separated, a latent electrostatic charge image is present upon the electrically insulating surface in a pattern corresponding to the triboelectrically separated or remote areas of the original that are intimately contacted with the insulating member. This latent image can be rendered visible by electrostatic development techniques. Alternatively, a second member that is uniformly triboelectrically separated can be intimately contacted with an electrically insulating member or surface in an imagewise fashion, thereby producing a latent electrostatic charge image on such insulator in a pattern corresponding to the imagewise contact. This image can also be made visible by electrostatic development.

3,579,331

ELECTROPHOTOGRAPHIC MATERIALS CONTAINING CYANINE DYE SENSITIZERS

John D. Mee and Donald W. Heseltine, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Apr. 8, 1968, Ser. No. 719,690

Int. Cl. G03g 5/02, 5/06

U.S. Cl. 96—1.6

26 Claims

Organic photoconductors are spectrally sensitized with a cyanine dye containing a carbazole nucleus.

3,579,332

SINGLE-CRYSTAL ZINC OXIDE AND AN ELECTROPHOTOGRAPHIC PLATE MADE THEREFROM

Richard Williams, Princeton, N.J., assignor to RCA Corporation

Filed May 27, 1968, Ser. No. 732,326

Int. Cl. G03g 5/00

U.S. Cl. 96—1.8

6 Claims

An improved electrophotographic plate has a photoconductive layer of one or more relatively large wafers of single-crystal, n-type zinc oxide. Each wafer is fixed to, and in electrical contact with, an electrically conductive backing. The novel method of charging the electrophotographic plate comprises (1) wetting a major surface of the zinc oxide layer with a solution of an ionizable salt in a relatively volatile solvent while biasing the solution with a negative voltage with respect to the backing, and (2) allowing the solvent to evaporate, whereby to leave an electrostatic charge on the zinc oxide surface.

3,579,333

MULTICOLOR DIFFUSION TRANSFER PHOTOGRAPHIC PRODUCTS AND PROCESSES WITH A DEVELOPING COMPOSITION COMPRISING A DESENSITIZING AGENT

Edwin Land, Cambridge, Howard G. Rogers, Weston, and Richard W. Young, Wellesley Hills, Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed July 18, 1968, Ser. No. 745,749


Int. Cl. G03c 7/00, 5/54, 5/32

U.S. Cl. 96—3

18 Claims

The present invention relates to a composite photosensitive structure containing, as essential layers, in sequence, a dimensionally stable layer; a photosensitive direct negative silver halide emulsion layer having associated therewith a dye which is a silver halide developing agent and is processing composition soluble and diffusible as a function of the photosensitive silver halide emulsion layer's exposure and a silver halide desensitizing agent adapted to effect, subsequent to photoexposure, desensitization of the photosensitive silver halide emulsion layer without substantial detriment to the latent image carried by the emulsion layer; a polymeric layer dyeable by dye

diffusing thereto; a dimensionally stable layer transparent to actinic radiation; and to specified photographic diffu-



sion transfer processes employing such composite photo-sensitive structure.

3,579,334

DYE DEVELOPERS WHICH ARE NON-REVERSIBLY SPECTRALLY SHIFTED BY ALKALINE HYDROLYSIS IN COLOR DIFFUSION TRANSFER PROCESSES AND ELEMENTS


Ronald F. W. Ciecuch, Boston, and Myron S. Simon, Newton Center, Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Aug. 30, 1968, Ser. No. 756,481


Int. Cl. G03c 5/54, 7/00

U.S. Cl. 96—29


13 Claims



Transfer images in color are formed by exposing a photosensitive element containing a silver halide emulsion and a mono or disazo dye which contains not less than one or more than two groups selected from the group represented by the formulae.



wherein R is a lower alkyl group, said dyes also containing not less than one nor more than two dihydroxyphenyl silver halide developing radicals; permeating the photosensitive element with an aqueous alkaline processing composition, and deacylation of the



groups by hydrolysis to provide hydroxyl groups, thereby providing a non-reversible bathochromic shift of the spectral absorption characteristics of dye; immobilizing the dye as a result of the development of the exposed areas of the emulsion; and transferring, by diffusion, at least a portion of the imagewise distribution of dyes to a superposed image receiving layer to provide a positive dye image therein.

3,579,335

METHOD FOR MANUFACTURING COLOR TELEVISION RECEIVER TUBES

Michio Tamura, Kanagawa-ken, Japan, assignor to Sony Corporation, Tokyo, Japan

Continuation-in-part of application Ser. No. 540,671, Apr. 6, 1966, now Patent No. 3,437,482. This application Mar. 31, 1967, Ser. No. 627,521

Claims priority, application Japan, Apr. 2, 1966, 41/20,606

Int. Cl. G03c 5/00

U.S. Cl. 96—36.1

10 Claims

A method for manufacturing color television screens for cathode ray tubes comprising the steps of printing a shadow image of a post-deflection-focusing grid on a plate, positioning the optical mask relative to a face plate in accordance with a spurious pattern resulting from light interference, and forming color phosphors on the face plate.

3,579,336

PHOTOCHEMICAL RECORDING PROCESS

Eric Maria Brinckman, Mortsel, Walter August Van den Heuvel, Berchem, and Johan Eugene Vanhalst, Wilrijk, Belgium, assignors to Gevaert-Agfa N.V., Mortsel, Belgium

No Drawing. Filed Dec. 15, 1967, Ser. No. 690,799

Claims priority, application Great Britain, Dec. 15, 1966, 56,296/66, 56,297/66

Int. Cl. G03c 1/56, 1/58, 1/64

U.S. Cl. 96—49

10 Claims

Process of reproduction using a recording layer containing hexacyanoferrate (III) ions and a substance providing ions of selected metals, preferably an n-type photoconductor. The layer is exposed to an electromagnetic radiation image reducing the hexacyanoferrate (III) ions in the exposed regions to hexacyanoferrate (II) ions. The exposed layer is developed by contacting uniformly with an aqueous developing solution containing a dye intermediate which is oxidizable into a dye. The hexacyanoferrate (III) ions in the unexposed regions oxidize the dye intermediate and are in turn reduced to hexacyanoferrate (II) ions which combine with the metal ions to form a precipitate having a strong affinity for the dye oxidation product. If the exposure is through a positive original, a positive copy is obtained since the image areas of the original shield the corresponding areas of the recording layer from exposure. A layer containing photoconductive zinc oxide is especially preferred.

3,579,337

PHOTOCHEMICAL RECORDING METHOD BY MEANS OF HEXACYANOFERRATE(III)

Eric Maria Brinckman, Mortsel, Johan Eugene Vanhalst, Wilrijk, and Walter August Van den Heuvel, Berchem, Belgium, assignors to Gevaert-Agfa N.V., Mortsel, Belgium

No Drawing. Filed Dec. 15, 1967, Ser. No. 690,800

Claims priority, application Great Britain, Dec. 15, 1966, 56,294/66, 56,295/66

Int. Cl. G03c 1/52, 1/58, 1/64

U.S. Cl. 96—49

12 Claims

Process of reproduction using a recording layer containing hexacyanoferrate(III) ions and a substance providing ions of selected metals. The layer is exposed to an electromagnetic radiation image reducing the hexacyanoferrate(III) ions to hexacyanoferrate(II) ions which react

with the metal ions to form a precipitate having a strong attraction for a cationic dye. The exposed layer is developed by contracting uniformly with a developing solution containing the cationic dye.

3,579,338

PROCESS FOR MAKING METAL-GLOSSY IMAGES AND PROJECTION USING THE SAME

Shingo Ooue and Hiroyuki Ueda, Saitama, and Yoshihide Hayakawa, Ashigara-Kamigun, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Feb. 14, 1968, Ser. No. 705,456

Claims priority, application Japan, Feb. 14, 1967, 42/9,421

Int. Cl. G03c 5/26, 5/24; G03b 27/54, 27/76

U.S. Cl. 96—50

15 Claims



A projection process which comprises subjecting a silver halide image to a sulfiding treatment, treating the image thus treated with a solution containing a solvent for silver halide to provide a metal-glossy image, applying to the surface of the metal-glossy image an illuminating light beam for transmission and an illuminating light beam for reflection, combining the penetrating light beam and the reflected light beam, and projecting on a screen the combined light beam to provide a projected image having various contrasts. A process for making a metal-glossy image which comprises subjecting a silver halide image to a sulfiding treatment and then treating the image thus treated with a solution containing a solvent for silver halide.

3,579,339

PHOTOPOLYMERIZABLE DISPERSIONS AND ELEMENTS CONTAINING NONMIGRATORY PHOTOREDUCTIBLE DYES

Catherine Teh-lin Chang, New Brunswick, and Peter Walker, Red Bank, N.J., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed May 23, 1967, Ser. No. 640,496

Int. Cl. G03c 1/76, 3/00, 1/68

U.S. Cl. 96—74

12 Claims

A photopolymerizable dispersion and layers comprising a continuous phase with an organic macromolecular polymer dispersion medium (e.g., gelatin) and a dispersed phase including an addition polymerizable ethylenically unsaturated compound (e.g., a monomer such as pentaerythritol triacrylate, and at least one of the ingredients of a color image-yielding composition (e.g., a photographic color former) in reactive association with a photoinitiator mixture comprising (a) a nonmigratory, photoreducible dye, e.g., Methylene Blue having the four methyl radicals replaced by butyl radicals, and (b) a free-radical producing agent, e.g., N-phenylglycine.

3,579,340

ISOLATING ACIDIC MATERIALS FROM A THIN FILM EVAPORATE


Rudolf G. K. Strobel, Colerain Township, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

Filed May 8, 1969, Ser. No. 822,943

Int. Cl. A23f 1/08, 1/04

U.S. Cl. 99—71

17 Claims



Coffee flavor present in a thin film evaporate consists of both beneficial and detrimental flavor constituents. Disclosed is a process of separating beneficial constituents from detrimental constituents by an acid/base liquid/liquid extraction process. The thin film evaporate is separated into acid fractions, a basic fraction and a neutral fraction. The basic and neutral fractions are detrimental and are discarded. The acidic fractions are beneficial and are added back to dry soluble coffee to provide improved flavor.

3,579,341

PULPY TEXTURED FOOD SYSTEMS CONTAINING INHIBITED STARCHES

Paolo C. Trubiano, Somerville, and Nicholas G. Marotta, Green Brook, N.J., assignors to National Starch and Chemical Corporation, New York, N.Y.

No Drawing. Filed May 7, 1969, Ser. No. 822,722

Int. Cl. A231 1/00, 1/10, 1/40

U.S. Cl. 99—83

5 Claims

A method for the preparation of starch containing food products exhibiting a grainy, pulpy texture, as well as the food products thus prepared, said method comprising the step of admixing the non-starch ingredients of said food product with an amylose-containing starch product which has been inhibited by reaction with a crosslinking agent, then precooked, gelatinized, and pulverized to within a certain particle size range, and thereafter heating the resulting mixture at a temperature of at least about 160° F. so as to effect the swelling of the starch particles therein.

3,579,342

LEUCO TRIARYLMETHANE/HEXAARYLBIMIDAZOLE COLOR FORMING SYSTEM CONTAINING A DEACTIVATOR

Peter S. Strilko, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed June 27, 1968, Ser. No. 740,476

Int. Cl. G03c 1/72

U.S. Cl. 96—90

14 Claims

A photoimaging and photodeactivatable composition of (A) A salt of a leuco triarylmethane and a salt-forming acid; (B) A hexaarylbiimidazole which absorbs principally in the ultraviolet region and is a photooxidant for the salt

of the leuco triarylmethane present in an amount of from about 1 to 2 moles per mole of said salt of the leuco triarylmethane;

(C) 1,6-pyrenequinone or 1,8-pyrenequinone or both, present in an amount of from about .04 to .4 mole per mole of hexaarylbiimidazole;

(D) A visible light-absorbing carbonyl compound selected from 9,10-phenanthrenequinone, perinaphthenone, or 4-methoxy-1,2-naphthoquinone; present in an amount of from about .05 to 2 moles per mole of hexaarylbiimidazole; and

(E) An ether containing at least one oxymethylene group wherein the methylene bears at least one hydrogen; present in an amount providing from about 50 to 500 oxymethylene groups per mole of the combined quinone components (C) and (D).

3,579,343

PHOTORESIST-FORMING COMPOSITIONS


Motoo Kogure and Shoichiro Hoshino, Tokyo, Japan, assignors to Konishiroku Photo Industry Co., Ltd.
No Drawing. Filed Apr. 16, 1968, Ser. No. 721,621
Claims priority, application Japan, Apr. 25, 1967, 42/25,988

Int. Cl. G03c 1/70, 1/72

U.S. Cl. 96—90R

2 Claims

A photoresist-forming composition comprising a photo activator having a polychlorinated or polybrominated methyl group capable of forming a free radical by the action of light and a homopolymer or a co-polymer with other vinyl monomer, of a monomer represented by the general formula



wherein A is a hydrogen atom, a carboxylic acid or carboxylic acid amide; X is $-\text{COOCH}_2\text{CH}_2-$,

$-\text{CONHCH}_2\text{CH}_2-$

$-\text{COSCH}_2\text{CH}_2-$, $-\text{CONH}-$, $-\text{CH}_2-$, $-\text{SO}_2\text{NH}-$, $-\text{SO}_2\text{O}-$, $-\text{CONH}-$; R_1 is a hydrogen atom or a lower alkyl group; R_2 is a hydrogen atom, a lower alkyl group or a substituted or unsubstituted phenyl group; and R_3 and R_4 are individually a hydrogen atom or a lower alkyl group, provided that in the case of the Formula II, R_2 and R_3 may form a heterocyclic ring together with nitrogen and the benzene ring, and R_3 and R_4 may form a naphthalene ring together with the benzene ring.

3,579,344

NOVEL DYES AND DIRECT POSITIVE PHOTOGRAPHIC EMULSIONS

Frank G. Webster, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Sept. 8, 1967, Ser. No. 666,512

Int. Cl. G03c 1/08

U.S. Cl. 96—139

18 Claims

Novel merocyanine and oxonol dyes are provided which feature a 3-arylamino or a 3-lower fatty acid

amido substituted 2-pyrazolin-5-one nucleus. Merocyanine dye salts of the invention sensitize direct positive photographic silver halide emulsions.

3,579,345

DIRECT POSITIVE EMULSIONS SENSITIZED WITH PYRYLIUM AND/OR THIAPYRYLIUM SALTS

Jean E. Jones, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Continuation-in-part of abandoned application Ser. No. 609,762, Jan. 17, 1967. This application Oct. 2, 1967, Ser. No. 671,971

Int. Cl. G03c 1/08, 1/28

U.S. Cl. 96—102

19 Claims

Pyrylium, thiapyrylium or selenapyrylium salts are incorporated in direct positive photographic silver halide emulsions.

3,579,346

SILVER HALIDE EMULSIONS WITH DYES CONTAINING A PYRYLIUM NUCLEUS JOINED TO A PYRAZOLE NUCLEUS

Leslie G. S. Brooker, Donald W. Heseltine, and Daniel S. Daniel, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Mar. 25, 1968, Ser. No. 715,530

Int. Cl. G03c 1/10; C09b 23/10

U.S. Cl. 96—106

32 Claims

Novel photographic methine dyes are provided which feature a pyrylium nucleus joined, by a methine chain, to a pyrazole nucleus or a nitro substituted nucleus of the type used in cyanine dyes. Light sensitive silver halide emulsions are also provided comprising the novel dyes of this invention.

3,579,347

SILVER HALIDE EMULSION CONTAINING WATER-SOLUBLE POLYMER

Henry Walter Wood, Ilford, England, assignor to Ilford Limited, Ilford, Essex, England

No Drawing. Filed June 10, 1969, Ser. No. 832,021
Claims priority, application Great Britain, June 14, 1968, 28,394/68

Int. Cl. G03c 1/28, 1/72

U.S. Cl. 96—114

6 Claims

This application describes photographic material which comprises a gelatino silver halide emulsion layer the photographic material being characterized in that there is present in the said emulsion layer or in a layer in operative contact with the said emulsion layer a water-soluble homopolymer of a compound of the general formula:



where R_1 and R_2 are each hydrogen atoms or alkyl groups and X is an anion, or a water-soluble copolymer thereof with minor amounts of other ethylenically unsaturated monomers.

3,579,348

DIRECT-PRINT SILVER HALIDE EMULSIONS

Delbert Dale Fix and Richard Warren Karlson, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Oct. 21, 1966, Ser. No. 588,342

Int. Cl. G03c 1/08, 1/10, 1/28

U.S. Cl. 96—126

14 Claims

Direct-print silver halide emulsions comprising the combination of a urazole halogen acceptor and a merocyanine dye having carboxy-containing substituents thereon provide improved photographic systems having better image properties such as, for example, improved image discrimination upon storage.

3,579,349

PREPARATION OF CHOCOLATE EXTRACT

Abraham R. Mishkin, Richard D. Martin, and Joseph L. Ohler, Marysville, Ohio, assignors to Societe d'Assistance Technique pour Produits Nestle S.A., Lausanne, Switzerland

No Drawing. Filed Aug. 19, 1968, Ser. No. 753,779

Int. Cl. A23g 1/00

U.S. Cl. 99—23

7 Claims

A chocolate extract is prepared by steam-stripping a mixture of water and cocoa liquor to remove and recover aromatic constituents, heating the stripped mixture, separating the aqueous phase containing the water-soluble constituents and adding the recovered aromatics.

3,579,350

BEVERAGE TAPE


Lloyd K. Rudd, Berwyn, and George R. Schollhamer, Philadelphia, Pa., assignors to Rudd-Melikian, Inc., Warminster, Pa.

Filed Apr. 7, 1967, Ser. No. 629,138

Int. Cl. B65b 29/02

U.S. Cl. 99—77.1

4 Claims



Beverage tape consisting of a pair of water permeable strips encapsulating within cavities pods of beverage material. The cavities are interconnected by flat web portions and are located within one of the strips so that substantially all of the beverage material is positioned on one side of the web. The pods are of elongated plan shape with its major axis extending transversely to the length of the strips. The pods act to self-position the tape within a brewing machine.

3,579,351

COFFEE POWDER PACKAGE

Hans Wege, Hanau-Hobe Tanne, and Eric Gast, Frankfurt, Germany, assignors to Firm Wilhelm Kuhn, Hanau, Germany


Filed Jan. 17, 1969, Ser. No. 791,980

Claims priority, application Germany, Aug. 5, 1968, K 61,973

Int. Cl. B65d 65/00

U.S. Cl. 99—77.1

1 Claim



A filter paper bag has an open top end and is partly filled with coffee powder. A flanged plate is secured to said open top end and laterally outwardly protrudes

therefrom and is formed with an aperture which communicates with the interior of said bag. A cover closes the aperture. The filter paper bag is entirely enclosed by an aroma-tight wrapper bag.

3,579,352

EXTRUDER-COOKED CEREAL ENDOSPERM PARTICLES AND INSTANT BEVERAGE MIXES COMPRISING THE SAME

George N. Bookwalter, Peoria, Howard F. Conway, Pekin, and Edward L. Griffin, Jr., Peoria, Ill., assignors to the United States of America as represented by the Secretary of Agriculture

No Drawing. Filed Oct. 31, 1968, Ser. No. 772,380

Int. Cl. A23l 1/00, 1/10

U.S. Cl. 99—78

4 Claims

Cereal grain endosperms having a moisture content of 10–20% are heated at 325–400° F. in a screw-type extruder at a pressure of 2000–4000 p.s.i. The ejected material is milled to provide a cold water soluble product which is combined with soybean flour, nonfat dry milk solids, sugar, salt, minerals and vitamins to form an instant beverage mix.

3,579,353

FOOD PRODUCTS CONTAINING ALKYL-SUBSTITUTED PYRAZINES

Gunther M. Nakel and Brinton Marlo Dirks, Springfield Township, Hamilton County, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed Oct. 23, 1967, Ser. No. 677,030

Int. Cl. A23l 1/18, 1/22

U.S. Cl. 99—81

4 Claims

Food products are made more flavorful by adding 0.15–10,000 p.p.m. of alkyl-substituted pyrazines, especially those having molecular weight less than 140.

3,579,354

PREPARATION OF AN ELASTIC CHEESE PRODUCT

Robert L. Kasik and Anthony J. Luksas, Chicago, Ill., assignors to Beatrice Foods Co., Chicago, Ill.

No Drawing. Filed Aug. 1, 1968, Ser. No. 749,309

Int. Cl. A23c 19/02

U.S. Cl. 99—116

12 Claims

An elastic cheese product is made by inoculating sodium caseinate containing butterfat with lactic acid organisms in aqueous medium, then inoculating with a micrococcus, fermenting aerobically until the system becomes elastic and plastic, then acidifying the pH 4.5 and drying.

A bland product can be prepared by growing trained *Streptococcus lactis* and/or micrococci on aqueous sodium caseinate, acidifying, removing the liquid, resuspending with aid of alkali to pH 6–7 and drying.

3,579,355

MULTILAYERED GELATIN CONTAINING DESSERTS

Clement R. Wyss, Scarsdale, Robert Cassanelli, Yorktown Heights, and Joseph Russo, Irvington, N.Y., assignors to General Foods Corporation, White Plains, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 783,738, Dec. 13, 1968. This application Oct. 22, 1969, Ser. No. 868,578

Int. Cl. A23l 1/04

U.S. Cl. 99—130

8 Claims

Dry composition comprising a combination of gelatin and fat, sugar and an emulsifier for the fat which upon successive whipping with water at various temperatures produces a 2 or 3 layered multitextured gelatin dessert when the product cools.

3,579,356 TITANIUM DIOXIDE WHITENED COMESTIBLE COMPOSITIONS

Donald E. Miller, Oak Park, and Cecelia R. Gilmore, Oak Lawn, Ill., assignors to SCM Corporation, Cleveland, Ohio

No Drawing. Filed Apr. 24, 1968, Ser. No. 723,920
Int. Cl. A23l 1/27

U.S. Cl. 99—148 8 Claims
Compositions comprising comestible base and a blend of TiO_2 , and an edible organic nitrogen-containing, sulfur containing, or sulfur and nitrogen containing edible organic compound are described.

The compositions are advantageous in that they make possible comestible products of enhanced whiteness or lightness of color. The compositions are further advantageous in that TiO_2 which is a relatively dense material does not settle but remains dispersed in the compositions.

3,579,357 FOODSTUFFS CONTAINING AN ANTIOXIDANT

Hirotochi Samejima, Machida-shi, Tokyo-to, Kiyoshi Nakayama, Sagami-hara-shi, and Yuji Nagano, Machida-shi, Tokyo-to, Japan, assignors to Kyowa Hakko Kogyo Kabushiki Kaisha, Tokyo-to, Japan

Filed Jan. 15, 1968, Ser. No. 697,771
Claims priority, application Japan, Jan. 16, 1967, 42/2,731

U.S. Cl. 99—154 3 Claims
There are provided compositions comprising at least one substance susceptible to oxidation by atmospheric air and a compound of the formula



wherein R represents a hydrogen atom or a lower alkyl group and n is 2 or 3. The oxidation of the substance is greatly inhibited.

3,579,358 METHOD OF PREPARING AN EDIBLE TUBULAR COLLAGEN CASING

Albert Courts, Solihull, England, assignor to Lever Brothers Company, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 810,917, Mar. 24, 1969, which is a continuation of application Ser. No. 463,021, June 10, 1965. This application Nov. 26, 1969, Ser. No. 880,436
Int. Cl. A22c 13/00

U.S. Cl. 99—176 31 Claims
Collagen is chemically modified by treatment with a strong alkali in the presence of an alkali metal salt capable of preventing swelling of the collagen. The collagen is then swollen and formed into a dough and is extruded into a precipitating bath to form a tubular casing, particularly a sausage casing.


3,579,359 METHOD FOR PRODUCTION OF DEEP FROZEN FISH PRODUCTS

Eiler Schjolberg, Reinslettveien 32, Bodo, Norway

Filed Mar. 26, 1968, Ser. No. 716,055
Claims priority, application Norway, Apr. 5, 1967, 167,593

U.S. Cl. 99—195 3 Claims
The invention relates to a method for production of foodstuffs in the form of deep frozen, shaped products, for example, the so-called fish sticks, grill fingers, breaded portions and similar substantially processed products, produced from fish or other raw materials, in which the raw material is ground to a mass consisting of grain size particles, formed into a band-like product and frozen to a

consistency and temperature suitable for portioning, whereafter portioning into shaped portions is carried out



and the said products are further frozen to the desired keeping temperature.

3,579,360 LYOPHILISING A CARBON DIOXIDE SOLUTION

Louis René Rey, St.-Legier, Switzerland, Monick Dousset, Paris, France, and Françoise Chaffard, Vevey, Switzerland, assignors to Societe d'Assistance Technique pour Produits Nestle S.A.

No Drawing. Filed July 6, 1967, Ser. No. 651,378
Claims priority, application Switzerland, July 8, 1966, 10,054

U.S. Cl. 99—199 5 Claims
Porous composite materials, consisting of a continuous phase and a disperse phase in intimate association with the continuous phase may be obtained by the application of freeze-drying techniques. The materials may be prepared either by freeze-drying a first solution, impregnating the dry material with a second solution and again freeze-drying, or by freeze-drying a system consisting of two solutes dissolved in different solvents which may be immiscible. Freeze-drying of both aqueous and non-aqueous systems is envisaged.

3,579,361 VISCIOUS LIQUID MATERIAL AND PROCESS FOR MAKING SAME

Joseph E. Blaze, Jr., Beaver, Pa., assignor to The Babcock & Wilcox Company, New York, N.Y.

No Drawing. Filed Apr. 22, 1969, Ser. No. 818,446
Int. Cl. C09d 5/08

U.S. Cl. 106—14 2 Claims
A viscous liquid material prepared by adding acetic acid to an aqueous solution containing aluminum chloride and a solidification inhibitor acid, and then concentrating the resultant solution at a temperature below its boiling point until it attains a selected viscosity within the range 2 to 20 poises. The inhibitor acid can be either boric acid, phosphoric acid or a mixture of both these acids. Colloidal silica can be added to the solution before final concentration to make a product containing dispersed silica.

3,579,362 DIELECTRIC $3\text{NiO} \cdot \text{X}_2\text{O}_3 \cdot 6\text{TiO}_2$ COMPOSITIONS

Russell G. West, Alexandria, Va. (% Trans-Tech, Inc., 12 Meem Ave., Gaithersburg, Md. 20760)

No Drawing. Filed Oct. 20, 1969, Ser. No. 867,910
Int. Cl. C04b 33/00

U.S. Cl. 106—39 7 Claims
The ceramic dielectric composition of about 30 mole percent NiO , about 10 mole percent of Al_2O_3 , Fe_2O_3 or mixtures thereof, and about 60 mole percent TiO_2 is disclosed. The composition is a high dielectric constant value, stable, passive, low loss dielectric medium which may be used in microwave device applications.

3,579,363 PLASTICIZED RESIN COMPOSITIONS

James K. Sears, Webster Groves, Mo., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Nov. 19, 1968, Ser. No. 777,165
Int. Cl. C08b 27/52

U.S. Cl. 106—176 23 Claims
This invention relates to the use of certain phthalimidoacetates as plasticizers for thermoplastic resins.

3,579,364 PLASTICIZED RESIN COMPOSITIONS

James K. Sears, Webster Groves, Mo., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Nov. 21, 1968, Ser. No. 777,913
Int. Cl. C08b 27/52

U.S. Cl. 106—176 21 Claims
This invention relates to the use of certain bisphthalimidoacetates as plasticizers for thermoplastic resins.

3,579,365 COMPOSITIONS FOR AND METHODS OF IMPROVING ADHESION OF PLATED METAL ON PLASTIC SUBSTRATES

John J. Grunwald, New Haven, and Eugene D. D'Ottavio, Thomaston, Conn., assignors to MacDermid Incorporated, Waterbury, Conn.

No Drawing. Filed June 14, 1967, Ser. No. 645,901
Int. Cl. C08h 9/00; B01j 13/00

U.S. Cl. 106—265 8 Claims
A method of and composition for promoting adhesion between plated metal and a plastic substrate, in which the active agent is provided in finely divided dispersed or colloidal aqueous emulsion form. The active agents are any of a group of low molecular weight organic unsaturated compounds of the fatty acid type, and more especially of the group of naturally occurring products such as linseed, tall, tung and castor oils, turpentine and similar wood rosins. These, when dispersed in water to provide stable emulsions, are used as a pretreatment bath for plastic substrates, prior to plating of the substrate, in order to promote the formation of a stronger bond between the metal plate and substrate.

3,579,366 GRANULATED ADDITIVE, METHOD OF MAKING THE SAME, AND CEMENTITIOUS GROUT AND CONCRETE COMPOSITIONS CONTAINING THE SAME

Solomon J. Rehmar, East Cleveland, Ohio, assignor to Intrusion-Prepakt, Cleveland, Ohio

No Drawing. Filed July 12, 1968, Ser. No. 744,303
Int. Cl. C04b 21/02, 31/40

U.S. Cl. 106—314 6 Claims
As an additive for cementitious grout and concrete, a porous granule characterized by a skeletal structure and a network of interstitial voids formed by in situ gas liberation, the skeletal structure consisting essentially of a dispersion of finely divided, substantially oxide free aluminum particles in a matrix formed of a powdered inorganic extender and a water soluble binder which is inert with respect to the aluminum particles.

3,579,367 METHOD OF METALLIZING A LUMINESCENT SCREEN

Himanshu M. Patel, Pine City, N.Y., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Nov. 22, 1968, Ser. No. 778,260
Int. Cl. H01j 31/20

U.S. Cl. 117—33.5 3 Claims
This invention relates to luminescent screens and to the application of a metallic backing layer thereon. More particularly, this invention describes a method of depositing a double coating of an organic heat removable ma-


terial over the phosphor in the luminescent screen for the purpose of providing a smooth substrate upon which the metallic backing layer may be deposited.

3,579,368 SIMULATED SLATE AND METHOD FOR MAKING THE SAME

Eugene Bleiweiss, Maywood, N.J., assignor to Metaframe Corporation

Filed July 1, 1968, Ser. No. 741,487
Int. Cl. C03c 17/00

U.S. Cl. 117—54 12 Claims



Simulated slate, particularly suitable for use as an aquarium bottom, made by subjecting both sides of a sheet of glass to treatment which will render said sides in a nonsmooth or discontinuous surface, and thence applying an opaque coating to one of the discontinuous surfaces thereof.

3,579,369 WOOD MEMBERS IMPREGNATED WITH SYNTHETIC ORGANIC RESINS AND METHOD OF PRODUCING SUCH IMPREGNATED MEMBERS

Newton C. Foster, Pittsburgh, Pa., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

No Drawing. Filed June 26, 1968, Ser. No. 740,098
Int. Cl. B44d 1/28; B27k 3/36

U.S. Cl. 117—57 9 Claims
A method of making a synthetic organic resin impregnated wood member wherein the wood is pretreated with an activator, such as dimethyl aniline, in the vapor phase. A synthetic organic liquid resinous composition containing, for example, styrene and an unsaturated polyester catalyzed with benzoyl peroxide is then impregnated into the wood at about room temperature causing the resin to polymerize within the wood.

3,579,370 COMPOSITE LAYERED TETRAHALOETHYLENE STRUCTURE

John Oliver Punderson and Miguel Jacinto Roura, Wilmington, Del., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

Continuation-in-part of abandoned application Ser. No. 687,691, Dec. 4, 1967. This application Oct. 1, 1969, Ser. No. 862,829

U.S. Cl. 117—72 13 Claims



A coating is provided which is self-adherent to a surface of tetrahaloethylene polymer, e.g., polytetrafluoroethylene, to make the polymer surface either more print-

able or to serve as an adhesive for a coating, e.g., polyvinylidene fluoride, which protects the polymer surface. In one embodiment, the coating comprises a blend of 10 to 90 percent by weight of a copolymer of tetrafluorethylene hexafluoropropylene and the remainder, to total 100 percent, of polyvinylidene fluoride.

the atmosphere, the condensible volatiles moving from the high temperature lower portion condense in the upper portion and are prevented from being moved into the atmosphere. The ingredients of the pack include an anti-fusing agent, a metal source component, halide of the metal source component, and barium chloride.

3,579,371

BARRIER STRUCTURE FOR PACKAGING PURPOSES

Joseph A. Dooley, Cedar Grove, and Michael J. Gnozzio, Lincoln Park, N.J., assignors to Immount Corporation
No Drawing. Filed May 22, 1968, Ser. No. 731,319
Int. Cl. B32b 29/06, 23/08; B44d 1/14

U.S. Cl. 117-76

3 Claims

A packaging structure comprising a cellulosic substrate carrying a subcoating of a polyvinylidene chloride resin and a topcoating consisting of a blend of an alkyd resin and an amine-aldehyde resin.

3,579,372

DEPOSITION OF MICROPOROUS FILM EMPLOYING DIELECTRIC HEATING

Lawrence W. Healy, Glen Rock, N.J., assignor to Genset Corporation, Newark, N.J.
Filed Dec. 4, 1968, Ser. No. 780,987
Int. Cl. B44d 1/50, 1/092

U.S. Cl. 117-93.1

6 Claims

Describes procedure for deposition of microporous grain layer in and on a substrate for the production of leather replacement products in which a substrate which is coated with a solution of a polymer and wetted with water is exposed to dielectric heating to vaporize the water. The vapors mix with the organic solution and effect deposition of the polymer.


3,579,373

CARBIDING

Vernon J. Pingel, 812 W. Grove St., Arlington Heights, Ill. 60005
Filed Oct. 18, 1968, Ser. No. 768,836
Int. Cl. C23c 11/08

U.S. Cl. 117-106

4 Claims



A method of applying a carbide coating to a surface of an article having 0.5% or more carbon which includes imbedding the article in a packed bed which has an upper portion at a lower temperature and in communication with

3,579,374


SHEET SUPPORTED ARTICLES COATED WITH HEAT-ACTIVABLE TANNING AGENTS AND IMPROVED METHODS OF HARDENING SAID ARTICLES AND RELATED COMPOSITIONS

René Jean Dennilauler, Maurice Edgar Pfaff, and Pierre Amédée Roman, Vincennes, France, assignors to Eastman Kodak Company, Rochester, N.Y.
No Drawing. Filed June 26, 1967, Ser. No. 649,435
Claims priority, application France, June 28, 1966, 67,164

Int. Cl. C09d 3/04; C08h 17/62
U.S. Cl. 117-164

16 Claims

Tanning (hardening) agents in a colloid layer of gelatin or the like are inactive at ordinary temperatures but are activated at temperatures above 70° C. to rapidly tan the colloid in which they are incorporated. Suggested uses are in thermography and photography. Specific examples describe various gelatin layers containing the heat-activated hardeners. The class of useful tanning agents is described by the formula



wherein the substituents R and R' are selected from hydrogen and halogen atoms and alkyl, carboxyl, alkoxy, formyl, tertiary amino and sulfo radicals. Some specific new compounds of this class are described.


3,579,375

METHOD OF MAKING OHMIC CONTACT TO SEMICONDUCTOR DEVICES

Edmund Wonilowicz, Englishtown, and Henry F. Machnac, Somerville, N.J., assignors to RCA Corporation
Filed Oct. 18, 1968, Ser. No. 768,719
Int. Cl. B44d 1/14

U.S. Cl. 117-212

4 Claims



A method of making ohmic contacts to a semiconductor device wherein aluminum is deposited on at least one of several contact areas on the semiconductor body, nickel is deposited electrolessly simultaneously on the aluminum layer and on a contact area not covered with aluminum, the nickel layer being built up in a series of

separate depositions, the nickel is sintered after each deposition and solder is finally deposited on all the nickel surfaces.


3,579,376

METHOD OF FORMING A RESIST PATTERN ON A CIRCUIT BOARD OR THE LIKE

George E. Vincent, Jr., Bethel, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.
Filed July 23, 1968, Ser. No. 746,951
Int. Cl. H05k 3/00

U.S. Cl. 117-212

5 Claims



A method of applying a resist coating to the surface of a circuit board or the like having a plurality of holes therethrough in which the board is assembled over an opening in a pressurized fixture with the periphery of the board in fluidtight relationship with the periphery of the opening to cause the pressurizing fluid to flow through the holes and outwardly of the exposed surface of the board. Under these conditions, a coating of resist is applied to the exposed surface in any suitable manner known to the art with the fluid flowing through the holes preventing the flow of resist into the holes and keeping the holes open. At locations at which the board has relatively large holes, posts or pins on the fixture extend upwardly through the central portions of the openings to the surface of the board, the size of the posts being such as to fill the centers of the holes while leaving annular spaces therearound for the flow of fluid.


3,579,377

METHOD OF PRODUCING TIN OR TIN-ALLOY COATED COPPER JUMP WIRE BY MEANS OF HOT METALIZING

Horst Schreiner, Nuremberg, and Helmut Ohmann, Erlangen, Germany, assignors to Siemens Aktiengesellschaft, Berlin and Munich, Germany
Filed Apr. 25, 1968, Ser. No. 724,012
Claims priority, application Germany, Apr. 29, 1967, S 109,665

Int. Cl. B44d 1/44; C23c 1/04
U.S. Cl. 117-217

7 Claims



Described is a method of producing copper wire, uniformly coated around its periphery with tin or a predominantly tin-containing alloy, by hot metalizing. In this method a scraping die is placed at such a distance from the surface of the bath of tin or a predominantly tin-containing alloy, that the scraping die is positioned just within the solidification range of the bath component.


3,579,378

METHOD OF COATING AN ELECTRIC DISCHARGE DEVICE

Walter T. Millis, Owensboro, Ky., assignor to General Electric Company
Division of application Ser. No. 531,082, Mar. 2, 1966, now Patent No. 3,465,196. Continuation-in-part of application Ser. No. 302,490, Aug. 9, 1963. This application Nov. 12, 1968, Ser. No. 798,830

Int. Cl. C23d 5/04
U.S. Cl. 117-229

1 Claim



A method of making an electric discharge device having a vitreous coating on the interior of the envelope is described. The vitreous coating inhibits the release of occluded gases from the envelope which upon release would adversely affect the operation and life of the device.

3,579,379

PROCESS FOR PRODUCING CONDUCTORS INSULATED WITH POLYETHYLENE TEREPHTHALATE

Franciscus C. A. A. van Berkel, 8 Deerfield Road, Asheville, N.C., and Stanley F. Luques, Lakeview Drive, Columbia, Conn.
Filed Dec. 1, 1966, Ser. No. 598,276
Int. Cl. B44d 1/09, 1/18; C09d 3/48

U.S. Cl. 117-232

8 Claims



Process for producing insulated electrical conductors comprising applying a coating of polymeric ethylene terephthalate to electrical conductors, the improvement comprising (1) utilizing molten polyethylene terephthalate having an initial relative viscosity of at least 1.80 and containing from 0.01 to 5% by weight of a liquid crystallization promoting compound, (2) followed by cooling the coating and then (3) heating the cooled coating to a temperature of at least 100° C. to effect a crystallization of at least 15% in said polymeric coating. In the practice of this process, lengthy injection molding cycles and/or unduly long cooling cycles are avoided.

3,579,380

PROCESS FOR THE PRODUCTION OF XYLOSE SOLUTIONS

Hermann Friese, Hamburg, Germany, assignor to Sud-Chemie AG, Munich, Germany
No Drawing. Filed Dec. 4, 1969, Ser. No. 882,318
Int. Cl. C13k 9/00

U.S. Cl. 127-37

7 Claims

Xylose solutions free from crystallization-inhibiting substances are obtained, without any pre-treatment steps, from stone fruit shells such as of coconut, walnut and apricot, peach or plum pits by hydrolysis with aqueous mineral acids followed by separation from undissolved reaction residue and decolorizing.

3,579,381


AUTOMATIC BOBBIN AND PIRN CLEANING
Lawrence L. Bailey and Donel C. Autin, Columbia, S.C.,
assignors to Allied Chemical Corporation, New York,
N.Y.

Filed Oct. 25, 1968, Ser. No. 770,557

Int. Cl. B08b 1/02

U.S. Cl. 134—8

15 Claims



An improved method and apparatus for cleaning textile bobbins or pirns involving the steps of removal of merge disc, removal of metallic scale or dust from the core, and cleaning and drying of the exterior for surface of the bobbin or pirl as an automated combined operation wherein the sequence of continuous feed, merge disc removal, dry core cleaning and loading and discharge of the pirl or bobbin surface after cleaning and drying is an automatic, continuous and high-speed operation which is adapted to clean bobbins and pirns with a range of internal and external diameters and lengths.

3,579,382

SEALED CONTAINER FOR ELEMENTAL SODIUM


Harold A. Christopher, Scotia, N.Y., assignor to
General Electric Company

Filed Mar. 27, 1969, Ser. No. 811,014

Int. Cl. H01m 35/02

U.S. Cl. 136—20

2 Claims



An evacuated, sealed container for pure elemental sodium is disclosed which has an open-ended casing of an ionic conducting material sealed at one end with a high temperature ceramic plug by means of a high melting point sodium resistant glass, an electronic conductor in contact with the interior surface of the ionic conducting material and extending outwardly from the casing, and a seal at the other end of the casing. Such a container provides a suit-

able device for storing and dispensing pure elemental sodium, or provides a sodium electrode with an associated ionic conducting electrolyte. Methods are also described for forming evacuated, sealed containers for pure elemental sodium.

3,579,383

PROCESS FOR ACTIVATING METAL FOIL FOR USE AS A POSITIVE ELECTRODE IN ALKALINE STORAGE BATTERIES

Trevor Stanley Turner, Kidderminster, England, assignor to
The International Nickel Company, Inc., New York,
N.Y.

No Drawing. Filed July 16, 1969, Ser. No. 842,347
Claims priority, application Great Britain, Aug. 2, 1968,
37,995/68; Apr. 3, 1969, 17,617/69

Int. Cl. H01m 35/30, 43/04

U.S. Cl. 136—76

9 Claims

Process for activating a metal surface, e.g., nickel foil, for use as the positive electrodes in alkaline storage batteries, in which the foil is immersed in a bath containing a nickel ammine complex and then made the anode in an electrolytic treatment during which current is passed through the bath to deposit the battery active mass on the metal. A high capacity activated metal foil is also disclosed.

3,579,384

ELECTRIC CURRENT-PRODUCING CELLS
Sandors G. Abens, Philadelphia, Pa., assignor to
Honeywell Inc., Minneapolis, Minn.

No Drawing. Filed Mar. 19, 1969, Ser. No. 808,650

Int. Cl. H01m 17/02

U.S. Cl. 136—100

6 Claims

An improved current-producing cell system wherein the electrolyte comprises a solution of lithium-hexafluoroarsenate in methyl formate and the cathode is copper fluoride. The novel cell consists essentially of a lithium metal anode, a copper fluoride cathode, and an electrolyte solution of lithium-hexafluoroarsenate in methyl formate.

3,579,385

METHOD OF IMPREGNATING METALLIC FIBER BATTERY ELECTRODES

William Feduska, Edgeworth, and Jack T. Brown, Pittsburgh, Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.

Continuation of application Ser. No. 764,461, Oct. 2,
1968. This application Apr. 13, 1970, Ser. No. 28,179

Int. Cl. H01m 35/30, 43/04

U.S. Cl. 136—75

6 Claims

A method of loading active material into flexible, bonded, metallic fiber, porous battery plaques, by a plurality of molten salt impregnation and electrolysis steps, for use as positive and negative electrodes in cells and batteries, wherein the active material is conditioned by an intermediate charging and/or intermediate charging and discharging formation step. The conditioning step is between the loading steps and causes the active material, precipitated during electrolysis, to compact against and between the flexible metal fibers, opening the pores of the plaque and allowing additional loading at a high rate in subsequent impregnation-electrolysis steps.

3,579,386

INTERCELL CONNECTORS IN BATTERIES AND METHOD OF FORMING SAME

Ernest G. Tiegel, Redwood City, and Ralph G. Tiegel, San Carlos, Calif., assignors to Tiegel Manufacturing Co., Belmont, Calif.

Filed Oct. 22, 1965, Ser. No. 501,037

Int. Cl. H01m 13/10

U.S. Cl. 136—134

16 Claims

Leakproof electric storage battery intercell connectors passing through the cell divider wall, and method and

3,579,388

MODULAR THERMOGENERATOR

Paul Zahn, Ottobrunn, and Veit Merges, Munich, Germany, assignors to Bolkow Gesellschaft mit beschränkter Haftung, Ottobrunn, Germany


Filed Apr. 11, 1968, Ser. No. 720,662

Claims priority, application Germany, Apr. 29, 1967,
B 92,311

Int. Cl. G21h 1/10

U.S. Cl. 136—202

10 Claims



cementing material, which may be thermoplastic. Alternate forms are shown having a plurality of ridges and grooves in the upper and lower surfaces of the connector. The molding apparatus grips and inverts the battery case with the plates in place and then elevates a mold filled with molten lead into contact with the lugs of the plates to cast the connector onto the lugs and soften the cementing material. The mold is then chilled by fluid passing through an internal passageway and lowered away from the finished connector.

3,579,387

SEALED AQUEOUS ALKALINE ELECTROLYTE CELLS WITH CREEP BARRIERS


Peter R. Voyentzie and Robert J. Lehnen, Gainesville, Fla., assignors to General Electric Company

Filed Aug. 12, 1968, Ser. No. 751,968

Int. Cl. H01m 1/02

U.S. Cl. 136—163

2 Claims



A sealed cell having an aqueous alkaline electrolyte may be protected from leakage by interposing a creep barrier within the creep path of the electrolyte. Alpha, alpha-dihydroperfluoroacrylate polymers have been found to be superior creep barriers when used as an adherent layer intersecting the creep path. The creep barrier may be interposed between an O-ring seal and its seat in a vented cell construction.

3,579,390

METHOD OF MAKING A CERMET

T. O. Paine, Acting Administrator of the National Aeronautics and Space Administration, with respect to an invention of Alexis I. Kaznoff, Castro Valley, and Mickey O. Marlow, Livermore, Calif.

No Drawing. Filed Dec. 20, 1968, Ser. No. 785,780

Int. Cl. C21d 1/00


U.S. Cl. 148—126

6 Claims

A cermet in which ceramic particles dispersed in a metal matrix are uncoupled therefrom. The cermet is made by pressing metal coated ceramic particles in a die at a temperature sufficient to cause bonding of the metal coatings to one another. The cermet is then heat treated to mechanically uncouple the ceramic particles from the metal matrix whereby expansion of the cermet when heated is substantially the same as that of the metal matrix.

3,579,391
METHOD OF PRODUCING DIELECTRIC ISOLATION FOR MONOLITHIC CIRCUIT
 James Lang Buie, Panorama City, Calif., assignor to TRW Inc., Redondo Beach, Calif.
 Continuation-in-part of application Ser. No. 355,605, Mar. 30, 1964, now Patent No. 3,320,485. This application Jan. 5, 1967, Ser. No. 613,712
 Int. Cl. H01l 7/36
 U.S. Cl. 148—175

11 Claims



A microelectronic geometry and manufacturing process in which an electrode or region remote from the top surface of the substrate has a continuous portion deposited on the top surface to provide easier and better deposition or other emplacement of electrical contacts thereto. The method of producing dielectric isolation for one or more regions in the substrate includes the steps of cutting a groove in a semiconductor wafer surrounding the region to be isolated, establishing a highly conductive layer of semiconductor material on the top surface of the wafer and on all surfaces of the groove, establishing an insulating layer adjacent to the highly conductive layer, providing mechanical supporting substrate material to fill the groove and continue above the original top surface, and cutting off the original bottom portion along a line intersecting the bottoms of the groove and including the layer of conductive material on the bottom thereof so as to expose the insulating layer whereby when the wafer is inverted the exposed semiconductor material in the area surrounded by the groove will be dielectrically isolated by the insulating layer.


3,579,392
NITROGLYCERIN-NITROGLYCOL BLASTING COMPOSITION
 Bertil Petrus Enoksson, Gytorp, Sweden, assignor to Nitro Nobel Aktiebolag, Gytorp, Sweden
 Filed Nov. 27, 1968, Ser. No. 779,496
 Claims priority, application Sweden, Nov. 27, 1967, 16,275/67
 Int. Cl. C06b 1/04

U.S. Cl. 149—7 9 Claims
 This invention relates to blasting compositions comprising a blasting oil, an inorganic nitrate and certain desensitizing agents. These compositions are less dangerous to manufacture, less dangerous to handle, and less impact sensitive yet have the same heat of explosion and the same blasting strength as ordinary straight dynamites.

3,579,393
MONOPROPELLANT COMPRISING CERTAIN DI-FLUOROAMINO COMPOUNDS AND NITRIC ACID
 Barry D. Allau, Huntsville, Ala., assignor to the United States of America as represented by the Secretary of the Army
 No Drawing. Filed Jan. 28, 1963, Ser. No. 254,510
 Int. Cl. C06b 7/00

U.S. Cl. 149—74 9 Claims
 1. A liquid monopropellant composition comprising a

mixture of a difluoroamino substituted compound of the formula:




wherein R, R', R'', and R''' are each selected from the group consisting of alkyl, alkoxy, alkenoxy, carbalkoxy, carboxy, carbalkenoxy, alkanoyloxy, hydroxyalkyl, haloalkyl, alkoxyalkyl, and alkenyl, the total number of carbon atoms in R, R', R'', and R''' collectively not to exceed six and the total number of carbon atoms in each of R, R', R'', and R''' not to exceed four; and a white fuming nitric acid oxidant, the ratio of said acid oxidant to said difluoroamino substituted compound being from a trace amounting to 1.5 times the stoichiometric amount.

3,579,394
SOFT GROUND ETCHING METHOD
 Robert F. Nelson, 410 Monrovia Ave., Long Beach, Calif. 90814
 Filed Jan. 31, 1968, Ser. No. 705,882
 Int. Cl. C23f 1/02


U.S. Cl. 156—10 6 Claims
 In preparing a metal plate to produce a desired picture or other designs, a resistant material covers the plate against the action of acid, and these resistant materials, called soft ground, are picked off to bare the metal plate so that the plate will be etched by the acid. The soft ground is a sticky substance which will adhere to the pattern on a cover sheet extending over the metal plate, which is called the resist. The pattern on the cover sheet may be formed in many shapes, and the protruding pattern of the sheet will pick off spots or areas of the soft ground when the sheet is pressed into engagement with the soft ground by means of a manually operated stylus. Subsequent treatment of the metal plate with a suitable acid will etch the areas picked off by the sheet and thus form the outlines of the picture or other subject.

3,579,395
METHOD AND APPARATUS FOR FORMING A MULTI-PLY THERMOPLASTIC MOLDED ARTICLE
 Paul S. Rath, West Hartford, Conn., assignor to Monsanto Company, St. Louis, Mo.
 Continuation-in-part of application Ser. No. 158,643, Dec. 6, 1961. This application Jan. 17, 1967, Ser. No. 632,118
 Int. Cl. B32b 31/20
U.S. Cl. 156—94 8 Claims




A method and apparatus for forming a rigid, laminated thermoplastic article, by treating the surfaces of plastic sheets to render them hydrophilic, pressing the treated surfaces together to form a semi-rigid, block-bonded laminate, and molding the semi-rigid laminate to form the rigid article.

3,579,396
METHOD FOR PRODUCING ROLLED EDGE BOARD
 Robert L. Washburn, Whittier, and William J. Kruk, Fullerton, Calif., and William S. McDonald, Georgetown, S.C., assignors to International Paper Company, New York, N.Y.
 Filed Oct. 3, 1968, Ser. No. 764,815
 Int. Cl. B31f 5/00
U.S. Cl. 156—202 1 Claim



A method and apparatus for making strips of closed edge corrugated board with the edges of one facing sheet folded around the open ends of the corrugated core convolutions and secured to the other facing sheet from a sheet of single faced corrugated board, cut into strips.

3,579,397
PROCESS OF MANUFACTURING BAGS HAVING TEAR STRIPS AND CONSISTING OF SYNTHETIC THERMOPLASTICS
 August Schwarzkopf, Lengerich, Westphalia, Germany, assignor to Windmoller & Holscher, Westphalia, Germany
 Filed Aug. 7, 1967, Ser. No. 658,928
 Claims priority, application Germany, Aug. 16, 1966, W 42,222; June 20, 1967, W 44,214
 Int. Cl. B32b 31/10
U.S. Cl. 156—251 6 Claims




A tubing length portion corresponding to the length of the desired bag, and flat sheeting in a length portion corresponding to the desired width of the tear strip, are fed during each cycle of the machine between the jaws of a transverse heat sealing and cutting station, the width of the flat sheeting exceeds the width of the tubing by the length of the tear tab. A transverse heat-sealed seam joining the tubing walls and the flat sheeting is formed during the working stroke of the heat sealing and cutting device. A transverse severing cut is effected at the same time at a small distance from the heat-sealed seam and behind the same in the direction of travel.

3,579,398
METHOD OF CURLING THERMOPLASTIC RESIN FILM INTO PIPES AND CONSTRUCTING UP-HOLSTERY THEREWITH
 Yasuhiro Oshima, 860 Kashida, Hagasiosaka, Osaka Prefecture, Japan
 Filed July 23, 1968, Ser. No. 746,878
 Int. Cl. B32b 31/00


U.S. Cl. 156—250 4 Claims
 Method of forming a decorative plastic material in which a thin plastic material is thermally expanded and sealed to another thin plastic material on a heated surface

of a rotary cylinder to form a single laminated plastic film, which is simultaneously notched with a desired number of decorative patterns so that the notched portions



are curled to the side of the plastic material thereby supplying ornamental parts faster, easier and more economically, than prior art methods.

3,579,399
METHOD AND APPARATUS FOR ASSEMBLING A PLURALITY OF PAPER CUPS IN TRAY FORMATION AND GLUING THEM TOGETHER
 Albert L. Ehe, Jamaica Estates, N.Y., assignor to Multicup Automation Company, Inc., Long Island City, N.Y.
 Filed Nov. 22, 1968, Ser. No. 778,233
 Int. Cl. B31b 31/12; B32b 1/62
U.S. Cl. 156—293 6 Claims



A method of assembling a plurality of paper cups in tray formation and gluing them together in said assembled relation together with apparatus for carrying out the method. The method consists essentially of the steps of: arranging a plurality of paper cups in a series of tray units, each of a predetermined cup number and formation, moving said tray units through a gluing station at which the cups are held in position relative to one another; applying glue to engaging cup portions; and discharging finished trays. The apparatus comprises, as characteristic elements an endless conveyor; cup receiving plates carried by the conveyor; a gluing station including a supply of heated glue below the upper ply of the conveyor, devices for holding cups in position in the plates while glue is applied, and glue applying means in the form of a gang of upright pile coated wires; means for indexing the conveyor with a stepped motion; mechanism for operating the cups holding devices and glue applying means in proper relation to movement of the conveyor, and a block out device for rendering the gluing means ineffective on certain predetermined steps to provide trays in a separated state.

3,579,400

METHOD OF POSITIONING A MEMBRANE

Anthony J. Kanyok, East Hanover, and William H. Keller, New Brunswick, N.J., assignors to American Standard Inc., New York, N.Y.

Continuation of application Ser. No. 640,304, May 22, 1967. This application Dec. 8, 1969, Ser. No. 880,465
Int. Cl. B29c 19/00

U.S. Cl. 156—294

4 Claims



A resilient filtration membrane is inserted in a porous support tube by wrapping the membrane around a resilient tubular member, and holding the membrane in place around the tubular member while inserting the membrane and resilient tubular member into the porous support tube. The resilient member is expanded under fluid pressure and then returned to its normal state leaving the membrane against the interior wall of the porous support.

3,579,401

PROCESS FOR PRODUCING THERMAL INSULATING CARBONIZED FELT LAMINATED ASSEMBLIES

Roland Cauville and Andre Pernollet, Paris, and Gilberte Moutaud, Neuilly-sur-Seine, France, assignors to Societe le Carbone Lorraine, Paris, France

No Drawing. Filed June 30, 1967, Ser. No. 650,191
Claims priority, application France, July 26, 1966, 70,918

Int. Cl. C09f 5/00; C10b 49/00; F16l 59/00

U.S. Cl. 156—327

4 Claims

A low density carbon felt assembly for thermal insulation is made by arranging a number of layers of viscose rayon felt coated with a relatively small amount of furane resin, applying a very light pressure, e.g. about 5 g./cm.², polymerising at atmospheric conditions, and carbonising at a temperature of 900° to 1200° C. The layers may be stacked one upon another, or wound in approximately cylindrical layers one around the other. The carbonised product may be graphitised at 2400° to 3000° C. Thus, a thermal insulating carbonized or graphitized viscose rayon having a density of less than 0.485 gm./cm.³ is produced.

3,579,402

METHOD AND APPARATUS FOR PRODUCING FILAMENT REINFORCED TUBULAR PRODUCTS ON A CONTINUOUS BASIS

William B. Goldsworthy, Palos Verdes, and Ethridge E. Hardesty, Pine Valley, Calif., assignors to Goldsworthy Engineering, Inc.

Continuation-in-part of application Ser. No. 633,146, Apr. 24, 1967. This application Apr. 23, 1968, Ser. No. 723,554


Int. Cl. B65h 81/02

U.S. Cl. 156—392

19 Claims

A device for making filament reinforced tubular products in a continuous manner. The device includes a series of filament spools. Filaments from the spools are passed through a resin tank and around a fixed mandrel to form the longitudinal strands of the tube. The mandrel has substantially the same internal size and shape of the continuous tube to be produced. The mandrel extends through a plurality of helical filament wrap devices which are designed to apply opposing helically wound strands of filament upon the interspersed layers of longitudinal

strands. The mandrel extends also through a pair of circumferential filament wrap devices for laying outermost surface circumferential strands in opposite directions with respect to each other and superimposed upon the helical immediately preceding final strands. The several layers of such strands which have been wound on the fixed mandrel are urged into the R. F. curing zone on the mandrel which also extends into the curing zone. After the resin matrix has been cured, the finally formed and



cured tube is pulled from the mandrel by a pulling unit.

A number of embodiments are disclosed for making continuously wound pipe. In another embodiment, the device is mounted on a moving vehicle such as a boat where pipe which is continuously made is deposited from the moving vehicle. In an additional embodiment of the invention, a rectangular mandrel is employed for wrapping tube-like sections having a somewhat rectangular cross section, capable of being used in the construction of ladder rails and similar structural elements.

3,579,403

APPARATUS FOR MAKING COMPOSITE FILAMENT OR FIBER THERMOPLASTIC PRODUCTS


John Henry Stroop, New York, N.Y., assignor to Total Packaging, Inc., New York, N.Y.

Filed Dec. 16, 1966, Ser. No. 602,348

Int. Cl. B65h 51/16

U.S. Cl. 156—433

4 Claims



Paper is ordinarily produced by a Fourdrinier process and apparatus, and textile fabrics are produced by spinning and weaving. This invention has many of the advantages of each and utilizes a plurality of multi-product spinner nozzles. A plate on which the spinner nozzles are mounted is reciprocated so that filaments discharged from the plurality of spinner nozzles are overlaid and produce a thermoplastic fabric. The filaments are composed of more than one material and are called composite filaments.

A modification provides a box containing a plurality of cut fibers which are advanced by a carding loom picker. One of the substances described in the first alternative as discharged from the spinner nozzles is in this alternative sprayed onto a moving sheet which then proceeds through calendaring and desired embossing, perforating and printing rolls.

3,579,404

CUTTING AND SEALING UNIT


Robert J. Spitznagel, Cincinnati, Ohio, assignor to Phillips Petroleum Company

Filed Mar. 6, 1969, Ser. No. 804,846

Int. Cl. B32b 31/20; B65b 51/14, 51/30

U.S. Cl. 156—515

5 Claims



A cutting and sealing unit for plastic packaging machines. The unit comprises three relatively movable frames, two of which include gripping jaws and the third, a heat sealing and cutting knife.

3,579,405

MACHINE FOR INTERCONNECTING VENEER PANELS


John H. Crawford, Corvallis, Oreg., assignor to Leading Plywood, Corvallis, Oreg.

Filed Apr. 9, 1968, Ser. No. 719,972

Int. Cl. B32b 31/12, 31/10

U.S. Cl. 156—546

8 Claims



A machine for the application of continuous elements to a series of abutting veneer panels to interconnect contiguous panels for use in an article of manufacture. Means are disclosed for both conveying and positioning each of the panels into side-by-side relationship with an adjacent panel subsequent to which the continuous element is applied. Such means includes continuous belts disposed above and below the panels. The continuous elements disclosed is glue bearing and applied by wheels in rolling contact with the panels. For drying the glue bearing elements on said panels a directed air flow is provided.

3,579,406

HIGH SPEED PRECISION COMBINER

William H. Eburn, Jr., Stamford, and Charles T. Raymond, Westport, Conn., assignors to Selchow & Righter Company, Bay Shore, N.Y.

Filed July 25, 1968, Ser. No. 747,689


Int. Cl. B65c 9/08; B65h 1/22

U.S. Cl. 156—571

13 Claims

Apparatus for combining two sets of sheet material in a registered relationship to one another includes separate means for feeding each set of sheet material in synchronization with one another, a number of gripping mechanisms for grasping the individual sheets of a first material to transport it onto a rotating drum mechanism

wherein the gripping mechanisms accelerate from a position at rest to a speed substantially equal to the speed of rotation of the drum to deposit the first sheet material in a registered position thereon, a blanket mounted in registered position on the surface of the drum and having perforations for developing a vacuum to retain the individual sheet material, means for applying adhesive to the individual sheets of the material on said drum, means for combining the two sheets of material in aligned relationship to each other, and means connected with said drum to provide a positive blow-off pressure to said first sheet material at said means for combining. The



means for delivering the second sheet material includes a hopper for receiving and storing the material in vertically stacked relationship and means for sensing the height of the material to control the delivery of a second sheet material to the hopper. The delivery and hopper mechanisms are mounted on movable rails whereby those mechanisms can be elevated to disengage the second sheet material from a feeding mechanism in the absence of second sheet material. The delivery means for the second sheet material has a speed control which is regulated to prevent damage of the second sheet material when it is engaged by the driving means and when the second material is delivered to the means for combining.

3,579,407

MACHINE FOR HEAT SEALING CONTINUOUSLY MOVING WORK-MATERIAL SHEETING IN THE MANUFACTURE OF BAGS OF PLASTICS MATERIALS

Kurt Rochla, Lengerich, Westphalia, Germany, assignor to Windmoller & Holscher, Westphalia, Germany


Filed Aug. 15, 1968, Ser. No. 752,930

Claims priority, application Germany, Aug. 18, 1967, W 44,584

Int. Cl. B30b 15/34; B32b 31/20

U.S. Cl. 156—583

19 Claims



A plurality of heat sealing jaw sets are secured to endless conveyor chains and revolve at the velocity of the

workpieces. A plurality of said heat sealing jaw sets are in action simultaneously. The heat sealing set is adapted to be energized in dependence on the machine cycle and to be de-energized by means of a timing element after a predetermined interval of time.

3,579,408 ORNAMENTAL DEVICE FOR ATTACHMENT TO WIRE SPOKED WHEELS

Wesley P. Dowhan, 46 N. Water St., P.O. Box 272, Warehouse Point, Conn. 06088
Filed June 21, 1968, Ser. No. 739,102
Int. Cl. D04d 7/04; B60b 7/04
U.S. Cl. 161—7

6 Claims




Ornamental device for attachment to a wheel having wire spokes, said device comprising: a central, segmented annular disc; a plurality of fan-shaped blades; means for connecting the small ends of said blades to said disc, and means securing the wide ends of said blades to the spokes of a wheel.

3,579,409 HIGH STRENGTH PLASTIC COATED FIBER YARN FABRIC FOR STRUCTURAL REINFORCEMENT

Richard F. Shannon, Lancaster, Ohio, assignor to Owens-Corning Fiberglas Corporation
Filed May 17, 1967, Ser. No. 639,069
Int. Cl. B32b 5/16

U.S. Cl. 161—39

18 Claims



A flexible, extremely thin fabric particularly well-suited for the reinforcement of thin layers of plaster, mortar, cement, or like structural materials. The fabric is comprised of fabric yarns having barbed anti-slip surfaces firmly interfused in crosswise open-mesh relationship. Additionally, the fabric yarns respectively define a generally rectangular cross-sectional configuration in which the width across which the yarn is interfused is from approximately six to eighteen times greater than the yarn


thickness. The method of producing the fabric involves heating an open-mesh fabric constructed from glass fiber yarns coated with a thermoplastic organic coating to a temperature sufficient to transform the thermoplastic coating to a heat-softened fusible condition. While the thermoplastic coating remains in a fusible condition, the fabric is compressed to flatten and interfuse the fabric yarns. Also, while the thermoplastic coating is in a heat-softened condition, finely-divided solid fragments of an inorganic material are randomly deposited or scattered on the surfaces of the fabric and embedded in the plastic coating to form a barbed anti-slip surface on the fabric.

3,579,410 PARQUET FLOORING BLOCK AND METHOD OF MAKING SAME

Lawrence G. Barrett, Lynchburg, Va., assignor to The American Novawood Corporation, Lynchburg, Va.
Filed Sept. 6, 1967, Ser. No. 665,860
Int. Cl. E04f 13/10, 13/18, 15/16

U.S. Cl. 161—38

6 Claims




A prefinished unit of parquet flooring impregnated throughout the total thickness thereof with a monomer that is polymerized to a plastic material having a high resistance to abrasive wear. The separate slats, which may be quite thin, are assembled in blocks prior to conversion from ordinary wood to a wood-plastic composite, and the block may thereafter be prefinished before shipping and easily laid on a sub-floor without the need for on-site floor finishing crews.

3,579,411 FILAMENT REINFORCED STRUCTURE AND METHOD OF MAKING

William L. Mackie, 394 Court Ave., and Edgar D. Wilson, 5239 Aurora Drive, both of Ventura, Calif. 93003
Filed Sept. 27, 1967, Ser. No. 671,157
Int. Cl. B32b 7/08

U.S. Cl. 161—53

1 Claim



A lightweight, high strength structure and method of making same. Spaced panels are interconnected by high tensile strength flexible filaments of glass fiber or metal which filaments penetrate through the panels, and are woven back and forth. The portions of the filaments extending between the panels are subsequently rigidized by the addition of a coating which, when solidified, imparts substantial compressive strength. To counter shear


forces certain filaments may be arranged to slant in the direction of anticipated stress. Since the filaments pass through and overlie portions of the panels they effectively counter delamination or peeling.

3,579,412 FLUID IMPERVIOUS BARRIER INCLUDING LIQUID METAL ALLOY AND METHOD OF MAKING SAME

T. O. Paine, Administrator of the National Aeronautics and Space Administration, with respect to an invention of Albert J. Bauman, Sierra Madre, Calif.
Filed May 29, 1968, Ser. No. 732,922
Int. Cl. D06q 1/04

U.S. Cl. 161—89

15 Claims




A flexible barrier membrane comprising a porous substrate and incorporated liquid metal provides structures highly impervious to gases and liquids, and self-sealing to small punctures. Fabrics of metal or synthetic textile are impregnated with low melting alloys, such as alloys of gallium or indium metal, and used as sealant barriers for spacecraft walls and as flexible membrane barriers for pumping liquid propellants.

3,579,413 CORRUGATED BOARD CONSTRUCTION

Russell E. Koons, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.
Filed Jan. 3, 1966, Ser. No. 519,813
Int. Cl. B32b 11/06

U.S. Cl. 161—135

3 Claims



Corrugated board materials having improved properties are made utilizing a corrugated sheet comprising a laminate of at least two corrugated sheets laminated together with an asphalt-wax composition. The composition is comprised of 80 to 97 weight percent asphalt and 3 to 20 weight percent petroleum derived wax. The composition has a softening point of from 170 to 230° F., a penetration at 32° F., 200 grams, 60 seconds of 15 to 30 mm./10, a penetration at 77° F., 100 grams, 5 seconds of 25 to 45 mm./10, a penetration at 115° F., 50 grams, 5 seconds of 40 to 70 mm./10 and a viscosity (Saybolt Furol) at 375° F. of 25 to 250 seconds.

3,579,414
POLYAMIDE CONJUGATE FILAMENT
Keizo Ueda, Nishinomiya, Tsuneo Ohkawahara, Hira-kata, and Masao Matsui and Satoshi Ando, Osaka, Japan, assignors to Kanegafuchi Boseki Kabushiki Kaisha, Tokyo, Japan
No Drawing. Application Sept. 26, 1968, Ser. No. 768,956, now Patent No. 3,515,703, dated June 2, 1970, which is a continuation of application Ser. No. 368,691, May 19, 1964. Divided and this application Aug. 14, 1969, Ser. No. 871,232

Int. Cl. D02g 3/04

U.S. Cl. 161—173


2 Claims

A drawn nylon filament having superior heat durability, Young's modulus and dyeability which consists essentially of a copolyamide of undecamethylene terephthalamide and epsilon-caproamide, the latter being present in the range of from about 3 to 40% by weight of the copolyamide.

3,579,415
STRUCTURAL LAMINATES
Lloyd R. Allen, Belmont, Norman Beecher, Concord, Frank Feakes, Lexington, and James F. Springfield, Reading, Mass., assignors to National Research Corporation, Newton Highlands, Mass.
Filed June 29, 1967, Ser. No. 650,103
Int. Cl. B32b 15/04; C23c 13/0, 13/04

U.S. Cl. 161—184

1 Claim




Lightweight structures of high specific modulus and specific strength (modulus of elasticity and ultimate strength, respectively, divided by density) can be achieved by structural laminates comprising rigid materials characterized by brittleness and high stiffness formed as films and laid up in laminates. The adjacent films of the laminates are secured to each other by adhesives or hot pressed self bonding. The laminates offer a significant advantage over the prior art filament and fiber reinforced composite systems in that the laminates offer their strength and rigidity in all directions in the plane of the laminate.

3,579,416
PACKAGING FILM COMPRISING POLYOLEFIN OUTER LAYERS AND PLURAL INNER GAS BARRIER LAYERS

Walter J. Schrenk, Bay City, Mich., assignor to The Dow Chemical Company, Midland, Mich.
Filed Dec. 19, 1966, Ser. No. 602,899
Int. Cl. B32b 27/08, 27/30, 27/32

U.S. Cl. 161—254

6 Claims



A packaging film is claimed which incorporates a gas barrier core such as vinylidene chloride polymer, the gas

barrier core is slit into a plurality of layers which provides improved barrier properties and crumple resistance over a single layer core.

3,579,417 CONTINUOUS DIGESTER WOOD CHIP LEVEL CONTROL

Lawrence Allan Carlsmith, Amherst, N.H., assignor to Improved Machinery Inc., Nashua, N.H.
Continuation of application Ser. No. 543,363, Apr. 18, 1966. This application May 12, 1969, Ser. No. 828,421
Int. Cl. D21c 3/26

U.S. Cl. 162—17

3 Claims

Apparatus and method for continuous pulping in an upright elongated reaction vessel by feeding substantially continuously wood chips and a liquid into the reaction vessel at its lower end to maintain therein a columnar mass of compacted wood chips with its lower end normally spaced upwardly from the lower end of the vessel and advancing the wood chips upwardly throughout the length of said column by advancing liquid upwardly through a liquid propelling zone in the lower portion of the column. The vessel has three vertically spaced pressure sensing means with the lower two of the pressure sensing means spaced respectively above and below the normal position of the lower end of the chip mass and the uppermost one of the pressure sensing means spaced above said lower two to sense said position for control thereof. Comparator means are connected to each of the lower and upper two of the pressure sensing means for comparing the sensed signals therefrom providing output signals responsive to said position and means are provided for comparing the output signal from the lower two of the pressure sensing means with the output signal from the upper two of the pressure sensing means to produce a corrected output signal responsive to the position of the lower end of said chip mass by means of which the propelling liquid flow rate is controlled to control said position.

3,579,418 METHOD AND APPARATUS FOR COMMON DIGESTION OF WOOD CHIPS AND SAW DUST


Bengt Sven Erik Ostberg, Karlstad, Sweden, assignor to Aktiebolaget Kamyr, Karlstad, Sweden
Filed Sept. 18, 1968, Ser. No. 760,487

Claims priority, application Sweden, Sept. 21, 1967, 12,989/67

Int. Cl. D21c 7/06

U.S. Cl. 162—18

6 Claims



A method and apparatus wherein saw dust is mixed with regular wood chips and digested. In order to prevent clogging of the screens in the chips feeding devices and

the digester, coherent bodies, for example pellets or plugs, are formed out of the saw dust by compression. The cohesion of the bodies may be further improved by adding an adhesive or cementing agent. The saw dust bodies are added to the chips in the chute of the high-pressure feeder valve and are fed to the digester top by circulating liquid.

3,579,419 TREATMENT OF FLUFFED PULP FIBERS WITH GASEOUS CHLORINE

Frederic H. Yorston, Montreal, Quebec, and Norman Liebergott, Chomedey, Laval, Quebec, Canada, assignors to Pulp and Paper Research Institute of Canada, Pointe Claire, Quebec, Canada
Filed Apr. 24, 1967, Ser. No. 633,292
Int. Cl. D21c 9/12

U.S. Cl. 162—66

6 Claims

The invention is directed to treating a solid, such as wood pulp in the form of fluff, with a gaseous reactant such as chlorine. The fluff is first passed through a zone containing the gas. The residence time is limited to such that less than the potential amount of the gas is acquired by the fluff. Then the fluff including the acquired gas is allowed to remain in a zone free of the treating gas for a length of time sufficient to permit the acquired gas to react with the fluff.

3,579,420 SIEVE DEVICE IN AN UPRIGHT CYLINDRICAL CONTAINER FOR CONTINUOUS FLOW OF CEL- LULOSIC MATERIAL


Johan C. F. C. Richter, St. Jean Cap Ferrat, France, assignor to Aktiebolaget Kamyr, Karlstad, Sweden
Filed Apr. 30, 1968, Ser. No. 725,287

Claims priority, application Sweden, May 5, 1967, 6,340/67

Int. Cl. D21c 7/00

U.S. Cl. 162—237

1 Claim



At least one hollow sieve body having coaxial cylindrical sieve faces is located near the lower end of a cylindrical container through which a mixture of cellulosic material and a treating liquid is passed vertically downwards. The sieve body is suspended by a vertical tube located centrally of the container which tube further serves for discharging filtrate from the interior of the sieve body. An operating means at the top of the container periodically lifts the sieve body, which, intermediate of the periodic lifts, moves downwardly with the cellulosic material. The sieve body is given stability by radial support arms which slidably communicate with guide means fixed to the inner side of the container.

3,579,421 CONTINUOUS CELLULOSE DIGESTER WITH TWO SEPARATE PULP OUTLETS


Johan C. F. C. Richter, St. Jean Cap Ferrat, France, assignor to Aktiebolaget Kamyr, Karlstad, Sweden
Filed May 13, 1968, Ser. No. 728,396

Claims priority, application Sweden, May 16, 1967, 6,788/67

Int. Cl. D21c 7/08

U.S. Cl. 162—237

8 Claims



A continuous cellulose digester is provided with two pulp discharging means, one discharging the core of the moving plug of cellulosic material through a first outlet and the other discharging the peripheral parts of the plug through a second outlet. The first discharging means may be a rotary scraper working in the center area only of the outlet end of the digester, the second discharging means working in the surrounding annular space. The first outlet and discharging means is separated from the second outlet and discharging means by a partition means which is concentric to the digester wall.

3,579,422 FILAMENT WOUND CYLINDRICAL STRUCTURES FOR USE IN PAPER MAKING


David G. Minick, Westfield, and David H. Sinclair, South Hadley, Mass., assignors to The Sinclair Company, Holyoke, Mass.

Filed Oct. 7, 1968, Ser. No. 765,487

Int. Cl. D21f 1/46

U.S. Cl. 162—314

8 Claims



Cylindrical structure, such as a "dandy roll," constructed by the method of continuous filament winding in a honeycomb or open-work pattern formed on a collapsible mandrel. The filaments are impregnated with a thermosetting resin at the time of their application to the mandrel and the resin is cured and hardened to provide

the open-work rib structure. In one embodiment the structure is composed of upstanding ribs formed on the dandy roll and bonded together in a hexagonal-triangular honeycomb pattern.

3,579,423 PREPARATION OF TISSUE CULTURE MEDIA

Isao Yamane and Yutaka Matsuya, Sendai, and Katsuhiko Jimbo, Saitama, Japan, assignors to Flow Laboratories, Inc., Rockville, Md.

No Drawing. Filed Dec. 13, 1968, Ser. No. 784,296

Int. Cl. A61k 27/00

U.S. Cl. 195—1.7

11 Claims

A powdered nutrient composition is provided containing most of the nutrition requirements for culturing animal cells and an acidic buffering agent to maintain the pH of an aqueous solution of the composition at 3.5–5.0. This composition can be dissolved in water and sterilized by autoclaving prior to its incorporation in a tissue culture medium. After autoclaving of the nutrient composition, sterile solutions of glutamine and bicarbonate ions are aseptically added to the composition to form a tissue culture medium.

3,579,424 MICROBIAL PRODUCTION OF CARBON ¹⁴C LABELLED ALL-TRANS BETA-CAROTENE

Albert E. Purcell and William M. Walter, Jr., Raleigh, N.C., assignors to the United States of America as represented by the Secretary of Agriculture

No Drawing. Filed Apr. 7, 1969, Ser. No. 814,526

Int. Cl. C12d 5/00

U.S. Cl. 195—28

4 Claims

Purified all-trans ¹⁴C beta-carotene has been prepared in multimilligram amounts with over three million ¹⁴C disintegration per minute per milligram. This process utilizes economical radioactive substrates more efficiently than processes of the prior art. Better than 1% ¹⁴C tagged atom goes into beta-carotene. The labeled (¹⁴C beta-carotene) obtained can be used as a tracer in studies of autooxidation in food products and metabolisms of beta-carotene and vitamin A in animals.

3,579,425 PREPARATION OF PROSTAGLANDINS

David Adriaan van Dorp and Roelof Karel Beerthuis, Vlaardingen, Diederik Hendrik Nugteren, Rhooen, and Hendrik Vonkeman, Maassluis, Netherlands, assignors to Unilever N.V., Rotterdam, Netherlands

No Drawing. Continuation-in-part of application Ser. No. 700,030, Jan. 24, 1968, which is a continuation-in-part of application Ser. No. 453,483, May 5, 1965. This application Aug. 29, 1969, Ser. No. 854,250
Claims priority, application Great Britain, May 8, 1964, 19,237/64; July 15, 1964, 29,052/64

Int. Cl. C12d 1/02

U.S. Cl. 195—30

21 Claims

The specification discloses a process for preparing prostaglandins which comprises incubating, under aerobic conditions, a mixture comprising a prostaglandin-synthesizing enzyme system prepared from animal tissue, glutathione, and an all-cis polyunsaturated carboxylic acid of the formula



wherein n is a number from 0 to 5, p is a number from 3 to 5, and q is a number from 0 to 8, with the proviso that the sum of $n+3p+q$ is from 16 to 20 and that when p is 3 then n is a number from 3 to 5. The enzyme system is obtained from living animal organ cells, e.g., thymus, iris, genital glands and the like.

3,579,426

MICROBIOLOGICAL DEMETHYLATION OF 7-HALO-7-DEOXYLINCOMYCINS

Alexander D. Argondelis, John H. Coats, Donald J. Mason, and Oldrich K. Sebek, Kalamazoo, Mich., assignors to The Upjohn Company, Kalamazoo, Mich.

No Drawing. Filed Oct. 21, 1968, Ser. No. 769,411

Int. Cl. C12d 9/00

U.S. Cl. 195—80

7 Claims

A microbiological process for the 1'-demethylation of 7-halo-7-deoxylincomycins to obtain the corresponding 7-halo-7-deoxy-1-demethylincomycins, which are known active antibacterial agents with broader scope of activity than the present compounds.

3,579,427

PROCESS FOR PRODUCING METHIONINE DECARBOXYLASE

Kiyoshi Nakayama, Sagami-hara-shi, and Hiroshi Hagino, Hachioji-shi, Japan, assignors to Kyowa Hakko Kogyo Co., Ltd., Tokyo, Japan

No Drawing. Filed Feb. 13, 1968, Ser. No. 704,992

Claims priority, application Japan, Feb. 20, 1967, 42/10,419

Int. Cl. C12d 13/10

U.S. Cl. 195—66

9 Claims

A process for producing the enzyme methionine decarboxylase which comprises culturing a microorganism capable of producing methionine decarboxylase under aerobic conditions in an aqueous nutrient medium containing L-methionine, accumulating the methionine decarboxylase in the resultant culture liquor, and recovering the same therefrom. Suitable microorganisms which may be employed are those belonging to the genus Streptomyces.

3,579,428

METHOD OF MANUFACTURING PLATED POLYPROPYLENE SHAPED ARTICLES

Toshihiko Kuroda, Sotou Sutani, Haruo Nitta, Rikio Takahashi, and Sadao Saito, Yokkaichi-shi, Japan, assignors to Mitsubishi Petrochemical Co., Ltd., Tokyo, Japan


Filed Sept. 23, 1968, Ser. No. 761,767

Claims priority, application Japan, Sept. 30, 1967, 42/62,648; June 17, 1968, 43/41,335

Int. Cl. C23b 5/60, 3/02

U.S. Cl. 204—30

1 Claim



Method of manufacturing a plated polypropylene which comprises subjecting a polypropylene composition containing 20-50% by weight of an inorganic powder having an average particle size of less than 20 microns based on the total weight of said composition to a treatment with an acid solution containing an oxidizing agent and further subjecting thus treated polypropylene composition to a plating process.

3,579,429

PROCESS FOR APPLYING A WHITE PAINT ELECTROPHORETICALLY

Frank E. Manson, Lansdale, and Lester Steinbrecher, Southampton, Pa., assignors to Amchem Products, Inc., Ambler, Pa.

No Drawing. Continuation-in-part of application Ser. No. 630,839, Apr. 14, 1967. This application Jan. 6, 1970, Ser. No. 1,056

Int. Cl. B01k 5/02; C23b 13/00

U.S. Cl. 204—181

20 Claims

A white paint film applied to an iron or steel surface by the electrophoretic method of painting tends to be of a muddy, off-white or yellowish color; also, foreign deposits on the surface to be painted show-up in the white paint film as color imperfections. These problems are avoided by pretreating the iron or steel surface with an aqueous solution of copper to apply thereto copper deposits and thereafter painting the pretreated surface with a white paint by the electrophoretic method of painting.

3,579,430

APPARATUS FOR ELECTROPLATING WIRE


Philip E. Lawler, Papillion, Nebr., assignor to Western Electric Company, Incorporated, New York, N.Y.

Filed Mar. 13, 1969, Ser. No. 806,899

Int. Cl. C23b 5/08

U.S. Cl. 204—206

5 Claims



In apparatus for electroplating wire, in which the wire is advanced longitudinally through a plating tank, the wire passes over electrical contact members mounted externally of the plating tank adjacent its wire entrance and wire exit ends. The contact members are rotatably driven by separate adjustable torque motors so as to maintain the wire under tension and thereby maintain good electrical contact between the wire and the contact members. In order that the tension in the wire, and thus the plating current flowing in the system, will be maintained at substantially uniform values, the magnitude of friction variables in the system is reduced by fixedly mounting each contact member on a cantilevered portion of a drive shaft of its respective motor, and by feeding electrical current into each contact member through a single contact brush engageable therewith at its axis of rotation.

3,579,431

CELL FOR ELECTROLYTIC DEPOSITION OF METALS

Peter M. Jasberg, Kellogg, Idaho, assignor to The Bunker Hill Company, Kellogg, Idaho

Filed Feb. 23, 1968, Ser. No. 707,847

Int. Cl. B01k 3/00, 3/02

U.S. Cl. 204—275

18 Claims

A cell assembly for electrolytic deposition of metals, designed to facilitate the electrolytic deposition and recovery of zinc or other metals similarly processed. The

3,579,433

VERTICAL COLUMN ELECTROPHORESIS APPARATUS

Donald A. Dahlgren, Portage, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Filed Apr. 24, 1968, Ser. No. 723,658

Int. Cl. B01k 5/00


U.S. Cl. 204—299

6 Claims

cell assembly includes an improved cell box comprising a treated wooden structure having a one piece protective liner. The liner includes an integral inlet box and outlet weir to insure consistent solution line elevation. An improved cathode structure is utilized, having protective non-conductive coverings applied thereto along the side and top portions of the plate on which metal is deposited.



Improved anode assemblies include stiffening plastic guides attached thereto which position the cathodes relative to the anode structures in a constant spaced parallel relationship. Control of the deposition of metal is further achieved by an improved bus bar support system for the cathode and anode units, facilitating accurate adjustment and leveling of the units relative to the electrolyte.



An apparatus for gel electrophoresis of proteinaceous materials includes an electrophoretic gel column, means to establish a substantially uniform unidirectional potential longitudinally across the column, and a collection chamber below the column. A buffer solution enters the collection chamber and radially sweeps the proteinaceous material entering the chamber from the column toward a centrally situated exit means and downwardly there-through.

3,579,434

HYDROCRACKING OF NAPHTHA

Robert B. Smith, Pitman, and Barton W. Rope, Mullica Hill, N.J., assignors to Mobil Oil Corporation

No Drawing. Filed July 2, 1968, Ser. No. 741,867

Int. Cl. C10g 13/02, 13/10

U.S. Cl. 208—111

2 Claims

A composition comprising a small quantity of palladium, generally between 0.05 and 5.0 weight percent palladium, deposited on a chelated hydrogen form of zeolite Y. A method of hydrocracking naphtha to LPG which comprises contacting a naphtha charge under hydrocracking conditions with the aforementioned catalyst.

3,579,435

HYDROCRACKING PROCESS

Albert T. Olenzak, Media, and Sheldon L. Thompson, Glen Mills, Pa., assignors to Sun Oil Company, Philadelphia, Pa.


Filed June 20, 1968, Ser. No. 738,432

Int. Cl. C10g 13/00, 37/02

U.S. Cl. 208—59

9 Claims

A process for hydrocracking lubricating oil stocks to lubricating oils of higher viscosity index in which the portions of a crude suitable for hydrocracking are fractionated into a plurality of fractions commensurate with the boiling point, molecular weight, or polyfused-ring aromatic content and each of said fractions is subjected to hydrocracking conditions commensurate with the polyfused-ring aromatic content over a hydrocracking catalyst at a temperature in the range of about 650° to 875° F. and a hydrogen partial pressure of at least about 1500 p.s.i. Preferably, the charge stock is fractionated into three fractions, the first fraction boiling in the range of about 650° to 850° F., the second fraction boiling in the range of about 850° to 1000° F., and the third fraction containing all the material boiling above about 1000° F. which has been deasphalted; and each of the foregoing



A composite electrical conductor adapted to contact an electrode in current transmitting engagement. A ferrous metal plate is affixed to the free end of a ferrous metal rod adapted to be embedded in the electrode. A soft aluminous plate is roll bonded along one face to the ferrous plate affixed to the rod. An aluminum conductor rod is welded to the aluminous plate roll bonded to the ferrous plate and is adapted to be connected to a source of electric current.

other metals, the solution is introduced into a vessel containing a moving bed of a material such as sand in a water medium. Simultaneously, a solid or a liquid precipitant is introduced into the vessel, and the heavy metals, precipitating from the resultant reaction, deposit on the individual particles of the sand bed. The precipitate thus formed is dense and low in retained water. A clean water effluent, substantially free of dissolved heavy metals, is removed from the vessel.

3,579,444

METHODS OF SCALE INHIBITION

Al F. Kerst, Littleton, Colo., assignor to Monsanto Company, St. Louis, Mo.


No Drawing. Filed Apr. 13, 1970, Ser. No. 27,983

Int. Cl. C02b 5/06

U.S. Cl. 210—58

11 Claims

The precipitation of scale-forming salts in an aqueous system is inhibited by adding either stoichiometric or sub-stoichiometric amounts to said system of an organo-phosphorous compound which is a substituted epoxy ethane polyphosphonic acid or its salt, said organo-phosphorus compound having the formula



wherein R is hydrogen or a metal ion, and X and Y are hereinafter defined.

3,579,445

METHOD OF AND COMPOSITION FOR THE TREATMENT OF SCALE

Jack F. Tate, Houston, Tex., assignor to Texaco Inc., New York, N.Y.

No Drawing. Filed June 24, 1968, Ser. No. 739,207

Int. Cl. C02b 5/06

U.S. Cl. 210—58

7 Claims

Method of and composition for the treatment of scale, particularly calcium sulfate scale, using a quaternary trimethylalkyl ammonium halide, acetate, sulfate or hydroxide containing 8 to 20 carbon atoms in the alkyl group including mixtures.

3,579,446

FIRE-EXTINGUISHING FOAM COMPOSITION INCLUDING A BASIC, NITROGENOUS COMPOUND

Hermann Kroke, Erkrath-Unterbach, and Kurt Raffalsky, Urach, Wurttemberg, Germany, assignors to Minimax Aktiengesellschaft, Urach, Wurttemberg, and Henkel & Cie. G.m.b.H., Dusseldorf, Germany

No Drawing. Filed Mar. 24, 1969, Ser. No. 809,945

Claims priority, application Austria, Apr. 29, 1968, A 4,153/68

Int. Cl. A62d 1/00

U.S. Cl. 252—3

11 Claims

In a foaming composition useful as a fire extinguisher composed of

- (1) A foaming agent such as substituted or unsubstituted alkyl or alkyl-ether sulfate;
- (2) A stabilizing additive to improve the water-retaining capacity of the foam, such as higher aliphatic alcohol or ether containing from 8 to 25 carbon atoms, or a higher aliphatic alcohol containing a few alkylene oxide molecules;

- (3) Optionally, a compensating agent, which aids in production of foams with reduced weight and of lower discharge velocities, such as monovalent poly-ether alcohols;

the improvement comprising the use of water-soluble, basic, organic or inorganic nitrogenous compound which neutralizes corrosive effects of halides in the combustion gases.

3,579,447

METHOD OF REMOVING COPPER DEPOSITS FROM FERROUS METAL SURFACES USING HYDROXYALKYL THIOUREA

Thaddeus M. Muzyczko, Melrose Park, William J. Ludwig, Westmont, Jon A. Loboda, Chicago, and Samuel Shore, Roselle, Ill., assignors to The Richardson Company, Melrose Park, Ill.

No Drawing. Filed Sept. 30, 1968, Ser. No. 763,914

Int. Cl. C02b 5/06; C07c 157/02; C23g 1/06

U.S. Cl. 252—8.7

12 Claims

Removal of copper-containing incrustations from ferrous metal surfaces accomplished in improved manner by addition of a hydroxyalkyl thiourea having at least two carbon atoms in the alkyl group such as 1-hydroxyethyl-3-methyl thiourea to an aqueous treating solution and subsequent treatment of ferrous metal surfaces wherein reduced sludge formation accompanies removal of copper and the avoidance of copper plating.

3,579,448

GREASE COMPOSITION

Alvin Harrison, Irvington, N.Y., assignor to Stauffer Chemical Company, New York, N.Y.

No Drawing. Filed June 25, 1968, Ser. No. 739,634

Int. Cl. C10m 7/26, 7/24

U.S. Cl. 252—28

5 Claims

A grease composition consisting of a synthetic ester thickened to a grease-like composition with bentonite clay, wherein a pyrogenic silica gelling agent is added thereto.

3,579,449

LUBRICANT COMPOSITION

Robert Earl Wann, Denzel Allan Nicholson, and Ted Joe Logan, Hamilton, Ohio, assignors to the Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed Sept. 26, 1968, Ser. No. 762,966

Int. Cl. C10m 1/46, 1/30

U.S. Cl. 252—49.5

8 Claims

Lubricant compositions comprising a major amount of a lubricating base fluid and a minor amount of extreme pressure additives which contain either a methylene, monohalomethylene or dihalomethylene group between two moieties selected from the group consisting of phosphono, dihydrocarbylphosphoryl, phenyl, substituted phenyl, keto, cyano, and carboxylate ester moieties.

3,579,450

LUBRICANTS AND FUELS CONTAINING EPOXIDE TREATED ESTERS

William M. Lesuer, Cleveland, Ohio, assignor to The Lubrizol Corporation, Wickliffe, Ohio

No Drawing. Continuation of application Ser. No. 712,606, Mar. 13, 1968, which is a continuation-in-part of applications Ser. No. 567,052, now Patent No. 3,522,179, and Ser. No. 567,320, now Patent No. 3,381,022, both July 22, 1966. This application Oct. 3, 1969, Ser. No. 866,084

Int. Cl. C10m 1/26

U.S. Cl. 252—56

19 Claims

A process for post-treating oil-soluble esters of mono- or polycarboxylic acids and polyhydric alcohols with or-

ganic epoxides. The acyl moiety of the esters is derived from mono- or polycarboxylic acids containing at least about fifty aliphatic carbon atoms exclusive of the carboxyl carbon atoms. The products are useful as lubricant and fuel additives. A typical example of the process would be the post-treatment of a diester of polyisobutenyl-substituted succinic acid and sorbitol with propylene oxide.

3,579,451

ELECTROPHOTOGRAPHIC DEVELOPER MADE FROM CROSS-LINKED SILICONE INTERMEDIATE RESIN

Louis J. Sciambi, Wenonah, N.J., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Continuation-in-part of application Ser. No. 582,541, Sept. 28, 1966. This application Jan. 22, 1969, Ser. No. 793,152

Int. Cl. G03g 9/02, 9/04

U.S. Cl. 252—62.1

3 Claims

The method of preparing a stable, dry electrophotographic developer composition concentrate consists essentially of admixing and suspending about one part by weight of a silicone intermediate resin with from about one to five parts by weight of a cross-linking promoting catalyst in an aromatic carrier liquid and heating the admixture at a temperature of from about 50 to 100° C. for a period of about 1 to 24 hours; admixing the heated admixture with from about 0.5 to 4 parts by weight of an insoluble solid pigment per part of resin plus catalyst present (solvent-free basis); milling the resin-catalyst and pigment mixture together in a grinding mill for at least about 8 hours; and evaporating the solvent from the so-milled admixture.

The dry concentrate is made into a liquid concentrate by milling the dry solids for from about 8 to 24 hours with sufficient organic carrier liquid, such as a liquid aliphatic hydrocarbon, to provide a suitable grinding slurry viscosity. This milled liquid concentrate is diluted further with carrier liquid to provide the proper concentration of catalyst per liter of composition as well as an electrical conductivity within the desired range and the so-diluted mixture is a working electrophotographic developer composition.

3,579,452

PROCESS FOR THE PRODUCTION OF FERROMAGNETIC PURE OR ISOTOPE MANGANATE MIXED PHASES CRYSTALLIZING IN THE ILMENITE LATTICE

Franz Hund, Krefeld-Bockum, Germany, assignor to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

Filed Aug. 28, 1968, Ser. No. 755,937

Claims priority, application Germany, Sept. 1, 1967, F 53,389

Int. Cl. C01g 45/12

U.S. Cl. 252—62.51

9 Claims

Production of ferromagnetic pure and isotope manganate mixed phases of the composition



where $0 \leq x \leq 0.20$ that crystallize in the ilmenite lattice, by precipitating such mixed phase constituents from an aqueous salt solution of manganese and nickel, or manganese, nickel and cobalt, ions, in quantitative proportions which correspond directly to those of the required end compound, by instantly intermixing such reactants with a basic precipitant at about 0-100° C., oxidizing the resulting suspension, and then filtering, washing, calcining and cooling the resulting precipitate.

3,579,453

ALKALI-SOLUBLE SURFACTANT CONSISTING OF SUBSTITUTED SUCCINIC ACID-NONIONIC ETHOXYLATE BLENDS

Jean Dupre, Levittown, and Harrison Scott Killam, Holland, Pa., assignors to Rohm and Haas Company, Philadelphia, Pa.

No Drawing. Filed Nov. 12, 1968, Ser. No. 775,137

Int. Cl. C11d 1/66

U.S. Cl. 252—89

8 Claims

Nonionic ethoxylated surfactants, which are known to be very desirable components in heavy duty cleaning products, suffer from the fact that they have limited solubility in solutions of alkaline electrolytes and thus are not soluble in alkaline builder concentrates. Addition of moderate amounts of substituted succinic acids overcomes this defect and permits the inclusion of these non-ionics in built liquid detergent concentrates.

3,579,454

DETERGENT COMPOSITIONS CONTAINING AN OXIDIZING BLEACH AND PROTEOLYTIC ENZYME DERIVED FROM THERMOPHILIC STREPTOMYCES RECTUS VAR. PROTEOLYTICUS

Everett J. Collier, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Continuation-in-part of abandoned application Ser. No. 777,485, Nov. 20, 1968. This application Aug. 15, 1969, Ser. No. 850,656

Int. Cl. C11d 9/42

U.S. Cl. 252—97

7 Claims

Detergent composition containing an organic synthetic detergent and an alkaline builder in a weight ratio of about 1:30 to about 5:1, an oxidizing bleach and a proteolytic enzyme derived from thermophilic *Streptomyces rectus* var. *proteolyticus* ATCC 21067. These compositions are useful in any application where the combined effect of an oxidizing bleach and proteolytic enzyme activity are desired, such as laundering and soaking compositions.

3,579,455

MACHINE DISHWASHING COMPOSITIONS CONTAINING SODIUM POLYACRYLATE

Philip M. Sabatelli, Cincinnati, Ohio, and Charles A. Brungs, Covington, Ky., assignors to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed Aug. 2, 1968, Ser. No. 749,592

Int. Cl. C11d 7/14, 7/16, 7/26

U.S. Cl. 252—135

5 Claims

A machine dishwashing composition is disclosed which includes alkali metal carbonate, a tetra-alkali metal pyrophosphate, an alkali metal hexametaphosphate, a water-soluble salt of polyacrylic acid, and an alkali metal metasilicate. Cooking and eating utensils may be cleaned by a low foaming aqueous solution of the present machine dishwashing composition with less spotting and greater clarity.

3,579,456

LIQUID DETERGENT COMPOSITION

Cushman M. Cambre, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed Dec. 18, 1968, Ser. No. 784,886

Int. Cl. C11d 3/08, 3/14

U.S. Cl. 252—137

6 Claims

Stable, liquid detergent compositions (for cleaning aluminum and rust stains from hard surfaces) containing

particulate materials (e.g., abrasives), water, alkylbenzenesulfonate detergent, zwitterionic synthetic detergent and an acid electrolyte; said compositions have a pH of from about 1 to about 5.

3,579,457

EPOXIDE TAURINE CONDENSATION PRODUCTS AND DETERGENT COMPOSITIONS CONTAINING THEM

Robert M. Lincoln, Moylan, and Joseph A. Meyers III, Springfield, Pa., and Richard W. Sauer, Cherry Hill, N.J., assignors to Atlantic Richfield Company, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 625,281, Mar. 23, 1967, which is a continuation-in-part of application Ser. No. 548,876, May 10, 1966. This application Apr. 2, 1969, Ser. No. 812,919

Int. Cl. C11d 3/34

U.S. Cl. 252—137

3 Claims

Novel condensation products wherein a C₃-C₅ aliphatic epoxide and a C₃-C₁₈ aliphatic epoxide are condensed with taurine, and built synthetic detergent compositions wherein at least a portion of the sodium triphosphate is replaced by this epoxide-aurine condensation product.

3,579,458

COMPOSITION OF MATTER

Joseph E. Callen and Robert D. Haxby, Springfield Township, Hamilton County, and William T. Fagin, Colerain Township, Hamilton County, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Continuation-in-part of application Ser. No. 517,941, Jan. 3, 1966. This application May 8, 1968, Ser. No. 727,654

Int. Cl. C11d 3/42

U.S. Cl. 252—152

8 Claims

A composition consisting essentially of certain relatively water insoluble brighteners essentially completely dissolved in an acidic solvent which forms a detergent when it is neutralized; processes for preparing said composition; and the corresponding neutralized composition.

3,579,459

METAL VAPOR GENERATING COMPOSITIONS

Paolo Della Porta and Elio Rabusin, Milan, Italy, assignors to S.A.E.S. Getters S.p.A., Milan, Italy

Filed Dec. 13, 1967, Ser. No. 690,125

Claims priority, application Italy, Dec. 13, 1966, 31,040/66; Oct. 12, 1967, 21,538/67

Int. Cl. C09k 3/00; H01v 39/22

U.S. Cl. 252—181.4

24 Claims



(A) an open sintered matrix of a sinterizable material in a vacuum releases a metal vapor. The structure comprises

- (A) an open sintered matrix of sinterizable material and,
- (B) a mixture, fixedly held within the sintered matrix, said mixture comprising:

- (1) a compound of a metal selected from the group consisting of mercury and the alkali metals said compound being reducible to its metal, and,

- (2) a stoichiometric excess of a reducing agent for said compound.

Devices employing these composite structures and processes for producing these structures.

3,579,460

SULFENAMIDE COMPOSITIONS STABILIZED BY ORGANIC DISULFIDES

Joseph Edward Kerwood, 2886 Burr Oak Drive, Akron, Ohio 44313

No Drawing. Filed June 16, 1969, Ser. No. 833,736

Int. Cl. C08d 11/02

U.S. Cl. 252—182

15 Claims

A composition comprising a thiazolesulfenamide accelerator and a sulfenamide prevulcanization inhibitor can be stabilized by the addition of an organic disulfide of the formula T—S—S—T wherein T independently is lower alkyl, aralkyl, aryl, alkenyl or a 2-thiazolyl radical.

3,579,461

EMULSIFICATION PROCESS

Wayne R. Glaub, Racine, Wis., assignor to S. C. Johnson & Son, Inc., Racine, Wis.

Filed Nov. 20, 1967, Ser. No. 684,436

Int. Cl. B01j 13/00

U.S. Cl. 252—311

9 Claims

An improved process for manufacturing a wax emulsion under pressure is described. According to the process, the wax and a minor amount of the total water used in the emulsion are added to the pressure vessel and heated under pressure. An emulsifier is added, preferably beneath the surface of the wax/water concentrate, with agitation to obtain uniformity and provide a water-in-wax emulsion. The emulsion is diluted rapidly with sufficient water being added beneath the surface to obtain a wax-in-water emulsion.

3,579,462

TREATMENT OF SILICA SOLS

Henry Thomas Joseph Chilton and Patricia Gertrude Burns, Llangollen, Denbighshire, Wales, assignors to Monsanto Chemicals Limited, London, England

No Drawing. Filed Sept. 6, 1968, Ser. No. 758,116
Claims priority, application Great Britain, Sept. 12, 1967, 41,593/67

Int. Cl. B01j 13/00; C01b 33/14

U.S. Cl. 252—313S

14 Claims

A process for the isolation, from an initial silica sol having a relatively wide range of particle sizes, of one or more fractions in each of which the particle size of the silica is relatively uniform, which comprises placing the initial silica sol on a permeable bed of a porous gel, which gel comprises a solid phase substantially insoluble in the liquid dispersion medium of the silica sol, and a liquid phase which is the same as or is compatible with the liquid dispersion medium, the gel having an average pore size comparable with the average particle size of the silica, washing the silica through the bed with an eluant which is the same as or compatible with the liquid dispersion medium of the initial sol and with the liquid phase of the gel and collecting as an effluent from the bed at least one fraction of colloiddally dispersed silica in which the range of particle size is less than that in the initial silica sol.

3,579,463

METHOD OF PREPARING CRYSTALLINE CALCIUM HALOPHOSPHATE PHOSPHOR Anselm Wachtel, Parlin, N.J., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa. Filed May 7, 1969, Ser. No. 822,501 Int. Cl. C09k 1/36

U.S. Cl. 252—301.4

8 Claims

Method of preparing crystalline calcium halophosphate of a particle size distribution which can be advantageously used in commercial fluorescent lamps. A raw mix is prepared of the constituents required to form the calcium halophosphate matrix with an excess of calcium and halogen constituents in predetermined amounts. The firing is carried out at a predetermined temperature and time to form the halophosphate matrix having the desired crystallinity and particle size distribution. Then, a selected amount of activator constituent is mixed with the halophosphate matrix and is incorporated into the matrix during a subsequent firing to form the phosphor.

3,579,464

NONDECREPITATING SILICA GEL AND METHOD FOR ITS PREPARATION

Harvey Rosen, Laurel, and Ellsworth G. Acker and Hanjo Lee, Baltimore, Md., assignors to W. R. Grace & Co., New York, N.Y.

No Drawing. Filed May 20, 1968, Ser. No. 730,620

Int. Cl. B01j 13/00; C01b 33/16; C09k 3/00

U.S. Cl. 252—317

10 Claims

Conventional partially dried silica hydrogel particles having about 2–20% moisture content are ground to about 1–500 microns. This powder is then blended with silica hydrosol solution in proportions such that the weight ratio of silica from the hydrogel particles to silica in the hydrosol is about 15:1. The resultant mixture is then extruded, beaded, pelleted or otherwise shaped. The thus shaped products are then aged, washed, dried and activated.

3,579,465


AQUEOUS GELS OF POLYOXYETHYLATED POLYOXYPROPYLENE GLYCOL ADDUCTS OF ETHYLENE DIAMINE

Irving R. Schmolka, Grosse Ile, Mich., assignor to Wyandotte Chemicals Corporation, Wyandotte, Mich.
Filed Oct. 16, 1967, Ser. No. 675,505

Int. Cl. A01n 9/00; A61k 7/00; B01j 13/00

U.S. Cl. 252—316

6 Claims



Aqueous gels, useful in the formulation of pharmaceutical, cosmetic and detergent compositions, are prepared from certain polyoxyethylated polyoxypropylene glycol adducts of ethylene diamine.

3,579,466

POLYGLYCIDYL POLYMERS AS DEMULSIFIERS Patrick M. Quinlan, Webster Groves, Mo., assignor to Petrolite Corporation, Wilmington, Del.

No Drawing. Original application Mar. 8, 1965, Ser. No. 438,115. Divided and this application Jan. 17, 1969, Ser. No. 792,157

Int. Cl. B01d 17/04

U.S. Cl. 252—331

14 Claims

A process of demulsification which employs polyglycidyl polymers and copolymers thereof and derivatives thereof as demulsifiers.

3,579,467

ORGANOPOLYSILOXANES HAVING HYDROXYARYL SUBSTITUENTS

Edgar D. Brown, Jr., Schenectady, N.Y., assignor to General Electric Company

No Drawing. Continuation-in-part of application Ser. No. 600,787, Dec. 12, 1966. This application Nov. 27, 1968, Ser. No. 779,622

Int. Cl. C10m 1/50

U.S. Cl. 252—46.3

11 Claims

Organopolysiloxanes useful as hydraulic fluids comprise organopolysiloxanes in which a majority of the siloxane groups contain methyl radicals and higher alkyl radicals, and a minor proportion of the siloxane groups contain silicon-bonded tertiary butyl-substituted hydroxyaryl radicals attached to silicon through a divalent propylene radical. Optionally, a minor amount of aryl and aralkyl radicals can also be present on the siloxane groups. These compounds are prepared by reacting polysiloxanes containing methylhydrogen units and phenylhydrogen units with higher alkenes and hydroxyaryl compounds containing both nuclear substituted allyl radicals and nuclear substituted tertiary butyl radicals.

3,579,468

PROCESS FOR RECONSTITUTING NATURAL CITRONELLA OIL

Robert P. T. Young, Ponte Vedra, Fla., assignor to SCM Corporation, New York, N.Y.

No Drawing. Filed Aug. 26, 1966, Ser. No. 575,238
Int. Cl. C11b 9/00, 9/02

U.S. Cl. 252—522

1 Claim

Reconstituted citronella oil in which at least a portion of the naturally occurring d-citronellal in the natural oil is replaced by substantially equivalent weight proportion of dl-citronellal is described. The reconstituted citronella oil has substantially the same odor value as that of the natural citronella oil. Processes for preparing this product are also described. The invention is advantageous in that it provides d-citronellal which would not otherwise be available and which is useful in making hydroxy citronellal, a perfumery chemical and is also advantageous in that it extends the supply of citronella oil.

3,579,469

SILOXANE PAPER RELEASE COATINGS

Maurice E. Grenoble, Ballston Lake, N.Y., assignor to General Electric Company

No Drawing. Filed Dec. 13, 1968, Ser. No. 783,773
Int. Cl. C08k 1/66

U.S. Cl. 260—18

5 Claims

A paper release coating composition contains a silanol-terminated polysiloxane gum, a silane of the formula HSiX₃, where X is a hydrolyzable radical, a metal salt and an organic solvent. A surface of a sheet of paper is coated with the composition, the solvent is evaporated, and the silanol-terminated polysiloxane is cross-linked by reaction with the silane in the presence of moisture at an elevated temperature. The coated paper produced is useful as a backing sheet for bumper stickers.

3,579,470
DIPHENYL OXIDE MODIFIED PHENOLIC RESIN INSULATING VARNISHES
 Robert H. Runk, Pittsburgh, Pa., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.
 No Drawing. Continuation of applications Ser. No. 394,312, Sept. 5, 1964, and Ser. No. 706,706, Feb. 19, 1968. This application Dec. 30, 1968, Ser. No. 800,313

Int. Cl. C08g 37/20

U.S. Cl. 260—20 **14 Claims**
 Monomeric monofunctional chloromethyl diphenyl oxide and/or alkoxy methyl diphenyl oxide is reacted with a substantially equimolar amount of a phenol. The product is further reacted with formaldehyde to form a resole that that may be converted to a cross-linked polymer by the application of heat. The resole resins may be blended with modifying compositions such as epoxy esters and/or oil modified alkyls and the like.

3,579,471
CELL MODIFYING AGENTS FOR POLYURETHANE FOAMS
 Willem Dijkhuizen, Harmannus Kliphuis, and Jan Lolkema, Hoogezand, Netherlands, assignors to Scholten Research N.V., Groningen, Netherlands
 No Drawing. Filed Oct. 18, 1967, Ser. No. 676,085
 Claims priority, application Great Britain, Oct. 22, 1966, 47,454/66

Int. Cl. C08g 22/44, 53/08

U.S. Cl. 260—2.5 **21 Claims**
 Polyurethane foams having improved physical properties are provided herein by producing the foams in the presence of cell modifying agents, at least one of which is an organic high molecular weight emulsifying agent substantially soluble in mineral oil but substantially insoluble in water, and which emulsifying agent is capable of producing heat-stable water-in-oil emulsions. The emulsifying properties of these new cell modifying agents are such that upon subjecting 20 cm.³ of 0.5% solution of said emulsifying agent in a mineral oil of a viscosity of 1–5° Engler at 20° C. to the A.S.T.M. "Steam Emulsion Test"; the time for separating 5 cm.³ of one of the phases of the emulsion at a temperature of 93° C. to 95° C. is at least 20 minutes.

3,579,472
METHOD OF FABRICATING EXPANDABLE THERMO-PLASTIC RESINOUS MATERIAL
 Louis C. Rubens and William B. Walsh, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.
 No Drawing. Continuation-in-part of application Ser. No. 526,358, Feb. 10, 1966, which is a continuation-in-part of application Ser. No. 439,969, Mar. 15, 1965. This application May 31, 1968, Ser. No. 733,231
 Int. Cl. C08f 1/16, 7/06, 47/10

U.S. Cl. 260—2.5 **8 Claims**
 Replicating foam plastic bodies are prepared by polymerization at room temperature of chlorostyrene, methyl methacrylate, a cross-linking agent and a blowing agent, without requiring a closed mold or vessel.

3,579,473
EPOXY SOLDERS
 George A. Salensky, Metuchen, N.J., assignor to Union Carbide Corporation, New York, N.Y.
 No Drawing. Filed Dec. 27, 1968, Ser. No. 787,555
 The portion of the term of the patent subsequent to June 10, 1986, has been disclaimed
 Int. Cl. C09g 51/06, 51/04, 31/12

U.S. Cl. 260—18 **13 Claims**
 This invention relates to epoxy solders, containing a talc of specified properties, which are characterized by excellent thermal shock resistance, and cure speed and adhesion to oil contaminated surfaces.

3,579,474
ELASTOMERIC COPOLYMERS OF TETRAFLUOROETHYLENE CONTAINING PHENOXYETHYL GROUPS, AND THEIR VULCANIZATION
 Rolland S. Ro, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
 No Drawing. Filed Dec. 16, 1968, Ser. No. 784,234
 Int. Cl. C08f 19/04, 45/24

U.S. Cl. 260—29.6 **10 Claims**
 Novel elastomeric copolymers of tetrafluoroethylene with (1) (a) an alkyl vinyl ether, or either (b) an olefin which is from 50 to 100 mole percent of propylene, butene-1 or a mixture of them, any remainder being ethylene or isobutylene, or (c) ethylene and isobutylene in about equimolar proportions, and (2) 0.5 to 5 percent by weight of the product of a cure-site monomer which is an aryloxyalkyl vinyl ether, are made by catalytically uniting the components in an inert medium. The copolymer products are cleanly, quickly and efficiently cured by mixing with small amounts of polyformaldehyde or methylol-containing condensation products of formaldehyde with urea, phenol, or melamine under non-basic, preferably acidic, conditions to form novel elastomeric products having improved elastic properties.

3,579,475
CROSS-LINKED POLY(ARYLSULPHONE ETHERS)
 Michael Edward Benet Jones, 45 Richmond Crescent, Vicars Cross, Chester, England, and Brian Edmund Jennings, Cherry Acre, 40 Harmer Green Lane, Digs-well, Welwyn, Hertfordshire, England
 No Drawing. Continuation of application Ser. No. 755,492, Aug. 7, 1968. This application Feb. 17, 1970, Ser. No. 12,141
 Int. Cl. C08g 25/00

U.S. Cl. 260—37 **9 Claims**
 A thermoplastic polymer containing aromatic residues in the polymer chain is cross-linked by heating with an aromatic compound containing at least two sulphonyl chloride, bromide, hydrazide or ester groups. The thermoplastic polymer may itself contain at least two of these reactive sulphonyl groups per chain and can be cross-linked on heating alone.

3,579,476
GLASS FILLED GRAFT COPOLYMERS OF AN OLEFIN AND AN UNSATURATED ACID
 James K. Rieke and Frank H. Justin, Midland, Mich., assignors to Dow Chemical Company, Midland, Mich.
 No Drawing. Continuation-in-part of application Ser. No. 531,381, Mar. 3, 1966. This application Feb. 14, 1969, Ser. No. 799,487
 Int. Cl. C08f 45/10

U.S. Cl. 260—41 **11 Claims**
 Polymer compositions having improved tensile properties and improved impact resistance comprising a blend of between about 10 and about 40 weight percent glass fibers and between about 60 and about 90 weight percent of a graft copolymer of an olefin such as ethylene and an ethylenically unsaturated carboxylic acid such as acrylic acid. The polymer compositions can be molded or extruded to produce useful articles of manufacture including gears, sprockets, washing machine agitators, gear housings, and the like.

3,579,477
POLYESTER COATING AND MOLDING COMPOSITION
 Samuel P. Vess, Marfa, Tex., assignor to Decor Dimensionals, Inc., Greenville, Tex.
 No Drawing. Filed Sept. 3, 1968, Ser. No. 757,104
 Int. Cl. C08k 1/02

U.S. Cl. 260—40 **29 Claims**
 A composition and method for forming semi-flexible and rigid polyester articles and coatings which are vapor-

permeable and liquid impervious. The compositions comprise mixtures of polyesters, expanded mineral fillers and a monomeric polymerizable solvent.

3,579,478
POLYOLEFIN STABILIZATION
 Howard E. Dunn and Ronald D. Mathis, Bartlesville, Okla., assignors to Phillips Petroleum Company
 No Drawing. Filed Jan. 6, 1969, Ser. No. 789,384
 Int. Cl. C08f 45/62

U.S. Cl. 260—45.75 **7 Claims**
 Minor amounts of nickel complexes of the type
 $(R_2NCH_2CH_2S)_2Ni$


wherein R is hydrogen or a hydrocarbon radical, are incorporated into solid homopolymers or copolymers derived from olefins having from 2 to 6 carbon atoms per molecule for protection against the deteriorating effects of ultraviolet light.

3,579,479
3-ENDO-METHYL - 3 - EXO(4' - METHYL - 5'-HYDROXYPENTYL)NORCAMPOR AND 2-METHYL-5-BROMOPENTANOL, AND PROCESS FOR THE PREPARATION OF THESE COMPOUNDS
 Wayne I. Fanta and William F. Eрман, Springfield Township, Hamilton County, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
 No Drawing. Filed Mar. 29, 1968, Ser. No. 717,360
 Int. Cl. C07c 49/27

U.S. Cl. 260—586 **12 Claims**
 The novel compounds, 2-methyl-5-bromopentanol and 3-endo-methyl-3-exo(4' - methyl - 5' - hydroxypentyl) norcamphor and the process for preparing 2-methyl-5-bromopentanol and 3 - endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl)norcamphor from 2 - methyl-4-pentenol comprising the steps of (1) borating 2-methyl-4-pentenol with boric acid and/or boric anhydride to obtain tri(2-methyl-4-pentenyl)borate; (2) hydrobrominating the tri(2-methyl-4-pentenyl)borate in the presence of a free radical catalyst and, subsequently, hydrolyzing the reaction product to obtain 2-methyl-5-bromopentanol; (3) borating the 2-methyl-5-bromopentanol with boric acid and/or boric anhydride to obtain tri(2-methyl-5-bromopentyl)borate; (4) alkylating 3 - methylnorcamphor with the tri(2-methyl-5-bromopentyl)borate and, subsequently, hydrolyzing the reaction product to obtain 3-endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl)norcamphor.

3,579,480
CATALYST SYSTEM FOR POLYMERIZING SATURATED, ALIPHATIC ALDEHYDES
 Henricus Gerardus Josef Overmars, Zeist, and Jan Gerrit Noltes, Utrecht, Netherlands, assignors to International Lead Zinc Research Organization, Inc., New York, N.Y.
 No Drawing. Filed June 5, 1968, Ser. No. 734,577
 Claims priority, application Netherlands, June 20, 1967, 6708558
 Int. Cl. C08g 1/06, 1/08

U.S. Cl. 260—67R **11 Claims**
 A catalyst system for polymerizing or copolymerizing aldehydes, comprising a mixture of (1) dialkylzinc, (2) a co-catalyst, such as alcohol, amine, or water, and (3) a stabilizing agent having the formula



wherein each R represents hydrogen, alkyl, cycloalkyl, aralkyl, or aryl radicals, and when R₁, R₂, and R₃=hydrogen, R₄ contains at least three carbon atoms.

3,579,481
CATALYST SYSTEM FOR POLYMERIZING SATURATED, ALIPHATIC ALDEHYDES
 Henricus Gerardus Josef Overmars, Zeist, and Jan Gerrit Noltes, Utrecht, Netherlands, assignors to International Lead Zinc Research Organization, Inc., New York, N.Y.
 No Drawing. Filed June 5, 1968, Ser. No. 734,576
 Claims priority, application Netherlands, June 20, 1967, 6708558
 Int. Cl. C08g 1/06, 1/08

U.S. Cl. 260—67R **12 Claims**
 A catalyst system for polymerizing or copolymerizing aldehydes, comprising a mixture of (1) dialkylzinc, (2) a co-catalyst, such as alcohol, amine, or water, and (3) a stabilizing agent having the formula Aryl—NR—CO—R' wherein R represents hydrogen, alkyl, cycloalkyl, or aryl radicals, and R' represents alkyl, aryl, alkoxy, aryloxy or carbamate radicals.

3,579,482
POLYMERS OF OLEFINICALLY UNSATURATED DIISOCYANATES (III)
 Thomas K. Brotherton and John W. Lynn, Charleston, W. Va., assignors to Union Carbide Corporation
 Division of application Ser. No. 409,921, Nov. 9, 1964, now Patent No. 3,427,346, which is a continuation-in-part of application Ser. No. 212,480, July 25, 1962. This application Apr. 2, 1968, Ser. No. 718,080
 Int. Cl. C08g 22/18

U.S. Cl. 260—77.5 **14 Claims**
 Polyisocyanato-containing polymers obtained via the vinyl polymerization of unsaturated diester diisocyanates as exemplified by bis(2-isocyanatoethyl) fumarate with/without ethylenically unsaturated compounds, e.g., styrene, vinyl acetate, etc., which have utility in the manufacture of foamed products, coatings, reinforced plastic materials, and other areas.


3,579,483
ε-CAPROLACTAM CONTINUOUS POLYMERIZATION PROCESS
 Ian C. Twilley, Chester, and William N. Russell and Weldon H. Peterson, Colonial Heights, Va., assignors to Allied Chemical Corporation, New York, N.Y.
 Filed Apr. 15, 1969, Ser. No. 916,285
 Int. Cl. C08g 20/14, 20/42

U.S. Cl. 260—78 **11 Claims**
 Apparatus and process for continuous polymerization of polyamides to produce a polymer wherein the required viscosity can be obtained much more rapidly and the extent of polymerization far greater than heretofore possible by use of a vacuum demisting column within the polymerization train wherein the pre-polymer is converted to polyamide of higher molecular weight in a short period of time by exposing at least about 0.2 square foot of pre-polymer per pound thereof to a temperature of between about 230° C. and about 300° C. at pressures of less than about 500 mm. Hg. The apparatus and process yields even greater efficiencies when used in conjunction with polyamidation catalysts.

3,579,484
COMPOUNDING AIDS FOR THERMOSETTING ALLYLIC RESIN MOLDING COMPOUNDS
 James Larue Thomas, Baltimore, Md., assignor to FMC Corporation, New York, N.Y.
 Filed Mar. 18, 1968, Ser. No. 713,675
 Int. Cl. C08f 3/60, 45/04

U.S. Cl. 260—78.4 **8 Claims**
 The compounding characteristics of thermosetting allylic resin molding compounds are improved by the addition of 1 to 100 parts per million, by weight based on resin,

of a metal, in chemically combined form, selected from the group consisting of magnesium, potassium, calcium, vanadium, chromium, manganese, iron, cobalt, nickel, copper, zinc, zirconium, molybdenum, antimony, tungsten, lead and cerium.



Addition of an effective amount of these selected metals causes a substantial improvement in compounding performance in terms of controllable uniform rate of viscosity increase during compounding and elimination of sticking to compounding equipment without substantially altering the properties of the molding compound or the final molded product.

3,579,485

CHLORINATED CARBOXYL GROUP CONTAINING POLY- α -OLEFINS

Paul D. Folzenlogen, Windell C. Watkins, and Hugh J. Hagemeyer, Jr., Longview, Tex., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Feb. 7, 1969, Ser. No. 797,700
Int. Cl. C08f 3/02, 3/04, 3/08

U.S. Cl. 260—78.4D

19 Claims

This invention relates to chlorinated carboxyl group containing poly- α -olefins which can be prepared by chlorinating a carboxyl group containing poly- α -olefin. These chlorinated poly- α -olefins form primer coatings for use on untreated poly- α -olefin substrates, which can be decorated by printing or painting.

3,579,486

MALEATED POLYOLEFINS

Richard L. McConnell and Frederick B. Joyner, Kingsport, Tenn., assignors to Eastman Kodak Company, Rochester, N.Y.

No Drawing. Filed Dec. 22, 1967, Ser. No. 692,703
Int. Cl. C08f 15/04, 27/04, 27/08

U.S. Cl. 260—78.4

7 Claims

Normally available maleated polyolefins are improved by treating with a base to neutralize residues in the nature of maleic or fumaric acid; such bases include organic amines, metal hydroxides or metal alkoxides. The improved products have greater adhesion to paper, leather, fabrics, metal foils and other substrates, are generally free of toxic constituents and produce improved stereographic sheets and other coated objects.

3,579,487

POLYANHYDRIDE-MONOEPoxide COMPOSITIONS CONTAINING A MONOANHYDRIDE

Stanley M. Hazen, Cheswick, and William J. Heilmann, Allison Park, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed Oct. 19, 1967, Ser. No. 676,408

Int. Cl. C08f 15/00

U.S. Cl. 260—78.5T

7 Claims

Liquid coating and molding compositions are provided which are curable to an infusible resin article or coating. The composition comprises a solution of a saturated or unsaturated monooxirane compound, for example epichlorohydrin, a monoanhydride of a dicarboxylic acid containing at least 5 carbon atoms, such as phthalic anhydride and a solid polyanhydride having succinic anhydride groups (excluding aromatic anhydrides in which the α -carbon atoms of the anhydride group are included in the aromatic ring) for example the copolymer of a straight chain α -monoolefin and a maleic anhydride. Preferably a tertiary amine, such as 3-picoline, is included as a cure accelerator. The composition shows little or no shrinkage and weight loss during curing, in contrast to the same composition minus the mono-anhydride. Thus for example, films and coatings free of lifting and etching are obtained.

3,579,488

WATER-SOLUBLE COPOLYMERS OF ALKYL-ENIMINE AND ALKYLENE SULFIDE

Giffin D. Jones and Nancy B. Tefertiller, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Jan. 16, 1969, Ser. No. 791,806

Int. Cl. C08g 25/00

U.S. Cl. 260—79

6 Claims

Water-soluble copolymers of a C_2 - C_4 alkyl enimine and a C_2 - C_4 alkylene sulfide are obtained by an acid catalyzed copolymerization using as a catalyst about 3-15 mole percent based on total monomer of a strong water-soluble organic acid, preferably an aromatic sulfonic acid. The resulting water-soluble copolymers, having an average molecular weight of about 5-50 thousand contain about 10-40 mole percent copolymerized alkylene sulfide and are effective dispersants and dewatering agents in sewage treatment and also have flocculant activity.

3,579,489

POLYMERIZATION OF BETA-LACTONES

Willem M. Wagner, Amsterdam, Netherlands, assignor to Shell Oil Company, New York, N.Y.

No Drawing. Filed Dec. 20, 1968, Ser. No. 785,795
Claims priority, application Great Britain, July 1, 1968, 31,239/68

Int. Cl. C08g 17/02

U.S. Cl. 260—78.3

12 Claims

The molecular weight distribution and heat stability of polylactones, particularly poly(beta-lactones), are controlled by polymerizing the lactones in the presence of an ionic initiator and certain chain-transfer agents such as alpha-halo-ketones and alpha-halo-aldehydes.

3,579,490

METHOD OF PRODUCING RESINS FOR USE IN ADHESIVES

Stanley Kordzinski, deceased, late of Old Bridge, N.J., by Eileen Kordzinski, executrix, Old Bridge, and Milton B. Horn, Plainfield, N.J., assignors to Ashland Oil & Refining Company, Ashland, Ky.

No Drawing. Continuation-in-part of abandoned application Ser. No. 20,822, Apr. 8, 1960. This application Aug. 31, 1964, Ser. No. 393,433

Int. Cl. C08f 15/14, 15/18, 15/20

U.S. Cl. 260—80.72

11 Claims

A tacky and pressure sensitive adhesive comprising one or more aliphatic esters of acrylic, methacrylic and acetic acid together with one or more of glycidyl acrylate, glycidyl methacrylate or glycidyl allyl ether is disclosed. The proportions of monomeric ingredients are selected to give a calculated glass transition temperature from about -20° C. to about -55° C. The monomeric system is copolymerized at a temperature not exceeding about 100° C. in order to keep the glycidyl compounds intact during polymerization.

3,579,491

METHOD FOR PREPARING POLYMERS AND COPOLYMERS OF VINYL CHLORIDE BY BULK POLYMERIZATION AT LOW TEMPERATURE AND PRODUCTS THEREOF

Marc E. Carrega, Chatenay-Malabry, France, assignor to Produits Chimiques Pechiney-Saint-Gobain, Neuilly-sur-Seine, France

No Drawing. Filed Jan. 30, 1969, Ser. No. 795,347
Claims priority, application France, Feb. 7, 1968, 139,017

Int. Cl. C08f 3/30, 15/06

U.S. Cl. 260—85.5

11 Claims

The polymerization and copolymerization of vinyl chloride in bulk, in the absence of oxygen and at a temperature within the range of -100° to 20° C. in the presence of a catalytic system comprising an alpha-halo-generated diacyl peroxide and an organo aluminum compound.

3,579,492

METHOD FOR PREPARING LONG CHAIN ALKYL COMPOUNDS

William Novis Smith, Jr., Exton, Pa., assignor to Foote Mineral Company, Exton, Pa.

No Drawing. Filed Apr. 18, 1968, Ser. No. 722,179

Int. Cl. C08f 1/76, 3/06

U.S. Cl. 260—94.9

10 Claims

Ethylene is polymerized in a solution of an n-butyl-lithium: N,N,N',N'-tetramethylethylene diamine complex under temperature and pressure conditions selected from a narrow range of each until substantially all of the resulting polymer has precipitated from the solution as a long chain n-alkyllithium compound which may be converted to the corresponding polyethylene having a molecular weight from about 1500 to about 4000 with a Mw/Mn ratio of about 1.

3,579,493

POLYMERIZATION OF ETHYLENE USING REDUCED GROUPS IV-B, V-B AND VI-B METAL SALTS AS THE POLYMERIZATION CATALYST

Karl Ziegler, 1 Kaiser Wilhelm Platz, Muelheim (Ruhr), Germany, and Heinz Breil, Muelheim (Ruhr), Germany; said Breil assignor to said Ziegler

No Drawing. Filed Aug. 9, 1955, Ser. No. 527,412
Claims priority, application Germany, Aug. 13, 1954, Z 4,371; Aug. 14, 1954, Z 4,374

Int. Cl. C08d 3/04, 3/08

U.S. Cl. 260—94.9

13 Claims

The polymerization of ethylene utilizing a catalyst formed by reducing a halide or acetylacetonate of a metal of Groups IV-B, V-B and VI-B of the periodic chart of the elements, including thorium and uranium, with an alkali metal or magnesium, or a mixture or an alloy thereof, or sodium-, lithium- or calcium hydride. The reduction agent may be in the form of a complex, as for example a complex compound with an organo boron compound. The catalyst may also be admixed with table salt.

3,579,494

C-SULFONATED TYROSYL PEPTIDES RELATED TO CHOLECYSTOKININ-PANCREOZYMIN (CCK-PZ)

Miguel A. Ondetti, North Brunswick, John T. Sheehan, Middlesex, and Josip Pluscec, East Brunswick, N.J., assignors to E. R. Squibb & Sons, Inc., New York, N.Y.

No Drawing. Filed July 18, 1968, Ser. No. 745,688

Int. Cl. C07c 103/52

U.S. Cl. 260—112.5

7 Claims

Novel peptide amides of the general formula



wherein R represents L-aspartyl-3'-sulfonyl-L-tyrosyl, L-aspartyl-L-arginyl-L-aspartyl-3'-sulfonyl-L-tyrosyl, or isoleucyl-L-seryl-L-aspartyl-L-arginyl-L-aspartyl-3'-sulfonyl-L-tyrosyl, and intermediates in the production thereof. The peptide amides of this invention as well as the pharmaceutically acceptable salts thereof have been found to possess cholecystokinin activity.

3,579,495

ISOLATION OF ORGOTEIN FROM BLOOD

Wolfgang Huber, San Francisco, Calif., assignor to Diagnostic Data, Inc., Palo Alto, Calif.

No Drawing. Continuation-in-part of application Ser. No. 815,175, Apr. 16, 1969, which is a continuation-in-part of application Ser. No. 728,777, May 13, 1968. This application Apr. 24, 1970, Ser. No. 31,791

Int. Cl. A61k 17/00; C07g 7/04

U.S. Cl. 260—115

5 Claims

Orgotein is isolated from lysed plasma-free erythrocytes by a series of steps which include removing the hemoglobin from the lysate, heating the remaining soluble proteins in the presence of buffer and divalent metal ion until the carbonic anhydrase is inactivated, removing the precipitate, and separating the orgotein protein from the supernatant liquid.

3,579,496

SELECTIVE EXTRACTION PROCESS PRODUCING PROTEIN ISOLATES FROM OILSEED MEALS USING WATER OR DIVALENT METAL SALTS AS EXTRACTING AGENTS

Wilda H. Martinez and Leah C. Berardi, New Orleans, La., assignors to the United States of America as represented by the Secretary of Agriculture

Filed July 17, 1969, Ser. No. 842,576

Int. Cl. A23j 1/14; C07g 7/00

U.S. Cl. 260—123.5

26 Claims

A process for extracting selectively protein fractions from oilseed flour which process comprises a preliminary extraction with water or a dilute (.008 M) polyvalent cationic salt solution and subsequently with aqueous base (.015 N sodium hydroxide).

The protein isolates thus extracted differ in composition, average molecular weight and solubility characteristics. With certain oilseeds, the disclosed process provides for the recovery of somewhat more of the total nitrogen from the flour being processed and for an improved flavor and color in the major isolate than does a conventional single-step alkaline extraction process.

3,579,497

WATER-INSOLUBLE MONOAZO DYESTUFFS

Visvanathan Ramanathan, Basel, and Klaus Artz, Muttentz, Switzerland, assignors to Ciba Limited, Basel, Switzerland

No Drawing. Filed Oct. 31, 1967, Ser. No. 679,522
Claims priority, application Switzerland, Nov. 7, 1966, 16,002/66

Int. Cl. C09b 29/06; D06p 1/02

U.S. Cl. 260—158

10 Claims

Water-insoluble monoazo dyestuffs of the formula



in which A represents a benzene radical or a heterocyclic radical and B represents a benzene radical containing an amino group in para-position to the azo group, one of the hydrogen atoms of the amino group being replaced by an alkyl radical that may be substituted and the other being replaced by a phenalkyl radical bearing a negative substituent. The compounds are suitable for dyeing and painting materials such as fibers and fabrics.

3,579,498


METHOD OF MAKING AZO, 3-SUBSTITUTED PYRAZOLONE DYES

William Paul Dunworth, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.


No Drawing. Continuation-in-part of application Ser. No. 594,352, Nov. 15, 1966. This application Nov. 6, 1967, Ser. No. 680,968

Int. Cl. C09b 29/38, 31/14, 33/12

U.S. Cl. 260—158 8 Claims
Arylazo-, aryl disazo-, and benzothiazolylarylazo-1,3-substituted-5-pyrazolones, for example,



and



useful as paper dyes having good water solubility, bleachability, brightness, lightfastness and tinctorial strength, and as intermediates for cationic dyes which in turn are useful in dyeing acid modified acrylic, polyester and polyamide fibers.

3,579,499

AMINO ALKYL ESTERS OF 5 β -PREGN-20-ENE-21-CARBOXYLIC ACIDS AND THE 3-GLYCOSIDES THEREOF

Richard Clarkson, Macclesfield, England, assignor to Imperial Chemical Industries Limited, London, England

No Drawing. Filed July 1, 1968, Ser. No. 741,241
Claims priority, application Great Britain, July 10, 1967, 31,671/67

Int. Cl. C07c 173/00

U.S. Cl. 260—210.5 5 Claims

The disclosure relates to aminoalkyl esters of 5 β -pregn-20-ene-21-carboxylic acids, processes for their manufacture, pharmaceutical compositions containing them and a method of using them to increase the force of contraction of the heart of warm-blooded animals. Representative of the steroid derivatives disclosed is 2-dimethyl-aminoethyl 3 β -14 β -dihydroxy-5 β -pregn-20-ene-21-carboxylate.


3,579,500

1-ARYL-3-ALKYLURETIDINEDIONES

Arthur G. Jelinek, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed May 28, 1968, Ser. No. 732,558
Int. Cl. C07d 47/00

U.S. Cl. 260—239 9 Claims
Compounds useful as herbicides of the formula:



where

A is hydrogen, halogen, alkyl, alkoxy, nitro, cyano, trifluoromethyl, p-chlorophenoxy or m-(tertiary butyl-carbamoyloxy);

Z is hydrogen or halogen;

m is 1 or 2, and

R is alkyl, cycloalkyl, methylcyclohexyl, cyclohexylmethyl, cyclopentylmethyl, allyl, methallyl.

Typical is 1-(3,4-dichlorophenyl)-3-methyluretidinedione.

3,579,501

6-[α -(3-GUANYL-1-UREIDO)PHENYL-OR THIENYL-ACETAMIDO]PENICILLANIC ACIDS

Donald Neil McGregor, Fayetteville, N.Y., assignor to Bristol-Myers Company, New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 780,557, Dec. 2, 1968. This application Aug. 22, 1969, Ser. No. 852,457

Int. Cl. C07d 99/16

U.S. Cl. 260—239.1 16 Claims

6-[α -(3-guanyl-1-ureido)phenylacetamido]- and 6-[α -(3-guanyl-1-ureido)thienylacetamido]-penicillanic acids are valuable as antibacterial agents, nutritional supplements in animal feeds, therapeutic agents in poultry and animals, including man, and are especially useful in the treatment of infectious diseases caused by Gram-positive and Gram-negative bacteria, most particularly those caused by the *Pseudomonas* genus. 6-[D- α -(3-guanyl-1-ureido)phenylacetamido]-penicillanic acid, a preferred embodiment of the invention, is prepared by the reaction of 6-(D- α -amino-phenylacetamido)-penicillanic acid (ampicillin) with a guanylcabamylating agent.

3,579,502

PROCESS FOR PREPARING TETRAHYDRO[2,1-d]-BENZO[f][1,4]-DIAZEPIN-6(7H)-ONES AND INTERMEDIATES

Marcel Müller, Frenkendorf, and Paul Zeller, Allschwil, Switzerland, assignors to Hoffmann-La Roche Inc., Nutley, N.J.

No Drawing. Filed Jan. 16, 1967, Ser. No. 609,321
Claims priority, application Switzerland, Jan. 21, 1966, 855/66

Int. Cl. C07d 53/06

U.S. Cl. 260—239.3 4 Claims

In the instant case, there is disclosed various processes for preparing 5,9,10,14b-tetrahydroisoquinolo[2,1-d]-benzo[f][1,4]diazepin-6(7H)-ones(A). In one important process variation, a 1-(o-amino-phenyl)-3,4-dihydroisoquinoline(B) is reacted with a member capable of providing a halo-lower alkanoyl group such as halo lower alkanoyl halide to give a novel (2'-halo-lower alkanoyl-amino-phenyl)(C) derivative. C is then ring closed to a novel 6-oxo-6,7,9,10-tetrahydroisoquinolo[2,1-d]benzo[f][1,4]diazepin-(8)-ium(D). D is then reduced to A.

In another important process variation, B or a 1-(o-nitro-phenyl)-3,4-dihydroisoquinoline is treated with an α -substituted acetic acid derivative. The resulting product is reduced and ring closed at elevated temperatures to A.

Compounds A are useful for pharmaceutical purposes, e.g. as sedatives, as tranquilizers, as anti-convulsants and as muscle relaxants.

3,579,503

PYRROLO[3,2,1-jk][1,4]BENZODIAZEPINONES

Jackson B. Hester, Jr., Portage, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

No Drawing. Filed Nov. 3, 1969, Ser. No. 873,718
Int. Cl. C07d 53/06

U.S. Cl. 260—239.3 21 Claims

1,2-dihydro-7-phenylpyrrolo[3,2,1-jk][1,4]benzodiazepin-4(5H)-ones; 6,7-dihydro-7-phenyl-

pyrrolo[3,2,1-jk][1,4]benzodiazepin-4(5H)-ones; 7-phenylpyrrolo[3,2,1-jk][1,4]benzodiazepin-4(5H)-ones; 1,2-dihydro-6-phenylpyrrolo[1,2,3-ef][1,5]benzodiazepin-4(5H)-ones; 1,2-dihydro-4-phenylpyrrolo[1,2,3-ef][1,5]benzodiazepin-6(7H)-ones and 1,2,4,5-tetrahydro-4-phenylpyrrolo[1,2,3-ef][1,5]benzodiazepin-6(7H)-ones, processes for preparing the same and novel intermediates prepared by said processes. The novel compounds of this invention exhibit tranquilizing and anti-convulsant activity in animals.

3,579,504

DERIVATIVE OF $\Delta^4,9$ -GONADIENE AND PROCESS OF PREPARATION


Gerard Nominé, Noisy-le-Sec, Robert Bucourt, Clichy-sous-Bois, and André Pierdet, Noisy-le-Sec, France, assignors to Roussel-UCLAF, S.A., Paris, France

No Drawing. Continuation-in-part of application Ser. No. 282,587, May 23, 1963. This application Apr. 26, 1965, Ser. No. 451,051

Int. Cl. C07c 173/00

U.S. Cl. 260—239.55 8 Claims

The present invention relates to a new derivative of $\Delta^4,9$ -gonadiene of Formula I;



as well as a process of preparation of the said compound. The invention also relates to intermediates useful in the production of the compound of Formula I.

3,579,505

ALISOL COMPOUNDS

Masuo Miyamoto, Kyoto, and Tadakazu Murata, Suita, Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

No Drawing. Filed Sept. 25, 1968, Ser. No. 762,637
Int. Cl. C07c 169/38, 173/00

U.S. Cl. 260—239.55 17 Claims

The crude extract of an Alismataceae plant or saponification product thereof is brought into contact with an acid (mineral acid, sulfonic acid, carboxylic acid, Lewis acid) whereby the Alisol B contained in the extract is converted into Alisol A. The Alisol compounds of the invention, including Alisol A itself, show hypercholesterolemic activities.

3,579,506

 α -AMINOISOTHIAZOLYLACETIC ACIDS AND THEIR PENICILLIN AND CEPHALOSPORIN DERIVATIVES

Raymond Urgel Lemieux and Rintje Raap, Edmonton, Alberta, Canada, assignors to R & L Molecular Research Ltd., Edmonton, Alberta, Canada

No Drawing. Filed Oct. 23, 1968, Ser. No. 770,068
Int. Cl. C07d 99/24, 99/16

U.S. Cl. 260—239.1 13 Claims

α -aminoisothiazolylacetic acid derivatives of 6-amino- have been prepared and used in the preparation of α -aminoisothiazolylacetic acid derivatives of 6-amino-penicillanic acid and 7-aminocephalosporanic acid which have been found to be useful as antibacterial agents.

3,579,507


7 $\alpha,8\alpha$ -DIFLUOROMETHYLENE STEROIDS

David J. Marshall, Hampstead, Quebec, and Amedeo A. Failli, Montreal, Quebec, Canada, assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Filed July 28, 1969, Ser. No. 845,538
Int. Cl. C07c 173/00

U.S. Cl. 260—239.5 10 Claims

7 $\alpha,8\alpha$ -difluoromethylene steroids of the formula



in which R represents hydrogen, lower alkyl or cycloalkyl, or lower aliphatic acyl and R¹ represents O (ketonic oxygen) or the group



in which R² represents hydrogen, lower alkyl, lower alkynyl, lower dialkynyl, 2- or 3-furyl, or 2- or 3-thienyl groups.

3,579,508

21-SUBSTITUTED 6-CHLORO-16 $\alpha,17\alpha$ -ISOPROPYLIDENEDIOXY-PREGNA-4,6-DIENE-3,20-DIONE AND METHOD OF PREPARING THE SAME

Milton David Heller, New City, N.Y., Robert Herman Lenhard, Paramus, N.J., and Seymour Bernstein, New City, N.Y., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Mar. 20, 1969, Ser. No. 808,983
Int. Cl. C07c 173/00

U.S. Cl. 260—239.55 1 Claim

The compounds 21-chloro or 21-methanesulfonyloxy-6-chloro-16 $\alpha,17\alpha$ -isopropylidenedioxypregna-4,6-diene-3,20-dione are described along with methods of preparing the same. They are useful as anti-fertility agents.

3,579,509

PROCESS AND 6- β -SUBSTITUTED ETHYL INTERMEDIATES FOR PREPARING 6,6-ETHYLENE-3-KETO- Δ^4 STEROIDS

Kenneth G. Holden, Stratford, N.J., assignor to Smith Kline & French Laboratories, Philadelphia, Pa.

No Drawing. Continuation-in-part of abandoned application Ser. No. 465,788, June 21, 1965. This application Sept. 20, 1965, Ser. No. 488,758

Int. Cl. C07c 173/00

U.S. Cl. 260—239.57 17 Claims

6,6-ethylene steroids having potent, often enhanced, pharmacodynamic activity compared with their respective parent compounds are prepared by condensing a 3-lower alkoxy-3,5-diene steroid with β -acyloxyethylmercuric acylate, hydrolyzing the resulting 6- β -acyloxyethyl-3-lower alkoxy-3,5-diene steroid to give a 6- β -hydroxyethyl-3-lower alkoxy-3,5-diene steroid or a 6- β -hydroxyethyl-3-keto- Δ^4 steroid, esterifying same and cyclizing said ester.

3,579,510

3-(HYDROXY-PHENYL) SUBSTITUTED AMIDINES AND DERIVATIVES THEREOF AS ANTHELMINTIC AGENTS

James W. McFarland, Lyme, Conn., assignor to Pfizer Inc., New York, N.Y.

No Drawing. Filed Aug. 30, 1967, Ser. No. 664,258
Int. Cl. C07c 123/00; C07d 49/34, 51/36

U.S. Cl. 260—240 4 Claims

The preparation and anthelmintic properties of certain ω -(3-R-O-phenyl)substituted cyclic and acyclic amidines;

3,579,524

2-AMINOALKYL DERIVATIVES OF PHTHALIMIDINES

John William Van Dyke, Jr., Elkhart, Ind., assignor to Miles Laboratories, Inc., Elkhart, Ind.
No Drawing. Filed June 5, 1968, Ser. No. 734,574
Int. Cl. C07d 29/30


U.S. Cl. 260—294 6 Claims
2-aminoalkyl derivatives of phthalimidine that are useful as antihypertensive agents. Prepared by reacting phthalic anhydride with a suitable amine and selectively reducing one of the oxo groups of the resulting phthalimide to form the desired compound.

3,579,525

S-(PYRIDYL)METHYL THIO- AND DITHIO-CARBAMATES

Harry Tilles, El Cerrito, and Mervin E. Brokke, Moraga, Calif., assignors to Stauffer Chemical Company, New York, N.Y.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,681
Int. Cl. C07d 31/50

U.S. Cl. 260—294.8 32 Claims
S-(pyridyl)methyl thio- and dithio-carbamates having the formula



in which X is oxygen or sulfur, R and R₁ are independently alkyl, alkenyl, or cyclohexyl and R and R₁ taken together are alkylene and dialkyl substituted alkylene, provided that when X is sulfur and R and R₁ are both alkyl, at least one of the alkyl groups contains 3 or more carbon atoms. The above compounds, as well as those excluded by the proviso, are effective herbicides. Representative compounds are

S-(3-pyridyl)methyl di-n-propylthiocarbamate,
S-(2-pyridyl)methyl di-n-butylthiocarbamate,
S-(4-pyridyl)methyl methylcyclohexylthiocarbamate,
S-(4-pyridyl)methyl ethyl-n-butylthiocarbamate and S-(3-pyridyl)methyl 1-(5-ethyl-2-methyl-piperidinecarbothioate).

3,579,526

PREPARATION OF THIENOPYRIDINES

Le Roy H. Klemm and Joseph Shabtai, Eugene, Oreg., and David R. McCoy, Wappingers Falls, N.Y., assignors to Research Corporation, New York, N.Y.
No Drawing. Filed Nov. 13, 1968, Ser. No. 775,534
Int. Cl. C07d 31/50

U.S. Cl. 260—294.8 13 Claims
Thienopyridines are prepared by the decomposition of benzyl 2-(pyridyl) ethyl sulfides. The thermal decomposition may be catalytic or non-catalytic and is desirably carried out at a temperature in the range 500–700° C. Thieno[3,2-b] pyridine is prepared by the thermal decomposition of benzyl 2-(2-pyridyl) ethyl sulfide and thieno[2,3-c] pyridine is prepared by the thermal decomposition of benzyl 2-(4-pyridyl) ethyl sulfide.

3,579,527

N-SUBSTITUTED PYRIDO-INDOLE DERIVATIVES
Meier E. Freed, Philadelphia, Pa., assignor to American Home Products Corporation, New York, N.Y.
No Drawing. Original application June 27, 1966, Ser. No. 560,811. Divided and this application July 18, 1969, Ser. No. 870,805
Int. Cl. C07d 39/00

U.S. Cl. 260—296 2 Claims
N-substituted-tetrahydropyrido-indoles are prepared having useful pharmacological activity, particularly on the central nervous system.

3,579,528

2,6-DIHYDROXYTRICHLOROPYRIDINE AND ITS PREPARATION

Robert Neville Haszeldine, "Windyridge," Lyme Road, Disley, Cheshire, England, and William Thain Flowers, 19 Birch Grove, Rusholme, Manchester 14, England
No Drawing. Filed May 22, 1968, Ser. No. 731,273
Claims priority, application Great Britain, June 7, 1967, 26,218/67

Int. Cl. C07d 31/28 4 Claims
The new compound 2,6-dihydroxytrichloropyridine is prepared by reacting 2,6-diaminopyridine with chlorine while in admixture with aqueous mineral acid. The dihydroxytrichloropyridine is useful as a contact herbicide and as a novel intermediate in the preparation of pentachloropyridine.

3,579,529

HETEROCYCLIC COMPOUNDS

Kevan Brown, Woodley, and John F. Cavalla, Isleworth, England, assignors to John Wyeth & Brother Limited, Taplow Maidenhead, England
No Drawing. Filed Oct. 15, 1968, Ser. No. 767,853
Claims priority, application Great Britain, Oct. 26, 1967, 48,641/67

Int. Cl. C07d 91/32, 85/44 11 Claims
U.S. Cl. 260—302

A group of oxazoles and thiazoles substituted by a cycloaliphatic radical in the 2-position and an aliphatic acidic radical in the 4-position is described. The compounds are useful as anti-inflammatory agents.

3,579,530

PROCESS FOR THE RESOLUTION OF RACEMIC TETRAMISOLE

Robert Alfred Dewar, Ashburton, Victoria, Volker Elmar Maier, Hampton, Victoria, and Margaret Anthea Ingram, South Yarra, Victoria, Australia, assignors to Imperial Chemical Industries of Australia and New Zealand Limited

No Drawing. Filed Aug. 12, 1968, Ser. No. 751,716
Claims priority, application Australia, Aug. 24, 1967, 26,376; Jan. 11, 1968, 32,285; Jan. 18, 1968, 32,424
Int. Cl. C07d 99/06

U.S. Cl. 260—306.7 7 Claims
Resolution of tetramisole into its optically active D- and L-isomers using a resolving acid in a predominantly aqueous medium whereby said acid forms a salt with one of the isomers and said salt crystallises from the medium to the substantial exclusion of the other tetramisole isomer salt.

3,579,531

PROCESS FOR PREPARING 1-PHENYL-1,2,3-TRIAZOLES

Peter Scheiner, Princeton, N.J., assignor to Mobil Oil Corporation
No Drawing. Filed Feb. 28, 1968, Ser. No. 708,753
Int. Cl. C07d 55/02

U.S. Cl. 260—308 6 Claims
Phenyl triazole and various substituted phenyl triazoles are prepared by reacting substituted phenyl azides or phenyl azide with a vinyl ester of a lower alkanolic acid preferably vinyl acetate, at reflux temperature and at atmospheric pressure. 1-phenyl-1,2,3-triazole and substituted derivatives thereof are stabilizers for polyolefins. The 1-halophenyl-1,2,3-triazoles are effective fungicides and miticides.


3,579,532

BIS-PHOSPHONO-PROPIONAMIDE SUBSTITUTED ETHYLENE GLYCOLS AND IMIDAZOLIDINONES

Hermann Nachbar, Dornach, Switzerland, Bernard Peter Stark, Stapleford, Cambridge, England, and Arthur Maeder, Therwil, Switzerland, assignors to Ciba Limited, Basel, Switzerland
No Drawing. Filed July 22, 1968, Ser. No. 746,308
Claims priority, application Great Britain, July 28, 1967, 34,922/67

Int. Cl. C07d 49/34 10 Claims
U.S. Cl. 260—309.7

This invention provides phosphorus-containing products which are obtained by reacting a compound of the formula



wherein R₁ represents a substituent bound through a carbon atom to the oxygen atom and R₂ e.g. a hydrogen atom or a methyl group, with glyoxal, formaldehyde, urea and an etherifying agent like a saturated or unsaturated aliphatic alcohol.

These phosphorus-containing reaction products are useful as agents for flameproofing.

3,579,533

PREPARATION OF PORPHIN, SUBSTITUTED PORPHIN AND METAL CHELATES THEREOF

Richard G. Yalman, Yellow Springs, Ohio, assignor to Antioch College, Yellow Springs, Ohio
No Drawing. Filed Mar. 18, 1968, Ser. No. 714,064
Int. Cl. C07d 27/76

U.S. Cl. 260—314 10 Claims

Preparation of porphin, meso monomethyl-, meso dimethyl-, meso trimethyl-, and meso tetramethylporphin, and the metal chelates thereof in relatively large quantities with yields in the range of 1% to 20% is accomplished by cyclic condensation of a pyrrole having a primary or secondary carbinol in the 2 position thereof to form a metal chelate followed by demetallation to form porphin or the meso substituted porphin. The reaction mixture includes the hydroxypyrrole, a metal acetate, an organic acid and a polar solvent, and by (1) controlling the pH of the buffer formed by the metal acetate and the acid to between 3.2 and 5.5 based on a water system, (2) controlling the temperature of the reaction mixture in the range of 120° C. to 150° C., and (3) reducing the self-polymerization of the hydroxy-pyrrole by dropwise addition of a precooled mixture thereof to a preheated solvent system, much improved yields of the metal chelates are obtained. Also, the yields of porphin and meso substituted porphins were increased by an improved demetallation procedure permitting 75% to 85% yields from the corresponding metal chelates. Various metal acetates, solvents, temperature ranges, ratios of reactants and reaction conditions and techniques are described.

3,579,534

TETRAHYDROCARBAZOLECARBOXYLATES

Ruddy Littell, Rivervale, and George Rodger Allen, Jr., Old Tappan, N.J., assignors to American Cyanamid Company, Stamford, Conn.
No Drawing. Filed May 9, 1969, Ser. No. 823,471
Int. Cl. C07d 27/68

U.S. Cl. 260—315 6 Claims
Preparation of substituted tetrahydrocarbazolecarboxyl-

ic derivatives, are described. They are useful for their central nervous system activity, as anticonvulsants.

3,579,535

SUBSTITUTED PHENYLACETIC ACIDS AND ESTERS THEREOF

Rolf Denss, 43 Schutzenmattstr., Basel, Switzerland; Niels Clauson-Kaas, 28 Rugmarken, Farum, Denmark; and Franz Ostermayer, 5 Am Hang, Riehen, Switzerland
No Drawing. Filed Oct. 30, 1967, Ser. No. 679,224
Claims priority, application Switzerland, Oct. 31, 1966, 15,768; Jan. 31, 1967, 713; Aug. 7, 1967, 11,178

Int. Cl. C07d 27/26 24 Claims
U.S. Cl. 260—326.3

Substituted phenyl acetic acids, addition salts thereof with bases as well as esters thereof, which compounds exhibit useful antiinflammatory (antiphlogistic), analgesic and antipyretic activity, and processes for the production of these compounds, as well as starting materials used in said processes; therapeutic compositions containing these compounds, and methods of treatment, particularly methods of inducing antiinflammatory, analgesic and antipyretic effects in mammals. Illustrative embodiments are 2-[p-(1-pyrryl)-phenyl]-butyric acid, [3-chloro-4-(1-pyrryl)-phenyl]-acetic acid and 2-[p-(1-pyrryl)-phenyl]-propionic acid methyl ester.

3,579,536

ADDITION PRODUCTS OF METHYLFORMAMIDE OR SUCCINIMIDE WITH GLYOXAL

Sidney L. Vail and Andrew G. Pierce, Jr., New Orleans, La., Clifford M. Moran, San Gabriel, Calif., and Robert H. Barker, Metairie, La., assignors to the United States of America as represented by the Secretary of Agriculture

No Drawing. Filed Feb. 23, 1966, Ser. No. 529,251
Int. Cl. C07d 27/10

U.S. Cl. 260—326.3 3 Claims

The invention provides the compounds N,N'-dihydroxyethylenebis(methylformamide), N,N'-dihydroxyethylenebisuccinimide, and N,N'-(1,2-diacetoxyethylene)bissuccinimide which are useful as textile finishing agents for cellulosic fabrics, in resin applications, and in pharmaceutical and allied industries.

3,579,537

PROCESS FOR SEPARATION OF SULTONES FROM ALKENYL SULFONIC ACIDS

Joseph Rubinfeld and Henry Leon Levinsky, Brooklyn, N.Y., assignors to Colgate-Palmolive Company, New York, N.Y.

No Drawing. Filed Aug. 15, 1966, Ser. No. 581,409
Int. Cl. C07c 143/16; C07d 89/06

U.S. Cl. 260—327 13 Claims

The instant process is directed to separation of a sultone and an alkenyl sulfonic acid from a mixture thereof prepared by sulfonation of an olefin with SO₃, which comprises adding to said mixture (a) a water-soluble lower ketone which is a solvent for said sultone and said acid, and (b) a base which forms with said sulfonic acid a water soluble sodium, potassium, lithium or ammonium salt insoluble in said solvent, whereby to form a precipitate of said salt and a solution of said sultone, the temperature at the time of formation of said precipitate being at least about 15° C.

3,579,538


SUBSTITUTED BIS(2-HYDROXY-4-METHYL-5-METHYLTHIOPHENYL) METHANES

Ronald J. Meyer, Orville E. Horsley, and Herman J. Eichel, Cincinnati, Ohio, assignors to American Hoechst Corporation, New York, N.Y.
No Drawing. Filed June 26, 1968, Ser. No. 740,054
Int. Cl. C07c 15/12; C07d 63/12, 63/22

U.S. Cl. 260—330.5

1 Claim

Substituted bis(2-hydroxy-4-methyl-5-methylthiophenyl)methane compounds having laxative (cathartic) properties of the general formula:



and a process for preparing them.

3,579,539

DUAL SOLVENT SEPARATION OF 4-HYDROXY-BENZOTHIOPHENE FROM 4-OXO-4,5,6,7-TETRAHYDROBENZOTHIOPHENE

Edward M. Bullard, Fords, N.J., assignor to Mobil Oil Corporation

Filed Jan. 16, 1969, Ser. No. 791,614

Int. Cl. C07d 63/18, 63/22

U.S. Cl. 260—330.5

2 Claims

4-hydroxybenzothiophene is separated from 4-oxo-4,5,6,7-tetrahydrobenzothiophene by liquid-liquid extraction using a dual solvent system of a polar solvent, preferably propylene glycol, and a non-polar solvent, preferably toluene. The 4-hydroxybenzothiophene can be converted into N-methyl-4-benzothienyl carbamate, an effective pesticide (see U.S. 3,288,673 and 3,288,808).

3,579,540

METHOD FOR PROTECTING NONPOROUS SUBSTRATES AND FOR RENDERING THEM WATER REPELLENT

Howard G. Ohlhausen, 82 Graymoor Lane, Olympia Fields, Ill. 60461


No Drawing. Filed Nov. 1, 1968, Ser. No. 772,856

Int. Cl. C08g 31/02, 51/34

U.S. Cl. 260—33.4

16 Claims

Method and composition for treating nonporous substrates to protect and render same water repellent. A mineral acid is added to a solvent and an alkyl polysiloxane is then added to that mixture to produce the composition. The alkyl polysiloxane has the formula:



wherein n is an integer greater than 1, R_1 is a lower alkyl containing 1-7 carbon atoms and R_2 is hydrogen, a lower alkyl containing 1-7 carbon atoms or an aryl radical containing about 6 carbon atoms.

3,579,541

CYCLIC DIPEROXIDES

Yun G. Chang, Austin, Tex., assignor to Reichhold Chemicals, Inc., White Plains, N.Y.

No Drawing. Filed June 4, 1968, Ser. No. 734,258

Int. Cl. C07d 19/00

U.S. Cl. 260—338

9 Claims

Cyclic peroxides are prepared by reacting hydroxy acetone with a difunctional hydroperoxide. The reaction takes place in a solvent at a temperature ranging from about 0° C. to 100° C. in presence of an acidic catalyst. The resulting cyclic peroxides are found to be highly efficient polymerization initiators and cross-linking agents.

3,579,542


4,4',4''-TRIHIDROXYTRIPHENYLMETHYL-METHANE

Ronald J. Meyer, Orville E. Horsley, and Herman J. Eichel, Cincinnati, Ohio, assignors to American Hoechst Corporation, New York, N.Y.
No Drawing. Filed June 26, 1968, Ser. No. 740,066
Int. Cl. C09b 11/08

U.S. Cl. 260—395

1 Claim

4,4',4''-trihydroxytriphenylmethane having laxative (cathartic) properties of the formula:



and a process for preparing it.

3,579,543

 $\Delta^{1,3,5(10)}$ -2- (OR 4)-FORMYL-3-HYDROXY-OESTRADIENE COMPOUNDS

Max Salomon de Winter and Jan Evert Ribbers, Oss Netherlands, assignors to Organon Inc., West Orange, N.J.

No Drawing. Filed May 13, 1966, Ser. No. 549,786

Claims priority, application Netherlands, May 22, 1965, 6506542; Jan. 15, 1966, 6600548

Int. Cl. C07c 167/14

U.S. Cl. 260—397.4

2 Claims

$\Delta^{1,3,5(10)}$ -3-hydroxy-oestradiene compounds substituted in position 2 or 4 by a formyl group, and the 3-ethers or 3-esters thereof, are prepared by reacting the 3-hydroxy-oestradiene compound with chloroform in the presence of a metal hydroxide, followed by etherification or esterification of the 3-hydroxy group. The resulting products are biologically active in decreasing the serum concentration of cholesterol and the cholesterol/phospholipid ratio, and exhibit weak estrogenic activity and osteotropic activity.

3,579,544

TOTAL PROCESS FOR MAKING 13-HYDROCARBON SUBSTITUTED GONAPOLYENE - 17 - ONE COMPOUNDS AND INTERMEDIATES PRODUCED IN THE COURSE OF THE PROCESS

Kentaro Hiraga, Ikeda, Tsunehiko Asako, Sulta, and Takuichi Miki, Amagasaki, Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

No Drawing. Filed May 24, 1968, Ser. No. 731,968

Claims priority, application Japan, May 24, 1967, 42/32,973; May 25, 1967, 42/33,238

Int. Cl. C07c 169/08

U.S. Cl. 260—397.5

9 Claims

A compound having a 16-(etherified or esterified hydroxy)-17-acyloxy-13-substituted gona-1,3,5(10),8,14-pentaene nucleus is obtained by allowing a compound having a 17-acyloxy-13-substituted 8,14-secogona-1,3,5(10),9(11),15-pentaene-14-one nucleus to contact with an acid catalyst in presence of alcohol, phenol or fatty acid, and converting the resultant compound having a 16-(etherified or esterified hydroxy)-17-acyloxy-13-substituted gona-1,3,5(10),8,14-pentaene nucleus, directly or after reduction of its double bond at the 8-position or bands at the 8- and 14-positions, to a compound having a 13-(hydrocarbon substituted)gonapolyen-17-one nucleus. It is thus made possible to effect the total synthesis of the gona polyenes (e.g. estrone) via a lesser number of steps than has heretofore been possible.

3,579,545

NOVEL 11 β -ALKOXY GONA-1,3,5(10)-TRIENES
Daniel Bertin, Montrouge, and Andre Pierdet, Noisy-le-Sec, France, assignors to Roussel-UCLAF, Paris, France
No Drawing. Continuation-in-part of application Ser. No. 643,062, June 2, 1967. This application Aug. 25, 1969, Ser. No. 852,905


Claims priority, application France, Sept. 7, 1966, 75,528; Dec. 9, 1966, 86,879; Feb. 28, 1967, 96,848; Mar. 9, 1967, 98,154

Int. Cl. C07c 169/08

U.S. Cl. 260—397.5

20 Claims

Novel 11 β -lower alkoxy- $\Delta^{1,3,5(10)}$ -gonatrienes substituted in the 3-position by a member selected from the group consisting of hydroxy, alkoxy of 1 to 4 carbon atoms, cycloalkoxy of 5 to 6 carbon atoms, and acyloxy, wherein the acyl is derived from an organic carboxylic acid having 1 to 18 carbon atoms, in the 13-position by a lower alkyl radical, and in the 17-position by the group-



wherein X is selected from the group consisting of hydrogen and alkyl of 1 to 4 carbon atoms, and Y is selected from the group consisting of a hydrocarbon radical and a substituted hydrocarbon radical. These compounds possess estrogenic activity.

3,579,546

ORGANIC SULFONATE PRODUCTION BY BUFFERED ADDITION OF BISULFITE TO UNSATURATED HYDROCARBONS

Charles J. Norton, Berkeley, Calif., assignor to Marathon Oil Company, Findlay, Ohio

No Drawing. Filed Sept. 30, 1968, Ser. No. 763,929

Int. Cl. C07c 143/90

U.S. Cl. 260—400

10 Claims

This invention details a process for the manufacture of organic sulfonates from unsaturated hydrocarbons containing 6 to about 30 carbon atoms per molecule including reacting the unsaturated hydrocarbons and bisulfite in a cosolvent system comprising water and an organic hydroxyl-containing compound at from 0 to about 300° C. in the presence of a free radical initiator. Also, a sufficient quantity of a buffer compound is present to maintain the pH from about 5 to about 9, where the buffer is a partially neutralized non-bisulfite poly-basic weak acid. The buffer is left in the reaction mixture as a builder for the final alkane sulfonate highly biodegradable low foam detergent formulation.

3,579,547

CARBOXYLIC ACID ESTERS

James T. Traxler, Evanston, Ill., assignor to SCM Corporation, New York, N.Y.

No Drawing. Filed Dec. 16, 1966, Ser. No. 602,166

Int. Cl. C11c 3/04

U.S. Cl. 260—410.6

15 Claims

Novel internal carboxylic acid esters of linear aliphatic polyatomic alcohols have been prepared. The polyatomic alcohols comprising the alcohol portion of the esters contain from 4 to 12 carbon atoms and the carboxylic acid portion of the esters contain from 2 to 26 carbon atoms. Preferred esters are carboxylic acid esters of mannitol and sorbitol and are useful as emulsifying agents. Particularly preferred esters are the mono- and di-stearoyl and palmitoyl esters of sorbitol and mannitol. The novel esters are prepared by reacting a carboxylic acid or a lower alkyl ester of a carboxylic acid with a ketalized linear aliphatic polyatomic alcohol in the presence of an alkaline catalyst to form a carboxylic acid ester of the ketalized alcohol

and thereafter hydrolyzing the ketal of the ester to form hydroxyl groups at the terminal carbon atom. The hydrolysis is preferably accomplished by acid.

3,579,548

TRIGLYCERIDE ESTERS OF α -BRANCHED CARBOXYLIC ACIDS

David D. Whyte, Wyoming, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed May 10, 1968, Ser. No. 728,362

Int. Cl. C11c 3/02; A23d 3/00

U.S. Cl. 260—410.7

1 Claim

Glycerol esters of α -branched carboxylic acids have the physical properties and utility, e.g., in food compositions, of ordinary triglyceride fat but are less digested or absorbed and are thus low calorie.

3,579,549

ACYL DERIVATIVES OF THE CONDENSATION POLYMERS OF ALPHA-HYDROXY-PROPIONIC ACID WITH BETA-HYDROXYBUTYRIC ACID AND/OR BETA-HYDROXYPROPIONIC ACID

Hans H. Stockmann, Plainfield, Dilip K. Ray-Chaudhuri, Somerset, and Richard M. Boettger, Morristown, N.J., assignors to National Starch and Chemical Corporation, New York, N.Y.

No Drawing. Filed Sept. 29, 1967, Ser. No. 671,566

Int. Cl. A21d 2/16; C11c 3/04

U.S. Cl. 260—410.9R

14 Claims

Acyl derivatives of the condensation polymers of alpha-hydroxypropionic acid with beta-hydroxybutyric acid and/or beta-hydroxypropionic acid, as well as the alkali metal, alkaline-earth metal and ammonium salts thereof; the latter derivatives serving as food emulsifiers and as shortening aids. A process for preparing baked goods as well as the baked goods resulting therefrom, said process comprising the incorporation of the above specified derivatives into the raw dough mix prior to the baking thereof. The resulting baked goods are characterized by their prolonged retention of freshness, fine texture, good color and substantial volume.

3,579,550

OXYGENATED DERIVATIVES OF ACYCLIC OLEFINS

Edouard P. Demole, Geneva, Switzerland, assignor to Firmenich & Cie, Geneva, Switzerland


No Drawing. Filed Jan. 16, 1969, Ser. No. 791,770
Claims priority, application Switzerland, Jan. 17, 1968, 792/68

Int. Cl. C08h 17/36

U.S. Cl. 260—413

7 Claims

Compounds having the formula



wherein a double bond is located in one of the positions indicated by the dotted lines and wherein R represents a -COOH or -CH2OH group and n stands for the integer 1 or 2; and methods for manufacturing the said compounds which are useful as fragrances and fixatives in the perfume industry.

3,579,551

PRODUCTION OF CARBOXYLIC ACIDS

John H. Craddock, Ballwin, and Arnold Herschman, Creve Coeur, Mo., Frank E. Paulik, Houston, Tex., and James F. Roth, Creve Coeur, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Aug. 15, 1968, Ser. No. 752,795

Int. Cl. C08h 17/36

U.S. Cl. 260—413

27 Claims

The present invention relates to a process for the preparation of carboxylic acids, specifically by the reaction

of ethylenically unsaturated compounds with carbon monoxide and water, in the presence of catalyst compositions essentially comprising iridium compounds and complexes, together with an iodide promoter.

3,579,552

PRODUCTION OF CARBOXYLIC ACIDS

John H. Craddock, Ballwin, and Arnold Hershman, Creve Coeur, Mo., Frank E. Paulik, Houston, Tex., and James F. Roth, Creve Coeur, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Aug. 15, 1968, Ser. No. 752,746

Int. Cl. C08h 17/36

U.S. Cl. 260—413

25 Claims

The present invention relates to a process for the preparation of carboxylic acids, specifically by the reaction of ethylenically unsaturated compounds with carbon monoxide and water, in the presence of catalyst compositions essentially comprising rhodium compounds and complexes, together with an iodide promoter.

3,579,553

PHENYLMERCURY COMPOUNDS

John R. Leebrick, Old Lyme, Conn., assignor to Cosan Chemical Corporation, Clifton, N.J.


No Drawing. Filed Aug. 21, 1968, Ser. No. 754,490

Int. Cl. C07f 3/12

U.S. Cl. 260—434

5 Claims

Novel compounds are provided of the formula



wherein R is an aliphatic or cyclic alkyl radical, aralkyl radical or aliphatic alkenyl radical. These compounds are useful as catalysts for making polyurethanes, and also act antimicrobially in the polyurethanes, and as antimicrobial agents for coating compositions, including common and marine paints and coatings, and for turf and seeds and as marine antifouling agents and as preservatives. The term "antimicrobial" as employed herein includes "cidal" and static control of bacteria, yeasts, fungi and the like.

3,579,554

DESLUDGING TEL WITH OXYGENATED WATER

Jean Claude Boudreau, Landenberg, Pa., assignor to E. I. du Pont de Nemours and Company

Filed Oct. 31, 1968, Ser. No. 772,339

Int. Cl. C07f 7/26

U.S. Cl. 260—437

9 Claims

A process for purifying impure tetraethyllead by mixing said impure tetraethyllead with water containing dissolved oxygen thereby converting the impurities into a sludge phase.

3,579,555

CHROME COMPLEXES OF SUBSTITUTED BENZOIC ACID

William J. Pagonis, West Chester, Pa., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed Feb. 3, 1969, Ser. No. 796,224

Int. Cl. C07f 11/00; C23c 3/00

U.S. Cl. 260—438.5

3 Claims

This invention relates to novel chrome complexes of benzoic acid. These complexes are exemplified by p-sulfamylbenzoic acid chrome complex and p-acetamidobenzoic acid chrome complex.

3,579,556

NICKEL KETOXIME CHELATES

Peter James Briggs and Ronald James Hurlock, Manchester, England, assignors to Imperial Chemical Industries Limited, London, England

No Drawing. Filed June 21, 1968, Ser. No. 738,839

Claims priority, application Great Britain, June 26, 1967, 29,427/67

Int. Cl. C07j 15/04; C08j 45/62

U.S. Cl. 260—439R

4 Claims

Nickel chelate complexes of syn-alkyl 2-hydroxyaryl ketoximes in which the alkyl group contains at least 6 carbon atoms are used as light stabilizers for polymers, especially polyolefins. The chelate complexes are prepared from the syn-alkyl 2-hydroxyaryl ketoximes by reacting with a solution of a nickel salt.

3,579,557

WATER AND OIL REPELLENTS

Thomas W. Brooks and Paul D. Schuman, Gainesville, and Calvin D. Padgett, Waldo, Fla., assignors to Calgon Corporation, Pittsburgh, Pa.

No Drawing. Filed Aug. 21, 1968, Ser. No. 754,457

Int. Cl. C07f 7/10

U.S. Cl. 260—448.2N

3 Claims

Certain fluorosilazanes and chlorosilanes are disclosed. The new compounds are of the formulas



in which x is 0-10 and R₁ and R₂ are independently selected alkyl groups. They are useful as oil and water repellents and as derivatizing agents to facilitate gas-liquid chromatographic analyses.

3,579,558

PROCESS FOR THE PRODUCTION OF ω-AMINOALKANE NITRILES

Otto Immel, Krefeld-Uerdingen, Hans-Helmut Schwarz, Krefeld-Bockum, and Hermann Schnell, Krefeld-Uerdingen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Filed Sept. 25, 1968, Ser. No. 762,630

Claims priority, application Germany, Oct. 14, 1967, F 53,775, F 53,776

Int. Cl. C07c 121/02

U.S. Cl. 260—465.2

5 Claims

Process of producing ω-aminoalkane nitriles by heating corresponding lactams with a stoichiometric excess of ammonia in the gaseous phase in the presence of a catalytic amount of a solid catalyst, said catalyst consisting essentially of magnesium silicate, calcium silicate, zinc silicate, aluminum silicate, manganese silicate, iron silicate, fluorinated aluminum oxide, fluorinated magnesium silicate, fluorinated calcium silicate, fluorinated zinc silicate, fluorinated aluminum silicate, fluorinated manganese silicate or fluorinated iron silicate.

3,579,559

PREPARING MUCONONITRILE FROM BENZENE

Manfred Otto Unger, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed May 29, 1968, Ser. No. 732,873

Int. Cl. C07c 121/02

U.S. Cl. 260—465.3

4 Claims

Vapor phase reaction of benzene with ammonia and oxygen at above 300° C. to produce mucononitrile.

3,579,560

ISOMERIZATION OF NITRILES

William Charles Drinkard, Jr., Wilmington, Del., and Brian W. Taylor, Pittsburgh, Pa., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Continuation-in-part of application Ser. No. 680,969, Nov. 6, 1967. This application Oct. 28, 1968, Ser. No. 771,313

Int. Cl. C07c 121/30

U.S. Cl. 260—465.9

20 Claims

Process of isomerizing 2-methyl-3-butenenitrile to 3-pentenitriles and 3-pentenitriles to 4-pentenitrile using a compound of cobalt or rhodium in conjunction with an oxidizing agent or reducing agent present in an amount such that the cobalt or rhodium has an effective valence below +2 and generally of from 0.25 to 1.75 as catalyst and of adding hydrogen cyanide to carbon-carbon double bonds such as in 4-pentenitrile at from -25 to 200° C. using the same cobalt or rhodium catalyst system.

3,579,561

HYDROXYBENZYL-SUBSTITUTED BIS-PHENYL CARBONATES

Bernard R. Meltsner, Royal Oak, Mich., assignor to Ethyl Corporation, New York, N.Y.

No Drawing. Filed July 9, 1965, Ser. No. 470,890

Int. Cl. C07c 69/00

U.S. Cl. 260—463

10 Claims

Hydroxybenzylphenyl carbonates and carboxylates are useful as stabilizers for organic material. They may be used alone or in combination with a dihydrocarbylthio-dialkanoate.

3,579,562

PROCESS FOR HYDROFORMYLATING UNSATURATED ESTERS OR NITRILES

Wolfgang Weigert, Offenbach am Main, Germany, assignor to Deutsche Gold- und Silber-Scheldeanstalt vormals Roessler, Frankfurt am Main, Germany

No Drawing. Filed Dec. 17, 1965, Ser. No. 514,648

Claims priority, application Germany, Dec. 22, 1964, D 46,116; May 22, 1965, D 47,334

Int. Cl. C07c 121/34, 69/66

U.S. Cl. 260—465.1

14 Claims

Methacrylic acid esters and nitrile are hydroformylated in the presence of a rhodium catalyst. α-formyl products predominate when reacting below 100° C. and β-formyl products predominate when reacting above 100° C.

3,579,563

PROCESS FOR THE HYDROGENATION OF MIXED NAPHTHALENE ESTERS AND COMPOSITIONS DERIVED THEREFROM

Philip W. Storms, Denver, and Grover L. Farrar, Littleton, Colo., assignors to Marathon Oil Company, Findlay, Ohio

No Drawing. Filed Mar. 2, 1967, Ser. No. 619,950

Int. Cl. C07c 69/76

U.S. Cl. 260—468

12 Claims

Hydrogenated derivatives of dimethylnaphthalenes are prepared by

- cracking a gas oil to form a light catalytic cycle oil having a boiling range between about 300 to 700° F.,
- hydrotreating said light catalytic cycle oil at temperatures of from about 600 to about 800° F. and pressures of from about 200 to about 1000 p.s.i.a. to form a hydrotreated cycle oil,
- extracting at least a portion of the aromatics from said hydrotreated cyclic oil,
- separating the extracted aromatics from the extracting solvent,
- oxidizing the extracted aromatics,
- hydrogenating the aromatics.

3,579,564

ESTERS OF 5-HYDROXYTETRACYCLINES

Robert K. Blackwood and Manfred Schach von Wittenau, Gales Ferry, Conn., assignors to Chas. Pfizer & Co., Inc., New York, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 439,974, Mar. 15, 1966. This application Feb. 3, 1969, Ser. No. 796,202

Int. Cl. C07c 103/19, 139/76; C07d 5/20

U.S. Cl. 260—473

15 Claims

Esters of oxytetracyclines including O^{12a}-esters of oxytetracycline, α- and β-6-deoxy-oxytetracycline, 6-demethyl-6-deoxy-6-methyleneoxytetracycline, the mercaptan adducts of the latter compound and acid addition and metal salts of said esters and their utility as antibacterial agents and as intermediates in the preparation of other biologically active compounds.

3,579,565

SULFONATE MONOMERS

Joel A. Zaslow and Henry Gould, Baltimore, Md., assignors to Alcolac Chemical Corporation, Baltimore, Md.

No Drawing. Filed June 12, 1967, Ser. No. 645,493

Int. Cl. C07c 69/54, 69/60

U.S. Cl. 260—485

3 Claims

A new class of sulfonate monomers, both as new compositions of matter, and homopolymers and copolymers containing them.

3,579,566

REDUCTION OF ANHYDRIDES

Donald M. Fenton, Anaheim, Calif., assignor to Union Oil Company of California, Los Angeles, Calif.

No Drawing. Filed Dec. 13, 1967, Ser. No. 690,067

Int. Cl. C07c 47/06, 69/16, 67/00

U.S. Cl. 260—488

10 Claims

A process for reduction of organic acid anhydrides comprising reacting the anhydride with hydrogen in the presence of a catalyst comprising a complex of a Group VIII noble metal with a biphilic ligand from the group consisting of organic phosphines, organic arsines and organic stibines.

3,579,567

TRICYCLO[4.4.0.0^{3,8}]DECAN-1-AMINE AND PROCESS FOR PREPARING SAME

Pierre Deslongchamps, Sherbrooke, Quebec, Canada, assignor to Ayerst, McKenna and Harrison Limited, Ville St. Laurent, Quebec, Canada

No Drawing. Filed July 10, 1968, Ser. No. 743,623

Int. Cl. C07c 69/14, 87/02, 103/32

U.S. Cl. 260—488

10 Claims

There is disclosed herein tricyclo[4.4.0.0^{3,8}]decan-1-amine and the intermediates used in this preparation 8-hydroxytricyclo[4.4.0.0^{3,8}]decan-4-one acetate, 8-hydroxytricyclo[4.4.0.0^{3,8}]decan-4-one acetate thioketal, tricyclo[4.4.0.0^{3,8}]decan-1-ol acetate, tricyclo[4.4.0.0^{3,8}]decan-1-ol, and N-1-tricyclo[4.4.0.0^{3,8}]decanylacetamide. The compound possesses anti-viral properties, and methods for its use as well as a process for its preparation are also disclosed.

3,579,568

SYNTHESIS OF CARBOXYLIC ACIDS FROM ETHYLENE AND CARBON MONOXIDE AND NOBLE METAL COMPOUNDS

Richard F. Heck, Wilmington, and Patrick M. Henry, McDaniel Crest, Del., assignors to Hercules Powder Company, Wilmington, Del.

No Drawing. Original application Aug. 18, 1965, Ser. No. 480,809. Divided and this application Jan. 16, 1969, Ser. No. 791,789

Int. Cl. C07c 67/04

U.S. Cl. 260—497

4 Claims

The disclosed process is a method for producing carboxylic acids by carbonylation of olefinic hydrocarbons.

An olefin such as ethylene, and water or an acid such as acetic acid, are brought into contact with carbon monoxide in the presence of a compound of a Group VIII noble metal such as palladium at a temperature in the range of 25° to 250° C. Using ethylene and acetic acid as reactants, the product contains β -acetoxypropionic acid. A redox agent such as cupric chloride may be used to effect regeneration of the noble metal compound.

3,579,569

PREPARATION OF VINYL ACETATE

Stewart R. Montgomery, Silver Spring, and Melville E. Hillmann, Rockville, Md., assignors to W. R. Grace & Co., New York, N.Y.
No Drawing. Filed Oct. 6, 1967, Ser. No. 673,297
Int. Cl. C07c 67/04

U.S. Cl. 260—497 4 Claims


Vinyl acetate is produced by reacting ethylene and acetic acid in the vapor phase in the presence of a novel catalyst. The catalyst is solid titanium dioxide which has been treated with an aqueous solution of a basic material and with a solution of a soluble salt of a Group VIII noble metal. The Group VIII noble metal salt which deposited on the surface of the titanium dioxide is subsequently reduced to the metallic state with hydrogen.

3,579,570


ETHANE-1,2 - DICARBOXY - 1,2-DIHYDROXY-1,2-DIPHOSPHONIC ACID, LOWER ALKYL ESTERS, ALKALI METAL SALTS THEREOF AND PROCESS FOR PREPARING SAME

Denzel Allan Nicholson, Springfield Township, Hamilton County, Ohio, and Darrel Campbell, King of Prussia, Pa., assignors to The Procter & Gamble Company, Cincinnati, Ohio
No Drawing. Filed Dec. 24, 1968, Ser. No. 786,765
Int. Cl. C07f 9/38; C11d 3/08

U.S. Cl. 260—502.4 8 Claims



in which R is hydrogen, alkali metal, or an alkyl group having from 1 to about 6 carbon atoms, ammonium or alkanolammonium having 1 to 3 carbon atoms in each alkanol group by a process which comprises reacting an ester of ethane-1,2-dicarboxy-1,2-diphosphonic acid with an alkali metal hypohalite to form an epoxide compound having the formula



in which R' is an alkyl group having from 1 to about 6 carbon atoms, and hydrolyzing said epoxide. The compounds are useful as detergency builders, sequestering agents and anti-calculus agents in oral compositions.

3,579,571

PROCESS FOR THE PREPARATION AND ISOLATION OF DEHYDROABIETIC ACID

Noah J. Halbrook and Ray V. Lawrence, Olustee, Fla., assignors to the United States of America as represented by the Secretary of Agriculture
No Drawing. Filed Nov. 13, 1967, Ser. No. 682,541
Int. Cl. C07c 61/30

U.S. Cl. 260—514.5 6 Claims

Dehydroabietic acid is separated from rosin, other rosin acids, and rosin materials either present in rosin or

formed in the disproportionation of rosin, by forming the 2-aminoethanol salt of dehydroabietic acid and recovering the pure acid from the amine salt.

3,579,572

PROCESS FOR THE PRODUCTION OF TEREPHTHALIC ACID

Garabed Amedjian, Maurice Fenoglio, and Michel Oberdorf, Lyon, France, assignors to Rhone-Poulenc S.A., Paris, France
No Drawing. Filed Jan. 5, 1968, Ser. No. 695,879
Int. Cl. C07c 63/26

U.S. Cl. 260—515 6 Claims

Terephthalic acid is produced by treating aqueous lithium or magnesium terephthalate solution with carbon dioxide under pressure, and separating the precipitated terephthalic acid.

3,579,573

OXIDATION OF α,β -UNSATURATED ALDEHYDES TO THE CORRESPONDING UNSATURATED CARBOXYLIC ACIDS

Dieter Gilde, Hanau am Main, and Edgar Koberstein, Konstanz, Germany, assignors to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler, Frankfurt am Main, Germany
No Drawing. Filed Jan. 20, 1964, Ser. No. 338,610
Claims priority, application Germany, Jan. 29, 1963, D 40,744; Dec. 23, 1963, D 43,244
Int. Cl. C07c 51/26

U.S. Cl. 260—530 6 Claims

Process for the production of α,β -unsaturated carboxylic acid by catalytic oxidation of α,β -unsaturated aldehydes in the gas phase with molecular oxygen using a mixture of phosphoric acid and vanadic acid in which the atomic ratio of phosphorus to vanadium is from 1:10 to 10:1 which may also contain antimony trioxide as oxidation catalyst.

3,579,574

PRODUCTION OF ACRYLIC ACID

Wilhelmus Teunis van der Meer, London, England, assignor to The Distillers Company Limited, Edinburgh, Scotland
No Drawing. Filed Jan. 22, 1965, Ser. No. 427,502
Claims priority, application Great Britain, Feb. 5, 1964, 4,804/64
Int. Cl. C07c 51/26, 51/32

U.S. Cl. 260—530 11 Claims

Acrylic acid is prepared by the vapor phase oxidation of propylene or acrolein with oxygen in the presence of a catalyst consisting essentially of an oxide composition containing antimony and vanadium or antimony, vanadium and at least one polyvalent metal selected from the group of iron, manganese, chromium, cobalt, nickel, copper, zinc, cadmium, tungsten and thorium, the catalyst being heated to a temperature above 700° to about 900° C. in molecular oxygen gas before use.

3,579,575

PROCESS FOR OXIDIZING LOWER ALIPHATIC ALDEHYDES

Albert Bouniot, Melle, Deux-Sevres, France, assignor to Melle-Bezons, Melle, Deux-Sevres, France
No Drawing. Filed May 8, 1968, Ser. No. 727,705
Claims priority, application France, May 26, 1967, 107,982
Int. Cl. C07c 53/22

U.S. Cl. 260—530 14 Claims


Process for oxidizing lower aliphatic aldehydes wherein the oxidation is carried out by passage of an oxygen containing gas through a liquid medium containing the aldehyde, in which the liquid medium comprises heterogeneous liquid phases, one of which is an aqueous phase.

3,579,576

ORGANOPHOSPHORUS COMPOUNDS AND A PROCESS FOR THE MAKING THEREOF

Howard P. Angstadt, Wilmington, Del., assignor to Sun Oil Company, Philadelphia, Pa.
No Drawing. Filed Feb. 25, 1964, Ser. No. 347,105
Int. Cl. C07f 9/34, 9/30
U.S. Cl. 260—543P 19 Claims

Compounds of the structure



where the R's are alkyl or cycloalkyl groups and X is halogen. Process of preparing these compounds from white phosphorus and an alkyl halide or cycloalkyl halide in a solvent such as carbon disulfide at from -80° C. to 100° C. in the presence of any of AlCl_3 , AlBr_3 , BF_3 , FeCl_3 or TiCl_4 as catalyst followed by hydrolyzing the thus formed product with water at from 0° to 50° C. to produce the final product which is then separated from the reaction medium. When the alkyl or cycloalkyl halide is primary or secondary compounds of structures II and III as set forth above are formed and when tertiary alkyl or cycloalkyl halides are used compounds of structures I and II are formed.

3,579,577

METHOD OF PREPARING 4,5,6, HEXACHLORO-TOLUYL CHLORIDE

Paul E. Hoch, Youngstown, N.Y., assignor to Hooker Chemical Corporation, Niagara Falls, N.Y.
No Drawing. Continuation-in-part of abandoned application Ser. No. 818,517, June 8, 1959. This application Oct. 29, 1962, Ser. No. 233,885
Int. Cl. C07c 51/58

U.S. Cl. 260—544 2 Claims

4,5,6, α,α,α -hexachlorotoluyll chloride is prepared by heating 3,4,5,6,7,7-hexachloro-3,6-menthano-1,2,3,6-tetrahydrophthaloyl chloride to at least 180° C. The toluyl chloride so produced is a useful chemical intermediate for making dyestuffs, herbicides, flame retardants and flame-proofing agents.

3,579,578

3,4-DIHALO-3' AND 4'-LOWER ALKYL CARBANILIDES

Edward J. Nikawitz, Glen Rock, and George R. Walter, Ho-Ho-Kus, N.J., assignors to Glvandan Corporation, Clifton, N.J.
No Drawing. Filed July 8, 1966, Ser. No. 563,673
Int. Cl. C07c 127/00

U.S. Cl. 260—553 10 Claims

The present invention relates to novel 3,4-dihalo-3'- and 4'-lower alkyl carbanilides having bacteriostatic activity, a process for their manufacture, bacteriostatic compositions containing these compounds, synergistic bacteriostatic compositions of the new compounds with hexachlorophene, and a method for controlling bacteria by the use of said compounds.

ERRATUM

For Class 260—555 see:
Patent No. 3,579,636

3,579,579

SUBSTITUTED 7- AND/OR 9-AMINO-6-DEMETHYL-6-DEOXYTETRACYCLINES

Joseph J. Hlavka, Tuxedo, Panayoto Bitha, New York, and Adma Schneller Ross and Michael Joseph Martell, Suffern, N.Y., assignors to American Cyanamid Company, Stamford, Conn.
No Drawing. Filed Apr. 18, 1968, Ser. No. 722,167
Int. Cl. C07c 103/19

U.S. Cl. 260—559 2 Claims

This disclosure describes compounds of the class of 7- or 9-di(lower alkyl)amino-6-demethyl-6 - deoxytetracyclines and 7-monoalkylamino - 6 - demethyl-6-deoxytetracyclines useful as antibacterial agents.

3,579,580

PROCESS FOR PREPARING 1,4-BENZODIAZEPINES

Giles A. Archer, Essex Fells, and Leo Henryk Sternbach, Upper Montclair, N.J., assignors to Hoffmann-La Roche Inc., Nutley, N.J.
No Drawing. Filed July 26, 1966, Ser. No. 567,827
Int. Cl. C07c 119/00

U.S. Cl. 260—566 5 Claims

Preparation of 1,4-benzodiazepines via the reaction of 2 - (2 - amino - 5 - Y - α -phenylbenzylideneamino)ethanol wherein Y is selected from the group consisting of halogen, nitro, trifluoromethyl and hydrogen with a leaving group providing agent, e.g. thionyl chloride whereby to obtain the novel corresponding 2-(2-amino-5-Y- α -phenylbenzylideneamino)ethyl X wherein X is a leaving group and ring closing the last-mentioned compound whereby to obtain a 1,4-benzodiazepine. 1,4-benzodiazepines are known compounds of pharmacological utility, and are useful as anticonvulsant, muscle relaxant and sedative agents.

3,579,581

PREPARATION OF QUATERNARY AMMONIUM HYDROXIDES

Jim N. Maloney, Jr., Pensacola, and Ralph W. Smith, Gulf Breeze, Fla., assignors to Monsanto Company, St. Louis, Mo.
No Drawing. Continuation-in-part of application Ser. No. 711,200, Mar. 7, 1968. This application Apr. 3, 1968, Ser. No. 718,362
Int. Cl. C07c 85/00

U.S. Cl. 260—567.6 6 Claims

Quaternary ammonium hydroxides can be prepared in high yield and purity from quaternary ammonium salts in the aqueous residue from extraction of an olefinic nitrile electrohydrodimerization effluent by contacting at least a portion of the aqueous residue with a basic anion exchange resin.


3,579,582

HYDROXY AND/OR HYDROCARBYLOXY AND AMINO SUBSTITUTED TETRAHYDRONAPHTHALENES

Ted Symon, Lombard, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.
No Drawing. Filed Feb. 16, 1967, Ser. No. 616,474
Int. Cl. C07c 91/42

U.S. Cl. 260—574 8 Claims

Compounds of the formula



where R, R' and R'' are independently selected from hydrogen, alkyl, aralkyl, aryl, alkaryl or cycloalkyl. The compounds are useful as stabilizing additives in organic substrates such as lube oils, greases and polyolefin plastics.

3,579,583

PROCESS FOR PREPARATION OF N-METHYL-ALKYL AMINES

Horst Rutzen, Dusseldorf-Holthausen, Germany, assignor to Henkel & Cie., G.m.b.H., Dusseldorf-Holthausen, Germany

No Drawing. Filed Dec. 9, 1968, Ser. No. 782,426
Claims priority, application Germany, Dec. 7, 1967, H 64,693

Int. Cl. C07c 85/12

U.S. Cl. 260—583

10 Claims

A new method of producing N-methyl-alkyl amines by hydrogenating a monocarboxylic acid or a dicarboxylic acid which will not form an internal anhydride at 200 to 400° C. in the presence of mono and/or dimethyl amine and an oxide catalyst.

3,579,584

PREPARATION OF AMINES

Horst Rutzen and Rolf Brockmann, Dusseldorf-Holthausen, Germany, assignors to Henkel & Cie., G.m.b.H., Dusseldorf, Germany


No Drawing. Filed Dec. 9, 1968, Ser. No. 782,427
Claims priority, application Germany, June 11, 1968, P 17 68 641.8

Int. Cl. C07c 85/00, 85/02, 85/12


U.S. Cl. 260—583

9 Claims


A process for the preparation of amines having the formula



wherein R_1 and R_2 are selected from the group consisting of hydrogen and alkyl of 1 to 4 carbon atoms and R is selected from the group consisting of saturated and unsaturated straight and branch aliphatic and cycloaliphatic of 4 to 24 carbon atoms and aromatic of 6 to 24 carbon atoms which may be substituted with one



which comprises reacting a carboxylic acid ester in one step with a nitrogen compound of the formula



at a temperature of 200 to 400° C. in the presence of hydrogen which may be diluted with a reaction-inert gas at a pressure of 50 to 400 atmospheres and in the presence of a metal oxide catalyst in lump form selected from the group consisting of zinc oxide-chromium oxide and zinc oxide-aluminum oxide catalysts.

3,579,585

PREPARATION OF AMINES

Horst Rutzen, Dusseldorf-Holthausen, Germany, assignor to Henkel & Cie., G.m.b.H., Dusseldorf-Holthausen, Germany


No Drawing. Filed Dec. 9, 1968, Ser. No. 782,480
Claims priority, application Germany, Dec. 8, 1967, H 64,713

Int. Cl. C07c 85/00, 85/02, 85/12

U.S. Cl. 260—583


11 Claims

A process for the preparation of aliphatic amines of the formula



wherein R is selected from the group consisting of saturated and unsaturated aliphatic radicals of 6 to 22

carbon atoms and R_1 and R_2 are selected from the group consisting of hydrogen and alkyl of 1 to 4 carbon atoms which comprises reacting a fatty acid glyceride having an R radical with a nitrogen compound of the formula



wherein R_1 and R_2 have the above definitions at 200 to 400° C. and a hydrogen pressure of 50 to 400 atmospheres in the presence of a metal oxide catalyst in lump form selected from the group consisting of zinc oxide-aluminum oxide and zinc oxide-chromium oxide catalysts.

3,579,586

PROCESS FOR THE PREPARATION OF THE DEXTROROTATORY 2,2' - (ETHYLENE-DI-IMINO)-DI-1-BUTANOL

Giorgio Zoja, Milan, Italy, assignor to Laboratorio Chimico Farmaceutico Giorgio Zoja S.p.A., Milan, Italy

No Drawing. Filed Nov. 13, 1968, Ser. No. 775,508
Claims priority, application Germany, June 5, 1968, P 17 68 612.3

Int. Cl. C07c 89/04

U.S. Cl. 260—584R

7 Claims

A process for the production of highly pure, levoisomer free, (+) 2,2-ethylenediimino-di-1-butanol dihydrochloride involving resolution of ($\pm$) 2-amino-1-butanol (+) tartrates with boiling methanol, reaction of (+) 2-amino-1-butanol with ethylene dichloride and precipitating the intermediate product with gaseous hydrochloric acid to obtain the desired product.

3,579,587

PROCESS FOR THE PREPARATION OF THE DEXTROROTATORY 2,2' - (ETHYLENE-DI-IMINO)-DI-1-BUTANOL

Giorgio Zoja, Milan, Italy, assignor to Laboratorio Chimico Farmaceutico Giorgio Zoja S.p.A., Milan, Italy

No Drawing. Filed Nov. 13, 1968, Ser. No. 775,536
Claims priority, application Great Britain, Apr. 18, 1968, 18,491/68

Int. Cl. C07c 89/00

U.S. Cl. 260—584

8 Claims

A process for the production of pure (+)2,2'-(ethylenediimino)-di-1-butanol dihydrochloride formed by reacting a solution of (+)2-amino-1-butanol and (−)2-amino-1-butanol with (+)tartaric acid, separating the diastereoisomers by fractional crystallization using boiling methyl alcohol and reacting the highly pure (+)2-amino-1-butanol (+)hydrogen tartrate with ethylene dichloride in the presence of an inert organic solvent and a calcium compound, concentrating the reaction solution, removing insoluble calcium salts and saturating with gaseous HCl to precipitate (+)2,2'-(ethylenediimino)-di-1-butanol dihydrochloride.

3,579,588

6,6,7,7-TETRACHLOROBICYCLO(3.2.0)HEPTAN-2-ONE

Wendell L. Dilling, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed July 24, 1968, Ser. No. 747,116

Int. Cl. C07c 49/00; B01j 1/10

U.S. Cl. 260—586

1 Claim

The present disclosure is directed to the compound 6,6,7,7-tetrachlorobicyclo(3.2.0)heptan-2-one, its method of preparation as well as its use as a bactericide and fungicide.

3,579,589

PROCESS FOR MANUFACTURING A CATALYST, RESULTING CATALYST AND PROCESS FOR MANUFACTURE OF BENZOIC ALDEHYDE FROM TOLUENE IN THE PRESENCE OF SAID CATALYST

Bernard Delmon, Seyssins, France, assignor to Institut Francais du Pétrole des Carburants et Lubrifiants, Ruell Malmaison, France

No Drawing. Filed Sept. 5, 1968, Ser. No. 757,755
Claims priority, application France, Sept. 13, 1967, 120,933

Int. Cl. C07c 47/48, 47/52

U.S. Cl. 260—599

19 Claims

Process for manufacturing a catalyst used for oxidizing toluene to benzaldehyde, which process comprises admixing an uranium oxide or salt with a molybdenum oxide or salt in the presence of sulfuric acid, drying and calcinating the resulting mixture.

Optionally, there can be added to the mixture, before drying and calcinating, an alkaline or alkaline-earth metal compound and/or metals or compounds of metals such as chromium, tungsten, silver, copper, yttrium, cerium and other elements from the group of the rare earths.

3,579,590

METHOD OF PREPARING DIARYL SULFONES

David S. Davis, West Orange, N.J., assignor to Witco Chemical Corporation, New York, N.Y.


No Drawing. Filed Dec. 12, 1967, Ser. No. 689,809

Int. Cl. C07c 147/06

U.S. Cl. 260—607

5 Claims

Production of diaryl sulfones having the formula



by reacting in admixture (a) aryl compounds having the formula RH wherein R represents an aryl hydrocarbon such as benzene or naphthalene in which the nuclear carbon atoms have their outer valences satisfied by hydrogen or one or more of alkyl (including cycloalkyl), alkoxy, thioalkyl, halogen, phenyl, substituted phenyl, phenoxy, and substituted phenoxy groups and mixtures thereof (b) anhydrous sulfonating agents as, for instance, fluorosulfonic acid, sulfur trioxide, chlorosulfonic acid and mixtures thereof, and (c) at least 0.04 mole of a non-metallic condensing agent for instance, P_2O_5 , phosphorus pentachloride, phosphorus oxychloride, and boric anhydride, per mole of sulfonating agent, said diaryl sulfones being produced in high yield and having a high degree of purity, free from metallic impurities.

3,579,591

4,4'-BIS-(HYDROXYARLOXY)-PHENYLSULFONE

Hermann Schnell and Gerhard Darow, Krefeld-Uerdingen, and Ludwig Bottenbruch, Krefeld-Bockum, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Continuation-in-part of application Ser. No. 620,233, Mar. 3, 1967. This application Oct. 8, 1968, Ser. No. 765,993


Claims priority, application Germany, Mar. 18, 1966, F 53,836

Int. Cl. C07c 142/10, 51/00; C08a 22/14

U.S. Cl. 260—607

5 Claims

Aryl ethers of the formula



wherein R is a bivalent aromatic radical and the utility thereof as intermediates for reaction with carboxylic acid halides, dicarboxylic acid dihalides, isocyanates and polyisocyanates to produce, respectively, diesters, polyesters, diurethanes and polyurethanes. The aforesaid ethers are

prepared by reacting 1 mol of 4,4'-dihalo-diphenylsulfone with about 2 mols diphenolate at a temperature between about 100 and 160° C. and acidifying resulting product.

3,579,592

1-ALLYLTHIO-3-CHLORO-2-PROPANOL

Leonard Levine, Lake Jackson, and Russell T. McFadden, Freeport, Tex., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Oct. 22, 1968, Ser. No. 769,706

Int. Cl. C07c 149/18; A61k 27/00; C08f 15/00

U.S. Cl. 260—609

4 Claims

1-allylthio-3-halo-2-propanol is made by reacting an allyl halide with 1-mercapto-3-halo-2-propanol, wherein the halogen in each reactant has an atomic weight of at least 35, in the presence of a hydrogen halide acceptor. The compound is used as an anthelmintic.

3,579,593

PROCESS FOR PREPARING BETA-PHENYLETHYL ALCOHOL

Thomas F. Wood, Wayne, N.J., assignor to Glvandan Corporation, Clifton, N.J.

No Drawing. Filed Apr. 18, 1968, Ser. No. 722,224

Int. Cl. C07c 29/00

U.S. Cl. 260—618

6 Claims

β -Phenylethyl alcohol suitable for perfumery use is prepared in excellent yields by the hydrogenation of styrene oxide in the presence of the two catalysts: Raney nickel and palladium, and fractionally distilling the alcohol.

3,579,594

PREPARATION OF DINITRO ALCOHOLS

John M. Larkin, Hopewell Junction, N.Y., assignor to Texaco Inc., New York, N.Y.


No Drawing. Filed Nov. 30, 1967, Ser. No. 686,820

Int. Cl. C07c 79/18, 87/04


U.S. Cl. 260—632

14 Claims

A method for preparing dinitro alcohols having at least 4 carbon atoms by heating a vicinal nitroalkyl nitrate having at least 4 carbon atoms at a temperature of at least 100° C. The dinitro alcohols so prepared correspond to the formulas:



and



and are useful as solvents, plasticizers, bactericides, lubricants and fuel additives.

3,579,595

1-BROMO-1-CHLORO-2,3,3-TRIFLUOROPROPENE AND METHOD OF PREPARING SAME

Bernard M. Regan, Chicago, Ill., assignor to Baxter Laboratories, Inc., Morton Grove, Ill.

No Drawing. Filed Jan. 19, 1968, Ser. No. 699,060

The portion of the term of the patent subsequent to

Mar. 3, 1987, has been disclaimed

Int. Cl. C07c 17/34, 21/18

U.S. Cl. 260—653.3

2 Claims

1-bromo-1-chloro-2,3,3-trifluoropropene, useful as a general anesthetic.

3,579,596

HYDROGENOLYSIS OF CARBON TETRACHLORIDE AND CHLOROFORM

Charles R. Mullin and C. Elmer Wymore, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Mar. 29, 1968, Ser. No. 717,383
Int. Cl. C07c 17/06

U.S. Cl. 260—658 12 Claims

A process for the selective vapor phase dechlorination of carbon tetrachloride and chloroform, resulting in lower chlorinated methanes, which comprises:

(A) Reacting carbon tetrachloride with an excess of hydrogen, at a temperature below 200° C. and a liquid hourly space velocity of 0.1 to 10, in the presence of a catalyst chosen from the metals Ru, Rh, Pd, Os, Ir, Pt, Cu, Ag, or Au, to produce predominantly chloroform; or

(B) Reacting carbon tetrachloride with an excess of hydrogen, at a temperature of 125° to 350° C. and a liquid hourly space velocity of 0.5 to 10, in the presence of one of the catalysts of (A) above, to produce predominantly methylene chloride; or

(C) Reacting chloroform with an excess of hydrogen, at a temperature of 75° to 350° C. and a liquid hourly space velocity of 0.1 to 10, in the presence of one of the catalysts of (A) above, to produce predominantly methylene chloride.

3,579,597

PREPARATION OF C₂ SATURATED CHLORINATED COMPOUNDS BY OXYCHLORINATION OF ETHYLENE AND VINYL CHLORIDE WITH A FLUID BED CATALYST

Albert Antonini and Philippe Joffre, Paris, and Claude Vrillon, Montmagny, France, assignors to Produits Chimiques Pechiney-Saint-Gobain, Paris, France

No Drawing. Filed May 20, 1968, Ser. No. 730,611
Claims priority, application France, May 19, 1967, 106,971

Int. Cl. C07c 17/06

U.S. Cl. 260—658R 16 Claims

A process for the preparation of 1,2-dichloroethane, 1,1,2-trichloroethane, 1,1,2,2-tetrachloroethane and penta-chloroethane simultaneously by oxychlorination of ethylene and vinyl chloride in admixture with a fluidized bed catalyst.

3,579,598

DEHYDROCYCLIZATION PROCESS AND CATALYST

Rowland C. Hansford, Yorba Linda, Calif., assignor to Union Oil Company of California, Los Angeles, Calif.

No Drawing. Filed Aug. 14, 1967, Ser. No. 660,240
Int. Cl. C07c 5/18, 15/02; B01j 11/16

U.S. Cl. 260—673.5 7 Claims

Paraffin hydrocarbons are converted to aromatic hydrocarbons by dehydrocyclization at elevated temperatures and low pressures, in the presence of added hydrogen and a catalyst comprising minor proportions of a Group VIII noble metal and at least one oxide of the metals calcium, strontium, or barium, supported on a silica gel base.

3,579,599

PROCESS FOR EXTRACT-SEPARATION OF AROMATIC HYDROCARBONS

Yoshiro Ito, Tamotsu Ueno, Takashi Nakano, and Kazuo Okamoto, Kurashiki-shi, Japan, assignors to Japan Gas-Chemical Company, Inc., Tokyo, Japan


Filed Nov. 18, 1968, Ser. No. 776,728
Claims priority, application Japan, Nov. 21, 1967, 42/74,896

Int. Cl. C07c 7/10

U.S. Cl. 260—674 10 Claims

A process for extract-separating aromatic hydrocarbons having larger basicity into a hydrogen fluoride phase by

allowing an extracting agent consisting of hydrogen fluoride and boron trifluoride to come in contact with a mixture containing two or more aromatic hydrocarbons having different basicity from each other. More particularly, a process for extract-separating aromatic hydrocarbons in a



high yield and purity without substantially refluxing said aromatic hydrocarbon having larger basicity, heretofore considered a necessity, by feeding extracting agent consisting of HF and BF₃, and diluent in highly precise amounts according to a predetermined correlation.

3,579,600

CATALYST FOR THE INTERCONVERSION OF PROPYNE AND PROPADIENE

Richard T. Dickerson, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Nov. 8, 1968, Ser. No. 774,487
Int. Cl. C07c 11/14, 11/22

U.S. Cl. 260—678 10 Claims

Propyne and propadiene are catalytically interconverted by a mixture of a highly polar solvent, e.g. dimethyl sulfoxide, and a base, e.g. potassium hydroxide. This process facilitates the conversion of C₃H₄ mixtures entirely to either propyne or propadiene as may be required for specific chemical application.


3,579,601

PYROLYSIS OF HYDROCARBONS

John A. Kivlen, Sparta, N.J., assignor to Esso Research and Engineering Company

Filed June 10, 1968, Ser. No. 738,716
Int. Cl. C07c 3/08; C10g 9/20, 9/14

U.S. Cl. 260—683 12 Claims



This invention relates to process and apparatus for the pyrolysis, or thermal cracking, of hydrocarbons or hydro-

carbon feedstocks to produce products useful as chemical raw materials or fuels. In particular, mobile hydrocarbons, i.e., normally gaseous or liquid paraffinic hydrocarbons, or other suitable feedstocks, are cracked to obtain unsaturated hydrocarbon compounds, particularly olefins. Faster reaction rates, increased product yields, and better selectivities are obtained by thermally cracking (with or without steam) a raw, or fresh hydrocarbon feed in admixture with a stream of hot reacting, thermally cracked (with or without steam) product. The process is thus characterized by steps wherein a feed is thermally cracked to form at least partially converted products, and fresh feed, which preferably is preheated to supply some of the needed sensible and reaction heat, is thermally cracked in admixture with the said at least partially converted products. In one embodiment, fresh hydrocarbon feed, and steam if desired, is preheated and fed at spaced locations through a tubular reactor, or reaction zone, resulting in fresh feed being contacted with at least partially converted products from a preceding portion of the tubular reactor, or reaction zone (except for the portion introduced at the entrance to the reactor).

3,579,602

OLEFIN CONVERSION PROCESS AND CATALYSTS THEREFOR

Robert E. Reusser, Bartlesville, Okla., assignor to Phillips Petroleum Company

No Drawing. Filed Apr. 3, 1967, Ser. No. 627,638
Int. Cl. C07c 5/00

U.S. Cl. 260—683 10 Claims

Olefins are converted into other olefins of different molecular weight by contact with an olefin reaction catalyst, having activity for disproportionating propylene into ethylene and butene, which catalyst has been treated with an inorganic base or a material convertible to an inorganic base, followed by treatment with a stream of hydrogen, carbon monoxide, a gaseous acyclic olefin or a gaseous paraffin.


3,579,603

PROCESS UTILIZING LIQUID ACID SETTLING IN AN ALKYLATION-FRACTIONATOR

Edwin K. Jones, Kenilworth, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.

Filed June 4, 1969, Ser. No. 830,344
Int. Cl. C07c 3/54

U.S. Cl. 260—683.48 10 Claims



An isoparaffin-olefin admixture is alkylated with a liquid acid alkylation catalyst (HF or H₂SO₄) and the total

reaction effluent from the alkylator is passed to an alkylation-fractionator vessel which provides a settling zone therein for separating the liquid catalyst. The hydrocarbon phase undergoes fractionation and separate fractions are removed from above and below the settling zone. The process produces high octane alkylated hydrocarbons utilizing a simplified flow scheme where a single vessel separates the total reaction effluent.

3,579,604

ISOMERIZATION OF OCTALINS

Anthony L. Tumolo, Havertown, Pa., assignor to Sun Oil Company, Philadelphia, Pa.

No Drawing. Filed Apr. 27, 1970, Ser. No. 32,363
Int. Cl. C07c 13/08

U.S. Cl. 260—666 4 Claims

An octalin is isomerized to another octalin, in particular 1,9-octalin to 9,10-octalin, by contact, preferably in a nonaqueous system, with strongly acidic ion exchange resin having a macroporous structure.

3,579,605

ISOMERIZATION OF OCTALINS

Anthony L. Tumolo, Havertown, Pa., assignor to Sun Oil Company, Philadelphia, Pa.

No Drawing. Filed Apr. 27, 1970, Ser. No. 32,436
Int. Cl. C07c 13/28

U.S. Cl. 260—666 6 Claims

An octalin is isomerized to another octalin, in particular, 1,9-octalin to 9,10-octalin, by contact with a catalyst combination comprising silica gel and a hydrogen halide, or sulfuric acid, or phosphoric acid.

3,579,606

N-DECATRIENE ISOMERIZATION

Wilfried Umbach, Langenfeld, Germany, assignor to Henkel & Cie, GmbH, Dusseldorf-Holthausen, Germany

No Drawing. Filed Apr. 10, 1969, Ser. No. 815,185
Claims priority, application Germany, June 29, 1968, P 17 68 792.2
Int. Cl. C07c 11/00

U.S. Cl. 260—677 3 Claims

As a new compound, n-decatriene-1,6,8, useful as a modifier for coating agents, particularly for reducing the dust drying time of air-drying alkyd resin coating agents.

3,579,607

POLYESTER-SUBSTITUTED ORGANOSILICON COMPOSITIONS

Markus Matzner, Edison, and Allen Noshay, East Brunswick, N.J., assignors to Union Carbide Corporation, New York, N.Y.

No Drawing. Filed Jan. 17, 1969, Ser. No. 792,132
Int. Cl. C08g 39/10, 47/10, 17/13

U.S. Cl. 260—824 13 Claims

This invention relates to cyclobutane diol polyester-substituted organosilicon compositions characterized by a polymeric segment or block that is composed of recurring cyclobutylene groups linked to each other through carbonate linkages (—OCO—) or di(carbonyloxy)hydrocarbylene linkages and that is chemically bonded to a silicon atom. The novel compositions have a silicon-containing segment derived from a silane or a siloxane. In the latter case, the compositions are block copolymers. The compositions are stable to heat and light and are useful as protective coatings, molding resins and elastomers.

3,579,608

WIRE COATING OF BROMINATED DIGLYCIDYL ETHER OF BISPHENOL A AND POLYVINYL CHLORIDE

John B. De Coste, Basking Ridge, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Aug. 26, 1968, Ser. No. 755,124
Int. Cl. C08g 45/04

U.S. Cl. 260—837

4 Claims

An abrasion resistant, insulating wire coating comprises plasticized vinyl chloride and a brominated bisphenol epoxy resin.

3,579,609

FLEX-RESISTANT POLYESTER FILM CONTAINING OLEFIN OR POLYTETRAMETHYLENE OXIDE ADDITIVE POLYMER

Robert J. Sevenich, White Bear Lake, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Sept. 23, 1968, Ser. No. 761,786
Int. Cl. C08g 39/10, 51/54

U.S. Cl. 260—873

6 Claims

Physically blending minor amounts of fusible heat-stable polymers of lower-mono-alpha olefin or tetramethylene oxide into polyester resin which is to be extruded into a film and thereafter oriented, imparts unexpectedly superior flex resistance to the ultimate film. The film also displays excellent "slip" and, in many instances, improved electrical properties. Among the suitable additive polymers are polyethylene, polypropylene, polybutylene, poly-4-methyl pentene, ethylene vinyl acetate copolymer, ethylene propylene copolymers and polytetramethylene oxide.

3,579,610

PROTECTIVE AND DECORATIVE THERMO-SETTING COATING

John Christos Petropoulos, Norwalk, and Ralph Earl Layman, Stamford, Conn., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Oct. 2, 1968, Ser. No. 764,595
Int. Cl. C08g 37/32; C08f 37/18, 29/22

U.S. Cl. 260—853

10 Claims

A coating composition comprising an acrylic resin, polyvinylidene fluoride and hexakisethoxymethyl melamine is disclosed.

3,579,611

CROSSLINKED POLYOXYETHYLENES AND PROCESS THEREFOR

Fred F. Holub and Moyer M. Safford, Schenectady, N.Y., assignors to General Electric Company

No Drawing. Filed Dec. 26, 1967, Ser. No. 693,166
Int. Cl. C08f 29/50, 27/00

U.S. Cl. 260—874

10 Claims

Polyoxyethylenes are mixed with an organic crosslinking agent and an organic peroxide and heated at elevated temperatures to crosslink the polyoxyethylene to yield a water-insoluble polymer. These crosslinked polyoxyethylene compositions are useful as membrane material, wire coating, and the like and as water-insoluble coatings for cloth, metal, metallic screen, etc.

3,579,612

SUSPENSION SYSTEM FOR PRODUCING HIGH IMPACT POLYSTYRENE

Arthur I. Lowell, Edison, N.J., assignor to Mobil Oil Corporation

No Drawing. Filed Sept. 3, 1968, Ser. No. 757,152
Int. Cl. C08f 1/11, 15/04

U.S. Cl. 260—880

2 Claims

In the preparation of high impact polystyrene by bulk prepolymerization of a rubber in a styrene followed by aqueous suspension polymerization using water-soluble

suspending agents, excessive foaming and emulsification occurs. These difficulties are reduced by using in the suspension system a combination of a water-soluble hydroperoxide and a water-soluble metal formaldehyde sulfonate or its equivalent, together with the water-soluble suspension agent.

3,579,613

POLYSALTS CONTAINING SULFONATED ACRYLICS

Raymond J. Schaper, Pittsburgh, and Merwin Frederick Hoover, Bethel Park, Pa., assignors to Calgon Corporation

No Drawing. Filed Nov. 16, 1967, Ser. No. 683,467
Int. Cl. C08f 29/50, 33/08

U.S. Cl. 260—901

3 Claims

Poly(sulfonated acrylics) are reacted with various cationic polymers to form polysalts.

3,579,614

2-CYANOVINYL PHOSPHATES AND PHOSPHOROTHIOATES

Bernard Miller, Plainsboro, and Howard Margulies, Princeton Junction, N.J., assignors to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Aug. 8, 1967, Ser. No. 659,014
Int. Cl. C07f 9/08; A01n 9/36

U.S. Cl. 260—940

9 Claims

The present invention relates to novel 2-cyanovinyl phosphates and phosphorothioates and their isomers, a method for their preparation and the use of said compounds for control of pests which damage or destroy agronomic crops and/or spread infection or disease to man, animal and bird populations.

3,579,615


PHOSPHORUS-CONTAINING SULFONYL-CHLORIDESJohn E. Herweh and Algirdas C. Poshkus, Lancaster, Pa., assignors to Armstrong Cork Company, Lancaster, Pa.
No Drawing. Original application Apr. 6, 1966, Ser. No. 540,486, now Patent No. 3,423,485, dated Jan. 21, 1969. Divided and this application June 24, 1968, Ser. No. 765,716

Int. Cl. C07f 9/12, 9/40

U.S. Cl. 260—947

3 Claims

A class of chlorosulfonated phosphorus esters of the formula:

where R may be lower alkyl; R' may be Cl, NO₂, lower alkyl and H; m is an integer from 1 to 3; n is an integer from 0 to 2; and the sum of m+n is an integer from 1 to 3. These compounds find utility as intermediates in the formation of sulfonylhydrazides by reaction with hydrazine. The sulfonyl-hydrazides are useful as blowing agents for resinous blends.

3,579,616



METHOD OF CARRYING OUT ENDOTHERMIC PROCESSESLothar Reb, Bergen-Enkheim, Karlheinz Rosenthal, Neu Isenburg, and Hans Werner Schmidt, Frankfurt am Main, Germany, assignors to Metallgesellschaft Aktiengesellschaft, Frankfurt am Main, Germany
Filed May 5, 1969, Ser. No. 821,773Claims priority, application Germany, May 30, 1968, P 17 67 628.7
Int. Cl. F26b 3/08; F27b 15/00

U.S. Cl. 263—52

8 Claims

In an endothermic process, raw solids are first dried in a suspension-type heat-exchanger system by hot gas

coming from a fluidized-bed furnace with material recycling and then introduced into the fluidized bed. Hot solids taken from the fluidized bed are used in a heat vacuum means remove from the system any loose ends of ribbons that may become severed during orientation, preventing such severed ribbons from becoming entangled in the stretching rolls.



preventing such severed ribbons from becoming entangled in the stretching rolls.

3,579,619

ROASTING MARL TO PRODUCE A POZZOLANA MATERIALDietrich Harkort, Am Schwalbenschwanz 56; and Rudolf Rasch, Georg-Speyer-Strasse 86, both of 6 Frankfurt am Main, Germany; Rolf Iberg, Chapfstrasse 19, CH-8142 Uitikon, Switzerland; and Jurg H. Heberlein, Rohrbaldenstrasse 41, CH-8712 Stafa, Switzerland
No Drawing. Filed Aug. 23, 1968, Ser. No. 754,993
Claims priority, application Germany, Aug. 25, 1967, B 94,148

Int. Cl. C04b 7/12, 7/44

U.S. Cl. 264—42

2 Claims


Construction materials of high strength and low volumetric weight are formed by hardening in an autoclave at about 165° and at an atmospheric pressure and for a time such that the multiplicand equals about 65 atmosphere hours a thermally active earth mixed with water. The earth or "washed clay" is a mineral substance or marl comprising by weight calcium carbonate (10–30%), clay minerals (40–70%) and quartz (20–50%) having about a 1:1 ratio of CaO:SiO₂ and a TiO₂ content of 0.2 to 3%. The marl is first roasted at a temperature below its melting phase (700–900° C.) and crushed to a grain size of 4 to 6 mm. 4–8% by weight of portland cement, lime or hydraulic lime is added before hardening to give increased compression strength to the final construction material.

3,579,620

BLOW MOLDINGLennart K. Pettersson, Bloomfield, Conn., assignor to Monsanto Company, St. Louis, Mo.
Filed Nov. 26, 1968, Ser. No. 778,995
Int. Cl. B29c 17/07

U.S. Cl. 264—98

15 Claims



A method of providing a perfectly flat surface plate for use as a measurement reference plane in styling automobiles, wherein a magnetic fixture having a flat lower magnetic face is positioned over the floor on which it is desired to provide the surface plate and a strip of cold rolled steel is positioned against the flat lower magnetic face of the fixture; the magnetic force generated by the fixture forces the strip to conform to the flatness of the magnetic face and the strip is thereafter set in place by filling the space between the strip and the base surface with an epoxy adhesive which, when hardened, serves to maintain the strip in the flat configuration imparted to it by the magnetic fixture.

3,579,618

HIGH SPEED FIBRILLATION PROCESS

Dan F. Stewart, Bob C. Blair, Max E. Greene, and Lloyd R. Alexander, Bartlesville, Okla., assignors to Phillips Petroleum Company

Filed Aug. 9, 1968, Ser. No. 751,458

Int. Cl. B29c 17/14; B29d 7/24; D01d 5/00

U.S. Cl. 264—37

4 Claims

A process for forming a fibrillated product comprising forming a film from a flattened plastic tube, molecularly orienting the film and fibrillating the oriented film, wherein


Parison pinch off surfaces of a blow mold and/or the area of the mold defining an opening extending through the body of a handleware container are kept at elevated temperature in comparison with remaining cooled portions of the mold during closing of the mold sections and

formation of the article, in order to facilitate subsequent removal of waste flash which is integrally formed with the article in these areas of the mold.

3,579,621

METHOD AND APPARATUS FOR FORMING HOLLOW PLASTIC ARTICLES

Gottfried Mehnert, Berlin-Mariendorf, Germany, assignor to Conduco AG, Zug, Switzerland
Filed Nov. 7, 1968, Ser. No. 774,091
Claims priority, application Germany, Nov. 10, 1967, P 17 04 209.0
Int. Cl. B29c 17/06, 17/07, 23/00
U.S. Cl. 264-99 13 Claims




The extruder of a blow molding apparatus extrudes a tubular blank and moves continuously with reference to a series of sectional blow molds or vice versa. The movements of mold sections to closed positions are timed in such a way that the upper end of the extruded portion of the blank is clampingly engaged by the mold sections later than the lower end or vice versa, always with such a delay that the axis of the thus engaged portion of the blank is coaxial with the mold cavity. This is achieved by pivoting the mold sections between upright and inclined positions or by providing the mold sections with movable upper or lower blank-engaging parts.

3,579,622

METHOD FOR BLOW MOLDING PLASTIC ARTICLES

Charles H. Shaw, Bloomfield, and Robert G. Strauss, West Hartford, Conn., assignors to Monsanto Company, St. Louis, Mo.
Original application Oct. 17, 1966, Ser. No. 587,255, now Patent No. 3,509,596, dated May 5, 1970. Divided and this application Apr. 10, 1969, Ser. No. 839,746
Int. Cl. B29c 17/07
U.S. Cl. 264-99 1 Claim




A method of blow molding a hollow article wherein the parison is preblown and then allowed to partially deflate and shrink in size to obtain the benefit of stretching during pre-inflation while avoiding chill marks in the finished article.

3,579,623

FORMING FILLED CONTINUOUS PLASTIC ROD SUCH AS PLASTIC CIGARETTE FILTER ROD FILLED WITH A TOW OF CELLULOSE ACETATE

Richard N. Thomson, Jerome S. Osmalov, and George L. Mathe, Richmond, Va., assignors to Philip Morris Incorporated, New York, N.Y.
Filed July 24, 1968, Ser. No. 747,279
Int. Cl. B29d 9/00, 23/14
U.S. Cl. 264-135 3 Claims




A method with which a continuous length, tubular article filled with a gas or liquid pervious filler material such as a tow filled plastic cigarette filter rod is formed by extruding plastic as a sheath around an advancing bloomed tow of fibrous filter material, heat from the plastic extrudate being utilized in the course of the forming operations to accelerate curing of a plasticizer impregnating the tow. A crosshead type extrusion die is utilized for the forming operation and is provided with a central tube extending longitudinally therein for receiving the advancing tow and isolating it from the molten plastic with which the extrudate is formed, the latter entering the die laterally and issuing from the mouth thereof as a continuous tubular sheath which makes first contact with the tow at a distance downstream of the die mouth. The extrudate on leaving the crosshead die is then sized by passing it through a cooling chamber wherein the external dimension of the plastic sheath is accurately controlled within predetermined limits.

3,579,624

INSULATED ALKALI METAL CONDUCTOR

Alvin Guttag, Bethesda, Md., assignor to Weston Chemical Corporation, New York, N.Y.
Original application Sept. 25, 1967, Ser. No. 670,166. Divided and this application Mar. 7, 1969, Ser. No. 828,037
Int. Cl. B29c 27/20; B29f 3/10; D01d 5/16
U.S. Cl. 264-171 19 Claims




Electrical conductors comprising an alkali metal conducting core are coated with a preformed heat shrinkable inert olefin hydrocarbon polymer film or sheet and the hydrocarbon shrunk into tight engagement with the alkali metal. The heat of the molten metal or of the metal while it is cooling can be used to shrink the polymer.

3,579,625

PROCESS FOR FORMING TRILOBAL YARNS

Jean-Louis Jacquinet, Lyon, Rhone, France, assignor to Société Rhodiaceta
Filed Sept. 27, 1967, Ser. No. 670,862
Claims priority, application France, Sept. 29, 1966, 78,186; Aug. 11, 1967, 117,816
Int. Cl. B29f 3/00, 21/54
U.S. Cl. 264-177 4 Claims




The invention discloses a spinneret for producing a trilobal filament, and filaments produced using such spinneret. The shape of each orifice of the spinneret can be considered as being produced by a circular aperture, diameter D into which project at 120° intervals, three identical triangular portions, sides of the triangles being tangent to one or more coaxial circles having a diameter between 1/4 and 1/3 of D, the angle at the apex of each triangle being between 60 and 100°.

3,579,626

METHOD FOR CURING TIRES AND THE LIKE

Glenn B. Brittain, Amiens, France, assignor to The Good-year Tire & Rubber Company, Akron, Ohio
Filed Oct. 30, 1968, Ser. No. 771,757
Int. Cl. B29h 5/01, 5/02
U.S. Cl. 264-297 19 Claims



A method for curing tires in a bladder-equipped press. During the main heating period, the bladder is filled first with steam to conform the tire and bladder to the mold and to begin the cure of the tire. The steam is then replaced with water at a high pressure and at a temperature approximately equal to the maximum permissible vulcanizing temperature so as to maintain the tire against the mold and to continue the cure. In the final phase of the main heating period, steam at a high pressure at least equal to the vapor pressure of the water is utilized to force the water, without vaporization, from the bladder without interruption of the curing operation. The remaining steam is then vented to the atmosphere. In this manner, the water used to cure the tire can be reused without a change of state and the bladder is maintained at a high temperature for subsequent curing cycles.

3,579,627

RH₀ BLOOD TESTING SERUM

Zenro Hayakawa, Matsumoto, Japan, assignor to Takeda Chemical Industries, Ltd., Osaka, Japan
No Drawing. Filed Sept. 29, 1967, Ser. No. 671,550
Claims priority, application Japan, Sept. 29, 1966, 41/64,581
Int. Cl. G01n 33/16 2 Claims

U.S. Cl. 424-11
Rh₀ testing serum comprises anti-Rh₀ incomplete antibody of human origin and anti-Rh₀ complete antibody of animal origin, the Coombs titre and the agglutinin titres being at least about 32 and about 16, respectively, the ratio of Coombs titre to agglutinin titre being from about 1:2 to about 8:1.

3,579,628

DRESSING FILM

Robert J. Gander, Whitehouse, and David T. Rovee, Hopewell, N.J., assignors to Johnson & Johnson
No Drawing. Filed July 3, 1967, Ser. No. 650,599
Int. Cl. A61l 15/00, 15/01, 15/03 11 Claims

U.S. Cl. 424-28
Dressings having a hydrophilic acrylic film component adapted to contact a wound surface are prepared in which the wound contacting film is insoluble in body fluids but has a substantial affinity for water. Moisture absorbed by the film acts to plasticize the film and provide a moist, flexible, conforming surface to the underlying wound tissue. The dressing may consist of a single piece of the hydrophilic acrylic film or the film may form a part of a composite dressing wherein the wound contacting surface of the dressing is formed of a hydrophilic acrylic film. The hydrophilic acrylic films are particularly suitable for use as occlusive dressings and for controlling the proliferation of bacteria where the same have, dispersed therethrough, compositions which react with water to generate a bacteriostatic substance. Where the film base is a hydrophilic acrylic the effectiveness of the presence of the bacteriostat-generating materials, when present, is appreciably increased while any chance of tissue irritation is substantially reduced.

3,579,629

SALTS OF COPOLYMERS OF VINYL ACETATE/CROTONIC ACID/VINYLIC OR ALLYLIC OR METHALLYLIC ESTERS IN HAIR COSMETICS

Regine Pasero, nee Perruche, and Andre Viout, Paris, France, assignors to Societe Anonyme dite: L'Oreal
No Drawing. Filed July 25, 1967, Ser. No. 655,770
Claims priority, application France, Aug. 3, 1966, 71,998
Int. Cl. A61k 7/06 7 Claims

U.S. Cl. 424-47
Compositions containing copolymers for use as hair dressing preparations. The copolymers consist of vinyl acetate, crotonic acid and either a vinylic ester, allylic ester or methallylic ester.

3,579,630

TREATING THE HAIR WITH OXAZOLINE POLYMER AND COPOLYMER HAIR DRESSING FORMULATIONS

Jack L. Herz, Parsippany, Alan J. Levy and Morton H. Litt, Morristown, and Joseph L. Zuckerman, Livingston, N.J., assignors to Allied Chemical Corporation, New York, N.Y.
No Drawing. Filed Dec. 29, 1966, Ser. No. 605,590
Int. Cl. A61k 7/06 9 Claims

U.S. Cl. 424-47
An improved hair dressing formulation containing (a) from about 0.1 to about 10 weight percent of a water-

DESIGNS

MAY 18, 1971

220,741
BRASSIERE

Joseph P. Marcario, Saddle Brook, and Jack J. LoCascio, Bayonne, N.J., assignors to Sarong, Inc., New York, N.Y.

Filed Nov. 3, 1969, Ser. No. 19,877
Term of patent 14 years
Int. Cl. D2—02


U.S. Cl. D2—24



220,742
SWIM SUIT OR SIMILAR ARTICLE
Edward H. Mohl, 5716 Woodbine Ave., Philadelphia, Pa. 19131

Original design application Nov. 25, 1968, Ser. No. 14,642, now Patent No. 216,245, dated Dec. 9, 1969. Divided and this application July 24, 1969, Ser. No. 19,343
Term of patent 14 years
Int. Cl. D2—01

U.S. Cl. D2—42



220,743
GOGGLES

Theodore C. Neward, 2066 W. 11th St., Upland, Calif. 91786

Original design application Apr. 7, 1969, Ser. No. 16,604, now Patent No. 218,547, dated Sept. 1, 1970. Divided and this application Jan. 16, 1970, Ser. No. 20,958
Term of patent 14 years
Int. Cl. D2—03

U.S. Cl. D2—234




220,744
FRICTION TYPE BOTTLE CAP REMOVER

James E. Guthrie, 5917-B Woodson Road, Kansas City, Mo. 64133

Filed Sept. 2, 1969, Ser. No. 18,943
Term of patent 14 years
Int. Cl. D8—02

U.S. Cl. D8—18




220,745
GLASS CUTTING TOOL

Stephen J. Kovacik, Rossford, Ohio, assignor to Libbey-Owens-Ford Company, Toledo, Ohio

Filed Apr. 20, 1970, Ser. No. 22,514
Term of patent 14 years
Int. Cl. D8—02

U.S. Cl. D8—51




220,746
TYPE SOLDERING JIG

Robert C. Lokey, Tamal, Calif. (% Lokey Tool, Inc., 220 Juana Ave., San Leandro, Calif. 94577)

Filed Nov. 5, 1969, Ser. No. 19,961
Term of patent 14 years
Int. Cl. D8—02

U.S. Cl. D8—71



MAY 18, 1971

U. S. PATENT OFFICE


627

220,747
STATIONARY PULL

James R. Deadrick, Winston-Salem, N.C., assignor to Stewart-Warner Corporation, Chicago, Ill.

Filed Feb. 9, 1970, Ser. No. 21,340
Term of patent 14 years
Int. Cl. D8—03

U.S. Cl. D8—159




220,750
COMBINED PACKAGING TRAY AND COVER

Kenneth W. Artz, Mohnton, Pa., assignor to W. R. Grace & Co., Duncan, S.C.

Filed Dec. 17, 1968, Ser. No. 15,021
Term of patent 14 years
Int. Cl. D9—04

U.S. Cl. D9—185



220,748
BOTTLE

Jerome Gould, Encino, Calif., assignor to Johnson & Johnson

Filed June 1, 1970, Ser. No. 23,240
Term of patent 14 years
Int. Cl. D9—01

U.S. Cl. D9—82




220,751
COMBINED PACKAGING TRAY AND COVER

Kenneth W. Artz, Mohnton, Pa., assignor to W. R. Grace & Co., Duncan, S.C.

Filed Dec. 17, 1968, Ser. No. 15,022
Term of patent 14 years
Int. Cl. D9—04

U.S. Cl. D9—219




220,749
COMBINED PACKAGING TRAY AND COVER

Kenneth W. Artz, Mohnton, Pa., assignor to W. R. Grace & Co., Duncan, S.C.

Filed Dec. 17, 1968, Ser. No. 15,018
Term of patent 14 years
Int. Cl. D9—04

U.S. Cl. D9—185




220,752
COMBINED PACKAGING TRAY AND COVER

Kenneth W. Artz, Mohnton, Pa., assignor to W. R. Grace & Co., Duncan, S.C.

Filed Dec. 17, 1968, Ser. No. 15,023
Term of patent 14 years
Int. Cl. D9—04


U.S. Cl. D9—219



220,753
CONTAINER END

Arthur P. Zundel, 5959 S. Cicero Ave., Cary, Ill. 60638
Filed Jan. 26, 1970, Ser. No. 21,080
Term of patent 14 years
Int. Cl. D9—99


U.S. Cl. D9—253



220,754
CONTAINER END

Arthur P. Zundel, 5959 S. Cicero Ave., Cary, Ill. 60638
Filed Jan. 26, 1970, Ser. No. 21,081
Term of patent 14 years
Int. Cl. D9—99


U.S. Cl. D9—253



220,755
CONTAINER END

Arthur P. Zundel, 5959 S. Cicero Ave., Cary, Ill. 60638
Filed Jan. 26, 1970, Ser. No. 21,093
Term of patent 14 years
Int. Cl. D9—99

U.S. Cl. D9—253




220,756
UNIT FOR DISPENSING LIQUID FROM A CONTAINER

Richard D. Zenger, 2745 College Ave., Downers Grove, Ill. 60515, and Raymond M. Traczyk, 5428 S. Sayre, Chicago, Ill. 60638
Continuation-in-part of design application Ser. No. 10,963, Mar. 13, 1968. This application Sept. 22, 1969, Ser. No. 19,490

Term of patent 14 years
Int. Cl. D9—99

U.S. Cl. D9—290



220,757
BOTTOM RAIL FOR A ROLL-TYPE DOOR

Richard E. Smith, Columbus, Ohio, assignor to Kinneer Corporation, Columbus, Ohio
Filed Sept. 11, 1969, Ser. No. 19,116
Term of patent 14 years
Int. Cl. D25—02

U.S. Cl. D13—1



220,758
BUILDING

Donald J. Thomas, St. Louis County, Mo., assignor to Burger Chef Systems, Inc.
Filed Nov. 26, 1969, Ser. No. 20,295
Term of patent 14 years
Int. Cl. D25—04


U.S. Cl. D13—1



220,759
BUILDING OR THE LIKE

William C. Renwick, Barrington, Ill., assignor to Brunswick Corporation, Chicago, Ill.
Filed Apr. 8, 1970, Ser. No. 22,332
Term of patent 14 years
Int. Cl. D25—04


U.S. Cl. D13—1



220,760
MODULAR HOME

John M. Evans, Fort Lauderdale, Fla., assignor to Behring Corporation, Fort Lauderdale, Fla.
Filed Apr. 10, 1970, Ser. No. 22,371
Term of patent 14 years
Int. Cl. D25—04


U.S. Cl. D13—1



220,761
MOBILE LOUNGE CHAIR


Clarence E. Jackson, P.O. Box 1109, Texas City, Tex. 77590
Filed Dec. 19, 1969, Ser. No. 20,577
Term of patent 14 years
Int. Cl. D6—01

U.S. Cl. D15—11



220,762
FIRE EXTINGUISHER HOUSING
Lawton M. Dial, Jr., and Louis J. Grosshelm, Houston, Tex., Donald M. Schramme, Baton Rouge, La., and Walter H. Zenneker, Houston, Tex., assignors to Arthur Dooley and Son, Inc., Beaumont, Tex.
Filed Feb. 12, 1970, Ser. No. 21,411
Term of patent 14 years
Int. Cl. D29—01


U.S. Cl. D16—2



220,763
LAWN SPRINKLER

Melvin H. Best, Pasadena, Calif., assignor to Rain Bird Sprinkler Mfg. Corp., Glendora, Calif.
Filed Feb. 16, 1970, Ser. No. 21,450
Term of patent 14 years
Int. Cl. D23—01

U.S. Cl. D23—7




220,764
HOUSING FOR COMPUTER INTERFACE UNIT
Charles J. Ortega, Van Nuys, and Frederic L. Naff, Jr., Los Angeles, Calif., assignors to Computer Transmission Corporation, Los Angeles, Calif.
Filed Mar. 23, 1970, Ser. No. 22,016
Term of patent 14 years
Int. Cl. D14—02

U.S. Cl. D26—5




220,765
PANEL BOX FOR REFRIGERATOR CONTROL
Gus Romanias, 2611 S. Grant St., Arlington, Va. 22202, and Herman H. Gorham, 5616 Bouffant Blvd., Alexandria, Va. 22311
Filed Nov. 28, 1969, Ser. No. 20,302
Term of patent 14 years
Int. Cl. D13—03

U.S. Cl. D26—13




220,766
STANDARD FOR USE IN SUPPORTING
HORIZONTAL BOOKSHELVES
 Phillip E. Miller, 1861 Heatherdale Ave.,
 San Jose, Calif. 95126
 Filed July 16, 1969, Ser. No. 18,225
 Term of patent 14 years
 Int. Cl. D6—99

U.S. Cl. D33—3




220,767
INSTRUCTION CUBICLE
 Lawrence H. Power, 710 Leona Drive,
 Ann Arbor, Mich. 48103
 Filed Jan. 6, 1970, Ser. No. 20,776
 Term of patent 14 years
 Int. Cl. D6—01

U.S. Cl. D33—7




220,768
COCKTAIL TABLE
 John H. Jordan, Jr., 8211 S. Maryland Ave.,
 Chicago, Ill. 60619
 Filed Aug. 29, 1969, Ser. No. 18,919
 Term of patent 14 years
 Int. Cl. D6—01

U.S. Cl. D33—14




220,769
SLIDABLE GOLF BALL FOR PUTTING PRACTICE
 Paul D. LaHue, 5880 N. Rural, Indianapolis, Ind. 46220
 Filed Nov. 7, 1969, Ser. No. 19,986
 Term of patent 14 years
 Int. Cl. D21—01

U.S. Cl. D34—5




220,770
PLANTER BOWL
 Lynn R. Townsend, 10707 Jamacha Blvd., Space 174,
 Spring Valley, Calif. 92077
 Filed Sept. 5, 1969, Ser. No. 19,041
 Term of patent 14 years
 Int. Cl. D31

U.S. Cl. D35—1



220,771
POWER TRAIN FOR SUGAR HARVESTERS
 Vernon P. Broussard, P.O. Box 227,
 St. Martinville, La. 70582
 Continuation-in-part of abandoned design application Ser.
 No. 11,429, Apr. 12, 1968. This application Dec. 18,
 1969, Ser. No. 20,558
 Term of patent 14 years
 Int. Cl. D15—03

U.S. Cl. D40—1



220,772
PULLER
 Harold V. Hawkins, 4985 Meadowbrook Road; and Ralph
 A. Dick, 8667 Bonview, both of Williamsville, N.Y.
 14221; and John Wendel, 42 Susan Lane, Cheektowaga,
 N.Y. 14225
 Filed Feb. 5, 1970, Ser. No. 21,286
 Term of patent 14 years
 Int. Cl. D8—02

U.S. Cl. D41—1




220,773
COVERED BEVERAGE PITCHER
 Richard D. Dilyard, Wooster, Ohio, assignor to
 Rubbermaid Incorporated, Wooster, Ohio
 Filed Feb. 16, 1970, Ser. No. 21,558
 Term of patent 14 years
 Int. Cl. D7—01

U.S. Cl. D44—1




220,774
FOOD SERVICE TRAY
 Harford E. Goings, 5428 Center Drive,
 Camp Springs, Md. 20031
 Filed Oct. 10, 1969, Ser. No. 19,496
 Term of patent 14 years
 Int. Cl. D7—01

U.S. Cl. D44—10




220,775
**COMBINED EGG HOLDER AND OPENER, CONDI-
 MENT DISPENSERS AND HOLDER THEREFOR
 AND SPOON HOLDER**
 Frank D. O'Neill, 94 Willcocks St. W.,
 Toronto, Ontario, Canada
 Filed Feb. 10, 1970, Ser. No. 21,392
 Term of patent 14 years
 Int. Cl. D7—99

U.S. Cl. D44—24



220,776
**EXPANSIBLE END LINK FOR A BRACELET
 OR SIMILAR ARTICLE**
 Murray L. Cowan, Norwood, Mass., assignor to
 Textron Inc., Providence, R.I.
 Filed May 5, 1970, Ser. No. 22,815
 Term of patent 14 years
 Int. Cl. D11—01

U.S. Cl. D45—4





220,777

MOTOR VEHICLE LAMP LENS

Philip Garcia, Sterling Heights, Mich., assignor to General Motors Corporation, Detroit, Mich.
 Filed Jan. 26, 1970, Ser. No. 21,067
 Term of patent 7 years
 Int. Cl. D12—99

U.S. Cl. D48—32





220,779

MOTOR VEHICLE LAMP LENS

Philip Garcia, Sterling Heights, Mich., assignor to General Motors Corporation, Detroit, Mich.
 Filed Jan. 26, 1970, Ser. No. 21,089
 Term of patent 7 years
 Int. Cl. D12—99

U.S. Cl. D48—32




220,778

LUMINAIRE


Edward R. Jablonski, South Milwaukee, Wis., and Giacinto C. D'Ercoli, Part Forest, Ill., assignors to McGraw-Edison Company, South Milwaukee, Wis.
 Filed Jan. 26, 1970, Ser. No. 21,083
 Term of patent 14 years
 Int. Cl. D26—03

U.S. Cl. D48—31

**220,780
AUTOMOTIVE LAMP**

Charles J. Newman, Madison, Ind., assignor to The Grote Manufacturing Company, Madison, Ind.
 Filed Apr. 27, 1970, Ser. No. 22,685
 Term of patent 14 years
 Int. Cl. D12—99

U.S. Cl. D48—32



220,781

BALLOON VENDING MACHINE

Monte L. Levin, New York, N.Y., assignor to Miner Industries, Inc., New York, N.Y.
 Filed May 14, 1970, Ser. No. 22,984
 Term of patent 14 years
 Int. Cl. D20—01

U.S. Cl. D52—3




220,782

PORTABLE BATTERY TESTER

Albert Mazeika, Chicago, Ill., assignor to Milton Manufacturing Company, Inc., Chicago, Ill.
 Filed July 10, 1970, Ser. No. 23,894
 Term of patent 14 years
 Int. Cl. D10—11

U.S. Cl. D52—6




220,783

SPOON OR SIMILAR ARTICLE OF FLATWARE

Ronald A. Guodace, Tracy, Conn., assignor to International Silver Company, Meriden, Conn.
 Filed June 8, 1970, Ser. No. 23,341
 Term of patent 14 years
 Int. Cl. D7—03

U.S. Cl. D54—12



220,784

SPOON OR SIMILAR ARTICLE OF FLATWARE

Robert King, Wallingford, Conn., assignor to International Silver Company, Meriden, Conn.
 Filed June 8, 1970, Ser. No. 23,382
 Term of patent 14 years
 Int. Cl. D7—03

U.S. Cl. D54—12



220,785

SPOON OR SIMILAR ARTICLE OF FLATWARE
Siro R. Toffolon, Meriden, Conn., assignor to International Silver Company, Meriden, Conn.
Filed June 10, 1970, Ser. No. 23,432
Term of patent 14 years
Int. Cl. D7—03


U.S. Cl. D54—12



220,788

**OCCUPANT-BODY-STEERABLE SELF-PROPEL-
LABLE AQUAPLANE OR SIMILAR ARTICLE**
Joe E. Piazza, Pacifica, Calif., assignor to Leisure Products Corporation, Menlo Park, Calif.
Filed Apr. 15, 1970, Ser. No. 22,450
Term of patent 14 years
Int. Cl. D21—03


U.S. Cl. D71—1



220,786

PHOTOGRAPHIC SLIDE SORTING RACK
Aaron E. Gandy, P.O. Box 741, 2613 W. Storey,
Midland, Tex. 79701
Filed Apr. 22, 1970, Ser. No. 22,571
Term of patent 14 years
Int. Cl. D16—99


U.S. Cl. D61—1



220,789

COSMETIC CASE
Klein K. Haddaway, 1650 21st Road N.,
Arlington, Va. 22209
Filed Aug. 8, 1969, Ser. No. 18,594
Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D86—10



220,787

TYPEWRITER
John Svezia, Millburn, N.J., assignor to Ing. C. Olivetti &
Co., S.p.A., Ivrea, Italy
Filed Feb. 24, 1970, Ser. No. 21,576
Term of patent 14 years
Int. Cl. D18—01



U.S. Cl. D64—11



220,790

IDENTIFICATION TAG BLANK
William T. Rives, 38 Decorie Drive,
Wilbraham, Mass. 01095
Filed June 16, 1969, Ser. No. 17,730
Term of patent 14 years
Int. Cl. D20—99


U.S. Cl. D96—3



220,791

SIGN PANEL
Marilyn Lewis, Beverly Hills, Calif., assignor to
Hamburger Hamlets, Inc.
Filed Dec. 15, 1969, Ser. No. 20,494
Term of patent 14 years
Int. Cl. D20—03

U.S. Cl. D96—12



LIST OF PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 18TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- Aas, Helge: *See—*
Dowhan, Wesley P.; Aas, Helge; and Nordheim, Rolf, 3,579,328.
- Abend, Irving J., to Lear Siegler, Inc. Protection circuit with simultaneous voltage and current sensing means. 3,579,042, Cl. 317-33.
- Abens, Sandors G.: *See—*
Neti, Radhakrishna M.; and Abens, Sandors G., 3,579,384.
- Abex Corporation: *See—*
Adams, Cecil E., 3,578,888.
- Abrams, Albert; Hill, Harold J.; and Thigpen, David R., to Shell Oil Company. Clay treating and oil-wetting dispersion and method of use thereof. 3,578,781, Cl. 166-305.
- Acker, Ellsworth G.: *See—*
Rosen, Harvey; Acker, Ellsworth G.; and Lee, Hanju, 3,579,464.
- Acme Visible Records, Inc.: *See—*
Toms, Lloyd M., 3,578,832.
- Acoustic Research, Inc.: *See—*
Grodinsky, Robert, 3,579,085.
- Adams, Cecil E., to Abex Corporation. Fluid pump having internal rate of pressure gain limiting device. 3,578,888, Cl. 418-133.
- Adronics, Inc.: *See—*
Antista, Santo M.; Koptula, Milton M.; and Burggraf, Gerard L., 3,579,241.
- Aerojet-General Corporation: *See—*
Stewart, Robert M., 3,579,202.
- Aeronautics and Space Administration with respect to an invention of: *See—*
Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., 3,579,412.
- Affel, John J., to International Telephone and Telegraph Corporation. Decade counter or the like. 3,578,792, Cl. 235-144.
- Aga, Takashi; and Yamanaka, Masami, to Yamato Scale Company, Limited. Pulse counting device with memory. 3,579,205, Cl. 340-173.
- Agfa-Gevaert Aktiengesellschaft: *See—*
Thate, Kurt; Winkler, Friedrich; and Theer, Anton, 3,578,856.
- Air Instruments, Inc.: *See—*
McBurnie, Thomas W., 3,578,872.
- Air Products and Chemicals, Inc.: *See—*
Miller, Keith A., 3,578,793.
- Air Reduction Company, Incorporated: *See—*
Tschang, Teh C., 3,579,068.
- Airoil Burner Company (GB) Limited: *See—*
Wilkinson, Ronald D., 3,578,892.
- Aisin Seiki Kabushiki Kaisha: *See—*
Yamazaki, Takeo, 3,578,759.
- Aktiebolaget Astra: *See—*
Sandberg, Rune Verner; Sjöberg, Berndt Olof Harald; and Tegner, Claes Philip, 3,579,523.
- Aktiebolaget Bofors: *See—*
Verdier, Emile Joseph-Henri, 3,579,285.
- Aktiebolaget Kamy: *See—*
Ooue, Shingo; Ueda, Hiroyuki; and Hayakawa, Yoshihide, 3,579,338.
- Richter, Johan C.F.C., 3,579,420.
- Richter, Johan C.F.C., 3,579,421.
- Aktiengesellschaft Brown, Boveri & Cie: *See—*
Bossi, Hans Jurg; and Faust, Werner, 3,579,082.
- Giess, Wilfried Elmar, 3,579,089.
- Albert, Dorothy S.: *See—*
Albert, Harry Elmer, 3,579,516.
- Albert, Harry Elmer, deceased (by Albert, Dorothy S.; executrix), to Pennwalt Corporation. Bis(thiocarbamylthiomethyl) polysulfides. 3,579,516, Cl. 260-246.
- Alcolac Chemical Corporation: *See—*
Zaslowsky, Joel A.; and Gould, Henry, 3,579,565.
- Aldridge, Charles A., to Bell & Howell Company. Motion picture apparatus having sensing means for film carried cue signals. 3,578,852, Cl. 352-92.
- Alexander, Lloyd R.: *See—*
Stewart, Dan F.; Blair, Bob C.; Greene, Max E.; and Alexander, Lloyd R., 3,579,618.
- Alexo, Corporation: *See—*
Wildman, Alexander J., 3,578,744.
- Allan, Barry D.; and Cunningham, John J., Jr., to United States of America, Army Quinn Brothers, Incorporated. Monopropellant comprising certain difluoroamino Dust and smoke removal in tire buffing compounds and nitric acid. 3,579,314, Cl. 51-273.
- Allen, George Rodger, Jr.: *See—*
Littell, Ruddy; and Allen, George Rodger, Jr., 3,579,534.
- Allen, Lloyd R.: *See—*
Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.
- Allen-Bradley Company: *See—*
De Smidt, Woodrow A.; and Kuhn, Edward H., 3,578,933.
- Dickinson, Clarence R., 3,579,169.
- McCall, Amiel J., 3,578,956.
- Alliance Manufacturing Company: *See—*
Deming, Andrew F., 3,579,240.
- Allied Chemical Corporation: *See—*
Herz, Jack L.; Levy, Alan J.; Litt, Morton H.; and Zuckerman, Joseph L., 3,579,630.
- Sefton, Verner B.; Bailey, Lawrence L.; and Autin, Donel C., 3,579,381.
- Twilley, Ian C.; Russell, William N.; and Peterson, Weldon H., 3,579,483.
- Allis, Louis, Company, The: *See—*
Appelgren, James W., 3,579,227.
- Vollrath, Donald E., 3,579,080.
- Allis-Chalmers Manufacturing Company: *See—*
Goeller, Charles P., 3,579,043.
- Keogh, Thomas H.; and Krupit, Adolph E., 3,579,045.
- Allmanna Svenska Elektriska Aktiebolaget: *See—*
Bjork, Lennart, 3,579,083.
- Alton, Kelly F., 49% to Earle, James D. Pumping apparatus. 3,578,885, Cl. 417-454.
- Altshuler, Thomas L., to United States of America, National Aeronautics and Space Administration. Orifice gross leak tester. 3,578,758, Cl. 73-40.7.
- Amchem Products, Inc.: *See—*
Manson, Frank E.; and Steinbrecher, Lester, 3,579,429.
- Amedjian, Garabed; Fenoglio, Maurice; and Oberdorf, Michel, to Rhone-Poulenc S.A. Process for the production of terephthalic acid. 3,579,572, Cl. 260-515.
- American Atomics Corporation: *See—*
Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,972.
- Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,973.
- American Cyanamid Company: *See—*
Castellion, George Augustus, 3,578,843.
- Heller, Milton David; Lenhard, Robert Herman; and Bernstein, Seymour, 3,579,508.
- Hlavka, Joseph J.; Bitha, Panayota; Ross, Adma Schneller; and Martell, Michael Joseph, 3,579,579.
- Littell, Ruddy; and Allen, George Rodger, Jr., 3,579,534.
- Miller, Bernard; and Margulies, Howard, 3,579,614.
- Petropoulos, John Christos; and Layman, Ralph Earl, 3,579,610.
- American Electronic Laboratories, Inc.: *See—*
Moore, Michael, 3,579,152.
- American Hoechst Corporation: *See—*
Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,538.
- Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,542.
- American Home Products Corporation: *See—*
Freed, Meier E., 3,579,527.
- Marshall, David J.; and Failli, Amedeo A., 3,579,507.
- American Novawood Corporation, The: *See—*
Ando, Kenichiro; and Barrett, Lawrence G., 3,579,410.
- American Optical Corporation: *See—*
Harris, George J.; and Day, Christopher C., 3,579,138.
- American Standard Inc.: *See—*
Kanyok, Anthony J.; Stoller, Jerry H.; and Keller, William H., 3,579,321.
- Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,578,737.
- AMP de France: *See—*
Dumeige, Daniel, 3,579,179.
- AMP Incorporated: *See—*
Couper, William Dean, 3,579,282.
- Travis, Allen Edwin, 3,579,178.
- Welburn, Norman, 3,579,283.
- Ampex Corporation: *See—*
Steiger, Richard J., 3,579,268.
- Anders, Walter G.; and Kumpf, Henry W., Jr., to Diebold, Incorporated. Signature authorization and verification equipment and system. 3,578,905, Cl. 178-6.
- Anderson, James M.; and Fenton, Marvin J., to Perkin-Elmer Corporation, The. Laser. 3,579,140, Cl. 331-94.5

Anderson, Robert A.; Faulkner, Alfred H.; and Hughes, Edwin L., to General Motors Corporation. Method and apparatus for fault testing a digital computer memory. 3,579,199, Cl. 340-172.5

Anderson, Robert K., to Medtronic, Inc. Filter network and method. 3,579,135, Cl. 330-30.

Anderson, Tage O.: See—
Paine, Thomas O., Administrator of the National Aeronautics and Space Administration with respect to an invention of; Anderson, Tage O.; and Hurd, William J., 3,579,122.

Ando, Kenichiro; and Barrett, Lawrence G., to Tokyo Shibaura Electric Co., Ltd. American Novawood Corporation. The. Oxidation resistant iron-chromium-aluminum alloys Parquet flooring block and method of making same. 3,579,410, Cl. 161-38.

Ando, Satoshi: See—
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.

Andreae, John Hugh: See—
Sears, James K.; Andreae, John Hugh; Gaines, Brian Ronald; and White, Peter, 3,579,191.

Andreev, Vladimir Prokhorovich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Andrianov, Georgy Grigorievich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Angstadt, Howard P., to Sun Oil Company. Organophosphorus compounds and a process for the making thereof. 3,579,576, Cl. 260-543.

Anker-Werke Aktiengesellschaft: See—
Priebs, Horst, 3,578,929.

Anthony, William H.: See—
Pryor, Michael J.; Enoksson, Bertil Petrus; and Anthony, William H., 3,579,392.

Antioch College: See—
Yalman, Richard G., 3,579,533.

Antista, Santo M.; Koptula, Milton M.; and Burggraf, Gerard L., said Antista and said Koptula assors. to Adronics, Inc. Telescoping rod antenna with hinged joint at a medial section. 3,579,241, Cl. 343-702.

Antonini, Albert; Joffré, Philippe; and Vrillon, Claude, to Produits Chimiques Pechiney-Saint-Gobain. Preparation of a saturated chlorinated compounds by oxychlorination of ethylene and vinyl chloride with a fluid bed catalyst. 3,579,597, Cl. 260-658.

Appelgren, James W., to Allis, Louis, Company, The. Digital-to-analog converter system. 3,579,227, Cl. 340-347.

Applequist, Roy A., to International Business Machines Corporation. Magnetic head accessing mechanism utilizing spring bias. 3,579,213, Cl. 340-174.1

Arbeitsstelle für Molekularelektronik: See—
Drescher, Kurt; and Springer, Reinhard, 3,579,071.

West, Russell G.; and Armgarth, Dietrich, 3,579,058.

Archer, Giles A.; and Sternbach, Leo Henryk, to Hoffmann-La Roche, Inc. Process for preparing 1,4-benzodiazepines. 3,579,580, Cl. 260-566.

Argoudelis, Alexander D.; Coats, John H.; Mason, Donald J.; and Sebek, Oldrich K., to Upjohn Company, The. Microbiological demethylation of 7-halo-7-deoxylincomycins. 3,579,426, Cl. 195-80.

Arko, Robert E., to Teletype Corporation. Signal responsive function performing mechanism. 3,578,910, Cl. 178-23.

Armco Steel Corporation: See—
Siebol, George; and Kolec, Robert F., 3,578,762.

Armgarth, Dietrich: See—
West, Russell G.; and Armgarth, Dietrich, 3,579,058.

Armstrong Cork Company: See—
Herweh, John E.; and Poshuk, Algirdas C., 3,579,615.

Arnouat, Fernand R.: See—
Le Goffic, Yves H.; Le Dorh, Maurice F.; and Arnouat, Fernand R., 3,578,915.

Arthur M. Forsythe, Jr., to Simmonds Precision Products, Inc. Attitude error detection fluid gauging system without correction. 3,579,218, Cl. 340-253.

Artz, Klaus: See—
Ramanathan, Visvanathan; and Artz, Klaus, 3,579,497.

Arundale Manufacturers, Inc.: See—
Tausig, Frederick; and Tanner, Robert Gene, 3,578,812.

Arvin Industries, Inc.: See—
Sands, Oran J., 3,578,940.

Asahi Kasei Kogyo Kabushiki Kaisha: See—
Tiegel, Ernest G.; and Tiegel, Ralph G., 3,579,386.

Asako, Tsunehiko: See—
Hiraga, Kentaro; Asako, Tsunehiko; and Miki, Takuichi, 3,579,544.

Ashauer, Karl; and Manthey, Dieter. Spreading spring for speed selection and synchronizing devices for motor vehicles. 3,578,784, Cl. 192-53.

Ashland Oil & Refining Company: See—
Kordzinski, Stanley; and Horn, Milton B., 3,579,490.

Ashley, John Raymond; and Douglas, Colin Grahame. Alarm system. 3,579,221, Cl. 340-277.

Atkins, Thomas M., to Kelsey-Hayes Company. 3,578,819, Cl.

Atlantic Richfield Company: See—
Lincoln, Robert M.; Meyers, Joseph A., III; and Sauer, Richard W., 3,579,457.

Atlas Chemical Industries, Inc.: See—
Lee, John T. M., 3,578,767.

Atto Laboratories, Inc.: See—
Moyer, Elmo E., 3,579,084.

Auffret, René, to Nord-Aviation Societe Nationale de Constructions Aeronautiques. Electric safety-box. 3,579,048, Cl. 317-135.

Aumick, Kenneth Donald: See—
Long, Emile David; and Aumick, Kenneth Donald, 3,578,879.

Austin, Robert R., to Perkin-Elmer Corporation, The. Method of making an interference filter. 3,578,848, Cl. 350-320.

Autin, Donel C.: See—
Sefton, Verner B.; Bailey, Lawrence L.; and Autin, Donel C., 3,579,381.

'Automatic' Sprinkler Corporation: See—
Stevenson, Louis A., Jr., 3,579,220.

Automobiles Peugeot: See—
Guettier, Michel, 3,578,821.

Lombard, Claude Edmond; Maurice, Jean Henri; and Piret, Jean, 3,578,981.

Avery, Julian M. Machine for interconnecting veneer panels Process for the production of magnesium. 3,579,326, Cl. 156-546.

Ayerst, Mc Kenna and Harrison Limited: See—
Deslongchamps, Pierre, 3,579,567.

Ayres, Bruce L.: See—
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.

Ayres, John; and Reich, Irving, to Carter-Wallace, Inc. Heater for aerosol foam-dispensing containers. 3,578,945, Cl. 219-214.

Ayres, Robert F.: See—
Muendel, Carl H.; Howell, George D.; and Ayres, Robert F., 3,579,389.

Babcock & Wilcox Company, The: See—
Blaze, Joseph E., Jr.; and Damon, Ivan R., 3,579,039.

Lapple, Walter C.; and Poole, Edward M., 3,578,798.

Backderf, Robert P.: See—
Chaffard, Françoise; Backderf, Robert P.; and Kanitz, Douglas R., 3,579,038.

Badessa, Rosario S., to Damon Engineering, Inc. Voltage controlled oscillator. 3,579,150, Cl. 332-19.

Badische Anilin- & Soda-Fabrik Aktiengesellschaft: See—
Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.

Baez, Guillermo Federico. Counter-rotary pumps for chemical liquids and particularly dyes and the like. 3,578,873, Cl. 415-68.

Baglai, Vitaly Mikhailovich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Bailey, Denis M., to Sterling Drug Inc. 4-(4-Piperidinyl-methyl or-1-ethyl)amino-7-chloroquinolines. 3,579,520, Cl. 260-288.

Bailey, Lawrence L.: See—
Sefton, Verner B.; Bailey, Lawrence L.; and Autin, Donel C., 3,579,381.

Balamuth, Lewis, to Ultrasonic Systems, Inc. Ultrasonic motor. 3,578,996, Cl. 310-8.7

Barker, Robert H.: See—
Vail, Sidney L.; Pierce, Andrew G., Jr.; Moran, Clifford M.; and Barker, Robert H., 3,579,536.

Barrett, Arthur Lee. Method of steering. 3,578,807, Cl. 299-1.

Barrett, James P.; and Gamble, John G., to Veeder Industries Inc. High speed magnetic counter. 3,578,954, Cl. 235-92.

Barrett, Lawrence G.: See—
Ando, Kenichiro; and Barrett, Lawrence G., 3,579,410.

Barrington, Alfred E., to United States of America, National Aeronautics and Space Administration. Device for measuring light scattering wherein the measuring beam is successively reflected between a pair of parallel reflectors. 3,578,867, Cl. 356-103.

Bartlett, Edwin S.: See—
Bradley, Elihu F.; Bartlett, Edwin S.; Ogden, Horace R.; and Jaffee, Robert I., 3,578,743.

Bartlett, Peter G., to Gulf & Western Industries, mesne. Ceramic memory amplifier. 3,579,208, Cl. 340-173.2

Bartlett, Peter G.; and Meschi, Joseph E., to Gulf & Western Industries, mesne. Load sequencer controller. 3,579,207, Cl. 340-173.

Barton, Sterling C.: See—
Kindl, Fred H.; and Barton, Sterling C., 3,579,006.

Bassier, Friedrich-Karl; and Tekathen, Hans, to Gebr., Eickhoff, Maschinenfabrik und Eisengiesserei mbH. Roller cutter. 3,578,811, Cl. 299-45.

Basu, Rabindra N.; and Dvorak, Alfred, to Nothern Electric Company Limited. Highdow voltage detector. 3,579,050, Cl. 317-148.5

Bates, Homer J.: See—
Schneider, Thomas E., Jr.; Carstens, Marion R.; and Bates, Homer J., 3,578,776.

Bates, James W., to Gulton Industries, Inc. Low frequency sine wave generator circuit. 3,579,081, Cl. 321-9.

Bauman, Albert J.: See—
Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., 3,579,412.

Baumanis, Bruno; and Sebastian, Robert W., to Molex Incorporated. Modular electrical connector assembly. 3,579,170, Cl. 339-17.

Baxter Laboratories, Inc.: See—
Regan, Bernard M., 3,579,595.

Bearfield, Clair C.; and Cole, Raymond, to Tri W-G Inc. Brake motor attachment device. 3,579,066, Cl. 318-372.

Beatrice Foods Co.: See—
Lukas, Anthony J.; and Guillet, Hubert, 3,578,849.

Beatty, John W., to General Electric Company. Gas blast circuit breaker using a generally axial flow main blast. 3,579,258, Cl. 200-148.

Beauvais, Rene G. Wire condensor mat welder and method of forming. 3,578,934, Cl. 219-56.

Beavers, William E., Jr.; and Sturdevant, William H., to Singer-General Precision, Inc. Sound generator. 3,578,912, Cl. 179-1.

Beck, Peter J.: See—
Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., 3,579,325.

Becker, Willy: See—
Sturm, Konrad; Becker, Willy; Timm, Heinz; and Rummel, Karl-Heinz, 3,579,047.

Beckman Instruments, Inc.: See—
Georgi, Heinz W.; and Nather, Roy E., 3,578,960.

Neti, Radhakrishna M.; and Abens, Sandors G., 3,579,384.

Beecher, Norman: See—
Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.

Beerthuis, Roelof Karel: See—
Van Dorp, David Adriaan; Beerthuis, Roelof Karel; Nugteren, Diederik Hendrik; and Vonkeman, Hendrik, 3,579,425.

Bell & Howell Company: See—
Aldridge, Charles A., 3,578,852.

Ross, Bernd, 3,578,864.

Ross, Bernd, 3,579,055.

Bell Telephone Laboratories, Incorporated: See—
Clarke, Patrick W.; and Scuderi, Rudolph, 3,579,091.

Cutler, Cassius C., 3,579,108.

De Coste, John B., 3,579,608.

De Lange, Owen E., 3,579,145.

Edington, John E.; and Warnock, Merville L., 3,579,253.

Giunta, John A., 3,579,198.

Madsen, Eric V., 3,579,090.

Norris, Walter E.; and Shoap, Stephen D., 3,579,117.

O'Neill, John F., 3,578,919.

Walden, Robert H., 3,579,137.

Wang, Han-Chiu, 3,579,153.

Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.

Bender, Warren G.; and Mac Kenzie, Robert C., to Communication Technology, Inc. Telephone wire pair compensator utilizing negative capacitance circuit. 3,578,911, Cl. 178-45.

Bendix Corporation, The: See—
Curran, Peter; and Delistovich, John, 3,579,120.

Straub, Kenneth Luke; and Shear, Wayne Gregory, 3,579,235.

Walker, John H., 3,578,746.

Bendszus, Otto; Niehaus, Clemens; and Patheiger, Manfred, to Farbenfabriken Bayer Aktiengesellschaft. Process for the production of polyester varnish solutions. 3,579,522, Cl. 260-29.1

Benerito, Ruth R.: See—
Bleiweiss, Eugene; Soignet, Donald M.; and Benerito, Ruth R., 3,579,289.

Bentham, Frederick Percy; Sheridan, Phillip Robert; Foreman, Joseph Trevor; and Stimpson, Ian William, to Strand Electric & Engineering Company, Limited, The. Stage lighting control unit. 3,579,030, Cl. 315-291.

Bentley-Harris Manufacturing Company: See—
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.

Berardi, Leah C.: See—
Martinez, Wilda H.; and Berardi, Leah C., 3,579,496.

Berardy, James E.; and Weinstein, David A., to Lobaugh, Rollin J., Inc., mesne. Automatic adding machine. 3,579,266, Cl. 235-61.6

Berger, Jean-Pierre L.: See—
Lucas, Pierre M.; Duquesne, Jean F.; Berger, Jean-Pierre L.; and Courtois, Roger L., 3,578,918.

Berkey/Colortran Mfg., Inc.: See—
Tawil, Joseph N.; Hartz, George R.; and Walsh, Edmund F., 3,578,965.

Bernier, Donald R., to Intercontinental Systems Inc. Editing and revision system. 3,579,193, Cl. 340-172.5

Bernstein, Seymour: See—
Heller, Milton David; Lenhard, Robert Herman; and Bernstein, Seymour, 3,579,508.

Berry, James M., to Teletype Corporation. Method of transferring liquid. 3,579,245, Cl. 346-1.

Bertin, Daniel; and Pierdet, Andre, to Roussel-UCLAF. Novel 11 β -alkoxy gona-1,3,5(10)-trienes. 3,579,545, Cl. 260-397.5

Beyl, Jean Joseph Alfred. Safety abutment of ski binding. 3,578,804, Cl. 280-11.35

Bird Machine Company: See—
Gerwig, Jack N., 3,579,442.

Bissell, Harold R., Jr.: See—
Cavestany, Adrian V.; Smith, Donald R.; and Bissell, Harold R., Jr., 3,578,891.

Bissell Inc.: See—
Hughes, Martin Robert, 3,578,738.

Bitha, Panayota: See—
Hlavka, Joseph J.; Bitha, Panayota; Ross, Adma Schneller; and Martell, Michael Joseph, 3,579,579.

Bjork, Lennart, to Allmanna Svenska Elektriska Aktiebolaget. Protection means for rectifiers upon the occurrence of undesired discharge currents. 3,579,083, Cl. 321-13.

Black and Decker Manufacturing Company, The: See—
Wickham, John L., 3,579,002.

Black, John W., to Pemco Wheel Company. Coating apparatus including plural, sequential conveying means. 3,578,771, Cl. 118-6.

Blackwood, Robert K.; and von Wittenau, Manfred Schach, to Pfizer, Chas., & Co., Inc. Esters of 5-hydroxytetracyclines. 3,579,564, Cl. 260-473.

Blair, Bob C.: See—
Stewart, Dan F.; Blair, Bob C.; Greene, Max E.; and Alexander, Lloyd R., 3,579,618.

Blanc, Roger: See—
Garnier, Marcel; and Blanc, Roger, 3,578,745.

Blaze, Joseph E., Jr.; and Damon, Ivan R., to Babcock & Wilcox Company, The SCM Corporation. Viscous liquid material and process for making same Surge protection circuit. 3,579,039, Cl. 317-22.

Bleiweiss, Eugene; Soignet, Donald M.; and Benerito, Ruth R., to Metaframe Corporation United States of America, Agriculture. Simulated slate and method for making the same Acid salt form of DEAE cellulosic fabric providing. 3,579,289, Cl. 117-54.

Bloom, Martin S., 3,579,300, Cl.

Blume, Alan E., to General Electric Company. Grid directional coupler for oversize circular waveguides. 3,579,148, Cl. 333-10.

Blumer, Armin, to Maschinenfabrik und Giesserei Netstal AG. Valve for a plastifying device. 3,578,741, Cl. 18-30.

Boersma, Rintje, to N.V. 'COO'. Metal clad switch gear for high voltages. 3,578,924, Cl. 200-48.

Boettger, Richard M.: See—
Stockmann, Hans H.; Ray-Chaudhuri, Dilip K.; and Boettger, Richard M., 3,579,549.

Bokor, Michael; and Moulin, Norbert L., to Hughes Aircraft Company. Microminiature printed circuit connector. 3,579,176, Cl. 339-176.

Bolkow Gesellschaft mit beschränkter Haftung: See—
Mautz, Karlheinz, 3,578,877.

Zahn, Paul; and Merges, Veit, 3,579,388.

Bolton, R. B., (Mining Engineers) Limited: See—
Newstead, Gordon, 3,578,810.

Bondarenko, Oleg Petrovich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Bonner, George A.: See—
Dagne, Louis C.; McLean, Howard J.; and Bonner, George A., 3,578,889.

Bookwalter, George N.: See—
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.

Boose, Robert C., to Escoa Fintube Corporation. Tubular electrical heating element with a segmented helical fin. 3,578,952, Cl. 219-540.

Bossi, Hans Jurg; and Faust, Werner, to Aktiengesellschaft Brown, Boveri & Cie. Arrangement for dividing and limiting the voltage for a converter having a plurality of thyristor valves connected in series. 3,579,082, Cl. 321-11.

Bottenbruch, Ludwig: See—
Schnell, Hermann; Darsow, Gerhard; and Bottenbruch, Ludwig, 3,579,591.

Boudouris, Angelo, to Eprad Incorporated. Projector frame control. 3,578,855, Cl. 352-163.

Boudreau, Jean Claude, to Du Pont de Nemours, E. I., and Company. Desludging tel with oxygenated water. 3,579,554, Cl. 260-437.

Bouniot, Albert, to Melle-Bezons. Process for oxidizing lower aliphatic aldehydes. 3,579,575, Cl. 260-530.

Bradley, Elihu F.; Bartlett, Edwin S.; Ogden, Horace R.; and Jaffee, Robert I., to United Aircraft Corporation, mesne. Aluminum coated columbium base alloys. 3,578,743, Cl. 29-194.

Bradley, William E., Jr., to Tesco Chemicals, Inc. Sewage treatment system. 3,579,440, Cl. 210-18.

Bragg, Lorel J.: See—
Redding, Billy J.; Steadman, John T.; and Bragg, Lorel J., 3,578,740.

Brandt Chem. Co., Inc.: See—
Kanyok, Anthony J.; Stoller, Jerry H.; and Keller, William H., 3,579,321.

- Brasket, Denis R. Method and apparatus for conducting a signal. 3,579,215, Cl. 340-198.
- Braun Aktiengesellschaft: *See—*
Cyrener, Gerd; and Fahrenholz, Joachim, 3,579,256.
- Breil, Heinz: *See—*
Ziegler, Karl; and Breil, Heinz, 3,579,493.
- Breitbord, Jacob Louis; and MacDougall, Richard Donald, to Itek Corporation. Apparatus for continuous dodging printing. 3,578,860, Cl. 355-80.
- Brickett, Alan E.; and Windahl, Everett R., to Northwest Engineering Corporation. Control system. 3,578,787, Cl. 212-59.
- Briggs, Peter James; and Hurlock, Ronald James, to Imperial Chemical Industries Limited. Nickel ketoxime chelates. 3,579,556, Cl. 260-439.
- Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, to Gevaert-Agfa N.V. Dow Chemical Company, The. Packaging film comprising polyolefin outer layers Photochemical recording process and plural inner gas barrier layers. 3,579,416, Cl. 161-254.
- Brinckman, Eric Maria; Vanhalst, Johan Eugene; Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, to Improved Machinery Inc. Gevaert-Agfa N.V. Continuous digester wood chip level control Photochemical recording method by means of hexacyanoferrate (III). 3,579,417, Cl. 96-49.
- Bristol-Myers Company: *See—*
McGregor, Donald Neil, 3,579,501.
McGregor, Donald Neil, 3,579,514.
- British Lighting Industries Limited: *See—*
Ranby, Peter Whitten; and Palowkar, David Richard, 3,579,018.
- Brigman, Glenn B., to Goodyear Tire & Rubber Company, The. Method for curing tires and the like. 3,579,626, Cl. 264-297.
- Brockmann, Rolf: *See—*
Rutzen, Horst; and Brockmann, Rolf, 3,579,584.
- Brokke, Mervin E.: *See—*
Tilles, Harry; and Brokke, Mervin E., 3,579,525.
- Brooker, Leslie G. S.; Heseltine, Donald W.; and Daniel, Daniel S., to Eastman Kodak Company. Silver halide emulsions with dyes containing a pyrylium nucleus joined to a pyrazole nucleus. 3,579,346, Cl. 96-106.
- Brooks, Robert E., to TRW Inc. Double-diffuser holographic system. 3,578,837, Cl. 350-3.5
- Brooks, Robert E.; Heflinger, Lee O.; and Wuerker, Ralph F., to TRW Inc. Holographic focusing diffraction gratings for spectroscopes and method of making same. 3,578,845, Cl. 350-162.
- Brooks, Thomas W.; Schuman, Paul D.; and Padgett, Calvin D., to Calgon Corporation. Water and oil repellents. 3,579,557, Cl. 260-448.2
- Brotherton, Thomas K.; and Lynn, John W., to Union Carbide Corporation. Polymers of olefinically unsaturated diisocyanates (III). 3,579,482, Cl. 260-77.5
- Brown, Boveri & Cie A.G.: *See—*
Gross, Franz; and Krapf, Rudolf, 3,578,991.
- Brown, Clinton E., to Hydronautics, Incorporated. Blood purification by dual filtration. 3,579,441, Cl. 210-23.
- Brown, Edgar D., Jr., to General Electric Company. Organopolysiloxanes having hydroxyaryl substituents. 3,579,467, Cl. 252-46.3
- Brown, Garland Richard. Novel antacid compositions and methods for their administration. 3,579,634, Cl. 424-154.
- Brown, Jack T.: *See—*
Crane, Margaret M.; Feduska, William; and Brown, Jack T., 3,579,385.
- Brown, Kenneth H.; and Fitting, Robert C., to United States of America, National Aeronautics and Space Administration. Phase modulator. 3,579,147, Cl. 332-29.
- Brown, Kevan; and Cavalia, John F., to Wyeth, John, & Brother Limited. Heterocyclic compounds. 3,579,529, Cl. 260-302.
- Brown, Martin Granger; Van Berkel, Franciscus C.A.A.; and Luques, Stanley F., to Imperial Chemical Industries Limited. Continuous process for the production of calcium sulphate hemi-hydrate from gypsum Process for producing conductors insulated with polyethylene terephthalate. 3,579,379, Cl. 117-232.
- Brunell, Albert D.: *See—*
Corbett, William H.; Brunell, Albert D.; and Koharchik, George M., 3,579,263.
- Brungs, Charles A.: *See—*
Sabatelli, Philip M.; and Brungs, Charles A., 3,579,455.
- Bryan, Coleman J.: *See—*
Evans, Fred D.; Springfield, Carlos L.; and Bryan, Coleman J., 3,578,756.
- Buchanan, Edward E., Jr., to Electronic Control Corporation. Proportional power control circuit. 3,579,096, Cl. 323-22.
- Bucourt, Robert: *See—*
Nomine, Gerard; Bucourt, Robert; and Pierdet, Andre, 3,579,504.
- Bugaj, Leonard J., to Ford Motor Company. Welding electrode assembly. 3,578,942, Cl. 219-119.
- Buie, James Lang: *See—*
Short, Oliver A.; and Buie, James Lang, 3,579,391.
- Bullard, E. D., Company: *See—*
Raschke, Herbert A., 3,579,233.
- Bullard, Edward M., to Mobil Oil Corporation. Dual solvent separation of 4-hydroxybenzothioephene from 4-oxo-4,5,6,7-tetrahydrobenzothioephene. 3,579,539, Cl. 260-330.5
- Bunker Hill Company, The: *See—*
Jasberg, Peter M., 3,579,431.
- Bunker-Ramo Corporation, The: *See—*
Gregg, Roland S., Jr.; Danberg, Arnold S.; and Larson, Kenneth N., 3,579,196.
- Scarborough, Alfred D., 3,579,019.
- Tuchto, Jeff, 3,579,155.
- Bureau of Engraving, Inc.: *See—*
Luden, Alfred J., 3,579,097.
- Burggraf, Gerard L.: *See—*
Antista, Santo M.; Koptula, Milton M.; and Burggraf, Gerard L., 3,579,241.
- Burnier, Pierre; and Moreau, Jack, to Societe Generale de Constructions Electriques et Mecaniques (ALSTHOM). System for detection of transition between superconductive and resistant state in superconductive coils. 3,579,035, Cl. 317-13.
- Burns, Patricia Gertrude: *See—*
Chilton, Henry Thomas Joseph; and Burns, Patricia Gertrude, 3,579,462.
- Burroughs Corporation: *See—*
Johnson, Robert R.; and Dunham, Richard L., 3,579,186.
Malmer, Michael M., Jr., 3,579,203.
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.
- Burroughs Wellcome & Co. (U.S.A.) Inc.: *See—*
Thomson, Robert Orrock, 3,579,633.
- Busch, Edwin. Plural unit projection system. 3,578,857, Cl. 353-96.
- Buttenhoff, Edward W.; and Hill, Lyman L., Jr., to Honeywell Inc. Indicating condition controller having a face including a rotatable scale plate cooperating with a wide angle 250° meter. 3,579,107, Cl. 324-157.
- Bynum, Bobby G.; and Talley, Drayton H., to United States of America, National Aeronautics and Space Administration. Response analyzer for sensors. 3,578,755, Cl. 73-1.
- Caires, Eugene J., to Vitramon, Incorporated. Lead terminal. 3,578,895, Cl. 174-74.
- Calgon Corporation: *See—*
Brooks, Thomas W.; Schuman, Paul D.; and Padgett, Calvin D., 3,579,557.
Schaper, Raymond J.; and Hoover, Merwin Frederick, 3,579,613.
- California Institute of Technology: *See—*
Kohler, Bryan E.; and Dubin, Alan S., 3,578,866.
- Callen, Joseph E.; Haxby, Robert D.; and Fagin, William T., to Procter & Gamble Company, The. Composition of matter. 3,579,458, Cl. 252-152.
- Cambre, Cushman M., to Procter & Gamble Company, The. Liquid detergent composition. 3,579,456, Cl. 252-137.
- Cameron, Douglas R. G., to Pylon Electronic Development Company. Regulated static DC to DC converter including start-up means. 3,579,077, Cl. 321-2.
- Campbell, Darrel: *See—*
Nicholson, Denzel Allan; and Campbell, Darrel, 3,579,570.
- Canadian General Electric Company Limited: *See—*
Eastcott, Peter De Hertel, 3,578,817.
Eastcott, Peter De Hertel, 3,578,818.
- Canadian Patents and Development Limited: *See—*
Kusters, Norbert L.; and Moore, William J. M., 3,579,101.
- Cann, Everett Douglas: *See—*
Wonilowicz, Edmund; Cann, Everett Douglas; and Machnacz, Henry F., 3,579,296.
- Capol, Roman J.: *See—*
Schuessler, John C.; and Capol, Roman J., 3,578,928.
- Carlsmith, Lawrence Allan: *See—*
Brinckman, Eric Maria; Vanhalst, Johan Eugene; Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, 3,579,417.
- Carmody, Doyle V.; and Welch, John S., to International Telephone and Telegraph Corporation. Calling subscriber party line identification circuit. 3,579,254, Cl. 179-17.
- Carrega, Marc E., to Produits Chimiques Pechiney-Saint-Gobain. Method for preparing polymers and copolymers of vinyl chloride by bulk polymerization at low temperature and products thereof. 3,579,491, Cl. 260-85.5
- Carrier Corporation: *See—*
Cavestany, Adrian V.; Smith, Donald R.; and Bissell, Harold R., Jr., 3,578,891.
- Carstens, Marion R.: *See—*
Schneider, Thomas E., Jr.; Carstens, Marion R.; and Bates, Homer J., 3,578,776.
- Carter-Wallace, Inc.: *See—*
Ayres, John; and Reich, Irving, 3,578,945.
- Cartmell, James V.: *See—*
Churchill, Donald; and Cartmell, James V., 3,578,844.
- Casey, Thomas J.; and Loeffler, George F., to Thomas Machinery Corporation. Method and apparatus for detecting and indicating malfunction of a tableting machine. 3,579,217, Cl. 340-253.
- Casey, William E.: *See—*
Murphy, Frank T.; Clark, Norman R.; and Casey, William E., 3,578,802.
- Cassanelli, Robert: *See—*
Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, 3,578,858.
- Cassella Farbwerke Mainkur Aktiengesellschaft: *See—*
Rehmar, Solomon J., 3,579,366.

- Castellion, George Augustus, to American Cyanamid Company. Control of light reflected from a mirror. 3,578,843, Cl. 350-160.
- Casterlin, James H., to Quantametric Devices, Inc. Digital transducer and memory system therefor. 3,579,230, Cl. 340-347.
- Cattermole, Kenneth William, to International Standard Electric Corporation. Analog-to-digital converter. 3,579,228, Cl. 340-347.
- Cauville, Roland: *See—*
Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilberte, 3,579,401.
- C.A.V. Limited: *See—*
Mowbray, Dorian Farrar; and Kemp, Kenneth Albert Walters, 3,578,881.
- Cavalia, John F.: *See—*
Brown, Kevan; and Cavalia, John F., 3,579,529.
- Cavestany, Adrian V.; Smith, Donald R.; and Bissell, Harold R., Jr., to Carrier Corporation. Crossover lighter structure for gas burners. 3,578,891, Cl. 431-191.
- Cerwenka, Peter: *See—*
Kleinbagger, Otmar; Samejima, Hiroto; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.
- Chalpin, William: *See—*
Wentzheimer, William W.; Reynolds, Ronald W.; and Chalpin, William, 3,579,437.
- Champion Spark Plug Company: *See—*
Corbett, William H.; Brunell, Albert D.; and Koharchik, George M., 3,579,263.
- Peeps, Donald J., 3,579,262.
- Chandler Evans Inc.: *See—*
Cygnor, John E., 3,578,880.
- Chang, Catherine Teh-Lin; and Walker, Peter, to Du Pont de Nemours, E. I., and Company. Treatment of fluffed pulp fibers with gaseous chlorine Photopolymerizable dispersions and elements containing nonmigratory photoreducible dyes. 3,579,339, Cl. 162-66.
- Chang, Hoy Ying: *See—*
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.
- Chang, Yun G., to Reichhold Chemicals, Inc. Cyclic diperoxides. 3,579,541, Cl. 260-338.
- Chao, Junn-Ling, to Shell Oil Company. Method of facilitating the resuspension of the solid phase of a slurry in a shut-down pipeline. 3,578,816, Cl. 302-66.
- Chapman, Thomas G., to General Electric Company. Electrical capacitor with thermal fuse. 3,579,062, Cl. 317-247.
- Chapman, Thomas G.; Backderf, Robert P.; and Kanitz, Douglas R., to Societe d'Assistance Technique pour Produits Nestle S.A. Square D Company. Lyophilising a carbon dioxide solution Electrical fault protection system. 3,579,038, Cl. 317-18.
- Chemical Separations Corporation: *See—*
Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilberte, 3,579,401.
- Chen, Wu, to Sperry Rand Corporation. Multiple-stage optical information processing system. 3,578,846, Cl. 350-162.
- Cheney, Lawrence W., to Copeland Refrigeration Corporation. Unloader for multicylinder refrigeration compressors. 3,578,883, Cl. 417-286.
- Cheng, Dah Yu: *See—*
Paine, T. O., acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; and Cheng, Dah Yu, 3,579,028.
- Chidester, Gerald E.: *See—*
Shultz, Forrest G.; Chidester, Gerald E.; and Collet, Fernand E., 3,579,293.
- Chilton, Henry Thomas Joseph; and Burns, Patricia Gertrude, to Monsanto Chemicals Limited. Treatment of silica sols. 3,579,462, Cl. 252-313.
- Christopher, Harold A., to General Electric Company. System for handling specimens and other substances in medicine and physical sciences Sealed container for elemental sodium. 3,579,382, Cl. 136-20.
- Chrysler Corporation: *See—*
Smith, Robert H.; Payne, Robert K.; and Haw, Thomas, III, 3,579,617.
- Churchill, Donald; and Cartmell, James V., to National Cash Register Company, The. Radiation sensitive display device containing encapsulated cholesteric liquid crystals. 3,578,844, Cl. 350-160.
- Ciba Limited: *See—*
Moergeli, Eduard, 3,579,518.
Nachbur, Hermann; Stark, Bernard Peter; and Maeder, Arthur, 3,579,532.
Ramanathan, Visvanathan; and Artz, Klaus, 3,579,497.
Weber, Kurt; Liechti, Peter; Meyer, Rudolf; and Siegrist, Adolf Emil, 3,579,511.
- Cieciuch, Ronald F. W.; and Simon, Myron S., to Polaroid Corporation. Dye developers which are non-reversibly spectrally shifted by alkaline hydrolysis in color diffusion transfer processes and elements. 3,579,334, Cl. 96-29.
- Cities Service Research and Development Company: *See—*
Mounce, William R., 3,579,436.
- Clare, C. P., & Company: *See—*
Kutyla, John, 3,579,158.
- Clark, George Archer: *See—*
Rath, Paul S.; Dyott, Richard Burnaby; and Clark, George Archer, 3,579,316.
- Clark, Howard S.: *See—*
Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,578,737.
- Clark, Marvin A. Solderless connector assembly. 3,579,172, Cl. 339-97.
- Clark, Norman R.: *See—*
Murphy, Frank T.; Clark, Norman R.; and Casey, William E., 3,578,802.
- Clark, Robert John, to RCA Corporation. Light probe circuit for persistent screen display system. 3,579,225, Cl. 340-324.
- Clarke, Patrick W.; and Scuderi, Rudolph, to Bell Telephone Laboratories, Incorporated. Switching regulator with random noise generator. 3,579,091, Cl. 323-22.
- Clarkson, Richard, to Imperial Chemical Industries Limited. Amino alkyl esters of 5 α -pregn-20-ene-21- carboxylic acids and the 3-glycosides thereof. 3,579,499, Cl. 260-210.5
- Clauson-Kaas, Niels: *See—*
Denss, Rolf; Clauson-Kaas, Niels; and Ostermayer, Franz, 3,579,535.
- Clymer, Frank, to Lloyds (Burton) Limited. Links for the endless tracks of track-laying vehicles. 3,578,823, Cl. 305-42.
- Coats, John H.: *See—*
Argoudelis, Alexander D.; Coats, John H.; Mason, Donald J.; and Sebek, Oldrich K., 3,579,426.
- Cobb, Clifton A.: *See—*
Mason, Anthony; and Cobb, Clifton A., 3,579,284.
- Cohen, Murray F.: *See—*
United States of America, National Aeronautics and Space Administration, Administrator, 3,579,146.
- Cohu Electronics, Inc.: *See—*
Tompkins, William R., 3,578,908.
- Cole, Raymond: *See—*
Bearfield, Clair C.; and Cole, Raymond, 3,579,066.
- Colello, William L., to National Cash Register Company, The. Thermal print head wafer and method of making the same. 3,578,946, Cl. 219-216.
- Colgate-Palmolive Company: *See—*
Rubinfeld, Joseph; and Levinsky, Henry Leon, 3,579,537.
- Collet, Fernand E.: *See—*
Shultz, Forrest G.; Chidester, Gerald E.; and Collet, Fernand E., 3,579,293.
- Collier, Everett J., to Procter & Gamble Company, The. Detergent compositions containing an oxidizing bleach and proteolytic enzyme derived from thermophilic streptomyces rectus variety proteolyticus. 3,579,454, Cl. 252-97.
- Collins Radio Company: *See—*
Deen, Glen W., 3,579,154.
- Colombo, Winifred M.: *See—*
Dootson, Norman L., 3,578,736.
- Cometa S.A.R.L.: *See—*
Laurent, Bernard, 3,578,978.
- Commissariat a l'Energie Atomique: *See—*
Lukas, Anthony J.; and Guillet, Hubert, 3,578,849.
Weber, Jacques Robert, 3,578,941.
- Communication Technology, Inc.: *See—*
Bender, Warren G.; and Mac Kenzie, Robert C., 3,578,911.
- Comstock & Wescott, Inc.: *See—*
Decker, John A., Jr.; and Harwit, Martin O., 3,578,980.
- Conduco A.G.: *See—*
Mehner, Gottfried, 3,579,621.
- Continental Can Company, Inc.: *See—*
Gerber, Howard L., 3,578,936.
- Contraves AG: *See—*
Spreitzer, Helmuth, 3,579,257.
- Controls Company of America: *See—*
Moratz, Clyde C., 3,578,950.
Obermann, George, 3,578,926.
- Conway, Howard F.: *See—*
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.
- Cook, Harold D., to Teletype Corporation. Dynamic shift register. 3,579,273, Cl. 307-221.
- Copeland Refrigeration Corporation: *See—*
Cheney, Lawrence W., 3,578,883.
- Corbett, William H.; Brunell, Albert D.; and Koharchik, George M., to Champion Spark Plug Company, mesne. Electric steam vaporizer. 3,579,263, Cl. 219-295.
- Corpew, Charles R., to Stromberg Datagraphics Inc. Shaped beam tube having fine mesh closely adjacent substantially rectangular trim aperture. 3,579,014, Cl. 313-86.
- Cosan Chemical Corporation: *See—*
Leebrick, John R., 3,579,553.
- Couper, William Dean, to AMP Incorporated. Transmission line connector with means including cam surfaces for altering connector element dimensions to compensate for junction gaps, and method. 3,579,282, Cl. 333-97.
- Courtois, Roger L.: *See—*
Lucas, Pierre M.; Duquesne, Jean F.; Berger, Jean-Pierre L.; and Courtois, Roger L., 3,578,918.
- Courts, Albert, to Lever Brothers Company. Method of preparing an edible tubular collagen casing. 3,579,358, Cl. 99-176.
- Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., to Monsanto Company. Production of carboxylic acids. 3,579,551, Cl. 260-413.

- Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., to Monsanto Company. Production of carboxylic acids. 3,579,552, Cl. 260-413.
- Crane, Margaret M.; Feduska, William; and Brown, Jack T., to Organon, Inc., mesne Westinghouse Electric Corporation. Diagnostic test device Method of impregnating metallic fiber battery electrodes. 3,579,385, Cl. 136-75.
- Cras, Ake Karl Gustaf, to Skandal, Karl Arvid. Discharge device for the bottom fraction at a vortex type separator. 3,578,786, Cl. 210-512.
- Crawford, John H., to Leading Plywood. 3,579,405, Cl. 75-51.
- Crocker, Weyman S.; White, Philip H.; and McDonald, William T., to Pneumo Dynamics Corporation. Machine tool servo system including feed-rate control. 3,579,070, Cl. 318-571.
- Cronin, Donald L.; Farber, Bertrand F.; and Nockey, Charles R., to TRW Inc. Constant current high voltage power supply. 3,579,078, Cl. 321-2.
- Cronin, John C., to Westinghouse Electric Corporation. Liquid filled transformer with foamed insulation. 3,579,163, Cl. 336-94.
- Cruse, Carl M., to Monsanto Company. Thermal cracking. 3,579,438, Cl. 208-130.
- Csaszar, Erno: See—
Mandzu, Jozsef; and Csaszar, Erno, 3,579,265.
- CTS Corporation: See—
Sawyer, Roderick V., 3,579,166.
- Cullen, William F.; and Ringeman, Othmar E., to General Electric Company. Electron discharge device with electrode spacer having integral electron vibration dampening member thereon. 3,579,020, Cl. 313-269.
- Cunningham, John J., Jr.: See—
Allan, Barry D.; and Cunningham, John J., Jr., 3,579,314.
- Cunningham, Vernon. Method and apparatus for forming subterranean structures. 3,578,809, Cl. 299-33.
- Cunninham, Robert G., 3,579,330, Cl.
- Curran, Peter; and Delistovich, John, to Bendix Corporation, The. Self-testing logic gate. 3,579,120, Cl. 328-92.
- Cutler, Cassius C., to Bell Telephone Laboratories, Incorporated. Differential coder and decoder. 3,579,108, Cl. 325-38.
- Cygnor, John E., to Chandler Evans Inc. Diaphragm operated priming device for centrifugal impeller pump. 3,578,880, Cl. 417-203.
- Cyrenier, Gerd; and Fahrenholz, Joachim, to Braun Aktiengesellschaft. Combination subcarrier filter and bias trap for magnetic tape recorders. 3,579,256, Cl. 179-100-2.
- Dagne, Louis C.; McLean, Howard J.; and Bonner, George A., to United Aircraft Corporation. Rotary engine vane sealing means. 3,578,889, Cl. 418-147.
- Dahlgren, Donald A., to Upjohn Company, The. Vertical column electrophoresis apparatus. 3,579,433, Cl. 204-299.
- Daly, Norman Richard; and Powell, Royal Edward, to United Kingdom Atomic Energy Authority. Energy selective ion beam intensity measuring apparatus and method utilizing a scintillator to detect electrons generated by the beam. 3,579,270, Cl. 250-41-9.
- Damon Engineering, Inc.: See—
Badessa, Rosario S., 3,579,150.
- Damon, Ivan R.: See—
Blaze, Joseph E., Jr.; and Damon, Ivan R., 3,579,039.
- Danberg, Arnold S.: See—
Gregg, Roland S., Jr.; Danberg, Arnold S.; and Larson, Kenneth N., 3,579,196.
- Danfoss A/S: See—
Jensen, Arne; and Petersen, Tom Kastrup, 3,579,274.
- Daniel, Daniel S.: See—
Brooker, Leslie G. S.; Heseltine, Donald W.; and Daniel, Daniel S., 3,579,346.
- Darsow, Gerhard: See—
Schnell, Hermann; Darsow, Gerhard; and Bottenbruch, Ludwig, 3,579,591.
- Datel Corporation: See—
Larsen, Raymond B., 3,579,211.
- Davies, Robert L., to General Electric Company. Thyristor with improved current and voltage handling characteristics. 3,579,060, Cl. 317-235.
- Davis, David S., to Witco Chemical Corporation. Method of preparing diaryl sulfones. 3,579,590, Cl. 260-607.
- Davis, Peter Grant, to Molins Machine Company, Limited, The. Devices for securing or positioning workpieces for machining operations. 3,578,799, Cl. 269-51.
- Davis, Robert H.; and Harris, Jerry S., to International Business Machines Corporation. Data processing system. 3,579,200, Cl. 340-172-5.
- Day, Christopher C.: See—
Harris, George J.; and Day, Christopher C., 3,579,138.
- Deane, Clifford T., to Stampco, Inc. Automatic drum forming machine. 3,578,935, Cl. 219-64.
- DEC International Inc.: See—
Peters, Norman J., 3,578,780.
- Decker, John A., Jr.; and Harwit, Martin O., to Comstock & Wescott, Inc. Spectral analysis using modes having different combinations of transmitting and non-transmitting portions. 3,578,980, Cl. 250-237.
- Decor Dimensionals, Inc.: See—
Vess, Samuel P., 3,579,477.
- De Coste, John B., to Bell Telephone Laboratories, Incorporated. Wire coating of brominated diglycidyl ether of bisphenol A and polyvinyl chloride. 3,579,608, Cl. 260-837.
- Deen, Glen W., to Collins Radio Company. VHF filter having absorptive tuned section to eliminate narrow spurious pass band. 3,579,154, Cl. 333-76.
- De Gain, William J., to Koppy Tool Corporation. Corrugated tubing. 3,578,777, Cl. 138-121.
- De Jong & De Vlieger Machinehandel N.V.: See—
van Hazendonk, Johannes Franciscus, 3,578,770.
- De Lange, Owen E., to Bell Telephone Laboratories, Incorporated. Modulator stabilization circuits. 3,579,145, Cl. 332-7-51.
- Delavan Manufacturing Co.: See—
Janssen, Leonard F., 3,578,882.
- Delistovich, John: See—
Curran, Peter; and Delistovich, John, 3,579,120.
- Della, Porta, Paolo; and Rabusin, Elio, to S.A.E.S. Getters S.p.A. Metal vapor generating compositions. 3,579,459, Cl. 252-181-4.
- Della Porta, Paolo; and Rabusin, Elio, to S.A.E.S. Getters S.p.A. Generation of alkali metals. 3,578,834, Cl. 316-16.
- Delmon, Bernard, to Institut Francais du Petrole des Carburants et Lubrifiants. Process for manufacturing a catalyst, resulting catalyst and process for manufacture of benzoic aldehyde from toluene in the presence of said. 3,579,589, Cl. 260-599.
- Deming, Andrew F., to Alliance Manufacturing Company. Selective radio receiver system. 3,579,240, Cl. 343-228.
- Demole, Edouard P., to Firmenich & Cie. Oxygenated derivatives of acyclic olefins. 3,579,550, Cl. 260-413.
- Dempsey, Richard C.; and Lind, Francis E., to International Telephone and Telegraph Corporation. Collapsible antenna employing flexible tape radiators. 3,579,244, Cl. 243-797.
- Dennilaule, Rene Jean: See—
Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.
- Denss, Rolf; Clauson-Kaas, Niels; and Ostermayer, Franz. Substituted phenylacetic acids and esters thereof. 3,579,535, Cl. 260-326-3.
- Deslongchamps, Pierre, to Ayerst, Mc Kenna and Harrison Limited. *Tricyclo[4.4.0.0.3]Decan-1-amine* and process for preparing same. 3,579,567, Cl. 260-488.
- De Smidt, Woodrow A.; and Kuhn, Edward H., to Allen-Bradley Company. Corrosion resistant enclosure. 3,578,933, Cl. 200-168.
- Deutsche Akademie der Wissenschaften: See—
Steenbeck, Max; and Krause, Fritz, 3,578,999.
- Deutsche Gold- und Silber-Scheideanstalt vormals Roessler: See—
Gilde, Dieter; and Koberstein, Edgar, 3,579,573.
- Deutsche Gold- und Silber-Scheideanstalt vormals Roessler: See—
Weigert, Wolfgang, 3,579,562.
- De Vos, Hendrik A.J.; and Haraden, Thomas, to Sylvania Electric Products, Inc. Lighting fixture. 3,578,963, Cl. 240-3.
- Dewar, Robert Alfred; Maier, Volker Elmar; and Ingram, Margaret Anthea, to Imperial Chemical Industries of Australia and New Zealand Limited. Process for the resolution of racemic tetramisole. 3,579,530, Cl. 260-306-7.
- De Werth, Douglas W.; and Weber, Earl J., to Dover Corporation. Resistance-sensing system with fail-safe circuit. 3,578,987, Cl. 307-252.
- Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., to Reynolds Metals Company. Feature counter with feature discrimination and/or masking. 3,578,904, Cl. 178-6.
- Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., to Reynolds Metals Company. Feature counter having between limits amplitude and/or width discrimination. 3,579,249, Cl. 178-6.
- De Winter, Max Salomon; and Ribbers, Jan Evert, to Organon Inc. 1,3,5(10)-2-(or 4)-formyl-3-hydroxy-oestratriene compounds. 3,579,543, Cl. 260-397-4.
- Diagnostic Data, Inc.: See—
Huber, Wolfgang, 3,579,495.
- Dickason, Richard T.; and Richardson, John A., to Ford Motor Company. Windshield antenna system. 3,579,243, Cl. 343-713.
- Dickerson, Richard T., to Dow Chemical Company, The. Catalyst for the interconversion of propyne and propadiene. 3,579,600, Cl. 260-678.
- Dickinson, Clarence R., to Allen-Bradley Company. Variable resistor for dual operation. 3,579,169, Cl. 338-170.
- Diebold, Incorporated: See—
Anders, Walter G.; and Kumpf, Henry W., Jr., 3,578,905.
- Diehl Firma: See—
Sturm, Konrad; Becker, Willy; Timm, Heinz; and Rummel, Karl-Heinz, 3,579,047.
- Dijkhuizen, Willem; Kliphuis, Harmannus; and Lolkema, Jan, to Scholten Research N.V. Cell modifying agents for polyurethane foams. 3,579,471, Cl. 260-2-5.
- Dilling, Wendell L., to Dow Chemical Company, The. 6,6,7,7-Tetrachlorobicyclo(3.2.0) heptan-2-one. 3,579,588, Cl. 260-586.
- Di Nepi, Paolo. Foldable bicycle-type exercising device. 3,578,800, Cl. 272-73.
- Diolot, Lucien, to Societe Nouvelle Spidem. Variable pressure embossing machine. 3,578,766, Cl. 101-23.
- Dirks, Brinton Marlo: See—
Nakel, Gunther M.; and Dirks, Brinton Marlo, 3,579,353.
- Distillers Company Limited, The: See—
van der Meer, Wilhelmus Teuis, 3,579,574.
- Doda, Robert J.: See—
Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,972.
- Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,973.

- Dominion Engineering Works, Limited: See—
Sproule, Robert Stanley; Kanger, Feodor; and Seybold, Hugh Laurie, 3,578,874.
- Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., to American Atomics Corporation. Extended self-luminous light sources employing fiber optics. 3,578,972, Cl. 250-77.
- Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., to American Atomics Corporation. Self-luminous light sources employing fiber optics. 3,578,973, Cl. 250-71.
- Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silviu A., to Inmont Corporation Union Carbide Corporation. Barrier structure for packaging purposes Process and composition for separation of oxygen from air using strontium oxide-peroxide as the. 3,579,292, Cl. 117-76.
- Dootson, Norman L., 1/3 to Colombo, Winifred M. Hat and sweatband insert therefor. 3,578,736, Cl. 2-181.
- D'Ottavio, Eugene D.: See—
Grunwald, John J.; and D'Ottavio, Eugene D., 3,579,365.
- Douglas, Colin Grahame: See—
Ashley, John Raymond; and Douglas, Colin Grahame, 3,579,221.
- Dousset, Monick: See—
Rey, Louis Rene; and Dousset, Monick, 3,579,360.
- Dover Corporation: See—
De Werth, Douglas W.; and Weber, Earl J., 3,578,987.
- Dow Chemical Company: See—
Rieke, James K.; and Justin, Frank H., 3,579,476.
- Dow Chemical Company, The: See—
Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, 3,579,416.
- Dickerson, Richard T., 3,579,600.
- Dilling, Wendell L., 3,579,588.
- Jones, Giffin D.; and Tefertiller, Nancy B., 3,579,488.
- Levine, Leonard; and Mc Fadden, Russell T., 3,579,592.
- Mullin, Charles R.; and Wymore, C. Elmer, 3,579,596.
- Rubens, Louis C.; and Walsh, William B., 3,579,472.
- Sciambi, Louis J., 3,579,451.
- Walles, Wilhelm E., 3,579,515.
- Dowhan, Wesley P.; Aas, Helge; and Nordheim, Rolf, to Spigerverk, Christiania. Ornamental device for attachment to wire spoked wheels Process for the production of ferro-vanadium directly from slag obtained from vanadium-containing pig iron. 3,579,328, Cl. 161-7.
- Dreier, Clarence R., Jr.: See—
Stewart, Aubrey P., Jr.; Dreier, Clarence R., Jr.; and Gregory, Jim C., 3,579,631.
- Drescher, Kurt; and Springer, Reinhard, to Arbeitsstelle fur Molekularelektronik. Electronic circuit arrangement for performing work steps in the production or testing of semi-conductor means. 3,579,071, Cl. 318-603.
- Dresser Industries, Inc.: See—
Mougne, Marcel L., 3,579,098.
- Drinkard, William Charles, Jr.; and Taylor, Brian W., to Du Pont de Nemours, E. I., and Company. Isomerization of nitriles. 3,579,560, Cl. 260-465-9.
- Drown, John L.; and Patel, Nager J., to Westinghouse Electric Corporation. Drawout type switchgear. 3,578,925, Cl. 200-50.
- Dubin, Alan S.: See—
Kohler, Bryan E.; and Dubin, Alan S., 3,578,866.
- Dubinsky, Rudolf Solomonovich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruk, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.
- Ducellier & Cie: See—
Habert, Roger, 3,578,922.
- Dudko, Daniil Andreevich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruk, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.
- Dumeige, Daniel, to AMP de France. Fuse connectors. 3,579,179, Cl. 339-258.
- Dunham, Richard L.: See—
Johnson, Robert R.; and Dunham, Richard L., 3,579,186.
- Dunn, Howard E.; and Mathis, Ronald D., to Phillips Petroleum Company. Polyolefin stabilization. 3,579,478, Cl. 260-45-75.
- Dunworth, William Paul, to Du Pont de Nemours, E. I., and Company. Azo, 3-substituted pyrazolone dyes. 3,579,498, Cl. 260-158.
- Du Pont de Nemours, E. I., and Company: See—
Boudreau, Jean Claude, 3,579,554.
- Chang, Catherine Teh-Lin; and Walker, Peter, 3,579,339.
- Drinkard, William Charles, Jr.; and Taylor, Brian W., 3,579,560.
- Dunworth, William Paul, 3,579,498.
- George, Henry H., 3,578,739.
- Jelinek, Arthur G., 3,579,500.
- Muendel, Carl H.; Howell, George D.; and Ayres, Robert F., 3,579,389.
- Pangonis, William J., 3,579,555.
- Pomerantz, Marc Paul, 3,579,271.
- Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.
- Ro, Rolland S., 3,579,474.
- Short, Oliver A.; and Buie, James Lang, 3,579,391.
- Strilko, Peter S., 3,579,342.
- Unger, Manfred Otto, 3,579,559.
- Dupre, Jean; and Killam, Harrison Scott, to Rohm and Haas Company. Alkali-soluble surfactant consisting of substituted succinic acid-nonionic ethoxylate blends. 3,579,453, Cl. 252-89.
- Duquesne, Jean F.: See—
Lucas, Pierre M.; Duquesne, Jean F.; Berger, Jean-Pierre L.; and Courtois, Roger L., 3,578,918.
- Dura Corporation: See—
Forestal, Robert J., 3,579,184.
- Dutton, Lloyd K., to Mooney Brothers Corporation. Tube coupling. 3,578,805, Cl. 285-55.
- Dvorak, Alfred: See—
Basu, Rabindra N.; and Dvorak, Alfred, 3,579,050.
- Dyott, Richard Burnaby: See—
Rath, Paul S.; Dyott, Richard Burnaby; and Clark, George Archer, 3,579,316.
- Earle, James D.: See—
Alton, Kelly F., 3,578,885.
- Eastcott, Peter De Hertel, to Canadian General Electric Company Limited. Control of mine hoist braking. 3,578,817, Cl. 303-16.
- Eastcott, Peter De Hertel, to Canadian General Electric Company Limited. Pneumatic engine for mine hoist braking. 3,578,818, Cl. 303-16.
- Eastman Kodak Company: See—
Brooker, Leslie G. S.; Heseltine, Donald W.; and Daniel, Daniel S., 3,579,346.
- Fix, Delbert Dale; and Karlson, Richard Warren, 3,579,348.
- Folzenlogen, Paul D.; Watkins, Windell C.; and Hagemeyer, Hugh J., Jr., 3,579,485.
- Hodges, Howard T., 3,578,797.
- Hood, Harrison P., III; Mackie, William L.; and Wilson, Edgar D., 3,579,411.
- Jones, Jean E., 3,579,345.
- Laukaitis, Joseph F., 3,579,065.
- McConnell, Richard L.; and Joyner, Frederick B., 3,579,486.
- Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., 3,579,412.
- Schweizer, Hans R., 3,579,519.
- Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.
- Webster, Frank G., 3,579,344.
- Eburn, William H., Jr.; and Raymond, Charles T., to Selchow & Righter Company. High speed precision combiner. 3,579,406, Cl. 156-571.
- Edington, John E.; and Warnock, Merville L., to Bell Telephone Laboratories, Incorporated. Coin telephone circuit for dial-tone-first service. 3,579,253, Cl. 179-6-3.
- Edmonds, Byron P.; and Ruse, Douglas C., to Kalium Chemicals Limited. Solution mining method and apparatus. 3,578,808, Cl. 299-4.
- Edson, Alvin W., to General Electric Company. Parabolic waveform generating circuit. 3,578,985, Cl. 307-229.
- Ehe, Albert L.; and Pesses, Marvin, to General Ecological Systems, Inc. Multicup Automation Company, Inc. Method and apparatus for assembling a plurality of Process for producing and recovering valuable materials from municipal waste paper cups in tray formation and gluing them together. 3,579,399, Cl. 156-293.
- Eichel, Herman J.: See—
Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,538.
- Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,542.
- Ekblom, Karl Gote; and Vincent, George E., Jr., to Fosfatbolaget AB United Aircraft Corporation. Process of manufacturing ammonium salts Method of forming a resist pattern on a circuit board or the like. 3,579,376, Cl. 117-212.
- Electro-Calmp Corporation: See—
Lawlor, Robert E., 3,579,177.
- Electrolux Corporation: See—
Muendel, Carl H.; Howell, George D.; and Ayres, Robert F., 3,579,389.
- Electronic Associates Inc.: See—
Proskauer, Walter, 3,578,969.
- Electronic Control Corporation: See—
Buchanan, Edward E., Jr., 3,579,096.
- Electronic Memories, Incorporated: See—
Gilligan, Thomas J.; and Nozaki, Arthur T., 3,579,209.
- Elektrophysikalische Anstalt Bernhard Berghans: See—
Spescha, Gelli, 3,579,029.
- Elmer, William B. Rear projection screen. 3,578,841, Cl. 99-81.
- Elox Inc.: See—
Sennowitz, Kurt H., 3,578,937.
- Emhart Corporation: See—
Wythe, Frederick J.; Oshima, Yasuhiro; and Hoette, Harald, 3,579,398.
- Engelhardt, Fritz: See—
Heid, Christian; Gunzert, Willi; and Engelhardt, Fritz, 3,579,286.

- Enoksson, Bertil Petrus: *See—*
Pryor, Michael J.; Enoksson, Bertil Petrus; and Anthony, William H., 3,579,392.
- Entron, Inc.: *See—*
Kuzminsky, Irving; and Kauffman, Ray B., 3,578,898.
- Eprad Incorporated: *See—*
Boudouris, Angelo, 3,578,855.
- Erman, William F.: *See—*
Fanta, Wayne I.; and Erman, William F., 3,579,479.
- Escoa Fintube Corporation: *See—*
Boose, Robert C., 3,578,952.
- Esso Research and Engineering Company: *See—*
Kivlen, John A., 3,579,601.
- Ethyl Corporation: *See—*
Meltner, Bernard R., 3,579,561.
- Euerle, William C., to Massachusetts Institute of Technology. Polyphase alternating current generator. 3,578,998, Cl. 310-11.
- Evans, Fred D.; Springfield, Carlos L.; and Bryan, Coleman J., to United States of America, National Aeronautics and Space Administration. Autoignition test cell. 3,578,756, Cl. 73-15.
- Excellon Industries: *See—*
Smith, Joseph E., 3,578,827.
- Fagin, William T.: *See—*
Callen, Joseph E.; Haxby, Robert D.; and Fagin, William T., 3,579,458.
- Fahrendholz, Joachim: *See—*
Cyrener, Gerd; and Fahrendholz, Joachim, 3,579,256.
- Failli, Amedeo A.: *See—*
Marshall, David J.; and Failli, Amedeo A., 3,579,507.
- Fanta, Wayne I.; and Erman, William F., to Proctor & Gamble Company, The. 3-Endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl) nor-campor and 2-methyl-5-bromopentanol, and process for the preparation of these compounds. 3,579,479, Cl. 260-586.
- Farbenfabriken Bayer Aktiengesellschaft: *See—*
Bendszus, Otto; Niehaus, Clemens; and Patheiger, Manfred, 3,579,522.
- Hund, Franz, 3,579,452.
- Immel, Otto; Schwarz, Hans-Helmut; and Schnell, Hermann, 3,579,558.
- Schnell, Hermann; Darsow, Gerhard; and Bottenbruch, Ludwig, 3,579,591.
- Farber, Bertrand F.: *See—*
Cronin, Donald L.; Farber, Bertrand F.; and Nockey, Charles R., 3,579,078.
- Fargo Mfg. Company, Inc.: *See—*
Greener, Richard G., 3,579,173.
- Farrand, Richard George. Comparator device using parallax of two photographs. 3,578,863, Cl. 356-2.
- Farrar, Grover L.: *See—*
Storms, Phillip W.; and Farrar, Grover L., 3,579,563.
- Faulkner, Alfred H.: *See—*
Anderson, Robert A.; Faulkner, Alfred H.; and Hughes, Edwin L., 3,579,199.
- Faust, Werner: *See—*
Bossi, Hans Jurg; and Faust, Werner, 3,579,082.
- Feakes, Frank: *See—*
Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.
- Feduska, William: *See—*
Crane, Margaret M.; Feduska, William; and Brown, Jack T., 3,579,385.
- Felici, Noel, to Tunzini-Sames. Electric generators. 3,578,997, Cl. 310-10.
- Fenoglio, Maurice: *See—*
Amedjian, Garabed; Fenoglio, Maurice; and Oberdorf, Michel, 3,579,572.
- Fenton, Donald M., to Union Oil Company of California. Reduction of anhydrides. 3,579,566, Cl. 260-488.
- Fenton, Marvin J.: *See—*
Anderson, James M.; and Fenton, Marvin J., 3,579,140.
- Ferri, Giampiero. Toy gun. 3,578,789, Cl. 222-79.
- Filho, Francisco Muniz: *See—*
Radford, David L.; Frisby, Paul W.; and Filho, Francisco Muniz, 3,578,790.
- Finnegan, Walter D., to Kaiser Aluminum & Chemical Corporation. Electrolytic reduction cell. 3,579,432, Cl. 204-279.
- Firmenich & Cie: *See—*
Demole, Edouard P., 3,579,550.
- Fitting, Robert C.: *See—*
Brown, Kenneth H.; and Fitting, Robert C., 3,579,147.
- Fix, Delbert Dale; and Karlson, Richard Warren, to Eastman Kodak Company. Direct-print silver halide emulsions. 3,579,348, Cl. 96-102.
- Fletcher, Taylor C.; Silva, Lawrence M.; and Wilkinson, Bruce L. Ferroresonant transformer with controllable flux. 3,579,088, Cl. 323-6.
- Flo-Root, Inc.: *See—*
Florance, Douglas A.; and Nordholm, Lloyd P., 3,579,280.
- Florance, Douglas A.; and Nordholm, Lloyd P., to Flo-Root, Inc. Electrical ground fault detector with transformer coupling, a battery supply source and battery charging means. 3,579,280, Cl. 324-51.
- Flow Laboratories, Inc.: *See—*
Yamane, Isao; Matsuya, Yutaka; and Jimbo, Katsuhiko, 3,579,423.
- Flowers, William Thain: *See—*
Haszeldine, Robert Neville; and Flowers, William Thain, 3,579,528.
- Floyd, Linton E., to General Electric Company. Compact battery charger for rechargeable batteries of various physical sizes and electrical capabilities. 3,579,075, Cl. 320-2.
- FMC Corporation: *See—*
Slemmons, Arthur J., 3,578,822.
- Thomas, James Larue, 3,579,484.
- Fok-Gyem Finommechanikai Es Elektronikus Muszergyarto: *See—*
Mandzsó, Jozsef; and Csaszar, Erno, 3,579,265.
- Folzenlogen, Paul D.; Watkins, Windell C.; and Hagemeyer, Hugh J., Jr., to Eastman Kodak Company. Chlorinated carboxyl group containing poly- α -olefins. 3,579,485, Cl. 260-78.4.
- Foote Mineral Company: *See—*
Smith, William Novis, Jr., 3,579,492.
- Ford Motor Company: *See—*
Bugaj, Leonard J., 3,578,942.
- Dickason, Richard T.; and Richardson, John A., 3,579,243.
- Irland, Max J.; and Lindberg, Victor L., 3,578,869.
- Foreman, Joseph Trevor: *See—*
Bentham, Frederick Percy; Sheridan, Phillip Robert; Foreman, Joseph Trevor; and Stimpson, Ian William, 3,579,030.
- Forestal, Robert J., to Dura Corporation, mesne. Portable extendable signal light platform. 3,579,184, Cl. 340-137.
- Forsberg, Charles A.: *See—*
Griffin, John R.; and Forsberg, Charles A., 3,579,224.
- Fosfatbolaget AB: *See—*
Ekblom, Karl Gote; and Vincent, George E., Jr., 3,579,376.
- Foss, Richard Charles, to Plessey Company Limited, The. Logic circuits. 3,579,272, Cl. 307-218.
- Foster, Newton C., to Westinghouse Electric Corporation. built-in catalysis for the reaction with aminoplasts Wood members impregnated with synthetic organic. 3,579,369, Cl. 8-116.3.
- Fox, Morton H., to Honeywell Inc. Control apparatus. 3,579,023, Cl. 315-18.
- Foxboro Company, The: *See—*
Richardson, David A., 3,578,958.
- Franz, Raymond A., to Monsanto Company. Production of vinyl substituted aromatics from methyl substituted aromatics. 3,579,521, Cl. 260-290.
- Frederick, Philip, to Supreme Equipment & Systems Corporation. Drawer suspension. 3,578,833, Cl. 312-330.
- Freed, Meier E., to American Home Products Corporation. N-Substituted pyrido indole derivatives. 3,579,527, Cl. 260-296.
- Freeman, Wilbern Marvin. Portable burglar alarm. 3,579,222, Cl. 340-283.
- Freeman, William P., Jr., to Mitchell, John E., Company. Liquefied petroleum vaporizer with automatic vaporizer bypass. 3,578,753, Cl. 62-51.
- French State, The: *See—*
Loustalet, Pierre; and Roujas, Guy, 3,578,783.
- Friend, Aaron L.; Patterson, Arthur G.; and Wilen, James G., to General Electric Company. Soldering and desoldering hand tool employing air blast or suction. 3,578,948, Cl. 219-230.
- Friese, Hermann: *See—*
Wiesboeck, Robert A.; and Friese, Hermann, 3,579,380.
- Frisby, Paul W.: *See—*
Radford, David L.; Frisby, Paul W.; and Filho, Francisco Muniz, 3,578,790.
- Fuji Photo Film Co., Ltd.: *See—*
Ooue, Shingo; Ueda, Hiroyuki; and Hayakawa, Yoshihide, 3,579,338.
- Fujii, Toshikazu: *See—*
Hata, Kotaro; and Fujii, Toshikazu, 3,578,829.
- Fujitsu Limited: *See—*
Inaba, Seiueemon; Shimizu, Kanryo; Hashimoto, Yoshihiro; and Kobayashi, Kengo, 3,579,279.
- Fukuda, Toshio, to Shimadzu Seisakusho Ltd. Operational amplifier. 3,579,131, Cl. 330-9.
- Furuno Electric Company Ltd.: *See—*
Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, 3,579,247.
- Gabor, Andrew, to Honeywell Inc. Reproducing head in a liquid medium. 3,579,212, Cl. 340-174.1.
- Gaines, Brian Ronald: *See—*
Sears, James K.; Andrae, John Hugh; Gaines, Brian Ronald; and White, Peter, 3,579,191.
- Gamble, John G.: *See—*
Barrett, James P.; and Gamble, John G., 3,578,954.
- Gander, Robert J.; and Rovee, David T., to Johnson & Johnson. Dressing film. 3,579,628, Cl. 424-28.
- Gardner-Denver Company: *See—*
Hufendick, William Rowe; and Nelson, Robert F., 3,579,394.
- Garnier, Marcel; and Blanc, Roger. Dental instrument. 3,578,745, Cl. 32-57.
- Gast, Erich: *See—*
Shimura, Kimio; Wege, Hans; and Gast, Erich, 3,579,351.
- Gatlin, James A., to United States of America, National Aeronautics and Space Administration. Sampled data controller. 3,578,957, Cl. 235-150.1.
- Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., to

- Goldworthy Engineering, Inc. Österreichische Stickstoffwerke Aktiengesellschaft. Process for the manufacture of a chloride-free Method and apparatus for producing filament reinforced tubular products on a continuous basis high-strength potassium ammonium nitrate phosphate fertilizer. 3,579,402, Cl. 71-35.
- Gebr., Bohler & Co. Aktiengesellschaft: *See—*
Kleinagauer, Otmar; Samejima, Hirotsoshi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.
- Pater, Maximilian, 3,579,027.
- Gebr., Eickhoff, Maschinenfabrik und Eisengiesserei mbH: *See—*
Bassier, Friedrich-Karl; and Tekathen, Hans, 3,578,811.
- Gehrmann, Klaus: *See—*
Sennewald, Kurt; Gehrmann, Klaus; and Schafer, Stefan, 3,579,309.
- Geigy Chemical Corporation: *See—*
Kuhnis, Hans Herbert; and Renner, Ulrich, 3,579,512.
- Kuhnis, Hans Herbert; and Renner, Ulrich, 3,579,513.
- General Dynamics Corporation: *See—*
Hatley, Derek J., 3,579,109.
- General Ecological Systems, Inc.: *See—*
Ehe, Albert L.; and Pesses, Marvin, 3,579,399.
- General Electric and English Electric Companies Limited, The: *See—*
Rowley, Donald Edward, 3,579,157.
- Sylanski, Piotr, 3,579,231.
- General Electric Company: *See—*
Beatty, John W., 3,579,258.
- Blume, Alan E., 3,579,148.
- Brown, Edgar D., Jr., 3,579,467.
- Chapman, Thomas G., 3,579,062.
- Christopher, Harold A., 3,579,382.
- Cullen, William F.; and Ringeman, Othmar E., 3,579,020.
- Davies, Robert L., 3,579,060.
- Edson, Alvin W., 3,578,985.
- Floyd, Linton E., 3,579,075.
- Friend, Aaron L.; Patterson, Arthur G.; and Wilen, James G., 3,578,948.
- Grenoble, Maurice E., 3,579,469.
- Holub, Fred F.; and Safford, Moyer M., 3,579,611.
- Jacobson, Chester F., 3,578,884.
- Johnson, Wallace M., 3,579,165.
- Kelley, Fred W., Jr., 3,579,079.
- Kindl, Fred H.; and Barton, Sterling C., 3,579,006.
- McCoy, John J., 3,579,311.
- McGuffin, August L.; and Philip, Ralph M., 3,578,986.
- Millis, Walter T., 3,579,378.
- Perkins, Donald W.; and Wickes, William E., 3,578,959.
- Savkar, Sudhir D., 3,579,162.
- Voyentzie, Peter R.; and Lehnen, Robert J., 3,579,387.
- Waldon, Paul L., 3,579,061.
- General Foods Corporation: *See—*
Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, 3,578,858.
- General Motors Corporation: *See—*
Anderson, Robert A.; Faulkner, Alfred H.; and Hughes, Edwin L., 3,579,199.
- General Telephone & Electronics Laboratories Incorporated: *See—*
Palilla, Frank C., 3,579,016.
- General Time Corporation: *See—*
Patrick, Alan E.; and Kern, Kenneth E., 3,579,004.
- Genkin, Jury Markovich: *See—*
Samuilov, Viktor Ivanovich; Genkin, Jury Markovich; and Suvorova, Maria Dmitrievna, 3,578,757.
- Genset Corporation: *See—*
Healy, Lawrence W., 3,579,372.
- George, Henry H., to Du Pont de Nemours, E. I., and Company. Apparatus for applying electrostatic charge to fibrous structure. 3,578,739, Cl. 18-8.
- Georgi, Heinz W.; and Nather, Roy E., to Beckman Instruments, Inc. Radiation detection system with automatic sample counting rate determination. 3,578,960, Cl. 235-156.
- Gerber, Howard L., to Continental Can Company, Inc. Container body separation utilizing radiation discrimination. 3,578,936, Cl. 219-68.
- Gerber, Robert L., to United States of America, Navy. Light producing device. 3,578,962, Cl. 240-225.
- Gerwig, Jack N., to Bird Machine Company. Coal converting process. 3,579,442, Cl. 210-44.
- Ges.: *See—*
Wopkemeier, Helmut Friedrich; and Richter, Werner, 3,578,868.
- Gevaert-Agfa N.V.: *See—*
Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, 3,579,416.
- Brinckman, Eric Maria; Vanhalst, Johan Eugene; Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, 3,579,417.
- Giess, Wilfried Elmar, to Aktiengesellschaft Brown, Boveri & Cie. Stabilized power supply circuits. 3,579,089, Cl. 323-22.
- Gifaudan Corporation: *See—*
Nikawitz, Edward J.; and Walter, George R., 3,579,578.
- Gilbert, Marcellus N., Jr., to Sylvania Electric Products, Inc. Lamp-base assembly. 3,579,174, Cl. 339-144.
- Gilde, Dieter; and Koberstein, Edgar, to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler. Oxidation of α,β -unsaturated aldehydes to the corresponding unsaturated carboxylic acids. 3,579,573, Cl. 260-530.
- Gillett Tool Co.: *See—*
Long, Emile David; and Aumick, Kenneth Donald, 3,578,879.
- Gilligan, Thomas J.; and Nozaki, Arthur T., to Electronic Memories, Incorporated. High speed core memory system. 3,579,209, Cl. 340-174.
- Gilmore, Cecelia R.: *See—*
Stillings, William K.; Miller, Donald E.; and Gilmore, Cecelia R., 3,579,356.
- Girard, Pierre; Lerouge, Clade Paul Henri; and Regnier, Marc Andre, to International Standard Electric Corporation. Non-linear digital to analog decoder with a smooth characteristic. 3,579,232, Cl. 340-347.
- Giraud, Francois L., to Societe de L'Aerotrain. Partitioning system for fluid cushions in ground effect machines. 3,578,768, Cl. 104-23.
- Giunta, John A., to Bell Telephone Laboratories, Incorporated. Microprogrammed wired logic memory. 3,579,198, Cl. 340-172.5.
- Givaudan Corporation: *See—*
Wood, Thomas F., 3,579,593.
- Glaub, Wayne R., to Johnson, S. C., & Son, Inc. Emulsification process. 3,579,461, Cl. 252-311.
- Gnozzio, Michael J.: *See—*
Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silvius A., 3,579,292.
- Goeller, Charles P., to Allis-Chalmers Manufacturing Company. Reverse power relay. 3,579,043, Cl. 317-36.
- Goldworthy Engineering, Inc.: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.
- Goldsworthy, William B.: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.
- Goncharoff, Nikolai; and Jabbar, Kamil Y., to Motorola, Inc. Electronically tuned oscillator. 3,579,115, Cl. 325-438.
- Goodman, David M. Computer driven displays employing pattern recognition techniques. 3,579,252, Cl. 178-7.85.
- Goodrich Gulf Chemicals, Inc.: *See—*
Redding, Billy J.; Steadman, John T.; and Bragg, Lorel J., 3,578,740.
- Goodyear Tire & Rubber Company, The: *See—*
Brittain, Glenn B., 3,579,626.
- Goto, Eizo: *See—*
Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., 3,579,317.
- Gottschall, Gernot: *See—*
Stock, Hans Joachim; and Gottschall, Gernot, 3,578,907.
- Gould, Henry: *See—*
Zaslowsky, Joel A.; and Gould, Henry, 3,579,565.
- Gower, George H., to Inert Gas Corporation. 3,579,308, Cl.
- Grable, Jack W., to Texas Instruments, Incorporated. Thermostatic switch with improved heater assembly and method of assembling same. 3,579,167, Cl. 337-102.
- Grace, W. R., & Co.: *See—*
Montgomery, Stewart R.; and Hillmann, Melville E., 3,579,569.
- Rosen, Harvey; Acker, Ellsworth G.; and Lee, Hanju, 3,579,464.
- Sabatelli, Philip M.; and Brungs, Charles A., 3,579,455.
- Grandjean, Charles Henri Emile; and Perrault, Jean, to International Standard Electric Corporation. Security circuit for multi-exchange telecommunications network. 3,578,917, Cl. 179-18.
- Grange, Robert A., to RCA Corporation. Low inductance interconnection of cryoelectric memory system. 3,579,206, Cl. 340-173.1.
- Granger Associates: *See—*
Phillips, Larry B., 3,579,033.
- Grant, Alan H. Anti-flare contact lens. 3,578,850, Cl. 351-160.
- Grantham, William L., to United States of America, National Aeronautics and Space Administration. Antenna design for surface wave suppression. 3,579,242, Cl. 343-708.
- Graphic Sciences, Inc.: *See—*
Von Hippel, Eric A.; and Stimus, Charles C., Jr., 3,578,909.
- Gray, Robert C. Magnetic braking system. 3,579,003, Cl. 310-93.
- Grayhill, Inc.: *See—*
Kikta, Donald D., 3,579,049.
- Green, Randolph E. Backing gas attachment saving device for heliarc welding. 3,578,939, Cl. 219-74.
- Greene, Max E.: *See—*
Stewart, Dan F.; Blair, Bob C.; Greene, Max E.; and Alexander, Lloyd R., 3,579,618.
- Greener, Richard G., to Fargo Mfg. Company, Inc. Underground cable tap connector. 3,579,173, Cl. 339-97.
- Gregg, Roland S., Jr.; Danberg, Arnold S.; and Larson, Kenneth N., to Bunker-Ramo Corporation, The. Data storage and display system. 3,579,196, Cl. 340-172.5.
- Gregory, Jim C.: *See—*
Stewart, Aubrey P., Jr.; Dreier, Clarence R., Jr.; and Gregory, Jim C., 3,579,631.
- Gregory, Robert O., to Monsanto Company. Electron beam addressed plasma display panel. 3,579,015, Cl. 313-89.
- Grenoble, Maurice E., to General Electric Company. Siloxane paper release coatings. 3,579,469, Cl. 260-18.
- Grey, David S., to Polaroid Corporation. Three element objective lens. 3,578,847, Cl. 350-226.

- Griepentrog, Dal F., to RCA Corporation. Video amplifier for driving a delay line between grounded collector and grounded base stages. 3,578,901, Cl. 178-5.4
- Griffin, Edward L., Jr.: *See—*
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.
- Griffin, John R.; and Forsberg, Charles A., to Tektronix, Inc. Character generator apparatus. 3,579,224, Cl. 340-324.
- Grodinsky, Robert, to Acoustic Research, Inc. Power supply for providing main and standby sources of power. 3,579,085, Cl. 321-27.
- Gross, Franz; and Krapf, Rudolf, to Brown, Boveri & Cie A.G. Thermionic converter with concentric collector and emitter. 3,578,991, Cl. 310-4.
- Grunwald, John J.; and D'Ottavio, Eugene D., to MacDermid Incorporated. Data system incorporating method and apparatus for referencing media locations. Composition for and methods of improving. 3,579,365, Cl. 340-172.5
- Guettier, Michel, to Regie Nationale des Usines Renault, and Automobiles Peugeot. Brake limiters. 3,578,821, Cl. 303-22.
- Guillet, Hubert: *See—*
Lukas, Anthony J.; and Guillet, Hubert, 3,578,849.
- Gulf & Western Industries: *See—*
Bartlett, Peter G.; and Meschi, Joseph E., 3,579,207.
Bartlett, Peter G., 3,579,208.
Morey, Fred E., III; and Mork, George B., 3,578,923.
Mork, George B.; and Morse, Donald J., 3,579,264.
- Gulf Energy & Environmental Systems, Inc.: *See—*
Thomas, Harold A., 3,579,127.
- Gulf Research & Development Company: *See—*
Hazen, Stanley M.; and Heilman, William J., 3,579,487.
Rhodes, Donald F., 3,579,118.
- Gulton Industries, Inc.: *See—*
Bates, James W., 3,579,081.
- Gunnerson, Dale B.: *See—*
Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., 3,578,737.
- Gunzert, Willi: *See—*
Heid, Christian; Gunzert, Willi; and Engelhardt, Fritz, 3,579,286.
- Guttig, Alvin, to Weston Chemical Corporation. Insulated alkali metal conductor. 3,579,624, Cl. 264-171.
- Haag, Eugen, to Siemens Aktiengesellschaft. Apparatus for detecting nonrecurrent pulses in the nanosecond range with a delay line. 3,579,121, Cl. 328-124.
- Habert, Roger, to Ducellier & Cie. Ignition distributor. 3,578,922, Cl. 200-19.
- Hackman, Donald J.; Legue, Ronald L.; Harris, Jeremy M.; and Roop, Donald E., to Oceanautic Manufacturing and Research Company. Portable tool. 3,579,037, Cl. 317-18.
- Hadel, Donald H.: *See—*
Knott, Robert L.; and Hadel, Donald H., 3,579,187.
- Haefl, Andrew V.; and Harris, Franklin H., to United States of America, Navy. Automatic power control of a pulse modulator. 3,579,238, Cl. 343-18.
- Hagemeyer, Hugh J., Jr.: *See—*
Folzenlogen, Paul D.; Watkins, Wendell C.; and Hagemeyer, Hugh J., Jr., 3,579,485.
- Hagino, Hiroshi: *See—*
Nakayama, Kiyoshi; and Hagino, Hiroshi, 3,579,427.
- Hagler, Travis J.; Puckett, William R.; and Tanner, Bobby G., to Thiokol Chemical Corporation. Spinning and stabilizing system for solid propellant rocket or missiles. 3,578,796, Cl. 244-3.23
- Hakanson, Nils L.: *See—*
Michaud, David E.; and Hakanson, Nils L., 3,578,970.
- Halbrook, Noah J.; and Lawrence, Ray V., to United States of America, Agriculture. Process for the preparation and isolation of dehydroabiatic acid. 3,579,571, Cl. 260-514.5
- Hallmark, T. Milton; and Woodward, John M., to International Business Machines Corporation. Plasticized resin compositions. 3,579,195, Cl. 106-176.
- Hallmark, T. Milton: *See—*
Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.
Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.
- Hallock, James N., to United States of America, National Aeronautics and Space Administration. Multiple hologram recording and read out system. 3,578,838, Cl. 350-3.5
- Halls, Lawrence M.; Lausch, Henry N.; and Schwalm, Bruce D., to Sperry Rand Corporation. Crop guiding and arranging means for a self-propelled harvesting machine. 3,578,750, Cl. 56-23.
- Hamel, William J.: *See—*
Potter, John J., Jr.; and Hamel, William J., 3,578,788.
- Hanley, Robert B.: *See—*
Noble, Lowell A.; and Hanley, Robert B., 3,578,835.
- Hannan, William J., to RCA Corporation. Retrieval of holographically recorded data. 3,578,836, Cl. 350-3.5
- Hansford, Rowland C., to Union Oil Company of California. Dehydrocyclization process and catalyst. 3,579,598, Cl. 260-673.5
- Haraden, Thomas: *See—*
De Vos, Hendrik A.J.; and Haraden, Thomas, 3,578,963.
- Hardesty, Ethridge E.: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.
- Harford, Jack R., to RCA Corporation. Automatic gain control systems. 3,579,112, Cl. 325-319.
- Harford, Jack R., to RCA Corporation. Signal translating stage. 3,579,133, Cl. 330-19.
- Harkort, Dietrich; Rasch, Rudolf; Iberg, Rolf; and Heberlein, Jurg H. Roasting marl to produce a pozzolana material. 3,579,619, Cl. 264-42.
- Harris, Franklin H.: *See—*
Haefl, Andrew V.; and Harris, Franklin H., 3,579,238.
- Harris, George J.; and Day, Christopher C., to American Optical Corporation. Automatic gain presetting circuit. 3,579,138, Cl. 330-86.
- Harris, Intertype Corporation: *See—*
Sarka, Albert J., 3,578,761.
- Harris, Jeremy M.: *See—*
Hackman, Donald J.; Legue, Ronald L.; Harris, Jeremy M.; and Roop, Donald E., 3,579,037.
- Harris, Jerry S.: *See—*
Davis, Robert H.; and Harris, Jerry S., 3,579,200.
- Harrison, Alvin, to Stauffer Chemical Company. Grease composition. 3,579,448, Cl. 252-28.
- Hartmann, Robert F.: *See—*
Polkinghorn, Robert W.; Pfeifer, Arthur F.; and Hartmann, Robert F., 3,579,275.
- Hartwick, Richard W.: *See—*
Orkin, Stanley S.; and Hartwick, Richard W., 3,578,828.
- Hartz, George R.: *See—*
Tawil, Joseph N.; Hartz, George R.; and Walsh, Edmund F., 3,578,965.
- Harwit, Martin O.: *See—*
Decker, John A., Jr.; and Harwit, Martin O., 3,578,980.
- Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, to Windmoller & Holscher Nisso Kinzoku Kabushiki Kaisha. Machine for heat sealing continuously moving work—material sheeting in the manufacture of bags of plastics materials. Cobalt removal from zinc electrolyte solution. 3,579,327, Cl. 75-109.
- Hashimoto, Yoshihiro: *See—*
Inaba, Seiemon; Shimizu, Kanryo; Hashimoto, Yoshihiro; and Kobayashi, Kengo, 3,579,279.
- Haszeldine, Robert Neville; and Flowers, William Thain. 2,6-Dihydroxytrichloropyridine and its preparation. 3,579,528, Cl. 260-297.
- Hata, Kotaro; and Fujii, Toshikazu, to Matsushita Electric Industrial Co., Ltd. Bottom bracket for bicycle. 3,578,829, Cl. 308-179.5
- Hatley, Derek J., to General Dynamics Corporation. Automatic equalizer for digital data transmission systems. 3,579,109, Cl. 325-42.
- Hauber, Erwin J. Digital data condensation system. 3,579,110, Cl. 325-47.
- Haw, Thomas, III: *See—*
Smith, Robert H.; Payne, Robert K.; and Haw, Thomas, III, 3,579,617.
- Haxby, Robert D.: *See—*
Callen, Joseph E.; Haxby, Robert D.; and Fagin, William T., 3,579,458.
- Hayakawa, Shigeru: *See—*
Wasa, Kiyotaka; and Hayakawa, Shigeru, 3,579,063.
- Hayakawa, Yoshihide: *See—*
Ooue, Shingo; Ueda, Hiroyuki; and Hayakawa, Yoshihide, 3,579,338.
- Hayakawa, Zenro, to Takeda Chemical Industries, Ltd. Rh₀ blood testing serum. 3,579,627, Cl. 424-11.
- Haydl, William H., to North American Rockwell Corporation. Method for increasing the efficiency of LSA oscillator devices by uniform illumination. 3,579,143, Cl. 331-107.
- Hazeltine Corporation: *See—*
Jorgensen, Otto A., 3,579,094.
- Hazen, Stanley M.; and Heilman, William J., to Gulf Research & Development Company. Polyanhydride-monoepoxide compositions containing a monoanhydride. 3,579,487, Cl. 260-78.5
- Healy, Lawrence W., to Genset Corporation. carrier Deposition of microporous film employing dielectric. 3,579,372, Cl. 23-2.
- Heberlein, Jurg H.: *See—*
Harkort, Dietrich; Rasch, Rudolf; Iberg, Rolf; and Heberlein, Jurg H., 3,579,619.
- Heck, Richard F.; and Henry, Patrick M., to Hercules Powder Company. Synthesis of carboxylic acids from ethylene and carbon monoxide and noble metal compounds. 3,579,568, Cl. 260-497.
- Heer, John, to Varian Associates. Surface barrier diode having a hypersensitive N⁰ region forming a hypersensitive voltage variable capacitor. 3,579,278, Cl. 317-234.
- Heflinger, Lee O.: *See—*
Brooks, Robert E.; Heflinger, Lee O.; and Wuerker, Ralph F., 3,578,845.
- Heid, Christian; Gunzert, Willi; and Engelhardt, Fritz. adhesion of plated metal on plastic substrates. 3,579,286, Cl. 106-265.
- Heilman, William J.: *See—*
Hazen, Stanley M.; and Heilman, William J., 3,579,487.
- Heller, Milton David; Lenhard, Robert Herman; and Bernstein, Seymour, to American Cyanamid Company. 21-Substituted 6-chloro-16 α , 17 α -isopropylidenedi-oxy-pregna-4,6-diene-3,20-dione and method of preparing the same. 3,579,508, Cl. 260-239.55
- Hellwig, Helmut W., to United States of America, Army. Molecular frequency standard. 3,578,968, Cl. 250-41.3
- Henkel & Cie. GmbH: *See—*
Kroke, Hermann; and Raffalsky, Kurt, 3,579,446.
- Rutzen, Horst, 3,579,583.

- Rutzen, Horst; and Brockmann, Rolf, 3,579,584.
- Rutzen, Horst, 3,579,585.
- Umbach, Wilfried, 3,579,606.
- Hennig, Walter; Sedlatschek, Karl; and Machenschalk, Rudolf, to Schwarzkope Development Corporation. Rotary anode for X-ray tube. 3,579,022, Cl. 313-330.
- Henry, Patrick M.: *See—*
Heck, Richard F.; and Henry, Patrick M., 3,579,568.
- Herbst, John A.; and Seliger, Victor H., to Singer-General Precision, Inc. Charge control system for batteries. 3,579,076, Cl. 320-36.
- Hercules Powder Company: *See—*
Heck, Richard F.; and Henry, Patrick M., 3,579,568.
- Herman, Elvin E., to Hughes Aircraft Company. Cathode ray tube having radially directed commutator elements. 3,579,013, Cl. 313-73.
- Hershman, Arnold: *See—*
Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,551.
Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,552.
- Herweh, John E.; and Poskus, Algirdas C., to Armstrong Cork Company. Phosphorus-containing sulfonylchlorides. 3,579,615, Cl. 260-947.
- Herz, Jack L.; Levy, Alan J.; Litt, Morton H.; and Zuckerman, Joseph L., to Allied Chemical Corporation. Treating the hair with oxazoline polymer and copolymer hair dressing formulations. 3,579,630, Cl. 424-47.
- Heseltine, Donald W.: *See—*
Brooker, Leslie G. S.; Heseltine, Donald W.; and Daniel, Daniel S., 3,579,346.
- Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., 3,579,412.
- Hester, Jackson B., Jr., to Upjohn Company, The. Pyrrolo[3,2,1-jk][1,4]benzodiazepinones. 3,579,503, Cl. 260-239.3
- Heuner, Robert Charles, to RCA Corporation. Pulse width stabilized monostable multivibrator. 3,578,989, Cl. 307-273.
- Hewlett-Packard Company: *See—*
McGrath, Walter R., Jr., 3,579,248.
- Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilberte, to Chemical Separations Corporation Societe le Carbone Lorraine. Recovery of phosphate from phosphate containing pond water. Process for producing thermal insulating carbonized felt laminated assemblies. 3,579,401, Cl. 156-327.
- Hill, Harold J.: *See—*
Abrams, Albert; Hill, Harold J.; and Thigpen, David R., 3,578,781.
- Hill, Lyman L., Jr.: *See—*
Buttenhoff, Edward W.; and Hill, Lyman L., Jr., 3,579,107.
- Hillmann, Melville E.: *See—*
Montgomery, Stewart R.; and Hillmann, Melville E., 3,579,569.
- Hiraga, Kentaro; Asako, Tsunehiko; and Miki, Takuichi, to Takeda Chemical Industries, Ltd. Total process for making 13-hydrocarbon substituted gonapolyene-17-one compounds and intermediates produced in the course of the process. 3,579,544, Cl. 260-397.5
- Hitachi, Ltd.: *See—*
Kozawa, Tokinori; Kuzuma, Noboru; and Miwa, Ichiro, 3,579,114.
- Hladny, Wolfgang: *See—*
Kleinhagauer, Otmar; Samejima, Hirotooshi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.
- Hlavka, Joseph J.; Bitha, Panayota; Ross, Adma Schneller; and Martell, Michael Joseph, to American Cyanamid Company. Substituted 7-and/or 9-amino-6-demethyl-6-deoxytetracyclines. 3,579,579, Cl. 260-559.
- Hoch, Paul E., to Hooker Chemical Corporation. Method of preparing 4,5,6, hexachlorotoluyl chloride. 3,579,577, Cl. 260-544.
- Hodges, Claire F.: *See—*
Hodges, Howard T., 3,578,797.
- Hodges, Howard T., deceased (by Hodges, Claire F.; executrix), to Eastman Kodak Company. Fusing method and apparatus. 3,578,797, Cl. 263-3.
- Hoette, Harald: *See—*
Wythe, Frederick J.; Oshima, Yasuhiro; and Hoette, Harald, 3,579,398.
- Hoffmann-La Roche, Inc.: *See—*
Archer, Giles A.; and Sternbach, Leo Henryk, 3,579,580.
Muller, Marcel; and Zeller, Paul, 3,579,502.
- Holden, Kenneth G., to Smith Kline & French Laboratories. Process and 6- β -substituted ethyl intermediates for preparing 6,6-ethylene-3-keto- Δ_4 steroids. 3,579,509, Cl. 260-239.57
- Holland, Richard J.; Kilduff, Timothy J.; and Sztankay, Zoltan G., to United States of America, Army. Exploding mirror for optical viewing system. 3,578,842, Cl. 350-160.
- Holmes, Ronald W., to Robertshaw Controls Company. Reversibly mountable limit switch construction. 3,578,932, Cl. 200-168.
- Holmstrom, Larry W.; Tuttle, James A.; and Young, Harold J., to International Business Machines Corporation. Close circuit television measurement system. 3,578,906, Cl. 178-6.
- Holtwijk, Theodoor: *See—*
Van Bruck, Heinrich Eduard; and Holtwijk, Theodoor, 3,579,210.
- Holub, Fred F.; and Safford, Moyer M., to General Electric Company. Crosslinked polyoxyethylenes and process therefor. 3,579,611, Cl. 260-874.
- Holzgruber, Wolfgang: *See—*
Kleinhagauer, Otmar; Samejima, Hirotooshi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.
- Honda Giken Kogyo Kabushiki Kaisha: *See—*
Miyoshi, Takeomi, 3,578,782.
- Honeywell Inc.: *See—*
Buttenhoff, Edward W.; and Hill, Lyman L., Jr., 3,579,107.
Fox, Morton H., 3,579,023.
Gabor, Andrew, 3,579,212.
Miu, Ming-Tzer, 3,578,961.
Neti, Radhakrishna M.; and Abens, Sanders G., 3,579,384.
- Honeywell Information Systems Inc.: *See—*
Milford, Richard E.; and Maclean, George, 3,578,953.
- Hood, Harrison P., III; Mackie, William L.; and Wilson, Edgar D., to Eastman Kodak Company. Image-forming process utilizing contact electrification filament reinforced structure and method of making. 3,579,411, Cl. 161-53.
- Hooker Chemical Corporation: *See—*
Hoch, Paul E., 3,579,577.
- Hoover, Merwin Frederick: *See—*
Schaper, Raymond J.; and Hoover, Merwin Frederick, 3,579,613.
- Horn, Milton B.: *See—*
Kordzinski, Stanley; and Horn, Milton B., 3,579,490.
- Horsley, Orville E.: *See—*
Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,538.
Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., 3,579,542.
- Horst, Russel J. Formation of dense precipitates. 3,579,443, Cl. 210-49.
- Horvath, Leo J.: *See—*
Stahlhut, Leo G.; and Horvath, Leo J., 3,578,967.
- Hoshino, Shoichiro: *See—*
Mavrovic, Ivo; Kogure, Motoo; and Hoshino, Shoichiro, 3,579,636.
- Houlihan, William J.; and Manning, Robert E., to Sandoz-Wander, Inc. Secondaryamino pyridazines. 3,579,517, Cl. 260-250.
- Howell, George D.: *See—*
Muendel, Carl H.; Howell, George D.; and Ayres, Robert F., 3,579,389.
- Hubby, John S.: *See—*
O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, 3,579,377.
- Huber, Wolfgang, to Diagnostic Data, Inc. Isolation of orgotein from blood. 3,579,495, Cl. 260-115.
- Hudock, Edward P.; Russell, Irving G.; and Sorensen, Robert L., to Time, Incorporated. Photographic exposing apparatus. 3,578,862, Cl. 355-104.
- Hufendick, William Rowe; and Nelson, Robert F., to Gardner-Denver Company. Soft ground etching method Method of precision form milling. 3,579,394, Cl. 51-288.
- Hughes Aircraft Company: *See—*
Bokor, Michael; and Moulin, Norbert L., 3,579,176.
Herman, Elvin E., 3,579,013.
Hyman, Julius, Jr., 3,579,011.
Steingart, Richard D.; and Wilmot, Richard D., 3,579,237.
Taddeo, Fausto V., 3,579,180.
- Hughes, Edwin L.: *See—*
Anderson, Robert A.; Faulkner, Alfred H.; and Hughes, Edwin L., 3,579,199.
- Hughes, Martin Robert, to Bissell Inc. Floor mat. 3,578,738, Cl. 15-215.
- Hughes, Richard J.: *See—*
Kam, George H.; and Hughes, Richard J., 3,579,281.
- Huhn, Dieter Karl Wilhelm. Slide-ring seal. 3,578,803, Cl. 277-85.
- Huisman, Peter Hendrik: *See—*
Meiring, Pieter Gerhard Jacobus; and Huisman, Peter Hendrik, 3,579,439.
- Hund, Franz, to Farbenfabriken Bayer Aktiengesellschaft. Process for the production of ferromagnetic pure or isotype manganese mixed phases crystallizing in the ilmenite lattice. 3,579,452, Cl. 252-62.51
- Hurd, Raymond M. Ice fishing hole cover. 3,578,748, Cl. 43-44.9
- Hurd, William J.: *See—*
Paine, Thomas O., Administrator of the National Aeronautics and Space Administration with respect to an invention of; Anderson, Tage O.; and Hurd, William J., 3,579,122.
- Hurlock, Ronald James: *See—*
Briggs, Peter James; and Hurlock, Ronald James, 3,579,556.
- Hydronautics, Incorporated: *See—*
Brown, Clinton E., 3,579,441.
- Hyman, Julius, Jr., to Hughes Aircraft Company. Liquid-metal cathode with single capillary flow impedance. 3,579,011, Cl. 313-29.
- I-T-E Imperial Corporation: *See—*
Jensen, Otto, 3,579,034.
- Iberg, Rolf: *See—*
Harkort, Dietrich; Rasch, Rudolf; Iberg, Rolf; and Heberlein, Jurg H., 3,579,619.
- Ilford Limited: *See—*
Wood, Henry Walter, 3,579,347.
- Imahashi, Issei, to Kabushiki Kaisha Suwa Seikosa. Brushless direct current motor. 3,579,277, Cl. 310-156.

Immel, Otto; Schwarz, Hans-Helmut; and Schnell, Hermann, to Farbenfabriken Bayer Aktiengesellschaft. Process for the production of γ -aminoalkane nitriles. 3,579,558, Cl. 260-465.2
 Imperial Chemical Industries Limited: See—
 Briggs, Peter James; and Hurlock, Ronald James, 3,579,556.
 Brown, Martin Granger; Van Berkel, Franciscus C.A.A.; and Luques, Stanley F., 3,579,379.
 Clarkson, Richard, 3,579,499.
 Imperial Chemical Industries of Australia and New Zealand Limited: See—
 Dewar, Robert Alfred; Maier, Volker Elmar; and Ingram, Margaret Anthea, 3,579,530.
 Improved Machinery Inc.: See—
 Brinckman, Eric Maria; Vanhalst, Johan Eugene, Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, 3,579,417.
 Inaba, Seiemon; Shimizu, Kanryo; Hashimoto, Yoshihiro; and Kobayashi, Kengo, to Fujitsu Limited. Step motor acceleration-deceleration control system. 3,579,279, Cl. 318-696.
 Inductosyn Corporation: See—
 Tripp, Robert W., 3,579,229.
 Inductotherm Corporation: See—
 Stroop, John Henry; Kennedy, Theodore R.; and Rowan, Henry M., 3,579,324.
 Inert Gas Corporation: See—
 Gower, George H., 3,579,308.
 Ingram, Margaret Anthea: See—
 Dewar, Robert Alfred; Maier, Volker Elmar; and Ingram, Margaret Anthea, 3,579,530.
 Ingro, Benedict, 45% to Ingro, John, Jr. Electric stoves. 3,578,951, Cl. 219-444.
 Ingro, John, Jr.: See—
 Ingro, Benedict, 3,578,951.
 Inmont Corporation: See—
 Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silviu A., 3,579,292.
 Institut Francais du Pétrole des Carburants et Lubrifiants: See—
 Delmon, Bernard, 3,579,589.
 Intercontinental Systems Inc.: See—
 Bernier, Donald R., 3,579,193.
 International Business Machines Corporation: See—
 Applequist, Roy A., 3,579,213.
 Davis, Robert H.; and Harris, Jerry S., 3,579,200.
 Hallmark, T. Milton; and Woodward, John M., 3,579,195.
 Holmstrom, Larry W.; Tuttle, James A.; and Young, Harold J., 3,578,906.
 Solyst, Erik R., 3,579,214.
 Spruth, Wilhelm, 3,579,185.
 Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.
 International Lead Zinc Research Organization, Inc.: See—
 Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, 3,579,480.
 Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, 3,579,481.
 International Nickel Company, Inc.: See—
 Turner, Trevor Stanley; and Padley, Frederick Bolton, 3,579,383.
 International Paper Company: See—
 Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., 3,579,317.
 International Standard Electric Corporation: See—
 Cattermole, Kenneth William, 3,579,228.
 Girard, Pierre; Lerouge, Clade Paul Henri; and Regnier, Marc Andre, 3,579,232.
 Grandjean, Charles Henri Emile; and Perrault, Jean, 3,578,917.
 Kaiser, Walter, 3,579,255.
 Lord, Michael Robert, 3,579,106.
 Pignard, Jean; and Wintz, Bernard, 3,579,104.
 Sears, James K.; Andraea, John Hugh; Gaines, Brian Ronald; and White, Peter, 3,579,191.
 International Telephone and Telegraph Corporation: See—
 Affel, John J., 3,578,792.
 Carmody, Doyle V.; and Welch, John S., 3,579,254.
 Dempsey, Richard C.; and Lind, Francis E., 3,579,244.
 Karras, Ernest C., 3,579,190.
 Intrusion-Prepakt: See—
 Rehmar, Solomon J., 3,579,366.
 Ippolito, Anthony C.: See—
 Schwartz, Harold O.; and Ippolito, Anthony C., 3,578,894.
 Irland, Max J.; and Lindberg, Victor L., to Ford Motor Company. Method for detecting and indicating wedge in glass. 3,578,869, Cl. 356-239.
 Irvine, Robert G., to LTV Ling Altec, Inc. Voltage-holding circuit and method. 3,579,129, Cl. 330-3.
 Ishida, Hiroshi: See—
 Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, 3,579,247.
 Ishizaki, Kan, to Shingu Shoko, Ltd. Bar for a chain saw. 3,578,779, Cl. 143-32.
 Israel, State of, Atomic Energy Commission: See—
 Kermen, Arich, 3,578,944.
 Israel, State of, Prime Minister's Office: See—
 Suszer, Adalbert; and Patel, Himanshu M., 3,579,288.

Itek Corporation: See—
 Breitbord, Jacob Louis; and MacDougall, Richard Donald, 3,578,860.
 Ito, Yoshiro; Ueno, Tamotsu; Nakano, Takashi; and Okamoto, Kazuo, to Japan Gas-Chemical Company, Inc. Process for extract-separation of aromatic hydrocarbons. 3,579,599, Cl. 260-674.
 Jabbar, Kamil Y.: See—
 Goncharoff, Nikolai; and Jabbar, Kamil Y., 3,579,115.
 Jabbar, Kamil Y.; and Nilssen, Ole K., to Motorola, Inc. Antenna coupling circuit. 3,579,113, Cl. 325-376.
 Jacobs, Robert B., to Standard Oil Company (Indiana). Process for improving the oleophilic property of polymers. 3,579,032, Cl. 317-2.
 Jacobson, Chester F., to General Electric Company. Oral hygiene apparatus. 3,578,884, Cl. 417-317.
 Jacquinet, Jean-Louis, to Societe Rhodioceta. Process for forming trilobal yarns. 3,579,625, Cl. 264-177.
 Jaffee, Robert I.: See—
 Bradley, Elihu F.; Bartlett, Edwin S.; Ogden, Horace R.; and Jaffee, Robert I., 3,578,743.
 Janiszewski, Kasimir. Oilier bushing. 3,578,826, Cl. 308-4.
 Janssen, Leonard F., to Delavan Manufacturing Co. Injector. 3,578,882, Cl. 417-345.
 Japan Gas-Chemical Company, Inc.: See—
 Ito, Yoshiro; Ueno, Tamotsu; Nakano, Takashi; and Okamoto, Kazuo, 3,579,599.
 Japan Radio Company, Limited: See—
 Tsumura, Takao; Kaoaka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.
 Jasberg, Peter M., to Bunker Hill Company, The. mesne. Cell for electrolytic deposition of metals. 3,579,431, Cl. 204-275.
 Jelinek, Arthur G., to Du Pont de Nemours, E. I., and Company. 1-Aryl-3-alkyluretidinediones. 3,579,500, Cl. 260-239.
 Jennings, Brian Edmund: See—
 Jones, Michael Edward Benet; and Jennings, Brian Edmund, 3,579,475.
 Jensen, Arne; and Petersen, Tom Kastrup, to Danfoss A/S. Generator for producing triangular signals. 3,579,274, Cl. 307-228.
 Jensen, Christian, to MPO Videotronics, Inc. Automatically threaded film apparatus incorporating a projection apparatus and a pre-threaded film cartridge assembly. 3,578,851, Cl. 352-72.
 Jensen, Oluf F., Rotary steam engine. 3,578,890, Cl. 418-199.
 Jensen, Otto, to I-T-E Imperial Corporation. Compressed gas system for arc extinction. 3,579,034, Cl. 317-11.
 Jimbo, Katsuhiko: See—
 Yamane, Isao; Matsuya, Yutaka; and Jimbo, Katsuhiko, 3,579,423.
 Joffre, Philippe: See—
 Antonini, Albert; Joffre, Philippe; and Vrillon, Claude, 3,579,597.
 Johannessen, Paul R.; and Knutrud, Thorleif, to Sylvania Electric Products, Inc. Variable mutual coupling circuit employing transformers in an inductive balanced configuration. 3,579,093, Cl. 323-50.
 Johannessen, Paul R.; and Knutrud, Thorleif, to Sylvania Electric Products, Inc. Radio frequency pulse generator using DC charging. 3,579,111, Cl. 325-141.
 Johnson & Johnson: See—
 Gander, Robert J.; and Rovee, David T., 3,579,628.
 Johnson, Robert R.; and Dunham, Richard L., to Burroughs Corporation. Personal identification method and apparatus. 3,579,186, Cl. 340-146.3.
 Johnson, S. C., & Son, Inc.: See—
 Glaub, Wayne R., 3,579,461.
 Johnson, Wallace M., to General Electric Company. Winding connection for single phase two leg electric transformer. 3,579,165, Cl. 336-170.
 Johnstone, Richard; and Stobbe, Richard E. Spindle growth compensator. 3,579,073, Cl. 318-634.
 Jones, Edwin K., to Universal Oil Products Company. Process utilizing liquid acid settling in a alkylation-fractionator. 3,579,603, Cl. 260-683.48.
 Jones, Garth S.: See—
 Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,578,904.
 Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,579,249.
 Jones, Giffin D.; and Tefertiller, Nancy B., to Dow Chemical Company, The. Water-soluble copolymers of alkylenimine and alkylene sulfide. 3,579,488, Cl. 260-79.
 Jones, Jean E., to Eastman Kodak Company. Direct positive emulsions sensitized with pyrylium and/or thiapyrylium salts. 3,579,345, Cl. 96-102.
 Jones, Michael Edward Benet; and Jennings, Brian Edmund. Cross-linked poly(arylsulphone ethers). 3,579,475, Cl. 260-37.
 Jones, Robert C., to Philco-Ford Corporation. Elongated aperture electron gun structure for flat cathode ray tube. 3,579,010, Cl. 313-86.
 Jordan, Charles Edward, to Jordan Controls, Inc. Electrical housing assembly having a plurality of chambers with adjacent circuit board elements. 3,579,046, Cl. 317-120.
 Jordan Controls, Inc.: See—
 Jordan, Charles Edward, 3,579,046.
 Jorgensen, Otto A., to Hazeltine Corporation. Voltage generating apparatus. 3,579,094, Cl. 323-100.
 Joyner, Frederick B.: See—
 McConnell, Richard L.; and Joyner, Frederick B., 3,579,486.

Junger Instrument Aktiebolag: See—
 Lindblad, Lars A.; and Kahlbom, Rune N., 3,579,125.
 Justin, Frank H.: See—
 Rieke, James K.; and Justin, Frank H., 3,579,476.
 K-S-H, Inc.: See—
 Stahlhut, Leo G.; and Horvath, Leo J., 3,578,967.
 Kabushiki Kaisha Honda Gijutsu Kenkyusho: See—
 Shimura, Kimio; Wege, Hans; and Gast, Erich, 3,579,351.
 Kabushiki Kaisha Ricoh: See—
 Kobayashi, Yugo, 3,578,861.
 Kabushiki Kaisha Suwa Seikosa: See—
 Imahashi, Issei, 3,579,277.
 Kabushiki Kaisha Tajima Seisakusho: See—
 Kawaguchi, Toshiji; Tanaka, Takeo; and Okada, Masaru, 3,578,979.
 Kahlbom, Rune N.: See—
 Lindblad, Lars A.; and Kahlbom, Rune N., 3,579,125.
 Kaiser Aluminum & Chemical Corporation: See—
 Finnegan, Walter D., 3,579,432.
 Kaiser Industries Corporation: See—
 Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., 3,579,325.
 Kaiser, Walter, to International Standard Electric Corporation. Outgoing trunk connection for PABX. 3,579,255, Cl. 179-18.
 Kalium Chemicals Limited: See—
 Edmonds, Byron P.; and Ruse, Douglas C., 3,578,808.
 Kam, George H.; and Hughes, Richard J., to Sierra Research Corporation. Combining network providing compensated tuning voltage for varactor. 3,579,281, Cl. 332-302.
 Kaman Aerospace Corporation: See—
 Orkin, Stanley S.; and Hartswick, Richard W., 3,578,828.
 Kanbayashi, Takayuki. Flow detection apparatus using specially located hall detector elements. 3,579,099, Cl. 324-37.
 Kanegafuchi Boseki Kabushiki Kaisha: See—
 Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
 Kanger, Feodor: See—
 Sproule, Robert Stanley; Kanger, Feodor; and Seybold, Hugh Laurie, 3,578,874.
 Kanitz, Douglas R.: See—
 Chauffard, Francoise; Backderf, Robert P.; and Kanitz, Douglas R., 3,579,038.
 Kanyok, Anthony J.; Stoller, Jerry H.; and Keller, William H., to Brandt Chem. Co., Inc. American Standard Inc. Ammonium phosphate fertilizer composition and method Method of positioning a membrane. 3,579,321, Cl. 71-25.
 Kaooka, Toshio: See—
 Tsumura, Takao; Kaoaka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.
 Karlson, Richard Warren: See—
 Fix, Delbert Dale; and Karlson, Richard Warren, 3,579,348.
 Karras, Ernest C., to International Telephone and Telegraph Corporation. Automatic alarm detector. 3,579,190, Cl. 340-167.
 Kasik, Robert L., 3,579,354, Cl. 350-127.
 Kato, Shigeru, to Nippon Rocta Pipes Co., Ltd. Apparatus for making a double-layer reinforcing cage for concrete pipes. 3,579,259, Cl. 219-56.
 Kato, Takaaki; and Kawakubo, Mamoru, to Nippon Denso Kabushiki Kaisha. System for driving a D. C. electromagnet. 3,579,052, Cl. 317-148.5.
 Kauffman, Ray B.: See—
 Kuzminsky, Irving; and Kauffman, Ray B., 3,578,898.
 Kawaguchi, Toshiji; Tanaka, Takeo; and Okada, Masaru, to Kabushiki Kaisha Tajima Seisakusho. Electrical signal generating apparatus having a scale grid. 3,578,979, Cl. 250-237.
 Kawai, Mitsuo: See—
 Mito, Satoru; Kawai, Mitsuo; and Yoshida, Hiroshi, 3,579,329.
 Kawakubo, Mamoru: See—
 Kato, Takaaki; and Kawakubo, Mamoru, 3,579,052.
 Kaznoff, Alexis I.: See—
 United States of America, National Aeronautics and Space Administration, Administrator, 3,579,390.
 Kearns, William J., to Xerox Corporation, mesne. Zero arc drop thyatron. 3,579,031, Cl. 315-363.
 Keating, John F.; and Zutkis, Joseph A., to Western Electric Company, Incorporated. Methods of and apparatus for testing successive ones of a plurality of electrical components. 3,579,102, Cl. 324-73.
 Keller, William H.: See—
 Kanyok, Anthony J.; Stoller, Jerry H.; and Keller, William H., 3,579,321.
 Kelley, Fred W., Jr., to General Electric Company. Current source magnetic gating circuit for controlled rectifiers. 3,579,079, Cl. 321-5.
 Kelsey-Hayes Company: See—
 Atkins, Thomas M., 3,578,819.
 Manthei, William J., 3,578,742.
 Riordan, Hugh E., 3,578,820.
 Kemp, Kenneth Albert Walters: See—
 Mowbray, Dorian Farrar; and Kemp, Kenneth Albert Walters, 3,578,881.
 Kennedy, Theodore R.: See—
 Stroop, John Henry; Kennedy, Theodore R.; and Rowan, Henry M., 3,579,324.

Keogh, Thomas H.; and Krupit, Adolph E., to Allis-Chalmers Manufacturing Company. High voltage air terminal chamber for indoor power center with interlocks between fuse drawers and circuit breakers, fuse clamping and latching means, and universally pivotal terminal means. 3,579,045, Cl. 317-114.
 Kermen, Arich, to Israel, State of, Atomic Energy Commission. Welding assemblage. 3,578,944, Cl. 219-130.
 Kern, Kenneth E.: See—
 Patrick, Alan E.; and Kern, Kenneth E., 3,579,004.
 Kerst, Al F., to Monsanto Company. Methods of scale inhibition. 3,579,444, Cl. 210-58.
 Kerwood, Joseph Edward. Sulfenamide compositions stabilized by organic disulfides. 3,579,460, Cl. 252-182.
 Kikta, Donald D., to Grayhill, Inc. Safety control system for actuating electrically controlled mechanical device. 3,579,049, Cl. 317-135.
 Kilduff, Timothy J.: See—
 Holland, Richard J.; Kilduff, Timothy J.; and Sztankay, Zoltan G., 3,578,842.
 Killam, Harrison Scott: See—
 Dupre, Jean; and Killam, Harrison Scott, 3,579,453.
 Kimball, Stephen F., to Sylvania Electric Products, Inc. Incandescent lamp having linear output. 3,579,021, Cl. 313-274.
 Kindl, Fred H.; and Barton, Sterling C., to General Electric Company. Liquid cooled collector rings for dynamoelectric machine. 3,579,006, Cl. 310-227.
 King of Prussia Research and Development Corporation: See—
 Stratenko, Andrew, 3,578,876.
 Kinoshita, Kokiti: See—
 Nishino, Tsutomu; Kinoshita, Kokiti; and Maeda, Haruo, 3,579,009.
 Kivlen, John A., to Esso Research and Engineering Company. Pyrolysis of hydrocarbons. 3,579,601, Cl. 260-683.
 Kleinhagauer, Otmar; Samejima, Hiroto; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, to Gebr. Bohler & Co. Aktiengesellschaft Kyowa Hakko Kogyo Kabushiki Kaisha. Foodstuffs containing an anti-Electrical component clamping device in an electro-melting installation for metals oxidant. 3,579,357, Cl. 13-16.
 Klemm, Le Roy H.; Shabta, Joseph; and Mc Coy, David R., to Research Corporation, mesne. Preparation of thienopyridines. 3,579,526, Cl. 260-294.8.
 Kline, Richard M.: See—
 Raun, Arthur P.; and Kline, Richard M., 3,579,635.
 Kliphuis, Harmannus: See—
 Dijkhuizen, Willem; Kliphuis, Harmannus; and Lolkema, Jan, 3,579,471.
 Kloven, Gerald P., to Ramsey Engineering Company. Totalizer for integrating the product of two variables with digital registration. 3,578,955, Cl. 235-92.
 Knapsack Aktiengesellschaft: See—
 Zahn, Paul; and Merges, Veit, 3,579,388.
 Knauert, William F., to Sonotone Corporation. Miniature multiple-diaphragm acoustic mechano-electric transducer device. 3,578,921, Cl. 179-139.
 Knirsch, Herbert, to Schlumberger Overseas Messgeratebau und Vertrieb GmbH. Frequency mixer. 3,579,116, Cl. 325-439.
 Knott, Robert L.; and Hadel, Donald H. Music responsive light power current switching device. 3,579,187, Cl. 340-148.
 Knutrud, Thorleif: See—
 Johannessen, Paul R.; and Knutrud, Thorleif, 3,579,093.
 Johannessen, Paul R.; and Knutrud, Thorleif, 3,579,111.
 Kobayashi, Kengo: See—
 Inaba, Seiemon; Shimizu, Kanryo; Hashimoto, Yoshihiro; and Kobayashi, Kengo, 3,579,279.
 Kobayashi, Takeji: See—
 Kusuda, Zenji; and Kobayashi, Takeji, 3,578,754.
 Kobayashi, Tatsuo; and Tsujimoto, Kayoshi, to Minolta Camera Kabushiki Kaisha. Electric eye camera. 3,578,765, Cl. 95-10.
 Kobayashi, Yugo, to Kabushiki Kaisha Ricoh. Copy paper feeding device for use with photocopying machine. 3,578,861, Cl. 355-91.
 Koberstein, Edgar: See—
 Gilde, Dieter; and Koberstein, Edgar, 3,579,573.
 Kodaira, Nobuhisa; and Motegi, Norio. Apparatus for driving spindle for effecting false twisting of yarns. 3,578,751, Cl. 57-77.45.
 Koga, Hiroto; to Nippon Electric Company, Limited. D.C. restorer apparatus. 3,579,123, Cl. 328-164.
 Kogure, Motoo: See—
 Mavrovic, Ivo; Kogure, Motoo; and Hoshino, Shoichiro, 3,579,636.
 Koharchik, George M.: See—
 Corbett, William H.; Brunell, Albert D.; and Koharchik, George M., 3,579,263.
 Kohler, Bryan E.; and Dubin, Alan S., to California Institute of Technology. Frequency modulated optical spectrometer. 3,578,866, Cl. 356-74.
 Kolec, Robert F.: See—
 Siebol, George; and Kolec, Robert F., 3,578,762.
 Kondo, Yoshihiko, to Nippon Denso Company Limited. Transistor protecting circuit. 3,578,983, Cl. 307-202.
 Konishiroku Photo Industry Co., Ltd.: See—
 Mavrovic, Ivo; Kogure, Motoo; and Hoshino, Shoichiro, 3,579,636.
 Koons, Russell E., to RCA Corporation Monsanto Company. Single crystal zinc oxide and an electrophotographic plate made therefrom Corrugated board construction. 3,579,413, Cl. 161-135.

Koppy Tool Corporation: *See—*
De Gain, William J., 3,578,777.

Koptula, Milton M.: *See—*
Antista, Santo M.; Koptula, Milton M.; and Burggraf, Gerard L., 3,579,241.

Kordzinski, Stanley, deceased (by Kordzinski, Eileen, executrix); and Horn, Milton B., to Ashland Oil & Refining Company, mesne. Method of producing resins for use in adhesives. 3,579,490, Cl. 260-80.72.

Kowalski, Xavier, to Monsanto Company. Bleaching process. 3,579,287, Cl. 8-108.

Kozawa, Tokinori; Kuzuma, Noboru; and Miwa, Ichiro, to Hitachi, Ltd. Automatic gain control system radio receivers and the like. 3,579,114, Cl. 325-410.

Krapf, Rudolf: *See—*
Gross, Franz; and Krapf, Rudolf, 3,578,991.

Krause, Fritz: *See—*
Steenbeck, Max; and Krause, Fritz, 3,578,999.

Kremzner, Sigmunt J.; and Pasechnik, William. Singer-General Precision, Inc. Electromagnetic device. 3,579,161, Cl. 335-272.

Kroke, Hermann; and Raffalsky, Kurt, to Minimax Aktiengesellschaft, and Henkel & Cie. GmbH. Fire-extinguishing foam composition including a basic, nitrogenous compound. 3,579,446, Cl. 252-3.

Kruk, William J.: *See—*
Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., 3,579,317.

Krupit, Adolph E.: *See—*
Keogh, Thomas H.; and Krupit, Adolph E., 3,579,045.

Kuhn, Edward H.: *See—*
De Smidt, Woodrow A.; and Kuhn, Edward H., 3,578,933.

Kuhn, Wilhelm: *See—*
Shimura, Kimio; Wege, Hans; and Gast, Erich, 3,579,351.

Kuhnis, Hans Herbert; and Renner, Ulrich, to Geigy Chemical Corporation. 1-(4-Piperidyl)-butanones. 3,579,512, Cl. 260-240.

Kuhnis, Hans Herbert; and Renner, Ulrich, to Geigy Chemical Corporation. 1-(1-substituted-4-acetonyl-4-piperidyl)-1-butanones. 3,579,513, Cl. 260-240.

Kumpf, Henry W., Jr.: *See—*
Anders, Walter G.; and Kumpf, Henry W., Jr., 3,578,905.

Kuroda, Toshihiko; Sutani, Sotou; Nitta, Haruo; and Saito, Sadao, to Mitsubishi Petrochemical Co., Ltd. Method of manufacturing plated polypropylene shaped articles. 3,579,428, Cl. 204-30.

Kusters, Norbert L.; and Moore, William J. M., to Canadian Patents and Development Limited. Alternating current apparatus for measuring capacitance or phase angle. 3,579,101, Cl. 324-60.

Kusuda, Zenji; and Kobayashi, Takeji, to Matsushita Electronics Corporation. Defrosting controller for electric refrigerator. 3,578,754, Cl. 62-156.

Kutyla, John, to Clare, C. P., & Company. Armature structure for reed switches. 3,579,158, Cl. 335-151.

Kuzminsky, Irving; and Kauffman, Ray B., to Entron, Inc. Automatic gain control for multi-channel television systems. 3,578,898, Cl. 178-5.2.

Kuzuma, Noboru: *See—*
Kozawa, Tokinori; Kuzuma, Noboru; and Miwa, Ichiro, 3,579,114.

Kyowa Hakko Kogyo Co., Ltd.: *See—*
Nakayama, Kiyoshi; and Hagino, Hiroshi, 3,579,427.

Kyowa Hakko Kogyo Kabushiki Kaisha: *See—*
Kleinhagauer, Otmar; Samejima, Hirotoishi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.

Laboratorio Chimico Farmaceutico Giorgio Zoja S.p.A.: *See—*
Zoja, Giorgio, 3,579,586.

Laird, Edward E. Spooling apparatus. 3,578,794, Cl. 242-25.

Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, to Polaroid Corporation Kanagafuchi Boseki Kabushiki Kaisha. Multicolor diffusion transfer photographic products and processes with a developing composition Polyamide conjugate filament comprising a desensitizing agent. 3,579,414, Cl. 96-3.

Langley, Frank J., to Raytheon Company. Method of performing digital computations using multipurpose integrated circuits and apparatus therefor. 3,579,201, Cl. 340-172.5.

Lapple, Walter C.; and Poole, Edward M., to Babcock & Wilcox Company, The. Cyclonic fluid bed reactor. 3,578,798, Cl. 263-21.

Larkin, John M., to Texaco Inc. Preparation of dinitro alcohols. 3,579,594, Cl. 260-632.

Larsen, Raymond B., to Datel Corporation. Read-after-write verification of data on magnetic storage medium. 3,579,211, Cl. 340-174.1.

Larson, Kenneth N.: *See—*
Gregg, Roland S., Jr.; Danberg, Arnold S.; and Larson, Kenneth N., 3,579,196.

Lasky, Harold J. Mammographic X-ray apparatus and technique. 3,578,971, Cl. 250-50.

La Soudure Electrique Autogene, Procedes Arcos: *See—*
Schoumaker, Henry P.J.F.M.C., 3,578,943.

Laukaitis, Joseph F., to Eastman Kodak Company. Web speed control apparatus. 3,579,065, Cl. 318-314.

Laurent, Bernard, to Cometa S.A.R.L. Optical projector including photo-sensitive device. 3,578,978, Cl. 250-221.

Lausch, Henry N.: *See—*
Halls, Lawrence M.; Lausch, Henry N.; and Schwalm, Bruce D., 3,578,750.

Lauver, Palmer R. Flashlight adapted for short-circuit testing. 3,579,100, Cl. 324-58.

Lawler, Philip E., to Western Electric Company, Incorporated. Apparatus for electroplating wire. 3,579,430, Cl. 204-206.

Lawlor, Robert E., to Electro-Calmp Corporation. Terminal board electrical connector. 3,579,177, Cl. 339-198.

Lawrence, Ray V.: *See—*
Halbrook, Noah J.; and Lawrence, Ray V., 3,579,571.

Layman, Ralph Earl: *See—*
Petropoulos, John Christos; and Layman, Ralph Earl, 3,579,610.

Leach Corporation: *See—*
Schuessler, John C.; and Capol, Roman J., 3,578,928.

Leading Plywood: *See—*
Crawford, John H., 3,579,405.

Lear Siegler, Inc.: *See—*
Abend, Irving J., 3,579,042.

Lebenbaum, Paul, Jr. Frequency conversion cycloconverter system for both single and multi-phase applications. 3,579,086, Cl. 321-60.

Le Dorh, Maurice F.: *See—*
Le Goffic, Yves H.; Le Dorh, Maurice F.; and Arnouat, Fernand R., 3,578,915.

Lee, Hanju: *See—*
Rosen, Harvey; Acker, Ellsworth G.; and Lee, Hanju, 3,579,464.

Lee, John T. M., to Atlas Chemical Industries, Inc. Safety and arming device. 3,578,767, Cl. 102-70.2.

Leebrick, John R., to Cosan Chemical Corporation. Phenylmercury compounds. 3,579,553, Cl. 260-434.

Le Goffic, Yves H.; Le Dorh, Maurice F.; and Arnouat, Fernand R. Telephone switching system employing time division and delta-modulation. 3,578,915, Cl. 179-15.

Legue, Ronald L.: *See—*
Hackman, Donald J.; Legue, Ronald L.; Harris, Jeremy M.; and Roop, Donald E., 3,579,037.

Lehnen, Robert J.: *See—*
Voyentzie, Peter R.; and Lehnen, Robert J., 3,579,387.

LeMarr, Wesley A.: *See—*
Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, 3,578,858.

Lemieux, Raymond Urgel; and Raap, Rintje, to R&L Molecular Research Ltd. α -Aminoisothiazolylacetic acids and their penicillin and cephalosporin derivatives. 3,579,506, Cl. 260-239.1.

Lenhard, Robert Herman: *See—*
Heller, Milton David; Lenhard, Robert Herman; and Bernstein, Seymour, 3,579,508.

Lerouge, Clade Paul Henri: *See—*
Girard, Pierre; Lerouge, Clade Paul Henri; and Regnier, Marc Andre, 3,579,232.

Lesuer, William M., to Lubrizol Corporation. The. Lubricants and fuels containing epoxide treated esters. 3,579,450, Cl. 252-56.

Lever Brothers Company: *See—*
Courts, Albert, 3,579,358.

Turner, Trevor Stanley; and Padley, Frederick Bolton, 3,579,383.

Levin, Robert E., to Sylvania Electric Products, Inc. Vehicle driving light. 3,578,966, Cl. 240-93.

Levine, Leonard; and Mc Fadden, Russell T., to Dow Chemical Company, The. 1-Allylthio-3-chloro-2-propanol. 3,579,592, Cl. 260-609.

Levinsky, Henry Leon: *See—*
Rubinfeld, Joseph; and Levinsky, Henry Leon, 3,579,537.

Levy, Alan J.: *See—*
Herz, Jack L.; Levy, Alan J.; Litt, Morton H.; and Zuckerman, Joseph L., 3,579,630.

Levy, Bernardo N.: *See—*
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.

Lewis, George L., 3,579,310, Cl.

Liebergott, Norman: *See—*
Yorston, Frederic H.; and Liebergott, Norman, 3,579,419.

Liechti, Peter: *See—*
Weber, Kurt; Liechti, Peter; Meyer, Rudolf; and Siegrist, Adolf Emil, 3,579,511.

Lilly, Eli, and Company: *See—*
Raun, Arthur P.; and Kline, Richard M., 3,579,635.

Lincoln, Andrew James, to Sperry Rand Corporation. Variable conduction threshold transistor memory circuit insensitive to threshold deviations. 3,579,204, Cl. 340-173.

Lincoln, Robert M.; Meyers, Joseph A., III; and Sauer, Richard W., to Atlantic Richfield Company. Epoxide taurine condensation products and detergent compositions containing them. 3,579,457, Cl. 252-137.

Lind, Francis E.: *See—*
Dempsey, Richard C.; and Lind, Francis E., 3,579,244.

Lindberg, Victor L.: *See—*
Irland, Max J.; and Lindberg, Victor L., 3,578,869.

Lindblad, Lars A.; and Kahlbom, Rune N., to Junger Instrument Aktiebolag. Apparatus for resetting an analog integrator. 3,579,125, Cl. 328-127.

Lipschutz, Paul, to Societe d'Exploitation des Brevets Neiman S.A. Signalling device to prevent leaving a key in a lock. 3,579,183, Cl. 340-52.

Litt, Morton H.: *See—*
Herz, Jack L.; Levy, Alan J.; Litt, Morton H.; and Zuckerman, Joseph L., 3,579,630.

Littell, Ruddy; and Allen, George Rodger, Jr., to American Cyanamid Company. Tetrahydrocarbazolecarboxylates. 3,579,534, Cl. 260-315.

Littwin, Arthur K. Magnetizing and demagnetizing apparatus and method. 3,579,053, Cl. 317-157.5.

Lloyds (Burton) Limited: *See—*
Clymer, Frank, 3,578,823.

Lobaugh, Rollin J., Inc.: *See—*
Berardy, James E.; and Weinstein, David A., 3,579,266.

Loboda, Jon: *See—*
Muzyczko, Thaddeus M.; Ludwig, William J.; Loboda, Jon; and Shore, Samuel, 3,579,447.

Loeffler, George F.: *See—*
Casey, Thomas J.; and Loeffler, George F., 3,579,217.

Logan, Lewis J. Machine for welding studs for beams. 3,579,260, Cl. 219-98.

Logan, Ted Joe: *See—*
Wann, Robert Earl; Nicholson, Denzel Allan; and Logan, Ted Joe, 3,579,449.

Lolkema, Jan: *See—*
Dijkhuizen, Willem; Kliphuis, Harmannus; and Lolkema, Jan, 3,579,471.

Lombard, Claude Edmond; Maurice, Jean Henri; and Piret, Jean, to Regie National des Usines Renault, and Automobiles Peugeot. Engine starter control circuits. 3,578,981, Cl. 290-38.

Long, Emile David; and Aumick, Kenneth Donald, to Gillett Tool Co. Spring actuated fuel pump for fuel injection systems. 3,578,879, Cl. 417-62.

Lord, Michael Robert, to International Standard Electric Corporation, mesne. Loop current detector. 3,579,106, Cl. 324-140.

Loustalet, Pierre; and Roujas, Guy, to French State, The. Extractor for an umbilical connector of a rocket. 3,578,783, Cl. 185-37.

Lovelace, Ralph E., to Sylvania Electric Products, Inc. Video signalling processing apparatus with noise protection. 3,579,251, Cl. 178-7.3.

Lowell, Arthur I., to Mobil Oil Corporation. Suspension system for producing high impact rene. 3,579,612, Cl. 260-880.

LTV Ling Altec, Inc.: *See—*
Irvine, Robert G., 3,579,129.

Ross, James A., 3,579,132.

Lubrizol Corporation, The: *See—*
Lesuer, William M., 3,579,450.

Lucas, Pierre M.; Duquesne, Jean F.; Berger, Jean-Pierre L.; and Courtois, Roger L. Computer controlled switching system using flip-flops for control of repetitive operations. 3,578,918, Cl. 179-18.

Lucas, Pierre M.; and Rouzier, Michel M. Telephone switching systems. 3,578,916, Cl. 179-186.

Luden, Alfred J., to Bureau of Engraving, Inc. Apparatus and method for measuring the amount of a selected vapor in an atmosphere. 3,579,097, Cl. 324-30.

Ludwig, William J.: *See—*
Muzyczko, Thaddeus M.; Ludwig, William J.; Loboda, Jon; and Shore, Samuel, 3,579,447.

Ludwig, Winfried: *See—*
Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.

Luksas, Anthony J.; and Guillet, Hubert, to Beatrice Foods Co. Commissariat a l'Energie Atomique. Preparation of an elastic cheese product Diaphragm for a laser amplifier chain. 3,578,849, Cl. 350-321.

Luques, Stanley F.: *See—*
Brown, Martin Granger; Van Berkel, Franciscus C.A.A.; and Luques, Stanley F., 3,579,379.

Lyall Electric, Inc.: *See—*
Shroyer, Larry L., 3,579,175.

Lynch Communication Systems, Inc.: *See—*
Simonelli, Richard A., 3,578,914.

Lynch, Leslie S., to Thomas & Betts Corporation. Electrical connector with fusible plug means and heating material. 3,578,896, Cl. 174-84.

Lynn, John W.: *See—*
Brotherton, Thomas K.; and Lynn, John W., 3,579,482.

MacDermid Incorporated: *See—*
Grunwald, John J.; and D'Ottavio, Eugene D., 3,579,365.

MacDougall, Richard Donald: *See—*
Breitbord, Jacob Louis; and MacDougall, Richard Donald, 3,578,860.

Machamer, George A. Multi-stage power amplifier in which each stage conducts for only a predetermined portion of the input. 3,579,136, Cl. 330-30.

Machenschalk, Rudolf: *See—*
Hennig, Walter; Sedlatschek, Karl; and Machenschalk, Rudolf, 3,579,022.

Machnacz, Henry F.: *See—*
Wonilowicz, Edmund; Cann, Everett Douglas; and Machnacz, Henry F., 3,579,296.

MacKenzie, Robert C.: *See—*
Bender, Warren G.; and MacKenzie, Robert C., 3,578,911.

Mackie, William L.: *See—*
Hood, Harrison P., III; Mackie, William L.; and Wilson, Edgar D., 3,579,411.

Mackway, Harold Jessup, to RCA Corporation. Push button mechanism. 3,579,160, Cl. 335-206.

Maclean, George: *See—*
Milford, Richard E.; and Maclean, George, 3,578,953.

Madsen, Eric V., to Bell Telephone Laboratories, Incorporated. Switching regulator with rapid switching drive. 3,579,090, Cl. 323-22.

Maeda, Haruo: *See—*
Nishino, Tsutomu; Kinoshita, Kokiti; and Maeda, Haruo, 3,579,009.

Maeder, Arthur: *See—*
Nachbur, Hermann; Stark, Bernard Peter; and Maeder, Arthur, 3,579,532.

Magnavox Company, The: *See—*
Nelson, Alfred M., 3,579,250.

Mahon, Arthur F.: *See—*
Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,972.

Dooley, Harry H.; Doda, Robert J.; and Mahon, Arthur F., 3,578,973.

Maier, Volker Elmar: *See—*
Dewar, Robert Alfred; Maier, Volker Elmar; and Ingram, Margaret Anthea, 3,579,530.

Makimoto, Kuninobu: *See—*
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.

Malmer, Michael M., Jr., to Burroughs Corporation. Recirculating buffer memory. 3,579,203, Cl. 340-173.

Maloney, Jim N., Jr.; and Smith, Ralph W., to Monsanto Company. Preparation of quaternary ammonium hydroxides. 3,579,581, Cl. 260-567.6.

Mandzu, Jozsef; and Csaszar, Erno, to Fok-Gyem Finommechanikai Es Elektronikus Muszergyarto. Method and apparatus for transmitting information. 3,579,265, Cl. 235-61.11.

Manning, Robert E.: *See—*
Houlihan, William J.; and Manning, Robert E., 3,579,517.

Manson, Frank E.; and Steinbrecher, Lester, to Amchem Products, Inc. Process for applying a white paint electrophoretically. 3,579,429, Cl. 204-181.

Manthei, William J., to Kelsey-Hayes Company. Throw-away tool insert. 3,578,742, Cl. 29-96.

Manthey, Dieter: *See—*
Ashauer, Karl; and Manthey, Dieter, 3,578,784.

Mapes, Robert S.: *See—*
Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,578,904.

Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,579,249.

Marathon Oil Company: *See—*
Norton, Charles J., 3,579,546.

Storms, Phillip W.; and Farrar, Grover L., 3,579,563.

Margulies, Howard: *See—*
Miller, Bernard; and Margulies, Howard, 3,579,614.

Marlowe, Mickey O.: *See—*
United States of America, National Aeronautics and Space Administration, Administrator, 3,579,390.

Marotta, Nicholas G.: *See—*
Trubiano, Paolo C.; and Marotta, Nicholas G., 3,579,341.

Marshall, David J.; and Failli, Amedeo A., to American Home Products Corporation. 7 α ,8 α -Difluoromethylene steroids. 3,579,507, Cl. 260-239.5.

Martell, Michael Joseph: *See—*
Hlavka, Joseph J.; Bitha, Panayota; Ross, Adma Schneller; and Martell, Michael Joseph, 3,579,579.

Martin, Richard D.: *See—*
Mishkin, Abraham R.; Martin, Richard D.; and Ohler, Joseph L., 3,579,349.

Martin-Marietta Corporation: *See—*
Purcell, William O., Jr.; and Trippe, Walter D., 3,579,239.

Martinez, Wilda H.; and Berardi, Leah C., to United States of America. Agriculture. Selective extraction process producing protein isolates from oilseed meals using water or divalent metal salts as extracting agents. 3,579,496, Cl. 260-123.5.

Maschinenfabrik Reinhausen Gebruder Scheubeck K.G.: *See—*
Matzl, Manfred, 3,579,092.

Maschinenfabrik und Giesserei Netstal AG: *See—*
Blumer, Armin, 3,578,741.

Mason, Anthony; and Cobb, Clifton A., to Whirlpool Corporation. Reset and adjustment mechanism for a pressure responsive switch. 3,579,284, Cl. 200-83.

Mason, Donald J.: *See—*
Argoudelis, Alexander D.; Coats, John H.; Mason, Donald J.; and Sebek, Oldrich K., 3,579,426.

Massa Division, Dynamics Corporation of America: *See—*
Massa, Frank, 3,578,994.

Massa, Frank, 3,578,995.

Massa, Frank, 3,579,181.

Massa, Frank, to Massa Division, Dynamics Corporation of America. Piezoelectric clamped-free beam type transducer. 3,578,994, Cl. 310-8.6.

Massa, Frank, to Massa Division, Dynamics Corporation of America. Transducers of the bilaminar flexural vibrating type. 3,578,995, Cl. 310-8.8.

Massa, Frank, to Massa Division, Dynamics Corporation of America. Sonar ranging system for locating submerged objects. 3,579,181, Cl. 340-3.

Massachusetts Institute of Technology: *See—*
Euerle, William C., 3,578,998.

- Mathe, George L.: *See—*
Thomson, Richard N.; Osmalov, Jerome S.; and Mathe, George L., 3,579,623.
- Mathews, Joseph W. Suspended motor vibratory apparatus. 3,579,000, Cl. 310-15.
- Mathis, Ronald D.: *See—*
Dunn, Howard E.; and Mathis, Ronald D., 3,579,478.
- Matsui, Masao: *See—*
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
- Matsushita Electric Industrial Co., Ltd.: *See—*
Hata, Kotaro; and Fujii, Toshikazu, 3,578,829.
- Wasa, Kiyotaka; and Hayakawa, Shigeru, 3,579,063.
- Matsushita Electric Industrial Company Limited: *See—*
Nishino, Tsutomu; Kinoshita, Kokiti; and Maeda, Haruo, 3,579,009.
- Matsushita Electronics Corporation: *See—*
Kusuda, Zenji; and Kobayashi, Takeji, 3,578,754.
- Matsuya, Yutaka: *See—*
Yamane, Isao; Matsuya, Yutaka; and Jimbo, Katsuhiko, 3,579,423.
- Mattel, Inc.: *See—*
Woodward, Arthur S., 3,579,171.
- Matthew Machine Company, Inc.: *See—*
Matthews, Ernest L.; and Matthews, Ralph E., 3,578,778.
- Matthews, Ernest L.; and Matthews, Ralph E., to Matthew Machine Company, Inc. Packaging apparatus for filling individual containers. 3,578,778, Cl. 141-144.
- Matthews, Ralph E.: *See—*
Matthews, Ernest L.; and Matthews, Ralph E., 3,578,778.
- Matzl, Manfred; to Maschinenfabrik Reinhausen Gebrüder Scheubeck K.G. Tap-changing regulating transformer with solid state circuitry. 3,579,092, Cl. 323-43.55.
- Matzner, Markus; and Noshay, Allen, to Union Carbide Corporation. Polyester-substituted organosilicon compositions. 3,579,607, Cl. 260-824.
- Maurice, Jean Henri: *See—*
Lombard, Claude Edmond; Maurice, Jean Henri; and Piret, Jean, 3,578,981.
- Mautz, Karlheinz; to Bolkow Gesellschaft mit beschränkter Haftung. Rotor construction with elastic interconnection of opposite blades. 3,578,877, Cl. 416-134.
- Mavrovic, Ivo; Kogure, Motoo; and Hoshino, Shoichiro, to Konishiroku Photo Industry Co., Ltd. Urea synthesis process Photoreis-forming compositions. 3,579,636, Cl. 96-90.
- McBurnie, Thomas W., to Air Instruments, Inc. Speed and torque control for surgical turbine. 3,578,872, Cl. 415-25.
- McCall, Amiel J., to Allen-Bradley Company, mesne. Phase modulator of two dynamic counters. 3,578,956, Cl. 235-92.
- McConnell, Richard L.; and Joyner, Frederick B., to Eastman Kodak Company. Maleated polyolefins. 3,579,486, Cl. 260-78.4.
- Mc Coy, David R.: *See—*
Klemm, Le Roy H.; Shabtai, Joseph; and Mc Coy, David R., 3,579,526.
- McCoy, John J., to General Electric Company. 3,579,311, Cl. 148-6.15.
- Mc Coy, Marion B., to National Cash Register Company, The. Crowbar circuit for voltage cut off with series and shunt switchable means. 3,579,036, Cl. 317-16.
- Mc Cready, Karl F.: *See—*
Rhyne, Theodore Lauer; and Mc Cready, Karl F., 3,579,246.
- Mc Cready, Newton W.: *See—*
Sams, Robert H.; and Mc Cready, Newton W., 3,579,299.
- McDonald, Harold P., Jr. Urological endoscopic irrigation machine. 3,578,774, Cl. 128-227.
- McDonald, William S.: *See—*
Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., 3,579,317.
- McDonald, William T.: *See—*
Crocker, Weyman S.; White, Philip H.; and McDonald, William T., 3,579,070.
- Mc Fadden, Russell T.: *See—*
Levine, Leonard; and Mc Fadden, Russell T., 3,579,592.
- McFarland, James W., to Pfizer Inc. 3-(Hydroxy-phenyl) substituted amides and derivatives thereof as anthelmintic agents. 3,579,510, Cl. 260-240.
- McGrath, Walter R., Jr., to Hewlett-Packard Company. Horizontal Z-fold recorder. 3,579,248, Cl. 346-76.
- McGraw-Edison Company: *See—*
Radford, David L.; Frisby, Paul W.; and Filho, Francisco Muniz, 3,578,790.
- McGregor, Donald Neil, to Bristol-Myers Company. 6-[α -(3-guanyl-1-ureido)-phenyl- or thienyl- acetamido]penicillanic acids. 3,579,501, Cl. 260-239.1.
- McGregor, Donald Neil, to Bristol-Myers Company. 7-[α -(3-Guanyl-1-ureido)aryl-acetamido] cephalosporanic acids and derivatives thereof. 3,579,514, Cl. 260-243.
- McGuffin, August L.; and Philip, Ralph M., to General Electric Company. Stacked pulse-forming network switching circuit. 3,578,986, Cl. 307-246.
- McKaig, Arthur B. Transistorized monitoring circuit. 3,579,223, Cl. 340-248.
- McLean, Howard J.: *See—*
Dagne, Louis C.; McLean, Howard J.; and Bonner, George A., 3,578,889.
- McMillen, James W. Vehicle washing apparatus. 3,578,775, Cl. 136-45.
- McNair, Samuel L., to Songrand Corporation, The. Electrically heated hair curling instrument. 3,578,947, Cl. 219-226.
- Medical Products Corporation: *See—*
Ostensen, Ralph G., 3,579,269.
- Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevrak, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich. Method of electroslag welding. 3,578,938, Cl. 219-73.
- Medtronic, Inc.: *See—*
Anderson, Robert K., 3,579,135.
- Mehner, Gottfried, to Conduco A.G. Method and apparatus for forming hollow plastic articles. 3,579,621, Cl. 264-99.
- Meiring, Pieter Gerhard Jacobus; and Huisman, Peter Hendrik, to South African Inventions Development Corporation. Treatment of sewage. 3,579,439, Cl. 210-5.
- Melle-Bezons: *See—*
Bouniot, Albert, 3,579,575.
- Meltsner, Bernard R., to Ethyl Corporation. Hydroxybenzyl-substituted bis-phenyl carbonates. 3,579,561, Cl. 260-463.
- Merges, Veit: *See—*
Zahn, Paul; and Merges, Veit, 3,579,388.
- Merlin Gerin Societe Anonyme: *See—*
Pelenc, Yves F., 3,579,001.
- Merrrow, George W.; and West, Robert F., to Stanley Works, The. Hand tool. 3,578,825, Cl. 306-32.
- Meschi, Joseph E.: *See—*
Bartlett, Peter G.; and Meschi, Joseph E., 3,579,207.
- Messerschmitt-Bolkow-Blohm: *See—*
Tiefenthaler, Wolfgang, 3,578,930.
- Mesur-Matic Electronics Corporation: *See—*
Newell, Harold R., 3,579,276.
- Metaframe Corporation: *See—*
Bleiweiss, Eugene; Soignet, Donald M.; and Benerito, Ruth R., 3,579,289.
- Metallgesellschaft Aktiengesellschaft: *See—*
Reh, Lothar; Rosenthal, Karlheinz; and Schmidt, Hans Werner, 3,579,616.
- Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., to American Hoechst Corporation. Substituted bis(2-hydroxy-4-methyl-5-methylthiophenyl) methanes. 3,579,538, Cl. 260-330.5.
- Meyer, Ronald J.; Horsley, Orville E.; and Eichel, Herman J., to American Hoechst Corporation. 4,4'-Trihydroxytriphenylmethylmethane. 3,579,542, Cl. 260-395.
- Meyer, Rudolf: *See—*
Weber, Kurt; Liechti, Peter; Meyer, Rudolf; and Siegrist, Adolf Emil, 3,579,511.
- Meyers, Joseph A., III: *See—*
Lincoln, Robert M.; Meyers, Joseph A., III; and Sauer, Richard W., 3,579,457.
- Michaud, David E.; and Hakanson, Nils L., to Plastic Coating Corporation, The. Variable width corona discharge apparatus with means to shield or vary a predetermined length of a corona discharge wire. 3,578,970, Cl. 250-49.52.
- Miki, Takuichi: *See—*
Hiraga, Kentaro; Asako, Tsunehiko; and Miki, Takuichi, 3,579,544.
- Milch, Alfred: *See—*
Schjolberg, Eiler; Zwicker, Walter K.; and Milch, Alfred, 3,579,359.
- Miles Laboratories, Inc.: *See—*
Van Dyke, John William, Jr., 3,579,524.
- Milford, Richard E.; and Maclean, George, to Honeywell Information Systems Inc., mesne. System for reading intermixed marks and symbols from documents. 3,578,953, Cl. 235-61.11.
- Miller, Bernard; and Margulies, Howard, to American Cyanamid Company. 2-Cyanovinyl phosphates and phosphorothioates. 3,579,614, Cl. 260-940.
- Miller, Donald E.: *See—*
Stillings, William K.; Miller, Donald E.; and Gilmore, Cecelia R., 3,579,356.
- Miller, Keith A., to Air Products and Chemicals, Inc. Variable flame oxy-fuel burner. 3,578,793, Cl. 239-132.3.
- Millet, Jacques: *See—*
Tamise, Louis; and Millet, Jacques, 3,579,295.
- Tamise, Louis; Dennilauler, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.
- Millis, Walter T., to Philadelphia Quartz Company General Electric Company. Porous silicate Method of coating an electric discharge device. 3,579,378, Cl. 117-229.
- Milwaukee Boiler Manufacturing Company: *See—*
Stevens, Richard W., 3,578,752.
- Minick, David G.; and Sinclair, David H., to Sinclair Company, The. Starches. 3,579,422, Cl. 99-83.
- Minimax Aktiengesellschaft: *See—*
Kroke, Hermann; and Raffalsky, Kurt, 3,579,446.
- Minnesota Mining and Manufacturing Company: *See—*
Sevenich, Robert J., 3,579,609.
- Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, to Furuno Electric Company Ltd. Multi-stylus pen recording system. 3,579,247, Cl. 346-35.

- Minolta Camera Kabushiki Kaisha: *See—*
Kobayashi, Tatsuo; and Tsujimoto, Kayoshi, 3,578,765.
- Mishkin, Abraham R.; Martin, Richard D.; and Ohler, Joseph L., to Societe d'Assistance Technique pour Produits Nestle S.A. Preparation of chocolate extract. 3,579,349, Cl. 99-23.
- Mitchell, John E., Company: *See—*
Freeman, William P., Jr., 3,578,753.
- Mito, Satoru; Kawai, Mitsuo; and Yoshida, Hiroshi. High strength plastic coated fiber yarn fabric for structural reinforcement. 3,579,329, Cl. 161-39.
- Mitsubishi Petrochemical Co., Ltd.: *See—*
Kuroda, Toshihiko; Sutani, Sotou; Nitta, Haruo; and Saito, Sadao, 3,579,428.
- Miu, Ming-Tzer, to Honeywell Inc. Pre-conditioned divisor to expedite division by successive subtraction. 3,578,961, Cl. 235-159.
- Miwa, Ichiro: *See—*
Kozawa, Tokinori; Kuzuma, Noboru; and Miwa, Ichiro, 3,579,114.
- Miya, Masao, to Nippon Electric Company, Limited. Gas laser tube. 3,579,141, Cl. 331-94.5.
- Miyamoto, Masuo; and Murata, Tadakazu, to Takeda Chemical Industries, Ltd. Alisol compounds. 3,579,505, Cl. 260-239.55.
- Miyaoka, Senri, to Sony Corporation. Color tube having asymmetrical electrostatic convergence correction system. 3,579,008, Cl. 313-79.
- Miyata, Tomoyoshi: *See—*
Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, 3,579,247.
- Miyoshi, Takeomi, to Honda Giken Kogyo Kabushiki Kaisha. Apparatus for the retraction of a steering wheel of a vehicle in the event of a front end collision thereof. 3,578,782, Cl. 180-82.
- Mobil Oil Corporation: *See—*
Bullard, Edward M., 3,579,539.
- Lowell, Arthur I., 3,579,612.
- Scheiner, Peter, 3,579,531.
- Smith, Robert B.; and Rope, Barton W., 3,579,434.
- Traver, Alfred E., 3,578,865.
- Moergeli, Eduard, to Ciba Limited. Anthrapyrimidine-substituted anthraquinone amides. 3,579,518, Cl. 260-256.4.
- Molex Incorporated: *See—*
Baumanis, Bruno; and Sebastian, Robert W., 3,579,170.
- Molins Machine Company, Limited, The: *See—*
Davis, Peter Grant, 3,578,799.
- Monsanto Chemicals Limited: *See—*
Chilton, Henry Thomas Joseph; and Burns, Patricia Gertrude, 3,579,462.
- Monsanto Company: *See—*
Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,551.
- Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,552.
- Cruse, Carl M., 3,579,438.
- Franz, Raymond A., 3,579,521.
- Gregory, Robert O., 3,579,015.
- Kerst, Al F., 3,579,444.
- Koons, Russell E., 3,579,413.
- Kowalski, Xavier, 3,579,287.
- Maloney, Jim N., Jr.; and Smith, Ralph W., 3,579,581.
- Pettersson, Lennart K., 3,579,620.
- Rath, Paul S.; Dyott, Richard Burnaby; and Clark, George Archer, 3,579,316.
- Sears, James K.; Andrae, John Hugh; Gaines, Brian Ronald; and White, Peter, 3,579,191.
- Sears, James K., 3,579,364.
- Shaw, Charles H.; and Strauss, Robert G., 3,579,622.
- Monsay, John, to RCA Corporation. Apparatus for synchronized generation of a signal from a composite color video signal subjected to signal perturbations. 3,578,902, Cl. 178-5.4.
- Montgomery, Stewart R.; and Hillmann, Melville E., to Grace, W. R., & Co. Preparation of vinyl acetate. 3,579,569, Cl. 260-497.
- Mooney Brothers Corporation: *See—*
Dutton, Lloyd K., 3,578,805.
- Moore, Michael, to American Electronic Laboratories, Inc. Interdigital stripline filter means with thin shorting shim. 3,579,152, Cl. 333-73.
- Moore, William J. M.: *See—*
Kusters, Norbert L.; and Moore, William J. M., 3,579,101.
- Moran, Clifford M.: *See—*
Vail, Sidney L.; Pierce, Andrew G., Jr.; Moran, Clifford M.; and Barker, Robert H., 3,579,536.
- Morat, Franz, G.m.b.H.: *See—*
Schunack, Johannes, 3,578,976.
- Stock, Hans Joachim, 3,578,897.
- Stock, Hans Joachim; and Gottschall, Gernot, 3,578,907.
- Moratz, Clyde C., to Controls Company of America. Electric heat sequence control. 3,578,950, Cl. 219-486.
- Moreau, Jack: *See—*
Burnier, Pierre; and Moreau, Jack, 3,579,035.
- Morey, Fred E., III; and Mork, George B., to Gulf & Western Industries, mesne. Electro-magnetically clutched reset timer. 3,578,923, Cl. 200-38.
- Mork, George B.; and Morse, Donald J., to Gulf & Western Industries. Reversible programmer for electric circuits. 3,579,264, Cl. 219-486.
- Mork, George B.: *See—*
Morey, Fred E., III; and Mork, George B., 3,578,923.
- Morris, Philips, Incorporated: *See—*
Thomson, Richard N.; Osmalov, Jerome S.; and Mathe, George L., 3,579,623.
- Morrison Products, Inc.: *See—*
Ross, Richard V., 3,578,878.
- Morse, Donald J.: *See—*
Mork, George B.; and Morse, Donald J., 3,579,264.
- Mortgage Production Inc.: *See—*
Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, 3,578,858.
- Motegi, Norio: *See—*
Kodaira, Nobuhisa; and Motegi, Norio, 3,578,751.
- Motorola, Inc.: *See—*
Goncharoff, Nikolai; and Jabbar, Kamil Y., 3,579,115.
- Jabbar, Kamil Y.; and Nilssen, Ole K., 3,579,113.
- Mougne, Marcel L., to Dresser Industries, Inc. Method and combination well logging apparatus for conducting both deep and shallow investigation of the formations surrounding a borehole. 3,579,098, Cl. 324-10.
- Moulin, Norbert L.: *See—*
Bokor, Michael; and Moulin, Norbert L., 3,579,176.
- Moulton, David S. Gravimeter utilizing mass of ions. 3,579,054, Cl. 317-231.
- Mounce, William R., to Cities Service Research and Development Company. Multi-stage conversion process. 3,579,436, Cl. 208-59.
- Moutaud, Gilberte: *See—*
Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilberte, 3,579,401.
- Mowbray, Dorian Parrar; and Kemp, Kenneth Albert Walters, to C.A.V. Limited. Liquid fuel pumping apparatus for supplying fuel to an internal combustion engine. 3,578,881, Cl. 417-206.
- Moyer, Elmo E., to Atto Laboratories, Inc. Ferro-resonant power device. 3,579,084, Cl. 321-16.
- MPO Videotronics, Inc.: *See—*
Jensen, Christian, 3,578,851.
- Muendel, Carl H.; Howell, George D.; and Ayres, Robert F., to Du Pont de Nemours, E. I., and Company Electrolyx Corporation, mesne. Preparing acicular titanium dioxide from rutile TiO₂. High free-acid iron phosphate conversion coating composition and method. 3,579,389, Cl. 23-301.
- Muller, Marcel; and Zeller, Paul, to Hoffmann-La Roche, Inc. Process for preparing tetrahydro[2,1-d]-benzo[f][1,4]-diazepin-6(7H)-ones and intermediates. 3,579,502, Cl. 260-239.3.
- Muller, Walter: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.
- Mullhaupt, Joseph T.: *See—*
Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silviu A., 3,579,292.
- Mullin, Charles R.; and Wymore, C. Elmer, to Dow Chemical Company, The. Hydrogenolysis of carbon tetrachloride and chloroform. 3,579,596, Cl. 260-658.
- Multicup Automation Company, Inc.: *See—*
Ehe, Albert L.; and Pesses, Marvin, 3,579,399.
- Mundinger, William D.; and Nagy, Ernest J., to Pullman Incorporated. Material discharge arrangement for hopper structures. 3,578,815, Cl. 302-52.
- Murata, Tadakazu: *See—*
Miyamoto, Masuo; and Murata, Tadakazu, 3,579,505.
- Murphy, Frank T.; Clark, Norman R.; and Casey, William E., to Williams Electronic Manufacturing Corporation. Vertically adjustable bumper for ball rolling games. 3,578,802, Cl. 273-129.
- Murphy, Frank W., Jr.: *See—*
Murphy, Frank W.; and Murphy, Frank W., Jr., 3,578,931.
- Murphy, Frank W.; and Murphy, Frank W., Jr. Self-cleaning electrical switch contact. 3,578,931, Cl. 200-166.
- Muzyczko, Thaddeus M.; Ludwig, William J.; Loboda, Jon; and Shore, Samuel, to Richardson Company, The. Method of removing copper deposits from ferrous metal surfaces using hydroxyalkyl thiourea. 3,579,447, Cl. 252-87.
- N/A: *See—*
Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., 3,579,412.
- Nachbur, Hermann; Stark, Bernard Peter; and Maeder, Arthur, to Ciba Limited. Bis-phosphono-propionamide substituted ethylene glycols and imidazolidinones. 3,579,532, Cl. 260-309.7.
- Nadella: *See—*
Pitner, Alfred, 3,578,830.
- Nagano, Yuji: *See—*
Kleinhaugauer, Otmar; Samejima, Hirotohi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.
- Nagy, Ernest J.: *See—*
Mundinger, William D.; and Nagy, Ernest J., 3,578,815.
- Nakano, Takashi: *See—*
Ito, Yoshiro; Ueno, Tamotsu; Nakano, Takashi; and Okamoto, Kazuo, 3,579,599.
- Nakayama, Kiyoshi; and Hagino, Hiroshi, to Kyowa Hakko Kogyo Co., Ltd. Process for producing methionine decarboxylase. 3,579,427, Cl. 195-66.
- Nakayama, Kiyoshi: *See—*
Kleinhaugauer, Otmar; Samejima, Hirotohi; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.

Nakel, Gunther M.; and Dirks, Brinton Marlo, to Proctor & Gamble Company, The. Skid control system Food products containing alkyl-substituted pyrazines. 3,579,353, Cl. 303-21.

Natelson, Samuel, to Rohe Scientific Corporation. Reflection tests having photocell with aperture. 3,578,977, Cl. 250-219.

Nather, Roy E.: See—
Georgi, Heinz W.; and Nather, Roy E., 3,578,960.

National Cash Register Company, The: See—
Churchill, Donald; and Cartmell, James V., 3,578,844.

Colello, William L., 3,578,946.

Mc Coy, Marion B., 3,579,036.

National Research Corporation: See—
Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.

National Semiconductor Corporation: See—
Widlar, Robert J., 3,579,059.

National Starch and Chemical Corporation: See—
Stockmann, Hans H.; Ray-Chaudhuri, Dilip K.; and Boettger, Richard M., 3,579,549.

Trubiano, Paolo C.; and Marotta, Nicholas G., 3,579,341.

Naubereit, Henry, to United States of America, Navy. Pulse generator timing circuits. 3,578,990, Cl. 307-293.

Neiman, William T.: See—
Woniowicz, Edmund; Cann, Everett Douglas; and Machnacy, Henry F., 3,579,296.

Nelson, Alfred M., to Magnavox Company, The. Production of latent images by curie point recording. 3,579,250, Cl. 178-6.6

Nelson, Robert F.: See—
Hufendick, William Rowe; and Nelson, Robert F., 3,579,394.

Nelson, Rolland D., to RTE Corporation. Corrosion protection for metal enclosures for electrical equipment. 3,578,982, Cl. 307-95.

Nepveu, Raymond R.: See—
Whitney, David J.; and Nepveu, Raymond R., 3,579,151.

Neti, Radhakrishna M.; and Abens, Sanders G., to Beckman Instruments, Inc. Honeywell Inc. Scrubber apparatus Electric current-producing cells. 3,579,384, Cl. 136-100.

Newell, Harold R., to Mesur-Matic Electronics Corporation. Harmonic drive for digital step motor. 3,579,276, Cl. 310-82.

Newstead, Gordon, to Bolton, R. B., (Minning Engineers) Limited. Cable handler troughs. 3,578,810, Cl. 299-43.

Nicholson, Denzel Allan; and Campbell, Darrel, to Procter & Gamble Company, The. Ethane-1,2-dicarboxy-1,2-dihydroxy-1,2-diphosphonic acid, lower alkyl esters, alkali metal salts thereof and process for preparing same. 3,579,570, Cl. 260-502.4

Nicholson, Denzel Allan: See—
Wann, Robert Earl; Nicholson, Denzel Allan; and Logan, Ted Joe, 3,579,449.

Niehaus, Clemens: See—
Bendszus, Otto; Niehaus, Clemens; and Patheiger, Manfred, 3,579,522.

Niezoldi & Kramer GmbH: See—
Roth, Johann; Roppel, Alfred; and Steibl, Theodor, 3,578,853.

Roth, Johann, 3,578,854.

Nihei, Seiji: See—
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.

Nikawitz, Edward J.; and Walter, George R., to Gifaudan Corporation. 3,4-Dihalo-3' and 4'-lower alkylcarbanilides. 3,579,578, Cl. 260-553.

Nilssen, Ole K.: See—
Jabbar, Kamal Y.; and Nilssen, Ole K., 3,579,113.

Nino, Victor J., to Texas Petroleum Company. Downhole producing pump. 3,578,886, Cl. 417-495.

Nippon Denso Company Limited: See—
Kondo, Yoshihiko, 3,578,983.

Nippon Denso Kabushiki Kaisha: See—
Kato, Takaaki; and Kawakubo, Mamoru, 3,579,052.

Nippon Electric Company, Limited: See—
Koga, Hirotooshi, 3,579,123.

Miya, Masao, 3,579,141.

Nippon Roca Pipes Co., Ltd.: See—
Kato, Shigeru, 3,579,259.

Nishino, Tsutomu; Kinoshita, Kokiti; and Maeda, Haruo, to Matsushita Electric Industrial Company Limited. Electron gun assembly including two part threaded electrode. 3,579,009, Cl. 313-83.

Nisso Kinzoku Kabushiki Kaisha: See—
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.

Nitro Nobel Aktiebolag: See—
Pryor, Michael J.; Enoksson, Bertil Petrus; and Anthony, William H., 3,579,392.

Nitta, Haruo: See—
Kuroda, Toshihiko; Sutani, Sotou; Nitta, Haruo; and Saito, Sadao, 3,579,428.

Noble, Bruce P. Homopolar dynamoelectric apparatus. 3,579,005, Cl. 310-178.

Noble, Lowell A.; and Hanley, Robert B., to Varian Associates, mesne. Art of making vacuum envelopes. 3,578,835, Cl. 316-25.

Nockey, Charles R.: See—
Cronin, Donald L.; Farber, Bertrand F.; and Nockey, Charles R., 3,579,078.

Noltes, Jan Gerrit: See—
Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, 3,579,480.

Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, 3,579,481.

Nomine, Gerard; Bucourt, Robert; and Pierdet, Andre, to Roussel-UCLAF, S.A. Derivatives of $\Delta 4,9$ -gonadiene and process of preparation. 3,579,504, Cl. 260-239.55

Nord-Aviation Societe Nationale de Constructions Aeronautiques: See—
Auffret, Rene, 3,579,048.

Nordheim, Rolf: See—
Dowhan, Wesley P.; Aas, Helge; and Nordheim, Rolf, 3,579,328.

Nordholm, Lloyd P.: See—
Florance, Douglas A.; and Nordholm, Lloyd P., 3,579,280.

Norley, Ronald Richard, to RCA Corporation. Circuits using transistors to provide variable phase shift. 3,579,095, Cl. 323-108.

Norris, Walter E.; and Shoap, Stephen D., to Bell Telephone Laboratories, Incorporated. Waveform generator. 3,579,117, Cl. 328-27.

North American Rockwell Corporation: See—
Haydl, William H., 3,579,143.

Polkinghorn, Robert W.; Pfeifer, Arthur F.; and Hartmann, Robert F., 3,579,275.

Northrop Corporation: See—
Rhyne, Theodore Lauer; and Mc Cready, Karl F., 3,579,246.

Northwest Engineering Corporation: See—
Brickett, Alan E.; and Windahl, Everett R., 3,578,787.

Northwestern University: See—
Yau, Sik-Sang; and Tang, Calvin K., 3,579,119.

Norton, Charles J., to Marathon Oil Company. Organic sulfonate production by buffered addition of bisulfite to unsaturated hydrocarbons. 3,579,546, Cl. 260-400.

Noshay, Allen: See—
Matzner, Markus; and Noshay, Allen, 3,579,607.

Nothern Electric Company Limited: See—
Basu, Rabindra N.; and Dvorak, Alfred, 3,579,050.

Nozaki, Arthur T.: See—
Gilligan, Thomas J.; and Nozaki, Arthur T., 3,579,209.

Nozawa, Kazuo: See—
Okamoto, Noriaki; Wakabe, Teruo; and Nozawa, Kazuo, 3,578,920.

Nugteren, Diederik Hendrik: See—
Van Dorp, David Adriaan; Beerthuis, Roelof Karel; Nugteren, Diederik Hendrik; and Vonkeman, Hendrik, 3,579,425.

Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., to Bentley-Harris Manufacturing Company United States of America, Agriculture. Oven door seal and method of making same Extruder-cooked cereal endosperm particles and instant beverage mixes comprising the same. 3,579,352, Cl. 99-78.

N.V. 'COQ': See—
Boersma, Rintje, 3,578,924.

Oberdorf, Michel: See—
Amjedjan, Garabed; Fenoglio, Maurice; and Oberdorf, Michel, 3,579,572.

Obermann, George, to Controls Company of America. Snap switch. 3,578,926, Cl. 200-67.

O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, to Phillips Petroleum Company Siemens Aktiengesellschaft. Production of ammonium nitrate Method of producing tin or tin-alloy coated copper jump wire by means of hot metalizing. 3,579,377, Cl. 117-217.

Oceanautic Manufacturing and Research Company: See—
Hackman, Donald J.; Legue, Ronald L.; Harris, Jeremy M.; and Roop, Donald E., 3,579,037.

Ogden, Horace R.: See—
Bradley, Elihu F.; Bartlett, Edwin S.; Ogden, Horace R.; and Jaffee, Robert I., 3,578,743.

Oguri, Yoshiyuki. Rotary wing assembly. 3,578,875, Cl. 416-109.

O'Hara, John Henry, to United States of America, Army. Compensated sweep generator. 3,579,124, Cl. 328-181.

Ohkawahara, Tsuneo: See—
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.

Ohler, Joseph L.: See—
Mishkin, Abraham R.; Martin, Richard D.; and Ohler, Joseph L., 3,579,349.

Ohlhausen, Howard G. Method for protecting non-porous substrates and for rendering them water repellent. 3,579,540, Cl. 260-33.4

Ohmann, Helmut: See—
O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, 3,579,377.

Oishi, Naoyoshi: See—
Tsumura, Takao; Kaooka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.

Tsumura, Takao; Kaooka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.

Okada, Masaru: See—
Kawaguchi, Toshiiji; Tanaka, Takeo; and Okada, Masaru, 3,578,979.

Okamoto, Kazuo: See—
Ito, Yoshiro; Ueno, Tamotsu; Nakano, Takashi; and Okamoto, Kazuo, 3,579,599.

Okamoto, Noriaki; Wakabe, Teruo; and Nozawa, Kazuo, to Sony Corporation. Ferrite magnetic head with gap spacer of silicon oxide and metal oxides. 3,578,920, Cl. 179-100.2

Olenzak, Albert T.; and Thompson, Sheldon L., to Sun Oil Company. Hydrocracking process. 3,579,435, Cl. 208-59.

Olin Mathieson Chemical Corporation: See—
Pryor, Michael J.; Enoksson, Bertil Petrus; and Anthony, William H., 3,579,392.

Olsen, Robert M., to Vapor Corporation. Sensitive magnetic amplifier relay driver. 3,579,051, Cl. 317-148.

Omron Tateisi Electronics Co.: See—
Osaki, Keisuke, 3,579,188.

Ondetti, Miguel A.; Sheehan, John T.; and Pluscec, Josip, to Squibb, E. R., & Sons, Inc. C-sulfonated tyrosyl peptides related to cholecystokinin-pancreozymin (CCK-PZ). 3,579,494, Cl. 260-112.5

O'Neill, John F., to Bell Telephone Laboratories, Incorporated. Time compression tone detector. 3,578,919, Cl. 179-84.

Ontario Research Foundation: See—
Sefton, Verner B.; Bailey, Lawrence L.; and Autin, Donel C., 3,579,381.

Ooue, Shingo; Ueda, Hiroyuki; and Hayakawa, Yoshihide, to Aktiebolaget Kamyri Fuji Photo Film Co., Ltd. Method and apparatus for common digestion of wood chips and saw dust Process for making metal-glossy images and. 3,579,338, Cl. 162-18.

Organon, Inc.: See—
Crane, Margaret M.; Feduska, William; and Brown, Jack T., 3,579,385.

De Winter, Max Salomon; and Ribbers, Jan Evert, 3,579,543.

Orkin, Stanley S.; and Hartswick, Richard W., to Kaman Aerospace Corporation, mesne. Split-race bearing construction. 3,578,828, Cl. 308-37.

Osaki, Keisuke, to Omron Tateisi Electronics Co. Automatic ticket gate. 3,579,188, Cl. 340-149.

Oshima, Yasuhiro: See—
Wythe, Frederick J.; Oshima, Yasuhiro; and Hoette, Harald, 3,579,398.

Osmalov, Jerome S.: See—
Thomson, Richard N.; Osmalov, Jerome S.; and Mathe, George L., 3,579,623.

Ostberg, Bengt Sven Erik, 3,579,418, Cl.

Ostensen, Ralph G., to Medical Products Corporation. Autoclavable power-pak seal. 3,579,269, Cl. 240-10.68

Oster, Rudolf: See—
Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.

Ostermayer, Franz: See—
Denss, Rolf; Clauson-Kaas, Niels; and Ostermayer, Franz, 3,579,535.

Osterreichische Stickstoffwerke Aktiengesellschaft: See—
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.

Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, to International Lead Zinc Research Organization, Inc. Catalyst system for polymerizing saturated, aliphatic aldehydes. 3,579,480, Cl. 260-67.

Overmars, Henricus Gerardus Josef; and Noltes, Jan Gerrit, to International Lead Zinc Research Organization, Inc. Catalyst system for polymerizing saturated, aliphatic aldehydes. 3,579,481, Cl. 260-67.

Owens-Corning Fiberglas Corporation: See—
Shannon, Richard F., 3,579,409.

Padgett, Calvin D.: See—
Brooks, Thomas W.; Schuman, Paul D.; and Padgett, Calvin D., 3,579,557.

Padley, Frederick Bolton: See—
Turner, Trevor Stanley; and Padley, Frederick Bolton, 3,579,383.

Paget, Frederick W., to Sylvania Electric Products, Inc. Lamp ballast. 3,579,026, Cl. 315-99.

Paine, T. O., acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; and Cheng, Dah Yu. Converging-barrel plasma accelerator. 3,579,028, Cl. 315-111.

Paine, T. O., acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; Reynolds, Willard E.; and Reinhold, Henry W. Circuit breaker utilizing magnetic latching relays. 3,579,041, Cl. 317-33.

Paine, T. O., Administrator of the National Mee, John D.; Heseltine, Donald W.; Aeronautics and Space Administration with respect to an invention of; and Bauman, Albert J., to Eastman Kodak Company N/A. Electrophotographic materials containing cyanine dye sensitizers Fluid impervious barrier including liquid metal alloy and method of making same. 3,579,412, Cl. 161-89.

Paine, T. O., Deputy Administrator of the National Aeronautics and Space Administration with respect to an invention of; and Shimada, Katsunori. Cavity emitter for thermionic converter. 3,578,992, Cl. 310-4.

Paine, Thomas O., Administrator of the National Aeronautics and Space Administration with respect to an invention of; Anderson, Tage O.; and Hurd, William J. Digital filter for reducing sampling jitter in digital control systems. 3,579,122, Cl. 328-167.

Palilla, Frank C., to General Telephone & Electronics Laboratories Incorporated. Post deflection tube with all rare earth phosphors. 3,579,016, Cl. 313-92.

Palowkar, David Richard: See—
Ranby, Peter Whitten; and Palowkar, David Richard, 3,579,018.

Pangonis, William J., to Du Pont de Nemours, E. I., and Company. Chrome complexes of substituted benzoic acid. 3,579,555, Cl. 260-438.5

Parfitt, Peter, to Worcester Controls Corporation. Shielded filter. 3,579,156, Cl. 333-79.

Pasechnick, William: See—
Kremzner, Sigmunt J.; and Pasechnick, William, 3,579,161.

Pasero, Regine nee Perruche; and Viout, Andre, to Societe Anonyme dite: L'Oreal. Salts of copolymers of vinyl acetate crotonic acid/vinyl or allylic or methallylic esters in hair cosmetics. 3,579,629, Cl. 424-47.

Patel, Himanshu M.: See—
Suszer, Adalbert; and Patel, Himanshu M., 3,579,288.

Patel, Nager J.: See—
Drown, John L.; and Patel, Nager J., 3,578,925.

Pater, Maximilian, to Gebr. Bohler & Co. Aktiengesellschaft. Igniting aid for high efficiency plasma producers. 3,579,027, Cl. 315-111.

Patheiger, Manfred: See—
Bendszus, Otto; Niehaus, Clemens; and Patheiger, Manfred, 3,579,522.

Patrick, Alan E.; and Kern, Kenneth E., to General Time Corporation. Synchronous motor for clocks and the like. 3,579,004, Cl. 310-164.

Patterson, Arthur G.: See—
Friend, Aaron L.; Patterson, Arthur G.; and Wilen, James G., 3,578,948.

Patterson, James A., to Sandell Research & Development Co. Outlet plug and conduit for chromatograph. 3,578,785, Cl. 210-198.

Paul, John J., to Sperry Rand Canada Limited. Dual speed gated counter. 3,579,126, Cl. 328-129.

Paulik, Frank E.: See—
Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,551.

Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,552.

Payne, Robert K.: See—
Smith, Robert H.; Payne, Robert K.; and Haw, Thomas, III, 3,579,617.

Pechiney-Compagnie de Produits Chimiques et Electrometallurgiques: See—
Tamise, Louis; and Millet, Jacques, 3,579,295.

Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.

Pedden, Allan W.: See—
Taylor, Robert B.; and Walker, Robert G., 3,578,772.

Peeps, Donald J., to Champion Spark Plug Company. Electric steam vaporizer. 3,579,262, Cl. 219-295.

Pelenc, Yves F., to Merlin Gerin Societe Anonyme. Linear motor having radial armature plates. 3,579,001, Cl. 310-13.

Pemco Wheel Company: See—
Black, John W., 3,578,771.

Pennwalt Corporation: See—
Albert, Harry Elmer, 3,579,516.

Perkin-Elmer Corporation, The: See—
Anderson, James M.; and Fenton, Marvin J., 3,579,140.

Austin, Robert R., 3,578,848.

Scott, Larkin B., 3,579,105.

Wheeler, Chester C., 3,578,975.

Perkins, Cornelius C.: See—
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.

Perkins, Donald W.; and Wickes, William E., to General Electric Company. Digital resolver with alternately phased digital differential analyzers. 3,578,959, Cl. 235-152.

Pernollet, Andre: See—
Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilberte, 3,579,401.

Perrault, Jean: See—
Grandjean, Charles Henri Emile; and Perrault, Jean, 3,578,917.

Pesses, Marvin: See—
Ehe, Albert L.; and Pesses, Marvin, 3,579,399.

Peters, Norman J., to DEC International Inc. Apparatus for comminuting materials. 3,578,780, Cl. 146-79.

Petersen, Tom Kastrup: See—
Jensen, Arne; and Petersen, Tom Kastrup, 3,579,274.

Peterson, Weldon H.: See—
Twilley, Ian C.; Russell, William N.; and Peterson, Weldon H., 3,579,483.

Petrolite Corporation: See—
Quinlan, Patrick M., 3,579,466.

Petropoulos, John Christos; and Layman, Ralph Earl, to American Cyanamid Company. Protective and decorative thermosetting coating. 3,579,610, Cl. 260-853.

Pettersson, Lennart K., to Monsanto Company. Blow molding. 3,579,620, Cl. 264-98.

Pfaff, Maurice Edgar: See—
Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.

Pfeifer, Arthur F.: See—
Polkinghorn, Robert W.; Pfeifer, Arthur F.; and Hartmann, Robert F., 3,579,275.

Pfizer, Chas., & Co., Inc.: See—
Blackwood, Robert K.; and von Wittenau, Manfred Schach, 3,579,564.

Pfizer Inc.: See—
McFarland, James W., 3,579,510.

Philadelphia Quartz Company: See—
Millis, Walter T., 3,579,378.

- Philco-Ford Corporation: *See—*
Jones, Robert C., 3,579,010.
- Philip, Ralph M.: *See—*
McGuffin, August L.; and Philip, Ralph M., 3,578,986.
- Phillips, Larry B., to Granger Associates. Electrostatic discharger with internal resistance element. 3,579,033, Cl. 317-2.
- Phillips, Lawrence, Jr. Unit substation with transformer and control compartments. 3,579,044, Cl. 317-103.
- Phillips Petroleum Company: *See—*
Dunn, Howard E.; and Mathis, Ronald D., 3,579,478.
- O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, 3,579,377.
- Reusser, Robert E., 3,579,602.
- Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., 3,579,325.
- Stewart, Dan F.; Blair, Bob C.; Greene, Max E.; and Alexander, Lloyd R., 3,579,618.
- Phillips, William W.: *See—*
Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., 3,579,192.
- Pickering, Donald E., 3,579,303, Cl.
- Pickstone, Richard Esdaile. resins and method of producing such impregnated members Sterilisation of surgical instruments. 3,579,290, Cl. 21-2.
- Piechocki, Kurt Wilhelm, to Zellweger, Ltd. Template for evaluating photographs of doppler radar speed measurements. 3,579,236, Cl. 343-8.
- Pierce, Andrew G., Jr.: *See—*
Vail, Sidney L.; Pierce, Andrew G., Jr.; Moran, Clifford M.; and Barker, Robert H., 3,579,536.
- Pierdet, Andre: *See—*
Bertin, Daniel; and Pierdet, Andre, 3,579,545.
- Nomine, Gerard; Bucourt, Robert; and Pierdet, Andre, 3,579,504.
- Pignard, Jean; and Wintz, Bernard, to International Standard Electric Corporation. Digital phase meter with compensating means for asymmetric waveform distortion. 3,579,104, Cl. 324-83.
- Pingel, Vernon J., to United States of America, Interior. Removal of hydrogen sulfide from gaseous mixtures Carbiding. 3,579,373, Cl. 117-106.
- Piret, Jean: *See—*
Lombard, Claude Edmond; Maurice, Jean Henri; and Piret, Jean, 3,578,981.
- Pitner, Alfred, 1/2 to Nadella. Needle bearings. 3,578,830, Cl. 308-207.
- Pittinger, Abraham L.: *See—*
Thomas, Raymond W.; and Pittinger, Abraham L., 3,578,974.
- Pizza, Raymond. Practice baseball bat. 3,578,801, Cl. 273-26.
- Plastic Coating Corporation, The: *See—*
Michaud, David E.; and Hakanson, Nils L., 3,578,970.
- Platou, Jan Hendrik. Floatable cords. 3,578,763, Cl. 87-6.
- Plessey Company Limited, The: *See—*
Foss, Richard Charles, 3,579,272.
- Ryley, John E., 3,578,984.
- Plummer, Dexter Robert; Wright, Keith Lawrence; and Wild, Colin Arthur, to Rank Organisation Limited, The. Servo position control including integral control in forward and feedback controls. 3,579,072, Cl. 318-609.
- Pluscec, Josip: *See—*
Ondetti, Miguel A.; Sheehan, John T.; and Pluscec, Josip, 3,579,494.
- Pneumo Dynamics Corporation: *See—*
Crocker, Weyman S.; White, Philip H.; and McDonald, William T., 3,579,070.
- Polaroid Corporation: *See—*
Ciecuch, Ronald F. W.; and Simon, Myron S., 3,579,334.
- Grey, David S., 3,578,847.
- Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
- Polese, Gaspare, to Utita Officine E Fonderie Di Este S.p.A. Cop winder with controlled yarn tension. 3,578,795, Cl. 242-45.
- Polkinghorn, Robert W.; Pfeifer, Arthur F.; and Hartmann, Robert F., to North American Rockwell Corporation. Isolation circuit for gating device. 3,579,275, Cl. 307-251.
- Pomerantz, Marc Paul, to Du Pont de Nemours, E. I., and Company. Method of measuring coating weight by using strontium as a tracer. 3,579,271, Cl. 250-51.5.
- Poole, Edward M.: *See—*
Lapple, Walter C.; and Poole, Edward M., 3,578,798.
- Posey, William T. Push button magnetic reed switch. 3,579,159, Cl. 335-205.
- Poshkus, Algirdas C.: *See—*
Herweh, John E.; and Poshkus, Algirdas C., 3,579,615.
- Postmaster General, Her Majesty's: *See—*
Rath, Paul S.; Dyott, Richard Burnaby; and Clark, George Archer, 3,579,316.
- Potter, John J., Jr.; and Hamel, William J., to Union Carbide Corporation. Gas liquid withdrawal valve. 3,578,788, Cl. 222-4.
- Powell, Royal Edward: *See—*
Daly, Norman Richard; and Powell, Royal Edward, 3,579,270.
- PPG Industries, Inc.: *See—*
Ward, Cecil R.; and Schwarzkopf, August, 3,579,397.
- Pratt & Whitney Inc.: *See—*
Reuteler, Johann F.; and Warren, James A., 3,579,069.
- Priebs, Horst, to Anker-Werke Aktiengesellschaft. Slider switch with adjustable abutment on frame, and stationary contact faces with an angle greater than 180° therebetween bridged by a fork shaped. 3,578,929, Cl. 200-153.
- Prince, Edward J.: *See—*
Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., 3,579,325.
- Procter & Gamble Company, The: *See—*
Callen, Joseph E.; Haxby, Robert D.; and Fagin, William T., 3,579,458.
- Cambre, Cushman M., 3,579,456.
- Collier, Everett J., 3,579,454.
- Nicholson, Denzel Allan; and Campbell, Darrel, 3,579,570.
- Wann, Robert Earl; Nicholson, Denzel Allan; and Logan, Ted Joe, 3,579,449.
- Whyte, David D., 3,579,548.
- Procter & Gamble Company, The: *See—*
Fanta, Wayne I.; and Erman, William F., 3,579,479.
- Nakel, Gunther M.; and Dirks, Brinton Marlo, 3,579,353.
- Strobel, Rudolf G. K., 3,579,340.
- Produits Chimiques Pechiney-Saint-Gobain: *See—*
Antonini, Albert; Joffre, Philippe; and Vrillon, Claude, 3,579,597.
- Carrega, Marc E., 3,579,491.
- Proskauer, Walter, to Electronic Associates Inc. Solid sample inlet system for a mass spectrometer. 3,578,969, Cl. 250-41.9.
- Pryor, Michael J.; Enoksson, Bertil Petrus; and Anthony, William H., to Olin Mathieson Chemical Corporation Nitro Nobel Aktiebolag. Nitroglycerin-nitroglycol blasting composition Composite of steel and aluminum containing zinc and boron, and a cable sheath made therefrom. 3,579,392, Cl. 29-196.2.
- Puckett, William R.: *See—*
Hagler, Travis J.; Puckett, William R.; and Tanner, Bobby G., 3,578,796.
- Pullman Incorporated: *See—*
Mundinger, William D.; and Nagy, Ernest J., 3,578,815.
- Pulp and Paper Research Institute of Canada: *See—*
Yorston, Frederic H.; and Liebergott, Norman, 3,579,419.
- Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, to Du Pont de Nemours, E. I., and Company Badische Anilin- & Soda-Fabrik Aktiengesellschaft. Composite layered tetrahaloethylene structure Removing phenyl azide from gases. 3,579,291, Cl. 23-2.
- Purcell, Albert E.; and Walter, William M., Jr., to United States of America, Agriculture. Microbial production of carbon C labelled all-trans beta carotene. 3,579,424, Cl. 195-28.
- Purcell, William O., Jr.; and Trippe, Walter D., to Martin-Marietta Corporation. Angularly selective monopulse reception. 3,579,239, Cl. 343-16.
- Pylon Electronic Development Company: *See—*
Cameron, Douglas R. G., 3,579,077.
- Quantametric Devices, Inc.: *See—*
Casterlin, James H., 3,579,230.
- Quinlan, Patrick M., to Petrolite Corporation. Polyglycidyl polymers as demulsifiers. 3,579,466, Cl. 252-331.
- Quinn Brothers, Incorporated: *See—*
Allan, Barry D.; and Cunningham, John J., Jr., 3,579,314.
- Raap, Rintje: *See—*
Lemieux, Raymond Urgel; and Raap, Rintje, 3,579,506.
- Rabusin, Elio: *See—*
Della Porta, Paolo; and Rabusin, Elio, 3,578,834.
- Della Porta, Paolo; and Rabusin, Elio, 3,579,459.
- Radford, David L.; Frisby, Paul W.; and Filho, Francisco Muniz, to McGraw-Edison Company. Cabinet pants press. 3,578,790, Cl. 223-73.
- Radio Steel & Mfg. Co.: *See—*
Tonelli, Roger R., 3,578,806.
- Raffalsky, Kurt: *See—*
Kroke, Hermann; and Raffalsky, Kurt, 3,579,446.
- Ramanathan, Visvanathan; and Artz, Klaus, to Ciba Limited. Water-insoluble monoazo dyestuffs. 3,579,497, Cl. 260-158.
- Ramsey Engineering Company: *See—*
Kloven, Gerald P., 3,578,955.
- Ramsey, Kurt G., to Westinghouse Electric Corporation. Waveguide to stripline transition means. 3,579,149, Cl. 333-11.
- Ranby, Peter Whitten; and Palowkar, David Richard, to British Lighting Industries Limited. Luminescent materials. 3,579,018, Cl. 313-109.
- Rank Organisation Limited, The: *See—*
Plummer, Dexter Robert; Wright, Keith Lawrence; and Wild, Colin Arthur, 3,579,072.
- Rasch, Rudolf: *See—*
Harkort, Dietrich; Rasch, Rudolf; Iberg, Rolf; and Heberlein, Jurg H., 3,579,619.
- Rasche, David; Levy, Bernardo N.; Ayres, Bruce L.; Chang, Hoy Ying; Perkins, Cornelius C.; and Phillips, William W., to Burroughs Corporation. Data processing machine. 3,579,192, Cl. 340-172.5.
- Raschke, Herbert A., to Bullard, E. D., Company. Ambient noise frequency responsive audible vehicle alarm. 3,579,233, Cl. 340-384.
- Rath, Paul S.; Dyott, Richard Burnaby; and Clark, George Archer, to Monsanto Company Postmaster General, Her Majesty's. Method and apparatus for forming a multiply thermoplastic molded article Process for optical waveguide coupler. 3,579,316, Cl. 65-4.
- Raun, Arthur P.; and Kline, Richard M., to Lilly, Eli, and Company. Antibiotic treatment of ruminant animals with bis-urea adducts of aldehyde-containing macrolide antibiotics. 3,579,635, Cl. 424-181.

- Ray-Chaudhuri, Dilip K.: *See—*
Stockmann, Hans H.; Ray-Chaudhuri, Dilip K.; and Boettger, Richard M., 3,579,549.
- Raymond, Charles T.: *See—*
Eburn, William H., Jr.; and Raymond, Charles T., 3,579,406.
- Rayner, Harold J., to Raytheon Company. Numerical indicator tube with built-in translating circuit. 3,579,025, Cl. 315-84.6.
- Raytheon Company: *See—*
Langley, Frank J., 3,579,201.
- Rayner, Harold J., 3,579,025.
- RCA Corporation: *See—*
Clark, Robert John, 3,579,225.
- Grange, Robert A., 3,579,206.
- Griepentrog, Dal F., 3,578,901.
- Hannan, William J., 3,578,836.
- Harford, Jack R., 3,579,112.
- Harford, Jack R., 3,579,133.
- Heuner, Robert Charles, 3,578,989.
- Koons, Russell E., 3,579,413.
- Mackway, Harold Jessup, 3,579,160.
- Monsay, John, 3,578,902.
- Norley, Ronald Richard, 3,579,095.
- Rotolo, Michael, Jr., 3,579,144.
- Stoller, Arthur Irwin, 3,579,057.
- Weimer, Paul K., 3,579,189.
- Willis, Donald H., 3,578,900.
- Willis, Donald H., 3,578,903.
- Wonilowicz, Edmund; Cann, Everett Douglas; and Machnacz, Henry F., 3,579,296.
- Wright, Carl Macey, 3,579,267.
- Yongue, James M., 3,578,899.
- Redding, Billy J.; Steadman, John T.; and Bragg, Lorel J., to Goodrich Gulf Chemicals, Inc. Dewatering pelletizer apparatus. 3,578,740, Cl. 18-12.
- Regan, Bernard M., to Baxter Laboratories, Inc. 1-Bromo-1-chloro-2,3,3-trifluoropropene and method of preparing same. 3,579,595, Cl. 260-653.3.
- Regie National des Usines Renault: *See—*
Lombard, Claude Edmond; Maurice, Jean Henri; and Piret, Jean, 3,578,981.
- Regie Nationale des Usines Renault: *See—*
Guettier, Michel, 3,578,821.
- Regnier, Marc Andre: *See—*
Girard, Pierre; Lerouge, Clade Paul Henri; and Regnier, Marc Andre, 3,579,232.
- Reh, Lothar; Rosenthal, Karlheinz; and Schmidt, Hans Werner, to Metallgesellschaft Aktiengesellschaft. Method of carrying out endothermic processes. 3,579,616, Cl. 263-52.
- Rehmar, Solomon J., to Cassella Farbwerke Mainkur Aktiengesellschaft Intrusion-Prepakt. Polyalkylene polyamine thiosulfonated sulfur dye composition and dyeing therewith Granulated additive, method of making the same, and cementitious grout and concrete compositions containing the same. 3,579,366, Cl. 106-314.
- Reich, Irving: *See—*
Ayres, John; and Reich, Irving, 3,578,945.
- Reichhold Chemicals, Inc.: *See—*
Chang, Yun G., 3,579,541.
- Reinert, Owen E., to Sperry Rand Corporation. Generator semiconductor voltage regulator. 3,579,087, Cl. 322-28.
- Reinhold, Henry W.: *See—*
Paine, T. O., acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; Reynolds, Willard E.; and Reinhold, Henry W., 3,579,041.
- Renner, Ulrich: *See—*
Kuhnis, Hans Herbert; and Renner, Ulrich, 3,579,512.
- Kuhnis, Hans Herbert; and Renner, Ulrich, 3,579,513.
- Renz Wacker & Co.: *See—*
Wacker, Hans, 3,579,261.
- Research Corporation: *See—*
Klemm, Le Roy H.; Shabtai, Joseph; and Mc Coy, David R., 3,579,526.
- Reusser, Robert E., to Phillips Petroleum Company. Olefin conversion process and catalysts therefor. 3,579,602, Cl. 260-683.
- Reuteler, Johann F.; and Warren, James A., to Pratt & Whitney Inc. Numerical machine tool control system including means to digitally simulate a template follower. 3,579,069, Cl. 318-571.
- Rey, Louis Rene; and Dousset, Monick, 3,579,360, Cl.
- Reynolds Metals Company: *See—*
Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,578,904.
- Dewey, Raymond D.; Mapes, Robert S.; and Jones, Garth S., 3,579,249.
- Reynolds, Ronald W.: *See—*
Wentzheimer, William W.; Reynolds, Ronald W.; and Chalpin, William, 3,579,437.
- Reynolds, Willard E.: *See—*
Paine, T. O., acting Administrator of the National Aeronautics and Space Administration with respect to an invention of; Reynolds, Willard E.; and Reinhold, Henry W., 3,579,041.
- Rhee, Dong Woo, to Sylvania Electric Products, Inc. Horizontal circuitry for television receivers. 3,579,139, Cl. 331-8.
- Rhodes, Donald F., to Gulf Research & Development Company. Multiple mode frequency divider circuit. 3,579,118, Cl. 328-41.
- Rhone-Poulenc S.A.: *See—*
Amedjian, Garabed; Fenoglio, Maurice; and Oberdorf, Michel, 3,579,572.
- Rhyne, Theodore Lauer; and Mc Cready, Karl F., to Northrop Corporation. Time sharing recorder drive circuit. 3,579,246, Cl. 346-34.
- Ribbers, Jan Evert: *See—*
De Winter, Max Salomon; and Ribbers, Jan Evert, 3,579,543.
- Richards, John O. Revolving reflector. 3,578,840, Cl. 350-99.
- Richardson Company, The: *See—*
Muzyczko, Thaddeus M.; Ludwig, William J.; Loboda, Jon; and Shore, Samuel, 3,579,447.
- Richardson, David A., to Foxboro Company, The. Digital and analog process control apparatus. 3,578,958, Cl. 235-150.5.
- Richardson, John A.: *See—*
Dickason, Richard T.; and Richardson, John A., 3,579,243.
- Richell, Clement Michael, 25% to Roberts, Ray R. Electronic powered pulse amplifier. 3,579,074, Cl. 320-1.
- Richter, Johan C.F.C., to Aktiebolaget Kamyr. Sieve device in an upright cylindrical container. 3,579,420, Cl. 96-74.
- Richter, Johan C.F.C., to Aktiebolaget Kamyr. evaporate. 3,579,421, Cl. 99-71.
- Richter, Werner: *See—*
Wopkemeier, Helmut Friedrich; and Richter, Werner, 3,578,868.
- Rieke, James K.; and Justin, Frank H., to Dow Chemical Company. Glass filled graft copolymers of an olefin and an unsaturated acid. 3,579,476, Cl. 260-41.
- Riester, William C., to Trico Products Corporation. Motor control system. 3,579,067, Cl. 318-444.
- Riggle, Grant C.; and White, James P., to United States of America, Health, Education and Welfare. Automated device for protecting lens systems. 3,578,839, Cl. 350-61.
- Ringeman, Othmar E.: *See—*
Cullen, William F.; and Ringeman, Othmar E., 3,579,020.
- Riordan, Hugh E., to Kelsey-Hayes Company. Two wheel skid control by modulation of brake power booster. 3,578,820, Cl. 303-21.
- R&L Molecular Research Ltd.: *See—*
Lemieux, Raymond Urgel; and Raap, Rintje, 3,579,506.
- Ro, Rolland S., to Du Pont de Nemours, E. I., and Company. Elastomeric copolymers of tetrafluoroethylene containing phenoxethyl groups, and their vulcanization. 3,579,474, Cl. 260-29.6.
- Roberts, Ray R.: *See—*
Richell, Clement Michael, 3,579,074.
- Robertshaw Controls Company: *See—*
Holmes, Ronald W., 3,578,932.
- Rochla, Kurt: *See—*
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.
- Rogers, Howard G.: *See—*
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
- Rohe Scientific Corporation: *See—*
Natelson, Samuel, 3,578,977.
- Rohm and Haas Company: *See—*
Dupre, Jean; and Killam, Harrison Scott, 3,579,453.
- Roman, Pierre Amedee: *See—*
Tamise, Louis; Dennilauler, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.
- Roop, Donald E.: *See—*
Hackman, Donald J.; Legue, Ronald L.; Harris, Jeremy M.; and Roop, Donald E., 3,579,037.
- Rope, Barton W.: *See—*
Smith, Robert B.; and Rope, Barton W., 3,579,434.
- Roppel, Alfred: *See—*
Roth, Johann; Roppel, Alfred; and Steibl, Theodor, 3,578,853.
- Rosen, Harvey; Acker, Ellsworth G.; and Lee, Hanju, to Grace, W. R., & Co. Non-decrepitating silica gel and method for its preparation. 3,579,464, Cl. 252-317.
- Rosenthal, Karlheinz: *See—*
Reh, Lothar; Rosenthal, Karlheinz; and Schmidt, Hans Werner, 3,579,616.
- Ross, Adma Schneller: *See—*
Hlavka, Joseph J.; Bitha, Panayota; Ross, Adma Schneller; and Martell, Michael Joseph, 3,579,579.
- Ross, Bernd, to Bell & Howell Company. Semiconductor stress transducer. 3,578,864, Cl. 356-32.
- Ross, Bernd, to Bell & Howell Company. Semiconductor laser device and method for its fabrication. 3,579,055, Cl. 317-234.
- Ross, James A., to LTV Ling Altet, Inc. Class 'D' linear audio amplifier. 3,579,132, Cl. 330-10.
- Ross, Richard V., to Morrison Products, Inc. Blower wheel and method of making same. 3,578,878, Cl. 416-178.
- Roth, Adrian W., to Sprecher & Schuh AG. High voltage switching assembly. 3,578,927, Cl. 200-145.
- Roth, James F.: *See—*
Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,551.
- Craddock, John H.; Hershman, Arnold; Paulik, Frank E.; and Roth, James F., 3,579,552.
- Roth, Johann, to Niezoldi & Kramer GmbH. Motion picture projector. 3,578,854, Cl. 352-158.
- Roth, Johann; Roppel, Alfred; and Steibl, Theodor, to Niezoldi & Kramer GmbH. Motion picture camera. 3,578,853, Cl. 352-91.

Rotolo, Michael, Jr., to RCA Corporation. Relaxation oscillator gated by transistor switch. 3,579,144, Cl. 331-111.

Rotruck, James L., to Westinghouse Electric Corporation. Noise reduction systems for electrical transformers. 3,579,164, Cl. 336-100.

Roujas, Guy: *See—*
Loustalet, Pierre; and Roujas, Guy, 3,578,783.

Roura, Miguel Jacinto: *See—*
Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.

Roussel-UCLAF: *See—*
Bertin, Daniel; and Pierdet, Andre, 3,579,545.

Roussel-UCLAF, S.A.: *See—*
Nordine, Gerard; Bucourt, Robert; and Pierdet, Andre, 3,579,504.

Rouzier, Michel M.: *See—*
Lucas, Pierre M.; and Rouzier, Michel M., 3,578,916.

Rovee, David T.: *See—*
Gander, Robert J.; and Rovee, David T., 3,579,628.

Rowan, Henry M.: *See—*
Stroop, John Henry; Kennedy, Theodore R.; and Rowan, Henry M., 3,579,324.

Rowley, Donald Edward, to General Electric and English Electric Companies Limited, The. Electric crossbar switches. 3,579,157, Cl. 335-112.

RTE Corporation: *See—*
Nelson, Rolland D., 3,578,982.

Rubens, Louis C.; and Walsh, William B., to Dow Chemical Company, The. Method of fabricating expandable thermoplastic resinous material. 3,579,472, Cl. 260-25.

Rubinfeld, Joseph; and Levinsky, Henry Leon, to Colgate-Palmolive Company. Process for separation of sulfones from alkenyl sulfonic acids. 3,579,537, Cl. 260-327.

Rudd, Lloyd K.; and Schollhamer, George R., to Rudd-Melikian, Inc., mesne. Beverage tape. 3,579,350, Cl. 99-77.1

Rudd-Melikian, Inc.: *See—*
Rudd, Lloyd K.; and Schollhamer, George R., 3,579,350.

Ruggles, Kay L.; Gunnerson, Dale B.; and Clark, Howard S., to American Standard, Inc., mesne. Monolithic sink and vanity top combination. 3,578,737, Cl. 4-166.

Rummel, Karlheinz: *See—*
Sturm, Konrad; Becker, Willy; Timm, Heinz; and Rummel, Karlheinz, 3,579,047.

Runk, Robert H., to Westinghouse Electric Corporation. Diphenyl oxide modified phenolic resin insulating varnishes. 3,579,470, Cl. 260-20.

Ruscitti, Tomaso. Device for imparting a pre-arranged array to and carrying an orderly train of elongated bodies, the barycentre of which being adjacent an end thereof. 3,578,813, Cl. 302-14.

Ruse, Douglas C.: *See—*
Edmonds, Byron P.; and Ruse, Douglas C., 3,578,808.

Russell, Charles H., to United States of America, National Aeronautics and Space Administration. Analog-to-digital converter tester. 3,579,103, Cl. 324-73.

Russell, Irving G.: *See—*
Hudock, Edward P.; Russell, Irving G.; and Sorensen, Robert L., 3,578,862.

Russell, William N.: *See—*
Twilley, Ian C.; Russell, William N.; and Peterson, Weldon H., 3,579,483.

Russo, Joseph: *See—*
Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, 3,578,858.

Rutzen, Horst, to Henkel & Cie, G.m.b.H. Process for preparation of N-methyl-alkylamines. 3,579,583, Cl. 260-583.

Rutzen, Horst, to Henkel & Cie, G.m.b.H. Preparation of amines. 3,579,585, Cl. 260-583.

Rutzen, Horst; and Brockmann, Rolf, to Henkel & Cie, G.m.b.H. Preparation of amines. 3,579,584, Cl. 260-583.

Ryley, John E., to Plessey Company Limited, The. Master/slave switching circuit employing insulated-gate field-effect transistors. 3,578,984, Cl. 307-221.

Sabatelli, Philip M.; and Brungs, Charles A., to Grace, W. R., & Co. Machine dishwashing compositions containing sodium polyacrylate. 3,579,455, Cl. 252-135.

S.A.E.S. Getters S.p.A.: *See—*
Della Porta, Paolo; and Rabusin, Elio, 3,578,834.

Safford, Moyer M.: *See—*
Hohub, Fred F.; and Safford, Moyer M., 3,579,611.

Safonnikov, Anatoly Nikolaevich: *See—*
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Saito, Sadao: *See—*
Kuroda, Toshihiko; Sutani, Sotou; Nitta, Haruo; and Saito, Sadao, 3,579,428.

Sakamoto, Tetsuzo, to Tokyo Shibaura Electric Co., Ltd. Control device for an object such as a rotor in a prime mover or the like. 3,578,871, Cl. 415-10.

Salensky, George A., to Union Carbide Corporation. Epoxy solders. 3,579,473, Cl. 260-18.

Samejima, Hiroto: *See—*
Kleinhauger, Otmar; Samejima, Hiroto; Holzgruber, Wolfgang; Cerwenka, Peter; Nakayama, Kiyoshi; Nagano, Yuji; and Hladny, Wolfgang, 3,579,357.

Sams, Robert H.; and Mc Cready, Newton W., 3,579,299, Cl. Samullov, Viktor Ivanovich; Genkin, Jury Markovich; and Suvorova, Maria Dmitrievna. Chromatograph for determination of admixtures in gases. 3,578,757, Cl. 73-23.1

Sandberg, Rune Verner; Sjoberg, Berndt Olof Harald; and Tegner, Claes Philip, deceased (by Tegner, Gunnel Margareta; executrix), to Aktiebolaget Astra. Anilides of quinuclidine-2-and quinuclidine-3-carboxylic acid. 3,579,523, Cl. 260-293.4

Sandell Research & Development Co.: *See—*
Patterson, James A., 3,578,785.

Sanders Associates, Inc.: *See—*
Stapleford, Gary N., 3,579,197.

Whitney, David J.; and Nepveu, Raymond R., 3,579,151.

Sandoz-Wander, Inc.: *See—*
Houlihan, William J.; and Manning, Robert E., 3,579,517.

Sands, Oran J., to Arvin Industries, Inc. Welding process. 3,578,940, Cl. 219-91.

Sarka, Albert J., to Harris, Intertype Corporation. Severing apparatus. 3,578,761, Cl. 83-343.

Sauer, Richard W.: *See—*
Lincoln, Robert M.; Meyers, Joseph A., III; and Sauer, Richard W., 3,579,457.

Savkar, Sudhir D., to General Electric Company. Winding duct construction for power transformer. 3,579,162, Cl. 336-57.

Sawyer, Roderick V., to CTS Corporation. Electrical coil. 3,579,166, Cl. 336-192.

Scarborough, Alfred D., to Bunker-Ramo Corporation, The. Light cell matrix structure. 3,579,019, Cl. 313-109.5

Schafer, Stefan: *See—*
Sennwald, Kurt; Gehrmann, Klaus; and Schafer, Stefan, 3,579,309.

Schaper, Raymond J.; and Hoover, Merwin Frederick, to Calgon Corporation, mesne. Polysalts containing sulfonated acrylics. 3,579,613, Cl. 260-901.

Scheifele, Hudson B. Composite tapered roller bearing and method of making the same. 3,578,831, Cl. 308-214.

Scheiner, Peter, to Mobil Oil Corporation. Process for preparing 1-phenyl-1,2,3-triazoles. 3,579,531, Cl. 260-308.

Schjoberg, Eiler; Zwicker, Walter K.; and Milch, Alfred, to U.S. Philips Corporation, mesne. Method for production of deep frozen fish products. Imaging device with combined thin monocrystalline semiconductor target-window assembly. 3,579,359, Cl. 313-65.

Schlumberger Overseas Messgeratebau und Vertrieb GmbH: *See—*
Knirsch, Herbert, 3,579,116.

Schmidt, Alfred: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.

Schmidt, Hans Werner: *See—*
Reh, Lothar; Rosenthal, Karlheinz; and Schmidt, Hans Werner, 3,579,616.

Schmitz, Albert: *See—*
Te Velde, Ties Siebolt; and Schmitz, Albert, 3,579,056.

Schmolka, Irving R., to Wyandotte Chemicals Corporation. Aqueous gels of polyoxyethylated polyoxypropylene glycol adducts of ethylene diamine. 3,579,465, Cl. 252-316.

Schneider, Leonard. Anchor dragging alarm control based on anchor inclination. 3,579,182, Cl. 340-29.

Schneider, Thomas E., Jr.; Carstens, Marion R.; and Bates, Homer J., to Tesco Chemicals, Inc. Chemical feeder. 3,578,776, Cl. 137-268.

Schnell, Hermann: *See—*
Immel, Otto; Schwarz, Hans-Helmut; and Schnell, Hermann, 3,579,558.

Schnell, Hermann; Darsow, Gerhard; and Bottenbruch, Ludwig, to Farbenfabriken Bayer Aktiengesellschaft, 4,4-Bis-(hydroxy aryloxy)-phenylsulfone. 3,579,591, Cl. 260-607.

Schollhamer, George R.: *See—*
Rudd, Lloyd K.; and Schollhamer, George R., 3,579,350.

Scholten Research N.V.: *See—*
Dijkhuizen, Willem; Kliphuis, Harmannus; and Lolkema, Jan, 3,579,471.

Schoumaker, Henry P.J.F.M.C., to La Soudure Electrique Autogene, Procides Arcos. Protective coating for plasma apparatus. 3,578,943, Cl. 219-121.

Schramm, Richard F., to Speed Equipment Incorporated. Shrink tunnel with turntable. 3,578,747, Cl. 34-184.

Schreiner, Horst: *See—*
O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, 3,579,377.

Schrenk, Walter J.: *See—*
Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, 3,579,416.

Schuessler, John C.; and Capol, Roman J., to Leach Corporation. Spring mounted arc deflector. 3,578,928, Cl. 200-144.

Schultz, August L. Supportive orthopedic device. 3,578,773, Cl. 128-78.

Schuman, Paul D.: *See—*
Brooks, Thomas W.; Schuman, Paul D.; and Padgett, Calvin D., 3,579,557.

Schunack, Johannes, to Morat, Franz, G.m.b.H. Optical scanning device. 3,578,976, Cl. 250-219.

Schwalm, Bruce D.: *See—*
Halls, Lawrence M.; Lausch, Henry N.; and Schwalm, Bruce D., 3,578,750.

Schwartz, Harold O.; and Ippolito, Anthony C., to Wurlitzer Company, The. Radio frequency keying pulse in electronic organ. 3,578,894, Cl. 84-1.01

Schwarz, Hans-Helmut: *See—*
Immel, Otto; Schwarz, Hans-Helmut; and Schnell, Hermann, 3,579,558.

Schwarzko Development Corporation: *See—*
Hennig, Walter; Sedlatschek, Karl; and Machenschalk, Rudolf, 3,579,022.

Schwarzkopf, August: *See—*
Ward, Cecil R.; and Schwarzkopf, August, 3,579,397.

Schweizer, Hans R., to Eastman Kodak Company. Crystalline form of quinacridone. 3,579,519, Cl. 260-279.

Sciambi, Louis J., to Dow Chemical Company, The. Electrophotographic developer made from cross-linked silicone intermediate resin. 3,579,451, Cl. 252-62.1

Scientific Research Instruments Corporation: *See—*
Vestal, Marvin L., 3,579,017.

SCM Corporation: *See—*
Blaze, Joseph E., Jr.; and Damon, Ivan R., 3,579,039.

Stillings, William K.; Miller, Donald E.; and Gilmore, Cecelia R., 3,579,356.

Traxler, James T., 3,579,547.

Young, Robert P. T., 3,579,468.

Scott, Larkin B., to Perkin-Elmer Corporation, The. Digital readout system having an automatic zero-setting circuit. 3,579,105, Cl. 324-99.

Scuderi, Rudolph: *See—*
Clarke, Patrick W.; and Scuderi, Rudolph, 3,579,091.

Seaman, Edward L. Differential feed attachment means for shirring. 3,578,769, Cl. 112-208.

Sears, James K., to Monsanto Company., 3,579,364, Cl. 340-172.5

Sears, James K.; Andreev, John Hugh; Gaines, Brian Ronald; and White, Peter, to Monsanto Company International Standard Electric Corporation. Plasticized resin compositions Network using adaptive elements. 3,579,191, Cl. 106-176.

Sebastian, Robert W.: *See—*
Baumanis, Bruno; and Sebastian, Robert W., 3,579,170.

Sebek, Oldrich K.: *See—*
Argoudelis, Alexander D.; Coats, John H.; Mason, Donald J.; and Sebek, Oldrich K., 3,579,426.

Sedlatschek, Karl: *See—*
Hennig, Walter; Sedlatschek, Karl; and Machenschalk, Rudolf, 3,579,022.

Sefton, Verner B.; Bailey, Lawrence L.; and Autin, Donel C., to Ontario Research Foundation Allied Chemical Corporation. Method of forming sulfur from SO₂ containing gases Automatic bobbin and pirn cleaning. 3,579,381, Cl. 134-8.

Selchow & Righter Company: *See—*
Eburn, William H., Jr.; and Raymond, Charles T., 3,579,406.

Seliger, Victor H.: *See—*
Herbst, John A.; and Seliger, Victor H., 3,579,076.

Sennwald, Kurt; Gehrmann, Klaus; and Schafer, Stefan. creep barriers. 3,579,309, Cl. 136-163.

Sennowitz, Kurt H., to Elox Inc. Electrical discharge machining power supply circuit of the superimposed voltage type. 3,578,937, Cl. 219-69.

Sevenich, Robert J., to Minnesota Mining and Manufacturing Company. Flex-resistant polyester film containing olefin or polytetramethylene oxide additive polymer. 3,579,609, Cl. 260-873.

Sevruck, Albert Nikolaevich: *See—*
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Seybold, Hugh Laurie: *See—*
Sproule, Robert Stanley; Kanger, Feodor; and Seybold, Hugh Laurie, 3,578,874.

Shabtai, Joseph: *See—*
Klemm, Le Roy H.; Shabtai, Joseph; and Mc Coy, David R., 3,579,526.

Shannon, Richard F., to Owens-Corning Fiberglass Corporation., 3,579,409, Cl. 75-133.5

Shaw, Charles H.; and Strauss, Robert G., to Monsanto Company. Method for blow molding plastic articles. 3,579,622, Cl. 264-99.

Shear, Wayne Gregory: *See—*
Straub, Kenneth Luke; and Shear, Wayne Gregory, 3,579,235.

Sheehan, John T.: *See—*
Ondetti, Miguel A.; Sheehan, John T.; and Pluscec, Josip, 3,579,494.

Shell Oil Company: *See—*
Abrams, Albert; Hill, Harold J.; and Thigpen, David R., 3,578,781.

Chao, Junn-Ling, 3,578,816.

Wagner, Willem M., 3,579,489.

Sheridan, Phillip Robert: *See—*
Bentham, Frederick Percy; Sheridan, Phillip Robert; Foreman, Joseph Trevor; and Stimpson, Ian William, 3,579,030.

Sherman, Ralph H. Vehical identification light. 3,578,964, Cl. 240-8.1

Shimada, Katsunori: *See—*
Paine, T. O., Deputy Administrator of the National Aeronautics and Space Administration with respect to an invention of; and Shimada, Katsunori, 3,578,992.

Shimadzu Seisakusho Ltd.: *See—*
Fukuda, Toshio, 3,579,131.

Shimizu, Kanryo: *See—*
Inaba, Seiemon; Shimizu, Kanryo; Hashimoto, Yoshihiro; and Kobayashi, Kengo, 3,579,279.

Shingu Shoko, Ltd.: *See—*
Ishizaki, Kan, 3,578,779.

Shimmura, Kimio; Wege, Hans; and Gast, Erich, to Kabushiki Kaisha Honda Gijutsu Kenkyusho Kuhn, Wilhelm, Firma. Power transmission apparatus Coffee powder package. 3,579,351, Cl. 99-77.1

Shoap, Stephen D.: *See—*
Norris, Walter E.; and Shoap, Stephen D., 3,579,117.

Shore, Samuel: *See—*
Muzyczko, Thaddeus M.; Ludwig, William J.; Loboda, Jon; and Shore, Samuel, 3,579,447.

Short, Oliver A.; and Buie, James Lang, to TRW Inc. Du Pont de Nemours, E. I., and Company. Printed circuits from non-migrating solders Method of producing dielectric isolation for monolithic circuit. 3,579,391, Cl. 148-175.

Shroyer, Larry L., to Lyall Electric, Inc. Electric circuit adapter member. 3,579,175, Cl. 339-156.

Shultz, Forrest G.; Chidester, Gerald E.; and Collet, Fernand E. heating. 3,579,293, Cl. 117-93.1

Siebol, George; and Kolec, Robert F., to Armco Steel Corporation. Self drilling, reaming and tapping screw. 3,578,762, Cl. 85-41.

Siegrist, Adolf Emil: *See—*
Weber, Kurt; Liechti, Peter; Meyer, Rudolf; and Siegrist, Adolf Emil, 3,579,511.

Siemens Aktiengesellschaft: *See—*
Haag, Eugen, 3,579,121.

O'Brien, George; Hubby, John S.; Schreiner, Horst; and Ohmann, Helmut, 3,579,377.

Sierra Research Corporation: *See—*
Kam, George H.; and Hughes, Richard J., 3,579,281.

Silva, Lawrence M.: *See—*
Fletcher, Taylor C.; Silva, Lawrence M.; and Wilkinson, Bruce L., 3,579,088.

Simmonds Precision Products, Inc.: *See—*
Arthur M. Forsythe, Jr., 3,579,218.

Simon, Myron S.: *See—*
Ciecuch, Ronald F. W.; and Simon, Myron S., 3,579,334.

Simonelli, Richard A., to Lynch Communication Systems, Inc. Equalizer with automatic line build-out. 3,578,914, Cl. 179-15.

Sinclair Company, The: *See—*
Minick, David G.; and Sinclair, David H., 3,579,422.

Sinclair, David H.: *See—*
Minick, David G.; and Sinclair, David H., 3,579,422.

Sindeev, Valentin Stepanovich: *See—*
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruck, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Singer-General Precision, Inc.: *See—*
Beavers, William E., Jr.; and Sturdevant, William H., 3,578,912.

Herbst, John A.; and Seliger, Victor H., 3,579,076.

Sjoberg, Berndt Olof Harald: *See—*
Sandberg, Rune Verner; Sjoberg, Berndt Olof Harald; and Tegner, Claes Philip, 3,579,523.

Skandal, Karl Arvid: *See—*
Cras, Ake Karl Gustaf, 3,578,786.

Slemmons, Arthur J., to FMC Corporation. Dynamically balanced power transmission. 3,578,822, Cl. 305-24.

Slowikowski, Daniel F., to United States of America, National Aeronautics and Space Administration. Digital pulse width selection circuit. 3,578,988, Cl. 307-265.

Smiley, Vern N., to United States of America, Navy. Thin film active interference filter. 3,579,130, Cl. 330-4.3

Smiley, Vern N., to United States of America, Navy. Thin film laser. 3,579,142, Cl. 331-94.5

Smith, Donald R.: *See—*
Cavestany, Adrian V.; Smith, Donald R.; and Bissell, Harold R., Jr., 3,578,891.

Smith, Ervin; and Wedel, John O., to United States of America, Navy, mesne. Phase controller. 3,579,128, Cl. 328-155.

Smith, Joseph E., to Excellon Industries. Arrangement for providing precise movement. 3,578,827, Cl. 308-5.

Smith Kline & French Laboratories: *See—*
Holden, Kenneth G., 3,579,509.

Smith, Ralph W.: *See—*
Maloney, Jim N., Jr.; and Smith, Ralph W., 3,579,581.

Smith, Robert B.; and Rope, Barton W., to Mobil Oil Corporation. Hydrocracking of naphtha. 3,579,434, Cl. 208-111.

Smith, Robert H.; Payne, Robert K.; and Haw, Thomas, III, to Chrysler Corporation. Method of installing surface plate. 3,579,617, Cl. 264-34.

Smith, William Novis, Jr., to Foote Mineral Company. Method for preparing long chain alkyl compounds. 3,579,492, Cl. 260-94.9

Societe Anonyme dite: L'Oreal: See—
Pasero, Regine nee Perruche; and Viout, Andre, 3,579,629.

Societe Appareils et Evaporateurs Kestner: See—
Tamise, Louis; and Millet, Jacques, 3,579,295.

Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, 3,579,374.

Societe d'Assistance Technique pour Produits Nestle S.A.: See—
Chaffard, Francoise; Backderf, Robert P.; and Kanitz, Douglas R., 3,579,038.

Mishkin, Abraham R.; Martin, Richard D.; and Ohler, Joseph L., 3,579,349.

Societe de L'Aerotrain: See—
Giraud, Francois L., 3,578,768.

Societe d'Exploitation des Brevets Neiman S.A.: See—
Lipschutz, Paul, 3,579,183.

Societe Generale de Constructions Electriques et Mecaniques (ALSTHOM): See—
Burnier, Pierre; and Moreau, Jack, 3,579,035.

Societe le Carbone Lorraine: See—
Higgins, Irwin R.; Cauville, Roland; Pernollet, Andre; and Moutaud, Gilbert, 3,579,401.

Societe Nouvelle Spidem: See—
Diolot, Lucien, 3,578,766.

Societe Rhodiacta: See—
Jacquinet, Jean-Louis, 3,579,625.

Soignet, Donald M.: See—
Bleiweiss, Eugene; Soignet, Donald M.; and Benerito, Ruth R., 3,579,289.

Sokolov, David A., to Xerox Corporation. Selective blanking control circuit, 3,579,024, Cl. 315-22.

Sola Basic Industries, Inc.: See—
Wolfram, Bodo M., 3,579,219.

Solyst, Erik R., to International Business Machines Corporation. Multichannel magnetic head with common leg, 3,579,214, Cl. 340-174.1

Songrand Corporation, The: See—
McNair, Samuel L., 3,578,947.

Sonnen, Victor G. Hair and scalp treatment with a principally sodium chloride thick viscous aqueous slurry, 3,579,632, Cl. 424-70.

Sonotone Corporation: See—
Knauer, William F., 3,578,921.

Sony Corporation: See—
Miyakawa, Senri, 3,579,008.

Okamoto, Noriaki; Wakabe, Teruo; and Nozawa, Kazuo, 3,578,920.

Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.

Sorensen, Robert L.: See—
Hudock, Edward P.; Russell, Irving G.; and Sorensen, Robert L., 3,578,862.

South African Inventions Development Corporation: See—
Meiring, Pieter Gerhard Jacobus; and Huisman, Peter Hendrik, 3,579,439.

Speed Equipment Incorporated: See—
Schramm, Richard F., 3,578,747.

Sperry Rand Canada Limited: See—
Paul, John J., 3,579,126.

Sperry Rand Corporation: See—
Chen, Wu, 3,578,846.

Halls, Lawrence M.; Lausch, Henry N.; and Schwalm, Bruce D., 3,578,750.

Lincoln, Andrew James, 3,579,204.

Reinert, Owen E., 3,579,087.

Taylor, John R., 3,579,064.

Spescha, Gelli, to Elektrophysikalische Anstalt Bernhard Berghans. Monitoring circuit for a high-intensity glow discharge for metallurgical processes, 3,579,029, Cl. 315-127.

Spigerverk, Christiania: See—
Dowhan, Wesley P.; Aas, Helge; and Nordheim, Rolf, 3,579,328.

Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., to Phillips Petroleum Company Kaiser Industries Corporation. Cutting and sealing unit Steel-making process employing an auxiliary composition, 3,579,325, Cl. 156-515.

Sprecher & Schuh AG: See—
Roth, Adrian W., 3,578,927.

Spreitzer, Helmut, to Contraves AG. Multipositional switch construction, 3,579,257, Cl. 200-11.

Springer, Reinhard: See—
Drescher, Kurt; and Springer, Reinhard, 3,579,071.

Springfield, Carlos L.: See—
Evans, Fred D.; Springfield, Carlos L.; and Bryan, Coleman J., 3,578,756.

Springfield, James F.: See—
Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., 3,579,335.

Sproule, Robert Stanley; Kanger, Feodor; and Seybold, Hugh Laurie, to Dominion Engineering Works, Limited. Removable runner seal, 3,578,874, Cl. 415-170.

Spruth, Wilhelm, to International Business Machines Corporation. Method and apparatus for checking a data transfer operation, 3,579,185, Cl. 340-146.1

Square D Company: See—
Chaffard, Francoise; Backderf, Robert P.; and Kanitz, Douglas R., 3,579,038.

Squibb, E. R., & Sons, Inc.: See—
Ondetti, Miguel A.; Sheehan, John T.; and Pluscec, Josip, 3,579,494.

Stahlhut, Leo G.; and Horvath, Leo J., to K-S-H, Inc. Prismatic lighting panel, 3,578,967, Cl. 240-106.

Stampco, Inc.: See—
Deane, Clifford T., 3,578,935.

Standard Oil Company (Indiana): See—
Jacobs, Robert B., 3,579,032.

Stanley Works, The: See—
Morrow, George W.; and West, Robert F., 3,578,825.

Stapleford, Gary N., to Sanders Associates, Inc. Apparatus for programmable control of electromechanical devices, 3,579,197, Cl. 340-172.5

Stark, Bernard Peter: See—
Nachbur, Hermann; Stark, Bernard Peter; and Maeder, Arthur, 3,579,532.

Stauffer Chemical Company: See—
Harrison, Alvin, 3,579,448.

Tilles, Harry; and Brokke, Mervin E., 3,579,525.

Steadman, John T.: See—
Redding, Billy J.; Steadman, John T.; and Bragg, Lorel J., 3,578,740.

Steenbeck, Max; and Krause, Fritz, to Deutsche Akademie der Wissenschaften. Magneto-hydrodynamic energy conversion process, 3,578,999, Cl. 310-11.

Steibl, Theodor: See—
Roth, Johann; Roppel, Alfred; and Steibl, Theodor, 3,578,853.

Steiger, Richard J., to Ampex Corporation. Automatic quadrature and amplitude stabilizer, 3,579,268, Cl. 235-189.

Steinbrecher, Lester: See—
Manson, Frank E.; and Steinbrecher, Lester, 3,579,429.

Steingart, Richard D.; and Wilmot, Richard D., to Hughes Aircraft Company. Method and apparatus for azimuth bias error correction of sequential-observer detectors, 3,579,237, Cl. 343-6.

Sterling Drug Inc.: See—
Bailey, Denis M., 3,579,520.

Stern, Silviu A.: See—
Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silviu A., 3,579,292.

Sternbach, Leo Henryk: See—
Archer, Giles A.; and Sternbach, Leo Henryk, 3,579,580.

Stevens, Richard W., to Milwaukee Boiler Manufacturing Company. Segmented bulkhead for tunnels and the like, 3,578,752, Cl. 61-83.

Stevenson, Louis A., Jr., 'Automatic' Sprinkler Corporation. Alarm system, 3,579,220, Cl. 340-258.

Stewart, Aubrey P., Jr.; Dreier, Clarence R., Jr.; and Gregory, Jim C. Sterilization of materials containing protein, 3,579,631, Cl. 424-86.

Stewart, Dan F.; Blair, Bob C.; Greene, Max E.; and Alexander, Lloyd R., to Phillips Petroleum Company. High speed fibrillation process, 3,579,618, Cl. 264-37.

Stewart, Robert M., to Aerojet-General Corporation. Electrochemical inhibit gate, 3,579,202, Cl. 340-173.

Stillings, William K.; Miller, Donald E.; and Gilmore, Cecelia R., to Xerox Corporation SCM Corporation. Mechanical stripping apparatus Titanium dioxide whitened comestible compositions, 3,579,356, Cl. 99-148.

Stimpson, Ian William: See—
Bentham, Frederick Percy; Sheridan, Phillip Robert; Foreman, Joseph Trevor; and Stimpson, Ian William, 3,579,030.

Stimus, Charles C., Jr.: See—
Von Hippel, Eric A.; and Stimus, Charles C., Jr., 3,578,909.

Stobbe, Richard E.: See—
Johnstone, Richard; and Stobbe, Richard E., 3,579,073.

Stock, Hans Joachim, to Morat, Franz, G.m.b.H. Arrangement and process for reproducing color patterns electronically, 3,578,897, Cl. 178-5.2

Stock, Hans Joachim; and Gottschall, Gernot, to Morat, Franz, G.m.b.H. Optical-electronic picture storage apparatus, 3,578,907, Cl. 178-6.8

Stockmann, Hans H.; Ray-Chaudhuri, Dilip K.; and Boettger, Richard M., to National Starch and Chemical Corporation. Acyl derivatives of the condensation polymers of alpha-hydroxy-propionic acid with beta-hydroxybutyric acid and/or beta-hydroxypropionic acid, 3,579,549, Cl. 260-410.9

Stoller, Arthur Irwin, to RCA Corporation. Method of making a semiconductor article and the article produced thereby, 3,579,057, Cl. 317-234.

Stoller, Jerry H.: See—
Kanyok, Anthony J.; Stoller, Jerry H.; and Keller, William H., 3,579,321.

Stone, Joseph K.: See—
Spitznagel, Robert J.; Stone, Joseph K.; Beck, Peter J.; and Prince, Edward J., 3,579,325.

Storms, Phillip W.; and Farrar, Grover L., to Marathon Oil Company. Process for the hydrogenation of mixed naphthalene esters and compositions derived therefrom, 3,579,563, Cl. 260-468.

Strand Electric & Engineering Company, Limited, The: See—
Bentham, Frederick Percy; Sheridan, Phillip Robert; Foreman, Joseph Trevor; and Stimpson, Ian William, 3,579,030.

Stratienko, Andrew, to King of Prussia Research and Development Corporation. Mixer, 3,578,876, Cl. 416-121.

Straub, Kenneth Luke; and Shear, Wayne Gregory, to Bendix Corporation. The. Collision avoidance readout on air traffic control radar beacon systems, 3,579,235, Cl. 343-6.5

Strauss, Robert G.: See—
Shaw, Charles H.; and Strauss, Robert G., 3,579,622.

Strehlow Robert J., to Wehr Corporation. Multi-point control system, 3,579,226, Cl. 340-339.

Strilko, Peter S., to Du Pont de Nemours, E. I., and Company. Filament wound cylindrical structures for use in paper making Leuco triaryl-methane hexaarylbiimidazole color forming system containing a deactivator, 3,579,342, Cl. 96-90.

Strobel, Rudolf G. K., to Proctor & Gamble Company, The. for continuous flow of cellulosic material Isolating acidic materials from a thin film, 3,579,340, Cl. 162-237.

Stromberg Datagraphics Inc.: See—
Corpew, Charles R., 3,579,014.

Stroop, John Henry; Kennedy, Theodore R.; and Rowan, Henry M., to Total Packaging Inc. Inductotherm Corporation. Apparatus for making composite filament or fiber thermoplastic products Method for induction melting of fine particles, 3,579,324, Cl. 75-10.

Sturdevant, William H.: See—
Beavers, William E., Jr.; and Sturdevant, William H., 3,578,912.

Sturm, Konrad; Becker, Willy; Timm, Heinz; and Rummel, Karlheinz, to Diehl Firma. Keyboard using switches having light obstructing elements, 3,579,047, Cl. 250-221.

Sud-Chemie AG: See—
Wiesboeck, Robert A.; and Friese, Hermann, 3,579,380.

Sun Oil Company: See—
Angstadt, Howard P., 3,579,576.

Olenzak, Albert T.; and Thompson, Sheldon L., 3,579,435.

Tumolo, Anthony L., 3,579,604.

Tumolo, Anthony L., 3,579,605.

Wentzheim, William W.; Reynolds, Ronald W.; and Chalpin, William, 3,579,437.

Sunbeam Corporation: See—
Walter, John, 3,579,007.

Supreme Equipment & Systems Corporation: See—
Frederick, Philip, 3,578,833.

Suschuk-Sljusarenko, Igor Ivanovich: See—
Medovar, Boris Izrailevich; Dudko, Daniil Andreevich; Baglai, Vitaly Mikhailovich; Bondarenko, Oleg Petrovich; Sevruk, Albert Nikolaevich; Dubinsky, Rudolf Solomonovich; Andreev, Vladimir Prokhorovich; Andrianov, Georgy Grigorievich; Sindeev, Valentin Stepanovich; Safonnikov, Anatoly Nikolaevich; and Suschuk-Sljusarenko, Igor Ivanovich, 3,578,938.

Suszer, Adalbert; and Patel, Himanshu M., to Westinghouse Electric Corporation Israel, State of, Prime Minister's Office. Method of metallizing a luminescent screen Permeable selective cellulose membranes reacted with a sulfonated trichloropyrimidine dye, 2,3-dichloroquin-oxaline dye or dichloro-s-triazines, 3,579,288, Cl. 8-116.2

Sutani, Sotou: See—
Kuroda, Toshihiko; Sutani, Sotou; Nitta, Haruo; and Saito, Sadao, 3,579,428.

Suvorova, Maria Dmitrievna: See—
Samuilov, Viktor Ivanovich; Genkin, Jury Markovich; and Suvorova, Maria Dmitrievna, 3,578,757.

Suzuki, Keisuke: See—
Tsumura, Takao; Kaooka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.

Sylanski, Piotr, to General Electric and English Electric Companies Limited, The. Code translation circuits, 3,579,231, Cl. 340-347.

Sylvania Electric Products, Inc.: See—
De Vos, Hendrik A.J.; and Haraden, Thomas, 3,578,963.

Gilbert, Marcellus N., Jr., 3,579,174.

Johannessen, Paul R.; and Knutrud, Thorleif, 3,579,093.

Johannessen, Paul R.; and Knutrud, Thorleif, 3,579,111.

Kimball, Stephen F., 3,579,021.

Levin, Robert E., 3,578,966.

Lovelace, Ralph E., 3,579,251.

Paget, Frederick W., 3,579,026.

Rhee, Dong Woo, 3,579,139.

Symon, Ted, to Universal Oil Products, Company. Hydroxy and/or hydrocarbyloxy and amino substituted tetrahydronaphthalenes, 3,579,582, Cl. 260-574.

Sztankay, Zoltan G.: See—
Holland, Richard J.; Kilduff, Timothy J.; and Sztankay, Zoltan G., 3,578,842.

Taddeo, Fausto V., to Hughes Aircraft Company. Beam interpolating system, 3,579,180, Cl. 340-3.

Takahira, Jiro: See—
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.

Takahashi, Takeyoshi: See—
Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, 3,579,247.

Takeda Chemical Industries, Ltd.: See—
Hayakawa, Zenro, 3,579,627.

Hiraga, Kentaro; Asako, Tsunehiko; and Miki, Takuichi, 3,579,544.

Miyamoto, Masuo; and Murata, Tadakazu, 3,579,505.

Talley, Drayton H.: See—
Bynum, Bobby G.; and Talley, Drayton H., 3,578,755.

Talley Industries, Inc.: See—
Thomas, Raymond W.; and Pittinger, Abraham L., 3,578,974.

Tamise, Louis; Dennilaule, Rene Jean; Millet, Jacques; Pfaff, Maurice Edgar; and Roman, Pierre Amedee, to Pechiney-Compagnie de Produits Chimiques et Electrometallurgiques, and Eastman Kodak Company Societe Appareils et Evaporateurs Kestner. Process for extraction of alumina from ores by Sheet supported articles coated with heat-activable tanning agents and improved methods of hardening said solution of caustic soda and sodium aluminate articles and related compositions, 3,579,374, Cl. 117-164.

Tamise, Louis; and Millet, Jacques, to Pechiney-Compagnie de Produits Chimiques et Electrometallurgiques, and Societe Appareils et Evaporateurs Kestner. Process for attack of bauxite with alkaline solution, 3,579,295, Cl. 23-52.

Tamura, Michio; Allen, Lloyd R.; Beecher, Norman; Feakes, Frank; and Springfield, James F., to Sony Corporation National Research Corporation. Method for manufacturing color television receiver tubes Structural laminates, 3,579,335, Cl. 161-184.

Tanaka, Takeo: See—
Kawaguchi, Toshiji; Tanaka, Takeo; and Okada, Masaru, 3,578,979.

Tang, Calvin K.: See—
Yau, Sik-Sang; and Tang, Calvin K., 3,579,119.

Tanner, Bobby G.: See—
Hagler, Travis J.; Puckett, William R.; and Tanner, Bobby G., 3,578,796.

Tanner, Robert Gene: See—
Tausig, Frederick; and Tanner, Robert Gene, 3,578,812.

Tate, Jack F., to Texaco Inc. Method of and composition for the treatment of scale, 3,579,445, Cl. 210-58.

Tausig, Frederick; and Tanner, Robert Gene, to Arundale Manufacturers, Inc. Support wheel and method of making same, 3,578,812, Cl. 301-63.

Tawil, Joseph N.; Hartz, George R.; and Walsh, Edmund F., to Berkey/Colortran Mfg., Inc. Foldable luminaire, 3,578,965, Cl. 240-36.

Taylor, Brian W.: See—
Drinkard, William Charles, Jr.; and Taylor, Brian W., 3,579,560.

Taylor, John R., to Sperry Rand Corporation. Solid state motor control circuit using triac elements, 3,579,064, Cl. 318-207.

Taylor, Robert B.; and Walker, Robert G., said Walker assor to Peden, Allan W. Apparatus for applying coating to sheet material, 3,578,772, Cl. 118-33.

Tefertiller, Nancy B.: See—
Jones, Giffin D.; and Tefertiller, Nancy B., 3,579,488.

Tegner, Claes Philip: See—
Sandberg, Rune Verner; Sjoberg, Berndt Olof Harald; and Tegner, Claes Philip, 3,579,523.

Tegner, Gunnar Margareta: See—
Sandberg, Rune Verner; Sjoberg, Berndt Olof Harald; and Tegner, Claes Philip, 3,579,523.

Tekathen, Hans: See—
Bassier, Friedrich-Karl; and Tekathen, Hans, 3,578,811.

Tektronix, Inc.: See—
Griffin, John R.; and Forsberg, Charles A., 3,579,224.

Teletype Corporation: See—
Arko, Robert E., 3,578,910.

Berry, James M., 3,579,245.

Cook, Harold D., 3,579,273.

Tenenbaum, Nathaniel D., to Westinghouse Electric Corporation. Desensitizing circuit for a differential relay, 3,579,040, Cl. 317-27.

Tesco Chemicals, Inc.: See—
Bradley, William E., Jr., 3,579,440.

Schneider, Thomas E., Jr.; Carstens, Marion R.; and Bates, Homer J., 3,578,776.

Te Velde, Ties Siebolt; and Schmitz, Albert, to U.S. Philips Corporation, mesne. Semiconductor circuit having active devices embedded in flexible sheet, 3,579,056, Cl. 317-234.

Texaco Inc.: See—
Larkin, John M., 3,579,594.

Tate, Jack F., 3,579,445.

Texas Instruments, Incorporated: See—
Grable, Jack W., 3,579,167.

Texas Petroleum Company: See—
Nino, Victor J., 3,578,886.

Thate, Kurt; Winkler, Friedrich; and Theer, Anton, to Agfa-Gevaert Aktiengesellschaft. motion picture camera with footage counter, 3,578,856, Cl. 352-172.

Theer, Anton: See—
Thate, Kurt; Winkler, Friedrich; and Theer, Anton, 3,578,856.

Thigpen, David R.: See—
Abrams, Albert; Hill, Harold J.; and Thigpen, David R., 3,578,781.

Thiokol Chemical Corporation: See—
Hagler, Travis J.; Puckett, William R.; and Tanner, Bobby G., 3,578,796.

Thomas & Betts Corporation: See—
Lynch, Leslie S., 3,578,896.

Thomas, Harold A., to Gulf Energy & Environmental Systems, Inc., mesne. Apparatus for monitoring pulses, 3,579,127, Cl. 328-145.

Thomas, James Larue, to FMC Corporation. Compounding aids for thermosetting allylic resin molding compounds, 3,579,484, Cl. 260-78.4

Thomas Machinery Corporation: See—
Casey, Thomas J.; and Loeffler, George F., 3,579,217.

Thomas, Raymond W.; and Pittinger, Abraham L., to Talley Industries, Inc. Infrared source utilizing an exothermic chemical charge having stable and non-segregating reaction products, 3,578,974, Cl. 250-85.

- Thompson, Sheldon L.: *See—*
Olenzak, Albert T.; and Thompson, Sheldon L., 3,579,435.
- Thomson, Richard N.; Osmalov, Jerome S.; and Mathe, George L., to Morris, Philips, Corporation. Forming filled continuous plastic rod such as plastic cigarette filter rod filled with a tow of cellulose acetate. 3,579,623, Cl. 264-135.
- Thomson, Robert Orrock, to Burroughs Wellcome & Co. (U.S.A.) Inc. Multiple clostridial antigen vaccine for cattle and sheep. 3,579,633, Cl. 424-92.
- Tiefenthaler, Wolfgang, to Messerschmitt-Bolkow-Blohm. Multiple electric switch. 3,578,930, Cl. 200-153.
- Tiegel, Ernest G.; and Tiegel, Ralph G., to Asahi Kasei Kogyo Kabushiki Kaisha Tiegell Manufacturing Co. Apparatus for recovering acrylonitrile monomer in the production of a polymer intercell connectors in batteries and method of forming same. 3,579,386, Cl. 136-134.
- Tiegell Manufacturing Co.: *See—*
Tiegel, Ernest G.; and Tiegel, Ralph G., 3,579,386.
- Tiegel, Ralph G.: *See—*
Tiegel, Ernest G.; and Tiegel, Ralph G., 3,579,386.
- Tilles, Harry; and Brokke, Mervin E., to Stauffer Chemical Company. S-(pyridyl)methyl thio- and dithio-carbamates. 3,579,525, Cl. 260-294.8
- Time, Incorporated: *See—*
Hudock, Edward P.; Russell, Irving G.; and Sorensen, Robert L., 3,578,862.
- Timm, Heinz: *See—*
Sturm, Konrad; Becker, Willy; Timm, Heinz; and Rummel, Karl-Heinz, 3,579,047.
- Todd, Percy E., to Todd, Percy Manufacturing Company. Method and apparatus for conveying dust. 3,578,814, Cl. 302-40.
- Todd, Percy Manufacturing Company: *See—*
Todd, Percy E., 3,578,814.
- Tokumitsu, Kunio: *See—*
Wakita, Eiichi; and Tokumitsu, Kunio, 3,579,307.
- Tokyo Shibaura Electric Co., Ltd.: *See—*
Ando, Kenichiro; and Barrett, Lawrence G., 3,579,410.
Sakamoto, Tetsuzo, 3,578,871.
Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., 3,579,317.
- Tompkins, William R., to Cohu Electronics, Inc. Automatic peak video control system. 3,578,908, Cl. 178-7.2
- Toms, Lloyd M., to Acme Visible Records, Inc. Stabilized elevator filing device. 3,578,832, Cl. 312-268.
- Tonelli, Roger R., to Radio Steel & Mfg. Co. Trailer and undercarriage therefor. 3,578,806, Cl. 298-5.
- Total Packaging Inc.: *See—*
Stroop, John Henry; Kennedy, Theodore R.; and Rowan, Henry M., 3,579,324.
- Traver, Alfred E., to Mobil Oil Corporation. Method and apparatus for photo-electrically monitoring the degradation of an oil stream. 3,578,865, Cl. 356-70.
- Travis, Allen Edwin, to AMP Incorporated. Electrical terminal and housing therefor. 3,579,178, Cl. 339-221.
- Traxler, James T., to SCM Corporation, mesne. Carboxylic acid esters. 3,579,547, Cl. 260-410.6
- Tri W-G Inc.: *See—*
Bearfield, Clair C.; and Cole, Raymond, 3,579,066.
- Trico Products Corporation: *See—*
Riester, William C., 3,579,067.
- Tripp, Robert W., to Inductosyn Corporation. Precision switching network for a digital to analog converter. 3,579,229, Cl. 340-347.
- Tripp, Walter D.: *See—*
Purcell, William O., Jr.; and Tripp, Walter D., 3,579,239.
- Trubiano, Paolo C.; and Marotta, Nicholas G., to National Starch and Chemical Corporation. Continuous cellulose digester with two separate pulp outlets Pulp textured food systems containing inhibited. 3,579,341, Cl. 162-237.
- TRW Inc.: *See—*
Brooks, Robert E., 3,578,837.
Brooks, Robert E.; Heflinger, Lee O.; and Wuerker, Ralph F., 3,578,845.
Cronin, Donald L.; Farber, Bertrand F.; and Nockey, Charles R., 3,579,078.
Short, Oliver A.; and Buie, James Lang, 3,579,391.
- Tschang, Teh C., to Air Reduction Company, Incorporated. Servo controlled height control. 3,579,068, Cl. 318-478.
- Tsujimoto, Kayoshi: *See—*
Kobayashi, Tatsuo; and Tsujimoto, Kayoshi, 3,578,765.
- Tsumura, Takao; Kaooka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, to Japan Radio Company, Limited. Character generator for radar display. 3,579,234, Cl. 343-5.
- Tuchto, Jeff, to Bunker-Ramo Corporation, The. Filtered connector pin contact. 3,579,155, Cl. 333-79.
- Tumolo, Anthony L., to Sun Oil Company. Isomerization of octalins. 3,579,604, Cl. 260-666.
- Tumolo, Anthony L., to Sun Oil Company. Isomerization of octalins. 3,579,605, Cl. 260-666.
- Tunzini-Sames: *See—*
Felici, Noel, 3,578,997.
- Turner, Trevor Stanley; and Padley, Frederick Bolton, to Lever Brothers Company International Nickel Company, Inc. Process for activating metal foil for use as a Heat scanned chromatographic detector positive electrode in alkaline storage batteries. 3,579,383, Cl. 136-76.
- Turolia, Marco. Geared pumps. 3,578,887, Cl. 418-132.
- Tuttle, James A.: *See—*
Holmstrom, Larry W.; Tuttle, James A.; and Young, Harold J., 3,578,906.
- Twilley, Ian C.; Russell, William N.; and Peterson, Weldon H., to Allied Chemical Corporation. E-caprolactam continuous polymerization process. 3,579,483, Cl. 260-78.
- Ueda, Hiroyuki: *See—*
Ooue, Shingo; Ueda, Hiroyuki; and Hayakawa, Yoshihide, 3,579,338.
- Ueda, Keizo: *See—*
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
- Ueda, Yoshiaki: *See—*
Tsumura, Takao; Kaooka, Toshio; Suzuki, Keisuke; Oishi, Naoyoshi; Ueda, Yoshiaki; and Oishi, Naoyoshi, 3,579,234.
- Ueno, Tamotsu: *See—*
Ito, Yoshiro; Ueno, Tamotsu; Nakano, Takashi; and Okamoto, Kazuo, 3,579,599.
- Ufkes, Pieter Johan, to U.S. Philips Corporation, mesne. Transistor amplifier with negative feedback volume control. 3,578,913, Cl. 179-1.
- Ultrasonic Systems, Inc.: *See—*
Balamuth, Lewis, 3,578,996.
- Umbach, Wilfried, to Henkel & Cie, G.m.b.H. N-decatriene isomerization. 3,579,606, Cl. 260-677.
- Umehara, Yoichi: *See—*
Minohara, Kiyomi; Ishida, Hiroshi; Miyata, Tomoyoshi; Takashima, Takeyoshi; and Umehara, Yoichi, 3,579,247.
- Unger, Manfred Otto, to Du Pont de Nemours, E. I., and Company. Preparing mucononitrile from benzene. 3,579,559, Cl. 260-465.3
- Unilever N.V.: *See—*
Van Dorp, David Adriaan; Beerthuis, Roelof Karel; Nugteren, Diederik Hendrik; and Vonkeman, Hendrik, 3,579,425.
- Uniline Corporation: *See—*
Viti, Florindo, 3,578,870.
- Union Carbide Corporation: *See—*
Brotherton, Thomas K.; and Lynn, John W., 3,579,482.
Dooley, Joseph A.; Gnozzio, Michael J.; Mullhaupt, Joseph T.; and Stern, Silviu A., 3,579,292.
Matzner, Markus; and Noshay, Allen, 3,579,607.
Potter, John J., Jr.; and Hamel, William J., 3,578,788.
Salensky, George A., 3,579,473.
- Union Oil Company of California: *See—*
Fenton, Donald M., 3,579,566.
Hansford, Rowland C., 3,579,598.
- United Aircraft Corporation: *See—*
Bradley, Elihu F.; Bartlett, Edwin S.; Ogden, Horace R.; and Jaffee, Robert I., 3,578,743.
- Dagne, Louis C.; McLean, Howard J.; and Bonner, George A., 3,578,889.
- Ekblom, Karl Gote; and Vincent, George E., Jr., 3,579,376.
- United Kingdom Atomic Energy Authority: *See—*
Daly, Norman Richard; and Powell, Royal Edward, 3,579,270.
- United States of America
Agriculture: *See—*
Bleiweiss, Eugene; Soignet, Donald M.; and Benerito, Ruth R., 3,579,289.
Halbrook, Noah J.; and Lawrence, Ray V., 3,579,571.
Martinez, Wilda H.; and Berardi, Leah C., 3,579,496.
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.
Purcell, Albert E.; and Walter, William M., Jr., 3,579,424.
Vail, Sidney L.; Pierce, Andrew G., Jr.; Moran, Clifford M.; and Barker, Robert H., 3,579,536.
- Army: *See—*
Allan, Barry D.; and Cunningham, John J., Jr., 3,579,314.
Hellwig, Helmut W., 3,578,968.
Holland, Richard J.; Kilduff, Timothy J.; and Sztankay, Zoltan G., 3,578,842.
O'Hara, John Henry, 3,579,124.
- Health, Education and Welfare: *See—*
Riggle, Grant C.; and White, James P., 3,578,839.
- Interior: *See—*
Pingel, Vernon J., 3,579,373.
- National Aeronautics and Space Administration, Administrator, with respect to an invention of:
Cohen, Murray F. Digital modulator and demodulator. 3,579,146, Cl. 332-9.
Kaznoff, Alexis I., and Marlowe, Mickey O. Process and apparatus for producing UO₂ powder Method of making a cermet. 3,579,390, Cl. 148-126.
- National Aeronautics and Space Administration: *See—*
Altshuler, Thomas L., 3,578,758.
Barrington, Alfred E., 3,578,867.
Brown, Kenneth H.; and Fitting, Robert C., 3,579,147.
Bynum, Bobby G.; and Talley, Drayton H., 3,578,755.
Evans, Fred D.; Springfield, Carlos L.; and Bryan, Coleman J., 3,578,756.
Gatlin, James A., 3,578,957.
Grantham, William L., 3,579,242.

- Hallock, James N., 3,578,838.
Russell, Charles H., 3,579,103.
Vary, Alex, 3,579,168.
- National Aeronautics and Space Administration: *See—*
Slowikowski, Daniel F., 3,578,988.
- Navy: *See—*
Gerber, Robert L., 3,578,962.
Haef, Andrew V.; and Harris, Franklin H., 3,579,238.
Naubereit, Henry, 3,578,990.
Smiley, Vern N., 3,579,130.
Smiley, Vern N., 3,579,142.
Smith, Ervin; and Wedel, John O., 3,579,128.
- United States Steel Corporation: *See—*
Wiesboeck, Robert A.; and Friese, Hermann, 3,579,380.
- Universal Oil Products Company: *See—*
Jones, Edwin K., 3,579,603.
Symon, Ted, 3,579,582.
- Upjohn Company, The: *See—*
Argoudelis, Alexander D.; Coats, John H.; Mason, Donald J.; and Sebek, Oldrich K., 3,579,426.
Dahlgren, Donald A., 3,579,433.
Hester, Jackson B., Jr., 3,579,503.
- Urbach, Hans: *See—*
Punderson, John Oliver; Ludwig, Winfried; Roura, Miguel Jacinto; Oster, Rudolf; and Urbach, Hans, 3,579,291.
- U.S. Philips Corporation: *See—*
Schjolberg, Eiler; Zwicker, Walter K.; and Milch, Alfred, 3,579,359.
Te Velde, Ties Siebolt; and Schmitz, Albert, 3,579,056.
Ufkes, Pieter Johan, 3,578,913.
Van Bruck, Heinrich Eduard; and Holtwijk, Theodoor, 3,579,210.
- Utita Office E Fonderie Di Este S.p.A.: *See—*
Polese, Gaspare, 3,578,795.
- Vail, Sidney L.; Pierce, Andrew G., Jr.; Moran, Clifford M.; and Barker, Robert H., to United States of America, Agriculture. Addition products of methylformamide or succinimide with glyoxal. 3,579,536, Cl. 260-326.3
- Van Berkel, Franciscus C.A.A.: *See—*
Brown, Martin Granger; Van Berkel, Franciscus C.A.A.; and Luques, Stanley F., 3,579,379.
- Van Bruck, Heinrich Eduard; and Holtwijk, Theodoor, to U.S. Philips Corporation. Matrix storage device. 3,579,210, Cl. 340-174.
- Van Den Heuvel, Walter August: *See—*
Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, 3,579,416.
Brinckman, Eric Maria; Vanhalst, Johan Eugene; Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, 3,579,417.
- van der Meer, Wilhelmus Teuis, to Distillers Company Limited, The. Production of acrylic acid. 3,579,574, Cl. 260-530.
- Van Dorp, David Adriaan; Beerthuis, Roelof Karel; Nugteren, Diederik Hendrik; and Vonkeman, Hendrik, to Unilever N.V. Preparation of prostaglandins. 3,579,425, Cl. 195-30.
- Van Dyke, John William, Jr., to Miles Laboratories, Inc. 2-Aminoalkyl derivatives of phthalimidenes. 3,579,524, Cl. 260-294.
- Vanhalst, Johan Eugene: *See—*
Brinckman, Eric Maria; Van Den Heuvel, Walter August; Schrenk, Walter J.; and Vanhalst, Johan Eugene, 3,579,416.
Brinckman, Eric Maria; Vanhalst, Johan Eugene; Carlsmith, Lawrence Allan; and Van Den Heuvel, Walter August, 3,579,417.
- van Hazendonk, Johannes Franciscus, to De Jong & De Vlieger Machinehandel N.V. Sewing machine. 3,578,770, Cl. 112-219.
- Vapor Corporation: *See—*
Olsen, Robert M., 3,579,051.
- Varian Associates: *See—*
Heer, John, 3,579,278.
Noble, Lowell A.; and Hanley, Robert B., 3,578,835.
- Vary, Alex, to United States of America, National Aeronautics and Space Administration. Cyclic switch. 3,579,168, Cl. 337-114.
- Vasel, Alfred W. Particle detector. 3,579,216, Cl. 340-237.
- Veeder Industries Inc.: *See—*
Barrett, James P.; and Gamble, John G., 3,578,954.
- Verdier, Emile Joseph-Henri, to Aktiebolaget Bofors. Hydraulic anti-theft system for vehicles. 3,579,285, Cl. 307-10.
- Vess, Samuel P., to Decor Dimensionals, Inc., mesne. Polyester coating and molding composition. 3,579,477, Cl. 260-40.
- Vestal, Marvin L., to Scientific Research Instruments Corporation. Harp electron multiplier. 3,579,017, Cl. 313-105.
- Vincent, George E., Jr.: *See—*
Ekblom, Karl Gote; and Vincent, George E., Jr., 3,579,376.
- Viout, Andre: *See—*
Pasero, Regine nee Perruche; and Viout, Andre, 3,579,629.
- Viti, Florindo, to Uniline Corporation. Ink writing instrument. 3,578,870, Cl. 401-199.
- Vitramon, Incorporated: *See—*
Caires, Eugene J., 3,578,895.
- Vollrath, Donald E., to Allis, Louis, Company, The. Zero deadband reversing control. 3,579,080, Cl. 321-5.
- Von Hippel, Eric A.; and Stimus, Charles C., Jr., assors. to Graphic Sciences, Inc. Paper feed cable indexing system. 3,578,909, Cl. 178-7.6
- Vonkeman, Hendrik: *See—*
Van Dorp, David Adriaan; Beerthuis, Roelof Karel; Nugteren, Diederik Hendrik; and Vonkeman, Hendrik, 3,579,425.
- von Wittenau, Manfred Schach: *See—*
Blackwood, Robert K.; and von Wittenau, Manfred Schach, 3,579,564.
- Voyentzie, Peter R.; and Lehn, Robert J., to General Electric Company. Apparatus for manufacturing high pressure inert gas Sealed aqueous alkaline electrolyte cells with. 3,579,387, Cl. 23-281.
- Vrillon, Claude: *See—*
Antonini, Albert; Joffe, Philippe; and Vrillon, Claude, 3,579,597.
- Wachtel, Anselm, to Westinghouse Electric Corporation. Method of preparing crystalline calcium halophosphate phosphor. 3,579,463, Cl. 252-301.4
- Wacker, Hans, to Renz Wacker & Co. Making of rivet head bimetallic electrical contacts. 3,579,261, Cl. 219-154.
- Wagner, Willem M., to Shell Oil Company. Polymerization of beta-lactones. 3,579,489, Cl. 260-78.3
- Wakabe, Teruo: *See—*
Okamoto, Noriaki; Wakabe, Teruo; and Nozawa, Kazuo, 3,578,920.
- Wakita, Eiichi; and Tokumitsu, Kunio, 3,579,307, Cl.
Walden, Robert H., to Bell Telephone Laboratories, Incorporated. Thin film thermal device. 3,579,137, Cl. 330-38.
- Waldon, Paul L., to General Electric Company. Individual current limiting fuse for the rolls of a multiple roll capacitor. 3,579,061, Cl. 317-247.
- Walker, John H., to Bendix Corporation, The. Gaging apparatus and method. 3,578,746, Cl. 33-174.
- Walker, Peter: *See—*
Chang, Catherine Teh-Lin; and Walker, Peter, 3,579,339.
- Walker, Robert G.: *See—*
Taylor, Robert B.; and Walker, Robert G., 3,578,772.
- Walles, Wilhelm E., to Dow Chemical Company, The. Molecular complexes of cyclic carbamate polymers with phenols and thiophenols. 3,579,515, Cl. 260-244.
- Walsh, Edmund F.: *See—*
Tawil, Joseph N.; Hartz, George R.; and Walsh, Edmund F., 3,578,965.
- Walsh, William B.: *See—*
Rubens, Louis C.; and Walsh, William B., 3,579,472.
- Walter, George R.: *See—*
Nikawitz, Edward J.; and Walter, George R., 3,579,578.
- Walter, John, to Sunbeam Corporation. Commutator brush structure for electric motor. 3,579,007, Cl. 310-242.
- Walter, William M., Jr.: *See—*
Purcell, Albert E.; and Walter, William M., Jr., 3,579,424.
- Wang, Han-Chiu, to Bell Telephone Laboratories, Incorporated. Microwave filter. 3,579,153, Cl. 333-73.
- Wann, Robert Earl; Nicholson, Denzel Allan; and Logan, Ted Joe, to Procter & Gamble Company, The. Lubricant composition. 3,579,449, Cl. 252-49.5
- Ward, Cecil R.; and Schwarzkopf, August, to PPG Industries, Inc. Windmoller & Holscher. Method of and apparatus for forming glass sheets by drawing downwardly Process of manufacturing bags having tear strips and consisting of synthetic thermoplastics. 3,579,397, Cl. 156-251.
- Warnock, Merville L.: *See—*
Edington, John E.; and Warnock, Merville L., 3,579,253.
- Warren, James A.: *See—*
Reuteler, Johann F.; and Warren, James A., 3,579,069.
- Wasa, Kiyotaka; and Hayakawa, Shigeru, to Matsushita Electric Industrial Co., Ltd. Thin film capacitor. 3,579,063, Cl. 317-258.
- Washburn, Robert L.; Kruk, William J.; Goto, Eizo; and McDonald, William S., to Tokyo Shibaura Electric Co. Ltd. International Paper Company. Method of mutually bonding parts by use of glass Method for producing rolled edge board. 3,579,317, Cl. 156-202.
- Watkins, Windell C.: *See—*
Folzenlogen, Paul D.; Watkins, Windell C.; and Hagemeyer, Hugh J., Jr., 3,579,485.
- Weber, Earl J.: *See—*
De Werth, Douglas W.; and Weber, Earl J., 3,578,987.
- Weber, Kurt; Liechti, Peter; Meyer, Rudolf; and Siegrist, Adolf Emil, to Ciba Limited. Triazole compounds, processes for their manufacture and use. 3,579,511, Cl. 260-240.
- Webert, Jacques Robert, to Commissariat a l'Energie Atomique. Surgical electric welding apparatus. 3,578,941, Cl. 219-114.
- Webster, Frank G., to Eastman Kodak Company. Novel dyes and direct positive photographic emulsions. 3,579,344, Cl. 96-102.
- Wedel, John O.: *See—*
Smith, Ervin; and Wedel, John O., 3,579,128.
- Wege, Hans: *See—*
Shimura, Kimio; Wege, Hans; and Gast, Erich, 3,579,351.
- Wehr Corporation: *See—*
Strehlow Robert J., 3,579,226.
- Weigert, Wolfgang, to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler. Process for hydroformylating unsaturated esters or nitrile. 3,579,562, Cl. 260-465.1
- Weil, Thomas L.: *See—*
Nunnally, Robert L.; Bookwalter, George N.; Weil, Thomas L.; Conway, Howard F.; and Griffin, Edward L., Jr., 3,579,352.
- Weimer, Paul K., to RCA Corporation. Coupling and driving circuit for matrix array. 3,579,189, Cl. 340-166.
- Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., to Bell Telephone Laboratories, Incorporated International Business Machines Corporation. Process for determining the simple cycles of a finite

- directed graph Data system incorporating method and apparatus for referencing media locations Data system incorporating method and apparatus for referencing media locations. 3,579,194, Cl. 340-172.5
- Weinrotter, Ferdinand: *See—*
Gauster, Wolfgang; Muller, Walter; Schmidt, Alfred; Goldsworthy, William B.; Weinrotter, Ferdinand; and Hardesty, Ethridge E., 3,579,402.
- Weinstein, David A.: *See—*
Berardy, James E.; and Weinstein, David A., 3,579,266.
- Welburn, Norman, to AMP Incorporated, mesne. Cam grip flat conductor connector. 3,579,283, Cl. 339-217.
- Welch, John S.: *See—*
Carmody, Doyle V.; and Welch, John S., 3,579,254.
- Wentzheimer, William W.; Reynolds, Ronald W.; and Chalpin, William, to Sun Oil Company. Preparation of high V.I. lube oils. 3,579,437, Cl. 208-87.
- Werkzeuamashinenfabrik Gildemeister & Comp., AG: *See—*
Wopkemeier, Helmut Friedrich; and Richter, Werner, 3,578,868.
- West, Robert F.: *See—*
Morrow, George W.; and West, Robert F., 3,578,825.
- West, Russell G.; and Armgarth, Dietrich, to Arbeitsstelle für Molekularelektronik. Dielectric $3\text{NiO}_x\text{O}_2\text{-}6\text{TiO}_2$ compositions Semiconductor module and method of its production. 3,579,058, Cl. 317-235.
- Western Electric Company, Incorporated: *See—*
Keating, John F.; and Zutkis, Joseph A., 3,579,102.
Lawler, Philip E., 3,579,430.
- Westinghouse Electric Corporation: *See—*
Crane, Margaret M.; Feduska, William; and Brown, Jack T., 3,579,385.
Cronin, John C., 3,579,163.
Drown, John L.; and Patel, Nager J., 3,578,925.
Foster, Newton C., 3,579,369.
Ramsey, Kurt G., 3,579,149.
Rotruck, James L., 3,579,164.
Runk, Robert H., 3,579,470.
Suszer, Adalbert; and Patel, Himanshu M., 3,579,288.
Tenenbaum, Nathaniel D., 3,579,040.
Wachtel, Anselm, 3,579,463.
Weyrick, Paul M., 3,578,949.
- Weston Chemical Corporation: *See—*
Gutttag, Alvin, 3,579,624.
- Weyrick, Paul M., to Westinghouse Electric Corporation. Combination bake and auxiliary broil heater for a cooking appliance. 3,578,949, Cl. 219-403.
- Wheeler, Chester C., to Perkin-Elmer Corporation, The. Apparatus for monitoring the guidance and focus of telescope. 3,578,975, Cl. 250-203.
- Whirlpool Corporation: *See—*
Mason, Anthony; and Cobb, Clifton A., 3,579,284.
- White, James P.: *See—*
Riggle, Grant C.; and White, James P., 3,578,839.
- White, Peter: *See—*
Sears, James K.; Andrae, John Hugh; Gaines, Brian Ronald; and White, Peter, 3,579,191.
- White, Philip H.: *See—*
Crocker, Weyman S.; White, Philip H.; and McDonald, William T., 3,579,070.
- Whitney, David J.; and Nepveu, Raymond R., to Sanders Associates, Inc. Acoustic and electromagnetic shield and mechanical support for ultrasonic strip delay line. 3,579,151, Cl. 333-30.
- Whyte, David D., to Procter & Gamble Company, The. Triglyceride esters of branched carboxylic acids. 3,579,548, Cl. 260-410.7
- Wickes, William E.: *See—*
Perkins, Donald W.; and Wickes, William E., 3,578,959.
- Wickham, John L., to Black and Decker Manufacturing Company, The. Reversing switch for power tools. 3,579,002, Cl. 310-50.
- Widlar, Robert J., to National Semiconductor Corporation. Multiple collector lateral transistor device. 3,579,059, Cl. 317-235.
- Wiesboeck, Robert A.; and Friese, Hermann, to United States Steel Corporation, mesne Sud-Chemie AG. Condensed phosphoric acid having reduced viscosity Process for the production of xylose solutions. 3,579,380, Cl. 127-37.
- Wild, Colin Arthur: *See—*
Plummer, Dexter Robert; Wright, Keith Lawrence; and Wild, Colin Arthur, 3,579,072.
- Wildman, Alexander J., to Alexo, Corporation. Method and apparatus for orthodontic treatment. 3,578,744, Cl. 32-14.
- Wilen, James G.: *See—*
Friend, Aaron L.; Patterson, Arthur G.; and Wilen, James G., 3,578,948.
- Wilkinson, Bruce L.: *See—*
Fletcher, Taylor C.; Silva, Lawrence M.; and Wilkinson, Bruce L., 3,579,088.
- Wilkinson, Ronald D., to Airoil Burner Company (GB) Limited. Gaseous sealing devices. 3,578,892, Cl. 431-202.
- Williams Electronic Manufacturing Corporation: *See—*
Murphy, Frank T.; Clark, Norman R.; and Casey, William E., 3,578,802.
- Williams, Richard., 3,579,332, Cl.
- Willis, Donald H., to RCA Corporation. Video amplifier circuit. 3,578,900, Cl. 178-5.4
- Willis, Donald H., to RCA Corporation. Control circuits for preventing kinescope color saturation during blooming. 3,578,903, Cl. 178-5.4
- Wilmot, Richard D.: *See—*
Steingart, Richard D.; and Wilmot, Richard D., 3,579,237.
- Wilson, Edgar D.: *See—*
Hood, Harrison P., III; Mackie, William L.; and Wilson, Edgar D., 3,579,411.
- Windahl, Everett R.: *See—*
Brickett, Alan E.; and Windahl, Everett R., 3,578,787.
- Windmoller & Holscher: *See—*
Hasegawa, Tokushige; Rochla, Kurt; Makimoto, Kuninobu; Nihei, Seiji; and Takahira, Jiro, 3,579,327.
- Ward, Cecil R.; and Schwarzkopf, August, 3,579,397.
- Winkler, Friedrich: *See—*
Thate, Kurt; Winkler, Friedrich; and Theer, Anton, 3,578,856.
- Wintz, Bernard: *See—*
Pignard, Jean; and Wintz, Bernard, 3,579,104.
- Witco Chemical Corporation: *See—*
Davis, David S., 3,579,590.
- Wolfframm, Bodo M., to Sola Basic Industries, Inc. Leakage current detector. 3,579,219, Cl. 340-255.
- Wonilowicz, Edmund; Cann, Everett Douglas; and Machnacz, Henry F., 40% to Neiman, William T. RCA Corporation. Dual cycle treatment of sulfur dioxide containing flue gas and the like Method of making ohmic contact to semiconductor devices. 3,579,296, Cl. 117-212.
- Wood, Henry Walter, to Ilford Limited. Silver halide emulsion containing water-soluble polymer. 3,579,347, Cl. 96-114.
- Wood, Thomas F., to Givaudan Corporation. Process for preparing beta-phenylethyl alcohol. 3,579,593, Cl. 260-618.
- Woodward, Arthur S., to Mattel, Inc. Safety socket. 3,579,171, Cl. 339-34.
- Woodward, Earl R., Jr., to Woodward, Inc. Endless track tread. 3,578,824, Cl. 305-54.
- Woodward, Inc.: *See—*
Woodward, Earl R., Jr., 3,578,824.
- Woodward, John M.: *See—*
Hallmark, T. Milton; and Woodward, John M., 3,579,195.
Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.
Weinblatt, Herbert B.; Hallmark, T. Milton; Woodward, John M.; Hallmark, T. Milton; and Woodward, John M., 3,579,194.
- Wopkemeier, Helmut Friedrich; and Richter, Werner, to Werkzeuamashinenfabrik Gildemeister & Comp., AG Ges. Apparatus for facilitating precision mounting of tools in tool holders. 3,578,868, Cl. 356-165.
- Worcester Controls Corporation: *See—*
Parfitt, Peter, 3,579,156.
- Woten, Homer G. Self-locking drop-door. 3,578,749, Cl. 49-387.
- Wright, Carl Macey, to RCA Corporation. Decimal to binary conversion. 3,579,267, Cl. 235-155.
- Wright, Keith Lawrence: *See—*
Plummer, Dexter Robert; Wright, Keith Lawrence; and Wild, Colin Arthur, 3,579,072.
- Wuerker, Ralph F.: *See—*
Brooks, Robert E.; Heflinger, Lee O.; and Wuerker, Ralph F., 3,578,845.
- Wurlitzer Company, The: *See—*
Schwartz, Harold O.; and Ippolito, Anthony C., 3,578,894.
- Wyandotte Chemicals Corporation: *See—*
Schmolka, Irving R., 3,579,465.
- Wyeth, John, & Brother Limited: *See—*
Brown, Kevan; and Cavalia, John F., 3,579,529.
- Wymore, C. Elmer: *See—*
Mullin, Charles R.; and Wymore, C. Elmer, 3,579,596.
- Wyss, Clement R.; Cassanelli, Robert; LeMarr, Wesley A.; and Russo, Joseph, to General Foods Corporation Mortgage Production Inc. Slide mount and tape guide Multi-layered gelatin containing deserts. 3,578,858, Cl. 353-120.
- Wythe, Frederick J.; Oshima, Yasuhiro; and Hoette, Harald, to Emhart Corporation. Method of curling thermoplastic resin film into Adjustable shear blade and drop guide mounting for pipes and constructing upholstery therewith molten glass straight line shears. 3,579,398, Cl. 65-334.
- Xerox Corporation: *See—*
Kearns, William J., 3,579,031.
Sokolov, David A., 3,579,024.
Stillings, William K.; Miller, Donald E.; and Gilmore, Cecelia R., 3,579,356.
- Yalman, Richard G., to Antioch College. Preparation of porphin, substituted porphin and metal chelates thereof. 3,579,533, Cl. 260-314.
- Yamanaka, Masami: *See—*
Aga, Takashi; and Yamanaka, Masami, 3,579,205.
- Yamane, Isao; Matsuya, Yutaka; and Jimbo, Katsuhiko, to Flow Laboratories, Inc., mesne. Preparation of tissue culture media. 3,579,423, Cl. 195-1.7
- Yamato Scale Company, Limited: *See—*
Aga, Takashi; and Yamanaka, Masami, 3,579,205.
- Yamazaki, Takeo, to Aisin Seiki Kabushiki Kaisha. Foot-operated hand-released brake of the vehicle. 3,578,759, Cl. 74-540.
- Yau, Sik-Sang; and Tang, Calvin K., to Northwestern University. Universal logic circuitry having modules with minimum input-output connections and minimum logic gates. 3,579,119, Cl. 328-92.
- Yongue, James M., to RCA Corporation. Automatic chroma control circuit. 3,578,899, Cl. 178-5.4

- Yorston, Frederic H.; and Liebergott, Norman, to Pulp and Paper Research Institute of Canada. projection using the same. 3,579,419, Cl. 96n50.
- Yoshida, Hiroshi: *See—*
Mito, Satoru; Kawai, Mitsuo; and Yoshida, Hiroshi, 3,579,329.
- Young, Harold J.: *See—*
Holmstrom, Larry W.; Tuttle, James A.; and Young, Harold J., 3,578,906.
- Young, Richard W.: *See—*
Land, Edwin; Rogers, Howard G.; Ueda, Keizo; Ohkawahara, Tsuneo; Young, Richard W.; Matsui, Masao; and Ando, Satoshi, 3,579,414.
- Young, Robert P. T., to SCM Corporation, mesne. Process for reconstituting natural citronella. 3,579,468, Cl. 252-522.
- Zahn, Paul; and Merges, Veit, to Knapsack Aktiengesellschaft Bolkow Gesellschaft mit beschränkter Haftung. Column for carrying out organic chemical reactions in contact with fine, particulate catalysts Modular thermogenerator. 3,579,388, Cl. 136-202.
- Zaslowsky, Joel A.; and Gould, Henry, to Alcolac Chemical Corporation. Sulfonate monomers. 3,579,565, Cl. 260-485.
- Zeller, Paul: *See—*
Muller, Marcel; and Zeller, Paul, 3,579,502.
- Zellweger, Ltd.: *See—*
Piechocki, Kurt Wilhelm, 3,579,236.
- Ziegler, Karl; and Breil, Heinz, said Breil assor to said Ziegler. Polymerization of ethylene using reduced group IVB, VB and VIB metal salts as the polymerization catalyst. 3,579,493, Cl. 260-94.9
- Zoja, Giorgio, to Laboratorio Chimico Farmaceutico Giorgio Zoja S.p.A. Process for the preparation of the dextrorotatory 2,2'-(ethylene-diimino)-di-1-butanol. 3,579,586, Cl. 260-584.
- Zoja, Giorgio, to Laboratorio Chimico Farmaceutico Giorgio Zoja S.p.A. Process for the preparation of the dextrorotatory 2,2'-(ethylene-diimino)-di-1-butanol. 3,579,587, Cl. 260-584.
- Zuckerman, Joseph L.: *See—*
Herz, Jack L.; Levy, Alan J.; Litt, Morton H.; and Zuckerman, Joseph L., 3,579,630.
- Zutkis, Joseph A.: *See—*
Keating, John F.; and Zutkis, Joseph A., 3,579,102.
- Zwicker, Walter K.: *See—*
Schjolberg, Eiler; Zwicker, Walter K.; and Milch, Alfred, 3,579,359.

LIST OF REISSUE PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 18TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Alber, Norman E., and W. E. Smith, to Clevite Corporation. Extruding fibers having oxide skins. Re. 27,123, 5-18-71, Cl. 164-86.
Clevite Corporation: See—
Alber, Norman E., and Smith, Re. 27,123.
Erickson, Robert W., to The Regents of the University of Minnesota. Wood drying method. Re. 2,124, 5-18-71, Cl. 34-5.
Smith, Walter E.: See—
Alber, Norman E., and Smith, Re. 27,123.
University of Minnesota, The Regents of the: See—
Erickson, Robert W. Re. 2,124.

LIST OF DESIGN PATENTEEES

Alaska, St. Barth. Hand magnifier. 220,724, 5-18-71, Cl. D57-1.
Artz, Kenneth W., to W. R. Grace & Co. Combined packaging tray and cover. 220,749, 5-18-71, Cl. D9-185.
Artz, Kenneth W., to W. R. Grace & Co. Combined packaging tray and cover. 220,750, 5-18-71, Cl. D9-185.
Artz, Kenneth W., to W. R. Grace & Co. Combined packaging tray and cover. 220,751, 5-18-71, Cl. D9-219.
Artz, Kenneth W., to W. R. Grace & Co. Combined packaging tray and cover. 220,752, 5-18-71, Cl. D9-219.
Behring Corporation: See—
Evans, John M. 220,760.
Best, Melvin H., to Rain Bird Sprinkler Mfg. Corporation. Lawn sprinkler. 220,763, 5-17-71, Cl. D23-7.
Bio-Logics, Inc.: See—
Larson, Roger V. 220,740.
Broussard, Vernon P. Power train for sugar harvesters. 220,771, 5-18-71, Cl. D40-1.
Brunswick Corporation: See—
Renwick, William C. 220,759.
Burger Chef Systems, Inc.: See—
Thomas, Donald J. 220,758.
Computer Transmission Corporation: See—
Ortega, Charles J., and Naff. 220,764.
Cowan, Murray L., to Textron Inc. Expandible end link for a bracelet or similar article. 220,776, 5-18-71, Cl. D45-4.
Dansk Designs, Ltd.: See—
Nield, Refsgaard. 220,712.
Quistgaard, Jens H. 220,713.
Deadrick, James R., to Stewart-Warner Corporation. Stationary pull. 220,747, 5-18-71, Cl. D8-159.
D'Ercoli, Giacinto C.: See—
Jablonski, Edward R., and D'Ercoli. 220,778.
Dial, Lawton M., Jr., L. J. Grossheim, D. M. Schramme, and W. H. Zenneker, to Arthur Dooley and Son, Inc. Fire extinguisher housing. 220,762, 5-18-71, Cl. D16-2.
Dick, Ralph A.: See—
Hawkins, Harold V., Dick, and Wendel. 220,772.
Dilyard, Richard D., to Rubbermaid Incorporated. Covered beverage pitcher. 220,773, 5-18-71, Cl. D44-1.
Dooley, Arthur, and Son, Inc.: See—
Dial, Lawton M., Jr., Grossheim, Schramme, and Zenneker. 220,762.
Erkers, Arne. Handsaw. 220,677, 5-18-71, Cl. D8-96.
Evans, John M., to Behring Corporation. Modular home. 220,760, 5-18-71, Cl. D13-1.
Gandy, Aaron E. Photograph slide sorting rack. 220,786, 5-18-71, Cl. D61-1.
Garcia, Philip, to General Motors Corporation. Motor vehicle lamp lens. 220,777, 5-18-71, Cl. D48-32.
Garcia, Philip, to General Motors Corporation. Motor vehicle lamp lens. 220,779, 5-18-71, Cl. D48-32.
General Motors Corporation: See—
Garcia, Philip. 220,777.
Garcia, Philip. 220,779.
Goings, Harford E. Food service tray. 220,774, 5-18-71, Cl. D44-10.
Gomez, Claudio G. and F. Kvapil, to The National Cash Register Company. Cash register or similar article. 220,719, 5-18-71, Cl. D52-4.
Gorham, Herman H.: See—
Romanias, Gus, and Gorham. 220,765.
Gould, Jerome, to Johnson & Johnson. Bottle. 220,748, 5-18-71, Cl. D9-82.
Grace, W. R., & Co.: See—
Artz, Kenneth W. 220,749.
Artz, Kenneth W. 220,750.
Artz, Kenneth W. 220,751.
Artz, Kenneth W. 220,752.
Grossheim, Louis J.: See—
Dial, Lawton M., Jr., Grossheim, Schramme, and Zenneker. 220,762.
Grote Manufacturing Company, The: See—
Newman, Charles J. 220,780.
Guodace, Ronald A., to International Silver Company. Spoon or similar article of flatware. 220,783, 5-18-71, Cl. D54-12.
Guthrie, James E. Friction type bottle cap remover. 220,744, 5-18-71, Cl. D8-18.
Haddaway, Klein K. Cosmetic case. 220,789, 5-18-71, Cl. D86-10.
Hamburger Hamlets, Inc.: See—
Lewis, Marilyn. 220,791.
Hawkins, Harold V., R. A. Dick, and J. Wendel. Puller. 220,772, 5-18-71, Cl. D41-1.
International Business Machines Corporation: See—
Kapper, Henry. 220,698.
International Silver Company: See—
Guodace, Ronald A. 220,783.
King, Robert. 220,784.
Toffolon, Siro R. 220,785.
Jablonski, Edward R., and G. C. D'Ercoli, to McGraw-Edison Company. Luminaires. 220,778, 5-18-71, Cl. D48-31.
Jackson, Clarence E. Mobile lounge chair. 220,761, 5-18-71, Cl. D15-11.
Johnson & Johnson: See—
Gould, Jerome. 220,748.
Jordan, John H. Cocktail table. 220,768, 5-18-71, Cl. D33-14.
Kapper, Henry, to International Business Machines Corporation. Telephone terminal. 220,698, 5-18-71, Cl. D26-14.
King, Robert, to International Silver Company. Spoon or similar article of flatware. 220,784, 5-18-71, D54-12.
Kinnear Corporation: See—
Smith, Richard E. 220,757.
Kovack, Stephen J., to Libbey-Owens-Ford Company. Glass cutting tool. 220,745, 5-18-71, Cl. D8-51.
Kvapil, Francesco: See—
Gomez, Claudio G. and Kvapil. 220,719.
LaHue, Paul D. Sldable golf ball for putting practice. 220,769, 5-18-71, Cl. D34-5.
Larson, Roger V., to Bio-Logics, Inc. Information plate for a hospital patient. 220,740, 5-18-71, Cl. D96-13.
Leisure Products Corporation: See—
Piazza, Joe E. 220,788.
Levin, Monte L., to Miner Industries, Inc. Balloon vending machine. 220,781, 5-18-71, Cl. D52-3.
Lewis, Marilyn, to Hamburger Hamlets, Inc. Sign panel. 220,791, 5-18-71, Cl. D96-12.
Libbey-Owens-Ford Company: See—
Kovack, Stephen J. 220,745.
Lo Cascio, Jack J.: See—
Marcario, Joseph P., and Lo Cascio. 220,741.
Lokey, Robert C. Type soldering jig. 220,746, 5-18-71, Cl. D8-71.
Marcario, Joseph P., and J. J. Lo Cascio, to Sarong, Inc. Brassiere. 220,741, 5-18-71, Cl. D2-24.
Mazeika, Albert, to Milton Manufacturing Company, Inc. Portable battery tester. 220,782, 5-18-71, Cl. D52-6.
McGraw-Edison Company: See—
Jablonski, Edward R., and D'Ercoli. 220,778.
Miller, Phillip E. Standard for use in supporting horizontal bookshelves. 220,766, 5-18-71, Cl. D33-3.
Milton Manufacturing Company, Inc.: See—
Mazeika, Albert. 220,782.
Miner Industries, Inc.: See—
Levin, Monte L. 220,781.
Mohl, Edward H. Swim suit or similar article. 220,742, 5-18-71, Cl. D2-42.
Naff, Frederic L., Jr.: See—
Ortega, Charles J., and Naff. 220,764.
National Cash Register Company, The: See—
Gomez, Claudio G. and Kvapil. 220,719.
Neward, Theodore C. Goggles. 220,743, 5-18-71, Cl. D2-234.
Newman, Charles J., to The Grote Manufacturing Company. Automotive lamp. 220,780, 5-18-71, Cl. D48-32.
Nield, Refsgaard, to Dansk Designs, Ltd. Cup. 220,712, 5-18-71, Cl. D44-9.
Olivetti, Ing. C., & Co., S.p.A.: See—
Svezia, John. 220,787.
O'Neill, Frank D. Combined egg holder and opener, condiment dispensers and holder therefor and spoon holder. 220,775, 5-18-71, Cl. D44-24.
Ortega, Charles J., and F. L. Naff, Jr., to Computer Transmission Corporation. Housing for computer interface unit. 220,764, 5-18-71, Cl. D26-5.
Pallet, David M. Coin-holder and dispenser. 220,718, 5-18-71, Cl. D52-4.
Piazza, Joe E., to Leisure Products Corporation. Occupant-body-steerable self-propellable aquaplane or similar article. 220,788, 5-18-71, Cl. D71-1.
Power, Lawrence H. Instruction cubicle. 220,767, 5-18-71, Cl. D33-7.
Quistgaard, Jens H., to Dansk Designs, Ltd. Candelabra. 220,713, 5-18-71, Cl. D48-2.

Rain Bird Sprinkler Mfg. Corporation: See—
Best, Melvin H. 220,763.
Reid, Essie M. Combined cabinet and accessory tray unit. 220,706, 5-18-71, Cl. D33-19.
Renwick, William C., to Brunswick Corporation. Building or the like. 220,759, 5-18-71, Cl. D13-1.
Rives, William T. Identification tag blank. 220,790, 5-18-71, Cl. D96-3.
Romanias, Gus, and H. H. Gorham. Panel box for refrigerator control. 220,765, 5-18-71, Cl. D26-13.
Rubbermaid Incorporated: See—
Dilyard, Richard D. 220,773.
Sarong, Inc.: See—
Marcario, Joseph P., and Lo Cascio. 220,741.
Schramme, Donald M.: See—
Dial, Lawton M., Jr., Grossheim, Schramme, and Zenneker. 220,762.
Smith, Richard E., to Kinnear Corporation. Bottom rail for a roll-type door. 220,757, 5-18-71, Cl. D13-1.
Stewart-Warner Corporation: See—
Deadrick, James R. 220,747.
Stineman, James S. Air-supported structure. 220,685, 5-18-71, Cl. D13-1.
Stineman, James S. Air-supported structure. 220,686, 5-18-71, Cl. D13-1.
Svezia, John, to Ing. C. Olivetti & Co., S.p.A. Typewriter. 220,787, 5-18-71, Cl. D64-11.
Textron Inc.: See—
Cowan, Murray L. 220,776.
Thomas, Donald J., to Burger Chef Systems, Inc. Building. 220,758, 5-18-71, Cl. D13-1.
Toffolon, Siro R., to International Silver Company. Spoon or similar article of flatware. 220,785, 5-18-71, Cl. D54-12.
Townsend, Lynn R. Planter bowl. 220,770, 5-18-71, Cl. D35-1.
Traczyk, Raymond M.: See—
Zenger, Richard D., and Traczyk. 220,756.
Wendel, John: See—
Hawkins, Harold V., Dick, and Wendel. 220,772.
Zenger, Richard D., and R. M. Traczyk. Unit for dispensing liquid from a container. 220,756, 5-18-71, Cl. D9-290.
Zenneker, Walter H.: See—
Dial, Lawton M., Jr., Grossheim, Schramme, and Zenneker. 220,762.
Zundel, Arthur P. Container end. 220,753, 5-18-71, Cl. D9-253.
Zundel, Arthur P. Container end. 220,754, 5-18-71, Cl. D9-253.
Zundel, Arthur P. Container end. 220,755, 5-18-71, Cl. D9-253.

CLASSIFICATION OF PATENTS

ISSUED MAY 18, 1971

NOTE.—First number, class; second number, subclass; third number, patent number

2-181 : 3.578.736	96-126 : 3.579.348	162-17 : 3.579.417	219-69 : 3.578.937	260-2.5 : 3.579.471	260-465.2 : 3.579.558
4-166 : 3.578.737	139 : 3.579.344	18 : 3.579.418	73 : 3.578.938	3.579.472	.3 : 3.579.559
8-37 : 3.579.286	140 : 3.579.345	66 : 3.579.419	74 : 3.578.939	18 : 3.579.469	.9 : 3.579.560
108 : 3.579.287	142 : 3.579.346	237 : 3.579.420	91 : 3.578.940	3.579.473	468 : 3.579.563
116.2 : 3.579.288	99-23 : 3.579.349	3.579.421	98 : 3.579.260	20 : 3.579.470	473 : 3.579.564
.3 : 3.579.289	71 : 3.579.340	314 : 3.579.422	114 : 3.578.941	29.1 : 3.579.522	485 : 3.579.565
13-16 : 3.578.893	77.1 : 3.579.350	164-86 : Re.27.123	119 : 3.578.942	.6 : 3.579.474	488 : 3.579.566
15-215 : 3.578.738	3.579.351	166-305 : 3.578.781	121 : 3.578.943	33.4 : 3.579.540	473 : 3.579.567
18-8 : 3.578.739	78 : 3.579.352	174-74 : 3.578.895	130 : 3.578.944	37 : 3.578.945	497 : 3.579.568
12 : 3.578.740	81 : 3.579.353	84 : 3.578.896	154 : 3.579.261	40 : 3.579.477	3.579.569
30 : 3.578.741	83 : 3.579.341	178-5.2 : 3.578.897	214 : 3.578.945	41 : 3.579.476	502.4 : 3.579.570
21-2 : 3.579.290	116 : 3.579.354	3.578.898	216 : 3.578.946	45.75 : 3.579.478	514.5 : 3.579.571
23-2 : 3.579.291	130 : 3.579.355	4 : 3.578.899	226 : 3.578.947	67 : 3.579.480	515 : 3.579.572
3.579.292	148 : 3.579.356	3.578.900	230 : 3.578.948	3.579.481	530 : 3.579.573
3.579.293	154 : 3.579.357	3.578.901	295 : 3.579.262	77.5 : 3.579.482	3.579.574
52 : 3.579.294	176 : 3.579.358	3.578.902	388 : 3.578.936	78 : 3.579.483	3.579.575
3.579.295	195 : 3.579.359	3.578.903	403 : 3.578.944	.3 : 3.579.489	543 : 3.579.576
103 : 3.579.297	199 : 3.579.360	6 : 3.578.904	444 : 3.578.951	.4 : 3.579.484	544 : 3.579.577
3.579.298	101-23 : 3.578.766	3.578.905	486 : 3.578.950	3.579.485	553 : 3.579.578
110 : 3.579.299	102-70.2 : 3.578.767	3.578.906	3.579.264	3.578.986	555 : 3.579.636
122 : 3.579.300	104-23 : 3.578.768	3.579.249	540 : 3.579.250	.5 : 3.579.487	559 : 3.579.579
165 : 3.579.301	106-14 : 3.579.361	.6 : 3.579.250	222-4 : 3.578.788	79 : 3.579.488	566 : 3.579.580
178 : 3.579.296	39 : 3.579.362	.8 : 3.578.907	79 : 3.578.789	80.72 : 3.579.490	567.6 : 3.579.581
226 : 3.579.302	176 : 3.579.363	7.2 : 3.578.908	223-73 : 3.578.790	85.5 : 3.579.491	574 : 3.579.582
230 : 3.579.303	3.579.364	.3 : 3.579.251	229-85 : 3.578.791	94.9 : 3.579.492	583 : 3.579.583
232 : 3.579.304	265 : 3.579.365	.6 : 3.578.909	235-61.11 : 3.578.953	3.579.493	3.579.584
3.579.305	314 : 3.579.366	85 : 3.579.252	112.5 : 3.579.494	3.579.494	3.579.585
253 : 3.579.306	112-208 : 3.578.769	23 : 3.578.910	115 : 3.579.495	115 : 3.579.495	584 : 3.579.586
263 : 3.579.307	219 : 3.578.770	45 : 3.578.911	123.5 : 3.579.496	123.5 : 3.579.496	3.579.587
281 : 3.579.308	117-33.5 : 3.579.367	179-1 : 3.578.912	158 : 3.579.497	158 : 3.579.497	586 : 3.579.479
288 : 3.579.309	54 : 3.579.368	3.578.913	3.579.498	3.579.498	3.579.588
301 : 3.579.310	57 : 3.579.369	6.3 : 3.579.253	210.5 : 3.579.499	210.5 : 3.579.499	599 : 3.579.589
355 : 3.579.311	72 : 3.579.370	15 : 3.578.914	239 : 3.579.500	239 : 3.579.500	607 : 3.579.590
29-96 : 3.578.742	76 : 3.579.371	3.578.915	.1 : 3.579.501	.1 : 3.579.501	3.579.591
194 : 3.578.743	93.1 : 3.579.372	17 : 3.579.254	150.1 : 3.578.957	3.579.506	609 : 3.579.592
195 : 3.579.312	106 : 3.579.373	18 : 3.578.916	.5 : 3.578.958	.3 : 3.579.502	618 : 3.579.593
196.2 : 3.579.313	164 : 3.579.374	3.578.917	152 : 3.578.959	3.579.503	632 : 3.579.594
32-14 : 3.578.744	212 : 3.579.375	3.578.918	155 : 3.579.267	155 : 3.579.503	633 : 3.579.595
57 : 3.578.745	3.579.376	3.579.255	156 : 3.578.960	.5 : 3.579.507	653.3 : 3.579.595
33-174 : 3.578.746	217 : 3.579.377	3.579.255	159 : 3.578.961	.55 : 3.579.504	658 : 3.579.596
34-5 : Re.27.124	229 : 3.579.378	84 : 3.578.919	189 : 3.579.268	3.579.505	3.579.597
184 : 3.578.747	232 : 3.579.379	100.2 : 3.578.920	239-132.3 : 3.578.793	3.579.508	666 : 3.579.604
43-44.9 : 3.578.748	118-6 : 3.578.771	3.579.256	240-2.25 : 3.578.962	.57 : 3.579.509	3.579.605
49-387 : 3.578.749	33 : 3.578.772	139 : 3.578.921	3 : 3.578.963	240 : 3.579.510	673.5 : 3.579.598
51-273 : 3.579.314	127-37 : 3.579.380	180-82 : 3.578.782	8.1 : 3.578.964	3.579.511	674 : 3.579.599
288 : 3.579.315	128-78 : 3.578.773	185-37 : 3.578.783	10.68 : 3.579.269	3.579.512	677 : 3.579.606
56-14.4 : 3.578.750	227 : 3.578.774	192-53 : 3.578.784	36 : 3.578.965	3.579.513	678 : 3.579.600
57-77.45 : 3.578.751	134-8 : 3.579.381	195-1.7 : 3.579.423	93 : 3.578.966	243 : 3.579.514	683 : 3.579.601
61-83 : 3.578.752	45 : 3.578.775	28 : 3.579.424	106 : 3.578.967	244 : 3.579.515	3.579.602
62-51 : 3.578.753	136-20 : 3.579.382	30 : 3.579.425	242-25 : 3.578.794	246 : 3.579.516	48 : 3.579.603
156 : 3.578.754	75 : 3.579.385	66 : 3.579.427	45 : 3.578.795	250 : 3.579.517	824 : 3.579.607
65-4 : 3.579.316	76 : 3.579.383	80 : 3.579.426	244-3.23 : 3.578.796	256.4 : 3.579.518	837 : 3.579.608
43 : 3.579.317	100 : 3.579.384	200-11 : 3.579.257	250-41.3 : 3.578.968	279 : 3.579.519	853 : 3.579.610
90 : 3.579.318	134 : 3.579.386	19 : 3.578.922	.9 : 3.578.969	288 : 3.579.520	873 : 3.579.609
334 : 3.579.319	163 : 3.579.387	38 : 3.578.923	3.579.270	290 : 3.579.521	874 : 3.579.611
71-9 : 3.579.320	202 : 3.579.388	48 : 3.578.924	49.5 : 3.578.970	293.4 : 3.579.523	880 : 3.579.612
25 : 3.579.321	137-268 : 3.578.776	50 : 3.578.925	50 : 3.578.971	294 : 3.579.524	901 : 3.579.613
34 : 3.579.322	138-121 : 3.578.777	67 : 3.578.926	51.5 : 3.579.271	.8 : 3.579.525	940 : 3.579.614
35 : 3.579.323	141-144 : 3.578.778	83 : 3.579.284	71 : 3.578.973	3.579.526	947 : 3.579.615
73-1 : 3.578.755	143-32 : 3.578.779	144 : 3.578.928	77 : 3.578.972	296 : 3.579.527	263-3 : 3.578.797
15 : 3.578.756	146-79 : 3.578.780	145 : 3.578.927	85 : 3.578.974	297 : 3.579.528	21 : 3.578.798
23.1 : 3.578.757	148-6.15 : 3.579.389	148 : 3.579.258	203 : 3.578.975	302 : 3.579.529	52 : 3.579.616
40.7 : 3.578.758	126 : 3.579.390	153 : 3.578.929	219 : 3.578.976	306.7 : 3.579.530	264-34 : 3.579.617
74-540 : 3.578.759	175 : 3.579.055	3.578.930	3.578.977	308 : 3.579.531	37 : 3.579.618
701 : 3.578.760	3.579.391	166 : 3.578.931	221 : 3.578.978	309.7 : 3.579.532	42 : 3.579.619
75-10 : 3.579.324	149-7 : 3.579.392	168 : 3.578.932	3.579.047	314 : 3.579.533	98 : 3.579.620
51 : 3.579.325	74 : 3.579.393	204-30 : 3.579.428	3.578.980	315 : 3.579.534	99 : 3.579.621
67 : 3.579.326	156-10 : 3.579.394	181 : 3.579.429	3.579.446	326.3 : 3.579.535	3.579.622
109 : 3.579.327	94 : 3.579.395	206 : 3.579.430	3.579.446	3.579.536	135 : 3.579.623
124 : 3.579.329	202 : 3.579.396	275 : 3.579.431	28 : 3.579.448	327 : 3.579.537	171 : 3.579.624
133.5 : 3.579.328	250 : 3.579.398	279 : 3.579.432	46.3 : 3.579.467	330.5 : 3.579.538	177 : 3.579.625
83-343 : 3.578.761	251 : 3.579.397	299 : 3.579.433	49.5 : 3.579.449	3.579.539	297 : 3.579.626
84-1.01 : 3.578.894	293 : 3.579.399	208-59 : 3.579.435	56 : 3.579.450	338 : 3.579.541	269-51 : 3.578.799
85-41 : 3.578.762	294 : 3.579.400	3.579.436	62.1 : 3.579.451	395 : 3.579.542	272-73 : 3.578.800
87-6 : 3.578.763	327 : 3.579.401	87 : 3.579.437	.51 : 3.579.452	397.4 : 3.579.543	273-26 : 3.578.801
3.578.764	392 : 3.579.402	111 : 3.579.434	87 : 3.579.447	.5 : 3.579.544	129 : 3.578.802
95-10 : 3.578.765	433 : 3.579.403	130 : 3.579.438	89 : 3.579.453	3.579.545	277-85 : 3.578.803
96-1 : 3.579.330	515 : 3.579.404	210-5 : 3.579.439	97 : 3.579.454	400 : 3.579.546	280-11.35 : 3.578.804
.6 : 3.579.331	546 : 3.579.405	23 : 3.579.440	135 : 3.579.455	410.6 : 3.579.547	285-55 : 3.578.805
.8 : 3.579.332	571 : 3.579.406	44 : 3.579.441	137 : 3.579.456	.7 : 3.579.548	290-38 : 3.578.981
3 : 3.579.333	583 : 3.579.407	23 : 3.579.442	3.579.457	.9 : 3.579.549	298-2 : 3.578.806
29 : 3.579.334	161-7 : 3.579.408	49 : 3.579.443	152 : 3.579.458	413 : 3.579.550	299-1 : 3.578.807
36.1 : 3.579.335	38 : 3.579.410	58 : 3.579.444	181.4 : 3.579.459	3.579.551	4 : 3.578.808
49 : 3.579.336	39 : 3.579.409	3.579.445	182 : 3.579.460	3.579.552	33 : 3.578.809
50 : 3.579.338	53 : 3.579.411	198 : 3.578.785	301.4 : 3.579.463	434 : 3.579.553	43 : 3.578.810
74 : 3.579.339	89 : 3.579.412	512 : 3.578.786	311 : 3.579.461	437 : 3.579.554	45 : 3.578.811
90 : 3.579.342	135 : 3.579.413	212-59 : 3.578.787	313 : 3.579.462	438.5 : 3.579.555	301-63 : 3.578.812
3.579.343	173 : 3.579.414	219-56 : 3.578.934	316 : 3.579.465	439 : 3.579.556	302-14 : 3.578.813
114 : 3.579.347	184 : 3.579.415	64 : 3.578.935	317 : 3.579.464	448.2 : 3.579.557	40 : 3.578.814
	254 : 3.579.416		331 : 3.579.466	463 : 3.579.561	52 : 3.578.815
			522 : 3.579.468	465.1 : 3.579.562	66 : 3.578.816

CLASSIFICATION OF PATENTS

303-16	3,578,817	313-109.5	3,579,019	321-2	3,579,078	330-38	3,579,137	340-172.5	3,579,195	350-160	3,578,842
	3,578,818	269	3,579,020	5	3,579,079	86	3,579,138		3,579,196		3,578,843
21	3,578,819	274	3,579,021		3,579,080	331-8	3,579,139		3,579,197		3,578,844
	3,578,820	330	3,579,022	9	3,579,081	94.5	3,579,140		3,579,198	162	3,578,845
22	3,578,821	315-18	3,579,023	11	3,579,082		3,579,141		3,579,199		3,578,846
305-24	3,578,822	22	3,579,024	13	3,579,083		3,579,142		3,579,200	226	3,578,847
42	3,578,823	84.6	3,579,025	16	3,579,084	107	3,579,143		3,579,201	320	3,578,848
54	3,578,824	99	3,579,026	27	3,579,085	111	3,579,144	173	3,579,202	321	3,578,849
306-32	3,578,825	111	3,579,027	60	3,579,086	332-7.51	3,579,145		3,579,203	351-160	3,578,850
307-10	3,579,285		3,579,028	322-28	3,579,087		3,579,146		3,579,204	352-72	3,578,851
95	3,578,982	127	3,579,029	323-6	3,579,088		3,579,150		3,579,205	91	3,578,853
202	3,578,983	291	3,579,030		3,579,089		3,579,147	1	3,579,206	92	3,578,852
218	3,579,272	363	3,579,031		3,579,090		3,579,147	2	3,579,207	158	3,578,854
221	3,578,984	316-16	3,578,834		3,579,091	333-10	3,579,148		3,579,208	163	3,578,855
	3,579,273	25	3,578,835		3,579,096	11	3,579,149	174	3,579,209	172	3,578,856
228	3,579,274	317-2	3,579,032	43.5	3,579,092	30	3,579,151		3,579,210	353-94	3,578,857
229	3,578,985		3,579,033	50	3,579,093	73	3,579,152	1	3,579,211	120	3,578,858
246	3,578,986	11	3,579,034	100	3,579,094		3,579,153		3,579,212	355-3	3,578,859
251	3,579,275	13	3,579,035	108	3,579,095	76	3,579,154		3,579,213	80	3,578,860
252	3,578,987	16	3,579,036	324-10	3,579,098	79	3,579,155		3,579,214	91	3,578,861
265	3,578,988	18	3,579,037	30	3,579,097		3,579,156	198	3,579,215	104	3,578,862
273	3,578,989		3,579,038	37	3,579,099	97	3,579,282	237	3,579,216	356-2	3,578,863
293	3,578,990	22	3,579,039	51	3,579,280	335-112	3,579,157	248	3,579,223	32	3,578,864
308-4	3,578,826	27	3,579,040	53	3,579,100	151	3,579,158	253	3,579,217	70	3,578,865
5	3,578,827	33	3,579,041	60	3,579,101	205	3,579,159		3,579,218	74	3,578,866
37	3,578,828		3,579,042	73	3,579,102	206	3,579,160	255	3,579,219	103	3,578,867
179.5	3,578,829	36	3,579,043		3,579,103	272	3,579,161	258	3,579,220	165	3,578,868
207	3,578,830	103	3,579,044	83	3,579,104	336-57	3,579,162	277	3,579,221	239	3,578,869
214	3,578,831	114	3,579,045	99	3,579,105	94	3,579,163	283	3,579,222	401-199	3,578,870
310-4	3,578,991	120	3,579,046	140	3,579,106	100	3,579,164	324	3,579,224	415-10	3,578,871
	3,578,992	135	3,579,048	157	3,579,107	170	3,579,165		3,579,225	25	3,578,872
8.3	3,578,993		3,579,049	325-38	3,579,108	192	3,579,166	339	3,579,226	68	3,578,873
6	3,578,994	148	3,579,051	42	3,579,109	337-102	3,579,167	347	3,579,227	170	3,578,874
7	3,578,996	5	3,579,050	47	3,579,110	114	3,579,168		3,579,228	416-109	3,578,875
8	3,578,995		3,579,052	141	3,579,111	338-170	3,579,169		3,579,229	121	3,578,876
10	3,578,997	157.5	3,579,053	319	3,579,112	339-17	3,579,170		3,579,230	134	3,578,877
11	3,578,998	231	3,579,054	376	3,579,113	34	3,579,171		3,579,231	178	3,578,878
	3,578,999	234	3,579,056	410	3,579,114	97	3,579,172		3,579,232	417-62	3,578,879
13	3,579,001		3,579,057	438	3,579,115		3,579,173	384	3,579,233	203	3,578,880
15	3,579,000		3,579,058	439	3,579,116	144	3,579,174	343-5	3,579,234	206	3,578,881
50	3,579,002	235	3,579,059	328-27	3,579,117	156	3,579,175	6.5	3,579,235	245	3,578,882
82	3,579,276		3,579,060	41	3,579,118	176	3,579,176	8	3,579,236	286	3,578,883
93	3,579,003		3,579,061	92	3,579,119	198	3,579,177	16	3,579,237	317	3,578,884
156	3,579,277	247	3,579,062		3,579,120	217	3,579,178		3,579,239	454	3,578,885
164	3,579,004		3,579,063	124	3,579,121	221	3,579,178	18	3,579,238	495	3,578,886
178	3,579,005	258	3,579,064	127	3,579,125	258	3,579,179	228	3,579,240	418-132	3,578,887
227	3,579,006	318-207	3,579,065	129	3,579,126	340-3	3,579,180	702	3,579,241	133	3,578,888
242	3,579,007	314	3,579,066	145	3,579,127		3,579,181	708	3,579,242	147	3,578,889
312-268	3,578,832	372	3,579,067	155	3,579,128	29	3,579,182	713	3,579,243	199	3,578,890
330	3,578,833	444	3,579,067	164	3,579,123	137	3,579,184	797	3,579,244	424-11	3,579,627
313-29	3,579,011	478	3,579,068	167	3,579,122	146.1	3,579,185	346-1	3,579,245	28	3,579,628
65	3,579,012	571	3,579,069	181	3,579,124	3	3,579,186	34	3,579,246	47	3,579,629
73	3,579,013		3,579,070	330-3	3,579,129	148	3,579,187	35	3,579,247		3,579,630
79	3,579,008	603	3,579,071		3,579,134	149	3,579,188	76	3,579,248	70	3,579,632
83	3,579,009	609	3,579,072	4.3	3,579,130	166	3,579,189	350-3.5	3,578,836	86	3,579,631
86	3,579,010	634	3,579,073	9	3,579,131	167	3,579,190		3,578,837	92	3,579,633
	3,579,014	696	3,579,074	10	3,579,132	172.5	3,579,191		3,578,838	154	3,579,634
89	3,579,015	320-1	3,579,074	19	3,579,133		3,579,192	61	3,578,839	181	3,579,635
92	3,579,016	2	3,579,075	30	3,579,135		3,579,193	99	3,578,840	431-191	3,578,891
105	3,579,017	36	3,579,076		3,579,136		3,579,194	127	3,578,841	202	3,578,892
109	3,579,018	321-2	3,579,077								

CLASSIFICATION OF DESIGNS

D 2-24	220,741	D 9-185	220,750	D13-1	220,759	D33-7	220,767	D44-24	220,775	D54-12	220,783
42	220,742	219	220,751		220,760		220,768	D45-4	220,776		220,784
234	220,743		220,752	D15-11	220,761	D34-14	220,769	D48-31	220,778		220,785
D 8-18	220,744	253	220,753	D16-2	220,762	D35-5	220,770	32	220,777	D61-1	220,786
51	220,745		220,754	D23-7	220,763	D40-1	220,771		220,779	D64-11	220,787
71	220,746		220,755	D26-5	220,764	D41-1	220,772		220,780	D71-1	220,788
159	220,747	290	220,756	13	220,765	D44-1	220,773	D52-3	220,781	D86-10	220,789
D 9-82	220,748	D13-1	220,757	D33-3	220,766	10	220,774	6	220,782	D96-12	220,791
185	220,749		220,758								

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

1 : 3,578,755	6 : 3,579,110	9 : 3,579,140	13 : 3,579,301	18 : 3,578,815	25 : 3,578,911
3,578,778	3,579,127	3,579,182	3,579,440	3,578,899	3,578,912
3,578,796	3,579,129	3,579,319	3,579,003	3,578,900	3,578,939
3,579,000	3,579,130	3,579,326	3,579,431	3,578,901	3,578,958
3,579,393	3,579,132	3,579,365	3,579,802	3,578,903	3,578,961
2 : 3,579,013	3,579,142	3,579,376	3,578,806	3,579,095	3,578,963
4 : 3,578,948	3,579,143	3,579,395	3,578,852	3,579,166	3,578,964
3,578,953	3,579,171	3,579,406	3,578,910	3,579,175	3,578,966
3,578,972	3,579,172	3,579,408	3,578,926	3,579,184	3,578,970
3,578,973	3,579,176	3,579,510	3,578,932	3,579,253	3,578,980
3,578,974	3,579,177	3,579,553	3,578,936	3,579,524	3,578,994
3,579,147	3,579,180	3,579,564	3,578,940	3,579,634	3,578,995
6 : 3,578,736	3,579,187	3,579,610	3,578,951	3,579,635	3,578,998
3,578,762	3,579,196	3,579,620	3,578,971	3,579,021	3,579,021
3,578,785	3,579,199	3,579,622	3,578,977	3,578,890	3,579,025
3,578,792	3,579,202	3,579,632	3,579,007	3,579,207	3,579,026
3,578,794	3,579,203	3,579,632	3,579,032	3,579,208	3,579,043
3,578,801	3,579,219	3,579,312	3,579,039	3,579,264	3,579,093
3,578,822	3,579,214	3,579,314	3,579,049	3,579,631	3,579,111</

26 : 3,579,192	34 : 3,579,076	36 : 3,578,858	36 : 3,579,611	41 : 3,578,744	47 : 3,578,814
3,579,193	3,579,090	3,578,859	3,579,636	3,578,775	3,579,254
3,579,203	3,579,091	3,578,865	37 : 3,579,004	3,579,224	3,579,322
3,579,243	3,579,102	3,578,879	3,579,200	3,579,303	3,579,486
3,579,284	3,579,108	3,578,884	3,579,379	3,579,405	48 : 3,578,753
3,579,416	3,579,112	3,578,894	3,579,424	3,579,526	3,578,781
3,579,426	3,579,133	3,578,906	38 : 3,579,066	3,578,750	3,578,816
3,579,433	3,579,137	3,578,921	39 : Re.27,123	3,578,764	3,579,096
3,579,465	3,579,144	3,578,959	3,578,746	3,578,767	3,579,098
3,579,472	3,579,145	3,578,985	3,578,761	3,578,793	3,579,105
3,579,476	3,579,159	3,578,986	3,578,798	3,578,824	3,579,154
3,579,488	3,579,160	3,578,996	3,578,840	3,578,846	3,579,220
3,579,503	3,579,161	3,579,006	3,578,876	3,578,876	3,579,438
3,579,515	3,579,189	3,579,012	3,578,855	3,578,902	3,579,445
3,579,561	3,579,198	3,579,016	3,578,878	3,578,925	3,579,477
3,579,588	3,579,206	3,579,024	3,578,883	3,579,010	3,579,541
3,579,596	3,579,241	3,579,060	3,578,888	3,579,034	3,579,592
3,579,600	3,579,245	3,579,061	3,578,905	3,579,045	49 : 3,578,737
3,579,617	3,579,246	3,579,062	3,578,946	3,579,064	3,578,790
27 : Re.27,124	3,579,267	3,579,065	3,578,949	3,579,079	3,579,054
3,578,955	3,579,271	3,579,067	3,578,956	3,579,100	50 : 3,579,070
3,579,097	3,579,324	3,579,084	3,578,987	3,579,118	3,579,218
3,579,107	3,579,332	3,579,094	3,579,036	3,579,152	51 : 3,578,788
3,579,135	3,579,339	3,579,109	3,579,037	3,579,163	3,578,832
3,579,215	3,579,341	3,579,120	3,579,038	3,579,164	3,578,904
3,579,609	3,579,368	3,579,139	3,579,074	3,579,178	3,578,988
29 : 3,578,747	3,579,371	3,579,148	3,579,168	3,579,258	3,579,103
3,578,812	3,579,372	3,579,162	3,579,240	3,579,263	3,579,242
3,578,967	3,579,375	3,579,173	3,579,260	3,579,282	3,579,249
3,579,015	3,579,400	3,579,229	3,579,262	3,579,299	3,579,362
3,579,087	3,579,434	3,579,230	3,579,320	3,579,318	3,579,410
3,579,287	3,579,436	3,579,252	3,579,340	3,579,350	3,579,483
3,579,363	3,579,451	3,579,280	3,579,349	3,579,361	3,579,623
3,579,364	3,579,463	3,579,281	3,579,353	3,579,369	53 : 3,579,223
3,579,413	3,579,490	3,579,292	3,579,366	3,579,384	3,579,238
3,579,466	3,579,494	3,579,306	3,579,404	3,579,385	3,579,432
3,579,521	3,579,509	3,579,330	3,579,409	3,579,429	54 : 3,578,740
3,579,551	3,579,517	3,579,331	3,579,449	3,579,435	3,578,809
3,579,552	3,579,531	3,579,344	3,579,450	3,579,437	3,578,935
31 : 3,579,430	3,579,534	3,579,345	3,579,454	3,579,443	3,579,293
33 : 3,579,151	3,579,539	3,579,346	3,579,455	3,579,453	3,579,442
3,579,153	3,579,549	3,579,348	3,579,456	3,579,457	3,579,482
3,579,197	3,579,578	3,579,355	3,579,458	3,579,470	55 : 3,578,748
3,579,276	3,579,580	3,579,367	3,579,460	3,579,485	3,578,752
3,579,417	3,579,590	3,579,382	3,579,479	3,579,487	3,578,780
34 : 3,578,739	3,579,593	3,579,399	3,579,533	3,579,492	3,578,787
3,578,805	3,579,601	3,579,403	3,579,538	3,579,516	3,578,826
3,578,836	3,579,607	3,579,448	3,579,542	3,579,527	3,578,923
3,578,896	3,579,608	3,579,467	3,579,548	3,579,554	3,578,933
3,578,919	3,579,612	3,579,469	3,579,570	3,579,555	3,578,950
3,578,945	3,579,614	3,579,501	40 : 3,578,931	3,579,604	3,578,982
3,578,968	3,579,628	3,579,508	3,578,952	3,579,605	3,579,046
3,578,989	3,579,630	3,579,514	3,579,298	3,579,613	3,579,073
3,578,990	35 : 3,578,841	3,579,520	3,579,308	3,579,615	3,579,080
3,579,040	36 : 3,578,769	3,579,537	3,579,478	43 : 3,578,862	3,579,169
3,579,042	3,578,774	3,579,577	3,579,602	45 : 3,579,381	3,579,461
3,579,057	3,578,797	3,579,579	3,579,618	46 : 3,578,773	56 : 3,579,211
3,579,068	3,578,833	3,579,594			

Design Patents

6 : 220,743	9 : 220,783	17 : 220,759	26 : 220,767	37 : 220,747	42 : 220,751
220,746	220,784	220,768	220,777	39 : 220,745	220,752
220,748	220,785	220,782	220,779	220,757	48 : 220,761
220,763	12 : 220,760	18 : 220,769	29 : 220,744	220,773	220,762
220,764	17 : 220,753	220,780	220,758	220,787	220,786
220,766	220,754	22 : 220,771	34 : 220,741	42 : 220,742	51 : 220,765
220,770	220,755	24 : 220,774	36 : 220,772	220,749	220,789
220,788	220,756	25 : 220,776	220,781	220,750	55 : 220,778
220,791					

U.S. GOVERNMENT PRINTING OFFICE: O—1971

OFFICIAL GAZETTE of the UNITED STATES PATENT OFFICE

May 25, 1971

Volume 886

Number 4

CONTENTS

Issue of May 25, 1971	637
Patents and Trademark Notices	
Deposit of Microorganisms	638
Patent Suits	638
Patent Notices	
Disclaimers	640
Service by Publication	640
Certificates of Correction for the Week of May 25, 1971	640
Condition of Patent Applications	641
Reissue Patents Granted	642
Patents Granted	
General and Mechanical	643
Chemical	897
Electrical	948
Design Patents Granted	1031
Index of Patentees	PI 1
Indices of Reissues and Designs	PI 46
Classification of	
Patents (Including Reissues)	PI 47
Designs	PI 49
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 50
Designs	PI 52

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:
THE OFFICIAL GAZETTE (PATENTS SECTION), issued weekly, subscription \$89.00 per annum, foreign mailing \$22.25 additional; single copies \$2.00 each.
THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$17.00 per annum, foreign mailing \$4.25 additional; single copies 40 cents each.
CIRCULARS OF GENERAL INFORMATION concerning PATENTS or TRADEMARKS, price 15 cents each.

PRINTED COPIES OF PATENTS are furnished by the Patent Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS and DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents, Washington, D.C., 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S. Code P.O.

PATENT OFFICE NOTICES

Deposit of Microorganisms

Some inventions which are the subject of patent applications depend on the use of microorganisms which must be described in the specification in accordance with 35 U.S.C. 112. No problem exists when the microorganisms used are known and readily available to the public. When the invention depends on the use of a microorganism which is not so known and readily available, applicants must take additional steps to comply with the requirements of Section 112.

In *re Argoudelis et al.*, 168 USPQ 99 (CCPA, 1970), accepted a procedure for meeting the requirements of 35 U.S.C. 112. Accordingly, the Patent Office will accept the following as complying with the requirements of Section 112 for an adequate disclosure of the microorganism required to carry out the invention:

- (1) The applicant, no later than the effective U.S. filing date of the application, has made a deposit of a culture of the microorganism in a depository affording permanence of the deposit and ready accessibility thereto by the public if a patent is granted, under conditions which assure (a) that access to the culture will be available during pendency of the patent application to one determined by the Commissioner to be entitled thereto under Rule 14 of the Rules of Practice in Patent Cases and 35 U.S.C. 122, and (b) that all restrictions on the availability to the public of the culture so deposited will be irrevocably removed upon the granting of the patent;
- (2) Such deposit is referred to in the body of the specification as filed and is identified by deposit number, name and address of the depository, and the taxonomic description to the extent available is included in the specification; and
- (3) The applicant or his assigns has provided assurance of permanent availability of the culture to the public through a depository meeting the requirements of (1). Such assurance may be in the form of an averment under oath or by declaration by the applicant to this effect.

A copy of the applicant's contract with the depository may be required by the Examiner to be made of record as evidence of making the culture available under the conditions stated above.

RICHARD A. WAHL,
Assistant Commissioner.

Apr. 29, 1971.

Patent Suits

Notices under 35 U.S.C. 290; Patent Act of 1952

2,611,813, Sharpless and Elchert, Jr. MAGNETIC DATA STORAGE SYSTEM, filed Nov. 20, 1970, D.C., N.D. Ill. (Chicago), Doc. 70c2916, *Technitrol, Inc. v. Digital Equipment Corporation*.

2,706,236, Stepath, Krumm and Ross, CUTTING AND GOUGING ELECTRODE HOLDER AND METHOD, filed Dec. 14, 1970, D.C., N.D. Tex. (Dallas), Doc. CA-3-4362-D, *Arcaim v. James T. Jeter, Jr., doing business as J.W. Mfg. Co. and Automation Engineering & Mfg. Co.*

2,734,226, W. H. Willert, INJECTION MOLDING APPARATUS, filed Nov. 23, 1970, D.C. Conn. (New Haven), Doc. 14149, *Egan Machinery Company and William H. Willert v. Polymer Machinery Corp.*

2,742,327, T. Marks, FULLY AUTOMATIC MACHINE FOR MAKING BRUSHES, filed Jan. 12, 1971, D.C., S.D.N.Y., Doc. 71-C-152, *American Technical Industries, Inc. v. Poloron Products Inc.*

2,786,741, Huebler and Beggs, METALLURGICAL GAS GENERATOR, filed Dec. 14, 1970, D.C., N.D. Ill. (Chicago), Doc. 70c3119, *Sunbeam Equipment Corp. v. Midland Ross Corp.*

2,824,315, G. D. McKenny, RELEASABLE COUPLING DEVICE, filed July 28, 1967, D.C., W.D. Wash. (Seattle), Doc.

7294, *C. J. Hendry Company v. Manolides, Inc.* Dismissed, Jan. 29, 1970.

2,904,449, S. W. Bradstreet, METHOD AND COMPOSITIONS FOR FLAME SPRAYING, filed July 17, 1968, D.C., N.D. Ill. (Chicago), Doc. 68c1320, *Continental Coatings Corp. v. Metco, Inc. et al.* Motion for summary judgment granted to defendants in part and complaint and counterclaim are dismissed, Jan. 22, 1971.

3,036,642, O. D. Twist, FAN; D. 187,272, same, filed Dec. 22, 1970, D.C., W.D. Wash. (Tacoma), Doc. 4220, *Flex-A-Lite Corporation v. Hurricane Automotive Products*.

3,205,708, J. H. Andresen, Jr., COMBINED AIRSPEED AND MACH INDICATOR; 3,435,675, E. P. Knapp, MAXIMUM ALLOWABLE AIRSPEED POINTER, filed July 4, 1970, D.C.N.J. (Newark), Doc. 891-70, *Lear Siegler, Inc. v. Intercontinental Dynamics Corp.* Stipulation and order of dismissal, Jan. 5, 1971.

3,210,053. (See D. 207,293.)

3,229,413, H. K. Bross, TOYS AND RACK ACTUATING MEANS THEREFOR; 3,229,543, same, RACKS; D. 205,459, same, FLEXIBLE PULL STRAP FOR AN AERIAL TOY OR THE LIKE, filed Dec. 24, 1970, D.C.N.J. (Newark), Doc. 1725-70, *Kenner Products Company v. Helmut Karl Bross and Frank T. Johmann*.

3,229,543. (See 3,229,413.)

3,272,397, S. G. Bean, FEEDER OF NON-FLOWING MATERIAL, filed Feb. 3, 1971, D.C., N.D. Ill. (Chicago), Doc. 71c322, *Food Packaging, Inc. v. U.S. Sugar Company, Inc. et al.*

3,275,316, G. V. Cleary, Jr. INSERT FOR NEWSPAPERS, filed Jan. 18, 1971, D.C., N.D. Ill. (Chicago), Doc. 71c134, *Free Standing Stuffer, Inc. v. Parent's Magazine Enterprises*.

3,297,831, W. O. Stanton, MAGNETIC STEREOPHONIC PHONOGRAPH PICKUP, filed Jan. 5, 1971, D.C., S.D.N.Y., Doc. 71-C-31, *Pickering & Company Inc. v. Brooks Radio and Television Corporation*.

3,313,443, Dial, Habegger and Kays, FLOATING COVER FOR A LIQUID STORAGE RESERVOIR, filed Jan. 4, 1971, D.C.N.J. (Newark), Doc. 1-71, *Globe Linings, Inc. and Howard D. Webb v. Revere Plastics, Inc.*

3,319,872, Beckman and Beerbohm, MAILER, filed Jan. 12, 1971, D.C., W.D. Pa. (Pittsburgh), Doc. 71-46, *2B System Corporation v. Accounting and Business Forms, Inc. and the County of Allegheny*.

3,324,954, W. J. Westendorf, LOADER DEVICE AND METHOD OF MOUNTING SAME ON TRACTOR, filed Dec. 23, 1970, D.C., N.D. Iowa (Sioux City), Doc. 70-C-3061-W, *Walter J. Westendorf v. Sioux Steel Company*.

3,435,675. (See 3,205,708.)

3,445,324, Curler and Lineburg, FLEXIBLE WRAPPING MATERIAL, filed Jan. 8, 1971, D.C., N.D. Ill. (Chicago), Doc. 71c53, *Curwood, Inc. v. Standard Packaging Corporation*.

3,446,892, D. M. Stout, IMMOBILIZING INSETS BY SUDEN REDUCTION OF BODY TEMPERATURE, filed Feb. 1, 1971, D.C., N.D. Ill. (Chicago), Doc. 71c286, *Whitmore Research Laboratories, Inc. v. Chase Products Co., Universal Safety Equipment Co.*

3,450,212, A. G. Sylvester, MULTIPLE TOOTH SUBSOIL PLOW, filed Jan. 11, 1971, D.C., N.D. Tex. (Lubbock), Doc. CA-5-866, *Cline Industries, Inc. v. Sam Stevens, Inc.*

3,464,424, F. D. Buzzelli, METHOD FOR RETAINING HAIR, filed Jan. 12, 1971, D.C., E.D. Mich. (Detroit), Doc. 35919, *Frank Buzzelli v. Minnesota Mining & Mfg. Co.*

3,486,127, Back and Garellick, INSTRUMENTATION CIRCUIT WITH D-C AMPLIFIER HAVING TEMPERATURE STABILIZATION, filed Dec. 29, 1970, D.C., N.D. Ohio (Cleveland), Doc. C 70-1199, *Acromag, Incorporated v. Transmation, Inc.*

3,494,056, B. J. Elzer, DISPLAY DEVICE, filed Dec. 23, 1970, D.C., N.D. Ill. (Chicago), Doc. 70c3216, *Grafka Commercial Arts Inc. v. Parisian Novelty Co. Inc. and Joseph Mfg. Co.*

MAY 25, 1971

U. S. PATENT OFFICE

639

3,498,485, B. L. Godbersen, BOOM AND FORK LIFT APARATUS, filed Oct. 29, 1970, D.C., N.D. Ind. (South Bend), Doc. 70-S-153, *Midwest Industries, Inc. v. Freeman Industries Corporation*. Dismissed upon plaintiff's motion without prejudice, Nov. 17, 1970.

3,515,087, R. S. Stuart, PLANING BOAT, filed Jan. 4, 1971, D.C., S.D. Fla. (Miami), Doc. 71-5-C-WM, *Penn Yan Boats, Inc. v. Sea Lark Boats, Inc. et al.*

Re. 24,017, J. A. Henricks, METHOD OF COATING AND DRAWING METAL AND COMPOSITION THEREFOR, filed July 21, 1965, D.C. Del. (Wilmington), Doc. 3058, *Dever Corporation et al. v. General Motors Corporation*. (Transferred from Northern District of Illinois, E.D.) Final judgment, defendant has not infringed claim 4 of the patent. The amended complaint is dismissed with prejudice, Jan. 13, 1971.

Re. 24,730, C. E. Reeves, PORTABLE SIGNALLING DEVICE, filed Dec. 28, 1970, D.C., N.J. (Newark), Doc. 1732-

70, *Falcon Safety Products, Inc. v. Wagner Electric Sales Corp.*

Re. 24,899, B. K. Green, OIL-CONTAINING MICROSCOPIC CAPSULES AND METHOD OF MAKING THEM, filed Apr. 18, 1968, D.C. Del. (Wilmington), Doc. 3518, *The National Cash Register Company v. Minnesota Mining & Manufacturing Company, Inc., and Charles Pfizer & Co., Inc. (Coty Div.)*. Parties reached a compromise and agreement, therefore, it is ordered adjudged and decreed as follows: Action dismissed without prejudice, Jan. 7, 1971.

D. 187,272. (See 3,036,642.)

D. 205,459. (See 3,229,413.)

D. 207,293, C. W. Ferm, SEWAGE SEPTIC TANK; D.207,294, same, SEWAGE SEPTIC TANK; 3,210,053, C. F. Boester, AERATOR STRUCTURE, filed Jan. 13, 1971, D.C., M.D. Pa. (Scranton), Doc. C-71-23, *Cromaglass Corporation v. Carl Ferm, Fred R. Sechler and Plast-A-Form Corporation*.

D. 207,294. (See D. 207,293.)

Disclaimers

Re. 26,656.—*Raymond W. Guzzardo*, McHenry, Ill. CONTAINER FABRICATING AND ORIENTING APPARATUS. Patent dated Sept. 2, 1969. Disclaimer filed Sept. 17, 1970, by the assignee, *E. M. Melahn, doing business as Northern Illinois Machine Company*.

Hereby enters this disclaimer to claims 1 to 20, inclusive, of said patent.

Re. 26,969.—*Patrick J. O'Shea*, Hazel Crest, Ill. METAL CASTING PROCESS. Patent dated Oct. 20, 1970. Disclaimer filed Jan. 11, 1971, by the assignee, *Nalco Chemical Company*.

Hereby enters this disclaimer to claim 14 of said patent.

3,364,260.—*Saul L. Neidleman*, Highland Park, N.J. 4N-DE-METHYL-4N-ETHYL TETRACYCLINES. Patent dated Jan. 16, 1968. Disclaimer filed Sept. 14, 1970, by the assignee, *E. R. Squibb & Sons, Inc.*

Hereby enters this disclaimer to claim 1 of said patent.

3,401,866.—*Everett C. Johnson*, North Riverside, and *Donald G. Meier*, Tinley Park, Ill. CONTAINER WITH SELF-LOCKING LID. Patent dated Sept. 17, 1968. Disclaimer filed Dec. 21, 1970, by the assignee, *Owens-Illinois, Inc.*

Hereby enters this disclaimer to claims 1 and 2 of said patent.

3,422,656.—*Howard S. Orr*, Upper St. Clair Township, Allegheny County, Pa., and *Anthony D. Reinhardt*, South Holland, Ill. METHOD OF ROLLING SLABS IN PLANETARY MILL. Patent dated Jan. 21, 1969. Disclaimer filed Jan. 22, 1971, by the assignee, *United States Steel Corporation*.

Hereby enters this disclaimer to claim 1 of said patent.

3,444,134.—*Anthony C. Soldatos*, Kendall Park, N.J. PHENOLATED POLYMERS OF ISOPRENE. Patent dated May 13, 1969. Disclaimer filed Jan. 22, 1971, by the assignee, *Union Carbide Corporation*.

Hereby enters this disclaimer to claims 1 through 6 of said patent.

3,515,796.—*Roger J. Schoerner*, Carrollton, Ga. INSULATED TELEPHONE CABLE. Patent dated June 2, 1970. Disclaimer filed May 25, 1970, by the assignee, *Southwire Company*.

Hereby disclaims the terminal portion of the term of said patent subsequent to May 19, 1987.

3,533,812.—*Howard B. Cummings* and *Ralph Gibson*, New Castle, Pa. PROCESS FOR THE MANUFACTURE OF CERAMIC ARTICLES, AND PRODUCT DERIVED FROM SUCH PROCESS. Patent dated Oct. 13, 1970. Disclaimer filed Dec. 23, 1970, by the assignee, *Interpace Corporation*.

Hereby enters this disclaimer to claims 10, 24, 25 and 26 of said patent.

3,567,080.—*Mack S. Johnston*, Rolling Hills, Calif. TAPPING DEVICE FOR BEER KEGS AND THE LIKE. Patent dated Mar. 2, 1971. Disclaimer filed Sept. 29, 1970, by the assignee, *Republic Corporation*.

Hereby disclaims the terminal portion of the term of said patent subsequent to Jan. 25, 1983.

Service by Publication

Richard L. Marshall

In accordance with Rule 47 of the Rules of Practice of the United States Patent Office in Patent Cases, notice is hereby given of the filing on April 24, 1969, of an application for patent entitled "Rifled Bore Construction for a Gun Barrel," on behalf of Richard L. Marshall, whose last known address was 1342 Glenarm Place, Englewood, Colorado. The application was made in compliance with Rule 47(a) and 35 U.S.C. 116 by joint inventor Anthony A'Costa without execution by the said Richard L. Marshall. Notice of the filing directed to the above noted address has been returned undelivered.

Any action to be taken by the said Richard L. Marshall, or if he is deceased, his legal representatives or heirs, in connection with the said application must be taken within thirty days of the publication of this notice.

RICHARD A. WAHL,
Assistant Commissioner of Patents.

Certificates of Correction for the Week of May 25, 1971

Re. 27,018	3,542,809	3,553,282	3,559,348
Re. 27,059	3,543,385	3,553,425	3,559,350
3,351,164	3,543,833	3,553,573	3,559,511
3,442,962	3,543,923	3,553,964	3,559,538
3,445,181	3,544,431	3,554,041	3,559,557
3,452,301	3,545,819	3,554,698	3,559,655
3,454,401	3,546,190	3,554,993	3,559,816
3,472,933	3,546,378	3,554,996	3,559,818
3,475,564	3,546,832	3,555,038	3,559,891
3,478,469	3,548,561	3,555,271	3,560,429
3,479,258	3,548,860	3,555,864	3,560,718
3,480,523	3,548,991	3,556,063	3,560,931
3,489,696	3,549,601	3,556,142	3,561,267
3,500,966	3,549,625	3,556,159	3,561,313
3,507,872	3,549,787	3,556,218	3,561,498
3,522,034	3,549,945	3,556,230	3,561,591
3,522,160	3,550,298	3,556,508	3,561,843
3,523,078	3,550,414	3,556,637	3,562,212
3,525,733	3,550,549	3,556,669	3,562,314
3,525,958	3,550,730	3,556,795	3,562,448
3,533,647	3,551,249	3,556,890	3,562,549
3,534,030	3,551,355	3,557,033	3,562,635
3,534,574	3,551,466	3,557,068	3,563,939
3,537,577	3,551,677	3,557,099	3,564,843
3,537,930	3,551,748	3,557,393	3,565,328
3,538,209	3,551,770	3,557,505	3,565,399
3,538,668	3,552,232	3,557,564	3,565,597
3,538,920	3,552,258	3,557,605	3,565,847
3,539,911	3,552,514	3,557,841	3,566,173
3,540,015	3,552,657	3,557,962	3,566,484
3,540,103	3,552,672	3,558,612	3,566,675
3,541,042	3,552,970	3,558,663	3,567,637
3,541,060	3,553,179	3,558,853	
3,541,172	3,553,194	3,558,922	
3,541,490	3,553,198	3,558,966	

PATENT EXAMINING CORPS

R. A. WAHL, Assistant Commissioner
F. H. BRONAUGH, Deputy Assistant Commissioner

CONDITION OF PATENT APPLICATIONS AS OF MAY 4, 1971

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—M. STERMAN, Director..... Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	1-02-70
GENERAL ORGANIC CHEMISTRY, GROUP 120—I. MARCUS, Director..... Heterocyclic; Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	9-02-69
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—L. J. BERCOVITZ, Director..... Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Natural Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g.: Coating; Molding; Ink; Adhesive and Abrading Compositions; Molding, Shaping, and Treating Processes.	2-10-70
COATING AND LAMINATING, BLEACHING, DYEING AND PHOTOGRAPHY, GROUP 160—A. P. KENT, Director..... Coating; Processes and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; Bleaching; Dyeing and Photography.	2-03-70
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—W. B. KNIGHT, Director..... Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	10-17-69
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS AND RELATED ELEMENTS, GROUP 210—N. ANSHER, Director..... Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Miscellaneous.	8-17-70
SECURITY, GROUP 220—R. L. CAMPBELL, Director..... Ordnance, Firearms and Ammunition; Radar, Underwater Signalling, Directional Radio, Torpedoes, Seismic Exploring, Radio-Active Batteries; Nuclear Reactors, Powder Metallurgy, Rocket Fuels; Radio-Active Material.	12-11-69
INFORMATION TRANSMISSION, STORAGE AND RETRIEVAL, GROUP 230—J. F. COUCH, Director..... Communications; Multiplexing Techniques; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	3-13-70
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—W. L. CARLSON, Director..... Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	3-03-70
PHYSICS, GROUP 260—R. L. EVANS, Director..... Photography; Sound and Lighting; Indicators and Optics; Measuring and Testing; Geometrical Instruments.	1-21-70
DESIGNS, GROUP 290—R. L. CAMPBELL, Director..... Industrial Arts; Household, Personal and Fine Arts.	6-03-70
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—A. BERLIN, Director..... Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet and Web Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Railways and Railway Equipment; Brakes; Rigid Flexible and Special Receptacles and Packages.	3-09-70
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—D. J. STOCKING, Director..... Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion—Bonding, Metal Founding; Metallurgical Apparatus; Plastics Working Apparatus; Plastic Block and Earthenware Apparatus; Machine Tools for Shaping or Dividing; Work and Tool Holders Woodworking; Tools; Cutlery; Jacks.	1-02-70
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—A. RUEGG, Director..... Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Butchering; Earth Working and Excavating; Fishing, etc.; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Stationery; Information Dissemination.	2-02-70
HEAT, POWER AND FLUID ENGINEERING, GROUP 340—C. F. GAREAU, Director..... Power Plants; Combustion Engines; Fluid Motors; Pumps; Turbines; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Vaporizing; Temperature and Humidity Regulation; Machine Elements; Power Transmission; Fluid Handling; Lubrication; Joint Packing.	6-08-70
CONSTRUCTIONS, SUPPORTS, TEXTILES, CLEANING, GROUP 350—T. J. HICKEY, Director..... Joints; Fasteners; Rod, Pipe and Electrical Connectors; Miscellaneous Hardware; Locks; Building Structures; Closure Operators; Bridges; Closures; Earth Engineering; Drilling; Mining; Furniture; Receptacles; Supports; Cabinet Structures; Centrifugal Separations; Cleaning; Coating; Pressing; Agitating; Foods; Textiles; Apparel and Shoes; Sewing Machines; Winding and Reeling.	1-06-70

Expiration of patents: The patents within the range of numbers indicated below expire during May 1971, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 819, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents..... Numbers 2,677,129 to 2,679,644, inclusive
Plant Patents..... Numbers 1,274 to 1,281, inclusive


REISSUES

MAY 25, 1971

Matter enclosed in heavy brackets **[]** appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

27,125 MEANS FOR REMOVING GLARE OF A LIGHT BEAM

John F. Steel, P.O. Box 401, Palm Beach, Fla. 33480
Original No. 3,333,094, dated July 25, 1967, Ser. No. 421,742, Dec. 14, 1964, which is a continuation-in-part of Ser. No. 406,973, Oct. 26, 1964. Application for reissue Jan. 21, 1969, Ser. No. 802,277
Int. Cl. F21v 11/04
U.S. Cl. 240—46.11




A sealed-beam headlamp includes a coaxial lens and reflector, and an incandescent filament which generates a light source. A transparent plate is interposed between the filament and the lens to divide the headlamp into a hermetically sealed, evacuated filament compartment and a non-evacuated louver compartment. A frame which is fixedly mounted in the louver compartment is maintained stationary with respect to the lens and the plate. A plurality of louvers are rotatably mounted in the frame, the louvers being spaced-apart and mechanically coupled for simultaneous rotation sequentially through a fully closed position and a fully open position. A drive mechanism cooperates with the louver coupling to rotate the louvers in unison at such rate that a beam of light passing through the headlamp lens appears uninterrupted.

Alternatively, the louvers may be mounted for oscillation rather than rotation or a suitable louver coupling

device may be provided to rotate adjacent louvers in opposite directions.

27,126 DUAL SPLINED SHAFT ASSEMBLY FOR A CLUTCH

Wayne P. Gingery, Harlan, Iowa, assignor to Super-Drive Products, Inc., Los Angeles, Calif.
Original No. 3,465,860, dated Sept. 9, 1969, Ser. No. 642,363, May 31, 1967. Application for reissue May 8, 1970, Ser. No. 35,835
Int. Cl. F16d 13/44, 13/58
U.S. Cl. 192—70.13



A dual splined sleeve which will protect the original shaft from damage due to high engine torque, and where-in greater lateral resistance is provided. When the splines of the shaft become worn at their central portions, the dual splined sleeve is fitted over them so as to engage the shaft splines and extend beyond the worn portion. At least one disc member is provided with an internally splined hub and friction facing means on its outer portions, and the splined hub is fitted over the external splines of the sleeve so as to position the friction facing means for engagement by the clutch-actuating mechanism.

8 Claims

PATENTS


GRANTED MAY 25, 1971

GENERAL AND MECHANICAL

3,579,637 PROTECTIVE HELMET OF ADJUSTABLE SIZE Jackson Anthony Aileo, Carbondale, Pa., assignor to Gentex Corporation, Carbondale, Pa. Filed Apr. 1, 1969, Ser. No. 812,073 Int. Cl. A42b 1/08

U.S. Cl. 2—3

10 Claims




A protective helmet of adjustable size including a hollow shell adapted to receive the head of a wearer and made up of two complementary halves and a partially overlapping strip extending along their adjoining edges. The halves have, in their overlapped portions, a series of apertures elongated transversely to the strip. The strip has circular apertures aligned with the elongated apertures on the halves. Screws extend through the apertures and cooperate with nuts to hold the halves to the strip. When the screws are loosened, the halves can slide in relation to the strip over a distance limited by the length of the elongated apertures, thereby adjusting the size of the shell as required to fit the head of a particular wearer.

by unidirectional rotation of a self-reversing worm working in a pawl attached to the lens frame. The worm is an extension of the drive shaft of a miniature electric motor powered by rechargeable batteries through circuitry arranged to provide maximum starting speed followed by reduced speed. Starting of the motor is conveniently controlled by a breath-operated switch and stopping, at the limits of lens travel, by respective limit switches. Battery recharging terminals are preferably provided as suspension hooks to engage with electric power terminals of a storage rack when the helmet is not in service.

3,579,639 SUSPENDING DEVICE FOR GARMENTS James M. Faulkner, Laurel, Del. (Box 231, Georgetown, Del. 19947) Filed Nov. 8, 1968, Ser. No. 774,244 Int. Cl. A41f 3/02, 5/00

U.S. Cl. 2—117

4 Claims



Garment suspending device comprises pair of shoulder straps with fasteners connecting ends of straps together to form loop. Pair of intermediate adjustable straps is provided with one adjustable strap secured at one end thereof to each fastener. Terminal straps are connected at their mid portions to intermediate straps, and releasable attaching structure at ends of terminal straps secure suspending device to garment of type worn below waist. Suspending device is concealed by shirt or other outer upper garment.


3,579,638 EYE-SHIELD OPERATING SYSTEM FOR WELDING HELMETS

Frank J. Davis and George Zahnor Edwards, Salt Lake City, Utah, assignors to Kedman Company, Salt Lake City, Utah

Filed Sept. 23, 1969, Ser. No. 860,210
Int. Cl. A61f 9/06

U.S. Cl. 2—8

9 Claims



The eye-shield lens of a welding helmet is extended and retracted into and out of working position, respectively,


3,579,640 HEARING PROTECTOR HEADSETS Fred P. Beguin, Sturbridge, and Harry Dostourian, Worcester, Mass., assignors to American Optical Corporation, Southbridge, Mass. Filed Feb. 11, 1970, Ser. No. 10,473 Int. Cl. A42b 1/06

U.S. Cl. 2—209

4 Claims

Hearing protector headsets comprising an adjustable headband, sound-attenuating earcups, and attachment and supporting means for rotatably supporting and universally slidably tilting each earcup for adjustment of headband and earcups as needed while being worn. The adjustment and supporting means for each earcup includes at each end portion of the headband a spherically-shaped aperture

formation through which parts of the attachment and supporting means extend and against the sides of which



spherically-shaped end clamping members of selected kind and shape frictionally engage.

3,579,641

END CLIP FOR LOAD CARRYING BELT


Wesley S. Larson, Hazardville, Conn., assignor to the United States of America as represented by the Secretary of the Army

Filed Oct. 9, 1969, Ser. No. 864,992

Int. Cl. A41f 9/02, 19/00

U.S. Cl. 2—325

4 Claims



An end clip for attachment to an end of load carrying belt to serve as means for varying the length of the belt. The end clip has prongs formed on an outer surface thereof, the prongs being releasably engagable with eyelets in the belt forming a loop in the belt of variable size which carries a portion of means for fastening the belt about the body. The end clip is preferably made of rigid plastic material with pins and openings to receive the pins formed as elements thereof during molding of the end clip, the pins serving to affix the end clip to an end of the belt.

3,579,642

HEART VALVE ASSEMBLY AND METHOD OF IMPLANTING IN THE BODY

Bart T. Heffernan, 604 Laurel, Wilmette, Ill. 60091, and Efrem M. Ostrowsky, 2775 Fort Sheridan Ave., Highland Park, Ill. 60035

Filed Apr. 15, 1968, Ser. No. 721,360


Int. Cl. A61f 1/22

U.S. Cl. 3—1

4 Claims

A check valve for use in a human heart or the like in which the body portion contains check valve means on the inside thereof and in which the outer wall portions contain a groove around the periphery thereof to receive

a fastener in the form of a snap ring or the like. A method is described in which a membrane is opened, a stiff but resilient fastener such as a snap ring is sewn in place therein, closely adjacent the edges of the membrane which define the opening therein, and a check valve such as that described is napped into place in the opening in the mem-



brane as the ring is opened and closed over the valve, in registry with the groove. Preferably, the valve is a plastic material and the ring is stainless steel or stiff silicone rubber. The valve and method make it possible to immobilize thrombogenic materials resulting from the inclusion of a heart valve or the like in the body.

3,579,643

ARTIFICIAL ARTICULAR EMINENCE FOR THE MANDIBULAR JOINT


Douglas H. Morgan, 1700 Lila Lane, La Canada, Calif. 91011

Filed Dec. 12, 1968, Ser. No. 783,334

Int. Cl. A61f 1/24

U.S. Cl. 3—1

6 Claims



The present invention relates to the specialized field of dentistry known as oral surgery and particularly to an artificial articular eminence for the cure of disorders or dysfunctions of the mandibular joint. The artificial articular eminence of the present invention is surgically applied and provides an artificial surface for the condylar head of the mandible to contact and slide upon in opening and closing the jaw.

3,579,644

ARTIFICIAL HEART

William G. Esmond, 537 Stamford Road, Baltimore, Md. 21229

Filed Feb. 26, 1969, Ser. No. 802,580

Int. Cl. A61f 1/00


U.S. Cl. 3—1

8 Claims

This disclosure relates to an artificial heart which is so constructed whereby it may be mounted in the human body and permanently connected to the blood vessels of that body with the heart being powered by an external

source. The heart makes use of a low boiling point liquid and a heating coil which is periodically actuated so as to effect boiling of the liquid, followed by the rapid cooling

toilet and in which heavier solids settle out; a longitudinal baffle screen which is self cleaning due to ship motion and which screens out other solids; and a pick up chamber



of the liquid to condense the same whereby an expansion and contraction function is performed and constantly repeated so as to effect a pumping action.

3,579,645

CARDIAC VALVE OCCLUDER HAVING A DENSITY APPROXIMATELY EQUAL TO BLOOD


Jack C. Bokros, San Diego, Calif., assignor to Gulf Energy & Environmental Systems, Inc.

Filed Apr. 30, 1969, Ser. No. 820,361

Int. Cl. A61f 1/22

U.S. Cl. 3—1

10 Claims



An improved movable occluder for intermittently opening and closing the aperture in a heart valve. The occluder has an inner substrate portion and an exterior coating of a material, such as isotropic pyrolytic carbon, that is chemically nonreactive with blood. Although the exterior coating material has a density greater than blood, the substrate has an apparent density less than blood so that the composite occluder has a density that approximates blood. The substrate may be hollow or made of a porous material. An intermediate layer of low density material may be employed to deaden the sound.

3,579,646

SHIPBOARD RECIRCULATION SEWAGE SYSTEM

Robert L. Lekberg, 4040 W. 123rd St., Alsip, Ill. 60658


Filed May 16, 1968, Ser. No. 729,774

Int. Cl. E03d 1/00; E03f 5/10

U.S. Cl. 4—10

11 Claims

Recirculation sewage system for shipboard use having a holding tank which enables the toilet flushing liquid to be re-cycled following removal of sizable particulate matter therefrom in the tank. The tank includes: a chamber part which receives incoming waste discharged by the



3,579,647

TOILET TANK COVER



William L. Nielson, Janesville, Wis., assignor to Monterey Mills, Inc., Janesville, Wis.

Filed Feb. 11, 1969, Ser. No. 798,386

Int. Cl. B65b 11/00; B65d 65/02; A47k 17/00

U.S. Cl. 4—1

5 Claims



A one piece toilet tank cover wherein the top cover is integral with the side wall cover only along the front edge thereof so that the tank top may be removed easily without disturbing the side wall cover, which, at the same time, maintains a trim tailored appearance.

3,579,648

COMMUNE FLUSHING MECHANISM

Walter K. Owens, P.O. Box 5641, Pensacola, Fla. 32505

Filed Sept. 9, 1968, Ser. No. 758,366


Int. Cl. E03d 1/34

U.S. Cl. 4—52

4 Claims

A highly compact, low cost, pressure flushing mechanism for commodes suitable for initial installations or replacement kits within existing flush tanks of the gravity type. The mechanism or plural mechanisms may also be

enclosed within a wall by virtue of its compactness. The maximum effect of city water main pressure is utilized vent water trap emptying during air pressure fluctuations. In an alternative embodiment, venting is through an odor



for flushing without the need for oversized piping or expensive flush valves.

3,579,649


TOILET TANK AND GUIDE FOR FLUSH CONTROL VALVE

Arthur M. Dyer, 423 N. Graves, El Cajon, Calif. 92020
Filed Nov. 13, 1968, Ser. No. 775,313

Int. Cl. E03d 1/34

U.S. Cl. 4-56

7 Claims



A combination of a toilet tank and a movable baffle below the flush control valve which, in conjunction with a chain extending into the drain pipe and under the influence of water being flushed, guides a float type valve toward the valve seat leading from the tank.

3,579,650

VENTING DEVICE FOR TOILETS



Frank Philip Sloan, Toronto, Ontario, Canada, assignor to Aquair Corporation Limited, Nassau, Bahamas
Filed Mar. 11, 1969, Ser. No. 806,164

Int. Cl. E03d 9/04

U.S. Cl. 4-72

11 Claims

A device for sucking bathroom air through the rim holes of a toilet and for venting such air to a sewer. The device has a water trap preventing odor travel from the sewer to the room, an aspirator to empty the trap during use to permit air flow, and an inlet leg connected to the toilet flushing conduits at a location to be refilled by water flowing to the bowl during a flush, so that the trap can be refilled even if mains water pressure fails during venting. A check valve in the venting device pre-



removing filter which also serves to collect spray water from the aspirator and to muffle aspirator noise.

3,579,651


SELF-CONTAINED SEWERAGE SYSTEM

Ronald D. Russo, Wethersfield, Conn., assignor to Koehler-Dayton, Inc., Dayton, Ohio
Filed Nov. 28, 1969, Ser. No. 880,725

Int. Cl. E03d 7/00; B01d 33/02

U.S. Cl. 4-78

11 Claims



In a self-contained sewerage system of the type in which the sewage is accumulated and stored within the system and recirculated for flushing, when the level of liquid and

solid wastes within the collection tank reaches a preset level, the liquid wastes are withdrawn from the tank and pumped to an evaporative still where they are evaporated and vented from the system.

and constructed adjacent the top thereof with a fluid inlet opening capable of assuming and retaining a generally circular configuration, the bottom and end walls being

3,579,652



SANITARY URINE COLLECTOR

Richard E. Ericson, Keene, N.H., assignor to Elliot Laboratories, Inc., Fitzwilliam, N.H.
Filed Nov. 12, 1968, Ser. No. 774,696

Int. Cl. E03d 13/00

U.S. Cl. 4-110

27 Claims



arranged for folding upon themselves to permit said side walls to be disposed in substantially parallel plane and the portions defining said inlet opening disposed substantially in such plane to provide a relatively flat compact package.

3,579,654

DISPOSABLE SELF-INFLATABLE BED PAN

Henry S. Kuhn, 609 Austin Ave., Park Ridge, Ill. 60068
Filed Sept. 5, 1969, Ser. No. 855,603

Int. Cl. A61g 9/00

U.S. Cl. 4-113

19 Claims

3,579,653





DISPOSABLE URINAL

Henry S. Kuhn, 609 Austin Ave., Park Ridge, Ill. 60068
Filed Sept. 5, 1969, Ser. No. 855,602

Int. Cl. A47k 11/00

U.S. Cl. 4-110

11 Claims



A disposable urinal comprising a container constructed of thin sheet stock such as relatively stiff paper or light board, having a bottom wall, side walls and end walls,


A disposable self-inflatable bed pan comprising a body structure having an inflatable portion, constructed to produce a pan-shaped configuration when said portion is inflated, and activatable means arranged for reception in said inflatable portion and operable upon activation to effect inflation thereof, said activatable means comprising a material adapted to release a gas upon mixture with an activating liquid, with said material being disposed or disposable in said inflatable portion with said activating liquid being contained in said inflatable portion, out of contact with said material, or discharged into said inflatable portion at the time of usage.

3,579,655 PORTABLE TOILET AND SINK STRUCTURES AND THE LIKE

Alan F. Sundberg, Amityville, N.Y.
(256 W. 21st St., New York, N.Y. 10011)
Filed Aug. 13, 1968, Ser. No. 752,308
Int. Cl. A47k 11/02

U.S. Cl. 4-116

4 Claims




A portable toilet structure or the like which includes a plurality of side panels connected together along their respective adjacent edges. Connected to the side panels is a top panel having a through aperture. Surrounding the aperture and extending downwardly therefrom is a substantially waterproof bag. The bag is adapted to receive waste materials and the like thereby to provide a portable toilet or the like which may be assembled easily and quickly.

A method of fabricating the portable structure also is described.

3,579,656
PORTABLE HAIR WASH SINK
Joseph S. Guarrasi, 39 Buckingham Road,
Brooklyn, N.Y. 11226
Filed Feb. 20, 1969, Ser. No. 800,926
Int. Cl. A45d 19/00

U.S. Cl. 4-159

7 Claims



A portable hair wash sink in the form of a compact body unit including a basin, self-contained means for supplying water under pressure, and spray means for applying water to the head of the user. The sink also includes shoulder boards and a mating neck rest forming a yoke around the neck of the user. The boards and neck rest are dished to insure drainage into the sink basin.



3,579,657
SWIMMING POOL COVER DRAIN
Salvatore J. Gurrieri, Sylmar, Calif., assignor to
Anthony J. Pilarski, San Fernando, Calif.
Filed Sept. 4, 1969, Ser. No. 855,238
Int. Cl. E04h 3/18

U.S. Cl. 4-172.12

14 Claims

A device for pumping water from a swimming pool cover including a first unit located on a swimming pool cover, the first unit having a float valve opened by water accumulating on the cover, the valve connecting to a

second unit at the pool skimmer so that water from the cover is conducted to the inlet of the pump for the pool's circulation system. A valve member in the second unit is spring-biased to a closed position, but opened in re-




sponse to suction upon the closing of the float valve, thereby providing normal system operation through the pool skimmer when no water is present on top of the cover.

3,579,658
BATH TUB FOR INVALIDS
Rita Marie Choquette, 1589 Gouin Blvd.,
East Montreal, Quebec, Canada
Filed Dec. 9, 1968, Ser. No. 782,059
Int. Cl. A47k 3/024

U.S. Cl. 4-173

3 Claims



A bath tub primarily intended for invalid babies and to be used in hospitals specialized in the care of such babies, adapted to be fitted within a countertop opening and providing an inclined bottom wall portion to maintain the babies' head above water level, the tub being associated with a water sprayer head and flexible hose so arranged that one attendant can bathe invalid babies.

3,579,659
BUBBLE BATH DEVICE
Ludwig Baumann, Niederhelfenschwil, Switzerland
Filed Feb. 28, 1969, Ser. No. 803,170
Claims priority, application Belgium, Feb. 29, 1968,
711,465
Int. Cl. A61h 33/02


U.S. Cl. 4-180

7 Claims

The invention provides a bubble bath device which is operated by compressed-air generating means such as a blower or a compressor and comprises a support for the

body of a user and at least one tubular conduit which is immersed in a foam forming emulsion and extends along at least part of the periphery of the support in a plane below the upper surface of the support. The tubular conduit, which may be a hose, has a plurality of very fine

ing of kitchen utensils, such as pots or pans, which are of different diameter, by moving the utensil to the appro-




lateral apertures and is in communication with the compressed-air generating means so that upon actuation of the latter compressed air will be discharged through the apertures into the foam forming emulsion to produce small bubble foam which rises on both sides of the support so as to envelop the body of the user from above.

3,579,660
BATHTUB HOIST DEVICE
Willard H. Whitaker, 314 W. Tate St.,
Corinth, Miss. 38834
Filed Sept. 6, 1968, Ser. No. 758,052
Int. Cl. A47k 3/12

U.S. Cl. 4-185

3 Claims




A bathtub hoist device comprising lift means including a support for motor drive means and starter means for the motor means which can be operated by a person using the lift, and seat means detachably connected to bar support means, said bar support means being pivotally connected to a fixed member, and cable means disposed on drum means and connected to said bar means for lowering and raising said bar means and the seat means detachably connected thereto.

3,579,661
SINK
Millard H. Lien, Omaha, Nebr., assignor to
Crane Co., Chicago, Ill.
Filed May 6, 1969, Ser. No. 822,152
Int. Cl. E03c 1/18

U.S. Cl. 4-187

2 Claims

A plumbing fixture, such as a kitchen sink, wherein at least one corner has a radius of curvature which progressively increases from the top portion of the sink to the bottom portion. Such variation in radii enables the drain-




priate position along the sink corner which substantially conforms to the curvature of the utensil.

3,579,662
FREEZE PROTECTED WASTE TRAP
Robert D. Lowry and Russell B. Strout, Winchester,
Mass., assignors to Lowry Development Corporation,
Winchester, Mass.
Filed Mar. 20, 1969, Ser. No. 808,905
Int. Cl. E03c 1/284

U.S. Cl. 4-206

5 Claims




A waste trap for water drains having a U-shaped conduit the legs of which have internal transverse cross sectional areas increasing progressively upwardly of said legs to the round top level of water contained in said trap the waste trap being provided with an electrical heater element and thermostatic control.

3,579,663
TOILET SEAT COVER
Robert Paul Leiter, 1219 Poplar Grove Drive, and
Thomas G. Ware, 1029 N. Virginia Ave., both of
Atlanta, Ga. 30306
Continuation-in-part of application Ser. No. 755,137,
Aug. 26, 1968. This application Nov. 18, 1968,
Ser. No. 776,318
Int. Cl. E03d 9/00

U.S. Cl. 4-230

8 Claims



A toilet seat assembly having a cover pivotally secured to the seat member wherein there is provided a flat fo-

raminous bottom member which has a common pivot with the cover, and cooperating members on the cover and flat bottom such that they may be snapped together or pulled apart. A central island having a pair of diverging walls extending therefrom is located on the inside face of the cover to define an open area for receiving deodorant material which is held in place by the flat bottom member when interlocked with the cover.

3,579,664




TOILET FLUSHING ATTACHMENT

Evar C. Johnson, 2927 9th St., Rockford, Ill. 61109
Filed July 28, 1969, Ser. No. 845,316
Int. Cl. E03d 5/04

U.S. Cl. 4—250

16 Claims

A crank oscillatable by pressure rearwardly against the toilet seat lid turns a cross-shaft supportedly horizontally on the front of the flushing tank to operate



with a retaining channel to receive the edge of a pool liner.

3,579,666

SWIMMING POOL



Ebbe Torsten Leonard Regebro, Lunnagardsvagen 15, and Karl-Olof Pettersson, Engagatan 50, both of Alvesta, Sweden

Filed Jan. 21, 1969, Ser. No. 792,609
Claims priority, application Sweden, Jan. 31, 1968, 1,241


Int. Cl. E04h 3/16

U.S. Cl. 4—172.19

9 Claims



A swimming pool formed of plates of light weight metal such as aluminium. The walls of the pool are



A swimming pool structure wherein a combination of interlocking aluminum side wall members are retained at their lower and upper ends in channels of lower and upper channel members, and a coping member surmounts the upper channel member. The coping and

formed of elements which are concave vis a vis the interior of the pool and have no conventional splash channels but instead are provided with a peripheral portion extending outwardly from the top of the walls which include spaced apart inverted U-shaped beams with grids therebetween for receiving splash-over water. The innermost inverted U-shaped beam forms the edge of the pool which coincides with the level of water in the pool when it is filled.

3,579,667


BATHTUB CONSTRUCTION

Gino Giglio, 32 Cornelia St., New York, N.Y. 10014
Filed June 5, 1969, Ser. No. 830,642

Int. Cl. A47k 3/00

U.S. Cl. 4—181

4 Claims



A bathtub formed with a water distribution channel arranged along one side of the tub adjacent the water entry to the tub, with the channel formed to guide the entering water horizontally along the upper edges of the side walls of the tub, whence the water falls along the side walls to continuously wash the side walls of the tub as the water is being admitted thereto, to prevent water falling through air to eliminate splashing, and to impart a swirling, mixing motion to water in the tub. The channel is formed with an inner wall of progressively decreasing height serving to implement desired direction of the water.

3,579,668


BATH AND SHOWER SEAT

Manuel Aronovitz, 913 Tampa St., Tampa, Fla. 33602
Filed Mar. 21, 1969, Ser. No. 809,102

Int. Cl. A47k 3/12

U.S. Cl. 4—185

7 Claims



The seat of the present invention comprises an easily installed panel having a plastic finish which can be colored

to match any bathroom color scheme. In one embodiment the seat, when in use, is supported in a horizontal position by the edges of the sides of a bathtub and is pivotable upward so as to be stored vertically against a wall above the tub. When stored the seat may be recessed in the wall and provided with a magnetic latch to secure the stored seat. In another embodiment the seat when in use, is supported by its own hinge, and is pivotable downward to its vertical storage position. The latter embodiment is suited for use in showers since support by sides of a bathtub is not required.

3,579,669

SANITARY SINGLE USE TOILET SEAT COVERS


Gideon Loewenstein, 39—37 46th St.,
Long Island City, N.Y. 11104

Filed Apr. 14, 1969, Ser. No. 815,550

Int. Cl. A47k 13/14

U.S. Cl. 4—245

4 Claims



A package of sanitary, disposable seat covers is formed by superimposed seat covers adapted to be secured to the toilet seat. Each seat cover has a tab extending from its outer periphery, which tab is offset from the tabs of the adjacent seat covers, whereby the assembly of seat covers provides an arrangement of staggered tabs to thereby facilitate the gripping of a tab with the fingers.

3,579,670


PIPE CONNECTOR

Emil A. Frank, Long Beach, Calif., assignor of fractional part interest to Ronald L. Frank, Long Beach, Calif.
Filed July 2, 1968, Ser. No. 742,040

Int. Cl. F16l 37/04

U.S. Cl. 4—252

8 Claims



A device for connecting pipes together, connecting a pipe to a water closet or supporting a closet bend pipe which utilizes a collar squeezing a resilient gasket against the pipe to provide a water-tight, mechanical seal without the problems usually associated with the normal hot lead type of sealant.

3,579,671

ADJUSTABLE BED

Helmut Kötter, Schweicheln-Bermbach, Germany, assignor to Joh. Stieglmeier & Co. G.m.b.H., Herford, Westphalia, Germany


Filed Feb. 19, 1969, Ser. No. 800,628

Claims priority, application Germany, June 7, 1968, P 17 66 522.4

Int. Cl. A61g 7/00, 7/10

U.S. Cl. 5—62

9 Claims



An adjustable bed including a chassis, a bed frame disposed on the chassis, two or three hydraulic cylinder and piston units disposed at the ends of the bed, an articulated connection between the cylinder and piston unit and the bed frame so that the bed frame may be moved to various elevated and/or inclined positions.

3,579,672

METHOD AND APPARATUS FOR MOVING OBJECTS


Laurel A. Koll and Walter Crook, Jr., Ruleville, Miss., assignors to Diamondhead Properties, Inc.

Continuation-in-part of application Ser. No. 706,755, Feb. 14, 1968. This application Feb. 5, 1970, Ser. No. 9,029

Int. Cl. A61g 7/08, 7/10

U.S. Cl. 5—81

28 Claims



An improved transporter device includes a pair of superposed aprons formed as endless belts or portions thereof and which function to receive, carry, or deposit objects in accordance with desired transferring and carrying requirements. Each of the aprons is supported by a non-rigid support means which maintains supporting surfaces of the pair of aprons in substantially horizontal planes of operation for transferring objects from one horizontal surface to a surface provided on the transporter device itself. Transferring movements of the two aprons can be carried out by controlled translating movements of the supporting means contained within the two belts, and the lower apron or belt includes a section which is fixed relative to a base portion of the transporter device so that the lower apron does not have to be driven. In addition, the upper apron defining belt can be alternatively driven or not driven relative to its support means in accordance with loading, unloading, or positioning functions that may be desired. The non-rigid support means are made up of a number of flexible fingers so that the

apron can conform to irregularly shaped objects, such as a patient being moved onto or from a hospital bed, so that the weight of the object is transferred downwardly through the aprons and their associated support means to an area of surface directly beneath the object when the object is supported by the apron. Control means are provided for controlling cycles of loading, unloading and positioning with the transporter device, and the device offers a variety of functions and methods of use.

3,579,673

COMBINATION CAR SEAT AND CRIB


Kenneth A. Hirschey, 6804 Southdale Road, Edina, Minn. 55435

Filed Dec. 3, 1968, Ser. No. 780,818

Int. Cl. A62b 35/00; A47d 7/00, 9/00

U.S. Cl. 5—94

9 Claims



A combination car seat and crib for children including a crib portion composed of a bottom wall and four vertical walls formed from a strong lightweight molded material, e.g. foamed polystyrene, within which the child lies when sleeping. The child's head is cradled between energy absorbing bumpers consisting of vertical partitions molded integrally with the crib at one end. A removable seat slides into place above the partition. Seat belts normally provided with the car secure the crib or crib and seat in place and also function to hold the child in the seat.

3,579,674

INFANT'S SAFETY CAR BED


Zoel W. Blais, Templeton, and Harold F. Shaw, Leominster, Mass., assignors to Thayer, Inc., Gardner, Mass.

Filed Nov. 13, 1969, Ser. No. 876,293

Int. Cl. A47d 7/04

U.S. Cl. 5—94

10 Claims



A folding car bed comprising an upper open rectangular frame and a depending flexible body support with a mattress therein, a safety harness, a strap on the safety harness extending through the mattress and the bottom of the flexible support for securement underneath the same; a folding leg frame on the upper frame at each end thereof, each

leg frame comprising a forwardly extending free-ended foot having a rearwardly extending spur thereon, each foot being pivotally mounted with respect to its leg, an adjustable locking bracket for each foot, said leg frames being foldable flatwise against the upper frame.

3,579,675

CHILD'S SLEEPING BAG


Leila C. Scheer, 1272 Balboa Ave., Burlingame, Calif. 94010

Filed Feb. 24, 1970, Ser. No. 14,260

Int. Cl. A47g 9/00

U.S. Cl. 5—343

6 Claims



A child's sleeping bag having a lower panel projecting endwise beyond the top edge of an upper panel at the head end of the bag, with an ornamental pillow attractive to a child secured to the projecting part, and a flap secured at an edge to the lower panel so that the flap may be moved into a position to overlie and protect the pillow from being soiled when a child occupies the bag, the flap being foldable into a compartment between the panels to thus expose the pillow.

3,579,676

BEEHIVE


Paul W. Pierce, 1630 W. 9th St., Upland, Calif. 91786

Filed Apr. 16, 1969, Ser. No. 816,679

Int. Cl. A01k 47/02

U.S. Cl. 6—2

10 Claims



A bee frame and a super for a beehive. The bee frame is a unitary molded plastic structure including a permanent, molded plastic comb foundation characterized by a

novel cellular configuration and integrally joined to the frame bars in such a way as to condition the frame to support the weight of a honeycomb for an extended period of time without warping and to permit machine uncapping of the comb. The super has notched frame supports of novel configuration for supporting a number of bee frames in laterally spaced side by side relation to provide an optimum spacing between adjacent frames and permit handling and transportation of a hive containing bees and honeycomb without damage to the bees or honeycomb.

3,579,677

FLEXIBLE ROTARY COMPOUND TOOL


Robert Ullman, Wilton, Conn., assignor to Ullman Devices Corporation, Ridgefield, Conn.

Filed Feb. 7, 1969, Ser. No. 797,650

Int. Cl. B25f 1/04

U.S. Cl. 7—1

6 Claims



A complete self-contained compound tool, useful in particular as a carburetor-distributor adjustment device. It incorporates a flexible shaft-flexible tube combination that is capable of functioning through a tortuous path and integrates in a single head two implements, a hex key and a screw driver, each being rendered alternately usable by a sliding head adjustment.

3,579,678

PAINT CAN RIM PIERCER


James L. Regan, Hayward, Calif.
(409 Dunkel St., Fairbanks, Alaska 99701)

Filed Apr. 30, 1969, Ser. No. 820,511

Int. Cl. B25f 1/04; B67b 7/44

U.S. Cl. 7—14.1

11 Claims




A paint can rim trough punch means for punching drain holes in the rim trough of a paint can including a handle member having a hook on one end receivable under the paint can rim and an inwardly positioned outwardly extending V-shaped piercer member movable when the hook is positioned under the rim to pierce the rim trough.

3,579,679 **TENSIONLESS LIQUID TREATING APPARATUS AND METHOD**

David M. Willis, Spartanburg, S.C., assignor to Jonathan Logan Inc., New York, N.Y.
Filed Dec. 10, 1968, Ser. No. 782,587
Int. Cl. B05c 5/00

U.S. Cl. 8-151

11 Claims




A method of and apparatus for treating a running length of textile web material with a fluid wherein the textile web material is transported through a fluid treating zone without any appreciable tensional forces being imposed thereon and while in a substantially tension-free state by overfeeding the textile web material onto a horizontally moving supporting surface, advancing the textile web material through the treatment zone while spraying opposite faces of the web material with treatment fluid and while causing the web material to follow an undulating path of travel with any given portion thereof only intermittently engaging the supporting surface.

3,579,680 **MOTORIZED FLOAT**

Leslie R. McLean, Box 414, 414 Strathcona Ave., Kelowna, British Columbia, Canada
Filed Mar. 3, 1969, Ser. No. 803,732
Int. Cl. B63b 35/00; B63c

U.S. Cl. 9-1

3 Claims



A motorized float for supporting house trailers having a trailer-supporting deck structure supported by a plurality of elongated fore and aft flotation units, each of the latter being formed of at least three pontoons which are arranged in a tight, compact bundle by straps extended therearound and connected to the deck structure. A protective member connected to the straps extends longitudinally of and beneath each bundle of pontoons.

3,579,681 **SECTIONAL AND LONGITUDINALLY ADJUSTABLE SURFBOARD FIN ASSEMBLY**

Karl D. Pope III, 6377 Clemens St., and Thomas H. Morey, 36 Lincoln Drive, both of Ventura, Calif. 93003, and Robert R. Tierney, 412 Mallory Way, Ojai, Calif. 93023


Filed Apr. 1, 1969, Ser. No. 811,810
Int. Cl. A63c 15/00

U.S. Cl. 9-310

7 Claims

A surfboard fin assembly includes a longitudinally adjustable fin section movably mounted within an elongated channel formed by a fin base section. The fin base section has tapered exterior side walls sized for wedging engagement with tapered interior side walls of a mounting box. The fin base section can be selectively interlocked with the

fin section by use of a retaining plate that is slidably coupled to the fin base section and is located in the




elongated channel. The retaining plate has a positioning groove for receiving a portion of the fin section.

3,579,682 **SKI-BOARD**

Craig A. Wood, 707 Sycamore Lane No. 1, Davis, Calif. 95616
Filed May 12, 1969, Ser. No. 823,637
Int. Cl. A63c 15/00

U.S. Cl. 9-310B

11 Claims




An elongated hull includes shaped spaces to receive a skier's feet. A rudder on the after end of the hull affords steering capabilities, the rudder being controlled by a bridle held by one hand of the skier, the other hand holding a lead line extending to the forward end of the hull and helping the skier to maintain balance.

3,579,683 **HORSESHOE-SHAPED LIFEBOUY AND METHOD OF MAKING THE SAME**

James H. Robertson, 5238 Vineland Ave., North Hollywood, Calif. 91601
Filed Aug. 15, 1969, Ser. No. 850,432
Int. Cl. B63c 9/10

U.S. Cl. 9-340

12 Claims




A horseshoe-shaped life buoy and method of making the same in which a substantially U-shaped body member

3,579,686 **AUTOMATIC SCREW MACHINE** Jess Frank Sorenson, Yucaipa, Calif., assignor to Sorenson Engineering, Inc. Filed Oct. 7, 1968, Ser. No. 765,391 Int. Cl. B23b 7/00, 13/00, 15/00; B23g 1/00, 11/00; B22p 23/00

U.S. Cl. 10-87

10 Claims




An automatic screw machine with a pulley-driven collet and spindle assembly for reciprocally moving parts into and out of contact with boring tools. The assembly has two rearwardly extending rods which fit slidably within receptive openings in a drive pulley to permit its axial reciprocation while being driven by the pulley. The assembly also has a pair of chucking levers mounted to pivot about one end, under the direction of a timing cam, and exert cam-like collet opening and closing pressures on a responsive member. The machine has an index rod and an index plate with receptive holes for the rod. The plate is affixed to a cam-controlled shaft to which a tool holder is also affixed. When the index rod is moved into one of the holes in the plate, a part held by the collet and spindle assembly is guided to a particular tool on the tool holder.

3,579,684 **METHODS OF MAKING SELF-LOCKING THREADED ELEMENTS**

Richard J. Duffy, Salem, Mass., assignor to USM Corporation, Flemington, N.J., and Boston, Mass.
Original application Apr. 5, 1967, Ser. No. 628,683, now Patent No. 3,498,352, dated Mar. 31, 1970. Divided and this application Nov. 25, 1968, Ser. No. 778,636
Int. Cl. B23g 9/00; B21k 1/44, 1/56, 1/64

U.S. Cl. 10-10

9 Claims



Method of making a self-locking threaded element, e.g. a screw including a strongly adhered convexly curved plastic body on its threaded surface allowing smooth assembly and giving strong frictional engagement between the element and a mating threaded surface. In the method, a stream of fine particles of heat-softenable plastic is directed against a threaded surface portion of a heated metallic element. Contacting particles are caught on the heated surface and fused by heat from the element to form a continuous plastic body which is then hardened by cooling.


3,579,685 **MECHANISM FOR EJECTING WORKPIECES FROM THE MATRICES OF UPSETTING MACHINES**

Gerardus Cornelis van de Meerendonk, Helmond, Netherlands, assignor to Nederschroef Octrooi Maatschappij N.V., Helmond, Netherlands
Continuation of application Ser. No. 602,001, Dec. 15, 1966. This application July 17, 1969, Ser. No. 849,552
Claims priority, application Netherlands, Dec. 17, 1965, 6516468

Int. Cl. B21k 1/44

U.S. Cl. 10-12

6 Claims




The disclosure is of an improved mechanism for ejecting a workpiece from a matrix after forming therein and includes a rocker shaft carrying an adjustable cam pivoted thereon on an axis parallel to the axis of the rocker shaft, a lever having an ejecting arm and a follower arm, the latter engaging the cam on the rocker shaft.

3,579,687 **TAPPING APPARATUS**

Hideo Hoshi, 40 Minamiide Nakaodai, Yamada-cho, Nishi-ku, Nagoyashi, Japan; and Masao Washi, 3083 Ozaikeda, Ikeda-cho, Kitaazumigun; and Hiroshi Yoshiki, 11-382 Higashi, Arigasaki, Matsumotoshi, both of Nagano-ken, Japan
Filed Sept. 30, 1968, Ser. No. 763,856
Claims priority, application Japan, Oct. 9, 1967, 42/64,686, 42/64,687
Int. Cl. B23g 1/00

U.S. Cl. 10-129

4 Claims



A tapping machine in which a ball screw and a spline shaft with a tap secured at its end are mounted to a press ram in a mutually meshed relation through gearing, and

as the press ram is moved up and down, the up and down strokes of the press are converted into rotation by the ball screw, with the produced rotating force being transmitted to the spline shaft to thereby effect tapping operation.

3,579,688

TAP HOLDER


Lawrence W. Keltz, Chicago, and Charles Marek, Berwyn, Ill., assignors to The Chicago Roller Skate Company, Chicago, Ill.

Filed Apr. 28, 1969, Ser. No. 819,543

Int. Cl. B23b 31/08; B23g 5/16

U.S. Cl. 10—134

5 Claims



A tap holder assembly including relatively axially and rotatably movable parts with a one-way rotary clutch therebetween, and a spring-biased plate for maintaining elements of the clutch in proper assembled relationship during axial relative movement of the parts.

3,579,689

THREAD CONDITIONING AND RESTORING TOOL


Edward F. Ferkovich, 1341 S. 5th St., Raton, N. Mex. 87740

Filed Oct. 4, 1968, Ser. No. 765,190

Int. Cl. B23g 5/04, 5/06

U.S. Cl. 10—140

1 Claim



A threaded restoring tool comprising die elements having internal cutting teeth for restoring threads, a nut member in threaded engagement with external threads on the die elements which are arranged for a threaded direction of movement by the nut member which is opposite to the threaded direction of movement by the cutting teeth so that rotation of the nut member in its threaded direction of movement serves not only to tighten the die elements about the threads to be restored but causes the cutting teeth to rethread the threads to be restored by moving the cutting teeth in its opposite direction of movement.

3,579,690
TOE LASTING MACHINE


Jacob S. Kamborian, 70 Crestwood Road, West Newton, Mass. 02165

Filed Sept. 17, 1969, Ser. No. 858,667

Int. Cl. A43d 21/00

U.S. Cl. 12—12.4

18 Claims



A machine for wiping the margin of the toe portion of an upper draped about a last against an insole located on the bottom of the last. The wiping is performed by wipers, having a toe to heel component of movement, that perform their wiping operation in response to the engagement of a heel clamp with the heel portion of the last while the heel clamp is locked against movement away from the last.

3,579,691

SHOE LASTING MACHINES


Rudi Fichtner, Ober Horgern, and Wilhelm Klein, Frankfurt am Main, Germany, assignors to USM Corporation, Boston, Mass.

Filed Jan. 19, 1970, Ser. No. 3,912

Int. Cl. A43d 21/00

U.S. Cl. 12—12.4

5 Claims



A shoe lasting machine in which a stop limits movement of wipers to an intermediate position in which an upper has been wiped over a shoe bottom only enough to hold an insole against a last bottom, and a pressure plate which previously held the insole is thereafter retracted and controls continued movement of the wipers.

3,579,692

SHOE MACHINES

Anton Muhlbach and Gerhard Lauckhardt, Frankfurt am Main, Germany, assignors to USM Corporation, Boston, Mass.


Filed Feb. 16, 1970, Ser. No. 11,597

Claims priority, application Germany, Feb. 25, 1969, P 19 09 474.7

Int. Cl. A43d 21/00

U.S. Cl. 12—8.3

6 Claims



A machine for automatically operating on the margin of a shoe bottom including a rotary tool movable along the margin and cooperating with guide means for directing lateral movement of the tool relative to the margin. The guide means includes a light responsive means such as a photocell which registers on a light guide comprising a light source and a template located to the front of the light source.

3,579,693

PINCERS ASSEMBLY


Charles A. Robinson, Waltham, Mass., assignor to Jacob S. Kamborian, West Newton, Mass.

Filed Mar. 9, 1970, Ser. No. 17,406

Int. Cl. A43d 23/00

U.S. Cl. 12—14.5

6 Claims



A pincers assembly for stretching an upper about a last and moving the margin of the upper inwardly of the insole periphery. The assembly comprises a pincers that is mounted in a housing with the housing being mounted to a support for heightwise movement and the support being mounted to a base for inward-outward movement.

3,579,694

AUTOMATIC SHOE MACHINERY AND OPERATION OF THE SAME


Herman A. Imhof, Hamilton, Mass., assignor to USM Corporation, Boston, Mass.

Filed June 2, 1969, Ser. No. 829,307

Int. Cl. A43d 25/00; A43b 13/00

U.S. Cl. 12—17

17 Claims



A through feed finishing machine designed to provide an operation such as sole reduction on defined margins or edges of an unattached shoe sole initiated relative to the ball point of the sole. The machine includes pairs of finishing tools, for example, rotatable reducing tools mounted in biased relationship to operate on opposite sides of a sole. Pressure equalizing means are mounted opposite each of the tools to assist in keeping the sole moving along a path of travel through the machine and insure uniform finishing by each of the tools during the finishing operation of the lengthwise margins at predetermined points defined relative to the ball points of the sole. The sole is urged through the machine by drive rolls and is stabilized by holddown rolls acting in pairs.

3,579,695

SHOE SUPPORTS

Herbert W. Boot, Leslie R. Parr, and Shirley L. W. Fudger, Leicester, England, assignors to USM Corporation, Boston, Mass.


Filed Oct. 8, 1969, Ser. No. 864,704

Claims priority, application Great Britain, Oct. 10, 1968, 48,014/68

Int. Cl. A43d 21/00, 23/00

U.S. Cl. 12—127

6 Claims



A shoe support for holding a shoe bottom upmost in position to be engaged by tools which rough the marginal

portion of the overlaid upper. The support includes a holddown foot which engages the bottom of the shoe at the heel area. Means are provided for selectively removing the holddown foot to an inoperative position to permit the tools to act on the entire margin from toe to heel as distinguished from only from the toe to the heel breast line when the holddown foot is in operative clamping position.


3,579,696 DOCKBOARD

Robert W. Hecker, Jr., Clare, Mich., and Robert C. Beckwith, Milwaukee, Wis., assignors to Loomis Machine Company, Clare, Mich.

Filed Dec. 30, 1968, Ser. No. 787,652
Int. Cl. B65g 11/00

U.S. Cl. 14—71

22 Claims



A dockboard assembly including a ramp pivotally connected to a support means and biasing means urging the ramp to pivot upwardly. A releasable holding means acts in opposition to the biasing means for restraining the biasing means from raising the ramp. A lip is pivotally connected to the ramp for pivotal movement between an extended position and a pendent position. The improvement is to include a control means responsive to the pivotal movement of the lip for releasing the holding means so that the ramp will automatically pivot upwardly.


3,579,697 MEAT CLEANING BRUSH

Gilbert L. Smith, 1305 23rd St., Peru, Ill. 61354

Filed Dec. 1, 1969, Ser. No. 881,157
Int. Cl. A46b 13/02

U.S. Cl. 15—3.1

12 Claims



A meat cleaning appliance for removal of foreign material from the surface of pieces of meat comprising a housing having opposite sidewalls, a grid structure between said sidewalls for supporting the meat on a cleaning pass, and rotary brush means mounted for rotation in said housing on an axis spaced longitudinally between said sidewalls below said grid structure. The grid structure comprises a plurality of spaced apart V-shaped grids having the apexes spaced below the upper edges of the housing sidewalls and the radial bristles of the brush means project upwardly above the apexes of the grids for cleaning engagement with the meat surfaces.


3,579,698 TAILGATE WINDOW WASHER

Marcel E. Verdoodt, Warren, and Klaus A. Michalke, Utica, Mich., assignors to Chrysler Corporation, Highland Park, Mich.

Filed Aug. 30, 1968, Ser. No. 756,615
Int. Cl. A47l 1/02

U.S. Cl. 15—250.1

8 Claims



A washer mechanism for the window glass of a tailgate of a motor vehicle of the station wagon type in which a pair of wiper blades are mounted within the gate for selective movement between wiping and retracted positions in response to up and down movement of the window glass with a plurality of nozzles, supplied by a reservoir and pump assembly positioned within the gate, positioned directly below the wipers to selectively direct cleaning fluid against the window glass to facilitate the wiping operation. The wipers, in their wiping position, remain stationary and the glass is moved past the wipers to accomplish the wiping and washing action.


3,579,699 SUCTION CLEANER NOZZLE ADJUSTMENT

Jerry L. Balzer, Canton, Ohio, assignor to The Hoover Company, North Canton, Ohio

Filed Feb. 20, 1969, Ser. No. 800,893
Int. Cl. A47l 5/34

U.S. Cl. 15—361

5 Claims



In an upright suction cleaner, movement of the propelling handle to its rest position raises the nozzle from one of a plurality of selected operative positions to an inoperative position and renders a nozzle adjusting device ineffective, and movement of the handle from its rest position renders the nozzle adjusting device effective to reposition the nozzle to any one of the plurality of positions selected prior to movement of the handle to its rest position.


3,579,700 CAR WASHING APPARATUS

David Merl Haley, Glendale, Calif., assignor to California Car Wash Systems, Inc., Sun Valley, Calif.

Filed Aug. 1, 1969, Ser. No. 846,851
Int. Cl. B60s 3/06

U.S. Cl. 15—21

4 Claims



Car washing apparatus including a moveable frame to be advanced over a stationary car. A pair of vertically disposed side brushes are carried from the frame and control means are provided for selectively moving the brushes transversely across the ends of the car and for holding them at the respective sides of the car while the frame is moved longitudinally thereof. A safety control is responsive to such brushes engaging projections at the end of the car during their transverse travel to cause the frame to back away from the car and move the brushes clear of the projections so they can continue their transverse travel.


3,579,701 AUTOMATIC CAR WASHER

Clair R. Crisp, Jr., 3308 E. 30th Ave., Spokane, Wash. 99203

Filed June 3, 1968, Ser. No. 734,083
Int. Cl. B60s 3/06; A46b 13/02

U.S. Cl. 15—21

5 Claims



Washing mechanism for a stationary automobile providing a first brush rotatable about a vertical axis transiting about the car and a second brush rotating about a horizontal axis transiting across the top with mechanical linkage therebetween causing the vertical brush to move the horizontal brush. The invention provides auxiliary systems for application of washing and auxiliary solutions. The device is economic in construction and adapted particularly for attendantless coin activated operation.

3,579,702 SWEEPER

David R. Thompson, Denver, Colo., assignor to Rental Equipment Manufacturing Corporation, Denver, Colo.


Filed July 22, 1969, Ser. No. 843,608
Int. Cl. E01h 1/04

U.S. Cl. 15—79

8 Claims

A self-propelled, wheel mounted sweeper carrying an engine to drive the unit; a sweeper brush adapted to be

rotated to pick up debris on a lawn, ground surface or the like with the brush being directly connected to the engine to rotate it at a fixed speed with respect to the speed of rotation of the engine. This sweeper unit includes a pair of drive wheels mounted upon a shaft and operatively connected to the engine to propel the unit. This connection to the engine is through a differential carried upon a drive shaft connected to the engine and a driving shaft connected to the drive wheels. The differential is free to rotate upon these shafts and when being so rotated by the driven shaft, it does not apply any driving torque to



the driving shaft. A brake is provided to reduce the rate of rotation of this differential or to stop its rotation completely and in either case, impart driving torque to the driving shaft. The driving shaft rotates in a direction opposite to the driven shaft when so restrained by the brake. This action is advantageously used to permit the drive wheels to rotate in a forward direction to propel the sweeper, while at the same time the engine and the sweeper brush rotate in the opposite direction to effect an overthrow of debris into a basket carried behind the sweeper.

3,579,703 ARRANGEMENTS FOR CREATING DELAYED ELECTRIC CONTROL EFFECTS IN RESPONSE TO THE RECEPTION OF ELECTRIC IMPULSES


Alfred Schmermund, 62 Kornerstrasse, Gevelsberg, Westphalia, Germany

Filed Mar. 3, 1966, Ser. No. 531,550
Claims priority, application Great Britain, Mar. 12, 1965, 1,048/65

Int. Cl. H01h 47/24

U.S. Cl. 317—124

7 Claims




An arrangement for creating a delayed electric control effect in response to the reception of an electric impulse comprises a relay chain including a plurality of relays connected so that on energization of any of the relays (except for the last relay of the chain) a succeeding relay is prepared for being energized and receives a voltage to energize said succeeding relay when subsequently a switch actuator operates a timing switch, the electric impulse energizing the first relay of said relay chain, and at least one of the succeeding relays having means for creating the control effect when said one relay is energized. The relays of the relay chain may be electromagnetic relays or photoelectric relays.

3,579,704

ARTICULATED FLOOR MAT

Hans Holzl, Maulach, Germany, assignor to Kunststoffe, Hans Holzl KG, Maulach, Germany
 Filed Feb. 25, 1969, Ser. No. 801,963
 Claims priority, application Germany, Oct. 12, 1968, P 18 02 766.2
 Int. Cl. A47I 23/22; A47g 27/02
 U.S. Cl. 15—215

9 Claims




An articulated floor mat formed of hingedly interconnected links each having internal dirt chambers, two opposed marginal connecting portions and an enlarged mid portion which is wider at its base than at its upper face. The hinging links fit together in such a manner that a mat base is formed which is continuous and uninterrupted. The upper face of the mat comprises a plurality of relatively small openings to permit dirt to fall into said dirt chambers.

3,579,705

PAIL HAVING MOP WRINGING GRILL

Gordon L. Blumenschein, Box 122, Lake Villa, Ill. 60046
 Filed Jan. 23, 1969, Ser. No. 793,351
 Int. Cl. A47I 13/58
 U.S. Cl. 15—260

7 Claims




Mop pail structure in the form of a round plastic pail having a tapered wall and having a rectangular open frame pressed along the outside of the wall of the pail and forming the top of the pail into a rectangular open pail structure. The open frame cooperates with the normal pivot ears for the conventional bail of the bucket, to form a pivotal mounting for a grill-like bail. The grill-like bail is in the form of a rectangular grill having a handle on the outer side thereof, which may be used to carry the pail from place to place, and may be engaged with the top of the pail to accommodate the placing of a mop on the grill and the squeezing of the mop by the pressure of the foot. The rectangular open frame not only forms the top of the pail into a generally rectangular form, to obtain a greater area for the grill, but also strengthens the pail to the extent that heavy foot pressure may be exerted on the mop and grill without deforming or overturning the pail during a mop wringing operation.

3,579,706

VACUUM CLEANER MOTOR CONTROL

Thomas E. Hetland, St. Paul, Minn., assignor to Whirlpool Corporation
 Filed Nov. 12, 1968, Ser. No. 774,922
 Int. Cl. A47I 5/36
 U.S. Cl. 15—327

10 Claims




A vacuum cleaner having a first electric motor for a motor fan unit, a second electric motor for a floor contacting motor brush unit and a switch for controlling both of the motors that can conveniently be mounted on the handle of the hose assembly for connection to the motor brush unit. The switch control mechanism preferably comprises a first switch circuit including an electric current varying means for varying the current to the first motor and thus the degree of suction of the suction unit and a second switch circuit for energizing the motor of the motor brush unit in cleaning the floor.

3,579,707

FASTENING DEVICES FOR CARPETS

Sidney Whistler, Maidstone, England, assignor to Whistler Green Engineering Products Limited, Rushden, Northamptonshire, England
 Filed Sept. 19, 1968, Ser. No. 760,752
 Claims priority, application Great Britain, Sept. 21, 1967, 43,083/67
 Int. Cl. A47g 27/04
 U.S. Cl. 16—8

5 Claims



A carpet fastener is formed of a length of strip material at least one of the edges of which is bent to form an upwardly-extended flange having a series of spikes which project from it and which will enter the carpet to hold the latter. Preferably both edges of the strip are bent up and carry spikes and the planes of the flanges and of the spikes are substantially parallel to each other and form acute angles with the plane of the floor on which the fastener is mounted.

3,579,708

SPRING CHECK

James O. Lee, 243 Olive, Claremont, Calif. 91711
 Filed Mar. 24, 1969, Ser. No. 809,613
 Int. Cl. E05f 3/10
 U.S. Cl. 16—52

1 Claim


A spring check comprising a hydraulic cylinder having a piston movable therein, a fastener on the cylinder for

3,579,710

TRAVERSABLE HARDWARE IN GUIDEWAY FOR SHELF OR DRAPERY USE

Rudolf E. Gartzke, Madison, Wis., assignor to Gartzke's Refrigeration, Inc., Madison, Wis.
 Continuation-in-part of applications Ser. No. 650,480, June 30, 1967, and Ser. No. 691,104, Dec. 4, 1967. This application Sept. 9, 1968, Ser. No. 766,663
 Int. Cl. A47h 15/00; E05d 13/02
 U.S. Cl. 16—93

9 Claims




A guideway and member traversable therein is shown; the member is resiliently urged into contact with the guideway to resist movement by force applied through a moment arm. The guideway is configured as a slotted box section wherein the member is urged against the inner surfaces of lip projections bounding the slot.

3,579,711

MEANS FOR ATTACHING A DETACHABLE HANDLE FOR KITCHEN UTENSIL VESSELS

André J. Nicolin, Paris, France, assignor to L'Équipement par l'Acier Inoxydable (Equipinox), Paris, France
 Filed July 3, 1969, Ser. No. 838,766
 Claims priority, application France, July 10, 1968, 158,659; Dec. 3, 1968, 176,433
 Int. Cl. A47b 45/02
 U.S. Cl. 16—114

9 Claims



A support secured to the wall of a kitchen utensil vessel and housing a hook, and an arm with a locking notch in its free end arranged opposite the hook, the hook and the locking notch engaging respectively the shoulder and abutment of a detachable handle to secure the handle to the support.

3,579,712

DOOR HINGE WITH SPACED AUTOMATIC LATCHING POSITIONS FOR SELECTIVE DEGREES OF DOOR OPENING

Cecil R. Smith, 719 Old Orchard, Excelsior Springs, Mo. 64024
 Filed Sept. 6, 1968, Ser. No. 758,002
 Int. Cl. E05d 11/08
 U.S. Cl. 16—141

2 Claims

A hinge having an externally threaded sleeve spaced in parallelism with the hinge pin and containing internally;


cylinder, the fastener consisting of a pair of pivotally connected plates having arcuate portions surrounding the spring, and a bolt and wing nut connection for clamping the plates about the spring.

3,579,709

DOOR RETURN AND CHECK MECHANISM


Charles G. Pierie, 1460 Creek Road, Huntingdon Valley, Pa. 19006
 Filed Dec. 24, 1969, Ser. No. 887,969
 Int. Cl. E05f 1/08
 U.S. Cl. 16—65

12 Claims



A door return mechanism including door checking means for slowing the rate of return as the door approaches its closed position. The return mechanism includes a coil spring which, in addition to its door return function, serves to hold the door open when the linkage is moved to an over-center position. The checking means comprises a disc-type brake, the brake surfaces of which are maintained in frictional engagement by an adjustable spring force. The brake is mounted across a parallel linkage which is arranged to provide a greater angular movement of the brake surfaces and hence a greater braking effect as the door approaches the door frame.

a plug actuating a compression spring and bearing block against a ball; the sleeve having a reduced opening to per-



mit the ball to extend outward therefrom sufficiently to engage any of several recesses of a relatively stationary plate.


3,579,713

SKEWER MEAT DEVICE

Katherine K. H. Kang and Young Ok Kang, both of
1198 Alewa Drive, Honolulu, Hawaii 96817
Filed Sept. 2, 1969, Ser. No. 854,659
Int. Cl. A47j 43/28

U.S. Cl. 17—1

4 Claims



A skewer meat device which facilitates the skewering of pieces of meat by a skewer. Pieces of meat are placed lengthwise on the middle portion of one of two grids of the device. Then the device is closed to press the pieces of meat into alternate ridges and furrows. Then a skewer is inserted into the pieces of meat through a lengthwise hole in the device. Then the device is opened and the skewered meat is removed. The process is repeated as often as necessary for other pieces of meat to be skewered.


3,579,714

GIZZARD PROCESSING DEVICE

John C. Edwards, Sr., 519 Hilltop Drive,
Raleigh, N.C. 27610
Filed Nov. 21, 1968, Ser. No. 777,649
Int. Cl. A22c 21/00

U.S. Cl. 17—11

4 Claims



In abstract, a preferred embodiment of this invention is a gizzard cleaning machine which uses a vacuum nozzle to remove dirt from split gizzards, uses a vacuum to hold the gizzards on a conveying belt and uses a vacuum to pull the stomach gut into engagement between a pair of skinning rolls.


**3,579,715
STUFFER WITH A RESILIENT CUSHIONING
MEANS FOR PISTON**

Carl Oscar Schmidt, Jr., Cincinnati, Ohio, assignor to
The Cincinnati Butchers' Supply Company, Cincinnati,
Ohio

Filed May 2, 1969, Ser. No. 821,287
Int. Cl. A22c 11/06

U.S. Cl. 17—39

9 Claims



Resilient cushioning means are interposed between the adjacent faces of the piston and the manhole cover in the bottom of a conventional sausage stuffer to prevent damage to the cover from impact of the piston thereon.

3,579,716


MEAT TENDERIZING METHOD

James R. Stouffer, Dennis R. Buege, and Wayne A. Gillis,
Ithaca, N.Y., assignors to Cornell Research Founda-
tion, Inc., Ithaca, N.Y.
Continuation-in-part of application Ser. No. 792,023,
Jan. 17, 1969. This application Feb. 24, 1969, Ser.
No. 801,483

Int. Cl. A22c 9/00

U.S. Cl. 17—45

21 Claims



A method of tenderizing a selected, intact muscle contained in the carcass of a recently slaughtered meat animal where that intact muscle is connected with a portion of the bone structure of the carcass, characterized by applying tension to that muscle in a direction so that it is extended and maintained in a stretched extended condition throughout the onset, duration and completion of rigor mortis in the carcass. The invention is particularly suitable for tenderizing the edible back, front leg, rear leg and rump portions of meat animals in general, and specifically, animals of the bovine, ovine and porcine species

(i.e. beef, lamb and pork, respectively). Following completion of rigor mortis as aforesaid and/or additional amount of time representing the usual market handling time (i.e. 3-5 days), the treated meat will exhibit improved tenderness.

3,579,717

APPARATUS FOR PELLETIZING CARBON BLACK


Ollie Middlebrooks, Houston, Tex., assignor to
Continental Carbon Company, Houston, Tex.

Filed Aug. 28, 1968, Ser. No. 755,909

Int. Cl. B29b 5/00; C09c 1/58; B29c 23/00

U.S. Cl. 18—1

11 Claims



Finely divided solid carbon black is wet pelletized introducing the carbon black and the wet pelletizing liquid into a pelletizing or pelleting apparatus for mixing, agglomerating and pelletizing the black and liquid into pellet form. The pelletizing apparatus is an elongate truncated conical housing rigidly mounted with the axis being in a substantially horizontal plane. The housing has a gradually reduced diameter between its enclosed ends, accordingly being of tapered configuration. The housing has inlet means for introduction of the black and liquid near one end, and an outlet means for the discharge of pellets at the other end. An agitator means comprising a rotatable and axially mounted member having rigidly mounted pins extending from said member to about the interior of the pelletizer housing is mounted within said housing and is connected to a drive means.


3,579,718

**APPARATUS FOR STRETCHING SHEET
MATERIAL**

Harold A. Miller, Castro Valley, William K. Nider,
Orinda, and Igor P. Zavialoff, San Francisco, Calif.,
assignors to The Sierracin Corporation, Sylmar, Calif.
Filed Oct. 17, 1968, Ser. No. 768,368
Int. Cl. B29c 17/02; D06c 3/08

U.S. Cl. 18—1

9 Claims



Apparatus for stretching sheet material having working beams arranged transversely to each other to define an enclosed area in which the sheet is placed. One of the beams is stationary to provide a fixed reference. Two of the beams are movable in a direction away from the

center of the sheet. A fourth beam is movable along its axis to follow the stretching action. A plurality of clamps are mounted on the respective beams for gripping the sheet and connecting it with the working beams. Drive means are coupled to the movable beams to move them and subject the sheet to stretching forces. The sheet is stretched in transverse directions to increase its surface area and decrease its thickness.

3,579,719


**APPARATUS AND METHOD FOR MAKING
SPHERICAL GRANULES**

Nobuharu Moriya, Harakata, Japan, assignor to Fuji
Denki Kogyo Co., Ltd., Osaka, Japan
Filed Nov. 15, 1968, Ser. No. 776,080

Int. Cl. B29b 1/02

U.S. Cl. 18—1

3 Claims



A method and apparatus for converting pasty materials into spherical granules in which extruded segments are fed into a rotating indented plate which effects a centrifugal force on the segments. The rotating segments are retained within a cylindrical wall and a plurality of vertical and horizontal blades are counter-rotated to effect an undulating rotary force on the segments, transforming them into spherical granules.

3,579,720

**APPARATUS FOR SUBDIVIDING FLUID
MASS INTO GRAINS**


Emile Plumet, Gilly, and Jean Duthoit, Marcinelle, Bel-
gium, assignors to Glaverbel, S.A., Watermael Boits-
fort, Belgium

Filed Jan. 4, 1968, Ser. No. 695,757

Int. Cl. B22d 23/08; B29c 23/00

U.S. Cl. 18—2.5

15 Claims



An apparatus for subdividing a mass of material, which may be either in liquid or pasty form, into small grains by bringing the material into contact with a rotating piece so that the mass of material will be impelled from the periphery of the piece and divided into individual pieces,

and permitting these pieces to solidify into grains as they travel through a gaseous medium, this being accomplished by submitting the particles to gaseous currents which are nonuniform along the travel paths followed by such particles.


3,579,721 APPARATUS FOR OBTAINING UNIFORM DROPLETS

Roger Max Kaltenbach, 3 Avenue Erlanger, Paris, France

Filed Oct. 18, 1968, Ser. No. 768,679
Claims priority, application Switzerland, Oct. 19, 1967, 14,648/67

Int. Cl. B29d 23/08
U.S. Cl. 18—2.7

14 Claims



The disclosure relates to a method and apparatus for forming droplets of substantially constant size from a liquid, wherein the said liquid is passed through a perforated wall, and using vibrations to divide the liquid into droplets, the said method being characterized in that the liquid issues from the perforations in the form of laminary jets; the plate is vibrated at one of the resonance frequencies thereof; the stationary wall is maintained in one of its nodal zones so that it is continuously superposed upon the laminar flow of the periodic perturbations which divide the jets into uniform droplets. Among the applications of said method, may be mentioned the manufacture of granulated chemical fertilizers (pure or mixed urea-ammonium nitrate, calcium nitrate, complex fertilizers, etc.), but the method can be used just as advantageously in all cases where it is desired that solid granulated products should be obtained by the dispersal of a liquid, or a product which can be solidified by cooling or drying liquid droplets (as in the manufacture of shot for instance).


3,579,722 APPARATUS FOR CONTINUOUS PRODUCTION OF FOAM PLASTIC SECTIONS

Wolfgang Schmidt, Cologne, Flittard, Karl-Josef Kraft, Leverkusen, and Willi Kurth, Troisdorf, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

Filed May 22, 1968, Ser. No. 731,080
Claims priority, application Germany, June 1, 1967, F 52,569

Int. Cl. B29d 27/04
U.S. Cl. 18—4

5 Claims



The continuous production of foam plastic sections is accomplished in an apparatus comprising a double con-

veyor belt assembly confined at the sides by lateral side boundary members wherein the inlet aperture between the upper and lower conveyor belts and the lateral side boundaries is closed by a sealing member which has at least one supply nozzle positioned therein.


3,579,723 EXTRUDER-MOLDER

Gaylord W. Brown, Beaverton, Mich., assignor to Koehring Company, Milwaukee, Wis.

Filed July 25, 1969, Ser. No. 844,865

Int. Cl. B29c 3/04
U.S. Cl. 18—4

9 Claims



Extruding-molding apparatus wherein a sheet of synthetic plastic is directed vertically from an extruder to a differential pressure molding assembly which has molds movable into clamped relationship with the sheet. The molds are of less width than the extruding orifice of the extruding head so that a tight seal is assured and the edges of the plastic sheet are cooled at the side edges of the molds so that they may be gripped by members downstream from the mold assembly which support the weight of the sheet and prevent its tearing off, or orientation, under its own weight.


3,579,724 APPARATUS FOR THE MANUFACTURE OF COMPOSITE STRUCTURAL ELEMENTS

Louis Toth, Easton, Conn., assignor to Anchor Enterprises Corporation, Bridgeport, Conn.

Original application May 8, 1967, Ser. No. 636,866, now Patent No. 3,517,472, dated June 30, 1970. Divided and this application Sept. 19, 1969, Ser. No. 859,426

Int. Cl. B29d 3/02, 12/00; B29c 27/00
U.S. Cl. 18—4

4 Claims



A structural element with thermal barrier means having an elongated thermal insulating plastic locking member with portions which interlock in elongated tracks formed in two elongated metal members to form a rigid unitary member.


3,579,725 MACHINE FOR PRODUCING HOLLOW ARTICLES

Bent Preben Hansen, Glostrup, Denmark, and Saul Blitz, New York, N.Y., assignors to T.W. Manufacturing Company, Inc., New York, N.Y.

Filed May 15, 1968, Ser. No. 729,224
Claims priority, application Denmark, Oct. 13, 1967, 5,080/67

Int. Cl. B29d 23/03
U.S. Cl. 18—5

3 Claims



A method of molding and subsequently blow molding plastic parts in suitable molds by retaining the parts, after molding, on cores which are subsequently moved together with the parts to a position from which they are inserted into the respective blow molds for the blow molding operation and a molding machine for performing the method according to the invention. The molding machine has moving means for moving the cores between a position in which they cooperate with the injection molding means and a position in which they cooperate with the blow molding means of the machine.


3,579,726 TEMPLATE ASSEMBLY

Herbert G. Vore and Donald E. Bardsley, Nashua, N.H., assignors to Improved Machinery Inc., Nashua, N.H.

Filed July 25, 1968, Ser. No. 747,687

Int. Cl. B29c 1/00, 23/00; B29f 1/10
U.S. Cl. 18—5

16 Claims



A template assembly for guiding the nozzle of a plastic molding apparatus which assembly has resiliently mounted sockets for engaging and locating the nozzle, for spacing the nozzle from the workpiece, for transmitting fluidized or plasticized and pressured plastic therethrough, to the workpiece, and for transmitting the force of the molding apparatus to the workpiece; a back-up plate providing a bearing surface for the workpiece, and for forming a rivet-type head of the molding plastic "slug" beneath the workpiece; and an alignment edge and stop for orienting the workpiece relative to the nozzle.


3,579,727 FOAM MOULD

Kurt Schwenk, Ernst Gallasch, and Hermann Hablitzel, Wolfsburg, Hannover, and Friedrich Jacob, Stelmke, Hannover, Germany, assignors to Volkswagenwerk A.G., Wolfsburg, Germany

Filed Dec. 4, 1968, Ser. No. 781,132
Claims priority, application Germany, Dec. 6, 1967, P 17 29 112.2

Int. Cl. B29d 12/00
U.S. Cl. 18—5P

3 Claims



A foam mould for the manufacture of the vehicle body from synthetic plastic material having a base plate with inner and outer mould halves arranged on the plate and subdivided into sections which are movable inwardly and outwardly respectively.


3,579,728 POLYMER SEPARATION

Richard K. Reid, Midwest City, and Richard O. Welty, Bartlesville, Okla., assignors to Phillips Petroleum Company

Original application July 9, 1965, Ser. No. 470,670, now Patent No. 3,506,640, dated Apr. 14, 1970. Divided and this application Dec. 5, 1969, Ser. No. 882,629

Int. Cl. B01d 11/00; B29f 3/03
U.S. Cl. 18—12

4 Claims



Means for passing a solution of a solid polymer directly from a reactor and flashing it into a vented extruder, analyzing the extrudate and controlling the reaction in response thereto.

3,579,729 APPARATUS FOR EXTRUDING NET-LIKE STRUCTURES


Theodore H. Fairbanks, West Chester, Pa., assignor to FMC Corporation, Philadelphia, Pa.

Filed May 16, 1969, Ser. No. 825,212
Int. Cl. B29f 3/01

U.S. Cl. 18—12
Apparatus in which flowable strand-forming material is extruded through recesses formed along opposing edges

10 Claims

of relatively movable plates and including means for interlacing strands formed from such streams and/or twisting




the extruded streams alternately with relative movement of the plates to provide net-like structures.

3,579,730
APPARATUS FOR MAKING A WEB HAVING INTEGRAL INTERLOCKING RIB AND GROOVE PORTIONS
Steven Ausnit, 134 E. 61st St., New York, N.Y. 10021
Original application Oct. 22, 1965, Ser. No. 500,562, now Patent No. 3,371,696, dated Mar. 5, 1968. Divided and this application Feb. 2, 1968, Ser. No. 702,586
Int. Cl. B29f 3/04

U.S. Cl. 18—12

10 Claims




An apparatus for making reclosable bags having a first extruder channel for extruding a first thermoplastic substance and having a series of minor extrusion channels for extruding a second thermoplastic substance such that interlocking rib and groove elements of a flexible reclosable container may be formed separately, yet integrally with the film forming the closure strips or walls of the container.

3,579,731
EXTRUSION HEAD
Beresford B. Cooper, Mystic, Conn., assignor to The Entwistle Company
Filed Jan. 21, 1969, Ser. No. 792,337
Int. Cl. B29f 3/04

U.S. Cl. 18—13

3 Claims




A cross head for plastic material having a guide tube with flow compensating means affixed thereto and which may be readily disassembled for cleaning.

3,579,732
DRY LUBRICANT COATING OF EXTRUDED TUBING
Earl E. Heinzelman, Lancaster, Pa., assignor to Armstrong Cork Company, Lancaster, Pa.
Filed Jan. 23, 1969, Ser. No. 793,488
Int. Cl. B05b 13/06; B29d 23/04

U.S. Cl. 18—14

2 Claims




A dry lubricant is applied to the interior surface of an extruded tubing to assist in the placement of the tubing on piping. As the tubing is emerging from the extruder, mica powder is sprayed on the inside of the tubing. The mica powder is placed on the inside of the tubing by a rotating and reciprocating drive which reciprocates to force the powder into the interior of the tube and rotates to keep the mica powder in a nonpacked state. Air may also be supplied to the interior of the tubing to eliminate any vacuum which may be formed during the extrusion of the tube.

3,579,733
APPARATUS FOR VARIABLE PARISON FORMING
Walter H. West, Bay City, Mich., assignor to The Dow Chemical Company, Midland, Mich.
Division of application Ser. No. 615,032, Feb. 9, 1967, which is a continuation of application Ser. No. 288,863, June 17, 1963. This application Feb. 5, 1969, Ser. No. 813,358
Int. Cl. B29d 23/04

U.S. Cl. 18—14

2 Claims



This invention relates to apparatus for controlling the diameter and thickness of an extruded plastic melt. More particularly, this invention relates to the control of parison diameter by rotation of one extruding die member in relation to another.


3,579,734
FLOAT-OPERATED LEVEL CONTROL
Maharaj K. Mehta, Cardiff, Wales, assignor to P. Leiner & Sons (Encapsulations) Limited, Treforest, Glamorgan-shire, Wales
Filed May 27, 1968, Ser. No. 732,201
Claims priority, application Great Britain, July 18, 1967, 32,919/67
Int. Cl. B29d 7/02

U.S. Cl. 18—15

4 Claims

A spreader box for containing gelatine to be cast into ribbons or sheets on a casting drum including a float-

operated valve consisting of a hollow cylindrical rotary valve member and a cylindrical float parallel to the rotary axis of the valve member and connected thereto so that angular movement of the float about said axis is transmitted to the valve member. The valve member has an




aperture in its side wall which cooperates with the end of a stationary flow passage to limit the flow of gelatine into the spreader box. The float is rotatable manually beyond a position above the rotary axis of the valve member to close the valve.

3,579,735
APPARATUS FOR BALANCING PRESSURE APPLIED TO FILM-FORMING MATERIAL IN THE DEPOSITION THEREOF ONTO A CASTING SURFACE
Peter J. Metz, Jr., Castro Valley, Calif., assignor to Crown Zellerbach Corporation, San Francisco, Calif.
Original application July 31, 1967, Ser. No. 657,094, now Patent No. 3,520,964, dated July 21, 1970. Divided and this application Oct. 2, 1969, Ser. No. 871,373
Int. Cl. B29d 7/02, 7/10

U.S. Cl. 18—15R

5 Claims




In the extrusion of film-forming material from an extrusion device wherein a vacuum is applied to the trailing

face of an unsupported section continuously deposited onto a continuously moving casting surface, the pressure applied to such unsupported section is substantially balanced to cause substantially even deposit on the casting surface by concentrating application of suction by independent duct openings at the respective ends of the extrusion device to withdraw outside air which can enter behind the trailing face of said section adjacent said ends.

3,579,736
TIRE VULCANISING PRESS
Walter Balle, Dornigheim, and Gunter Pommer, Frankfurt am Main, Germany, assignors to Leonhard Herbert Maschinenfabrik, Bergen-Enkheim, Germany
Filed May 15, 1969, Ser. No. 824,879
Claims priority, application Germany, May 17, 1968, P 17 78 616.2
Int. Cl. B29h 5/02

U.S. Cl. 18—17

7 Claims



A tire vulcanising press includes a heating bag, an upper part having an upper mould half and a lower part having a lower mould half, an assembly on the lower part including an outer or ejection cylinder, an inner bag guiding cylinder within the outer cylinder, it being arranged that the bag when folded fits into the annular space between the cylinders and that the two cylinders are axially displaceable, a driving system for driving the outer cylinder axially whereby the inner cylinder is moved axially by the frictional force between the outer cylinder, the bag and the inner cylinder so that the bag is introduced into a tire, and a locking device for locking the inner cylinder in its raised position.


3,579,737

BRIM CURLING APPARATUS

Reinhold Gerber, Rolling Meadows; James Edward Kerrigan, Arlington Heights, and Harry Ray Hawley, Lombard, Ill., assignors to American Can Company, New York, N.Y.
Filed Oct. 15, 1968, Ser. No. 767,752
Int. Cl. B29c 17/02

U.S. Cl. 18-19

6 Claims



In forming a curled turned-in lip about the open mouth of a flexible-walled, thermoplastic container, a plurality of threaded rollers engage the brim of the containers so that the faces of the thread progressively turn in the brim as the container is advanced longitudinally of the rollers. The threaded rollers are arranged to bias the brim between the faces of the threads to facilitate formation of the turned-in lip as the rollers are rotated.


3,579,738

APPARATUS FOR CASTING AND THERMALLY CURING PLASTIC SHEETS

John O. Beattie, 57 Crawford Terrace, Riverside, Conn.
Continuation-in-part of application Ser. No. 604,242, Dec. 23, 1966, now abandoned. This application Nov. 8, 1969, Ser. No. 874,702
Int. Cl. B29c 5/00; B29d 7/02

U.S. Cl. 18-26

8 Claims



An apparatus for casting a plurality of plastic sheets is disclosed. It is comprised of an elevated support track having one or more temperature control cells suspended from it, the cells being enclosed chambers with inlet and outlet ports for the passage of U-shape fluid and at least one sidewall which is suitable as a mold surface of a plastic casting zone. A second mold surface is independently suspended from the elevated support track and is positioned in facing relationship with the first surface, a resilient sealing gasket between the

two mold surfaces serving as an edge enclosure for a casting zone. A port in the gasket is provided for feeding casting fluid such as methyl methacrylate. Casting is carried out by applying a pressure to the exterior of the two mold surfaces thereby sealing them against the gasket, filling the casting zone, and effecting polymerization and cure by passing heated water through the temperature control cell.

A liquid plastic feed system is mounted on the frame above the casting zones and includes a plurality of charge vessels connected to a common vacuum producing source and to a common source of liquid plastic, and manifolded to one another at their lower ends to equalize the plastic charge in each vessel. Each vessel is connected via tube to one of the casting zones.

3,579,739

APPARATUS FOR FORMING MOULDING COMPONENTS


James Edwin Henry Cosier, Northolt Park, Middlesex, England, assignor to Her Majesty's Postmaster General, London, England

Filed May 24, 1967, Ser. No. 659,247
Claims priority, application Great Britain, May 25, 1966, 23370/66

Int. Cl. B29f 1/00

U.S. Cl. 18-30

4 Claims



A method of and apparatus for sealing together certain component parts of a submarine cable repeater housing. The casing of the housing is closed by a bulkhead which is sealed to the casing by injection moulding polythene round cooperating surfaces on both casing and bulkhead. The apparatus comprises a moulding machine having several moulding cylinders each with a piston and having at least one injection nozzle.

3,579,740


MECHANISM FOR CLOSING AND OPENING INJECTION MOLDS

Herbert Rees, Toronto, Canada, assignor to Husky Manufacturing and Tool Works Ltd., Toronto, Ontario, Canada
Filed Aug. 21, 1968, Ser. No. 754,181

Int. Cl. B29f 1/00

U.S. Cl. 18-30

12 Claims



The movable platen of an injection molding machine is rigid with a nonrotatable lead screw whose rear end, remote

from this platen, is engaged by a rotatable drive nut at a location beyond the tie rods on which the platen slides. The machine frame, supporting the fixed platen with reference to which the movable platen is displaceable, carries a motor which can be reversibly operated to turn the nut in either direction for respectively advancing and retracting the movable platen; a cylinder at the rear of the frame carries an axially movable piston which, upon a stopping of the motor in the mold-closed position, is brought to bear under hydraulic pressure against the nut to clamp the mold between the platens against the tie bars anchored to the frame.

3,579,741


MACHINE AND CLAMP FORCE CONTROL SYSTEM THEREFOR

William H. Schwartz, University Heights, Ohio, assignor to Lester Engineering Company, Cleveland, Ohio
Filed Nov. 4, 1968, Ser. No. 773,237

Int. Cl. B29f 1/06

U.S. Cl. 18-30

18 Claims



A machine such as a diecasting or injection molding machine having a frame with a bed and movable die plate supporting relatively movable molds or dies, such molds or dies being closed by a clamp cylinder to obtain a clamping tonnage, die height adjustment which is operative to control the relative position of the relatively movable dies or molds, and a control system which measures the force or tonnage exerted by the clamp and compares the measured tonnage against a preset or predetermined tonnage which then automatically energizes the die height adjustment mechanism so that the clamp tonnage will be substantially the same and correct for each cycle of operation of the machine and will not vary due to mold growth or shrinkage as temperatures change.

3,579,742

CLAMPING MECHANISM FOR MOLDING MACHINE


Vincent H. Muttart, 902 Rockaway Drive, Placentia, Calif.

Filed Dec. 5, 1968, Ser. No. 781,499

Int. Cl. B29f 1/00

U.S. Cl. 18-30

9 Claims



In a molding machine, a pair of toggle mechanisms, each of which includes a pair of toggle links connected between a moveable platen and a reciprocating piston. The toggle joint

3,579,743

APPARATUS FOR MAKING STATORS FOR ROTARY ELECTRIC SWITCHES


Mogens W. Bang, Ridgway, Pa., assignor to Stackpole Carbon Company, St. Marys, Pa.

Division of Ser. No. 698,015, Jan. 15, 1968, Pat. No. 3,538,602, filed June 30, 1970, Ser. No. 51,153

Int. Cl. B29d 3/00

U.S. Cl. 18-36

8 Claims



A plurality of wires are fed radially inward toward a common central point and then are stopped a predetermined distance from it. Then a rigid ring of insulating material, concentric with the same point, is molded around the wires near their inner ends, after which the wires are severed a short distance from the outside of the ring. The short lengths of wire left embedded in the ring project from the inside to form electric contact pins, and project from the outside to form electric terminals. The severing of the long wires may be done by lifting the mold, in which the wires are embedded in the insulating ring, to cut the wires where they emerge from wire-guiding means around the mold.

3,579,744

APPARATUS FOR SEPARATING FIBERS


William C. Menzies, Jr., Charlotte, N.C., assignor to Atlantic Wool Combs Co., Charlotte, N.C.

Continuation-in-part of application Ser. No. 472,974, July 19, 1965, now abandoned. This application Nov. 14, 1967, Ser. No. 687,415

Int. Cl. D01b 3/00

U.S. Cl. 19-97.5

1 Claim



The invention relates to apparatus for separating a specialty fiber such as cashmere from its natural guard hair. The organization employs an air baffle and rotating comb and brush cylinders to create an air flow about the comb cylinder which transports the desired "down" fibers to a collecting chamber, but which rejects the undesirable guard hair.


3,579,745

FLAG FOOTBALL BELT DEVICE

Porter C. Wilson, 320 E. Elvira, Tuscon, Ariz.
 Filed Mar. 24, 1969, Ser. No. 809,890
 Int. Cl. A44b 21/00, 17/00

U.S. Cl. 24-73

5 Claims



An improved belt mounted separable holder for displaying the flags used in playing flag football and other flag-tag games. The belt anchored portion of a male and female coupling, used to form the separable holder, is swivelly attached to the belt so as to allow free motion of the flag in any direction thereby improving the motion of the flag and then adding an element of unpredictability to play.

3,579,746

TIE-DOWN CLIP

James Marik, Tallmadge, Ohio, assignor to Marik Spring Inc., Summit, Ohio
 Filed Feb. 20, 1969, Ser. No. 801,111
 Int. Cl. F16g 11/14, 45/00

U.S. Cl. 24-131

3 Claims



A tiedown clip comprising a substantially J-shaped metal member having a closed loop at its upper end is provided and is adapted to receive a pair of sections of a resilient rope in the closed loop of the metal member to secure the rope rapidly and snugly to the metal member, which metal member is normally formed from a metal wire and has all portions thereof lying in a common plane.

3,579,747

STRIP FASTENERS

Edwin L. Hawley, Sittingbourne, Kent, England, assignor to E.P.S. (Research & Development) Limited, Sittingbourne, Kent, England

Filed Jan. 21, 1969, Ser. No. 792,491

Claims priority, application Great Britain, Feb. 1, 1968, 5273/68


Int. Cl. A44b 19/14

U.S. Cl. 24-201

5 Claims

In a slide fastener wherein a barbed rib of a male strip is arranged to interlock with a barbed jaw of a female strip, the

jaw of the female strip is closed by the slider by means of a locking strut which is hinged to the female strip over one of



the barbed fingers which defines the jaw, the locking strut being firmly engageable by a recess in the one barbed finger.


3,579,748

SLIDE FASTENER DEVICE AND METHOD OF MAKING THE SAME

Walter V. Chery, Meadville, Pa., assignor to Textron Inc.
 Filed Aug. 22, 1969, Ser. No. 852,331
 Int. Cl. A44b 19/10, 19/32; D05b 3/12

U.S. Cl. 24-205.1

11 Claims



A slide fastener device having a filamentary stringer made of plastic material constructed with a series of head portions interconnected with a series of heel portions by spaced leg elements, is attached to a carrier tape by securing threads which include one set of threads passing through one portion of the tape and with a second set of threads passing through another portion of the tape.


3,579,749

ZIPPER SAFETY FASTENER

Elmer Holman, 1005 Hill St., Dallas, Oreg. 97338
 Filed Oct. 28, 1969, Ser. No. 871,920
 Int. Cl. A44b 19/30

U.S. Cl. 24-205.14

5 Claims



A zipper safety fastener including a toggle mounted pivotally on the slider of the zipper and a spring-type catch operatively associated with the slider and toggle and releasably engaged with the interlocking fastener elements of the zipper to automatically retain the slider in adjusted position when the toggle or handle on the slider is released.

3,579,750

LOCK FOR SAFETY BELTS


Erich Carbon, Fallersleben, and Wolfgang Wagner, Weyhausen, Germany, assignors to Volkswagen Aktiengesellschaft, Wolfsburg, Germany

Filed Oct. 10, 1969, Ser. No. 865,452

Claims priority, application Germany, Oct. 15, 1968, P 18 03 151.1

Int. Cl. A44b 11/26

U.S. Cl. 24-230



The invention relates to a lock member for safety belts having a locking link and a spring in the member with the spring composed of two portions of which one end abuts a release actuator and the other end abuts the end of the belt.

3,579,751

CLIPS USEFUL IN THE MEDICAL FIELD

Lucien Julienne Arthur Jonckheere, 88 The Gardens, Bedford, Middlesex, England


Filed Apr. 15, 1969, Ser. No. 816,291

Claims priority, application Great Britain, May 30, 1968, 26012/68

Int. Cl. A44b 21/00; A61b 17/08

U.S. Cl. 24-252

1 Claim



Spring clip of nontoxic plastic material for medical use consisting of an integral one-piece body having two similar rigid arms, one superimposed over the other, which are joined together intermediately by a resilient waist piece acting as a fulcrum, the adjacent pair of arm ends at one extremity being mating gripping jaws, the other pair of ends being usable for finger operation for pressing together so as to open the jaws, and a spring interposed between the finger-pressing ends to force the jaw ends together, when the finger pressure is relaxed, into a mutual gripping position.

3,579,752


AUTOMATIC ROTARY SLIPS

Cicero C. Brown, 5429 Sturbridge Drive, Houston, Tex.
 Filed Apr. 9, 1970, Ser. No. 26,841

Int. Cl. F16l 7/00

U.S. Cl. 24-263

7 Claims



Automatic slips mountable in a rotary table for gripping and releasing drill pipe or casing being run through the table

and for rotating the pipe when desired. The mechanism includes a slip spider which is raised and lowered by fluid pressure operated pistons and is held in a balanced position by telescopic supports mounted on the rotary table housing in a symmetrical arrangement about the pistons.

3,579,753

PIPE-GRIPPING APPARATUS


Dale H. Pryor, Houston, Tex., assignor to Youngstown Sheet and Tube Company, Youngstown, Ohio

Filed Mar. 9, 1970, Ser. No. 17,778

Int. Cl. F16l 7/00

U.S. Cl. 24-263

7 Claims



This invention relates to a new type of pipe-gripping apparatus wherein pipe-engaging slips are carried by linkage elements which are supported at one end by shoes engaging a slip bowl and at the other end by a floating ring, resulting in the frictional forces between the shoes and the bowl being less than those between the slips and the pipe so that the slips are able to retain the pipe by friction alone and without the aid of knurls, teeth, serrations, or the like on the slips.

3,579,754


COMPRESSION BAND

Hans Oetiker, Oberdorfstrasse 21, Horgen, Switzerland
 Filed Apr. 1, 1969, Ser. No. 811,784

Int. Cl. B65d 63/00

U.S. Cl. 24-279

26 Claims



A compression band which includes a perforated band adapted to be tightened over a hoselike object by means of a closure mechanism consisting of two closure parts movable relative to one another; one end of the band is looped around one of the two closure parts while the other end of the band is threaded through openings formed in the two closure parts and is held in position by the engagement of hooks at the other closure part engaging in the perforation apertures, the closure mechanism is then tightened by means of a machine screw or the like.

3,579,755

SLINGER APPARATUS FOR LINING THE INTERIOR OF A VESSEL


Gerhard Blankenhorn, Rheinstrasse 20, Friedrichstal, and Gunter Muller, Turmbergstrasse 16, Karlsruhe-Durlach, Germany

Filed May 20, 1968, Ser. No. 730,286
Claims priority, application Germany, Oct. 4, 1967,
P1,583,528.6

Int. Cl. B28b 1/00

U.S. Cl. 25—1R

19 Claims



Slinger apparatus for lining the interior of a vessel. The apparatus includes a support for holding the vessel, an applicator head for slinging the material with which the vessel is to be lined, and a support for holding the applicator head, either the vessel support or the applicator head support providing a means for movably supporting the vessel or applicator head, respectively. The apparatus also includes means for producing relative motion between the applicator head and the vessel and a means having a configuration matching that of the contour of the mouth of the vessel for guiding the applicator head, during the relative movement between the applicator head and the vessel, along a path matching that of the contour of the vessel.

3,579,756

DEVICE TO FACILITATE REMOVAL OF ASBESTOS-CEMENT PIPES FROM THE MANDREL IN A PLANT FOR MANUFACTURE OF SUCH PIPES


Leonid Mikhailovich Gurevich, ulitsa Gor Kogo, 5, kv. 4, Moscow, U.S.S.R.

Filed May 1, 1969, Ser. No. 820,912

Int. Cl. B28b 21/42

U.S. Cl. 25—30

2 Claims



A device to facilitate removal of asbestos-cement pipes from a mandrel in a plant for manufacture of such pipes, and comprising two single-arm levers hinged to each other and to an upright. The free end of the lever which is not connected to the upright is provided with a needle, which is essentially a double-arm lever, and a roller whose axes of turning and rotation are respectively aligned one with the other. The inoperative end of the needle is connected to the joint connect-

ing the levers with the upright through the intermediary of springs. Hinged to said upright is a power cylinder capable of turning in the plane of movement of the levers. The cylinder is hinged to a lever abutting the upright, and imparts motion to the levers. The levers moving, the roller rolls over a cam which is essentially a mandrel on which said asbestos-cement pipe is formed.

3,579,757

FLY PRESS FOR PRODUCING CERAMIC TILES

Aurelio Mingotti, Imola Bologna, Italy, assignor to S.A.C.M.I. Cooperativa Meccanici Imola Soc. Coop. A.R.L., Imola Bologna, Italy


Filed Nov. 12, 1968, Ser. No. 774,866

Claims priority, application Italy, Nov. 18, 1967, 22856A/67

Int. Cl. B28b 3/02

U.S. Cl. 25—45

6 Claims



A fly press for manufacturing ceramic tiles or like articles is disclosed, which comprises an additional flywheel capable of being engaged, at the proper instant, by the usual flywheel solid with the pressing screw, so as to effect the moulding, deaerating and final compression stages as single step process.

3,579,758

EXPLOSIVE TENDON-TENSIONING MEANS


James L. Regan, Hayward, Calif. (409 Dunkel St., Fairbanks, Alaska 99701)

Filed Aug. 22, 1969, Ser. No. 852,217

Int. Cl. E04g 21/12

U.S. Cl. 25—118T

10 Claims



A concrete embedded barrel member in which a reinforcing tendon extends with explosive means inside the barrel for exerting a substantial tensioning force on the tendon through a cushioning member of soft metal and a plurality of apertured discs engaging the interior of the barrel so that the discs serve to retain the tendon in permanent tensioned condition.

3,579,759

TRELLIS UNIT FOR MAKING OF BEAMS

Giorgio Zuccolo, Via Arrigoni, Peraga di Vigonza, Padova, Italy

Filed Dec. 11, 1967, Ser. No. 689,631

Claims priority, application Italy, Dec. 13, 1966, 66,631/66

Int. Cl. E04g 9/10

U.S. Cl. 25—131.6

3 Claims



A construction trellis unit for the formation and setting up of beams and the like in cement conglomerate, consists of a two-sided reticular framework movable longitudinally or transversely to its axis by bearing rollers. A metal form with movable walls can be slid into the framework for effecting the castings of conglomerate. When completed, the castings are lowered directly upon bridge bearings by hoists movable upon the upper booms of the trellis and prior to the withdrawal of the movable form.

3,579,760

TEXTURIZING APPARATUS


Ralph A. Caneer; William J. Anderson; Bert B. Morgan, Asheville, and Jerry M. Goodman, Swannanoa, N.C., assignors to Northrop Carolina, Inc., Swannanoa, N.C.

Filed June 16, 1969, Ser. No. 833,602

Int. Cl. D02g 1/12

U.S. Cl. 28—1.7

4 Claims



Method and apparatus useful in the textile art for maintaining the uniformity of a filament in a crimping facility in which the facility functions to continuously monitor the level of crimped material in a crimping chamber, thereby assuring a constant and predetermined level therein.

3,579,761

APPARATUS FOR YARN REMOVAL

Harvey R. Plonsker, Greenville; Reuben F. Vaughn, Seneca, S.C.; Felix C. Lang, Port Washington, Wis.; Christoph W. Aurich, Clemson, and Philip A. Bowie, Pendleton, S.C., assignors to Maremont Corporation, Chicago, Ill.

Filed Oct. 16, 1969, Ser. No. 866,909


Int. Cl. D03d 45/58

U.S. Cl. 28—19

10 Claims

Yarn underwindings upon the spindles of a textile-spinning frame or like machine are removed by a portable apparatus releasably connected to the machine for guided movement longitudinally of its spindle rail. Yarn is dislodged from the

spindles by a rotatable disclike member mounted for lateral and axial tilting movement, and having a smooth annular surface engageable with the rotating spindles. Dislodged yarn is withdrawn by suction into a collection chamber of the ap-



paratus, from which it can later be readily removed. The apparatus operates with equal efficiency and effectiveness when moved in either longitudinal direction, and can be quickly connected to and disconnected from a spinning frame.

3,579,762

COLD DRAWING OF NYLON FILAMENTS


Donald I. MacKey, 33 Forest Road, and Terance Donald MacKey, R. R. 4, Galt, Ontario, Canada

Filed Dec. 27, 1968, Ser. No. 787,333

Int. Cl. D02j 1/22

U.S. Cl. 28—71.3

7 Claims



An apparatus for cold-draw stretching at least one tow of nylon filaments including a frame, first and second pairs of spaced rollers mounted for rotation transversely of said frame, said second pair of rollers being spaced from said first pair of rollers in a direction longitudinally of said frame, said rollers defining a path in which a tow of said yarn passes around said first pair of rollers in a plurality of loops and around said second pair of rollers in a plurality of loops, said loops being spaced axially along said rollers such that said tow passes to said first pair of rollers and leaves said second pair of rollers adjacent one end thereof and passes between said pair of rollers adjacent the other end thereof, said second pair of rollers being adapted to rotate at a peripheral speed higher than said first pair of rollers whereby said tow is stretched during its passage between said pairs of rollers, the axes of rotation of the rollers in each of said first and second pairs of rollers being horizontally inclined such that the point of intersection of the axes of rotation of said first pair of rollers is axially remote from the point of intersection of the axes of rotation of said second pair of rollers whereby the tow may be passed to said first and second pair of rollers at a point remote from said point of axial intersection and removed therefrom at a point adjacent said point of axial intersection with reduced bunching of said loops around said first and second pairs of rollers.

3,579,763

METHOD OF NON-WOVEN CLOTH MANUFACTURE
 Francois Noel Sommer, Paris, France, assignor to Sommer S. A., Paris, France


Filed Apr. 24, 1967, Ser. No. 633,073

Claims priority, application France, Apr. 27, 1966, 59,330

Int. Cl. D04h 18/00

U.S. Cl. 28—72.2

14 Claims



A process for napped surface nonwoven web of interturned continuous filaments. Stretchable filaments are employed as starting material to form a web and various of the filaments are then forced through the web surface and stretched in the process to form loops on one surface of the web.

3,579,764

PROCESS FOR PRODUCING TEXTURED YARNS
 William H. Kleffer, Summit, N.J., assignor to Indian Head Inc., New York, N.Y.


Continuation-in-part of application Ser. No. 758,677, Sept. 10, 1968, now abandoned. This application Feb. 26, 1969,

Ser. No. 802,640

Int. Cl. D02g 1/20

U.S. Cl. 28—72.11

10 Claims



A process for producing textured yarns from synthetic fiber yarns including the steps of knitting the yarn, heating the knit yarn to stabilize it prior to dyeing, dyeing the yarn, unraveling the dyed yarn and texturing the dyed yarn. The resulting yarns exhibit combinations of bulk and uniformity which are superior to those previously available commercially.

3,579,765

METHOD OF OPENING CRIMPED YARN
 Jannes Eshuis, Klingelbeekseweg 11, and Horatius Tjebbes, Oude Kraan 24-1a, Arnhem, Netherlands assignors to Algemeene kunstzijde unie N.V. Arnhem, Netherlands

Filed Aug. 6, 1968, Ser. No. 750,596

Claims priority, application Netherlands, Aug. 12, 1967, 6,711,131


Int. Cl. D04b 19/00

U.S. Cl. 28—72.16

10 Claims

A process for opening a crimped synthetic yarn made up of a number of filaments which comprises passing the crimped yarn through a relaxation zone in which the yarn is not under

any significant tension and immediately thereafter applying a frictional force to the yarn to displace the filaments relative



to one another and thereby open the yarn. An apparatus for carrying out this process is also disclosed.

3,579,766

PROCESS FOR MANUFACTURING PRESS-FREE, RESINATED, DOUBLE-FACE, INTERLOCK KNIT FABRIC


Emanuel M. Feinberg, 64 Genesee Blvd., Atlantic Beach, N.Y.

Filed Aug. 31, 1967, Ser. No. 664,675

Int. Cl. D06c 27/00

U.S. Cl. 28—74

3 Claims



This invention relates to the process for providing a permanently shaped fabric. A resin resistant yarn and resin absorbing yarn are knitted to provide a fabric having the resin absorbing yarns on the back and the resin resistant yarns on the face. A thermosetting resin is applied to the absorbing yarns and the fabric is partially cured, thereby providing the garment fabric with the resin absorbing yarns along the inside surface thereof.

3,579,767

METHOD FOR FORMING FLASH HOLES IN CARTRIDGE CASES


Otto E. Reider, Etobicoke, Ontario, Canada, assignor to General Impact Extrusions (Manufacturing) Ltd., Toronto, Ontario, Canada

Filed June 2, 1969, Ser. No. 829,280

Int. Cl. B23p 15/22

U.S. Cl. 29—1.3

6 Claims



A method of forming flash holes in cartridge shells wherein the holes are impact punched rather than drilled. It has been

discovered that these holes can be impact punched where the shell metal has a difference of at least 5 percent between its yield strength and its ultimate tensile strength, with an attendant substantial saving in time and cost over drilling.

3,579,768

METHOD OF FABRICATING CATHODE RAY TUBE SCREEN

Glen A. Burdick, Waterloo, N.Y., assignor to Sylvania Electric Products Inc.


Division of Ser. No. 605,783, Dec. 29, 1966, Pat. No. 3,509,802,

filed Aug. 19, 1969, Ser. No. 851,381

Int. Cl. H01j 9/18

U.S. Cl. 29—25.13

5 Claims



A method for providing a tri-dot patterned color cathode ray tube screen having phosphor patterns of improved symmetry. The photofabricating method involves discretely refracting light for exposing a sensitized screen panel through an associated apertured mask by utilizing a predeterminedly positioned optical system. A portion of the exposure light radiation is refracted therein by a modified plano-concave lens having at least one modified plano chordal portion whereby improved exposure is provided for one or more specific peripheral quadrantal portions of the screen to effect substantially improved equilateral phosphor dot pattern formation thereon.

3,579,769

CAPACITORS AND PRODUCTION THEREOF

Akira Matsushita, 1088-312, Kitakase, Kawasaki-shi, Kanagawa-ken, Japan

Filed Feb. 19, 1969, Ser. No. 800,506


Claims priority, application Japan, Feb. 19, 1968, Feb. 19,

1968, 43/10241;43/12483

Int. Cl. H01g 13/00

U.S. Cl. 29—25.42

11 Claims



Capacitors, each having a high-molecular dielectric layer electrode-positioned on at least one of two opposite electrodes thereof and having various excellent properties such as heat-resistivity, moisture-resistivity, high breakdown voltage, and high insulating resistivity, are adaptable to mass-production, miniaturization, and large capacitances. The high-molecular dielectric layer is manufactured by the method of passing a direct current on a current obtained by superposition of a direct current and an alternating current or a rectified current between a cathode and the electrode to be deposited thereon with said dielectric layer, said electrode

being used as an anode, in an electrodeposition bath consisting of a resin emulsion or resin water solution containing as its main ingredient an anionic poly-high-molecular electrolytes or in an electrode positioning bath consisting of said emulsion or water solution in which a dielectric material consisting of powdery fine crystal particles or corpuscles is mixed, thereby to deposit a high-molecular dielectric layer on said anodic electrode, and subjecting said electrodeposited layer, successively, to after-treatments such as washing, drying, and polishing treatments.

3,579,770

METHOD OF FORMING TUBULAR MICA CAPACITOR
 William H. O'Mara, New Bedford, and Owen J. Wood, Mattapoisett, Mass., assignors to Aerovox Corporation, New Bedford, Mass.


Division of Ser. No. 743,787, July 10, 1968, Pat. No. 3,522,493,

filed Sept. 29, 1969, Ser. No. 861,824

Int. Cl. H01g 13/00

U.S. Cl. 29—25.42

2 Claims



This disclosure relates to the art of electric capacitors of the mica type and more particularly relates to a method of forming a capacitor comprising a rigid tubular member of insulating material in which is positioned a substantially rectangular mica capacitor section that is retained in fixed position with terminal leads protruding from opposed ends of the tubular member by filling the latter with a thermosetting resin.

3,579,771

MACHINE FOR AUTOMATICALLY ASSEMBLING ARMATURE CORES AND COMMUTATORS THEREFOR

Thomas L. Schuette, Osseo; Melvin J. Straub, Minnetonka; Pierre Dumas, and Peter F. Aurich, Minneapolis, Minn., assignors to Possis Machine Corporation, Minneapolis, Minn.

Filed Feb. 20, 1969, Ser. No. 801,084


Int. Cl. H02k 15/02

U.S. Cl. 29—33

13 Claims

Feeding mechanism successively brings armature cores and commutators therefor to an assembly station where they are held in coaxial endwise spaced relationship and where rotation imparting mechanism brings each armature core and commutator pair into correct angular relationship. A ram then pushes the commutator axially towards the armature core with the terminal tangs on the commutator facing the core, and presses it onto the shaft thereof, moving the commutator through a die which straightens tangs that may be askew. The tank straightening die has a round hole that slideably accepts the commutator, and longitudinally extending circumferentially spaced parallel grooves that slideably accommodate the tangs. When the commutator reaches proper position on the armature shaft, and while still in the die, a tang-shaping member having circumferentially spaced

parallel fingers, one for each tang, telescopes over the commutator, each finger moving along one of the grooves to en-



gage under the tang therein and lift it into contact with the bottom of the groove.

3,579,772


MANUFACTURE OF INTERIORLY COATED TUBING
Brian C. Coad, Fairfield, near Bromsgrove, Warc., England, assignor to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 605,837, Dec. 29, 1966, Pat. No. 3,457,626, filed Jan. 27, 1969, Ser. No. 852,125

Int. Cl. B23p 3/12; B21c 27/08

U.S. Cl. 29—33

5 Claims



This disclosure relates to continuously drawing a precleaned strip of metal past heating and evaporating means for the coating material and deforming the strip to bring the margins of the strip together to form an open-seamed, open-ended tube. The margins of the open seam are welded after the strip has been folded. The evaporated coating material enters the tube through its open end where it is being formed from strip to tube. As a result the inside surface of the tube has evaporated material condensed upon it in solid form. The condensate covers all of the inside surface, including also the welded seam. The inside-coated tube is cooled and passed through an appropriate finishing die or the like.

3,579,773

HANDLE ATTACHING APPARATUS AND METHOD
Milton Zysman, Toronto, Ontario, Canada, assignor to Convex Limited, Nassau, Bahamas

Filed Feb. 26, 1969, Ser. No. 802,358


Int. Cl. B68g 7/12

U.S. Cl. 29—91

11 Claims

Apparatus for simultaneously attaching ventilator handles to mattress border and puncturing the border in registration with the handle vents. The apparatus comprises a bed over which border material is movable, a press movable downwardly towards the bed for attaching successive handles to the upper surface of the border and a pair of rotary cutters

below the bed movable upwardly through passageways therein to puncture the border in registration with the handle



vents at approximately the same time as they are attached as aforesaid.

3,579,774


METHOD OF CONSTRUCTING A MATTRESS
Robert N. Shreve, Roseville, Minn., assignor to Conwed Corporation, St. Paul, Minn.

Filed Mar. 18, 1969, Ser. No. 808,232

Int. Cl. B68g 7/00

U.S. Cl. 29—91.1

14 Claims



An extruded plastic net, having heavy strands in one direction and lighter strands in the other direction, is used to replace the two previous elements i.e. (1) a wire rope spring-bridging unit, and (2) a cotton scrim in a mattress construction thus permitting sewing of the spring-bridging unit to the cushioning material.

3,579,775

TOOL SURFACE TEMPERATURE MEASURING APPARATUS

Gerald J. Carlson, Scotia, N.Y., assignor to General Electric Company


Division of Ser. No. 632,621, Apr. 21, 1967, Pat. No. 3,486,378,

filed Apr. 3, 1969, Ser. No. 830,168

Int. Cl. B26d 1/00

U.S. Cl. 29—96

4 Claims



Opto-electronic apparatus for hot spot temperature measurement by indirect viewing of a heated surface of a cutting tool through a small diameter hole therein which terminates close to the hot spot surface. A first end of a light guide within the hole views the radiant energy emitted from the heated end surface of the hole during a cutting operation and the remote second end directs the radiant energy to a ratio pyrometer comprising a rotating disc, two infrared filters and a first photocell. The photocell output is a series of electrical

pulses of first and second amplitude representing the intensity of the radiant energy in the two spectral bands determined by the filters. Opto-electronic circuitry separates the pulses into two separate pulse trains comprising the first and second amplitude pulses, detects, and compares the peak amplitude of the pulses to obtain a ratio of pulse amplitudes. The hot spot temperature is determined from a known correlation of temperature versus pulse amplitude ratio.

3,579,776

TOOLHOLDER ASSEMBLIES


Wlajko Mihic, Tegnergaven 9, 802 28 Gavle, Sweden

Filed Nov. 18, 1968, Ser. No. 776,443

Int. Cl. B26d 1/00

U.S. Cl. 29—96

4 Claims



A toolholder assembly incorporates a body which at one end has a recess for receiving an indexable cutting insert. A bore for a two-armed lever which is pivotally connected to the body extends from the recess in the toolholder body, and one end of the lever cooperates with the cutting insert, while the other end of the lever cooperates with a piston which is movable in the body. The piston is under the action of a pressure medium which is contained in a hollow space in the body and acted upon by a pressure actuating member movable into and out of the space.

3,579,777

HELICAL END MILL


Vistor Milewski, Troy, Mich., assignor to The Valeron Corporation

Filed Mar. 10, 1969, Ser. No. 805,442

Int. Cl. B26d 1/12

U.S. Cl. 29—105

8 Claims



3,579,778

UNITARY BI-STABLE CODE WHEEL FOR MECHANICAL CONVEYORS AND SORTING APPARATUS

Peter T. DiPaolo, Jr., Ridley Park, and Joseph C. Carbine, Wyncote, Pa., assignors to Burroughs Corporation, Detroit, Mich.

Filed Aug. 13, 1969, Ser. No. 851,774


Int. Cl. B60b 5/02

U.S. Cl. 29—110

10 Claims

This disclosure relates to a code wheel for a conveyor system such as employed in a sorting apparatus for letters

and other articles. The wheel is of unitary construction and has a rim that can be translated from one to the other of two stable positions. The connecting support for the rim may be either a plurality of pivotally mounted spokes or an approximately conical web where the length of the respective spokes



or of the conical element is greater than the difference between the rim radius and the hub radius. During translation of the rim from one stable position to the other, distortion occurs either in the rim of the spoked embodiment or in the web. Material resistance to this distortion serves to urge the rim to its nearest stable position.

3,579,779

TOP ROLLER FOR TEXTILE DRAFTING DEVICES


Marcel Stein, 560 Riverside Drive, New York, N.Y.

Filed Aug. 14, 1968, Ser. No. 752,656

Int. Cl. D01h 5/74

U.S. Cl. 29—113

8 Claims



A top roller for a textile drafting device, having an interior annular space is rotatably mounted on a fixed shaft. The space is in fluid communication with an axial duct in the shaft through which a compressed medium can be passed to inflate the roller. Compressed air supplied to a second axial duct in the shaft blows off dirt that may accumulate on the end of the roller.

3,579,780

METHOD OF MAKING A BEARING HAVING A FULL COMPLEMENT OF BALLS


Richard J. Matt, Simsbury, and Ronald E. Restelli, Cromwell, Conn., assignors to Textron Incorporated, Providence, R.I.

Filed Sept. 9, 1968, Ser. No. 758,358

Int. Cl. B23p 11/00, 11/02; B23b 19/00

U.S. Cl. 29—148.4

16 Claims



A bearing having a full complement of balls is described wherein an outer ring is made of a wrought heat-resistant alloy and provided with a depth-of-track to ball-diameter

ratio of at least 1 : 10. Cobalt base and nickel base alloys or a combination thereof have been found to be particularly useful with this type of bearing. A method of making the bearing includes preassembling a bearing structure by placing a thermally expanded conical outer ring over an assembly comprising an inner ring and a full complement of balls within the inner ring face. Subsequently, the conical outer ring is compressed to bring a tapered portion thereof towards the balls and produce the desired depth-of-track to ball-diameter ratio with final radial clearance and fit. A particular selection of component parameters is described for the manufacture of the device.

3,579,781

SLEEVED ROLL AND METHOD OF MAKING THE SAME
Toshio Yaegashi, Katsuta, Japan, assignor to Hitachi, Ltd., Tokyo-To, Japan


Filed July 24, 1968, Ser. No. 747,153

Claims priority, application Japan, July 27, 1967, 43/64862

Int. Cl. B23p 11/00, 11/02

U.S. Cl. 29—148.4

20 Claims



A sleeved roll which comprises a sleeve and an arbor fitted in the sleeve by means of shrink fitting wherein the arbor and the sleeve are, respectively, provided at the opposed end portions thereof with annular grooves into which metal rings having good welding characteristics are tightly fitted, respectively, in such a manner that the metal rings in the sleeve combine with those in the arbor to form a U-shaped annular ring when they are firmly secured to each other by means of deposit metal which has a smooth surface, the radial section of the grooves and the united metal rings having such a contour as to withstand slip between the sleeve and the arbor.

3,579,782

METHOD OF MANUFACTURING ROLLING BEARING COMPONENTS


Stig Lennart Hallerback, Blodboksgatan 12, Vastra Frolunda, Sweden

Filed Aug. 2, 1968, Ser. No. 749,783

Int. Cl. B23p 11/00, 17/00

U.S. Cl. 29—148.4

6 Claims



A method of manufacturing rolling bearing components consisting of the steps of forming a tubular member by bending up a flat sheet and joining the sheet at confronting edges, separating the tubular member into a plurality of annular rings, and simultaneously rolling and bending at least one flange at one end of said annular ring at grooved portions formed by rolling.

3,579,783

METHOD FOR MANUFACTURING WHEELS

Edward J. Hayes, Ann Arbor, and Stephen E. Crick, Livonia, Mich., assignors to Kelsey-Hayes Company, Romulus, Mich.

Filed July 5, 1968, Ser. No. 742,590


Int. Cl. B21d 53/26; B21k 1/28, 1/42

U.S. Cl. 29—159

26 Claims

A method and apparatus for manufacturing vehicle wheels wherein a structural adhesive material is applied to the rim

bead seat section of the wheel rim while simultaneously rotating the wheel about its axis of rotation, the material being distributed over the bead seat section by means of a suitable tool disposed adjacent the wheel and adapted to en-



gage the material upon rotation of the wheel, whereby the material forms a surface of constant radius from the rotational axis of the wheel and upon which an associated vehicle tire is adapted to be mounted.

3,579,784

ENGINE BLOCK STRIPPING APPARATUS


George R. Klempner, and Sam Rosenberg, Louisville, Ky., assignors to Foundry Suppliers, Inc., Louisville, Ky.

Filed Feb. 24, 1969, Ser. No. 801,668

Int. Cl. B23p 19/00; B26f 3/00

U.S. Cl. 29—200

3 Claims



Disclosed is an apparatus in which movable elements engage opposite ends of, and rigidly hold, the crankshaft of a junked engine block, subsequently, an additional movable portion of the apparatus applies a force to one end of the engine block parallel to and above the crankshaft to fracture the engine block portions carrying the main crankshaft bearings. Finally, the movable elements holding the crankshaft are dropped or lowered to extract and separate the crankshaft, rods and pistons from the engine block.

3,579,785

APPARATUS FOR UNITING A PLURALITY OF FIRST OBJECTS WITH A CORRESPONDING NUMBER OF SECOND OBJECTS

Lars Ingvar Hellborg, Lund, Sweden, assignor to Sobrefina S.A., Fribourg, Switzerland

Filed Apr. 8, 1969, Ser. No. 814,249

Claims priority, application Sweden, May 12, 1966, 6504/66


Int. Cl. B23p 19/00, 19/04

U.S. Cl. 29—200

4 Claims

Apparatus for uniting a plurality of container bodies with outer sleeves comprises a pair of parallel spaced rotationally mounted members having pockets which receive the sleeves. The pocketed members are rotated in a step-by-step manner so as to simultaneously advance the sleeves into a spacial

configuration wherein the centers of the sleeves are located in longitudinal spaced relation along two parallel straight lines. A rotationally mounted multisided turret also rotatable in a step-by-step manner includes along each side thereof a like number of holders having the same spacial configuration



as that of the sleeves, plungers transfer the sleeves from their pockets to the holders, and the container bodies arranged with the same spacial configuration as the sleeves are then inserted in the sleeves after the sleeves have been transferred to the holders on the turret.

3,579,786

HOSE STRAIGHTENING DEVICE


Theodore C. Johnson, 6011 Briardall Lane, Solon, Ohio

Filed Apr. 23, 1969, Ser. No. 818,749

Int. Cl. B23p 19/00, 19/02

U.S. Cl. 29—200

8 Claims



A device for holding straight a short length of normally curved semirigid hose while metal fittings of an external diameter greater than the internal diameter of the hose are forced into the ends of the hose. The device consists of a pair of clamping members somewhat shorter than the hose arranged to clamp the central portions of the hose straight, in combination with a pair of supporting fingers at opposite ends of the clamping members. The fingers are biased in a direction to straighten the ends of the hose projecting beyond the clamping members, the fingers being yieldingly supported to allow expansion of the hose ends as the fittings are forced thereto.

3,579,787

MACHINE FOR APPLYING LUGS OR THE LIKE TO BOBBINS OR THE LIKE

Joseph J. Cervinka, 428 E. Crescent, Elmhurst, Ill., and Marvin E. Hetzel, 177 Michaux Road, Riverside, Ill.

Filed Sept. 17, 1968, Ser. No. 760,267


Int. Cl. H05k 13/04; B23p 19/04

U.S. Cl. 29—203

9 Claims

Machine for applying lugs or the like to plastic bobbins or the like when the bobbins include post means and the lugs include hole means matable with the post means and collapsible means coacting with the hole means to decrease the size of the hole means and lock the lug to the bobbin, and the machine includes means feeding lugs into alignment with

bobbins at a lug-applying station, means severing lugs from a strip form of lugs, means applying the lugs to the bobbins,



and means collapsing the lug collapsible means to secure the lug to the bobbin.

3,579,788


APPARATUS FOR COMPRESSING LAMINATED CORES
Harold L. Fritzsche, Fort Wayne, Ind., assignor to General Electric Company

Filed Feb. 27, 1969, Ser. No. 802,861

Int. Cl. H02k 15/00

U.S. Cl. 29—205

6 Claims



An assembly for compressing laminated articles, such as stator cores for dynamoelectric machines. There is provided an assembly including a doughnut-shaped electromagnet and a tapered nonmagnetic plug mounted within the electromagnet. A core, previously coated with a material intermixed with magnetic particles, is slipped over the plug and moved by suitable mechanical means toward the center of the electromagnet while the electromagnet is energized. The resultant magnetic field attracts the core to the center of the electromagnet. Also mounted in the assembly are spring-biased clamps which cooperate with adjustable stop members for clamping the core therebetween, thereby mechanically compressing the laminations of the core together. The magnetic field produced by the electromagnet magnetically compresses the laminations and also draws the coating material intermixed with magnetic particles to selected surfaces of the core, thereby forming an increased thickness of material on those surfaces.

3,579,789


MACHINE FOR THE MANUFACTURE OF RELAY COIL BOBBINS

Lucien Ernest Grente, and Roger Leveque, Boulogne, France, assignors to International Standard Electric Corporation, New York, N.Y.

Filed Aug. 1, 1969, Ser. No. 847,535
Int. Cl. H01r 43/00

U.S. Cl. 29—203D

9 Claims



A machine is provided for manufacturing electromagnetic relays. Bare relay bobbins are introduced into the machine and these bobbins are then equipped with magnetic cores and connection prongs. Thereafter, the finished relays are ejected from the machine.

3,579,790


DEVICES AND ACCESSORIES FOR ELECTRIC ARMORED CABLES AND STUFFING TUBES

Paul M. D'Amico, 2709 S. 12th St., Philadelphia, Pa. Division of Ser. No. 502,048, Oct. 22, 1965, abandoned, filed Oct. 31, 1958, Ser. No. 772,179

Int. Cl. H05k 13/00

U.S. Cl. 29—203

3 Claims



Devices and accessories in the form of tool means and associated equipment for the installing and servicing, including emergencywise preparation, of electric armored cables, in the form of a circular T-wrench, a safety shield with accurate cutter grooves in a combined ring-cutter, which limits the depth in cutting the outer interstices of shielding or layers of insulation if required, and said devices also may be affixed and grouped into a piece unit for storing and ever-ready utility.

3,579,791

COIL DEVELOPING APPARATUS

Richard B. Arnold, Fort Wayne, Ind., assignor to General Electric Company

Continuation-in-part of application Ser. No. 748,406, July 29, 1968. This application Dec. 11, 1969, Ser. No. 884,145

Int. Cl. H02k 15/00


U.S. Cl. 29—205

13 Claims

Apparatus for developing one or more coil groups of electrically conductive wire. The apparatus includes a coil turn-

forming assembly having a jump form portion and a snap out form portion. The jump form portion includes a plurality of turn-gauging steps with an interruption formed at one side. The snap out form portion is supported adjacent to the interruptions on the turn-gauging steps and includes a corresponding number of snap out winding form plates, each having a fill-in winding section for spanning one of the associated interruptions on the jump form portion.

The apparatus also includes a flyer for placing wire on the coil turn-forming assembly to generate turns and a jump means for locating a turn-gauging step of the jump form portion in the path of the wire being wound by the flyer. Concurrently, as the jump means locates a turn-gauging step in the path of the wire wound by the flyer, a snap out plate is extended to place a fill-in winding section in alignment with its associated interruption of a turn-gauging step. The turn-gauging step of the jump form portion and its associated fill-in winding section cooperate to provide a form for winding or generating turns of a predetermined length for receipt in a coil group accommodating means or device. Preferably, the coil group accommodating means is comprised of spaced curved blades defining turn receiving slots. The spaced



curved blades and corresponding fill-in winding sections of the snap out plates have associated mating curved surfaces whereby, when a snap out plate is engaged with a curved blade, the entry of the turns of a coil being generated into the corresponding turn receiving slot is facilitated by the mating curved surfaces. Thus each coil is developed directly in the coil group accommodating means as the turns for the coil are generated about the coil turn-forming assembly. Also, the jump form portion and the snap out plates may be supported for movement in essentially a vertical direction, and the curved blades are supported in alignment with the snap-out plates so that the force of gravity facilitates the removal of the turns from the coil form assembly.

Additionally at least part of the jump form portion is movable relative to the snap out portion during the turn-generating operation for selectively varying the lengths of successive turns.

A coil group is developed in the coil group accommodating means by producing a plurality of serially connected wound coils of a coil group in the coil group accommodating means. Thereafter the coil group may be inserted directly from the coil group accommodating means into preselected slots of a stator core.

3,579,792

APPARATUS FOR ASSEMBLING PIECEPARTS INTO CUP-SHAPED ADAPTERS

Edward H. Craver, Clemmons, N.C., assignor to Western Electric Company, Incorporated, New York, N.Y.


Filed Sept. 30, 1969, Ser. No. 862,235
Int. Cl. B23p 19/04; B23q 7/10

U.S. Cl. 29—208

7 Claims

A loading apparatus assembles a ferrite core into a cup-shaped adapter. First the adapter is pushed to an assembly station to receive the ferrite core where it is accurately positioned by a slanted end of a pusher and a corner. The ferrite core is then pushed to the assembly station where it is held between a pusher and a spring-biased member in an elevated

position over the adapter. The cores are fed from a stack where a pronged member gently lowers the stack after a pusher has retracted. A spring-biased plunger at the assembly station pushes the ferrite core down into the adapter. A



switch on the plunger senses any failure of the ferrite core to assemble into the adapter to release an ejection mechanism to drop the unassembled ferrite core and adapter from the assembly station.

3,579,793

POWER TOOL FOR THREAD INSERTS


Charles A. Williams, Highland, Mich., and Richard E. Waller, Erie, Pa., assignors to Microdot Inc., Greenwich, Conn.

Filed Sept. 24, 1968, Ser. No. 761,979

Int. Cl. B23p 19/04

U.S. Cl. 29—240.5

11 Claims



The power tool has a shaft which engages and advances an insert into an aperture of a workpiece in one direction of rotation and screws the threaded end of the shaft from the insert in the other direction of rotation. The distance of advancement of the insert and the threaded aperture of the workpiece is controlled by a stop collar that is adjustable on the exterior of the shaft for causing cam means to interrupt the drive of the shaft when the insert has been advanced a required distance.

3,579,794

MEANS FOR SECURING COUPLINGS TO PIPE


Jonathan S. Powell, 11 W. State St., Pasadena, Calif.

Division of Ser. No. 678,932, Oct. 30, 1967, Pat. No. 3,477,750, filed Oct. 3, 1969, Ser. No. 863,511

Int. Cl. B23p 19/04

U.S. Cl. 29—237

2 Claims



A means and method of constricting a coupling having internal teeth onto a pair of abutting pipe sections; the means comprising an assembly of split rings which may be secured around a pair of abutting pipe sections and a coupling having internal teeth initially slidable on the pipe sections, at least one of the rings containing a constricting die adapted, when forced axially over the coupling, to constrict the coupling

and force the teeth into the pipe sections; a hydraulic ram being placed between a pair of rings to effect relative movement of the die and coupling and thus constrict the coupling. One embodiment involves a pair of constricting dies movable toward each other and another involving a single die and a sleeve for forcing the coupling through the die.

3,579,795

COMPONENT REMOVING TOOL


Per Aron Burman, Temple City, Calif., assignor to Burroughs Corporation, Detroit, Mich.

Filed Aug. 8, 1969, Ser. No. 848,545

Int. Cl. B23p 19/04

U.S. Cl. 29—252

17 Claims



A power augmented handtool particularly useful for removing integrated circuit components from a printed circuit board is described. The tool has a body in which a plunger is movable between an extended and a retracted position. A pair of opposed, component gripping, jaws are pivotally connected to the plunger at the nose end of the tool. When the plunger is in the retracted position, the jaws are positively cammed open. While the plunger travels toward the extended position, the jaws are resiliently biased open. When the plunger is in the extended position, the jaws are positively cammed to a closed position to grip a circuit board component. A relatively strong spring biases the plunger toward the retracted position so that when the solder holding a component to a printed circuit board is melted, the jaws draw the component away from the board. The component is released when the jaws are cammed open when the plunger reaches the retracted position. Either compressed air pressure or a mechanical arrangement may be employed for extending the plunger and jaws.

3,579,796

PULLER DEVICE FOR GENERALLY CYLINDRICAL STEM ASSEMBLIES OR VALVES


Walter A. Fillion, 705 2nd St. N.E., Minneapolis, Minn.

Filed Aug. 19, 1969, Ser. No. 851,223

Int. Cl. B23p 19/04

U.S. Cl. 29—263

5 Claims



A puller device for longitudinally extracting generally cylindrical valve assemblies and the like and which have a

slightly protruding outer end provided with a circumferential indentation. The improved device combines the use of an elongated puller shaft having means at the inner end for grasping and interlocking with said circumferential indentation, together with an annular abutment member surrounding the inner portion of the stem and having an end for abutment against the mounting of said cylindrical assembly, and a second cooperating puller nut also surrounding said stem and disposed outwardly of the first annular member and having extended threaded interconnection therewith. The combination further requires a shiftable lock device carried by the annular puller member for selective engagement with two diminished collars or grooves provided intermediately of the elongated stem. The outer annular puller element is screw threaded inwardly against the abutment member then interlocked with one of the collars of said stem and, in operation, is screwed outwardly with powerful force to pull the stem outwardly through the first abutment member.

3,579,797

TOOL FOR REMOVING CONCENTRIC KNOCKOUTS


Frank W. Pepe, 637 Prospect Drive, Lordship, Conn.

Filed Feb. 20, 1968, Ser. No. 706,899

Int. Cl. B23p 19/04

U.S. Cl. 29—267

13 Claims



A tool for removing concentric ring knockouts from electric wire junction and terminal boxes, etc., after removal of the center disc knockout. The tool has opposed groove defining gripping means set at an acute angle relative to each other which engage opposite points on the ring knockout so as to fracture the knockout by a back and forth movement of the tool until the points of connection of the ring knockout with the rest of the box fracture.

3,579,798

METHOD OF VERIFYING THE REPLACEMENT OF A DAMAGED WINDSHIELD


William P. Henderson, 1109 Crayton Road, Naples, Fla.

Filed Feb. 13, 1969, Ser. No. 799,027

Int. Cl. B23p 7/00

U.S. Cl. 29—401

12 Claims



Replacement of a damaged windshield on a motor vehicle or the like is verified by removing the damaged windshield to obtain access to an identification serial number of the vehicle located immediately adjacent the windshield and then taking an impression of the vehicle serial number before installing a new replacement windshield. The impression is taken on a

label which is then attached to a statement which is forwarded to an insurance company for payment. Verification of the type of replacement windshield installed is also obtained by removing a manufacturer's label from the replacement windshield and attaching the manufacturer's label to the label bearing the impression.

3,579,799

METHOD OF MAKING A GROOVED MOLD


Alvin J. Furstenburg, Chicago, and Edmund J. Kujawa, Wilmette, Ill., assignors to Felt Products Mfg. Co.

Division of Ser. No. 542,343, Apr. 13, 1966, Pat. No. 3,406,430, filed Apr. 10, 1968, Ser. No. 745,056

Int. Cl. B23p 17/00; B29c 1/02

U.S. Cl. 29—416

9 Claims



This invention deals with a method for producing a mold member having a plurality of helical molding grooves. Endless grooves are formed on the surface of a mold blank which is then divided along a line which intersects each endless groove twice. The divided mold blank segments are then aligned in such a way as to define a plurality of helical grooves.

3,579,800

PRODUCTION OF ELONGATED EXTRUSIONS COMPOSED OF TITANIUM BASE METAL


Robert F. Packard, Brookline, Mass., assignor to Technical Metals, Inc., Brockton, Mass.

Filed Jan. 28, 1969, Ser. No. 794,647

Int. Cl. B23p 17/00

U.S. Cl. 29—423

10 Claims



Elongated extrusions of titanium base metal are produced from billets in the form of coils of titanium base metal. In such a coil, the rolling direction of the sheet and the axis of the convolutions of the sheet are at right angles to each other. It is believed that striated roughness of the resulting extrusion is minimized because grain elongation in the rolling direction and grain elongation in the extruding (axial) direction are such that strain hardening is neutralized.

3,579,801

OPENER FOR A FILM PACK

Frank Y. Ishihara, Seattle, Wash., assignor to Leonard H.


Tall, Mercer Island, Wash., fractional part interest

Filed Apr. 1, 1968, Ser. No. 717,636

Int. Cl. B23p 19/04; B67b 7/30; B25b 27/14

U.S. Cl. 29—427

5 Claims



This invention is directed to a method and an apparatus for opening a film pack so as to easily and quickly remove the film from the film pack. It is necessary to remove the film from the film pack without damaging the film such as by scratching the undeveloped film or by tearing in two the undeveloped film or by allowing the film to become unraveled from the film pack and generally mixed. I have approached this problem from the standpoint of enlarging the opening in the film pack so that the undeveloped film can be removed from the film pack without substantially touching any of the body of the container of the film pack around the opening.

3,579,802

METHOD FOR INSULATING BOILER OR LIKE HOUSING WALL


Frank R. Gajovski, 4112 Swain Drive, Barberton, Ohio

Filed Dec. 2, 1968, Ser. No. 780,322

Int. Cl. B23p 11/00

U.S. Cl. 29—432.2

5 Claims



Method and means for securing thin-webbed metalwork on boiler or like housing wall, as for retaining insulation and/or finishing sheeting thereon. Studs may have inner ends welded to housing wall by use of a stud welder. Areas of metalwork strip impacted against reduced ends of studs to punch through web, and further impactation forms heads to retain metalwork against peripheral shoulders defined by reduced ends.

3,579,803

METHOD FOR BRINGING TWO STATIONARY GEARWHEELS INTO ENGAGEMENT WITH ONE ANOTHER ON A LAPPING OR TESTING MACHINE

Alfred Johann Lautenschlager, Zurich, Switzerland, assignor to Oerlikon-Buhle Holding AG, Zurich, Switzerland

Division of Ser. No. 612,378, Jan. 30, 1967, Pat. No. 3,403,569, filed June 13, 1968, Ser. No. 737,789


Int. Cl. B23p 19/00

U.S. Cl. 29—434

9 Claims

A method for bringing into engagement two gearwheels on a lapping or testing machine. The gearwheels are displaced towards one another until they come into mutual contact and

in the event of the tips of two teeth contacting one gearwheel is rotated through a fraction of the tooth pitch and engage-



ment of the two gearwheels is prevented until a tooth of one gearwheel is opposite a gap in the other gearwheel.

3,579,804

METHOD OF MAKING LUGGAGE CASES

Jack Slan, Toronto, Ontario, Canada, assignor to Dominion


Luggage Co. Limited

Filed Nov. 19, 1968, Ser. No. 784,510

Int. Cl. B23p 19/00, 9/00

U.S. Cl. 29—434

9 Claims



The method of obtaining an accurate interlock between opposing case sections by clamping two edge strips and a tongue strip which are to make up the confronting edges of the case sections in interfitting relation prior to bending, then bending the strips while clamped to effect matched bends and at the same time a permanent locking of the tongue strip in one of the edge strips and matched interfit with the other edge strip. A luggage case is produced by such a method of manufacture.

3,579,805

METHOD OF FORMING INTERFERENCE FITS BY HEAT TREATMENT


Howard Berdolt Kast, Fairfield, Ohio, assignor to General Electric Company

Filed July 5, 1968, Ser. No. 742,882

Int. Cl. B23p 11/02

U.S. Cl. 29—447

10 Claims



An interference fit can be provided between metal components where at least one of the components is formed of a precipitation-hardenable metal alloy which undergoes a substantially permanent dimensional change in addition to a reversible dimensional change upon heat treatment at elevated temperatures. The interference fit itself will be irreversible if both components are formed of the precipitation-hardenable alloy and reversible if only one of the components is formed of the alloy.

3,579,806

METHOD OF PRODUCING TOROIDAL BODIES FROM HARD, BRITTLE STEELS

Gerard Huberdeau, Atelier de Construction de Tarbes, France, assignor to French State represented by the Minister of Armed Forces Ministerial Delegation of Weapons, Technical Delegation of Land Weapons Manufacturing Workshops of Tarbes, Paris, France


Filed June 19, 1969, Ser. No. 834,632

Claims priority, application France, June 19, 1968, 155,597

Int. Cl. B21d 39/02

U.S. Cl. 29—463

10 Claims



A toroidal body of hard, brittle material is produced by joining two semicircular toroidal bodies in face-to-face relation, each semicircular toroidal body being formed from a ring of material by first spin forming the ring in two steps to produce a U-shape peripheral portion on the ring, thereafter machining the peripheral portion to provide uniform thickness and then heat treating the body and hot stamping the same to form semicircular portions on said peripheral portions which are separated from the remainder of the body by machining.

3,579,807

METHOD AND APPARATUS FOR PRODUCING A STREAM FEEDER


Leonard A. Matulewicz, 931 Continental Blvd., Toledo, Ohio

Filed May 29, 1968, Ser. No. 733,040

Int. Cl. B23k 31/02

U.S. Cl. 29—471.3

9 Claims



Apparatus and method for forming a feeder for flowing streams of filament-forming material such as molten glass by deforming tubular members into contoured longitudinal members and subsequently securing the longitudinal members to a plate with orifice openings in alignment with such openings.

3,579,808

TANTALUM CLAD NIOBIUM

Melvin A. Hagan, Palos Verdes Peninsula, and Roy I. Batista, Palos Verdes Estates, Calif., assignors to TRW Inc., Redondo Beach, Calif.

Filed Mar. 20, 1969, Ser. No. 809,039

Int. Cl. B235 31/02

U.S. Cl. 29—497.5

1 Claim

This invention relates to composite metal article and method for making the same wherein tantalum metal is applied to the surface of niobium metal and the two metals are diffusion bonded in a protective environment. The bonded metals may be cold worked to produce the final fabricated article.

3,579,809

METHOD OF JOINING SHEETS OF RIGID DEFORMABLE MATERIAL


Cecil R. Wolf, Rock Falls, and John P. Holland, Sterling, both of, Ill., assignors to Frantz Manufacturing Company, Sterling, Ill.

Filed Dec. 13, 1968, Ser. No. 792,194

Int. Cl. B21d 39/00; B23p 11/00

U.S. Cl. 29—509

13 Claims



A method of securing together, as by staking, superimposed strips or sheets of rigid yet deformable material, such as mild steel, having generally planar surfaces. The method includes positioning the superimposed sheets between a driven punch and the working face of a stationary anvil upon sheet-supporting members resiliently urged toward each other mounted laterally of said anvil and providing with said punch and anvil a forming space extending directly as well as laterally above, and laterally below, the anvil working face. By a single stroke of said punch, the punch causes a flow of the material of the strips into the forming space to form therein telescoped hollow bosses, or rivets, with a lower wall portion of the inner boss expanded laterally into interlocking engagement with the corresponding laterally confined wall portion of the outer boss and with the material of the lower transverse end of the outer boss yieldably restrained by said resiliently urged members to a predetermined degree of lateral expansion yet free to flow into the portion of the forming space laterally below said anvil working face to provide downwardly extending lateral flanges.

The punch is preferably formed with a pair of opposed lower downwardly converging surfaces and with an intermediate pair of parallel surfaces which together define a generally rectangular striking end, the face of which is arcuate. With this configuration, the striking end of the punch forms hollow bosses that interlock in one plane including the common axis of the bosses, but that are noninterlocking in a plane normal to the first and also including the common axis.

3,579,810

METHOD OF MAKING CAPILLARY ASSEMBLIES FOR OXYGENATORS AND THE LIKE


George Mon, Silver Spring, Md., assignor to the United States of America as represented by the Secretary of the Army

Filed June 13, 1969, Ser. No. 833,056

Int. Cl. B23p 17/00; 25/00

U.S. Cl. 29—527.1

8 Claims



An inexpensive and rapid method of assembling capillary units and the like is disclosed. Commercially available capil-

lary tubing is first wound around two end pins spaced apart a predetermined distance slightly greater than the length of the capillary strands in the completed unit. Each end pin is then dipped into an epoxy potting compound and caused to harden. The hardened ends are thereafter cut in appropriate places so as to expose the capillary tubes. A suitable outer housing, having appropriate conduits for the transfer of blood and oxygen to the unit, may then be provided to the assembled capillaries.

3,579,811

METHOD OF MAKING PASSIVE ELECTRONIC COMPONENTS INCLUDING LAMINATING TERMINALS TO SUBSTATE

Masao Matsuo, Takarazuka-shi, and Hiroshi Tomiwa, Osaka, Japan, assignors to Matsuo Electric Company, Limited, Toyonaka-shi, Osaka-fu, Japan


Filed Dec. 11, 1969, Ser. No. 884,226

Claims priority, application Japan, Dec. 21, 1968, 43/93890

Int. Cl. H01g 13/00

U.S. Cl. 29—570

3 Claims



A method of making a chip-shaped electronic component by forming a laminated structure consisting of a metal plate and a substrate adhesively secured to one side thereof. Etching the metal plate to form a plurality of raised terminals and then forming a plurality of elongated conductive members having electronic elements formed on the outer ends thereof, which elements are then electrically and mechanically secured to selected terminals while adjoining portions of said conductive members are secured to other terminals of each set. Enclosing the formed structure within a molded resin and then stripping the substrate to expose one surface of the sets of terminals. Thereafter the structure is cut to separate the components one from the others. An improved electronic component is provided having the terminals on one face thereof which thereby facilitates attachment to a printed circuit board or other electronic circuit structure.

3,579,812

MACHINE TOOL


Stanley A. Pfister, Wilmington, Ohio, assignor to Cincinnati Milacron Inc., Cincinnati, Ohio

Filed Sept. 20, 1968, Ser. No. 761,235

Int. Cl. B23q 3/157

U.S. Cl. 29—568

4 Claims



This invention relates to a machine tool and, more particularly, to apparatus for performing a machining operation,

which apparatus is provided with a multiple-tool storage rack and means for moving selected tools from that rack into position on a rotatable spindle. The rack is provided with a plurality of identical sockets to carry the tools from the rack to an interchange position and return them to the rack.

3,579,813

METHOD OF MAKING ELECTRONIC COMPONENTS ON COMBLIKE METAL FINGERS AND SEVERING THE FINGERS

Hiroshi Tomiwa, Osaka, Japan, assignor to Matsuo Electric Company, Limited, Toyonaka-shi, Osaka-fu, Japan


Filed Dec. 11, 1969, Ser. No. 884,257

Claims priority, application Japan, Dec. 23, 1968, 43/94395

Int. Cl. H01g 13/00

U.S. Cl. 29—570

3 Claims



A method of making a chip-shaped electronic component by etching a metal plate to form a plurality of raised terminals, forming a comblike metal plate having electronic elements formed on the outer ends of the projections and then electrically and mechanically securing the electronic elements to the terminals and then separating the individual chip-shaped components to form a resultant structure having downwardly extending terminals which may be readily soldered or otherwise attached to a printed circuit board or other electronic circuit structure.

3,579,814

METHOD FOR FABRICATING A SEMICONDUCTOR DEVICE HAVING AN EPITAXIALLY GROWN REGION

Frederick H. Dill, Jr., Putnam Valley, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.


Division of Ser. No. 446,780, Mar. 31, 1965, Pat. No. 3,398,335.

Filed Mar. 18, 1968, Ser. No. 734,185

Int. Cl. B01j 17/00; H01L 5/00


U.S. Cl. 29—578

9 Claims



Disclosed is a method of making minute semiconductor devices wherein superposed apertured insulating, metal contact and insulating layers are applied to the semiconductor base layer and semiconductor material is provided within the aperture but spaced from the metal contact layer by the second insulating layer.

3,579,815
PROCESS FOR WAFER FABRICATION OF HIGH BLOCKING VOLTAGE SILICON ELEMENTS
 Finis E. Gentry, Skaneateles, N.Y., assignor to General Electric Company
 Filed Aug. 20, 1969, Ser. No. 851,596
 Int. Cl. B01j 17/00; H01l 5/00
 U.S. Cl. 29—580 17 Claims



A silicon wafer provided with at least one voltage-blocking junction is strengthened by epitaxially depositing silicon onto one major surface. The wafer is then etched to form grooved surfaces intersecting the junction. A passivation layer is deposited and fast diffusing impurities are gettered and removed. The wafer is broken into a plurality of discrete, separately useable silicon elements.

3,579,816
METHOD OF PRODUCING SEMICONDUCTOR DEVICES
 Robert C. Ingraham, Topsfield, and Hubert J. Ramsey, Burlington, Mass., assignors to Sylvania Electric Products Inc.
 Filed Dec. 23, 1968, Ser. No. 786,208
 Int. Cl. H01l 7/00; B01j 17/00
 U.S. Cl. 29—583 8 Claims




Method of producing stacked semiconductor rectifiers by placing a plurality of wafers of semiconductor material in a jig alternately with thin wire spacers. The jig is immersed in molten solder, the spacers are removed from between the wafers, and the jig is removed from the solder. The wafers are pressed together while the solder cools, and the solidified assembly is sawed through each wafer to form a plurality of stacks of dice.

3,579,817
COVER FOR COPLANAR WALLS OF AN OPEN TOP CIRCUIT PACKAGE
 Martin A. Boyle, Woodcliff Lake, N.J., assignor to Alpha Metals, Inc., Jersey City, N.J.
 Filed May 21, 1969, Ser. No. 826,600
 Int. Cl. H01l 1/02 11 Claims


A cover for hermetically sealing the open end of a circuit package in which a solder border is applied to the marginal

areas of the cover, and a dielectric dress is applied within the border; the dielectric dress is sufficiently thick to fit into the



open end of a circuit package and to position the lid in exact registration with the circuit package.

3,579,818
METHOD AND APPARATUS FOR FORMING SHAPED INSULATORS AND FOR DEVELOPING COILS OF A MAGNETIC CORE
 Richard B. Arnold, and Dallas F. Smith, Fort Wayne, Ind., assignors to General Electric Company
 Filed Mar. 11, 1969, Ser. No. 806,057
 Int. Cl. H02k 15/00 20 Claims




Method and apparatus for developing shaped insulators of different axial lengths and coil turns into coil groups in preselected slots of a magnetic core. The insulators are automatically formed into the desired lengths from a continuous strip of insulative material at an insulator-forming station by apparatus including a feeding mechanism, slotted magazine, cutter, and linkage having a movable pivot operative to effect a change in the length of material advanced into predetermined slots of the magazine. The magazine is mounted to telescope with an outer surface of an insulator and turn-accommodating mechanism or assembly into which the insulators are transferred. Turns are formed into coil groups in the assembly through the outer surface at a turn-forming station, and thereafter the coil groups and insulators are distributed into the preselected slots of the core from the assembly. Where two or more winding phases are to be distributed, the core may be conveniently mounted in a holding device carried by a conveyor which transports the core through a first phase-winding development, where the insulators and one winding are placed in the core, a winding pressback station where the winding is transformed into the desired configuration, and into a second phase-winding development where additional insulators and a winding are added to the core.

3,579,819
METHOD OF MAKING A RESISTOR
 Arthur L. Rozema, Elkhart, Ind.; Lynn J. Brady, Edwardsburg, Mich., and Wayne A. Barden, Elkhart, Ind., assignors to CTS Corporation, Elkhart, Ind.
 Filed Mar. 24, 1969, Ser. No. 809,655
 Int. Cl. H01k 17/00 6 Claims


High-voltage circuit arrangement includes a load connected to a power supply of at least 20,000 volts, and a single

discrete high-voltage electrical resistor connected to the power supply and load. The high-voltage resistor comprises a spiral resistive path supported on a ceramic substrate which provides a uniform and continuous heat dissipation path between the ends of the resistor. A heat-dissipating mounting member forms an electrical termination for the resistor, rapidly transfers heat away from the substrate, and includes a substrate alignment surface and seat in close proximity to a surface of the substrate. A threaded portion of the heat-dissipating member is useful for mounting the resistor on a supporting surface and insulative means including an insulative jacket surrounds the substrate. High-voltage corona-inhibiting means include an insulative body that extends one-half



inch beyond an end of the resistive path and embeds a lead wire connected to the resistive path. The resistive path is a cermet-film-type material having a resistivity of 5 megohms per square, a voltage coefficient of less than 400 parts per million per volt per square, and a voltage withstanding ability of 3,000 volts per inch of resistive path. The resistive path itself comprises an intersticed mass of inert particles and a conductive phase forming an interstitial mass within the intersticed mass. The method includes the steps of positioning the mounting member and substrate at a work station, compressively centering the substrate on the mounting member with a movable platen, controlling the transfer of heat relative to the mounting member, and soldering the mounting member to the substrate.

3,579,820
METHOD OF MAKING GALVANOMAGNETIC RESISTOR UTILIZING GRID FOR SHORT-CIRCUITING HALL VOLTAGE
 Paul Hini, Erlangen, Germany, assignor to Aktiengesellschaft Siemens, Berlin, Germany
 Division of Ser. No. 665,928, Setp. 6, 1967, Pat. No. 3,490,070.
 Filed June 24, 1969, Ser. No. 862,547
 Int. Cl. H01c 17/00 7 Claims




A metal grid is placed on the surface of a semiconductor layer for short-circuiting Hall voltage in the semiconductor layer. The semiconductor layer is placed on a carrier plate with the grid interposed between the semiconductor layer and the carrier plate.

3,579,821
METHOD OF MAKING CONFORMAL BLOCKS FOR EVAPORATIVELY COOLING CIRCUIT ASSEMBLIES
 Albert G. Kurisu, Anaheim, Calif.
 Assignor to the United States of America as represented by the Secretary of Navy.
 Filed Aug. 21, 1969, Ser. No. 851,866
 Int. Cl. H05k 3/28 2 Claims


A conformal block for evaporatively cooled modular electronic packages is disclosed. The conformal block provides a predetermined convective path for a coolant and controls the

mixture ratio of the two-phase (liquid and vapor) flow to provide an optimized vapor/liquid mixture at the outlet port. This result is achieved by confining the components within a vertical flow duct and sizing the liquid inlet passage at the bottom of the block as a function of the heat load. The outlet



port is located above the normal liquid level to prevent further liquid entrainment. The fixed location of the outlet provides a relatively consistent flow path to the condenser under adverse inclination angles in respect to gravity direction.

3,579,822
METHOD AND BLANK FOR MAKING POTENTIOMETER CONTACT SPRINGS
 Frank L. Dieterich, 3727 S. Robertson Blvd., Culver City, Calif.
 Filed May 13, 1968, Ser. No. 728,683
 Int. Cl. H01r 9/00 4 Claims



A method of manufacturing miniature potentiometer contact springs by winding a substantial length coil of a single layer of fine, heat-treatable precious metal alloy wire on a generally cylindrical form, masking spaced strips longitudinally of the wire coil, silver plating the wire coil between the masked strips, removing the strips and cutting the strip-plated wire band from the mandrel as a sheet, cutting the wire sheet in the middle of the plated and unplated strips to produce control strip blanks having short free wires at one end and joined plated wires at the other end. The free ends of the wires in the blank are then formed into radiused points of contact, and the blank heat-treated to develop hardness, wear resistance and spring characteristics in the wire fingers. This blank may itself form an article of commerce with the customer (or the original manufacturer) slicing the strip blank into the desired contact widths, forming the plating bonded portion, if desired, and attaching it to a support. The wire may be wound on a solid mandrel and the coil plated only on its outer surface or on a slotted mandrel and the coil plated on both inside and outside surfaces at the slots.


3,579,823

APPARATUS AND METHOD FOR APPLYING INDEXING STRIPS TO CABLE PAIR GROUPS

Tillman J. Gressitt, Lutherville, Md., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.
Filed Sept. 12, 1969, Ser. No. 857,503
Int. Cl. H01r 6/00

U.S. Cl. 29—630

10 Claims



This application describes apparatus for placing thin complaint strips at intervals crosswise over a group of advancing twisted wire pairs. The two wires of each pair thread through separate threadways in a lockable rotor. As the twisted pairs advance in unison, the respective rotors turn at rates differing with the various pair twist lengths. The rotors are locked at different times, but each in a position that conforms all threadways in a single plane. The strips are then applied downstream of the rotors, where by then the wires lie flat. Thereafter, the rotors are unlocked.

3,579,824

ELECTRIC DRY SHAVER


Masamiki Matsumoto; Motohisa Nishino, and Yoshimasa Tanaka, Kadoma-shi, Osaka, Japan, assignors to Matsushita Denko Kabushiki Kaisha, Osaka, Japan
Filed May 26, 1969, Ser. No. 827,847

Claims priority, application Japan, May 31, 1968, Nov. 30, 1968, Dec. 6, 1968, Dec. 13, 1968, Feb. 26, 1969, 43/45,514; 43/104,450; 43/106,847; 43/109,426; 44/14,496

Int. Cl. B26b 19/02

U.S. Cl. 30—43.92

12 Claims



An electric dry shaver having a shaving blade part, which comprises an outer cutter blade provided with side cutting surfaces respectively continuous to its upper cutting surface, at least a pair of inner cutter blades reciprocally driven inside and relative to the outer cutter blade in its longitudinal direction and provided respectively with a side blade part to oppose to one of the side cutting surfaces of outer cutter blade and with an upper blade part to be opposed to a part of the upper cutting surface of outer cutter blade adjacent said side cutting surface, and a biasing means to urge the inner cutter blades to resiliently engage inner surfaces of the outer cutter blade. Said biasing means is provided with a means to

distribute its biasing force uniformly to each of the inner cutter blades and, specifically to those inner blades having the side blade part, in a diagonal direction with respect to axial line of the biasing means toward respective corner edges between the upper cutting surface and side cutting surfaces of outer cutter blade, so that such inner cutter blades are always pressed against the upper and side surfaces of outer blade simultaneously.

3,579,825


ELECTRICIAN'S TOOL FOR LONGITUDINALLY AND CIRCUMFERENTIALLY CUTTING INSULATION ON WIRE

Alfred H. Powell, 19321 108th Ave. N.E., Bothell, Wash.
Filed Nov. 27, 1968, Ser. No. 779,557

Int. Cl. B26b 27/00

U.S. Cl. 30—90.7

3 Claims



This tool has a blade carrying assembly supporting a blade so it can be adjusted for depth of cut and can be set in one position to slit insulation lengthwise on a wire and in another position to cut the insulation around the wire. The blade has graduation marks on it so the depth of cut it is set to make can be read directly. Two wire-guiding members at opposite sides of the blade and the blade-carrying assembly are adjustable toward and away from each other to receive and hold wires of different sizes.

3,579,826

TOOL FOR SIMULTANEOUSLY BEVELING MATING PIPES


Eldon W. Morain, Tulsa, Okla., assignor to Continental Industries, Inc., Tulsa, Okla.

Filed July 9, 1969, Ser. No. 840,201

Int. Cl. B23d 21/06

U.S. Cl. 30—93

1 Claim



This invention relates to a method for permanently joining the ends of two lengths of plastic pipe and includes a beveling tool and heating tool for use in preparing the pipes for the joining.

3,579,827

HEDGE TRIMMER


Robert D. Grahm, Hinsdale, Ill., assignor to Sunbeam Corporation, Chicago, Ill.

Filed Aug. 1, 1966, Ser. No. 569,490

Int. Cl. B25f 3/00

U.S. Cl. 30—144

4 Claims



An electric hedge trimmer having an elongated split housing with the front portion enlarged to house the motor and the rear portion providing a handle. The motor drives a toothed cutter blade with a saw blade attached to the end. A transversely disposed loop-shaped handle is provided and a level gauge is secured on top of the housing.

3,579,828


HEAVY-DUTY METAL SNIPS

Andrew M. Hexdall, c/o A. M. Hexdall Company, Morris, Ill.
Filed June 30, 1969, Ser. No. 837,623

Int. Cl. B26b 13/00

U.S. Cl. 30—251

15 Claims



A pair of heavy-duty metal snips is disclosed in which the operative blade is moved by an eccentric pin coupled to the operative handle by a crank arm and link. The other blade is rigid with a flat mounting plate and the link is designed to nest within cooperative portions of the handle. The crank arm, link and eccentric are arranged so that the mechanical advantage transferred to the operative blade increases as it moves toward the closed position.

3,579,829

PERICORTICAL DENTAL IMPLANT AND INSERTER THEREFOR


Arnold Sampson, Pittsburgh, Pa., assignor to The Sampson Corporation, Pittsburgh, Pa.

Filed Jan. 22, 1970, Ser. No. 4,904

Int. Cl. A61c 13/00

U.S. Cl. 32—10

13 Claims



A pericortical implant for the retention of various dental prosthetic replacements in the form of a two-part clamp

adapted to be placed about either the mandible or maxilla of the patient and having a mounting post for reception of the dental prosthesis. An inserter device including a force-applying screw for moving one clamp half with respect to the other and having extendible arms for temporarily retaining the clamp halves in position is provided for rapid application of the clamp.

3,579,830

BONE IMPLANT

Joseph Morel, 14 Villers Bocage, France


Filed Oct. 1, 1969, Ser. No. 862,728

Claims priority, application France, Oct. 1, 1968, Sept. 19, 1969, 168337; 69-31944

Int. Cl. A61c 13/00

U.S. Cl. 32—10

7 Claims



A bone prothesis implant as disclosed is formed by a metal rod which terminates in a screw in the form of a gimlet of conical pitch with rounded edges. This screw, intended to be introduced into the bone, is characterized in that each of its threads, except that of the point, appears in elevation as a truncated cone, of which the bases are inclined relatively to the axis of the screw. The end of the screw preferably ends in a point, so as to be able easily to penetrate into the bone.

3,579,831

BONE IMPLANT


Irving J. Stevens, 130 Margaret Blvd., Merrick, N.Y., and Jerry Alexander, 64 Hedgerow Lane, Jericho, N.Y.

Filed Mar. 5, 1969, Ser. No. 804,625

Int. Cl. A61c 13/00

U.S. Cl. 32—10

9 Claims



A bone implant such as a dental implant to be received in a jaw bone. The bone implant includes a screw which has a pair of opposed end regions, one of which is threaded for the purpose of screwing into bone and the other of which is provided with a means for fastening any other desired structure to the screw. For example, in the case of a dental implant this fastening means can be used to fasten a crown to the screw. In addition to the screw the bone implant of the invention includes at least one stabilizing pin operatively connected with

the screw to stabilize the latter in the bone, so that as a result of the stabilizing, the screw will be reliably retained in the bone.


3,579,832

ANATOMY RELATING DEVICE FOR DENTISTS

Hugh Cooper, Jr., 425 E. Washington St., Ann Arbor, Mich.
Filed Oct. 2, 1969, Ser. No. 863,288
Int. Cl. A61c 9/00

U.S. Cl. 32-17

10 Claims



A flat sheet of expanded polystyrene is creased to provide a hinge between an insert to be placed between a patient's maxillary and mandibular teeth and a two-part flap, the outer part being swung upwardly before the patient's face so that his interpupillary line and midsagittal plane can be marked thereon. With the sheet flattened, the midsagittal plane location is also marked on the inner flap. The insert takes a permanent impression of the patient's cusps when the patient bites thereon. When the insert is transferred to a laboratory model, the flaps are turned upwardly to facilitate transferring the information marked thereon directly to the model.

3,579,833

ODONTOLOGICAL INSTRUMENT

Americo Colombo, and Ugo Ronchetti, via dei Partigiani 12, Como, Italy
Filed Jan. 2, 1969, Ser. No. 788,389
Claims priority, application Italy, Jan. 19, 1968, 3802-A/68
Int. Cl. A61c 1/10

U.S. Cl. 32-27

1 Claim



An odontological instrument for introduction into and hollowing out the root channels of the teeth, comprising an angled-off longitudinal handle terminating in a head accommodating a worm and worm wheel, fixed and movable cam means, a spring acting upon the movable cam, and a tool carrying shaft which imparts to the tool a screwing movement and a rapid axial retracting movement.


3,579,834

CROWN AND BRIDGE REMOVER

Charles C. Reed, Jr., 4225 Mayfield Road, Cleveland, Ohio
Filed Aug. 21, 1969, Ser. No. 851,801
Int. Cl. A61c 3/16

U.S. Cl. 32-43

10 Claims



A crown and bridge remover comprises an arch bar, a pair of stabilizers and two pronged crown lifters. The lifter prongs

are adapted to fit under the crown. The arch bar is substantially the shape of an average row of teeth and is bendable to fit the mouth of an individual patient. The stabilizers are mounted on the arch bar so that they may be on either side of the crown or bridge to be pulled. The lifter is mounted on the arch bar between the stabilizers and provided with threaded means to draw the prongs toward the arch bar and thus remove the crown.


3,579,835

DENTAL PASTE DISPENSING TOOL

Myron F. Levenson, 5596 Mayfield Road, Lyndhurst, Ohio
Filed Jan. 6, 1969, Ser. No. 789,252
Int. Cl. A61c 3/06

U.S. Cl. 32-58

10 Claims



A rotary dental tool is provided with self-contained means for automatically feeding a dentifrice to an applicator. The dentifrice is contained in an elongated tubular element that serves as a flexible coupling extending between a rotary drive and the tool head. During operation, the drive causes twisting of the tubular element, thereby urging the dentifrice toward the applicator.


3,579,836

ARRANGEMENT FOR MEASURING OF LENGTHS

Heinz Kraus, and Siegbert Holstein, Traunreut, Germany, assignors to Dr. Johannes Heidenhain, Traunstein, Germany
Filed May 8, 1969, Ser. No. 822,935
Claims priority, application Germany, May 10, 1968
P 17 73 403.1

U.S. Cl. 33-1R

22 Claims



An arrangement for measuring of lengths, which comprises a measuring system including a measuring rod and a sensing device. The measuring system is enclosed for protection against disturbing outer influences. A covering shaft has a U-

profile and receives the sensing device. Resilient sealing lips of bendable material engage the leg portions of the covering shaft over its entire length and covers as a roof member the covering shaft. A driver projects through the sealing lips and has a cross section of a sword favoring the adherence of the sealing lips.


3,579,837

FOOT MEASURING APPARATUS

Charles A. Soriano, Fairfield, Conn., assignor to Atwater-Forbes Corporation, Westport, Conn.
Filed June 12, 1969, Ser. No. 832,570
Int. Cl. A43d 1/00

U.S. Cl. 33-3

7 Claims



A portable, battery-operated human foot-measuring apparatus is provided for simultaneously measuring the arch length and related width length of the foot as well as the heel-toe length. The apparatus operates in such a manner that one can measure either right or left foot within a single four sided measuring zone without mechanical rotation or change of scales and electronic readout means are provided for indicating all measurements.


3,579,838

METHOD OF THERMOMETER POINTING AND APPARATUS THEREFOR

Waldemar A. Ayres, Rutherford, N.J., assignor to Becton, Dickinson and Company, Rutherford, N.J.
Continuation-in-part of application Ser. No. 612,692, Jan. 30, 1967, now abandoned. This application Apr. 5, 1968, Ser. No. 719,214
Int. Cl. B43i 13/24

U.S. Cl. 33-19

10 Claims



A thermometer-pointing apparatus which automatically performs the required facing operation and horizontal

scanning to sense and accurately locate the top of a mercury column for purposes of pointing. For such purposes a photoelectric control system is connected with electromechanical means for manipulating the thermometer automatically as the top of the mercury column is being located and an improved optical system is provided for projecting a magnified image of the mercury column onto the photoelectric control system which is responsive thereto, thereby facilitating the pointing of the thermometer.


3,579,839

ARCHERY BOW SIGHT

Robert J. Kowalski, 512 Berner St., Pittsburgh, Pa.
Filed Nov. 5, 1968, Ser. No. 773,525
Int. Cl. F41g 1/00; F41b 5/00

U.S. Cl. 33-46

4 Claims



Described is an archery bow sight in which a sighting element is held in position on a bracket at a location for an approximate range, and incorporating vernier adjustment means on the bracket whereby fine adjustments in range can be made after the sighting element is positioned at its approximate range position on the bracket.


3,579,840

SNAP OFF TELESCOPE MOUNT

Joseph A. Heinzel, El Paso, Tex., assignor to Olin Corporation
Filed Sept. 4, 1969, Ser. No. 855,131
Int. Cl. F41g 1/38, 1/42

U.S. Cl. 33-50

11 Claims



A mount for securing a telescope sight to a firearm, which mount is snapped on and off of the firearm without the need of special tools. The mount includes a base portion which is secured to the firearm, and a ring portion which is secured to the scope. A tongue and groove connection positions the ring portion longitudinally with respect to the base portion and prevents longitudinal movement from occurring between the scope and the firearm such as would be initiated by recoil when the firearm is fired. A spring clamp is arranged to position the ring portion laterally with respect to the base portion to resist lateral movement of the scope.

3,579,841


PROTRACTOR

Dana Peterson, P.O. Box 412, Coronado, Calif.
Continuation of application Ser. No. 752,695, Aug. 14, 1968,
now abandoned. This application Feb. 2, 1970, Ser. No.
4,435

Int. Cl. B43I 13/00

U.S. Cl. 33—75

2 Claims



A compact protractor having an outer transparent semicircular shaped outer casing part and an opaque similarly shaped inner member snugly received therein for rotation. Openings and indicia are provided on the transparent outer casing.

3,579,842


CABLE-MEASURING MACHINE

Joseph William Scher, Short Hills, N.J., assignor to Weber & Scher Mfg. Co., Inc., Newark, N.J.
Filed Sept. 27, 1968, Ser. No. 763,324

Int. Cl. G01b 3/12

U.S. Cl. 33—133

11 Claims



In a machine for the measurement of length of cable passing a given point, a rotating constant-pressure belt measuring unit which comprises structural features, including a rotatable measuring unit, maintaining a constant and continuing contact with the cable to accurately measure same without interfering with the movement of the cable through the machine.

3,579,843

GAGE WITH VARIABLE RESPONSE AMPLIFIER

Edward Peonski, West Dundee, Ill., assignor to American Gage & Machinery Company, Elgin, Ill.

Filed Apr. 8, 1969, Ser. No. 814,405


Int. Cl. G01b 5/00; G01r 15/08

U.S. Cl. 33—147

8 Claims

An improved gage in combination with an amplifier which

will respond more rapidly to a change of signal in one direction than to a change of signal in the opposite direction



and where the ratio of the response rate in one direction to the response rate in the other direction is adjustable.

3,579,844

BACKING RING CENTERING DEVICE


Arne K. Olofson, 15396 S.E. River Forest Road, Milwaukee, Oreg.

Filed Sept. 23, 1968, Ser. No. 761,432

Int. Cl. G01b 3/38

U.S. Cl. 33—180

7 Claims



A device for centering an annular backing ring within a tire casing, the device including an elongated guide supported against diametrically opposed regions of a bead on the casing and an indicator bar mounted for movement relative to the guide. The indicator bar may be moved into contact with diametrically opposite internal regions of the backing ring and cooperating graduations and marker on the guide and bar indicate the position of the bar, and thus the position of the backing ring, relative to the guide member.

3,579,845

DYNAMIC WHEEL TOE AND TIRE PULL TESTING APPARATUS


Lee Hunter, St. Louis County; David A. Senften, Florissant, Mo., and Edwin W. Logan, Belleville, Ill., assignors to Hunter Engineering Company, Bridge, Mo.

Filed Mar. 27, 1969, Ser. No. 811,160

Int. Cl. G01b 19/28

U.S. Cl. 33—203.13

7 Claims



Dynamic testing apparatus for vehicle wheels for determining the wheel toe relationship and for measuring the extent of

lateral pull or scuffing developed between the tire tread and the road surface. The apparatus includes adder-memory and subtractor-memory circuits responsive to wheel toe signals generated by a dynamic wheel driving apparatus which rotates the wheels in forward and reverse directions to obtain wheel toe measurements independent of the lateral pull developed by the tire characteristics on the rotating surfaces and to obtain an indication of the tire pull characteristics of the tire.

3,579,846

LASER GYROMETER SYSTEM

Jean-Michel Catharin, Savigny-Sur-Orge, France, assignor to


Compagnie General D'Electricite, Paris, France

Filed Dec. 15, 1967, Ser. No. 690,814

Claims priority, application France, Dec. 15, 1966, June 5, 1967, 87563; 109148

Int. Cl. G01c 21/00

U.S. Cl. 33—204



Variation of output frequency of a laser gyrometer, the plane of which rotates about a vertical axis, is utilized to ascertain the direction of geographical North. Adequate mechanical construction reduces several inaccuracies to a minimum.

3,579,847

ATTITUDE INDICATOR


John W. Winter, and Guy K. Harrison, Jr., Houston, Tex., assignors to Aviation Instrument Manufacturing Corporation

Filed May 29, 1968, Ser. No. 732,987

Int. Cl. G01c 19/44; G01d 7/02, 5/02

U.S. Cl. 33—204

12 Claims



An instrument for indicating roll and pitch attitude of a host craft. The instrument comprises a support for attaching the instrument to the host craft and a terrain reference including a horizon line fixed relative to the host craft parallel to the transverse axis of the craft. A gyroscope is universally mounted in the support to maintain a stabilized datum reference perpendicular to the earth. The gyroscope is coupled through gears and linkages to a simulator which represents the host craft as viewed from the rear. The simulator is mounted adjacent the terrain reference for angular movement with respect to the horizon line to indicate roll

and for radial movement relative to the horizon line center to indicate pitch. In one embodiment the simulator is a three dimensional representation of the host craft pivotably connected to the coupling mechanism for pitch movement relative to the horizon line in the same sense the host craft pitches relative to the natural horizon. As the host craft rolls or pitches relative to the stabilized datum gyroscope the rotation and movement of the gear and linkage coupling devices effect the various responsive displacements of the simulator for attitude indication.

3,579,848

METHOD OF CONTROLLING HUMIDITY CONTAMINATION OF HYGROSCOPIC MATERIAL-HANDLING MACHINES


Tomas Hernandez, 9220 S.W. 38th St., Miami, Fla., and Valentin E. Lorenzo, 119 N.E. 20th St., Miami, Fla.

Division of Ser. No. 720,259, Apr. 10, 1968, Pat. No. 3,500,554.
Filed Jan. 19, 1970, Ser. No. 3,781

Int. Cl. F26b 5/04

U.S. Cl. 34—15

5 Claims



The method of reducing and substantially eliminating water contamination of hygroscopic materials of the type being processed by a series of enclosed material-processing machines and conveyed from each material-processing machine to the next machine through closed material conveyance passages extending between and continuously communicated with the enclosed material-processing machines. The method comprises the step of pumping heated air of low relative humidity under pressure into the enclosed area of the last material-processing machine to which the material is conveyed and allowing the heated air to flow upstream, relative to the direction of material flow, through the material-processing machines and closed conveyance passages to the material-processing machine into which the material to be processed is first discharged.

3,579,849

HEAT SETTING OF FOOTWEAR

Alfred Freeman, 94 Orlingburg Road, Isham, Northamptonshire, England

Filed Sept. 16, 1968, Ser. No. 762,234

Claims priority, application Great Britain, Sept. 21, 1967, 42909/67


Int. Cl. F26b 19/00

U.S. Cl. 34—48

6 Claims

Heat-setting footwear by advancing same through closed chamber in which hot, moisture-saturated air is circulated. Moisture saturation maintained by hot air passing over shallow evaporation tank continuously supplied with water via a ball valve. Air-heating coils in chamber controlled by tem-

perature-responsive device adjacent footwear being treated so as to maintain temperature constant. Also discloses plu-



ality of spaced unit-construction heat-setting chambers in conjunction with chain conveyor.

3,579,850

DEVICE FOR FEEDING PULVERULENT MATERIAL


Herbert Deussner, Bensberg-Refrath, and Jurgen Langmaack, Niederkassel, Germany, assignors to Klockner-Humboldt-Deutz Aktiengesellschaft, Cologne-Deutz, Germany
Filed Mar. 3, 1969, Ser. No. 803,801

Claims priority, application Germany, Mar. 15, 1968,

P 16 67 148.0
Int. Cl. F26b 17/10

U.S. Cl. 34—57E

1 Claim



A device for feeding pulverulent material into a cyclone for treatment therein by a gas. The pulverulent material is introduced into a ring-shaped chamber near the bottom of which a gas is tangentially injected by a number of nozzles which is mixed with the pulverulent material to form a uniform mist which through an annular overflow aperture at the top wall of the ring-shaped chamber overflows into an annular connecting slot which latter discharges the mixture of pulverulent material and gas downwardly into the upper portion of the treatment chamber in the cyclone.

3,579,851

POP-OUT LINT TRAP AND DOOR INTERLOCK FOR LAUNDRY APPARATUS

Richard A. Elmy, Mansfield, Ohio, assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed May 19, 1969, Ser. No. 825,644


Int. Cl. F26b 21/06

U.S. Cl. 34—82

9 Claims

A combination interlock and maintenance reminder for clothes dryer apparatus which prevents unintentional restart-

ing of the dryer after interruption thereof, prior to the end of the cycle, and which reminds the operator to keep the lint trap clean. The invention is characterized by a lint filter located at the front of the dryer and operatively associated with the access door thereof such that when the latter is open



the lint trap moves partially beyond the front wall of the dryer to thereby remind the user that it should be cleaned. Both the lint filter and the front door cooperate with circuit interrupt means such that both must be closed in order for the apparatus to operate.

3,579,852

VERTICAL GRAIN-DRYING DEVICE


Nikola Beograd Ivackovic, and Milija Urošević, Cacak, Yugoslavia, assignors to Cer Preduzece Termo-Tehnickin Uredajaja I Montaza, Cacak, Yugoslavia

Filed Oct. 17, 1969, Ser. No. 867,236

Int. Cl. F26b 17/12

U.S. Cl. 34—167

9 Claims



A grain-drying device is constituted by a plurality of horizontal layers which are vertically juxtaposed and respectively formed of inverted truncated pyramid sections adjacent one another and with common upper bounding edges to define a honeycomb arrangement, the sections of each layer being horizontally offset from the sections of the next lower layer such that apertures in the lower ends of the sections of the upper layer are disposed at the junctions of the sections of the lower layer whereby downwardly flowing material in each section will divide and pass into the adjoining sections in the lower layer. The downwardly flowing material is dried by passing a drying medium through broken channels formed between adjacent sections in each layer.

3,579,853

CIRCUIT BOARD DRIER

Joseph J. Martino, 7013 El Prauo Circle, Buena Park, Calif.

Filed Dec. 5, 1968, Ser. No. 781,566


Int. Cl. F26b 19/00

U.S. Cl. 34—218

11 Claims

In an apparatus for drying circuit boards, two sets of rollers convey a circuit board past a set of air knives of novel configuration. Each air knife comprises a pair of planar blade members converging to form adjacent their apex an elongate orifice having a width on the order of 0.085 inches. A deflector lip projects from one edge of the orifice. Air forced through the orifice forms an air knife edge having an anemometer static pressure of greater than 10 inches of

water, providing exceptionally quiet, highly effective drying of the board. In some embodiments, a plurality of upper and



lower horizontally disposed guidewires facilitate drying of thin, flexible boards.

3,579,854

ISOLATION OF INFORMATION


John R. Tusson, R.I. Box 683, Belle Chasse, La.

Filed May 20, 1968, Ser. No. 730,334

Int. Cl. G09b 3/00

U.S. Cl. 35—8

17 Claims



Graphic information contained in coordinated arrays is released a bit at a time by the use of an information isolating device. When an instruction mark on the device is located next to a bit of information in one array, a retrieval mark will be located next to a coordinated bit of information in another array. An endless belt or a metal clip at least in part transparent is placed about a leaf or collection of leaves containing graphic information and is moved to isolate the information.

3,579,855

TEACHING MACHINES

Maurice Reginald Worthy, and Clive Reginald Worthy, 398 Moreland Park, West Brunswick, Victoria, Australia

Filed May 17, 1968, Ser. No. 730,153


Claims priority, application Australia, May 17, 1967,

21891/67

Int. Cl. G09b 5/06

U.S. Cl. 35—8

8 Claims



A teaching machine having means to display a plurality of items of visual information and to reproduce audio informa-

tion. The visual information carrier is intermittently advanced to present new items. Means are provided to cause reproduction of the sound information during a portion of the dwell period of each visual item and to render the reproduction means ineffective while the visual information carrier is advancing to a new item.

3,579,856

AUTO-CHESS APPARATUS AND PUNCHED CARD THEREFOR


Frederick L. Way, 8 Hillcrest Lane, Woodbury, N.Y.

Filed July 22, 1968, Ser. No. 746,449

Int. Cl. G09b 19/22; A63f 3/02

U.S. Cl. 35—8

8 Claims



As described herein, a light source mounted in a housing illuminates each column of a prepunched chess card as the card is intermittently driven through the housing. Each column of the card, except for a start of new game column, includes at least two apertures which transmit the light to the light receiving ends of two of a possible 64 light fibers. The light transmitting ends of the fibers extend to the squares of a chess pattern formed in the top plate of the housing and illuminate the squares when their corresponding light receiving ends are illuminated by the light source. The illuminated squares indicate the chess piece to be moved and the square to which the piece is to be moved.

3,579,857

ELECTRIC TEACHING DEVICE


Jack L. Lamberson, Miami, Fla. (1200 Missouri St., Apt. 609, Baytown, Texas, 77520)

Filed Oct. 3, 1969, Ser. No. 863,430

Int. Cl. G09b 7/00

U.S. Cl. 35—9

7 Claims



An electric device in which a selected teaching sheet is inserted and registered thereon. The sheet has printed thereon a number of different characters. A network of circuit closing conductors are positioned in the device under the sheet

and covered by a resilient member having openings therein corresponding in position to each character. Each sheet has a conducting area on the opposite side of certain selected characters. The student is asked to press a finger directly on one of the selected characters. When correctly pressed, the circuit connected to the network will energize a lamp and buzzer.

3,579,858

ANATOMICAL MODEL


Itzhak E. Bentov, Belmont, Mass., assignor to Medi-Tech Incorporated, Belmont, Mass.

Filed Aug. 28, 1969, Ser. No. 853,849

Int. Cl. G09b 23/32

U.S. Cl. 35-17

10 Claims



An anatomical model comprises a simulated main body blood vessel having a predetermined curvature at a portion thereof and is formed of a yieldable plastic material. At least one simulated secondary blood vessel is interconnected with the main body blood vessel at the curved portion. Means mount the model and comprise means for varying the positioning of the secondary blood vessel with respect to the main body blood vessel to correspond with variations caused by aging or abnormalities in naturally occurring blood vessels. Preferably the anatomical model simulates the aorta and attached arteries.

3,579,859

DESIGN GRID WITH VARIABLE GUIDE

Pierre Malenge, 19Rie Nationale, Raches, (Nord), France


Filed Jan. 29, 1969, Ser. No. 795,092

Claims priority, application France, Feb. 2, 1968, 138,577

Int. Cl. G09b 1/04

U.S. Cl. 35-27

10 Claims



A game for making drawings or FIGS. and constituted by a plurality of ornamental elements adapted to be suitably positioned on a support, said game comprising at least one colored sheet or plate covered with a plurality of suitably located spots on the surface thereof, said sheet being associated to a grid provided with openings superimposed to said sheet and adapted to unveil through the openings thereof some of the spots of said colored sheet, which altogether form a design or drawing.

3,579,860 VISUAL AID FOR TEACHING AND TESTING THE SIGHT READING OF THE FRACTIONAL DIVISIONS OF AN INCH


Lawrence F. Strem, 810 Valley View Drive, La Vale, Md.

Filed Apr. 10, 1969, Ser. No. 814,998

Int. Cl. G09b 19/00

U.S. Cl. 35-31

3 Claims



A visual aid for teaching and testing sight reading of the fractional divisions of a unit of measure which includes a plurality of selectively energizable indicators associated with an enlarged scale reproduction of the unit of measure.

3,579,861

SINGLE-CHANNEL ELECTRONIC QUESTION-RESPONSE SYSTEM


Thomas E. Hallett, Bainbridge Island, Wash., assignor to BRD Inc., Bainbridge Island, Wash.

Filed Feb. 6, 1969, Ser. No. 797,181

Int. Cl. G09b 5/00

U.S. Cl. 35-48R

12 Claims



The teaching response system disclosed entails a control unit used by an instructor and a plurality of response unit used by individual students. The correct answer to a question is selected on a multiposition switch in the control unit and the students select their answers on similar multiposition switches in the response units. A timed correct answer signal is transmitted to the response units, wherein the students' answers are individually compared with the indicated correct answer and individual correctness signals are derived and transmitted over a single communication channel in sequence from the respective response units back to the control unit, in which they are recorded and displayed. The system relies upon time coincidence for determining correctness of the answers selected on the response units and sequencing means for monitoring the individual correctness signals.

3,579,862

SET A TABLE PUZZLE


Sue Ballen, 651 Desert Lane, Las Vegas, Nev.

Filed May 15, 1969, Ser. No. 824,921

Int. Cl. G09b 1/10; A63f 9/08

U.S. Cl. 35-8

1 Claim



An educational toy particularly for girls and for teaching them the proper place setting of a table, the device comprising a base panel having various design-shaped indentations for receiving corresponding configured protrusions on the undersides of various dishes and other table placement items, thus serving as a puzzle for proper alignment of corresponding design indentation and protrusions while at the same time serving an educational purpose.

3,579,863

VIP JACKET UNDER SKID WIRE OF PAPER POWER CABLES


Martin H. McGrath, 200 E. 15th St., New York, N.Y.

Filed June 19, 1969, Ser. No. 834,795

Int. Cl. H02g 15/20

U.S. Cl. 174-10

7 Claims



Oil-impregnated paper cables are kept dry during storage, shipment and installation by covering the cable, under the skid wire, with a sheath comprising a laminated tape of aluminum coated with plastic on both sides. The plastic seals the seam of the sheath, and as the cable is pulled into a pipe the sheath is ruptured or torn in a haphazard manner by use of pliers, about once for each turn of the reel, to create breaks in the sheath which permit rapid and thorough evacuation of the completed system and also permit normal interchange of the pipe filling oil on load cycle changes.

3,579,864

TEACHING DEVICE

Sheldon Littwin, 38-21 Garvey Place, Fairlawn, N.J., and Alexander Schure, 257 Wheatley Road, Old Westbury, N.Y.

Filed Mar. 4, 1969, Ser. No. 804,150


Int. Cl. G09b 7/06

U.S. Cl. 35-9

14 Claims

A response display system which is compatible to data processing and computer systems is described.

The device displays information as the result of a particular inquiry such as in a learning system, teaching system, a game, or a directory. The display employs a multiple-leaf answer response sheet. An intermediate surface on the



answer sheet is provided with response characters which are ordinarily concealed but may be silhouetted upon illumination by lamps placed in selected registration with the response characters. A matrix device is used to key punch data processing cards. Several embodiments are shown.

3,579,865

METHOD FOR MEASURING THE EFFECTS OF STRESS ON A MAN'S PERFORMANCE OF PRIMARY AND SECONDARY TASKS


Norman Kenneth Walker, 6613 Sulky Lane, Rockville, Md.

Filed Feb. 27, 1969, Ser. No. 802,977

Int. Cl. G09b 19/00

U.S. Cl. 35-22

8 Claims



A method for measuring the effects of stress on a man's performance of a primary task, while a secondary task is also provided to be performed simultaneously by the test subject. The secondary task thus produces a "distraction stress" on the test subject thereby degrading his performance on both of the tasks. A Zero Input Tracking Analyzer (ZITA) is used as the primary task, which provides a unique tracking task that has no initial input or error source, and requires the test subject to null only his own error from his previous response after he has initiated the tracking task with his initial response. A number of variations, such as velocities and accelerations, as well as various amounts of lag or lead may be introduced into the response system. An Auditory Discrimination Task (ADT) can be used as the secondary task, to produce the "distraction stress" for the test subject while he is carrying out the primary task. This task requires that the test subject respond to the stimuli of high or low tones, presented to him by head phones, by moving a response stick forward or backward for the high and low pitch, respectively. A common display/recorder is used to record the performance on both tasks.


3,579,866

POLYBASE COUNTER

John Everett Miller, 4568 E. 45th St., Tulsa, Okla.
Filed Mar. 3, 1969, Ser. No. 804,058
Int. Cl. G09b 19/02

U.S. Cl. 35—32

4 Claims



This invention relates to a simple mechanical counter to be used as an instructional aid in teaching number systems of various different bases. It consists of a plurality of prismatic-shaped or cylindrical-shaped blocks freely mounted on a shaft which extends from a handle. The lateral faces of these blocks are numbered according to the base of the number system being used—each block in a set of blocks for base two being numbered "0" and "1," each block in a set of blocks for base three being numbered "0," "1," and "2," each block in a set of blocks for base four being numbered "0," "1," "2," and "3," and so on in this manner. A set of blocks is mounted on the shaft in such a way that by rotating the blocks in the proper manner consecutive numbering in a given base number system may be shown.


3,579,867

WRITING GUIDE FOR TRAINING PURPOSES AND USE BY THE BLIND

Henry S. Kuhn, 609 Austin Ave., Park Ridge, Ill.
Filed Sept. 5, 1969, Ser. No. 855,604
Int. Cl. G09b 21/00

U.S. Cl. 35—38

10 Claims



A writing guide in the form of a generally planar board, the upper face of which forms the surface on which may be disposed the paper sheet to be written on, the board having a series of parallel edges extending horizontally across at least a portion of the upper face of the board, each of which defines respective writing lines along and above which the particular line is to be disposed, with each of such edges forming an abutment at the writing line defined thereby which faces upward toward the top of the board and is operative to impart a distinct resistance to movement of a writing instrument, applied to such a paper sheet, in a downward direction below such writing line. In a preferred embodiment of the invention the writing surface between each pair of adjacent abutment-forming edges is inclined from the inner boundary of the lowermost of such pair to the outer boundary of the uppermost of such pair. Such abutments may be placed in any desired configuration to define specific writing areas on the board and means is also provided for indicating margins as well as a designated line of writing.


3,579,868

TEST SCORING ANSWER SHEET AND METHOD OF EMPLOYING SAME

Thaddeus Leroy Scott, 306 Hyde Drive, Hayward, Calif.
Filed Nov. 14, 1969, Ser. No. 876,835
Int. Cl. G09b 7/06

U.S. Cl. 35—48

10 Claims



An answer sheet for automatic test scoring, and scoring method employing same which facilitate automatic scoring with apparatus of an extremely simplified nature and attendant low cost. The sheet and method are such as to eliminate the usual requirement for a master score card and associated comparison circuitry, complex programmed logic circuitry, or the like, in the scoring machine.


3,579,869

AUTOMATIC ANSWER CONFIRMATION SYSTEM

Terry L. Hewitt, Schenectady, N.Y., assignor to General Electric Company
Filed Sept. 2, 1969, Ser. No. 854,417
Int. Cl. G09b 7/00

U.S. Cl. 35—48

7 Claims



An automatic answer confirmation system employable with a student response system is described wherein the problem and test designator numerals are logically combined to extract a single correct answer for the multiple choice question being answered. To effect this result, the problem and test designator numerals are encoded into the answer confirmation system as binary coded decimal digits and the digits are summed in two exclusive-OR stages to produce a composite digital number related to the problem being answered. The composite number then is entered into an answer select matrix for extraction of the correct answer for the problem and the correct answer is compared with the student selected choice to automatically determine the correctness of the student's choice.

3,579,870

TEST ADMINISTERING APPARATUS

George K. Bennett, Bronxville, and Richard G. Buchanan, New York, N.Y., assignors to The Psychological Corporation, New York, N.Y.

Filed Aug. 27, 1969, Ser. No. 853,315
Int. Cl. G09b 7/00

U.S. Cl. 35—48R

10 Claims

A test administering apparatus has a plurality of tape playback units individually controllable by an examiner at a

console to provide verbal instructions for, and to time a respective test, and the outputs of the playback units are selectively fed, as by station selector switches at the console, to any of a plurality of headphones or earpieces to be utilized by individual examinees and/or to selected loudspeakers in



examination rooms occupied by groups of examinees. An alert signal is provided from each operating playback unit to the examiner near the end of the allotted time for the respective test and the end of such allotted time is also signalled to the examiner as well as to each examinee taking the test.


3,579,871

RECORD BOOK

Lloyd H. Eddington, 4330 Kling St., Burbank, Calif.
Filed July 24, 1969, Ser. No. 844,460
Int. Cl. B43I 1/00

U.S. Cl. 35—66

10 Claims



A record book comprising a plurality of leaves wherein each leaf is centrally divided in the transverse direction with separate writing sections located on each side of the division. Each writing section includes a series of longitudinal separate writing spaces, each space having a wax backing with an opaque writing strip covering the backing and a clear plastic outside cover over the writing strip. The writing strip of each space can be removed from in contact with the wax backing. The stylus is to be retained when not in use within a hinge connection which maintains the entire book in the closed, not-in-use position.

3,579,872

DREDGING APPARATUS WITH SURGE COMPENSATING MEANS

Robert J. Jantzen, Baltimore, Md., assignor to Ocean Science and Engineering, Inc., Washington, D.C.


Filed Nov. 5, 1968, Ser. No. 773,613
Int. Cl. E02F 3/90

U.S. Cl. 37—66

8 Claims

A dredging system including a floating vessel, a ladder pivotally connected to the vessel and capable of being

lowered to selected angular positions with respect to the vessel, an excavator at the free end of the ladder for digging and removing material, and a surge compensator on the ladder



for adjusting the length of the ladder in response to changes in distance between the vessel and the material being dredged.

3,579,873


RAILWAY BALLAST WORKING APPARATUS

John Knox Kershaw, Southport, Ind., assignor to The Marmom Group Inc., Chicago, Ill.

Filed Feb. 14, 1968, Ser. No. 705,421
Int. Cl. E01b 27/02

U.S. Cl. 37—105

15 Claims



A self-propelled road and rail vehicle has four retractable rail wheels and has four pneumatic-tired drive wheels which are used for road travel and which ride on the rails during rail travel to produce high tractive effort for driving various roadbed maintenance and rehabilitation equipment. Such equipment may include a ballast distributing plow carried at the front of the vehicle and a track broom at the rear carried by head blocks on the vehicle, and in particular, has a side ballast-working wing mounted on an adjustable carrier at each side of the vehicle. All are controlled hydraulically from the vehicle cab, and have operating positions for use on the roadbed and transport positions within limited road travel dimensions. Each ballast-working wing has front scarifying teeth to break up compacted ballast on a side bank of the roadbed, two sets of discing elements to work and redistribute the loosened ballast of the side bank, and a mold board behind the disc units for reshaping the side banks. Each such wing is supported from the vehicle frame by an adjustable carrier providing both lateral and tilting adjustment over a wide range, and movement between operating and travel position, and the wing is readily removable for replacement by other bank-dressing units.

3,579,874

EDUCATIONAL DEVICE FOR TRAINING IN MATHEMATICS


Thomas B. Smith, 672 Jefferson St., Ste. Genevieve, Mo., and Raymond H. Swassing, Jr., 35 Northwood Apts., Storrs, Conn.

Filed Jan. 24, 1969, Ser. No. 793,681

Int. Cl. G09b 19/02; G06c 27/00

U.S. Cl. 35—32

3 Claims



An educational device for training in mathematics embodied in a housing having a series of disc structures rotatably mounted therein, each structure including a rotatable axially aligned disc having a forward facing disclosing a sequence of numerical values, usually mathematical numbers contained in select bases other than only defined in the decimal system; the various disc structures cooperate to provide for rearrangement in sequence of the numerical values of the base system under investigation by incorporating catch means for effecting a degree of limited rotation of one disc upon rotation of the adjacent disc.

3,579,875

APPARATUS FOR THE SYSTEMATIC CORRECTION AND SELECTIVE APPRECIATION OF TEACHING TESTS

Pierre J. Dubost, 262, Avenue Daumesnil, 75 Paris, and Henry Perret, 7, Rue des Freres Lumiere, 92 Rueil-Malmaison, France


Filed Dec. 20, 1968, Ser. No. 785,709

Claims priority, application France, Feb. 1, 1968, 138,246

Int. Cl. G09b 19/08

U.S. Cl. 35—48

14 Claims



Apparatus for systematic correction and assigning marks for teaching tests comprising a case having windows. Codes carried by four rotary discs mounted in the case can be caused to be displayed in the windows by rotation of the discs. The codes comprise codes of partial identification of questions, codes of appraisal of possible answers to each question, codes indicating the correct answer, codes indicating the value of the various questions, which complete the identification of each question, codes indicating the degree of difficulty of the test, as many codes of choice as there are possible answers to each question, codes of the marks assigned to the various answers, and a code corresponding to the marks given to the chosen answer.

ERRATA

For Classes 37—66 and 37—105 see:
Patents Nos. 3,579,872 and 3,579,873

3,579,876

APPARATUS FOR FOLDING, FEEDING AND PRESSING PIECES OF FABRIC MATERIAL

Hans Freermann, Ochtrup, Germany, assignor to Firma Carl Schmale, Ochtrup Westphalia, Germany


Filed Dec. 29, 1967, Ser. No. 694,707

Claims priority, application Germany, Dec. 29, 1966, Sept. 9, 1967, 40,033; 41,278

Int. Cl. D06f 61/06; 63/02, 69/00

U.S. Cl. 38—2

18 Claims



Apparatus for automatically hemming the edges of pieces of fabric material. The apparatus includes both a mechanism for use in machinery for folding over the edge of a piece of material and a mechanism for feeding the material into and out of the folding mechanism and for pressing the material in the area of the edge before as well as after its edge is folded.

3,579,877

DEVICE FOR HOLDING PLEATED MATERIAL


Aaron C. Bray, Jr., Evans Drive, P.O. Box 203, Houston, Miss.

Filed Aug. 2, 1968, Ser. No. 749,801

Int. Cl. D06f 71/40

U.S. Cl. 38—12

8 Claims



A device for facilitating pressing of pleated garments. A U-shaped frame is attached to the work surface of a pressing buck or ironing board. The frame has narrow strips of friction material affixed thereto so that when a pleated garment is placed over the work surface the friction material engages the garment and keeps the pleats from falling out.

3,579,878

CARD RETAINER

Anthony L. Griffin, 107 Division St., Amsterdam, N.Y., and Earl G. Chetwynd, 6 Steele Ave., Gloversville, N.Y.

Filed Feb. 28, 1969, Ser. No. 803,310


Int. Cl. G09f 3/18

U.S. Cl. 40—10

9 Claims

An envelope-type enclosure for receiving a panellike card having indicia on at least one side thereof. The enclosure in-

cludes structure adapting it to be hung on a suitable support, a rotatable sign supporting member for mounting a plurality of signs. The supporting member is capable of rotation about a window in one side thereof with which the indicia of the



card may be registered and coin retaining pockets for retaining a plurality of different value coins to be paid out in tolls.

3,579,879

FLUIDIC CHARACTER DISPLAY DEVICE


Walter E. D. Samuels, Cleveland Heights, Ohio, assignor to Corning Glass Works, Corning, N.Y.

Filed July 22, 1969, Ser. No. 843,483

Int. Cl. G09f 11/00

U.S. Cl. 40—28

9 Claims



A plurality of stacked movable slides is arranged such that a small movement of any one thereof from an inactivated position to an activated position will align information containing apertures of the moved slide with base apertures of the remaining slides to allow light to pass through the entire stack of slides and indicate a character that is outlined by the information apertures of the moved slide. A pair of pneumatic cylinders which are disposed at opposite ends of each of the slides move the slides between their inactivated and activated positions. A masking slide, which is moved from its inactivated to its activated position concurrently with the movement of any one of the plurality of slides to its activated position, prevents the display of any light when all of the plurality of slides are in their inactivated position.

3,579,880

CAROUSEL SIGN

Edward L. Murphy, 2500 Farrier Place, Owensboro, Ky.


Filed June 16, 1969, Ser. No. 833,623

Int. Cl. G09f 11/10

U.S. Cl. 40—33

10 Claims

A system for displaying a plurality of messages comprising



a vertical shaft and may be raised for viewing or lowered to ground level for facilitating the change of messages.

3,579,881

MILITARY RIBBON HOLDER


Gene F. Cherry, 331 Fountain Ave., Redlands, Calif.

Filed Feb. 14, 1969, Ser. No. 799,195

Int. Cl. A44c 3/00

U.S. Cl. 40—1.5

4 Claims



One or more military campaign ribbons are mounted on the front of a uniform by sliding them lengthwise along an elongated channel-shaped metallic strip having a base portion with a pair of forwardly diverging sides. The base is arcuate in cross section, and the sides have arcuate rib portions with flanges adapted to slidably receive the ribbon.

3,579,882

PERPETUAL CALENDAR

Yoshio Miyahune, No. 238, Kitakase, Kawasaki-shi, Kanagawa-Ken, Japan


Filed Mar. 24, 1969, Ser. No. 809,893

Claims priority, application Japan, Apr. 17, 1968, 43/31257

Int. Cl. G09d 3/02

U.S. Cl. 40—107

2 Claims



A mechanical type of perpetual calendar utilizing laterally interlocking blocks having both faces of different color and which are arranged by being moved and turned upside down for the purpose of distinguishing in appearance the week days from flag days or red letter days. A frame holder is provided to slidably receive the blocks in rows, and has a side

access frame member providing access for the blocks, and which frame member interlocks with the adjacent end blocks of the respective rows placed within the frame to hold same in a stabilized condition.

3,579,883

PILL DISPENSER WITH INDICATING MEANS


Thomas H. Hayes, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.

Filed Feb. 24, 1969, Ser. No. 801,543

Int. Cl. G09f 9/00

U.S. Cl. 40-107

6 Claims



A pill dispenser with indicating means in the form of a flexible strip having a plurality of day indicia which are selectively adjustable to align any set of a predetermined number of successive indicia with a like number of columns of pills, thereby providing an indication of when each pill is to be taken.

3,579,884

FORWARD PLANNING APPARATUS

Nicholas P. Holwell Bray, Penny Farm, near Sherborne, England


Filed Sept. 27, 1968, Ser. No. 763,079

Claims priority, application Great Britain, Oct. 13, 1967, Jan. 22, 1968, 46,796/67; 3,303/68

Int. Cl. G09t 11/00

U.S. Cl. 40-110

6 Claims



A forward planning apparatus comprising in combination a time scale with a plurality of pointers movable together over it in accordance with the passage of time, the pointers being set to indicate given periods of time between them and each representing a stage of an enterprise, and at least one multi-sided element representing a unit of the enterprise, the sides of said element each bearing an indication for one stage of the enterprise, such element being capable of application to the time scale with any side thereof in a given visible position to indicate the stage of the enterprise in hand.

3,579,885

ADVERTISING DISPLAY SUPPORT


Peter B. Iverson, Excelsior, Minn., assignor to Postmark Corporation, Minneapolis, Minn.

Filed Jan. 31, 1969, Ser. No. 795,614

Int. Cl. G09f 7/18

U.S. Cl. 40-145

6 Claims



A support structure for an advertising display in the form of a spider member having a plurality of notched legs for supportably engaging the sidewalls of a multisided advertising display through apertures therein, the spider member being mounted on an upright post or suspended by an overhead string. The spider member preferably has a ring-shaped central body portion within which an adapter may be removably inserted for attachment to a string or to the top end of a tubular support post.

3,579,886

PICTURE FRAME MOUNTING CONSTRUCTION


George T. Hughes, Newburgh, N.Y., assignor to Ovitron Corporation, Newburgh, N.Y.

Filed May 4, 1970, Ser. No. 34,140

Int. Cl. G09f 1/12

U.S. Cl. 40-152

5 Claims



A low-cost picture frame assembly includes a stretch frame onto which a print, lithograph or the like is initially secured such as by an adhesive substance provided over at least a portion of one surface of the stretch frame. The inner frame having the print secured thereto is frictionally engaged by means of locking means provided on one of the frames, to thereby unite the two frames into the desired assembly.

3,579,887

DESK FRAME

Gunter Rochelt, 7 Schulinstr. 1110, Ulm, Germany

Filed Jan. 7, 1969, Ser. No. 789,466


Int. Cl. G09f 1/12

U.S. Cl. 40-152.1

8 Claims

A frame for pictures and the like comprised of a transparent member and a lightweight supporting member having a much smaller total mass and weight than the transparent member. The supporting member positions and frames the transparent member on two opposite parallel sides while framing the picture inserted within the support member on all four sides so as to completely conceal the sides of the pic-

ture when the frame is fully assembled. The support member is provided with a recess along the rear surface to facilitate hanging of the frame upon a wall or other surface and is further provided with diagonally aligned support surfaces which together with the disposition of the center of gravity of the assembled frame, enables the frame to be supported



diagonally relative to a support surface upon any of the diagonal aligned surfaces of the support member. In addition, the two opposite parallel sides of the support member which embrace the transparent member as well as the two exposed sides of the transparent member may be optionally employed as supporting surfaces for supporting the frame assembly in a vertically aligned fashion upon a suitable supporting surface.

3,579,888

COPY HOLDER


Clifford Henry Burnham, 17 Sherwood Ave., Scarborough, Ontario, Canada

Filed Dec. 6, 1968, Ser. No. 781,735

Int. Cl. B41j 11/64

U.S. Cl. 40-356

5 Claims



A copyholder for holding sheets of material, such as paper, for the copying of information therefrom, for example by a typist. The holder has a rectangular frame slightly larger than the sheets to be held, a stand for supporting the frame upright, and a bar extending across the frame to underline the line being copied. A knob, pulley and cord arrangement move the bar up and down on rotation of the knob. A resiliently biased member is positioned at the top of the frame for gripping the top of the sheet.

3,579,889

ANESTHETIZING GUN FOR USE IN SLAUGHTERING ANIMALS

Adolf Pallich, Brno, Czechoslovakia, assignor to Zbrojovka, narodni podnik, Brno, Czechoslovakia

Filed Mar. 10, 1969, Ser. No. 805,516

Claims priority, application Czechoslovakia, Mar. 18, 1968, 2084-68


Int. Cl. F41c 3/00; A22b 3/02

U.S. Cl. 42-1

6 Claims

An anesthetizing gun to be used in connection with the slaughtering of animals. The gun has a barrel which at its muzzle end is provided with a bore through which an anesthetizing instrument is axially guided. A piston is fixed to the rear end of the instrument and is slidable in the gun barrel while a suitable structure behind the piston supplies a gas

under pressure to drive the piston forwardly to displace the instrument forwardly beyond the muzzle along its working stroke. The barrel is formed with passages communicating with the interior of the barrel and having front and rear ends displaced from each other along the barrel axis by a distance greater than the axial length of the piston, with the latter moving along these passages during part of the stroke of the



3,579,890

COLLAPSIBLE FISH NET


James D. Maxwell, 11001 S.E. 19th St., Vancouver, Wash.

Filed June 2, 1969, Ser. No. 829,519

Int. Cl. A01k 77/00

U.S. Cl. 43-12

5 Claims



A collapsible fish net including a hoop for supporting a flexible, mesh basket portion and also including a neck member secured to the hoop. The neck member has an opening therethrough which extends radially relative to the hoop, and a handle is slidably mounted in such opening for moving a portion thereof into the hoop to reduce the overall size of the net. Latch means are connected between the neck member and the handle and include a latch pin in the handle engageable with a bayonet slot in the neck member whereby the latch means are moved into a locking position for securing the handle in a use condition by a combination of relative axial movement and axial rotation of the neck member and handle. A lock member is used in the latch means to positively hold the neck member and handle latched together. The

hoop has disconnected ends secured to the neck member by frictional engagement in bores in the neck member. The hoop is made of springy material, and the disconnected ends of the hoop in the manufacture thereof are disposed apart a distance different than the distance between the bores in the neck member so that the frictional engagement of the ends of the hoop in the bores is accomplished by a springing action developed from springing the ends of the hoop to a spacing to fit in the bores.

ERRATUM

For Class 42—84 see:
Patent No. 3,580,113

3,579,891


SINGLE SELECTIVE TRIGGER SYSTEM FOR DOUBLE BARREL FIREARMS

John J. Kuzma, North Haven, and Robert I. Gawrych, Killingworth, Conn., assignors to Olin Mathieson Chemical Corporation

Filed Feb. 14, 1969, Ser. No. 799,217
Int. Cl. F41c 19/00

U.S. Cl. 42—42

2 Claims



A trigger system for double barrel firearms having a pair of hammers and a single trigger, a selector actuated by the trigger and operable to release only one of the hammers from its cocked position while permitting the other hammer to remain undisturbed in its cocked position. The selector then being operable to release the other hammer from its cocked position upon a second actuation of the trigger.

ERRATUM

For Class 43—12 see:
Patent No. 3,579,890

3,579,892


BEAD-HEAD FLY WITH DANGLING SPINNER

James O. Olvey, Sr., P.O. Box 287, La Follette, Tenn.

Filed Aug. 8, 1969, Ser. No. 848,493
Int. Cl. A01k 85/00

U.S. Cl. 43—42.11

9 Claims



A bead-head fly lure for jigging, casting or trolling for game fish, comprising a molded bead head of the weight desired. The forward right-angled end of the shank of the hook is embedded in the upper half-portion of the head in a manner to expose the line eye. The hook end of the shank projects beyond a flared neck on the rearward side of the head to accommodate either live or artificial bait, usually a

bucktail. A swivel on the bottom of the head is equipped with a snap fastener for a dangling spinner.

3,579,893

REFLECTING FISHING FLOAT


Henry S. Wolfe, Beaver Hill Bldg., Jenkintown, Pa.

Filed Dec. 23, 1968, Ser. No. 786,203

Int. Cl. A01k 93/00

U.S. Cl. 43—17.5

1 Claim



A reflecting fishing float comprising a buoyant body member preferably of generally spherical configuration having an upper hemispherical portion provided with a plurality of flat, angularly disposed reflecting surfaces thereon adapted to reflect rays from the sun directly to a viewer. The lower hemispherical portion has a smooth external configuration. A plunger means extends axially through the upper hemispherical portion and has line-attaching means thereon.

3,579,894

FISH-IMPALING AND GRAPPLING IMPLEMENT

Ephraim Henry Kidder, 617 Selma, Cadillac, Mich.

Filed Mar. 24, 1969, Ser. No. 809,513

Int. Cl. A01k 81/04

U.S. Cl. 43—6

8 Claims



A fish-impaling, grappling and landing implement embodying self-contained features which well serve the purposes for which they have been devised. An elongated handle embodies compact and convenient telescoping latch-retained sections. The forward end embodies an axial spearing prong and openable and closable grappling jaws provided with inwardly angled fish-impaling times. A shiftable latch-retained sleeve provides a ferrule which releasably fastens pivoted shank portions of the jaws in fish grappling position.

3,579,895

ARTIFICIAL FISH LURE AND METHOD OF MAKING SAME

Vernon B. Orn, 12733 S.E. 163rd, Renton, Wash., and Richard E. Cook, 9821 N.E. 16th, Bellevue, Wash.

Filed Oct. 21, 1968, Ser. No. 769,238

Int. Cl. A01k 85/00

U.S. Cl. 43—17.6

19 Claims

Artificial fish lures, such as simulated bait fish eggs, characterized by a substantially homogeneous body form,

either as single spheres or as fused clusters. A typical formulation involves highly plasticized polyvinyl chloride resin with a cured Shore-A-Durometer hardness of 3—10, and with fish-attracting odorant and plasticizer, such as salmon oil, dispersed throughout each spherical egg and continually forming a milky emulsion at the surface when the egg is exposed to water. A typical method of forming the simulated



eggs comprises introducing unfused plastisol into a hot liquid bath of a regulated specific gravity so that each plastisol droplet enters the bath and drops toward the bottom of the bath until its temperature increases sufficiently to lower its specific gravity whereupon each droplet rises to the surface of the bath as a substantially spherical body. The spherical bodies are then removed and cooled, either singly or as clusters.

3,579,896

SPRING-OPERATED FISHING ROD DEVICE

Thomas Flottorp, 207 Argyle St., Regina, Saskatchewan, Canada

Filed July 18, 1969, Ser. No. 842,919

Int. Cl. A01k 91/02

U.S. Cl. 43—19

2 Claims



A device consisting of a tension spring secured by one end thereof to a rod and having an ejector rod extending through the spring to the other end, terminating in a finger-engaging portion so that the spring can be extended, thus drawing the ejector through the spring. A socket is provided on the other end of the ejector rod within which a lure assembly may be engaged so that when the spring is released, the ejector rod is moved forwardly thus ejecting the lure in axial alignment with the coil spring.

3,579,897

FISH-CATCHING APPARATUS WITH SNAP-ACTUATABLE HOOKS

Dean V. Babst, 31 Linden Road, Ho-Ho-Kus, N.J.

Filed Apr. 18, 1969, Ser. No. 817,524


Int. Cl. A01k 83/00

U.S. Cl. 43—35

5 Claims

Fish-catching apparatus including a spring mechanism having a pair of spring legs with fish hooks extending toward each other from each of the legs. The spring mechanism biases the legs toward each other and a trigger is fixed relative to one leg and releasably fixable relative to the other leg for holding the legs and hooks apart from each other against the bias of the spring. When a fish bites at the apparatus the

fish will strike the trigger moving the trigger from between the spring legs to allow the legs and hooks to move toward each other so the fish biting at the apparatus will be caught on at least one of the hooks.



3,579,898

BUBBLE BLOWING DEVICE

Rolf Hein, Gartenstrasse 85, Tübingen, Germany

Filed Jan. 21, 1969, Ser. No. 792,723


Claims priority, application Germany, Jan. 25, 1968,

P 16 78 342.9

Int. Cl. A63h 33/28

U.S. Cl. 46—7

10 Claims



A compact bubble blowing device wherein a film-forming bubble solution and the member from which the bubbles are blown, are contained in one unit. The member is projected out of, and retracted into, the solution through a singlehanded operation of the device.

3,579,899

TOY HAY BALER


Amos F. Hannah, Hollister, Calif. (Star Rte. Box 239, Snelling, Calif. 95369)

Filed Sept. 12, 1968, Ser. No. 759,415

Int. Cl. A63h 33/30

U.S. Cl. 46—39

4 Claims



A mechanical toy for baling hay, the toy including operative mechanism for feeding and compressing hay material within a press so to form rectangular configured hay bales which are tied together so to retain their shape.


3,579,900

TOY WATERCRAFT

David Argent Brown, 46 Willway Ave., Richmond, Va.
Filed Dec. 30, 1968, Ser. No. 787,781
Claims priority, application Great Britain, Jan. 3, 1968, May
10, 1968, 461/68; 22272/68
Int. Cl. A63h 23/02

U.S. Cl. 46-93

13 Claims



A toy watercraft propelled by a rowing action. The cars are driven by a motor through a double cam device which imparts reciprocating horizontal and vertical components of motion to the oars so that they move in oblong paths, the longest axis of the oblong being parallel to the water surface.


3,579,901

KALEIDOSCOPE PULL-TOY CONSTRUCTION

Leslie Perhacs, Jr., Topanga, Calif., assignor to Cragstan Industries, Inc., New York, N.Y.
Filed May 28, 1969, Ser. No. 828,633
Int. Cl. A63h 11/10

U.S. Cl. 46-103

19 Claims



The present invention pertains to a pull-toy construction employing a horizontally disposed kaleidoscope assembly wherein there is provided means for translating the rotational movement of the wheels of the toy about a horizontal axis into rotational movement of the kaleidoscope assembly about a vertical axis, and including means for translating the wheel rotation about a horizontal axis into movement of other parts of the toy with various movement patterns in various planes of motion, and for also producing audible effects in combination therewith.

3,579,902

DOLL STRUCTURE INCLUDING APPENDAGE WITH FASTENER TRAPPED THEREIN FOR CONNECTING TO TORSO

Brian G. Osborne, Manhattan Beach, Calif., assignor to Mat-tel, Inc., Hawthorne, Calif.

Filed Mar. 5, 1969, Ser. No. 804,503


Int. Cl. A63h 11/00

U.S. Cl. 46-149

4 Claims

A walking doll wherein each leg can be attached to the torso after the leg has been completely finished, to eliminate extensive handling of the entire doll. The leg has two housing

halves, one formed with a mount for holding a fastener which locks onto a torso shaft pushed into the leg, and the other



half constructed to trap the fastener on the mount until the torso shaft is inserted into the leg.


3,579,903

ANIMAL CALL

Johnny E. Stewart, P.O. Box 7765, Waco, Tex.
Filed Sept. 9, 1968, Ser. No. 758,329
Int. Cl. A63h 5/00

U.S. Cl. 46-180

9 Claims



This disclosure relates to an animal call of the type adapted to simulate the sounds of game birds and other wild life, and includes a tubular body through which air is blown to vibrate a reed for generating sound waves and a depressible plunger for contacting the reed to vary the pitch as desired, the plunger being constructed of relatively soft resilient material and being disposed immediately adjacent a mouthpiece end of the tubular body whereupon the plunger can be depressed by a user's mouth, lips or teeth thus leaving his hands free to manipulate a gun, camera or other instrument.

3,579,904

TOY RAILROAD ASSEMBLY


Robert Genin, Scarsdale, N.Y., assignor to Child Guidance Toys, Inc., Bronx, N.Y.

Filed July 7, 1969, Ser. No. 839,180

Int. Cl. A63h 19/36

U.S. Cl. 46-216

8 Claims



A versatile toy railroad assembly in which various track layouts may be formed by different arrangements of square boards, each board having a depressed track section therein adapted to communicate with track sections on contiguous

3,579,907

AUTOMATED CONTROLLED ENVIRONMENT FOR CONTINUOUS PRODUCTION OF PLANT LIFE


Rodney J. Graves, 119 E. Hancock, Williams, Ariz.

Filed Oct. 3, 1969, Ser. No. 863,620

Int. Cl. A01g 9/18, 31/00

U.S. Cl. 47-17

7 Claims



An automated controlled environment system for the continuous production of plants in which there is provided a cool, low-light environmental unit for the production of hydroponic oat, barley and the like grass plants.

3,579,908

SUPPORT FOR GROWING PLANTS


John Robert Morgan, Palmer Hill Road, Old Greenwich, Conn.

Filed May 12, 1969, Ser. No. 823,597

Int. Cl. A01g 17/06; B05b 13/02

U.S. Cl. 47-45

15 Claims



Plant support devices are provided in the form of a multiflanged tubular member having apertures in the flanges to receive tie means, such as string or rope. One end of the device is conical and the flanges are beveled to facilitate driving it in the ground. Apertures are provided in the conical end to permit liquid placed in the tubular section to drain slowly outward into the ground adjacent plant roots. An elaborate support system such as for vines may be provided by connecting a plurality of such devices together with tubular branch connectors. Modifications include outlet openings along the length of horizontal tubes to permit spray patterns of liquid introduced through a branch of one of the branch connectors. Various other modifications are also provided.

3,579,905

AIRCRAFT, BATTERY AND BATTERY-CARRYING MEANS, WHEREIN THE CONDUCTIVE WIRES SERVE AS MANIPULATING WIRES


James T. Radford, 1219 Van Buren, Houston, Tex., and
Ronald A. Mizrany, 4321 Greeley, Houston, Tex.

Filed Oct. 16, 1967, Ser. No. 675,417

Int. Cl. A63h 27/04

U.S. Cl. 46-244

7 Claims



A fractional horse power motor in a toy aircraft has slack conductive wires therefrom connected to opposite ends of the crossarm of a pivotally mounted bellcrank with its short arm connected to control the elevator. From the crossarm the wires extend for operative distance to a handle, including a switch and thence to a battery housed in a case having a shoulder strap. A single operator needs only to hold the handle and to carry the power source, as a battery, at which the wires terminate; thus pressing the switch drives the engine and manipulating the wires for bellcrank movement controls flight elevation.

3,579,906

MINIATURE STEERABLE VEHICLE AND TRACK SYSTEM THEREFOR


David H. La Forge, R.R. 1, Box 648, Makawao, Hawaii

Filed Dec. 19, 1969, Ser. No. 886,572

Int. Cl. A63h 33/26

U.S. Cl. 46-244

30 Claims



A miniature four-wheeled vehicle is provided with a solenoid having a linearly movable armature for turning the steering wheels in response to electrical impulses received by a set of contact brushes on the vehicle which selectively engages the conductive track system on a supporting surface which also supplies power to the vehicle and includes conductive guiding areas on the surface for steering the vehicle through a switch in the track system.

3,579,909


BALANCED DOOR

Louis L. Schacht, New York, and Ralph Turner, Queens County, N.Y., assignors to Schacht Associates, Inc., Bronx, N.Y.

Filed July 16, 1969, Ser. No. 842,151
Int. Cl. E05d 15/30

U.S. Cl. 49—252

3 Claims



A balanced door, namely, a door which swings on upper and lower arms which are connected thereto and to a pivotally movably vertical torque rod, is provided with a door check and closer device, the arrangement being such that the door check and closer device can be readily installed through the top of the door and readily removed through the top of the door, when the door is opened and tilted in its own plane in a direction away from the torque rod, thereby making it unnecessary to remove the door from the door frame to install or remove the door check and closer device. The connections between the door and said arms are within the door thus eliminating the pivot projections referred to in the art as "blisters" or knuckles.

3,579,910


LOCKING MEANS FOR A VERTICALLY MOVABLE DOOR

Allan E. Wetter, Bloomfield Hills, Mich., assignor to Byrne Doors, Inc., Ferndale, Mich.

Filed Mar. 27, 1969, Ser. No. 811,175
Int. Cl. E05d 17/00

U.S. Cl. 49—322

11 Claims



Safety latch means for locking a vertically movable door against accidental descent. A latch carried by the door has a notch which normally freely receives a guide angle flange extending along the path of door movement. The latch turns or cocks to cause the notch to bind upon the flange and lock the door against accidental descent in response to the failure of the cable.

ERRATUM

For Class 49—394 see:
Patent No. 3,579,934

3,579,911


BALL BEARING LAPPING MACHINE

Floyd Steinmetz, 205 W. Timonium Road, Timonium, Md.

Filed June 5, 1968, Ser. No. 734,683
Int. Cl. B24b 7/00, 9/00

U.S. Cl. 51—3

8 Claims



A ball bearing lapping machine having members with relatively rotatable concentric conical portions, one of the conical portions provided with a spiral groove, a ball feed device for depositing the ball bearings to be lapped at the top of the members, the ball bearings, entering the spiral groove and rolled therealong between the members upon rotation of one member with respect to the other, a receptor to receive the ball bearings as they are discharged upon completion of their rolling course through the spiral groove and an elevator for returning the ball bearings from the receptor to the ball feed device for recycling the ball bearings through the machine. A means to supply lapping compound to space between the conical members and the ball bearings therein is also provided.

3,579,912


UNIVERSAL CLAMP FOR ABRASIVE TOOL

Walter B. Panko, Chicago, and Julius P. Steindler, Wilmette, Ill., assignors to Engis Equipment Company, Morton Grove, Ill.

Filed Apr. 25, 1969, Ser. No. 819,244
Int. Cl. B24b 7/00, 9/00

U.S. Cl. 51—59SS

2 Claims



A universal clamp having specially formed gripping faces and adapted to hold lapping rods and lapping sticks of various diameters as well as abrasive stones and other abrasive tools in any position of use.

3,579,913

HYDROELECTRICAL CONTROL FOR A ROTARY SURFACE GRINDER

Kinichiro Suzuki, Tokyo, Japan, assignor to Sansei Manufacturing Co., Ltd., Minato-ku, Tokyo, Japan


Filed Dec. 12, 1968, Ser. No. 783,345
Int. Cl. B24b 7/02

U.S. Cl. 51—95

1 Claim

Hydroelectrical control for a rotary surface grinder having

a table driven by an electric motor for its controlled revolution and by a hydraulic system for its reciprocal movement correlated with the controlled revolution.



tion and by a hydraulic system for its reciprocal movement correlated with the controlled revolution.

3,579,914


WORK DRIVING DEVICE

Ralph E. Price, Waynesboro, Pa., assignor to Landis Tool Company, Waynesboro, Pa.

Filed July 12, 1968, Ser. No. 744,350
Int. Cl. B24b 17/02; B25b 41/06

U.S. Cl. 51—101

12 Claims



This disclosure relates to a work driving apparatus, particularly for a cam contour grinder, for applying a driving torque at two angularly spaced points on a workpiece so that the entire force transmitted by the work driving apparatus acts to turn the workpiece and there is no force to cause radial displacement of the workpiece. The work driving apparatus is particularly adapted for use in conjunction with a workpiece having a flange at one end and an orienting hole in the flange. The work driving apparatus includes a driving block which carries a locating pin which is proportioned for a close fit in the hole in the workpiece flange to maintain the workpiece in a predetermined oriented position during the grinding thereof. The driving block is mounted for floating movement so as to compensate for variations in workpieces and is pivotable about the axis of the locating pin to engage a jaw carried thereby with the workpiece at a point remote from the locating pin.

3,579,915

FREE ORBITAL SURFACE TREATING TOOL


James Glenn Satterthwaite, 1 Dogwood Trail, Chesapeake, Va., and Waverly Hope Wilcox, 1214 Sheppard Ave., Norfolk, Va.

Filed Nov. 8, 1968, Ser. No. 774,393
Int. Cl. B24b 23/02

U.S. Cl. 51—120

10 Claims

There is provided a tool for treatment or modification of a surface, for example, buffing, having drive means including a shaft, an eccentric member secured to the shaft and rotatable therewith, a supporting member which is adapted to support a surface modifying agent, e.g. buffing material and buffing compound, the support member being characterized by a



and the eccentric to enable the eccentric to rotate freely relative to the support member.

3,579,916


POLISHING MACHINE

Stephen A. Boettcher, Deerfield (Riverwoods), and Louis F. Simonetti, Morton Grove, both of, Ill., assignors to Speedfam Corporation, Des Plaines, Ill.

Filed Nov. 15, 1968, Ser. No. 776,024
Int. Cl. B24b 7/04

U.S. Cl. 51—131

6 Claims



A polishing machine spindle assembly and associated load plate unit having passageway means opening at the lower surface of the unit and adapted to be placed under vacuum for maintaining a workpiece in engagement with the lower surface of the unit.

3,579,917


POLISHING MACHINE

Stephen A. Boettcher, Deerfield (Riverwoods), and Louis F. Simonetti, Morton Grove, Ill., assignors to Speedfam Corporation, Des Plaines, Ill.

Filed Nov. 15, 1968, Ser. No. 776,023
Int. Cl. B24b 7/04

U.S. Cl. 51—131

7 Claims



A polishing machine load plate unit to which workpieces are affixed for polishing, and through which a liquid is selectively circulated.

3,579,918

PLATEN-TYPE BELT GRINDER


Robert L. Schaller, Camillus, N.Y., assignor to Sundstrand-Engelberg Inc., Syracuse, N.Y.

Filed July 23, 1969, Ser. No. 844,149

Int. Cl. B24b 21/00, 23/06, 25/00

U.S. Cl. 51-148

5 Claims



The frame of the grinder includes inner and outer spaced apart sidewalls. The abrasive belt idler roll is carried by a cylinder and piston structure which is fixed to one of the sidewalls. The platen-supporting member is fixed to the other sidewall, whereby stresses developed in the cylinder are not transmitted to the platen.

3,579,919

VIBRATING MACHINE


Charles E. Jones, Gates Mills, Ohio, assignor to Sabin Machine Co., Cleveland, Ohio

Filed May 16, 1969, Ser. No. 825,227

Int. Cl. B24b 31/06

U.S. Cl. 51-163

10 Claims



A machine for finishing parts by vibrating the parts in the presence of an abrasive media. The machine comprises a rounded bottom tube which is pivotally suspended in a frame around the tub, the suspension being by means of axially aligned shafts which project from end walls of the tub. These shafts are offset to one side of the tub center of gravity. Along the bottom of the tub on the opposite side of the center of gravity are three eccentric weights rotated on axes which are parallel with each other and with the tub pivot axis. The weights are so phased as to produce centrifugal forces which effectively vibrate the tub, and at the same time minimize the vibration transmitted to the frame around the tub.

3,579,920

POLISHING MACHINE FOR WORKPIECES

Ernst Helberger, Reichenbach Rechberg, Germany, assignor to Jualdipex S.A., Zurich, Switzerland


Filed Dec. 23, 1968, Ser. No. 785,987

Claims priority, application Germany, Dec. 22, 1967, P1652065.3

Int. Cl. B24b 31/02

U.S. Cl. 51-164

20 Claims



A polishing machine is provided which has an oscillatable frame supporting at least one hollow drum adapted for receiving the workpieces to be treated, each drum being rotatably supported from a pair of discs which in turn are supported from the frame for rotation about an axis which is perpendicular to the axis of rotation of the frame and is in the same plane therewith. The drum undergoes movement influenced by three independent rotations which are respectively controllable.

3,579,921

ROCK-POLISHING RUMBLE


Donald J. Bobo, 8511 Roosevelt Way N.E., Seattle, Wash.

Filed Apr. 3, 1969, Ser. No. 813,060

Int. Cl. B24b 31/02

U.S. Cl. 51-164

10 Claims



A molded tubular drum of elastomeric material having a generally cylindrical external shape and a polygonal internal shape. Identical and closures for the drum, each also of molded elastomeric material and each having a radial end wall, an axially inwardly extending center plug shaped to snugly fit within the inner cavity of the drum, and a peripheral drive rim. A girth rib and girth groove seal is provided between each drive rim and the drum. The drive rim has a reduced diameter portion axially inwardly of the seal which receives a squeeze band acting to force the drive rim radially inwardly and the sealing surfaces of the groove and rib together.

3,579,922

APPARATUS FOR ABRADING ARTICLES

Nicholas J. Mandonas, Medford, and Paul A. Ryll, Haverhill, Mass., assignors to Western Electric Company, Incorporated, New York, N.Y.

Filed Oct. 11, 1968, Ser. No. 766,735

Int. Cl. B24b 49/04


U.S. Cl. 51-165

7 Claims

Apparatus for fine lapping of thin piezoelectric crystals to a desired resonant frequency characteristic includes a number of holders urging and lapping the crystals against a vibrating, relatively movable lapping plate bearing very fine

abrasive particles. Probes are successively pivoted into engagement with selected holders, one at a time, during lapping to sample the instant resonant frequency of each of the vibrating crystals by coupling the crystals successively into a

is ground into a split point, whereby the drill can be ground in two ways in a single step of process. This means a great advantage over the prior art in speed of the processing and quality of the resultant product.



test circuit. While lapping of the other crystals continues, a crystal which has attained the desired frequency characteristic may be withdrawn with its holder and replaced by another holder and crystal.

3,579,923

DRESSING TOOL METHOD AND MEANS


Prentiss Whited, 603 N. Jackson, Pratt, Kans.

Filed Aug. 4, 1969, Ser. No. 847,024

Int. Cl. B24d 5/00, 7/00; B24b 19/00

U.S. Cl. 51-209R

7 Claims



This invention relates to a method and means of dressing abutting shoulders of oil well drill pipe stems on location. More particularly, this invention is a dressing tool means having spring-biased abrasive plates engageable with the shoulders of mating pipe stems. The method of dressing pipe joints involves the steps of utilizing the working tongs and the drill rotary table for the required power to efficiently and effectively dress abutting shoulders of drill pipe stems on location.

3,579,924

METHOD FOR CONTINUOUSLY GRINDING A DRILL TIP END INTO A NORMAL SHAPE AND INTO A SPLIT POINT

Mataichi Saito, No. 13-3 6-chome Chuo, Ota-ku, Tokyo-to, Japan

Filed Apr. 16, 1968, Ser. No. 721,683


Claims priority, application Japan, May 10, 1967, 42/29150

Int. Cl. B24b 19/64, 3/24

U.S. Cl. 51-288

1 Claim

The specification discloses a novel method for continuously grinding a drill tip end into a normal shape and into a split point form, without removing and replacing the drill between the normal shape grinding procedure and the split point grinding procedure. A drill to be ground is first ground at its tip end portion into a normal shape, and subsequently but continuously to the preceding procedure the drill tip end



3,579,925

ABRASIVE WHEEL


William P. Densmore, Worcester, Mass., assignor to Norton Company, Troy, N.Y.

Filed Dec. 2, 1968, Ser. No. 780,404

Int. Cl. B24d 9/00

U.S. Cl. 51-330

1 Claim



A rotary abrasive device having a plurality of independent depending leaves mounted internally of a rotary hub structure for abrading or polishing purposes.

3,579,926

SANDBLASTING STENCIL AND METHOD OF MAKING SAME


Anthony Mario Gaspari, Montreal, Quebec, Canada, assignor to Pall (Canada) Ltd., Montreal, Quebec, Canada

Filed Aug. 2, 1968, Ser. No. 749,722

Int. Cl. B24b 55/00

U.S. Cl. 51-262

9 Claims



This invention provides a method for precutting sandblasting stencil by cutting with a die a two-ply stencil comprising a soft, elastomeric masking sheet of material resistant to erosion by sandblasting, having on one face a layer of adhesive which is removably bonded to a harder, flexible nonelastomeric plastic backing sheet, so as to cut out the

stencil pattern through the masking sheet without cutting through the backing sheet. The second face of the masking sheet is then covered with an adherent sandblast-erodable retaining sheet to form a three-ply die-cut stencil sheet. For use in sandblasting, the backing sheet is stripped off, exposing the adhesive layer on the masking sheet, which is thereby bonded to a stone surface after the cutout portions are removed. This invention also provides the three-ply die-cut stencil sheet comprising sandblasting-erosion-resistant masking sheet, an adhesive layer bonded to a backing sheet on one surface of the masking sheet and an adherent retaining sheet bonded to the second face of the masking sheet.

3,579,927


VIBRATORY GRINDING METHOD

Loring Coes, Jr., Princeton, Mass., assignor to Norton Company, Worcester, Mass.

Division of Ser. No. 597,598, Nov. 29, 1966, Pat. No. 3,451,171.
Int. Cl. B24b 1/00

U.S. Cl. 51—281

4 Claims



This invention relates generally to improvements in methods and machines for grinding wheels, and particularly to methods and machines for providing intermittent pressure contact between a grinding wheel and a workpiece.

In a particular embodiment of the invention, intermittent or vibratory pressure is applied to successive positions on the cutting surface of a grinding wheel in grinding contact with a workpiece by mounting a drive member or a gear having a given number of teeth on the wheel spindle for driving or meshing with a driven member or gear with an unbalanced weight distribution and having a different number of teeth from the number on the driver gear.

ERRATUM

For Class 51—315 see:
Patent No. 3,579,933

3,579,928

SELF-AIR COOLING ABRADING WHEEL


Gerhard R. Held, 22644 Shiell Drive, Mount Clemens, Mich.

Filed July 14, 1969, Ser. No. 841,439

Int. Cl. B24b 55/02

U.S. Cl. 51—356

4 Claims



A self-air cooling abrading wheel having a flat annular web and an axially enlarged annular rim with a peripheral abrading

surface thereon, and with a first series of elongated angularly related slots formed in said rim around its periphery extending inwardly of the rim for a portion of its width, said slots having air inlets adjacent said web and outlets extending radially outward of said rim, and a second series of said angularly related slots extending inwardly from the other side of said web, the slots of the second series being alternated with the slots of the first series and independent thereof.

3,579,929

FLEXIBLE STRUCTURE ORIENTATION CONTROL


Philip D. Holthenrichs, Malvern, and Robert P. Wanger, Valley Forge, Pa., assignors to General Electric Company

Filed Jan. 29, 1969, Ser. No. 794,874

Int. Cl. F16f 7/00, 15/30; F04h 12/00

U.S. Cl. 52—1

3 Claims



Separated parts of a flexible structure are maintained in a predetermined desired orientation with respect to each other against the action of distorting forces by applying to selected part or parts of the structure inertially developed torques (e.g. from flywheels) to main the selected part in its desired orientation with respect to a selected reference part of the structure.

3,579,930

SNOW DEFLECTOR UNIT


Herman G. Murphy, P. O. Box 446, Incline Village, Nev.

Filed July 17, 1969, Ser. No. 842,616

Int. Cl. E04d 13/10

U.S. Cl. 52—24

10 Claims



A sheet metal snow deflector unit comprising an apertured baseplate having a tapered column extending upwardly therefrom into a generally pyramidal shaped deflector secured to the baseplate. The deflector comprises a pair of substantially triangular sidewalls connected along a line which extends at a predetermined angle of inclination relative to the baseplate to define a cleavage edge for a mass of snow moving down an inclined roof to which the deflector unit is secured to protect a vent pipe projecting through the roof into the deflector. The front wall of the deflector comprises a wire mesh screen to permit exhaust to emanate from the vent pipe.

3,579,931

METHOD FOR POST-TENSIONING TENDONS

Frederic A. Lang, Landenberg, Pa., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

Division of Ser. No. 712,796, Mar. 13, 1968, Pat. No. 3,513,609,


Continuation-in-part of application Ser. No. 623,709, Mar.

16, 1967, now abandoned.

Int. Cl. E04c 3/29, 5/01; E04g 21/12

U.S. Cl. 52—741

5 Claims



An anchoring system is provided wherein the end of a post-tensioned tendon extending from a concrete structure is encased in a metallic sheath and the sheath is crimped in a series of reversals of increasing angularity in the direction away from the concrete structure.

3,579,932

CABLE-SUSPENDED ROOF STRUCTURE

Ross T. Atkinson, Federal Way, Wash. (2nd & University


Bldg., Suite 406, Seattle, Wash. 98101)

Filed Apr. 28, 1969, Ser. No. 819,821

Int. Cl. E04b 7/14

U.S. Cl. 52—83

8 Claims



A cable-suspended roof structure is provided to span wide areas as, for example, stadiums, coliseums, arenas, playing fields and the like. More specifically, a roof is provided in which cables under tension extend between substantially centrally located tension ring means and a surrounding continuous or enclosed ringlike compression member, their ends being anchored securely therein and said cables being under tension. An upper and a lower double layer of cables is employed and compression spreader means spanned between each cable of either set and each of the proximate cables of the other set.

3,579,933

METHOD OF MANUFACTURING A CAM FOR USE IN AN IGNITION DISTRIBUTOR

John Snell, Welford-On-Avon, England, assignor to Joseph Lucas (Industries) Limited, Birmingham, England

Filed Jan. 7, 1969, Ser. No. 789,504


Claims priority, application Great Britain, Jan. 8, 1968,

981/68

Int. Cl. B24b 1/00

U.S. Cl. 51—315

1 Claim



A cam for use in a distributor in a road vehicle is made by grinding the cam to the desired profile in the usual way, this

operation leaving the cam surface with sharp edged asperities defining therebetween channels which in use store lubricant. The cam is then placed in a container with abrasive particles and the container is so moved that the particles collide with the cam surface and round off the sharp edges of the asperities without removing the asperities.

3,579,934

MAGNETIC DOOR CATCH WITH RISER


Raymond L. Pietsch, Flint, Mich., assignor to The Engineered Products Company, Flint, Mich.

Filed Sept. 17, 1969, Ser. No. 858,650

Int. Cl. E05c 19/16

U.S. Cl. 49—394

9 Claims



A combined door catch and riser unit having a magnet and two exposed pole faces carried by a body having opposed flanges providing a mounting surface. A ramp with an inclined surface projects generally perpendicular to the pole faces and is carried by the body adjacent its mounting surface to raise a door when it engages the catch.

3,579,935

SYSTEM FOR ERECTING MULTISTOREY BUILDINGS


James L. Regan (409 Dunkel St., Fairbanks, Alaska, 99701), and David L. Garnhart, Hayward, Calif.

Filed June 14, 1968, Ser. No. 737,022

Int. Cl. E04b 1/35

U.S. Cl. 52—126

25 Claims



A slab lifting jack assembly system associated with a vertical H-beam having a row of aligned vertical openings on each side of each flange of the beam with the jack assembly having an upper set of pins movable by hydraulic cylinder means into and out of engagement with the openings in the flanges

and a lower set of pins similarly movable with a main hydraulic cylinder connected between an upper frame supporting the upper pins and a lower frame supporting the lower pins with the upper frame also being connected to a concrete slab so that extension of the hydraulic cylinder serves to lift the slab when the upper pins are retracted out of engagement with the flange openings and the lower pins are extended to remain in the flange openings so that the slab is consequently lifted by extension of the frame cylinder and with control means including logic circuitry for detecting and preventing malfunctions of the system.

3,579,936


POLE BASE PROVIDING ADJUSTABILITY FOR ANGULAR AXIAL ALIGNMENT OF THE POLE

Gustav Mattias Andersson, Barnhemsgatan 10, 731 00 Kopling, and Ernst Henning Ture Granstrom, Kopling, Sweden
Filed May 23, 1969, Ser. No. 827,416

Claims priority, application Sweden, May 29, 1968, 7188/68
Int. Cl. E02d 27/42; F16b 2/14

U.S. Cl. 52—297

4 Claims



An arrangement for providing an angular adjustment of the vertical axis of a post relative to a foundation block in which the post is mounted includes an annular guiding retaining means, having a convex surface for making a line contact with the post, carried in an upper end of the foundation block together with a plurality of jaw means for effecting lateral adjustment of the lower end of the post within the foundation block.

3,579,937


FOAM PLASTIC PANEL WITHOUT TRUSS MEMBERS

Edward E. Lukens, 1427 Lane Ave., Bethlehem, Pa.
Filed May 29, 1969, Ser. No. 828,996

Int. Cl. E04c 2/22; E04b 1/24

U.S. Cl. 52—309

5 Claims



A lightweight insulating panel is provided of large area suitable for building use which consists of a hard top and immediately there-below a lath or wire mesh with truss members fastened to the lath and rigid plastic foam surrounding the lath and the truss members.

3,579,938

SCREED HOLDING DEVICE

Iner O. Hanson, P.O. Box 918, Whitefish, Mont.
Filed May 8, 1969, Ser. No. 823,119


Int. Cl. E04f 13/04

U.S. Cl. 52—365

4 Claims

A device for supporting a screed at the proper elevation in a concrete form. The device has a convenient base which is

attached to the lower surface of the form, and an upright support that is releasably engaged in the base. The upright



member has a bracket adjustably and releasably supported therealong to receive the screed member therein.

3,579,939


FRAME STRUCTURE FOR GLASS OR SOLID PANEL WALLS

Ellis V. Eichman, Irving, Tex. (790 Fruitdale Road, Brownsville, Tex. 78520)
Filed Oct. 17, 1969, Ser. No. 867,230

Int. Cl. E04b 2/88

U.S. Cl. 52—397

8 Claims



A frame structure for glass or solid wall panels providing for the arrangement of the glass or other type panels in a common plane and in such manner as to prevent lateral movement thereof due to vibrations caused by traffic movement, wind pressures, and other factors, minimizing the framing profile and the number of parts comprising the structure by providing a single frame element and panel retention means of unique design for fabricating all parts of a frame structure.

3,579,940


ROOFING TILE

James O. Greenleaf, Los Angeles, Calif., assignor to Stepan Chemical Company
Filed June 13, 1969, Ser. No. 833,107

Int. Cl. E04d 1/20, 3/32

U.S. Cl. 52—542

6 Claims



Plastic molded roofing tile arranged so that laterally positioned tiles overlap in a ridge and channel arrangement. An

upstanding flange at the top end of this overlap dams water flow against movement in that direction. Longitudinally related tiles are also overlapped with an upstanding flange at the upper end of the lower tile engaging in a transverse groove through reinforcing ribs in the bottom of the upper tile. Upstanding nailing bosses in the lower tile engage between the flanges to provide a locator stop to locate and rigidize the interrelationship. In one embodiment, the upstanding flange lockingly engages the downwardly directed ribs to prevent direct upward lifting of the upper tile.

3,579,941


WOOD PARQUET BLOCK FLOORING UNIT

Howard C. Tibbals, P.O. Drawer A, Oneida, Tenn.
Filed Nov. 19, 1968, Ser. No. 777,070

Int. Cl. E04b 5/00; E04f 15/04, 15/16

U.S. Cl. 52—384

6 Claims



Wooden parquet block flooring incorporating cellular foam in multiple parquet block units having rubberlike flexible adhesive joining tongue and groove formations within the multiple block unit.

3,579,942

FASTENER ANCHORED IN HONEYCOMB PANEL

John M. Cole, New Hope, Pa., assignor to Thomas & Betts Corporation, Ellizabeth, N.J.
Filed Dec. 5, 1969, Ser. No. 882,568

Int. Cl. E04b 2/28; F16b 13/08

U.S. Cl. 52—615

10 Claims



A honeycomb fastener retainer includes the combination of a fastener receiving body member designed to be inserted through an opening in one surface of the panel and into a hollowed out cavity area of the panel core where it is retained in place by means of body attached, elongated, flexible finger elements which collapse in a limited manner to permit the body member to pass through the outer panel opening which spread out to a normal position beneath the panel surface in the area of the outer panel opening to permit removal of the body member from the panel. A cap member covers the panel opening, and interlocks with the finger element of the body member and engages the panel surface by suitable means to prevent rotation of the fastener retainer assembly upon its receiving a threaded fastener.

3,579,943


PANEL FRAME ASSEMBLY

Wayne C. Tam, Monterey Park, Calif. (752 La Portada, South Pasadena, Calif. 91030)
Filed May 28, 1969, Ser. No. 828,654

Int. Cl. E04c 2/38

U.S. Cl. 52—656

7 Claims



In a disclosed panel frame system at least one sill assembly is supported by an elongated base member, with a pair of vertically extending mullion or jamb assemblies disposed on the base member at opposite ends of the sill assembly, and with an elongated head channel assembly secured to the ceiling in alignment with the base member. The sill, mullion, and head channel assemblies each include a removable plate which may be snapped into rigid mating relationship with the sill, mullion, or head channel members. The inwardly facing surfaces of the sill, mullion and head channel plates may be provided with a panel receiving recess. The lower extremity of a mullion member broad wall defines a pair of notches which snugly receive flanged sidewalls of the base member. A single base rail embodiment and a ledge sill embodiment of the frame system are also disclosed.

3,579,944

APPARATUS AND METHOD FOR BANDING GROUPS OF ENVELOPES


Vincent E. Heywood, Worcester; Donald H. Bushey, Shrewsbury, and William A. Chapman, Jr., Hubbardston, Mass., assignors to United States Envelope Company, Springfield, Mass.

Division of Ser. No. 502,759, Oct. 18, 1965, Patn. No. 3,399,788, Continuation-in-part of application Ser. No. 326,024, Nov. 26, 1963, now abandoned.

Int. Cl. B65b 27/08, 57/14; B65h 33/08

U.S. Cl. 53—3

7 Claims



In an apparatus and method for banding envelopes, envelopes first advance in succession from an envelope making machine toward a banding station by moving perpendicular to their faces while supported on their edges in face to back relation. Immediately prior to reaching the banding station the forwardmost group is segregated from the advancing succession by a laterally movable pusher which shifts the group endwise to the banding station where it is temporarily sup-

ported between spaced side fingers. At the banding station is an opening in the floor plate which extends across the width of the envelope group and which is straddled by the length of the group. A sliding plate covers the opening during the movement of the envelope group to the banding station. After the envelope group is properly positioned at the banding station the sliding plate is withdrawn and a band placed across the top of the group is pressed by two vertically moving blades down both sides of the group. The band is of such a length and so positioned that the portion thereof extending along one side of the envelope group terminates at approximately the bottom edge of the group and so that the portion thereof extending along the other side of the group extends below the bottom edge of the group and through the floor plate opening. The sliding plate is thereafter returned to closing relation with the opening and as it is so moved its forward edge carries the protruding portion of the band along the bottom of the group. Other means thereafter fold the remaining free end portion of the band upwardly into sealing engagement with the opposite end portion and the group is then pushed from the banding station by the next following group.

3,579,945

APPARATUS FOR REDUCING THE ATMOSPHERIC OXYGEN CONTENT OF FLUENT SOLID POURABLE MATERIALS BY GAS EXCHANGE

Norbert Buchner, Beutelsbach, Wurttemberg, and Klaus Domke, Stuttgart-Weilimdorf, Germany, assignors to Fr. Hesser Maschienenfabrik Aktiengesellschaft, Stuttgart-Bad Cannstatt, Germany

Filed Aug. 8, 1969, Ser. No. 848,479


Claims priority, application Germany, Aug. 22, 1968,

P 17 86 137.9

Int. Cl. B65b 31/04

U.S. Cl. 53-112

11 Claims



To prevent spoiling of fluent solid materials by the action of atmospheric oxygen entrapped in the material during the packaging thereof in a form, fill and seal machine, the materials are subjected to a counterflow treatment with a gas which will take up the oxygen. For this purpose there is a gas supply conduit opening into the zone of the materials in the feed pipe of the machine, and a gas-storage chamber in the forming mandrel of the machine above this zone.

3,579,946

METHOD OF PRODUCING A ROLLED BUNDLE OF PREFORMED VALLEY FLASHING

Robert S. Graving, Rte. 4 Box 432, Osseo, Minn.

Filed Oct. 1, 1969, Ser. No. 862,898


Int. Cl. B65b 63/04, 61/02, 13/02

U.S. Cl. 53-21FW

5 Claims

A method of producing seamless rolled valley flashing by creasing an elongated relatively narrow length of flexible sheet material along its length to provide a cross-sectionally relatively shallow V-shaped form having an obtuse included angle. The creased sheet material is positioned on a cylindrical

arbor with the obtuse included angle disposed to face radially toward the arbor and by increasing the included



angle rolled onto the cylindrical arbor and secured to provide a rolled bundle of preformed valley flashing.

3,579,947

METHOD OF PRINTING AND FOLDING A MAILING PIECE


Mario Kalman, Philadelphia, Pa., assignor to Goodway Inc., Philadelphia, Pa.

Filed Apr. 7, 1969, Ser. No. 813,892

Int. Cl. B65b 63/04; B31b 1/16, 1/72

U.S. Cl. 53-23

5 Claims



The method of printing and folding a mailing piece including the steps of running a continuous paper web, printing desired information on the web, selectively feeding insertion envelopes with previously glued tabs onto said web at one side thereof in spaced relationship, adding an axially aligned strip of glue to the other side of the said web, transversely perforating the said web intermediate the said affixed envelopes, transversely cutting the said web immediately adjacent the said perforation, rotating the said cut web portions to a folder utilizing the said perforations, transporting the said cut and folded web sections to a final folder and trimming the edges to thereby provide a finished mailing piece having a glued tab envelope inserted therein.

3,579,948

BAG HANDLING APPARATUS AND METHOD

Bernard Lerner, Hudson, Ohio, assignor to Automated Packaging Corporation, Bedford Heights, Ohio

Filed Apr. 29, 1968, Ser. No. 731,672


Int. Cl. B65b 43/04, 43/30, 43/36

U.S. Cl. 53-29

13 Claims

A chain of bags in part carried by a gas-permeable mov-

ble belt is held in place against the belt by a vacuum while the belt is advanced and a flow of gas expands a bag for load-



ing. Marginal edges of the bag chain may be isolated from the vacuum to facilitate bag expansion.

3,579,949

WRAPPING METHOD AND APPARATUS


Charles E. Michels, Racine, Wis., assignor to Wrapping Machinery Company, Inc., Franksville, Wis.

Filed Aug. 23, 1967, Ser. No. 662,674

Int. Cl. B65b 67/08

U.S. Cl. 53-33

17 Claims



Disclosed herein is a wrapping method and apparatus in which an article is positioned on a table at one side of a film web withdrawal port. At the other side of the port there is a hot-wire web-severing tool and a package rest or support in the form of a narrow, open-ended, outwardly projecting arm. A length of film web is drawn through the port upwardly and forwardly about the article to partially wrap it. The partially wrapped article is then drawn toward the operator to sweep it past the hot wire to cut the web. The article is deposited on the arm, and laterally extending film wings are folded downwardly and around the arm to the undersurface thereof. The article is then transferred to a sealing surface against which the underfolded wings are sealed.

3,579,950

METHOD OF AND APPARATUS FOR OBVIATING SPILLAGE IN MOVING CONTAINERS


Glenn V. Davis, Watertown, N.Y., assignor to Borden, Inc., New York, N.Y.

Filed Jan. 3, 1969, Ser. No. 788,753

Int. Cl. B65b 3/04, 7/28

U.S. Cl. 53-37

4 Claims



The present invention relates to a high-speed conveyor-type canning machine comprising means for supplying containers, means for affixing closures on a filled container,

comestible depositing means interposed between said supplying means and said affixing means, means for continuously advancing said containers to said depositing means and said affixing means, and means for intercepting and rotating said container prior to positioning same beneath said closure affixing means whereby a vortex is induced in said comestible to prevent overflow.

3,579,951

ARRANGEMENT FOR BAGGING ARTICLES


Louie R. Lowery, Cedar Knolls, N.J., assignor to Keyes Fibre Company, Waterville, Maine

Filed June 16, 1969, Ser. No. 833,410

Int. Cl. B65b 57/02, 43/36

U.S. Cl. 53-55

11 Claims



Arrangement for bagging articles comprises frame with conveyor on frame for propelling articles along longitudinal path of travel. Supply of flexible bags is adjacent longitudinal path of article travel, and each bag of supply has closed and open ends with portion adjacent open end thereof secured to bag retainer on frame. Bags are singly inflated open into article-receiving position in longitudinal path of article travel so that closed end of each inflated bag is downstream of opened end thereof. Conveyor propels each article into inflated bag so that momentum of propelled article tears associated bag away from bag retainer which enables next bag of supply to be inflated into article-receiving position for next article on conveyor.

3,579,952

PACKING MACHINES

Robert William Davies; Charles Thomas Hall; Dennis Hinchcliffe; Alan Keith McCombie, London, England, and Derek Henry Youngman, Maitland, Cape Province, South Africa, assignors to Molins Machines Company Limited, London, England

Filed Oct. 24, 1966, Ser. No. 590,153


Claims priority, application Great Britain, Nov. 1, 1965,

46143/65

Int. Cl. B65b 19/04, 19/12, 43/10

U.S. Cl. 53-37

63 Claims



A rotary cigarette packing machine having three layers, namely: a top layer in the form of a hopper which receives a continuous stream of cigarettes and divides them up into bundles; a bottom layer which forms open-ended packets from webs of packet material; and a middle layer which pushes the bundles into the packets, closes them and delivers them in one continuous stream. The machine rotates continuously about a vertical axis past a continuous supply of cigarettes and a continuous supply of each of the packet materials and comprises a number of sets of mechanisms, considered vertically, each of which will perform the complete packing operation so that that operation is being performed a number of times simultaneously.


3,579,953

CIGARETTE PACKERS

Goffredo Glanese, Bologna, Italy, assignor to AMF Incorporated
Continuation-in-part of application Ser. No. 734,371, June 4, 1968, now Patent No. 3,531,911, and a continuation-in-part of 734,372, June 4, 1968, now Patent No. 3,553,925. Filed May 27, 1969; Ser. No. 828,197
Int. Cl. B65b 19/04

U.S. Cl. 53-59

10 Claims



A packaging machine comprising an endless conveyor having a plurality of successive containers for receiving rodlike articles, such as cigarettes, including means for feeding a predetermined number of rodlike articles to the container from the feeder as the conveyor moves. Particularly, the feeding means comprise a vertical channel in which a plurality of superimposed cigarettes are maintained, said channel being provided with an oscillating support at its bottom which is actuated in synchronism with the passage of the containers to lower and permit the cigarettes to fall into the container.

3,579,954

CARTON-SEALING APPARATUS WITH ROTATION CONTROL


Tex Bates, Union City, Calif., assignor to The Finn Industries, Inc., Chicago, Ill.

Filed Aug. 21, 1969, Ser. No. 851,844

Int. Cl. B65b 57/00, 7/20

U.S. Cl. 53-76

7 Claims



An improved means in a carton-sealing apparatus for actuating rotation of a turn box which turns a vertically received carton to a horizontal position by a 90° turn. An elongated switch of the actuating mechanism is contacted by a carton only after it has turned to the horizontal position, and a stop member checks the advance of a following carton in the vertical position in the turn box to prevent jamming.

3,579,955

APPLICATOR FOR BAG CLOSURES


John Christie Gonyou, Toronto, Ontario, and Stanley Albert Charles Browning, Glen Williams, Ontario, Canada, assignors to Hybrid Turkeys Limited, Brampton, Ontario, Canada

Filed Feb. 27, 1969, Ser. No. 802,961

Int. Cl. B65b 7/06

U.S. Cl. 53-138

8 Claims



Bag closures in strip form so that adjacent bag closures are joined by two links therebetween, are fed through an applicator seriatim, and are applied one at a time around a gathered neck of the bag as it is drawn across the upper face of the applicator. The applicator has a restricting motion relative to its support; means are provided to restrict movements of the strip of bag closures as the body of the applicator moves downwards; other means are provided to cut one of the links between the leading and next adjacent bag closure in the strip in the applicator as near its lower limit of motion; and other means are provided to secure the bag closures within the applicator as it moves upwards, thereby advancing the strip of bag closures through the applicator seriatim.

3,579,956

PACKAGING APPARATUS


Wolfgang Hoffmann, Beaconsfield, Quebec, and Paul Wick, Valois, Quebec, Canada, assignors to Canadian International Paper Company, Montreal, Quebec, Canada

Filed June 3, 1968, Ser. No. 734,029

Int. Cl. B65b 35/50

U.S. Cl. 53-159

10 Claims



A wrapping apparatus whereby a commodity is wrapped from the bottom upwardly, the wrapping apparatus having wrapping-feeding means preferably with glue-applying means for placing glue on selected portions of the wrapper as the wrapper is fed. The commodity-feeding component for placing the commodities on the wrapper is either a one or two level device for placing single or double layers of commodities on the wrapper.

3,579,957

BAGGING APPARATUS

James Claiborne Mills, Jr., Chesterfield County, and Gordon W. Hays, Richmond, Va., assignors to AMF Incorporated


Filed Feb. 19, 1968, Ser. No. 706,435

Claims priority, application Great Britain, May 3, 1967, June 7, 1967, 10201/67; 26296/67

Int. Cl. B65b 5/04

U.S. Cl. 53-190

10 Claims



A bagging apparatus comprising a frame, an electric drive motor mounted thereon and a power train for transmitting the power of the motor to the driven members hereinafter described. These include a flighted infeed conveyor, a bagging mechanism operable to receive articles from the infeed conveyor, pickup a bag from a supply thereof, and in conjunction with a blockade member to effect relative movement between the article supported therein and the bag to pull the bag over the article and strip the bagged article from the mechanism, a drop transfer mechanism for temporarily supporting an article at the transfer area between the forward end of the infeed conveyor and the bagging mechanism, and an elevator mechanism for receiving bagged articles stripped from the scoop-tray mechanism and transporting them to an outfeed conveyor.

3,579,958

MACHINE FOR FORMING, FILLING, AND SEALING CONTAINERS


Ronald L. Hentges, Minneapolis, and Howard R. Garrett, St. Paul, Minn., assignors to Haskon Incorporated, Warsaw, Ind.

Filed Aug. 15, 1969, Ser. No. 850,417

Int. Cl. B65b 7/18, 43/28

U.S. Cl. 53-183

17 Claims



A machine for automatically forming, filling, and sealing tubular container blanks that continuously holds the container blanks in an open and upright position from their external vertical sides and feeds them in sequence to the machine's forming, filling, and sealing operations.

3,579,959

AUTOMATIC GROCERY BAG FILLING APPARATUS WITH INNER AND OUTER TRAY


Gaspar Robert Bossetta, Rte. 1, Box 297, Lacombe, La.

Continuation-in-part of application Ser. No. 664,195, Aug. 29, 1967, now abandoned. Filed Aug. 27, 1968, Ser. No. 766,661

Int. Cl. B65b 5/06, 39/00, 67/02

U.S. Cl. 53-260

15 Claims



An apparatus for automatically filling grocery bags with items purchased by a customer in a supermarket or the like including a tray in which the items are placed as they are registered on the checkout cash register, a bag holder on which an opened grocery bag is placed with the bag holder being movable into a position for telescopically receiving the tray while the items are discharged from the tray into the grocery bag together with a conveyor structure for removing the grocery bag from the grocery bag holder and storing in an accessible position. In one embodiment of the invention, the tray is supported within a drawer structure which is actuated by a mechanism to first elevate the drawer into an inclined position in aligned relation to the grocery bag and then inserting the tray from the drawer into the grocery bag, releasing the items into the bag and then retracting the tray and returning the tray and drawer to its normal position for placing subsequent items in the tray.

3,579,960

POWDER-ENCAPSULATION MACHINE

Maharaj Krishen Mehta, Lakeside, Cardiff, Wales, assignor to P. Leiner & Sons (Encapsulations) Limited, Treforest, Glamorganshire, Wales


Filed Mar. 10, 1969, Ser. No. 805,687

Claims priority, application Great Britain, June 26, 1968, 30567/68

Int. Cl. B65b 47/02

U.S. Cl. 53-184

5 Claims




Apparatus for forming filled gelatine capsules having two pocketed die rolls and a heater block supported between the die rolls to heat the gelatine ribbons as they approach the nip of the rolls, the side faces of the heater block being spaced from the ribbons to heat them by radiation. A tip member for heating the ribbons by direct contact immediately before their passage through the nip can be freely suspended from the heater block.

3,579,961 CAKE WRAPPING DEVICE

Hans J. Dessauer, Childersburg, Ala.
Filed Apr. 10, 1969, Ser. No. 815,011
Int. Cl. B65b 67/08, 11/00
U.S. Cl. 53—390

5 Claims U.S. Cl. 54—24




The yarn cake wrapping device comprises a tubular member passing through an arm which is pivotally mounted near one end so that it can be swung from one side of the mount to the other. A rigid tubular cake wrapper is placed in the tubular member and a cake of yarn is disposed about the tubular member and wrapper while the arm is in the load position. The upper end of the wrapper is drawn down about the cake and the arm is swung to a horizontal position on the other side of the mount to discharge the cake. The free end of the wrapper is then drawn over the second end of the cake.

3,579,962 COMBINED WRAPPING AND TAPING WORK TABLE

Frank P. Mitten, 182 W. 55th St., New York, N.Y.
Filed Sept. 10, 1969, Ser. No. 856,755
Int. Cl. B65b 67/10
U.S. Cl. 53—390

8 Claims




The present invention provides a combined wrapping and taping work table for shipping department use having a flat working surface which is divided into two areas, one being fixed and the other being hingedly connected for upward movement, a compartment below the fixed area having vertically disposed rolls of wrapping paper with spring-pressed tearing bars in engagement with their peripheries, and the compartment below the hinged area having two gummed tape delivery and moistening machines, and a labeling device, one of said gummed tape delivery and moistening machines having a hinged crank arm extension or handle which lies horizontally below said hinged work table surface when at rest, an enlarged opening in said work table above said hinged crank arm connecting to a forwardly directed slot, said hinged crank arm being manually engageable through said enlarged opening and movable along said slot to deliver a preselected amount of moistened tape.

3,579,963 ANIMAL HALTERS

Colonel Henry, Lawton, Iowa
Filed July 11, 1969, Ser. No. 841,052
Int. Cl. B68b 01/02

3 Claims



Animal halters constructed of a braided hollow-core line are described. One form of halter having a locking piece in the nosepiece for locking the sidepieces to the nosepiece without requiring hardware clamps is described. Other halter embodiments interwoven from segments of braided hollow-core line, are also described.


3,579,964 SQUIB-POWERED AUTOMATIC INFLATION DEVICE

Paul E. Ohlstein, Smithtown, N.Y., assignor to the United States of America as represented by the Secretary of the Navy

Filed July 1, 1969, Ser. No. 838,164
Int. Cl. B67b 7/24

U.S. Cl. 222—5

1 Claim



An explosive squib device for automatically inflating a life vest when the device is immersed in sea water. The explosive squib, when fired, actuates piercing pins which allow pressurized CO₂ to escape from a pair of gas cartridges into the life vest. The gas cartridges are formed from electrically conductive material, electrically insulated from each other, separated from each other physically, and made part of the electric circuit which fires the explosive squib. The cartridges thus form a pair of electrodes separated by an air gap, the circuit being closed when the cartridges are immersed in sea water.

3,579,965 MOWING MACHINE


Johnnie J. Musgrove, 1604 Amberly Road, Charleston, S.C.
Filed Dec. 31, 1968, Ser. No. 788,287
Int. Cl. A01d 75/30

U.S. Cl. 56—7

9 Claims

A four-wheel drive mowing machine including a frame having pairs of driven front and rear wheels provided with tires, the width of the tires being substantially greater than the width of the sidewalls. The front wheels are mounted on opposite ends of an axle mounted on the frame for pivotal movement in a substantially vertical plane about the frame

central axis and a pair of laterally extending front cutters are supported on the frame on opposite sides of the central axis



together with a rear cutter supported on the frame and arranged centrally of the central axis between the rear wheels.


3,579,966 GRASS CATCHER ASSEMBLY

Stanley F. Allina, Ladue, Mo., assignor to The Perfection Manufacturing Company, St. Louis, Mo.

Filed Oct. 4, 1968, Ser. No. 765,080
Int. Cl. A01d 35/22

U.S. Cl. 56—202

8 Claims



The grass catcher assembly includes a catcher bag having an open end and a closed end, the closed end being supported from the lawn mower by a cantilever support arm. The mouth of the catcher bag includes a split hoop wire frame stitched within the hem, the split frame includes opposed hook portions at each end. An adapter plate attached to the lawn mower housing above the discharge orifice includes engagement means in the form of a pair of spaced lugs. The split wire frame is sprung into interlocking engagement with the spaced lugs to hold the open end of the bag in overlapping relation with the discharge orifice.

3,579,967 GRAIN-LIFTER FOR GRAIN-CUTTING ASSEMBLIES

Gustav Schumacher, Eichelhardt, Haus Nr. 51, Germany
Filed Sept. 16, 1969, Ser. No. 858,479


Claims priority, application Germany, Sept. 18, 1968, Sept. 18, 1968, Aug. 12, 1969,

P 17 82 561.5, P 17 82 562.6 and P 19 40 955.3

Int. Cl. A01d 55/13

U.S. Cl. 56—313

8 Claims



A grain lifter for a grain-cutting assembly of the type used, for example, in a harvester thresher and grain binder. A holder is engaged by a finger which is fastened thereto by a bolt and nut. This nut is formed with an annular groove, and a grain lifter has a springy supporting arm formed at its rear end with a notch which receives the part of the nut which is surrounded by the groove thereof with portions of the supporting arm on opposite sides of the notch thereof being

received in said groove. This springy supporting arm of the grain lifter has a hook unit fixed thereto, and this hook unit extends around the finger and is pressed against the same by the springy action of the supporting arm when the rear end thereof is in the groove of the finger-fixing nut. The hook unit carries a blocking device which prevents automatic removal or unhooking of the hooking unit from the finger as a result, for example, of up-and-down movement of the springy supporting arm due to engagement of ground irregularities.

3,579,968 CROP HARVESTER ADJUSTABLE FOR DIFFERENT ROW SPACINGS AND FOR DIFFERENT TYPES OF FINAL OPERATION


Fredrick L. Hill, Rio Vista; Lauren W. Gates, Concord, and William V. Colbert, Lodi, Calif., assignors to The Regents of the University of California

Filed Oct. 21, 1968, Ser. No. 769,053

Int. Cl. A01d 45/00

U.S. Cl. 56—327

24 Claims



A crop harvester with a basic unit comprising a wheel-supported main frame, crop-pickup means, separating means for detaching the crop from the bearing plants, a collecting conveyor for receiving the detached crop and moving it rearwardly, and a cross conveyor at the rear for moving the collected crop to one side of the harvester. To this basic frame are attached, removably and one at a time, (1) a direct-loading conveyor, (2) a manual sorting unit, and (3) a mechanical sorting unit. Pivotal attachment enables folding whichever attachment is mounted on the basic unit. The basic unit also has means for varying the distance between one rear wheel unit and another between a minimum said distance and a maximum said distance, to accommodate different row spacings and to enable support of the sorting units when they are attached.

3,579,969 NUT HARVESTER


Eugene P. Richter, Jr., R.F.D. #2, Cairo, Ga.

Filed Oct. 30, 1969, Ser. No. 872,642

Int. Cl. A01d 51/00

U.S. Cl. 56—328R

10 Claims



Nuts lying on the ground are engaged by chain sections depending from a rotating reel so as to be dragged over a supporting arm on opposite sides of the notch thereof being

screen flap into a collection trough during forward movement of a mobile harvester frame on which the reel, flap and trough are mounted. The nuts are conveyed laterally through the trough to a delivery conveyor while being aerated.

3,579,970 ADJUSTABLE SUPPORT FOR TREE SHAKING APPARATUS


Edward I. Gilbert, deceased, late of Dallas; Edith M. Graff, Administratrix, Dallas, and William A. Rogers, Portland, Oreg. Said Edith M. Graff, administratrix assignor to Edith M. Graff

Continuation of application Ser. No. 641,951, May 29, 1967, now abandoned. Filed July 10, 1969, Ser. No. 871,763

Int. Cl. A01g 19/00

U.S. Cl. 56—328

9 Claims



An adjustable support is designed for mounting tree shaking apparatus in a wide variety of positions as required to connect the apparatus to selected branches of fruit and nut trees about to be harvested. The support includes a base; a first vertical shaft is journaled on the base. A first horizontal arm has its inner end fixed to the first vertical shaft. A second vertical shaft is journaled on the outer end of the first horizontal arm. A second horizontal arm is keyed to the second vertical shaft. Mounting means on the outer end of the second horizontal arm mount the shaking apparatus. Drive means are provided for driving the arms independently of each other, as required to place the shaking unit in positions where it can reach the tree branches to which it is to be attached.

3,579,971 CATCH FLOOR FOR GRAPE HARVESTERS


Jean Sagousse, and Eugene D. Riley, Los Banos, Calif., assignors to Genle Grape Harvester, Inc., Los Banos, Calif.

Filed Feb. 5, 1970, Ser. No. 8,944

Int. Cl. A01g 19/00

U.S. Cl. 56—330

10 Claims



A longitudinal, transversely centrally peaked, detached-grape catch floor for a grape harvester of the type which straddles and moves along a row of grapevines growing on

wires supported by posts; the catch floor, which is fashioned to permit the unobstructed relative passage therethrough of the posts and adjacent grapevine trunks with advance of the harvester, comprising—between transversely spaced, longitudinal side conveyors—two longitudinal panels of heavy-duty and flexible and resilient material disposed side-by-side with their inner edges lapped, and each thence inclining downwardly and laterally outwardly to its outer edge and to the corresponding side conveyor, and said panels each having therein a row of longitudinally spaced diagonal slits open to its inner edge whereby pairs of laterally mating flaps are formed on the panels. Such pairs of flaps yield upwardly in progression with the relative passage through the catch floor of each post and adjacent grapevine trunk, and then immediately return to their edge-lapped closed position. The panels are spring-finger supported from below, clear of the flaps, and out of the path through the catch floor of said posts and grapevine trunks.

3,579,972 AGRICULTURAL IMPLEMENT


Levi L. Sears, Oxnard, and Richard N. Sommer, Pacolma, Calif., assignors to SSP Industries, Burbank, Calif.

Filed Apr. 18, 1969, Ser. No. 817,538

Int. Cl. A01d 79/00

U.S. Cl. 56—370

4 Claims



An agricultural implement to be moved by a powered vehicle for collecting brush and cuttings and the like, into a single windrow. The implement includes a plurality of spring-steel tines arranged on a power-actuated revolving annular support, and cam means associated with said tines to move them from a vertical raking position to a discharging position.

Further, a fender may be utilized for specific raking and discharging operations when the trees involved are citrus, to enable the implement to function under the tree skirts.

3,579,973 STOP MECHANISM FOR ROTARY TEXTILE SPINDLE

Gustav Fetzter, Gingen, and Gerhard Freytag, Faurndau, both of, Germany, assignors to Zinser-Textilmaschinen Gesellschaft Mit Beschränkter Haftung, Ebersbach, Germany


Filed Feb. 25, 1969, Ser. No. 801,993

Claims priority, application Germany, Feb. 29, 1968, Feb. 1, 1969, P 17 10 059.3 and P 19 05 063.6

Int. Cl. D01h 7/22

U.S. Cl. 57—88

16 Claims



A rotary textile spindle is stopped by an electromagnetic brake means producing magnetic fields passing through the

spindle and raising the brake means to a higher braking position, when energized. The brake means is nonrotatably mounted on the stationary support of the spindle, and is movable in axial direction to and from the braking position. In one embodiment, the spindle carries a freely rotatable driven pulley, and coupling means are provided which couple the pulley to the spindle when the electromagnetic brake means is deenergized and inoperative, and disengage the pulley from the spindle when the electromagnetic brake means is energized and brakes the spindle to a stop.

3,579,974 ELECTRONICALLY-CONTROLLED DRIVE MECHANISM PARTICULARLY FOR CLOCKS

Karl Schmidt, Achern, Baden, Germany, assignor to Firma GEHAP Gesellschaft fuer Handel und Patentverwertung mbH & Co. KG., Achern, Baden, Germany


Filed Apr. 8, 1968, Ser. No. 719,782

Claims priority, application Germany, Apr. 8, 1967, F33765

Int. Cl. G04c 3/00

U.S. Cl. 58—23

13 Claims



A drive mechanism for clocks includes a stabilized transistor oscillator. One or more drive coils within the oscillator circuit are located adjacent poles provided about the circumference of a rotor wheel mounted on the same shaft as a drive pinion. The magnetic interaction between the drive coils and the poles causes a rotation of the wheel.

3,579,975 FLEXURE-TYPE SYMMETRICAL OSCILLATOR

Rene Besson, and Remy Chopard, Neuchatel, Switzerland, assignors to Ebauches S.A.


Filed Aug. 25, 1969, Ser. No. 852,811

Claims priority, application Switzerland, Aug. 30, 1968, 13,112/68

Int. Cl. G04c 3/00

U.S. Cl. 58—23

2 Claims



A flexure-type symmetrical oscillator for an electric timepiece, having a U-shaped part with two flexible limbs connected at their free ends to two rigid arms which in turn have counterbalancing masses at their free ends and drive transducers at the location where they are connected to the flexible limbs, the dimensioning of the arms and limbs being such that the instantaneous center of rotation thereof is substantially coincident with the center of gravity during flexure, whereby the frequency of the oscillator is substantially independent of changes of position and orientation of the oscillator with respect to gravity, means being provided which permits adjustment of the frequency of the oscillations of such an oscillator, like the regulator assembly of a conventional

watch with balance-wheel and balance-spring, in view of the adjustments of the running of the watch.

3,579,976 ELECTRONIC TIMEPIECE


Thomas F. D'Muhala, Exeter Road, Lebanon, Conn.

Filed Nov. 21, 1969, Ser. No. 878,663

Int. Cl. G04b 19/32

U.S. Cl. 58—50

6 Claims



A miniaturized electronic timepiece employing an electroluminescent display is disclosed. The indicia on the display are energized in the proper sequence through the use of logic circuitry and electronic switches controlled thereby.

3,579,977 REGULATOR-ASSEMBLY FOR TIMEPIECE

Andre Meylan-Rochat, Le Brassus, Switzerland, assignor to Parechoc S.A., Le Sentier, Vaud, Switzerland


Filed Aug. 4, 1969, Ser. No. 847,117

Claims priority, application Switzerland, Aug. 9, 1968, 12,019/68

Int. Cl. G04b 17/14; G04c 7/00

U.S. Cl. 58—112

1 Claim



A regulator-assembly for a timepiece in which the regulator has a catch engaged in the groove of a tangential screw threaded in the frame of the clockwork in such a way that the angular position of the regulator is modified by rotating the screw, characterized by the fact that the catch is constituted by a thin elastic tongue urged, by its own elasticity, to apply itself against the bottom of the groove, the two terminal faces of the groove being frustoconical and opening towards the outside, the width of the bottom of the groove being less than that of the tongue, so that the tongue bears simultaneously on both frustoconical surfaces, wherefore the displacements of the screw, when they are carried out alternately in one direction and in the other, produce corresponding displacements of the regulator, without idle running.

3,579,978 HYDRAULIC DRIVE CONTROL ARRANGEMENT

Dietrich Stams, Sindelfingen, Germany, assignor to Robert Bosch GmbH, Stuttgart, Germany

Filed May 7, 1969, Ser. No. 822,381

Claims priority, application Germany, May 11, 1968, P1750545.2


Int. Cl. F02b 41/00

U.S. Cl. 60—19

12 Claims

A drive for a car or machine comprises a combustion engine driving a hydrostatic pump-motor transmission. The fuel

supply of the combustion engine, the discharge volume of the pump, and the acceptance volume of the hydraulic motor are simultaneously adjusted by three cam followers under the control of three three-dimensional cam faces of a control



cam which is manually turned, and axially shifted distances depending on the hydraulic pressure in the hydrostatic transmission so that maximum efficiency and performance are obtained.

3,579,979

REGULATED HYDRAULIC DRIVE CONTROL APPARATUS

Paul Bosch, Ludwigsburg, and Walter Kobald, Stuttgart-Feuerbach, both of, Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany


Filed June 4, 1969, Ser. No. 830,324

Claims priority, application Germany, June 5, 1968, P 17 51 471.5

Int. Cl. F15b 15/18

U.S. Cl. 60—19

12 Claims



3,579,980

UNIFLOW STIRLING ENGINE AND FRICTIONAL HEATING SYSTEM

Donald A. Kelly, 58-06 69th Place, Maspeth, N.Y.

Filed Nov. 10, 1969, Ser. No. 875,252

Int. Cl. F03g 7/06

U.S. Cl. 60—24


8 Claims

The Uniflow Sterling engine consists of multiple power and displacer sections which are arranged in in-line form. The in-line arrangement allows for the ganging of the piston sets so that a simple modular, easily-serviced engine is produced.

Hot and cold conduction rods within the displacer aid in transferring heat within the displacer sections.

Alternating one-way gas flow bores within the displacer blocks provide a uniflow gas flow loop for improved thermal effectiveness.

A frictional heating system is advocated as a sustaining heating means, which utilizes an electric motor and battery



3,579,981

ANTI-POLLUTION EXHAUST VALVE COMBINATION WITH FLUIDIC CONTROL AND VALVE COOLING FEATURES


Leonard P. Gau, Birmingham, Mich., assignor to Chrysler Corporation, Highland Park, Mich.

Continuation-in-part of application Ser. No. 802,944, Feb. 27, 1969, now abandoned. Filed May 6, 1970, Ser. No. 35,051

Int. Cl. F01n 3/00

U.S. Cl. 60—29

9 Claims



3,579,982

GAS TURBINE POWER PLANT INCLUDING A NUCLEAR REACTOR AS HEAT SOURCE

Rene Strub, Winterthur, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland

Filed July 29, 1968, Ser. No. 748,555

Claims priority, application Switzerland, July 27, 1967, 10681/67


Int. Cl. F01k 25/00, 3/18

U.S. Cl. 60—36

1 Claim

There is disclosed a closed cycle CO₂ gas turbine power plant in which part of the CO₂ flow downstream of an intermediate level compressor is condensed prior to pumping to higher pressure and in which heat is applied to the CO₂ from a nuclear reactor in a heating step between successive expan-

sions, and in which for control of pressure in the reactor a line is provided, with adjustable flow control means therein to the accumulator fluid pressure but normally blocking communication between the accumulator and the fluid motor



3,579,983

IMPROVEMENTS IN OR RELATING TO COMBUSTION CHAMBERS


Jacques Emile Jules Caruel, Dammarie-les-Lys; Herve Alain Quillevere, Issy-les-Moulineaux, and Louis Jules Bauger, Vanves, France, assignors to Societe Nationale D'Etude Et De Construction De Moteurs D'Aviation, Paris, France

Filed May 5, 1969, Ser. No. 821,794

Int. Cl. F02g 1/00

U.S. Cl. 60—39.71

1 Claim



An annular combustion chamber comprising a plurality of ducts adapted to inject axially in an upstream direction a gasiform mixture containing vaporized fuel, each duct being associated with a pair of radial nozzles adapted to inject into said chamber two air jets directed toward one another, the geometrically defined area in which the jets are to meet being located at the outlet end of said duct.

3,579,984

FLUID POWER STEERING SYSTEM WITH FLUID PRESSURE RESERVE

Robert P. Rohde, Saginaw, Mich., assignor to General Motors Corporation, Detroit, Mich.


Filed June 4, 1969, Ser. No. 830,241

Int. Cl. F15b 1/02, 15/18

U.S. Cl. 60—51

2 Claims

A reserve supply of fluid pressure is provided for a vehicle fluid power steering system including an accumulator kept charged to a predetermined minimum pressure and communicated to the fluid power steering gear in parallel with the normal or primary pump source of pressure fluid. The rotary control valve for the fluid power gear includes a primary set of open center configuration lands and grooves operable over a normal steering travel range in the valve to selectively pressurize either side of the fluid motor, and a further set of closed center configuration lands and grooves communicated



3,579,985

PRESSURE INTENSIFIER


George M. Barrett, R.R. #5, Galt, Ontario, Canada

Filed Apr. 25, 1969, Ser. No. 819,154

Int. Cl. F15b 3/00, 15/18

U.S. Cl. 60—52

3 Claims



This disclosure relates to a hydraulic system incorporating a pressure intensifier which is a combination motor and pump and wherein the pressure intensifier has two discharge sources, one discharge source being a free discharge to a reservoir and the other discharge source being a high pressure discharge to a motor, the pressure intensifier being of the piston and cylinder type with the pistons being freely mounted within the cylinders and being associated with a cam so as to provide the required motor and pumping action.

3,579,986

DEVICE FOR CONTROLLING PUMPS FOR OPERATING HYDRAULIC MOTORS

Katsuro Abe, Matsudo-shi; Saburo Kakinuma, Kashiwa-shi, and Masaaki Uno, Tokyo, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed June 6, 1969, Ser. No. 830,940

Claims priority, application Japan, Sept. 6, 1968, 43/63756

Int. Cl. F15b 15/18

U.S. Cl. 60—52

3 Claims



A device for controlling pumps for operating hydraulic motors comprising at least two variable displacement pumps,

valve means for each said pump disposed between the discharge side of the pump and the hydraulic motors for switching a charge of hydraulic fluid delivered to the hydraulic motors upon operation of an operating lever, and a hydraulic servomechanism for each said pump operated by a control lever coupled to said operation lever for moving a discharge flow control member of the pump, said servomechanism having a control circuit including a first control valve operated by said control lever for forming a flow of hydraulic fluid therethrough to move said discharge flow control member of the pump to a position corresponding to the amount of operation of the control lever, and a second control valve responding to the discharge pressure of the pump for forming another flow of hydraulic fluid therethrough to move said discharge flow control member of the pump to a position corresponding to the discharge pressure of the pump.

3,579,987

ADJUSTABLE HYDRAULIC OPERATION ARRANGEMENT

Herbert Busse, Stuttgart-Stammheim, Germany, assignor to Robert Bosch GmbH, Stuttgart, Germany

Filed Oct. 2, 1969, Ser. No. 863,211


Claims priority, application Germany, Oct. 4, 1968,

P 18 01 13.5

Int. Cl. F15b 11/16

U.S. Cl. 60—52

10 Claims



A hydraulic arrangement in which a pump is adjustably set to supply pressurized fluid to a number of different hydraulically operated devices with different operating requirements. Each of the devices has connected in front of it a control valve which is, in turn, connected in series with a flow limiter. The control valves have position indicators which transmit signals indicative of the valve position. The flow limiters and the pump are settable through electrical signals derived from an electronic control circuit. The control circuit applies the setting signals to the pump and flow limiters in response to the electrical signals received from the valve position indicators.

3,579,988

HYDROSTATIC TRANSMISSION CONTROL SYSTEM

Donald Firth; Roger Harvey Yorke Hancock, and James McCallum, East Kilbride, Glasgow, Scotland, assignors to National Research Development Corporation, London, England

Filed Mar. 24, 1969, Ser. No. 809,492

Claims priority, application Great Britain, Mar. 25, 1968,

14374/68

Int. Cl. F16d 31/06; B60k 7/00

U.S. Cl. 60—53

12 Claims


A hydrostatic pump-and-motor transmission system, e.g. for a vehicle, in which the pump and the motor can have their displacement volumes varied in discrete steps to give a number of predetermined fixed ratios.

The pump is either a swashplate or variable eccentric pump adjustable to and between predetermined settings, or,

a plurality of fixed displacement pumps switchable on the hydraulic side between, e.g. small pump alone, large pump alone, both pumps together.

The motor is either a multibank piston/cylinder motor with valving arrangements for cutting out one bank of cylinders from the fluid supply, or several separate motors — some disconnectable.

A hand selector sets up the various conditions e.g. three alternative pump displacement values with the motor at max-



3,579,989

LINEAR SELF-SYNCHRONIZING MASTER-SLAVE HYDRAULIC REMOTE CONTROL DEVICE


Donald A. Stark; Ernest A. Di Bartolo; Harry A. Feather, and Charles H. Sundin, Sarasota, Fla., assignors to Fluid Controls, Inc., Mentor, Ohio

Filed Apr. 15, 1969, Ser. No. 816,231

Int. Cl. F15b 7/00

U.S. Cl. 60—54.5

10 Claims



A plurality of manually operable master piston and cylinder assemblies and one or more slave piston and cylinder assemblies are connected in series with each other in a closed hydraulic circuit continuously pressurized at low pressure by way of an accumulator.

Each master assembly has a valving bypass circuit such that when the piston is manually driven it functions as a conventional piston. When it is driven by a differential in the fluid pressures applied to its opposite faces, it functions as a conventional piston until it closely approaches the ends of its strokes in opposite directions, respectively, whereupon the valving bypass circuit is rendered operative and bypasses the pressure fluid around the piston from one end of the cylinder to the opposite end. This renders the device self-synchronizing simply by manual movement of one of its master pistons

through a complete forward and return stroke. Relief of excess pressures, and reduction of, and compensation for, thermal expansion and contraction are provided.

3,579,990

VAPOR GENERATOR


Richard A. Grams, Medina, Ohio, assignor to The Babcock & Wilcox Company, New York, N.Y.

Filed Apr. 3, 1969, Ser. No. 813,166

Int. Cl. F01k 7/16

U.S. Cl. 60—73

4 Claims



An improved marine vapor generator of the type which includes a reheater and the means for tempering the heating gases flowing toward the reheater. The tempering means operates to control the reheater outlet steam temperature during ahead operation and to protect the reheater tube metal during astern operation of the ship propulsion system. The tempering means includes a duct arranged to discharge a regulable quantity of heated combustion air into the heating gases flowing toward the reheater. An alternative arrangement uses unheated combustion air as the tempering agent. A third arrangement uses low temperature gases as the tempering agent and includes a gas recirculating fan.

3,579,991

THRUST REVERSING APPARATUS FOR JET-PROPELLED AIRCRAFT


Harold E. Nelson, Jr., Chula Vista, Calif., assignor to Rohr Corporation, Chula Vista, Calif.

Filed Jan. 8, 1970, Ser. No. 1,510

Int. Cl. F02k 1/24

U.S. Cl. 60—232

4 Claims



Thrust reversing doors are mounted on an aircraft jet engine housing by means of links each pivoted at one end to the housing and pivoted at its other end to the aft portion of one of the two side edges of a respective one of the doors. Means are provided to limit the rotation of the links relative to the housing and the rotation of the doors relative to the links.

3,579,992

POWER PLANT VARIABLE GEOMETRY CONTROL


Louis A. Urban, Granby, Conn., and Charles F. Stearns, East Longmeadow, Mass., assignors to United Aircraft Corporation, East Hartford, Conn.

Filed Jan. 3, 1969, Ser. No. 788,856

Int. Cl. F02k 1/16, 1/18

U.S. Cl. 60—239

10 Claims



Means for controlling the variable geometry of a gas turbine engine having a mechanism for varying the power turbine stator geometry or the gas generator exhaust nozzle geometry to achieve maximum acceleration time by matching the geometry of the engine to the acceleration and droop schedules of the fuel control.

3,579,993

SOUND SUPPRESSION SYSTEM


Carole S. Tanner, and Remo Tontini, San Diego, Calif., assignors to Rohr Corporation, Chula Vista, San Diego, Calif.

Filed Aug. 4, 1969, Ser. No. 847,052

Int. Cl. F02k 3/04; B64d 33/06

U.S. Cl. 60—262

2 Claims



System includes a nozzle connected to turbine exhaust outlet to confine and direct gas stream. Nozzle is corrugated to form peripherally spaced radially extending lobes to divide gas into small jet streams. Conduit surrounds exhaust outlet and discharges to exterior of nozzle, and fan air flows through passages between lobes to meet gas streams at exit margin of nozzle. Shroud or ejector sleeve defines and surrounds a mixing zone aft of the exit margin. Leading edge of shroud is spaced aft of fan air conduit to provide annular flow path for entry of ambient air to surround and mix with fan air and gas. Shroud is retractable to surround nozzle in spaced relation and prevent dispersion of fan air before mixing in normal cruising flight.


3,579,994 BARRIER FOR CONTROL OF SUBSTANCES IN BODIES OF WATER

Paul Preus, Smith Road, and Charles E. Rosendahl, Flag Point, Toms River, N.J.

Filed Jan. 17, 1969, Ser. No. 792,074
Int. Cl. E02b 15/04

U.S. Cl. 61-1

3 Claims



A barrier for control of waterborne substances having a plurality of units interconnected to one another in end to end relationship. Each unit has articulated flotation chambers and a flexible, depending skirt with permanent ballasting along the lower edge thereof. Means are provided to selectively reef the skirt and water ballasting pockets are formed on the skirt to provide restraint against wind action on the barrier.


3,579,995 VENTED LEACHING CHANNEL

John F. Flynn, 358 Strawberry Hill Road, Concord, Mass.

Filed June 10, 1969, Ser. No. 831,881
Int. Cl. E02b 13/00

U.S. Cl. 61-13

3 Claims



This invention relates to sewage systems, FIG. 3, it particular to a vented leaching channel for use in such systems. A plurality of vented leaching channels are arranged in a corresponding plurality of trenches in the leaching field of a sewage system so as to control the flow of sewage and to form a volume underground for storage output during aerobic action thereon. Each leaching channel comprises a series of leaching channel units arranged end-to-end, the first unit having an end cover adapted to receive the sewage and the last unit having a vent. Except for the end cover and vent, the units are identical for ease of manufacture and installation, and each includes a barn or shedlike structure having sheltered apertures in its walls adapted to permit outward flow of sewage while preventing inward flow of dirt and other undesirable material. Special access apertures are also provided in all the units.

3,579,996 PORTABLE BOAT RAMP

Jerry W. Edson, Wichita, Kans. (R1 Clearwater, Kans. 67026)


Filed Sept. 5, 1969, Ser. No. 855,623
Int. Cl. B63c 1/00, 3/12

U.S. Cl. 61-66

7 Claims

A portable boat ramp for beaching or launching small boats which eliminates the need to drag such boats across a sandy or rocky beach with resulting damage to the hull. The ramp may be conveniently carried manually and is capable of

being quickly adjusted between an extended operative position and a folded position for storage or transportation. Adjustable bolsters are provided for engaging hull sides of dif-



ferent configurations and cooperate with a stabilizing bar which is disposed therebeneath to provide a stable support for a boat while supported on the ramp.


3,579,997 CRYOPUMPING INSTALLATIONS WITH HIGH FLOW-RATES

Michel Rapinat, Fontaine, France, assignor to L'Air Liquide, Societe Anonyme pour L'etude et L'exploitation, des procedes Georges Claude

Filed July 10, 1969, Ser. No. 840,734
Claims priority, application France, July 30, 1968, 161,161
Int. Cl. B01d 5/00

U.S. Cl. 62-55.5

12 Claims



A cryopump is constituted by a fluidtight casing inside which is arranged a plurality of condensation plates carried by a cooling coil supplied with very cold fluid, the whole disposed externally of and around a baffle formed by a plurality of frustoconical rings arranged in the extension of a stop valve. The baffle is preferably cooled by a moderately cold fluid (80°K) through conduits, while a coil embedded in the wall of the casing and traversed by a moderately cold fluid cools an internal wall of the casing. This cryopumping device is adapted to extract high flow rates at a relatively moderate pressure of the order of 10⁻¹² torr.

3,579,998 CRYOGENIC PUMPING DEVICE FOR THE CREATION OF VERY HIGH VACUA

Jean-Jacques Thibault, Saint-Martin D'Uriage, and Jean-Claude Boissin, Montbonnot-Saint-Martin, France, assignors to L'Air Liquide, Societe Anonyme pour L'etude et L'exploitation, des procedes Georges Claude


Filed July 25, 1969, Ser. No. 844,779
Claims priority, application France, Aug. 1, 1968, 161,426
Int. Cl. B01d 5/00

U.S. Cl. 62-55.5

7 Claims

A cryogenic pumping device for the creation of very high vacuum, comprising means for collecting gases at very low

temperature, said collecting means including adsorption means and condensation means, the condensation means being located upstream of the adsorption means with respect to the travel of the gases, the whole being housed in a casing cooled to a moderately low temperature and formed, on the



side of the passage communicating with the chamber to be pumped, by a baffle adapted to form a screen against external radiation. The adsorption means are mounted on an extension of a metal wall which forms the condensation means, each metal wall being adjacent to a segment of a cooling coil through which is circulated a fluid at very low temperature.


3,579,999 METHOD AND APPARATUS FOR THE PRESERVATION OF BIOLOGICAL SUBSTANCES

Ralph E. Schwartz, Lindenhurst, N.Y., assignor to Redeco, Inc., East Islip, L. I., N.Y.

Filed Aug. 8, 1968, Ser. No. 757,195
Int. Cl. A61m 1/02

U.S. Cl. 62-56

8 Claims



Biological substances such as blood are stored under pressure at below 0° C. temperatures, in a substantially nondilatable vessel. Upon being introduced into the vessel, the temperature of the vessel and the blood are reduced to 4° C.; when equilibrium has been achieved the blood within the vessel is precompressed at a controlled rate several thousand pounds per square inch by the application of mechanical leverage to a vessel piston. Thereafter, the vessel and blood are reduced to a final temperature from 0° C. to -21° C. This temperature reduction, because of the conjunctive effect of the volumetric expansion of the blood and nondilation of the vessel, self-generates a pressure from 15 to 35,000 p.s.i. The vessel may now be stored at the final temperature and the blood within it maintained without deleterious effects.


3,580,000 CHAMBER FOR FOOD TREATING APPARATUS

Richard C. Wagner, Clarendon Hills, Ill., assignor to Integral Process Systems, Inc.

Filed Mar. 17, 1969, Ser. No. 807,904
Int. Cl. F25d 3/10, 25/04

U.S. Cl. 62-77

11 Claims



To provide for the ease of cleaning of an elongated food treating chamber, such as a flash freezing chamber, which contains a conveyor for the passage of food therethrough, means are provided for separating the chamber into sections, opening a lid portion of each section and lifting the conveyor out of the chamber by means of lifting jacks which pass through the spaces between the separated sections.

Another aspect of the invention provides means for accommodating differential thermal expansion or contraction of inner and outer walls of the chamber section by connecting said inner and outer walls only by cover caps and end caps which are slidably attached thereto.


3,580,001 ABSORPTION REFRIGERATION MACHINE WITH CONCENTRATION CONTROL TANK

Keith V. Eisberg, Martinsville, Ind., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Sept. 3, 1968, Ser. No. 756,783
Int. Cl. F25b 15/04

U.S. Cl. 62-101

4 Claims



An absorption refrigeration system employing a liquid storage tank to vary the concentration of refrigerant in the solution supplied to the absorber under varying ambient temperature operating conditions.

3,580,002 FREEZE LIMITING ABSORPTION REFRIGERATION

John T. Fisher, Indianapolis, Ind., assignor to Carrier Corporation, Syracuse, N.Y.


Filed June 7, 1968, Ser. No. 735,380
Int. Cl. F25b 15/04, 3/12

U.S. Cl. 62-101

2 Claims

An absorption refrigeration system utilizing chilled water as a heat exchange medium. The system includes a chiller

which provides reduced heat exchange area upon a drop in ambient air temperature by selectively block water flow receive liquid therefrom when circulation of absorption liquid has stopped. Fluid raised by the second pump is con-



paths between the chiller coils by the formation of ice to prevent complete freezeup of the chiller.

3,580,003

COOLING APPARATUS AND PROCESS FOR HEAT-ACTUATED COMPRESSORS


Joseph P. Dolan, Chicago, Ill., assignor to The Institute of Gas Technology, Chicago, Ill.

Filed Aug. 14, 1968, Ser. No. 752,710

Int. Cl. F25b 1/00

U.S. Cl. 62-115

18 Claims



Apparatus and process for cooling heat-actuated engines or compressors by use of boiling refrigerant, especially suitable for use with heat-actuated regenerative compressor systems used in conjunction with a condenser-expansion-compression cooling cycle.

ERRATUM

For Class 62-148 see:
Patent No. 3,580,013

3,580,004

APPARATUS FOR DEFROSTING COOLING UNITS OF ABSORPTION REFRIGERATION SYSTEMS

Wilhelm Georg Kogel, Stockholm, Sweden, assignor to Aktiebolaget Electrolux, Stockholm, Sweden

Filed Nov. 18, 1968, Ser. No. 776,535

Claims priority, application Sweden, Nov. 17, 1967, 15818/67


Int. Cl. F25b 15/10

U.S. Cl. 62-148

6 Claims

This invention relates to an absorption refrigeration system of the inert gas type including cooling structure having low and higher temperature cooling elements to which refrigerant is supplied from a vapor expulsion unit having a heat receiving part from which heat is derived for expelling refrigerant vapor from absorption liquid. The vapor expulsion unit includes a first pump for lifting liquid by vapor-liquid lift action to effect normal circulation of absorption liquid during operation of the system. The heat receiving part is heated by a source of heat controlled by a thermostat affected by the temperature of the higher temperature cooling element either to render said first pump operable to circulate absorption liquid or to render it inoperable to stop circulation of the liquid. The absorption liquid circuit has a part at a level normally free of liquid and above the liquid surface level therein when normal circulation of liquid is effected and at a level below the liquid surface level in the circuit when normal circulation of liquid has stopped. The important feature of the invention resides in providing a second pump for lifting liquid by vapor-liquid lift action by heat which also is derived from the heat receiving part and is connected to the one part to

The present invention is directed to refrigeration systems of the type referred to in the art as heat pumps comprising a compressor, a pair of series-connected heat exchangers, reversing valve means for reversibly connecting the compressor to the heat exchangers for effecting flow of refrigerant through a portion of the circuit in either direction, refrigerant flow control means in the circuit, and a refrigerant container or receiver connected between the two heat exchangers for storing a portion of the refrigerant charge during operation of the system, the container being so constructed and arranged as to readily accommodate varying charge imbalances in the system and also having in communication therewith tubular means for effecting essentially complete removal of oil entrapped in the container and its return to the compressor when the system is reversed from the heating to the cooling cycle, thereby assuring an adequate supply of oil in the compressor for lubrication purposes.



3,580,005

REFRIGERATION SYSTEM


Harry T. Hale, Bridgeport, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Apr. 1, 1969, Ser. No. 812,215

Int. Cl. F25b 45/00

U.S. Cl. 62-149

2 Claims



3,580,006

CENTRAL REFRIGERATION SYSTEM WITH AUTOMATIC STANDBY COMPRESSOR CAPACITY


Lester K. Quick, 868 Westview Crescent, Vancouver, British Columbia, Canada

Filed Apr. 14, 1969, Ser. No. 815,866

Int. Cl. F25b 5/00

U.S. Cl. 62-196

18 Claims



A central refrigeration system for supermarkets and the like requiring two or more temperature levels of refrigerated fixtures wherein separate compressors operate the fixtures at different temperature levels and with only one or two large compressors for each temperature level. The system employs a single condenser-receiver for the refrigerant discharged from all of the compressors and a single oil separator for returning oil to the compressors. A control arrangement responsive to an abnormal increase in the suction pressure on a given compressor automatically operates a valving arrangement to transfer at least a portion of the refrigerant load on that compressor to another compressor normally operating fixtures at a different temperature level.

3,580,007

BELT-DRIVEN ICE MAKER

Carl C. Bauerlein, Clearwater, Fla., assignor to Eaton Yale & Towne Inc.


Division of Ser. No. 702,914, Feb. 5, 1968.

and this application Aug. 22, 1969, Ser. No. 870,711

Int. Cl. F25c 1/10

U.S. Cl. 62-345

5 Claims



An automatic ice cube maker including a sprocket-driven endless belt having a plurality of flexible invertible ice cube forming cup-shaped members or cells formed therein. A water-fill station and an ice cube harvest station are situated respectively adjacent upper and lower horizontal reaches of the belt. A stallable electric motor drives the sprockets

through a gear train to move the belt continuously through a looped path of travel and past the water-fill and ice-harvest stations. A water supply mechanism for filling the cells with water comprises a pair of alignable cooperating cams which are connected to different ones of the gears of the gear train for rotation at different speeds. A water control switch controls the operation of the water supply mechanism so that a predetermined amount of water is supplied to each of the cells as each cell passes through the water-fill station in timed relation with the alignment of the cams. Rigid abutment members are provided at the harvest station to invert the cells or cup-shaped members or turn them inside out to remove the frozen cubes therefrom. A spring-biased member is provided beyond the harvest station to reinvert or return the cup-shaped members to the original position thereof. The spring bias member includes a stripper for ensuring complete removal of the cubes from the cells. An ice level sensing mechanism is also driven by the gear train to physically stop the rotation of the motor when the ice at the harvest station has attained a predetermined level, but only when the cam members are out of alignment with one another and the water control switch is inoperative to avoid overflowing of the cup-shaped members at the water-fill station.

3,580,008

ICEMAKER WITH WATER DISTRIBUTOR


Walter C. Barnard, White Bear Lake, and Donald C. Hodapp, St. Paul, Minn., assignors to Whirlpool Corporation

Filed Apr. 24, 1969, Ser. No. 818,973

Int. Cl. F25c 1/12

U.S. Cl. 62-347

16 Claims



An icemaker having a refrigerated member over a surface of which water is directed to form an ice slab and including a water distributor with an internal reservoir means for receiving water and a plurality of outlets for distributing water along the width of the ice slab portion of the refrigerated member and flow-impeding means in the reservoir for impeding flow of water through the reservoir for achieving substantially even distribution of water within the reservoir means before flow through the outlet means in order that the water distribution is even onto the refrigerated member to aid in the formation of an ice slab of substantially uniform thickness.

3,580,009

ICE MAKER


Lawrence E. Snow, Greenville, Mich., assignor to White Consolidated Industries, Inc., Greenville, Mich.

Filed Jan. 13, 1969, Ser. No. 790,820

Int. Cl. F25c 1/10

U.S. Cl. 62-353

1 Claim



An automatic icemaker in which a flexible ice tray is twisted to loosen the ice cubes by unidirectional rotation of

one end of the tray while rotation of the opposite end of the tray is temporarily restrained and a reverse twist force is imparted to the tray by relatively accelerating the other end of the tray before the tray is returned to its normal upright position.

3,580,010

UNIVERSAL JOINT


Sidney L. Fisher, Renton, Wash., assignor to Spider Staging, Inc., Seattle, Wash.

Filed Sept. 29, 1969, Ser. No. 861,866

Int. Cl. F16d 8/18

U.S. Cl. 64-9

7 Claims



The essential components are a pair of identical end members, a coupler member, and a retainer ring. Each end member is connectable to the shaft part and includes cylindrical pivot head means having an axis perpendicular to the main axis of the end member. The coupler member comprises a pair of transverse socketways, each of which is circular in cross section and extends perpendicular to the other socketway. The head means of one end member is slid axially into one of the socketways and the head means of the other end member is slid axially into the second socketway. A retainer ring is slid longitudinally over one of the end members into a position surrounding the coupler member in which said ring covers the end openings of the socketways.

3,580,011

COUPLING


Erwin Pfarrwallner, Winterthur, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland

Continuation-in-part of application Ser. No. 676,590, Oct. 19, 1967, now abandoned. This application Nov. 24, 1969, Ser. No. 879,135

Int. Cl. F16d 3/14

U.S. Cl. 64-27

2 Claims



A coupling for the transmission of torques comprises two discs and means to permit limited relative rotation of the discs, with friction between them. For restoration of an equilibrium relative angular position of the discs, there are oppositely acting separate circumferentially disposed springs of adjustable prestress engaged between the two discs. In another embodiment each of the springs is permitted to undergo compression but not expansion, and the prestressed

compression of the springs undergoing compression for one sense of relative rotation of the discs is greater than the maximum force of friction between the discs so that upon release of the discs they will be restored to their equilibrium relative angular position notwithstanding the force of friction.

3,580,012

DEVICE FOR CONTROLLING THE DELIVERY OF THREAD TO A KNITTING MACHINE


Eugene Voisin, Souigny; Jean-Pierre Raisin, Troyes, and Jean-Paul Delair, Troyes, France, assignors to Centre Technique Industriel dit, Institut Textile De France, Boulogne, S/Seine, France

Filed Sept. 19, 1969, Ser. No. 859,416

Claims priority, application France, Sept. 23, 1968, 167,161 Int. Cl. D04b 15/48

U.S. Cl. 66-55

3 Claims



A device for controlling the delivery of thread to a knitting machine comprises a speed variator which is connected to a mechanical transmission extending between a cylinder and thread furnisher of the knitting machine, and a motor which controls the variator. The motor is reversible in forward and reverse directions and has two pairs of switches which start and stop the motor in both directions. The starting switches are operated by a control cam and programming element of the knitting machine. A follower device is provided whose travel corresponds to a predetermined length of fabric produced by the knitting machine and this follower device operates the stopping switches.

3,580,013

ABSORPTION REFRIGERATION MACHINE WITH GENERATOR LEVEL CONTROL


Gary W. Ballard, Liverpool, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Filed June 2, 1969, Ser. No. 829,622

Int. Cl. F25b 15/04

U.S. Cl. 62-148

5 Claims



An absorption refrigeration system including an electronic control circuit employing a level sensing probe to prevent

operation of the absorption refrigeration system heating means when the probe is not submerged in absorbent solution.

3,580,014

MACHINE HAVING A ROTARY MOTION, ESPECIALLY WASHING MACHINE, FURNISHED WITH BALLAST

Lamberto Mazza, Pordenone, Italy, assignor to Industrie A. Zanussi S.p.A., Pordenone, Italy


Filed Jan. 22, 1969, Ser. No. 792,962

Claims priority, application Italy, Feb. 13, 1968, 12701A/68

Int. Cl. D06f 37/22

U.S. Cl. 68-23.1

8 Claims



A machine having a unidirectional or reciprocating rotary motion, such as a washing machine, wherein a container is provided which can be charged with a ballast material, preferably water, in order to dampen the oscillations and vibrations transmitted to the whole machine during its operation, the ballast material being dischargeable to facilitate the transport and the handling of the machine.

3,580,015

DEVICE FOR TREATING TEXTILE FABRIC

Hajime Horie, Tadao Hirano, and Tokihide Suzuki, Fukui-ken, Japan, assignors to Fukui Seiren Kako Kabushiki Kaisha Keya, Fukui-shi, Fukui-ken, Japan


Filed Aug. 15, 1969, Ser. No. 850,511

Claims priority, application Japan, Sept. 6, 1968, 43/63721

Int. Cl. B05c 3/134, 3/136

U.S. Cl. 68-53

1 Claim



A device for continuously treating a textile fabric, comprising a tank containing liquid therein, an arcuately curved, concave false bottom provided in said tank, a rotary frame pivotally mounted in said tank above said false bottom and having a curvature corresponding to that of said false bottom, means for alternately rotating said rotary frame in forward and backward directions like a pendulum, said rotary frame being provided on its peripheral surface with a plurality of partitioning plates each lying in a radial plane of said rotary frame to divide said peripheral surface into sections and a plurality of resistance plates each lying in an axial plane of said rotary frame to produce turbulent flow in the liquid above said false bottom during operation, whereby the textile fabric is successively passed through the respective sections and is subjected to breaking action by the turbulent flow of the liquid between the rotary frame and the false bottom.

3,580,016

KEEPER LOCK FOR A SLIDE FASTENER


William J. Kerr, Glenview, Ill., assignor to Chicago Lock Co., Chicago, Ill.

Filed Apr. 15, 1970, Ser. No. 28,656

Int. Cl. E05b 67/38, 11/06; A44b 19/00

U.S. Cl. 70-68

10 Claims



A concentric three-part, key-operated keeper lock for a slide fastener and including an outer lock barrel having a radial anvil portion which underlies the pull tab of the slide fastener when the fastener is in its closed position, an intermediate telescopically movable rotatable handle having a radial keeper flange which is adapted to overlie the pull tab when the barrel and handle are telescoped together, and an inner tumbler-type cylinder having a locking bolt which maintains the barrel and handle telescoped. In the telescoped position of the handle and barrel, interlocking shoulders prevent rotation of the handle. In the unlocked condition of the cylinder, the handle may be moved axially to free the interlocking shoulders, after which the handle may be rotated throughout a 90° arc in order to withdraw the keeper flange from its tab-overlying position. The keeper lock is self-locking in that when it is in its unlocked condition it may be manipulated to a locked condition without the use of the proper key.

3,580,017

LOCK WITH MEANS CONCEALING MOUNTING FASTENERS


Russell W. Waldo, St. Paul, Minn., assignor to Ideal Security Hardware Corporation, St. Paul, Minn.

Filed Nov. 5, 1969, Ser. No. 874,277

Int. Cl. E05b 9/08, 15/02

U.S. Cl. 70-81

10 Claims



A deadlock including a bolt housing and a cooperating strike element each having openings for reception of fastening means for anchoring the same one to a door and the other to a door frame. A bolt-operating knob on the housing conceals the fastening means when the bolt is in both its extended strike-engaging and retracted strike-releasing positions, the fastening means being exposed only when the bolt is moved to an intermediate position between its fully extended and retracted positions. A cover is press fitted on the strike to conceal the fastening means thereon.

3,580,018

MACHINE FOR COILING ELONGATED STRIPLIKE MATERIAL

Hans Gott, Graz, and Josef Rittler, Graz-Kroetsbach, Austria, assignors to EVG Entwicklungs- und Verwertungsgesellschaft m.b.H., Graz, Austria


Filed June 13, 1968, Ser. No. 736,852

Claims priority, application Austria, June 16, 1967, A5638/67

Int. Cl. B21b 37/00; B21c 47/00; B21d 45/00

U.S. Cl. 72-12

10 Claims



A machine for coiling elongated striplike material such as welded mesh reinforcement of the kind in which the material is coiled on a mandrel from which the completed coil is removed after the coil and mandrel have been separated by axial movement relative to each other is provided with a gripper mechanism for gripping the coil and this mechanism is arranged to travel between a first position near the mandrel and a second position away from the mandrel. The gripper mechanism has at least two grippers capable of pivoting inwards from opposite sides into contact with the outer surface of a coil mounted on the mandrel so that they thrust against the surface of the coil and hold it together. The gripper mechanism is arranged so that during its movement from the first position into the second position, the grippers continue to hold the coil firmly together and prevent it from uncoiling.

3,580,019

METHOD OF MANUFACTURING ROD, SHAPED AND TUBULAR PRODUCTS FROM DIFFICULT-TO-WORK METALS AND ALLOYS, PREFERABLY HIGH MELTING-POINT AND CHEMICALLY ACTIVE ONES


Boris Ivanovich Beresnev, Krasnoprudnaya 7/9, kv.31; Evgeny Dmitriyevich Martynov, MGU sektor 1, kv. 13; Jury Nikolaevich Ryabinin, Vorobievskoe shosse 2, kv. 40; Mikhail Vasilievich Maltsev, ul Streletskaya 26-a kv. 40; Georgy Pavlovich Britnev, ul Lobachika 10, kv. 4; Anatoly Vasilievich Kocherov, 3 Pavlovsky per., 13, kv. 2, Moscow; Dmitry Konstantinovich Bulychyev, ul Kuibysheva, 123-B, kv. 24, Sverdlovsk, and Kuzma Petrovich Bodionov, ul Malysheva 135, Kv. 1, Sverdlovsk U.S.S.R.

Filed May 10, 1967, Ser. No. 637,450

Int. Cl. B21c 23/24

U.S. Cl. 72-47

7 Claims



A method of extruding materials that are difficult to extrude in which a blank of the material is enclosed in a con-

tainer with a portion extending into an extrusion die and the blank is subjected to high pressure fluid to press the blank through the blank may be coated with a metal or metals such as nickel and copper, and a lubricant applied thereto. The outer coating of a blank coated with plural layers of metal may be porous.

3,580,020

APPARATUS FOR CALIBRATING PIPES

Ali Bindernagel, Dusseldorf-Gerresheim; Erwin Kost, Osterath, and Karl-Hans Staat, Homburg Bie Ratingen, Germany, assignors to Firma Friedrich Kocks, Dusseldorf, Germany


Filed Aug. 23, 1968, Ser. No. 754,759

Claims priority, application Germany, Sept. 1, 1967, P 16 02 289.2

Int. Cl. B21d 39/08

U.S. Cl. 72-58

11 Claims



Apparatus for calibrating pipes by expansion or swaging, comprises a housing holding an annular deforming tool consisting of a number of axially extending segments which are arranged side-by-side to form a cylinder and which are movable radially outwards or inwards, this radial movement being limited by stops which engage the ends of the segments, and a cylindrical sleeve which bears on either the inner or the outer faces of the segments and which forms a pressuretight chamber between itself and the housing, so that, in use, when the chamber is supplied with fluid under pressure the sleeve is forced radially outwards or inwards, hence forcing the segments radially outwards or inwards into engagement with the inside or outside of a pipe until further radial movement is prevented by the stops, at which time the pipe is expanded or swaged to an exact size determined by the apparatus.

3,580,021

STRIP STOCK HANDLING EQUIPMENT


Donald L. Cramer, and Paul D. Limpach, Napoleon, Ohio, assignors to Automatic Feed Company, Napoleon, Ohio

Filed July 24, 1968, Ser. No. 747,309

Int. Cl. B21d 55/00

U.S. Cl. 72-5

8 Claims



Equipment for uncoiling and conditioning strip stock to be utilized in devices such as punch presses, shears, and stamping machines.

3,580,022

ROLLING MILL INCLUDING GAUGE CONTROL


Marion D. Waltz, and Lewis A. Drake, Youngstown, Ohio, assignors to The Youngstown Sheet and Tube Company, Mahoning County, Ohio

Filed Nov. 12, 1968, Ser. No. 774,775

Int. Cl. B21b 37/08

U.S. Cl. 72-8

10 Claims



In combination with a rolling mill and control means for controlling the spacing between a set of work rolls thereof the method and means for producing an electrical control signal for said control means which is free of a component which varies cyclically with the rotation of the rolls, e.g., the eccentricity of the rolls.

3,580,023

AUTOMATED STOPS FOR BAR BENDING MACHINE


Neal W. Merrill, Bethlehem, and Charles R. Nippert, Allentown, Pa., assignors to Bethlehem Steel Corporation

Filed Dec. 9, 1968, Ser. No. 782,197

Int. Cl. B21j 7/26

U.S. Cl. 72-22

2 Claims



A bar bending machine comprising a rotatable bending disc having a central pin and a bending pin is provided with a plurality of stops for positioning a bar longitudinally prior to the actuation of said disc. The machine is programmed whereby said disc sequentially rotates through predetermined angles, bending the bar a plurality of times, each rotation being controlled by a switch. The stops are connected to a circuit whereby the proper stop is sequentially moved into and out of the path of the bar during the bending operation.

3,580,024

METHOD AND APPARATUS FOR CORRUGATING TUBES

Howard F. Mattil, Yonkers, N.Y., assignor to Phelps Dodge Copper Products Corporation, New York, N.Y.

Filed Nov. 27, 1968, Ser. No. 779,456


Int. Cl. B21d 13/04

U.S. Cl. 72-77

15 Claims

This invention comprises a tube corrugating method and

apparatus in which a forming tool is selectively engaged forcefully with and disengaged from the tube while the tube ad-



vances axially past the tool. The tube may be pressurized internally with a fluid to improve corrugation shape.

3,580,025

END PLATE FORMING APPARATUS

Yasutoshi Hayashi, No. 2, 5-Chome Senbon-dori Nishinari-ku, Osaka, Japan


Filed Dec. 17, 1968, Ser. No. 784,358

Claims priority, application Japan, Aug. 24, 1969, 43/60584

Int. Cl. B21h 1/00

U.S. Cl. 72-84

6 Claims



End plate forming apparatus comprising an upper support member and a lower support member provided on the same axis to hold therebetween and revolve a blank and a plurality of sets of forming rollers to be moved on the same locus as the curved surface of the required end plate to form the required end plate by cooperative working.

3,580,026

METHOD AND APPARATUS FOR MANUFACTURING FINNED PIPES

Ioan Luca, Bucharest, Romania, assignor to Institutul De Cercetari Tehnologice Pentru Constructii De Masini Soseaua Oltenitei, Bucharest, Romania

Filed Dec. 17, 1968, Ser. No. 786,824


Int. Cl. B21d 19/08

U.S. Cl. 72-96

8 Claims

Cooling fins are rolled onto the outer surface of a pipe or tube, while simultaneously the cross section of the pipe or tube is changed to an oval or elliptical shape. The inner sur-

face of the pipe or tube may be either smooth or provided with grooves. The fins are formed by three rotating dies, and



the cross-sectional shape and inner surface is formed by drawing the pipe or tube over a rotating mandrel.

3,580,027

GEAR ROLLING


David W. Daniel, Birmingham, and Warren C. McNabb, Detroit, Mich., assignors to Lear Siegler, Inc., Santa Monica, Calif.

Filed Dec. 2, 1968, Ser. No. 780,390

Int. Cl. B21h 5/02

U.S. Cl. 72-98

14 Claims



Method and apparatus for producing gears from circular blanks by rolling them in metal deforming pressure contact with one or more toothed dies. The configuration of the space between the teeth of the die or dies is carefully controlled so as to provide surfaces which prevent the formation of "rabbit ears" and which accordingly eliminates the "cold shut" previously located at the crests of the teeth of gears rolled from circular blanks.

3,580,028

APPARATUS FOR PRODUCING EXTERNAL INTEGRAL FINS FOR TUBING


Frank F. Walters, Syracuse, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Mar. 3, 1968, Ser. No. 803,895

Int. Cl. B21h 3/12

U.S. Cl. 72-98

4 Claims



An improvement in apparatus for forming axially spaced integral helical fins on a length of tubing, the apparatus in-

cluding a body member mounted within and interconnected to an outer housing which defines the outer surface of a tube finning head assembly. Journaled within the body member are a plurality of crescent-shaped cams which operate a plurality of forming roll assemblies including tool support arbors. Supported on the arbors are a plurality of die means which define axially-spaced peripheral portions with grooves formed therebetween. The body member is made of heat-hardened steel, thereby increasing its wear resistance. The body member may be easily disengaged from the housing thereby expediting and reducing the cost of certain repairs.

3,580,029

ROLLING CHAMFERS ON GEAR TEETH


David W. Daniel, Birmingham; Henry O. Verschaeve, St. Clair Shores, and Warren C. McNabb, Detroit, Mich., assignors to Lear Siegler, Inc., Santa Monica, Calif.

Filed Dec. 5, 1968, Ser. No. 781,420

Int. Cl. B21h 5/00

U.S. Cl. 72-108

7 Claims



Gear rolling dies are provided with inclined chamfer-forming ramp surfaces at the bottoms of the tooth spaces adapted to form chamfers at the tops of the gear teeth along the corners defined by the intersection of the crests of the teeth and the flank surfaces.

3,580,030

COIL FORMER


Dennis P. Bean, and John C. Parks, Los Angeles, Calif., assignors to Solatron Enterprises, Los Angeles, Calif.

Filed Nov. 15, 1968, Ser. No. 776,034

Int. Cl. B21f 37/00

U.S. Cl. 72-130

12 Claims



A method of making single-turn, planar, circular coils is disclosed in which a substantially linear rodlike element is cut and bent into a circle of predetermined radius through successive bending and cutting steps. The circular ring is formed from an element which has been precut in the shape of an elongated "C" which has, at each of its ends, a 90° bend to a radius of curvature substantially equal to the predetermined radius.

3,580,031

MANUFACTURING APPARATUS

Vincent J. Donadio, Pompton Plains, and Olavi F. Anderson, Succasunna, N.J., assignors to The United States of America as represented by the Secretary of the Army

Filed June 20, 1969, Ser. No. 835,045


Int. Cl. B21d 13/10

U.S. Cl. 72-186

4 Claims

A machine for manufacturing flechettes at substantially higher rates of production and operating efficiency. The

machine has a plurality of rotatable wheels each having a plurality of peripherally spaced eccentric bushings. Each bushing has a central axis that extends radially of its wheel and perpendicularly of a peripheral centerline of the wheel. Each bushing contains a die insert and is mounted for transverse adjustment of the bushing central axis relative to the



corresponding wheel centerline. Each die insert has a fin-forming portion and a nose-forming portion that cooperate to provide a positive means of feeding a workpiece through the machine. Each wheel has a main body-forming portion intermediate the fin-forming portion of each die and the nose-forming portion of the following adjacent die.

3,580,032

APPARATUS FOR REDUCING THE WIDTH OF METALLIC SLABS


Morris Denor Stone, and Howard Hubbell Talbot, Pittsburgh, Pa., assignors to United Engineering and Foundry Company

Filed Apr. 17, 1969, Ser. No. 817,133

Int. Cl. B21b 15/00, 31/16

U.S. Cl. 72-199

8 Claims



Disclosed are two embodiments of apparatuses for performing work on metallic slabs to substantially reduce their width. In the first embodiment there is provided a pair of driven slab reducing rolls, each rotatably supported in a housing. The rolls are adjustably positioned relative to each other to reduce the slabs to a desired width. Concentrically carried on each roll are a pair of spaced anvil collars, one of which is adjustably positionable relative to the other to accommodate slabs of different thicknesses. In the second embodiment there is provided a pair of adjustably positionable slab squeezer heads, one of which is reciprocated relative to the other. Pairs of platens adjustably support and locate the slab in a direction normal to the movement of the reciprocating squeezer head.

3,580,033

ROLLING MILL FOR PRODUCING THIN STRIP STOCK

Pierre Gay, La Tour en Jarez, France, assignor to Compagnie Des Ateliers Et Forges De La Loire (St. Chamond, Firminy, St. Etienne, Jacob-Holtzer), Paris, France

Filed Feb. 14, 1969, Ser. No. 799,228

Claims priority, application France, Feb. 16, 1968, 1218176


Int. Cl. B21b 39/08, 35/00

U.S. Cl. 72-205

11 Claims

Rolling mill for producing thin strip stock which comprises: a first tension unit acting as a retaining unit, a second tension unit acting as a driving unit, said first and second units comprising each a number of rolls driven at a same

peripheral velocity from driving means, said strip to be rolled being passed over said rolls; coupling means arranged between said first and second units and adapted to impart a constant and possibly adjustable value to the ratio of the tangential speeds of said rolls of said first and second units,



means for driving with an adjustable torque the combined mechanism consisting of said first and second tension units, and a four-high stand disposed between said units and provided with work rolls of relatively small diameter rotatably driven by frictional engagement from positively driven supporting rolls.

3,580,034

ROLLING MILLS


Alexander Ian Wilson, Sheffield, England, assignor to The Hille Engineering Company Limited, Sheffield, England

Filed July 30, 1968, Ser. No. 748,716

Int. Cl. B21b 31/00

U.S. Cl. 72-237

10 Claims



A rolling mill has adjacent roll chocks connected together by a pair of pins extending parallel to the axes of the rolls.

3,580,035

ROLLING MILLS

Harry Laurence Fred Bond, Hathersage; Dennis Stubbs, and Maltby Todwick, Sheffield, all of England, assignors to Davy and United Engineering Company, Limited, Yorkshire, England

Filed Apr. 5, 1968, Ser. No. 719,135


Int. Cl. B21b 31/16

U.S. Cl. 72-243

8 Claims

A rolling mill stand has two pairs of housing posts, the members of each pair defining a space therebetween for receiving one above the other the chocks for at least two rolls, a separate housing top overlying all four members and which is adjustably displaceable vertically relative to the posts, the top having a pair of parts extending sideways beyond the planes through the pairs of housing posts and means carried by the extended parts for bending the roll supported by the uppermost chock in each of said spaces. The base of the housing posts also has a pair of parts extending

sideways beyond the planes through the pairs of housing posts and means carried by the pair of extended parts for



bending the roll supported by the lowermost chock in each of the spaces.


3,580,036

METHOD OF ROLLING ON A PILGER MILL

Iosif Luovich Zayats, Moskovskoi oblasti ulitsa Zhulyabina, 3, kv. 99, Moskovskoi oblasti ulitsa Zhulyabina, 3, kv. 99; Vladimir Pavlovich Barabashkin, Moskovskoi oblasti, ulitsa Noginsky proezd, 30, kv. 21, Elektrostal; Boris Nikolaevich Matveev, Balaklavsky prospekt, 24, Korpus 2, kv. 157, and Jury Fedorovich Shevakin, Telegrafny pereulok, 11/11, kv. 53, Moscow, U.S.S.R.
Filed Oct. 15, 1968, Ser. No. 767,678
Int. Cl. B21b 35/00

U.S. Cl. 72-249

11 Claims



A method of pilger rolling is disclosed which employs a pilger mill which comprises spaced die rolls mounted for continuous rotation about fixed axes. The feeding and rolling are effected intermittently step by step. A step of feeding of the successive portion of a blank into the gap between rolls and the next step of rolling this portion are effected during one revolution of the rolls. The directions of blank movement are opposite in feeding and rolling. A device is provided between the drive motor and the rolls to convert the uniform rotation of the drive motor into a periodically varying rotation of rolls. Thus the rotary speed of the rolls is varied periodically within each revolution so that the rate of speed during feeding is lower than that when the feeding is arrested and the successive portion of blank is rolled. Several different forms of device are provided, such as an elliptical gear train, multitlink and slide block mechanisms.

3,580,037

TUBE EXTRUSION APPARATUS INCLUDING SEPARABLE ARRESTED MANDREL TIP TUBE CUTOFF


John W. Issott, Dearborn, Mich.; Harold E. Honkala, and Delbert V. Carraher, Decatur, Ala., assignors to Universal Oil Products Company, Des Plaines, Ill.
Filed Oct. 7, 1968, Ser. No. 765,406
Int. Cl. B21c 23/00

U.S. Cl. 72-255

7 Claims

Tube extrusion apparatus employing an arrested mandrel having a separable tip including axially spaced extrusion and

cutoff portions. The mandrel tip is substantially smaller than the main mandrel which supports the tip during billet piercing operation resulting in back extrusion of the billet materi-



al. The mandrel is stationary during the extrusion operation and at the completion advances slightly to introduce the tube cutoff portion of the mandrel tip into the extrusion die.


3,580,038

EXTRUSION MANDREL AND METHOD

Jean-Michel Andreassian, Parmain, France, assignor to Compagnie Du Filage Des Metaux Et Des Joints Curty, Paris, France
Filed Apr. 3, 1968, Ser. No. 718,416
Int. Cl. B21c 23/04, 25/00; B21b 17/02

U.S. Cl. 72-264

5 Claims



An improvement in an extrusion mandrel in combination with the cylindrical part of the mandrel that defines the interior contour of the extruded workpieces which includes a short front member of generally cylindrical configuration but having a cross-sectional diameter and a length less than the cylindrical part and a base member joining the front member to the cylindrical part. In use, the mandrel is positioned so that the short front member always cooperates with the die at the beginning of the extrusion.


3,580,039

DEVICE FOR MANUFACTURING BLADES FOR THE BLADE WHEEL OF AN AXIAL FLOW MACHINE

Martti Heinonen, Turku, Finland, assignor to Valmet Oy, Helsinki, Finland
Filed June 20, 1968, Ser. No. 738,547
Claims priority, application Finland, June 21, 1967, 1753/67
Int. Cl. B21d 41/02

U.S. Cl. 72-316

5 Claims



Blades which are to be attached to the blade wheel of an axial flow machine, have a paddle part and an attachment surface which are simultaneously shaped in two molds. One of these molds shapes the paddle part in the desired manner

while the other mold imparts the final shape to the attachment surface. Then the two molds with the blade still clamped in them are twisted to produce the desired blade angle.


3,580,040

PROCESS AND TOOL FOR FORMING HOLES IN PROFILED MEMBERS WITH A PREDETERMINED SPACING

Gunther Lang, Triesterstrasse 388, Graz-Puntigam, Steiermark, Austria
Filed Oct. 30, 1968, Ser. No. 771,805
Claims priority, application Austria, Oct. 30, 1967, 9764/67
Int. Cl. B21d 43/28; B21c 37/02; B26d 1/00

U.S. Cl. 72-324

7 Claims



A process is disclosed for providing holes with particular spacing in profiled metal sheets, preferably of steel, wherein the shaping of the sheets follows the formation of the holes in the sheet. The invention contemplates cutting the perforations in the sheet while it is flat and prior to its shaping, such that the spacing between the holes in the longitudinal direction of the sheet is less than the standard spacing to be provided in the shaped member to compensate for the elongation of the sheet in the longitudinal direction during the shaping of the sheet. A tool for punching the holes includes insert members which are adjustable for regulating the reduced spacing of the holes to be punched in the sheet.


3,580,041

DIE ASSEMBLY

Lorenz Tilly, Montreal, and Barrie Bonner, Westmount, Quebec, Canada, assignors to Universal Alufolien Verfahren A.G., Zug, Switzerland
Filed Feb. 5, 1968, Ser. No. 702,901
Int. Cl. B21d 22/22

U.S. Cl. 72-336

12 Claims



A method and apparatus for forming sheet material, such as light gauge foil, into containers and the like. A punch and die arrangement includes supporting the forming portions of the die assembly by a pressurized fluid such as air so that these portions yieldably conform with precision to the punch surfaces during a forming operation.


3,580,042

WIRE GROOVING METHOD AND MACHINE

David W. Snyder, Hilton, N.Y., assignor to Snyder Specialty, Inc., Hilton, N.Y.
Filed Nov. 12, 1968, Ser. No. 774,751
Int. Cl. B21d 28/00, 31/00; B21c 3/02

U.S. Cl. 72-339

8 Claims



Wire stock is given an encircling, coaxial groove by shearing off a pair of slugs of material along equal and parallel chord planes on opposite sides of the wire axis, and pressing the remaining core of material in the direction of the chord planes first from one side and then the other to form the cylindrical surfaces of the groove. The shearing tool preferably includes a semicylindrical, concave die for forming half the groove surface in the shearing stroke, and a die with a slightly larger diameter semicylindrical surface presses from the opposite direction to complete the groove.


3,580,043

WHEEL ROUNDING MACHINE

George E. Gollwitzer, Belleville, Mich., assignor to Kelsey-Hayes Company
Filed Oct. 22, 1968, Ser. No. 769,625
Int. Cl. B21d 41/00

U.S. Cl. 72-402

7 Claims



A machine for rounding assembled wheels and for accurately forming and aligning a locating hole in the wheel spider with relation to the rim. The machine includes a plurality of radially movable rounding dies for engagement with the rim of the assembled wheel for rounding the rim. In addition, a forming tool in the form of a rotating cutter is provided for forming and aligning a locating opening in the wheel spider. The forming tool is supported by aligning means that are engageable with the inner periphery of the rim of the wheel when the rounding dies are in their rounding position for accurately aligning the forming tool with respect to the rounded rim. The aligning means comprises a floating backup ring to assist in the wheel rounding operation.

3,580,044

TUBE BENDING MANDREL


Edwin A. De Voss, 2550 Pacific Coast Highway, Torrance, Calif., and Antone M. Guerreiro, 3730 W. 132nd St., Hawthorne, Calif.

Filed Mar. 24, 1969, Ser. No. 809,713

Int. Cl. B21d 9/01

U.S. Cl. 72-466

3 Claims



A mandrel useful in tube bending operations, the mandrel being constructed—for the most part of plastic or like materials—and includes means whereby the mandrel may be reshaped insuring smooth continuous bends therein free of wrinkles corrugations and the like.

3,580,045

METER PROVER


Raymond H. Pfrehm, Houston, Tex., assignor to Esso Research and Engineering Company

Filed July 16, 1968, Ser. No. 745,256

Int. Cl. G01f 25/00

U.S. Cl. 73-3

15 Claims



A bidirectional meter prover adapted to be connected to a conduit having a meter arranged therein is provided with a valve means connected to the calibration barrel of the meter prover and to the meter such that the valve means is rapidly shifted for movement of the piston in the meter prover in either direction in the calibration barrel for proving the meter. The meter prover is adapted for proving meters used for metering cryogenic liquids with the cryogenic liquid being introduced into the meter proving system and with the cryogenic liquid being vented as the system is cooled to equilibrium temperature; venting is stopped while introduction of cryogenic liquid is continued until thermal equilibrium is reached. Thereafter, the system is operated to prove the meter at equilibrium temperature.

3,580,046

METHOD AND APPARATUS FOR TESTING ROTATION-RESPONSIVE DELAY DEVICES

Oliver F. Cheney, Philadelphia, Pa., assignor to Delaware Valley Armaments, Inc., Mt. Laurel Twp., N.J.

Filed June 13, 1969, Ser. No. 833,007


Int. Cl. F42c 21/00

U.S. Cl. 73-5

8 Claims

Arming delay-devices, suitable for delaying the arming of

an artillery shell until it is well away from the gun by which it is fired, are tested in production by rotating each of them in a



test stand and determining the number of turns of the device required for it to become armed.

3,580,047

POUR AND CLOUD POINT ANALYZER


Samuel W. Simpson, Florissant, Mo., assignor to Shell Oil Company, New York, N.Y.

Filed Nov. 24, 1967, Ser. No. 685,587

Int. Cl. G01n 25/02

U.S. Cl. 73-17

6 Claims



Apparatus for determining the pour point of an oil sample by observing the temperature at which the solidified constituents in the oil sample, upon being heated, will no longer support a small object. This point is indicated by discontinuance in an automatically recorded time/temperature curve during the warming portion of the cycle. The inception point of a plateau in the time/temperature curve during the cooling portion of the cycle is the crystal point. This crystal point correlates with the ASTM cloud point. Modification of the apparatus for continuous service can be accomplished by automatically introducing the sample, then cooling, heating, removing the sample and recirculating a fresh sample.

3,580,048

SIMULATOR FOR SIMULATING THE ACTION OF THE PRESSURE OF A SHOCK WAVE OF A NUCLEAR EXPLOSION

Walter Trinks, Bad Honnef; Theodor Karl Netzer, Pocking-Starnberg; Hans T. Victoria, Bliesheim bei Lechenich; Hermann Saurer, and Heinrich Von Paulgerg, Bonn, Germany, assignors to Berliner Maschinenbau A Gvorm. L. Schwartzkopff, Bonn-Tannenbusch, Germany

Filed Feb. 21, 1967, Ser. No. 617,619

Int. Cl. G01m 7/00



U.S. Cl. 73-35

15 Claims

A simulator to simulate the effects of a nuclear explosion and wherein the simulator is adapted to be placed on the object to be tested. The simulator includes an outer housing in which is situated a thrust-producing means for producing a thrust having the nature of a rocket thrust, and a transfer means is carried by the housing for transferring from the latter the reaction of the thrust to the object to be tested. The housing has an opening through which a fluid discharges during action of the thrust-producing means, and this thrust-producing means may take the form of a body of water situ-

ated in the housing and acted upon by air under pressure. A burstable membrane closes the discharge opening of the housing, and an explosive is provided for bursting the membrane or diaphragm so as to release the pressure in the hous-

ing, the water being discharged therefrom by the air under pressure so as to provide a thrust which can be transmitted to the object to be tested for simulating the action of a nuclear explosion.



ing, the water being discharged therefrom by the air under pressure so as to provide a thrust which can be transmitted to the object to be tested for simulating the action of a nuclear explosion.

3,580,049

ROCKET BURN RATE TESTING DEVICE


Lonnie D. Cardwell, Irving; Fred T. Esenwein, and Arthur E. Pierard, Arlington, Tex., assignors to The United States of America as represented by the Secretary of the Navy

Filed July 25, 1968, Ser. No. 750,426

Int. Cl. G01n 33/22

U.S. Cl. 73-35

1 Claim



A closed chamber designed to hold one or more strands of a solid propellant is equipped with igniting means, pressure indicating means, and burning rate indicating means. The apparatus avoids the problems inherent in static burning rate tests using an inert pressurizing gas.

3,580,050

TESTING DEVICE FOR STRETCHABLE SHEET MATERIALS UNDER SIMULTANEOUS DISTORTION IN THREE DIMENSIONS

Paul H. R. Waldron, 175 Jupiter Point Road, Groton, Conn.

Filed May 19, 1969, Ser. No. 825,856

Int. Cl. G01m 3/02

U.S. Cl. 73-37

13 Claims

Apparatus for testing stretch, recovery and hysteresis characteristics of fabrics particularly useful for elastic fabrics of type used in foundation garments and brassieres, including multidirectionally stretchable isotropic or nonisotropic fabrics. Test sample is secured against an elastomeric diaphragm which is progressively inflated to distort sample in three dimensions while measuring volumetric change in relation to force applied. Device also plots relationship of force to dimension change in sample in any desired direction or directions. Both volumetric and dimensional changes are also plotted to show recovery characteristics of fabric during

paper, felts or other sheet material to test stretch and/or bagging and/or bursting characteristics.

3,580,051


METHOD FOR LEAK TESTING MASKS

William V. Blevins, Joppa, Md., assignor to the United States of America as represented by the Secretary of the Army Division of Ser. No. 662,209, Aug. 21, 1967, Pat. No. 3,504,542. application Oct. 3, 1969, Ser. No. 871,119

Int. Cl. G01m 3/26

U.S. Cl. 73-40

1 Claim



A method for leak testing masks by hermetically sealing a flowmeter at the mouth area of the mask undergoing test and monitoring leakage due to external pressure during mask wearer's breathing function.

3,580,052

DISCHARGE GAGE FOR HELIUM LEAK DETECTOR USE


James Roger Young, Rexford, N.Y., assignor to General Electric Company

Filed Oct. 23, 1969, Ser. No. 868,877

Int. Cl. G01m 3/04

U.S. Cl. 73-40.7

6 Claims



A Penning-type discharge gage for a leak detector using a mass spectrometer and helium as a probe gas uses graphite cathodes to eliminate the helium memory associated with cathodes consisting of other materials.

3,580,053

CIGARETTES TESTING

Desmond Walter Molins, Deptford, London, England, assignor to Molins Machine Company Limited, London, England


Filed Oct. 7, 1968, Ser. No. 765,374

Claims priority, application Great Britain, Oct. 11, 1967, 46375/67

Int. Cl. G01m 3/04

U.S. Cl. 73-41

4 Claims



Testing cigarettes for leaks by passing them endwise through a suction chamber which draws air from atmosphere through the end of a cigarette and through its wrapping and the pressure of which fluctuates according to the air flow.

3,580,054

APPARATUS FOR DETECTING LEAKS IN HOLLOW BODIES

Hermann Schlumbaum, Wennigsen, Deister, Germany, assignor to Stephan-Werke GMBH & Co., Hamel/Weser, Germany


Filed Oct. 4, 1968, Ser. No. 765,078

Claims priority, application Germany, Oct. 5, 1967, P 16 48 736.8

Int. Cl. G01m 3/26

U.S. Cl. 73-49.2

7 Claims



Apparatus for detecting the presence or absence of leaks in bodies of automotive vehicles comprises a frame which supports an electric motor serving to drive a suction generating device whose inlet is connected with a suction conduit. The latter can be placed against the opening of an automobile body to evacuate air, and a gauge, U-tube or analogous measuring device is provided to determine the pressure in the opening and/or in the suction conduit to thereby indicate the presence or absence of leaks. The frame may be provided with legs and/or wheels so that it can be readily transported between storage and one or more locales of use. The frame is further provided with means for storing the suction conduit, for storing the conductor which supplies current to the motor, and/or for storing nozzles one of which can be coupled to the intake end of the suction conduit for insertion into or for placing against an opening.

3,580,055

TANK SYSTEM TIGHTNESS TESTER

Richard B. White, Orchard Lake, Mich., assignor to Kent-Moore Corporation, Warren, Mich.

Filed Oct. 25, 1968, Ser. No. 770,763


Int. Cl. G01m 3/26

U.S. Cl. 73-49.2

15 Claims

This disclosure relates to a test apparatus for measuring the tightness of tanks, such as underground fuel storage tanks, and a method of performing the test. The apparatus includes a temperature sensing device adapted to measure the temperature of the fluid within the tank, a means to establish a fluid head in communication with the fluid in the tank to

measure the change in volume of fluid in the system during the test period, and a fluid circulating system which continuously circulates fluid from the tank and back to equalize the temperature of the fluid in the tank, and permit accurate



compensation for temperature variations in the system. In the disclosed embodiment, a means is provided to adjust the height of the fluid head to stabilize the deflection of the walls of the tank.

3,580,056

NONDESTRUCTIVE, RESONANT TESTING APPARATUS WITH MAGNETIC PICKUP


Robert F. Warner, Coldwater, Mich., assignor to Hayes Albion Corporation, Jackson, Mich.

Filed Oct. 12, 1967, Ser. No. 674,798

Int. Cl. G01h 13/00

U.S. Cl. 73-67.2

3 Claims



A casting under test is placed in a magnetic field and struck with a hammer causing the casting to vibrate at its resonant frequency. There is a pickup coil disposed in the field to sense variations thereof caused by vibration of the casting. The pickup coil develops a test signal whose frequency and amplitude represent the vibration of a casting. The test signal is processed via a frequency discrimination circuit and a decay rate detection circuit to ascertain when the vibration frequency and the vibration decay rate are acceptable.

3,580,057

PROBE DEVICE USABLE IN MEASURING STRESS

Ben L. Seegmiller, Salt Lake City, Utah, assignor to The University of Utah, Salt Lake City, Utah

Filed June 19, 1969, Ser. No. 834,834


Int. Cl. G01n 29/00

U.S. Cl. 73-67.6

2 Claims

U.S. Cl. 73-71.5

26 Claims



A probe device for use with stress-measuring apparatus and having plural probes provided with mutually and, in one form of the invention, variably spaced tips. These tips preferably comprise parallel, chisel-contact tips. Transducers such as piezoelectric crystals are respectively operatively associated with said tips, with the intercoupling areas of the crystals and coaxial cable conductors coupled thereto being constructed to provide maximum shielding of such areas against external electromagnetic-wave or other interference. The rearward face of each crystal is connected by highly flexible conductor means to the central conductors of the coaxial cables. The forward faces of the respective crystals are preferably grounded through the tips and the jackets electrically connected thereto to the coaxial shields of the cables. Central members or plugs are employed to connect the shield to its respective jacket and at the same time isolate the crystal-conductor junction areas.

3,580,058

DUAL ULTRASONIC SENSORS EMPLOYING A SINGLE MODE OF ULTRASONIC TRANSMISSION


Lawrence C. Lynnworth, Waltham, Mass., assignor to Panametrics, Inc., New York, N.Y.

Filed May 21, 1968, Ser. No. 730,713

Int. Cl. G01n 29/00

U.S. Cl. 73-67.7

13 Claims



An ultrasonic measuring system for determining ambient conditions on two sensing elements. The elements may be positioned either to respond to a distribution in space of one ambient condition or to respond to two different ambient conditions in the same area. An ultrasonic transducer produces waves in only one ultrasonic mode, which are coupled to two sensors by means of a single lead-in element. The relative acoustic impedances of the sensors and their dimensions in a direction of propagation of the ultrasonic waves are such that the reflection pulses generated at each end of each of the sensors are identifiable with those ends of the sensors based upon their distribution in time, or their polarity or both. These dimensions and relative impedances are controlled so that reverberation pulses do not create an ambiguity and the identification of the primary marking pulses are generated at each end of the sensors.

3,580,059

SPHERICAL BEARING TESTER


Robert Barry Dalton, Monroe, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed Jan. 13, 1969, Ser. No. 790,645

Int. Cl. G01m 13/04

U.S. Cl. 73-71.5

26 Claims



A spherical bearing tester providing oscillatory rotating motion of the inner bearing race with respect to the outer bearing race about the thru-shaft longitudinal axis, also providing an oscillatory relative motion between the outer and inner races about an axis perpendicular to the thru-shaft longitudinal axis, also providing a bearing load along the axis of the thru-shaft, and also providing a bearing load so as to cause the outer race to attempt to move with respect to the inner race as a result of a force which is perpendicular to both the thru-shaft longitudinal axis and the axis about which the outer race oscillates with respect to the inner race.

3,580,060

HARDNESS TESTER


Joseph E. Huskey, Copperhill, Tenn., assignor to Cities Service Company

Filed Oct. 24, 1968, Ser. No. 770,150

Int. Cl. G01n 3/18, 3/08

U.S. Cl. 73-78

4 Claims



The hardness of crushable materials is determined by an apparatus capable of applying a uniformly increasing compression force to the material undergoing test. This force is

applied by a plunger exerting a downward pressure on the crushable material and by the weight of a receiving container suspended from the plunger. During the test, the weight exerted by the suspended container is continuously and uniformly increased by the flow of fluid from a reservoir tank into the receiving container. The flow of fluid is commenced by the opening of a normally closed solenoid valve in response to the closing of a relay switch. This switch is adapted to assume an open position when the weight of fluid in the receiving container becomes sufficient to cause the plunger to drop to a lower position upon crushing of the crushable material being tested. The opening of the relay switch, in turn, causes the solenoid valve to close upon crushing of the material being tested. The weight of the plunger and the suspended receiving container, together with the fluid in the container, provides a precise measure of the hardness of the crushable material.


3,580,061 SEAL-TESTING DEVICE

William H. Neuman, Cedar Falls, Iowa, and James A. Repella, Madison Heights, Mich., assignors to Federal-Mogul Corporation, Southfield, Mich.

Filed Jan. 16, 1970, Ser. No. 53,333
Int. Cl. G01n 3/08

U.S. Cl. 73-88R

3 Claims



A device for indicating whether a lip-type seal may be satisfactorily reinstalled. A simulated shaft and seal retaining environment is provided, and the simulated shaft has a plurality of radially extending members normally urged radially outwardly at a predetermined pressure. When the seal urges all of these members in at a somewhat greater pressure, a series circuit is completed to give a signal. The seal is deemed satisfactory if the signal remains in operation for a predetermined time interval.


3,580,062 SURFACE-MEASURING DEVICE

Johannes Perthen, 3 Sedanstr. 13, Hannover; Werner Gerighausen, Ronnenberg; Konrad Kunzmann, Röllinghausen, and Heinz Dreyer, Devese, Germany assignee said Gerighausen, said Kunzmann and said Dreyer assignors to said Perthen

Filed July 24, 1968, Ser. No. 747,317
Int. Cl. G01b 5/28

U.S. Cl. 73-105

2 Claims



The device comprises mechanism for moving relative to one another a workpiece and a feeler point contacting the

surface of the workpiece. An electromechanical transducer is mechanically connected to the feeler point for converting into electrical signals the movements of the feeler point normal to the surface of the workpiece, and is electrically connected through an amplifier to an electrical integrator for integrating such electrical signals. A device for determining the length of the relative movement of the workpiece and feeler point is connected to apparatus for determining the magnitude of the electrical signals integrated by the integrator, to vary the magnitude of the integrated signals inversely with the length of such relative movement, so that the integration determines the mean value of the profile of the surface of the workpiece independently of such length.

3,580,063 SYNCHRONOUS SPARK TIMER

Daniel M. Goodnow, Box 306F, Opel Road, Stone Haven, Rte. 1, Glen Burnie, Md.

Filed Apr. 11, 1969, Ser. No. 815,449
Int. Cl. G01m 15/00

U.S. Cl. 73-118

3 Claims



A test harness and spark electrode arrangement is provided for facilitating the timing of electrical ignition gas engines. A permanent magnet allows the electrode to be positioned anywhere on the engine block and is especially useful in conjunction with the flywheel or cam gear timing mark where the spark can be made to appear at only the correct timing interval.


3,580,064 RADIAL RUNOUT RECORDER

Ari Bar-on, Cherry Hill, N.J., and Norman M. Emslie, Yardley, Pa., assignors to Philco-Ford Corporation, Philadelphia, Pa.

Filed Mar. 27, 1969, Ser. No. 811,138
Int. Cl. G01m 17/02

U.S. Cl. 73-146

4 Claims



Apparatus for recording "radial runout" of a loaded automobile wheel and tire combination. Linkage is provided to

measure the radial runout while the wheel is under normal load, and includes a device—such as an elongate indicator-pen arm—to multiply the measurement. The multiplied value is recorded on a chart secured to the wheel and concentric therewith.


3,580,065 LAMINATE BOND PEELING STRENGTH TESTER

David J. Strittmater, and Nicholas W. Voelker, La Crosse, Wis., assignors to Universal Oil Products Company, Des Plaines, Ill.

Filed May 7, 1969, Ser. No. 822,558
Int. Cl. G01n 19/04

U.S. Cl. 73-150

10 Claims



An apparatus for testing of laminate bonds having in a preferred embodiment a vacuum plate holddown device attached to a vertically movable fluid power-operated piston. A tension gage and clamping device is suspended above the piston and is free to move in a horizontal plane. The vacuum plate holds the sample in position while the clamping device is attached to a turned up strip of laminate. While being held in this position, the piston is moved downward at a fixed rate of speed, and the gage is read indicating the amount of forces exerted as the laminate is being peeled. In another embodiment a heating element and mechanically operated holddown device is provided therein to provide for testing under elevated temperatures.

3,580,066 METHOD FOR DETECTING EXPOSURE OF A BASE MATERIAL THROUGH AN OVERLYING COATING

William A. Pliskin, Poughkeepsie, and James E. Taylor, Wappingers Falls, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed June 19, 1969, Ser. No. 834,884

Int. Cl. G01n 13/00

U.S. Cl. 73-150

6 Claims

The method for determining the completeness of etching of an oxide from a silicon semiconductor device discloses that bare silicon surfaces are hydrophobic while clean freshly etched oxide surfaces are hydrophilic. To determine whether the silicon is exposed, and therefore free of any oxide film subsequent to etching, the device is cooled and subjected to a stream of moist gas and observed under a microscope. If the etching process by which small holes are formed is incomplete, oxide will remain in the hole and therefore a film of condensed water will form in the holes indicating incomplete etching. If the etching process has been properly completed in the holes, bare silicon will remain causing the moisture to form in small droplets. The form of the moisture can be observed through the microscope.


3,580,067 METHOD OF DETERMINING THE RATE OF VAPOR TRANSMISSION THROUGH SHEET MATERIALS

Melford E. Mandrell, and Wayne W. Blaser, Midland, Mich., assignors to The Dow-Chemical Company, Midland, Mich.

Filed Nov. 2, 1967, Ser. No. 680,128
Int. Cl. G01n 15/08

U.S. Cl. 73-159

1 Claim



This invention relates to a method of determining the rate of vapor transmission through sheet materials wherein a defined area of test sheet material fitted over the end of a bottle-like element is exposed to standardized radioactive water under constant conditions of temperature and humidity.

Radioactive water which penetrates the test sheet is, for example, absorbed on calcium chloride. After a known time interval the calcium chloride is analyzed for radioactivity by means of liquid scintillation counting. The vapor transmission rate is calculated from the amount of radioactivity present in the calcium chloride.


3,580,068 APPARATUS FOR TESTING ROTARY POWER TRANSMITTING COMPONENTS

Louis S. Hoodwin, Rte. 1, Box 246, Sawyer, Mich.

Filed Aug. 26, 1968, Ser. No. 755,361
Int. Cl. G01m 13/02

U.S. Cl. 73-162

5 Claims



This invention describes apparatus for testing rotary power transmitting components by measuring the differential angular accelerations between the inputs and outputs of such components.

3,580,069 SUBSONIC FLUIDIC ANGLE-OF-ATTACK SENSOR

Raymond W. Warren, McLean, and Elmer L. Swartz, Annapolis, Va. The United States of America as represented by the Secretary of the Army


Filed June 9, 1969, Ser. No. 831,526
Int. Cl. G01c 21/00

U.S. Cl. 73-180

11 Claims

A fluidic angle-of-attack indicator for subsonic aircraft is disclosed. Two sensing tubes are located in that portion of the stagnation region of the wing of the aircraft where the flow separates and are used to control the output position of the power jet of a proportional fluid amplifier. As the angle of attack changes the rate of fluid entrainment from each of the sensing tubes changes and causes deflection of the power jet. The source of fluid for the power jet is derived from a

ram tube located on the wing surface, with an air filter being positioned between the power jet and the open end of the ram tube. The readout consists of a piston-type float which is responsive to a fluid pressure differential on its opposing sides. A side-slip indicator, using the above arrangement, is



provided by rotating the sensing tubes 90° and locating them in the stagnation region of the aircraft's vertical stabilizer.

The invention described herein may be manufactured, used, and licensed by or for the United States Government for governmental purposes without the payment to us of any royalty thereon.


3,580,070 HEAT METER

Edward H. Cumpston, Jr., 43 Monument Ave., Old Bennington, Vt.

Filed July 11, 1968, Ser. No. 744,000
Int. Cl. G01n 1/00

U.S. Cl. 73-193

9 Claims



The heat carried by a variable temperature fluid moving at a known rate through a conduit is measured by recording the time required for a conductor thermally coupled to the conduit to lose heat to the conduit from a predetermined higher temperature that is maintained by a heater and a temperature-sensitive switch thermally coupled to the conductor.

ERRATUM

For Class 73-194 see:
Patent No. 3,580,092


3,580,071 FLOWMETER PROBE

Norman A. Hickman, Ventura, Calif., assignor to Statham Instruments Inc., Oxnard, Calif.

Filed Feb. 26, 1969, Ser. No. 802,517
Int. Cl. G01p 5/08

U.S. Cl. 73-194

9 Claims



An insulative hollow cylindrical tube of inner bore sufficient to accommodate a blood vessel under test, has a lon-

gitudinal wedge-shaped portion that is removable to provide an access opening. A first magnetizing coil includes a core that extends circumferentially about the insulative cylinder of substantial angular extent. A second coil has a core extending in the same direction, but of substantially less angular extent than the core of the first coil. The two coils are serially related and energized to induce a potential in the flowing blood which is measured by electrodes carried by the insulative cylinder. The entire assembly is enclosed with a further cover cylinder concentrically arranged about the first coil and end plates.

The present invention relates generally to a blood flowmeter, and, more particularly, to a probe for mounting about a blood vessel to measure the flow rate of blood passing therethrough.


3,580,072 TIME AVERAGING METHOD AND APPARATUS FOR OBTAINING FLUID MEASUREMENTS

John B. Cox, and Jacque R. Stoltz, Midland, Tex., assignors to Mobil Oil Corporation

Filed Dec. 27, 1967, Ser. No. 693,867
Int. Cl. G01p 5/00

U.S. Cl. 73-205

5 Claims



This specification discloses a method and apparatus for accumulating signals from a water-cut monitor and a flow meter in a form whereby the net oil and net water in an oil-water mixture may be determined. A flow meter signal in the form of constant-amplitude, frequency-variable DC pulses is applied to a capacitor to charge the same. A signal from the water-cut monitor is modulated in proportion to the meter signal in order to produce a modulated signal of DC pulses in which pulse amplitude is proportional to water content and pulse frequency is proportional to flow rate. This modulated signal is stored on another capacitor. Both capacitors are interrogated at periodic time intervals in order to obtain readout signals representative of the charges thereon and the capacitors are discharged. Also disclosed is a system for obtaining gas flow information. In this system a pressure signal is modulated in proportion to a ΔP signal to produce a modulated signal of DC pulses which is applied to a capacitor. The capacitor is interrogated as described above.

3,580,073 TEMPERATURE COMPENSATOR

Howard E. Siebold, Libertyville, Ill., assignor to Liquid Controls Corporation, North Chicago, Ill.

Filed June 3, 1968, Ser. No. 733,995
Int. Cl. G01f 3/02


U.S. Cl. 73-233

14 Claims

A temperature compensator modifies the output from a volumeter to compensate for the effect of temperature changes on the volume of a fluid being metered and includes a differential gear train having an output shaft that rotates at a speed equal to the rotational speed of one of its inputs, which is dependent on the volume of the fluid being measured, minus the rotational speed of its other input, which is dependent on the difference in temperature between the temperature of the fluid being metered and a standard temperature. The temperature-dependent input is controlled by a

pair of reciprocating linkages, which are pivotally connected to a bellcrank, which pivots in response to a temperature-

tric constant resulting from temperature changes in the liquid. The resulting compensated signal is further adjusted by subtracting from it a signal derived from the temperature sensor to account for expansion or contraction of the liquid below the bottom of the level sensor.



sensing device, for adjustably controlling the length of the stroke of the reciprocating linkages.


3,580,074 TEMPERATURE-COMPENSATED LIQUID QUANTITY GAGE

Vernon C. Wescott, Lincoln, and Sidney B. Williams, Lexington, Mass., assignors to Trans-Sonics, Inc., Lexington, Mass.

Filed May 23, 1969, Ser. No. 827,276
Int. Cl. G01f 23/26; G01k 7/12

U.S. Cl. 73-304C

6 Claims



A temperature sensor comprises the usual "hot" thermocouple junction exposed to the temperature to be monitored, a reference junction, a thermally sensitive resistor connected to compensate for changes in the temperature of the reference junction and a readout unit that converts the outputs of these elements to a temperature indication. The reference junction and the resistor are located in the probe that contains the hot junction, so that the leads extending from the probe to the readout unit need not be made of the materials of which the thermocouples are made. The thermally sensitive resistor is in series with the hot junction and reference junction. This permits the use of a single pair of leads to carry current for the resistor and, at the same time, bring back to the readout unit a net voltage comprising the thermocouple junction voltages and the compensating voltage from the resistor.

A capacitive-type liquid quantity gage extending partway down into a tank includes a capacitive liquid level sensor and a temperature sensor positioned to sense the temperature of the liquid monitored by the level sensor. The output of the temperature sensor controls the drive voltage to the level sensor so as to compensate for changes in density and dielec-


3,580,075 PRESSURE TRANSDUCER FOR IONIZABLE FLUIDS

David R. Steinberg, Raleigh, N.C., assignor to Corning Glass Works, Corning, N.Y.

Filed July 31, 1967, Ser. No. 657,370
Int. Cl. B21d 28/00

U.S. Cl. 73-339

11 Claims



A pressure transducer for ionizable fluids having no vibrating or moving parts and capable of reliable operation at high ambient temperatures is disclosed. The driving fluid to be detected is introduced into a space between a pair of electrodes across which an ionizing electrical potential exists. Ionic current flow between the transducer electrodes is a function of the instantaneous density of the driving fluid within the interelectrode space and produces corresponding current and voltage drops in an external circuit of sufficient intensity to drive detectors, amplifiers, or a variety of electrical instruments.

3,580,076 ACOUSTIC THERMOMETERS

Eric George Herbert Mobsby, Blandford Forum, England, assignor to United Kingdom Atomic Energy Authority, London, England


Filed June 28, 1967, Ser. No. 649,516

Claims priority, application Great Britain, June 29, 1966, Nov. 21, 1966, 29316/66; 52098/66

Int. Cl. G01k 11/24

U.S. Cl. 73-339

2 Claims



A thermometer which measures temperature by the time taken by a sound pulse to travel along a probe. The sound pulse emanates from a transducer coil and magnetostrictive element and travels in two opposite directions. One direction is toward a terminal mass polarized by a magnet where the sound is reflected by the terminal mass and so phased to increase the pulse width at the point of emanation. The other direction of the pulse is toward a probe by way of the magnetostrictive element itself and a transmission line. Reflections from the two ends of the probe are sensed and the time between the reflected pulses from the ends of the probe is measured as function of temperature. The magnetostrictive element is preferably twisted along its length.

3,580,077

CLINICAL THERMOMETER STORAGE AND STERILIZING APPARATUS


Seymour N. Blackman, 3 Horizon Road, Penthouse #4, Fort Lee, N.J.

Filed Nov. 18, 1968, Ser. No. 776,363

Int. Cl. G01k 1/00, 1/14; A61l 3/00

U.S. Cl. 73-343

10 Claims



A thermometer storage container is cylindrically shaped and longitudinally ribbed along its outer surface. The ribs engage resilient gripping flanges on a wall bracket permitting the container to be snapped forwardly into the bracket and axially withdrawn therefrom. A drip proof cover engages a diaphragm at the upper end of the container and encases the upper portion of a thermometer which projects through the diaphragm. The lower portion of the thermometer within the container below the diaphragm is immersed in propylene glycol which functions as a cold-sterilizing solution and additionally acts as a lubricant for rectal insertion of the thermometer.

3,580,078

THERMOCOUPLE FAILURE INDICATING DEVICE


Douglas James MacKenzie, Park Ridge, Ill., assignor to American Standard Inc., New York, N.Y.

Filed Apr. 16, 1969, Ser. No. 816,752

Int. Cl. G01k 1/08, 7/02

U.S. Cl. 73-344

4 Claims



A thermocouple for immersion in a bath of molten metal, or other liquid, comprising a closed-ended sheath having crushed ceramic insulation packed therein to thermally insulate certain hot junction wires contained within the sheath. A special auxiliary conductor is arranged within the sheath to energize an alarm circuit should a rupture develop in the sheath wall. Such rupture causes the molten metal to saturate the ceramic and electrically connect with the conductor for developing the alarm signal.

3,580,079

THERMOMETER INDICATOR

Nelson A. Crites, and Donald H. Lyons, Columbus, Ohio, assignors to Abbott Laboratories, North Chicago, Ill.

Filed Mar. 6, 1969, Ser. No. 804,878


Int. Cl. G01k 1/106; G02b 5/24

U.S. Cl. 73-358

9 Claims

A disposable clinical thermometer contains a temperature responsive material within a cell having a viewing window. The window is made translucent by abrading or roughening

its inner surface to diffuse light passing therethrough. When a predetermined temperature is reached, the material melts, spreads over and wets the roughened surface to optically



smooth it, thereby making it transparent. Indicia of temperature, previously obscured by the translucent window and the solid state temperature responsive material then becomes visible to one reading the thermometer.

3,580,080

FULL DATA ALTIMETER DISPLAY


Earl Stuart Perkins, Oak Brook, Ill., assignor to Butler National Corporation, Minneapolis, Minn.

Filed Feb. 4, 1969, Ser. No. 796,491

Int. Cl. G01l 7/20

U.S. Cl. 73-384

9 Claims



An altimeter which continuously presents to the pilot the altitude of an aircraft above ground derived from a radio altimeter or other source and which simultaneously presents to the pilot the altitude above sea level and ground obtained from a barometric altimeter. Means are provided for adjusting the reference on the barometric altimeter presentation so that the altitude of the terrain will be indicated.

3,580,081

VACUUM GAUGE

Sol Greenberg, Roslyn; Heinz Rosen, Hicksville; Richard Weinberger, Oceanside, and Guy Mongodin, Huntington, N.Y., assignors to Veeco Instruments, Incorporated, Plainview, N.Y.

Filed Sept. 10, 1969, Ser. No. 856,686

Int. Cl. G01l 21/12


U.S. Cl. 73-399

18 Claims

Disclosed herein is a Pirani-type pressure gauge having a sensor head incorporating a pressure-responsive filament, a calibrated pressure indicator, and related circuitry for converting the voltage drop across the filament into a meaningful pressure indication. The net current supplied to the filament includes both an energizing component and an indicator drive component. This net current is maintained constant by a constant current source so that, excluding ambient temperature affects, the voltage across the filament is indicative

of filament resistance and consequently ambient pressure, notwithstanding the effect of the indicator. Temperature effects are minimized by a simple compensating impedance in the filament-indicator circuit which also includes scale-

ing device for counting up the number of electrical pulses in accordance with the factor. In an alternative embodiment, high-frequency generators can be used along with a counting device for digitally accumulating electrical pulses in ac-



calibration controls and means for shaping filament response. The calibration, compensation, and shaping components are located in the filament sensor head in such a manner as to obviate the usual field adjustments required to match the sensor head and indicator.

3,580,082

PRESSURE TRANSDUCER

Richard R. Strack, Sturbridge, Mass., assignor to The Bendix Corporation, Detroit, Mich.


Division of Ser. No. 673,578, Oct. 9, 1967, Pat. No. 3,503,116, Mar. 31, 1970.

application Nov. 7, 1969, Ser. No. 871,264

Int. Cl. G01l 7/08

U.S. Cl. 73-406

9 Claims



A pressure transducer having a thin, edge-supported light-reflecting membrane or membranes with light-transmitting optical fibers for directing collimated light to the membrane for reflection thereby. A plurality of light-receiving optical fibers are disposed around each light-transmitting fiber and are connected to a light intensity measuring device. Upon membrane deflection, the direction of light reflected therefrom is changed, thereby changing the amount of light incident on the light-receiving fibers. The resultant change in light intensity transmitted to the measuring device serves as a measure of the membrane deflection and therefore the pressure acting thereon.

3,580,083

SPEED-MEASURING DEVICE

Frederick S. Zipser, 32 S. Broadway, Red Hook, N.Y.


Filed Dec. 18, 1968, Ser. No. 784,859

Int. Cl. G01l 3/00, 5/02

U.S. Cl. 73-432R

6 Claims

A device for measuring the rate of speed or distance covered by a person moving or running in place including a generator producing an electrical pulse each time a footfall is made, a device for calculating the rate at which the pulses occur, and a device for indicating the calculated rate. For distance measurements, a preset distance-factoring device can be adjusted so as to provide an indication of the distance covered between successive electrical pulses in accordance with the characteristic of the moving individual, and a count-



cordance with the interval between footfalls; and a device for producing an electrical pulse amplitude in accordance with the number of pulses representing the intrafootfall spacing, and indicating the rate and distance covered thereby.

3,580,084

PNEUMATIC PROBE SAMPLER


Harold A. Kramer, West Hyattsville, Md., assignor to The United States of America as represented by the Secretary of Agriculture

Filed Jan. 24, 1966, Ser. No. 522,784

Int. Cl. G01n 1/14

U.S. Cl. 73-421

3 Claims



A pneumatic probe for taking samples of grain and other particulate material from the bottom of a bin comprises two concentric tubes spaced sufficiently apart to permit passage of the material when entrained in a stream of air. The outer longer tube has a serrated edge to enable it to penetrate dense sections, while the inner, shorter tube is provided with helical vanes. Air, blown down the outer tube is caused to swirl in a vortex by the helical vanes, thereby entraining material lodged near the bottom of the outer tube. The air, together with entrained material, passes up the inner tube and is conducted to a cyclone separator to recover the sample.

3,580,085

POINTER STABILIZER


Alan L. Hitzelberger, Grand Blanc, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed June 2, 1969, Ser. No. 829,585

Int. Cl. G01p 1/08; G01d 11/10

U.S. Cl. 73-496

1 Claim



The invention relates to a speedometer. The following specification describes a speedometer having an improved indicating mechanism. The hub of the indicating needle is

machined to act as a bearing on the spindle, and the needle and spindle are interconnected by a damping member to filter out oscillations occurring in the pointer.

3,580,086

FLUIDIC SPEED GOVERNOR


Martin C. Doherty, Scotia, N.Y., assignor to General Electric Company

Filed Mar. 20, 1969, Ser. No. 808,869

Int. Cl. G01p 3/26

U.S. Cl. 73—506

7 Claims



A fluidic speed governor for controlling the speed of pneumatic or hydraulic machines senses the machine speed directly from pressure pulsations in the pressurized fluid supply or exhaust of the machine. The governor includes a fluidic speed-sensing circuit having no moving mechanical parts and an input connected to the pressurized fluid supply or exhaust of the machine for generating a DC-type pressurized fluid signal having a pressure magnitude proportional to the pressure pulsation frequency which is directly proportional to the actual machine speed. A second fluidic circuit connected to the output of the first circuit is provided with a speed reference input signal and generates a pressurized fluid signal indicative of the deviation of the actual machine speed from the reference speed. A fluid power amplifier connected to the output of the second circuit develops a pressurized fluid flow for controllably driving the governed machine.

3,580,087

FLUID ACTUATED INSTRUMENT SENSITIVE TO DENSITY TEMPERATURE OR LINEAR ACCELERATION


Richard L. Sampson, Excelsior, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Nov. 21, 1968, Ser. No. 777,833

Int. Cl. G01p 15/00; G01k 1/00

U.S. Cl. 73—515

10 Claims



Apparatus for measuring fluid temperature, fluid density, or acceleration, including a cylindrical chamber having a pair of radial input connections at diametrically opposite points and an axially output connection including means responsive to any vortical component of fluid flow therein. Concentric with the housing, and of somewhat smaller diameter, is an annular coupling element for insuring initial radial flow of fluid toward the output connection. The apparatus is

mounted for acceleration normal to the axis of the chamber. If this acceleration is constant (e.g. gravity) and fluids of different temperatures or different densities are supplied to the input connections, the discharging fluid has a vortical component which varies with the temperature difference or the density difference, and if one temperature or one density is also held constant, the vortical component varies with the other temperature or density. If, on the other hand, the temperatures or densities are held constant, or their differences are held constant, the vortical component varies with the acceleration.

3,580,088

CURVE GENERATING LINKAGE


James A. Clark, Rochester, N.Y., assignor to Bausch & Lomb Incorporated, Rochester, N.Y.

Filed May 1, 1968, Ser. No. 725,816

Int. Cl. F16h 21/00

U.S. Cl. 74—1

2 Claims



A multibar linkage is used to produce a noncircular motion for generating aspherical surfaces. Linkages can be optimized to conform their output motions very accurately to predetermined curves such as those developed by optical designers for aspheric lenses and mirrors. Also, in optical design, the parameters of linkages may be used in place of mathematically expressed curves thus facilitating the simultaneous optimization of an optical system and a linkage for producing an aspheric surface for the system. A dressing tool mounted on the linkage dresses a cutting wheel to conform it to the desired curvature. The wheel shapes the workpiece accordingly.

3,580,089

MOTION-CONVERTING MECHANISM

Serge Ramseier, Carouge, Geneva, Switzerland, assignor to The Battelle Development Corporation, Columbus, Ohio


Filed Nov. 21, 1968, Ser. No. 777,665

Claims priority, application Switzerland, Nov. 21, 1967, 16377/67

Int. Cl. F16h 21/18

U.S. Cl. 74—49

16 Claims



A mechanism for converting the continuous rotational motion of a crankpin into an alternating motion of a lever by means of two hinged levers, the free end of one lever being connected to the crankpin and the free end of the other lever able to move along a substantially rectilinear path (output). The connection between the crankpin and the free end of the first lever is such that the latter may describe cyclically a closed drive path located on opposite sides of the extended rectilinear path described by the free end of the second lever. Two holding members act respectively on the second lever to prevent it from moving otherwise than by a sliding motion along the latter rectilinear path, and on the guide element to

immobilize it at a fixed point coinciding with the upper end of this alternating motion. Either one or the other of the holding members is made operative and the first is arranged so as to form, when energized an abutment against which the second lever can back on to as soon as the free end of the first lever has crossed the rectilinear path (working stroke) and from which the second lever may move away when it is not energized by pivoting about the fixed point (idle stroke).

3,580,090

WINDING PITCH CHANGER OF A STATOR-WINDING MACHINE


Alexandr Andreevich Bondarenko, Moskovsky prospekt, 198/2, Kv. 69, and Fedor Grigorievich Klevanov, ulitsa Kotovskogo, 62-9, Kharkov, U.S.S.R.

Filed June 20, 1969, Ser. No. 835,170

Int. Cl. F16h 22/44; H16h 21/00; B65h 81/06

U.S. Cl. 74—96

2 Claims



A winding pitch changer of a stator-winding machine comprises a changeover transmission for swinging a winding head and connected mechanically with an adjusting mechanism, the changeover transmission being in the form of a ratchet with a retainer linked kinematically with a former cam which is connected mechanically with a slide located in the slot of a link mechanism which rotates the winding head rod, the slide being moved at the moment when the ratchet is braked by the adjusting mechanism. The adjusting mechanism comprises a spring-loaded slide provided at one end with a stop interacting with a splined disc and a roller interacting with a cam which is kinematically linked with the splined disc while at the other end it has a tooth for braking the ratchet at the moment of the pitch change.

3,580,091

ACTUATOR FOR MIXING VALVE


Lloyd Spencer, 220 Patricia Way, Pasadena, Calif., and Tor Petterson, 1344 E. 6th St., San Pedro, Calif.

Filed Apr. 10, 1969, Ser. No. 814,991

Int. Cl. F16h 21/44

U.S. Cl. 74—107

6 Claims



An actuator for a hot and cold water mixing valve, the valve terminating in a journal ball in which is mounted a pair of valve operating cam followers movable in parallel axes, the journal ball terminating in an annular stop shoulder; the actuator including an inner cap member having internal cam areas engageable by the cam followers and a peripheral movement limiting cam engageable with the stop shoulder,

3,580,092

ACOUSTIC FLOWMETER


Thomas J. Scarpa, Edison, N.J., assignor to Scarpa Laboratories, Inc.

Filed Dec. 23, 1969, Ser. No. 887,505

Int. Cl. G01f 1/00

U.S. Cl. 73—194

21 Claims



A clamp-on flowmeter having a pickup element designed to be removably secured on an external surface of a pipe, which is responsive to ultrasonic radiation generated by shear action of fluid flowing in the pipe. The signal from the pickup element is filtered, frequency-selectively amplified, and integrated, the output being used to operate indicating means, and various types of relay-actuated devices. In one embodiment, the pickup element is a piezoelectric wafer; and the response characteristic for the overall circuit including the pickup element is designed to be fairly uniform over a broad range of frequencies extending from just above the audio range to at least about 100 kilocycles. In a modification of this, the pickup element is designed to respond to a relatively narrow band of frequencies well above the audio range, to which band the amplifier-integrator circuit is specifically tuned.

3,580,093

LOWER ROLLER FOR ENDLESS TREAD FOR VEHICLE


Kazuhiro Tomizawa, Tokyo, Japan, assignor to Nittai Lease Company, Ltd., Tokyo, Japan

Filed Mar. 10, 1969, Ser. No. 805,395

Int. Cl. B62d 55/14

U.S. Cl. 74—230.3

1 Claim



A lower roller for the endless treads of various vehicles, particularly to a lower roller comprising a hub, elastic element provided between tire flanges and metal ring provided around said elastic element.

3,580,094

MOTION TRANSMISSION DRIVE


Charles E. Kraus, Allendale, N.J., assignor to Excelsmatic, Inc.

Filed Aug. 27, 1969, Ser. No. 853,429

Int. Cl. F16h 7/12

U.S. Cl. 74-242.11C

16 Claims



A traction drive with movable flange pulleys on parallel shafts which operates with a large amount of traction element sag, both on the tight and slack side, maintained by a dual roller tensioning means which, through servo means, compensates for load, wear, and ratio position by controlled flange movements.

3,580,095

CONSTANT MESHING FORCE RACK AND PINION


Aniese E. Seed, Toledo, Ohio, assignor to The Reliance Electric and Engineering Company, Toledo, Ohio

Filed Jan. 13, 1969, Ser. No. 790,605

Int. Cl. F16h 55/18; G01g 13/14

U.S. Cl. 74-409

4 Claims



In a condition responsive device, such as a load responsive weighing scale, a rotatably mounted pinion is engaged with a pivotably mounted balanced rack which is movable in response to change in the condition. A spring is provided for urging the rack into engagement with the pinion and for maintaining the meshing force between the rack and the pinion substantially constant during all positions of the rack.

3,580,096

DRIVING MECHANISM FOR SLIDE CHANGERS OR THE LIKE

Josef Scheibel, Ober-Morlen, Germany, assignor to Braun Aktiengesellschaft, Frankfurt, Main, Germany

Filed Sept. 5, 1969, Ser. No. 855,529

Claims priority, application Germany, Oct. 2, 1968, P1800516.8


Int. Cl. F16h 57/10; F16d 67/06

U.S. Cl. 74-411.5

16 Claims

The slide changer and the indexing mechanism for the tray of a slide projector are operated intermittently by a power

train which is connected to the output shaft of an electric motor. An electromagnet is energized in response to opening of the motor circuit to bring about rapid stoppage of the slide changer and indexing mechanism in a predetermined position. Energization of the electromagnet results in frictional



engagement of an element of the power train with a movable or stationary part of the electromagnet. A spring is provided to disengage the element of the power train from the stationary or movable part in response to deenergization of the electromagnet.

3,580,097

SCREW AND NUT DRIVER


Leonard Van Dalen, Cherry Hill, N.J., assignor to Seaboard Fabricators, Inc.

Filed Mar. 4, 1969, Ser. No. 804,139

Int. Cl. F16h 1/20; B25b 17/02

U.S. Cl. 74-421

9 Claims



A screw and nut driver including a housing mounting a gear train, a handle and a tool shank extending from opposite ends of the housing and respectively connected to the input and output of the gear train.

3,580,098

BALL SCREW AND NUT MECHANISM

Albert Goad, Hemel Hempstead, England, assignor to Rotax Limited, London, England

Filed Apr. 25, 1969, Ser. No. 819,352

Claims priority, application Great Britain, Apr. 29, 1968, 20134/68


Int. Cl. F16h 55/22, 1/18

U.S. Cl. 74-459

3 Claims

A ball screw and nut mechanism including an insert which is positioned within a recess in the nut, the insert defining

scoop portions which depend into the groove in the screw, the scoop portions being interconnected by a passage



whereby balls can recirculate during relative angular movement of the nut and screw.

3,580,099

ARTICULATING MECHANISM


Ralph S. Mosher, Schenectady, N.Y., assignor to General Electric Company

Filed Sept. 24, 1969, Ser. No. 860,640

Int. Cl. G05g 1/00

U.S. Cl. 74-469

10 Claims



An articulating mechanism to provide large angular motions using a plurality of links, one of which includes a long and a short member in crossed relationship and a pair of side bars each pivotally connected to respective adjacent ends of the members. Extension bars on one side and on the other side of the long member and integral therewith function as side bars of a preceding and a succeeding link. Elimination of one type of extension bar on a link at one end of the mechanism and the other type of extension bar on a link at the other end of the mechanism provides transitional links for pivotal connection of the long cross bar of each of the transitional links to a respective rigid member.

3,580,100

DRIVER TRAINING CAR THROTTLE DISCONNECT


Louis W. McDermott, c/o McDermott Ford Sales, R. R. #1, Dyersville, Iowa

Filed Dec. 30, 1969, Ser. No. 889,269

Int. Cl. G05g 11/00

U.S. Cl. 74-482

10 Claims



A selectively remotely actuatable control for operative connection between the throttle linkage and throttle valve control arm of an automotive carburetor including means operable, when the control is actuated, to render inoperative

a normally operative motion-transmitting connection between the throttle linkage and the throttle valve control arm and return, by spring return means, the throttle valve control arm to its idle position independent of the position of the throttle linkage.

3,580,101

TELESCOPING SECTION IN A STEERING COLUMN


Anker E. Jorgensen, Portland, Oreg. and Gerald K. Oxley, Lafayette, Ind., assignors to TRW Inc., Cleveland, Ohio

Filed Nov. 12, 1968, Ser. No. 774,911

Int. Cl. B62d 1/18

U.S. Cl. 74-493

1 Claim



Telescoping section between a steering shaft and steering gear, comprising an elongated tube and an intermediate shaft sliding connected therewith for rotational driving. The intermediate shaft journaled in a bushing in the end of the elongated tube. An internal stop in the tube spaced from but near the bushing prevents buckling between the tube and the shaft. The steering shaft housing is adjustably mounted in the vehicle cab by means of adjustable brackets attached to the dashboard of the vehicle cab and the steering shaft housing.

3,580,102

ADJUSTABLE FLEXIBLE CABLE FORCE TRANSMITTING ASSEMBLY


Voyta E. Wrabetz, Hubertus, and Ronald A. Banister, Mequon, Wis., assignors to Square D Company, Park Ridge, Ill.

Filed June 30, 1969, Ser. No. 837,813

Int. Cl. F16c 1/22

U.S. Cl. 74-501

7 Claims



The flexible cable assembly comprises an outer sheath and inner cable with plungers on its ends, respectively, for transmitting normal operating forces in a direction from an operator at one end of the assembly to a switch at the opposite end. Adjustment means are connected to one plunger and are arranged to be changed in overall length by opposed forces imposed thereon by, and endwise of, the cable in excess of the normal operating forces. The adjustment means is adjusted to the effective length required for proper operation of the switch by the operator by operating the remote operator through one complete operating cycle while the operator, the switch, and the assembly are in final installed position. The effective length remains unchanged thereafter.

3,580,103

REMOTE FLEXIBLE CABLE


Russell L. Shreve, Troy, Mich., assignor to Teleflex Incorporated, North Wales, Pa.

Filed Aug. 1, 1969, Ser. No. 846,713

Int. Cl. F16c 1/28

U.S. Cl. 74—501

10 Claims



A remote flexible control cable for transmitting tensile and compressive forces by means of a band member which is supported between two sets of a plurality of ball members with each set of ball members being held in place by a retainer and supported between a race or guide member and the band member; the sets of ball members, retainer and race or guide members all being supported for rotation within the cable; and the control cable being flexible in two directions in a common plane.

3,580,104

CONTROL LEVER FOR PARKING BRAKE SYSTEMS

Katsuji Yashiro, and Hiroshi Naito, Kanagawa-ken, Japan, assignors to Otsukakoki Kabashiki Gaisha, Yokohama-shi, Japan


Filed Jan. 24, 1969, Ser. No. 793,768

Claims priority, application Japan, July 29, 1968, 43/052960

Int. Cl. G05g 5/18

U.S. Cl. 74—535

5 Claims



The control lever comprises a hand lever pivotably mounted on a fixed ratchet sector and biased to the brake releasing position. A locking lever is pivotably supported on the ratchet sector for connection with a brake mechanism and is pivotably connected to a ratchet piece having a pawl engageable with the teeth on the sector, the ratchet piece in turn being connected to a link engaged in a slot provided in the hand lever. When the hand lever is moved between the brake release position and the brake actuating position, the pawl can travel past the teeth of the ratchet sector by oscillation of the ratchet piece and link as a result of displacement of the pin in the slot. A spring acts on the link to urge the pawl into engagement with the teeth when the hand lever reaches the brake actuating position.

3,580,105

PROGRAM CONTROL APPARATUS

Warren E. Gilson, 4801 Sheboygan Ave., Madison, Wis.

Filed May 9, 1969, Ser. No. 823,411


Int. Cl. F16h 54/04

U.S. Cl. 74—568

11 Claims

A program control apparatus includes a drum mounted for rotation and a stack of cam rings removably supported upon

the drum surface. The cam rings include outwardly projecting partly cut away flanges formed of easily removable material providing cam surfaces for the control of a program operation through a series of cam follower devices. The drum is mounted only at one end by means of a shaft connected to



a wall portion of a support, the support also supporting drive means for rotating the drum and the cam follower devices. The arrangement permits rapid and convenient setup and adjustment of programs through cutting away of portions of the cam ring flanges, through exchange of the cam rings, and through exchange of the entire drum assembly.

3,580,106

ALUMINUM PRESSED METAL LINK FOR 600 CLASS SEWING MACHINES


Frederick R. Wiehl, Westfield, and Edmund B. Wilson, III, Dover, N.J., assignors to The Singer Company, New York, N.Y.

Filed Sept. 23, 1969, Ser. No. 860,269

Int. Cl. F16c 7/02

U.S. Cl. 74—579

3 Claims



A drive link is disclosed for a sewing machine needle bar reciprocating mechanism. The drive link is constructed of an alloy containing principally aluminum and is formed at each extremity with porous lubricant accommodating bearing portions having a density which is a fraction of the theoretical solid alloy density of the aluminum alloy so as to provide porosity for lubricant retention and self-oiling bearing characteristics. The portion of the drive link joining the bearing portions, however, possesses superior structural characteristics because it is formed to a density which is substantially equal to the theoretical solid alloy density of the aluminum alloy which is used.

3,580,107

TRANSMISSION

Elias Orshansky, Jr., San Francisco, Calif., assignor to URS Systems Corporation, San Mateo, Calif.

Filed Oct. 21, 1968, Ser. No. 769,008


Int. Cl. F16h 47/08

U.S. Cl. 74—687

93 Claims

Power is transmitted by a planetary and hydraulic assembly which has one input shaft, two output means, and two reactions. While one output means is increasing its speed, the other output means is simultaneously decreasing its speed, and the ratio of the maximum speed of one output means to its minimum speed is substantially the same as the ratio of the maximum speed of the other output means to its minimum speed. This characteristic of speeding up one out-

put means while the other slows down is used over and over again by shifting the final output from the point where one of the output means is going at maximum speed to the other output means when it is going at minimum speed, thus going through this cycle again and again. The power transmission therefore connects successively the final output drive to one



output member of the planetary assembly and then to the other output member of the planetary assembly, and then back to the first output member of the planetary assembly at a different ratio from the previous connection, and so on, and this can be done because these output means continually increase and decrease their speeds.

3,580,108

DIFFERENTIAL MECHANISM


Spencer H. Mieras, Muncie, Ind., assignor to Borg-Warner Corporation, Chicago, Ill.

Filed Dec. 2, 1969, Ser. No. 881,346

Int. Cl. F16h 1/44

U.S. Cl. 74—711

5 Claims



A limited slip differential mechanism having preloaded conical friction members which retard differential action. The mechanism includes camming means operable independently of the mechanism side gears to proportionally decrease friction preload force on the conical friction members in response to increasing input torque.

3,580,109

PLANETARY-GEAR TRANSMISSION WITH INTERCONNECTED SUN GEARS AND RING GEARS
Franz Hill, Friedrichshafen, Germany, assignor to Zahnradfabrik Friedrichshafen Aktiengesellschaft, Friedrichshafen, Germany

Filed Sept. 4, 1969, Ser. No. 855,137

Claims priority, application Germany, Sept. 6, 1968, Z12082


Int. Cl. F16h 5/30

U.S. Cl. 74—763

4 Claims

An automotive transmission with two cascaded planetary gear trains has the two ring gears rigidly connected with each

other and with the output shaft, the input shaft being alternately connectable with one planet carrier (forward) or with the two interconnected sun gears (reverse). The driven



planet carrier supports two sets of intermeshing planet gears to invert the sense of output-shaft rotation in first and second gear.

3,580,110

TWO SPEED DRIVE MECHANISM FOR FACSIMILE RECORDING SYSTEM OR THE LIKE

Frans Brouwer, Glencoe, and Frank L. Sobchak, Chicago, Ill., assignors to Stewart-Warner Corporation, Chicago, Ill.


Division of Ser. No. 613,545, Feb. 2, 1967, Pat. No. 3,527,882.

Filed Dec. 1, 1969, Ser. No. 881,054

Int. Cl. F16h 5/52

U.S. Cl. 74—812

4 Claims



A facsimile device including a two speed drive mechanism for driving the recording medium. The mechanism includes a reversible motor and a gearing means to drive the medium at one speed in a forward direction when the motor is operated in one direction and at a different speed in the forward direction when the motor is operated in the opposite direction.

3,580,111

CAM-CONTROLLED INDEXING DEVICE


Joseph M. Tyrner, Brookside, N.J., assignor to Allied Chemical Corporation, New York, N.Y.

Filed Apr. 23, 1969, Ser. No. 818,607

Int. Cl. B23b 29/00

U.S. Cl. 74—817

6 Claims



This application relates to cam-controlled indexing devices. The subject indexing device includes a rotatable in-

dexing wheel perpendicularly mounted on a driven shaft and having cam rollers thereon equispaced alternately on opposite sides of said wheel at a constant radial distance from said driven shaft. The indexing wheel is driven by a cam drive comprising an oscillating sector cam having a groove therein and pivotably mounted adjacent said indexing wheel and for irreversible serial engagement with said cam rollers.

3,580,112

AUTOMATIC GEAR-SHIFT CONTROL FOR AUTOMOTIVE TRANSMISSION SYSTEM

Hansjorg Dach, Friedrichshafen, Germany, assignor to Zahnradfabrik Friedrichshafen Aktiengesellschaft, Friedrichshafen, Germany


Filed Apr. 21, 1969, Ser. No. 817,984

Claims priority, application Germany, Apr. 20, 1968, P 17 55 282.8

Int. Cl. B60k 21/08

U.S. Cl. 74—868

9 Claims



A throttle valve 40 connected to a supply of hydraulic fluid delivers a variable fluid pressure dependent on the engine load of an automotive vehicle whose accelerator controls a plunger 42 which, through the intermediary of a compression spring 43, resists the displacement of the body 41 of that valve in response to the supply pressure. In a retracted or partly depressed position of the accelerator, the plunger 42 blocks the transmission of the load-dependent fluid pressure via a first conduit 220 to an automatic switching device 90 having a control piston 91 acted upon by speed-dependent fluid pressure and biased by a countervailing spring 105 into a normal, low-speed position. In the absence of supplemental fluid pressure from the throttle valve 40, the control piston 91 together with an associated slider 98 is moved into an off-normal, high-speed position whenever the speed-dependent fluid pressure overcomes the force of the biasing spring 105; with the accelerator in a position approaching full throttle, i.e. beyond a predetermined load threshold, the biasing force is supplemented by the load-dependent fluid pressure so that upshifting occurs at higher drive shaft speeds only. The load-dependent fluid pressure is applied in aiding relationship via two branch conduits 220a, 220d to a face of the piston and to another face on the slider, the first branch conduit 220a being obstructed in the off-normal piston position so as to create a hysteresis effect whereby under unchanged load conditions the downshift takes place at a lower speed than the upshift. Another conduit 221, unblocked by the plunger 42 in a kick-down position of the accelerator, partly cancels the aforementioned hysteresis effect whereby downshift under maximum load occurs at a higher speed.

3,580,113

ELECTRICAL IGNITION FIREARM, WITH A FORWARDLY SLIDING BARREL

Marcus Ramsay, New Haven, Conn., and Arthur W. Lilley, Pittsburgh, Pa., assignors to Olin Corporation

Filed Sept. 12, 1969, Ser. No. 857,366


Int. Cl. F41c 19/12; F41f 13/08

U.S. Cl. 42—84

9 Claims

A firearm for electrically firing caseless ammunition having no primer. A switch is actuated by the trigger to permit passage of current from a capacitor to an electrode contact-

ing the ammunition. Elapsed time between trigger pull and firing of the ammunition is decreased as compared to impact



3,580,114

WIRE-STRIPPING APPARATUS


Walter J. Rozmus, Hubbardsville, N.Y., assignor to Utica Tool Company, Inc., Orangeburg, S.C.

Filed June 6, 1968, Ser. No. 734,984

Int. Cl. H02g 1/12

U.S. Cl. 81—9.5

27 Claims



An apparatus for removing or stripping the insulation from a wire and comprising a pair of plierslike lever members pivotally connected to one another and defining engageable jaw sections and manually grippable handle sections; a pair of rotatable stripper members mounted one on each of the jaw sections with each stripper member comprising a plurality of stripping elements; the elements on one of the stripper members corresponding to and adapted to be operatively associated with the stripping elements on the other stripper member; shaft means rotatably supporting the stripper members and means for effecting simultaneous rotation of the shaft means and stripper members thereon, whereby corresponding stripping elements may be moved into confronting cooperable relation; spring means for resiliently urging the jaw sections apart and for providing an audible signal in response to preselected rotational movement of the shaft means, and guide means on the forward ends of the jaw sections for guiding the wire from which insulation is to be stripped during relative axial movement of the wire with respect to the stripping apparatus.

3,580,115

WRENCH HAVING A LOCKED ADJUSTABLE POSITION

Harry W. Thompson, 8007 S. Chappel Ave., Chicago, Ill.

Filed July 24, 1969, Ser. No. 844,571


Int. Cl. B25b 13/16

U.S. Cl. 81—165

6 Claims

An adjustment wrench is afforded in which the adjusted

position is locked by a worm nut held in engagement, by a coil spring, with a nonrotatable key. The gear thread on the



nut, when turned, will adjust the movable jaw when the nut is unseated from the key.

3,580,116

CLUTCH ADJUSTMENT TOOL


Janis Tenisons, Edwardsburg, Mich., assignor to Tecumseh Products Company, Tecumseh, Mich.

Filed June 13, 1968, Ser. No. 736,717

Int. Cl. B25b 7/00

U.S. Cl. 81—302

5 Claims



A plierslike device with a pair of arms interconnected for movement relative to one another for manipulating a wear takeup nut and an associated spring detent in a friction clutch so that the detent may be readily released and the nut readily adjusted manually at a mechanical advantage provided by the tool and from outside the clutch housing. The working end of one arm of the tool has a slot between chisel point faces to pry out and hold the detent, and the working end of the other arm has a narrow projection or tongue to engage the notched periphery of the nut. Both ends of the tongue arm are offset with respect to the chisel point arm so that the arms do not interfere when they are pivoted past each other.

ERRATUM

For Class 82—2 see:
Patent No. 3,580,129

3,580,117

TOOL CARRIER ASSEMBLY FOR A LATHE OR OTHER MACHINE TOOL

Stefan Sarzinski, Sarajevo, Yugoslavia, assignor to "Zrak"-Preduzeće Precizne mehanike i optike, Sarajevo, Yugoslavia

Filed Feb. 27, 1969, Ser. No. 802,893

Claims priority, application Yugoslavia, Apr. 25, 1968, P-989/68


Int. Cl. B23b 29/00; B26d 1/12

U.S. Cl. 82—36

8 Claims

According to the present invention, there is provided a tool carrier assembly for a lathe or other machine tool, such

assembly comprising a substantially circular body, a removable tool carrier having means to clamp a tool thereto, and a circular concave surface adapted to cooperate with the outer surface of the body, at least two axially extending, cir-



3,580,118

MACHINE TOOL CUT-OFF SLIDE


Jack A. Hazel, Northolt, England, assignor to C.A.V. Limited, Warple Way, Acton, London, England

Filed Nov. 19, 1968, Ser. No. 776,897

Int. Cl. B23b 5/14

U.S. Cl. 82—46

5 Claims



A machine tool for use when parting off a component from a barstock using a parting off tool and comprising a pusher member engageable with the component and arranged to apply a lateral force to the component to shear the component from the barstock when the parting off tool has machined to a predetermined depth the bridge of material forming the connection between the component and the barstock.

3,580,119

MAINTAINING SHEETS OF GLASS IN MUTUALLY SPACED RELATIONSHIP WHEN STACKED TOGETHER FOR TRANSPORT OR STORAGE

Geoffrey Frank Witherington-Perkins, Redditch, England, assignor to Triplex Safety Glass Company Limited, London, England

Filed Jan. 31, 1969, Ser. No. 795,579

Claims priority, application Great Britain, Jan. 31, 1968, 4,902/68


Int. Cl. B26d 5/22

U.S. Cl. 83—23

6 Claims

A method and apparatus for maintaining sheets of glass in mutually spaced relation when stacked together. Flexible strip material is fed to a severing machine wherein strips are cut to length. Thereafter the cut strips are applied to sheets

of glass before the glass sheets are stacked together. One face of the strip material is smoother than the other face whereby theater and the like, which is capable of cutting a ticket into two halves after checking it, collecting one half in the ap-




the smoother face tends to adhere to the glass more strongly than the less smooth face.

3,580,120 MULTIPURPOSE PUNCH

Richard C. Adams, West Barrington, R.I.; William S. Coombes, Somerset, and Domenic Lerardo, Walpole, Mass., assignors to G. T. Schjeldahl Company, Northfield, Minn.
Filed Nov. 5, 1968, Ser. No. 773,612
Int. Cl. B26d 7/18

U.S. Cl. 83-98

7 Claims



Punching apparatus particularly adapted for use in connection with flexible film materials including a punching assembly and a die assembly arranged in aligned relation with the punching assembly, means for reciprocally shifting the punch into engagement with the die for performing a cutting operation on film disposed between the punch and the die, and including means for injecting a pulse of compressed gaseous fluid when the punch is in its extended disposition. Bores are formed within the punching apparatus to permit coupling of a source of gaseous fluid under pressure to the punching assembly for discharge from the surface of the punch member, the arrangement being such that gaseous fluid under pressure is discharged from the punch only when the punch member is in its extended position.

3,580,121 APPARATUS FOR CHECKING A TICKET

Takeo Asada, and Toshihiro Kamiya, Kyoto-fu, Japan, assignors to Omron Tateisi Electronics Co., Kyoto-fu, Japan
Filed Feb. 27, 1969, Ser. No. 802,965
Claims priority, application Japan, Mar. 6, 1968, 43/14426
Int. Cl. B65h 43/00; B26d 5/32

U.S. Cl. 83-107

8 Claims

An apparatus for checking a ticket and more particularly a device for checking tickets such as an admission ticket for a

paratus and returning the other half to the original user of the ticket from the outlet slot on the apparatus.


3,580,122 APPARATUS FOR MAKING KNOCKOUTS IN ELECTRICAL BOXES FORMED OF PLASTIC MATERIAL

James C. Powell, Elkhart, Ind., assignor to All-Steel Equipment Inc.

Filed Dec. 13, 1968, Ser. No. 783,584

Int. Cl. B26d 7/18; B26f 1/14
U.S. Cl. 83-108

16 Claims



Knockouts are formed in electrical fixtures, such as connector boxes made of plastic sheet material, by punching the knockouts from plastic sheet or blanks prior to shaping into the fixture or by shaping the fixture and then punching out the knockouts. By resiliently supporting the material surrounding the knockout area on the punch side and resiliently biasing a knockout stripper against the surface of the knockout opposite that contacted by the punch, knockouts can be punched out and replaced in the material in a single operation if the opposite biasing forces of the support and knockout stripper are properly correlated.

3,580,123 CUTTER

Dan P. Westra, and John J. Siewert, Grand Haven, Mich., assignors to The Challenge Machinery Company, Grand Haven, Mich.

Filed June 13, 1968, Ser. No. 736,808


U.S. Cl. 83-380

Int. Cl. B26d 5/42, 5/16

14 Claims

A cutter adapted particularly for cutting paper stock including a clamping mechanism and a knife member. The

knife member is reciprocated into and out of abutment with the paper-supporting table by means of an eccentric arm and a connecting rod. The eccentric arm is rotated by means of a hydraulic actuator, the actuator being reversible such that it runs in opposite directions depending upon whether the knife



is being raised from the table or lowered into abutment therewith. Suitable safety stops are provided for limiting the movement of the eccentric member in the event of failure of one of the controls therefor. The arm is positioned over-center when the knife is in its raised position.

3,580,124 NOVEL PITCH ADJUSTMENT MEANS FOR STRINGED INSTRUMENTS


John Mancini, Roselle, N.J. (215 S.E. Third Ave. Apt. 107 D Hallandale, Fla. 33009)

Filed Apr. 13, 1970, Ser. No. 27,622

U.S. Cl. 84-313

Int. Cl. G10d 3/00

21 Claims



There is provided a simple and novel device principally intended for use with a double bass or similar instrument, whereby the pitch of one string may be adjusted in a precise, predictable and reversible manner to a pitch other than that at which it is normally played. The device comprises a cylinder having a pulley mounted therein whose axis is parallel to but eccentric in relation to the principal axis of the cylinder. The device further optionally comprises excisions having adjustable plugs therein for the minor and, reversible, adjustment of the pitch of the other strings, means for rotating the cylinder into a "contact" and "noncontact" position wherein the string of the instrument to be adjusted in pitch either is in contact or is not in contact respectively with the pulley. The device further optionally comprises a means for controlling the degree of rotation of the device between the "contact" and "noncontact" positions.

3,580,125 KEY-ADJUSTABLE HARMONICA

Oliver W. Heatwole, 3900 16th St. N.W., Washington, D.C.

Filed Apr. 4, 1969, Ser. No. 813,463

U.S. Cl. 84-377

Int. Cl. G10d 7/12

28 Claims

A key-adjustable harmonica for selectively playing in any one of a plurality of musical keys by the use of seven consecutive blowholes per octave without the necessity for readjusting the harmonica to obtain the proper notes in the key. The harmonica includes means for selectively connecting all of the seven blowholes per octave with only those reed cells of chromatically arranged cells containing reeds tuned to the

notes of the selected key while blocking off those cells not in the selected key. In addition, the arrangement provides



means of access to a given reed in a plurality of adjustments of the harmonica. Any note can be played by either blowing or drawing at will.


3,580,126 LIGHT DISPLAY INSTRUMENT

John F. Forkner, 2670 Solana Way, Laguna Beach, Calif.

Filed Oct. 29, 1968, Ser. No. 771,479

Int. Cl. A63j 17/00

19 Claims



A device for producing esthetically pleasing patterns of light which is controllable like a musical instrument. The device includes an elastically stretchable reflective mirror surface which is spaced from a high intensity light source. A collimating and focusing lens is interposed between the reflective surface and the light source so that light beams emanating from said light source and reflected from said reflective surface are focused at a point within an aperture defined in the cabinet of the device. A dynamic image display may be produced by applying localized pressures to the reflective surface thereby distorting the reflected pattern. These localized forces may be applied by sound waves, manual pressure and the like. Further interesting effects are obtainable by varying the optical characteristics of the light beams as they pass through the focal point as by the use of light filters or masks.

3,580,127 CARTRIDGE CASE RELOADING

Richard J. Lee, R.R. 2, Hartford, Wis.

Filed Aug. 19, 1968, Ser. No. 753,461

Int. Cl. F42b 33/10, 35/02

U.S. Cl. 86-24

8 Claims



In apparatus for reloading used center-firing cartridge cases, a resizing sleeve having a bore therein of which the

upper portion is cylindrical and the lower portion is tapered to wedgingly receive the neck of a cartridge case driven upwardly therein to resize and reform the neck and to hold the neck in a reaming position therein; a reamer adapted for reaming the interior of the neck to obtain uniform neck wall thickness; a bullet-seating gauge threadably mounted on the projecting above the resizing sleeve and micrometrically alignable on the shell guide to reveal the distance which the bullet-seating gauge projects above the resizing sleeve; an elongated bullet seater adapted to engage and force a bullet downwardly a predetermined distance into a seated position within the neck while the neck is partially within the tapered lower portion of the bore in a bullet-seating position; and means for positioning the neck in the bullet-seating position.

3,580,128


AMMUNITION RELOADER

Robert A. Leich, Southfield, Mich., assignor to Camdex, Inc., Detroit, Mich.

Filed Sept. 4, 1969, Ser. No. 855,149
Int. Cl. F42b 33/02

U.S. Cl. 86—31

22 Claims



An automatic powder metering apparatus for loading ammunition including a powder slide, a cam for cyclically displacing the slide between a powder input position and a powder output position and means on the cam for cyclically pulsating the slide when in the two above-named positions to loosen the powder for correct feeding.

3,580,129

PRESETTABLE TOOL ARRANGEMENTS FOR MACHINE TOOLS

Eric R. Austin, Coventry, and Eric G. Bill, Solihull, England, assignors to B.S.A. Tools Limited, Birmingham, England


Filed Aug. 30, 1968, Ser. No. 756,458

Claims priority, application Great Britain, Sept. 1, 1967, 40086/67

Int. Cl. B23b 3/00

U.S. Cl. 82—2

2 Claims



A presettable tool arrangement incorporates a tool holder with a dovetail slide portion for slidably engaging a dovetail

guideway on a tool mount. An adjustable abutment rod on the tool holder engages an abutment on the tool mount for accurately positioning the preset tool holder on the tool mount.

3,580,130

BULLET TRAP ATTACHMENT FOR MACHINE GUNS


Paul W. Arvidson, Princeton, Iowa; William G. Park, Silvis, Ill., and Keith S. Williams, Davenport, Iowa assignors to The United States of America as represented by the Secretary of the Army

Filed Sept. 29, 1969, Ser. No. 861,691

Int. Cl. F41f 17/00; F41j 1/12

U.S. Cl. 89—31

8 Claims



The safe trapping of one or more bullets fired from a Gatling-type machine gun is accomplished by an attachment releasably secured to the muzzle end of the barrel cluster and provided with an interior chamber containing an elastomeric material at the rear end thereof capable of being penetrated by those bullets existing from the barrels and immediately recovering thereafter to seal any discharge gases then in the chamber, the forward wall of the chamber forming an impact surface against which the forward velocity of each bullet is terminated by the shattering thereof into discrete particles.

3,580,131

ANTIFEEDBACK DEVICE


John R. Zimmerman, Sterling Heights, Mich., assignor to the United States of America as represented by the Secretary of the Army

Filed Oct. 20, 1969, Ser. No. 867,614

Int. Cl. F41d 9/02

U.S. Cl. 89—34

4 Claims



A simplified antifeedback device for installation in vertically fed belt-type ammunition supply systems is disclosed. The device comprises a tube mounted in a cutaway portion of the feed guide in such a manner that it is moved up and out of the way as the ammunition belt advances, but lodges itself between links of the ammunition belt and the cutaway portion of the feed guide when the belt is drawn downward by gravity upon the cessation of ammunition feed.

3,580,132

BUFFER AND DELAY MECHANISM FOR A FIREARM

Edwin S. Vartanian, North Haven, Conn., assignor to Olin Mathieson Chemical Corporation

Filed Sept. 25, 1968, Ser. No. 762,593

Int. Cl. F41d 5/04, 1/12

U.S. Cl. 89—130

7 Claims

A mechanism for reducing the recoil force caused by reciprocation of a bolt assembly in a semiautomatic firearm,

3,580,134

MACHINING METHOD


Edwin C. Harrington, Jr., Wilbraham, Mass., assignor to Monsanto Company, St. Louis, Mo.

Filed Oct. 21, 1968, Ser. No. 769,342


Int. Cl. B23c 1/16

U.S. Cl. 90—13C

3 Claims



thus decelerates during its rearward stroke while the bolt assembly and slide arms are thus free to move away from the slide block to strike the rear of the receiver and rebound forwardly therefrom. After rebound, the slide arms and bolt assembly strike the rearwardly moving slide block to cause a pause in the reciprocation cycle, after which pause the slide block, slide arms, and bolt assembly all move forward to their original positions under the influence of the spring.



A method for cutting a curved surface on one face of a workpiece so as to produce a longitudinal curvature thereon such that when a specimen in planar sheet form is placed in face-to-face engagement with the resulting curved surface, the strain on the outer surface of such specimen varies linearly with distance along the surface of such specimen.

3,580,133

BALANCE COMPENSATING DEVICE

Charles William Berthiez, 5, Avenue Eglantine, Lausanne, Switzerland


Filed May 1, 1969, Ser. No. 820,943

Claims priority, application France, May 3, 1968, 150,473

Int. Cl. B23c 1/02

U.S. Cl. 90—11

12 Claims



3,580,135

CLAMPING APPARATUS FOR A MACHINE TOOL


Gordon H. Jones, Van Dyne, Wis., assignor to Giddings & Lewis, Inc., Fond du Lac, Wis.

Continuation-in-part of application Ser. No. 744,458, July 12, 1968, now Patent No. 3,540,346. This application Sept. 3, 1969, Ser. No. 854,998

Int. Cl. B23c 1/02

U.S. Cl. 90—11A

14 Claims



A milling and boring machine having an upright with a front face and a rear face and pulleys slideways on the front face, a saddle mounted for sliding movement on the vertical slideway, the saddle having horizontal slideways on which is mounted a headstock adapted for sliding movement with respect to the saddle. The machine tool is provided with a counterweight for the headstock to balance the horizontal movements of the latter which is fixed in the vertical direction. The balancing means includes a horizontal beam mounted on the upright adapted for pivotal movements around a vertical axis so that one end of the beam constantly hangs over the headstock. A loose pulley is mounted at each end of the beam and flexible extension means pass over both pulleys and connect the headstock to the counterweight on the rear face of the upright. A hydraulic takeup means is provided for the flexible suspension means which is adapted to maintain counterforces between the counterweight and the headstock.

A machine tool having a longitudinally adjustable machining spindle carried by a rotary spindle sleeve and securely clamped releasably within the sleeve by a clamping bushing encircling the spindle. The clamping bushing is force fitted within the encircling structure of the sleeve so that residual compressive stresses are established. The sleeve and clamping bushing define an elongate, annular chamber, cylindrical in nature, which is disposed intermediate the ends of said bushing and sealed to render same a fluid chamber. Fluid pressure means are associated with said chamber to provide fluid under pressure, whereby said clamping bushing is restricted circumferentially to effect hard compressive contact with a machine tool spindle. The clamping arrangement utilizes a relatively thick, stiff clamping bushing structure in conjunction with a plenum chamber that is extremely narrow in section, whereby numerous advantages over prior clamps are attained.

3,580,136

SONIC ENERGY IN MACHINING OPERATIONS


Albert G. Bodine, 7877 Woodley Ave., Van Nuys, Calif.

Filed Dec. 9, 1968, Ser. No. 782,347

Int. Cl. B23d 39/00; B23b 47/34; B23c 1/00

U.S. Cl. 90-64

7 Claims



A machine tool such as a drill has a stem of elastic material to which the cutting tool is attached. Supported on this stem is an orbiting-mass oscillator. While a machining operation is being performed, the orbiting-mass oscillator is driven at a frequency such as to resonantly elastically vibrate the stem, thereby providing sonic energy to the cutting tool which effectively pulverizes the cuttings made by the cutting tool so that they will not impede the machining operation.

3,580,137

FLUID PROXIMITY SENSOR AND DRIVE MECHANISM TO CONTROL DISTANCE OF AN OBJECT FROM THE SENSOR


Karl A. Brandenburg, Hayward, Calif., assignor to The Aero Corporation, Bryan, Ohio

Filed Sept. 20, 1968, Ser. No. 761,238

Int. Cl. F15b 11/15; F01I 15/04, 25/06

U.S. Cl. 91-50

12 Claims



A unipressure fluid logic control and power supply device which utilizes a single air pressure source for sensing and indicating the proximity or gap between a sensor and a driven element. The same supply means provides power to an air motor which drives the driven member and maintains it in a desired position in relation to the proximity sensor. The sensing device includes a fluid oscillator adapted to drive the piston-type air motor and an air inhibitor which prevents the oscillator from operating whenever a sensed fluid signal indicates the proximity or position of the driven member is as desired.

3,580,138

VALVE OPERATING MECHANISM


Gunter Maasshoff, Glenview, Ill., assignor to Hawk Oil Field Equipment Corp., Evanston, Ill.

Filed July 28, 1969, Ser. No. 845,423

Int. Cl. F01I 25/06, 31/02

U.S. Cl. 91-277

14 Claims



A spring biased swing arm is operatively associated with a control arm of a valve assembly for moving the arm to quickly control the flow of fluid to a reciprocating hydraulic operating mechanism in a well pumping apparatus. The swing arm is moved with a snap action by a spring when a tripping block engages and moves a pivotally mounted toggle actuator which moves the spring over center to cause quick movement of the control arm to one of its operative positions.

3,580,139

CONTROL APPARATUS


Robert F. Rasmussen, Brooklyn Center, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Apr. 3, 1969, Ser. No. 813,018

Int. Cl. F15b 18/00; B64c 13/42

U.S. Cl. 91-411

11 Claims



Conventionally, in aircraft having fluid operated servomotors for positioning the control surfaces, aircraft engine driven pumps supply the operating fluid pressures for the servomotors while the aircraft is in flight.

3,580,140

LOCKING MECHANISM FOR FLUID TYPE ACTUATORS


William H. Walker, 2210 104th S.E., Bellevue, Wash.

Filed Dec. 9, 1968, Ser. No. 782,290

Int. Cl. F15b 15/26

U.S. Cl. 92-25

7 Claims



A device mounted to the piston of a hydraulic actuator to mechanically lock the piston in its retracted position. The piston carries several locking segments which, with the piston retracted, reach inwardly to engage the head of a locking stud that is fixed to the cylinder. When hydraulic fluid is fed into the cylinder so as to extend the actuator, the hydraulic pressure first pushes back a locking piston (located within the main piston) which positively moves the locking segments out of engagement with the locking stud, and then the main piston moves to its extended position. With no hydraulic pressure acting to extend the main piston, the segments lock the piston in its retracted position.

3,580,141

APPARATUS FOR PAPER SACKS MANUFACTURE

Herbert Richter, Beckum, Germany, assignor to Windmoller & Holscher, Lengerich, Germany


Filed Aug. 21, 1968, Ser. No. 754,247

Claims priority, application Germany, Aug. 28, 1967, H60025

U.S. Cl. 93-8

Int. Cl. B31b 1/00

5 Claims



A system of multiple conveyor belts designed to maintain a balance between the output of a tube-forming machine and a bottom-folding machine used in the manufacture of paper, plastic or similar sacks, in which an assemblage of conveyor belts having sufficient capacity for the piles of tubes produced by the tube-former acts as a magazine upon which the bottom-folder draws as required. Pivoting conveyor belts, directed by suitable monitoring devices, maintain a steady flow into and out of the magazine.

3,580,142

BAG STACK ACCUMULATING CONVEYOR

David K. Stock, and Robert J. Wech, Green Bay, Wis., assignors to FMC Corporation, San Jose, Calif.

Filed May 5, 1969, Ser. No. 821,754





Int. Cl. B31b 1/14, 1/64, 1/98

U.S. Cl. 93-33

12 Claims

A machine produces bags from thermoplastic web by intermittently feeding and severing the web with a heated reciprocating seal bar. The time interval between two seal

bar reciprocations represents a bag making cycle and the number of bag making cycles per minute is the production rate of the machine. Bags produced by the machine are discharged between stacking guides that constrain the bags to fall into a neatly registered stack on an index conveyor at the cyclical rate of bag production. When a predetermined bag count per stack is reached, bag production is interrupted for a period known as an interrupt cycle, during which the index



conveyor moves the stack of bags, relative to the stacking guides, at a rate independently of the bag making cycle. Upon resumption of bag production, a second stack of bags is formed in shinglelike fashion relative to the first stack and the operation is repeated. Since indexing is performed during an interrupt cycle which is independent of the bag making cycle, the production rate of the machine can be increased to a maximum by using a bag making cycle that is less than an indexing time interval.

3,580,143

MAGAZINE CONSTRUCTION FOR PACKING CASE ERECTING MACHINE

Daniel McIntyre, Portland, Conn., assignor to Emhart Corporation, Bloomfield, Conn.

Filed Apr. 22, 1968, Ser. No. 722,943


Int. Cl. B31b 1/06, 1/78, 1/94

U.S. Cl. 93-53

10 Claims

A secondary case magazine is provided above and to one side of an upwardly open primary case magazine from which the lowermost case is cyclically withdrawn for erection. The secondary magazine is disposed generally horizontally, and holds a large number of cases in generally vertical edgewise relation. Escapement means at the exit end of the secondary magazine successively ejects each case for downward movement onto the stack of cases in the primary magazine. Means

in the secondary magazine urges all of the cases therein toward said exit end, and said means operates in timed rela-




tionship with said escapement means and said means for withdrawing the lowermost case from the primary magazine.

3,580,144

APPARATUS FOR ERECTING AND FORMING INITIALLY COLLAPSED CARTONS INTO CONTAINERS
John J. Renard, 1541 Harold St., Green Bay, Wis.
Filed Dec. 31, 1968, Ser. No. 788,181
Int. Cl. B31b 1/78, 5/26, 1/94
U.S. Cl. 93—53AC

7 Claims



A folded case opener apparatus including a flap depressor periodically actuated downwardly to allow a cooperating pivotal hooked arm to engage the advancing laterally disposed edge of an adjacent nondepressed flap thereby to raise said flap and erect such advancing folded case.

3,580,145

COUNTING APPARATUS

Roy E. Vermes, Wilbraham, Mass., assignor to Revco Inc., Agawam, Mass.


Filed Jan. 16, 1969, Ser. No. 791,595
Int. Cl. B31b 1/96, 1/98; B65b 57/20

U.S. Cl. 93—93

1 Claim

A machine for accumulating carton blanks into in-seriatim-formed stacks of blanks of predetermined count and delivering the counted stacks as uniformly aligned units of blanks to a delivery station at one end of the machine, the machine comprising: a hopper for supporting a supply of the blanks to be counted, kicker means cooperant with the hopper for the in-seriatim ejecting of bundles of counted blanks from the hopper, an accumulator-aligner for accumulating and aligning a predetermined number of such bundles to form a

stack, intermittently openable gate means cooperant with the accumulator-aligner and operably into gate opening position as a predetermined number of bundles in the stack has been attained, first conveyor means for conveying the stack



delivered from the hopper by the kicker means to the accumulator-aligner, and second conveyor means for removing the stacks from the accumulator-aligner as the gate means is opened for delivery of the stack to a delivery station at one end of the apparatus.


3,580,146

METHOD OF MAKING ACCURATELY DIMENSIONED SMOOTH-SURFACED MULTI-LAYER CARDBOARD TUBES

Joseph Biancamaria, Ivry sur Seine, France, assignor to L'Homme (Societe Anonyme), Paris, France
Filed Feb. 7, 1969, Ser. No. 797,487
Claims priority, application France, Feb. 7, 1968, PV 139 051

Int. Cl. B31c 3/04, 11/04; B31b 1/64
U.S. Cl. 93—94

10 Claims



In order to obtain helically wound multilayer cardboard tubes of accurate diameter and very smooth external surface, the tubes are coated with a thermosetting resin and forced through the bore of a heated jacket to cause (1) curing of the resin and (2) reduction of the tube diameter to the precise desired dimensions. This reduction is taken up by a radially compressible layer of the tube.

3,580,147

VIBRATORY ROAD ROLLER

Benno Kaltenegger, Kurhausstrasse 73—79, 5202 Hennef Sieg, Germany

Filed Aug. 9, 1968, Ser. No. 751,429

Claims priority, application Germany, Aug. 25, 1967, K63208


Int. Cl. E01c 19/24

U.S. Cl. 94—50

16 Claims

This provides a vibratory road roller having at least two driven roller drums lying one behind the other in the direction of travel. The drums are carried by a rigid frame.

The drums which are placed one behind the other are of different weights. In one embodiment of the invention the roller



in and out of alignment with the optical axis of the camera lens system automatically by an electric motor responsive to closure of the normally open switch to achieve color correction in accordance with the spectral characteristics of the illuminated object to be photographed.

3,580,150

PANORAMIC CAMERA WITH FORWARD IMAGE MOTION COMPENSATION BY OPTICAL ROTATION OF IMAGE

John Thaxter Watson, Wellesley Hills, and Kenneth Robinson, Needham, Mass., assignors to Itek Corporation, Lexington, Mass.

Filed Apr. 15, 1968, Ser. No. 721,227

Int. Cl. G03b 29/00

U.S. Cl. 95—12.5

5 Claims

drums are also of different lengths. At least one of the roller drums has a vibration shaft which carries eccentric weights.

3,580,148

PHOTOCHROMIC EXPOSURE CONTROL


Donald M. Harvey, Webster, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Aug. 1, 1969, Ser. No. 846,817

Int. Cl. G03b 9/02, 11/00; G02b 5/20

U.S. Cl. 95—10

10 Claims



An exposure control system in a camera includes a plurality of transparent photochromic elements that darken as a function of the illumination intensity to which they are exposed. The elements are exposed separately to scene illumination and are then superimposed in alignment with the camera lens and shutter just before the shutter is operated to effect film exposure.

3,580,149

FILTER CORRECTION DEVICE

Shin Fujisawa, Kanagawa, Japan, assignor to Fuji Shashin Film Kabushiki Kaisha, Kanagawa, Japan


Filed Oct. 23, 1967, Ser. No. 677,347

Claims priority, application Japan, Oct. 26, 1966, 41/70217

Int. Cl. G03b 19/00

U.S. Cl. 95—11

4 Claims



A filter correction device including a pair of filters of different spectral characteristics, each filter of which is moved



Apparatus for compensating for forward image motion in panoramic cameras by rotating the image about the optic axis of the camera. In an aircraft camera a first scanning mirror is rotated relative to a second scanning mirror about their common axis in order to provide compensation for the forward motion of the plane.

3,580,151

LOW LIGHT LEVEL COLOR PHOTOGRAPHY


Kenneth C. Hudson, Philadelphia, Pa., and Fred E. Shashoua, Cherry Hill, N.J. assignors to The United States of America as represented by the Secretary of the Air Force

Filed Oct. 17, 1968, Ser. No. 768,424

Int. Cl. G03b 33/00

U.S. Cl. 95—12.20

2 Claims



A method and an apparatus for taking color photographs of subjects at very low light levels. A photo-electronic imaging system, including a color encoding filter, an image intensifier tube, and associated optical components is used to form an image of the subjects on black and white film. The film is developed and the resulting transparency then is projected through a decoding filter and associated optical components to form a color image which, if made to impinge upon color film and the film thereafter is developed and printed, results in a color photograph.

3,580,152

PHOTOGRAPHIC APPARATUS

Dieter Engelsmann, Unterhaching; Rolf Schroder, and Erwin Becker, Munchen, Germany, assignors to Agfa-Geuert Aktiengesellschaft, Leverkusen, Germany

Filed Apr. 11, 1969, Ser. No. 815,358

Claims priority, application Germany, Apr. 19, 1968, A29659


Int. Cl. G03b 1/62, 1/04

U.S. Cl. 95—31FM

10 Claims

A still camera wherein a pivotable and reciprocable slide permits operation of the shutter release when the film is

transported by the length of a frame and when the tip of a tracking lever extends into one of a row of perforations on the film. The film transporting wheel is arrested by an arresting lever when the latter is free to engage a ratchet wheel connected to the film transporting wheel. A star wheel which is rigid with the other two wheels can move the slide to inoperative position only when a tooth of the slide extends into one of several notches provided in the periphery of a disc



which is connected to the wheels by a friction coupling. The arresting lever is also provided with a tooth which can engage the ratchet wheel only when a lug of the arresting lever extends into another notch of the disc. When the film is removed, the slide is moved to inoperative position and the arresting lever is caused to engage the ratchet wheel when the transporting wheel is rotated through an angle which is smaller than the angle required to advance the film by the length of a frame.

3,580,153

APERTURE POSITION SELECTING SYSTEM FOR USE WITH MULTIPHOTOGRAPHIC DEVICE

Yoshio Fukushima, Tokyo, Japan, assignor to Kabushiki Kaisha Ricoh, Tokyo, Japan


Filed Oct. 2, 1968, Ser. No. 764,507

Claims priority, application Japan, Oct. 11, 1967, 42/65278

Int. Cl. G03b 19/02

U.S. Cl. 95—36

14 Claims



A multiphotographic device has an objective lens positioned to form a real image which serves as an object for a compound second lens. Immediately behind the objective lens are located a pair of superimposed shield plates movable transversely in orthogonal directions. Each plate is provided with a slot extending perpendicular to its direction of movement; the slots defining a rectangular aperture which admits light to the second lens from the first. Motion of the plates is controlled by a pair of cams. Each cam controls the excursion of a shield plate causing the aperture to advance in steps from a starting position to an extreme position while leaving gaps between the steps, and then back to the starting position in steps during a return movement. The aperture, during the return movement, occupies the gaps.

3,580,154 OPERATING MECHANISM FOR MIRROR-REFLEX CAMERA

Helmut Ettischer, Ruit/Krs. Esslingen, Germany, assignor to Eastman Kodak Company, Rochester, N.Y.


Filed Oct. 25, 1968, Ser. No. 770,533

Claims priority, application Germany, Nov. 22, 1967, K-63972

Int. Cl. G03b 19/12

U.S. Cl. 95—42

8 Claims



A mirror reflex camera has a mirror pivoting mechanism that is set in response to film winding and released with the shutter. The mechanism moves the viewing mirror from a viewing position to a picture taking position, and a rapid advance lever is provided for successively displacing the film advancing mechanism by varying amounts, depending on the amount of film on the film winding spool, and for simultaneously imparting substantially constant amounts of energy to the mirror pivoting mechanism with each successive displacement of the film advancing mechanism.

3,580,155

DRIVING ARRANGEMENT FOR SINGLE BLADE SHUTTER FOR PHOTOGRAPHIC APPARATUS

Wolfgang Zahn, Munich; Erlich Nagel, Anzing, and Reinhold Langer, Munich, Germany, assignors to Agfa-Gevaert Aktiengesellschaft, Leverkusen, Germany


Filed Nov. 7, 1968, Ser. No. 773,985

Claims priority, application Germany, Nov. 16, 1967, A28727

Int. Cl. G03b 9/10

U.S. Cl. 95—53R

9 Claims



A driving arrangement for filters, shutter blades or analogous light-obstructing elements of photographic cameras or photographic printing apparatus comprises an electromagnet having an armature which is turnable within a

predetermined angle to turn a one-armed lever which is rigid with the light-obstructing element. The motion transmitting connection between the armature and the lever comprises a gear segment on the armature, a gear provided on an intermediate shaft which carries a crank arm, and a pin-and-slot connection between the crank arm and the lever.

3,580,156

SWINGING SECTOR SHUTTER FOR PHOTOGRAPHIC CAMERAS

Peter Loseries, Diez, Germany, assignor to Ernst Leitz GmbH, Wetzlar, Germany


Filed Dec. 9, 1968, Ser. No. 782,173

Claims priority, application Germany, Dec. 19, 1967, P 15 97 308.7

Int. Cl. G03b 9/26

U.S. Cl. 95—60

13 Claims



This disclosure pertains to a camera shutter having two swinging sectors. Each sector includes a plurality of separately mounted lamellae actuated by pin and slit connections. The slit-forming edges of each are formed by a single lamella and by a plurality of adjacent lamellae.

3,580,157

AUTOMATIC EXPOSURE CONTROL DEVICE


Oran T. Casebeer, Interlaken, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Mar. 7, 1969, Ser. No. 805,174

Int. Cl. G03b 9/04, 19/18; G05b 6/02

U.S. Cl. 95—64

13 Claims



An automatic exposure control device for photographic cameras includes a photocell-controlled multivibrator for varying a diaphragm aperture between minimum light passage and maximum light passage positions. Separate means are provided for automatic positive drive of the diaphragm to its minimum light passage position when the camera is stopped.

3,580,158

LIQUID LEVEL SENSING DEVICE


Peter T. Scholle, Melbourne Beach, Fla., and Samuel L. Webb, Lisle, Ill., assignors to Addressograph-Multigraph Corporation, Mount Prospect, Ill.

Filed Sept. 29, 1969, Ser. No. 861,574

Int. Cl. G03d 3/12, 7/00, 3/06

U.S. Cl. 95—89G

1 Claim



Liquid level sensing apparatus is disclosed for use with liquid developing apparatus including a reservoir of conductive developer fluid. A current flow is maintained between the conductive fluid and an electrode included in the sensing apparatus, immersed in the reservoir of fluid. The depletion of developer fluid below a predetermined level causes the cessation of the current flow, which in turn causes the operation of additional circuitry of the sensing apparatus for, indicating the need for replenishment of the fluid, or for preventing the further operation of the developing apparatus.

3,580,159

DENTAL X-RAY FILM HOLDER


Jack B. Buck, 1800 South University Drive, Fort Worth, Tex.

Filed Feb. 20, 1969, Ser. No. 800,976

Int. Cl. G03d 3/00

U.S. Cl. 95—100

1 Claim



Apparatus for developing individual dental X-ray film consisting of a small processing tank and a holder for a plurality of individual films. The holder includes an elongated member which is H-shaped in transverse section and has a plurality of pairs of inwardly curved indentations formed in marginal portions of two sides thereof. The indentations coincide with the longitudinal edges of the oppositely facing legs of the H. The individual films are arranged transversely of the elongated member and extend laterally beyond the two other sides of the member.


3,580,160

FABRICATED VENTILATOR AND METHOD OF PRODUCING SAME

Francis J. McCabe, P. O. Box 131, Penns Park, Pa.
Filed Apr. 14, 1969, Ser. No. 815,896
Int. Cl. F24f 13/08

U.S. Cl. 98—121

12 Claims



A fixed blade ventilator is fabricated from blades which interlock with side channels to form, without more, a unified structure.


3,580,161

APPARATUS FOR PROCESSING CHEESE CURD INTO HOMOGENEOUS CHEESE

Nicholas E. Pontecorvo, Tarzana, Calif. (1548 18th St., Santa Monica, Calif. 90404)
Continuation-in-part of application Ser. No. 712,715, Mar. 13, 1968, now Patent No. 3,476,036. This application Aug. 11, 1969, Ser. No. 849,132
Int. Cl. A23c 19/00

U.S. Cl. 99—243

8 Claims



Cheese processing apparatus comprising a circular tub containing heated water for softening raw cheese curd delivered to it by a fixed hopper, the tub being rotatable to carry the cheese in a circular path of nearly 360° to an elevating conveyor operating adjacent the back side of the hopper to remove the softened curd from the bottom of the tub and elevate it over the tub rim to a kneading unit of the apparatus.

3,580,162

CHEESE KNEADING APPARATUS


Nicholas E. Pontecorvo, Tarzana, Calif. (1548 18th St., Santa Monica, Calif. 90404)
Filed Nov. 3, 1969, Ser. No. 873,265
Int. Cl. A23c 19/12

U.S. Cl. 99—243

10 Claims

Presoftened and moistened cheese curd is kneaded into homogenous consistency such as Mozzarella, by feeding it consecutively into successive annular kneading chambers

defined between the cylindrical internal surfaces of a series of axially spaced substantially coaxial rings and the surface of a cylindrical mandrel projecting through the series of rings in eccentric relation thereto, the curd moving circumferentially



through a restricted pass between areas of closest spacing of the opposed cylindrical surfaces into a wider area of a respective chamber, from which it is deflected axially to a succeeding chamber while carried on the surface of the mandrel.


3,580,163

VARIABLE CAPACITY COFFEE PERCOLATOR

Claude S. Farrell, Jr., Northbrook, Ill., assignor to Cory Corporation
Filed Feb. 5, 1969, Ser. No. 796,793
Int. Cl. A47j 31/04

U.S. Cl. 99—310

32 Claims



In a percolator having a pump stem for carrying a brewing basket adjacent the upper open end of the receptacle, or pot, cooperating means are provided on the stem and basket for selectively positioning the basket in a normal brewing position within the receptacle and in an extra-capacity position upwardly thereof whereby an additional quantity of beverage such as coffee may be brewed in the receptacle. The percolator includes a cover removably carried on the basket and provided with means for deflecting the hot pumped water downwardly onto the beverage charge in the basket in each of the normal and extra-capacity positions of the basket.

The cooperating support means may comprise shoulder means on the stem and basket. Alternatively, the support means may comprise a spring clip carried by the stem and having portions selectively engageable with the basket. The extra capacity of the percolator may be substantial, such as over 4 cups. The sidewall of the basket may be imperforate to preclude spillage of the hot water such as when the basket is raised to be substantially outward of the open top of the receptacle.

3,580,164

HAMBURGER COOKING MACHINE

Edward D. Baker, Belmont, Calif., assignor to National Industrial Manufacturing
Filed Oct. 9, 1969, Ser. No. 865,102
Int. Cl. A47j 37/00

U.S. Cl. 99—339

10 Claims

A hamburger cooking machine includes a cooking element of the gas-fired, radiant energy, surface combustion type


3,580,166

COMPACTION APPARATUS

Joseph F. Longo, New Canaan, Conn., assignor to International Dynetics Corporation, Norwalk, Conn.
Filed May 8, 1969, Ser. No. 823,059
Int. Cl. B30b 15/16

U.S. Cl. 100—49

22 Claims



A waste compactor is also mounted on the frame and is similarly moved with respect to a comparable source of heat so that a bun thereon is warmed or toasted. The hamburger patty and the bun are simultaneously conveyed through the machine, and are discharged at about the same time for assembly into a hamburger.

A waste compactor includes a horizontally extending compacting chamber with a cantilevered open-ended front section closed by an openable first gate and a chute communicating with a rear upper feed opening. A ram is hydraulically motivated along the chamber between advanced, retracted and intermediate positions. An electrical network controls the ram when the first gate is closed and material sensed in the chute to reciprocate the ram between intermediate and retract positions until the hydraulic pressure exceeds an adjustable value at the intermediate position and to reciprocate the ram between the retracted position and a point rearwardly of the intermediate position when hydraulic pressure exceeds a second predetermined value. Upon opening of the first gate the ram can be fully advanced.


3,580,167

CAN CRUSHING APPARATUS

Herbert H. Simshauser, 5532 Beechwood, Ravenna, Ohio
Filed Sept. 19, 1969, Ser. No. 859,411
Int. Cl. B30b 15/18, 15/22

U.S. Cl. 100—52

11 Claims



Apparatus for crushing waste objects such as cans, containers, bottles and the like, including motor-driven screw and nut means for displacing a crusher member in a given direction to compress waste objects contained in a crushing chamber. The invention is characterized by the provision of quick-release means for disengaging the nut means from the screw means to permit instantaneous return of the crusher member to its initial retracted position by return spring means. In the preferred embodiment of the invention, the nut means is of the split-nut type including nut sections that are automatically locked into threaded engagement with the screw by an axially shiftable collar upon closure of a cover member upon the crushing chamber. Means responsive to the crushing pressure near the end of the crusher stroke are provided for disengaging the nut sections from the screw means.


3,580,165

MEAT MOLD

Ralph M. Foldenauer, Chicago, Ill., assignor to Bloomer-Fiske, Inc.
Filed June 6, 1969, Ser. No. 831,039
Int. Cl. A47j 27/20

U.S. Cl. 99—351

3 Claims



A multiple cavity meat mold, wherein each cavity is open at both ends, has a closure-forming pressure plate for one end of each cavity, each plate being independently biased by a coil spring and provided with a guide pin, coaxial with the coil spring, that fits into a guide sleeve on the spring backing. The plates maintain the ends of the meat in the mold cavities perpendicular to the axis of the associated cavity during the cooking and chilling. The plates are held onto the mold body by a ratchet arrangement. At the bottom of each mold cavity is a removable closure end plate.

3,580,168


HAND SQUEEZER FOR FRUITS AND VEGETABLES

Karl Zysset, Hauptstrasse 31, 3250 Lyss, Switzerland
 Filed Aug. 19, 1969, Ser. No. 851,185
 Claims priority, application Switzerland, Aug. 28, 1968,
 12868/68

Int. Cl. B30b 7/00

U.S. Cl. 100—234

5 Claims



Squeezer has two levers pivotally connected together nearer one end than the other so as to divide the levers into two arms each of unequal length, of which the longer arms constitute the handle and the shorter arms respectively the receptacle for the fruit or vegetable and a plunger, and either the bottom of the receptacle or of the plunger is provided with holes through which the juice escapes.

3,580,169


SETTABLE DRUM SERIES PRINTING WHEEL ARRANGEMENT

John A. Maul, Lyndhurst; James T. Zofchak, Mentor, and David D. Anderson, Richmond Hts., Ohio, assignors to Addressograph Multigraph Corporation, Cleveland, Ohio
 Division of Ser. No. 698,871, Jan. 18, 1968, Pat. No. 3,508,488.
 Filed Oct. 8, 1969, Ser. No. 864,643

Int. Cl. B41j 5/02, 1/22

U.S. Cl. 101—110

2 Claims



A data recorder including a plurality of coaxial settable print wheels nested in closely spaced printing relation, and rotary gear trains for positioning the print wheels under control of selectively operable indexing wheels spaced only a short distance from the print wheels. Extension gears are provided for laterally spreading out the rotary gear train from the closely positioned print wheels to the indexing wheels, thereby spreading apart adjacent indexing wheels sufficiently to allow for operator finger contact with the indexing wheels individually to permit independent movement thereof.

3,580,170

SUPPORT ASSEMBLY FOR A TRAVEL CYLINDER HAVING ROLLING CONTACT WITH THE BED OF A PRINTING MACHINE

George R. Furman, Glenham, N.Y., assignor to Texaco Inc., New York, N.Y.

Filed Aug. 30, 1968, Ser. No. 756,440


Int. Cl. B41f 3/04

U.S. Cl. 101—269

6 Claims

A roller cylinder support assembly consisting of an outboard low friction bearing housing which is nested in an inboard recessed thrust washer and a shaft of appropriate

dimensions for supporting the same extending axially through the roller cylinder, the roller cylinder bracket yoke of the ac-



tuating handle contacting the roller cylinder shaft between the roller cylinder and the thrust washer.

3,580,171


FIELD SENSITIZED EXPLOSIVE DEVICES AND SENSITIZING METHOD

Michael E. Maes, Bellevue, Wash., assignor to Explosives Corporation of America, Issaquah, Wash.
 Continuation-in-part of application Ser. No. 703,994, Feb. 8, 1968, now abandoned, which is a continuation-in-part of application Ser. No. 631,123, Apr. 17, 1967, now Patent No. 3,419,443, dated Dec. 31, 1968. This application Feb. 25, 1969, Ser. No. 805,987

Int. Cl. F42b 3/10, 3/18

U.S. Cl. 102—28

23 Claims



Rigid and flexible container type portable devices incorporating an intrinsically nonexplosive solid constituent of an explosive composition. Sensitizing of the device at the site of use by adding thereto a complementary intrinsically nonexplosive liquid constituent of the explosive composition, for admixing with the solid constituent. Such devices including built-in electrical initiators or fuse wells. Such devices constructed for coupling with a similar container containing the liquid constituent in a frangible capsule, including means for cutting or fracturing the capsule when the containers are moved together, and means for preventing fluid leakage from the assembly or the device. Such two container devices which are joinable in a first prearm, nonmixing position, and are movable into a second mixing position, in which the frangible capsule is fractured.

3,580,172

UNDERWATER PROJECTILE FOR FIRING A CARTRIDGE UPON IMPACT

Grover E. Hendricks, 2241 Lake St., Niles, Mich.

Filed Nov. 27, 1968, Ser. No. 779,371

Int. Cl. F42b 13/54; A01k 81/00


U.S. Cl. 102—48

5 Claims

A projectile including an elongated tubular body having an open fore end portion defining a gun bore and an intermediate portion defining a chamber communicating with the gun bore for receiving an ammunition cartridge. A firing pin is slidably disposed within the tubular body rearwardly of the chamber therein and is adapted to be shifted forwardly

within the tubular body to engage the primer of an ammunition cartridge housed within the chamber upon fore end con-

situated in its position of rest in the cavity and a rod extends through the passage having the secondary detonator fastened



tact of the projectile body with a target to cause detonation of the ammunition cartridge.

3,580,173

EXPLOSIVE TABLE DECORATION


Adrien Machet, Saint-Denis, France, assignor to Etablissements MACHET, Saint-Denis, France
 Filed Mar. 26, 1969, Ser. No. 810,608

Claims priority, application France, Apr. 4, 1968, 146984

Int. Cl. C06d 1/00

U.S. Cl. 102—37.2

2 Claims



In an explosive table decoration covered with decorative cover which does not enable it to be seen at first glance what it actually is, and containing objects to be distributed and an explosive charge to blow out the decorative cover and the objects in question, a particular method of connection of the actual explosive device and the aforesaid decorative cover.

3,580,174

PROJECTILE WITH HOLLOW EXPLOSIVE CHARGE

Robert Apotheloz, Wallisellen; Hans-Ulrich Bigler, Opfikon, and Rene Kessler, Zurich, Switzerland, assignors to Werkzeugmaschinenfabrik Oerlikon-Bührle AG, Zurich, Switzerland

Filed Feb. 18, 1969, Ser. No. 800,161


Claims priority, application Switzerland, Mar. 7, 1968, 3494

Int. Cl. F42b 25/20, 25/16

U.S. Cl. 102—56

4 Claims

A projectile having a body with an explosive charge having a cavity. A lagging is located in the cavity and a passage in the charge extends centrally rearwardly from the cavity. A primary detonator for the charge is before firing located in a position of rest and after firing is located in an ignition position at the front end of the passage. A secondary detonator is



3,580,175

FRAGMENTATION EXPLOSIVE DEVICE


James E. Kenney, and Richard J. Ashenfelter, both of Toledo, Ohio, assignors to Gerity-Schultz Corporation, Toledo, Ohio

Filed Sept. 19, 1968, Ser. No. 760,761

Int. Cl. F42b 13/48

U.S. Cl. 102—67

4 Claims



A fragmentation explosive device consisting of a plurality of projectiles cast within matrix material which vaporizes at the explosion temperature, wherein the projectiles are formed of a length of strip material having frangible zones at spaced intervals along the length thereof.

3,580,176


FUZE WITH IMPACT SWITCH

George T. Boswell, Springfield, Va., assignor to The Susquehanna Corporation
 Division of Ser. No. 647,355, June 20, 1967, Pat. No. 3,457,382.
 Filed Feb. 28, 1968, Ser. No. 823,223

Int. Cl. F42c 1/08, 9/10

U.S. Cl. 102—75

17 Claims



An impact weight is releasably engaged, supported, and caged by a plurality of springlike supports which also releasably engage a spring-loaded operator and hold it in the cocked position. The weight moves in response to impact or

a predetermined level of vibration to dislodge the supports and allow the operator to be driven home by the spring.

In the fuze, a safety slide locks the supports until removed by the action of an explosive or mechanical delay mechanism. Once the supports are unlocked the weight is free to move upon impact, then dislodging the supports and allowing the operator to strike a detonator to fire the weapon. Should there be little or no impact, the delay train causes the operator to be released after a predetermined interval notwithstanding the position of the supports.

3,580,177

ROTATIONALLY RESPONSIVE DEVICE


Fred Krahulec, Phoenix, Ariz., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Oct. 2, 1968, Ser. No. 764,391

Int. Cl. F42c 15/26

U.S. Cl. 102—79

6 Claims



A rotor is rotationally supported on a housing and spring urged in a first rotational sense. The spring is a multiconvolution resilient steel tape wound on the rotor and disposed between the rotor and the housing in a narrow annular space. Rotation of the housing in a second rotational sense urges the rotor to unwind the spring tape and thereby rotate a predetermined distance. A configuration for a safe and arm mechanism is disclosed.

3,580,178

EXTERNALLY LUBRICATED PROJECTILE AND METHOD OF MAKING SAME


Paul J. Kopsch, 710 Easter Park Road West; Daniel Turcus, Jr., 1019 W. 38th St., Lorain, and Donald F. Ward, Telegraph Road, South Amherst, Ohio

Filed Oct. 31, 1967, Ser. No. 679,391

Int. Cl. F42b 11/14

U.S. Cl. 102—92.2

3 Claims



A bullet having a core which is secured to a jacket. At least the piercing end or extremity of the core is coated with a low-friction fluorocarbon resin, such as polytetrafluoroethylene. The resin may also be used to secure the jacket to the core.

3,580,179

AMMUNITION FOR TARGET PRACTICE OR OTHER SHORT-RANGE PURPOSES

Heinz Gawlick; Rudolf Stahlmann, Furth, and Hans Umbach, Stadeln, Kronacher, Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Germany

Filed Sept. 6, 1968, Ser. No. 757,898


Claims priority, application Germany, Sept. 6, 1967,

P 15 78 123.4

Int. Cl. F42b 11/18

U.S. Cl. 102—92.7

13 Claims



Projectiles designed for practice or other limited-range purposes, including a tip which will disintegrate and/or be jettisoned from the body of the projectile and laterally deflected from the path thereof shortly after exit from the barrel of the firearm, which tip is constructed with a longitudinal cross section deviating from rotational symmetry and/or an annular hollow space surrounding the central core thereof and extending rearward, which hollow space is defined by the outer shell of the tip, having a thickness such that it may be ruptured by the pressure of the propellant gases.

3,580,180

CONSUMABLE INDUSTRIAL PROPELLANT CARTRIDGE


Heinz Gawlick, Furth, and Gunther Marondel, Erlangen, Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Germany

Filed Sept. 19, 1967, Ser. No. 668,797

Int. Cl. F42b 1/02

U.S. Cl. 102—101

7 Claims



A consumable industrial propellant cartridge having a form-stabilized annular propellant charge body filled with loose ignitor composition and closed at both ends with a relatively thin powder foil coated on its inside surface with a percussion-sensitive material, for example, tetrazene or tetrazene-trizinate.

3,580,181

SURFACE-EFFECT TRANSPORT SUPPORT SYSTEMS

Jean Henri Bertin, Neuilly-sur-Seine, and Francis Marie Jean Croix-Marie, Viry-Chatillon, France, assignors to Bertin & Cie, Plaisir, France

Filed Dec. 29, 1969, Ser. No. 888,316

Claims priority, application France, Dec. 27, 1968, 181,381


Int. Cl. B60v 3/04, 1/06

U.S. Cl. 104—23FS

28 Claims

A transport system comprising a surface-effect vehicle movable along a prepared track, the vehicle having means

for defining a first fluid cushion of predetermined pressure below ambient pressure and cooperating with the track, and second means combining with the first means to define a



second fluid cushion of a pressure lower than said predetermined pressure, so that the vehicle cooperates with track through superimposed fluid cushions.

3,580,182

VARIABLE-SPEED TRANSPORT APPARATUS

Gabriel Bouladon, St.-Loup/Bersoix, and Paul Zuppiger, Athenaz/Geneva, Switzerland, assignors to Battelle Memorial Institute, Carouge/Geneva, Switzerland

Filed Apr. 22, 1969, Ser. No. 818,241


Claims priority, application Switzerland, Apr. 26, 1968,

6280/68

Int. Cl. B65g 17/06

U.S. Cl. 104—25

11 Claims



A variable-speed passenger transporter for conveying passengers from a stationary surface to a belt moving at constant speed, which includes a plurality of rhomboid platforms driven along guide means in a closed circuit along a section of which the platforms are in contacting relationship to form a moving floor. Along the initial portion of this section the platforms travel at low speed and at right angles to their center lines towards the belt but at an angle thereto. Along the following portion they are shifted along one another without changing their orientation to increase their speed until they come alongside the belt. The platforms then move with the belt at more or less the same speed as the latter and at an angle thereto, the oblique ends of the rhomboid platforms providing the moving floor with a substantially straight edge at least alongside the belt. A reverse, decelerating, arrangement and various modified constructional forms are also provided.

3,580,183

TROLLEY AND HANGER APPARATUS


Richard E. Nearman, Mount Airy, Md., assignor to Automated Handling Systems, Inc., Washington, D.C.

Filed May 13, 1968, Ser. No. 728,513

Int. Cl. B61b 3/00

U.S. Cl. 104—111

13 Claims



Flat trolley bodies having perpendicular tabs along upper edges thereof for mounting axles and guide rollers to prevent the trolley bodies from scraping along tracks, hangers having integrally formed arcuate bumpers, and combinations of trolleys and hangers having motion-limiting stops near hinged interconnections are described herein.

3,580,184

TRANSPORTATION SYSTEMS

Francois Louis Giraud, Plaisir, France, assignor to Societe De L—Aerotrans, Paris, France


Filed May 4, 1969, Ser. No. 813,597

Claims priority, application France, Apr. 5, 1968, 147,270

Int. Cl. B61b 13/08

U.S. Cl. 104—165

17 Claims



The present invention relates to improvements in transportation systems and in particular passenger transportation systems of the kind in which the payload carrier is borne by a conveyor arrangement, the improvements comprising means for automatically or manually engaging said payload carriers with, and disengaging them from, the conveyor means by the use of ground-effect arrangements in association with special track formations.

3,580,185

SYSTEM AND APPARATUS FOR HOLDING FREIGHT CONTAINERS TO VEHICLES AND THE LIKE

John Bridge, 407 S. Dearborn St., Chicago, Ill.

Filed Aug. 27, 1968, Ser. No. 755,677

Int. Cl. B65j 1/22


U.S. Cl. 105—366

8 Claims

System for locating and locking freight containers on vehicles such as freight cars, trailers, trucks, ships decks and the like. A series of loaded containers may be mounted on the vehicle deck, either in alignment with each other or one above the other. The loaded containers are located and retained to the deck by a dome lock accommodating limited vertical movement of the container but relieving the container from shocks and twisting forces of the vehicle deck.

Low-height containers are mounted directly on the deck

and retained to the deck by dome-centering devices extending upwardly of the deck. Crossbeams extend over the low-height containers and form supports for upper containers. These beams have centering domes thereon mounted at their ends for controlled vertical movement with respect to the deck.



In another form of the invention the domes are at opposite sides of the deck and are placed along the deck to take care of containers of various lengths and are mounted on the deck for vertical shifting movement in controlled paths.

In still another form the domes are mounted on the lower container, and a second container is supported directly on the lower container.

3,580,186

CARLOADING BOX SPACERS


Harold C. Pierce, 1527 Ganesha Place, Pomona, Calif.

Filed Apr. 15, 1968, Ser. No. 721,257

Int. Cl. B61d 45/00

U.S. Cl. 105-369

10 Claims



The invention provides a new spacer component and spacer assembly for use in the stabilization of carload boxes during transit, the assembly comprising an elongated spacer member carrying at one or each of its ends a molded plastic attachment having a body portion extending normal to the spacer and held thereto at one side, and having web means projecting from the opposite side of the body for reception between loaded boxes.

3,580,187

LOAD TIEDOWN TENSIONER

Lawrence P. Marks, Brown Deer, Wis., assignor to A. O. Smith Corporation, Milwaukee, Wis.

Filed July 2, 1968, Ser. No. 742,045


Int. Cl. B61d 45/00; B60p 7/08

U.S. Cl. 105-369

8 Claims

The present disclosure relates to tiedown means. A stack of vehicle frames are mounted on a bed. A box beam is disposed over the frames or integrated into the bed. A pair of parallel torsion shafts having a high spring rate are mounted in the box beam. The first shaft is fixed at one end to the beam end wall and protrudes from the opposite wall. A crank is secured to the free end of the first bar and disposed between a pair of stop elements on the end wall. The shaft is prestressed to engage the one stop with a selected stored energy with the holding rotation of the arm increasing the stress. The second shaft is similarly constructed, but oppositely disposed to dispose the crank to the opposite end of the assembly.

Suitable straps or chains are interconnected to the cranks to clamp the load to the bed. A one-way locking means selectively



tively limits the movement of the crank to prevent pivoting and increasing the shaft stress after the initial setting.

3,580,188

APPARATUS FOR PRODUCING FROZEN COATED ICE-CREAM CONES


Thomas H. Lutsey, Green Bay, Wis., assignor to Big Drum, Inc., Columbus, Ohio

Filed Sept. 23, 1969, Ser. No. 860,377

Int. Cl. A23g 3/24; F25c 7/04

U.S. Cl. 107-1A

8 Claims



Apparatus for making frozen edible articles, such as frozen ice cream cones of the type comprising a pastry container or cone having frozen ice cream filling and extending from the mouth end thereof, with a coating of chocolate and nuts on the protruding ice cream. The apparatus includes an endless conveyor which receives the upright cones to be filled with ice cream, and progressively moves the upright cones to a filling station where they are filled with ice cream that extends from the upper mouth end thereof; moves the filled cones through an elongated freezing chamber from which they emerge in inverted position on the conveyor fully frozen; moves the filled cones while inverted to successive stations where they are coated with syrup and edible particles, such as chocolate and nuts or the like; and finally discharges the frozen inverted coated cones at a wrapping station.

3,580,189

TABLES HAVING POSITIONS OF USE AND NONUSE


Edith Brown Eisenberg, 48 Brower Ave., Woodmere, N.Y.

Filed Sept. 18, 1969, Ser. No. 859,038

Int. Cl. A47f 5/12; A47b 3/00

U.S. Cl. 108-3

9 Claims



A table which has movable and stationary components coaxing to provide for the table a position of use and a position

tion of nonuse. The table includes a tabletop made up of a plurality of these components which closely surround each other and are located in a common plane when in the position of use. These components include an inner stationary section of the tabletop and a plurality of endless components one surrounding the other and including an inner endless component which directly surrounds the stationary inner section. A plurality of pivots interconnect the several components one with the next for swinging movement with respect to each other about predetermined axes for situating the several components in different planes, respectively, when the tabletop has a position of nonuse.

3,580,190

PALLET CONSTRUCTION


Timothy J. Fowler, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

Filed Jan. 7, 1970, Ser. No. 1,269

Int. Cl. B65d 19/18

U.S. Cl. 108-58

10 Claims



A substantially rectangular pallet which can be raised and transported by forklift truck arms inserted through any one of the four side edges thereof and which can span across its narrow width. The pallet has a top deck, a bottom deck, and a structural network mediate therebetween which all coact together. The structural network has longitudinally extending and transversely extending stringer members interconnecting with one another. The pallet construction is well suited for formation from two, or three preformed pieces of plastic material and is especially adapted for use by the food industry in shipping and warehousing foodstuffs.

3,580,191

REMOVABLE SHELF


Thomas M. McDonnell, 11 N. 4th Ave., Maywood, Ill.

Filed Mar. 2, 1970, Ser. No. 15,350

Int. Cl. A47b 5/00

U.S. Cl. 108-152

10 Claims



A shelf device adapted to be removably attached to a support extending at any angle in a vertical plane, comprising: a table, a retaining plate secured to one side of the table, a

clamp carried by the table, and means carried by the table for moving the clamp toward and away from the retaining plate for clamping the support therebetween.

3,580,192

COMPOSITE MANTLE SYSTEM


Louis Davidson, 24 Waterview Road, Oceanside, Long Island, N.Y.

Filed Dec. 11, 1969, Ser. No. 884,268

Int. Cl. A47g 29/02; E04f 19/08

U.S. Cl. 108-152

8 Claims



This invention is a composite mantle system for providing a room with a simple shelf mantle which can be added to from time to time to make a more elaborate mantle system and with provision for including a simulated fireplace under the mantle as part of the mantle system. Most parts are compatible with one another and constructed so that installations and additions can be made on a modular "do-it-yourself" basis, and most of the parts are designed for construction from heavy kraft paper or corrugated paperboard, or plastic materials, or a combination of them, to provide an inexpensive form of the invention. Combinations of parts and connecting brackets provide for additions without having to tear out previous constructions to permit the additions to the system.

3,580,193

HEAT TREATED WASTE SLUDGE DISPOSAL


Robert P. Logan, West Redding, and Orris E. Albertson, Norwalk, Conn., assignors to Dorr-Oliver Incorporated, Stamford, Conn.

Filed Sept. 5, 1969, Ser. No. 855,633

Int. Cl. F23g 7/00

U.S. Cl. 110-8

20 Claims



Sewage sludge is pressure cooked by heat exchange to 350-400° F. at a pressure sufficient to prevent evaporation for approximately 30 minutes to free bound cell water. The freed water is decanted and the remaining sludge is de-watered by centrifuge or filter to a very dry cake having a solids content of 35 to 75 percent. The cake is continuously fed to a fluidized bed combustion chamber for autogenous combustion wherein the sludge is reduced to inert burned exhaust gases and finely divided ash entrained with the gases. The dry cake readily crumbles into small pieces and may be screw fed or milled and blown into the combustion chamber. The high solids content, crumbly nature and nonodoriferous character of the cake simplifies feeding requires no auxiliary fuel after start up, or preheating of combustion air and decreases the size and capital cost of the combustion reactor.

3,580,194

LEAF BURNER ATTACHMENT FOR LAWN MOWERS


Harold Withers, 35 Ohio Ave., Poland, Ohio

Filed Nov. 13, 1969, Ser. No. 876,355

Int. Cl. F23g 9/00

U.S. Cl. 110-18

4 Claims



A leaf burner attachment for lawn mowers includes a cylindrical combustion chamber with a centrally disposed vertically standing perforated vent stack which extends from a bottom portion of the cylindrical combustion chamber and through a top portion thereof, leaves and air are introduced at one side of the cylindrical combustion chamber near the bottom thereof through an opening which communicates with a duct positioned on a tangent with respect to the wall of the cylindrical combustion chamber so that air and leaves introduced into the cylindrical combustion chamber will spin centrifugally therein and around the centrally disposed perforated vent stack.

3,580,195

GRATE FOR INDUSTRIAL FURNACES

Johannes Josef Martin, Leopoldstrasse 248, Munich 23, Germany

Filed Apr. 1, 1969, Ser. No. 811,765


Claims priority, application Germany, Apr. 6, 1968, P-

P 17 51 126.1

Int. Cl. F23b 1/24

U.S. Cl. 110-35

11 Claims



A grate, particularly of the type used for removing waste material from large industrial furnaces, which comprises a movable, biased transfer grate element between a fixed grate element and a rotary grate element. The transfer element is in sliding contact with the rotary grate element.

3,580,196

PLASTIC MULCH

Earlston Arthur Lofgreen, Coolidge, Ariz., assignor to Occidental Petroleum Corporation

Filed May 27, 1968, Ser. No. 732,226


Int. Cl. A01g 1/00

U.S. Cl. 111-1

2 Claims

An agronomic mulch sheet and method comprising a flexible mulch sheet having first openings spaced a distance equaling the desired spacing of plants and release portions in said sheet whereby the first openings may be enlarged when they are pulled upwardly over partially grown plants in order

to remove the sheet from a plant row; the method comprising preliminary planting of seeds in closely spaced relation, and



the growth of plants through areas only covered by said openings in said sheet.

3,580,197

SWITCH FOR SEWING MACHINE CONTROL AND THREAD CUTOFF


Angelo Mascaro, 808 S. E. Granger, Des Moines, Iowa

Filed Nov. 18, 1969, Ser. No. 877,659

Int. Cl. D05b 13/02

U.S. Cl. 112-11

9 Claims



A spring-urged lever oscillatably supported from a bag closing sewing machine head and including a free end swingable between first retracted and second extended positions on opposite sides of a feed path along which bags are fed into and discharged from the sewing machine. The lever is spring-biased toward the extended position thereof and its free end includes knife structure for cutting the thread chain extending rearwardly from a bag discharged from the sewing machine as the free end of the lever swings across the feed path of the machine. The base end of the lever has a switch operatively associated therewith for opening the electrical circuit to the electric motor of the sewing machine whenever a bag to be sewn by the machine is not disposed within a predetermined zone extending along the feed path on both sides of the sewing machine head.

3,580,198

APPARATUS FOR AUTOMATICALLY FABRICATING INDIVIDUAL ARTICLES

Richard K. Teed, Greenwood, S.C., and Karl W. Klose, Findlay, Ohio, assignors to Riegel Textile Corporation, Ware Shoals, S.C.

Filed Aug. 26, 1969, Ser. No. 853,225

Int. Cl. D05b 19/00

U.S. Cl. 112-121.11

14 Claims

Apparatus for automatically fabricating individual articles, such as blankets and the like, from a continuous length of textile material comprising the following component parts. Supply means supplying a continuous length of textile material. First interrelated, intertimed feeding means feeding the continuous length of material from the supply means in an elongate path of travel along a longitudinally extending axis

3,580,200

APPARATUS FOR AND METHOD OF FORMING A SHEETLIKE WORKPIECE


Daniel S. Cvacho, and Edward H. Fritchey, Richmond, Va., assignors to Reynolds Metals Company, Richmond, Va.

Filed July 17, 1968, Ser. No. 745,593


Int. Cl. B21d 51/26

U.S. Cl. 113-1

23 Claims



articles from the turning means and feeding them in a continued elongate path of travel along the aforesaid longitudinally extending axis through the apparatus. Third and fourth driven stitching means applying lines of stitching along the cut edges of each of the individually cut turned articles so that each of the articles will be stitched along all four of its edges.



An apparatus for and method of forming a sheetlike workpiece wherein the workpiece is formed utilizing forming dies which have control surfaces which do not engage the workpiece and such control surfaces control the action of the forming dies to assure that a known substantially exact amount of working material remains after forming such workpiece.

3,580,199

EMBROIDERY STITCHING SEWING MACHINE

Luigi Vigorelli, 80, Viale Partigiani, 27100 Pavia, Italy


Filed May 5, 1969, Ser. No. 822,862

Claims priority, application Italy, May 8, 1968, 16231A/68

Int. Cl. D05b 3/02

U.S. Cl. 112-158

8 Claims



The disclosure relates to an embroidery stitching sewing machine in which a laterally oscillatable needle-bar can be selectively connected to any cam of a plurality of cams for providing zigzag and ornamental stitching, and in which a work fabric feeding device can be automatically controlled by cam means for providing a feeding sequence including forward and rearward steps. Said cam means comprise one cam of such cam track profile to provide a sequence comprising two steps forward and one step backward to produce a stitching wherein in any stitch pitch three sewing stitches are present, the cams of said plurality providing ornamental and utility embroidery and zigzag patterns compatible with said sequence.

3,580,201

CLOSURE

Peter A. Vercillo, Chicago, Ill., assignor to Continental Can Company, New York, N.Y.


Division of Ser. No. 786,219, Dec. 23, 1968, Pat. No. 3,494,497

Filed Aug. 28, 1969, Ser. No. 872,794

Int. Cl. B21d 51/00

U.S. Cl. 113-121

3 Claims



A closure for a container having a top seal finish and a side finish having thread means or closure locking means thereon in which the closure includes an outer shell having a top panel portion, an outer margin portion, a gasket disposed at least partially within said margin portion on an interior surface thereof, and a skirt depending from said outer margin, and including a plurality of fastening elements disposed about the bottom thereof. The fasteners include inwardly extending fingers, spring biased inwardly but resiliently movable outwardly. The resulting closure may be pressed, without intentional rotation, over the finish portion of a container, and will lock in place thereover as the fastening elements deflect outwardly when passing over the threads and thereafter engage the threads to hold the closure in position, while the gasket portion engages at least the top finish of the container in a sealing relation. Subsequent rotation will then unscrew the cap in a conventional manner.

3,580,202

FLOATING WHARF STRUCTURE


Kenneth L. Thompson, Huntington Beach, Calif., assignor to Ye Dock Master, Inc.

Filed Mar. 11, 1969, Ser. No. 806,249

Int. Cl. B63b 35/00

U.S. Cl. 114—0.5

9 Claims



A floating wharf structure wherein interconnected walkways are provided spaced from the top surfaces of supporting pontoons. Each of the walkways comprises a flat sheet of wire mesh screen and spacing means are defined by reinforcing bars disposed downwardly from the sheet. The screen and bars are encased in concrete shaped to define the walkway and integral spacing means. The walkways are interconnected by flanges extending downwardly from the walkways to contralaterally flank underlying pontoons. Each pontoon comprises walls of concrete defining a chamber and polymer foam filling the chamber.

3,580,203
SAILBOAT


Benjamin P. Martin, 1249 Lime Drive, Sunnyvale, Calif.

Filed Nov. 5, 1968, Ser. No. 773,413

Int. Cl. B63b 35/00; B63h 9/06

U.S. Cl. 114—39

15 Claims



A sailboat including hull having a mast mounted for full 360° rotation thereon and forming the central portion of a sail having the configuration of an air foil and arranged to collapse together with means for adjusting the sail position, the sail being supported so that its aerodynamic center is closely adjacent its axis of rotation and cooperatively arranged with a rotatable centerboard to achieve optimum utilization of the propulsive forces of a wind.

3,580,204


ARRANGEMENT IN SHIPS

Fred Burmeister, Parksvangen; Ernst Enkvist, Grondal; Bengt Johansson, Kadettvagen, and Valter Kostilainen, Niittykumpu, Finland, assignors to Oy Wartsila Ab, Helsinki, Finland

Filed Nov. 12, 1968, Ser. No. 774,654
Claims priority, application Finland, Nov. 11, 1967, 3044/67
Int. Cl. B63b 1/38

U.S. Cl. 114—67

6 Claims



An arrangement in ships, especially in ships moving in ice filled waters, the arrangement comprising underwater/air blowing openings at the side of the ship, preferably in the bow area of the ship. By blowing air through the openings a strong upwards directed water flow is produced which at the water surface bows sideways. This water flow can be used to facilitate the moving of the ship in ice filled waters and as an auxiliary steering means.

3,580,205


SHIP STABILIZERS

John Bell, deceased, late of Beckenham, Kent, England, Barclays Bank Limited and Bella Bell Executors, Beckenham, Kent, England, assignors to Muirhead Limited, Kent, England

Filed Jan. 31, 1969, Ser. No. 796,649
Claims priority, application Great Britain, Feb. 2, 1968, 5374/68
Int. Cl. B63b 43/06

U.S. Cl. 114—125

6 Claims



A tank stabilizer for marine use has a high-Q tuned U-tank system in which the water levels in the two side tanks are boosted, when the system is operating at resonance, by a booster arrangement. The booster arrangement is insufficiently powerful to operate the stabilizer as an active stabilizer but improves the Q factor of the tank system to enhance its stabilizing power. The booster arrangement is controlled by roll-sensing means.

3,580,206

AUTOMATIC PILOT

William R. Duncan, Rte 3, Box 249, Sequim, Wash.

Filed Mar. 11, 1969, Ser. No. 806,105


Int. Cl. B63h 25/00

U.S. Cl. 114—144

8 Claims

A compass-controlled valve continuously regulates differential, atmospheric venting of opposite lateral sides of a venturi throat in a flow passage extending through a rudder which directionally controls movement of a craft. The dynamic pressure of a flow stream through the rudder passage is thereby controlled to directionally drive a turbine

wheel geared to the pivot shaft of the rudder for corrective angular movement of the rudder, reestablishing the craft



heading corresponding to the adjustable setting of the compass-controlled valve.

3,580,207

METHOD AND MEANS FOR MOORING


Frans V. A. Pangalila, Matawan Township, assignor to John J. McMullen Associates, Inc., New York, N.Y.

Filed Apr. 4, 1969, Ser. No. 813,598

Int. Cl. B63h 25/00; B63b 35/44

U.S. Cl. 114—144

9 Claims



A method and means for mooring and particularly adapted for mooring semisubmersible platforms, such as drilling platforms used in the offshore drilling of oil wells. The invention contemplates providing the platform with a series of tensioned mooring lines, sensing means for sensing tension in the various mooring lines, and means for relieving the tensions on selected mooring lines responsive to the tension on a mooring line rising above its initially tensioned condition due to surge motions of the platform resulting from wind and waves.

3,580,208

RUDDER CONTROL FOR A SAIL BOAT


Henry R. Hinckley, Southwest Harbor, Maine, assignor to Henry R. Hinckley & Company, Southwest Harbor, Maine

Filed June 26, 1969, Ser. No. 836,808

Int. Cl. B63h 25/06

U.S. Cl. 114—163

10 Claims



A rudder control for a sail boat which has a main rudder and an auxiliary rudder with means to selectively operate the rudders separately or in unison which includes the use of a locking member.

3,580,209

CONTROLLED RELEASE SAFETY CLEAT


Birger H. Olson, Lansing, Mich.

Filed Sept. 10, 1968, Ser. No. 856,657

Int. Cl. B63b 21/08

U.S. Cl. 114—218

7 Claims



A friction-controlled release safety cleat apparatus for automatically and controllably permitting movement of a sheet therethrough in response to an excess force acting on the sheet. The cleat apparatus consists of a base member having a raised sheet guide wall along one side thereof. A spring biased cam arm is pivotally mounted on the base member and is provided with a freely rotatable ratchet wheel thereon. The ratchet surface of the ratchet wheel is adapted to press against a sheet positioned against the guide wall. A tightening means is provided on the cam arm in association with the ratchet wheel so as to selectively restrict the ratchet wheel against rotation below a predetermined force level. The ratchet wheel and sheet guide wall are adapted to retainably hold a sheet therebetween against movement and to permit a controlled playing out of the sheet only while a predetermined force upon the sheet is being exceeded.

3,580,210

NONCLOGGING MARINE GRILLE WITH UNPOWERED WEED-CUTTING PROVISIONS


Niels Alf Svensen, Avon, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed July 3, 1969, Ser. No. 838,820

Int. Cl. B63h 5/16

U.S. Cl. 115—0.5

26 Claims



A nonclogging marine grille which includes a plurality of rod members extending rearwards from the forward end in cantilevered fashion substantially the full distance across the water inlet opening in the direction of vessel travel and spaced to prevent the passage therebetween of harmful debris and shaped to cause debris to move therealong due to hydrodynamic forces acting thereagainst due to vessel motion. The rod members terminate short of the after end of the inlet and at a selected distance therefrom so that objectionable debris cannot pass through the gap between the rod member ends and the inlet surface but so that weeds which have draped across the rod members and passed aft free of the rod members may be ingested into the inlet or passed free thereof. The grille also includes a central stiffener member similarly shaped but extending across the full inlet opening length and projecting from the hull and outwardly of said rod members to prevent damage to the inlet grille during beaching and shallow water operations, and including weed cutters propelled by weed movement and hydrodynamic forces coacting therewith to cut any weeds which drape therearound and are passed to the after end thereof and which would otherwise clog the inlet.


3,580,211
METHOD OF SHAFT ALIGNMENT OF A MAIN ENGINE
 SHAFT IN SHIPBUILDING
 Hajime Kurashiki, Tokyo, and Yoshiharu Ikuta, Ichihara,
 Chiba, Japan, assignors to Mitsui Shipbuilding and En-
 gineering Co. Ltd., Tokyo, Japan

Filed July 16, 1969, Ser. No. 842,250
 Claims priority, application Japan, July 18, 1968,
 43/50996

Int. Cl. B63b 11/06

U.S. Cl. 115—0.5

1 Claim



A method of aligning the shaft of a main engine with the centerline of the propeller shaft in which the main bearing pins of the crankshaft are made hollow to permit sighting through the crankshaft and the bearings for alignment of all of the elements. The elements are aligned approximately by threading a piano wire through the elements and are more precisely adjusted by visual alignment after removal of the wire.


3,580,212
CONTROL AND MOUNTING SYSTEM FOR ELECTRIC
TROLLING MOTOR

Warren D. Fortson, P.O. Box 97, Sturgis, Miss.
 Continuation-in-part of application Ser. No. 771,766, Oct. 30,
 1968. This application Dec. 4, 1969, Ser. No. 882,189

Int. Cl. B63h 21/26

U.S. Cl. 115—18

13 Claims



An electric outboard motor assembly and storage housing therefor including remotely disposed power and steering controls. The storage housing is constructed in a manner whereby a battery for the electric outboard motor assembly may be received therein and a voltage control is mounted on the housing and operatively connected to the battery and electric motor of the outboard motor assembly for controlling the speed of operation of the electric motor. Further, the steering control for the electric outboard motor assembly includes a pair of selectively usable steering components, one of which is removably supported from the housing and receivable in the latter for storing and the other of which is mountable directly on the outboard motor assembly and is also receivable in the housing for storage. In addition, the second mentioned steering control is provided with its own voltage control whereby one hand operation of the electric outboard motor assembly may be accomplished when the motor is being steered by the second mentioned steering control.


3,580,213
SWIMMING PADDLES
 Melville J. G. Yuen, 1707 Wilhelmina Rise, Honolulu,
 Hawaii

Filed Oct. 6, 1969, Ser. No. 863,931

Int. Cl. B63h 16/04

U.S. Cl. 115—22.3

4 Claims



A shaft has oppositely extending offset portions at opposite ends, each portion being connected to a corresponding flotation paddle. Straps secure the shaft rotatably to a user in water. The user, using hands or feet, rotates the shaft to move the paddles and propel himself in the water. The paddles are lighter than water and act as floats as well as assisting in propulsion.


3,580,214
MARINE PROPELLER SHAFTS BEARING
ARRANGEMENTS
 Ernest Muller, c/o Messageries-Maritimes, AMP Building,
 Sydney, Australia

Filed Apr. 3, 1969, Ser. No. 813,115

Int. Cl. 308 4

U.S. Cl. 115—34

13 Claims



Marine propeller shaft bearing assemblies feature a double-walled stern tube which is extremely rigid in construction so as to be capable of resisting primary bending stresses before they can affect the shafting proper. The rigid stern tube permits extension for a considerable distance aft of the stern post of the vessel, thus enabling the positioning of propellers a more favorable distance from the hull to reduce vibration. The annular passage between the walls of the stern tube is utilized for the flow of cooling and lubricating fluids. The structure is applicable to single propeller shafts and counter-rotating propeller shafts.

3,580,215
BURGLAR ALARM
 Paul G. Karasman, 3846 W. 26th St., Chicago, Ill.
 Filed Mar. 27, 1969, Ser. No. 811,084

Int. Cl. G08b 13/08


U.S. Cl. 116—87

3 Claims

A warning device of the type intended to be utilized in connection with windows, doors and the like to give notice of unauthorized entry of the type comprising a body having means for securement to a frame adjacent the door or window and an arm hinged to the body and intended to overlie the door or the window with spring means interconnecting the arm and the body so that slight displacement of the arm causes rapid return movement thereof to the body. One of the arm or body has a striker element and the other of the

arm and body has means for receiving an audible signal means, such as a blank ammunition cartridge or the like so

elastically yieldable means forming an overcenter mechanism with the actuating element. Return means urge the actuating



that the rapid return movement will cause the striker element to engage the cartridge thereby causing the cartridge to fire.

3,580,216
APPARATUS IN A MACHINE TOOL FOR INDICATING
DISPLACEMENT EFFECTED BY A FEED SPINDLE
 Lorenz Weber, Sussen, Germany, assignor to Gebruder
 Boehringer Gesellschaft mit Beschränkter Haftung, Goppin-
 gen, Germany

Filed Sept. 24, 1968, Ser. No. 761,978


Claims priority, application Germany, Sept. 25, 1967,

B94645

Int. Cl. B23g 17/00

U.S. Cl. 116—115.5

3 Claims



The novel apparatus in a machine tool for indicating displacement effected by a feed spindle includes at least one counter counting the number of revolutions of a rotary actuator which is driven by the feed spindle through the intermediary of motion-transmitting means including a slip clutch or the like. The actuator is connected with a manually rotatable element such as a knob and, therefore, may be manually rotated independently of the feed spindle. If desired, two such counters may be provided counting in opposite sense, one in the additive sense and the other one in the subtractive sense.

3,580,217
MECHANICALLY ACTUATED WARNING DEVICE
 Jean Charles Joseph Blossé, and Michel Jean Joseph Blossé,
 48 Boulevard de General de Gaulle 95, Sannois, France
 Filed Nov. 29, 1968, Ser. No. 779,955


Claims priority, application France, Dec. 7, 1967, 131,294

Int. Cl. G10k 1/10

U.S. Cl. 116—169

12 Claims

Mechanically actuated warning device of the doorbell type. A hammer is caused to strike sound plates by means of a push piece having a cam portion which acts on an actuating element which is drivingly connected to the hammer through



element to a position of rest in which the hammer is in the vicinity of one of the sound plates.

3,580,218
APPARATUS FOR APPLYING A COATING OF
ADHESIVE MATERIAL ON TO A SUPPORT
 Friedrich Grundschober, Confignon, Geneva, and Joerg Sam-
 beth, Carouge, Geneva, both of, Switzerland, assignors to
 Aktiebolaget Stadex, Malmo, Sweden
 Filed Feb. 8, 1968, Ser. No. 704,138


Claims priority, application Switzerland, Feb. 2, 1967,

2039/67

Int. Cl. B44d 1/094, 1/44

U.S. Cl. 118—621

6 Claims



The invention provides an apparatus for applying a coating of adhesive material on to a support, e.g. a strip of paper. To apply this coating, one surface of the strip is fed over a guide surface through a fluidized bed of the adhesive material in cooled comminuted form, the bed particles which come into contact with said surface being caused to become fixed thereto.

3,580,219
INSECT INSPECTION CAGE
 Robert C. Stebbins, 601 Plateau Drive, Kensington, Calif.
 Filed Aug. 18, 1969, Ser. No. 850,863


Int. Cl. A01k 67/00

U.S. Cl. 119—1


4 Claims

A new and useful enclosure or cage for insects, such as fruit flies (Drosophila), which is especially constructed and adapted to accommodate a colony of such insects, and to provide for such colony, an environment in which the insects may reside and multiply, and in which the insects may be subjected to experimental controls in various manners as may be desired. The enclosure or cage has at least one transparent wall, whereby the insects may be viewed, studied, counted, photographed, and otherwise observed and recorded.

The enclosure or cage has a portion into which the insects may be herded, by movement of a pistonlike wall or walls, and which has a dimension in one direction which provides accommodation for only one layer of insects in that direction, whereby all of the insects in the enclosure or cage are disposed substantially in a common plane and are thus



underlying relation to the shell, the screen being adapted to contact the animal's back. A seal is positioned around the outer edge of the shell so that upon introduction of vacuum



pressure in the space between the shell and screen, sufficient suction force can be maintained. The vacuum maintains contact between the animal and the supporter when hoists lift the supporter and animal.

3,580,222

APPARATUS FOR HOLDING PETS

Jane M. Dunn, 2113 N. Pacific Ave., Santa Cruz, Calif.

Filed July 14, 1969, Ser. No. 841,410

Int. Cl. A61d 03/00

U.S. Cl. 119-102

6 Claims

located immediately adjacent to a transparent wall, and, more specifically, between such wall and a source of light, which may be daylight or photoflash, in such manner as to permit photographic images or shadowgraphs of the mass of insects, so disposed, to be readily made for subsequent examination and counting.

3,580,220

SMALL ANIMAL-MILKING APPARATUS


Allen D. Cook, Philadelphia, and Kalman T. Szabo, Ambler, Pa., assignors to Smith, Kline & French Laboratories, Philadelphia, Pa.

Filed Aug. 20, 1969, Ser. No. 851,678

Int. Cl. A01j 03/00, 05/00

U.S. Cl. 119-14.01

10 Claims



A milking machine for rats or the like having a cage for holding the rat in a suckling position with its teats exposed and means for applying a suction to a plurality of cups which are adapted to receive teats or nipples of the rat. A valve means controls the application of suction to any desired number of cups and the suction is controlled to be provided intermittently by means of a pulsator.

3,580,221

VACUUM SUPPORT FOR ANIMALS

Theodore A. Noyes, 320 Dunn St., Bryan, Tex.

Filed Oct. 31, 1969, Ser. No. 872,980

Int. Cl. A01k 29/00, 67/00

U.S. Cl. 119-96

8 Claims

A vacuum supporter, including a rigid shell, shaped in the contour of an animal's back. A screen is attached in spaced

Apparatus for holding a dog or small animal in position during grooming provided with two cords having loops at the lower ends thereof for attaching to different parts of the animal. The upper parts of these cords are attached to spring-loaded reels which are supported on a shaft in a frame which is adapted to be attached to the ceiling of the dog grooming parlor. The reels are provided with members cooperating with a latch which is adapted to lock the reels in predetermined position after the looped parts of the cords are placed on the animal to hold it in grooming position. The latch is controlled by a manually operable cord attached thereto. A hook member is provided to the latch and this is adapted to be received by a locking device when the hook member is inserted therein by exerting pulling effort on the cord. Exerting further pulling effort on the cord serves to release the hook member from the locking device, thereby disengaging the latch and permitting rotation of the reels.

3,580,223

METHOD AND APPARATUS FOR OPERATION OF A POSITIVELY DRIVEN STEAM GENERATOR WITH ROLLED OVERLAP AND GASTIGHT WELDED VAPORIZER WALLS

Klaus Knizia, Nochen Uber, Engelskirchen, Germany, assignor to L. & C. Steinmuller G.m.b.H., Gummersbach, Germany

Filed Apr. 24, 1969, Ser. No. 819,013


Int. Cl. F22b 29/06

U.S. Cl. 122-1

2 Claims

A method of and arrangement for operating a steam generator with forced circulation and with circulation overlap and gastight welded evaporator walls, in which saturated steam freed in a separator vessel is conveyed not only to suc-

ceeding superheaters, but also through a withdrawal conduit and a control valve to a heat exchanger preceding the steam generator or its evaporator, and in which the said saturated



3,580,224

GAS-OPERATED WATER HEATER

James Rouet, Bois-Colombes, and Roger Vignes, Paris, France, assignors to Service National dit. Gas De France, Paris, France


Filed Aug. 6, 1969, Ser. No. 856,232

Claims priority, application France, Aug. 9, 1968, Dec. 5, 1968, 162,566; 176,864

Int. Cl. F22b 7/04

U.S. Cl. 122-16

20 Claims



A gas-operated water heater has a peripheral water tank surrounded by a thermally insulated jacket. A cavity within the peripheral tank contains a central water tank and an annular flue is defined between the two tanks. A burner and a pilot light are situated beneath the tanks the fumes from the burner passing through the annular flue and the fumes from the pilot light passing through a flue in the central tank. The tanks are in fluid connection and cold water may be fed to them and hot water drawn off.

3,580,225

ECONOMIZER

John W. Coy, Exton, Pa., assignor to Coy Oil Co., Inc., Exton, Pa.

Continuation-in-part of application Ser. No. 798,406, Feb. 11, 1969, now abandoned. This application Nov. 24, 1969, Ser. No. 879,355


Int. Cl. F22b 33/00; F28f 9/02

U.S. Cl. 122-20

13 Claims

A heating system having a furnace with a flue and a chimney in communication with the flue for venting combustion

gases to the atmosphere is provided with an economizer heat exchanger intermediate the flue and the chimney for extracting an additional quantity of heat from the combustion gases to improve the efficiency of the heating system. The economizer comprises a horizontally disposed cylindrical shell mounting a bank of tubes adjacent its bottom and having an inlet chamber at one end connected to the flue and an outlet chamber at its other end connected to the chimney, the chambers being in communication with one another through the tubes. The tubes are supported at their ends and



they are spaced apart by means of walls extending across the shell, the walls forming therebetween a cavity through which fluid is flowed upwardly across the tubes for extracting heat therefrom as the combustion gases flow through the tubes. A fan is mounted in the outlet chamber for inducing the gases to flow through the tubes and out the chimney, the fan having a greater capacity for removing the gases than the furnace has for producing them. In addition, means is provided to regulate the pressure in the combustion chamber of the furnace, the pressure being reduced below atmospheric due to the operation of the fan.

3,580,226

STEAM GENERATOR USING GAS RECIRCULATION


Samuel S. Blackburn, Jr., Avon, and Earl K. Rickard, East Granby, Conn., assignors to Combustion Engineering, Inc., Windsor, Conn.

Filed Dec. 4, 1969, Ser. No. 881,986

Int. Cl. F22g 5/06; F23j 5/02

U.S. Cl. 122-235

4 Claims



A steam-generating unit using gas recirculation for steam temperature control, where the recirculated gases are introduced into the furnace through the ash hopper. A liquid seal inside the ash hopper is used to control flow of recirculated gases.

3,580,227

BOILER INLET PLUG INSERT WITH HEAT DAMS

Alfred Koestel, Nogales, Ariz. assignor to The United States of America as represented by the Secretary of the Air Force

Filed Feb. 5, 1970, Ser. No. 8,797


Int. Cl. F22b 37/34

U.S. Cl. 122-406R

5 Claims

A device for eliminating the thermal instability of a liquid in forced feed convection boilers in which subcooled liquids which are introduced at the inlet have a tendency to superheat and flash into vapor to produce liquid slugs which are discharged at the outlet with the dry or superheated vapor. The invention is a rod-or sleeve-type insert located in the heating coils which produces liquid flow damping and controls the liquid superheating, and incorporates a nucleation device or devices disposed axially along the direction of

liquid flow and introduces heat dams at the nucleation sites created by vapor from the heated site to prevent the liquid clutch is held to a minimum by an auxiliary actuating mechanism which automatically moves the clutch into the



being heated from entering the nucleation site and flashing into vapor.


3,580,228

OSCILLATING INTERNAL COMBUSTION ENGINE
Octavio Rocha, Ave Tecnologias Sur #600, and Serafin Cano, Via Asinaria #315 Col. Fuentes del Valle, Monterrey, Mexico

Filed May 20, 1969, Ser. No. 826,151
Int. Cl. F02b 53/00

U.S. Cl. 123-18

9 Claims



The invention hereinafter disclosed is a power unit which includes an internal or external combustion engine having an annular cylinder, arcuate pistons which oscillate in that cylinder and improved mechanism for translating the power developed in the engine to a shaft to be driven. The engine may be supplied with fuel either by injection or carburetion or by steam or fluid or gas under pressure and the arrangement is such that vibrations due to explosions of the fuel mixture or of power strokes are minimized and the output shaft is powerfully driven at uniform speed.

3,580,229

METHOD AND MEANS FOR SWITCHING ON AND OFF THE FAN WHEEL OF A REGULATING FAN
Michael May, Stuttgart-Berg, Germany, assignor to Fichtel & Sachs AG, Schweinfurt am Main, Germany

Filed Feb. 25, 1969, Ser. No. 802,093

Claims priority, application Germany, Mar. 1, 1968, P 16 26 008.5


Int. Cl. F01p 7/02; F16d 7/00, 19/00

U.S. Cl. 123-41.12

8 Claims

The cooling fan of an internal combustion engine is driven through a temperature-controlled clutch. Slipping of the

fully engaged or the fully disengaged position as soon as it has been moved by a thermostat into an intermediate position. Several examples of clutch arrangements are given.



3,580,230

AIR-COMPRESSING INJECTION-TYPE INTERNAL COMBUSTION ENGINE WITH EXTERNALLY CONTROLLED IGNITION AND QUALITY REGULATION
Heinrich Hoffmann, Stuttgart-Gerokruhe, and Wilhelm Wagner, Stuttgart-O, Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart-Unterturkheim, Germany


Filed Oct. 3, 1968, Ser. No. 764,734

Claims priority, application Germany, Oct. 5, 1967, P 15 76 008.4

Int. Cl. F02b 19/10

U.S. Cl. 123-32SPA

23 Claims



An air-compressing internal combustion engine with externally controlled ignition and quality regulation which includes an at least approximately axially symmetrical combustion space arranged in the piston, in which an air rotary movement about the combustion space axis is present toward the end of the compression stroke, and which includes an injection system which injects fuel against the wall of the combustion space approximately in the direction of the air movement and approximately tangentially with a nonnegligible free length of the jet so that the fuel thus injected into the piston combustion space flows along the walls thereof; an auxiliary combustion space is arranged in the cylinder head which includes an injection nozzle and an ignition source whereby the auxiliary combustion space has the shape of an approximately semispherically shaped recess containing about 5 to 20 percent of the entire combustion space volume; the auxiliary combustion space is arranged within the area of a circumferential place of the piston combustion space while the injection nozzle is so arranged and constructed in the auxiliary combustion space that in addition to the partial fuel quantity injected into the piston combustion space a further partial fuel quantity is injected obliquely against the wall parts of the auxiliary combustion space.

3,580,231

VALVE MECHANISMS FOR USE WITH INTERNAL COMBUSTION ENGINES
Cyril Henry Bradbury, London, England, assignor to Simms Group Research and Development Limited, London, England


Filed Feb. 11, 1969, Ser. No. 798,378

Claims priority, application Great Britain, Feb. 14, 1968, 7,251/68

Int. Cl. F02m 67/00

U.S. Cl. 123-32

10 Claims



An internal combustion engine has a main cylinder and piston for receiving part of the main charge of combustible mixture for operating the engine, a subsidiary cylinder interconnected with the main cylinder by a passage, a valve controlling the passage so that part of the charge in the main cylinder passes into the subsidiary cylinder during the compression stroke of the main piston, a subsidiary piston in the subsidiary cylinder for increasing the compression of the part of the charge in the subsidiary cylinder, an additional fuel inlet to the subsidiary cylinder and a control mechanism for operating the valve, subsidiary piston and fuel inlet in timed relation.

3,580,232

ENGINE EXHAUST RECIRCULATION
Jorma O. Sarto, Orchard Lake, Mich., assignor to Chrysler Corporation, Highland Park, Mich.



Division of Ser. No. 807,706, Mar. 17, 1969

Filed June 18, 1970, Ser. No. 47,488

Int. Cl. F02n 25/06

U.S. Cl. 123-119

7 Claims



Controlled recycling of automobile exhaust gases through a bypass conduit connecting the exhaust system and the fuel

and air inlet system is accomplished during various engine-operating conditions by means of a venturi in the exhaust system at its connection with the bypass conduit, and also by means of a pitot-type opening of the bypass conduit into the inlet system, the dimensions and arrangement of the venturi and pitot opening being determined to effect a reverse flow of either fresh air or a fuel-air mixture into the exhaust system (depending on the location of the pitot opening upstream of downstream of the fuel supply into the inlet system) thereby to enhance complete combustion of the exhaust gases within an exhaust reactor in the exhaust system.

3,580,233


DEVICE FOR MIXING COMBUSTIBLE COMPONENTS RECOVERED FROM EXHAUST GASES WITH FUEL CHARGE OF CARBURETOR
Ewald A. Busse, Redwood City, Calif. (151 E. St. Auburn, Calif. 95603)

Filed July 25, 1969, Ser. No. 844,977

Int. Cl. F02m 25/06

U.S. Cl. 123-119A

3 Claims



A device for mixing combustible components recovered from the exhaust gases of an internal combustion engine with the fuel charge of a carburetor, the device being connected to the carburetor and the intake manifold, the recovered combustible components and disposed above the fuel charge being thoroughly intermixed before they reach the manifold. This device is used in conjunction with the apparatus for utilizing exhaust gases of an internal combustion engine, muffler and spark arrestor shown in my U.S. Pat. No. 3,435,810.

3,580,234

TOY GUN WITH STRETCHABLE DIAPHRAGM
Reynolds W. Guyer, Jr., Mendota Heights, and Wilbert A. Kruse, St. Louis Park, Minn., assignors to said Krause assignor to said Guyer d/b/a Winsor Concepts, Minneapolis, Minn.

Filed Nov. 29, 1968, Ser. No. 779,946

Int. Cl. F41b 7/08

U.S. Cl. 124-21

7 Claims



A toy gun having an elongated tube with a balloon secured over the rear end of the tube and a handle secured adjacent

the front end of the tube so that when the handle is held in one hand the balloon may be grasped by the other hand to be stretched and then released to propel a projectile deposited in a balloon. The handle has finger grooves therein to minimize the gripping force necessary to hold the handle.

3,580,235

MANUFACTURE OF SLATES

Lazio Lombos, Llandudno Junction, and Michael Robert Hughes, Old Colwyn, North Wales, assignors to The Dinorwic Slate Quarries Company, Limited, Port Dinorwic, Caernarvonshire, Wales


Filed July 22, 1968, Ser. No. 746,579

Claims priority, application Great Britain, Aug. 1, 1967, 35,259/67

Int. Cl. B28d 1/18, 1/32

U.S. Cl. 125—3

7 Claims



A slate-chamfering machine is disclosed which comprises at least one rotatably drivable cutting tool, the machine being adapted to present at least one edge of a substantially rectangular slate to the cutting tool, and feeding means for effecting relative movement between the cutting tool and the slate in a direction substantially parallel to the axis of rotation of the tool when the slate is presented to the tool, whereby the whole length of said edge may be roughly chamfered to achieve a "naturally broken" finish.

3,580,236

HEAT RADIATOR AND BURNER WITH ADJUSTABLE CONNECTION TO GAS SUPPLY LINE


Calvin C. Plummer, Box 333, Hastings, Mich.

Filed Oct. 10, 1969, Ser. No. 865,361

Int. Cl. A01g 13/06

U.S. Cl. 126—59.5

5 Claims



A hollow cylindrical radiator standing on end has a tubular burner extending transversely through its lower end. One end of the burner tube has a telescopic and slidably adjustable fit with a tee connector in a flexible fuel supply pipe. The stem of the tee is split to yieldably grip the end of the burner tube, and opens around the exterior of the crossmember of the tee.

The end of the burner tube adjusts axially toward closing engagement with the exterior of the crossmember to adjust the air opening into the base of the tee and the end of the burner tube.

3,580,237

AIR HEATER

Alan Barsby, Lea Meadows, Gainsborough, England, assignor to Marshall Sons & Company Limited, Gainsborough, Lincolnshire, England


Filed Feb. 4, 1969, Ser. No. 796,532

Claims priority, application Great Britain, Feb. 8, 1968, 6194/68

Int. Cl. F24h 3/12

U.S. Cl. 126—110

9 Claims



This invention relates to an air heater comprising a combustion chamber, means to supply air and a combustible fuel to the combustion chamber, an exhaust for the products of combustion from the combustion chamber, a first duct connecting the combustion chamber to the exhaust, an inlet and an outlet for air to be heated, a second duct interconnecting the inlet and outlet, said second duct surrounding the combustion chamber for part of its length and for a different part of its length being parallel to, and sharing a common boundary with, said first duct, to define a thermal regenerator, the thermal regenerator comprising a plurality of heat transfer discs extending through said common boundary into both ducts, and means to rotate each disc about its axis of symmetry.

3,580,238

AUTOMATIC DAMPER MEANS


Charles G. Diehl, North Little Rock, Ark., assignor to Save Fuel Corporation, Tunica, Miss.

Filed June 4, 1969, Ser. No. 830,431

Int. Cl. F23l 3/00

U.S. Cl. 126—295

8 Claims



An automatic damper for use in the exhaust flue of combustion devices such as furnaces and the like to prevent undesirable loss of hot or cold air out the flue during periods when no combustion is taking place and to assure that no combustion can take place unless and until the flue is open or unrestricted. The damper has a rotatable damper plate normally biased to a closed position for preventing flow com-

munication through the flue, motor means which when energized move the damper plate to an alternate open position to allow substantially unrestricted communication through the flue, and switch means connected in a circuit with the means that supply fuel to the combustion means, said switch means being closed when the damper plate moves to its open position to enable a combustion cycle to take place.

3,580,239

METHOD AND APPARATUS FOR IN VIVO POTENTIOMETRIC MEASUREMENTS


Hideo Watanabe, and John E. Leonard, Fullerton, Calif., assignors to Beckman Instruments, Inc.

Filed Oct. 3, 1969, Ser. No. 871,077

Int. Cl. A61b 5/04

U.S. Cl. 128—2.1R

4 Claims



A biomedical electrode assembly for detecting electrical signals from a living subject. The electrolyte reservoir of the assembly is divided into two separate sections by a dialysis membrane. The section which is in contact with the skin of the living subject contains an electrolyte which will not irritate the skin while the other section of the electrolyte reservoir contains an electrode component and an electrolyte which cooperates with the component to produce a constant, known reference voltage. The first mentioned electrolyte is preferably isotonic saline solution and the second electrolyte is at least 3 molar potassium chloride solution.

3,580,240

DISPOSABLE ELECTRODE WITH SELF-SEALING PLUG OUTLET


Louis Ciro Cosentino, West Paterson, N.J., assignor to Hoffman-La Roche Inc., Nutley, N.J.

Filed Jan. 17, 1969, Ser. No. 792,038

Int. Cl. A61b 5/04

U.S. Cl. 128—2.06

5 Claims



In an electrode apparatus for use in deriving electrical signals from an animal or human subject including a disposable interface unit and a reusable electrode plug unit where the disposable interface unit comprises: a unitary fabricated nonconductive member having a reservoir adapted to contain a viscous electrolyte, and outlet means extending from the reservoir to an upper surface of the member including a self-sealing closure means adapted to detachably receive the electrode plug when inserted therein.

3,580,241

CARDIOGRAPHIC APPARATUS WITH STYLUS CONTROL MEANS


Berel Weinstein, New York, N.Y., assignor to Bio-Medical Sciences, Inc., New York, N.Y.

Filed Aug. 8, 1968, Ser. No. 751,078

Int. Cl. A61b 5/04

U.S. Cl. 128—2.06

7 Claims



An electro- or phonocardiographic apparatus including a transducer adapted to convert the electric changes or sounds associated with the activity of the heart into corresponding graphic readings. A writing surface is provided and a stylus driven by a reversible servomotor is adapted to write on the surface. A first transistor switch connects the transducer with the motor so that the position or movement of the stylus is indicative of the heart activity as received by the transducer. A second transistor switch connects for restoring the stylus to a null position in the absence of a signal from the transducer.

3,580,242

FETAL SCALP ELECTRODE UNIT


George E. La Croix, 695 Vaughan Road, Bloomfield Hills, Mich.

Filed Apr. 1, 1968, Ser. No. 717,529

Int. Cl. A61b 5/04


U.S. Cl. 128—2.06

3 Claims




An electrode or lead unit for monitoring fetal heartbeat is disclosed which includes, in the illustrated embodiment, three electrical leads having jack connector ends to be plugged into female terminal sockets of an electrocardiogram-type recording device or audio visual or other sensing device. One of these is a ground lead electrically connected directly to an elongated, sleeve-like plastic grounding sheath which internally receives the other two positive and negative electrode leads. One of the latter terminates externally of an inner end of a terminal shield of the sheath, being formed as a small pointed and barbed, relatively rigid and nonbendable penetrating electrode element, a single element similar to a fishhook, which is lightly embedded in the scalp or another skin area of the fetus during the monitoring period. The other of the positive and negative electrodes is in encircling relation to a shank part of the penetrating element. The relationship of components is such that the sheath unit make continuous grounding contact with the vaginal mucosa, so as to afford a clear tracing on the recording device throughout the period of use.

3,580,243
MEANS AND METHOD FOR SUBTRACTING DC NOISE
FROM ELECTROCARDIOGRAPHIC SIGNALS
 Gilbert A. Johnson, Milwaukee, Wis., assignor to Marquette Electronics, Inc., Milwaukee, Wis.
 Filed Oct. 21, 1968, Ser. No. 769,314
 Int. Cl. A61b 5/04
 U.S. Cl. 128—2.06B
 6 Claims



The electrocardiographic signal and a DC noise level are applied to a first of two input terminals to a differential amplifier and the output of the differential amplifier supplies the electrocardiographic signal to an output terminal without the DC noise level. To offset the DC noise level, a feedback loop from the output terminal to the second input terminal of the differential amplifier includes a sample and hold circuit that first applies the output from the differential amplifier through a nulling amplifier to a capacitor and then applies the potential on the capacitor to the second input terminal of the differential amplifier.

3,580,244
THERAPEUTIC DEVICE OSCILLATING DEVICE
 Mary E. Graves, 4101 Providence Rd., Charlotte, N.C.
 Filed Mar. 20, 1969, Ser. No. 808,828
 Int. Cl. A61h 1/02
 U.S. Cl. 128—25A
 5 Claims




A therapeutic device used to relieve and prevent heel cord contractures, including a foot-supporting plate member pivotally mounted about a laterally extending axis located substantially beneath the ankle joint of the supported foot, and including a reciprocating hydraulic motor connected to the plate member to cause oscillation thereof. They hydraulic circuit for operating the motor includes a shiftable reversing valve that is selectively operable to control the angular extent of the plate member oscillations, and includes selectively adjustable flow control valves for regulating the speed of oscillation of the plate member. Additionally, the hydraulic circuit may include a selectively adjustable pressure relief valve for controlling the force applied to the supported foot by the plate member.

3,580,245
VIBRATORY MASSAGING DEVICE
 Onnie R. Dill, 10301 Hasley Place, Oklahoma City, Okla.
 Filed Feb. 3, 1969, Ser. No. 796,077
 Int. Cl. A61h 1/00
 U.S. Cl. 128—33
 8 Claims


Massaging apparatus which is capable of more effectively distributed vibratory motion, the apparatus consisting of a

frame constructed of expanded metal and having a vibratory element securely affixed thereto, with a resilient padding




overlying the frame structure and with a decorative outer cover removably disposed thereover.

3,580,246
MOTOR OPERATED VIBRATOR HAVING SOLAR TYPE MOTION
 Dave O. Foreman, 606 E. Broadway, Andrews, Tex.
 Filed Nov. 22, 1968, Ser. No. 778,255
 Int. Cl. A61h 1/00
 U.S. Cl. 128—36
 3 Claims



Motor driven apparatus, for inducing vibratory action into a person's body, comprised of a housing having a shaft rotatably journaled therein by spaced apart bearing means. Spaced apart eccentric weights placed near each bearing means and rigidly affixed to the shaft induces a circular vibratory motion in the extremities of the housing while the center of the housing remains relatively quiescent. A motor located apart from the housing rotatably drives the shaft by means of a flexible coupling member.

3,580,247
HYDROTHERAPEUTIC DEVICE
 Richard C. Schneider, 701 N.E. 23rd Terrace, Pompano Beach, Fla.
 Filed Sept. 12, 1968, Ser. No. 759,433
 Int. Cl. A61h 9/00, 33/02
 U.S. Cl. 128—66
 9 Claims




A hydrotherapeutic unit to be permanently installed with a bathtub or tank. The unit includes a manifold mounted on

the end wall of the tub and the manifold defines a water supply chamber and a return chamber. A pair of conduits extend through the end wall of the tub on opposite sides of the waste valve operating mechanism and one conduit establishes communication between the supply chamber and the discharge side of a pump located outside of the tub, while the second conduit establishes communication between the return chamber and the suction side of the pump.


A nozzle assembly is located within the tub and is connected to the supply chamber so that water discharged by the pump is delivered to the supply chamber and then ejected under high pressure from the nozzle assembly within the body of water in the tub. The water is recirculated from the tub through the return chamber to the pump.

3,580,248
BI-VALVED CAST
 Leighton W. Larson, P. O. Box 202, Waconia, Minn.
 Filed Dec. 2, 1968, Ser. No. 780,335
 Int. Cl. A61f 5/04
 U.S. Cl. 128—89
 8 Claims




A cast for immobilizing broken limbs which includes a pair of bivalved shells, an inflatable liner in each of the shells, an absorbent liner or padding, and means for releasably securing the bivalved shells together. The cast is reusable, permits convenient visual inspection of the broken limb without destruction of the cast, and provides for adjustment of the volume of the inside cavity and the pressure on the immobilized limb through adjustment of the inflatable liners.

3,580,249
AEROSOL NEBULIZERS
 Kentaro Takaoka, Avenida Bosque de Saude No. 519, Sao Paulo, Brazil
 Filed Sept. 16, 1968, Ser. No. 759,850
 Int. Cl. A61m 11/02
 U.S. Cl. 128—194
 1 Claim




This invention relates to nebulizers designed to introduce aerosols into the respiratory systems of persons suffering from respiratory ailments.

3,580,250
OXYGEN GENERATORS
 August Oroza, Santa Ana, Calif., assignor to U.S. Divers
 Filed Mar. 14, 1969, Ser. No. 807,358
 Int. Cl. A62b 7/08
 U.S. Cl. 128—203
 14 Claims



An Oxygen Generator which may be used for emergency purposes generally comprising an elongated housing for the receipt of a material which when burned produces a gas having a substantial amount of oxygen, said housing having a check valve permitting the release of the gas therefrom into a conduit connected to flexible tubing; said flexible tubing being connected to a plenum bag which feeds a face mask attached to a removable cover of the housing; said cover having a lanyard which releases hammers to fire percussion caps adjacent the oxygen-producing material of the container upon removal of said cover.


3,580,251
SELF-INJECTABLE AMPUL
 Raymond Guiriec, Bourron-Marlotte, France, assignor to Societe a Responsabilite Limitee Laboraver, Longjumeau, France
 Filed Apr. 11, 1969, Ser. No. 815,341
 Claims priority, application France, Apr. 12, 1968, 148,075
 Int. Cl. A61m 5/00
 U.S. Cl. 128—220
 7 Claims



A self-injectable ampul comprises an ampul containing medication and sealed by a penetrable plug. A hollow needle sharpened at both ends carried by the ampul penetrates the plug, and upon continued inward movement severs the plug and carries the plug with it as a piston to eject medicant from the opposite end of the needle. The needle has an external collar mounted between the middle and the inner end thereof. A sleeve extends outwardly from the plug, surrounds substantially one-half the length of the needle, has a bore adjacent to the plug, adapted to receive a portion of the needle, and a counter bore for the remainder thereof having a diameter sufficient to receive the collar. A second sleeve having an external diameter such that its inner end can enter the counter bore in the first sleeve and an internal diameter for receiving the needle has finger pieces extending radially outwardly therefrom at the outer end portion thereof. A sleeve extension surrounds the remainder of the needle and is removably attached to the outer end of the second sleeve. When the ampoule and the finger pieces are moved toward each other, the inner end of the second sleeve engages the collar and advances the needle so that the inner end thereof passes through the penetrable plug. The plug has a circular line of weakness so that the plug can be made to enter the ampoule and discharge the medication therefrom.

3,580,252 SANITARY TOWEL

Pierre A. Delort, 12, Avenue Marchal Foch, Nice, France
Filed Apr. 1, 1969, Ser. No. 812,236
Claims priority, application France, Feb. 20, 1969, 6,904,588
Int. Cl. A61f 13/16
U.S. Cl. 128—290 4 Claims



The invention covers a sanitary article constituted by a slip inside which is secured an absorbent lining for women's hygienic and medical purposes, said lining being constituted by superposed layers of fabric the size of which layers decreases in all directions from the outermost layer towards the innermost layer, said fabric being made at least partly of synthetic fibers welded together at a raised temperature.

3,580,253 SANITARY NAPKIN AND FLUSHABLE WRAPPER THEREFOR


Leo J. Bernardin, Appleton, Wis., assignor to Kimberly-Clark Corporation, Neenah, Wis.
Filed Dec. 9, 1968, Ser. No. 782,479
Int. Cl. A61f 13/16

U.S. Cl. 128—290 15 Claims
A flushable pad wrapper for sanitary napkins comprising a nonwoven web of cellulosic fibers in which the fibers are bonded together by sodium carboxymethylcellulose acidified to a pH of between 2.2 to 2.0. This wrapper has sufficient wet strength and abrasion resistance to perform satisfactorily in normal use but disintegrates readily when immersed and agitated in water.

3,580,254 BANDAGE CONTAINING A MEDICINAL MATERIAL AND METHOD OF USING

Henry P. Stuart, 821-32nd Ave., Seattle, Wash.
Filed July 13, 1967, Ser. No. 653,181
Int. Cl. A61f 7/02


U.S. Cl. 128—268 3 Claims



A bandage for covering a break in the skin such as a cut, a scratch or a tear. The bandage contains a medicinal material which may be released and activated after the bandage has been applied to the break in the skin. The medicinal material is contained within a capsule which is ruptured after the bandage is applied.

3,580,255 ASPIRATOR

Hugo S. Cimber, 22 Seven Gables Road, Staten Island, N.Y.
Filed Apr. 8, 1968, Ser. No. 719,659
Int. Cl. A61m 1/00
U.S. Cl. 128—276 8 Claims




A disposable, sterilizable aspirator for removal of body fluids comprising a hollow needle which is mounted for axial movement within a support chamber, and is movable out of the chamber for a limited distance to penetrate a body cavity containing fluid which is to be collected. The needle may be spring-loaded. After the needle is in the body cavity, fluid may be withdrawn by connecting a syringe to the free end of a tube connected to the needle, or by a catheter passed through the hollow needle. The needle may be double-ended to penetrate a sealable diaphragm within the support chamber so that the fluid volume to be collected will be collected and covered by the diaphragm after the instrument is removed from its operating position. A bent wire can be inserted in the catheter tube to cause the tube to deflect as it leaves the end of the catheter tube.

3,580,256 PRE-TIED SUTURE AND METHOD OF SUTURING

Jack E. Wilkinson, 2411 Divisadero, Fresno, Calif., and Victor G. Tahan, 1350 S. Orange Ave., Fresno, Calif.
Filed June 30, 1969, Ser. No. 837,590
Int. Cl. A61L 17/00

U.S. Cl. 128—335.5 8 Claims



A surgical suture or the like including a pair of butterfly-loops secured in superimposed registering relation by a casing through which the loops are visible, and a pair of tails extending from the loops. A suturing method wherein one of the tails is used as a suture which pierces the tissue to be sutured and is passed through the superimposed loops, the tails then being pulled tight to convert the interlooping formation into a square knot.

3,580,257 WEED SEED COLLECTOR FOR A THRESHER COMBINE

Earl E. Teague, Rte. 1, Box 92, Dermott, Ark.
Filed Dec. 24, 1969, Ser. No. 887,840
Int. Cl. A01f 12/42

U.S. Cl. 130—24 5 Claims
Apparatus mounted on a threshing machine or combine for removing and collecting weed and other obnoxious seeds during the threshing operation so that such seeds are not dis-

3,580,259 TOBACCO FLAVORING

Werner Richard Gotthard Luttich, Willersweg 341, Hamburg-Langenhorn, Germany
Filed Sept. 6, 1968, Ser. No. 758,144
Int. Cl. A24b 03/12, 15/08


U.S. Cl. 131—144 2 Claims

A method of influencing the smoke flavor of a tobacco by adding to the unsmoked tobacco a flavoring material which occurs in the smoke of natural tobacco, in which the flavoring material is a 2,5 - substituted pyrrole in which the 2 - substituent is selected from the group comprising; hydrogen, methyl -, and ethyl -, and the 5 - substituent is selected from the group comprising; formyl, acetyl, propionyl, carbomethoxy, carboethoxy, methylglyoxyl, ethylglyoxyl, and propandione - 1, 2 l - l, the material being added in a quantity between 10 and 500 ppm.

3,580,260 ASHTRAY STRUCTURE

Robert D. Moore, 8124 Lockheed, Houston, Tex.
Continuation-in-part of application Ser. No. 773,994, Nov. 7, 1968, now abandoned. This application July 17, 1969, Ser. No. 847,782
Int. Cl. A24f 19/02, 19/14

U.S. Cl. 131—242 3 Claims




Ashtray structures having large containers to receive the ashes and butts of cigarettes, and the like, wherein the container lid is supported inside of the container wall so that the lid is not dislodged when the container is lifted, the lid having a downwardly and inwardly sloping surface having cigarette supporting notches in an upwardly extending rim located at its lower edge for supporting cigarettes safely, the lid having an opening of limited size therethrough disposed to prevent ashes from blowing from the container. In some forms, snubbers are provided adjacent the ash and butt receptacle space.

3,580,261 PRINTING SCREEN CLEANER


John W. Key, 606 Ironwood Drive, Arlington Heights, Ill.
Filed May 12, 1969, Ser. No. 823,760
Int. Cl. B08b 3/02, 15/02

U.S. Cl. 134—104 11 Claims



Printing screens are carried through a tunnel by an overhead conveyor. In an enlarged central section of the tunnel

tributed and replanted in the field. The apparatus includes a transverse conveyor mounted on the rear of the combine and




located at the discharge position of larger separated tailings, an inclined conveyor and a hopper into which the seeds and tailings are discharged.

3,580,258 COMBINE

Clark E. Stroborg, and Eldon L. Stroborg, Blockton, Iowa
Filed Feb. 5, 1969, Ser. No. 796,749
Int. Cl. A01f 12/48


U.S. Cl. 130—27HF 5 Claims



An airflow system for a combine harvester to more effectively float and carry away the straw and chaff and thus increase the efficiency of the separating and cleaning mechanism which includes strawwalkers and a cleaning shoe as is well known. This invention is designed for combines using a concave grate in relation to the threshing cylinder and includes air intake fans mounted to opposed sides of the housing to induce and direct a flow of air upwardly through the grate and over the strawwalkers and out of the machine at the rear and also over the conveyor below the grate rearwardly up the trough below the strawwalkers and then upwardly through the walkers to float the chaff and straw without preventing the heavier grain on the conveyor from reaching the cleaning shoe or the grain on the walker from falling through the openings therein onto the trough for delivery by gravity to the cleaning shoe mechanism. Preferably, two opposed streams of air are generated which impact intermediate the grate and the conveyor whereby a portion of the deflected airstream passes upwardly through the grate, over the strawwalkers and out of the rear of the machine with the rest of the deflected airstream passing up the trough, then upwardly through the strawwalkers and out of the machine at the rear. The speed of such fans may be selectively varied and likewise control means are provided for the volume of intake air.


are opposed rows of spray heads to direct a cleaning solvent at the screens under pressure. A solvent with material removed from the screens drains into a removable separating tray to extract at least a portion of the material from the solvent. The solvent then drains into a sump from which it is pumped back to the spray heads. At opposite ends of the central cleaning section are entrance and exit sections having doors which are pushed aside by the screen as it is moved through the tunnel. A fan draws air in from the ends of the tunnel and discharges it out a stack. Fire quenching means has spray heads in the tunnel.

3,580,262
UMBRELLA HANDLE CARRYING STRAP ASSEMBLY
Heinz Weber, Hilden, Germany, assignor to Telesco Brophy Limited, Montreal, Quebec, Canada
Filed Apr. 30, 1969, Ser. No. 820,603
Claims priority, application Germany, May 31, 1968, P 17 57 674.8
Int. Cl. A45b 11/00
U.S. Cl. 135-20 7 Claims




An umbrella handle having a handle gripping portion and a snap-lock cover, and a flexible carrying strap connected to the handle underneath the cover and extending therefrom.

3,580,263
PRESSURE LIQUID LEVEL INDICATOR
Walter D. Hughes, Richmond, Calif., assignor to Chevron Research Company, San Francisco, Calif.
Division of Ser. No. 650,745, July 3, 1967, Pat. No. 3,498,320
Filed June 11, 1969, Ser. No. 870,865
1969, Ser. No. 870,865
Int. Cl. F17d 3/00
U.S. Cl. 137-2 2 Claims




A sensor member for use in a liquid level control system for maintaining a predetermined liquid level within a vessel composed of at least two elements formed of materials of different specific gravities adapted to angularly rotate in response to deviations of the controlled liquid relative to an established elevational set-point level coincident with the location of the sensor member.

3,580,264
FLUIDIC DEVICE
Franklin C. Eickenhorst, Mason, Ohio, assignor to Dayton Reliable Tool & Mfg. Company
Filed Jan. 27, 1969, Ser. No. 794,242
Int. Cl. F15c 1/04
U.S. Cl. 137-81.5 11 Claims




This disclosure describes a fluidic device which includes a primary supply orifice and a collector orifice with the collector orifice spaced from and generally confronting the primary supply orifice. Primary supply air is discharged from the primary supply orifice to form a primary airstream which flows into the collector orifice. To protect the primary airstream against ambient air currents, a protective fluid column at least partially surrounds the primary airstream and extends therealong to serve as a shield. The primary airstream may be disrupted or deflected in response to the presence or absence of the object which is being sensed. The presence or absence of a predetermined flow or pressure of primary air through the collector passage provides a signal indicating the presence or absence of the object.

3,580,265
BISTABLE FLUIDIC AMPLIFIER
Herbert P. Horacek, Scottsdale, Ariz., assignor to The Garrett Corporation, Los Angeles, Calif.
Filed Jan. 15, 1969, Ser. No. 794,842
Int. Cl. F15c 1/04
U.S. Cl. 137-81.5 7 Claims




This bistable fluidic amplifier has a converging-diverging, beam- or power-jet-forming inlet nozzle, the diverging sides being extended to form an interaction chamber with laterally spaced output ports opposite the inlet nozzle. A control pressure manifold is disposed at each side of the interaction chamber and a plurality of spaced sets of control pressure inlet nozzles lead from the manifold to the interaction chamber. The control pressure inlet nozzles are of different widths and serve to distribute the control flow into the interaction chamber to deflect the power jet beam over a wide range of supply pressures. As the supply pressure is varied, the flow issuing from the inlet nozzle into the interaction region varies between subsonic, sonic and supersonic flow.

3,580,266
COMPARATOR CIRCUIT FOR DIGITAL POSITIONING CONTROL
Karl A. Brandenburg, Hayward, Calif., assignor to The Aero Corporation, Bryan, Ohio
Filed Mar. 21, 1969, Ser. No. 809,214
Int. Cl. F15c 1/12
U.S. Cl. 137-81.5 4 Claims




A pneumatic comparator circuit comprised of a plurality of stages arranged in serial order, each stage including a pair of pneumatic OR devices in series with a pneumatic NOT device. One of the inputs to each OR is also connected with the control input of the unassociated NOT device of the stage. Depending upon whether a signal to one or the other of the respective OR devices is present, an output signal is provided to the appropriate NOT device and finally to an ultimate output.

3,580,267
CONDENSATE VALVE
Ralph J. Baker, 655 N. Main St., Marine City, Mich.
Filed Sept. 26, 1969, Ser. No. 861,366
Int. Cl. F16k 49/00, 51/00
U.S. Cl. 137-203 11 Claims



A condensate valve for connection to a compressed fluid tank, specifically an air tank associated with a compressor, to eject accumulated condensate in the tank, comprising a multiple piece valve body made of a tough, high impact plastic such as polycarbonate, each valve body section or part being internally configured to provide a passage for condensate through the valve normally closed by check valve means, and a chamber within which is disposed a diaphragm means having check valve actuating means responsive to diaphragm movement to momentarily open the check valve to exhaust condensate from the air tank.


3,580,268
LUBRICANT SEAL FOR ROTARY VALVE
Homer J. Shafer, 2300 Park Ave. W., Mansfield, Ohio
Filed Sept. 10, 1968, Ser. No. 758,787
Int. Cl. F16k 5/22
U.S. Cl. 137-246.22 6 Claims



A valve having a rotary valve element with an exterior seating surface substantially abutting seating elements in the upstream and downstream ends of the valve housing, there being lubricant sealing grooves in the seating surface or in the seating elements to provide lubricant seals at the upstream and downstream ends of the valve in its closed position, and separate lubricant passageways in the valve element for connecting with said sealing grooves and extending into and laterally out of the rotary valve stem, there being lateral lubricant supply ports in the stem housing for registering with said passageways in the closed position of the valve.

The invention relates generally to rotary valves, and more particularly to lubricant sealing construction for ball valves.

3,580,269
DEBRISLESS TAP VALVE WITH BACKRAKED PIERCING ELEMENT
Henry Ehrens, Bayside, N.Y., and Sidney Weiner, Cresskill, N.J., assignors to Sealed Unit Parts Co., Inc., Allenwood, N.J.
Filed Apr. 29, 1969, Ser. No. 820,207
Int. Cl. F16k 43/00; F16l 55/00
U.S. Cl. 137-318 4 Claims




A tap valve comprises a valve body having a portion to mate with a pipeline or container to be tapped. Within the body is a valve chamber having a passageway for communication with a fluid source or sink. There is also an opening in a mating face portion of the body for communication with the pipeline or container. A threaded passageway supports a valve stem member in the body which is floatingly coupled to a piercing element. The coupling is such that axial translational motion is transmitted by the stem member to the piercing element whereas the stem member is free to rotate with respect to the piercing element. The piercing element is a truncated cylinder with a backrake along its apex edge.

3,580,270
WRENCH

Wilbur R. Leopold, Jr., and John J. Smith, Decatur, Ill., assignors to Mueller Co., Decatur, Ill.
Filed Sept. 12, 1969, Ser. No. 857,446
Int. Cl. F16k 43/00

U.S. Cl. 137-318

5 Claims




A wrench or tool, of the type disclosed in U.S. patents to Mueller et al., No. 2,829,429, granted Apr. 8, 1958 and Smith No. 3,038,484 granted June 12, 1962, and wherein the rod portion, which is operatively connectable to the part, or structure to be manipulated, in the pressure chamber, is detachably connected to the piston-carrying plunger and a tubular sleeve is also detachably connected to the plunger in surrounding relation to the rod portion defining an annular passageway communicating with a chamber on one side of the piston whereby pressure from the region being worked will be utilized to assist positioning and operation of the wrench. The rod portion is solid, and the tubular sleeve is arranged coaxially therewith.

3,580,271
GAS PRESSURE REGULATORS

Sydney Farrer, Sheffield, England, assignor to The Bryan Donkin Company Limited, Chesterfield, England
Filed Dec. 13, 1968, Ser. No. 783,652
Int. Cl. F16k 17/64

U.S. Cl. 137-458

3 Claims



A diaphragm operated gas regulator has an operating spindle carrying a regulator valve member and a cutoff valve member respectively able to close a pair of orifices arranged back-to-back so that the cutoff valve member provides low-pressure cutoff, the connection between the operating spindle and the diaphragm including a spring loaded overcenter trip linkage so that when gas pressure becomes excessively high the linkage trips to "break" the connection and to close the cutoff valve so as also to provide high-pressure cutoff.


3,580,272

AUTOMATIC AIR FLOW REGULATOR

Russell G. Sherman, la Verne, and Robert P. Koenig, Torrance, Calif., assignors to Powers Regulator Company, Skokie, Ill.
Filed Aug. 14, 1969, Ser. No. 849,966
Int. Cl. G05d 7/03

U.S. Cl. 137-486

3 Claims



An automatic air flow regulator for use in the airline of a pneumatic tube system for automatically maintaining a preset velocity of air flow within the airline regardless of the load contained throughout the pneumatic tube system comprising a sensing means adapted to sense the pressure velocity of the air in the airline and a control means connected to the sensing means for regulating the velocity of the air flowing through the airline in response to the sensing means.


3,580,273

TWO-WAY CHECK VALVE

Ernest I. Schwarz, Middletown, Conn., assignor to The EIS Automotive Corporation, Middletown, Conn.
Filed Mar. 20, 1969, Ser. No. 808,934
Int. Cl. F16k 17/18

U.S. Cl. 137-493.2

1 Claim



A two-way check valve comprising a diaphragm and metal disc unit for use particularly in association with the discharge port of a master cylinder for a vehicle-braking system. Flow outwardly of the cylinder in the braking stroke is accommodated through the disc and diaphragm while flow around the unit is prevented, and flow inwardly of the cylinder during the return stroke is accommodated around the unit while flow through the unit is prevented.


3,580,274

COMBINED PRESSURIZING AND RELIEF VALVE FOR FIRE EXTINGUISHERS

Arne Hansen, New York, N.Y., assignor to Walter Kidde & Company, Inc., Belleville, N.J.
Filed Dec. 2, 1968, Ser. No. 780,400
Int. Cl. F16k 17/18

U.S. Cl. 137-493

3 Claims




A combined pressurizing and relief valve in the control head of a fire extinguisher including a spring-biased valve member controlling flow between the external fill port and the pressure vessel of the extinguisher and between the fill port and venting openings. The valve member is provided with a small piston area in communication with the pressure vessel for operating the valve to allow excessive pressure within the vessel to flow out through the fill port. The valve member is also provided with a large piston area in communication with the fill port for operating the valve first to allow charging fluid entering the fill port to flow to the pressure vessel and, when the vessel is properly pressurized, to further operate the valve to allow the charging fluid to flow out through the venting openings.

3,580,275
VALVE

John R. Hanson, and Karl B. Pierson, Warren, Pa., assignors to Tiona-Betts, Inc., Warren, Pa.
Filed Feb. 24, 1969, Ser. No. 801,321
Int. Cl. F16k 15/02

U.S. Cl. 137-516.29

1 Claim



A combination pressure relief and check valve including an elongated valve body having a longitudinal bore therethrough with a tapered restricted bore portion at one end thereof forming a tapered valve seat. Reciprocally disposed in the bore is a valve disc having a tapered end portion which contacts the tapered valve seat to form a fluid-sealing engagement therewith. The disc tapered portion may have an annular O-ring disposed circumferentially thereon to provide a positive fluid seal with the valve seat. A coiled spring is longitudinally disposed in the bore and is compressed between the disc and a spring retainer locked in the opposite end of the bore to bias the disc against the seat in a

normally closed position. An annular bore shoulder is formed at the juncture of the bore and the restricted bore portion, and the disc is formed with a coating disc shoulder to seat against such bore shoulder to restrict travel of the disc into the tapered seat. The bore wall has elongated longitudinal ridges formed therein to guide the disc in the bore and to permit escape of pressurized fluid past the valve seat and through the spaces between the ridges to the atmosphere.


3,580,276

MULTIPURPOSE LIQUID TRANSFER VALVE

Christ P. Korbilas, Chicago, and Raymond W. Smith, Park Ridge, Ill., assignors to Astro Controls, Inc., Chicago, Ill.
Filed Jan. 23, 1969, Ser. No. 793,527
Int. Cl. F16k 11/00; F11k 21/00

U.S. Cl. 137-517

10 Claims



A flow control three position dual spring controlled valve which snaps shut as an excess flow check valve with flow in one direction through a shutoff valve with high degree of accuracy, and, with flow in the opposite direction, accommodates maximum flow capacity permitted by the shut off valve. The flow control valve preferably is protectively disposed within a tank and is constructed to withstand without damage the hammerlike blows of valve ports rapidly propelled in their action.


3,580,277

RELIEF VALVES WITH CONTROLLED PRESSURE OVERRIDE

Roger W. Gettel, Bloomfield Hills, Mich., assignor to Sperry Rand Corporation, Troy, Mich.
Filed Mar. 12, 1969, Ser. No. 806,488
Int. Cl. F16k 15/14

U.S. Cl. 137-525.5

10 Claims




A contaminant-resistant relief valve comprising a housing having an inlet connected to an outlet with a preloaded, disc-type valve adapted to prevent communication between said inlet and said outlet below a predetermined pressure setting and means for resiliently biasing said disc-type valve, said means being of an adjustable nature.

3,580,278


FLUID-ACTUATED TRANSMISSION CONTROL
 Lewis D. Bennett, Dallas, Tex., assignor to Bennett Enterprises, Inc., Addison, Tex.
 Filed July 2, 1969, Ser. No. 848,377
 Int. Cl. F16k 37/00, 31/44
 U.S. Cl. 137—554

11 Claims



A pneumatic or hydraulic control mechanism for power shift transmissions of the type used in heavy duty power equipment, such as earth moving machines, cranes and material handling devices, marine equipment, deep well drilling rigs, and the like, whereby to control the movement of the range selector valve and insure proper function thereof when shifting from one transmission range to another, thus avoiding transmission failures, and possible damage thereto, through faulty manual shifting.

mounted in the chambers for movement axially therein. The piston has a head to which pressure is adapted to be supplied through one of the ports to shift the piston axially and a stem containing ports which in one position of the piston permits flow of pressure fluid through the valve and in the other position blocks flow through the valve. In conjunction two such




valves and a pilot valve connected thereto so that pressure supplied to the head of one valve, shifts the piston therein from a normally closed to an open position, which, in turn, supplies pressure to the head of the other valve which is normally open to shift the piston therein to a closed position, provide for switching the pressure from a source of pressure to one or the other of two activities.

3,580,279

LOCK AND SEAL MEANS FOR LONGITUDINALLY MOVABLE MEMBER INSERTED INTO A VESSEL
 Dale K. Harris, Monroe, La., assignor to Cities Service Company, New York, N.Y.
 Filed Dec. 23, 1968, Ser. No. 786,180
 Int. Cl. F16l 27/12

U.S. Cl. 137—590

16 Claims



In a fluid-containing vessel having a longitudinally movable elongated member which extends into the vessel through an opening in the wall thereof, means for altering the insertion distance of the member while preventing leakage of material through the wall opening. The elongated member, e.g. a conduit or probe, extends axially through a stationary housing attached to the vessel wall. The housing contains a plurality of clamping fingers for gripping the elongated member so that it is secured from longitudinal movement. The grip can be released at will for repositioning of the member. Seal means is also employed to prevent leakage of material into or out of the vessel through the wall opening.

3,580,280

PISTON VALVE


Robert D. Reis, Hingham, Mass., assignor to United Electric Controls Company, Watertown, Mass.
 Filed Oct. 10, 1969, Ser. No. 865,458
 Int. Cl. F16k 11/10; F15b 11/00

U.S. Cl. 137—596.14

11 Claims

A valve block containing axially aligned chambers one of which contains a port midway between its ends and the other three ports, two at one end and one at the other. A piston is

A plurality of spool-type valves are cascaded in tandem so that the spools of the valves are connected and respond to an input control force derived from a control mechanism, which is applied to one spool which acts against a bias force exerted on another spool so that the spools are positioned in unison and one spool delivers position feedback to the control mechanism so that the valves uniformly meter fluid flow at substantially the same pressure to a power actuator, whereby a signal power actuator may receive the total flow from all of the valves.




3,580,282

VALVE-OPERATING SYSTEM

Lyle R. Van Arsdale, and Francis M. Lathrop, II, Houston, Tex., assignors to M & J Valve Company, Houston, Tex.
 Continuation-in-part of application Ser. No. 719,338, Apr. 8, 1968, now abandoned. This application Oct. 24, 1968, Ser. No. 770,270
 Int. Cl. F17d 1/00

U.S. Cl. 137—608

2 Claims



A system including power operators for two or more main flow control valves. Devices (e.g., four-way valves) serve to control supply of energy (e.g., liquid under pressure) to the power operators, and in turn are conditioned by electrical means. In the event of failure of the electrical power supply, both of the control devices are set whereby the main valves are moved to or remain in a safe condition (e.g., closed).

3,580,283


SINGLE LEVER VALVE FOR AUTOMATIC WASHERS
 Robert W. De Vries, Grand Rapids, Mich., assignor to Wolverine Brass Works, a Division of Wolverine Industries, Inc., Grand Rapids, Mich.

Filed Jan. 24, 1969, Ser. No. 793,689

Int. Cl. F16k 11/06

U.S. Cl. 137—625.18

11 Claims



The valve is a single-lever shutoff valve for simultaneously terminating flow of hot and cold water supplied to an automatic washer or similar machine. The valve embodies a minimum number of simple and inexpensive parts, and is operable with great ease and despatch, to discourage the hazardous practice of leaving the machine elements pressurized with hot and cold water when not in use.


3,580,284

REGULATING VALVE FOR WATER MIXING IN AIR CONDITIONING SYSTEMS

Glancarlo Bini, and Gianfranco Tamoni, Milano, Italy, assignors to Carlo Gavazzi S. P. A., Milano, Italy
 Filed Apr. 2, 1969, Ser. No. 812,769
 Claims priority, application Italy, Apr. 3, 1968, 14,762A/68
 Int. Cl. F16k 31/165, 11/00

U.S. Cl. 137—625.18

2 Claims



Regulating valve for hot and cold water mixing in air-conditioning systems, comprising as a unit two three-way valve bodies having a single servomotor and stem for operation thereof, such that a substantial overall size reduction is provided in air-conditioning cabinet manufacturing, the valve being controlled by a pneumatic regulator responsive to temperature, moisture or pressure conditions.


3,580,285

WORK CONTROL DEVICE FOR FLUID DRIVEN APPARATUS

Karl A. Brandenburg, Hayward, Calif., assignor to The Aro Corporation, Bryan, Ohio
 Filed Aug. 28, 1969, Ser. No. 853,632
 Int. Cl. F15b 11/02

U.S. Cl. 137—624.2

8 Claims



A device for controlling the amount of work performed by a pneumatic tool including a pair of sensors adapted to sense the pressure drop caused by a restriction in a pneumatic line to the tool. The sensors produce signals that are summed thereby providing a pressure supply through a metered orifice whenever the tool begins work output. The metered orifice delays the pressure supply signal to a valve in the pneumatic line downstream from the restrictor in that line. The valve closes upon receipt of the pressure supply signal thereby stopping the tool. The sensors and orifices the device are adjustable in order to compensate for various work tools, workloads and time of operation of the device.

3,580,286 SPOOL VALVE


Sidney D. Bash, Indianapolis, Ind., assignor to Stewart-Warner Corporation, Chicago, Ill.

Filed Apr. 4, 1969, Ser. No. 813,689

Int. Cl. F16k 11/07

U.S. Cl. 137—625.68

5 Claims



A unitary sleeve member formed of a nylon-molybdenum disulfide composition is fixedly carried in concentric fashion intermediate of the valve casing and a reciprocating valve spool and in contact with the peripheral surface of the valve spool.

3,580,287

DIRECTIONAL CONTROL VALVE


William I. McLaughlin, Littleton, Colo., assignor to C. A. Norgren Co., Littleton, Colo.

Filed Feb. 10, 1969, Ser. No. 798,087

Int. Cl. F16k 11/07

U.S. Cl. 137—625.69

9 Claims



A spool-type valve and process of making same characterized by a ceramic spool member and ceramic sleeve which slidably receives same, the sleeve being bonded to the bore of a valve housing by an annular elastomeric wall which may be internally stressed between its bonded surfaces to prevent distortion of the sleeve in the event of temperature differences between the housing and sleeve or due to age warping of the housing. Since the elastomeric material is applied by injection and may fill an annular space of variable radial width, the dimension and finish of the housing bore and outer surface of the sleeve need not be held to critical tolerances.

3,580,288

FLOW CONTROL DEVICE INCLUDING A PRESSURE-BALANCED SINGLE-SEATED VALVE PLUG

Charles B. Schuder; Victor E. Skov, and Richard F. Lytle, Marshalltown, Iowa, assignors to Fisher Governor Company

Filed Oct. 18, 1968, Ser. No. 768,852


Int. Cl. F16k 11/22

U.S. Cl. 137—630.13

5 Claims

A flow control device providing for large flow capacity together with tight shutoff by the use of large pressure balanced single-seated valve plug having passage means

therethrough, with a separate single-seated valve plug for opening and closing the passage means, the large valve plug



being opened and closed with a minimal force output actuator.

3,580,289

FLEXIBLE HOSE CONSTRUCTION


Ralph E. James, Jr., Wyomissing, and Robert B. Koch, Reading, Pa., assignors to The Polymer Corporation

Filed Jan. 9, 1967, Ser. No. 607,985

Int. Cl. F16l 11/04, 11/18

U.S. Cl. 138—121

1 Claim



Corrugated flexible hose structure including one or more of the following features: a compressible filler material in the grooves of the hose sidewall for controlling sidewall flexure; a high tenacity yarn in the grooves; a braided covering bonded only to the crests of the ridges between the grooves; methods for filling the grooves; and methods for applying and bonding the braided covering.

3,580,290

ACCUMULATOR

Kazuo Sugimura, and Nobuyuki Sugimura, 1416 Sodeshi-cho, Shimizu-shi, Shizuoka-ken, Japan

Filed May 27, 1969, Ser. No. 828,120

Claims priority, application Japan, June 1, 1968, 43/37716

Int. Cl. F16l 55/04


U.S. Cl. 138—31

3 Claims

An accumulator comprises a rigid container having a valve seat at its fluid inlet and a bladder therein carrying a valve element that engages the valve seat when the bladder is fully expanded. There is a dashpot connection between the valve element and a fixed spider in the inlet, to guide the valve ele-

ment and so retard its motion when it is near the valve seat as to encourage radial rather than axial expansion and contrac-

tion with an open warp shed transversely to the path of the race comb so that the race comb is entered into the warp shed near the front position thereof, and is located substan-



tion of the bladder, thus preventing rubbing of the bladder on the container.

3,580,291

FILLING CARRIER FOR USE IN SHUTTLELESS LOOMS

Mario Piccoli, Gazzaniga, Italy, assignor to Somet S.p.A.

Societa Meccanica Tessile, Gazzaniga, Italy

Filed Aug. 5, 1968, Ser. No. 750,267


Claims priority, application Italy, Sept. 19, 1967, Mar. 6,

1968, 20,635/67; 13,607/68

Int. Cl. D03d 47/20

U.S. Cl. 139—122

1 Claim



A feeding gripper that transfers weft yarn to a drawing gripper in the warp sheds of a shuttleless loom comprises an open box-type structure or main body of plastic with a laterally projecting front wing. The wing is bifurcated by a forwardly opening horizontal slot, into superposed lower and upper jaws that receive between them the weft yarn. The upper jaw is in two laterally spaced portions one of which extends forwardly from the forward end of the main body and the other of which, at a lower level, overlies the lower jaw. The forward ends of the two portions of the upper jaw are interconnected by a downwardly laterally outwardly inclined portion, and a vertical fin having a forwardly downwardly inclined upper edge is disposed on the inner side of the forward end of the lower jaw. A resilient yarn-checking device is provided on the lower jaw, between the two portions of the upper jaw, comprising metallic laminae and an adjustable leaf spring which presses them against the lower jaw.

3,580,292

APPARATUS AND METHOD FOR POSITIONING WARP SHEDS

Zdenek Rambousek, Liberec, Czechoslovakia, assignor to Elitex, Zavody Textilniho Strojirenstvi, Liberec, Czechoslovakia

Filed June 2, 1969, Ser. No. 829,374

Claims priority, application Czechoslovakia, June 3, 1968,


PV4069-68

Int. Cl. D03d 49/00

U.S. Cl. 139—190

7 Claims

During weaving of a fabric and during reciprocation of a race comb for a gripper shuttle along a part-circular path with the slay, reciprocating guide means move a fabric por-



tially at the center of the warp shed when arriving at its rear position in which a gripper shuttle is picked through the race comb and warp shed.

3,580,293

WEAVING MACHINE

Theodorus Fransen, Deurne, Netherlands, assignor to N. V.

Machnefabriek L. Te Strake, Deurne, Netherlands

Filed Sept. 3, 1968, Ser. No. 756,973


Claims priority, application Netherlands, Sept. 15, 1967,

6712677

Int. Cl. D03d 49/70

U.S. Cl. 139—303

5 Claims



A suction nozzle is movably mounted at one side of the shed of the loom, and is provided with mechanism for displacing the suction nozzle, in synchronism with a beating movement of the reed, from an active position for receiving the free end of a weft to an end position. A locking device is provided for retaining the suction nozzle in such end position during the succeeding reverse movement of the reed, and apparatus is provided for releasing the locking device at the beginning of a succeeding reverse movement of the reed to permit the suction nozzle to return to its active position.

3,580,294

METHOD AND APPARATUS FOR DETECTING AN UNDESIRABLE CONDITION OF A SHUTTLE-CARRIED WEFT YARN

Jakob Muller, 5262 Frick, Aargau, Switzerland

Filed Jan. 23, 1969, Ser. No. 793,617

Claims priority, application Switzerland, Jan. 24, 1968,

1106/68


Int. Cl. D03d 51/34, 45/10

U.S. Cl. 139—371

8 Claims

Running out of the weft yarn of a bobbin carried by a shuttle, or breakage of the weft yarn, are sensed independently, and upon sensing of such a condition, the respective sensing means moves to a control position. In at least one end position of the shuttle, an actuated sensing means in the control

position engages in the beat-up position of the slay, stationary contact means or switch means for closing a control circuit so that a control impulse for stopping the loom is produced.



3,580,295

PARTLY WOVEN AND PARTLY KNITTED FABRIC AND APPARATUS FOR MAKING THE SAME


Miloslav Jisa, Liberec; Josef Zmatlik; Josef Mohelnicky, and Bohumil Milichovsky, Prague, Czechoslovakia, assignors to Stantni Vyzkumny Ustav Textilni, Liberec, Czechoslovakia
Filed Dec. 23, 1968, Ser. No. 786,863

Claims priority, application Czechoslovakia, Dec. 22, 1967, 9120/67

Int. Cl. D03d 25/00

U.S. Cl. 139—383

11 Claims



Longitudinal fabric sections, each of which include a group of warp threads and sectional double-weft elements, are connected to each other by a wale of chain stitches extending between two woven fabric sections in warp direction and tying the end loops and connecting loops of the double-weft elements of the adjacent fabric sections.

3,580,296

ARTICLES WOVEN FROM NONEXTENSIBLE MATERIALS

Ernest P. Carter, Durham; Robert P. Bell, Jr., Cary, and Alton P. Carroll, Jr., Durham, N.C., assignors to Monsanto Company, St. Louis, Mo.

Filed July 11, 1968, Ser. No. 744,078

Int. Cl. D03d 15/02

U.S. Cl. 139—425

6 Claims



A method and apparatus for weaving a composite fabric having a mixed warp of alternating ends of extensible and nonextensible yarns, and a fill of a flexible, extensible yarn.

3,580,297 DEVICE FOR TWISTING AND ALIGNING TERMINAL POSTS OF AN ELECTRICAL CONNECTOR


Frank G. Spadoni, Jr., Orange, N.H., and Michael P. Kleban, Oakville, Conn., assignors to Litton Precision Products, Inc., Beverly Hills, Calif.

Filed Sept. 18, 1968, Ser. No. 760,404

Int. Cl. B21f 7/00, 1/02

U.S. Cl. 140—149

6 Claims



A device for twisting as well as aligning the terminal posts of an electrical connector is disclosed. The device comprises a number of tubular elements located to correspond to the terminal posts of a connector and having interior cross sections similar to the cross sections of the posts. Each tubular element has a small pinion gear attached thereto and is located to operate with a rack so that the rack can impart rotational motion to the tubular elements. A second embodiment comprises laterally extending arms connected to the tubular elements which are movable for imparting rotational motion.

3,580,298

CONTAINER FILLING MACHINE


William H. Trusselle, Braintree, Mass., assignor to Pneumatic Scale Corporation, Quincy, Mass.

Continuation of application Ser. No. 550,390, May 16, 1966, now abandoned. This application Sept. 12, 1969, Ser. No. 857,593

Int. Cl. B65b 3/26

U.S. Cl. 141—40

15 Claims



A container filling machine provided with a plurality of filling heads having provision for automatically starting and

stopping the filling operation in successive filling heads which includes pneumatically operated control means for each filling head for detecting a predetermined height of the material in its container and pneumatically operated means responsive thereto for discontinuing the filling operation, the invention being characterized by improved control means facilitating adjustment of the control units for the various filling heads to obtain uniform filling heights in successive containers.

3,580,299

CONTAINER FILLING DEVICE


Jorge Alkalay, and Oton Alkaly, Ramon Lista 5376, Buenos Aires, Argentina

Filed Nov. 21, 1968, Ser. No. 777,819

Int. Cl. B65b 31/00

U.S. Cl. 141—59

9 Claims



A vacuum operated bottle filling device which includes a rotating platform and rotating reservoir tank. Container filling heads are positioned on the circumferential surface of the tank and include upper and lower head pieces adapted to cooperate to fill each container to a desired level without the operation of internal or external valves thus increasing the efficiency and simplifying the construction in relation to prior art apparatus of this type.

3,580,300

VACUUM APPARATUS AND SNORKEL NOZZLE


William H. Dunn, Jr., Spartanburg, S.C., assignor to W. R. Grace & Co., Duncan, S.C.

Filed July 25, 1969, Ser. No. 844,887

Int. Cl. B65b 31/04

U.S. Cl. 141—65

6 Claims



A vacuum operated device for withdrawing air from a package, lifting the package and positioning the package for closing. The device includes only a few parts and has two main assemblies connected by a quick clamp. The parts may be disassembled and assembled by hand without the use of tools for cleaning. One of the assemblies has two subassemblies, an axial suction tube and an axial slide handle which

are mounted in the first vacuum chamber and the other assembly includes a piston and a cylinder. A vacuum nozzle is provided having a sump. A new vacuum operated apparatus construction is also provided wherein a permanently open relief vent is present.

3,580,301

CONTINUOUS FLOW LIQUID DISTRIBUTING SYSTEM


Samuel Nejame, Jr., Medfield; George C. Kondel, Jamaica Plain, and Italo J. De Santis, Milford, all of, Mass., assignors to Damon Corporation, Needham Heights, Mass.

Filed Aug. 15, 1968, Ser. No. 752,976

Int. Cl. B65b 43/60; B67c 3/00

U.S. Cl. 141—131

18 Claims



Continuous flow liquid distributing systems are disclosed in which a turntable has a concentric series of abutting funnels for controlling delivery to subjacent containers with liquid continuously delivered thereto from a pump controlled source. The operation of the turntable drive, of the pump, or of both is variable and where there are two or more series of funnels, means are provided to shift the delivery nozzle from a position over the last funnel of one series to the first funnel of another series.

3,580,302

CONTAINER FILLING MACHINE


James H. Riesenbergh, Amherst, N.Y., assignor to Consolidated Packaging Machinery Corporation, Buffalo, N.Y.

Filed May 27, 1968, Ser. No. 732,151

Int. Cl. B65b 57/06

U.S. Cl. 141—141

14 Claims



A container filling machine having a container supporting tray and a filling head including a charging cylinder and a filling stem, the tray and head being mounted for movement

through a predetermined path. A piston is movable in the cylinder and a follower connected to the piston successively engages a first cam section extending along the path for moving the piston in a first direction to draw product from a source into the cylinder and a second cam section extending along the path for moving the piston in the opposite direction to discharge product from the cylinder. A spool-type valve is slidable between a first position placing the charging cylinder in communication with the source and a second position placing the cylinder in communication with the stem, the valve shifting arrangement being disabled prior to the discharge stroke in the absence of a container to be filled whereby the product is returned from the cylinder to the source. The cam sections are pivotally supported for movement in opposite directions to selectively vary the rise of the first cam section and thereby vary the piston stroke and consequently the volume of product dispensed. A spring-loaded check valve in the filling stem opens under discharging pressure applied by the piston, closing when the pressure is released, and a surface tension increasing element at the filling stem outlet avoids dripping. A return cam is positioned adjacent the exit end of the second cam section and is operable to engage the piston follower against the first cam section just prior to the conclusion of the discharge stroke, whereby the piston stroke is determined by the first cam section as a reference and the follower is eliminated as a variable.


3,580,303

INFLATABLE TOY DISPENSER

Robert A. Roberge, 438 Pearl St., Brockton, Mass.
Filed Apr. 16, 1969, Ser. No. 816,627
Int. Cl. B65b 43/42

U.S. Cl. 141-173

5 Claims



A coin operated balloon dispenser system having supply racks of uninflated balloons assembled as units on inflating needle-studs. Automatic electrical-mechanical system takes units from racks to inflation station where an inflator tube is brought into inflating connection from a helium supply, and inflated balloons are thereafter disengaged; subcombination of needle stud uninflated balloon assembly; method of needle stud-uninflated balloon assembly; and method of automatic inflation and dispensing of balloons.

3,580,304

GLASS FILLER

Robert W. Chermack, 14424 Spring Lake Road, Hopkins, Minn.


Filed July 11, 1968, Ser. No. 744,033
Int. Cl. B65b 3/28, 3/36

U.S. Cl. 141-244

5 Claims

Apparatus for simultaneously filling a plurality of receptacles, especially water glasses, having a distribution manifold with a plurality of downwardly directed discharge spouts and a flow control valve connected to the manifold, the operation of the valve being controlled by a lever positioned to be actuated in response to the movement of a glass tray into position beneath the aforesaid discharge spouts. The flow control valve may be a flush valve which passes a predetermined

volume of water when its operating lever is tripped, or it may be an ordinary on-off valve which must be actuated to its open and closed positions. In the latter case, a spring-supported, weight-responsive platform supports the glass tray,



and when the glasses are filled, their weight will depress the spring so as to move the glass tray out of engagement with the valve operating lever, thereby permitting the lever to return to its normal, closed position.


3,580,305

SAWING MACHINE

Herbert Leslie Wright, P. O. Box 179, Philo, Calif.
Filed Mar. 3, 1969, Ser. No. 803,580
Int. Cl. B27b 5/34

U.S. Cl. 143-37

13 Claims



A sawing machine with a number of thin blades carried on an arbor includes edge margins guided by fluid bearings defined between guide surfaces disposed on each side of each blade. The spacing between guide surfaces is varied in precise parallelism while precise coplanar blade alignment is derived from consolidating all guides and blades together by forces applied along an axis defined normal to the blades and radially within their guided margins.

3,580,306

MOBILE TREE SLASHER

Jean Paul Tanguay, St. Prime, Quebec, Canada, assignor to Placements Jean Paul Tanguay Ltée, St. Prime, Quebec, Canada

Continuation-in-part of application Ser. No. 698,764, Jan. 18, 1968, now Patent No. 3,500,882. This application Aug. 22, 1968, Ser. No. 754,606


Int. Cl. B27b 11/12, 31/00

U.S. Cl. 143-46F

3 Claims

An apparatus for cutting trees stems into logs comprising a horizontal conveyor transporting the stems, a first rotary saw for cutting the stems into a first set of logs having twice their final length, an upwardly sloping conveyor for lifting the said first set of logs and a second rotary saw for cutting the first logs in half while the logs are raised. A table for discharging

logs from the horizontal conveyor to the upwardly sloping conveyor comprises a sweeping blade extending longitudinally of the transfer table and a hydraulic jack is used for moving the blade laterally across the table to move the logs thereon on the upwardly sloping conveyor. An apron is



pivotally connected along one edge thereof to the discharge end of the transfer table and is downwardly inclined towards the sloping conveyor, springs biasing the apron upwardly and chains limiting the upward movement of the apron under the bias of the springs.

3,580,307

PROTECTION DEVICE FOR A CIRCULAR CUTTING SAW


Nicolae Minetos, Bucharest, Romania, assignor to Institutul De Cercetari Stiintifice Pentru Protectia Muncii, Bucharest, Romania

Filed Dec. 12, 1968, Ser. No. 783,195

Claims priority, application Romania, Dec. 12, 1967, 55,314
Int. Cl. B27g 19/02

U.S. Cl. 143-159

10 Claims



Safety device for use with a circular cutting saw in which a support means is provided forwardly of the saw with respect to the direction in which a workpiece is fed thereto. A pulley means is rotatably mounted on the support means forwardly of the saw and feeler is rotatable connected to the pulley means and extends forwardly of the saw into the path of a workpiece being fed thereto. A guard means connected to the support means covers the saw and includes a slideable guard member which is movable into and out of a safety position covering the forward edge of the saw. Cable means connects the pulley means to the slideable guard member. Thus, when the feeler means is contacted by a workpiece being fed to the saw and is caused to rotate toward the saw the pulley means is rotated causing the cable means to move the slideable guard member out of its safety position to an extent which is a function of the angle through which the feeler means is rotated by the workpiece being moved toward the saw.

3,580,308

TREE PROCESSING APPARATUS WITH FEED ROLLS

Douglas D. Hamilton, Montreal, Canada, assignor to Canadian International Paper Company, Montreal, Quebec; Quebec North Shore Paper Company, Montreal and St. Ann Abtibi Paper Ltd., Beupre, Canada, fractional part interest to each


Filed May 18, 1967, Ser. No. 639,536

Claims priority, application Canada, May 20, 1966, 960,902

Int. Cl. B27c 1/12, 9/00; B27l 1/00, 11/00

U.S. Cl. 144-3

15 Claims



A device for propelling trees or the like along a selected path through one or more processing units, such device consisting of three or more driven rollers mounted on the free ends of respective ones of a plurality of pivotally mounted arms having the free ends movable toward and away from said path to respectively bring the rollers into and out of engagement with a tree located in the path. The rollers are disposed in a generally triangular arrangement and each roller has an outer peripheral surface for tractive engagement with the tree, such tractive surface consisting of an undulated surface provided by a series of cleats extending preferably in a direction perpendicular to the feed path. The cleats permit a tree to shift laterally with respect to the feed path while being fed through the processing units thereby facilitating maintaining the tree in alignment with the feed path.

3,580,309


MACHINE FOR PROCESSING WHEELBARROW HANDLES

Eli Hochstetler, Star Route, Millersburg, Ohio
Filed Feb. 3, 1969, Ser. No. 795,818

Int. Cl. B27m 3/16; B27c 5/06

U.S. Cl. 144-11

8 Claims



An apparatus which during a continuous repetitive cycle delivers pieces of lumber, one at a time, to a supporting and clamping means. Each lumber piece in succession is shifted laterally during the supporting and clamping step to a work station where it is firmly held. During the shifting to the work station, each lumber piece is properly positioned longitudinally. While at the work station, plural right-angular

drilling means and a handle-shaping means are simultaneously activated to produce true openings transversely through each lumber piece while one end of the piece is being shaped into a handle. Some of the openings are formed at right angles to other openings. The drilling and shaping means are retracted and each handle is released onto a conveyor means for delivery to a coating sander for the shaped handle portion.


3,580,310

TREE-SHEAR DEVICE WITH BLADE

Edward V. Frankenberg, and Norman N. Griffith, Jacksonville, Fla., assignors to Fleco Corporation, Jacksonville, Fla.
Division of Ser. No. 727,853, May 9, 1968
Filed Oct. 16, 1969, Ser. No. 866,951
Int. Cl. A01g 23/02

U.S. Cl. 144—34

3 Claims



An improved tree-shear device having a pivotally mounted cutting blade powered by a cylinder and piston on which the rearward edge of the cutting blade is of a predetermined configuration to minimize the space between such rearward edge and the cylinder and piston disposed adjacent thereto during movement of the blade during its entire travel between its open and closed positions.

3,580,311

PROCESS FOR TREATING WOOD

Edward L. Fox, Jr., Fort Lauderdale, Fla., assignor to Canadian Cedar Inc.
Filed Oct. 16, 1968, Ser. No. 768,156
Int. Cl. B27k 5/00

U.S. Cl. 144—309
0000

7 Claims

A wood product for use as interior or exterior paneling formed by sandblasting cedar lumber employing a composition of silica and anhydrous oxalic acid for removing fungus growth thus forming recesses or holes through the lumber while at the same time brightening and bleaching the lumber to provide paneling of uniform color which closely simulates pecky tidewater cypress.


3,580,312

MAGNETIC HAMMER

Robert Lay Hallock, 32 Vine Road, Larchmont, N.Y.
Filed Feb. 28, 1968, Ser. No. 709,076
Int. Cl. B25d 1/04

U.S. Cl. 145—30

2 Claims



A hammer having a head of ferrous or other material with a striking face, at least one chamber at right angles to its striking face, with a permanent magnet in each chamber, and

a hardened cap or end closure in each of said chambers in a manner to seal the magnet within the chamber and at the same time form a part of the striking face of the hammer.

3,580,313

SURGICAL INSTRUMENT


Charles Allen McKnight, 2914 Painted Valley Drive, Little Rock, Ark.

Filed Jan. 7, 1969, Ser. No. 789,474

Int. Cl. B25c 3/00

U.S. Cl. 145—46

13 Claims



A surgical instrument including particularly a stapling-type instrument for attaching or anchoring fleshy parts of the body to adjacent bone structure including means to facilitate such attachments in areas of the body that are relatively inaccessible and difficult to operate in.

3,580,314

JUICE EXTRACTOR

Juan E. Besora, Avda. del Generalísimo, Franco No. 614—30 la, Barcelona, Spain


Filed Oct. 31, 1968, Ser. No. 772,180

Claims priority, application Spain, Nov. 3, 1967, 133,678

Int. Cl. A23n 1/02; A47j 19/02

U.S. Cl. 146—3

6 Claims



A juice extractor for citrus fruits and the like has a receptacle the upper side of which is open. A pulping member in form of an inverted bowl is mounted for rotation in the receptacle projecting upwardly beyond the open upper side thereof. The outer surface of the pulping member is provided with ribs. A handle is provided on the pulping member and extends outwardly through a slot in the circumferential wall of the receptacle so that the pulping member may be turned about the axis of the receptacle. A cap is pivoted to the receptacle and may be moved to a closed position in which it overlies the pulping member so as to compress a piece of fruit between the latter and the inside of the cap so that, when the pulping member is turned by means of the handle, the fruit will be pulped and juice extracted.

3,580,315

COMMINUTING MACHINE

Carl Schnell, Winterbach near Schorndorf-Wurttemberg, Germany, assignor to The Griffith Laboratories, Inc., Chicago, Ill.


Continuation-in-part of application Ser. No. 532,602, Mar. 8, 1966, now abandoned. This application Feb. 3, 1969, Ser. No. 795,912

Claims priority, applications Germany, Mar. 8, 1968, Mar. 11, 1965, June 1, 1965, Sept. 29, 1965, P 16 32 883.9, SCH 36,675, SCH 37,216, P 15 32 007.7

Int. Cl. B02c 18/06

U.S. Cl. 146—79

30 Claims



Comminuting apparatus for comminuting or precomminuting materials, particularly food products, under continuous circulating conditions and, preferably, under deaerating conditions. This apparatus can be used effectively in conjunction or combination with additional comminuting apparatus which more finely comminutes materials previously comminuted or precomminuted in said first-mentioned comminuting apparatus.

3,580,316

REINFORCED TIRE


George V. Mastrapas, 660 Virginia Park, Detroit, Mich.

Filed Jan. 8, 1969, Ser. No. 789,792

Int. Cl. B60c 19/12

U.S. Cl. 152—200

18 Claims



This invention relates to a reinforced tire. A thin steel sheet is wrapped radially interior to the tread. Rivets fixed to the sheet extend radially outward therefrom into the tread rubber. An array of indentations is provided on the sheet. Rubber adhering glue fixes the sheet to the tread rubber and more radially interior tire rubber. Brackets integral with the sheet and angularly displaced with respect thereto provide additional securing means between the sheet and the rubber of the tire.

3,580,317

DEVICE FOR EXTRACTING A Mired MOTOR VEHICLE

Clifford McHargue, P. O. Box 28, Lily, Ky.

Filed Dec. 19, 1968, Ser. No. 785,196


Int. Cl. B62d 57/00

U.S. Cl. 152—208

11 Claims

A device for removing a vehicle from a mired condition includes an elongated bar with an adjustable length. Connectors at the opposite ends of the bar are attached to spaced

apart wheels or lugs of a vehicle. Powered movement of the wheels or lugs will move the bar against an undisturbed sur-



face between the wheels or lugs to elevate the vehicle from its mired condition.

3,580,318

PNEUMATIC VEHICLE TIRE

Hans Menell, Ahlem, and Walter Scheithauer, Meyenfeld, Germany, assignors to Continental Gummi-Werke Aktiengesellschaft, Hannover, Germany

Filed Dec. 2, 1968, Ser. No. 780,424


Claims priority, application Germany, Nov. 30, 1967,

P 16 05 639.6

Int. Cl. B60c 9/02, 9/18

U.S. Cl. 152—354

8 Claims



A pneumatic vehicle tire with at least one zenith layer, the parallel strength members of which are at least approximately parallel to adjacent strength member sections of the carcass and cross-additional parallel strength members in the tire sidewalls leading from the bead cores to the tire shoulders and also crossing with sections of carcass strength members adjacent to said tire shoulders. Those strength members of the zenith layers which extend substantially parallel to adjacent tread sections of the carcass form at least approximately right angles with the marginal areas of additional strength sections in the tire sidewalls.

3,580,319

PNEUMATIC TYRE

Werner Gorter, Baden, and Johann Hauser, Modling, Austria, assignors to SEMPERIT Österreichisch-Amerikanische Gummiwerke Aktiengesellschaft, Vienna, Austria

Filed Apr. 11, 1969, Ser. No. 815,387

Claims priority, application Austria, Apr. 18, 1968,

A3770/68


Int. Cl. B60c 9/04

U.S. Cl. 152—361

4 Claims

A pneumatic tyre having reinforcements inserts of a maximum width of less than 95 percent (preferably 85—90 percent) or more than 105 percent of the tread with and in

which the rubber sidewall on at least one side, and preferably both sides, is extended between the edge of the reinforcing




inserts and the carcass to an extent of at least 10 percent of the maximum width of the inserts.

3,580,320 ADAPTERS FOR USE IN TIRE CHANGING AND WHEEL BALANCING

Warren A. Roberts, 514 Clinton St., Redwood City, Calif.
Filed Sept. 30, 1968, Ser. No. 763,771
Int. Cl. B60c 25/06

U.S. Cl. 157-1.24

15 Claims




A circular plate is provided with pins on one side for engaging lug holes of a Volkswagen wheel and is provided with pins on the other side for engaging lug holes of an eight-lug Pontiac wheel. The plate is also provided with a central hole for receiving the locking mechanism of a tire changer or the balancing head of a bubble wheel balancer. In addition, the plate may be provided with holes for receiving the hub cap retaining clips of the Volkswagen wheel and the spring-stop mechanism of a tire changer to provide a dual wheel mounting adapter for use in tire changing. Alternatively, the plate may be evenly balanced in weight about its central hole to provide a dual wheel mounting adapter for use in wheel balancing.

3,580,321 SMOKE DAMPER

James R. Root, Independence, Mo., assignor to Ruskin Manufacturing Company, Grandview, Mo.
Filed Apr. 25, 1969, Ser. No. 819,203
Int. Cl. E05f 15/20; E06b 9/204

U.S. Cl. 160-1

10 Claims



A damper for automatically sealing building passages against the flow of fluids such as smoke. The damper com-


prises a plurality of blades held in a standby position by an energized motor and which automatically move to the closed position when the electrical energy to the motor is interrupted. Axial shifting of the motor responsive to electromagnetic forces effects the holding and release of the blade assembly.

3,580,322 FLEXIBLE REFRACTORY CURTAIN

David B. Herbert, Holden, and Ronald N. Barney, Westboro, Mass., assignors to Norton Company, Worcester, Mass.
Filed Apr. 14, 1969, Ser. No. 815,732
Int. Cl. E06b 9/24

U.S. Cl. 160-231

3 Claims




A flexible refractory curtain or covering is disclosed which is made up of an essentially horizontal supporting rod or tube to which is attached a network of flexible vertical and horizontal wires or cables to which are affixed segments made from a refractory material like silicon carbide, alumina or the like. The segments are so shaped and assembled on the flexible network that when the curtain is hanging in a vertical position the segments mate to form an effectively solid wall which functions as a barrier to the passage of heat and gases.

3,580,323 WINDOW SHADE

Robert C. Gossling, Cincinnati, Ohio, and George Armstrong, Sydney, N.S.W., Australia, assignors to Clopay Corporation, Cincinnati, Ohio, by said Gossling
Filed Dec. 4, 1969, Ser. No. 882,055
Int. Cl. A47g 5/02; A47h 1/022

U.S. Cl. 160-263

6 Claims




A window shade having a transversely symmetrical design. By a "transversely symmetrical design" is meant a design that extends across the shade either in the form of a scalloped or otherwise configured lower edge, or in the form of an overall print so that the two edgewise areas of the design are the same. The disclosure is concerned primarily with a window shade roller of the type set forth that is adapted to be shortened quickly and easily by first cutting and removing equal widths of shade material from both ends of the roller, in order to preserve the symmetry of design, and second, telescoping the roller to bring the respective ends of the roller into proper relationship with the newly cut edges of the shade.

3,580,324 DOUBLE-ORIENTED SINGLE CRYSTAL CASTINGS

Stephen M. Copley, Madison; Anthony F. Giamei, Middletown; Merton F. Hornbecker, Woodbury, and Bernard H. Kear, Madison, Conn., assignors to United Aircraft Corporation, East Hartford, Conn.
Filed Mar. 13, 1969, Ser. No. 806,823
Int. Cl. B22d 25/06

U.S. Cl. 164-60

10 Claims




An apparatus and method by which to produce single crystal parts in which the orientation of the dendrite growth in two planes at right angles to one another is described. In effect this produces an orientation in all three right angle planes of the cast article.

3,580,325 CONTINUOUS CASTING MACHINE FOR SLABS

Hans Schrewe, Duisburg-Ungelsheim, Germany, assignor to Mannesmann Aktiengesellschaft, Dusseldorf, Germany
Continuation-in-part of application Ser. No. 550,713, May 17, 1966, now abandoned. This application Apr. 3, 1969, Ser. No. 813,171
Claims priority, application Germany, May 17, 1965
M65266
Int. Cl. B22d 11/00

U.S. Cl. 164-82

7 Claims



A continuous casting machine for slabs includes a mold that has a mold passage of trapezoidal cross section with the base surface on the side of the center of curvature of the casting and the opposite surface being symmetrically arranged about the central plane of the mold passage.

3,580,326 APPARATUS FOR MAKING FOUNDRY CORES AND MOULDS


Albert Edwards, Ailsworth, near Peterborough, England, assignor to British Cast Iron Research Association, Birmingham, England
Filed Mar. 26, 1969, Ser. No. 810,772
Claims priority, application Great Britain, Mar. 27, 1968,
14,654/68
Int. Cl. B22c 15/24

U.S. Cl. 164-200

5 Claims

In the production of sand-based foundry cores and mould bodies by a substantially cold curing process employing a resin and a catalyst, charges of sand containing resin and

sand containing catalyst are prepared in separate driven mixer-feeder units forming part of apparatus incorporating separate chambers into which the charges from the mixer-




feeder units are fed and from which they are blown into a common reaction chamber, the mixture then being blown from that chamber into a core-box or mould.

3,580,327 CONTINUOUS CASTING MOLD

Georgy Lukich Khimich; Vitaly Maximovich Niskovskikh, Sverdlovsk; Alexei Ivanovich Varaxin, Moscow; Evgeny Jukhimovich Gelfenbein; Leonid Alexandrovich Bykov; Anatoly Ivanovich Litvinov, and Stanislav Evgenievich Karlinsky, Sverdlovsk, U.S.S.R.
Filed July 15, 1968, Ser. No. 744,773
Int. Cl. B22d 11/00

U.S. Cl. 164-280

3 Claims



A continuous casting mold which has upper and lower portions made up of sidewalls, the sidewalls of the upper portion being fixed and defining a predetermined ingot path cross section, while the sidewalls of the lower portion are mutually movable. Fixing members, made up of rotary eccentric cams, connecting the vertically adjacent upper and lower sidewalls, and biasing means acting on the lower portion sidewalls to bias them radially inwardly to conform to the ingot shrinkage. Furthermore, second biasing means acting substantially in the direction of the ingot axis are provided on the sidewalls of both upper and lower portions to preclude a gap from occurring at the junction of the vertically adjacent upper and lower portions.

3,580,328 MOLD FOR IMPROVED CONTROL OF HEAT TRANSFER IN CASTING PLATE OR STRIP PRODUCTS


Robert E. Eppich, Southfield, and Fred J. Webber, Orchard Lake, Mich., assignors to General Motors Corporation, Detroit, Mich.
Filed May 12, 1969, Ser. No. 823,706
Int. Cl. B22d 11/00

U.S. Cl. 164-283

5 Claims

An open-ended mold is disclosed for continuously casting metal plate or strip, the mold having a graphite casting cavity

liner formed of two parallel plates separated at two of their opposing edges with spacer members so as to define an open ended cavity of substantially rectangular cross section, and two cooled metal jackets each tightly clamped against a liner plate. The two principal directions of heat transfer from the mold cavity defined by the liner are through the respective oppositely disposed graphite plates into the adjacent cooled jackets. Improved control over the rate of heat transfer from



the mold cavity is obtained by providing a slight convex curvature or crown of suitable height on either the internal surfaces of each cooled jacket or the adjacent external surfaces of the liner plates so that when a crowned surface is tightly clamped against an adjacent flat surface positive control is maintained over the area of contact between the surfaces during casting despite the inherent tendency of the graphite liners to bow to the mold cavity when in contact with hot metal due to thermal expansion.

3,580,329

PLURAL MOLD CASTING APPARATUS


Russell W. Taccone, Erie, Pa., assignor to Kelsey-Hayes Company

Original application Sept. 18, 1967, Ser. No. 674,044, now Patent No. 3,517,728. Divided and this application Sept. 4, 1969, Ser. No. 871,043

Int. Cl. B22c 9/22

U.S. Cl. 164—366

2 Claims



An apparatus and method for making castings which consist of successively forming a drag of a compacted green sand mixture having a cavity therein of a preselected pattern and disposed in an open ended flask, successively transferring the flasks by a transfer device into alignment with the inlet end of a casting tube adapted to guidably support a plurality of the molds disposed in face-to-face abutting relationship and pressing the mold from the flask in a manner to effect a trimming of the periphery of the mold to correspond with and to provide a sliding sealing fit with the inner surface of the casting tube, pouring molten metal into the cavities of the molds while disposed in stacked face-to-face abutting relationship within the casting tube and thereafter successively ejecting and transferring the filled molds to an elongated cooling tube provided with cooling means for accelerating the removal of heat from the molds. In some aspects of the apparatus and method comprising the present invention, a subatmospheric pressure is applied to the periphery of the molds while in the casting tube for removing gaseous

products formed during the casting operation. An improved mold is also described which consists of a mass of compacted green sand having a core of a thin-walled shell of bonded sand disposed in overlying relationship on one face thereof providing porosity and precision in castings heretofore unobtainable.

3,580,330

GEOTHERMAL SYSTEM

Pierre Marcel Maugis, Suresnes, France, assignor to Societe Technique, De Geothermie, Paris, France


Filed Jan. 2, 1969, Ser. No. 811,266

Claims priority, application France, Jan. 3, 1968, Nov. 13, 1968, 134,778; 175,285; 1,734,267

Int. Cl. F28f 19/00

U.S. Cl. 165—45

6 Claims



Hot geothermal water in liquid or vapor form rises, with the aid of a pump if necessary, in an insulated well and passes through a heat exchanger where its heat is utilized for urban heating. Subsequently, the spent water is reinjected through another well into the original geothermal body of water at a point sufficiently remote from the point at which it was extracted to prevent the cooled water from substantially lowering the temperature of the extracted water while ensuring a substantially steady hydrostatic pressure in the body of water.

3,580,331

APPARATUS FOR ANNEALING WITH ACCELERATED COOLING


William Wargo, Dearborn, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed May 23, 1969, Ser. No. 839,761

Int. Cl. F25b 29/00

U.S. Cl. 165—48

11 Claims



Apparatus for cooling stacked coils of steel sheet from an

annealing temperature at an accelerated rate. A hood is provided for sealing the coils from the oxidizing ambient atmosphere during the period when the coils are heated. Within the hood means, cooling separator structures are placed in contact with the planar coil surfaces. These separators include weight bearing members used to support the coils and provide space for closed fluid conduits. These conduits are interposed between, under and atop the coils in intimate contact with the planar surfaces of the coils. This arrangement provides for conductive heat transfer from the coils to coolant circulated in the fluid conduits without causing oxidation of the coils.

3,580,332

APPARATUS FOR CONTROLLING FLUID FLOW FROM GAS STORAGE WELLS AND RESERVOIRS


Michael R. Dean; Luis F. Castro, Houston, Tex., and John V. Salerni, Whittier, Calif., assignors to Baker Oil Tools, Inc., Commerce, Calif.

Filed Mar. 2, 1970, Ser. No. 15,403

Int. Cl. E21b 33/12

U.S. Cl. 166—184

23 Claims



A retrievable packer with a large passage area and control valve connected thereto are run and set in a cased well bore. A plug is set in the valve, after which a tubing is connected to the plug and fluid pressure applied thereto to open the valve so that gas from the well or reservoir can flow through the packer and opened valve into the tubing-casing annulus and into a gas delivery line at the top of the well bore. The valve is tapered to provide a greater annular area between it and the well casing to allow unrestricted flow of gas from the well at a very high rate. In the event of damage to the surface equipment, the well pressure automatically closes the control valve. The valve can be closed whenever desired and the tubing string removed, after which the plug and control valve and packer are removable from the well casing through use of wireline equipment, and without the necessity for "killing" the well.

3,580,333

WELL LIQUID REMOVAL DEVICE

Bobby L. Douglas, Ennis, Tex., assignor to Dresser Industries, Inc., Dallas, Tex.

Filed Sept. 11, 1969, Ser. No. 857,242


Int. Cl. E21b 33/00

U.S. Cl. 166—224

8 Claims

A device for removing liquid from a well bore which util-

izes two valve means. One valve admits liquid to the tubing



and the other valve admits gas to the tubing to lift liquid in the tubing to the earth's surface.

3,580,334

METHOD FOR PREVENTING DEFORMATION IN A WELL CASING


Leo P. Broussard, New Orleans, La.; Leon L. Dickson, Jr., and Wilhelmus J. G. Gardenier, Houston, Tex., assignors to Shell Oil Company, New York, N.Y.

Filed Jan. 22, 1970, Ser. No. 5,078

Int. Cl. E21b 17/08; 49/02; G01n 3/10

U.S. Cl. 166—250

7 Claims



A method for preventing deformation of the casing of a well bore hole extending into a reservoir interval within a subterranean hydrocarbon-bearing earth formation wherein such deformation is caused by the compaction of the reservoir interval in which unconsolidated sand therein compacts when the fluid pressure of the interval is reduced. A core sample is extracted from the interval containing a substantially undisturbed portion of unconsolidated sand typical of that contained in the interval. The extent of vertical compressibility of the cored sample is measured relative to its orientation within the reservoir interval and its lateral confinement in the configuration it exhibits under an isostatic compressive force equaling that existing within the interval. The vertical extent of the sand contained within the interval and the extent of reservoir interval compression that would result from a vertical compression of the sand contained in the reservoir interval by an amount corresponding to the

measured compressibility of the core sample are determined. The portion of the well casing to be disposed against the interval is equipped with slip couplings adapted to provide an extent of slip having a selected degree of correspondence with the predetermined extent of reservoir interval compressibility.

3,580,335

OIL RECOVERY BY A COMBINATION OF SOLUTION GAS DRIVE AND WATERFLOODING

Joseph C. Allen; Valery N. Bednarski, Bellaire, and Russell W. Hall, Jr., Houston, Tex., assignors to Texaco Inc., New York, N.Y.

Filed Dec. 19, 1969, Ser. No. 886,785
Int. Cl. E21b 43/22

U.S. Cl. 166—263

4 Claims

Improved oil recovery from an oil-bearing reservoir is obtained by a combination of solution gas drive and water flooding whereby the reservoir is produced by solution gas drive until the pressure of the reservoir is reduced below the bubble point pressure and a critical gas saturation is established, and thereafter the reservoir is produced by a water flood until the rate of oil production reaches a predetermined value or termination point, whereafter the cycle is repeated.

3,580,336


PRODUCTION OF OIL FROM A PUMPING WELL AND A FLOWING WELL

Robert F. Meldau, Bartlesville, Okla., assignor to Phillips Petroleum Company

Filed Jan. 6, 1969, Ser. No. 789,163
Int. Cl. E21b 43/25; F04f 1/20

U.S. Cl. 166—267

1 Claim



Production of oil from a pumping well and a flowing well wherein gas which is produced in the pumping well is conveyed to and utilized to facilitate production of oil from the flowing well. Flow from the flowing well may be initiated by pumping a light oil into the annulus. The method may be utilized with wells produced by fire flooding.

3,580,337

METHOD FOR STABILIZING THE MOBILITY OF POLYACRYLAMIDE SOLUTIONS FLOWING THROUGH POROUS MEDIA

William B. Gogarty, and Richard W. McAtee, Littleton, Colo., assignors to Marathon Oil Company, Findlay, Ohio

Filed Apr. 14, 1969, Ser. No. 816,047
Int. Cl. E21b 43/22

U.S. Cl. 166—273

27 Claims

Oil saturations are decreased by flooding the oil-bearing subterranean formation with an aqueous solution of relatively low salt content containing a high molecular weight partially hydrolyzed polyacrylamide having incorporated therein from about 1 to about 50 ppm of a divalent cation of a water-soluble salt. The divalent cation stabilizes the polyacrylamide in the aqueous solution with regard to mechanical degradation and such enables a bank of the aqueous solution to maintain its mobility while traveling through the formation.


3,580,338 METHOD FOR INJECTING FLUIDS INTO UNDERGROUND FORMATIONS HAVING DIFFERING PERMEABILITIES

Derry D. Sparlin, Ponca City, Okla., assignor to Continental Oil Company, Ponca City, Okla.

Filed Aug. 6, 1969, Ser. No. 847,897
Int. Cl. E21b 43/04

U.S. Cl. 166—276

4 Claims



A method of simultaneously injecting fluids into adjacent sections of subterranean formations of diverse permeability. A slotted sleeve or mesh cylinder is positioned in the wellbore opposite the formation and sand providing a low permeability pack is deposited in the annulus between the wellbore wall and the sleeve. Sand size is selected to provide a sand pack of permeability less than the lowest permeability of the formation. The sand pack may be consolidated with a resin. Fluid is injected down the interior of the sleeve, through apertures in the sleeve, through the low permeability, sand-filled annulus into the formation. Flow of fluids into the formation is more evenly distributed over the length of the wellbore section.

3,580,339


METHOD AND APPARATUS FOR COMBATTING AIRCRAFT FIRES

David Nance, P.O. Box 16291, Phoenix, Ariz.

Filed Jan. 30, 1969, Ser. No. 795,171
Int. Cl. A62c 3/06

U.S. Cl. 169—2

5 Claims



A method of combatting aircraft fires consisting of hovering an emergency aircraft, usually a helicopter, above an aircraft which has crash-landed or is in distress and is about to crashland, said helicopter thereby being positioned im-

mediately above the aircraft either during or immediately after the crash landing, and being specially equipped to emit clouds of flame-smothering vapors to envelop the aircraft in trouble, whereby either to prevent fires or to immediately extinguish fires which may start, thereby to save large numbers of lives and incalculable amounts of property damage, and the apparatus for performing said method.

3,580,340


ELECTRONIC MARKER ACTUATOR

David N. Brown, 1426 Erie St., Ottawa, Ill.

Filed Oct. 25, 1968, Ser. No. 770,740
Int. Cl. A01b 69/02

U.S. Cl. 172—126

3 Claims



An electronic marker actuator for use with an agricultural device such as a planter that is provided with a pivotally connected marker which may be disposed in a substantially vertical position at one time, and released so as to be disposed in a horizontal position at another time, with pushbutton means disposed on the planter and catch means normally maintaining the marker in an upright position, and solenoid means operatively connected to the pushbutton means so as to actuate the catch means and release the marker from its upright position to a horizontal position.

3,580,341


DOZER FOR A FARM TRACTOR

Kyle E. Terrell, and Darryl C. Rester, Yazoo City, Miss., assignors to Amco International, Yazoo City, Miss.

Filed Aug. 18, 1967, Ser. No. 661,607
Int. Cl. E02f 3/76

U.S. Cl. 172—805

15 Claims



A dozer for a farm tractor which includes a blade pivotally mounted at one end to one leg of a substantially U-shaped blade frame, and an extension arm selectively interconnected pivotally between the other blade end and the other leg of the blade frame to pivot and angularly dispose the blade toward one side of the tractor. The extension arm is selectively located in a reserve position between the blade and blade frame when the arm is not in use and when the said other blade end is attached to the said other leg. The extension arm is pivotally attached at one of a pair of longitudinally spaced, front and rear connection points, and the said other blade end and said other leg are attached at the other connection point when the extension arm is selectively pivoted behind the blade in the reserve position. A bearing means, pivotally connecting the bight of the blade frame to the chassis frame, includes a journal carried by a support


3,580,342 ROTARY TOOL ATTACHMENT FOR CHAIN SAW MOTOR

William F. Matthews, Rte. 2, Box 1061, Coos Bay, Oreg.

Filed May 12, 1969, Ser. No. 823,912
Int. Cl. B27b 17/00

U.S. Cl. 173—29

8 Claims



A rotary tool attachment for a chain saw motor drive unit, where such unit includes a motor housing and a motor-driven shaft protruding to one side of the housing and mounting a chain saw sprocket. The attachment comprises an elongated support adapted to be secured to the housing with such normal to the driven shaft of the drive unit. A tool-driving sprocket adjacent the end of the support remote from the driven shaft and in the plane of the chain saw sprocket is mounted on a power transmission input shaft which generally parallels the motor-driven shaft. The input shaft extends into a tool-housing assembly mounted on the remote end of the support and is connected through a power-transmitting means with right-angle drive train to a tool-driving head journaled on the tool housing assembly.

3,580,343


TRUCK WITH BUILT-IN WEIGHING MECHANISM AND LOAD HOLD-DOWN DEVICE

Dean M. Hogue, West Sacramento (10569 Dolcetto Drive, Rancho Cordova, Calif. 95670), and Carl M. Bender, 6007 Mack Road, Sacramento, Calif.

Filed Oct. 18, 1968, Ser. No. 768,787
Int. Cl. G01g 19/08, 23/02

U.S. Cl. 177—136

7 Claims



A truck chassis frame is provided with means for supporting a truck body thereabove, which means is utilized for operating a mechanism connected to a scale for weighing the body of the truck and the contents thereof. Before the truck operates in transit, the operator puts into operation means for fixing the truck body with respect to the chassis frame to prevent any movement of the truck body relative to the chassis frame during transit.

3,580,344

**STAIR-NEGOTIATING WHEEL CHAIR OR AN
IRREGULAR-TERRAIN-NEGOTIATING VEHICLE**


Johnnie E. Floyd, 2609 E. Side Drive, Austin, Tex.

Filed Dec. 24, 1968, Ser. No. 786,674

Int. Cl. B62d 57/02

U.S. Cl. 180-8-A

11 Claims



A vehicle including a variable-length central frame upon which is pivotally and rotatably mounted multiple wheel assemblies. A central propelling means powering the wheel assemblies. A central propelling means powering the wheel assemblies through a central differential operably connected to individual planetary gear set differential wheel transmissions driving individual spider arm wheel assemblies which rotate the peripheral wheels and/or spider-arms as the need demands to climb or descend stairs, negotiate uneven terrain, and execute various maneuvers. The operator preselects through a central control a desired maneuver or function. The vehicle senses the most appropriate mechanical function and performs the maneuver by the optimum safe means.

3,580,345

DISC BRAKE FOR TRACK-DRIVEN MACHINE


Archer W. Brown, Minneapolis; James L. Montgomery; Walter A. Beer, St. Paul, and Thomas J. Mero, Inver Grove Heights, Minn., assignors to American Hoist & Derrick Company, St. Paul, Minn.

Filed June 11, 1969, Ser. No. 832,203

Int. Cl. B62d 55/06

U.S. Cl. 180-9.2

11 Claims



A crane equipped with a crawler travel assembly having a pair of endless tracks trained about drive tumblers and idler tumblers. Separate self-contained disc brake units are drivably connected to the axles attached to the idler tumblers. The brake units have torque arms anchoring the units to the track frame.

3,580,346

TRUCK

Terrence F. McLaren, 5104 W. 105th place, Oak Lawn, Ill.

Filed Apr. 30, 1969, Ser. No. 820,364


Int. Cl. B62d 51/04; B62b 1/06

U.S. Cl. 180-19

3 Claims

A truck which is particularly adapted for use in hauling a bundle of bricks at a construction site. The truck includes a

flatbed to which is connected a pair of wheels. The flatbed has a plurality of pairs of spaced apertures, and a pair of cantilever arms is mounted in a selected pair of spaced aper-



tures. The arms may be readily inserted into open spaces in a bundle of bricks to support the bricks on the flatbed for hauling the bundle of bricks.

3,580,347

**TAPERED SPRING LEAF SUSPENSION FOR DRIVER
TANDEM AXLE ASSEMBLY**


Donald J. McGee, Troy, Mich., assignor to Dura Corporation

Filed Dec. 13, 1967, Ser. No. 690,164

Int. Cl. B60g 5/00, 19/02

U.S. Cl. 180-22

13 Claims



This specification discloses a suspension for a motor vehicle or trailer. The suspension comprises multiple tapered leaf springs fixed near their centers to an axle. At tareweight, the leaves are separated from each other near their ends. At full load, the leaves are compressed together near their ends. This provides a changing spring rate corresponding to variance of load. The arm of one leaf is rigid to horizontal compression, resisting acceleration and braking loads.

3,580,348

WHEEL COLLAPSIBLE FRAME

Rosario Di Biasi, Via G. Tell 2, Francoforte, Siracusa, Italy


Filed Apr. 7, 1969, Ser. No. 813,866

Claims priority, application Italy, Apr. 18, 1968, 15420A68

Int. Cl. B62k 15/00

U.S. Cl. 180-25

5 Claims



Collapsible frame for wheeled vehicles, comprising a main structure to which rear forks are pivoted and carry wheels, a front footboard carrying a steering wheel, and a seat.

3,580,351

SELF-PROPELLED GARDEN TRACTOR VEHICLE


Ignatius J. Mollen, Brillion, Wis., assignor to Ariens Company, Brillion, Wis.

Filed Jan. 7, 1969, Ser. No. 789,555

Int. Cl. B60k 17/28, 25/00

U.S. Cl. 180-53D

7 Claims



3,580,349

PORTABLE MOTORIZED CART


Edward N. Brennan, 9132 Edgewater Drive S. W., Tacoma, Wash., and Brian L. Brennan, 11616 Gorham, Los Angeles, Calif.

Filed Apr. 17, 1969, Ser. No. 816,892

Int. Cl. B62k 15/00

U.S. Cl. 180-27

4 Claims



A portable motorized cart useful for transporting a person and his golf clubs over a golf course, a person over a sand dune or beach, and/or a person around a industrial area, etc. The cart is conveniently adjusted to a smaller overall size for its over road transportation, for example, in the trunk space of an automobile. Compaction of the cart for such storage and travel involves tilting of a foot rest or floor, telescoping of frame members, tilting of steering and control means, and, as necessary, removal of a seat and a golf club rack.

3,580,350

VEHICLE POWER UNIT AND DRIVE TRAIN


Zora Arkus-Duntov, Grosse Pointe Shores, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Jan. 23, 1969, Ser. No. 793,311

Int. Cl. B60k 5/04, 17/34

U.S. Cl. 180-44

7 Claims



Arrangements for a vehicle power unit and drive train including a transversely mounted engine having a transmission mounted along one side thereof and a differential mounted along the other side. Power transfer means connect one end of the engine and transmission and may include a fluid coupling or torque converter, drive chain and mechanical clutch. A drive shaft passing under the engine crankshaft and preferably through the oil pan member drivably connects the transmission and differential. Alternative four-wheel drive arrangements provide a second drive shaft connected to a second differential with suitable differential or slip permitting drive means between the transmission and the two drive shafts.

3,580,352

STEERING TORQUE SERVO


Erling Hestad, Pontiac; Thomas E. Ritter, Utica, and Alton G. De Claire, Jr., Grosse Pointe Woods, Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Jan. 21, 1969, Ser. No. 792,466

Int. Cl. B62d 5/00

U.S. Cl. 180-79.2

3 Claims



A vehicle-steering system in which the steering column may be mechanically disengaged from the steering linkage after which steering control is accomplished by generation of electrical signals representing desired dirigible wheel position. Steering "feel" is provided by a controlled torque motor connected to the steering column through a torsion bar torque sensor.

3,580,353

REMOTE CONTROL FOR FUEL LINE SHUT-OFF

Kermith R. Thompson, 7722 Dexter Blvd., Detroit, Mich.

Filed Apr. 12, 1968, Ser. No. 720,900


Int. Cl. B60k 31/00

U.S. Cl. 180-98

4 Claims

This invention consists of a mechanism adapted to be connected into the fuel line of an internal combustion engine of

a vehicle between the fuel tank and the fuel pump, the aforesaid mechanism consisting of a two-piece vertically disposed metal receptacle that has its two sections screwed together on assembly. The uppermost one of the two piece receptacle contains an electric solenoid that is connected to an electric battery and to a signal receiver that receives its impulses from a transmitter located in another vehicle. The solenoid has a spring-loaded plunger that has its lower end extending down through a seal in the bottom of the upper-



most one of the two-piece receptacle and on into openings in the wall of a horizontally disposed Y-shaped tube that is located in the lowermost one of the two-piece receptacle. The side of the lower portion of the plunger has an opening therein through which fuel will flow when this invention is inactive; the lower end of the plunger is adapted to enter an opening in the wall of the angularly disposed portion of the Y-shaped tube. This invention also has a blinking light connected to the aforesaid signal receiver in such a location as to be seen outside the vehicle containing this invention.

3,580,354


VEHICLE TILT COMPENSATOR

Harlan Douglas Hewitt, 1210 Astor St., Chicago, Ill.
Continuation-in-part of application Ser. No. 665,056, Sept. 1, 1967, now abandoned. This application Jan. 21, 1969, Ser. No. 814,216

Int. Cl. B60r 21/00

U.S. Cl. 180-104

6 Claims



The following abstract is provided in accordance with Rule 72(b) and only for the purpose set forth therein.

In the present invention, apparatus is provided for use in combination with a vehicle to prevent the vehicle from overturning or to delay the overturning action long enough to allow the driver to leave the vehicle safely. The apparatus includes thrust producing means activated when the vehicle is inclined beyond the critical balance angle of the vehicle, or when the vehicle reaches some predetermined position in relation to the critical balance angle. The thrust produced is used to return the vehicle toward its normal upright position.

3,580,355 AUTOMATIC SPEED CONTROL APPARATUS FOR AUTOMOTIVE VEHICLES

Yasushi Kitano, Osaka, and Kozo Fujita, Kyoto, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Jan. 3, 1968, Ser. No. 695,419

Claims priority, application Japan, Jan. 13, 1967, Jan. 13, 1967, Jan. 16, 1967, Feb. 21, 1967, Aug. 15, 1967, Nov. 16, 1967, Nov. 16, 1967, 42/2869; 42/2870; 42/3551; 42/11663; 42/52814; 42/74123; 42/74124

Int. Cl. B60k 31/00

U.S. Cl. 180-105

9 Claims



An apparatus for the steady drive of an automotive vehicle at a predetermined speed setting, having a comparison means for comparing a signal representative of the vehicle running speed with a reference signal representative of the predetermined speed setting and a control means for driving a drive motor output regulator in a speed correcting direction depending on the difference between these two signals. In the apparatus, a third signal is introduced to shift the value of the difference signal and this shifted signal is used to attain the desired stabilization of the running condition of the vehicle.

3,580,356

PRESSURE WAVE SUSTAINED VEHICLE

Pieter VanStavern, Pijnacker, Netherlands, assignor to Nederlandse Organisatie voor Toegepast-Natuurwetenschappelijk Onderzoek ten behoeve van Nijverheid, Handel en Verkeer, The Hague, Netherlands


Filed May 27, 1968, Ser. No. 733,224

Claims priority, application Netherlands, May 29, 1967, 6707422

Int. Cl. B60v 1/00

U.S. Cl. 180-116

3 Claims



A method and devices are described for sustaining a vehicle by means of pressure wave pulses generated at the bottom side of the vehicle in the medium below the bottom.

The vehicle is hovering on a continuous sequence of spaced pressure waves which are moving substantially parallel to the bottom of the vehicle and it may be propelled by any appropriate means.

3,580,357

WAVE INTERFERENCE SILENCING SYSTEM

Donald R. Whitney, Birmingham, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed May 22, 1970, Ser. No. 39,705


Int. Cl. F01n 1/06, 1/12

U.S. Cl. 181-44

4 Claims

A wave interference silencing system for predictably attenuating sound waves in the frequency noise spectrum of

the exhaust gases from an internal combustion engine wherein a plurality of standardized serially connected attenuating sections includes a pair of discrete flow paths of differing acoustical lengths that are energy and flow compensated to establish actual sound propagational velocities so that the pressure waves of the individual paths are in phase



opposition at the exit end of the transited attenuating section so as to destructively interfere within a low-impedance coupling volume adjacent thereto. The coupling volume serves to equalize the vibrational energy between the separate flow paths and effect a flow stabilization at the entrance end of a succeeding attenuating section.

3,580,358

SAFETY ESCAPE BAG

Masatada Yamamoto, No. 2 Koujimachi Building 4-2, Koujimachi, Chiyoda-ku, Tokyo, Japan

Filed Aug. 8, 1969, Ser. No. 848,523

Int. Cl. A62b 1/20

U.S. Cl. 182-48

1 Claim



A safety escape chute having a series of pliant tubular columns connected by resilient portions made of spiral mesh so that when a first escaper is in the chute his weight so deforms the spiral mesh resilient portions downwardly that a second escaper cannot pass therethrough and thus cannot collide with the first escaper at the bottom of the chute.

3,580,359

LADDER FOR FRUIT PICKER

Andreys O. Akermanis, 3401 N. Westmoreland Drive, Orlando, Fla.

Filed Nov. 10, 1969, Ser. No. 875,296

Int. Cl. E06c 7/08

U.S. Cl. 182-49

6 Claims

An improved ladder for use by a fruit picker, involving the use of a removable, lightweight receiving basket utilized in conjunction with an elongate tubular member, and arranged to be interfitted therewith so that fruit placed in the basket can be guided into the tubular member and thence carried by this member to a receiving location near the bottom of the

ladder. My novel basket is very convenient for a fruit picker to use, and can be easily moved to any one of several loca-



tions on the ladder, depending on the height at which the picker may be working.

3,580,360

ELEVATOR SYSTEMS


Phillip C. Keiper, Shrewsbury, N.J.

Continuation of application Ser. No. 406,706, Jan. 28, 1954, now abandoned. This application Dec. 19, 1967, Ser. No. 691,913

Int. Cl. B66b 13/02

U.S. Cl. 187-29

17 Claims



A bank of elevator cars has a dispatching floor. At a landing the doors of an elevator car are held open for a time such as 5 seconds. However, if a person passes through the doorway, the remainder of the time is replaced by a short delay such as one-half second before the doors are reclosed. The time may be reduced to a still lower value by operation of a switch. If a car is at the dispatching floor it is prevented from starting during a dispatching interval.

3,580,361

DISC BRAKE CONSTRUCTION

Giorgio Eggstein, Ospedaletti San Remo, Italy, and Heinz Ungerer, Stuttgart-Zuffenhausen, Germany, assignors to Ernst Heinkel Aktiengesellschaft, Stuttgart-Zuffenhausen, Germany


Filed June 17, 1969, Ser. No. 833,997

Claims priority, application Germany, June 21, 1968, A5974/68

Int. Cl. F16d 55/224

U.S. Cl. 188-72.4

11 Claims



A disc brake comprises a rotor disc mounted for rotation about a predetermined axis. A mounting element straddles a section of the periphery of the disc and is adapted to be secured to a vehicle. A presser element also straddles the section and has portions located at the opposite sides of the disc. It is guided by the mounting element for movement axially of the disc. A friction pad is arranged between each of the portions of the presser element and the associated side of the rotor disc. Mounting means mounts each friction pad for free and independent sliding movement axially of the rotor disc between an inoperative position and an operative position in which latter it frictionally engages the rotor disc. Actuating means is associated with the presser element and one of the friction pads for urging the same in one axial direction to operative position while effecting concomitant movement of the presser element in opposite direction with resulting displacement of the other friction pad by the associated portion of the presser element to operative position.

3,580,362

DISC BRAKE


Edward J. Falk, St. Louis, Mo., assignor to Wagner Electric Corporation, Newark, N.J.

Filed Aug. 1, 1969, Ser. No. 846,721

Int. Cl. F16d 55/224

U.S. Cl. 188-73.4

29 Claims



A disc brake having a rotatable disc with a support plate extending across substantially a chordal portion of said disc on which a closed loop member is movable, and actuating means for moving a friction element in one direction into frictional engagement with one side of said disc and for mov-

ing said closed loop member in the opposite direction to frictionally engage another friction element connected therewith with the other side of said disc. The support plate includes a pair of anchor means adjacent to said disc one side and embracing said first named friction element and a third anchor means adjacent to said disc other side and connected between said closed loop member and said support plate.

3,580,363

HYDRAULIC GIMBAL LOCK


Moshe L. Plawner, Wayne; Vincent R. Vento, Morris Plains, and Abraham Gordon, Teaneck, N.J., assignors to the United States of America as represented by the Secretary of the United States Air Force

Filed Nov. 19, 1969, Ser. No. 878,116

Int. Cl. F16d 51/00

U.S. Cl. 188-74

8 Claims



An improved lock is disclosed, as applied to the elevation gimbal of a large telescope installation. Hydraulic pressure is employed firmly and simultaneously to force a number of contact members against a stationary surface of circular configuration and forming part of the fork gimbal or yoke pedestal. The hydraulic pressure is made effective by the use of a bellows system in which each bellows carries a contact head positioned a short distance from the stationary surface and the bellows are equally spaced from one another. A solenoid having a movable core and controlled from a position near the eyepiece of the telescope is employed to operate a miniature hydraulic pump which feeds oil under pressure simultaneously to each of the bellows. The latter elongate and press firmly against the stationary surface and at the same time, the motor which drives the gimbal to which the telescope is attached, can be declutched so that instant braking is effected. There is no overrun and the telescope remains strictly in line with the star being sighted when the control is operated.

3,580,364

STABILIZATION PENDULUM SYSTEM

Cornelis M. Verhagen, Heemstede, Netherlands (c/o Datawell N.V., Zomerluststr. 4, Haarlem)

Filed Feb. 5, 1969, Ser. No. 796,830

Claims priority, application Netherlands, Feb. 14, 1968, Nov. 29, 1968, 68 02128; 68 17189


Int. Cl. F16d 57/00

U.S. Cl. 188-87

17 Claims

Stabilization pendulum system comprising a vessel filled with a liquid, an object immersed in the liquid, the weight of the object differing very little from the weight of the displaced liquid, and the object containing electrical measuring equipment, the system also including a suspension means attached to the vessel. The suspension means includes a suspension thread one point along the length of which is

fixed, the object attaching to and suspending from the thread. The thread includes a free suspending portion between a point of the vessel and a point of the object, and further includes one or more electrical connectors integral therewith which serve as electrical connections for the measuring equipment. The suspension means also includes a



guiding body, the portion of which is nearest the object defines a guiding surface that includes a bore extending into the guiding body, the free suspending portion of the thread running through the bore whose diameter gradually increases in a direction toward the object. The thread also extends beyond the point of the vessel in a direction away from the object.

3,580,365

AUTOMATIC ADJUSTMENT MECHANISM PARTICULARLY FOR BRAKES


Ludwik S. Bialkowski, Troy, Ohio, assignor to The B. F. Goodrich Company, New York, N.Y.

Filed May 19, 1969, Ser. No. 825,717

Int. Cl. F16d 65/54, 55/18

U.S. Cl. 188-196P

8 Claims



A brake retractor assembly in which the automatic adjustment mechanism has a plurality of leaf springs in slidable engagement with the retractor rod and a spring engaging member on the rod is disposed so that sliding movement does not occur during retraction of the braking members and limited sliding movement does occur during actuation of the brake providing positive adjustment of the brake to compensate for wear and other changes.

3,580,366

BRAKE RETRACTOR RESETTING MECHANISM

C. Lucas Plaat, and Donald F. Linn, Troy, Ohio, assignors to The B. F. Goodrich Company, New York, N.Y.

Filed May 21, 1969, Ser. No. 826,418


Int. Cl. F16d 65/54, 55/18

U.S. Cl. 188-196

1 Claim

A brake retractor assembly in which the automatic adjustment mechanism has a locking plate carried by a sleeve member surrounding the retractor rod and held in tilted locking position during brake retraction and in which the locking plate is automatically moved into unlocked position during brake actuation when the rod is moved beyond the normal brake release clearance distance. A return spring

connection between the rod and sleeve member resets the rod automatically to its original position in the sleeve



member upon movement of the locking plate to the unlocked position when the brake lining needs replacement.

3,580,367

UNIVERSAL MOUNTING PLATE AND CONSTRUCTION METHOD


Richard H. McCarthy, Milwaukee, Wis., assignor to Stearns Electric Corporation, Milwaukee, Wis.

Filed Dec. 19, 1968, Ser. No. 785,320

Int. Cl. F16d 65/02

U.S. Cl. 188-206

2 Claims



Exemplification consists of a caliper brake end plate which also serves to mount the brake from a motor shell or the like. To hold the plate securely on motors having mounting bolts which are on bolt circles of differing radii, the plate is correspondingly arcuate about predetermined centers offset from the plate axis according to a formula.

3,580,368

DISC BRAKE COOLING MEANS AND PUMP DRIVE MECHANISM

Burnette Heck, Bloomfield Hills, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed June 2, 1969, Ser. No. 829,330


Int. Cl. F16d 65/84

U.S. Cl. 188-264

4 Claims

A liquid-cooled disc brake wherein the cooling liquid is pumped through the brake by a small high-speed rotary im-

PELLER pump driven by the rotating hub of the wheel to be braked. The pump drive uses the disc pack to provide a



clutch drive when the brake is energized and a slower speed viscous shear drive when the brake is released.

3,580,369

LIQUID-COOLED DISC BRAKE ASSEMBLY


Burnette Heck, Bloomfield Hills, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed June 27, 1969, Ser. No. 837,097

Int. Cl. F16d 65/84

U.S. Cl. 188-264

4 Claims



3,580,371

SELF-SYNCHRONIZING CLUTCH


Harold O. Kron, Philadelphia; John K. Liu, Valley Forge, and Edward Behnke, King of Prussia, Pa., assignors to King of Prussia Research and Development Corporation, King of Prussia, Pa.

Filed Oct. 16, 1969, Ser. No. 866,916

Int. Cl. F16d 23/04, 23/10

U.S. Cl. 192-18A

9 Claims



3,580,370

AUTOMATIC ACCELERATOR SAFETY DEVICE


James Elvin McCammon, 224 1/2 E. Broadway, West Memphis, Ark.

Filed Aug. 29, 1968, Ser. No. 756,740

Int. Cl. F16d 67/00

U.S. Cl. 192-3

2 Claims



My invention is an Automatic Accelerator Safety Device, a means for braking and accelerating an automobile equipped

with an automatic transmission, where the optional phases speed, and direction, are manually controlled, and the remaining functions are automatic. With the L-shaped braking pedal and the L-shaped accelerator pedal mounted on the inner side of the front dash panel, or the braking and accelerator treadle means, each the width of a shoe, mounted on the sloping floor boards, the braking means being activated by action of the left foot depressing the left or brake pedal or left treadle means, with the accelerator means being activated by like action of the right foot depressing the right accelerator pedal or right treadle means, disengaging the accelerator by action of a notched ratchet camlike face at the point where said brake pedal joins the connecting shaft, said shaft journaled in an inner sleeve, same journaled in an outer sleeve, same journaled in a bearing mounted on the motor side of the automobiles front dash panel, to the accelerator arm, engaging a like notched ratchet camlike edge of the end of a sleeve extending thru and journaled in same bearing and secured to the accelerator arm, same sleeve and arm rotating on connecting shaft, driving same accelerator arm out of mesh, disengaging notched ratchet camlike clutch face of the accelerator pedal rotating on outer sleeve said shaft, rendering same accelerator arm inactive, same remaining idle, held in place by a spring means as it is disengaged from the accelerator pedal means, until the braking means, the pedal or treadle is released by the left foot being removed, thus the accelerator arm connecting with the carburetor engages the accelerator pedal or treadle by action of a spring means, driving the notched ratchet camlike face clutch means into engagement, activating the accelerator pedal or treadle when the right foot is depressed or applied. This being the safety feature of my invention, as the automobile cannot be accelerated when the brake is depressed or applied.

3,580,372

CLUTCH WITH ADJUSTABLE CENTRIFUGAL PRESSURE ASSIST LEVERS


Paul J. Schiefer, Sherman Oaks, and James D. McFarland, Jr., Chatsworth, Calif., assignors to Schiefer Manufacturing Company, Monterey Park, Calif.

Filed May 26, 1969, Ser. No. 827,691

Int. Cl. F16d 43/06

U.S. Cl. 192-105

9 Claims



A centrifugal pressure assist type clutch utilizes the constant force of compression springs and a variable dynamic force to load a pressure plate against a driven disc. The clutch is adjustable to vary the dynamic loading of the pressure plate on the driven disc and therefore the engagement force of the clutch with a flywheel. The clutch has a plurality of radially disposed release fingers pivotally secured to a clutch cover in a common plane normal to the axis of rotation of the clutch. The fingers are also pivotally secured to the pressure plate. Each finger has a lever portion which extends radially inward from the finger's pivotal connection to the clutch cover for selective engagement by a clutch release bearing. Each finger also has a centrifugal weight to create a moment which is a function of the rotational speed of the finger that tends to pivot the finger about the pivotal connection to the clutch cover and force the pressure plate against the driven disc. The adjustment of the dynamic loading is effected through movement of the position of the fingers' pivot axes on the clutch cover relative to the finger pivot points on the pressure plate and therefore the moment of the fingers at a given rotational speed.

3,580,373

PORTABLE RAMP


Stanley A. Stickle, Anaheim, Calif., assignor to Clark Equipment Company

Filed Nov. 21, 1968, Ser. No. 777,564

Int. Cl. B65g 11/00

U.S. Cl. 193-5

2 Claims



A portable ramp having a plurality of elongated floor members with devices for detachably securing the floor members together in side-by-side relation to form a complete floor portion. A transverse member is detachably secured to the floor member at one end thereof and to a vehicle and another detachable transverse member is detachably secured to the floor portion at the other end thereof.

3,580,374

BOBBIN ORIENTING


Charles W. Brouwer, East Greenwich, R.I., assignor to Leeson Corporation, Warwick, R.I.

Filed Jan. 8, 1969, Ser. No. 789,758

Int. Cl. B65g 11/20

U.S. Cl. 193-43

2 Claims



A device for orienting bobbins having opposite ends of different sizes. A gauge is provided for receiving only the smaller end of the bobbin. As the bobbin is delivered to the device either the larger or the smaller end may be presented to the gauge. In the event that the smaller end is presented to the gauge the bobbin is supported solely on a trap door which opens so that the smaller end of the bobbin pivots about the gauge as the bobbin is discharged large end downward. If the larger end of the bobbin is presented to the gauge, the smaller end is above an abutment with an intermediate portion of the bobbin supported by the trap door so that when the trap door is opened the smaller end pivots about the abutment and again the bobbin is discharged larger end downward.

3,580,375

SOD-HANDLING MACHINE


John F. Nunes, Jr., 2037 Loquat Ave., Patterson, Calif.

Filed Mar. 3, 1969, Ser. No. 803,825

Int. Cl. A01b 45/04; B65g 65/06

U.S. Cl. 198-8

5 Claims



For picking up precut sod from the ground or other support surface, the lower one of a pair of cyclically driven carriers first nudges the transverse edge of the sod upwardly into engagement with a rearwardly moving reach of an upper cyclic carrier. The confronting reaches of the upper and lower carriers engage opposite surfaces of the slab of sod to feed the sod upwardly into the machine for handling.

3,580,376

ESCALATOR SYSTEM HAVING FAULT INDICATOR

Richard C. Loshbough, Toledo, Ohio, assignor to Reliance Electric Company, Toledo, Ohio

Filed Jan. 2, 1969, Ser. No. 788,474


Int. Cl. B66b 9/12

U.S. Cl. 198-16

8 Claims

An escalator system having a safety circuit to prevent operation under unsafe conditions and including a trouble indicator arranged to respond to any of a plurality of trouble-sensing switches in an escalator control circuit and structure. Two indicators are provided for each trouble condition, one which is actuated while trouble persists and the other is latched to retain an indication of trouble after the sensing

circuit has been reestablished whereby an indication of a currently existing trouble condition is augmented by an indication of a previously existing trouble condition. Adv-




vantageously, the indicator can be connected and disconnected from the escalator system and is mounted in a portable case.

3,580,377

CONVEYOR ARTICLE TRANSFER APPARATUS
Arthur H. Kiehl, 708 Rancho Drive, San Luis Obispo, Calif.
Filed Jan. 15, 1969, Ser. No. 791,373
Int. Cl. B65g 47/00

U.S. Cl. 198-20

13 Claims



This apparatus is for automatic transfer of articles from one conveyor to an adjacent second conveyor and it includes frame means positioned between the conveyors and having endless band means journaled thereon for movement from adjacent one conveyor to a point adjacent the second conveyor. Pickup means are carried by the band means to engage an article on the one conveyor and move it to a point adjacent the second conveyor where article deposit means engage the article on the pickup means and disengage it therefrom. Control means are provided to operate the article deposit means and place an article thereon onto a support on the second conveyor, and subsequently, by a similar apparatus, to return the article and normally its carrier means to its original position on the first conveyor.

3,580,378

AUTOMATIC HANGER DISCHARGE
Erik J. Pedersen, 1875 Conn. Ave. N.W. Suite 1205, Bethesda, Md.


Filed Nov. 14, 1968, Ser. No. 775,682
Int. Cl. B65g 47/61, 47/36, 47/46

U.S. Cl. 198-25

9 Claims

Hangers such as conventional coat hangers are suspended from a rod carried by a first conveyor. An end of a second conveyor having a toothed rotary transfer element and a guide means is swung into position along the rod. The guide means aligns the hangers on the pipe so that they may be engaged by the teeth of the transfer. As the transfer rotates, it lifts the hangers one at a time from the rod and deposits the

hangers on a continuously moving band which is exposed along an upper surface of the second conveyor. The band




carries the hangers along the second conveyor and drives the rotary transfer element.

3,580,379

PACKAGE TURNING DEVICE
Joseph Shuster, Saratoga, and Richard L. Brown, Sunnyvale, Calif., assignors to Icore Industries
Filed May 12, 1969, Ser. No. 823,840
Int. Cl. B65g 47/24, 47/26
U.S. Cl. 198-31AB

4 Claims



A package turning device wherein a package is supported on a series of carriers which are free to slide from side-to-side on rods carried by endless chains on each side of a conveyor. The turning action is provided by a switching mechanism whereby the front portion of the carton is conveyed in one direction by a series of carriers while the rear portion of the package is supported on carriers which are switched to a different direction, so that as the package travels it is turned about 90° to its previous orientation. In a preferred embodiment of the device, two lanes are provided so that a series of packages in single file are divided into two files with the packages turned at 90° to their former orientation.

3,580,380


METHOD OF AND APPARATUS FOR ORIENTING INDICIA BEARING CYLINDRICAL OBJECTS
Bryce W. Phillips, Henrico County, Va., assignor to Reynolds Metals Company, Richmond, Va.
Filed Sept. 11, 1968, Ser. No. 759,139
Int. Cl. B65g 47/24; G01n 21/28

U.S. Cl. 198-33

15 Claims

Indicia bearing cylindrical objects are oriented prior to being grouped and packaged so that the oriented objects provide their own advertising. In one embodiment, the objects are both rotated and translated as they traverse a plurality of inspection stations, each of which inspects less than a complete revolution of the object but the total of which inspects more than a complete revolution. Whenever any station produces a coincidence signal, rotation of the object is

stopped to permit oriented grouping. In another embodiment, the objects do not rotate until after a coincidence signal is produced by comparison with a segment of the




decorated object. Thereafter, a measured rotation is imparted to the object so that it is positioned in a desired orientation for grouping.

3,580,381

APPARATUS AND METHOD FOR LEVELLING DRUPE HALVES AND THE LIKE
George E. Kilner, Alameda, Calif., assignor to Filper Corporation, San Ramo, Calif.
Filed May 15, 1969, Ser. No. 825,005
Int. Cl. B65g 47/24

U.S. Cl. 198-33

7 Claims




Apparatus and method for automatically orienting and conveying hemispherical objects each having a planar surface opposite to a hemispherical surface so said planar surfaces, when facing generally upwardly, but if slanted relative to horizontal, will automatically position themselves, while conveyed along a path of travel, so their planar surfaces are horizontal.

3,580,382

SIGNAL DISABLING DEVICE
Richard E. Nearman, Mount Airy, Md., assignor to Eaton Yale & Towne Inc., Cleveland, Ohio
Filed Nov. 14, 1968, Ser. No. 775,883
Int. Cl. B65g 43/00

U.S. Cl. 198-38

7 Claims




A signal disabling device for a carrier identification signaling plate used in a conveyor system is described herein. The

disabling device of the present invention has a base, a signal indicia mounting means pivoted in the base and held against spring force in a first signal operative position by a latch on a lever. When the lever is tripped, the indicia mounting means is unlatched and is automatically moved into a second inoperative position.

3,580,383

VARIABLE PITCH CHAIN ASSEMBLY
Jurjen Van Der Wal, LaMirada, Calif. (1819 Port Stirling Place, Newport Beach, Calif. 92660)
Original application Jan. 24, 1968, Ser. No. 703,224. Divided and this application Sept. 29, 1969, Ser. No. 870,375
Int. Cl. B65b 9/12; B65g 15/02, 21/12
U.S. Cl. 198-16

45 Claims




A variable pitch chain link assembly adapted to be operated in tension from a single driving source. Different portions of the chain assembly travel simultaneously at different speeds varying as widely as six to one using a driving power source operating at uniform speed. Basically a single chain assembly suffices to practice the fundamental principles of the invention. A simple link chain is provided equipped with rigid arms projecting from the opposite sides thereof and each effective in cooperation with cam means confined to the related side of the chain to flex the chain linkage either in a direction to shorten or to lengthen the chain pitch depending upon the contour of the cam means. The rigid arms are so arranged as not to pivot across the plane of advance thereby permitting free access to the chain in this plane for connection of other equipment in a wide range of useful operating environments for the invention chain assembly.

3,580,384

MATERIAL FEEDING APPARATUS
Robert J. Pingree, Torrance, Calif., assignor to Ameron, Inc., Monterey Park, Calif.
Filed Jan. 27, 1969, Ser. No. 794,194
Int. Cl. B65g 33/26


U.S. Cl. 198-64

6 Claims



Screw conveyor means for elevating a relatively thick wet fluid substance, such as cement mortar, in which a first conveyor screw feeds toward a conduit of less diameter containing a second conveyor screw connected to the first by a universal joint located at a point ahead of a converging conduit section at the intake end of the conduit.

3,580,385
DOUGH FEEDING APPARATUS
 Daniel T. Thompson, 10584 Bradbury Road, Los Angeles, Calif.
 Filed Dec. 23, 1968, Ser. No. 785,932
 Int. Cl. B65g 37/00
 U.S. Cl. 198—103 9 Claims




An apparatus for transporting a plurality of divided elements of a tacky dough substance to a predetermined location where the elements are shaped into toroids. An impelling mechanism consisting essentially of driven impeller wheels is associated with the apparatus. The wheels engage and impel the elements from their predetermined location of a conveying portion of the apparatus at a uniformly predetermined rate, to a toroid-forming machine. The use of the impelling mechanism avoids pileup of one element upon another in the toroid-forming machine by overcoming the normally adhering characteristics of the elements to the material of the conveying portion of the apparatus, brought about by the normally tacky nature of the elements. The impelling mechanism, therefore provides only one element at a time through a feeder to a toroid-forming portion of the toroid-forming machine, thereby resulting in a toroid of uniform size and shape. The use of the impelling mechanism further prevents clogging of the toroid-forming machine by enabling only a single element at a time to be fed to this machine, thereby improving product reliability and reducing the rejection rate of the manufactured toroids.

3,580,386
PORTABLE ELEVATOR FOR TOBACCO STICKS
 Marcel M. Arnould, Newark, N.J.; John C. Ward, Jr., Clarendon; William Floyd Ray, Tabor City, N.C., and Boleslaw L. Budzyn, Passaic, N.J., assignors to Penstar Industries, Inc., South Plainfield, N.J.
 Filed Apr. 1, 1969, Ser. No. 812,179
 Int. Cl. B65g 15/00
 U.S. Cl. 198—131 9 Claims


A tobacco stick elevator having a pair of transversely spaced uprights with plates joining the top and bottom ends of the uprights. A motor driven endless conveyor chain passes around sprockets on the top and bottom plates. Longitudinally spaced socket bucket structures are fixed on the chain for removably receiving sticks loaded with tobacco leaves. Step units are fixed longitudinally along the uprights extending from one side thereof. A carriage is fixed on the uprights on the other side thereof adapted to ride on a track

on a horizontal beam. A spacer frame is provided to hold the uprights away from a vertical supporting surface. Looped



handles are also provided for protecting the motor mounted on the bottom plate.

3,580,387
CONVEYOR ARTICLE SUPPORT APPARATUS
 Jonathan W. King, Jr., Niles, Ohio, assignor to Georgia Pacific Corporation, Portland, Oreg.
 Filed Jan. 23, 1969, Ser. No. 793,372
 Int. Cl. B65g 17/20
 U.S. Cl. 198—178 11 Claims




The conveyor article support apparatus relates to a driven conveyor moved through a fixed path and a plurality of hanger means pivotally attached to the conveyor and dependent therefrom, the hanger means including a movable article-piercing means, and control means for the article-piercing means movably positioned in the hanger means and having a control member operatively connected to the control means to move the article-piercing means to and from operative positions. Inclined plane means are fixedly positioned adjacent the conveyor path to engage the control member for moving the article-piercing means to and from operative positions for securing articles to the hanger means.

3,580,388
ATTACHMENTS FOR A FLEXIBLE BELT
 Baird E. Resener, Indianapolis, Ind., assignor to Amsted Industries Incorporated, Chicago, Ill.
 Filed Mar. 3, 1969, Ser. No. 803,776
 Int. Cl. B65g 15/42, 19/00
 U.S. Cl. 198—198 8 Claims


A wire member is secured to a belt by tangs projecting into

holes in the sides of the belt. Attachments are secured to the wire member proximate the upper surface of the belt. The



belt may have notches in its sides to retain the wire member flush with the side of the belt.

3,580,389
SCREW CONVEYOR
 Friedrich Karl Nonnenmacher, Frankfurt am Main, Germany, assignor to Metallgesellschaft Aktiengesellschaft, Frankfurt am Main, Germany
 Filed Jan. 7, 1969, Ser. No. 789,508
 Claims priority, application Germany, Jan. 25, 1968, P 1,653,872.0
 Int. Cl. F28f 5/06
 U.S. Cl. 198—213 6 Claims




One of two parallel screws rotatable in the same direction in a screw conveyor is rotatable at different speeds from the other screw. This periodically brings the threads of one screw into wiping and cleaning engagement with the threads of the other screw.

3,580,390
PLASTER COLORANT SYSTEM
 John D. Shull, Jr., Tonawanda, N.Y., assignor to National Gypsum Company, Buffalo, N.Y.
 Filed Feb. 20, 1968, Ser. No. 706,920
 Int. Cl. B65d 81/00, 85/00
 U.S. Cl. 206—46 5 Claims




A set of water-soluble film packets each containing one of several available finely ground pigments and, when so desired, an additional amount of finely ground white extender, which are added singly or in any desired multiples to a container of gauging water to which is added a readily available standard quantity of dry cementitious powder, such as plaster, for providing controlled pigmented plaster for precolored plaster walls.

3,580,391
SOLID-STATE PULSED ELECTRONIC CONTROL FOR HIGH-SPEED CONVEYOR SORTING DEVICE
 Derwood F. Littlefield, Ballston Spa, N.Y., assignor to General Electric Company, Detroit, Mich.
 Filed Oct. 24, 1969, Ser. No. 869,120
 Int. Cl. B07c 5/342
 U.S. Cl. 209—73 15 Claims



This invention comprises a static electronic control for a high-speed conveyor sorting device of the type having a plurality of serially arranged, electrically operable diverter pins which are selectively raised and lowered between the rollers of at least two conveyor paths to selectively control which conveyor path a particular carton passing through the device is caused to follow. For this purpose a classifying signal is developed by a code reader, carton size measuring circuit, or the like for developing signals indicative of the classification and hence which conveyor path cartons or other objects are to follow. In addition, electro-optical scanning devices are provided for identifying the position or location of a carton traveling along the conveyor sorting device and for developing electric signals indicative of such positions. The electric signals thus developed are processed in a logic circuit which derives output pulsed electric signals that can be applied to the actuating solenoid of a clutch release mechanism or a brake release mechanism of a constant speed apparatus for raising and lowering diverter pins along the conveyor path selectively in accordance with the pulsed electric signals supplied from the static electronic control.

3,580,392
METHOD AND APPARATUS FOR REMOVING A FLACCID ARTICLE FROM A SUPPORT SURFACE
 Leslie Starbuck, Nottingham, and Arthur F. Whymark, Loughborough, England, assignors to Speizman Industries, Inc., Charlotte, N.C.
 Filed Aug. 19, 1969, Ser. No. 851,222
 Int. Cl. B07c 3/06
 U.S. Cl. 209—74 21 Claims



Method and apparatus for removing a stocking or the like from a support surface (i.e., conveyor) on which the stocking is positioned with an end portion thereof hanging from the

edge of the support surface, including a pair of clamping elements and an operating arrangement therefor which initially disposes them at an open position with the hanging portion of the stocking located therebetween, then closes the clamping elements to grasp the hanging portion, then moves the clamping elements generally horizontally so as to pull the stocking off the support surface, then opens the clamping elements to release the stocking, and then returns the clamping elements to their initial position. Preferably, the clamping elements are disposed vertically to receive and grasp the stocking, and are moved to an inclined disposition when the stocking is released, the inclination being in a direction to cause the stocking to slide from between the open clamping elements. Also, the clamping elements are preferably moved from the support surface with sufficient speed to maintain the lengthwise extent of the stocking in a horizontal plane whereby the extended stocking can be collected in a receiver located beneath the path of movement of the clamping elements.

3,580,393

DEVICE FOR COLLECTING SOLIDS IN A CENTRIFUGE
Ernst Ruegg, Kusknacht, Switzerland, assignor to Escher Wyss Limited, Zurich, Switzerland


Filed Oct. 17, 1969, Ser. No. 867,169

Claims priority, application Switzerland, Oct. 30, 1968, 16161/68

Int. Cl. B01d 21/26

U.S. Cl. 210-369

7 Claims



In a continuously operating centrifuge for dewatering solids, having a housing and a drum rotatable in said housing, and a member made of flexible material, mounted in said housing, and surrounding at least part of the periphery of said drum, so that said solids issuing from said drum impinge on said member, the improvement that said member is elongated and includes a portion in the form of a toric segment, the toric segment extending substantially in the peripheral direction of said drum, and that said member is mounted to be rotatable in said housing about its longitudinal axis.

3,580,394

ARTICLE HOLDER

Michael Elliot, 513 W. 54th St., New York, N.Y.

Filed May 16, 1969, Ser. No. 825,357


Int. Cl. A47f 7/00

U.S. Cl. 211-60

6 Claims

A holder for knives or the like implements, serving to maintain them with their cutting edges in a protected enclosed position, and permitting ready selective insertion and removal of the knife, or the like from the holder. The holder is formed by a block member having an interior vertically extending channel therein defined by a vertically extending surface spaced from an inclined surface, with the lower end of the inclined surface closer to the vertically extending surface. A locking member is loosely positioned in said channel for sliding between said surfaces, and a stop member at the lower end of said channel limits the downward movement of said locking member to prevent its being wedged into a jammed position between said surfaces, whereby a knife or the like inserted into said channel will be engaged by said

locking member against said vertical surface. The locking member is formed with a chamfered leading edge serving the



twofold function of implementing insertion of the knife blade and permitting honing of the blade.

3,580,395

INTENSIVE CARE APPARATUS

Robert L. Weaver, 153 Carol Lane, Toledo, Ohio, and Frank D. Myrice, 4700 Temperance Road, Ottawa Lake, Mich.

Filed June 30, 1969, Ser. No. 821,303

Int. Cl. A47f 5/08

U.S. Cl. 211-87

2 Claims



Medical intensive care apparatus, capable of versatile accommodation to different spacial configurations which, as a unit, provides an adequate source of oxygen and a variety of complete suction requirements for installation adjacent to or within a wall at a position of convenience for a patient and medical personnel.

3,580,396

SILENT BUTLER


Johannes Dietz, P. O. Box 61,800, Caracas, Venezuela

Filed Mar. 4, 1970, Ser. No. 16,305

Int. Cl. A47f 5/08

U.S. Cl. 211-88

5 Claims



A silent wall butler has a base member mountable on an upright surface of a support. A tray member is carried by said base member upwardly spaced therefrom. A first tubular hanger is connected to the base member projecting therefrom and being turnable about an upright axis. An arcuately curved second tubular hanger is rigidly mounted on the base member projecting beyond opposite lateral sides

thereof. One or more third hangers are also provided on the base member and have end sections extending beyond the aforementioned opposite lateral sides of the base member.

3,580,397

UTILITY ROD AND MOUNTING CONSTRUCTION THEREFOR


Lee Triplett, Salt Lake, Utah, assignor to Expando Products Company, Magna, Utah

Filed Aug. 5, 1968, Ser. No. 750,289

Int. Cl. A47h 1/08, 1/10; F16b 2/00

U.S. Cl. 211-105.4

1 Claim U.S. Cl. 213-76



The present invention relates to rod constructions and, more particularly, to a new and improved elongate rod construction wherein the apparatus disposed at each end thereof is easily secured to the rod and is provided with friction-lock means, both for rod retention and for exterior mount placement, such that the apparatus can be easily manipulated to accomplish selective securement of opposite ends of the rod structure to the mounting members employed. In the preferred embodiment of the invention the adjustment wheels or equivalent devices used at the rod ends may be employed, not only to friction-lock the compression sleeves of the rod construction to their mounts, but also to apply a thrusting force against the oppositely disposed mounting members such that the same are retained tightly against and in tight friction engagement with the wall surfaces with which they are associated.

3,580,398

SHELVING SYSTEM

Manfred Schafer, Oberes Gerstenfeld, Germany, assignor to Fritz Schafer K. G., Neunkirchen Kreis Siegen, Germany


Filed July 16, 1968, Ser. No. 745,270

Claims priority, application Germany, July 25, 1967, Sch 43062/34i Gbm

Int. Cl. A47b 9/00; A47f 5/00

U.S. Cl. 211-148

8 Claims



A shelving system consists of shelf units arranged in rows to form passages therebetween and floors or catwalks are

provided in the passages at a height which permits operators to walk beneath such floors, the floors preferably consist of gratings or grids supported by brackets hooked on to uprights forming part of the framework of the shelf units.

3,580,399


AUTOMATIC TRAINLINE CONNECTOR

Donald Willison, Lyndhurst, and Kenneth L. Depenti, Mayfield Heights, Ohio, assignors to Midland-Ross Corporation, Cleveland, Ohio

Filed Oct. 29, 1969, Ser. No. 872,036

Int. Cl. B61g 7/06

6 Claims



A railway automatic trainline connector has a connector head provided with a pair of forwardly extending and outwardly diverging gathering wings, with one of the wings being provided with a guide rib facing the horizontal plane containing the longitudinal axis of the connector.

3,580,400

ROTARY UNCOUPLING DEVICES


Kenneth L. De Penti, Mayfield Hts., Ohio, assignor to Midland-Ross Corporation, Cleveland, Ohio

Filed Apr. 10, 1969, Ser. No. 815,139

Int. Cl. B61g 3/08

U.S. Cl. 213-166

5 Claims



A coupler unlocking device for railway cars having a rotary coupler including a pivotally mounted arm connected to a coupler knuckle actuating mechanism and imposed in the path of movement of a bail type uncoupling rod assembly independently mounted on the end sill of the car. This improvement contemplates a preassembly of the coupler rotor and the operating arm and application of the rotor in interlock position with the knuckle actuating mechanism located within the coupler head, or removal of the rotor, without disassembly of the arm from the rotor.

3,580,401

MULTIPURPOSE AIR SUPPLY SYSTEM

Laddie L. Stahl, Rexford, N.Y., assignor to General Electric Company

Filed Dec. 12, 1968, Ser. No. 783,231


Int. Cl. B60r 3/04

U.S. Cl. 214-1BE

5 Claims

Air supply is provided by a network of longitudinal channel valves. Each channel valve includes a longitudinal channel member having an opening in the top wall thereof.

Another longitudinal member seated against the underside of the top wall hermetically seals the channel member except



when depressed by a plunger from an air cushion support vehicle or by fixed depressors.

3,580,402


APPARATUS FOR AUTOMATICALLY STACKING AND INVERTING STACKED UNITS OF SHEET MATERIAL
Ingvar L. Tolf; Vernon J. Herzog; Everett L. Miller, Battle Creek, and George L. Lightfoot, Bellevue, Mich., assignors to General Foods Corporation, White Plains, N.Y.

Filed Jan. 30, 1969, Ser. No. 795,187

Int. Cl. B65g 57/11


U.S. Cl. 214-6C

19 Claims




This specification discloses a machine for forming stacks or piles of sheet material, such as flat carton blanks (hereinafter also referred to merely as cartons), and delivering them in properly arranged and oriented condition to a receiving station where they are available for setup or shipment. Cartons are conveyed from a cutting press to an assembly magazine in one or more laterally spaced single file lines. Each line of cartons entering the magazine is jogged or shuffled to form a neat stack or pile on a vertically movable elevator in the magazine. In response to the action of sensing mechanism the elevator is lowered progressively carrying with it the piled cartons until a controlled separator is moved between adjacent cartons of the piled cartons and separates stacks of desired height or number of cartons therefrom, whereupon the elevator is lowered to a predetermined position. A horizontally movable pusher is then operative to push each stack beneath the separator from the elevator into an inverting turret and dispose it or them between opposed relatively movable clamping and conveying means carried thereby. The turret is rotated 180° thereby inverting the stacked cartons which are then unclamped and traveled by the turret conveying means out of the turret and delivered onto a receiving station. The turret is so designed that it accommodates itself to operate satisfactorily with cartons over a wide range of carton size and thickness, within the limits of the machine, which results in a machine having great versatility and capacity.

3,580,403
MATERIALS HANDLING APPARATUS
Thomas Lancashire, West Chester, Pa., assignor to The Boeing Company, Seattle, Wash.
Filed Oct. 30, 1968, Ser. No. 771,955
Int. Cl. B66c 1/00; B64c 1/22
U.S. Cl. 214-38 8 Claims



Materials handling apparatus for integrating a plurality of individual loads. A supporting structure includes a plurality of fingers which extend transversely in opposite directions from an elongated beam at spaced locations along the beam. Positioned in a substantially horizontal plane, the fingers are adapted to support individual loads such that they can be raised as a unit upon elevation of the structure. A cradle is provided for moving the supporting structure across a surface and, in a modified embodiment, the fingers can be folded to a retracted position for storage.

3,580,404
LOADING RAMPS FOR TRAILERS
William J. Moser, 2075 Leaf Terrace, Coos Bay, Oreg.
Filed July 31, 1969, Ser. No. 846,523
Int. Cl. B60p 1/44
U.S. Cl. 214-85 5 Claims



Ramp assemblies are disclosed mounted upon the rear of a lowboy-type trailer for loading construction equipment. Each assembly is of two hinged sections collapsible to a raised, stowed position by an arm engageable with both of the sections to lift same and to maintain same in a stowed position. A hydraulic circuit is included for selective control of each ramp assembly.

3,580,405
MULTIPLE V-BELT DRIVE FOR A CROWD MECHANISM OF A POWER SHOVEL
Charles R. Siegel, Cudahy, and Karl Schneider, Greenfield, Wis., assignors to Harnischfeger Corporation, Milwaukee, Wis.

Filed Apr. 23, 1969, Ser. No. 818,641


Int. Cl. E02f 3/00

U.S. Cl. 214-135

19 Claims


Crowd driving mechanism for the dipper stick of a power

shovel, and also including a multiple V-belt and means for creating a second stream of material by digging the angle side face of the pile over an upper area which extends above the



tensioning the same. An air supply inside the boom for cooling the belt and motor.


3,580,406
EARTHWORKING MACHINE
Jean-Pierre B. Bellart, Senlis, France, assignor to Societe Anonyme Poclain, Le Plessis, Belleville, France
Filed Aug. 18, 1969, Ser. No. 850,941
Claims priority, application France, Sept. 5, 1968, 165170
Int. Cl. E02f 3/00
U.S. Cl. 214-137 10 Claims



The invention relates to an earthworking machine in which an earthworking implement, such as a drag bucket, is carried by extensible and retractable means to effect forward and backward movement of the bucket, the invention consisting in an improved form of extensible and retractable means which comprises two pairs of arms pivoted together to form a deformable quadrilateral which is pivoted at one of its ends to the jib and has pivoted to its other end the bucket assembly.


3,580,407
METHOD OF RECLAIMING BULK MATERIAL
Fred T. Smith, Aurora, Ill., assignor to Barber-Greene Company, Aurora, Ill.
Original application Oct. 24, 1965, Ser. No. 504,739, now abandoned. Divided and this application June 4, 1968, Ser. No. 739,930
Int. Cl. B65g 65/28
U.S. Cl. 214-152 8 Claims

The present invention is directed to a method for converting a stockpile of material into a moving stream of material for loading into another area. More specifically, the method comprises digging into an angled side face of a pile at its lower end along a continuous path of the length of the side face, creating a first upward arcuate stream of material,




lower end, merging the two streams of material into a main stream which is directed angularly from the side face.

3,580,408
RECEPTACLE DISPOSAL CONTAINER ADAPTER
Augustus L. Newton, 211 Riverthorn Road, Baltimore, Md.
Filed Nov. 13, 1969, Ser. No. 876,441
Int. Cl. B65f 3/02
U.S. Cl. 214-302 5 Claims



An auxiliary device for adapting small containers to the hoist and dump arms of disposal vehicles is provided. A spanning bar to fit the usual load arms is provided with locking apertures to receive the narrower spaced lugs of containers for ready handling of same with the usual equipment.

3,580,409
FRUIT AND VEGETABLE JAR SUPPRESSOR DEVICE
Henry J. Soboleski, 1745 Kessler, South Bend, Ind.
Filed Oct. 9, 1969, Ser. No. 864,980
Int. Cl. B65d 51/14
U.S. Cl. 215-81 9 Claims



A fruit and vegetable jar suppressor device of a one-piece cup-shaped body construction having sidewalls which taper

inwardly and downwardly and having a bottom joined integrally to the lower edge of the sidewalls. The bottom preferably is concave upwardly and contains a center hole for the admission of liquid in the fruit or vegetable jar into the device while suppressing the fruit and vegetable solid material in the jar. The cup-shaped body is of flexible plastic material capable of adapting itself to jars with variations in the diameter of the opening.

3,580,410

COUPLING DEVICE FOR CONTAINER HANDLING SYSTEM


Andrew Abolins, Langhorne, Pa., assignor to Strick Corporation, Fairless Hills, Pa.

Original application June 12, 1967, Ser. No. 645,157, now Patent No. 3,460,867, dated Aug. 12, 1969. Divided and this application Feb. 13, 1969, Ser. No. 828,030

Int. Cl. B65j 1/02

U.S. Cl. 220-1.5

1 Claim



Herein are disclosed new and improved coupling means, and container assemblies and an article handling device which embody same, for use in a system for handling container assemblies, and particularly for transferring container assemblies to and from highway carriers, railway carriers and other mobile and stationary structures. The container assemblies are either of the typical, removable-bogey, highway trailer body type, or are containers with separable chassis equipped with the customary equipment for highway transportation.

3,580,411

CONTAINER HAVING MOVEABLE WALL


Oscar F. Mills, Grand Prairie, Tex., assignor to LTV Aerospace Corporation, Dallas, Tex.

Filed Feb. 13, 1969, Ser. No. 798,959

Int. Cl. B65d 7/00

U.S. Cl. 220-4

8 Claims



An open-top container or skid having a base, two spaced and parallel sidewalls, and at least one sidewall which is moveable between an upstanding position and a stored position, with the stored position being a position wherein said moveable sidewall lies flat against the base.

3,580,412
HINGE STRUCTURE FOR ELECTRIC POWER DISTRIBUTION BOX OR THE LIKE


Hubert L. Weiss, Los Angeles, Calif. (c/o American Construction Equipment Co., Inc. 5055 W. Jefferson Blvd.)

Continuation of application Ser. No. 724,187, Apr. 25, 1968, now abandoned. This application Nov. 10, 1969, Ser. No. 875,416

Int. Cl. B65d 43/16, 51/10

U.S. Cl. 220-35

7 Claims



A hinge structure is provided by hinge knuckle elements snapped into position at apertures of the members designed to be hingedly connected. The hinge knuckles are provided with stop flanges and spring means to secure the hinge knuckles in position. A straight hinge pin interconnects the knuckles and the members to be connected, and is restrained against longitudinal movement by the friction imposed by the lateral thrust of a cover closing spring.

3,580,413

CLEAR THERMOPLASTIC MULTI-PLY MEAT TRAY AND ABSORBENT STRIPS


John J. Quackenbush, Monroe, Conn., assignor to National Distillers and Chemical Corporation, New York, N.Y.

Filed Jan. 27, 1969, Ser. No. 795,141

Int. Cl. B65d 7/42

U.S. Cl. 220-83

8 Claims



A clear, plastic tray, and a method for the production thereof, intended for the packaging of food products, such as meats, and the like, where the package contents will be clearly visible. The tray is completely transparent and is produced from sheet material which includes a preinserted strip or plurality of strips of absorbent cellulosic material for the reception and retention of any fluid or fluids which may drain from the package contents subsequent to the packaging.

3,580,414

FUELING DEVICE FOR AUTOMOBILES AND THE LIKE

Irwin Ginsburgh, Morton Grove, Ill., and Hilbert J. Nebelsiek, Hammond, Ind., assignors to Standard Oil Company, Chicago, Ill.

Filed Dec. 20, 1968, Ser. No. 785,562


Int. Cl. B65d 39/02

U.S. Cl. 220-86

9 Claims

Our invention concerns a device adapted to be attached to the fill pipe of an automobile's gas tank and to receive the nozzle of a fuel dispenser. Its principal elements are: a cap

member having means which enable said cap member to be attached to the fill pipe, a passageway through the cap member which is adapted to pass the nozzle, and a closure member connected to one end of the passageway which seals said passageway, but which opens whenever the nozzle is in-



serted into the passageway. The passageway has one end protruding from the fill pipe and another end extending into the fill pipe. The closure member may be attached to either end, or two closure members can be employed, one attached to each end.

3,580,415

DECAL DISPENSING APPARATUS


Harvey T. Hollinger, Concordia, Kans.

Filed Aug. 11, 1969, Ser. No. 848,950

Int. Cl. B65h 5/28

U.S. Cl. 221-74

7 Claims



This invention relates to a dispensing apparatus operable to dispense decal members carried upon a roll of paper tape through the use of an actuator mechanism adapted to automatically pick up and hold the decals on longitudinal movement of the tape. More particularly, the dispensing apparatus includes an actuator mechanism provided with cooperating male and female actuator arms to grasp and hold the decal member until one desires to remove the same for applying to food products or the like.

3,580,416

METHOD AND APPARATUS FOR DISPENSING ICE CUBES AND THE LIKE

Walter H. Hoenisch, Albert Lea, Minn., assignor to King-Seeley Thermos Co., Ann Arbor, Mich.

Continuation-in-part of application Ser. No. 606,852, Jan. 3, 1967, now abandoned. This application Nov. 12, 1968, Ser. No. 775,094


Int. Cl. B65h 3/60

U.S. Cl. 221-203

89 Claims

A method and apparatus for transferring ice cubes and the like from a storage compartment to a remotely located

dispensing compartment, the apparatus comprising passage means extending between the storage compartment and dispensing compartment and means providing a flow of conveying fluid through the passage means of sufficient magnitude to cause ice cubes to be conveyed through the passage



3,580,417

MACHINES FOR PLANTING TUBERS AND THE LIKE

Peter Alfred Hobbs, St. Albans, England, assignor to National Research Development Corporation, London, England


Filed July 1, 1968, Ser. No. 741,759

Claims priority, application Great Britain, July 5, 1967, 31079/67

Int. Cl. B65h 5/00

U.S. Cl. 221-224

7 Claims



A machine for planting tubers, corms, bulbs or the like, such as potatoes, of the kind in which at least one coulter is adapted to draw a furrow in the soil as the machine is moved forward and means are provided for delivering a succession of the tubers from a supply carried by the machine on to driven belt means which are adapted to feed the tubers into furrow, has the belt means arranged to cause rotation of the tubers at least at some part of their travel along the belt means. The belt means may comprise a delivery trough of which one side at least comprises a continuous belt adapted to be driven at a speed related to the land speed of the machine but preferably both sides of the delivery trough comprise continuous driven belts and the belts are then arranged to be driven at substantially different speeds. The induced rotation of the tubers causes them to string out into line and substantially avoids the presentation of "doubles" to the furrow.

3,580,418

APPARATUS FOR FEEDING ROD STOCK AND THE LIKE


Johannes Werkmeister, Reichenbach (Fils), and Holger Scheler, Faurndau, Germany, assignors to Firma Hermann Traub, Reichenbach (Fils), Germany
Filed June 9, 1969, Ser. No. 831,349

Claims priority, application Switzerland, June 17, 1968, 8989/68

Int. Cl. B65g 59/00

U.S. Cl. 221—275

7 Claims



An apparatus for feeding rod-shaped workpieces by means of a feed rod along a trough-shaped channel in a guide rail to a machine tool. During the feeding operation the upper side of the channel in the guide rail is closed by a stationary cover rail, and when the channel is empty, the guide rail is lowered from the cover rail by a plurality of levers which are mounted at one lateral side of the rails so that a new workpiece may be inserted from a magazine rack which is mounted at the other lateral side of the rails.

3,580,419

METHOD AND APPARATUS FOR FEEDING AND COMPACTING FINELY DIVIDED PARTICULATE MATERIAL


Clarence F. Carter, Danville, Ill., assignor to Carter Engineering Company, Danville, Del.

Filed Apr. 2, 1968, Ser. No. 718,123

Int. Cl. B67d 5/88

U.S. Cl. 222—1

7 Claims



A method of feeding and compacting finely divided particulate material, which utilizes a rotating screw feeder for advancing the material along a sleeve passage provided by a stationary foraminous sleeve mounted closely about the screw feeder. The method includes the steps of advancing the particulate material axially along the sleeve with the interstitial air between the particles in the sleeve at an internal sleeve pressure. Suction pressure relatively lower than the internal sleeve pressure is applied to the exterior of the sleeve to withdraw air from between the particles of the material to effect compaction of the material. At predetermined times gas pressure relatively higher than the internal sleeve pressure is applied to the exterior of the sleeve to back-flush material from openings in the sleeve to prevent clogging thereof.

An apparatus for feeding and compacting finely divided particulate material, which includes a housing having fixedly mounted therein a tubular sleeve. The sleeve and housing define at least one closed hollow chamber extending about the sleeve with a plurality of perforations in the sleeve placing the interior thereof in fluid communication with the interior of the chamber. An axially extending screw feeder concentrically and rotatably mounted in the sleeve is adapted to advance material axially along the sleeve, with the interstitial air present between the particles of material in the sleeve at an internal sleeve pressure. Suction means in fluid communication with the chamber applies suction pressure relatively lower than the internal sleeve pressure to withdraw air from between the particles of material to affect compaction thereof. Gas pressure means in fluid communication with the chamber provides gas at a relatively higher pressure than the internal sleeve pressure at predetermined times to backflush particulate material from the perforations, to prevent clogging thereof.

3,580,420

EVACUATION SYSTEM FOR PIPELINE DISCHARGING PUMP


Garth P. Kennedy, and William E. Nelson, Oklahoma City, Okla., assignors to Corken Pump Company

Filed Jan. 27, 1969, Ser. No. 794,264

Int. Cl. B67d 5/04

U.S. Cl. 222—1

5 Claims



A vacuum relief valve installed on the suction side of a pump employed with a compartmented tank on a fuel delivery vehicle or the like to enable the pump and associated piping system to be completely purged of fuel that has been conveyed by the pump from one compartment to a delivery nozzle before the piping system for the pump is communicated with another compartment of the tank having a different fuel therein for eliminating contamination of one fuel with another during sequential delivery of various types of fuel from the various compartments of the multicompartiment tank to a delivery point.

ERRATUM

For Class 222—5 see:
Patent No. 3,579,964

3,580,421

FLUID DISPENSING APPARATUS INDICATOR SYSTEM

John H. Bickford, Middletown, Conn., assignor to Veeder Industries Inc., Hartford, Conn.

Filed Nov. 20, 1969, Ser. No. 878,319


Int. Cl. B67d 5/16

U.S. Cl. 222—27

30 Claims

A fuel dispensing system having an indicator subsystem with a liquid crystal indicating device adapted to be operated for displaying, one at a time, the established unit volume price of fuel, the volume of fuel delivered and the total cost of the fuel delivered. A sequencing switch provides for operating the indicating device to display the cost, volume and price information in sequence at the beginning and end of a fuel delivery and a manual selector provides for selectively operating the indicating device to continuously display the cost or volume or sequentially display the cost, volume and price during the delivery. The price is displayed between deliveries and a recycle button provides for temporarily displaying the cost, volume and price information both during

and between deliveries. A two-product dispensing system schematically shown in FIG. 2 comprises two indicator



subsystems and a manual selector for selection the product information to be displayed by each subsystem.

3,580,422

APPARATUS FOR ADDING FINELY DIVIDED SOLID MATERIAL TO A MIXTURE


Nelson Hartley, Towson, Md., assignor to Hartley Controls Corporation, Neenah, Wis.

Filed Nov. 25, 1968, Ser. No. 778,422

Int. Cl. B67d 5/56

U.S. Cl. 222—57

8 Claims



This disclosure relates to apparatus for adding both a liquid and a finely divided solid to a mixture and in which the quantity of finely divided solid that is added is measured in direct proportion to the liquid deficiency of the mixture and in which the mechanism for measuring out the addition of finely divided solid is directly responsive to a liquid deficiency sensing mechanism which operates a reversible motor. The motor turns a shaft which controls both the liquid deficiency make-up mechanism and the finely divided solid make-up mechanism. The device is particularly adapted for bond compensation in a foundry where the mixture is foundry sand, water, and bond.

3,580,423

CONTAINER CLOSURE AND APPARATUS FOR OPENING SAME


John M. Gilman, Cincinnati, Ohio, assignor to The Realistic Company, Cincinnati, Ohio

Filed Feb. 27, 1969, Ser. No. 802,821

Int. Cl. B67b 7/30

U.S. Cl. 222—81

6 Claims



A closure for a container which includes an impervious disc and can also include a resilient annulus overlying the mouth of the container. A retaining ring attached to the container adjacent the mouth having an inwardly directed flange overlies the disc and the annulus to hold the disc and the annulus firmly in assembled relation forming a seal with the mouth. A cap having a tubular spout with a pointed inner end perforates the disc to discharge contents of the container.

3,580,424

DISPENSING VALVE FOR A SEALED PRESSURIZED CONTAINER


Virgil Philipps, Chicago, Ill., assignor to Federal Auto Products Co., Inc., Chicago, Ill.

Filed Oct. 27, 1969, Ser. No. 869,592

Int. Cl. B67b 7/26

U.S. Cl. 222—89

5 Claims



A dispensing valve carried by a connector adapted to clamp upon the bezel of the container so as to center the valve thereon and to pierce and seal the closed top of the container.

The valve comprises a valve head, a penetrating dispensing tube and a seal. When the valve is clamped on to the bezel of the container the valve head is threaded through the clamping connector causing the seal to contact the top of the container at the point of penetration thereof by the dispensing tube. The valve and the connector can be removed and reused when the contents of the pressurized container have been dispensed.

3,580,425

BEVERAGE DISPENSER

Heiko T. DeMan, Morago, Calif., assignor to Electronic Dispensers International, Oakland, Calif.

Filed Sept. 26, 1968, Ser. No. 762,760


Int. Cl. B67d 5/56

U.S. Cl. 222—129.1


10 Claims

A beverage dispenser for selectively or concurrently dispensing syrup and carbonated water therefrom. The

discharge of such fluids from the dispenser is controlled by a pair of solenoid operated valves respectively associated with switches actuated by levers that depend from the dispenser adjacent the discharge nozzle thereof. The dispenser includes a body structure supporting the various functional components of the dispenser, and a resilient cover slidably related to the body structure is readily removable therefrom to




3,580,427
CREAM DISPENSER WITH PLEATED WALLS AND LIP TYPE OPENING
Robert E. Clarke, 1410 Saratoga Drive, Bel Air, Md.
Filed Nov. 8, 1968, Ser. No. 774,384
Int. Cl. B65d 37/00
U.S. Cl. 222—215 1 Claim



A cream dispenser in the form of a container of flexible material such as plastic having generally flexible top and bottom walls and pleated, collapsible sidewalls, an opening in one sidewall in the form of an elongated slit, flexible lips along the opposite sides of the slit, the lips normally closing the slit but being deflectable outwardly to permit discharge of the contents upon pressure being applied to container to collapse the same and said lips being deflectable inwardly upon insertion of a nozzle to recharge the dispenser and a removable closure for the opening.


provide access to such switch devices, valve parts, and the solenoid controls for the valves. The dispenser further includes a face piece cooperative with the cover in enclosing such functional components, and the face piece is snap-connected with the body structure so as to be easily removed therefrom in providing access to the functional components of the dispenser.

3,580,426
FERTILIZER DISTRIBUTOR
Peter R. J. Manning, Southfields, England, assignor to Tri-Ang Toys Limited, London, England
Filed July 17, 1969, Ser. No. 842,548
Claims priority, application Great Britain, July 18, 1969, 34284/68
Int. Cl. A01c 15/00
U.S. Cl. 222—177 7 Claims



A garden fertilizer distributor comprises a hopper having a bottom outlet and supported on a pair of wheels mounted one on each end of a roller. The roller is formed with longitudinal pockets which deliver metered quantities of the fertilizer to the outlet as the roller rotates with the wheels in use. A closure plate is pivoted on the hopper and is spring loaded to a position in which it closes the hopper outlet. Two marker fingers are rigid with the closure plate and engage the ground when the hopper is tilted to a position of use and thereby swing the closure plate about its pivot away from the hopper outlet to permit delivery of fertilizer through the outlet.

3,580,428
ICE DISPENSING MACHINE
Howard A. Garber, 1010 First Ave., Richmond, Va.
Filed Mar. 15, 1969, Ser. No. 816,316
Int. Cl. B67d 5/52; G01f 11/10
U.S. Cl. 222—241 10 Claims




An ice dispensing machine having an insulating casing with a platform adjacent the bottom for supporting a mass of flaked ice with a rotatable impeller mounted adjacent the bottom of the mass of ice to shave the ice therefrom and direct such ice to a vertically extending conveyor for carrying the ice upwardly to a discharge spout with a receptacle actuated lever for starting the operation of the impeller and conveyor.

3,580,429
PASTE DISPENSER WITH INTERCHANGEABLE BAGGED CARTRIDGES
John P. Trindle, Oklahoma City, Okla., assignor to Robert L. Fairbanks, Oklahoma City, Okla.
Filed Dec. 10, 1968, Ser. No. 782,550
Int. Cl. G01f 11/06
U.S. Cl. 222—327 10 Claims

A dispenser for dispensing a measured amount of nonsolid material such as, for example, paste hand cleaner, the dispenser receiving interchangeable cartridges containing the fluid material in operative affixture, and including a manually


depressible extracting valve in communication with the paste material and serving to dispense a proportionate amount upon depression of the valve; the cartridge including a liner

locked assembly. The interlocked assembly is comprised of a tip and stem, one being a hard material defining a recess or notch, and the other being of a soft cold-flowable material that is caused to cold-flow into the notch when the two mem-



protecting the paste material from exposure to the surrounding air, the liner also being secured within the cartridge to regulate the evacuation of the paste material.


3,580,430
AEROSOL CONTAINERS
Henry Angele, Riscle, Gers, France, assignor to Etablissements Valois, Marly-le-Roi, Yvelines, France
Filed Apr. 22, 1969, Ser. No. 818,274
Claims priority, application France, Apr. 25, 1968, 149,367
Int. Cl. B65d 83/14
U.S. Cl. 222—394 8 Claims



A liquid-dispensing (e.g. aerosol) container has a long plunger tube with a free end weighted by a cup and a ball carried thereon, the ball being embraced in fluidtight manner by the cup with formation of a void therebetween communicating on the one hand with the bore of the tube and on the other hand with the interior of the container via one or more passages in the cup.


3,580,431
AEROSOL VALVE TIP AND STEM ASSEMBLY AND METHOD OF ASSEMBLING SAME
Clarence O. Kuffer, Niles, and Thomas McAvoy, Roselle, Ill., assignors to Valve Corporation of America
Continuation of application Ser. No. 703,103, Feb. 5, 1968, now abandoned. This application Mar. 20, 1970, Ser. No. 21,251
Int. Cl. B65d 83/00
U.S. Cl. 222—402.1 8 Claims

This application describes and illustrates a method of making an aerosol valve tip and stem assembly and the inter-



bers are telescopically assembled. When the members are assembled, the soft cold-flowable material cold-flows into the notch to interlock the members and to make disassembly thereof difficult.

3,580,432
ACTUATING MECHANISM FOR PRESSURIZED FLUID DISPENSER
Ray G. Brooks, 2505 Custer Court, Irving, Tex.
Filed July 16, 1969, Ser. No. 842,201
Int. Cl. B65d 83/00
U.S. Cl. 222—402.13 7 Claims




An actuating mechanism for pressurized fluid dispensers involves a cap having a pillar with a hinged body carrying a tubular element engageable with the dispenser spout. The mechanism includes a trigger secured to the body whereby the application of force to the trigger depresses the body with the consequent movement of the tubular element and spout. Changeable nozzles direct the spray to selected target areas, and a locking system prevents inadvertent spray emission.

3,580,433
CIGARETTE TUBE PACKAGING APPARATUS
Arnold Kastner, 10220 Armand Lavergne, Montreal North 39, Quebec, Canada
Filed Mar. 3, 1969, Ser. No. 803,796
Claims priority, application Canada, Nov. 13, 1968, 035,079
Int. Cl. G01f 11/28
U.S. Cl. 222—440 16 Claims


A packaging apparatus for cigarette tubes including a supply hopper for the cigarette tubes and a chamber posi-

tioned beneath the supply hopper and in communication therewith. And at least one separation blade mounted for horizontal reciprocal movement to project into the chamber




3,580,434
CONVERTIBLE TRANSPORT CONTAINER WITH PLURAL FUNNEL-TYPE OUTLETS
Artur Spitzer, Mosbach, Baden, Germany, assignor to Ludwig Spitzer Sen. KG (Kommanditgesellschaft), Sonnenhalde, Germany

Filed Aug. 26, 1968, Ser. No. 755,284
Claims priority, application Germany, Oct. 9, 1967, S112326
Int. Cl. B67c 11/00
U.S. Cl. 222-461 6 Claims



A rectangular, stackable shipping container having top filling openings, a dustproof end closure in the form of hinged doors, and a plurality of collapsible funnel discharge openings. The funnels occupy a minimum amount of space when collapsed and enable the full use of the available container volume.


3,580,435
SPRAY GUN WITH PRESSURE OPERATED VALVE
Alf Georg Bertilsson, Harlingstorp, Axvall, Sweden, assignor to Atlas Copco Aktiebolag, Nacka, Sweden
Filed Apr. 15, 1968, Ser. No. 721,304
Int. Cl. B67d 5/06
U.S. Cl. 222-504 6 Claims



In a spray gun the supply of coating material to the nozzle means of the gun is controlled by a pressure fluid-actuated differential servo piston means dividing the cylinder thereof


in a first cylinder chamber around the stem and a second cylinder chamber opposite to the first cylinder chamber. During both strokes of the servo piston means the first cylinder chamber is pressurized by pressure fluid. A maneuvering valve is provided for either supplying pressure fluid to the second chamber for producing one of the strokes of the servo piston means against the action of pressure fluid in the first chamber, or relieving the pressure fluid in the second chamber for releasing the other stroke of the servo piston means under the action of said pressure fluid in the first chamber. More particularly the servo piston means may be of tandem design for quick actuation.

3,580,436
DEMOUNTABLE WIG STAND
Eugene W. Di Luco, 1760 Miriam St., North Brunswick, N.J.
Filed Apr. 7, 1970, Ser. No. 26,252
Int. Cl. D06f 59/00; A41h 5/00
U.S. Cl. 223-66 6 Claims



A demountable wig stand provided with a strip, the opposite ends of which are attachable together to form a base; and having a second strip attached to the first strip at one end, and also attachable at its other end to the first strip; a third strip is attached medially to the middle of the second strip, with its ends attachable to the base, to define a cagelike stand for a wig.


3,580,437
METHOD AND APPARATUS FOR MAKING HIP STOCKINGS FOR PANTY HOSE AND THE LIKE
Fritz Vorberg, Bischofswiesen-Winkl, Germany, assignor to Globotex AG, Zug, Switzerland
Filed Feb. 10, 1969, Ser. No. 797,847
Claims priority, application Germany, Mar. 5, 1968, G52570
Int. Cl. D06c 5/00
U.S. Cl. 223-75 10 Claims



A method of making stockings for panty hose comprising the steps of placing a crude stocking on a hose mold for shaping and treatment and making an elongated cut in the texture of said stocking while in place on said hose mold. The


apparatus of the invention includes a shaped hose mold for shaping and treatment of a hip length stocking placed thereon and a cutting means is mounted on the hose mold or in the path of said mold for making a precise elongated cut in the hip portion of a stocking which is placed on the hose mold so that a pair of said stockings may later be assembled into a pair of panty hose or may be worn as hip-high stockings.

3,580,438
WRISTBAND
Jean Ernest Paul Raval, rue du Lac, 2416 Les Brenets, Switzerland
Filed Nov. 26, 1968, Ser. No. 778,925
Claims priority, application Switzerland, Nov. 28, 1967, Mar. 26, 1968, 16713/67; 4476/68
Int. Cl. A44c 5/00
U.S. Cl. 224-4 13 Claims



A wristband formed of elements assembled in end to end relationship and mounted on at least one flexible assembly wherein the said assembly is constituted by a helical spring surrounding a clamped extruded steel wire.


3,580,439
VEHICLE LUGGAGE CARRIER
Lawrence A. Jewett, 17383 Greenbrier Drive, Strongsville, Ohio, and Walter C. Jewett, Box 245 Gripps Road, Willington, Ohio
Filed Mar. 4, 1969, Ser. No. 804,243
Int. Cl. B60r 9/04
U.S. Cl. 224-42.1 8 Claims



A vehicle top luggage carrier having a container removably fastened to the top of a vehicle. The container has a top, bottom, sides and an opening in front and back to permit access to the inside of the container. Hinged doors cover the openings. Drawer shells are slidably received through the openings in the container and themselves have a top, bottom and sides. The front and back of the shells are open to permit drawers to be slidably received in the drawer shells. Depressions on the top of the shells and complementary projections on the bottom of the shells permit them to be stacked and interfitted in a vertical position.


3,580,440
AUXILIARY CHUTE HOLD-DOWN MEANS FOR A TRUCK MOUNTED CONCRETE MIXER
William H. Fry, and Lawrence G. Zerba, Independence, Iowa, assignors to Construction Machinery Company, Waterloo, Iowa
Filed Feb. 13, 1969, Ser. No. 799,044
Int. Cl. B60r 11/06; B60p 3/16
U.S. Cl. 224-42.31 11 Claims

An auxiliary chute holddown means for a truck mounted concrete mixer including a pair of spaced apart support brackets secured to the mixer truck at one side thereof. The



side edge. The brackets include lip portions which extend over the other chute side edge to assist in maintaining the chute on the brackets. The cam lock means is movable from an unlocked position with respect to the chute wherein the flexible member is substantially tension free to a locked position with respect to the chute wherein the flexible member is under tension to maintain the chute on the brackets.

3,580,441
CLAMPLESS FENDER MOUNTED BRACKET
Richard C. Zercher, Box 130A, R.D. 02, Lititz, Pa.
Filed Apr. 30, 1969, Ser. No. 820,487
Int. Cl. B60r 9/00
U.S. Cl. 224-42.31 3 Claims




A cargo-carrying bracket adapted to be attached to a fender without clamps includes a load-bearing member adapted to be received in an inwardly directed channel on the edge of the fender, a load-supporting element extending from the load-bearing element, and a counterbalancing brace extending from the load-bearing element and adapted to engage the inner surface of the fender to balance a load applied to the load-supporting element.

3,580,442
METHOD AND APPARATUS FOR TRANSFERRING ARTICLES AND THE LIKE
Howard A. Rohdin, Waquoit, Mass., and Fred P. Brown, Jr., Centerville, Mass., assignors to Packaging Industries, Inc., Hyannis, Mass.
Filed Apr. 4, 1968, Ser. No. 718,732
Int. Cl. B26f 3/02
U.S. Cl. 225-2 32 Claims

The method and apparatus of the disclosure relate to the transfer of articles that are formed in a predetermined array at a fixed center-to-center relationship to form another predetermined array of articles which have a center-to-center relationship different from the first predetermined array. The apparatus includes at least one transfer arm, that is equipped

with a suction cup for pulling an individual article from its position in the first predetermined array, and for holding the

which an excess in length in the thread can hang down from such elements in the form of a loop. A downward-directed nozzle is arranged adjacent to the first thread-guiding element, through which thread enters the loop, for discharging



article while it is transferred from that position to a position in the second predetermined array.

3,580,443


APPARATUS FOR OPENING FILM CASSETTES

Fridolin Hennig; Hans-Jürgen Kellner; Klaus Potz, and Christian Gotze, Munich, Germany, assignors to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Germany
Filed Jan. 21, 1969, Ser. No. 792,288
Claims priority, application Germany, Jan. 19, 1968, Sept. 14, 1968, P 16 22 303.3 and P 17 97 336.3

Int. Cl. B26f 3/00

U.S. Cl. 225-96.5

22 Claims



Apparatus for opening plastic housings of film cassettes comprises a support which can hold a housing in a predetermined position, a tool having a cutting edge which is movable against and penetrates into the housing to produce therein a crack, and means for thereupon moving the tool with reference to the housing or vice versa so that the crack is propagated until the housing is sufficiently opened to permit evacuation of the reel which carries exposed film.

3,580,444

DEVICE FOR LOCALIZING AN EXCESS IN LENGTH IN A THREAD

Hubert P. Van Mullekom, Deurne, North Brabant, Netherlands, assignor to N. V. Machinefabriek L. Te Strake, Deurne, Netherlands

Filed Aug. 26, 1968, Ser. No. 755,260


Claims priority, application Netherlands, Sept. 4, 1967, 6712130

Int. Cl. B65h 17/32

U.S. Cl. 226-97

3 Claims

This device, which is adapted to be interposed between a device for continuously supplying a thread and a device for intermittently conveying the thread, comprises first and second thread-guiding elements, between which is a space in



fluid downward along the descending leg of the loop in order to place the descending leg under tension so as to prevent the loop from tangling. The ascending leg of the loop is relatively free of tension.

3,580,445

GUIDING APPARATUS FOR ELIMINATING ENTANGLEMENT AND TWIST IN PUDDLED MULTIFILAMENT YARN


Robert B. Moore, Jr., Kingsport, Tenn., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed June 16, 1969, Ser. No. 833,422

Int. Cl. B65h 17/32

U.S. Cl. 226-97

2 Claims



A guiding apparatus for eliminating filament entanglement and twist in a multifilament ribbon of yarn puddled by a gas-operated puddling jet. The apparatus is revolvably mounted on the inlet end of a puddling jet and provides a snubbing action on the yarn whereby the adverse effect produced by the twisting vortex of the jet may be minimized.

3,580,446

MAGNETIC TAPE MOVEMENT-INITIATION SYSTEM

Yoshiyo Wada; Katsuya Yasutake, Yokohama, and Yoshikazu Terao, Tokyo, Japan, assignors to Victor Company of Japan, Limited, Yokohama, Japan

Filed Aug. 14, 1969, Ser. No. 850,130

Claims priority, application Japan, Aug. 16, 1968, 43/58,027

Int. Cl. G11b 15/43


U.S. Cl. 226-108

10 Claims

A magnetic tape movement-initiation system which causes two magnetic tape drive means to operate such that one means is actuated with a time lag with respect to the other means. Said two magnetic tape drive means are mounted in the path of travel of a magnetic tape paid out from a supply

reel and wound on a takeup reel such that one means is disposed on the supply reel side and the other means is

on a pivotal lever for grasping a portion of the cable and easily pulling or pushing the cable in the desired direction. The gripping device comprises a split block member having one portion thereof movable for facilitating alternate gripping and releasing of the cable in order to permit a repetitious pivoting of the device for a substantially continuous pulling or pushing of the cable.



disposed on the takeup reel side with respect to magnetic heads which are brought into contact with the magnetic tape.

3,580,447

TEXTILE TREATING APPARATUS


Eduard Kusters, and Max Kruger, Krefeld, Germany, assignors to Eduard Kusters Maschinenfabrik, Krefeld, Germany

Continuation-in-part of application Ser. No. 729,748, May 16, 1968, now abandoned, Continuation-in-part of application Ser. No. 729,748, May 16, 1968, now abandoned. This application May 22, 1969, Ser. No. 826,990

Int. Cl. B65h 17/42

U.S. Cl. 226-119

17 Claims



This disclosure relates to a textile-treating apparatus wherein the textile is conveyed through a chamber and appropriately treated therein. The textile is conveyed along a circular path within the chamber and in one embodiment includes an endless conveying means arranged to form a screw thread surface upon which the textile is moved through the chamber. Alternatively, the textile may be conveyed along a grid surface by means of an oscillating movement thereof, again in a circular path.

3,580,448


CABLE FEED DEVICE

Buddy L. Cagle, Sr., 3326 E. 27th Place, Tulsa, Okla.
Filed Feb. 19, 1969, Ser. No. 800,608

Int. Cl. B65h 17/36

U.S. Cl. 226-127

6 Claims



A cable feed device for facilitating longitudinal movement of a cable into a bore whereby a gripping device is mounted

3,580,449
STOCK FEED APPARATUS


Michael J. Chaban, Jr., Wilbraham, Mass., assignor to Standard International Corporation, Andover, Mass.

Filed Oct. 11, 1968, Ser. No. 766,757

Int. Cl. B65h 17/36

U.S. Cl. 226-150

13 Claims



Stock-feeding apparatus of the intermittent reciprocating type having a simplified four-way valve for positive control of the sequencing of the apparatus. Particular features include a pressure-operated momentum-absorbing device and a practical simplified stock-release means.

3,580,450

GRIPPING MEANS FOR BINDING MATERIALS


Derick A. Sparks, Woodley, near Reading, England, assignor to Power Industries Limited, Maidenhead, England

Filed Aug. 16, 1968, Ser. No. 753,240

Int. Cl. B65h 17/24

U.S. Cl. 226-171

2 Claims



In a package-binding machine, a feed-drive device comprises an endless belt arranged to run on a plurality of pulleys or rollers, and guide means to pass binding material in running engagement between the belt and the surface of one of the pulleys or rollers, whereby a tension applied to the belt acts to grip binding material between the belt and the pulley or roller, and operation of drive means causes lengthwise feeding movement of the binding material.

3,580,451

CLAMP BLOCK CHAIN FOR HOLDING ONE EDGE OF A WEB OF MATERIAL

Raimund Fraitzl, Tengling, Upper Bavaria, Germany, assignor to Bruckner-Maschinenbau Gernot Bruckner, Tittmang, Upper Bavaria, Germany


Filed Sept. 18, 1969, Ser. No. 859,027

Claims priority, application Germany, Oct. 8, 1968, G6801212.4

Int. Cl. B65h 17/34

U.S. Cl. 226—173

4 Claims



A clamp block chain comprises a series of clamp blocks, interconnected to form a chain, for holding one edge of a web of material. A series of upper rollers and a series of lower rollers are mounted on the chain to rotate on vertical axes. The upper rollers run between an upper pair of vertical guides, and the lower rollers run between a lower pair of vertical guides. A series of supporting rollers, mounted on the chain, rotate on horizontal axes, and there is a horizontal rail on which the supporting rollers run.

3,580,452

WEB TRANSPORT APPARATUS


Thomas A. Chuhta, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Jan. 15, 1969, Ser. No. 791,375

Int. Cl. B65h 17/20

U.S. Cl. 226—191

10 Claims



Web transport apparatus utilizing web transport rollers having a longitudinal rib on the web-contacting surface. The rib is formed of a spongy material whereby a plurality of webs having slippery surfaces may be transported simultaneously in parallel paths with good tracking characteristics.

3,580,453

TENSION ARM

Robert E. Schoeneman, East Setauket, N.Y., assignor to Potter Instrument Company, Inc., Plainview, N.Y.

Filed Oct. 8, 1969, Ser. No. 864,811


Int. Cl. B65h 23/10

U.S. Cl. 226—195

1 Claim

An improved magnetic tape transport has a pivoted tension arm to which is attached a constant-tension flexure spring

that is attached to the arm and the chassis so that a line through the points of attachment and the tape path are substantially parallel, thus maintaining a constant tape tension for all positions of the arm.



3,580,454

YARN GUIDE

Raymond Victor Evans, Blackburn, England, assignor to Singer-Cobble Limited, Blackburn, England


Filed Jan. 9, 1969, Ser. No. 790,034

Claims priority, application Great Britain, Jan. 9, 1968, Aug. 8, 1968, 1354/68; 37831/68

Int. Cl. B65h 57/16

U.S. Cl. 226—198

8 Claims



A yarn guide comprises two or more closely spaced guide elements which define yarn-receiving pockets between successive such elements, the pockets being limited at the one end by a body part on which the elements are mounted and at the other side by a displaceable retention member. The retention member will usually be formed integrally with the related guide element and will be such as to be displaceable by a yarn moving transversely of its length into engagement with the pocket but relatively nondisplaceable by a yarn moving transversely of its length and outwardly of the pocket. The guide elements may be elongated in the direction of the yarns to be separated thereby to form plates between adjacent such yarns or they may take the form of pinlike members having not substantial length in the yarn direction.

3,580,455

FASTENER DRIVING DEVICE OPERATING MEANS

Adolf Cast, Oberlenningen, and Heinz Schwarz, Zizishausen, Germany, assignors to Karl M. Reich Maschinenfabrik, Nürtingen, Germany

Filed Mar. 21, 1969, Ser. No. 809,064

Int. Cl. B27f 7/14


U.S. Cl. 227—8

23 Claims

A powered fastener driving device having a power control means for selectively supplying power to a driver blade which drives fasteners out of the device, which power control means includes a member movable between a first position where no power is supplied to the driver blade and a second position where power is supplied to cause the driver blade in the device to drive a fastener, said control means including a counterreturn chamber therein which prevents said movable member from returning from said second position until after a predetermined lapse of time after the member is moved to said second position from said first position, and a cross-member pivotally mounted at its midpoint on said movable

member and arranged with a manually operated trigger and a slidable workpiece touch-member which extends slightly beyond the front end of the nose piece of the device to cause

the fasteners are fed uniformly oriented in a vertical plane from a source of supply to a pickoff locality. An installing head is reciprocable in a parallel plane between a fastener inserting locality and a retracted fastener receiving position,



the movable member to said second position when the trigger is pulled and the touch-member is moved rearwardly by engaging said device nose piece to the workpiece.

3,580,456

APPARATUS FOR INSERTING STICKLIKE OBJECTS INTO COMESTIBLE ARTICLES


Karl J. Zueger, 9 Shon Cr., Novato, Calif., and Eugene J. Decker, 514 Flagg St., San Jose, Calif.

Filed Oct. 9, 1969, Ser. No. 865,080

Int. Cl. B27f 7/02

U.S. Cl. 227—100

20 Claims



Apparatus for inserting toothpicks, or the like, into comestible articles such as hors d'oeuvres, diced cheeses or meats, bar fruits and similar articles including a suitable conveyor means for individually positioning the articles to be impaled relative to an impaling means, a container for storing the toothpicks or other objects with which the comestibles are to be impaled and impaling means operatively coupled to the conveyor means for retracting one or more of the impaling objects from the container and causing it to be driven into a comestible article to form the desired food preparation.

3,580,457

FASTENER INSERTING MACHINES

James N. Henshaw, Birmingham, Mich., assignor to USM Corporation, Flemington, N.J.

Filed May 15, 1969, Ser. No. 824,946


Claims priority, application Great Britain, June 26, 1968, 30358/68

Int. Cl. B21j 15/10

U.S. Cl. 227—116

9 Claims

A machine for successively installing fasteners, especially the pull-to-set-type blind rivet-mandrel assemblies, wherein



and a transfer device is operative between the pickoff locality and the receiving position successively to reorient and present the fasteners for insertion by the head in a work piece or work pieces.

3,580,458

COMPRESSED AIR STAPLING MACHINE FOR METALLIC STAPLES WITH CONTROL OF THE ANVIL FOR BENDING THE STAPLE ENDS

Umberto Monacelli, Via del Parco, Blassono (Milan), Italy


Filed July 14, 1969, Ser. No. 841,216

Claims priority, application Italy, July 19, 1968, 19,179

Int. Cl. B25c 5/02

U.S. Cl. 227—124

5 Claims



A compressed air stapling machine for metal staples provided with an anvil for bending the fixed staples ends and means for controlling said anvil.

3,580,459

VARIABLE POSITION MEANS FOR HOLDING A NONROTATING WORKPIECE IN FRICTION WELDING APPARATUS

Arthur F. Gage, Warren, and Alex F. Stamm, Rochester, Mich., assignors to Rockwell-Standard Company, Pittsburgh, Pa.

Filed Oct. 23, 1968, Ser. No. 769,964


Int. Cl. B23k 27/00

U.S. Cl. 228—2

14 Claims

Friction welding apparatus including a pair of members having transversely facing workpiece engaging surfaces thereon for holding a nonrotating workpiece and adjusting means for varying the positions of the members relative to each other and a machine support. The adjusting means includes transverse adjusting means for selectively and inde-

pendently moving the members toward or away from each other along an axis transverse to the normal welding axis and




for selectively and independently moving the members as a unit in either direction along the transverse axis.

3,580,460

THERMOCOMPRESSSION BONDING APPARATUS
Lewis D. Lipschutz, Poughkeepsie, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed July 26, 1968, Ser. No. 747,940
Int. Cl. B23k 1/00, 37/04

U.S. Cl. 228—4

6 Claims



A thermocompression bonding apparatus having a plurality of slidably disposed, independently operable impact surfaces. A plurality of pistons are slidably disposed in a housing, and each include extension means terminating in respective impact surfaces. The pistons are actuated so as to urge the impact surfaces into an impact zone so as to affect a plurality of thermocompression bonds.

3,580,461


METHOD AND APPARATUS FOR MAKING ELONGATED VESSELS, CONTAINERS AND TUBULAR MEMBERS
Curzon Dobell, Nassau, Bahamas, and Leslie P. Wilson, London, England, assignors to Caribbean Holdings Ltd., Nassau, Bahamas
Division of Ser. No. 341,835, Jan. 24, 1964, Pat. No. 3,425,118, Feb. 4, 1969. This application June 6, 1968, Ser. No. 753,316
Int. Cl. B23k 1/20

U.S. Cl. 228—15

17 Claims

Method and apparatus for forming elongated hollow pressure-resistant cylindrical articles from a continuous strip of prestressed and pretensioned material wherein the strip of material is laid down in a plurality of helical windings which may overlap or abut each other by the application of a rotative force; the windings are sealably bonded as laid down; and the forming cylindrical article is displaced axially by a force separate from the rotative force to lay down the

windings until the desired length of article is formed. The apparatus embodies fixed arcuate segments or rotatable cylindrical forming heads to shape the cylindrical articles from the strip; driven endless belt assemblies to rotate the forming ar-




ticle; and mechanical drives synchronized with the driven belt to axially move the forming article or pressurized fluid supplied interiorly of the forming article to axially displace the forming article under a controlled advance by mechanical linkages synchronized with the driven belt assembly.

3,580,462

SOLDERING APPARATUS
Louis Vanyi, 246 Crestwood Ave., Ventura, Calif.
Filed Dec. 14, 1967, Ser. No. 690,590
Int. Cl. B23k 3/02

U.S. Cl. 228—51

16 Claims



A soldering iron tip and method of soldering wherein the amount of solder applied is closely controlled and excess solder is automatically removed. It employs an elongate heated applicator with a solder reservoir area, said heated applicator having a plurality of small apertures on its work contacting face each leading to the reservoir area. In one embodiment the tip is made up of a bundle of rigid rods encased in a sleeve, the rods terminating substantially even with the end of the sleeve and the tip end being shaped to contact the work. It employs capillary attraction to apply solder and to draw excess solder off of a workpiece and into the reservoir area. When the reservoir is full of brief shake will dislodge accumulated solder from the reservoir and clear it for future use.

3,580,463

PACKAGE FOR SOLID PIECES OF FOODSTUFFS OR THE LIKE AND METHOD FOR MANUFACTURING SUCH PACKAGES

Steven Duerink, 14, Mussenstraat, Uden, and Leendert Steenvoort, 9, Prof. Regoutstraat, Best, Netherlands
Filed Mar. 19, 1969, Ser. No. 808,436

Claims priority, application Netherlands, Mar. 20, 1968,

68 03956

Int. Cl. B65d 1/00, 85/00

U.S. Cl. 229—2.5

11 Claims

A package characterized in that it has a substantially rectangular bottom having only at two opposite ends an up-

standing wall part, said wall parts having along their outer periphery in the zones where these wall parts are not connected to the bottom part, a flange, the generating lines of which flanges are parallel to the main surface of the bottom part and that to the flanges of the upstanding wall parts a separate closing cover of a sheet of easily printable material such as hard paper or thin white cardboard is applied which



extends along the entire periphery of the upstanding wall parts with the exception of the bottom part and has generating lines also parallel to the bottom part. This makes it possible to use a simple closing cover from a flat sheet, for instance of paper or thin white cardboard, which can easily be printed and given an attractive appearance and the foodstuffs can be displayed for sale in the package in such a way that substantially only the closing cover is visible.

3,580,464


HERMETICALLY SEALED COMPOSITE CONTAINER
Edwin D. Griffith, Pemberville, Ohio, assignor to Owens-Illinois, Inc.

Filed Mar. 17, 1969, Ser. No. 807,601

Int. Cl. B65d 3/10, 5/02

U.S. Cl. 229—5.6

4 Claims



An improved hermetically sealed composite container formed by double seaming a pair of heated and compounded metal ends to a flanged can body so that the heated compound is bonded to an inner liner of thermoplastic material on the can body to provide an effective seal.

3,580,465
CARTONS

Kenneth Knapton Davies, Chorleywood, England, assignor to The Metal Box Company Limited, London, England
Filed Sept. 25, 1968, Ser. No. 762,598


Claims priority, application Great Britain, Sept. 29, 1967,

44528/67

Int. Cl. B65d

U.S. Cl. 229—14

6 Claims



A carton having a lid hinged to the rear wall and arranged to cover the mouth and parts of the front and sidewalls of the carton is provided with an internal tubular liner an end por-

tion of which is bellows folded and overlies a closure panel infolded from the top of the front wall of the carton, and the top of the lid, when closed, overlies the bellows folded portion of the liner and the closure panel and lies in a plane substantially at right angles to the sides of the body.

3,580,466

SANITARY PACKAGE


Edmund J. Thelen, Deerfield, and Robert H. King, Evanston, Ill., assignors to Packaging Corporation of America, Evanston, Ill.

Filed Jan. 31, 1969, Ser. No. 795,647

Int. Cl. B65d 5/56, 17/00

U.S. Cl. 229—14

5 Claims



A sanitary package is provided with a reclosable cover to facilitate dispensing of a product therefrom. The package includes a foldable outer carton having a reclosable cover defined on the top panel thereof and a sealed product-accommodating bag disposed within the carton and affixed thereto.

3,580,467

CARBURETOR PACKAGE


Franklin B. Pieszak, Grosse Pointe Woods, and Marvin G. Knaggs, Livonia, Mich., assignors to Carroll Plastics Corporation, Detroit, Mich.

Filed May 21, 1969, Ser. No. 826,318

Int. Cl. B65d 5/58, 81/06, 85/30

U.S. Cl. 229—14

15 Claims



A packaging assembly for carburetors including a cardboard container, a preformed plastic bottom insert to receive and support the carburetor relative to the container and a preformed plastic top insert having a deep annular depression terminating in an annular surface which engages the carburetor air cleaner seat to seal the carburetor and restrain it within the container.

3,580,468

NESTABLE DOUBLE-WALLED DISPOSABLE CONTAINER


James A. McDevitt, Kalamazoo, Mich., assignor to Continental Can Company, Inc., New York, N.Y.

Filed Aug. 5, 1969, Ser. No. 847,561

Int. Cl. B65d 15/02, 3/22

U.S. Cl. 229-14

5 Claims



Composite frustoconical nestable, double-walled, disposable (i.e. inexpensive) containers (cups in the smaller sizes, tubs in the larger sizes) are formed by combining conventional outer paper cups and inner liner cups formed of thin-walled thermoformed seamless plastic. The outer paper cups have plain or straight (i.e. uninterrupted) sidewalls from top to bottom with outwardly curled rims or lips at the top and recessed bottoms resulting in a continuous rim at the bottom of each cup. The plastic inner liner cups also have frustoconical sidewalls which are somewhat smaller than the sidewalls of the outer paper cups so as to leave in each cup a space between the interfitted sidewalls. Each inner liner has a rim or lip at the top which is curled over, around and under the rim of the outer paper cup so as to snugly embrace the same. A short distance below the rim each plastic inner liner has a continuous, inwardly opening, circumferential lid-receiving groove, the outer periphery of which engages the surrounding inner surface of the sidewall of the outer paper cup so as to act as a spacer between the sidewalls. Adjacent the bottom of each inner liner cup there is a series of circumferentially spaced stacking indentations integrally formed partially in the lower sidewall and partially in the bottom of the liner cup. The segments of the sidewall intermediate the stacking indentations flare outwardly in respect to the frustoconical sidewall so as to join the liner bottom in circumferentially spaced arcuate corners which rest and engage in the continuous circumferential inner corner formed between the bottom and sidewall of the outer paper cup. The stacking indentations have generally horizontal top shelves or shoulders which are engaged by the bottom rims of the outer paper cups when the composite containers are in nested condition.

3,580,469

CORNER PAD


Larrie S. Reese, Mahtomedia, Minn., assignor to Logistics Industries Corporation, Philadelphia, Pa.

Filed Sept. 8, 1969, Ser. No. 855,811

Int. Cl. B65d 5/62, 25/26

U.S. Cl. 229-14

10 Claims



A corner pad for use in packaging fragile articles. The pad is formed from yieldable material and formed in a blank of

solid rectangular configuration. It can be conveniently shipped and stored in this form. Immediately prior to use the blank is "popped" or setup for placement into engagement with the corner of the fragile article.

3,580,470

CONTAINER FOR PACKING BAGS


Edwin Clifton Leonard, Richmond, Va., assignor to Eskimo Pie Corporation, Richmond, Va.

Filed May 23, 1968, Ser. No. 731,507

Int. Cl. B65d 3/24, 5/48

U.S. Cl. 229-15

11 Claims



The present invention involves a method of packaging flat bags for shipment and a shipping container for the bags. The bags have a folded bottom end which is substantially thicker than the open top end. In the disclosed method a number of bags are arranged flatwise into an elongated bundle with the thicker bottom ends of the bags at the top so that the longitudinal cross section of the bundle is a wedge shape that is narrower at the bottom, the bundles are arranged side-by-side in rows and inwardly directed forces are maintained on the supporting end surfaces of each row as well as against the sides of each row. The shipping container comprises an outer casing having end, side and bottom walls in which is inserted a packing insert having a pair of inclined wedging panels that extend between the casing end walls and are inclined outwardly and upwardly from a location on the casing bottom wall spaced inwardly from the bottom of the casing sidewalls. The upper portion of the wedging panels contact the upper portion of the casing sidewalls to form a wedgelike compartment for containing rows of bags stacked in fanlike bundles and locking tabs extend between the lower portion of the inclined wedging panels and the casing sidewalls.

3,580,471

COLLAPSIBLE CELLULAR BOX PARTITIONS


William R. Burke, and Frank S. McCall, Savannah, Ga., assignors to Union Camp Corporation, New York, N.Y.

Filed June 24, 1968, Ser. No. 739,300

Int. Cl. B65d 5/48, 85/00

U.S. Cl. 229-15

1 Claim



A collapsible cellular partition unit is formed by spacing parallel sheets and locating therebetween parallel, longitudi-

dinally extending wall sheets, each wall sheet having one longitudinal edge secured to one spaced sheet and the other edge secured to the other spaced sheet. For the continuous manufacture of such units, the spaced sheets are formed by two moving webs to which longitudinal glue lines are applied. The wall sheets are formed by webs moving between and with the first webs. The wall sheet webs are slit from a single stock roll and are scored to form longitudinal flaps to adhere to the glue lines on the respective first two webs. The first two webs are scored to form the outer wall portions of the partition unit. A partition structure of desired size may be built up by assembling the required number of partition units, the units being secured to each other by glue areas on their spaced sheets. The partition structure may then be secured in a collapsed position within a collapsed container and both shipped as an integrated package unit for simultaneous setup.

3,580,472

SWAB DISPENSER FOR PACKAGE THEREFOR

Theodore H. Stawski, Union, N.Y., assignor to Becton, Dickinson and Company, Rutherford, N.J.

Filed June 10, 1969, Ser. No. 831,929

Int. Cl. B65d 5/72

U.S. Cl. 229-17

6 Claims



A portable dispensing apparatus for dispensing a sterile unpackaged medical swab and a moisturizing charge of a liquid medium. A package member for storing the swab as one of a plurality of stacked swabs. The package, received and supported by the apparatus, having bottom supporting structure for the swabs and both a rear cutout to allow passage of a pivotal dispensing lever and a front exit to dispense, upon lever movement, the swab from the package and from an aligned dispensing slot in the apparatus.

3,580,473

PAPER BOARD CONTAINER WITH PLATFORM STYLE BOTTOM


Lester D. Gill, 302 North Road, Kinnelon, N.J.

Filed Feb. 6, 1969, Ser. No. 797,111

Int. Cl. B65d 3/08

U.S. Cl. 229-21

16 Claims



A merchandising container of paperboard or nonmetallic sheet material made from a blank that provides a platform bottom of polygonal shape and sidewalls that change to a top edge that is circular, oval, or at least more circular than the bottom. Panels fold back on themselves to hold the bottom at a level above the bottom of the sidewalls. The preferred

shape of the bottom is square and this makes a particularly effective blank that can be supplied flat and set up on a filling machine at a user's factory. A laminate blank can provide a moisture and vaporproof container.

3,580,474

CONTAINER-MAGAZINE FOR DISPENSING LABELS


Emile L. Provost, New York, and Antonio Tomasello, Yonkers, N.Y., assignors to Gellman Industries, Inc., New York, N.Y.

Filed Aug. 5, 1968, Ser. No. 750,345

Int. Cl. B65d 5/38, 5/72

U.S. Cl. 229-20

5 Claims



An elongated unitary container-magazine for dispensing folded labels having at least one flap, and a nonunitary container-magazine comprising an outer box and an inner box for the same purpose. The invention also includes patterns for forming the foregoing container-magazines.

3,580,475

STACKING TRAYS


Odess V. Mobley, Birmingham, Ala., assignor to Hoerner Waldorf Corporation, Ramsey County, Minn.

Filed Oct. 14, 1969, Ser. No. 866,210

Int. Cl. B65d 5/22

U.S. Cl. 229-34

8 Claims



A paperboard tray is provided which has opposed end walls including an outer end wall panel, corner flaps hinged to the sidewalls, and an end wall liner panel. The end wall liner panels are provided with a pair of hingedly connected flanges, one of which is hinged to the liner panel and extends on a horizontal plane, and the other of which engages an abutment on the corner flaps to support the first flange. The bottom of one tray is adapted to rest on the horizontal flanges of a similar tray for stacking purposes.

3,580,476

CARTON FOR USE WITH PACKAGING APPARATUS

Lester E. Cannon, Chicago Heights; John M. Tindall, Wilmette, and Howard N. Taylor, Chicago Heights, all of, Ill., assignors to Folding Cartons, Inc., Melrose Park, Ill.

Continuation-in-part of application Ser. No. 685,140, Nov. 22, 1967, now Patent No. 3,474,594. This application Oct.

23, 1969, Ser. No. 868,738


Int. Cl. B65d 5/02

U.S. Cl. 229-37

6 Claims


A carton for use with packaging apparatus for packaging food products and the like. The carton is formed of flexible board material and includes rectangular top, bottom, and sidewalls, the end portions of which are provided with fold

lines defining top, bottom, and side flaps. The fold line between the bottom wall and one of the sidewalls is provided with spaced-apart cut slots therealong to facilitate the folding of the carton. Each of the bottom flaps is provided with a rectangular notch extending inwardly from the free edge of



the flap at about the middle of the length thereof for accommodating a mechanical lifting element on the packaging apparatus. The side flaps are generally rectangular, and the grain of the board material extends generally parallel with the free edge of the bottom flap.

3,580,477
RECTANGULAR CARTON HAVING SIFT-PROOF AND SQUARING CLOSURE
Albert L. Roth, 11 Bradley Court, Spring Valley, N.Y.
Filed Mar. 17, 1969, Ser. No. 807,556
Int. Cl. B65d 5/10
U.S. Cl. 229-39
7 Claims




The invention provides an improved carton for powdered materials and the like, of rectangular or square shape, which has a top or bottom closure of inwardly foldable flaps, and preferably both, wherein the inwardly foldable flap on the rear wall of the carton is provided with two cutout portions each having a side edge which is engaged by a tongue provided on the sidewall flap so as to maintain the carton in squared condition; and at the same time such cutouts each have an oblique angled portion which permits one of said tongues to be interlocked therewith, so that the extension members on the rear wall and sidewalls may be readily glued or sealed to the flap on the front wall of the carton to provide a squared and sealed carton ready for shipping, stacking and display purposes.

3,580,478
PACKAGING
Robert P. Bemiss, Hillsborough, Calif., assignor to Alexander Donald, San Francisco, Calif., a part interest
Filed July 24, 1969, Ser. No. 844,494
Int. Cl. B65d 5/64, 43/00
U.S. Cl. 229-43
12 Claims


The carton and package provides for a new type of closure which may take several different forms, each of which incorporates a coated paperboard lid having a heat-sealable plastic coating such as polyethylene for example. Wherein a 180° bend is made to provide an outer edge of the lid which is

heat-sealed together to provide strength to support a divergent flange or edge which is used in accomplishing a closing and/or sealing of the carton or package. In one form, this edge provides a snap-on operation for mechanically securing the lid on a tray by an interlocking relation between the horizontal flange on the top of the tray and the lid.



In another form of the invention, to provide the mechanical securing the edge of the lid is heat-sealed to the underside of the lip of the tray while the body of the paperboard lid is being heat-sealed on the top side of the lip of the tray. In both instances, an adhesive seal is used in addition to the heat seal which melts at temperatures below 212° F. and preferably at about 170°-180° F.

3,580,479
MOLDED PULP EGG CARTON
Arthur J. Weiss, Bergenfield, N.J., assignor to Continental Can Company, Inc., New York, N.Y.
Filed Aug. 29, 1966, Ser. No. 576,511
Int. Cl. B65d 5/66, 1/00
U.S. Cl. 229-44
9 Claims




This disclosure relates to an egg carton or the like formed of a plurality of transverse pairs of pockets for receiving eggs, and a pair of covers for closing a body of the carton. Adjacent end panels of the covers are provided with concave, triangular recesses for facilitating the introduction of a person's fingers between the covers to readily open the same. The carton is preferably of a molded pulp construction, and bottom walls of at least selected ones of the pairs of compartments are rigidified by a wall bridging a longitudinal centerline of the carton while other transverse pairs are spaced from one another by a gap across the centerline.

3,580,480
LOCK FOR EGG CARTON COVER
Richard P. French, Chicago, Ill., assignor to Continental Can Company, Inc., New York, N.Y.
Filed Jan. 19, 1968, Ser. No. 699,086
Int. Cl. B65d 45/00, 1/00, 5/48
U.S. Cl. 229-45
7 Claims


This invention is directed to an egg or similar type carton which includes a carton body and a pair of covers for opening and closing an end of the body opposite a bottom wall thereof. Each of the covers includes a pair of locking panels which are normally disposed in side-by-side relationship along a centerline of the carton body in a closed position of the covers. The locking panels are received in slots of up-

wardly directed posts, and bosses are formed from the material of the locking panels for engagement beneath as-




sociated edges of the slots to interlock the covers therewith in the closed position.

3,580,481
EASY OPENING ARRANGEMENT FOR RECLOSABLE CAN
Melvin A. Koboldt, St. Louis, Mo., assignor to Container Corporation of America, Chicago, Ill.
Filed Jan. 27, 1969, Ser. No. 794,114
Int. Cl. B65d 3/10, 17/06
U.S. Cl. 229-51
1 Claim



A reclosable fiber can having body wall sections separated by a cut, an outer label, a pull element between the label and body located over the cut, wherein said label is secured to the outer surface of the body except in the marginal areas on opposite sides of said cut.


3,580,482
LATCH FOR RECLOSABLE CARTON AND BLANK THEREFOR
Richard F. Witte, Henrico, Va., assignor to Reynolds Metals Company, Richmond, Va.
Filed Feb. 17, 1969, Ser. No. 799,760
Int. Cl. B65d 5/54, 17/00
U.S. Cl. 229-51
12 Claims



A latch for a reclosable carton construction and blank therefor wherein means are provided to engage a reclosable


tab on a male locking member so as to resist its natural tendency to spring back when it is in its locked position. In the preferred form of the invention, the female locking member as well as the means to prevent spring back of the male locking member are each formed in a conventional glue line panel. The male and female locking members are so positioned and arranged in an overlapping relationship that the male locking member snaps into its locked position. A novel pushbutton-type unlatching member is provided integral with a male locking member to reopen the closed carton.

3,580,483
MEMBRANE SEALED CARTON
Chauncey Young, St. Louis, Mo., assignor to Riegel Paper Corporation, New York, N.Y.
Filed Feb. 20, 1969, Ser. No. 800,866
Int. Cl. B65d 5/54
U.S. Cl. 229-51
8 Claims



The disclosure relates to improvements in tear opening structures for end filled, end sealed cartons and, more specifically, to an improved opening structure for membrane sealed cartons of the type in which a separate "safety shield" material of polyethylene coated glassine or the like is heat sealed or otherwise tightly secured to the outfolded end flaps and side flaps of a carton prior to the infolding and adhering of at least a pair of said flaps to one another to complete the end structure.

3,580,484
PORTION ACCESS PIE PLATE
Michael S. Schneider, Los Angeles (5755 Cantelope Ave., Van Nuys, Calif.)
Filed Mar. 24, 1969, Ser. No. 809,573
Int. Cl. B65d 1/34, 17/02; A47j 37/01
U.S. Cl. 229-51
4 Claims




This invention relates to edible pies that are baked in plates and then cut into segmental portions and removed from the plate as individual servings, provision being made for gaining access to and to loosen each portion of pie in order to avoid mutilation thereto, and involving lines of weakening extending radially of the plate so as to define segments and specifically through the side and rim of the plate, whereby segmental sections of the side and rim are hinged and depressable for exposing cut portions of pie and for having a lever action that lifts and loosens the pie, thereby facilitating extraction of pie portions from the plate without mutilation.

3,580,485 CONTAINERS

Robert Leonard Hall, Streatham, London, England, assignor to Monsanto Chemicals Limited, London, England
Filed May 7, 1969, Ser. No. 822,482
Claims priority, application Great Britain, May 28, 1968, 23,848/69

U.S. Cl. 229—51R

Int. Cl. B65d 43/02




A packaging container which includes a flanged body sealed with a lid, the flange having an elongated depression formed therein which facilitates opening the container by pressing a portion of the lid into the depression to puncture it.

3,580,486

PLASTIC BAG WITH INTEGRAL HANDLE
Emanuel Kugler, 124 Richmond Ave., Lawrence, N.Y.
Filed Mar. 19, 1969, Ser. No. 808,581
Int. Cl. B65d 31/08, 33/10

U.S. Cl. 229—54

3 Claims




A plastic bag having an integral straplike handle at its upper end and having a bottom gusset or satchel bottom construction which unfolds under the weight of items carried in the bag into a three dimensional configuration.

3,580,487

GRAMOPHONE RECORD SLEEVES
Norman John Garrod, Betchingley, Surrey, Great Britain
Filed Sept. 10, 1969, Ser. No. 856,682
Claims priority, application Great Britain, Jan. 8, 1969, 1200/69

U.S. Cl. 229—68

Int. Cl. B65d 81/02



A gramophone record sleeve comprising two side members interconnected along three edges by spines, the fourth edge

of the sleeve being closable by a closure flap integral with one side member and pivotal along a hinge line in the one side member parallel to but spaced inwardly of the fourth sleeve edge.


3,580,488

CONTINUOUS ENVELOPE

Stanley Komen, 348 Swanson Road, Sycamore, Ill.
Filed Jan. 2, 1968, Ser. No. 695,188
Int. Cl. B65d 27/10

U.S. Cl. 229—69

6 Claims



A continuous envelope system in which a plurality of joined envelopes are made from a single web of sheet material, each of the envelopes has hinged joints at the three closed sides thereof so that full opening of the envelope is attained upon spreading of the front and back panels.


3,580,489

SHIPPING ENVELOPE

Joseph S. Oettinger, 21 Richwell Road, Scarsdale, N.Y.
Filed Aug. 1, 1969, Ser. No. 846,730
Int. Cl. B65d 27/02

U.S. Cl. 229—70

3 Claims



A shipping envelope having a front and back panel, the latter having an aperture to expose a portion of the surface of a shipping ticket contained in the envelope so that the back of the envelope and the exposed surface of the shipping ticket can be adhesively secured to a container, the envelope having means whereby the front panel thereof can readily be stripped from the back panel to expose the shipping ticket, the latter having readily removable end portions carrying shipping indicia thereon.

3,580,490

EASY OPENING FLAT OBJECT MAILER

Robert B. Shaad, Birch Lane, Watertown, N.Y.
Continuation-in-part of application Ser. No. 804,817, Mar. 6, 1969, now abandoned. This application Feb. 20, 1970, Ser. No. 13,149

Int. Cl. B65d 65/32, 3/26

U.S. Cl. 229—92.9

1 Claim

A mailer for small flat objects, adapted for insertion in an envelope, comprises a rectangular cardboard blank having a


3,580,492

CENTRIFUGAL SEPARATOR WITH ADJUSTABLE OUTLET MEANS

Jan R. Schnittger, Saltsjobaden; Carl-Goran Nilson, Tulling, and Bengt D. R. Larsson, Tumba, all of, Sweden, assignors to Alfa-Laval AB, Tumba, Sweden
Filed Aug. 15, 1968, Ser. No. 752,860
Claims priority application Sweden, Aug. 23, 1967, 11779/67; 11780/67; 11781/67
Int. Cl. B04b 1/20

U.S. Cl. 233—7

13 Claims



apart again. One corner of the blank is cut away along a convexly curved line leaving the corner of one of the folded panels projecting so that it may be pushed back exposing a small area of the under surface of the deformed corner for grasping the deformed corner for easy opening.


3,580,491

MAILBOX

Ray J. Campbell, R.R. 1, Ansonia, Ohio
Filed Aug. 23, 1968, Ser. No. 754,846
Int. Cl. A47g 29/12

U.S. Cl. 232—35

10 Claims



A mailbox of simple and economical construction is provided which is easy to open with one hand and is self-closing. The mailbox has a stationary inner container provided with a first opening therein and an outer member rotatably supported around the inner container and having a second opening provided therein and with the outer member having weight means thereon which is acted upon by gravity causing rotation of the outer member in one direction about the inner container until a portion of the outer member is aligned over the first opening with the second opening being angularly displaced from the first opening to define a closed position for the mailbox. The mailbox is easily opened by rotating the outer member in a direction opposite the one direction until the second opening is aligned over the first opening to provide unobstructed access to the interior of the inner container. The mailbox has a stop which limits rotation of the outer member in either direction and has a unique self-dropping signal flag which drops merely by opening the mailbox.


3,580,493

METHOD AND APPARATUS FOR DETECTING SLUDGE LEVEL IN A CENTRIFUGE

Lars-Erik Jonsson, Tumba, Sweden, assignor to Alfa-Laval AB, Tumba, Sweden
Filed Oct. 28, 1968, Ser. No. 770,977
Claims priority, application Sweden, Oct. 31, 1967, 14,886/1967
Int. Cl. B04b 11/02

U.S. Cl. 233—19

15 Claims



A centrifugal rotor has a separating chamber with a sludge-collecting space and also has an indicating channel adapted for passage of an indicating liquid through its radially outer end which is positioned to be blocked by sludge collected to a predetermined level in the collecting space. To detect when the blocking occurs, the apparatus registers a reference pressure condition sensed at a certain point of the indicating channel in a first time period, and this reference pressure condition is compared with an indicating pressure condition

sensed at the same point in a second time period commencing after the beginning of the first time period, these registering and comparing operations being repeated until the difference between the compared pressure conditions acquires a predetermined value indicative of said blocking. The compared pressure conditions may be pressures prevailing at said point at instants constituting said first and second time periods, respectively, or they may be pressure changes sensed at said point during time intervals constituting said first and second time periods, respectively.

3,580,494

APPARATUS FOR THE PRODUCTION OF CODED INTELLIGENCE ON A RECORD MEDIUM


Frank G. Higason, Jr., Arlington Heights, and Robert J. Sehner, Palatine, Ill., assignors to Ludlow Typograph Company, Chicago, Ill.

Filed Apr. 21, 1969, Ser. No. 817,987

Int. Cl. G06k 1/02

U.S. Cl. 234-6

9 Claims



Apparatus produces coded intelligence on a record medium, such as by perforating a moving tape, and has a keyboard input. An error correction capability is provided which utilizes the input data, itself, such as the word spaces, to control the operation of the system for deletion of the unwanted data on the medium. A computer word program capability may also be provided for producing selected multicharacter instruction codes on the medium from a single key at the keyboard.

3,580,495

CODED PUNCH ELECTROMAGNETIC INTERPOSER ASSEMBLY


John Paul Jones, Jr., Wayne, Pa., assignor to Navcor, Inc., a Division of KDI Corporation, Norristown, Pa.

Filed June 6, 1969, Ser. No. 831,190

Int. Cl. G06k 1/05

U.S. Cl. 234-115

11 Claims



A miniaturized electromagnetic interposer assembly is described capable of high speed operation from electronic trigger pulses and having coil-interposer arrays of dimensions suitable for direct positioning alongside a set of standard

paper tape punches stacked in parallel groups for ten punch positions per inch. An interposer member electromagnetically moved between two stable positions includes a semiflexible twisted leaf spring stiff in the direction of movement of an electromagnetically moved member and flexible in the direction of movement of punches in their cutting stroke. The interposers and a punch drive comb assembly attain side by side positions in a notch cut into the side of a punch pin shaft.

3,580,496

COUNTING DEVICE INCLUDING AN ESCAPEMENT WITH NO AUTOMATIC RETURN BIAS

Donald William Neild, Gatley, England, assignor to The General Electric Company Limited, London, England

Filed Oct. 18, 1967, Ser. No. 676,356


Claims priority, application Great Britain, Oct. 21, 1966,

47,177/66

Int. Cl. G08g 1/065

U.S. Cl. 235-92

6 Claims



A counting device for use in a road toll charging or similar system having a counter driven by a long life clockwork-type mechanism whose escapement is controlled by input means responsive to signals radiated by roadside sources. The mechanism is sealed in a tamper-proof casing providing with means for indicating that it is operative. The toll system may produce an incomplete half unit registration when a vehicle carrying the counting device enters a road zone which unit is completed by a further half unit registration as the vehicle leaves the zone.

3,580,497

TAMPER PREVENTION APPARATUS FOR ODOMETER


Patrick L. Powell, Franklin Park, Ill., assignor to Stewart-Warner Corporation, Chicago, Ill.

Filed May 28, 1969, Ser. No. 828,486

Int. Cl. G01c 22/00

U.S. Cl. 235-96

20 Claims



The following specification describes an arrangement for locking a counter or odometer on subtractive operation together with a clutch automatically operated on locking to

disengage the gear train and avoid damage to the train and effective on normal or additive operation to engage the gear train. A simple spring biased ratchet arrangement between one of the drive wheels and an adjacent higher digit order wheel is also used to permit additive operation and prevent subtractive counter or odometer operation. An additional feature provides a signal in the event of tampering with the odometer by moving one of the higher digit order dials.

3,580,498

ELECTROMAGNETIC COUNTING MECHANISM


Lloyd J. La Pointe, West Hartford; Howard J. Voegelin, Cheshire, and Ernest G. Hoffman, Middlefield, Conn., assignors to Veeder Industries, Inc., Hartford, Conn.

Filed Apr. 4, 1969, Ser. No. 813,490

Int. Cl. G06m 1/02, 1/10

U.S. Cl. 235-117

15 Claims



An electromagnetic counting mechanism having a one-piece molded plastic frame with a pair of elongated parallel end supports and an intermediate tubular connector extending transversely therebetween, an electromagnet comprising a coil encircling the tubular connector and a U-shaped magnetic core piece with one leg extending through the tubular connector and a second leg extending between the supports, a counter mounted between the supports, and a counter drive mechanism mounted on one of the supports in operative relationship with the electromagnet and counter for indexing the counter upon momentary energization of the electromagnet. The end supports of the frame are contoured to permit access to the tubular connector 360° thereabout and along its full length to provide for winding the coil about the tubular connector by treating the entire frame as a bobbin in conventional coil winding apparatus, and the remaining parts of the counting mechanism are assembled on the frame after the bobbin is wound.

3,580,499

FLUIDIC SLIP-RESOLVER SYSTEM


Peter Bauer, Germantown, and William R. Mentzer, Jr., Silver Spring, both of, Md., assignors to Bowles Fluidics Corporation, Silver Spring, Md.

Filed Oct. 30, 1968, Ser. No. 771,758

Int. Cl. G06d 5/00

U.S. Cl. 235-201

19 Claims



A fluidic system for monitoring relative frequency variations between two fluid pulse trains includes a fluidic clock pulse generator, a fluidic time synchronization circuit, a fluidic slip-resolver circuit and a fluidic up-down binary counter. The two fluid pulse trains are time synchronized and

fed to a slip-resolver circuit, the output stage thereof providing output pulses when two or more successive pulses occur in one input pulse train between successive input pulses in the other train. Output pulses from the slip-resolver are counted by an up-down counter. Logic circuitry is provided to determine up or down counting modes in accordance with which input pulse train is increasing in frequency. In addition, fluidic switching circuits in the system receive sharply defined switching pulses by utilizing a shaper.

3,580,500

MODULATING VALVE CONSTRUCTION


Frederic R. Quinn, Red Hook, N.Y., assignor to Zyrotron Industries, Inc., South Hackensack, N.J.

Division of Ser. No. 707,014, Feb. 12, 1968. This application Apr. 3, 1969, Ser. No. 813,226

Int. Cl. G05d 11/16; F16k 19/00

U.S. Cl. 236-12

2 Claims



This disclosure is directed to a fluid mixing system utilizing modulating valves responsive to the pressure of an independent actuating fluid operating on a diaphragm operatively connected to the valving member for controlling the fluid flow therethrough. The disclosure further contemplates controlling the pressure of the valve actuating fluid in response to temperature. The disclosure also contemplates a diaphragmed mixing valve for controlling the mixing of at least two fluids in response to the temperature of the resulting mixed fluids.

3,580,501

HUMIDITY AND TEMPERATURE SENSING AND CONTROL CIRCUIT


Donovan P. Streed, Rte. 2, Shakopee, Minn.

Filed Mar. 25, 1969, Ser. No. 810,309

Int. Cl. G05d 22/02

U.S. Cl. 236-44

6 Claims



An electronic relative humidity sensing and control circuit having outdoor temperature reset is described. A circuit having temperature and humidity sensors arranged in a bridge circuit for providing control signals to a transistor amplifier is shown for controlling humidity-determining equipment. Ad-

ditional bridge circuitry is also shown for automatically sensing an controlling heating and air conditioning equipment in response to sensed changes in outdoor temperature.

3,580,502

THERMOSTATIC PRESSURE TRANSMITTER


Ernest J. Duchek, Prospect Heights, Ill., assignor to Powers Regulator Company, Skokie, Ill.

Filed Mar. 28, 1969, Ser. No. 811,526

Int. Cl. G05d 23/275

U.S. Cl. 236-102

7 Claims



A temperature actuated pressure transmitter adapted to sense a temperature and transmit a proportional fluid signal. The transmitter includes a fluid pressure chamber, a cantilevered blade having a free end extended longitudinally adjacent said pressure chamber, a temperature sensing element adapted to transmit a force to said blade in response to a sensed temperature, and an exhaust nozzle assembly positioned in fluid communication with said chamber through which the fluid in said chamber can be exhausted. A valve member provided in an exhaust port of said nozzle assembly is engaged with the free end of said blade and is adapted to vary the rate of exhaust through said port and thereby vary the pressure in said chamber in accordance with the force transmitted to the valve member through the lever arm of said blade. The pressure in said chamber is thereby changed in proportion to the temperature sensed by said sensing means. In accordance with this invention, the nozzle assembly can be translated longitudinally with respect to the blade to adjust the span of the transmitter by adjusting the effective lever arm through which said blade operates against the valve member.

3,580,503

AERATOR AND FOUNTAIN ATTACHMENTS FOR FAUCETS


James T. Ligon, 800 South Main, Almont, Mich., and David L. Lang, 475 Main St., Rochester, Mich.

Filed Sept. 19, 1969, Ser. No. 859,330

Int. Cl. E03b 9/20

U.S. Cl. 239-25

7 Claims



An aerator and fountain attachment which converts selectively an ordinary faucet into a drinking fountain and/or an

aerating tap and with no moving parts. Flow directing channels are provided in a base element and the flow directing channels are aspirated through the base element. When specific aspiration is prevented the flow is shifted so that a portion of the flow is diverted from passing axially through the base element and is moved in a radial and upward disposition until aspiration is again permitted and then the flow is redirected in a normal aerating flow path through the attachment.

3,580,504

IRRIGATION CONTROL APPARATUS


Ralph E. Benham, Arcadia, Calif., assignor to Purex Corporation, Ltd., Lakewood, Calif.

Filed Jan. 24, 1969, Ser. No. 793,669

Int. Cl. A01g 27/00

U.S. Cl. 239-70

9 Claims



Automatic, remote operation of irrigation systems is provided without the use of central power facilities by controlling periodic water delivery to the irrigating heads through the use of battery charged capacitors to sequentially operate an electrically responsive valve actuator to open and close a valve in a predetermined time relation.

3,580,505

SPRAYER BOOM ASSEMBLY


Herbert V. Loeffler, Rte #2 & 71 By-Pass, Lee's Summit, Mo.

Filed Apr. 18, 1969, Ser. No. 817,437

Int. Cl. B05b 1/20

U.S. Cl. 239-168

8 Claims



A sprayer boom assembly adapted to be mounted on a truck or other vehicle and including an elongated boom having a spray nozzles spaced therealong, said boom being disposed horizontally and transversely of the vehicle, extending outwardly at both sides of the vehicle, and including a central boom section suspended from the vehicle on a fore-and-aft axis by resiliently yieldable means whereby to remain generally horizontal when the vehicle tilts laterally, a pair of outer boom sections each pivoted for vertical movement to the contiguous end of said central section, and flexible strand supporting each of said outer boom sections in a normally horizontal position, and said strands being connected to said vehicle at points above the pivots of said outer boom sections.

3,580,506

BEARING FOR IMPACT MOTOR DRIVEN SPRINKLER


Robert B. Costa, Covina, Calif., assignor to Rain Bird Sprinkler Mfg. Corp., Glendora, Calif.

Filed Mar. 21, 1969, Ser. No. 809,190

Int. Cl. B05b 3/02

U.S. Cl. 239-230

4 Claims



A bearing at the water entrance end of an impact motor for rotating sprinkler formed by the lower end of a tubular rotor and the walls of a surrounding socket, the bottom end of the socket having an inlet port of smaller diameter than the bore through the rotor so that incoming water and particles therein are jetted into the bore in such a manner that water flow between the confronting surfaces of the bearing is minimized.

3,580,507

DRIVE MECHANISM FOR LARGE VOLUME ROTARY SPRINKLERS


John D. Beamer, West Covina, Calif., assignor to Rain Bird Sprinkler Mfg. Corp., Glendora, Calif.

Filed June 9, 1969, Ser. No. 831,362

Int. Cl. B05b 3/08

U.S. Cl. 239-233

6 Claims



A drive mechanism for large volume rotary sprinklers having an upwardly sloping barrel rotatable about a vertical axis and terminating in a nozzle. An arm is supported intermediate its ends from the barrel for oscillation about a horizontal axis alongside the barrel. One end of the arm extends beyond the nozzle and is provided with a vane and a deflector spoon which move periodically into the water stream issuing from the nozzle to disrupt the stream and produce reaction forces which cause oscillation of the arm as well as rotation of the barrel, and the remaining end of the arm carries a counterbalance. A snubbing structure is journaled about the same axis as the arm and includes an adjustably connected snubber lever and counterbalance weight, the snubber lever being engaged after a preselected free travel of the arm, to lift the counterbalance weight.

3,580,508

MOTOR FOR ROTATING JET SPRINKLER


Ali Marandi, Azusa, and Kenneth H. Solomon, Claremont, both of, Calif., assignors to Rain Bird Sprinkler Mfg. Corp., Glendora, Calif.

Filed Mar. 25, 1969, Ser. No. 810,132

Int. Cl. B05b 3/04

U.S. Cl. 239-241

2 Claims



An impact type motor for rotating jet sprinklers in which impact lobes protruding from a rotor member are engaged by a polygonal impact ring; more particularly, to the construction in which the motive water is caused to flow over the axial ends of the impact ring thereby suspending the impact ring essentially friction free in the motor chamber.

3,580,509

CONTROL APPARATUS FOR HIGH-PRESSURE WATER SYSTEM


John B. Goss, 10950 Old Katy Road, Houston, Tex.

Filed Jan. 6, 1969, Ser. No. 789,238

Int. Cl. F02d 11/08

U.S. Cl. 239-302

9 Claims



Control apparatus for a pump powered by a gasoline engine or the like wherein means are connected to the exhaust manifold of the engine for increasing the pump speed and the fluid delivered by such pump to a nozzle at a point remote from the pump.

3,580,510

ALL-DIRECTION ATOMIZERS

George X. Batlas, Astoria, N.Y., assignor to Vincent Longo, Oceanside, N.Y.; Curtis F. Pearl and Anthony Genantonio, Teaneck, N.J., part interest to each

Filed June 23, 1969, Ser. No. 835,504


Int. Cl. B65d 1/32

U.S. Cl. 239-327

10 Claims

A resilient squeeze bottle has an elongated stopper extending downwardly therein, which provides an air duct and a

liquid duct extending therealong; said ducts being communicative with a slight mixing chamber at their upper ends, which chamber has an upward discharge orifice. The liquid duct has a branch extending upwardly where it is communicative with the bottle's interior at neck region, and said



liquid duct also has a downward extension to the bottom of the bottle. Said stopper has a downward openwork element. Both said stopper and element serve to limit the extent the bottle can be collapsed. The open end of the air duct is always above the liquid in the bottle regardless of the bottle's position when squeezed or not squeezed.

3,580,511

SUBMERSIBLE CLEANING GUN

Paul Hammelman, Zum Sundern 17, 474 Oelde Westphalia, and Heinz Lettmann, Im Schillfeld 19, 4832 Wiedenbruck, both of, Germany

Filed Dec. 27, 1968, Ser. No. 787,535


Claims priority, application Germany, Dec. 29, 1967,

P 15 31 571.6

Int. Cl. B05b 7/02

U.S. Cl. 239—419.5

14 Claims



A submersible cleaning gun having a working nozzle which discharges a jet of pressurized water against the surfaces of submerged bodies. The support for the working nozzle carries a reaction counter to the direction of discharge from the working nozzle to thus facilitate underwater manipulation of the gun. The support for the nozzles carries one or more inflatable and deflatable floats which determine the buoyancy of the gun. A handle is used to adjust the floats as well as to adjust a steering flap at the rear end of the gun.

3,580,512

GAS BURNER

Donald R. Smith, Diamond Bar, and Adrian V. Cavestany, Pasadena, Calif., assignors to Carrier Corporation, Syracuse, N.Y.

Filed Sept. 15, 1969, Ser. No. 857,973


Int. Cl. B05b 7/06

U.S. Cl. 239—432

6 Claims

A thin flat vane is disposed diametrically across the throat or air-gas passageway of the burner. The vane is mounted for rotation about its axis for movement of the flat side surfaces of the vane from a position parallel to the air-gas flow, in

which it creates substantially no turbulence in the flow, to a position transversely of the flow in which it creates maximum



turbulence therein. Increase in turbulence effects reduction of the volume of air in the mixture.

3,580,513

SHOWER HEAD


George Martin, Louisville, Ky., assignor to American Standard Inc., New York, N.Y.

Filed Jan. 31, 1969, Ser. No. 795,644

Int. Cl. B05b 1/32

U.S. Cl. 239—460

14 Claims



An adjustable shower head for the distribution of liquids having a control for regulating the flow of the spray. The shower head is constructed so that the forward pressure of the liquid on the shower head nozzle does not cause relative movement of the shower head parts. A piston-type of arrangement is employed wherein no fluid pressure is developed which acts on the adjusting mechanism.

3,580,514

DISTANCE SELECTOR FOR SPRINKLERS


Tony Radecki, West Covina, Calif., assignor to Rain Bird Sprinkler Mfg., Glendora, Calif.

Filed Apr. 2, 1969, Ser. No. '812,625

Int. Cl. B05b 1/26

U.S. Cl. 239—521

2 Claims



A distance selector for a sprinkler having an upwardly projecting stem in which is formed an upwardly and outwardly directed orifice, the selector being in the form of a ring rotatably mounted on the stem above the orifice and having a depending rim of varying depth which on rotary adjustment of the ring intercepts the water stream varying amounts; the stem having a handle projection so that the stem may be restrained to permit adjustment of the ring.

3,580,515 ALIGNMENT SYSTEM FOR ARRAYS OF A NONCONTACTING PRINTER


William Guy Cassill, McArthur, Ohio, assignor to The Mead Corporation, Dayton, Ohio

Filed Oct. 1, 1969, Ser. No. 862,718

Int. Cl. B05b 1/14

U.S. Cl. 239—536

12 Claims



A noncontacting printing system in which images are formed on a moving web by projecting drops of ink or the like onto the web. The drops are projected from a series of coating heads, each of which has a series of passages for projecting the drops, and structure is provided for supporting and positioning the coating heads with their passages offset with respect to each other to the extent that the drops may be projected onto the web in close enough relationship to each other to give a continuous coating, if desired.

3,580,516

METHOD OF SEPARATING A SHEET INTO CHIPS


Virgil Spencer, Lancaster, Pa., assignor to Armstrong Cork Company, Lancaster, Pa.

Division of Ser. No. 658,675, Aug. 7, 1967, Pat. No. 3,527,418, Sept. 8, 1970. This application Nov. 13, 1969, Ser. No. 871,284

Int. Cl. B02c 18/06, 18/44

U.S. Cl. 241—25

1 Claim



Method of separating a sheet into chips for use in the formation of a floor covering. Plastic particles are calendered into a sheet which is cooled by a cooling bath. The sheet is fed into a slitter which places intermittent cross-machine direction slits in the sheet. The sheet is then fed into a grinder where the knife-hammers traveling at high speed fracture the sheet into irregularly shaped chips.

3,580,517

APPARATUS FOR CHIPPING SCRAP MATERIALS

Stanley V. Ehrlich, Portland, Oreg., assignor to Western Manufacturing, Inc., Portland, Oreg.

Filed Mar. 8, 1968, Ser. No. 711,658


Int. Cl. B02c 13/04, 18/06, 13/286

U.S. Cl. 241—186

29 Claims

An apparatus for reducing bulk materials such as scrap lumber, metal and masonry to fist-sized chunks to facilitate disposal of the same. Sharp-pointed, hammerlike knives pivoted between pairs of spaced plates on a common horizontal driven shaft pass downwardly in sequence past an anvil to shear off pieces of scrap fed across the anvil. Materials too bulky or hard to be sheared by the knives pivot the

knives rearwardly to increase the clearance between knives and anvil and thus permit such materials to pass through the apparatus without damaging the mechanism. The apparatus



is mounted on a wheeled vehicle which also carries a vibratory conveyor and comblike material straightener for feeding scrap into the chipping apparatus in an orderly manner and at a predetermined rate.

3,580,518

RING HAMMERS


Sven B. Strom, St. Louis, Mo., assignor to American Pulverizer Company, St. Louis, Mo.

Filed Nov. 1, 1968, Ser. No. 772,505

Int. Cl. B02c 13/28, 13/04

U.S. Cl. 241—193

15 Claims



A ring hammer for use on the rotor of a material reducing machine and having a plurality of generally radial teeth which are interconnected by integrally formed fillets. The fillets, axially narrower than the teeth, act to prevent scrap material from lodging between the teeth to thus avoid any distending of the ring hammers. Furthermore, the fillets have cutting edges which extend continuously between adjacent teeth and act along with the teeth to shred material.

3,580,519

PROCESS FOR HINDERING THE AGGLOMERATION OR REAGGLOMERATION OF GROUND FINELY DIVIDED POWDERED SUBSTANCES

Kurt Klein, Langen, Hessen; Gerd Lumbeck, Gross-Auheim, and Joachim Maluzi, Gross-Auheim, Germany, assignors to Deutsche Gold-Und Silber-Scheideanstalt vormals Roessler, Frankfurt, Main, Germany

Filed Mar. 25, 1968, Ser. No. 715,581

Claims priority, application Germany, Mar. 23, 1967,

D52612

Int. Cl. B02c 19/00, 23/06

U.S. Cl. 241—22

3 Claims

Process for protecting ground finely divided powdered substances against agglomeration or reagglomeration wherein the substance to be protected is finely ground together with a finely divided hydrophobic silica or wherein a mixture of finely divided hydrophobic silica and finely divided hydrophilic silica is added to the substance to be protected already in finely ground state and intensively mixed therewith in a mill having a grinding action.

3,580,520

BREAKER PLATE ASSEMBLY FOR A DISINTEGRATOR

Thomas Leroy Myers, Lawrenceburg, Ind., assignor to Stedman Foundry and Machine Company, Incorporated, Aurora, Ind.

Filed Oct. 29, 1968, Ser. No. 771,524


Int. Cl. B02c 17/22

U.S. Cl. 241—299

4 Claims

A disintegrator of the type used in the sand and gravel in-

dustry. The breaker plate assembly of such a disintegrator is formed with two opposed projecting ribs, the ends of which form an opening for receiving a T-bar. A bolt passes through



the T-bar and through the housing of the disintegrator through which means the breaker plate is secured to the housing in a manner to allow slight relative movement between the breaker plate and the housing.

3,580,521


COIL WINDER AUTOMATICALLY SEQUENCING MULTIPLE PRESET WINDING SELECTIONS

Richard Settanni, Bethel, Conn., assignor to Leeson Corporation

Filed Mar. 25, 1969, Ser. No. 810,215
Int. Cl. H01F 41/08

U.S. Cl. 242-4

10 Claims



A toroidal coil winder is disclosed with electronic turn counter equipment and preset turn count registers, including program control circuits for automatically stepping through an ordered array of turn count registers for successive windings on a single core.

3,580,522

METHOD AND ARRANGEMENT FOR WINDING UP A CONTINUOUS WEB

Viggo Rasmus Hansen, Naestved, and Per Juel Hagemeister, Glostrup, Denmark, assignors to C. A. Harnden Limited, Hyde/Cheshire, England


Filed Nov. 4, 1968, Ser. No. 773,080
Claims priority, application Denmark, Nov. 9, 1967, 5582/67
Int. Cl. B65H 19/20

U.S. Cl. 242-56

9 Claims

A method of winding a continuous web to form wound packages comprises the following steps: Winding on a run of the web to a winding element thus forming a wound package; removing said winding element from said wound package; moving away said wound package; holding fast said web at a holding point between said winding element and said wound package; bringing said winding element again into engagement with said web and beginning a new winding operation for only a few revolutions; cutting through said web between

said winding element and said holding point; finishing said new winding operation. An apparatus for carrying out said



method comprises a winding element consisting of two rotating grippers which can be moved in axial direction, a holding device for holding fast said web arranged below said winding element, and a cutting device arranged between said winding element and said holding device.

3,580,523


RETRACTABLE SAFETY BELT FOR HOSPITAL GURNEYS AND THE LIKE

Walter George Preston, Tulare, Calif., assignor to John T. Posey

Filed Nov. 14, 1968, Ser. No. 775,793
Int. Cl. B65H 75/48

U.S. Cl. 242-107.1

11 Claims



A safety belt for use on patient supporting hospital equipment such as operating tables, gurneys, wheelchairs and the like which includes an elongated restraining strap adapted to be disposed in transversely circumscribing relation about the patient support and having opposite releasably connectable ends disposed in overlapping position about the patient. The strap has an intermediate portion connected to a retracting roller releasably detachable anchored to the hospital equipment, the strap in extended patient circumscribing relation serves to hold the anchors more securely in place.

3,580,524


UNIVERSAL YARN SPOOL HOLDER

Eugene E. Weaver, 1334 Stuart St., Chattanooga, Tenn.

Filed Dec. 1, 1969, Ser. No. 881,140
Int. Cl. B65H 49/00

U.S. Cl. 242-129.7

7 Claims



A yarn spool holder of unitary construction having a tapered U-shaped configuration with crossmembers secured to the rod on the creel by a wedging action thereby eliminating the use of setscrews, wrenches and the like for securing the holder on the rod and enabling the spool to be placed on

the holder by employing only one hand.

The present invention generally relates to a yarn spool holder for use in tufting machines.


3,580,525

ARRANGEMENT MAINTAINING CONSTANT TAPE TENSION IN MAGNETIC TAPE RECORDERS

Horst Dopner, Bensberg-Frankenforst, Germany, assignor to Telefunken, Patenverwertungsgesellschaft m.b.H., Ulm Donau, Germany

Filed Nov. 21, 1968, Ser. No. 777,803
Claims priority, application Germany, Nov. 21, 1967, P 15 49 107.3

Int. Cl. B65h 59/38; G03b 1/04; G11b 15/32
U.S. Cl. 242-189 10 Claims



Arrangement for maintaining constant the tension of the tape on the reels of a magnetic tape recorder during its normal forward and rewind operations. Feeler means is disposed in the path of the tape near the takeup reel. Such feeler means is arranged to respond to the tension in the tape to control the brake associated with the takeup spindle. Means are provided for automatically reversing, during rewind operation, the effect which the feeler means has on such brake during normal forward operation and thereby providing a control of the tension in the tape for both normal forward and rewind operations.


3,580,526

APPARATUS FOR STORING AND WINDING DISCONTINUOUSLY AND REVERSIBLY MOVING TAPE

Michel Wichoud, 1, rue de Drize 1227, Geneva, and Jean Pierre Engel, 3, Rue Schaub 1202, Carouge-Geneva, both of Switzerland

Filed Sept. 5, 1969, Ser. No. 855,550
Claims priority, application Switzerland, Sept. 6, 1968, 13432/68

Int. Cl. B65h 59/38; G03b 1/04; G11b 15/32
U.S. Cl. 242-190 6 Claims



In apparatus for storing and winding tape travelling discontinuously and reversibly through a reading unit and comprising drive means for reversibly driving the tape through the reading unit and a pair of reversibly driven spools off which and on to which the tape is wound, the provision of a takeup system, including a pair of pulley arrangements on opposite sides of the drive means, responsive to variations in the

length of the tape paths between the spools and the drive means, and electrical means controlled by the takeup system to restore the proper driving relationships between the spools and the tape as it passes through the reading unit.

3,580,527


ARTICULATED CARTRIDGES FOR PNEUMATIC CONVEYANCE

Simon Cynober, Bezons, France, assignor to Saunier Duval, Paris, France

Filed Sept. 16, 1968, Ser. No. 762,253
Int. Cl. B65g 51/04

U.S. Cl. 243-38

9 Claims



This disclosure includes a method and apparatus for propelling a cartridge through a pneumatic tube by creating a pressure differential within the tube and for braking the cartridge by reversing the pressure differential. Valve means are provided in each end of the cartridge to enable the pressure differential to act on the leading end of the cartridge when propelling the cartridge and to act on the trailing end of the cartridge during braking so that longitudinal compression of the cartridge is precluded.

3,580,528

MANEUVERING UNIT


William C. Boyce, and Edward C. Matza, Dallas, Tex., assignors to LTV Aerospace Corporation, Dallas, Tex.

Filed Feb. 3, 1969, Ser. No. 795,794

U.S. Cl. 244-1

Int. Cl. B64g 1/20

10 Claims



A hand-held device for propelling an individual through space wherein pressurized fluid is selectively and individually discharged from oppositely directed coplanar nozzles in response to movement of a pair of control handles relative to a supporting member.

3,580,529

ROCKET WITH SPREADABLE EMPENNAGE

Xaver Suter, Ruschlikon, Switzerland, assignor to Werkzeugmaschinenfabrik Oerlikon-Bührle A.G., Zurich, Switzerland

Filed Sept. 12, 1968, Ser. No. 759,364

Claims priority, application Switzerland, Sept. 21, 1967, 13225/67


Int. Cl. F42b 13/32

U.S. Cl. 244-3.29

5 Claims

Rocket with spreadable empennage comprising a nozzle body with pivotally mounted individual fins located around said body. Holding means releasable by gas pressure holding the fins in their folded-in position. The holding means for each fin comprising a holding member removable from said nozzle body supported in said nozzle body. A locking

member cooperating with the holding member locks the fin and when the holding member is removed, releases the fin. The fin is closer to the center of gravity of the airplane, to a rear supporting position, in which the landing wheel is farther away



The holding member extends inside the external surface of the nozzle body behind each fin.

3,580,530

LIFT FAN INSTALLATION OF VERTICAL OR SHORT TAKE-OFF AND LANDING AIRCRAFT

Misao Wada, Fujisawa-shi, and Kiyoshi Soda, Yokohama-shi, Japan, assignors to Japan Aircraft Manufacturing Co., Ltd., Yokohama-shi, Japan


Filed Feb. 25, 1969, Ser. No. 802,192

Claims priority, application Japan, Nov. 9, 1968, 43/81622

Int. Cl. B64c 29/04; F02k 3/04

U.S. Cl. 244—54

3 Claims



A lift fan installation of vertical or short takeoff and landing aircraft has a single or plurality of lift fan assemblies, and a casing or casings for housing said lift fan assembly. Said lift fan assembly involves a gas generator, a fan driven by the fluid derived from said generator, and an engine body in which said generator and fan are disposed. Between the inner wall of the casing and the outer wall of the engine body is defined an air passage, the effective cross-sectional area of which is less than one and a half times that of the exhaust duct of said lift fan assembly.

3,580,531

RETRACTABLE MAIN CARRIAGE FOR VERTICALLY STARTING AIRPLANES AND AIRPLANES STARTING ON A SHORT RUNWAY

Gerhard Bock, Bremen; Rolf Riccius, Worpswede; Gunter Weitkamp, and Bernhard Wolf, Bremen, Germany, assignors to Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung früher "Wesert" Flugzeugbau-Fock-Wulf/Heinkel-Flugzeugbau, Hünfeldstrasse, Bremen, Germany

Filed July 19, 1968, Ser. No. 746,015

Int. Cl. B64c 25/10

U.S. Cl. 244—102

2 Claims

A retractable main landing gear located behind the center of gravity of the airplane and comprising an adjusting mechanism operable selectively to adjust the landing wheel from a front supporting position, in which the landing wheel

from the center of gravity of the airplane, while the base or area over which the airplane is supported is increased.

3,580,532

TRUNNION MOUNTING


Regis V. Schmitt, Erie, Pa., assignor to Lord Corporation, Erie, Pa.

Filed Mar. 2, 1970, Ser. No. 15,787

Int. Cl. B60k 1/00

U.S. Cl. 248—9

4 Claims



The service life of bonded elastomer trunnion mountings is improved by tapered annular grooves in the outer surfaces of the elastomer adjacent the split metal ring by which the mounting is seated in the trunnion support.

3,580,533

GOLF CART BAG SECUREMENT APPARATUS


George W. Nordland, 8800 S. Harlam, Lot 119, Oak Lawn, Ill.

Filed Apr. 8, 1969, Ser. No. 814,273

Int. Cl. A63b 55/08

U.S. Cl. 248—96

5 Claims



An apparatus for removably connecting a golf bag to a golf cart. The apparatus includes a bag supporting base portion

on the frame of the cart which serves to removably retain a loop member connected near the bottom of a golf bag in a recess formed in the base portion and a locking device having an element connected near the upper end of the golf bag which is cooperable with an element on the cart frame to permit the ready removal of the bag from the cart.

3,580,534

SUSPENSION BRACKET FOR CONDUCTOR INSULATOR


L. E. Lindsey, 222 Vista Ave., Pasadena, Calif.

Filed June 16, 1969, Ser. No. 833,360

Int. Cl. H02g 7/20

U.S. Cl. 248—221

5 Claims



A triangular suspension bracket for supporting a power conductor offset from a pole or the like and having one member in tension and two longer underlying diverging legs loaded in compression and supplementing one another in resisting sidewise sway.

3,580,535

CONNECTING FIXTURE

Christoph Naske, Froschhausen, Germany, assignor to WHB-Anbaumobil von Poschinger K.G., Murnau, Germany

Filed Apr. 24, 1970, Ser. No. 31,583


Claims priority, application Germany, Apr. 24, 1969,

G6916620.7

Int. Cl. A47g 29/02

U.S. Cl. 248—239

4 Claims



A two-piece fixture for connecting two shelf parts or the like at right angles to each other consisting of a headed locking pin projecting from one side of one shelf part, and a cup-shaped slotted element to be mounted in one end of the other shelf part and adapted to be hooked laterally over the headed projecting part of the locking pin and to draw the two shelf parts tightly together. The largest part of the periphery of the cup-shaped element has a double wall, while the remaining part is formed by a single thicker wall which is flat at its outer side and provided with an axially extending slot which has an open end at the open side of the cup. The inner wall surface at least of this single-wall portion is inclined, tapering from the open end of the slot toward its closed end.

3,580,536

SLANT FRONT EASEL

Gordon E. Nichols, Middleboro, Mass., assignor to Winthrop-Atkins Co., Inc., Middleboro, Mass.


Filed Aug. 7, 1968, Ser. No. 750,985

Int. Cl. A47b 97/08

U.S. Cl. 248—459

3 Claims

An easel-type mount having a headboard and baseboard disposed at an angle to each other such that the headboard



tively flat angle, and a leg and brace for holding the headboard and baseboard at said angle.

3,580,537

PROCESS FOR DRESSING ASBESTOS ORE WASTE

Ehrhardt Andreas, Munster in Westfalen, Germany, assignor to Hazemag Hartzerkleinerungs-Und Zementmaschinenbau-Gesellschaft, m.b.h., Munster, Westphalia, Germany

Filed June 19, 1969, Ser. No. 834,694


Claims priority, application Germany, June 20, 1968,

P 17 60 686.9

Int. Cl. B27k 7/00; B27i 9/00; B27l 11/00

U.S. Cl. 241—4

10 Claims



A process for dressing asbestos ore waste in which the waste material is dried by whirling it through a stream of hot gas to prevent encrustation of the material during the drying process and to separate at least some of the asbestos fibers from the ore waste and by subsequently comminuting the material in an impact breaker to separate substantially all remaining fibers from the ore and the fibers from each other.

3,580,538

PNEUMATIC SYSTEM FOR AIR MOTOR CONTROL

Leon M. Wyrick, Pleasant Hill, Calif., assignor to Chevron Research Company, San Francisco, Calif.

Continuation-in-part of application Ser. No. 492,191, Oct. 1, 1965, now abandoned. This application Nov. 20, 1968, Ser.

No. 786,527


Int. Cl. F15b 13/16; F16k 13/12

U.S. Cl. 251—29

7 Claims

In a pneumatic amplifying and actuating circuit for a control system useful in controllably varying a stem of a valve within a process line, complementary output stages of the

amplifying and actuating circuit are separately utilized (depending on the direction of deviation of a control signal with



respect to a setpoint pressure level) to automatically control the repositioning of the valve stem.

3,580,539

VALVE SEAL AND SYSTEM


Davis A. Van Scoy, Houston, Tex., assignor to Helmerich & Payne, Inc., Houston, Tex.

Filed Jan. 15, 1968, Ser. No. 697,979

Int. Cl. F16k 25/00

U.S. Cl. 251-159

14 Claims




A hydraulically retractable valve seal comprising a sleeve seat member mounted for limited sliding movement in a counterbored flow passage of a valve. The seat member is biased toward the closure member of the valve by springs mounted between an outwardly flaring flange portion of the seat member and the valve body. A resilient sealing member is mounted on the inner face of the seat member for sealing contact with the valve closure member. An annular chamber is formed between the counterbore of the valve body and the cylindrical exterior of the seat member. This chamber is sealed at one end by a stationary ring seal connected to the valve body and at the other end by a ring seal connected to the seat member flange for sliding contact with the counterbore. The annular chamber is connected to a pressure source for selectively overcoming the spring bias to retract the seat member and consequently the sealing member from sealing contact with the valve closure member.

Also, a system employing a valve equipped with the seal described comprising an electrical power source for energizing relay and time delay devices to first activate a pump for retracting the seal then second activate an operator for rotating the valve closure member only after the seal is completely disengaged therefrom. A limit switch attached to the operator deenergizes the electrical circuits, after complete rotation of the closure member, to stop the pump and relieve pressure from the annular chamber of the valve seal. The seal once again engages the closure member under spring bias.

3,580,540
ROTATABLE MULTI-PORT VALVE WITH FLUID
PRESSURE CONTROLLED VALVE MEANS
Irving Joseph Heinen, 3758 Parkview Drive, Lakewood, Calif.
Filed Oct. 3, 1968, Ser. No. 764,743
Int. Cl. F16k 5/18

U.S. Cl. 251-159

1 Claim



A rotatable multiport valve structure which is susceptible of use, for example, in two, three, or four-way, and the like flow control valves, and includes a hollow valve body within which there is rotatably mounted a normally freely rotatable flow control gate means containing flow passages or channels which are selectively positionable in registration with body ports communicating with flow passages having connector members for connection with conduits. Sealing of the registered flow channels or passages at each port is accomplished by means of a fluid pressure actuated ring piston reciprocally motivated to seated and nonseated positions at its inner end with respect to an annular seat carried by the rotatable gate means, and wherein the piston in seated position acts to lockingly retain the gate means against movement.

3,580,541
COCK

Marcel Bouhot, 35 Avenue du General Sarrail, Paris, France


Filed Jan. 22, 1970, Ser. No. 4,995

Claims priority, application France, Jan. 27, 1969, 6,901,529

Int. Cl. F16k 5/06

U.S. Cl. 251-174

6 Claims




A cock comprising a body, a closure member displaceable within said body so as to establish or interrupt a communication between two orifices formed in opposite relation within said body and in the vicinity of each orifice a seal engaging said closure member. Each seal comprises a tubular ring of polytetrafluoroethylene which is engaged in a recess formed in the body and in fluidtight contact with a packing fitted in the wall of said recess; the tubular ring is provided with a deformable lip applied by a washer in fluidtight contact with the closure member. Owing to this arrangement, the polytetrafluoroethylene lip does not creep and the packing fitted in the wall of the recess is not caused to swell.

3,580,542
PUSHBUTTON VALVE
Allen C. Wright, Moraga, Calif., assignor to Haws Drinking
Faucet Company, Berkeley, Calif.
Filed Sept. 5, 1969, Ser. No. 855,599
Int. Cl. F16k 1/10

U.S. Cl. 251-282

10 Claims



A pushbutton valve of the type used in drinking fountains to control the flow of water to the discharge nozzle thereof. The moveable control component of the valve assembly is isolated from unbalanced pressure forces and is therefore displaceable between the open and closed positions thereof with substantially the same manual force irrespective of the pressure of the water supply delivered to the fountain. The valve assembly includes a casing defining a cylinder having inlet and outlet passages and communicating therewith intermediate its ends and at laterally spaced locations. A control piston reciprocable within the cylinder is moveable between open and closed positions and is spring biased toward the closed position thereof. The piston has a valve chamber intermediate its ends within which is located a valve structure providing a pressurizable chamber and inlet and outlet ports opening thereinto and communicable with the inlet and outlet passages of the assembly when the control piston is in its open position. The valve structure is comprised of a plurality of individual components, and water pressure within the pressurizable chamber biases the valve components into slidably sealing engagement with the walls of the cylinder.


3,580,543
TRAILER JACK

Otto F. Hafeli, Rte. 4, Box 929, Port Angeles, Wash.
Filed Nov. 29, 1968, Ser. No. 782,509

Int. Cl. B66f 3/36

U.S. Cl. 254-100

4 Claims



A generally rectangular bracket is secured to the underside of a trailer and provides a slot for receiving a tongue that is


mounted on a slidable sleeve. The lower side of the bracket is shorter than the upper side to receive a brace that is welded between the sleeve and the brace so that the weight of the trailer is supported on the brace. The sleeve is adjustably mounted on an elongated frame and is locked in any desired position along the frame by a conventional pawl and detent mechanism. A nut is welded to the lower end of the elongated frame and a guide collar is welded to the top end. A threaded shaft extends through the collar and nut to position the elongated frame above the ground. The upper end of the threaded shaft is provided with a square head to be turned by a wrench or ratchet. The lower end of the shaft is rounded and rests in a cup formed integrally on a flat support plate.

3,580,544
TOOL FOR USE WITH DISC BRAKES
Arthur Albert Payne, Birmingham, England, assignor to
Girling Limited, Birmingham, England
Filed Nov. 7, 1968, Ser. No. 774,067
Claims priority, application Great Britain, Nov. 10, 1967,
51255/67

Int. Cl. B66f 3/00

U.S. Cl. 254-131

5 Claims



A tool for pushing back a piston in a cylinder of a disc brake comprises a bar of substantial length. The opposed end edges of the bar are of outwardly convex section and the dimensions between these edges is greater than the thickness of the bar between opposed sides. The dimensions between the opposed end edges correspond to the distances between the disc of a disc brake and the inner end of the piston when the piston is fully retracted, and the distance between the sides of the bar is slightly less than the space between the piston and the disc left after removal of a friction pad assembly.

3,580,545
APPARATUS FOR AGGLOMERATING DUSTS AND THE
LIKE

Edward D. O'Brien, Woodside, Calif., assignor to Stauffer
Chemical Company, New York, N.Y.


Continuation-in-part of application Ser. No. 652,922, July 12,
1967, now abandoned. This application May 23, 1969, Ser.

No. 858,213

Int. Cl. B01f 9/06

U.S. Cl. 259-3

10 Claims



apparatus for agglomerating fine particles including a rotatable mixer, generally resembling a rotary drum dryer,

having optionally a conveyor, such as a spiral vane, as an aid in moving particulate base material therethrough, an applicator, such as a manifold with spray nozzles for applying a liquid or another solid particulate material to the base material and thereby effecting coating and agglomeration of the base material, and lifter elements mounted within the mixer and rotatable therewith adapted to move through the normally relatively dormant central region of the mass of base material and thereby cause the base material in this region to become mixed with the base material in the normally actively moving inner and outer regions of said mass.


3,580,546

DEVICE FOR MIXING AND PROPORTIONING LIQUIDS
Colin Kenneth Glenn Fraser; Ernest Favreau, and Willis Paul March, Vancouver, British Columbia, Canada, assignors to Kaydon Technical Enterprises, Ltd., Vancouver, Canada
Filed Sept. 3, 1969, Ser. No. 854,888

Claims priority, application Canada, Sept. 5, 1968, 029,275
Int. Cl. B01f 15/04; G05d 11/02

U.S. Cl. 259—4

23 Claims



An apparatus for mixing and proportioning liquids includes a plurality of tanks for containing liquids to be mixed together. Each of the tanks has a bucket carrying assembly disposed therein, each such assembly being arranged for rotation to cause the buckets to successively enter into and emerge from the liquid contained in their respectively associated tank. The buckets are provided with means whereby each bucket is completely filled during each rotation cycle of each assembly. The buckets are also provided with means to effect discharge of the content of the buckets at a discharge region and a mixing device is provided to receive the discharged liquids and mix them together. The liquid capacities for buckets of each assembly are preselected to permit the several liquids to be mixed together in the desired proportions.

3,580,547

PACKAGE, LIQUID FLUSHED, STEADY BEARING ASSEMBLY

Franklyn J. Amorese, Hilton, N.Y., assignor to Sybron Corporation, Rochester, N.Y.

Filed June 13, 1969, Ser. No. 832,929


Int. Cl. B01f 7/20; F16c 1/26

U.S. Cl. 259—23

10 Claims

Disclosed is a liquid flushed, steady bearing assembly which can be mounted as a package to the exterior of a mixing vessel to support the free end of an agitator shaft protruding outwardly from the vessel so that the wear bearing of the assembly is serviceable from outside of the vessel. The flushing liquid is discharged radially from the assembly and into

the vessel in a single stream from between a stationary member and a rotating member located within the vessel,



wherein the spacing between these members can be controlled in part from outside of the vessel.

3,580,548

CONVEYOR ATTACHMENT FOR PORTABLE FEED MILL


Carroll E. Moore, Minneapolis, Minn., assignor to Farmhand, Inc., Hopkins, Minn.

Filed May 16, 1969, Ser. No. 825,366

Int. Cl. B01f 5/12, 7/00

U.S. Cl. 259—95

7 Claims



An attachment for mounting a feeding auger to the mixing tank of a portable feed mill for driving engagement with a rotary mixing device in the mixing tank, to convey material selectively to a plurality of inlets to the mixing tank, from various points of supply exterior of the tank. Supporting structure is rotatively mounted on the mixing tank and the feeding auger is operatively connected to the supporting structure for universal swinging movements relative to the supporting structure.

3,580,549

GRAIN STIRRING DEVICE

David M. Murphy, Mason City, Iowa, assignor to David Manufacturing Co., Mason City, Iowa

Filed July 31, 1969, Ser. No. 846,362


Int. Cl. B01f 7/00

U.S. Cl. 259—102

16 Claims

A device for stirring material in a cylindrical container and which includes a support means mounted within the container for orbital movements about the vertical axis thereof, a trolley means mounted on the support means for movements radially toward and away from the all of the container, and a stirring auger having the upper end thereof rotatably

mounted on an auger support means carried by the trolley means. The auger support means depends from the trolley means and extends laterally outwardly therefrom toward the wall of the container so as to position the auger in close proximity and substantially parallel to the wall of the container



when the trolley means is fully moved radially toward the wall of the container. Drive means is connected to move the support means in its orbital path of travel, to move the trolley means radially toward and away from the wall responsive to movement of the support means, and to rotate the stirring auger.

3,580,550

MIXING APPARATUS


Roy Hunnicutt, Box 9108, Amarillo, Tex.

Filed June 13, 1968, Ser. No. 736,729

Int. Cl. B01f 7/20

U.S. Cl. 259—107

3 Claims



A bladed mixing rotor particularly for viscous liquids having plural radial blades projecting from a central hub. Each blade has a first recess in its lower surface adjacent the hub and a second recess in its top surface outwardly of the first recess. Two inclined pumping surfaces are thus formed on each blade, the pumping surfaces being reversely inclined.

3,580,551

CONCRETE AND THE LIKE MIXER

Heinz Hammann, Speyerdorf, and Werner Dick, Eisingen, Germany, assignors to Lico A G, Glarus, Switzerland

Filed Aug. 14, 1969, Ser. No. 850,112

Claims priority, application Germany, Aug. 21, 1968, Nov. 8, 1968, G6,752,714; G6,805,948


Int. Cl. B28c 7/16

U.S. Cl. 259—152

10 Claims

A concrete or the like mixer comprises an open-topped main mixing container and a premixer disposed above the main mixing container and having a circular bottom wall rotated about a vertical axis and normally frictionally engaging the lower part of a cylindrical sidewall forming a premixing container together with said bottom wall. In order to

discharge the contents of the premixer into the main mixing container, the bottom and sidewalls of the premixer are temporarily disengaged, to provide a peripheral annular discharge passage.



3,580,552

STACK PREHEATER

Dan Sigurd Hansen, Copenhagen-Valby, Denmark, assignor to F. L. Smidth & Co., New York, N.Y.


Filed Apr. 9, 1969, Ser. No. 814,774

Claims priority, application Great Britain, Apr. 24, 1968, 19,440/68

Int. Cl. F27b 7/02; F26b 17/00

U.S. Cl. 263—32

4 Claims



A heat exchanger for preheating granular or pulverulent material especially when such material is fed to a rotary kiln. The preheater is in the form of an upright stack or tubular conduit within which means is fixedly mounted extending from the bottom to the top of the stack and providing guiding surfaces for the heating gas which flows upwardly through the stack, and for the granular or pulverulent material as it flows downwardly countercurrent to the gas flow.

3,580,553

GRATE STRIPPER FOR PELLETIZING MACHINE


Daniel M. Ulrich, Hibbing, Minn., assignor to Eveleth Taconite Company, Forbes, Minn.

Filed May 14, 1969, Ser. No. 824,397

Int. Cl. F27b 7/02

U.S. Cl. 263—32

7 Claims



An improved pellet hardening machine or assembly includes a preheating section wherein pellets of iron ore are

preheated and an indurating section wherein the preheated pellets are heated to a desired hardness. A stripper assembly is provided for removing pellets from a conveyor on which they are transported. The stripper assembly is cooled by a flow of air from a pump or other source of air under pressure. This air is discharged from the stripper assembly in jets or streams which promote fluidization of relatively fine particles of material carried by the conveyor.

3,580,554

APPLIANCE FOR SUPPLYING GAS INTO A PREDETERMINED ZONE


Vladimir Pavlovich Bushuev, ul Mostovaya, 8, kv. 64; Georgy Viktorovich Gubin, ul Kharitonova, 8a, kv. 2; Petr Semenovich Zolotarev, ul Mostovaya, 18, kv. 45; Vladimir Andreevich Sorokin, ul 23 Ljutogo, 26, kv. 26; Vladimir Ivanovich Palamarchuk, per Zhurnalstov, 8, kv. 21, and Viktor Makarovitch Dmitrenko, ul Kropivnitskogo, 30, kv. 37, all of Krivoi Rog, U.S.S.R.

Filed Apr. 23, 1969, Ser. No. 818,611

Int. Cl. F27b 7/00

U.S. Cl. 263—33

3 Claims



A device for supplying gas into a predetermined zone of a roasting kiln rotating about its longitudinal axis. The device includes an annular collector externally enclosing the kiln and secured thereon. The collector is connected to a gas line and branch pipes of the collector to burners disposed in rows along the kiln. Mounted on the branch pipes are shut-off devices. Provided in the plane of rotation of the shut-off devices are stops: one for opening the cocks disposed at the inlet of the burners of its row into the predetermined zone of the kiln, and the other for closing the cocks disposed at the outlet of the burners from the predetermined zone of the kiln.

3,580,555

METHOD AND DEVICE FOR HEAT TREATMENT OF METALS


Harlan G. Gearhart, La Canada, Calif., assignor to VST Corporation, Pasadena, Calif.

Filed May 6, 1968, Ser. No. 732,796

Int. Cl. C21d 1/66

U.S. Cl. 266—4R

6 Claims



A furnace and resultant novel method for the heat treatment of metal parts, particularly of alloys containing titanium, comprising a heated retort maintained under continuous

pressure by an inert gas with the retort feeding directly into a liquid quench bath. The parts are admitted to the furnace through a vacuum trap so that no air can enter the furnace to contaminate the material.

3,580,556

SAFETY SHIELD FOR A FUME-COLLECTING APPARATUS


John D. Roscoe, Baltimore, Md., assignor to Bethlehem Steel Corporation

Filed Apr. 18, 1968, Ser. No. 722,295

Int. Cl. F27d 21/00

U.S. Cl. 266—16

2 Claims



A safety shield placed and secured under a fume-collecting apparatus for a metallurgical furnace when the furnace is not operating, thereby preventing slag accumulated within and on the apparatus during furnace operation from falling upon workmen below. The shield may be placed under the apparatus by setting it on a rig, moving the rig under the apparatus, securing the shield under the apparatus, and subsequently removing the rig.

3,580,557

RAILWAY SPRING SUSPENSION


Albert G. Dean, Narberth, Pa., assignor to The Budd Company, Philadelphia, Pa.

Filed Jan. 30, 1969, Ser. No. 795,218

Int. Cl. B61f 5/04; F16f 3/10, 13/00

U.S. Cl. 267—3

1 Claim



Air spring apparatus consisting of two axially aligned cylinders connected by an elastomer ring which provides an air seal. The shear capacity of the ring is slight, permitting relatively free axial movement between the cylinders but is substantially incompressible to compression loads to prevent relative lateral movement of the cylinders.

3,580,558

CUSHION MOUNTING IN PUNCH PRESS

Robert A. Helrigel, Hastings; James R. Brownell, Delton; Roderick K. Ward, and Harry E. Keithley, Hastings, Mich., assignors to E. W. Bliss Company, Canton, Ohio

Filed Jan. 8, 1969, Ser. No. 789,868


Int. Cl. F16k 9/31

U.S. Cl. 267—114

4 Claims

A machine press bed assembly including an air cushion seated in the press bed, air input means integral with the press bed floor, aperture means in an end wall of the cushion

accommodating said air input means, and holddown means which an elastomeric mass is confined in a chamber whose penetrating the press bed sides engaging the cushion, the volume is variable without any sliding joint, the chamber in-



cushion being removably from said press bed by disengaging the holddown means.

3,580,559

HYDROPNEUMATIC PISTON-CYLINDER ARRANGEMENT

Rudolf Spieth, Plochingenstrasse 156, Esslingen, and Gunter Otto, Lindenstrasse 3, Altbach, Germany

Filed Nov. 13, 1968, Ser. No. 775,472


Claims priority, application Germany, Oct. 1, 1968,

P1800020.9

Int. Cl. F16g 9/08

U.S. Cl. 267—126

11 Claims



An improved hydropneumatic piston-cylinder arrangement, adapted to be blocked from the outside, with a fluid-filled and a gas-filled chamber, a piston mounted in the fluid-filled chamber with an externally projecting piston rod, wherein the chamber filled with fluid contains a fixed partition provided with passages for the fluid and the said passages are completely closing by blocking means adapted to be opened from the outside. The arrangement may be constructed as a tension spring or as a compression spring, wherein the compression spring construction is preferred for the lockable, stepless adjustment of table tops, driving seats and the like.

3,580,560

RESILIENT DEVICES

Jacques Jarret, Le Vesinet, and Jean Jarret, Fourqueux, France, assignors to Societe D'Exploitation Des Ressources Auto-Amortisseurs Jarret, Paris, France

Filed Feb. 18, 1969, Ser. No. 800,227


Claims priority, application France, Feb. 19, 1968, 140,375

Int. Cl. F16f 1/37

U.S. Cl. 267—153

4 Claims

This invention is concerned with a compression spring in



cluding a toric portion enclosing a cylindrical portion whose height is small compared to its diameter.

3,580,561

ARTICLE HOLDING APPARATUS


Reuben J. Krein, Forest City, Iowa, assignor to Stitchcraft Corporation, Forest City, Iowa

Filed Dec. 3, 1968, Ser. No. 780,707

Int. Cl. B25b 5/14

U.S. Cl. 269—81

13 Claims



A jig for supporting a seat frame selectively in an upright position and in a horizontal position to facilitate mounting of backrest, cushion and covering on the seat frame. The jig has four spaced assembly stations each having an upright post pivotally carrying a support. Rotatably mounted on the support is a seat frame holder releasably attachable to a portion of the seat frame. A latch holds the support in an upright position. On release of the latch, the support can be pivoted into engagement with a stop to locate the seat in a generally horizontal position.

3,580,562

APPARATUS FOR OPENING FOLDED ARTICLES, SUCH AS NEWSPAPERS

Walter Reist, Hinwil, Switzerland, assignor to Ferag, Fehr & Reist AG, Hinwil, Zurich, Switzerland

Filed Jan. 29, 1969, Ser. No. 795,006

Claims priority, application Switzerland, Feb. 2, 1968,

1591/68


Int. Cl. B65h 39/02

U.S. Cl. 270—54

6 Claims

Apparatus for opening folded newspapers which arrive from a printing press in imbricated succession and are separated into single copies, comprises conveyor means to carry the folded copies along in spaced relation. Opposite gripping jaws are provided to grip the two folded halves of the newspapers and cause a sliding movement of the two halves relative to each other in a direction at right angles to

the fold to expose one edge portion of the folded newspaper while further gripping jaws grip the exposed edge portion and the edge portion of the other half of the folded newspaper. The gripping jaws are attached to endless conveyor means to



move along with the moving newspapers and are controlled to open the two halves of the newspapers, while further conveyor means supply enclosures or supplemental sheets to be slipped laterally into the opened newspapers.



3,580,563

COLLATING MACHINE FEEDING INTO OR OUT OF RACKS

Ernest D. Bassett, Box 545, Santa Barbara, Calif.
Filed Jan. 30, 1969, Ser. No. 795,153
Int. Cl. B65h 39/02

U.S. Cl. 270—58

3 Claims




A horizontal elongated framework carries a plurality of transverse, inclined, parallel, paper-supporting racks. A conveying system on the machine, including a belt, transports sheets of paper emerging from a reproduction apparatus into predetermined ones of the racks. After the desired number of sheets have been placed in the racks in the appropriate sequence, various adjustments are made to the machine, including reversal of belt movement, enabling the machine to collate the sheets of paper previously assembled in the racks. The collating mechanism includes structure enabling the operator to adapt the machine to varying paper sizes, textures and weights.

3,580,564
FEEDING APPARATUS FOR NONRIGID SHEET
Ira D. Boynton, Lexington, and Willard G. Sylvester, Concord, both of, Mass., assignors to Apparel Research Foundation, Inc., Washington, D.C.
Filed Dec. 2, 1968, Ser. No. 780,397
Int. Cl. B65h 3/20

U.S. Cl. 271—33

5 Claims




Apparatus for separating and delivering single sheets of a nonrigid material from a stack. The sheets in the stack are held in a slightly bent configuration and periodically a corner or peripheral area of the under surface of the bottom piece is exposed and pulled downwardly to allow horizontally movable separating means to move between the stack and the initially partially separated bottom piece to complete its separation, free it from the stack and permit it to drop by gravity.

3,580,565
SHEET FEEDING APPARATUS
Donald G. Mallory, Penfield, and Lyman H. Turner, Pittsford, assignors to Xerox Corporation, Rochester, N.Y.
Filed Dec. 11, 1968, Ser. No. 782,908
Int. Cl. B65h 3/06

U.S. Cl. 271—39

8 Claims




Sheet feeding apparatus incorporating a tray for storing precut sheets; first feeding means contactable with the topmost sheet of the precut sheet stock to feed precut sheets forward in seriatim; means to raise the tray to maintain the topmost sheet of the precut sheet stack in operative contact with the first feeding means as precut sheets are removed therefrom; second feeding means disposed under and jointly movable with the tray and cooperable with the base of the tray to form a passageway for feeding of ready cut sheets from a roll stock converter forward; and aperture means in the tray base enabling the first feeding means to drivingly contact the second feeding means when the tray is empty following raising of the tray to a maximum height.

3,580,566
ASYNCHRONOUSLY CONTROLLED ARRANGEMENT FOR FEEDING RECORD CARDS
Jacques Vasse, L'Hay les Roses, France, assignor to Societe Industrielle Bull-General Electric, (Societe-Anonyme), Paris, France

Filed Apr. 14, 1969, Ser. No. 815,846
Claims priority, application France, Apr. 23, 1968, 149,082
Int. Cl. B65h 1/06

U.S. Cl. 271—41

4 Claims




A card-feeding arrangement comprising a friction roller controlled by an electromagnet for advancing a card through a throat as far as driving rollers and a detector. A pulse generator receives a control pulse for feeding a card, transmits in response a first pulse to the electromagnet through a first switch and thereafter a signalling pulse through a second switch; the arrival of a card in the detector transmits a pulse which opens the switches and hence deenergizes the electromagnet and prevents the transmission of the signalling pulse.

3,580,567
AUTOMATIC ELEVATING MECHANISM FOR A PAPER FEED PLATFORM OF AN AUTOMATIC PAPER FEED DEVICE FOR USE WITH A PHOTOCOPYING MACHINE, PRINTING PRESS, OR THE LIKE
Hideo Hashimoto, Koshigaya-shi, Japan, assignor to Kabushiki Kaisha Ricoh, Tokyo, Japan
Filed Aug. 27, 1968, Ser. No. 755,539
Claims priority, application Japan, Aug. 31, 1967, 42/55507
Int. Cl. B65h 1/18

U.S. Cl. 271—62

3 Claims




When the height of a stack of papers to be copied or printed falls below a predetermined level, the level of the stack is sensed by a sensing roller which closes the circuit for a solenoid through a microswitch attached to the sensing roller. A blocking plate is pulled downwardly by the solenoid and a constantly reciprocating engaging pawl is thereby al-

lowed to engage a ratchet wheel, thereby moving upwardly a rack in mesh with a pinion integral with the ratchet wheel, whereby a paper feed platform supported by the rack can be elevated up to a predetermined level.

3,580,568
TIGHTROPE DEVICE
Guthrie B. Stone, Honeoye, N.Y.
Filed July 29, 1968, Ser. No. 748,353
Int. Cl. A63b 23/04

U.S. Cl. 272—60

4 Claims




A stout rope is glued or otherwise fastened in a groove atop the upper edge of a support rail which is about 6 inches high and an inch more or less in cross section. The lower edge of the support rail is retentively but removably seated in keeper notches provided in upper edge portions of longitudinally spaced transverse footlike blocks.

3,580,569
TRAINING FRAME FOR USE IN LEARNING HOW TO RIDE A UNICYCLE OR WALK ON THE HANDS
Henry Allen Wilson, General Delivery, Miami Beach, Fla.
Filed Oct. 14, 1968, Ser. No. 767,336
Int. Cl. A63b 69/16

U.S. Cl. 272—60

2 Claims



A unicycle training device in the form of a mobile frame open at the front to the supporting floor between vertical side rails that extend materially above the head of the learner when mounted on the seat of a unicycle between outwardly curved horizontal side rails which are adapted to be grasped by the hands of the learner, who must have freedom for balancing gyrations when so mounted prior to propelling the unicycle through the open front of said frame free of said rails and for other training in balancing free of said frame. The device comprises a pair of U-shaped members mounted on casters and secured together by parallel brackets. The lower bracket is an arc of a circle and spaced about hip high from the floor.


3,580,570 FOLDABLE TRAMPOLINE

Robert M. Fenner, and Donald E. Hamilton, Englewood, Colo.

Filed June 11, 1968, Ser. No. 736,043
Int. Cl. A63b 5/00

U.S. Cl. 272-65

8 Claims




Two U-shaped, trussed end frames hinged together at their terminal extremities by straight, trussed side frames so that the end frames may be folded over the side frames for storage or opened out into the plane of the side frames to form an open, rectangular, peripheral bed frame which tensionally supports a conventional trampoline bed. Foldable leg elements hinged below said side frames for supporting the latter from the floor and foldable leg-bracing elements hinged below said end frames for maintaining said leg elements in the proper supporting positions, said frames being covered by cushioned deck pads which form a deck-way completely about said trampoline bed.

3,580,571 CHAIN SWING

Martin Green, Mahwah, N.J., assignor to Blazon, Inc., Jamestown, Pa. Division of Ser. No. 587,455, Oct. 18, 1966, abandoned.

Filed Jan. 27, 1969, Ser. No. 798,575
Int. Cl. A63t 7/06; A47c 15/00; A47d 13/10
U.S. Cl. 272-85

3 Claims



A chain swing for an outdoor amusement device having four chains supporting a bar, curved seats which are held apart by spacebars and held fast to the chains by spring pin arrangements, the spring pin arrangements including springs interposed between the bottom of the spacebar and extensions or wings of the spring pin arrangement for resilient cushioning of said seats.


3,580,572 BOWLER'S EQUALIZING WEIGHT

Richard A. Stafford, 7200 Cerritos Ave. Apt. A, Stanton, Calif., and William J. Davis, 8652 San Carlos Ave., Stanton, Calif.

Filed Nov. 13, 1968, Ser. No. 775,409
Int. Cl. A63b 71/14

U.S. Cl. 273-54

1 Claim



An equalizing weight of elongate arcuate configuration that substantially conforms to the exterior surface of the hand or wrist, and may be removably secured thereto to improve the performance of the bowler using the same.

3,580,573 FOOTBALL FIELD AREA IDENTIFICATION MEANS


Michael F. Noonan, 136 Church St., Plymouth, Pa., and James J. Fisher, 11 Franklin St., Larksville, Pa.

Filed Apr. 22, 1968, Ser. No. 723,355

Int. Cl. A63b 67/00

U.S. Cl. 273-55

10 Claims



The present application discloses a standard-sized, rectangular football playing field characterized by the fact that it is marked off by parallel, transverse lines spaced every five yards between a pair of transverse goal lines spaced 100 yards apart. Normally, these transverse lines, called yard lines, are colored white, as are the parallel, longitudinal lines which extend the full length of the playing field and define its lateral boundaries; however, in the present disclosure, certain of the transverse lines, which preferably include the goal lines, the midfield or 50-yard line and each of the six transverse yard lines nearest each of the goal lines are colored other than white to distinguish these lines, and the zones defined thereby, from other lines and zones on the field.

3,580,574 FOOTBALL BLOCKING SLED

John C. Hornak, 617 Blossom Drive, and Douglas F. Thompson, 2329 "G" St., Lorain, Ohio

Filed Apr. 18, 1969, Ser. No. 817,341
Int. Cl. A63b 67/00

U.S. Cl. 273-55

10 Claims

Means are disclosed for limiting the height at which a football player may strike the contact pad on a blocking sled of


3,580,576 BILLIARD CUE AND REPLACEABLE CUE TIP ASSEMBLY

Anthony Merola, Pittsburgh, Pa., assignor to Amerola Products Corporation, Pittsburgh, Pa.

Filed Apr. 30, 1968, Ser. No. 725,450
Int. Cl. A63d 15/12

U.S. Cl. 273-70

6 Claims



A billiard cue having a ferrule secured to one end. The ferrule detachably receives a cue tip. In one embodiment, the ferrule is of aluminum and has a knurled stud at one end received in a bore in the end of the cue stick. The cue tip has a body of vulcanized fibrous material and a tip of leather. One end of the tip body has a tapered frustoconical portion frictionally fitting a bore in the ferrule. The other end of the tip body is bonded to the leather tip.


3,580,577 COPOLYLACTAM BOWLING PIN

Thomas J. Hyde, Woodbury, and Leonard A. Targonski, Pennsville, N.J., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

Filed May 9, 1968, Ser. No. 727,793
Int. Cl. A63d 9/00

U.S. Cl. 273-82

8 Claims



A bowling pin comprising a hollow elongated body made of a copolylactam composition containing at least 65 percent by weight polymerized caprolactam moieties, at least 1 percent by weight polymerized lactam moieties having from seven to 12 carbon atoms and N-alkyl pyrrolidone.


3,580,578 BOUNCING BALL GAME METHOD

James B. McCarthy, Verona, Pa., assignor to Game Innovations, Inc., Verona, Pa.

Filed June 9, 1969, Ser. No. 831,630
Int. Cl. A63b 63/00

U.S. Cl. 273-95R

1 Claim



Apparatus for playing a court game with a resilient ball is disclosed which includes a court divided into sections for opposing players having dividing lines and foul lines. At the end of each section there is a vertical plate or panel having a plurality of holes or goals each covered by a net. The object of the game is to bounce the ball into a goal at the opposite end. The goals are placed and shaped so as to require different degrees of skill for scoring and are assigned correspondingly different score points.

the type comprising a base, a support and a resilient member. The height-limiting means include a generally horizontally extending interference member capable of being positioned at a location spaced from the contact pad and at a predetermined height from the ground, and means for securing that member to the training sled so that the horizontal member effectively limits the height at which the player may contact


the sled. The member may be pivoted to a neutral position when not in use. A second feature of the invention includes means for causing the player to maintain his feet at least a predetermined distance apart during his line charge. The stance-extending means includes a telescoping member having a predetermined width. Both the height-limiting means and the stance-extending means may be attached to existing training sleds, or may be integrally built into new sleds.

3,580,575 GAME DEVICE INCLUDING SELECTIVELY IMPACT OPERABLE LIGHTS

Sheridan D. Speeth, Buffalo, N.Y., assignor to Autotelic Industries Limited, Fort Erie, Ontario, Canada

Filed Sept. 27, 1967, Ser. No. 670,875
Claims priority, application Canada, Aug. 28, 1967, 998,855
Int. Cl. A63b 43/06; A63h 33/26
U.S. Cl. 273-58

14 Claims



An impact toy, such as a ball, capable of withstanding an impact and having three different colored lamps supported within the interior of the toy. A switch device having a movable contact and three fixed contacts each associated with a different colored lamp is provided in an electrical circuit so that when the toy is subject to an impact, the movable contact touches a fixed contact to cause one lamp to be illuminated. The selected fixed contact is dependent on the point of impact. In alternative embodiments, the lamps may be embedded in the wall of the ball or within a transparent epoxy resin material filling the interior of the ball. The impact toy may take the form of a punching toy simulating a human figure, include audible signalling devices and electrical circuits including transistors and capacitor-resistor networks.

3,580,579

ELECTRIC TARGET APPARATUS FOR INDICATING HIT POINTS

Armin Scharz, and Oskar Scharz, Interlaken Bern, Switzerland, assignors to Polytronic S. A., Saint-Aubin (Neuchatel), Switzerland


Filed Feb. 21, 1969, Ser. No. 792,340

Claims priority, application Switzerland, Jan. 19, 1968, 861/68

Int. Cl. F41j 5/04

U.S. Cl. 273-102.2A

12 Claims



A target apparatus for automatically indicating the hit point of a projectile comprises a plurality of target elements mounted one behind the other, each element including two electrically insulated parallel sheets of electrically conductive material and included in an electric circuit, the distance between the two conductive sheets being less than the length of a projectile. At least two of the target elements are situated in planes which are inclined one relative to the other, whereby said relatively inclined target elements, when traversed by a projectile, produce pulses in timed sequence which are used to determine the hit point of the projectile on the target.

3,580,580

AERIAL SPINNING DISC


John D. Wark, 326 W. Lena Ave., Freeport, and Peter Schladermundt, 8 Park Ave., Bronxville, N.Y.

Filed Sept. 24, 1969, Ser. No. 860,485

Int. Cl. A63b 65/10; A63h 27/00

U.S. Cl. 273-106

4 Claims



A spinning aerial device or "flying saucer". It is a disc with a centered circular opening and has a plurality of concentric sections including an annular body section with downwardly extending flanges formed along the inner and outer edges of said body section.

3,580,581

PROBABILITY-GENERATING SYSTEM AND GAME FOR USE THEREWITH

Richard C. Raven, Reno, Nev., assignor to Raven Electronics Corporation

Filed Dec. 26, 1968, Ser. No. 787,146


Int. Cl. A63b 71/06

U.S. Cl. 273-138A

13 Claims

In order to select an event at random from a set of possible events, wherein each event has a preselected and different probability of being selected, an electrical circuit is provided for generating a continuous cyclic succession of electrical output signals each corresponding to one event in which the time duration of each signal is individually controlled and

preset to provide a different time portion of the total combined time duration of all of the output signals and means are provided for interrupting this continuous train of output signals at an arbitrary point in time, whereby the output signal occurring at the time of this interruption is sensed and



the event associated therewith is accordingly selected. Furthermore, a series of these circuits is disclosed in combination with a set of visual monitors for symbolically displaying the selection of events to provide a game for amusement and entertainment in which each event and combinations thereof is assigned a winning or losing value.

3,580,582

BOX GAME


Constantine P. Calamvotsakis, 1706 Brush Creek Blvd., Kansas City, Mo.

Filed Apr. 16, 1969, Ser. No. 816,756

Int. Cl. A63f 9/00

U.S. Cl. 273-139

3 Claims



A box game for selecting a winner from a group of players, or for designating one person from the group to pay a "party penalty," by means of a process and apparatus involving chance and a high degree of interest and suspense, the apparatus consisting of a series of nested and numbered boxes adapted to be removed one at a time in turn by the players, whereby eventually to disclose a "token piece" concealed between any two successive boxes, and a set of dice adapted to be rolled by a nonplaying "dealer," who then places the token in accordance with the roll of the dice and assembles the boxes preparatory to play. The players may preselect and record the number of the box in which they believe the token to be concealed.

3,580,583

PUTTING GREEN INCLUDING MEANS FOR SEQUENTIALLY RETURNING HOLED-OUT BALLS TO PERIPHERALLY SPACED BALL DISPENSERS

Joseph A. Gentiluomo, 1456 Belmont Ave., Schenectady, N.Y.


Continuation of application Ser. No. 550,664, May 17, 1966.

This application Jan. 21, 1969, Ser. No. 796,284

Int. Cl. A63b 67/02

U.S. Cl. 273-176

6 Claims



A continuous putting green surface having a cup, undulations, and surface texture similar to a golf course putting green, thereby, providing players with varied length putts in which the ball line-of-roll may involve level, uphill, downhill, or sidehill travel or any combination thereof, either against, across, or with the grain of the putting surface or any grain combination thereof. Utilization of automatic ball-dispensing and ball return means eliminates player bending or stooping for balls both at the putting tees and at the cup. When the ball-dispensing means releases a ball upon the putting green, the ball return means is translated into ball-receiving position underneath the cup. A holed out ball will enter the ball return means and roll by gravity to the ball-dispensing means for subsequent reuse. This returned ball will initiate operation of a second ball-dispensing means to discharge a ball and cause the previously used ball return means to retract, and the ball return means associated with the second dispensing means to move into ball-receiving position underneath the cup. This sequence of operations will continue until balls are putted and holed out from the plurality of putting tee positions located on the putting green periphery.

3,580,584

GOLF PRACTICE DEVICE


David P. Trosko, San Francisco, Calif. (Pacific Architects & Engineers, Inc., Employee #1-02661, APO San Francisco, Calif. 96307)

Filed Mar. 10, 1969, Ser. No. 805,420

Int. Cl. A63b 69/36, 57/00

U.S. Cl. 273-186

1 Claim



A practice device for golfers for teaching the basic principles of driving, the device comprising a flexible rope or chord for defining an arc of travel for a golf club head, a cross rod for defining the position of the player's feet, a forward ex-

tending rod extending from the cross rod a plastic cup upon which a golf ball is supported, and a straight bar extending from the plastic cup into the direction toward the green.

3,580,585


Edwin O. Stastny, Santa Ana; Lester T. Stormon, Redondo Beach, and Anson Sims, Manhattan Beach, Calif., assignors to Mattel, Inc., Hawthorne, Calif.

Continuation of application Ser. No. 716,543, Mar. 27, 1968, now abandoned. This application Nov. 26, 1969, Ser. No. 873,742

Int. Cl. G11b 3/00

U.S. Cl. 274-1A

3 Claims



A sound-producing tape is wound on a reel having a spring-driven rewind. As the tape is pulled from the reel past a sound reproducer and a pivoted finger, the finger is pivoted due to its frictional engagement with the tape allowing the tape to inoperatively pass the sound reproducer. Upon release, the tape is automatically rewound onto the reel and is brought into operative association with the sound reproducer by the pivoted finger so that sounds are reproduced only during the rewinding operation.

3,580,586

INFLATABLE PACKING FOR STUFFING BOXES


Alvin G. Burns, 1020 E. 34th St., and Sheldon M. Miller, 4636 S. Wheeling, Tulsa, Okla.

Continuation-in-part of application Ser. No. 633,664, Apr. 12, 1967, now Patent No. 3,471,156. This application Oct. 3, 1969, Ser. No. 863,588

Int. Cl. F16j 15/40, 15/00, 9/00

U.S. Cl. 277-3

4 Claims



An inflatable packing gland for stuffing boxes utilized around the reciprocal polished rod of a producing oil well wherein the pressure of the packing member against the outer periphery of the polished rod may be automatically maintained at the most desirable level regardless of wear on the inner periphery of the stuffing gland.

3,580,587

CONTACT-FREE HYDROSTATIC SEAL

Dieter Born, Hessheim; Peter Stech, and Werner Huebner, Roxheim, Germany, assignors to Klein, Schanzlin & Becker A.G., Frankenthal, Pfalz, Germany

Filed Jan. 31, 1968, Ser. No. 702,001


Claims priority, application Germany, July 22, 1967, Aug.

11, 1967, DK62907; DK63081

Int. Cl. F16j 15/00; F16i 17/00

U.S. Cl. 277—3

3 Claims



A contact-free hydrostatic seal wherein a rotary first annular sealing element defines with a second annular sealing element a gap for leak fluid. The second sealing element is biased toward the first sealing element by closing springs which tend to reduce the width of the gap. A pump delivers fluid into the gap to oppose the action of closing springs and to prevent direct contact between the sealing elements. When the pressure of fluid drops to such an extent that it can be overcome by the bias of closing springs, a safety device becomes operative to oppose such bias and to hold the second sealing element away from the first sealing element. The safety device includes a set of plungers which are subjected to fluid pressure and engage the second sealing element when the pressure of fluid in the gap drops to a certain minimum permissible value, or a lever which is pivoted into engagement with the second sealing element by one or more strong springs when such strong spring or springs overcome the fluid pressure at a time when the fluid pressure is too low to prevent the closing springs from moving the second sealing element into frictional engagement with the first sealing element.

3,580,588

MOTOR-PUMP SHAFT SEAL


Howard L. Allen, and Charles D. De Graff, North Canton, Ohio, assignors to The Hoover Company, North Canton, Ohio

Filed May 22, 1969, Ser. No. 826,798

Int. Cl. F16j 9/00, 15/00

U.S. Cl. 277—32

5 Claims



An integral motor-pump of a wet pickup floor conditioner has a housing comprising pump and motor chambers. The

housing is generally divided along a plane forming two housing sections each having an integral web portion extending between the pump and motor chamber portions therein. When the housing sections are assembled the mating web portions define a barrier wall having an aperture through which an output shaft, from a motor mounted in the motor chamber, extends. A groove is formed in the planar mating surface of each of the housing sections around the pump chamber. The grooves in the mating surfaces are each connected at their ends by a groove portion in the periphery or boundary edge of the opening in the respective web. A substantially continuous elastomeric sealing means is fitted in each groove. An impeller-fan unit, rotatably carrying a sealing disc between a motor-cooling fan and a pump impeller is mounted on the motor shaft. When assembled in the housing the impeller is located in the pump chamber and the motor-cooling fan located in the motor chamber, with the sealing disc extending into the groove portions in the periphery of the aperture in the barrier wall, in contact with the elastomeric seal therein. The disc is generally circular in shape with diametrically opposed tapered extensions mating with complementary-shaped groove portions at the intersections of the aperture and the adjacent planar mating surfaces of the web. A generally circular, axially offset, portion of the disc lies within the circular aperture and has a pair of diametrically opposed ears. Each ear has a flat, the flats lying flush against planar surfaces of the web of one of the housing sections adjacent the aperture. Arcuate opposing surfaces on the ears cooperate with camming cutouts in the internal web of the other housing section at the intersection of the planar mating surfaces and the central aperture to center the sealing disc in the aperture in the barrier wall.

3,580,589

CIRCUMFERENTIALLY EXPANDING OIL CONTROL RING


Herbert F. Prasse, Town and Country, and Loyd D. Hensley, Creve Coeur, Mo., assignors to Ramsey Corporation, St. Louis, Mo.

Filed May 31, 1968, Ser. No. 733,661

Int. Cl. F02f 5/00; F16j 9/00

U.S. Cl. 277—140

14 Claims



A circumferentially expanding ring for spacing and expanding rail rings in a piston ring groove which ring has a plurality of integrally connected circumferentially spaced sections having upper and lower U-shaped lands integrally connected by axially upstanding lands and tongues projecting from some of the axially upstanding lands between the U-shaped lands to reinforce the upper and lower lands against collapse and/or to provide rail ring supports.

3,580,590

BEARING SEAL CONSTRUCTION

John F. Zotter, Southington, Conn., assignor to Textron Inc., Providence R.I.

Filed Nov. 7, 1969, Ser. No. 874,927

Int. Cl. F16j 15/32

U.S. Cl. 277—227

5 Claims

The invention contemplates a laminated seal construction and method utilizing a flat annular sheet of flexible material,

such as elastomeric material, laminated to a backing material, which at an axially thick portion defines a body, and which at an axially thin portion defines a seal member to be axially resilient deflected with respect to the body. The method of the invention calls for removing backing material after the laminating step, the removed material affording a



remainder which meets all requirements as to concentricity, circumferential uniformity of action, and the like. The material-removing step may be so characterized as to provide a local region for axial flexure, radially spaced from the region of wiping contact with the bearing ring to which it is sealingly engaged.

3,580,591

WHEELCHAIR ATTACHMENT


H. Franklin Coffey, Albuquerque, and Samuel T. Powers, Tijeras, both of, N. Mex., assignors to Lovelace Foundation for Medical Education and Research, Albuquerque, N. Mex.

Filed Dec. 24, 1968, Ser. No. 786,695

Int. Cl. B62b 5/02

U.S. Cl. 280—5.32

26 Claims



Wheelchair attachments, ordinarily installed in pairs, for enabling patients confined to wheelchairs to easily negotiate obstacles, such as curbs, in a conventional wheelchair having two small front wheels and two large rear wheels which the patient manually rotates to propel and maneuver the wheelchair. Each attachment includes an elevating member attachable to an axle of one of large rear wheels and having one or more prongs extending for a distance greater than the distance from the point at which the elevating member is attached to the wheelchair to the ground so that to mount a curb or similar obstacle the wheelchair can be made to stand on the elevating member with the large wheels elevated above the ground and against the curb or obstacle. The large wheels can then be manually rotated while against the curb to cause the wheelchair to climb the curb. The attachments of the invention must be used with a second attachment which includes an extendible wheel, or dolly, which is connectable to the wheelchair through supporting members and which can be manually extended backwards by the patient to a locked position. When both dollies of a pair of attachments are in this extended and locked position, the wheelchair can be tilted backwards manually to rest in a stable, tilted position on the two large wheels and the extended dollies or

3,580,592

COMBINATION DEER-CARCASS SLED AND CHAISE LOUNGE


Eugene E. Schrecengost, R.D. #1, Box 65, Apollo, Pa.

Filed Jan. 23, 1969, Ser. No. 793,469

Int. Cl. B62b 13/16, 13/18

U.S. Cl. 280—8

5 Claims



A deer-carass sled is provided that folds and may conveniently be strapped to a hunter's back. It has ground-contacting members that comprise runners and/or tires, and are preferably capable of being turned into an inoperative position to afford a compact structure. The structure further comprises a back member that attaches to the sled or dolly to convert it into a chaise lounge.

3,580,593

ANTISWAY SUSPENSION SYSTEM FOR AN AXLED VEHICLE


Lynn H. Sprunger, P.O. Box 78, Albion, Ind.

Filed Apr. 14, 1969, Ser. No. 815,575

Int. Cl. B60g 9/00

U.S. Cl. 280—124

6 Claims



A suspension system having antisway properties for an axled vehicle. The vehicle includes a frame having a pair of spaced longitudinal members. A rigid elongated support member is spaced below and substantially parallel to each longitudinal frame member. A transverse axle is positioned below the longitudinal frame members and is secured to each support member intermediate the end portions thereof. A suspension unit is carried by each support member end portion and serves to interconnect the adjacent overlying longitudinal frame member with the support member. Each suspension unit includes upper and lower spaced brackets secured to the longitudinal frame and support members respectively and interconnected by resilient means which transmit the vehicle load to the axle.

3,580,594

TOE STOP MOUNTING FOR ROLLER SKATES

Gordon K. Ware, St. Charles, Ill., assignor to The Chicago Roller Skate Company, Chicago, Ill.

Filed May 20, 1969, Ser. No. 826,215


Int. Cl. A63c 17/14

U.S. Cl. 280—11.2

1 Claim

A toe stop mounting in which a rib or detent projects downwardly from the toe stop support for interlocking en-

gement with one of a plurality of grooves formed in the upper end of the toe stop member to oppose rotation of the toe stop member in response to offcenter frictional braking




forces developed thereby. The bottom of the detent is fractured in an irregular manner to increase its holding power with respect to such rotation of the toe stop member.

3,580,595

TOE STOP MOUNTING FOR STREET ROLLER SKATES
Gordon K. Ware, St. Charles, Ill., assignor to The Chicago Roller Skate Company, Chicago, Ill.
Filed June 4, 1969, Ser. No. 830,351
Int. Cl. A63c 17/14

U.S. Cl. 280-11.2

5 Claims



A toe stop mounting for the type of street roller skates that contain a channel-shaped soleplate, a flat toeplate attached to the top of the soleplate, a toe clamp assembly attached to the bottom of the toeplate, and a front roller truck assembly attached to the bottom of the toeplate. The toe stop mounting includes an elongated strap of rigid material which is attached to the bottom of the channel-shaped soleplate between the side edges thereof and which is shaped to depend downwardly from the soleplate in front of the front roller truck assembly and then to extend upwardly toward the front end of the toeplate. A resilient toe stop member is attached to the bottom surface of the elongated strap in the upwardly extending region thereof. The strap is approximately equal in width to the inside dimension of the channel-shaped soleplate so that it receives lateral support from the side edges of the soleplate and is shaped so as to make contact with the front portion of the front roller truck assembly and toe clamp assembly for support purposes.

3,580,596

SKI CONSTRUCTION


Franz Volkl, Straubing, Lower Bavaria, Germany, assignor to Franz Volkl, OHG, Straubing Lower Bavaria, Germany
Filed Feb. 25, 1969, Ser. No. 801,956
Claims priority, application Germany, Feb. 27, 1968, P1,678,299
Int. Cl. A63c 5/04

U.S. Cl. 280-11.13

20 Claims

An edge strip for a ski is formed of a plurality of separate segments interconnected by bridge pieces which extend, at least for a portion of their length, in a direction transverse to

the longitudinal direction of the strip. The individual segments are fixed to the ski by means of tabs fitted into grooves



in the body of the ski and the tabs are held within the grooves by an adhesive material.


3,580,597

HEEL DOWNHOLDER FOR SAFETY SKI BINDINGS

Jean Joseph Alfred Beyl, 1, rue Devieur Robelin, Nevers, France
Filed Mar. 18, 1969, Ser. No. 808,112
Claims priority, application France, Mar. 22, 1968, 144,577
Int. Cl. A63c 9/00

U.S. Cl. 280-11.35T

7 Claims



A base member is adapted to be fixed with respect to the top surface of a ski. A pivoting member is mounted on the base member about a first transverse pivot pin. A jaw adapted to grip the heel of the ski boot is carried by the pivoting member. A cam following pin is carried by the pivoting member. A third transverse pivot pin is rotatably mounted on the base member. A pivoting lever is rigid with the third transverse pivot pin. A cam member for controlling the movement of the cam following pin from a first to a second position with respect to the cam member is carried by the pivoting lever. The downholder is at a lowermost position when the cam following pin is at its first position. The pivoting lever is adapted to constitute a release lever for controlling the retraction of the cam member. The third rotary transverse pivot pin has a planar abutment surface including a pair of edges parallel to each other and to the axis of the third pivot pin. A piston having a complementary planar surface is adapted to contact the abutment surface. The plane containing the abutment surface is perpendicular to the axis of the piston when the downholder is in its lowermost position. A compression spring urges the piston against said edges.

3,580,598

TOBOGGAN

Robert C. de Pauw, 18 Edgewood Hills, East Peoria, Ill.
Filed Apr. 21, 1969, Ser. No. 817,763
Int. Cl. B62b 13/00

U.S. Cl. 280-18

22 Claims

A steerable toboggan having a transversely curved body

with longitudinal corrugations and steering ribs along each side. The steering ribs are deeper and narrower than the cor-

attached to the upwardly extending baseplate. A pantographic member, of the lazy tongs type, has its lower point attached to the center of the upper edge of the upwardly ex-



rugations, and are curved with wider spacing at the front than at the rear.


3,580,599

JACK AND TIEDOWN SYSTEM FOR A VEHICLE MOUNTED CAMPER

John N. Dodgen, and Kenneth R. Johnson, Humboldt, Iowa, assignors to Dodgen Industries, Inc., Humboldt, Iowa
Filed May 2, 1969, Ser. No. 821,183
Int. Cl. B62d 21/14; B60p 3/32

U.S. Cl. 280-34

10 Claims



A jack and tiedown system for a vehicle mounted camper including a first pair of jacks secured to the lower front corners of the camper and a second pair of jacks secured to the rearward end of the camper. The front jacks are adapted to be lowered into ground engagement at times to support the front end of the camper while the rear jacks are adapted to be lowered to the ground to support the rearward end of the camper at times. The vehicle has a pair of brackets secured to its frame which extends outwardly therefrom at opposite sides thereof and which are adapted to have the lower ends of the first pair of jacks connected thereto to tiedown the camper to the vehicle when the jacks are not being used to support the camper. The rear jacks are pivotally connected to the camper and are positioned rearwardly of the camper mud flaps to prevent the flaps from flapping in the wind when the second pair of jacks are not being used to support the rearward ends of the camper.

3,580,600


COLLAPSIBLE HANDTRUCK

Harry B. Caplin, 60 Copperfield Road, Worcester, Mass.
Filed May 7, 1969, Ser. No. 822,588
Int. Cl. B62b 1/04

U.S. Cl. 280-36

3 Claims

A collapsible handtruck comprises an upwardly extending baseplate to which a lower baseplate is hinged to form a support of generally L-shaped cross section. A pair of wheels are



tending baseplate and a handle attached to the upper point. The resulting structure may then be collapsed into a compact bundle for easy storage in the trunk of an automobile.


3,580,601

SKATE DEVICE FOR TRANSPORTING LARGE OBJECTS

Ray P. Miles, 8575 W. Melody Lane, Macedonia, Ohio
Filed Apr. 30, 1969, Ser. No. 820,574
Int. Cl. B62b 3/04

U.S. Cl. 280-47.13

3 Claims



The invention relates to a skate device for transporting unwieldy, large flat objects with ease. The device comprises an elongated base member containing a pair of brackets at each end and a clamping bracket member at its midsection. Rollers are provided on the bottom of the base member and are all in line. The end rollers are mounted slightly above the midsection roller to enable the skate to be tipped backward or forward on the end rollers for maneuverability. The skate is clamped to an edge of the flat object for transporting.


3,580,602

STORAGE RACK

Gerard E. Hebert, Livonia, Mich., assignor to Lockhart Manufacturing Corporation, Farmington, Mich.
Filed Dec. 12, 1968, Ser. No. 783,340
Int. Cl. B62b 5/00

U.S. Cl. 280-79.3

11 Claims



The storage rack disclosed herein comprises a base, sides and a back which can be manufactured and shipped

separately to a bakery or other user and can thereafter be readily assembled without welding to form the storage rack. The base, sides and back have interengaging means thereon which are engageable by a sliding movement.

3,580,603

INFLATABLE SAFETY APPARATUS


Richard Chute, Huntington Woods, Mich., and Charles O. Berryman, Madison, Wis., assignors to Eaton Yale & Towne Inc., Cleveland, Ohio

Filed July 19, 1968, Ser. No. 746,131

Int. Cl. B60r 21/08

U.S. Cl. 280-150

27 Claims



An improved safety apparatus for protecting the driver of a vehicle includes a confinement mounted on the steering wheel and having a circular cone portion which engages the torso of the driver when the confinement is expanded to thereby restrain movement of the driver during a collision. The confinement is inflated from a collapsed condition to an expanded condition in such a manner as to engage the rim of the steering wheel with the conical portion of the confinement. After forward movement of the torso of the driver has been retarded by engagement with the confinement, the head of the driver engages the conical portion of the confinement.

3,580,604

MUD FLAPS FOR DUMP TRUCKS


Thomas F. Overend, 4379 Dart Ave., Minneapolis, Minn.

Filed Sept. 18, 1969, Ser. No. 859,132

Int. Cl. B62d 25/16

U.S. Cl. 280-154.5

8 Claims



A two-part mud flap assembly for dump trucks, one flap being adjacent the upper portion of the wheel and being stationary with the truck frame; the other lower flap normally lapping the upper flap and slidable into confronting relation with the upper flap. A swingable arm mounting the lower flap normally held down by the dump box; a spring to swing the arm and lower flap upwardly as the dump box is raised.


3,580,605
HYDRAULIC STEERING AND BRAKING SYSTEM FOR SNOW SKIS

Nathan Shreve Spitler, 1802 Briar Ridge Court, McLean, Va.
Filed Oct. 29, 1969, Ser. No. 872,053

Int. Cl. A63c 5/06

U.S. Cl. 280-11.13H

8 Claims



A pair of rudder elements are disposed on a ski behind and, respectively to the right and left side of the boot area and are normally maintained in a retracted ineffective position by springs engaged between the rudders and the ski. A pair of elongate hydraulic lines are each connected at one end to one of the rudders and extend under the clothing of the skier whereby a compressible ball at the other end of the lines may be carried on the thumbs of the skier for actuating the rudders selectively with thumb pressure on the balls.

3,580,606

CARGO LOADING AND SUPPORT SYSTEM


Millard C. Wagner, Urbana, Ohio, assignor to Thomas Kappel, Inc., Springfield, Ohio

Filed May 19, 1969, Ser. No. 825,587

Int. Cl. B60p 7/00

U.S. Cl. 280-179

9 Claims



A system for loading and supporting several truck cabs in a van for shipment with the cabs stowed in nested but spaced relationship so that a maximum number of cabs may be shipped without damage to the cabs through contact with each other or the interior of the van. Each cab has a pair of bars having wheels at their outer ends attached to it and extending transversely of the van with the wheels engaging tracks running longitudinally of the van, and stops are associated with the tracks to prevent movement of one of the bars and stabilize the load during shipment.

3,580,607

BICYCLE SUPPORT

Theodor Pletscher, Zurich, Switzerland, assignor to Gebruder Pletscher, Marthalen, Zurich, Switzerland

Filed July 9, 1968, Ser. No. 743,405

Claims priority, application Austria, July 10, 1967, 6437/67

Int. Cl. B62h 1/02

U.S. Cl. 280-301

3 Claims

A bicycle support comprises a socket to be secured to the horizontal rear fork members of a bicycle frame, a support arm having one end pivotally connected to said socket for tilting movement of the arm from a position of rest into

operating position and held in one or the other of said positions by a tilting spring acting eccentrically on the arm with respect to its pivoting axis to urge the arm against an abutment on the socket, a spring counterbearing being associated



with said pivotally connected end of the arm. The spring counterbearing is formed by an arched surface, for example by the surface of a ball lodged in a trough formed on the pivotally connected end of the support arm, or by a concave arched surface of the trough itself.

3,580,608

TRAILER TOWING ARRANGEMENT

Charles Clark Simpson Grant, Kempston, Bedford, England, assignor to Ibbett Engineering Company Limited, Bedford, England

Filed Jan. 13, 1969, Ser. No. 790,634


Claims priority, application Great Britain, Jan. 19, 1968,

2,946/68

Int. Cl. B60d 1/16

U.S. Cl. 280-405

5 Claims



The towing arrangement for attachment to a vehicle having two pairs of parallel arms having pivotal mountings at each end for connection at one end to a vehicle and at the other end to a tow body housing thereby forming a wishbone arrangement converged towards the housing. A connector which fits a coupling on another vehicle is attached to the tow body housing. A spring or hydraulic element is provided between the vehicle and the pair of parallel arms to exert an upward force on the latter.

3,580,609

FIFTH WHEEL WITH LOAD-TRANSFERRING DEVICE

Michael F. Piatelli, 6841 Harding, Taylor, Mich.

Filed Dec. 8, 1969, Ser. No. 883,072


Int. Cl. B62d 53/00

U.S. Cl. 280-405

4 Claims

A fifth wheel for connecting tractors and trailers consisting of a pivoted coupling member having on the forward end thereof a hinged member supported by a pair of inflatable air bags seated on the tractor frame. The air bags are operatively

connected into the compressed air system of the tractor through a control valve which enables the driver to distribute



the load in the trailer between the steering, driving and trailer axles by varying the pressure in the inflatable air bags.

3,580,610

AUTOMATIC ANTIJACKKNIFING CONTROL FOR ARTICULATED VEHICLES


Robert C. Warren, 26 Salem Ave., and Robert G. Adams, P.O. Box 508, Carbondale, Pa.

Filed May 6, 1969, Ser. No. 822,201

Int. Cl. B62d 53/10

U.S. Cl. 280-432

5 Claims



A device for preventing the trailer portion of a vehicle from jackknifing by automatically restraining the trailer portion and the tractor portion of the vehicle from moving relative to each other, except during right- or left-hand steering maneuvers.

3,580,611

FIFTH WHEEL SUPPORT SYSTEM


Lewis F. McNitt, Bay Village, Ohio, assignor to Midland-Ross Corporation, Cleveland, Ohio

Filed Jan. 27, 1969, Ser. No. 794,126

Int. Cl. B62d 53/08

U.S. Cl. 280-433

3 Claims



A right-angled or T-shaped element is secured to the web of a tractor (tractor-trailer combination) frame over its spring hanger supports. The flat area of the T is spaced from the channel flanges and the depending section may or may not extend into the area of spring hanger supports. If it does the spring hanger supports are initially made with an offset upper section into which the T-section can be inserted. The offset spring hangers can be originally provided with spacer

elements which are removed when the dependent section of the T-element is positioned and secured to the frame web sections.

3,580,612

TRAILER HITCH


Arthur W. Pearson, 506 Ramblewood, Edmond, Okla.

Filed Apr. 3, 1969, Ser. No. 813,139

Int. Cl. B60d 1/16

U.S. Cl. 280—492

1 Claim



A pair of pivotally interconnected horizontal plates are pivotally connected, respectively, with a towing vehicle and a towed vehicle for movement about a horizontal axes.

3,580,613

BUMPER COMBINING HITCH AND STEP


Walter A. Northrop, Hayes Route, Box 9-A, Woodland, Wash.

Filed Feb. 27, 1969, Ser. No. 802,882

Int. Cl. B60d 1/06; B60r 3/02, 19/00

U.S. Cl. 280—500

4 Claims



A vehicle bumper having a trailer hitch step construction including an elongated bumper assembly which, in operative position, is mounted at the end of a vehicle and in a position extending transversely of the vehicle. A bumper section hinged to the bumper assembly between its ends is swingable from a raised position rearwardly and downwardly to form a step. The bumper section in its raised position seats within a well defined between end portions of the bumper assembly. The bumper section in its raised position is surfaced with a plate which is substantially flush with plates provided in the end portions of the bumper assembly. A trailer hitch component is mounted within a recess provided adjacent the rear margin of the bumper section.

3,580,614

POCKET REGISTER

Rodney W. Winston, North Tonawanda, and Peter M. Witham, Nottingham, N.Y., assignors to Moore Business Forms, Inc., Niagara Falls, N.Y.

Filed Jan. 23, 1969, Ser. No. 793,342


Int. Cl. B41I 5/16

U.S. Cl. 282—3B

8 Claims

A pocket register for containing a supply of manifolding material comprising a container for said material, a writing surface mounted within the container over which a strip of the material may be extended after being withdrawn from the interior of the container, means on the writing surface for engaging sheets of transfer material to be interposed between

superposed portions of several sheets of manifolding material and adapted to limit extension of the withdrawn sheets, and a



substantially open, easily locked cover means for positioning the strips of withdrawn record material onto the writing surface thereby enabling writing to take place.

3,580,615

SOFTENER CONTROL ASSEMBLY


David G. Prosser, Milwaukee, Wis., assignor to Autotrol Corporation, Milwaukee, Wis.

Filed June 24, 1968, Ser. No. 739,539

Int. Cl. F16I 37/14, 39/00

U.S. Cl. 285—81

5 Claims



A water-softener control assembly for automatically controlling regeneration and adapted for connection to a water-softening tank. The assembly has a base unit connected to the tank and containing all the external pipe connections, and a separately removable control unit containing substantially all of the working control elements but none of the external pipe connections. The control unit is releasably connected to the base unit by a U-shaped locking member whose projecting arms are received in the aligned apertures of cooperating ribs projecting from adjacent opposed surfaces of the units.

3,580,616

REINFORCED EXPANSION

Joseph Merkwacz, Penfield, N.Y., assignor to Garlock Inc., Palmyra, N.Y.

Continuation-in-part of application Ser. No. 666,870, Sept. 11, 1967, now abandoned. This application Aug. 18, 1969,

Ser. No. 850,983

Int. Cl. F16I 27/10, 51/00


U.S. Cl. 285—229

6 Claims

Cylindrical portions of an expansion joint, at opposite sides of an expansible arch of the joint, have reinforcing means integral therewith in the form of a spaced-turn coil of glass-fiber cord embedded within a cylindrical mass of flexible

rubber. The rubber prevents interengagement of the turns of the coil and enables the joint's cylindrical portions to expand

tending laterally from the plane of said wall and engaging said recess in such manner that said cleat is gripped on opposite sides thereof between said resiliently expandable



and contract axially. The coiled cord strongly opposes radial expansion of said cylindrical portions from internal pressure.

3,580,617

PIPE UNION

Hermann Ehrenberg, Langen-Hessen, Germany, assignor to Fouquet-Werk Frauz & Planck, Rottenburg Neckar, Germany

Filed May 28, 1969, Ser. No. 828,795


Claims priority, application Germany, May 28, 1968,

P 17 50 710.7

Int. Cl. F16I 19/08

U.S. Cl. 285—340

13 Claims



Two pipes have axially aligned proximal end portions. A sleeve surrounds the end portions with clearance and has an annular radially inwardly extending projection which forms an inner annular ridge located between the facing axial end-faces of the pipe end portions. At each axial side of the annular projection a sealing ring is received in the clearance, followed by a pressure-transmitting ring. Nuts are screwed exteriorly onto each axial sleeve end, surround the same and the associated pipe end portion, and deforming the sealing rings through the intermediary of the associated pressure-transmitting rings into sealing engagement with the sleeve and the associated pipe end portion.

3,580,618

COMBINATION CLEAT AND CLIP MEANS FOR ASSEMBLING COLLAPSIBLE CONTAINERS

Julius B. Kupersmit, 299 W. 12th St., New York, N.Y.


Filed Sept. 15, 1969, Ser. No. 857,838

Int. Cl. F16b 7/00

U.S. Cl. 287—20,924

1 Claim

A combination cleat and clip means for interconnecting the sides of a collapsible container with the bottom or floor thereof, the cleat being secured to said bottom or floor and having a recess, the principal axis of which is parallel to the plane of said bottom or floor; the clip being secured to a surface of a wall, and having resiliently expandable means ex-



3,580,619

SPRING CLIP


Frederick Jean Maltais, Camp Hill, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Mar. 6, 1970, Ser. No. 17,095

Int. Cl. F16d 1/06

U.S. Cl. 287—53

6 Claims



A clip has been provided for securing a knob to a D-shaped shaft, by inserting it in an aperture in the knob. The clip is a longitudinally split spring which seizes in the knob and grasps the shaft by means of springlike longitudinally tapered panels cooperating with centering protrusions in said spring thereby frictionally engaging and centering the shaft in the knob. A plurality of projecting, pointed barbs may be provided to depend from the spring and to engage in a locking or seizing relationship the clip spring into the inner wall of the receiving aperture. The centering protrusions also provide a positive engagement as well as proper centering of the D-shaft in the knob aperture, thereby holding the knob on the D-shaft substantially without wobbling and still allowing the D-shaft to be withdrawn and reinserted numerous times without substantial loss of performance.

3,580,620

FASTENING DEVICES

Adrian Gottfried Offenbroich, 49 Sodra Forstadsgatan 211, Malmö, Sweden

Filed Mar. 10, 1970, Ser. No. 18,063

Claims priority, application Sweden, Mar. 11, 1969, 3,292/69


Int. Cl. F16b 7/00

U.S. Cl. 287—54

1 Claim

Fastening device for disengageably joining a first and a second preferably tubular structural part, comprising an expander body, being at least partly slotted and nested in the

open end of the first structural part and having a longitudinal chamber for a joining member, which on its end has a hook for engagement behind an edge portion of an opening in the



second structural part and has a sloping surface for cooperation with the conical end of a screw, threadedly engaged in the expander body.


3,580,621

EYELET AND LUG ASSEMBLY

Robert F. Chambers, 504 Beverly Road, Newark, Del.
Division of Ser. No. 735,259, June 7, 1968, Pat. No. 3,520,981,
July 21, 1970. This application Mar. 23, 1970, Ser. No. 003,619
Int. Cl. F16c 11/00

U.S. Cl. 287-101

2 Claims




Assembly comprises eyelet in form of shaft with series of lugs mounted on shaft. Each lug includes looped end portion of same thickness that loosely surrounds shaft and coplanar end portion of same thickness as looped portion. Loop portions of lugs contact one another in line on shaft. At least one of end lugs in line includes additional portion connected and equal in thickness to its coplanar end portion with additional portion offset in direction of adjacent lug in line.

3,580,622
DOOR LATCH

Philip R. Morgan, Monrovia, Calif., assignor to Acme Appliance Manufacturing Company, Monrovia, Calif.
Filed May 12, 1969, Ser. No. 823,839
Int. Cl. E05b 3/06, 9/08, 15/16

U.S. Cl. 292-169

8 Claims



A door latch or lock to be mounted on a door having an opening therethrough adjacent one edge and having a hole in

such edge into the opening, comprising two escutcheon members respectively insertable into and adapted to overlie the ends of the opening through the door, two knobs respectively mounted on the escutcheon members, a latchbolt housing insertable into the hole in the door edge and containing a latchbolt, and means connected to the knobs for retracting the latchbolt. The latchbolt housing and the escutcheon members interlock, and a single screw coaxial with the knob axis interconnects the escutcheon members to secure the escutcheon members and the latchbolt housing in assembled relation. The knobs are merely snapped into place in rotatably mounting them on the escutcheon members. The device may be used either as a simple door latch capable of being opened by rotating either knob, or it may be used as a door lock which can be locked from one side and which can be unlocked from the other side in an emergency. With two or three exceptions, all of the parts of the device are made of plastic materials, the external surfaces of the exposed parts being suitably finished.

3,580,623

LATCH MECHANISM


Theodore F. Peters, Utica, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed July 31, 1969, Ser. No. 846,538

Int. Cl. E05b 51/00; E05c 3/06

U.S. Cl. 292-201

5 Claims



A latch mechanism of the type comprising a latchbolt pivotally mounted on a vehicle body for releasably engaging a striker secured to the vehicle deck lid, the latchbolt being moved from an unlatched position toward a latched position upon engagement with the striker. Continued movement of the latchbolt to the latched position is power assisted by a differential-fluid-pressure-operated motor connected to the latchbolt. The operation of the differential-fluid-pressure-operated motor is controlled by fluid valves, one of which is actuated upon initial movement of the latchbolt toward the latched position to operate the motor for effecting continued movement of the latchbolt to the latched position at which position it is releasably engaged by a latch hook.

3,580,624

INSTALLATION FOR CONTROLLING THE CLOSING CONDITION OF PARTS ADAPTED TO BE MUTUALLY LOCKED, ESPECIALLY IN MOTOR VEHICLES

Gunter Gmeiner, and Christian Grabner, Sindelfingen, Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart-Unterturkheim, Germany

Filed Aug. 23, 1968, Ser. No. 754,914

Claims priority, application Germany, Aug. 26, 1967,

P 16 53 957.4


Int. Cl. E05c 3/26

U.S. Cl. 292-216

16 Claims

An installation for controlling the closing condition of parts adapted to be mutually locked or closed, especially in motor vehicles in which the engaging condition of a closure

device is sensed by appropriate means and a feedback signal, which may be either mechanical, optical or acoustic in na-



ture, indicates when the parts are completely closed or locked.

3,580,625

ATTACHMENT FOR A TINED FORK


Edwin F. Booth, Rte. 1, Alamosa, Colo.

Filed July 22, 1969, Ser. No. 843,410

Int. Cl. A01d 9/00

U.S. Cl. 294-59

5 Claims



An attachment for a tined fork comprising a generally U-shaped body having substantially parallel hollow side members connected to a curved body portion, the side members being dimensioned to fit frictionally on the ends of a pair of adjacent tines of a fork, and to be firmly retained thereon without fastening means but removable for replacement. The attachment prevents injury to potatoes and other produce being handled by the fork.

3,580,626

CLAMPING FIXTURE FOR USE IN A HOISTING AND LIFTING DEVICE


Luell Hilburn, 7240 Manila Ave., El Cerrito, Calif.

Filed Feb. 14, 1969, Ser. No. 799,173

Int. Cl. B66c 1/12

U.S. Cl. 294-67

9 Claims



A hoisting device. A rigid base and a rigid symmetrical frame are joined by jack means comprising two members joined together for motion toward and away from each other,

one member being secured to the base and one to the frame, for moving the frame and base relatively to each other. The frame has at its upper end, a ring for engagement by a pickup device, and it has a pair of diagonal braces extending from the ring, and a transverse portion lying perpendicular to the angle bisecting the angle formed by the braces and joining the braces and extending beyond them, and a pair of vertical anchor slots, one adjacent each end of the transverse portion beyond the braces. Linear flexible retention means, such as a chain or cable, secured in the slots are passed around an object to be hoisted, the jack means being used to tighten the base against the object to be hoisted and causing it to bear against it and force the object tightly against the linear flexible retention means, so that the assembly can then be lifted by lifting the ring.

3,580,627

MOTOR VEHICLE LOADING AND TRANSPORTING DEVICE


Ray L. Underwood, 65 Spokane, Pontiac, Mich., and Thomas A. Campbell, 4885 Clarkston Road, Clarkston, Mich.

Filed Sept. 20, 1968, Ser. No. 761,052

Int. Cl. B60p 3/06

U.S. Cl. 296-1

2 Claims



This invention provides a method or means for telescopically loading motor vehicles for transporting them including a longitudinal track detachably mounted on the chassis box frame of a supporting vehicle and a rollable carriage having rollers on its lower portion riding on said track, the upper portion of the carriage adapted to be engaged by the front axle of a second vehicle which is driven over the rear end of the supporting vehicle, the front end of the second vehicle being carried rollably forward solely by the carriage as the second vehicle is driven forwardly partly on its rear wheels and partly on the chassis of the supporting vehicle.

3,580,628

ROCKER-MOLDING INSTALLATION


Charles W. Rantala, Warren, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed July 16, 1969, Ser. No. 842,129

Int. Cl. B62d 23/22

U.S. Cl. 296-1

4 Claims



An arrangement for securing a rocker molding to an automobile rocker panel notwithstanding the presence of a body panel lower molding immediately above the rocker panel. The rocker molding hooks over clips which may move vertically on the rocker panel and the ultimate location vertically of the rocker panel is fixed by screws entering the bottom of the rocker panel through a flange on the molding.


3,580,629 INSTALLATION FOR CLOSING OR OPENING APERTURES IN VEHICLES

Gerhard Heim, Sindelfingen, Germany, assignor to Daimler-Benz Aktiengesellschaft, Stuttgart-Unterturkheim, Germany

Filed Dec. 5, 1968, Ser. No. 781,502
Int. Cl. B60j 7/04

U.S. Cl. 296-137

35 Claims




An installation for the selective closing and opening of openings in vehicles by means of a closure part which is guided in appropriate guide means and which is actuated by an actuating mechanism; the closure part includes a chamber with variable volume while the forces acting in either the expansion or contraction direction of the chamber engage at the closure part and at a fixed place in the vehicle.

3,580,630 UTILITY HUMP SEAT AND DOUBLE TRAY

Paul E. Fetter, R.D. #1, Selinsgrove, Pa.
Filed Nov. 6, 1969, Ser. No. 874,461
Int. Cl. A47b 85/04

U.S. Cl. 297-125

10 Claims



This disclosure relates to a convertible seat tray constructed to overlie conventional humped engine housings of utility-type trucks, the seat tray including a back tray which is at all times accessible and a front tray which is accessible when a backrest is in its collapsed position. The front tray is formed by a ledge secured to the back side of the backrest and thus does not interfere with an occupant when the backrest is in its upright position.

3,580,631 INVALID CHAIR


Charles E. Murcott, Huntington, N.Y., assignor to Lumex Inc., Bay Shore, N.Y.
Filed Feb. 10, 1969, Ser. No. 797,753
Int. Cl. A47c 39/00

U.S. Cl. 297-155

16 Claims

An invalid chair is disclosed which includes first and second frames between which is removably supported a seat assembly which is longitudinally slidably supported to the side frames. The chair further includes a table tray which can be moved between a noninterfering or storage position with respect to bodily access to the seat, and a tablelike position by merely aligning a single arm fixed to the table with a

passageway within one of the chair arm rests. Additionally, a foot rest is slidably disposed beneath the seat assembly and




3,580,632 FOLDING TABLE AND SEAT SUPPORT STRUCTURE

Paul Maurice Seymour, 14 Fremont St., Marlboro, Mass.
Filed May 21, 1969, Ser. No. 826,594
Int. Cl. A47c 39/00

U.S. Cl. 297-157

8 Claims



A folding combination table and seat including a support structure therefor, including upper support means having two connector portions, spaced from each other in a first direction, for connection with the table, lower support means having two bearing means, spaced from each other in a second direction, for contacting a supporting surface, two seat support means, spaced from each other in a third direction, and intermediate support means interconnecting the upper support means with the lower support means.

3,580,633 STADIUM FOOT BAG AND SEAT

Florence Du Priest, 519 No. 13th St., Waco, Tex.
Filed May 9, 1969, Ser. No. 823,315
Int. Cl. A47c 7/10


U.S. Cl. 297-184

5 Claims

A foot bag for stadium use which completely encloses the feet and lower legs of the user and extends up over the upper legs and lap of the user when the user is seated, with a belt being attached to the upper end of the foot bag for attachment around the waist of the user. The foot bag is used

in conjunction with a stadium seat having a seat bottom and a seat back hinged together with bracing to limit the rear-

ward movement of the seat back and form a handle for the seat. Dual seats and foot bags are also disclosed.




3,580,634 TILTABLE DRUMMER'S SEAT

John T. Bock, 9 Hillview Place, Elmsford, N.Y.
Filed Jan. 28, 1969, Ser. No. 794,498
Int. Cl. A47c 9/12

U.S. Cl. 297-313

6 Claims



A stool having a horizontal plate constrained to a horizontal position and a similarly shaped seat plate hinged to the horizontal plate at its forward edge, and a cushion mounted on the seat plate, with adjusting screwbolts extending threadably through the rear portion of the horizontal plate to engage and tilt the seat plate to any desired angle within the range provided.


3,580,635 RECLINING FORWARD FOLDING SEAT

Raymond C. Posh, Livonia, Mich., assignor to Lear Siegler, Inc., Santa Monica, Calif.
Filed Aug. 14, 1968, Ser. No. 752,529
Int. Cl. A47c 1/032

U.S. Cl. 297-355

36 Claims

A seat assembly including a cushion frame and a back frame with control means operatively interconnecting the frames for allowing the back frame to recline from an upright seat-forming position while preventing forward folding movement and for allowing forward folding movement of the back frame from the upright seat-forming position while preventing reclining movement. Two embodiments are disclosed and in each embodiment the control means includes a C-shaped link pivotally connected to the cushion frame on the folding axis and pivotally connected to the back frame at a point on the reclining axis when in the upright seat-forming position. A second link is pivotally connected to the cushion frame on the reclining axis and depends therefrom and has various flanges to coact with a dependent arcuate section of the back frame and the C-shaped link for allowing folding movement



position of the back frame. In one embodiment the reclining and folding axes intersect and in another embodiment the axes are parallel.


3,580,636 DUAL SIDE ARM CONTROLLER

Joseph B. Setto, Los Angeles, Calif., assignor to the United States of America as represented by the Secretary of the Air Force

Filed Jan. 14, 1970, Ser. No. 2,708
Int. Cl. A47c 7/54; B64c 13/04

U.S. Cl. 297-417

9 Claims



A dual side arm controller for use within the armrests of a seat. The seat is made up of a back portion and a pair of retractable armrests. The side arm controller is made up of a handgrip, cables and torque tube. The relationship between these elements allow for the retractable movement of either of the armrests without substantially affecting the operation of the side arm controllers.

3,580,637 METHOD OF DESTROYING FERROCONCRETE, ROCK OR THE LIKE

Yoshishige Itoh; Masatada Kawamura, both of Tokyo, and Yoshio Kasai, Funabashi, all of Japan, assignors to Fuji Motors Corporation, Higashiyamato, Tokyo, Japan

Filed Oct. 9, 1968, Ser. No. 766,262
Claims priority, application Japan, Oct. 21, 1967, 42-67503
Int. Cl. H05b 1/00; E21c 37/18

U.S. Cl. 299-14

5 Claims




The method of destroying a ferroconcrete body formed of a concrete mass having metal reinforcement bars embedded therein, said method uses the reinforcement bars as electrical conductors and heats them by the application of electric current thereto to cause sufficient thermal expansion of the reinforcement bars to cause cracking of the concrete and to simultaneously lower the adhesion between the reinforcement bars and the concrete.

3,580,638 PACKED SNOW AND ICE REMOVER FOR HIGHWAYS AND THE LIKE

Robert K. Pullen, Fullerton, Nebr.
Filed June 13, 1969, Ser. No. 832,961
Int. Cl. E01h 5/12

U.S. Cl. 299-25

4 Claims




A powered rotor carrying a plurality of cutting blades is supported from a mobile frame. The cutting blades have cutting or milling edges for engaging and advancing laterally into a bed of ice or packed snow. The support connection between the rotor and frame is such as to provide control over the spacing and pressure of the blades with respect to the covered surface and the blades are resiliently floatable to accommodate unevenness in the surface.

3,580,639 CUTTER CHAIN

Ralph W. Mitchell, 1421 Liberty St., Franklin, Pa.
Filed Apr. 18, 1969, Ser. No. 817,346
Int. Cl. E21c 25/34

U.S. Cl. 299-84

10 Claims



An endless flexible cutter chain and more particularly a chain consisting of a plurality of rigid links with all of the rigid links consisting of two body portions and through the use of only two basic body portions, a chain is constructed which comprises single-bit cutter links, double-bit cutter links and/or cutter links having no means for receiving cutter bits therein.

3,580,640 SYSTEM FOR DISTRIBUTING AND ADVANCING OBJECTS


Birger Sture Erik Eriksson, Trarhalla, Sweden, assignor to Aktiebolaget Jonkoping, Vulcan, Jonkoping, Sweden
Filed Mar. 18, 1969, Ser. No. 808,179
Claims priority, application Sweden, Mar. 22, 1968, 3829/68
Int. Cl. B65g 47/26, 51/02

U.S. Cl. 302-2R

9 Claims

A system for distributing and advancing objects comprises a continuously pendulating, flexible distributing arm or chute with an inlet end into which said objects are fed sequentially at high velocity, and an outlet end which reciprocates transverse to a plurality of individual tracks which are separated from each other by separating means. The outlet end of the distributing arm is located on a higher level than that end of the separating means which is located nearest to the arm.

The system further comprises means for compulsory advancing said objects along said arm and said tracks so that the ob-




jects passing the arm in a single row become uniformly distributed amongst said tracks.

3,580,641 METHOD OF AND APPARATUS FOR INCREASING THE CAPACITY OF BUCKET ELEVATORS

Charles M. Schloss, Jr., 1626 Wazee St., Cherry Hills Village, Colo.
Filed Apr. 28, 1969, Ser. No. 827,458
Int. Cl. B65g 53/04

U.S. Cl. 302-12

24 Claims



The method comprises producing a flow of air at and adjacent and in the same direction of movement of an arcuate path of the buckets toward an outlet, by means of which air-flow the divided material carried by the buckets is assisted in the proper path out of the casing. Particles are separated from the air, after passage through the outlet, and this air may be circulated to an upper housing adjacent the arcuate path; or to a lower housing in which the buckets are loaded. The apparatus for carrying out the above method may include a cyclone separator or the like, a blower connected thereto or connected to the lower housing, or connected for discharge of air into the upper housing, such as tangentially to a concave top thereof. The apparatus may also include a discharge chamber having two outlets, one leading to the separator and the other to a discharge conveyor or the like. The blower may also be driven by the shaft of an upper pulley or incorporated in the upper pulley.

The method also includes producing a flow of air at and adjacent and in the same direction of movement of material entering a bucket elevator casing inlet, to enhance the transport of sluggishly flowing materials into said casing.

3,580,642 COMBINATION GRAVITY AND PNEUMATIC GATE ARRANGEMENT FOR HOPPERS


Ernest J. Nagy, Munster, Ind., assignor to Pullman Incorporated, Chicago, Ill.

Filed Mar. 10, 1969, Ser. No. 805,500

Int. Cl. B65g 53/40

U.S. Cl. 302-52

3 Claims



A hopper discharge arrangement includes a combination of a gravity gate and a pneumatic gate which may be positioned in closed relation underneath the discharge end of a hopper and which may be moved to one side of the discharge end for effecting gravity discharge of materials contained within the hopper. A manually operated rack and pinion arrangement is provided on the gravity gate which cooperates to effect sliding movement thereof. The pneumatic gate includes a dish-shaped pan having a pneumatic outlet connected thereto and the said gravity gate and pneumatic gate may be interconnected by means of an interlocking device to provide for conjoint movement. The interlock device is effective to lock the gravity and pneumatic gates in a closed position or together for simultaneous movement. The interlock device also may be readily disengaged to permit sole movement of the gravity gate to an open position whereby the pneumatic gate remains in a pneumatic discharge position underneath the discharge end of the hopper.

3,580,643 TRANSPORT CONTAINER FOR FLOWABLE MATERIAL

Artur Spitzer, Mosbach Baden, Germany, assignor to Ludwig Spitzer Sen. KG (Kommanditgesellschaft), Mosbach/Baden, Germany

Filed Aug. 8, 1968, Ser. No. 751,200


Claims priority, application Germany, Aug. 12, 1967,

P 15 86 914.4

Int. Cl. B65g 53/40

U.S. Cl. 302-53

9 Claims



A pressurized shipping container including a cylindrical tank surrounded by a rectangular frame. The tank is provided with a plurality of internal, inverted pyramid or funnel shaped, false bottoms for emptying the flowable contents of the container. The plurality of such inclined false bottoms greatly reduces the dead space in the tank. Discharge flow may be assisted by making the false bottoms of porous material and forcing air up through them to provide an air cushion on their inner surfaces.

3,580,644 PNEUMATIC FEED SYSTEM FOR UNIFORM SUPPLY OF TOBACCO TO CIGARETTE MAKING MACHINES

Francis J. Jr. Ballard, Louisville, Ky., assignor to Brown & Williamson Tobacco Corporation, Louisville, Ky.

Filed Mar. 4, 1969, Ser. No. 804,071


Int. Cl. B65g 53/40

U.S. Cl. 302-59

2 Claims

A tobacco discharger associated with a cigarette making

machine and an automatic tobacco conveying system for pneumatically conveying tobacco from a storage area to the cigarette machine wherein the conveying system includes a main feed pipe coupled with the source of the stored tobacco and the discharger, air differential pressure means for forcing air through the pipe at a predetermined conveying velocity, a tobacco feeder at the source of stored tobacco for feeding the tobacco into the main feed pipe, and air pressure sensitive means for sensing the air pressure in the main pipe and actuating the operation of the feeder upon attainment of the



predetermined conveying velocity of the air to the discharger. The discharger includes a housing having an air inlet end coupled with the main feed pipe and an air discharge end. It also contains tobacco separating means within the housing for separating tobacco carried by air entering the inlet end so that the separated tobacco is uniformly distributed within the housing. Means are also included for causing the uniformly separated tobacco to be discharged into the cigarette making machine in a constantly uniform manner due to the uniform positioning of the separated tobacco within the housing.

3,580,645 APPARATUS FOR TRANSPORTING AND COLLECTING SHREDDED TOBACCO OR THE LIKE

Klaus Hagenah, Hamburg, Germany, assignor to Hauni-Werke Korber & Co. K.G., Hamburg, Germany

Filed Mar. 7, 1969, Ser. No. 805,225


Claims priority, application Germany, Mar. 15, 1968,

P 16 57 255.7

Int. Cl. B65g 53/40

U.S. Cl. 302-59

10 Claims



Apparatus for supplying shredded tobacco to the distributor of a rod cigarette machine comprises a magazine having a front wall connected with the discharge end of a tobacco-admitting first pneumatic conduit and with the intake end of an air-evacuating second pneumatic conduit. A sieve divides the interior of the magazine into an upper compartment which communicates with the intake end of the second conduit and a lower compartment which communicates with the discharge end of the first conduit. The sieve has a first section which offers a relatively low resistance to the passage of air from the lower compartment into the upper compartment when the second conduit evacuates air from the magazine while the first conduit admits tobacco-laden air, and a second section which offers greater resistance to the passage of air and is bypassed by tobacco shreds which leave the discharge

end of the first conduit. The second section of the sieve permits flow of air into the second conduit on partial or complete clogging of the first section.

3,580,646


DUAL CIRCUIT BRAKE VALVE

George E. Ternent, Elyria, Ohio, assignor to Bendix-Westinghouse Automotive Air Brake Company, Elyria, Ohio

Filed Sept. 17, 1969, Ser. No. 858,702
Int. Cl. B60t 15/02

U.S. Cl. 303-52

7 Claims



A dual circuit brake valve including first and second self-lapping valve elements for respectively controlling primary and secondary fluid pressure braking circuits, the first valve element being manually controlled and the second valve element being controlled by a relay piston subject to the pressure in the primary circuit wherein the relay piston is subjected to the action of a pair of springs acting in opposite directions so that during operation of the first valve element the crack pressure required to open the second valve element is reduced to a minimum and the application of fluid pressure to the primary and secondary circuits is substantially simultaneous.

3,580,647


SNOWMOBILE TRACK

William R. Richards, Roseau, Minn., assignor to Textron Inc., Providence, R.I.

Filed Oct. 15, 1968, Ser. No. 767,641
Int. Cl. B62d 55/24

U.S. Cl. 305-35

9 Claims



An endless flexible drive belt having longitudinally spaced openings for meshing engagement with the teeth of a drive sprocket wheel, and belt reinforcing and wear elements mounted in the openings. The wear elements have portions that are curved in a direction longitudinally of the belt, the curved portions being formed to closely follow the curvature of the sprocket wheel.

3,580,648


ROLL AND ANTIFRICTION BEARING ASSEMBLY

Stanley C. Zink, Northport, and Joseph J. Slane, Fulton, both of, N.Y., assignors to The Black Clawson Company, Hamilton, Ohio

Filed Apr. 7, 1969, Ser. No. 814,114
Int. Cl. F16c 35/06

U.S. Cl. 308-207

5 Claims



Each journal of a roll is supported by an antifriction roller bearing including an outer race and two inner races spaced axially by a ring of predetermined thickness. The inner races and the spacer ring are pressed axially against a shoulder on the journal by a plurality of jackscrews extending axially through a locknut for minimizing radial runout of the roll.

3,580,649


HIGH THRUST BEARING APPARATUS

Shigeru Araki, Hirakata-Shi; Shozo Takahashi, and Ichiro Muto, Osaka, Japan, assignors to Matsushita Electric Industrial Co. Ltd., Osaka, Japan

Filed Aug. 12, 1969, Ser. No. 849,449
Claims priority, application Japan, Aug. 15, 1968, Dec. 7, 1968, 43/58793; 43/89800; 43/89801
Int. Cl. F16c 19/10

U.S. Cl. 308-233

5 Claims



A plurality of thrust bearings to be subjected to a thrust load are arranged coaxially around a thrust shaft. A volumetrically variable air space is formed on one side of each thrust bearing opposite to the load, by means of rigid parts, without using an elastic element such as a bellows, and fluid pressure is supplied to the respective air spaces from a common fluid pressure source so as to create an equal cushioning effect in the respective thrust bearings, whereby the thrust load is taken equally by the respective thrust bearings.

3,580,650

CABINET STRUCTURE

William J. Morris, Woodbury, N.J., assignor to Philco-Ford Corporation, Philadelphia, Pa.


Filed Dec. 23, 1968, Ser. No. 786,199
Int. Cl. A47b 81/06

U.S. Cl. 312-7

8 Claims

A molded, unitary, multisection plastic cabinet structure for a small portable device such as a radio receiver. The sec-

tions are joined by integral hinges comprising reduced cross-sectional areas of the plastic material from which the cabinet structure is molded. The sections are so foldable about their



respective hinges as to provide a case for the device, selectively foldable to a stored position within an outer case, and movable to a propped up position for use of the device, or to an extended position for servicing.

3,580,651


TOILET TISSUE HOLDING AND DISPENSING APPARATUS

Morris S. Gauper, 109 Lakeview Blvd., Coleraine, Minn.

Filed May 21, 1969, Ser. No. 826,517
Int. Cl. B65h 19/00

U.S. Cl. 312-39

2 Claims



A housing constructed to receive a plurality of rolls of toilet tissue in generally overlying relationship with cradle means for receiving a roll and maintaining it in a dispensing position, a portion thereof operable to reject the empty roll, and stop means operable to allow one roll at a time to be positioned in the cradle means, said cradle means and stop means operating simultaneously to renew the roll in the dispensing position.

3,580,652


TYPEWRITER TABLE

Erik Christian Valeur Nielsen, Birkerød, Denmark, assignor to Max Bodenhoff A/S, Copenhagen, Denmark

Filed Dec. 19, 1968, Ser. No. 785,076
Int. Cl. A47b 21/00

U.S. Cl. 312-208

7 Claims



A typewriter table has a steel tube frame which, in order to

provide rigidity and to permit ready dismantling, consists of two gable sections and three longitudinal girders rigidly connecting same, two of the girders being upper girders supporting the table top, whereas the third one connects the rear legs at a lower level.

3,580,653


ARTIST'S PAINTING KIT AND TRIPOD ADAPTER THEREFOR

Carroll E. Thomas, San Francisco, Calif.

Filed Nov. 18, 1968, Ser. No. 776,726
Int. Cl. A47b 97/04, 27/00

U.S. Cl. 312-231

8 Claims



The invention comprises, in combination with a camera tripod and a portable kit as described and claimed in my copending application, U.S. Ser. No. 609,536, filed Jan. 16, 1967, and entitled ARTIST'S PAINTING KIT now Pat. No. 3,414,343, for removably carrying artist's equipment and provided with a hinged lid for supporting an easel in predetermined inclined position with respect to a base plate, an adapter disposed in underlying relation to the bottom of said kit and bottom of said baseplate for removably mounting said kit and said artist's equipment upon the top plate of said camera tripod, and means extending through said easel and bearing upon said adapter for removably holding said kit and said artist's equipment including said easel against displacement.

3,580,654


METHOD OF MAKING DISPLAY DEVICES

George A. Kupsky, Milford, N.J., assignor to Burroughs Corporation, Detroit, Mich.

Filed Oct. 2, 1968, Ser. No. 764,983
Int. Cl. H01j 9/38

U.S. Cl. 316-20

6 Claims



A method of making a gas discharge display device comprising assembling the component parts of the device and providing a tabulation through which the device can be filled with the desired gas. A capsule containing an antispattering agent such as mercury is mounted within the tabulation, along with suitable means by which it may be heated. The device is suitably baked out and otherwise preliminarily processed; the desired gas is introduced; and the tabulation is sealed off with the capsule remaining therein. After any other

processing steps are carried out as required, the material is freed from the capsule, and, with the entire assembly heated to a suitable temperature to cause the anisputtering agent to enter the working area of the device, the tubulation is sealed off at an area close to the device itself and with the capsule within the portion of the tubulation which is removed.


3,580,655

WAVEFRONT RECONSTRUCTION

Emmett N. Leith, Plymouth, and Juris Upatnieks, Ann Arbor, both of Mich., assignors to The Battelle Development Corporation, Columbus, Ohio
Continuation-in-part of application Ser. No. 361,977, Apr. 23, 1964. This application Oct. 23, 1965, Ser. No. 503,993
Int. Cl. G02b 27/00

U.S. Cl. 350—3.5

7 Claims



This invention is directed to methods and apparatus for capturing various patterns of electromagnetic energy emanating from or as they are transformed after passing through an object and reproducing or reconstructing those patterns in their original configuration to produce images identical in appearance to the object itself.

3,580,656

HOLOGRAM APPARATUS AND METHOD


Arthur N. Carson, Bristol, Conn., assignor to Carson Laboratories Inc., Bristol, Conn.

Filed Feb. 1, 1966, Ser. No. 523,995

Int. Cl. G02b 27/22

U.S. Cl. 350—3.5

15 Claims



An information processing system is presented for information storage and retrieval with a color center crystal wherein the information to be stored is generated by electrically modulating a light beam, and the information is then stored by forming a hologram of the desired information in the absence of exposure of the crystal to light from the subject.

3,580,657

BLAZED SURFACE HOLOGRAM

Nicholas K. Sheridan, Fairport, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Filed May 14, 1968, Ser. No. 728,986


Int. Cl. G02b 27/22, 5/18

U.S. Cl. 350—3.5

27 Claims

A blazed hologram is produced by exposing a photohardenable material to a stationary standing wave pattern preferably followed by preferential dissolution of the relatively exposed (or relatively unexposed depending on the type of photohardenable material) portions of the exposed photohardenable material in a developer liquid to create, in a preferred embodiment, a blazed, step or sawtoothlike surface profile relief pattern produced by preferential etching, the extent of the etching following sections of the intensity sur-

faces because the areas of lower exposure are eroded where they come to the surface of the photoresist material and hence are subject to the developer liquid. The optical information presented in exposure is carried in the form of a sur-



face relief on the developed photohardenable member. This surface relief may be used to reconstruct the optical image and may be used in other advantageous ways as described herein.

3,580,658

GAS COOLED MICROSCOPE SLIDE


Percy L. Swanson, 2244 N.W. Overton, Portland, Oreg.

Filed June 24, 1968, Ser. No. 739,415

Int. Cl. G02b 21/34

U.S. Cl. 350—93

8 Claims



A gas cooled microscope slide having a built-in cooling chamber formed by a through opening in the slide body which is closed top and bottom by spaced laminated glass windows upon which a specimen is placed for observation. Internal passages in the slide body direct a gas coolant to and from the chamber and lead to edge openings in the slide body which are connected by flexible tubing to a coolant source and to cooling and drying elements.

3,580,659

PORTABLE TRAFFIC SIGN

Yoshio Fukushima, Tokyo, Japan, assignor to Kabushiki-Kaisha Ricoh, Tokyo, Japan


Filed July 7, 1969, Ser. No. 839,560

Claims priority, application Japan, July 8, 1968, 43/58015

Int. Cl. G02b 5/12

U.S. Cl. 350—98

3 Claims



A portable traffic sign comprising a frame having a handle and a reflex reflecting plate which may be fixedly or more

advantageously rotatably secured to the frame. For example, the portable traffic sign carried by a pedestrian crossing a street at night can give a positive warning to a driver.

3,580,660

IMAGE-FORMING APPARATUS


Joseph La Russa, Crestwood, N.Y., assignor to Farrand Optical Co., Inc., New York, N.Y.

Filed Apr. 25, 1966, Ser. No. 544,866

Int. Cl. G03b 21/08

U.S. Cl. 353—122

7 Claims



An object plane, the plane passing through the optical center of a lens and perpendicular to its axis, and the plane of an image-receiving means intersect in a common line to produce in the image plane a distorted image of an object in the object plane. A relay lens translates the image in the image plane to the focal plane of an infinity sight to present at infinity an image of the object in the object plane. A variable focal lens produces at the object plane as an object an image at variable magnification of an initial object such as a slide or film strip.

3,580,661

REAR PROJECTION VIEWING SCREEN FOR CLOSE VIEWING


Dexter P. Cooper, Jr., Pasadena, Calif., assignor to Bell & Howell Company, Chicago, Ill.

Filed Apr. 10, 1969, Ser. No. 815,092

Int. Cl. G03b 21/60

U.S. Cl. 350—128

18 Claims



A nonreflective, directional diffusing, rear projection plastic viewing screen for close audience viewing. The screen comprises a composite Fresnel lens structure which includes

suitably crossed convex cylindrical Fresnel lens patterns, and a superposed lenticular sheet structure for focusing incremental images—from horizontally overconverged light—at acentrically positioned light-transmitting areas on an opaque, plane viewing surface.

3,580,662

VARIABLE FOCAL LENGTH OBJECTIVE HAVING FOUR LENS GROUPS

Norbert Scholz, Deisenhofenerstr. 70, 8 Munich 90, Germany, assignor to Agfa-Gevaert Aktiengesellschaft, Leverkusen, Germany


Filed Mar. 10, 1969, Ser. No. 805,762

Claims priority, application Germany, Mar. 8, 1968, P 12 78 132.7-51

Int. Cl. G02b 15/14

U.S. Cl. 350—184

1 Claim



A variable focal length objective of high power has four groups of lenses, and altogether 10 lenses. The variation of the focal length is effected by displacement of the second group of lenses, and the picture is maintained in a constant position by a displacement of the first group of lenses. The aperture ratio is greater than 1 : 2, the quotient of the greatest and smallest focal length is substantially 2.5, and the maximum angle of field is at least $\pm 20^\circ$.

3,580,663

COMPOSITE LENSES

Harris Vernon Hicks, Lichfield, England, assignor to Joseph Lucas (Industries) Limited, Birmingham, England


Filed Sept. 10, 1968, Ser. No. 758,855

Claims priority, application Great Britain, Sept. 11, 1967, 41,302/67

Int. Cl. G02b 3/04, 3/08, 9/02

U.S. Cl. 350—189

6 Claims



A lens of large diameter and short focal length comprises a plurality of interengageable elements which are moulded in a transparent material, or in transparent materials having the same refractive index. The elements are interengaged to constitute the required lens.

3,580,664

TRANSMISSION ELEMENT FOR MAGNETO-OPTICAL APPLICATIONS, PARTICULARLY FOR THE MODULATION OF INFRARED RADIATION IN THE WAVELENGTH RANGE BETWEEN 1 AND 20 MICRONS
Piet Frans Bongers, and Giulio Zanmarchi, both of Emmasingel Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Jan. 7, 1969, Ser. No. 789,506


Claims priority, application Netherlands, Jan. 11, 1968, 6800387

Int. Cl. G02f 1/22

U.S. Cl. 350—320

4 Claims

A novel magneto-optical transmission element consisting of a substrate transparent to radiation in the wavelength range between 1 and 20 microns having thereon a monocrystalline or polycrystalline layer of a material having a spinel structure, a magnetic permeability, in vacuo, $\mu_0 = B/H$ exceeding 1.2 at temperatures lower than the Curie point, i.e. the material is either ferromagnetic or ferrimagnetic, a resistivity at the Curie point exceeding 100 ohm-cm and a chemical composition having the formula $A Cr_2Z_4$, Z being selenium, sulfur, or tellurium and A being in general a divalent metal or complex, preferably cadmium. The transmission element may also serve as a memory element in which information therein can be read out by determining the sign of the remanent magnetization thereof by means of polarized infrared radiation.



the cue roll provides for lap dissolve and checkerboarding in coordinated time relationship with the first printer.

3,580,665

METHOD FOR REMOVING FILM FROM A FILM CARTRIDGE


Marvin Ben Bassett, Randolph, Mass., assignor to Technicolor, Inc., Hollywood, Calif.

Filed Apr. 18, 1968, Ser. No. 722,399

Int. Cl. G03b 23/02

U.S. Cl. 352—78

1 Claim



Peeling back an edge of the cartridge exposure window far enough to relieve the film from any pressure or friction from the pressure plate and the edge of the exposure window, so that the film may be pulled obliquely from the cartridge without being scratched.

3,580,666

OPTICAL PRINTER FOR MOTION PICTURE FILM

Robert G. Vance, 8312 Frye Road, Alexandria, Va.

Filed July 31, 1969, Ser. No. 846,422


Int. Cl. G03b 21/32, 27/32

U.S. Cl. 352—90

22 Claims

An optical printer for superimposing titles or the like on motion picture film in which images from picture, title and title shadow matte rolls are projected onto raw film stock in a continuous operation. A cue roll provides for automatic advancement of this title and title-shadow matte and title rolls

and also enables variations in light intensity and fade-in and fadeout to be effected. A second printing unit operated by the cue roll provides for lap dissolve and checkerboarding in coordinated time relationship with the first printer.



3,580,667

ENTERTAINMENT SYSTEM

Robert D. Moore, Houston, Tex., assignor to Kenneth F. Faulkner, Kemah, Tex., a part interest

Filed Oct. 9, 1968, Ser. No. 766,093

Int. Cl. G03b 21/02, 21/43, 29/00

U.S. Cl. 352—124

8 Claims

3,580,668

CONTROL MECHANISM FOR MOTION PICTURE PROJECTOR

Hermann Claar, Stuttgart-Hedelfingen, Germany, assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Oct. 4, 1968, Ser. No. 765,112

Claims priority, application Germany, Oct. 7, 1967, K59048


Int. Cl. G03b 21/12, 1/22

U.S. Cl. 352—194

3 Claims

A driving arrangement for the film claw of a motion pic-

ture projector comprises a plurality of radial cams which rotate in synchronism on a common axis to selectively effect



various modes of up-and-down and in-and-out movement of the claw.

3,580,669

FILM-SOUND SYNCHRONIZING SYSTEM


Robert S. Beeler, Brighton, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Oct. 2, 1968, Ser. No. 764,558

Int. Cl. G03b 31/00

U.S. Cl. 353—15

9 Claims



A unit for synchronizing a sound recording with photographic projection employing an audible device to record a signal. A light responsive to the recorded signal in playback actuates a photoswitch coupled with a projector advance mechanism to operate the projector.

ERRATUM

For Class 353—122 see:
Patent No. 3,580,660

3,580,670

APPARATUS FOR DUPLEXING


Gopal C. Bhagat, Rochester, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Filed Aug. 12, 1968, Ser. No. 751,986

Int. Cl. G03b 27/32

U.S. Cl. 355—3

12 Claims



A apparatus for duplex printing by forming on the surface of a first plate an electrostatic latent image conforming to the

information to be placed on the first side of a support material, then forming on the surface of a second plate an electrostatic latent image conforming to the information to be placed on the opposite side of the support material, developing the latent images, and transferring the developed image on each plate to its respective side of support material.

3,580,671

EXPOSURE APPARATUS


Edward J. Lavander, Rochester, N.Y., assignor to Xerox Corporation, Rochester, N.Y.

Filed Oct. 24, 1968, Ser. No. 770,367

Int. Cl. G03g 15/04

U.S. Cl. 355—3

5 Claims



Improved exposure apparatus for use in electrostatic recording machines in which continuous tone and solid area images or line images are produced automatically at the option of the machine operator. The exposure apparatus comprises two exposure slits, each of which is adapted for movement into and out of the optical path in response to discrete electrical signals. One slit is open and used for line images. The other slit is provided with transparent and opaque lines and is used for producing tonal and solid area images.

3,580,672

ELECTROSTATIC PHOTOCOPYING APPARATUS

Sadanao Ando, Tokyo, Japan, assignor to Kabushiki Kaisha Ricoh, Tokyo, Japan


Filed Nov. 4, 1968, Ser. No. 773,167

Claims priority, application Japan, Nov. 14, 1967, 73193/67

Int. Cl. G03g 15/10

U.S. Cl. 355—3

4 Claims




An electrostatic photocopying apparatus having a corona discharge device positioned vertically between a projection optical unit and a copying paper stand which is associated with a developer solution container. The distance between the corona discharge device and the copying paper is maintained sufficiently large to create a weak corona discharge, and the corona discharge device is swingable out of the vertical line to allow operation of the optical unit.

3,580,673 CLEANING APPARATUS

Frank Y. Yang, Webster, N.Y., assignor to Xerox Corporation, Rochester, N.Y.
Filed Aug. 26, 1968, Ser. No. 755,266
Int. Cl. G03g 15/00

U.S. Cl. 355—15

14 Claims



A method and apparatus for cleaning the residual toner image from an electrostatic recording surface for reuse in the imaging system. This is accomplished by contacting the electrostatic recording surface to be cleaned with an electrically insulating magnetic cleaning material which is moved on a transport into sweeping contact with the residual image. An electrical potential is applied to the transport of opposite polarity to the residual image and of a magnitude sufficient to pull the residual image onto the magnetic cleaning material which wipes the residual image enabling mechanical as well as electrostatic forces to remove the residual image. The residual image is removed from the magnetic cleaning material by contacting it with an electrically biased member which is connected to a voltage potential of sufficient magnitude to remove the image from the cleaning material onto the surface of electrical biasing member ensuring continuous removal of the residual image for subsequent reuse in the imaging system.


3,580,674 DEVICE FOR FAST REMOVAL OF EXPOSED FILM FROM THE SUCTION BOARD OF PROCESS CAMERAS AND DELIVERY TO A SUBSEQUENT PROCESS STATION

Kurt Schunck, and Waldemar Baunach, Frankfurt, Germany, assignors to Klimsch & Co., Frankfurt Main, Postfach, Germany

Filed Nov. 19, 1968, Ser. No. 777,037
Int. Cl. G03b 29/00

U.S. Cl. 355—28

9 Claims



A device for the speedy removal of exposed light sensitive material such as films, foils, or papers from an appropriate holder in the exposure plane of a process camera, the holder being incorporated in the camera back in such a way that it may be moved out of the exposure plane to a position where the exposed film can be engaged by automatic gripper means and delivered for the automatic transport to a subsequent processing station.


3,580,675 STRIP SCANNING COPYING APPARATUS

Fritz Hieber, Grunwald, Munich; Erich Burger, Unterhaching, and Hans-Peter Huber, Munich, all of, Germany, assignors to Agfa-Gevaert Aktiengesellschaft, Leverkusen, Germany

Filed Nov. 25, 1968, Ser. No. 778,854
Claims priority, application Germany, Nov. 27, 1967, A57,493
Int. Cl. G03b 27/50

U.S. Cl. 355—50

18 Claims



Strip portions of an original are successively scanned by a row of lenses with toric refractive surfaces having a first radius of curvature in the scanning direction and a second smaller radius of curvature in a transverse direction. The first and second radii are selected so that the image of a part of the scanned strip-shaped portion projected by each lens is reversed in the scanning direction only, and not reversed in the transverse direction of the row of lens means the exposed strip-shaped portions of the copy sheet form together a continuous complete legible image of the original.


3,580,676 ART OF PLATE MAKING

Albert J. Sarka, Fairview Park, Ohio, and Trevor H. Blake, Naperville, Ill., assignors to Harris-Intertype Corporation, Cleveland, Ohio, by said Sarka and American Can Company, New York, N.Y., by said Blake

Filed July 5, 1967, Ser. No. 651,298
Int. Cl. G03b 27/04

U.S. Cl. 335—86

13 Claims



An apparatus for use in making a pair of plates having cooperating metal-forming projections thereon includes a support table. The support table has first and second plate supporting surfaces located on the opposite sides thereof. Means is provided for supporting the table for movement from a first position wherein the first surface of the table is located to support one of the plates and a second position wherein the second surface of the table is located to support the other of the plates. A chase carrier is adapted to be located overlying each of the plates located on the table. A

chase for carrying a negative is carried by the chase carrier. Means is provided for moving the chase and each plate relatively in transverse directions to accurately locate the chase and plates.


3,580,677 EXPOSURE APPARATUS FOR COPY MAKING MACHINES EQUIPPED WITH LIGHT REFLECTIVE CONVEYOR

Terrance G. Seelenbinder, Rolling Meadows, Ill., assignor to Addressograph-Multigraph Corporation, Mount Prospect, Ill.

Filed Sept. 16, 1968, Ser. No. 759,939
Int. Cl. G03b 27/10

U.S. Cl. 355—110

2 Claims



An exposure apparatus for copy making machines includes a light source within a light transmitting drum. A flexible endless belt is trained around a portion of the drum, and superimposed original and copy sheets are carried around the drum between the belt and the drum for exposure of the copy sheet in accordance with an image on the original. The amount of light in the exposure area is increased by providing the belt with a light reflecting surface.


3,580,678 OPTICAL PYROMETERS

Terrance S. Roman, Latrobe, Pa., assignor to Cross Electronics, Inc., Wexford, Pa.

Filed Dec. 18, 1968, Ser. No. 784,647
Int. Cl. G01j 5/48

U.S. Cl. 356—43

14 Claims



I disclose, in an optical pyrometer system, the combination comprising an optical system for receiving and focusing incident radiation from an object, a beam splitter disposed in a light path of said optical system, for passing a portion of said incident radiation to a direct viewing aperture of said optical system and the remainder of said incident radiation to a second aperture of said optical system, light sensitive detecting means juxtaposed to said second aperture for receiving incident radiation passing therethrough, and said direct viewing aperture and said second aperture being sized so that the light sensitive area of said detecting means is completely

covered by said second aperture radiation when an object image focused by said optical system completely fills said direct viewing aperture.


3,580,679 SOLAR SPECTROGRAPHS

Richard S. Perkin, New Canaan, Conn., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed Sept. 24, 1968, Ser. No. 761,988
Int. Cl. G01j 3/36

U.S. Cl. 356—76

7 Claims



In certain astronomical applications, it is desirable to photograph (or otherwise observe) a celestial body (e.g., spectroheliograms of the sun) at a very narrow spectral bandwidth (i.e., substantially monochromatically). It is proposed to modify an otherwise conventional astronomical telescope so as to allow the simultaneous photographing (or other recording) of, for example, the sun at a plurality of different extremely very narrow wave bands (i.e., discrete, substantially monochromatic spectroheliograms). This may be accomplished by providing a series (say, four) of discrete apertures at the entrance end of an otherwise conventional telescope; and means at the image or exit end of the telescope for separately forming an image from each of the four separate entrance beams. By providing different narrow band-pass filters (or other means for rendering each of the beams monochromatic at a different wavelength), a simultaneous photograph (or other measurement) of the sun at different spectral lines may be made. Comparison of such simultaneous photographs can yield information concerning relative intensity of spectral lines from any part of the sun, free from uncertainty due to, for example, the fluctuating intensity with time of the source (e.g., the sun) itself. Preferably the entrance apertures are provided with moderately broad-pass reflecting filters for rejecting (i.e., reflecting away) most of the radiant energy outside of the vicinity at which each of the separate spectral measurements are being made.


3,580,680 FLAME EMISSION INSTRUMENT FOR SELECTIVELY MONITORING METAL AEROSOLS

Walter Leslie Crider, Cincinnati, Hamilton, Ohio, assignor to The United States of America as represented by the Secretary of the Department of Health, Education and Welfare

Filed May 6, 1969, Ser. No. 822,191
Int. Cl. G01j 3/30, 3/48

U.S. Cl. 356—87

6 Claims



An instrument employing the principle of flame emission spectrophotometry is provided to selectively monitor the

mass concentration of Fe_2O_3 aerosol in animal exposure chambers. The instrument is calibrated over the range from 0.3 to 1.6 milligrams per cubic meter, and the maximum sensitivity is found to be about 3 micrograms of Fe_2O_3 aerosol per cubic meter of air.


3,580,681

APPARATUS FOR AUTOMATICALLY MEASURING THE PROPERTIES OF ELLIPTICALLY POLARIZED LIGHT
Andre Robert, Paris; Claude Bourdon, Montrouge, and Jean Luc Le Goer, Paris, all of France, assignors to Etat Francais representé par le Ministre des Armees, Delegation Ministerielle pour l'Armement, Paris, France
Filed Sept. 27, 1968, Ser. No. 763,325

Claims priority, application France, Sept. 28, 1967, 122,613
Int. Cl. G01n 21/40

U.S. Cl. 356—114

6 Claims



An apparatus for measuring the output of a photomultiplier tube energized by the output of a rotating analyzer which is in the path of a polarized light beam. The AC component of the output signal is compared to a reference signal whose frequency corresponds to twice the rotation rate of the analyzer and the phase difference between the two signals provides the spatial orientation of the polarized light. The amplitude of the AC component is proportional to the phase retardation of the polarized beam components. The DC component of the photomultiplier output is used to control the gain of the photomultiplier.


3,580,682

METHOD AND STEREOSCOPIC OPTICAL APPARATUS FOR DETERMINING THE ROUGHNESS OF THE SURFACES OF MACHINED PARTS

Liviu Iliescu, and Ion Dragos, Bucharest, Romania, assignors to Ministerul Industriei Constructoare De Masini, Bucharest, Romania
Filed Oct. 30, 1967, Ser. No. 678,805

U.S. Cl. 356—168

1 Claim



A method and apparatus for stereoscopically determining the roughness of the surfaces of machined parts. A stereo-

scopic viewing means is provided for presenting to the operator stereoscopic images of the surface of a machined part, and simultaneously stereoscopic images of gauge surfaces, so that a comparison of the surface of the machined part with the surface of the gauges can be made. A projecting means is provided for projecting to the stereoscopic viewing means an image of the machined surface which is to be checked, while a pair of projecting means coact with a pair of gauges to project separate images thereof respectively to a pair of ocular means of the stereoscopic viewing means so that in this way images of the gauges are provided for the operator to be viewed simultaneously with the stereoscopic images of the surface of the machined part.

3,580,683


COMPUTING COLORIMETER
Herbert Schulkind, Laurelton, N.Y., assignor to Photovolt Corporation, New York, N.Y.

Filed Jan. 14, 1969, Ser. No. 791,070

Int. Cl. G01j 3/48

U.S. Cl. 356—184

10 Claims



A colorimeter with a computing circuit by which the concentration of a sample fluid is linearly indicated. Light transmitted through a sample vial of the fluid is directed upon a photosensing device which provides an electrical signal corresponding to the intensity of a transmitted light. The electrical signal from the photosensing device is applied to a computing circuit which transforms the applied electrical signal into one linearly related to the concentration of the fluid under investigation. The output of the computing circuit deflects a current indicating device so that the deflection of this device is proportional to the concentration of the fluid.

3,580,684

OPTICAL DENSITY-CALIBRATED PHOTOMETER


Ernest S. Gordon, 12176 Terrence, Saratoga, Calif.

Filed Apr. 14, 1967, Ser. No. 631,061

Int. Cl. G01j 1/44

U.S. Cl. 356—226

8 Claims



A system in which changes in the optical density of a sample are measured by passing a light beam through the sample including a photomultiplier for intercepting the exit beam and providing an electrical signal corresponding to its intensity. An adjustable high voltage source is used to adjust the output voltage of the photomultiplier circuit to a predetermined reference level. An amplifier network and voltage divider having stepped positions calibrated to directly indicate

changes in optical density per volt of output couples the voltage to a fixed gain (volt/cm) oscilloscope or recorder so that change in optical density is directly related to the displacement of the oscilloscope or recorder trace.

3,580,685


MEANS FOR EXPOSING NORMALLY COVERED PLATE WHILE MOVING IT TO EXPOSURE SITUATION
Gustave Ragnar Eriksson, Jonkoping, Sweden, assignor to Saab Aktiebolag, Linkoping, Sweden

Filed Nov. 25, 1968, Ser. No. 778,573

Int. Cl. G01n 21/16

U.S. Cl. 356—244

4 Claims



A specimen plate having a lengthwise slidable cover is placed on a carriage to move therewith into and out of an isolation chamber. A cover holder, movable in and out both relative to the carriage and with it, detachably retains the cover and prevents it from moving with the carriage beyond predetermined limits, so that the specimen plate is slid out of the cover and exposed while moving into the isolation chamber with the carriage, and is slid back into the cover as it is moved out of the isolation chamber.

3,580,686


VESSEL HAVING INTERSAMPLE ANTICONTAMINATION CONSTRUCTION
Wallace H. Coulter, Miami Springs, Fla., assignor to Coulter Electronics, Inc., Hialeah, Fla.

Filed Mar. 17, 1969, Ser. No. 807,737

Int. Cl. G01n 1/10, 21/16

U.S. Cl. 356—246

5 Claims



A vessel particularly constructed to separate each of a sequence of liquids, such that each liquid is free of intersample contamination by a prior liquid. Such contamination, which could be caused by residue of the prior liquid adhering to the walls of the vessel, particularly near its drain, or because of inadvertent liquid or gas bubble backflow from the drain, is obviated by an isolation chamber interposed between a primary chamber of the vessel and its drain. A necked passageway or surface of connection between the two chambers is of such proportions that pressure differentials and surface tension hold a major portion of the fluid in the primary chamber and create a gas barrier between the two chambers.

A preferred embodiment of the improved vessel is useful as a cuvette in making hemoglobin determinations and in-

cludes a housing having an integral overflow reservoir, drain, and receptacles for radiant energy transmitting and receiving apparatus.


3,580,687

SURVEY LEVEL
Siegfried Hansen, Los Angeles, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.
Filed Feb. 20, 1969, Ser. No. 800,970

Int. Cl. G01c 9/24

U.S. Cl. 356—248

8 Claims



As level reference, the survey level incorporates an optical flat equipped with a leveling servo so that the optical flat is maintained accurately perpendicular to the direction of local gravity. Optics include an image rotating prism and a beam splitter arranged so that light from a target is split, part of it is reflected from the horizontal surface of the optical flat and the images are compared. When they horizontally correspond, the target is in the horizontal survey level reference plane. When the target is off that plane, two vertically displaced images are seen.


3,580,688

INFORMATION STORAGE WITH OPTIC MATERIALS
Irwin Schneider, 2402 Daphne Lane, Alexandria, Va.
Filed Feb. 26, 1968, Ser. No. 708,299

Int. Cl. G02b 27/28; G02f 1/16

U.S. Cl. 356—256

8 Claims



Anisotropic color centers, such as the M_4 center in optical materials like sodium doped potassium chloride crystals, are used for the storage of information. The color centers are first oriented in a common lattice direction with polarized light, and information is then stored by effectively causing reorientations of the color centers with radiation of the same wavelength but of altered polarity. The information is read with polarized light at a second longer wavelength. Optical materials are particularly useful for computer storage elements since they have a substantially greater information storage capacity than conventional magnetic core memories.

Apparatus employing the optical storage material is also disclosed.

3,580,689

TUBULAR WRITING HEAD FOR A TUBULAR WRITING PEN

Helmuth Riepe, Hamburg, Germany, assignor to Rapidograph, Inc., Bloomsbury, N.J.

Filed Nov. 18, 1968, Ser. No. 776,370


Claims priority, application Germany, Nov. 24, 1967,

P 16 11 558.5

Int. Cl. B43k 1/10

U.S. Cl. 401—258

3 Claims



The present invention is directed to a tubular writing head of a tubular writing pen, wherein the tubular writing head comprises a hollow cylindrical member having a writing tube mounted at one end thereof and the interior thereof containing a drop weight with a hair wire which extends through the tube. A loading member in the form of a mushroom-shaped member is also disposed within the interior of the hollow cylindrical member and acts upon the drop weight so as to cause the hair wire to extend through the tube even when the tubular writing pen is not held in a vertical position.

3,580,690

INSERT CHASER DIE HEAD


Arthur A. McClure, Orange, Conn., assignor to Michael Cerito, New Haven, Conn.

Filed June 9, 1969, Ser. No. 831,601

Int. Cl. B23g 1/00, 5/12

U.S. Cl. 408—178

17 Claims



An insert chaser die head having a main frame member to which is attached a control plate having at least one guiding groove on its front face and rotating plate means positioned adjacent said control plate. The rotating plate means has at least one bore therein for supporting an actuating pin member whose end travels in the guiding groove and is biased by a spring located in the groove. At least two more

bore are formed in the rotating plate for supporting at least two driven pin members, so that a portion of the ends of the pin members protrude from the rotating plate means. A stationary body member mounted adjacent the rotating plate means has at least two channels for slidably supporting at least two carrier members which, in turn, support individual chasers for cutting threads on workpieces. Individual guideways communicating with each channel are formed in the body member to permit the ends of the driven pin members to pass therethrough and engage cam grooves in the carrier members such that, upon rotation of the rotating plate means, the carrier members are moved toward or away from each other.

3,580,691

VIBRATION ABSORBING THROTTLE LIFT BAR


Charles C. Czusak, Greensburg, Pa., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Nov. 24, 1969, Ser. No. 879,473

Int. Cl. F01b 25/02; F01d 17/12; F03b 1/04

U.S. Cl. 415—155

2 Claims



A vibration absorbing throttle valve lift bar arrangement for steam or gas turbines. A plurality of tubular members are nested concentrically one within the other. The assembly is provided with diametrically disposed bushings to slidably receive the lift bar rods and the valve stems. The tubes are dimensioned to have clearance between them. Preferably, a closure cap is sealed to the ends of the outer tube, and the inner tubes have end clearance with the caps.

3,580,692

SEAL CONSTRUCTION


Alojzy Mikolajczak, Hartford, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.

Filed July 18, 1969, Ser. No. 843,114

Int. Cl. F01d 11/08

U.S. Cl. 415—174

1 Claim



A seal construction of the honeycomb type for turbomachinery, the cell geometry of the honeycomb being

selected and arranged to provide an increase in boundary layer stability and an improvement in overall compressor or turbine performance.

3,580,693

BOUNDARY LAYER CONTROL DEVICES

Ian Clifford Cheeseman, Camberley, and Michael Charles George Smith, Farnham, England, assignors to Minister of Technology in Her Britannic Majesty's Government of the United Kingdom of Great Britain and Northern Ireland, London, England


Filed Mar. 17, 1969, Ser. No. 808,386

Claims priority, application Great Britain, Mar. 22, 1968, 13885/68

Int. Cl. B64c 27/18

U.S. Cl. 416—90

10 Claims



A rotor blade on which lift is induced by circulation control is provided with a chordwise extending slot at the blade tip formed by a plate spaced from the tip by a distance piece extending around part of the blade periphery towards the rear of the blade, i.e., the slot extends around the front and under part of the blade for about 240°. Air blown from the interior of the blade into the slot is discharged radially as a sheet which forms a pneumatic fence and thus modifies flow over the blade tip. The normal tip vortex can be moved radially outwards relative to the blade root and an appreciable drag reduction obtained. In a variation, air is discharged spanwise relative to the blade.

3,580,694

COMBINED FLUID IMPELLERS AND SELF-SEALING CLOSURES

Ole Stig Andersen, Virum, and Ove Rathje, Vanløse, Denmark, assignors to F. S. Andersen, ingenior-og maskinforretning I/S, Vedbak, Denmark


Filed Apr. 7, 1969, Ser. No. 813,912

Claims priority, application Denmark, Apr. 8, 1968, 1559/68

Int. Cl. F01d 7/02

U.S. Cl. 416—136

2 Claims



A combined fluid impeller and self-sealing closure has a plurality of blades mounted on the periphery of a rotor ring for pivotal movement about a radial axis. The blades are arranged so that they are in overlapping, sealing relationship with respect to one another when the impeller is at rest, and are in an open, impelling position when the impeller is rotating. The blades are opened by means of weights arranged in the rotor ring which are moved by centrifugal force when the

3,580,695

BILGE PUMP FOR BOATS


Sven O. G. Tumba, Vartavagen 8 E, 183 63 Hölviksnäs, Sweden

Filed Mar. 12, 1969, Ser. No. 806,613

Int. Cl. F04b 35/00; F16j 15/18

U.S. Cl. 417—330

7 Claims



A bilge pump for boats driven by wave movements, the pump being supported from a boat on the end of a line and being entirely immersed in the water a short distance under the surface thereof. The pump is a float connected by means of a rod with a pump piston slidably mounted in a pump cylinder. The wave movements or the rolling of the boat causes the float to move the pump piston upwards and downwards within the cylinder. The wave movements or the rolling of the boat causes the float to move the pump piston upwards and downwards within the cylinder. The induction end of the cylinder is connected to a hose placed in the bilge of the boat for pumping out bilge water, the hose on its in-board end being provided with a nonreturn valve for preventing any backflow. Another nonreturn valve permits the water in the hose to be expelled out into the water surrounding the pump.

3,580,696

CONCRETE PUMP ASSEMBLY


Friedrich Schwing, Rathausstrasse 126, 468 Wanne-Eickel, Germany

Filed Apr. 18, 1969, Ser. No. 817,480

Int. Cl. F04b 1/00, 21/02, 15/02

U.S. Cl. 417—515

1 Claim




Concrete pump assembly regulated by control flap valves with two pump cylinders and a common outlet opening. On two sides of the outlet opening in a control housing is a pair

of control flap valves, which are rockable about their axes and alternately connect one of the two pump cylinders with the outlet opening and at the same time connect the other pump cylinder with a suction opening.

3,580,697 PUMP

John O. Youngblood, Rt. 1, Lamont, Okla.
Filed Apr. 23, 1969, Ser. No. 818,640
Int. Cl. F04b 21/00
U.S. Cl. 417—557

6 Claims




A pump for use in oil wells which includes an elongated production tubing, a working barrel positioned within the production tubing, a special orificed sub connected to the lower end of the working barrel, a standing valve cage connected to the special orificed sub, and a hold-down shoe connected to the standing valve cage and engaging the production tubing. A plunger carrying a traveling valve is reciprocally mounted in the working barrel and connected at its upper end to a sucker rod string. The special orificed sub is positioned immediately above the standing valve of the pump and has a bore therethrough which is radially offset from the axis of the aligned bores through the standing valve and the working barrel. Communicating with the bore through the special orificed sub is an orifice which extends upwardly and inwardly from the outside of the special sub.

3,580,698

LIQUEFIED GAS-FUELED SMOKING LIGHTER UTILIZING PIEZO-ELECTRIC ELEMENTS AS THE VOLTAGE GENERATION SOURCE

Kenjiro Goto, Setagaya-ku, Japan, assignor to Mansei Kogyo Kabushiki Kaisha, Kawaguchi, Saitama, Japan
Filed Aug. 26, 1969, Ser. No. 853,068
Claims priority, application Japan, Sept. 11, 1968, 43/78712
Int. Cl. F23q 3/01
U.S. Cl. 431—255

8 Claims



A liquefied gas-fueled smoking lighter utilizing piezo-electric elements as the voltage generation source comprising a

casing, a support frame structure disposed within and secured to said casing, a high voltage generation unit comprising piezoelectric elements received in said frame structure and pinched at their opposite ends by a pressure transfer plate and a washer, an eccentric cam disposed on said pressure transfer plate for applying a pressure to said piezoelectric elements, a valve manipulation lever fixedly mounted on the shaft of said cam and having said cam shaft as the axis of rocking movement, and a valve opening and closing member disposed adjacent to said lever with at least a portion of said member positioned in the path of rocking movement of said lever.


3,580,699

FUEL TRANSFER SYSTEM FOR CIGARETTE LIGHTERS

Harry L. Vaughan, Lawrenceville, Ga., assignor to Scripto, Inc., Atlanta, Ga.
Filed Jan. 22, 1969, Ser. No. 793,100
Int. Cl. F23d 3/18

U.S. Cl. 431—321

7 Claims



The fuel reservoir of a cigarette lighter is indirectly connected to the wick chamber by a transfer mechanism which dispenses a controlled amount of fuel to the wick chamber even if the fuel reservoir is under greater pressure than is the surrounding atmosphere.


3,580,700

BURNER FOR CIGARETTE LIGHTER

Thayer C. Hinckley, Inglewood, Calif. (P.O. Box 37218, Los Angeles, Calif. 90037)
Filed Nov. 27, 1968, Ser. No. 779,493
Int. Cl. F23d 13/04

U.S. Cl. 431—344

6 Claims



A burner for a gas fuel cigarette lighter is disclosed which provides a distributor to produce a plurality of gas jets, and an outer shield arranged so that a circular flame is produced which is windproof. This burner structure prevents deposition of carbon around the valve stem, due to incomplete combustion of the fuel, and avoids cleaning and repair.

CHEMICAL

3,580,701

PROCESS FOR PRODUCING SHRINK-RESISTANT WOOL BY TREATMENT WITH HYPOCHLOROUS ACID AND CATIONIC HYDROPHILIC RESINOUS CONDENSATION PRODUCT

Dennis Wray, Belper, and Janet M. Johnson, Duffield, England, assignors to Precision Processes (Textiles) Limited, Ambergate, Derbyshire, England
No Drawing. Filed July 27, 1967, Ser. No. 656,339
Claims priority, application Great Britain, July 29, 1966, 34,288/66

Int. Cl. D06m 15/36

U.S. Cl. 8—127.6

13 Claims

In the shrink-proofing of wool it has been found that a product having an exceptionally valuable combination of properties e.g. handle, flexural properties, tensile strength, resilience and elasticity is obtained when woollen materials are first subjected to a uniform treatment with hypochlorous acid at an acid pH, the treatment being limited to that which will reduce the shrinkage under standardised washing conditions by 15–80%, then impregnated with a water-soluble cationic hydrophilic resinous condensation product containing polyoxyalkylene groups in the molecule and finally heating the wool when impregnated with said condensation product.

3,580,702

METHOD OF REMOVING SULFUR OXIDES FROM GASES


John G. Myers and Joseph H. Field, Pittsburgh, Pa., assignors to the United States of America as represented by the Secretary of the Interior

Filed Sept. 10, 1968, Ser. No. 758,723

Int. Cl. B01d 53/34

U.S. Cl. 23—25

5 Claims



Sulfur oxides are removed from gases by contacting the same at elevated temperatures with a dry absorbent selected from the group consisting of red mud, retorted oil shale, retorted oil shale treated with sodium hydroxide and mixtures of retorted oil shale and red mud treated with sodium hydroxide. These absorbents may be used on a once-through basis or they may be regenerated. Catalytic oxidation of the gases, though not necessary, may precede contact with the absorbents.

3,580,703

PROCESS FOR THE PURIFICATION OF RESIDUAL GYPSUM FORMED IN THE MANUFACTURE OF PHOSPHORIC ACID BY THE ACTION OF SULPHURIC ACID ON NATURAL PHOSPHATES

Engelhard Pavonet, Chokier, Belgium, assignor to Fosindus Company, Willemstad, Curacao, Dutch Antilles
Continuation-in-part of abandoned application Ser. No. 434,834, Feb. 24, 1965. This application Feb. 27, 1969, Ser. No. 802,890

Claims priority, application France, Feb. 27, 1964, 965,314

Int. Cl. C01f 11/46

U.S. Cl. 23—122

14 Claims

A process is provided for the purification of residual gypsum formed in the manufacture of phosphoric acid by the sulphuric acid reaction on natural phosphates, the gypsum into coarse calcium sulfate hemihydrate crystals and phosphoric acids and continuously fed into an autoclave and treated therein at 105–150° C. to recrystallize the gypsum into coarse calcium sulfate hemihydrate crystals in the presence of a large amount of hemihydrate crystals already present in the autoclave, and recover P₂O₅. The slurry is continuously withdrawn from the autoclave and the hemihydrate is separated from the liquid.

3,580,704

COLORIMETRIC INDICATORS FOR DETERMINING pH OF MOTOR OIL

John Pickup, Montreal, and Theodor G. Brandts and Joseph A. Lichtenberger, Grand'Mere, Quebec, Canada, assignors to Consolidated Paper (Bahamas) Limited, Nassau, Bahamas

No Drawing. Filed Mar. 6, 1967, Ser. No. 620,683

Claims priority, application Canada, Mar. 10, 1966, 954,427

Int. Cl. G01m 21/08, 31/22, 33/26

U.S. Cl. 23—230

7 Claims

The pH of a non-aqueous system which, normally, on contact of a pH color indicator, does not show a detectable change in the color of this indicator, is colorimetrically measured by use of a treated solid adsorbent carrier containing adsorbed thereon a suitable pH color indicator and a non-aqueous, substantially non-volatile liquid solvent common to said indicator and said system, by bringing the non-aqueous system in contact with the carrier. In a preferred embodiment, a method of indicating the pH of a motor oil is described which consists in contacting the used motor oil with a paper which has previously been treated with a pH colour indicator soluble in a non-ionic solvent and a surface-active agent which is a non-ionic solvent for said indicator and said motor oil.

3,580,705

SELECTIVE STRIPPING OF PLUTONIUM FROM ORGANIC EXTRACTS

Charles Coleman and Boyd S. Weaver, Oak Ridge, Tenn., assignors to the United States of America as represented by the United States Atomic Energy Commission

Filed Oct. 2, 1968, Ser. No. 764,494


Int. Cl. B01d 11/00; C01g 56/00

U.S. Cl. 23—341

5 Claims

Dialkyl substituted hydroquinones dissolved in an organic solvent have been found effective in reducing plutonium in the +4 and +6 oxidation states dissolved


in diesters of orthophosphoric acids such as di(2-ethyl-hexyl) phosphoric acid to the +3 oxidation state. This



enables quantitative stripping of the plutonium with aqueous solutions of hydrochloric acid.

3,580,706
METAL STRAND HAVING A CHROMIUM STEEL CORE AND CORROSION-RESISTANT CLADDING
 Gerald H. Frieling, Jr., Barrington, R.I., assignor to Texas Instruments Incorporated, Dallas, Tex.
 Original application May 3, 1965, Ser. No. 452,767, now Patent No. 3,372,465. Divided and this application Dec. 28, 1967, Ser. No. 694,222

Int. Cl. B32b 15/00
 U.S. Cl. 29-196.3 6 Claims



An austenitic chromium steel core, from the surface of which chromium oxide has been removed, in a cleaning solution is back-plated in the solution with a solid-phase bondable chromium-free metal, such as copper or a precious metal such as, for example, silver, gold or the like. Clean strips of a cupronickel alloy or titanium are positioned on opposite sides of the plated core and moved through a reducing atmosphere, and thence directly into the bite between squeezing rolls. The core and strips are rapidly heated in their passage through the reducing atmosphere. The rolls squeeze the strips around the plated core to effect solid-phase bonding between the strips and the plating. The margins of the strips are also squeezed together and become solid-phase bonded to one another. Upon emergence of the clad material from the rolls, it is at once quickly cooled in a nitrogen atmosphere. Waste beyond the pinch lines is removed. By means of quick heating and quick cooling, excessive precipitation in the steel of detrimental carbides is avoided and the strength of the steel preserved. The plating shields the steel core against the inherently instantaneous oxidation of the steel surface to chromium oxide when exposed to air and substitutes the more slowly oxidizing surface of the copper or

precious metal for effective solid-phase bonding under pressure. The resulting cupronickel or titanium surface of the resulting clad strand is corrosion resistant and in the case of the cupronickel is antifouling because of the cupric ions provided thereby when used for making submarine cables or the like.

3,580,707
PROCESS FOR PREPARING OVERBASED BARIUM SULFONATES, PRODUCTS THEREFROM AND USE IN DISTILLATE FUEL OILS
 Warren L. Perlstein, Orchard Lake, Mich., assignor to Ethyl Corporation, New York, N.Y.
 No Drawing. Filed July 30, 1969, Ser. No. 846,229
 Int. Cl. C10I 1/24, 1/32

U.S. Cl. 44-51 20 Claims
 A process for preparing overbased barium olefin sulfonates featuring the use of (1) barium sulfide treated with acetic acid, (2) olefin sulfonic acids, and (3) sulfur dioxide; a product obtained from this process and the use of these products in distillate fuels are described.

3,580,708
METHOD OF FORMING CUTTING TOOL MATERIALS CONSISTING OF ALUMINA AND TITANIUM CARBIDE
 Kazuki Ogawa, Fukuoka-shi, and Michito Miyahara, Fukuoka-ken, Japan, assignors to Nippon Tungsten Company, Ltd., Fukuoka-shi, Japan
 No Drawing. Filed Mar. 6, 1969, Ser. No. 805,024
 Int. Cl. B24d 3/02; C04b 31/16

U.S. Cl. 51-307 1 Claim
 A method of preparing cutting tool materials comprising mixing alumina and titanium carbide particles having an average grain size of less than 3 microns placing said mixture in a graphite mold and hot pressing at a temperature between 1500-1800° C. and a pressure between 150-400 kg./sq. cm. for a period of time up to 40 minutes.


3,580,709
GLASS TREATMENT WITH DISCRETE AREAS
 Peter Baldwin Banks, Essex, England, assignor to English Electric Valve Company Limited, London, England
 No Drawing. Filed Sept. 7, 1967, Ser. No. 665,995
 Claims priority, application Great Britain, Sept. 14, 1966, 41,116/66
 Int. Cl. C03c 15/00; C03b 29/00

U.S. Cl. 65-30 7 Claims
 In the production of a glass target of an image orthicon a target of Elcon glass is first prepared in oxidising conditions. A thin layer of metal is then deposited through a fine mesh onto one side of the target to produce a mosaic of separated discrete area deposits. The target is finally differentially heated from the side remote from that on which the metal was deposited to raise the temperature of the glass at the discrete areas to about the softening point to render it conductive at those areas without changing the conductivity at the boundaries of the areas.

3,580,710
PARTICLE TUBE FUSION FURNACE
 Richard G. Britt, Burlington, and Frederick A. Loughridge, Manchester, Mass., assignors to Sylvania Electric Products Inc.
 Filed Nov. 15, 1968, Ser. No. 776,208
 Int. Cl. C03b 3/00, 19/00

U.S. Cl. 65-144 5 Claims
 Equipment for the manufacture of quartz bodies which are free of air pockets including a vacuum system associ-


ated with a holder for quartz tubing. The end of quartz which the parisons are inverted and delivered to a blow mold at another station for forming the final article.



soft, the quartz is cut off and a body of air-free quartz is formed.

3,580,711
SPRAYING MECHANISM FOR GLASSWARE FORMING MACHINES
 Joseph R. Hamilton, Anderson, Ind., assignor to Lynch Corporation, Anderson, Ind.
 Filed Aug. 5, 1968, Ser. No. 750,133
 Int. Cl. C03b 39/00


U.S. Cl. 65-169 12 Claims



Spraying mechanism for solid parison blanks wherein spray nozzles are mounted on an arm so that they can be located over parison blanks during the spraying operation and swung to a remote location therefrom during the parison pressing operation. Cam and roller means are provided for swinging the arm, and the arm is of dual character so that damage to the arm during certain operations is eliminated by reason of a secondary part of the arm being swingable upwardly out of the way if struck by an obstruction.

3,580,712
GLASS FORMING MOLD ELEMENTS WITH YIELDING SUPPORTS
 Eustace H. Mumford, Ottawa Lake, Mich., assignor to Owens-Illinois, Inc.
 Filed Feb. 10, 1969, Ser. No. 797,974
 Int. Cl. C03b 9/00, 9/40, 11/00


U.S. Cl. 65-307 11 Claims
 A glass forming machine wherein a plurality of charges of glass are delivered to a plurality of parison or blank mold cavities and are formed into parisons after



Means are provided for yielding by supporting and cooling each parison or blank mold.

3,580,713
APPARATUS FOR FEEDING GLASS
 Helmut T. Schirm, Toledo, and Robert O. Ziegler, Holland, Ohio, assignors to Owens-Illinois, Inc.
 Filed Nov. 29, 1968, Ser. No. 779,705
 Int. Cl. C03b 7/00

U.S. Cl. 65-327 18 Claims




An apparatus for feeding glass comprising a forehearth having an orifice. A refractory orifice ring is supported beneath the orifice by a holder assembly which in turn is supported by a ring support. The holder assembly includes a burner which directs flames against the outer periphery of the orifice ring.

3,580,714
DISCHARGE CONTROL ELEMENT FOR GLASS-MELTING FURNACES
 John R. Lucek, Pittsfield, Mass., assignor to General Electric Company
 Filed Oct. 30, 1968, Ser. No. 771,853
 Int. Cl. C03b 5/32

U.S. Cl. 65-330 4 Claims

The application discloses a discharge control element, such as a needle or plunger, for use in glass-melting furnaces. Such control elements, being movable or adjustable in operation, are adapted to be only partially immersed in molten glass with the immersed tip positioned adjacent a discharge orifice for control of stream-feeding or gob-feeding of the molten glass to utilization equipment. The tip of the rod is formed of a material substantially impervious to erosion in molten glass, and the shank portion of the rod is formed of a metal subject to rapid erosion in molten glass but resistant to oxidation in air. The shank portion is cooled to coat its immersed part with solid glass to protect it against erosion by the molten glass. As disclosed, a preferred form of discharge control element com-

prises a rod having a tubular shank portion of steel provided with passages for the circulation of cooling water,



and a removable immersed tip or head portion formed of molybdenum.

3,580,715 COATED FERTILIZER

Joseph T. Dilday, North Little Rock, Ark., assignor to Olin Corporation
No Drawing. Filed Apr. 16, 1969, Ser. No. 816,808
Int. Cl. C05c 9/00

U.S. Cl. 71—28 7 Claims
Tenacious coatings of fertilizer supplements are applied to granular high analysis fertilizers, by adding, in order, minor amounts of mineral oil and of aqueous calcium lignosulfonate and then substantial amounts of fertilizer supplements, maintaining the granules in motion during and after each addition until the added material uniformly coats the granules.

3,580,716 METHOD FOR PLANT GROWTH REGULATION

Dorsey R. Mussell, Clare, and Richard A. Schwartzbeck, Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Apr. 10, 1968, Ser. No. 720,393
Int. Cl. A01n 5/00, 9/20

U.S. Cl. 71—76 4 Claims
Disclosed is a method involving the exposure of plants and plant parts to a growth regulating amount of tetraisopentylammonium bromide or tetraisopentylammonium chloride, or compositions thereof. Such practice is particularly useful for the regulation of the growth pattern of plant life, particularly as evidenced by the retardation of growth and enhancement of maturation.


3,580,717 METHOD OF OBTAINING A SPONGY METAL INGOT IN A SHAFT FURNACE

Mikhail Ivanovich Kononov, Svobodny prospekt 9, korpus 2, kv. 55; Evgeny Anatolievich Krasheninnikov, Ulitsa A. Sviridova 1, kv. 7; Vladimir Fedorovich Knyazev, Nikitinskaya ulitsa 5, kv. 53; Evgeny Nikolaevich Vasiliev, Ulitsa Barklaya 5, korpus 1, kv. 54; Petr Yakovlevich Nasonov, 5 Parkovaya ulitsa 26, kv. 89; and Evgeny Petrovich Timofeev, Golynaoovo 18, kv. 89, all of Moscow, U.S.S.R.

Filed Sept. 22, 1967, Ser. No. 669,815
Int. Cl. C21b 13/02; C22b 5/02

U.S. Cl. 75—37 3 Claims
A method of obtaining a spongy metal comprises reducing metal-containing oxides with a solid reducing agent in an externally heated shaft furnace by charging the

furnace with separate flows of the metal-containing oxides and a solid reducing agent, the metal-containing oxides and reducing agent flowing coaxially with the reducing agent surrounding the metal-containing oxides. Heating the oxides and reducing agent to result in reduc-




tion of the oxides and sintering of the metal thereby produced into a sponge metal ingot. The metal ingot passes from the furnace through an opening in a receiving table while the reducing agent is removed from the table.

3,580,718 METHOD FOR THE UTILIZATION OF HOT WASTE GASES FROM FURNACES OF METALLURGICAL WORKS

Heinrich Rasworschegg, Demeter Markow, and Alfred Sandri, Graz, Austria, assignors to Waagner-Biro Aktiengesellschaft, Vienna, Austria

Filed Dec. 6, 1967, Ser. No. 688,593
Int. Cl. F22b 1/18

U.S. Cl. 75—60 11 Claims




A method of utilization of combustible hot waste gases from furnaces of metallurgical works, in particular from steel converters, in an installation for the utilization of waste heat, comprising the steps of first cooling the hot combustible waste gases for removing at least partially the enthalpy of the gases by passing them in indirect heat exchange relationship with water and air, burning the so cooled waste gases in a combustion chamber with the preheated air and without intermediate storing of the waste gases flowing the products of combustion so produced through the combustion chamber and feeding the preheated water to the combustion chamber and flowing it therethrough in indirect heat exchange relationship with the products of combustion to generate steam, whereby both the enthalpy of the waste gases and the heat of

combustion thereof are utilized in the generation of the steam, adding reaction heat liberated during the burning of the cooled waste gases in the combustion chamber with an additional medium during the cooling step; and the step of burning the cooled waste gases in a combustion chamber with the preheated air is performed in response to the speed of decarburization in the furnace.

3,580,719 THERMOGRAPHIC RECORDING PROCESS

Eric Maria Brinckman, Mortsel-Antwerp, Belgium, assignor to Gevaert-Agfa N.V., Mortsel, Belgium
Continuation of application Ser. No. 560,128, June 24, 1966. This application Aug. 4, 1969, Ser. No. 849,582
Int. Cl. G03c 5/04

U.S. Cl. 96—27 10 Claims



Information is reproduced by the steps of exposing to a mainly visible light image a recording layer containing at least about 80% by weight of a normally water-soluble polymer of certain selected types which is substantially insensitive to visible light but when heated undergoes a loss in its normal solubility in aqueous solvents and contacting the exposed recording layer with an aqueous solvent for the purpose of removing the unexposed soluble areas thereof thereby leaving a relief image corresponding to the original. The recording layer contains uniformly distributed therethrough a finely divided substance that absorbs and converts visible radiation into heat, the amount of such substance being sufficient to impart to the recording layer an optical density of about 0.2-1 in the event reflex exposure is practiced or of at least about 0.2 in the event the exposure is direct. The recording layer is substantially transparent except for the radiation absorbing and converting substance. The time of the exposure does not exceed 10⁻² seconds, and the intensity of the radiation is sufficiently large as to generate within that time by virtue of the absorption and conversion effect of the substance sufficient heat to produce a loss in solubility in the polymer in the exposed area.

3,580,720 PHOTOGRAPHIC SENSITIZED PAPERS EXCELLENT IN FLUORESCENT BRIGHTENING EFFECT AND PROCESS FOR PREPARING THE SAME

Yasushi Ohyama, Takatsuki-shi, and Sadayuki Miyazawa, Otokuni-gun, Kyoto, Japan, assignors to Mitsubishi Paper Mills, Ltd., Tokyo, Japan
No Drawing. Filed Mar. 26, 1969, Ser. No. 810,795
Claims priority, application Japan, Mar. 30, 1968, 43/20,412


Int. Cl. G03c 1/92, 1/84, 1/08
U.S. Cl. 96—82 4 Claims
A photographic sensitized paper can be greatly enhanced in fluorescent brightening effect by incorporating into a binder in the photographic layer a starch derivative

having in combination an aminoguanidine group and an aldehyde group. This starch derivative is a mordant which makes the binder completely non-diffusible to a fluorescent dye.


3,580,721 LIGHT-SENSITIVE COLOR-GRAPHIC MATERIAL

Masakuni Iwama, Isaburo Inoue, and Teruo Hanzawa, Tokyo, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan
No Drawing. Filed Oct. 22, 1968, Ser. No. 769,707
Claims priority, application Japan, Oct. 23, 1967, 42/67,820

Int. Cl. G03c 1/40
U.S. Cl. 96—100 8 Claims
Couplers for inclusion into the silver halide emulsion layer of a color-photographic material; said coupler having the formula:



wherein R is an aliphatic hydrocarbon residue having 8-18 carbon atoms; B is a coupler residue; X is a group bonding B to




and m and n are 1 or 2.


3,580,722 LIGHT-SENSITIVE SILVER HALIDE COLOR PHOTOGRAPHIC EMULSION

Kenro Sakamoto, Takao Takahashi, Takeo Koitabashi, and Mitsuto Fujiwara, Tokyo, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan
No Drawing. Filed Feb. 6, 1969, Ser. No. 797,277
Claims priority, application Japan, Feb. 9, 1968, 43/7,748


Int. Cl. G03c 1/40
U.S. Cl. 96—100 6 Claims
A color photographic emulsion containing a color former of the formula:



and at least one compound of the formula:



or



wherein R₁ is alkyl, acylamino or sulfonamido; X₁, X₂ and X₃ are hydrogen, alkyl, halogen, acylamino, alkylcarbamoyl, sulfonamido, sulfamoyl, alkoxy or aryloxy; A and B are —COR₂, —COOR₂', —CONHR₂' or —CN; R₂, R₂', R₂'', X₄ and X₅ are allyl, alkyl, aryl, cycloalkyl or arakyl and F is an atom or radical necessary to form a pyrazolone ring.

3,580,723

LIGHT-SENSITIVE SILVER HALIDE PHOTOGRAPHIC EMULSION


Shui Sato and Kaichiro Sakazume, Tokyo, and Eiichi Sakamoto, Hanno-shi, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Dec. 12, 1968, Ser. No. 783,222

Int. Cl. G03c 1/28

U.S. Cl. 96—122

12 Claims



Light sensitive silver halide photographic emulsions are supersensitized by coating with a supersensitizer constituted by a combination of two different oxacarbocyanine dyes.

3,580,724

LIGHT-SENSITIVE SUPERSENSITIZED SILVER HALIDE COLOR PHOTOGRAPHIC EMULSIONS

Shui Sato, Kaichiro Sakazume, and Tateshi Iytaka, Tokyo, Japan, assignors to Konishiroku Photo Industry Co., Ltd.

No Drawing. Filed May 28, 1969, Ser. No. 828,750


Claims priority, application Japan, June 4, 1968, 43/37,740

Int. Cl. G03c 1/28


U.S. Cl. 96—124

5 Claims

A supersensitized silver halide emulsion containing in combination a sensitizing dye of the formula



and a sensitizing dye of the formula



wherein the various symbols are described in the claims.

3,580,725

PROCESS FOR SEPARATING AND RECOVERING BONE AND COLLAGEN FROM ANIMAL BY-PRODUCTS

William Kuster, 1211 Avondale Road, Hillsborough, Calif. 94010

Filed Apr. 3, 1968, Ser. No. 718,629


Int. Cl. A23k 1/10

U.S. Cl. 99—7

4 Claims

Method for separating bone (and collagen) from partially hydrolyzed animal tissue by employing an aqueous hydrolyzing solution wherein, because of the specific gravity differential between the bone (and collagen) and the fleshy tissue, the fleshy tissue will at least temporarily float in the solution while the bone (and collagen) will

sink. As a result, the bone (and collagen) are separated from the fleshy tissue by passing the solution along an



elongated path where the bone (and collagen) settle out of the solution.

3,580,726

METHOD OF INCREASING SOLUBILITY OF FOOD ACIDULENTS

Charles Dame, Jr., Wheaton, Ill., assignor to General Foods Corporation, White Plains, N.Y.

No Drawing. Continuation-in-part of application Ser. No. 694,417, Dec. 29, 1967, which is a continuation-in-part

of application Ser. No. 370,356, May 26, 1964. This application Nov. 24, 1969, Ser. No. 879,623

Int. Cl. A231 1/00; B01J 1/00

U.S. Cl. 99—78

4 Claims

Ground fumaric or adipic acid is impregnated with an aqueous solution of propylene glycol, agglomerated, and dried. The dried agglomerates are then subdivided to provide an acid of increased solubility.

3,580,727

PROCESS FOR MAKING EXPANDED SNACK PRODUCT

Clayton O. Gulstad, Coon Rapids, Minn., assignor to General Mills, Inc.

No Drawing. Filed Aug. 28, 1967, Ser. No. 663,503

Int. Cl. A231 1/10

U.S. Cl. 99—81

11 Claims

A new food product and process for making it by explosively puffing grain kernels which have been tempered with a hull modifying and flavoring agent, milling the puffed grain into flour or meal, mixing the flour with water to make a dough which is formed into chips, and subjecting the chips to intense heat.

3,580,728

PROCESS FOR MAKING EXPANDED SNACK PRODUCT

Clayton O. Gulstad, Coon Rapids, and Francis J. Eastburn, Minneapolis, Minn., assignors to General Mills, Inc.

No Drawing. Filed Aug. 28, 1967, Ser. No. 663,501

Int. Cl. A231 1/10

U.S. Cl. 99—81

13 Claims

A new food product and process for forming it. A flour is formed by explosively puffing a cereal grain and milling the puffed grain to form a pulverulent material. A dough, formed by combining the flour with water and one or more flavoring ingredients, is then formed into pieces which are subjected to intense heat to produce the final product.

3,580,729

PROTEIN-SUPPLEMENTED PEANUT SPREAD

Richard T. Darragh and John A. Succo, Cincinnati, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

No Drawing. Filed Feb. 4, 1969, Ser. No. 796,584

Int. Cl. H231 1/38

U.S. Cl. 99—128

7 Claims

A peanut spread supplemented with soybean protein and having a peanut butter-like eating quality, color and flavor is prepared by admixing particular amounts of soy flour and liquid vegetable oil with conventional peanut butter ingredients, heat treating the resulting combination by maintaining it at a temperature ranging from about 300° F. to about 500° F. for from about 1 to about 5 minutes, and chilling the heat-treated mixture to a temperature ranging from about 35° to about 85° F., for example in a scraped wall heat exchanger.

3,580,730

DISCONTINUOUS POLYCARBONATE COATINGS

Thomas S. Grabowski, Vienna, W. Va., assignor to Borg-Warner Corporation, Chicago, Ill.

No Drawing. Filed June 12, 1968, Ser. No. 736,254

Int. Cl. B44d 1/44

U.S. Cl. 117—8

1 Claim

A method of providing a discontinuous polycarbonate coating on a thermoplastic substrate comprising the steps of dissolving a polycarbonate resin in a polycarbonate solvent, applying the resulting solution to a thermoplastic substrate, evaporating the solvent to form a continuous polycarbonate coating, and subsequently treating the coating with a developing solvent to form a discontinuous coating.

3,580,731

METHOD OF TREATING THE SURFACE OF A FILAMENT


John V. Milewski, Saddle Brook, and James J. Shyne, Caldwell, N.J., assignors to General Technologies Corporation

Filed Sept. 26, 1967, Ser. No. 670,628

Int. Cl. C01b 31/30; C23c 11/08

U.S. Cl. 117—66

14 Claims



The method of increasing the interlaminar shear strength capabilities of a material to be bonded to another material by growing integrally-attached monocrySTALLINE whiskers out from the surface of the first material both to roughen its surface for bonding to a deposited matrix material, or to a plastic, and to change its surface chemistry to improve bonding, for instance to a resin. The invention includes the reinforcing of fibrous structures by the intertwining of whiskers grown across voids therebetween, and further includes various whisker-grown structures per se.

3,580,732

METHOD OF GROWING SINGLE CRYSTALS

A Eugene Blakeslee, Mount Kisco, Thomas F. Gukelberger, Jr., Hopewell Junction, and Vincent J. Lyons, Poughkeepsie, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 15, 1968, Ser. No. 697,770


Int. Cl. B44d 1/02

U.S. Cl. 117—106

19 Claims

A method for selectively growing single crystal islands in a dielectric substrate and the resulting structure. The substrate has recesses formed in its surface to receive

bodies therein. By applying a temperature gradient across each of the bodies throughout the entire heating cycle, nucleation occurs only at a bottom point on each of the



bodies when a vapor containing the material to be nucleated is passed over the bodies with the material of the bodies being molten.

3,580,733

FOOD COOKING APPARATUS HAVING CONTINUOUS CLEANING PROPERTIES AND PROCESS FOR PRODUCING SAME


Robert E. Ott, Bel Air, Md., assignor to SCM Corporation, Cleveland, Ohio

Filed Apr. 17, 1969, Ser. No. 817,128

Int. Cl. C23d 5/00

U.S. Cl. 117—129

11 Claims



An improvement in the process for producing an adherent ceramic coating on a metal substrate used in food cooking apparatus, the coating having the continuous cleaning property of diminishing accumulation of carbonaceous residue which results from the exposure to grease spatters at ordinary operating temperatures, can be effected by: applying to the substrate in intimate contact with each other an enameling composition comprising alkali-bearing glass frit particles, about 1/2 to 25% halide basis weight of said glass frit, and about 2-75 parts, per 100 parts of solids in said enameling composition, of particulate elemental metal selected from the group consisting of aluminum, magnesium, high alloys of either, and mixtures of the same; heating the resulting deposit in a heating zone until it forms, by interaction of the frit and the particulate metal, an integral, porous, sorptive surface structure containing crystalline devitrification products; then arresting said interaction in a cooling zone before substantial coalescence of the structure occurs. Cooking oven walls, fixed or removable panels, broiler pans and racks incorporating the resulting coated metal substrates can be made.

3,580,734

ANTISTATIC FILM BASE MATERIAL AND PROCESS FOR PREPARING SAME

Margaret L. Clachan, Patrick T. McGrail, and Basil R. Shephard, Brantam, Manningtree, England, assignors to Bexford Limited, Manningtree, England

No Drawing. Filed Sept. 21, 1967, Ser. No. 669,384

Claims priority, application Great Britain, Sept. 30, 1966, 43,843/66

Int. Cl. B32b 27/06; C09k 3/16

U.S. Cl. 117—138.8

6 Claims

This application describes a process of rendering film base less prone to pick up static electricity which com-

prises coating the film base with a layer consisting essentially of a sodium, potassium or lithium salt of a copolymer of an alpha-beta unsaturated dicarboxylic acid or anhydride with an ethylenically unsaturated comonomer.

3,580,735

POLYOLEFIN-MOLDED ARTICLE HAVING GOOD ANTISTATIC PROPERTY AND PREPARATION OF THE SAME

Yutaka Shimodoi, Saita-shi, Heichiro Ootake, Kouichi Mihara, and Kiyoshi Takao, Ibaragi-shi, and Shogo Matsuda, Tokyo, Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan
No Drawing. Filed Dec. 30, 1968, Ser. No. 788,005
Claims priority, application Japan, Dec. 30, 1967, 43/84,662, 43/84,663
Int. Cl. B44d 1/22

U.S. Cl. 117—138.8E

6 Claims

In a polyolefin fiber, containing therein an internal antistatic agent such as quarternary ammonium salts, glycerides or higher fatty acid amides and a modifying agent selected from aluminum oxide, calcium chloride, calcium carbonate, diphenyl phthalate, tricresyl phosphate and polyethylene glycol, an improved article having more durable antistatic effect by coating the outer layer of the article with an external antistatic agent such as relatively high molecular vinyl polymer.

3,580,736

PAPERBOARD IMPREGNATED WITH A PETROLEUM WAX-POLYURETHANE BLEND

Hallard C. Moyer, Homewood, Ill., and Eugene M. Fauber, Hammond, Ind., assignors to Atlantic Richfield Company, New York, N.Y.
No Drawing. Filed Apr. 26, 1967, Ser. No. 633,717
Int. Cl. C08g 51/52; D21h 1/40

U.S. Cl. 117—155

7 Claims

Paperboard is impregnated with a composition containing a major amount of petroleum wax and a minor amount of a wax-compatible urethane which is prepared from an excess of a hydrocarbon diisocyanate and a hydroxy-terminated diene polymer. The preferred diisocyanate is tolylene diisocyanate and the preferred polybutadiene has at least two average terminal hydroxyl groups in the allylic position. Impregnation of paperboard with the composition provides a product having significantly improved strength, rigidity and water resistance.


3,580,737

CHEMICAL RADIUSING CONDUCTOR EDGES OF FLAT CABLE

Edward J. Traynor, Jr., Stoughton, Mass., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.
Filed Jan. 18, 1968, Ser. No. 698,968
Int. Cl. C23b 1/02; B44d 1/18

U.S. Cl. 117—212

10 Claims



A metal foil is coated on one side with a resinous film. An etch resist coating is deposited on the metallic foil

in a predetermined pattern to produce a desired configuration of metal conductor strips after the composite is passed first through a metal etching solution and then a solution which removes the resist coating. The resulting flat metallic conductors have sharp undercut etched edges. The composite is again passed through a metal etching solution. The sharp conductor edges are thereby rounded so that the metallic conductors are reduced to a cross section without sharp edges. The exposed conductors are coated with a resinous film to complete the insulation of the conductors. The rounded edges of the conductors permit the cable to be creased without cracking the insulation.

3,580,738

PLASTICS MATERIALS WITH CONDUCTIVE SURFACES


Peter Whitten Ranby and John Lenard Northwood, London, England, assignors to Thorn Electrical Industries Limited, London, England
Continuation of abandoned application Ser. No. 511,428, Dec. 3, 1965. This application Feb. 16, 1970, Ser. No. 10,094

Claims priority, application England, Dec. 4, 1964, 49,510/64

Int. Cl. B44d 1/14, 1/18

U.S. Cl. 117—215

4 Claims



A method of making light transmitting plastics electrically conductive including depositing a layer of indium metal upon the plastic, heating the layer and then washing it with an acid.

3,580,739

GRID ELECTRODE FOR ELECTRONIC TUBES

Gunter Ciriack, Berlin, and Georg Eckert and Horst Hoffmann, Munich, Germany, assignors to Siemens Aktiengesellschaft
No Drawing. Filed Jan. 2, 1968, Ser. No. 694,804
Claims priority, application Germany, Jan. 4, 1967, S 107,728

Int. Cl. H01j 19/38; C23b 5/50

U.S. Cl. 117—217

10 Claims

The invention is directed to electronic tubes wherein a grid electrode is constructed of any alloy containing a zirconium oxide which may be added either to the base metal forming the grid wires in amounts of 0.1 to 2% by weight or to a coating of zirconium in amounts of 10 to 50% by weight which covers the base metal.

3,580,740

ZINC ELECTRODE CONTAINING LEAD SULFIDE TO REDUCE GASSING AT THE ZINC ELECTRODE IN HEAT STERILIZED SILVER ZINC ALKALINE BATTERY

Herbert I. James, Levittown, Pa., assignor to ESB Incorporated

No Drawing. Filed Sept. 4, 1968, Ser. No. 758,653
Int. Cl. H01m 41/00

U.S. Cl. 136—30

6 Claims

A zinc electrode containing a lead sulfide additive to reduce gassing at the zinc electrode which is used as the

negative electrode in a heat sterilized silver-zinc alkaline battery. The lead sulfide effectively reduces gassing at the zinc electrode without adversely affecting the capacity of the heat sterilized battery, whereas the conventional mercuric oxide additive reduces the capacity of the heat sterilized battery. The lead sulfide additive may be used in amounts ranging from about 1 to about 10% by weight of the active material additive mixture.


3,580,741

UNIVERSAL AUTOMATIC SENSING AND ACTUATING CONTROL SYSTEM FOR FLUID CONSUMING POWER SOURCES AND THE LIKE

Thomas C. Hovious, Peabody, and Robert A. Torkildsen, Danvers, Mass., assignors to General Electric Company
Filed July 29, 1968, Ser. No. 748,469
Int. Cl. H01m 27/12

U.S. Cl. 136—86

8 Claims



A combined sensing and output power actuating control system for electrically operable devices such as electric power generation assemblies of the fluid consuming battery type, such as fuel batteries. The control system is comprised by a ratio detector circuit which is coupled, for example, across the output terminals of a fuel battery and also coupled across the last fuel cell unit in the fuel battery for comparing the ratio of the proportional voltage appearing across the last fuel cell to the output terminal voltage of the fuel battery to a preset value and deriving an output trigger signal in response to the ratio varying from the preset value. Timing circuit means are coupled to the output of the ratio detector circuit and are responsive to the output trigger signal from the ratio detector. An output power actuating circuit which is comprised by a purge valve actuator is energized for a predetermined time period by the timing circuit in response to the output from the ratio detector for purging the fuel battery of undesired accumulated inert gaseous matter thereby restoring the fuel battery to full operating capacity.

3,580,742

SEPARATOR-ELECTROLYTE CARRIER FOR PRIMARY CELLS

Viktor Arsenievich Naumenko, Novoslobodskaya ul. 62, kv. 64; Tatiana Nikolaevna Toroptseva, 3 Mytischinskaya ul. 14-a, kv. 109; Lidia Fedorovna Penkova, 3 Mytischinskaya ul. 14-a, kv. 124; Andrei Akimovich Vyselkov, Murmansk proezd 6, kv. 27; and Galina Ivanovna Rogova, Prospekt Mira 169, kv. 12, all of Moscow, U.S.S.R.
No Drawing. Filed Jan. 11, 1968, Ser. No. 697,001
Int. Cl. H01m 11/00

U.S. Cl. 136—155

3 Claims

A separator-electrolyte carrier for wet primary cells activated by water or electrolyte solutions, made of a cellulosic material impregnated by an aqueous solution, ensuring a rapid activation of the cells and increasing their

3,580,743

THERMOELECTRIC MODULE WITH DIAGONAL CONSTRUCTION AND METHOD OF MANUFACTURING

Colin A. A. MacPhee, Beaurepaire, and Antonio C. P. Haene, Laval des Rapides, Quebec, Canada, assignors to Borg Warner Corporation, Chicago, Ill.
Filed Jan. 7, 1966, Ser. No. 519,363
Int. Cl. H01v 1/30

U.S. Cl. 136—212

31 Claims

A thermoelectric module construction comprising a first row of blocks made of semi-conductive P-type material and a second row of blocks made of semi-conductive N-type material parallel to the first row, with the blocks in the first row located directly opposite those in the second row. One end of each block in the first row is joined by a conductor to a corresponding end of a block directly opposite in the second row. An opposite end of each block in the first row is joined by a conductor to a corresponding opposite end of a block diagonally opposite in the second row.


3,580,744

IMMERSION THERMOCOUPLE FOR ATMOSPHERIC AND VACUUM ENVIRONMENTS

Shingo Inouye, Kettering, and George Saul, Dayton, Ohio, assignors to the United States of America as represented by the Secretary of the United States Air Force
Filed Feb. 4, 1969, Ser. No. 796,356
Int. Cl. H01v 1/02

U.S. Cl. 136—234

3 Claims



A thermocouple assembly including a protection tube made of a tantalum alloy. The protection tube is of a length sufficient to encompass the thermocouple wires and is concentrically positioned inside of an outer tube made of quartz. Thus, the protection tube acts as a barrier and shields the thermocouple wires from the highly corrosive gases caused by metals acting on the quartz outer tube.

3,580,745

SEMICONDUCTOR DEVICE

Else Kooi and Aant Bouwe Daniel van der Meer, Emmasingel Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.
Filed May 27, 1966, Ser. No. 553,409

Claims priority, application Netherlands, June 5, 1965, 6507231

Int. Cl. H01l 7/34, 7/54

U.S. Cl. 148—1.5

5 Claims

A method of making different circuit elements integrated in a common semiconductive wafer by modifying the properties and composition of the oxide portions which cover the surface of the wafer over the elements. Various methods are described for obtaining different oxide properties, for example, providing a layer of silicon

monoxide over the usual silicon dioxide, or subjecting selected oxide coating portions to X-radiation or ultraviolet radiation.

3,580,746
PROCESS FOR THE MODIFICATION OF THE MECHANICAL CHARACTERISTICS OF CARBON STEEL WIRE

Isaac Behar, Bourg-en-Bresse, France, assignor to Trefileries & Cableries de Bourg et du Havre, Bourg-en-Bresse, Ain, France

Filed Sept. 29, 1967, Ser. No. 671,720
Claims priority, application France, Oct. 4, 1966, 78,740, 78,741
Int. Cl. C21d 9/52

U.S. Cl. 148—12 8 Claims

The invention deals with a process for the modification of the mechanical characteristics of carbon steel wire, consisting of the following first patenting, then cold deforming, and finally deforming said wire at a temperature above the ambient temperature but below the recrystallization temperature of the steel in said wire, by applying transverse force to said wire.

3,580,747
PRODUCTION OF ALUMINUM ZINC MAGNESIUM ALLOY ARTICLES

Fred Howitt, Collins Bay, Ontario, and Ian Taylor, Kingston, Ontario, Canada, assignors to Aluminium Laboratories Limited, Montreal, Quebec, Canada
No Drawing. Filed Nov. 17, 1967, Ser. No. 683,782
Int. Cl. C22f 1/04

U.S. Cl. 148—12.7 13 Claims

In procedure for producing a solution heat treated aluminum-zinc-magnesium alloy article which is subjected to substantial cold working after solution heat treatment, but is nevertheless characterized by superior resistance to stress corrosion, the successive steps of heating the article to a solution-heat-treating temperature; cooling the article, at a rate maintained between 0.1° C./second and 20° C./second at least during cooling of the article from 350° C. to 250° C.; and subjecting the article to more than 5% cold working. Preferably, the alloy contains 0.20–0.7% manganese and 0.10–0.25% zirconium. A specific preferred alloy composition consists essentially of 3.8–4.6% zinc; 1.0–2.0% magnesium; 0.20–0.7% manganese; 0.10–0.25% zirconium; not more than 0.4% iron; not more than 0.25% silicon; other elements, not more than 0.03% each and not more than 0.10% total; balance aluminum.

3,580,748
WELDING FLUX COMPONENT
William T. Delong, Manchester Township, York County, Pa., assignor to The McKay Company, Pittsburgh, Pa.
No Drawing. Filed July 12, 1968, Ser. No. 744,317
Int. Cl. B23k 35/36


U.S. Cl. 148—26 24 Claims

A welding flux component comprising a fused mixture consisting essentially of the following listed constituents in the specified weight percentages: about 40% to about 90% of at least one stabilizing compound selected from the group consisting of fluorides, silicofluorides and fluoaluminates and about 10% to 60% of basic oxide. The flux component may also contain acidic oxide and neutral oxide, the fused mixture having a base-to-acid mole ratio of at least 2 to 1. Preferred stabilizing compounds include manganese fluoride, aluminum fluoride, potassium silicofluoride, sodium silicofluoride, lithium silicofluoride, potassium fluoaluminate, sodium fluoaluminate and lithium fluoaluminate. Preferred welding flux components have a base-to-acid mole ratio of at least 3 to 1.

3,580,749
METHOD AND APPARATUS FOR SELECTIVE ETCHING OF INSULATING LAYERS
Alan J. Simon, Trafford, and Joseph E. Johnson and Terence W. O'Keeffe, Pittsburgh, Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.
Filed Nov. 13, 1968, Ser. No. 775,276
Int. Cl. H01l 7/00, 7/44

U.S. Cl. 148—187

11 Claims



In selective etching by the bombardment enhanced etching rate (BEER) effect, a metal layer on the bombardment insulator is used to provide increased etch enhancement. The metal layer also may serve as an electrode in biasing the structure to produce a beam induced current from which the applied dose is indicated.

3,580,750
TMETN-INORGANIC NITRATE EXPLOSIVES BLENDED WITH PETROLEUM OIL

George L. Griffith, Coopersburg, Pa., assignor to Commercial Solvents Corporation, Terre Haute, Ind.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,615
Int. Cl. C06b 15/00

U.S. Cl. 149—38 18 Claims

Explosive mixtures are provided, based on trimethylol-ethane trinitrate and an inorganic nitrate, in which the rate of detonation and, optionally, also sensitivity, are controlled by the use of petroleum oil in formulating the explosive.

3,580,751
TMETN-INORGANIC NITRATE EXPLOSIVES BLENDED WITH HOT INORGANIC NITRATE

George L. Griffith, Coopersburg, Pa., assignor to Commercial Solvents Corporation, Terre Haute, Ind.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,616
Int. Cl. C06b 19/00

U.S. Cl. 149—38 8 Claims

Explosive mixtures are provided, based on trimethylol-ethane trinitrate and an inorganic nitrate, having a high rate of detonation and good sensitivity due to the use of hot inorganic nitrate in formulating the explosive.

A process also is provided for preparing such explosive mixtures, by mixing the inorganic nitrate with the trimethylol-ethane trinitrate at a temperature within the range from about 100° to about 150° F. The mixing can be carried out in the presence of a small amount of water, to facilitate the blending and control rate of detonation, without affecting sensitivity.

3,580,752
TMETN-INORGANIC NITRATE EXPLOSIVES BLENDED WITH WATER

George L. Griffith, Coopersburg, Pa., assignor to Commercial Solvents Corporation, Terre Haute, Ind.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,656
Int. Cl. C06b 15/00

U.S. Cl. 149—38 11 Claims

Explosive mixtures are provided, based on trimethylol-ethane trinitrate and an inorganic nitrate, having a controlled rate of detonation and good sensitivity and explo-

MAY 25, 1971

CHEMICAL

907

sive power, due to the presence of water in an amount of at least 1%.

A process also is provided for controlling the rate of detonation while retaining good sensitivity and explosive power of such explosive mixtures, by mixing the inorganic nitrate with the trimethylol-ethane trinitrate, optionally at a temperature within the range from about 100° to about 150° F. in the presence of water in an amount in excess of 1%.

3,580,753
TMETN-INORGANIC NITRATE EXPLOSIVES BLENDED WITH ALUMINUM

George L. Griffith, Coopersburg, Pa., assignor to Commercial Solvents Corporation, Terre Haute, Ind.
No Drawing. Filed Oct. 7, 1968, Ser. No. 765,697
Int. Cl. C06b 9/00

U.S. Cl. 149—39 17 Claims

Explosive mixtures are provided, based on trimethylol-ethane trinitrate and an inorganic nitrate, having a high rate of detonation and good sensitivity due to the incorporation of aluminum particles in the explosive.

A process also is provided for preparing such explosive mixtures, by mixing the inorganic nitrate and particulate aluminum with the trimethylol-ethane trinitrate.

3,580,754
PROCESS FOR PREPARATION OF PENTOLITE

Philip Barnhard IV, West Chester, Pa., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Filed May 1, 1969, Ser. No. 821,083
Int. Cl. C06b 3/00


U.S. Cl. 149—93 7 Claims

Process for the preparation of stable pentolite from crude pentaerythritol tetranitrate comprising agitating in water a mixture of molten trinitrotoluene and crude pentaerythritol tetranitrate at a temperature above the melting point of the trinitrotoluene and below the melting point of the pentaerythritol tetranitrate, while maintaining the pH of the water in the range from 7 to about 10, followed by separating the pentolite from the aqueous phase.

3,580,755
NONFLAMMABLE, THIN, INTEGRALLY ILLUMINATED CONTROL PANEL OVERLAY

Thomas L. Kidd, Jr., Norristown, and Albert D. McClain, Jr., Philadelphia, Pa., assignors to General Electric Company
Filed Feb. 16, 1968, Ser. No. 706,044
Int. Cl. C23f 17/00; B44c 1/22

U.S. Cl. 156—3 2 Claims



A nonflammable control panel overlay with legible indicia openings, integral illumination and integral supporting means comprises a metallic member with indicia openings on the front thereof backed by a nonflammable, transparent backing member mounted in a recessed area on the back of the member behind the indicia openings, an electroluminescent lamp mounted in a second recessed area behind the transparent backing member and ribs on the back side of the member comprising the unetched areas left when the various mounting recesses are formed. Such a metallic overlay is made by mechanically engraving the indicia, on the front of a metal blank and then

chemically etching the rear of the blank, in a stepwise fashion to form the various recesses and remove unnecessary material, until breakthrough to the indicia occurs.

3,580,756
METHOD OF JOINTING SHEATHS OF ALUMINUM SHEATHED CABLES


Toshio Kashara, 1616 Ohmachi-7-chome, Kamakura-shi, Japan, and Mitsuru Numao, 10-101 Kudencho-Donchi, Nihon Jutaku Kodan, 740 Kudencho, Totsuka-ku, Yokohama-shi, Japan

Continuation of application Ser. No. 610,716, Jan. 20, 1967, now Patent No. 3,447,986. This application July 19, 1968, Ser. No. 746,017

Claims priority, application Japan, Jan. 31, 1962, 37/2,841

Int. Cl. H01r 5/00

U.S. Cl. 156—49 1 Claim



Method of jointing sheaths of cables in gas-tight and liquid-tight fashion wherein the end portions of the metal sheaths of the cables to be jointed are wrapped with composite layers of metal tape coated with a cold-setting synthetic resin, the sleeves of a junction box are positioned over the composite layers on each end of the cable, the sleeves are contracted into contact with the composite layers, and a protective layer is formed over the outer periphery of the sleeves and the outer surfaces of the cables over the sheaths.


3,580,757
WEB WINDING MACHINES

Otto Niepmann, Gevelsberg, Westphalia, Germany, assignor to Maschinenfabrik Fr. Niepmann & Co., Gevelsberg, Westphalia, Germany
Filed July 17, 1968, Ser. No. 745,660

Claims priority, application Germany, July 18, 1967, M 74,804

Int. Cl. B65h 19/08

U.S. Cl. 156—504 6 Claims




An apparatus for connecting the rear end of a web of a nearly empty unwinding roll to a front end portion of

a web carrying an adhesive strip and pertaining to a new roll to be unwound, which includes two pressing rollers for receiving therebetween the unwinding end of the web from one roller and the forward end of the web of a new roller while a cutter is provided between the web rollers and the pressing rollers for alternate cooperation with the rear end portion of the nearly empty web roll to cut said rear end portion off after it has been pressed and glued to the front portion of the new web, electromagnetic control means controlled by the rear end of the unwinding web being provided for reducing the speed of the respective unwinding web prior to the cutting off operation of said cutter.

3,580,758
METHOD FOR REPRODUCING THREE-DIMENSIONAL IMAGE
Isao Morioka, 3-23 Oookagima 2-chome Meguro-ku, Tokyo, Japan
Filed May 8, 1968, Ser. No. 727,419
Claims priority, application Japan, May 9, 1967, 42/29,325; May 15, 1967, 42/30,706
Int. Cl. B44b 1/00

U.S. Cl. 156—58

3 Claims



A method for reproducing a three-dimensional image comprising the steps of projecting on an object screens each consisting of a plurality of parallel lines as schematically shown in FIG. 6-c, photographing said object O having the shades in the form of curved lines formed thereupon by said projection so as to resolve the surface of said object into a multitude of curved lines, thereafter projecting thus obtained photographs and said screens at the same time upon a body of clay, and applying clay or removing clay from said body in such a manner that said curved lines are concentrated or converged upon the surface of said body and are appearing there as straight lines, when viewed from the screen side.

3,580,759
HEAT TRANSFER ADDITIVES FOR ABSORBENT SOLUTIONS
Clarence E. Albertson, Villa Park, and Robert H. Krueger, Palatine, Ill., assignors to Borg-Warner Corporation, Chicago, Ill.
No Drawing. Filed June 25, 1968, Ser. No. 739,629
Int. Cl. C09k 3/02

U.S. Cl. 252—71

8 Claims


Improved heat transfer additives for lithium bromide absorbent solutions are selected from a class of tertiary alcohols. The tertiary alcohols have greater oxidative stability and, therefore, do not react as rapidly with the chromate corrosion inhibitors which are commonly used in the absorbent solutions. In all cases, the heat transfer improvement is at least as good as known, less stable, primary (and secondary) alcohols.

3,580,760
PROCESS OF MAKING LAMINATED WOOD PRODUCT UTILIZING MODULUS OF ELASTICITY MEASUREMENT
Peter Koch, Alexandria, La., assignor to the United States of America as represented by the Secretary of Agriculture
Continuation-in-part of application Ser. No. 429,175, Jan. 29, 1965. This application May 29, 1969, Ser. No. 829,103

Int. Cl. G01b 5/00

U.S. Cl. 156—64

3 Claims




This invention relates to a process for producing laminated structures, and more specifically laminated beams, whereby the entire product of logs or bolts of wood is utilized, regardless of the presence of undesirable properties inherent in the lumber cut from said logs or bolts. Laminae are obtained from the logs by any convenient cutting method, dried to a low moisture content, relatively graded according to their deflection under a standard load at their center while supported near their end points, then arranged into a laminated structure with those laminae that have the greatest deflection in the center of the structure and those with progressively less deflection located away from the center such that the least deflective laminae are furthest from the center of the structure, and the laminae are then bonded by an adhesive.

3,580,761
METHOD OF FORMING NONWOVEN ARTICLES BY FUSING STRANDS TO A BASE
Harold D. Boultinghouse, Bartlesville, Okla., assignor to Phillips Petroleum Company
Filed Dec. 2, 1966, Ser. No. 598,682
Int. Cl. D04h 11/00

U.S. Cl. 156—72

5 Claims




1. A method of bonding meltable material to a receptive base which comprises

- passing at least one strand of said material through a hollow, tubular passage and through a restricted extremity thereof to project said material slightly beyond said extremity,
- melting at least a portion of the projecting material,
- contacting the thus melted material with said receptive base to bond said material to said base, and
- separating the passage and base to draw said material through said passage.

3,580,762
METHOD OF MAKING DOUBLE-WALLED PLASTIC ARTICLES
Fred R. Zumstein, Detroit, Mich., assignor to King-Seeley Thermos Co., Ann Arbor, Mich.
Filed Jan. 23, 1969, Ser. No. 793,301
Int. Cl. B32b 31/00; C09j

U.S. Cl. 156—73

4 Claims




A method of making double-walled, heat insulating plastic tableware or other plastic articles of a type having radially spaced inner and outer sets of seating and mating surfaces fused together by a spin welding operation.

3,580,763
METHOD OF PRODUCING FIBER-REINFORCED FOAM PRODUCTS
Gaspard X. Criner, Cary, and William A. Blackburn, Chapel Hill, N.C., assignors to Monsanto Company, St. Louis, Mo.
Continuation-in-part of application Ser. No. 578,073, Sept. 8, 1966. This application Mar. 13, 1969, Ser. No. 820,033

U.S. Cl. 156—78

Int. Cl. B32b 5/18

1 Claim



Flexible fiber-reinforced foam products, comprised of unitary cellular structure foam bodies, the foam bodies having a fiber content comprising a multiplicity of staple fibers randomly oriented in a multi-directional pattern and distributed with uniform randomness throughout the body, the fiber content per unit area being at least the amount determined with respect to the denier by the equation:

$$y = 1.9(7.368) \frac{x^{0.5}}{10.5}$$

where y = fiber denier and x = web weight in ounces per square yard, are produced by forming a nonwoven web consisting of randomly oriented fibers of controlled inter-fiber cohesion and porosity, dispensing a foamable mixture onto the web, and then compressing the foam-covered web.

3,580,764
MANUFACTURE OF BODIES FROM A BUNDLE OF BONDED RESIN TUBES
Fritz Gerlach, Weil am Rhein, Toni Hauskrecht, Hattlingen, and Hermann Holch, Lorrach, Germany, assignors to Lonza-Werke GmbH, Weil am Rhein, Germany
No Drawing. Filed July 5, 1967, Ser. No. 651,138
Claims priority, application Switzerland, July 5, 1966, 9,764/66

U.S. Cl. 156—83

Int. Cl. B32b 31/14


6 Claims

Parallel substantially rigid resin tubes are assembled to a bundle in which the tubes are mechanically held together; the bundle is then subjected to a treatment which swells and softens the contacting surfaces of the tubes whereby the tubes are bonded together under the pressure developed by the swelling action. Finally, the bundle is dried under said pressure while the tubes are still mechanically held together, and then the bundle is removed as a coherent body from the holding means.

3,580,765
RESILIENT O-RING AND METHOD OF MANUFACTURE
Marvin H. Grove, Houston, Tex., assignor to M & J Valve Company, and M & J Development Company, both of Houston, Tex.
Filed Apr. 21, 1969, Ser. No. 817,651
Int. Cl. B29h 5/02; F16j 9/00

U.S. Cl. 156—110

3 Claims




A resilient O-ring characterized by a particular type of junction between the ends of cured resilient stock. A conical cavity is formed in one end of the stock and a conical taper on the other end, the taper being on an included angle greater than that of the cavity. After applying cement the two parts are forced together with radial expansion at the junction. The junction is then trimmed away to the dimensions of the stock.

3,580,766
METHOD FOR MANUFACTURING PNEUMATIC TIRES
Antonio Pacciarini, Milan, and Renato Caretta, Gallarate, Italy, assignors to Pirelli S.p.A., Milan, Italy
Filed Mar. 13, 1968, Ser. No. 712,749
Claims priority, application Italy, Mar. 15, 1967, 13,715
Int. Cl. B29h 17/10

U.S. Cl. 156—123

4 Claims



A method for the manufacture of pneumatic tires wherein the tire carcass is positioned on two annular supporting


surfaces and freely shaped by mutually approaching the latter and by admitting compressed fluid inside the carcass. The shaped carcass is subjected to a slight axial compression from the portion of the carcass containing the bead cores to the proximity of its median plane by means of two rigid, equal and opposite surfaces having a toroidal profile axially narrower than that corresponding to the ideal shape of the freely shaped carcass, these surfaces being spaced from each other during the compression to define a space over the mid-circumferential portion of said carcass. The tire tread band may then be applied over the mid-circumferential portion of the carcass and between said surfaces.

3,580,767

METHOD OF MAKING A TOOTHED DRIVE BELT WITH AN ABRASION RESISTANT URETHANE COATING ON THE TRANSMISSION SURFACE
Gerald L. Barnes, Palatine, Ill., and Raymond G. Cichy, South Bend, and Gerald E. Adams, Mishawaka, Ind., assignors to Uniroyal, Inc., New York, N.Y.
Filed Mar. 28, 1969, Ser. No. 811,514
Int. Cl. F16g 1/00; B29n 7/22

U.S. Cl. 156—138

7 Claims



A toothed belt to be used in a positive transmission drive, and a method for manufacturing the said belt. According to the method, a grooved mandrel is coated with a skin coating of a wear and abrasion resistant elastomeric material. A highly viscous tooth filler compound, which is also an elastomeric material, is then applied filling the grooves of the mandrel and covering the entire surface of the skin coating forming the major portion of the belt teeth. Either before or after the filling of the grooves with the filler compound, and before the curing of the filler compound, a reinforcing filament is helically wound around the mandrel and at least partially embedded within the filler compound. Thereafter the mandrel and said coatings are placed in an oven and cured. The cured belt can then be stripped from the mandrel and may be cut into individual belts of smaller width if desired. The belt resulting from this method will have a wear and abrasion resistant elastomeric coating which covers a less wear resistant elastomeric layer. The reinforcing filament is separated from the teeth of the gears which coast with the belt by the wear and abrasion resistant coating.


3,580,768

METHOD OF FORMING DECORATIVE THREE DIMENSIONAL EFFECT DESIGNS AND COATINGS

Stanley Kukla, 1161 Summit Ave.,
Jersey City, N.J. 07307
Filed Nov. 29, 1967, Ser. No. 686,421
Int. Cl. B29c 24/00

U.S. Cl. 156—156

6 Claims



A method of forming decorative three dimensional effect designs and coatings on the smooth surface of a base

material by painting the surface, applying drops of liquid or chips of frozen liquid to the painted surface while the paint is wet, drying the paint surrounding the drops or chips, spraying paint over the entire surface to cover the drops or chips, respraying the surface with paint of another color from an angle of zero to sixty degrees to the surface to create highlight and depth effects, removing the liquid entrapped under the paint film by rolling the surface, drying the painted surface, applying a protective coating to the dried design.

3,580,769


METHOD OF MAKING CORRUGATED THERMOPLASTIC ARTICLES

Phillip H. Parker, San Rafael, Calif., assignor to Chevron Research Company, San Francisco, Calif.
Original application Apr. 5, 1968, Ser. No. 719,147.
Divided and this application Jan. 19, 1970, Ser. No. 4,086

Int. Cl. B31f 1/22

U.S. Cl. 156—206

11 Claims



Corrugated thermoplastic articles are made by simultaneously perforating in closely spaced parallel rows at least two uniaxially oriented sheets of thermoplastic polymer in intimate contact at an angle of at least about 10° relative to orientation with heat to at least fusion temperature of the thermoplastic, cooling fused peripheries of the perforations and annealing the perforated films.


3,580,770

METHOD FOR PRODUCING LAMINATED STRUCTURES

Gilford E. Dyal, San Antonio, Tex., assignor to Tripco, Inc., San Antonio, Tex.
Filed Jan. 31, 1967, Ser. No. 612,938
Int. Cl. B32b 3/04

U.S. Cl. 156—216

14 Claims



Postforming facing sheets such as the C-stage laminates are bonded to and around the returning peripheral edges of a planar polygonal core by a process involving heating only the peripheral outer portions of the sheet and bonding the outer portions of the sheet to the core with a heat activated adhesive while the main portion of the sheet is bonded to the core by a contact adhesive.

The apparatus for this method has a support surface surrounded by two sets of heating bars which heat only the outer portions of the sheet with the outer set of heating bars being movable relative to the core to wipe the sheet around the core after the sheet is heated to post-forming temperature by the heater bars. The apparatus

has a lower mechanism comprising the support and heaters and an upper mechanism having elements which exert downward pressure to enable positioning heating and bending of the sheet to the core.

3,580,771

METHOD FOR RENDERING AN IRREGULAR SURFACE SMOOTH UTILIZING DIRECT CONTACT TRANSFER

Kent N. Maffitt, Minneapolis, Minn., assignor to Litton Systems, Inc., Beverly Hills, Calif.
Filed Apr. 13, 1967, Ser. No. 630,704
Int. Cl. B44c 1/00

U.S. Cl. 156—235

5 Claims

A method for smoothing minute irregularities in the surface of magnetic recording tape. A thermoplastic material is applied to the tape oxide surface and the tape then is disposed against a gold-coated flat casting surface while heat and pressure are applied. Thermal shock from applied liquid nitrogen causes release of the coated tape from the casting surface. A weighted roller on the apparatus applies pressure to the tape.

3,580,772


METHOD AND APPARATUS FOR THE TRANSFER OF IMAGES ONTO SURFACES OF HOLLOW ELASTOMERIC ARTICLES

Alfonso Vergara Ochoa, Tepeyac 1287, Guadalajara, Jalisco, Mexico
Filed May 16, 1967, Ser. No. 638,964
Claims priority, application Mexico, Feb. 6, 1967, 93,867

Int. Cl. B44c 5/00

U.S. Cl. 156—240

10 Claims



A process for the transfer of images from a flat film onto the surface of moderately irregular hollow elastomeric articles, which comprises printing a film with an ink having a resin base incompatible with the resin of said film, applying a layer of a resin varnish on the surface of said printed film or on the surface of the article, said varnish having a resin base compatible with the base of said ink and with the resin of which said article has been formed, applying said film on the surface of said elastomeric article, inflating the article in order to extend and tighten the film on its surface, while the varnish is still on its mordant state, allowing the varnish to dry, and peeling off the film from the surface of said article whereby the printed image will be transferred unto the surface of said article.

An apparatus for carrying out the above described process which comprises a hydraulic press with a flat movable lower platen to accommodate a printed film and a concave fixed upper platen with means for supporting an irregular hollow article, and means for displacing said lower platen to contact said film with the article supported by the upper platen whereby the film will be adhered thereto.

3,580,773


APPARATUS FOR MOULDING ARTICLES FROM PLASTICS MATERIAL

Jack Marvin Schneider, Kingswood, England, assignor to Calmec Extrudorm Limited
Filed Apr. 19, 1967, Ser. No. 631,959
Claims priority, application Great Britain, Apr. 22, 1966, 17,699/66

Int. Cl. B29f 3/00

U.S. Cl. 156—244

7 Claims



A composite sheet of thermoplastics material is formed by bonding together a first, extruding sheet and a second, preformed sheet of cheaper material. The second sheet has a series of identification marks printed thereon at locations spaced lengthwise of the sheet and a series of register marks. Articles are formed by feeding the composite sheet from the bonding means to an article-forming apparatus. Means are provided for detecting the arrival of a register mark at a predetermined location on the path of the second or the composite sheet and controlling the operation of the article-forming apparatus so that each article bears an identification mark at a predetermined location thereon.

3,580,774

METHOD FOR COATING WORK PIECES WITH THERMOPLASTIC MATERIAL


Terence J. L. Clarke, Leicester, England, Ivor Evans, deceased, late of Leicester, England, by Josie V. Evans, administratrix, Cossington, England, assignors to United Shoe Machinery Corporation, Flemington, N.J.

Filed Sept. 6, 1967, Ser. No. 667,323
Claims priority, application Great Britain, Sept. 9, 1966, 40,366/66; Dec. 9, 1966, 55,212/66; Feb. 14, 1967, 6,894/67

Int. Cl. B23b 31/12

U.S. Cl. 156—247

3 Claims



A method of coating sheet material work pieces with thermoplastic adhesive material is provided by the present invention. According to the method, work pieces are


assembled between a layer of thermoplastic adhesive material and a layer of stripper material suitably newsprint, and the assembly is subjected to heat and pressure. The coated work pieces and the stripper layer are separated while the thermoplastic adhesive is in heat softened condition, the stripper material retaining surplus adhesive material. Suitably, the layer of thermoplastic adhesive material is a film, preferably supported on a layer of release material, suitably silicone paper, which enhances the cleanliness of the pressing operation and which upon separation serves to retain the work pieces while surplus thermoplastic adhesive material is removed on the stripper layer.

3,580,775

METHOD OF MAKING FIBERSCOPES WITH TRIMMED TIPS

Walter P. Siegmund, Woodstock, Conn., assignor to American Optical Corporation, Southbridge, Mass.
Filed Apr. 28, 1969, Ser. No. 819,791
Int. Cl. B32b 17/02; G02b 5/16
U.S. Cl. 156—247

5 Claims



Fiberscopes formed of a multiplicity of accurately superimposed circular fiber ribbons. A portion of the length of each ribbon is coated in one zone with a material of high glass-bonding strength and with a strip of an adhesive parting agent at each side of the high strength bonding material. The coated portions are accurately superimposed and cured at an elevated temperature to produce a high strength bond centrally of the coated portions through which a cut is made to form opposite ends of the fiberscope. These ends are cut, ground, sawed or core drilled partially into adjoining areas of the adhesive parting agent to provide the fiberscope with tips of a desired shape and size whereupon trimming of the remaining length of the fiberscope to a corresponding shape and size is effected by delamination.

3,580,776

METHOD OF PRODUCING ELECTRIC CONTACT BETWEEN TWO CEMENTED PARTS


Leonid Zalmanovich Shenfil, 1 Cherkivovskaya y1. 60, kv. 3; Valentin Evgenievich Gul, Zelenodolskaya 33, korp. 1, kv. 10; Galina Konstantinovna Melnikova, 1 Bas-manny per. 12, kv. 23; Nina Isidorovna Siprikova, B. Zjuzinskaya ul. 10, korp. 12, kv. 22; Maiya Konstantinovna Rozhdestvenskaya, Leninsky prosp. 101, korp. 179, kv. 22; and Alexandr Nikitichna Kuzina, N. Khoroskevskoe shoss 18, korp. 4, kv. 8, all of Moscow, U.S.S.R.

Filed June 9, 1967, Ser. No. 645,038

Int. Cl. B29c 19/06

U.S. Cl. 156—275

7 Claims



A method is provided for producing an electric contact by means of a current-conducting cement constituted

as a hardening epoxy resin containing a current-conducting ferromagnetic filler. The cement film is hardened in a non-uniform magnetic field having a variable intensity across the field section, and initially a pulsating magnetic field is applied having a frequency of 0.1 to 1000 c.p.s. when the static component of magnetic induction has a value of 50 to 15,000 gauss and when the amplitude is within the range of 10 to 5000 gauss.

3,580,777

METHOD OF BONDING ASBESTOS SHEET MATERIAL TO CONCRETE

Rowland S. Hartzell, Gibsonia, Pa., and Gene Gerek, Oswego, Ill., assignors to PPG Industries, Inc., Pittsburgh, Pa.
No Drawing. Continuation-in-part of application Ser. No. 528,347, Feb. 18, 1966. This application Dec. 2, 1968, Ser. No. 780,587
Int. Cl. B23b 31/00

U.S. Cl. 156—278

8 Claims

Composite coated concrete articles having a surface coating of a cured or other resinous material comprise a cementitious base and adherently bonded thereto a layer of asbestos sheet material which is coated with an organic coating. Such articles can be obtained by curing the cementitious base while in contact with the uncoated side of pre-coated asbestos sheet material to produce concrete articles in which the coated asbestos sheet material is directly bonded to the concrete with exceptional adhesion.

3,580,778

METHOD AND APPARATUS FOR PLYWOOD PANEL LAY-UP

Charles L. Larson, Grants Pass, Oreg., assignor to Jeddell Bros. Sweed Mills, Inc., Gold Hill, Oreg.
Filed June 27, 1968, Ser. No. 740,676
Int. Cl. B32b 31/06, 31/12

U.S. Cl. 156—299

9 Claims



Apparatus and method for laying up plywood panels. Included in the apparatus is a veneer conveyor for carrying a series of presized veneer sheets in one direction, and a core conveyor spaced above the veneer conveyor for carrying core pieces in the same direction. The core conveyor converges on the veneer conveyor to place core pieces on the veneer sheets at a placement station. Supply means upstream from the placement station deposits a charge of multiple core pieces on the core conveyor, with the grain of the core pieces extending transversely of the core conveyor. Glue sprayers are supported above the veneer conveyor, with one upstream of the placement station and another downstream of the placement station. And these apply glue to the upper faces of the veneer sheets and the upper faces of the core pieces, respectively.

3,580,779

HAND OPERATED TOOL FOR MARKING WIRE


Fred G. Schriever and Sigmund Cheslin, both of 16333 Harper Ave., Detroit, Mich. 48224
Filed Oct. 21, 1966, Ser. No. 588,534
Int. Cl. B32b; B41m

U.S. Cl. 156—384

4 Claims

This invention is directed to a portable hand tool used for on the job identification of wire, wherein adhesive tape is printed with selected indicia by the operator and

dispensed at the will of the operator for manual or automatic application to the wire at the desired locations, or



the indicia can be applied directly to the wire or other cylindrical object.


3,580,780

METHOD AND APPARATUS FOR BAR SEALING OF GIRDLE PANELS

Herbert G. Klawunn, Millington, and John Addison Herr, Garwood, N.J., assignors to The Singer Company, New York, N.Y.
Filed May 7, 1969, Ser. No. 822,627
Int. Cl. B29c 27/04

U.S. Cl. 156—380

7 Claims



This disclosure relates to a method and apparatus for bar sealing of girdle panels to form curved side seams, initially held in place by clamping and folding the same over a curved sealing die, which is subsequently mated with a second die along the seam to effect a seal, thermally or dielectrically.


3,580,781

APPARATUS FOR BUILDING UP TREAD MATERIAL ON A TIRE CARCASS

Jack Lyndon Hollis, Pottstown, Pa., and Ray Douglas Shockey, Uniontown, Ohio, assignors to The Firestone Tire & Rubber Company, Akron, Ohio
Continuation of abandoned application Ser. No. 316,287, Oct. 15, 1963. This application May 20, 1968, Ser. No. 740,795
Int. Cl. B29h 17/20

U.S. Cl. 156—397

4 Claims



A tire carcass supported in rotating contact with a roll picks up rubber tread material from the roll to build up


the desired contour of tread material on the carcass. Cutters on the roll separate a sheet of tread material into a plurality of ribbons, at least one of which is removed from the roll before the roll contacts the tire carcass. The cutters are positioned to vary their spacing and thus change the ribbon widths. By removing the center strip, tread material in the shoulder areas can be built up as desired.

3,580,782

APPARATUS FOR SHAPING TIRES
Jean Leblond, Compiègne, France, assignor to Uniroyal Englebert France S.A., Paris, France
Filed Sept. 12, 1968, Ser. No. 759,401
Claims priority, application France, Sept. 15, 1967, 121,259
Int. Cl. B29h 17/26

U.S. Cl. 156—415

35 Claims



A tire building machine comprising a pair of variably spaced carcass support rings coaxially disposed with respect to each other and providing for direct inflation of a first stage carcass supported thereon. At least one of the rings includes an expandable and contractible elastic band for sealingly engaging the respective bead of the carcass.


3,580,783

METHOD OF PRODUCING MULTITUDINOUS STRAIGHT CUT-TO-LENGTH FILAMENTS IN ORIENTED FORM

Ardelle Glaze, Fort Wayne, Ind., assignor to Fort Wayne Metals, Inc.
Filed Jan. 4, 1968, Ser. No. 695,633
Int. Cl. B31c 11/02

U.S. Cl. 156—426

1 Claim



Small diameter wire which has been prestressed is arranged in a plurality of substantially parallel or otherwise oriented strands which are bound together by a readily removable adhesive and thereafter cut to desired size. The adhesive binding the individual, cut strands together may or may not be removed to provide either a plurality of prearranged strands of wire bound together into non-woven cloth or a mass of individual strands oriented in parallel or other relationship.

3,580,784


APPARATUS FOR MAKING A BIAS LAID RIBBON
Charles A. Lee and Warren R. Furbeck, Knoxville, Tenn.,
assignors to International Paper Company, New York,
N.Y.

Filed Apr. 9, 1968, Ser. No. 719,986

Int. Cl. B65h 81/02

U.S. Cl. 156—429

13 Claims



A multiply ribbon is formed by apparatus in which at least one web of material is wound spirally about a mandrel and then stripped and flattened. To reduce inertia and gyroscopic forces encountered when unwinding a web parent roll about its longitudinal axis while it is spinning relative the mandrel about another axis, the parent roll is mounted in a rotatable carrier at one end of the mandrel with the respective axes being substantially coplanar. The mandrel may be suspended from the carrier and driven in a direction reverse to that of the carrier so that the mandrel remains stationary relative to nip rolls. The preferred ribbon is formed of bias laid, superimposed plies of creped tissue and has the surfaces of the ribbon textured by spaced depressions at which fibers in one ply are interlocked with fibers in an adjacent ply.

3,580,785

TAPE WRAPPING APPARATUS WITH TRAVELING WHEEL GEAR


Peter Mihalkanin, 1224 Maple Ave., Berwyn, Ill. 60402

Filed Sept. 3, 1968, Ser. No. 756,896

Int. Cl. B65b; B65c 3/02

U.S. Cl. 156—468

16 Claims



A taping apparatus particularly adapted to operate as a portable hand unit for peripherally wrapping a work piece with flexible adhesive tape. A split wheel gear is rotatable in a uniform rotational direction between elongated rack gears. The wheel gear is translated in a first direction in driving engagement with one rack while

the other rack is displaced longitudinally and away from the first rack. The wheel gear continues its uniform rotation by disengaging from the first rack and engaging the other rack in driving relationship during translation in the opposite direction. During such translation in both directions, the tape is initially wrapped around the work piece, is cut, and is finally wrapped around the work piece.

3,580,786


BANDING APPARATUS FOR STACKED ARTICLES
James E. Doane, 340 13th Ave. S., Naples, Fla. 33940,
and Robert C. Sheriff, 1401 Elm Ave., Round Lake,
Ill. 60073

Filed June 30, 1967, Ser. No. 650,296

Int. Cl. B65b 13/06; B65c 1/04

U.S. Cl. 156—475

10 Claims



Apparatus for adhering a band around stacked articles such as labels, facing slips and the like wherein a combination of clamping jaws operate to adhere ends of the bands around individual stacks and sever the bands between stacks, and transport claws engage the banded stack to advance it along a trough to a discharge position. Heating elements are provided for the clamping jaws and the sides of the trough if the bands are of heat-seal type.

3,580,787


PLASTIC LAMINATING APPARATUS
George W. Loy, Scio, Ohio, assignor to Scio Cabinet
Company, Inc., Scio, Ohio

Filed Dec. 15, 1969, Ser. No. 885,014

Int. Cl. B32b 31/26

U.S. Cl. 156—477

22 Claims



A plastic laminating apparatus for laminating plastic sheet material to a countertop core having a backplash attached at right angles thereto during a single pass through the apparatus. The apparatus consists of a plurality of longitudinally spaced work stations through which the work is successively moved for progressively shaping and adhering the plastic laminate to the work, such work being guided through the apparatus by receipt of a downwardly projecting portion from the work in a guide track extending the entire length of the apparatus. A back die bends the laminate to conform to the general shape of the backplash and countertop after heating, and fingers and pressure rolls are used to progressively bend and press the projecting edges of the laminate into firm-contact with the edges of the countertop and backplash. Floating cutters are also used to trim the excess laminate material extending beyond the countertop and backplash edges, and such excess material may be picked up by a suction blower or removed by a rotary brush prior to passage through final pressure rolls.

3,580,788

APPARATUS FOR FORMING A TUBE FROM A TRAVELLING WEB


Ake Gustafson, Chatel-Saint-Denis, Switzerland, assignor
to Tetra Pak AG, Zurich, Switzerland
Filed Sept. 28, 1967, Ser. No. 671,451

Claims priority, application Switzerland, Sept. 28, 1966, 13,998

Int. Cl. B32b 31/00

U.S. Cl. 156—497

1 Claim



A travelling web of material is formed into a tube with at least one of the longitudinal edges of the web passing through a heating means supplied with heated air. The two edges of the web are pressed together to form a welded seam after passing through the heating means. The heating means comprises a heating chamber having an internal lining of a non-adhering material. An air pipe opens into the chamber with means for supplying heated air. The lining is attached to the exterior surface of the heating chamber and is passed around the air pipe and has a vertical slit-shaped opening through which one edge of the travelling web can project into the interior of the heating chamber.

3,580,789

WELDING GEAR FOR OBJECTS OF THERMOPLASTIC MATERIAL

Günter Wenzel, Kelkheim, Taunus, Germany, assignor to
Farbwerke Hoechst Aktiengesellschaft vormals Meister
Lucius & Bruning, Frankfurt am Main, Germany


Filed July 9, 1968, Ser. No. 743,487

Claims priority, application Germany, July 25, 1967, F 53,049

Int. Cl. B32b 31/30

U.S. Cl. 156—497

5 Claims



The spout or shoe of a welding gear for objects of thermoplastic materials, by means of which fully plasticized welding material is brought into a prepared welding gap, comprises, between two lateral guide surfaces, a smoothing face, a connection for the supply of the welding material and at its leading end a nose projecting into the welding gap.

3,580,790

APPARATUS FOR THE AUTOMATIC WRAPPING OF ROTATABLE BODIES

Heinz Pollmeier, Rosrath, Bezirk Cologne, and Johann
Wittbuhn, Furstendamm, Germany, assignors to
Klebetchnik GmbH, Dusseldorf, Germany


Filed Apr. 23, 1969, Ser. No. 818,738

Claims priority, application Germany, May 6, 1968, P 17 60 342.8

Int. Cl. B65c 3/16, 9/04

U.S. Cl. 156—521

12 Claims



Apparatus for the automatic wrapping of rotatable bodies. The bodies are supported and moved into a wrapping position located beneath a suction roller which applies a foil strip to the rotatable body. The foil strip may be printed on and is automatically fed to the suction roller by various roller pairs. All of the operations are correlated so as to intermittently feed a single rotatable body to a wrapping work station simultaneously with the foil strip. The wrapped rotatable body is then carried to a discharge point on the apparatus.

3,580,791

DEVICE FOR APPLYING A BAND OF THERMOSETTING MATERIAL ONTO A LABEL AND FOR SEALING THE LABEL ONTO AN ARTICLE


Grant H. Jordan, Parma, Ohio, assignor to American
Greetings Corporation, Cleveland, Ohio

Filed June 19, 1968, Ser. No. 738,173

Int. Cl. C32b 31/00

U.S. Cl. 156—540

20 Claims




There is provided a device for producing a label with a band of thermosetting material on one side thereof for subsequent heat sealing of said label onto an article. This device comprises a means for moving a strip of label stock and an adhesive strip having a thermosetting layer and a backing strip along a feedline with the thermosetting layer adhered to said strip of label stock. A parting member pulls the backing strip from the adhesive strip while a stripper member prevents the backing strip from pulling the thermosetting layer from the label stock, and a cutting means cuts the label stock into separate labels. There is provided a further device for then heat sealing the label onto a package formed from thin plastic film material.

3,580,792

LUMBER AND VENEER JOINTER

Andrew M. Kvalheim, 823-825 Petaluma Blvd. S., Petaluma, Calif. 94952, and Bob L. McEvers, 7300 SW. Child Road, P.O. Box 28, Tualatin, Oreg. 97062
 Filed May 23, 1968, Ser. No. 731,525
 Int. Cl. B32b 31/12; B29c 19/00; B27d 3/00
 U.S. Cl. 156-546 15 Claims



A machine for jointing lumber on both longitudinal edges, simultaneously, by squaring said edges, and by applying glue, if desired, so that the finished lumber piece is ready for joining with other like pieces to form a panel. Either veneer or lumber strips may be prepared by the machine. The machine comprises a tubular frame assembly, an endless chain conveyor assembly for passing lumber to be treated through the machine, series of top and bottom hold-down rollers for guiding the lumber through the machine, and a pair of cutter assemblies for simultaneously finishing the longitudinal edges, each said cutter assembly being incrementally movable inwardly and outwardly with respect to the long axis of the machine by means of a positioning set works assembly, remotely controlled. The machine also includes a pair of glue applicators for applying glue to the finished lumber edges, and a top, hold-down roller assembly, each hold-down roller being individually actuable to a hold-down position, or, alternatively, the entire bank of rollers may be simultaneously actuable to a hold-down position. A vertical adjustment assembly is provided for setting each roller in a pre-determined hold-down position; the adjustment mechanism sets all top rollers simultaneously.

3,580,793

APPARATUS FOR WELDING THERMOPLASTIC SHEET MATERIAL

Eugene E. Hewitt, Walkerton, Ind., assignor to Uniroyal, Inc., New York, N.Y.
 Original application Aug. 19, 1966, Ser. No. 573,688, now Patent No. 3,468,732, dated Sept. 23, 1969. Divided and this application Apr. 21, 1969, Ser. No. 840,570
 Int. Cl. B29c 27/08; B23b 31/10
 U.S. Cl. 156-579 3 Claims




Apparatus for welding thermoplastic sheet material including conical shaped thermoplastic buttons spun welded

to join mating edges of two thermoplastic sheets and a friction driver mountable in a hand drill for spinning buttons.

3,580,794

STAMPING PRESS WITH LINEARLY APPLIED FORCE

Leonard A. Mintz, 27 Kettering Road, Norwood, Mass. 02062
 Filed Oct. 7, 1968, Ser. No. 765,557
 Int. Cl. B30b 1/40, 15/20; B32b 31/20
 U.S. Cl. 156-581 6 Claims



A stamping press having an air cylinder which transfers its force to a stamping head by means of a wedge forced by the air cylinder between a reaction roller and a ram driving the stamping head. During the approach stroke, one planar face of the wedge is at a substantial angle to the axis of the piston of said air cylinder, but during the pressure stroke another planar face of the wedge is disposed at a very small angle to the piston and it exerts its pressure substantially solely along the axis of travel of the stamping ram. The press also has a hand lever to rotate the air cylinder and wedge about an axis to permit hand operation of the ram. When used for roll leaf stamping a linear thrust drive is coupled to the roll leaf to advance it in the same direction upon both directions of motion of said thrust drive.

3,580,795


APPARATUS FOR WELDING HEAT SEALABLE SHEET MATERIAL

John E. Eichenlaub, 9321 Franklin Ave. W., Minneapolis, Minn. 55426
 Continuation-in-part of application Ser. No. 584,564, Oct. 5, 1966. This application Dec. 1, 1969, Ser. No. 881,250
 Int. Cl. B30b 15/34; B32b 31/20
 U.S. Cl. 156-583 24 Claims

An apparatus for welding heat sealable sheet material with heated fluid moving through a platen having a chamber. The chamber is closed with a flexible, nonelastic, thin cover having a surface area exposed to the chamber that is larger than the transverse area of the chamber, whereby the cover is moved by the pressure of the fluid in the chamber without elongating or deforming the cover to transmit force and heat to a surface of the sheet material. The cover is urged toward the sheet material by the heated fluid under pressure which transmits both heat and pressure to the sheet material to weld the material. The platen may be provided with fluid in a vapor phase to provide the platen

with totally uniform pressure on the cover which adjusts to the irregularities on the surface opposing the cover. The vapor also maintains, through condensation of the

and to completely surround a central area which is substantially free of embossing. The border forming embossed marginal areas are of substantially uniform width and extend inwardly along the opposite side edges of the table cover from the original untrimmed marginal side edges.



vapor, a uniform surface temperature on the cover. The condensed liquid is returned from the chamber back to a vapor generating source.

3,580,796

GLASS LAMINATED BY AN ADHESIVE COMPRISING THE POLYURETHANE RESULTING FROM THE REACTION OF BIS(2-ISOCYANATOETHYL) FUMARATE WITH POLYOLS WITHOUT OTHER ISOCYANATE


Robert M. Hick, Jr., Springfield, and Joseph C. Gould, Norwood, Pa., assignors to E. I. du Pont de Nemours and Company, Wilmington Del.
 No Drawing. Filed Mar. 16, 1967, Ser. No. 623,566
 Int. Cl. B32b 17/10, 27/40 7 Claims

A composite article is prepared by (a) providing a liquid polyurethane by reacting bis (2-isocyanatoethyl) fumarate with a polymeric polyol component which preferably comprises a triol obtained from propylene oxide and 1,2,6-hexanetriol, and (b) using said polyurethane to coat a layer of glass or acrylic plastic or to bond said layer (e.g., a windshield) to another layer of solid material (e.g., an auto body) with a cured bond which is highly resistant to adhesive failure when the article is exposed to sunlight and outdoor weather for extended periods of time.

3,580,797

TABLE COVER

James E. Asmuth, Neenah, Wis., assignor to Wisconsin Tissue Mills, Menasha, Wis.
 Filed Aug. 22, 1969, Ser. No. 852,390
 Int. Cl. B32b 1/00, 3/02 4 Claims



A table cover comprising at least one ply of thin cellulosic tissue and an additional ply of thin polyethylene film which is superimposed in an edge aligned relation with the first ply. The plies are secured in a laminated relation by embossing in areas of substantial width extending along the marginal edges to form a border for the table cover

3,580,798

BIAXIALLY STRETCHED TRIOXANE COPOLYMER FILM AND PROCESS FOR THE PREPARATION THEREOF

Gunter Kegelmann, Neustadt an der Weinstrasse, and Horst Gebler and Walter Seifried, Wiesbaden-Biebrich, Germany, assignors to Kalle Aktiengesellschaft, Wiesbaden-Biebrich, Germany
 Filed Apr. 23, 1969, Ser. No. 818,531
 Claims priority, application Germany, Apr. 26, 1968, P 17 69 257.8
 Int. Cl. C08f 15/12; C08g 1/04; D01d 5/12 4 Claims


The invention relates to a biaxially stretched film and process for the preparation thereof, the film being a high molecular weight linear trioxane/ethylene oxide copolymer having stabilized end groups and containing 80 to 99.9 percent by weight of trioxane based on the total weight of the polymer, the film exhibiting a sag of less than 0.2 percent characteristic for a flat film, a deviation in thickness of less than ± 6 percent from the average thickness, an elastic modulus in all directions of the film plane of at least 300 kg./mm.², an ultimate tensile strength above 15 kg./mm.² at an elongation at rupture of less than 100 percent, and a shrinkage capacity, at 140° C., of less than 5 percent.

3,580,799

LAMINATED PRODUCTS

Heinz Uelzmann, Cuyahoga Falls, and David C. Hidingier, Akron, Ohio, assignors to The General Tire & Rubber Company
 No Drawing. Original application Sept. 28, 1967, Ser. No. 671,187, now Patent No. 3,502,618. Divided and this application Nov. 26, 1969, Ser. No. 870,530
 Int. Cl. B32b 15/08, 27/38; C08g 30/14 9 Claims

Epoxy resin adhesives with improved adhesive properties, e.g., higher shear strengths under conditions of shorter cure time and/or lower cure temperature, are formed from mixtures of epoxy resins and aziridinyl compounds containing catalytic amounts of compounds that have both >NH and



groups, e.g., sulfamic acid or formamidine sulfinic acid.

3,580,800

METHOD FOR BONDING OLEFINIC TERPOLYMERS TO NATURAL RUBBER AND VULCANIZATES OBTAINED THEREBY

Luigi Torti and Guido Bertelli, Ferrara, Italy, assignors to The B. F. Goodrich Company, New York, N.Y.
 No Drawing. Filed June 26, 1967, Ser. No. 649,039
 Claims priority, application Italy, June 28, 1966, 14,823/66
 Int. Cl. C09j 3/12 4 Claims

Process for bonding (1) vulcanizable composition comprising low-unsaturation ethylene/higher alpha-olefin/unsaturated diolefin terpolymer, a vulcanizing agent therefor and carbon black with (2) vulcanizable composition comprising natural rubber, a vulcanizing agent therefor and carbon black, this process comprising interposing between layers of compositions (1) and (2) a layer of (3) vulcanizable composition comprising a brominated co-

polymer of isobutene with about 0.5-5% by weight of isoprene, a vulcanizing agent therefor and carbon black, the carbon black in composition (3) having a lower activity than the carbon black in layers (1) and (2), contacting the three layers under pressure, and then heating at a temperature of 130-210° C. to thereby covulcanize the three layers and obtain a high degree of adhesion therebetween.

3,580,801

METHOD FOR MANUFACTURING NONWOVEN FIBROUS PRODUCTS FROM GEL FIBERS

Thomas C. Spence, Yorktown, Va., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Division of application Ser. No. 567,846, July 26, 1966, now Patent No. 3,436,304, which is a continuation-in-part of applications Ser. No. 457,139, and Ser. No. 457,178, both May 19, 1965. This application July 25, 1968, Ser. No. 747,457

The portion of the term of the patent subsequent to Apr. 1, 1986, has been disclaimed and dedicated to the Public

Int. Cl. D21f 11/00; D21h 5/12

U.S. Cl. 162-157

8 Claims

A process for preparing a dry, nonwoven fibrous sheet, comprising:

(a) forming a web of self-bonding gel fibers of thermoplastic, fiber-forming polymer of acrylonitrile, said gel fibers having a gel network structure that has never been completely collapsed by drying and that consists essentially of interconnecting capillary spaces intimately intertwined with fibrillar structure of polymeric material;

(b) subjecting said web to drying conditions between two spaced barriers which limit the physical movement of said web in its thickness direction while providing substantially no restraint to movement in the other two directions; and

(c) recovering a dry, nonwoven fibrous sheet.

The product is useful as a textile fabric in the preparation of a variety of materials ranging from hard, boardy sheets to soft, fluffy fabrics to stretchable, tough fabrics.

3,580,802

DEVICE FOR DETERMINING THE SHAPE OF MAGNETIC SURFACES IN TOROIDAL CONFIGURATIONS CONTAINING PLASMA


John L. Johnson, Niels K. Winsor, John M. Dawson, Rolf M. Sinclair, and Joel C. Hosea, Princeton, N.J., assignors to the United States of America as represented by the United States Atomic Energy Commission

Filed Apr. 22, 1969, Ser. No. 818,374

Int. Cl. G21b 1/00

U.S. Cl. 176-1

5 Claims



Method of surveying the shape and location of magnetic surfaces in a stellarator with an electrostatic acoustic oscillation mode that dominates ordinary sound waves associated with plasma particle motion along the magnetic surfaces.

3,580,803

NUCLEAR REACTORS

Ivor Everson, Wantage, and Maurice William George, Swerford, England, assignors to United Kingdom Atomic Energy Authority, London, England


Filed Sept. 18, 1967, Ser. No. 668,393

Claims priority, application Great Britain, Sept. 21, 1966, 42,249/66


Int. Cl. G21c 19/10

U.S. Cl. 176-28

8 Claims



drops of fissile fuel collect on the bottom of said vertical channel. The inconvenience resulting from said collec-



tion of fissile fuel can be reduced if the vertical channel is divided into a plurality of shorter sections.

3,580,809

NUCLEAR REACTOR FUEL ELEMENT WITH SPACED REDUCTIONS OF DIAMETER

Albert Etheridge Williams, Poulton, and William Simpson Linkson, Blackpool, England, assignors to United Kingdom Atomic Energy Authority, London, England
Filed Mar. 28, 1968, Ser. No. 716,725

Claims priority, application Great Britain, Apr. 12, 1967, 16,875/67

Int. Cl. G21c 3/04

U.S. Cl. 176-76

4 Claims



A fuel pin for a fuel element for a fast breeder nuclear reactor has diameter reductions to bring about a reduction in the cross-sectional area of fissile fuel in register with these diameter reductions, so reducing the heat rating of the volumes of fissile fuel in register with the diameter reductions and reducing the tendency of such volumes to melt in the event of a temperature excursion of the reactor. The resulting barriers to re-orientation of fuel by melting are advantageous. The application of the invention to vibrocompacted fuel and to a combination of vibrocompacted and pelleted fuel is described.

3,580,810

FERMENTATIVE PRODUCTION OF L-THREONINE

Isamu Shiio, Kamakura-shi, and Shigeru Nakamori and Kounosuke Sano, Kawasaki-shi, Japan, assignors to Ajinomoto Co., Inc., Tokyo, Japan

No Drawing. Filed July 26, 1968, Ser. No. 747,828
Claims priority, application Japan, July 28, 1967, 42/48,568

Int. Cl. C12b 1/00

U.S. Cl. 195-29

4 Claims

Certain mutants of *Escherichia coli* which require isoleucine for growth and can grow in the presence of more than 1 mg./l. α -amino- β -hydroxy-valeric acid in an otherwise conventional culture medium produce L-threonine in amounts of several grams per liter of the medium.

3,580,811 SYNTHETIC FERMENTATION MEDIUM AND PROCESS USING SAME FOR CULTIVATING GIBBERELLA ZEAE

Phil Hidy, Terre Haute, Ind., assignor to Commercial Solvents Corporation

No Drawing. Continuation-in-part of application Ser. No. 670,455, Sept. 25, 1967. This application Apr. 16, 1968, Ser. No. 721,606

Int. Cl. C12b 3/02; C12d 13/00

U.S. Cl. 195-100

21 Claims

A synthetic fermentation medium, particularly for use in the production of an anabolic and estrogenic substance identified in U.S. Pat. No. 3,196,019, by cultivation of the microorganism *Gibberella zeae* (Gordon). The medium includes exfoliated vermiculite as a support for the microorganism and an aqueous nutrient production medium containing a sugar such as glucose as the carbohydrate source for the microorganism.

3,580,812

FERMENTER HAVING A MAGNETICALLY DRIVEN AGITATOR


Charles E. Bender and Douglas S. Fraser, New Paltz, N.Y., assignors to Cenco Medical/Health Supply Corporation, Chicago, Ill.

Filed Oct. 19, 1967, Ser. No. 676,419

Int. Cl. C12b 1/00

U.S. Cl. 195-143

4 Claims



A magnetic drive arrangement for fermenters wherein the sample or culture agitated must be maintained free of contamination. The magnetic drive includes a driven plate and a driving plate. The magnets on the driven plate are polygonally arranged with like poles adjacent to maximize field strength, and are mounted in a cup-shaped receptacle, located and held by a simple spacer plate. A cover plate captivates the magnets and is joined to the cup-shaped receptacle to isolate them from the sample agitated. The rotational drive includes a double shaft motor which drives the driving plate at one end through a reduction gear drive, with the other end of the motor shaft directly coupled to a tachometer generator to provide accurate speed readings in the lower speed ranges.

3,580,813

CONDITION RESPONSIVE WATER QUENCH IN A CLOSED COKE COOLING SYSTEM

Basil W. Hinchliffe, Pittsburgh, Pa., assignor to Koppers Company, Inc.

Filed Jan. 28, 1969, Ser. No. 794,485


Int. Cl. C10b 39/12

U.S. Cl. 201-39

11 Claims

Incandescent coke is received from a coke oven through a closed coke guide into a closed hopper car; the car

travels to a closed cooling unit where the coke is dumped. In the closed unit, the coke is charged at a predetermined rate onto a conveyor which travels at a set speed. The coke on the conveyor passes through



water sprays which direct water at a determined flow rate on to the coke to cool the coke to a predetermined temperature. Subsequently, the quenched coke is conveyed away for further processing.

3,580,814

FLOATING, SEA WATER DISTILLATION APPARATUS USING A RECIRCULATING, DIRECTLY CONTACTING FLUENT HEATING MEDIUM


Harry S. Green, R.R. 1, Box 22A, Wilmington, Ill. 60481

Filed Mar. 14, 1969, Ser. No. 807,253

Int. Cl. B01d 3/00

U.S. Cl. 202-234

6 Claims



Sea water, evaporated by direct contact with heated oil discharged into an insulated heat exchange tube, mounted within the lower submerged portion of a steam stack carried by a float member for vertically guided movement in response to tidal changes in the level of the sea water relative to a stationary frame. The oil rises to the top of the water within the heat exchange tube for withdrawal by a suction intake after transfer of its heat to the water. The evaporated water rises as a vapor through the steam stack to a condenser after passing through a steam trap. A pump connected to the suction intake recirculates the oil through a heater.

3,580,815 APPARATUS FOR SIMULTANEOUSLY ACTUATING STANDPIPE LID, DAMPER VALVE AND STEAM VALVE


Llnwood G. Tucker, Pittsburgh, Pa., assignor to Koppers Company

Filed Jan. 30, 1969, Ser. No. 795,185

Int. Cl. C10b 27/06

U.S. Cl. 202-258

5 Claims



Mechanism to actuate simultaneously a standpipe lid, damper valve and steam valve includes two rotary actuators mounted to the larry car each having an arm that engages and rotates linkage to actuate the standpipe lid, damper valve and steam valve.

3,580,816


APPARATUS FOR MAKING LARGE DISTILLATION PLANTS

Robert A. Tidball, Swarthmore, Pa., William M. King, Massillon, Ohio, and Dewey R. Bosley, Boothwyn, and Charles M. Jennings, Norwood, Pa., assignors to Baldwin-Lima-Hamilton Corporation, Philadelphia, Pa.
Continuation-in-part of application Ser. No. 554,453, June 1, 1966. This application Oct. 17, 1969, Ser. No. 868,978

Int. Cl. B01d 3/06; C02b 1/06


U.S. Cl. 202-173

3 Claims




The shell of a multi-stage distilling plant, wherein pre-assembled sections, each containing a like series of evaporation stages, have mating openings in their respective side walls providing vapor communication between corresponding stages of sections. Peripheral edges of the openings in the sections and abutting edges of internal partitions and reinforcing members of the sections serve as joints. The joined sections provide a single large multi-stage plant. The method includes steps of fabricating the sections, aligning the fabricated sections, and welding the sections together to form a single large plant.

3,580,817
METHOD AND APPARATUS FOR THE CENTRIFUGAL DISTILLATION OF A LIQUID
 Nicholas Joseph Schnur, 704 St. Agnes Lane, West Mifflin, Pa. 15122
 Filed Feb. 25, 1969, Ser. No. 802,152
 Int. Cl. B01d 3/10
 U.S. Cl. 203—11 12 Claims



Centrifugal distillation of a liquid in a rotary sealed container maintained at a pressure substantially equal to the vapor pressure of the liquid to withdraw and cool the molecular vapor and centrifugally force it to the periphery barrier of the chamber by acceleration due to the centrifugal speed of the chamber and creating sufficient pressure on the molecular vapor to condense the same into the distilled liquid. The barrier retains the distilled liquid until a sufficient entrapped quantity is enabled to be discharged from the chamber as an additional quantity of the liquid is distilled thereby maintaining a continuous self-contained process while adding liquid by the relative pressure differential between the chamber and atmospheric pressure.


3,580,818
SEA WATER MULTISTAGE DISTILLATION PROCESS WITH COMMON REHEATING MEANS
 Rocco Catoggio de Villiers, Brooklyn Pretoria, Transvaal, Republic of South Africa, and Loic Blachez, Paris, Francois Jegou, Bourg-la-Reine, and Jean Huyghe and Paul Vignet, Grenoble, France, assignors to Commissariat a l'Energie Atomique, Paris, France
 Filed Mar. 11, 1969, Ser. No. 806,078
 Claims priority, application France, Mar. 18, 1968, 144,284
 Int. Cl. B01d 3/06
 U.S. Cl. 203—11 5 Claims



A method and installation for the distillation of a solution to be treated in a plurality of lines. In each line, the solution is reheated in the liquid state, then caused to expand in a series of stages at progressively decreasing pressures consisting of stages for recovery at higher pressure and stages for heat rejection at lower pressure, and the

vapor produced at each stage is caused to condense. Condensation is produced at least in the recovery stages by exchange with the feed solution as this latter is circulated from one stage to the next prior to reheating and in counterflow to the reheated solution. The feed solution of each line consists of the non-vaporized brine of the preceding line as completed by a make-up quantity of fresh solution. Reheating is carried out either at temperatures which decrease progressively from one line to the next as a function of the increase in the concentration of a salt having reverse solubility in the reheated solution or at temperatures which increase progressively from one line to the next as a function of the increase in the concentration of a salt having normal solubility in the reheated solution.

3,580,819
RECOVERY OF PROPYLENE AND PROPYLENE OXIDE BY SELECTIVE SEPARATION WITH PLURAL STAGE DISTILLATION, PROPYLENE OXIDE ABSORPTION AND SUBSEQUENT DISTILLATION
 Sadok E. Hoory, El Cerrito, Stanley F. Newman, San Francisco, and Robert E. Vincent, Lafayette, Calif., assignors to Shell Oil Company, New York, N.Y.
 Filed Apr. 21, 1969, Ser. No. 817,721
 Int. Cl. B01d 3/34; C07c
 U.S. Cl. 203—42 4 Claims




Propylene oxide and propylene are separately recovered, in a high state of purity, from a crude propylene oxide, produced by reaction of propylene with an organic hydroperoxide, and containing the propylene oxide in admixture with unconverted propylene, water and higher boiling oxygen-containing organic impurities, by subjecting the crude propylene oxide to a two stage distillation, in the first stage of which propylene is taken overhead under controlled conditions resulting in the wilfull retention of a substantial amount of the propylene in the distillation bottoms and in the second stage of which propylene oxide is taken overhead in admixture with propylene, and separating propylene oxide from the second stage distillation overhead by selective absorption in an aqueous solvent.

3,580,820
PALLADIUM-NICKEL ALLOY PLATING BATH
 Katsumi Yamamura, Suwa-shi, Tsugumitsu Miyasaka, Suwa-gun, Nagano-ken, Shinichi Hayashi, Tokyo, Masao Yamamoto, Koshigaya-shi, and Yukio Matsubara, Tokyo, Japan, assignors to Kabushiki Kaisha Suwa Seikosha and Nisshin Kasai Kabushiki Kaisha
 No Drawing. Filed Jan. 4, 1968, Ser. No. 695,576
 Claims priority, application Japan, Jan. 11, 1967, 42/1,868
 Int. Cl. C23b 5/32, 5/46
 U.S. Cl. 204—43 5 Claims

A palladium-nickel alloy plating bath is formed of a solution of palladium salt and a nickel salt in ammonia and a brightener in the nature of a sulfonate or a sulfonamide is added to the bath in which a metal is plated for approximately 30 minutes at a pH in the range of 7.5, temperature in the range of 30° C., and cathode current density in the range of 1 a./dm.² without agitation.


3,580,821
BRIGHT SILVER ELECTROPLATING
 Hans-Gunther Todt and Wolfgang Dahms, Berlin, Germany, assignors to Schering A.G., Berlin, Germany
 No Drawing. Filed June 24, 1969, Ser. No. 838,040
 Claims priority, application Germany, June 27, 1968, P 17 71 699.3
 Int. Cl. C23b 5/26, 5/46
 U.S. Cl. 204—46 5 Claims

Fully bright silver electrodeposits are obtained from otherwise conventional cyanide-type silver plating electrolytes in the presence of small amounts of acids of the formula



and of their soluble salts, in the formula R being lower alkoxy or NHR'; R' being hydrogen, lower alkyl, phenyl, halophenyl, lower alkyl phenyl, or lower alkoxy phenyl; R' being hydrogen or lower alkyl; and X being oxygen, sulfur, or imino, but R being different from amino when X is sulfur.

3,580,822
METHOD FOR PRODUCING A CHROMIUM ACTIVATED ALUMINUM OXIDE SCINTILLATOR
 Robert W. Allison, Jr., Richmond, Robert W. Brokloff, Vallejo, and John R. Woodyard, Berkeley, Calif., assignors to the United States Atomic Energy Commission
 Filed July 7, 1969, Ser. No. 839,510
 Int. Cl. C23b 9/02
 U.S. Cl. 204—58 7 Claims




A radiation resistant chromium activated aluminum oxide scintillator produced by immersing an aluminum anode and lead cathode in an anodic bath and gradually increasing an applied potential until bright flashes or "anodic scintillation" occurs whereby Cr ions from the solution are injected into the Al₂O₃ base lattice. The scintillators produced by this process may be readily utilized to visually aid in the control and transport of high intensity beams without radiation damage thereto.

3,580,823
HYDROGEN PRODUCTION
 Harold Shalit, Drexel Hill, Pa., assignor to Atlantic Richfield Company, Philadelphia, Pa.
 Filed Mar. 17, 1969, Ser. No. 807,864
 Int. Cl. B01k 1/00
 U.S. Cl. 204—60 7 Claims

An improved process and apparatus for the production of hydrogen of high purity whereby a carbonaceous fuel is reformed to produce hydrogen and said hydrogen is

recovered economically from said reforming operation through the use of an electrolytic process using chemical



energy of the reforming process to reduce electrical energy needed and in a molten electrolyte environment.

3,580,824
IMPREGNATED GRAPHITE
 John E. Currey, Morris P. Grotheer, and Edward H. Cook, Jr., Lewiston, N.Y., assignors to Hooker Chemical Corporation, Niagara Falls, N.Y.
 No Drawing. Filed Dec. 31, 1968, Ser. No. 789,008
 Int. Cl. B01k 1/00; C01b 11/26
 U.S. Cl. 204—95 11 Claims

Graphite impregnated with iron in an amount between about 0.05 to about 3 percent by weight affords an excellent electrode material for the electrolysis of alkali metal halides. Electrode over voltage is decreased and electrode life is prolonged by iron deposition in comparison to conventional graphite electrodes.

3,580,825
ELECTROLYTIC PROCESS FOR PURIFYING IRON DISSOLVED FROM SCRAP STEEL
 Stanley Hills, Cherry Hill, N.J., assignor to ESB Incorporated
 No Drawing. Filed Oct. 28, 1968, Ser. No. 771,319
 Int. Cl. C22d 1/24
 U.S. Cl. 204—112 4 Claims

Iron sufficiently free of manganese impurities to be useful as active material in electrochemical cells is obtained in a continuous process by dissolving scrap steel containing an unacceptably high manganese content and subsequently plating out the iron but not much of the manganese. The pH of the electrolytic bath is maintained so the H₂ evolution will occur after iron deposition but before manganese deposition. The preferred conditions for the electrolytic bath are: a pH range from about 2.5 to about 3.0; a current density range from about 0.1 to about 0.25 amp/sq. in.; a ferrous ion concentration range from about 25 to about 40 gr./l.; and a supporting electrolyte concentration range from about 1/2 to about 1 mole/l.

3,580,826
ELECTROLYTIC DECOLORING OF FERTILIZER SOLUTIONS
 Donald L. Whitfill, Ponca City, Okla., assignor to Continental Oil Company, Ponca City, Okla.
 No Drawing. Filed Feb. 24, 1969, Ser. No. 801,829
 Int. Cl. B01k 1/00
 U.S. Cl. 204—131 8 Claims

Oxidizable impurities in fertilizer solutions are removed by addition of a soluble chloride followed by in situ electrochemical generation of chlorine.

3,580,827

ETCHING METHOD AND APPARATUS

Jean-Paul Lannegrace, Neuilly-sur-Seine, France, assignor to Imprimerie Chaix-Desfosses-Neogravure, Paris, France

Filed July 23, 1968, Ser. No. 746,915

Claims priority, application France, July 27, 1967, 115,993

Int. Cl. B23p 1/00

U.S. Cl. 204—143

2 Claims

To etch an electrically conducting metal surface, this surface is attacked with a liquid mordant through a photographically treated resist which is semi-permeable to the mordant, while varying the composition of the mordant such that the etching rate tends to lag slightly behind the ideal theoretical rate, this lag being compensated by applying to the surface a positive electrical potential with respect to the mordant.

3,580,828

ELECTRODEPOSITION OF LITHIUM

Thomas Bradley Reddy, Pound Ridge, N.Y., assignor to American Cyanamid Company, Stamford, Conn.

No Drawing. Filed Dec. 16, 1968, Ser. No. 784,202

Int. Cl. C23b 5/00

U.S. Cl. 204—14

9 Claims

Cohesive, dense deposits of lithium having a specular appearance are obtained by electrodeposition from anhydrous electrolyte of lithium salt in organic solvent. Electrolyte concentration is 0.05 to 0.20 mole lithium salt per liter and current density is 0.05 to 0.25 milliamperes per square centimeter.

3,580,829

PROCESS FOR IRRADIATING POLYVINYLIDENE FLUORIDE AND A COMPATIBLE POLYFUNCTIONAL MONOMER AND PRODUCT THEREOF

Vincent L. Lanza, Atherton, Calif., assignor to Raychem Corporation, Menlo Park, Calif.

No Drawing. Continuation-in-part of applications Ser. No. 257,763, Feb. 11, 1963, and Ser. No. 403,328, Oct. 12, 1964. This application Mar. 1, 1968, Ser. No. 709,804

Int. Cl. C08d 1/00; C08f 15/00, 19/00

U.S. Cl. 204—159.17

24 Claims

A composition comprising polyvinylidene fluoride and a compatible polyfunctional monomer may be treated with low doses of irradiation to provide a crosslinked polyvinylidene fluoride having excellent strength properties, resistance to heat aging and the property of elastic memory.

3,580,830

PREPARATION OF XANTHATE TERMINATED POLYMERS

Alan R. Siebert, Maple Heights, Ohio, assignor to The B. F. Goodrich Company, New York, N.Y.

No Drawing. Filed Sept. 5, 1968, Ser. No. 757,785

Int. Cl. C08d 1/00; C08f 1/16

U.S. Cl. 204—159.24

2 Claims

Xanthate terminated polyesters are known intermediates in the preparation of mercaptan terminated olefin polymers and copolymers. An improved process for the preparation of these intermediates involves the reaction of olefin monomer(s) with a xanthogen disulfide in the presence of a particular range of high energy radiation. The disulfide acts both as a source of free radicals and also as a polymerization modifier.

3,580,831

PHOTOCHLORINATION OF MONO- AND DI-CHLOROETHANE

Michael J. Mintz, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

No Drawing. Filed Jan. 13, 1969, Ser. No. 790,848

Int. Cl. B01j 1/10; C07c 17/00

U.S. Cl. 204—163

4 Claims

In the process for preparing compounds of the formula $\text{CH}_3\text{CCl}_2\text{X}$, wherein X is H or Cl, said process comprising reacting by contacting in the liquid phase, at a temperature of 0 to 50° C. in the presence of actinic light, a compound of the formula CH_3CHClX , wherein X is H or Cl, with Cl_2 , the improvement of carrying out said reaction in the presence of a catalytic amount of I_2 .

3,580,832

ELECTROLYTIC COULOMETER TITRATION SYSTEM


David R. Rhodes, Novato, Calif., assignor to Chevron Research Company, San Francisco, Calif.

Filed Feb. 13, 1968, Ser. No. 705,179

Int. Cl. G01n 27/44

U.S. Cl. 204—195

2 Claims



The presence and concentration of a constituent within either a continuous or discontinuous flowing sample, is determined by means of a coulometer titration system including (i) a titration cell containing hydrogen saturated electrolyte, subject to pressure variations, for absorbing the constituent, or a quantitatively related component thereof, to thereby change the hydrogen ion concentration (pH) of the electrolyte from a predetermined pH set point level, (ii) potential developing electrodes disposed in the electrolyte for sensing said change in hydrogen ion concentration from said set point level by means of a voltage produced therebetween, (iii) a pair of generating electrodes for electrolytically producing, in the electrolyte, in response to said voltage just enough of a component reactable with the constituent being analyzed for, or component thereof, to neutralize the constituent or component thereof, to return said hydrogen ion concentration to its predetermined set point level, and (iv) recording means maintaining a continuous record of the component reactable with the said constituent, or component thereof, so as to indicate the presence and concentration thereof within the titration cell. The present invention contemplates the use of first and second potential electrodes including an improved hydrogen-dissolved-in-palladium sensing electrode adapted, in combination, with a reference electrode to extend the response range of the system to detect low concentrations of the constituent being analyzed for, or component thereof, by dampening the rate of change, with time, of a potential developed between the improved sensing electrode and the reference electrode due to changes in hydrogen partial pressure at the surface of the improved sensing electrode. Preferably, the improved sensing electrode has a hydrogen-palladium (H/Pd) atomic ratio greater than 0.03 and up to and including about .60.

3,580,833

MERCURY CELL HAVING ROTATING ANODE

Roy M. Cooper, Groton, Conn., assignor to


Olin Mathieson Chemical Corporation

Filed Apr. 30, 1969, Ser. No. 820,459

Int. Cl. C23b 5/68; C01d 1/08

U.S. Cl. 204—212

8 Claims



A new rotary anode, mercury cathode electrolytic cell for the manufacture of chlorine and caustic alkalis from aqueous alkali metal chloride brines provides the advantages of high current density, high current efficiency, low floor space and low cost per ton of product.

3,580,834

APPARATUS FOR MACHINING METALS ELECTROCHEMICALLY


Robert K. Sedgwick, Waukesha, Wis., assignor to Kearney & Trecker Corporation, West Allis, Wis.

Filed Dec. 4, 1967, Ser. No. 687,776

Int. Cl. B23p 1/02

U.S. Cl. 204—224

3 Claims



An apparatus for the electrochemical machining of flat metal surfaces which utilizes a pool of viscous electrolyte of sufficient viscosity to support a workpiece and space the workpiece very slightly from the surface plate, as well as to facilitate movement of the workpiece over the surface plate. Movement of the workpiece in combination with various viscosities of the viscous electrolyte are utilized to obtain the degree of flatness desired.

3,580,835

ELECTROLYTIC REDUCTION CELL

John R. Peterson, Oakland, Calif., assignor to Kaiser Aluminum & Chemical Corporation, Oakland, Calif.

Filed Feb. 24, 1969, Ser. No. 801,454


Int. Cl. C22d 3/02, 3/08

U.S. Cl. 204—243

23 Claims

Improved electrolytic reduction cell for producing molten magnesium metal and the like and made up of uniquely and removably arranged outer and inner shells

having a mass of thermally resistant material interposed therebetween and wherein the interior of the cell is di-



vided in an improved fashion into feed and electrolytic chambers.

3,580,836

TREATMENT SYSTEM WITH COOLING MEANS

Arthur S. King, 1710 Baltimore,


Prairie Village, Kans. 64105

Continuation-in-part of application Ser. No. 727,835, May 9, 1968. This application Apr. 8, 1969, Ser. No. 814,279

Int. Cl. B01d 13/02

U.S. Cl. 204—308

12 Claims



A fluid is subjected to an electrostatic field between an inner and an outer electrode. By use of a cooling system through the inner electrode, a dielectric on the inner electrode is protected against the deleterious effects of the treated fluid when the latter is heated.

3,580,837

HYDROREFINING OF COKE-FORMING HYDROCARBON DISTILLATES

Ernest L. Pollitzer, Skokie, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.

No Drawing. Filed Apr. 7, 1969, Ser. No. 814,173

Int. Cl. C10g 23/00

U.S. Cl. 208—57

7 Claims

A process for hydrorefining sulfurous hydrocarbon distillates containing mono-olefinic, di-olefinic and aromat-

ic hydrocarbons. Through the use of particular catalytic composites containing metallic components from Group VII-B, having an atomic number greater than 25, and the noble metals of Group VIII, increased selectivity and stability of operation is attained. The selectivity is most noticeable with respect to the retention of aromatics, and in hydrogenating conjugated di-olefinic and mono-olefinic hydrocarbons.

3,580,838

HYDROCARBON PYROLYSIS PROCESS


Irvin H. Lutz, Dallas, Tex., assignor to The Lummus Company, Bloomfield, N.J.

Filed Feb. 24, 1969, Ser. No. 801,649

Int. Cl. C10g 9/14, 9/16

U.S. Cl. 208—100

8 Claims



Improved process for cracking a hydrocarbon feed in a pyrolysis furnace wherein the sensible heat of the effluent is employed to fractionate a fuel oil into a distillate and residual fraction. A fuel oil is added to the pyrolysis effluent, along with recovered quench oil, to effect quenching thereof and the mixture introduced into a gasoline fractionator to recover a distillate sidestream. The distillate sidestream, containing distillate fractions from both the effluent and residual fuel, may be employed to meet fuel requirements for the pyrolysis furnace. In addition, the residual recovered as fractionator bottoms is employed to provide quench oil and meet other fuel requirements for the pyrolysis plant or an extraneous operation.

3,580,839

RECOVERY OF AROMATIC HYDROCARBONS FROM MIXTURES OF HYDROCARBONS BY SELECTIVE EXTRACTION WITH A SUBSTITUTED PIPERAZINE SOLVENT

Ernst Fuerst, Neustadt, and Hans-Martin Weitz, Frankfurt, Germany, assignors to Badische Anilin- & Soda-Fabrik Aktiengesellschaft, Ludwigshafen (Rhine), Germany

No Drawing. Filed Dec. 19, 1968, Ser. No. 785,368


Claims priority, application Germany, Dec. 30, 1967, P 16 45 709.3

Int. Cl. C10g 21/20

U.S. Cl. 208—326

8 Claims

Recovery of aromatic hydrocarbons from mixtures of hydrocarbons which contain paraffins and possibly olefins and/or naphthenes by using as extractants piperazine derivatives having the general formula:



where X denotes formyl or acetyl and R denotes lower alkyl.

3,580,840
PROCESS FOR TREATING SEWAGE AND OTHER CONTAMINATED WATERS


Joseph E. Uridil, St. Paul, Minn., assignor to Litton Systems, Inc., Beverly Hills, Calif.

Filed Mar. 18, 1969, Ser. No. 808,267

Int. Cl. C02c 1/02

U.S. Cl. 210—11

9 Claims



Sewage and other chemically impure waters are made cleaner by a process which involves the removal or extraction from the water of various contaminants by the controlled growth of selected microorganisms using the sewage or other impure water as the basic growth substrate. The microorganisms (both as the inoculant and as the growth product) are isolated from the sewage or other contaminated water by means of a porous membrane or barrier of restricted pore size (e.g. 0.8–2 microns). These pores are large enough to permit molecules of the contaminants to pass through or penetrate the porous barrier to thereby contact and be acted upon or assimilated by the microorganisms. These pores are small enough to prevent the large scale escape or mass migration of the microorganisms through the membrane into the contaminated water. As a result of the process, one or more contaminants in the waste water are consumed in the microbial metabolism or growth process, thereby making the water cleaner.

3,580,841

ULTRATHIN SEMIPERMEABLE MEMBRANE

John E. Cadotte, Roseville, and Peter S. Francis, Edina, Minn., assignors to the United States of America as represented by the Secretary of the Interior

No Drawing. Original application Jan. 31, 1967, Ser. No. 613,054. Divided and this application July 31, 1969, Ser. No. 856,516

Int. Cl. B01d 13/00, 31/00

U.S. Cl. 210—23

17 Claims

An ultrathin semipermeable reverse osmosis membrane which may be made by casting a concentrated polymer solution on a liquid surface and then evaporating, and which may be laminated with a separate porous support membrane to form a composite reverse osmosis membrane. A process of separating solvent from solution by reverse osmosis comprising bringing that solution into contact with a membrane comprising a semipermeable ultrathin membrane at a pressure above the osmotic pressure.

3,580,842

DOWNFLOW ION EXCHANGE

Irwin R. Higgins, Oak Ridge, Tenn., assignor to Chemical Separation Corporation, Oak Ridge, Tenn.

Filed Apr. 8, 1968, Ser. No. 719,389


Int. Cl. B01d 15/02, 15/06; C02b 1/16

U.S. Cl. 210—25

11 Claims

A continuous cyclic process for countercurrent contact of a contaminant containing liquid with a solid in a

column loop which includes introducing the contaminant containing liquid into the upper portion of one section of the column loop for downward flow through the solids bed therein to transfer or load the contaminant onto the solids. The section is positioned adjacent the upper end of the column loop. Liquid with a reduced amount of



contaminant is withdrawn from the lower portion of this section. A regenerating agent is fed to the lower portion of another section of the column loop for flow through a bed of solids loaded with the contaminant. The flow of liquid and regenerating agent are interrupted and the solids bed is shifted around the loop and the loading and regenerating cycles are then repeated.

3,580,843

CHROMATOGRAPHIC MEDIUM AND METHOD


Ival O. Salyer, Dayton, Robert T. Jefferson, West Carrollton, and William D. Ross, Eaton, Ohio, assignors to Monsanto Research Corporation, St. Louis, Mo.

Filed July 27, 1970, Ser. No. 58,382

Int. Cl. B01d 15/08

U.S. Cl. 210—31

13 Claims



An improvement in a chromatographic column in which the chromatographic medium or support is an open-pore polyurethane structure filling the column wall-to-wall; the process for filling the column with a homogeneous precursor solution; and the process for using the column to separate organic compounds such as hydrocarbons and metal derivatives of diketones.

3,580,844
METHOD OF PROCESSING OIL EMULSIONS USED IN METAL MACHINING

Helmut Fratzscher, Gross-Auheim, Kurt Klein, Langen, Hessen, Joachim Maluzi, Gross-Auheim, and Peter Hansen and Werner Schmitz, Wolfgang B. Hanau am Main, Germany, assignors to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler, Frankfurt am Main, Germany

No Drawing. Continuation-in-part of application Ser. No. 654,990, July 21, 1967. This application Nov. 4, 1969, Ser. No. 874,035

Claims priority, application Germany, July 22, 1966, D 50,648; Jan. 19, 1967, D 52,051

Int. Cl. B01d 15/00

U.S. Cl. 210—40

3 Claims

Aqueous oil emulsions used in metal machining are separated into an aqueous phase and an oily phase by adding a mixture of a formate or acetate of an alkaline earth metal, earth metal, cadmium or zinc to the emulsion to break the emulsion with a finely divided absorbent and adsorb the separating oil, thereby converting the oil to a filterable form and filtering it off.

3,580,845

ACID CONTAINING ELECTROLYTIC LIQUID FOR AN ELECTROLYTIC CAPACITOR

Hildegard Dahle, Herborn, Germany, assignor to U.S. Phillips Corporation, New York, N.Y.

No Drawing. Filed Aug. 22, 1969, Ser. No. 852,449

Claims priority, application Germany, Aug. 22, 1968, P 17 64 869.0

Int. Cl. H01g 9/00

U.S. Cl. 252—62.2

4 Claims

The invention relates to a low-resistive electrolyte liquid for an electrolytic capacitor which liquid consists of a mixture of a multivalent alcohol in water as a solvent, a basic nitrogen compound, two inorganic acids and one organic acid and/or reaction products of these acids or of the nitrogen compound.

3,580,846

FERROELECTRIC CERAMIC MATERIALS

Chiyoichi Okuyama, 2-14 Nishiki-cho, and Syuzo Osumi, 1-15 Hikari-cho, both of Fujinomiya-shi, Shizuoka-ken, Japan

Filed Nov. 10, 1969, Ser. No. 875,368

Int. Cl. C04b 35/46, 35/48

U.S. Cl. 252—62.9

4 Claims

Ferroelectric ceramic materials having essentially the composition $\text{Pb}(\text{Zr-Ti})\text{O}_3$ or $\text{Pb}(\text{Zr-Ti-Sn})\text{O}_3$ and containing Bi and Nb in small percentage exhibit improved coupling coefficients. As modifications, the materials may also contain Mn in small percentage and part of the Pb may be replaced by Ba, Sr or both. The materials are particularly useful as ceramic wave filters and piezoelectric voltage sources.

ERRATUM

For Class 252—71 see:
Patent No. 3,580,759

3,580,847

HYDRAULIC FLUID

Matthew A. Boehmer, Allen Park, and Jerrold F. Maxwell, Trenton, Mich. (both % Wyandotte Chemicals Corp., Wyandotte, Mich. 48192)

No Drawing. Filed June 16, 1967, Ser. No. 646,498

Int. Cl. C09k 3/00

U.S. Cl. 252—75

7 Claims

A two-phase hydraulic fluid composition which comprises (A) a conventional aqueous hydraulic fluid base as a first phase and (B) a liquid having a specific gravity less than that of the aqueous hydraulic fluid base (A) as

a second phase which liquid (B) is immiscible with base (A) and forms a supernatant layer floating on the surface of the aqueous base (A).

3,580,848

FUNCTIONAL FLUIDS CONTAINING CARBON DIOXIDE FOR PREVENTING CAVITATION DAMAGE

Neal W. Furby, Berkeley, Douglas Godfrey, San Rafael, and Robert L. Peeler, Albany, Calif., assignors to Chevron Research Company, San Francisco, Calif.
No Drawing. Filed Dec. 18, 1967, Ser. No. 691,150
Int. Cl. C09k 3/00; C10m 3/40; C23f 11/18

U.S. Cl. 252-78

8 Claims

Functional fluid containing a minor amount of carbon dioxide as a cavitation damage-inhibiting additive.


3,580,849

LUBRICANT


Peter Geymayer and Siegfried Billenstein, Burgkirchen (Alz), and Werner Renz, Burghausen, Salzach, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
Filed Sept. 2, 1969, Ser. No. 854,599
Claims priority, application Germany, Sept. 5, 1968, P 17 94 094.2

Int. Cl. C09k 3/00; C10m 3/42; C07f 9/50
U.S. Cl. 252-78

2 Claims



Lubricants are described for hydraulic fluids which do not consist of mineral oil and contain minor or major proportions of water. Such lubricants are compounds corresponding to the general formula



in which X stands for S or O, R is CH₃ or H and n has the meaning 0-5/3. The compounds are, thus, tris-(hydroxymethyl)-phosphine oxide or sulfide and the oxalkylation products thereof which contain up to 5 ethylene oxide or propylene oxide units per molecule. Practically technical grade oxalkylation products are used which contain an average of 0 to 5 moles of alkylene oxide per mole, and consequently n may stand for any value within the defined limits.

3,580,850

STABILIZED NONIONIC SURFACTANTS IN SOLID FORMULATIONS CONTAINING ACTIVE CHLORINE COMPOUNDS

Jean Dupre, Levittown, Pa., assignor to Rohm and Haas Company, Philadelphia, Pa.
No Drawing. Filed July 17, 1967, Ser. No. 653,674

Int. Cl. C11d 7/56
U.S. Cl. 252-99

2 Claims

A solid built detergent formulation consisting of a low foaming nonionic surfactant containing a minor amount of an antioxidant, an active chlorine agent, and an alka-

line builder, the antioxidant serving to stabilize the surfactant against degradation caused by the oxidative or other aggressive effects of the chlorine.


3,580,851

STABLE ALKALI CHLORITE MIXTURES


Christian Heid and Karl-Heinz Keil, Frankfurt am Main-Fechenheim, Germany, assignors to Cassella Farbwerke Mainkur Aktiengesellschaft, Frankfurt am Main-Fechenheim, Germany
No Drawing. Filed July 29, 1969, Ser. No. 845,883
Claims priority, application Switzerland, Aug. 6, 1968, 11,744/68

Int. Cl. D06l 3/06
U.S. Cl. 252-99

6 Claims
Stable aqueous mixtures of alkali chlorite containing a compound of the formula



or alkali metal salts thereof wherein R is —C_nH_{2n+1} or



n is 6 to 18;
x is 6 to 30;
y is 0 or 1; and
R₁ is hydrogen or methyl.

3,580,852

DETERGENT FORMULATIONS CONTAINING TETRAHYDROFURAN 2,3,4,5 - TETRACARBOXYLIC ACID SALTS AS BUILDERS

Meiling T. Yang, Baton Rouge, La., assignor to Ethyl Corporation, New York, N.Y.
No Drawing. Filed May 19, 1969, Ser. No. 825,983
Int. Cl. C11d 3/20, 7/26

U.S. Cl. 252-135
10 Claims
To obviate eutrophication of water, non-phosphorus detergent builders are provided. These are the water-soluble salts of tetrahydrofuran 2,3,4,5-tetracarboxylic acid (e.g., the tetrasodium salt thereof). Conventional detergent actives may be used with these builders.

3,580,853

DETERGENT COMPOSITIONS CONTAINING PARTICLE DEPOSITION ENHANCING AGENTS

John J. Parran, Jr., Springfield Township, Hamilton County, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio
No Drawing. Filed Sept. 27, 1967, Ser. No. 671,117
Int. Cl. C11d 3/22, 3/48

U.S. Cl. 252-152
10 Claims

Detergent compositions containing water-insoluble particulate substances, such as antimicrobial agents, and certain cationic polymers which serve to enhance the deposition and retention of such particulate substances on surfaces washed with the detergent composition.

3,580,854

SEQUESTERING AGENTS FOR METAL ION CONTAMINATION IN SIDE-CHAIN HALOGENATION OF ALKYL-AROMATIC HYDROCARBONS COMPRISING PHOSPHOROUS HALIDE AND ORGANIC PHOSPHATE

Ralph H. Lasco, Painesville, Ohio, assignor to Diamond Alkali Company, Cleveland, Ohio
No Drawing. Filed June 29, 1966, Ser. No. 561,340
Int. Cl. B01j 1/10; C07c 17/14, 25/14

U.S. Cl. 252-181

1 Claim
Metal ion contaminated, alkyl-aromatic hydrocarbons such as p-xylene contaminated with a trace amount of iron, are successfully side-chain halogenated by employ-

ing during halogenation a synergistic mixture of sequestering agent for such contamination. This mixture contains a phosphorus halide plus an organic phosphate. Even visibly contaminated hydrocarbons can be successfully side-chain halogenated. The organic phosphate is provided by an aryl phosphate, an alkyl phosphate, or their mixtures.

3,580,855

PROCESS FOR INHIBITION OF SCALE AND CORROSION USING A POLYFUNCTIONAL PHOSPHATED POLYOL ESTER HAVING AT LEAST 75% PRIMARY PHOSPHATE ESTER GROUPS

James C. Mickus, Bloomington, Minn., David B. Fordyce, Moorestown, N.J., and Richard C. Mansfield, Warminster, Pa., assignors to Rohm and Haas Company, Philadelphia, Pa.
No Drawing. Continuation-in-part of application Ser. No. 576,252, Aug. 31, 1966. This application Apr. 9, 1969, Ser. No. 814,818

Int. Cl. C02b 5/06; C07f 9/08
U.S. Cl. 252-181

6 Claims
The invention is concerned with methods for maintaining an effective corrosion-inhibiting environment in aqueous systems, for preventing precipitation of Fe(II) from such systems, and for dispersing water-insoluble solids in aqueous suspension, said methods involving the treatment of the water systems with small amounts of a specific polyfunctional phosphated polyol ester characterized in that the ester has at least about 75% primary phosphate ester groups.

3,580,856

GETTER COMPOSITION FOR ELECTRIC LAMPS AND SIMILAR DEVICES

Edward G. Zubler, Chagrin Falls, Ohio, assignor to General Electric Company
Filed May 22, 1969, Ser. No. 826,888
Int. Cl. H01j 7/18; H01k 1/56

U.S. Cl. 252-181.6

2 Claims
The rate and extent (to about 100%) of thermal decomposition of P₃N₅ getter are increased by providing a catalyzer metal in contact with the solid P₃N₅ or its primary gaseous decomposition products.

3,580,857

STABLE LIQUID DICARBOXYLIC ACID ANHYDRIDE COMPOSITION

Chao-Shing Cheng, Williamsville, and Francis E. Evans, Hamburg, N.Y., assignors to Allied Chemical Corporation, New York, N.Y.
No Drawing. Filed Feb. 8, 1968, Ser. No. 703,866
Int. Cl. C07c 63/00; C08f 45/60

U.S. Cl. 252-182

20 Claims
Production of stable liquid organic carboxylic anhydrides by adding to an unstable liquid anhydride a freezethaw stabilizing amount of an organic isocyanate or carbodimide; if desired, the resultant liquid anhydride may be purified by subjecting the same to distillation to recover, as distillate, a pure anhydride which may be stored for extended periods without deposition of solids.

3,580,858

STABLE LIQUID ANHYDRIDE COMPOSITIONS

Francis E. Evans, Hamburg, and Chao-Shing Cheng, Williamsville, N.Y., assignors to Allied Chemical Corporation, New York, N.Y.
No Drawing. Filed Feb. 8, 1968, Ser. No. 703,902
Int. Cl. C07c 63/00; C08f 45/58

U.S. Cl. 252-182

17 Claims
Novel liquid cyclic polycarboxylic acid anhydride mixtures which are stabilized against deposition of solids by incorporation of a small amount of at least one polyether polyol of more than 12 carbon atoms.

3,580,859

ACTIVE MATERIAL FOR LASERS

Igor Mikhailovich Buzhinsky, Pervomaiskaya ul. 5, kv. 46, Moskovskaya Obl., Lytkarino, U.S.S.R.; and Mark Efremovich Zhabotinsky, Pogodinskaya ul. 2/3, kv. 53; Jury Petrovich Rudnitsky, Babushkin, Troitsky per. 43, kv. 65; Vadim Vasilievich Tsapkin and Irma Vyacheslavovna Tsapkina, both of Tatarskaya ul. 9-a, kv. 13; and Georgy Vladimirovich Ellert, Ul. Garibaldi 19, korp. 2, kv. 53, all of Moscow, U.S.S.R.
Filed Dec. 20, 1967, Ser. No. 692,179
Int. Cl. C09k 1/04; C03c 3/28

U.S. Cl. 252-301.1

5 Claims
Laser glasses consisting of 30-90 wt. percent of P₂O₅; 2-40 wt. percent of each of Na₂O and Li₂O; 1-6 wt. percent Nd₂O₃ and additives of aluminum oxides or halides, halides of tin and ions of Cu, Mn, Cr, U and Ag; the total amount of said additives being not more than 20 wt. percent.

3,580,860

INFRARED-EXCITABLE ALKALINE EARTH THORIUM FLUORIDE LUMINESCENT MATERIALS

James F. Sarver, Lyndhurst, and Ralph A. Hewes, Cleveland Heights, Ohio, assignors to General Electric Company
Filed May 2, 1969, Ser. No. 831,807
Int. Cl. C09k 1/06

U.S. Cl. 252-301.1

13 Claims
The invention relates to alkaline earth thorium fluoride materials activated with ytterbium and erbium. The materials respond to infrared excitation and produce visible light.

3,580,861

METHOD OF PREPARING RARE-EARTH METAL ORTHOVANADATE PHOSPHORS BY PRECIPITATION

Richard C. Ropp, Warren, N.J., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.
No Drawing. Filed Mar. 18, 1969, Ser. No. 808,320
Int. Cl. C09k 1/44

U.S. Cl. 252-301.4R

13 Claims
An improved method of precipitating rare-earth metal orthovanadate phosphor from aqueous solution. The constituents are dissolved in acid solution, with vanadium pentoxide being dissolved in hydrochloric acid to provide a high concentration of vanadyl radical in solution. Predetermined amounts of ammonium hydroxide and hydrogen peroxide are admixed with the rare-earth metal and vanadium containing acid solutions so that the pH of the resulting mixture is determined to provide a condition under which rare-earth metal orthovanadate is very efficiently precipitated. The precipitant is calcined to provide an activated, efficient rare-earth metal orthovanadate phosphor.

3,580,862

CONTINUOUS PROCESS FOR PREPARING ALKALI METAL DISPERSIONS AND APPARATUS

Lloyd M. Watson and William R. Birchall, Cincinnati, Ohio, assignors to National Distillers and Chemical Corporation, New York, N.Y.
Continuation-in-part of application Ser. No. 302,038, Aug. 14, 1963. This application Aug. 18, 1967, Ser. No. 667,023

Int. Cl. B01j 13/00
U.S. Cl. 252-309

12 Claims
A process for preparing continuously a dispersion in an inert organic diluent of a finely-divided alkali metal, such as sodium, substantially uniform in particle size and alkali metal concentration is provided wherein a molten alkali metal is dispersed in an inert organic diluent with a dispersing aid which is soluble in the inert diluent, and if necessary, a stabilizing agent, by subjecting the molten alkali metal to high shear forces, and forming alkali metal

particles less than and greater than a predetermined median. The coarse particles of molten alkali metal at or above the median size are allowed to settle out, and the supernatant fine particles of molten alkali metal at or below the median size are drawn off. The coarse particles are continuously returned to the zone of high shear to further reduce their size, and alkali metal is continuously added to the zone, while the dispersion of fine particles of alkali metal having a size at or below the median, and substantially uniform in alkali metal concentration is continuously withdrawn.

3,580,863


LATHER MACHINE

Albert B. Campbell, Glenn Ellyn, Ill., assignor to Royal Products Company, Bensenville, Ill.
Continuation-in-part of application Ser. No. 729,577, May 16, 1968. This application Aug. 22, 1968, Ser. No. 755,520

Int. Cl. B01f 7/08

U.S. Cl. 252—359

9 Claims



A compact, parallel, direct delivery type lather machine having a one-piece housing with compartments for a liquid soap reservoir and the lather forming components. The machine includes a lather guard having a first portion flush with the lower edge of the lather outlet, and a convex, extension-like portion depending below and on each side of the lather outlet to keep the operator's hand from blocking the outlet. An improved liquid soap valve has an O-ring seal readily replaceable by snapping the O-ring on the end of the valve stem. An improved one-piece frame member for lather machines which includes a heating chamber surrounding the whipping chamber, a liquid soap inlet at one end of the member, a lather outlet at the other end of the member, and the heating chamber being sealed at the liquid soap inlet end of the member with the other end of the heating chamber being open for insertion of the heating elements.

ERRATUM

For Class 252—389 see:
Patent No. 3,580,934

3,580,864

CHOLESTERIC-PHASE LIQUID-CRYSTAL COMPOSITIONS STABILIZED AGAINST TRUE-SOLID FORMATION, USING CHOLESTERYL ERUCYL CARBONATE

Newton N. Goldberg, Pittsburgh, Pa., and James L. Ferguson, Kent, Ohio, assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.
No Drawing. Filed Apr. 30, 1969, Ser. No. 820,658

Int. Cl. C07c 69/76; C09k 3/04

U.S. Cl. 252—408

8 Claims

Stability of cholesteric-phase liquid-crystal compositions is improved by incorporating therein an amount, up to

100%, of cholesteryl erucyl carbonate, a novel compound, made by reaction of cholesteryl chloroformate with erucyl alcohol and pyridine. The novel carbonate does not crystallize to true solid in several months, whereas most other liquid-crystal compositions transform to true solid within several hours to several days. Moreover, the novel carbonate does itself exhibit a color play, so that it may be used in very large amounts in cholesteric-phase liquid-crystal compositions, without decreasing the vividness of the color changes exhibited thereby.

3,580,865

STABILIZATION OF CHOLESTERIC-PHASE LIQUID CRYSTAL COMPOSITIONS AGAINST TRUE SOLID FORMATION, USING CHOLESTERYL p-NONYLPHENYL CARBONATE

Newton N. Goldberg, Pittsburgh, Pa., assignor to Westinghouse Electric Corporation, Pittsburgh, Pa.
No Drawing. Filed Apr. 30, 1969, Ser. No. 820,659

Int. Cl. C07c 69/76; C09k 3/04

U.S. Cl. 252—408

10 Claims

Stability of cholesteric-phase liquid-crystal compositions is improved by incorporating therein cholesteryl p-nonylphenyl carbonate, a new compound, made by reaction of cholesteryl chloroformate with p-nonylphenol and pyridine. The p-nonylphenyl carbonate does not crystallize to true solid in three years, but the corresponding p-octylphenyl carbonate starts crystallizing to true solid in three weeks.

3,580,866

PROCESS FOR PRODUCING HIGH MOLECULAR WEIGHT POLYMERS OF ALKYLENE OXIDES

Teruhiko Ito, Naoshi Mitsui, Seiichi Maeda, and Takeshi Kato, Kakogawa-shi, Japan, assignors to Seitetsu Kagaku Co., Ltd., Hyogo-ken, Japan

No Drawing. Filed Oct. 27, 1967, Ser. No. 678,516

Int. Cl. C08f 7/12

U.S. Cl. 260—2

41 Claims

A process for producing a high molecular weight polymer of an alkylene oxide which comprises contacting an alkylene oxide with a novel catalyst at a temperature of from -50°C. to $+150^{\circ}\text{C.}$, said catalyst being prepared by partially hydrolyzing an aluminum alkoxide with water in an amount of 0.01 to 2.8 moles per mole of the alkoxide in a liquid, inert medium and mixing the resulting partial hydrolyzate with an organo-metallic compound of a metal of Group II or III of the Periodic Table in an amount of 0.001 to 2.5 moles per mole of the starting aluminum alkoxide. When the above polymerization is effected in the presence of a tertiary amine, the polymerization degree is increased.

3,580,867

PROCESS FOR PREPARING A CLOSED CELL EPDM SPONGE COMPOSITION

Lawrence Spenadel, Westfield, N.J., assignor to Esso Research and Engineering Company
Filed Aug. 30, 1967, Ser. No. 664,493

Int. Cl. C08d 13/10, 9/16

U.S. Cl. 260—2.5

7 Claims

A compounded ethylene-propylene diene monomer (EPDM) suitable for use in manufacturing an improved closed cell sponge by the free expansion method and the process for preparing said compounded EPDM which comprises blending the EPDM with a reinforcing black and a chemical promoter and heat treating at an elevated temperature for a time sufficient to bond the EPDM to the reinforcing black, thereby increasing the tensile modulus of the EPDM.

3,580,868

POLYISOCYANURATE RESIN AND FOAM FORMATION CATALYZED BY MANNICH BASES

Hans Joachim Diehr, Rudolf Merten, Helmut Piechota, and Konrad Uhlig, Leverkusen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Filed Dec. 27, 1968, Ser. No. 787,559

Claims priority, application Germany, Jan. 2, 1968, P 17 20 769.1

Int. Cl. C08g 22/36, 22/46

U.S. Cl. 260—2.5

7 Claims

Synthetic resins especially foams are prepared by polymerization of compounds which contain more than one isocyanate group in the molecule, in the presence of Mannich base catalysts which are obtained by reaction between dimethylamine, formaldehyde and phenols which contain in the molecule at least one organic substituent which has at least 6 carbon atoms, optionally, in the presence of less than equivalent quantities of compounds which contain active hydrogen atoms and the usual auxiliary agents.

3,580,869

MICROCELLULAR POLYURETHANE FOAMS BASED ON AROMATIC POLYAMINES AND PROPOXYLATED ANILINE

Richard D. Rhodes, Jr., Somersworth, and Kirby E. L. Flanagan, Rochester, N.H., assignors to Davidson Rubber Company Inc., Dover, N.H.

No Drawing. Continuation-in-part of application Ser. No. 733,765, June 3, 1968. This application June 3, 1969, Ser. No. 830,095


Int. Cl. C08g 22/46

U.S. Cl. 260—2.5


2 Claims

A microcellular polyurethane foam prepared by reacting in the presence of an organometallic catalyst:

- (1) toluene diisocyanate;
- (2) a polyol selected from the group consisting of:
 - (A) organic triols having molecular weights of from about 1,500 to about 6,500 and
 - (B) mixtures of (I) organic triols having molecular weights of from about 1,500 to about 6,500 and (II) organic diols having molecular weights of from about 400 to about 2,800;
- (3) an aromatic amine having the formula:



where n equals from about 0.1 to about 0.3; and
(4) a propoxylated aniline having the formula:



proportions of (1) to (2) to (3) to (4) being such that:

- (a) the ratio of $-\text{NCO}$ to active hydrogen atoms is in the range of from 1.0:1.0 to 1.2:1.0;
- (b) the ratio of $-\text{NH}_2$ groups of the aromatic amine to $-\text{OH}$ groups is in the range of from 0.6:1.0 to 1.0:1.0; and
- (c) the weight ratio of aromatic amine to the sum of aromatic amine and propoxylated aniline is from 0.45:1.0 to 0.95:1.0.

3,580,870

BEADED INJECTABLE SEALING COMPOSITION

Robert E. Rosner, Ferguson, Mo., assignor to McDonnell Douglas Corporation, St. Louis County, Mo.

Filed Dec. 6, 1968, Ser. No. 781,796

Int. Cl. C08j 1/14; B01j 13/02

U.S. Cl. 260—2.5

4 Claims

A sealant composition including a sealant medium containing specifically sized and shaped particle to improve the completeness of sealing the gaps and spaces that occur between a pair of sealable components due to manufacturing tolerances, the sealant composition being injected under pressure so that said particles are available to fill the gaps and spaces by a clustering formation to block the escape paths of the sealant medium, without interfering with the normal passage provided for distribution of the sealant composition.

3,580,871

PROCESS FOR THE MANUFACTURE OF POLYMER DISPERSIONS WITH POSITIVE ZETA POTENTIAL

Karl Josef Rauterkus, Kelkheim, Taunus, and Hamsjorg Vollmann, Frankfurt am Main, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Continuation-in-part of application Ser. No. 640,490, May 23, 1967. This application July 15, 1969, Ser. No. 842,005

Claims priority, application Germany, June 1, 1966, F 49,358

Int. Cl. C08f 1/13

U.S. Cl. 260—17

5 Claims

Polymer dispersions with positive zeta potential produced by emulsion polymerization of at least one vinyl, vinylidene, acryl or methacryl compound in the presence of a free radical polymerization catalyst and in the presence of at least one basically substituted N-vinyl amide.

3,580,872

READY-TO-USE PHENOLIC ADHESIVES

Alan L. Lambuth, Bellevue, Wash., assignor to Monsanto Company, St. Louis, Mo.

No Drawing. Filed Oct. 22, 1968, Ser. No. 769,702

Int. Cl. C08g 51/14; C08h 17/26

U.S. Cl. 260—17.2R

11 Claims

A ready-to-use phenolic adhesive for the manufacture of plywood is described which contains a micronized solid residue of the acid hydrolysis of pentosan-containing materials. The adhesive is prepared by digesting the micronized solid residue in an alkali solution and then reacting phenol and formaldehyde in the solution containing the residue.

3,580,873

NONYELLOWING POLYURETHANE

Dominick Bianca, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Filed Oct. 18, 1967, Ser. No. 676,033

Int. Cl. C08g 22/08

U.S. Cl. 260—18

7 Claims

A nonyellowing polyurethane prepared by reacting an isocyanato-terminated prepolymer with a mixture of monoethanolamine and triethanolamine in the presence of a catalytic amount of a metal drier compound such as calcium-, zinc- or lead naphthenate or octoate.

3,580,874

DYEABLE PILL-RESISTANT POLYESTERS

Akihiro Nishimura, Williamsburg, Va., assignor to Dow Badische Company, Williamsburg, Va.

No Drawing. Filed July 16, 1969, Ser. No. 842,389

Int. Cl. C08f 11/02, 21/04; C08g 17/00

U.S. Cl. 260—22

15 Claims

Improved polyesters consist of the condensation product of a polyhydric alcohol, a major proportion of a first

dibasic acid, a minor proportion of a long chain aliphatic dibasic acid having 28-44 carbon atoms, and a minor proportion of a long chain polyfunctional compound having 30-60 carbon atoms and at least three reactive sites.

3,580,875

POLISHING COMPOSITION

John M. Behnke, Newark, N.J., assignor to Bristol-Myers Company, New York, N.Y.

No Drawing. Filed Dec. 7, 1967, Ser. No. 688,662
Int. Cl. C09g 1/10

U.S. Cl. 260-23

2 Claims

A composition used for polishing surfaces such as wood and Formica, comprised of synthetic wax, a combination of resins, a combination of plasticizers comprising a fatty acid amine soap and a fatty alcohol amine sulfate, and a non-aqueous solvent system.

3,580,876

FILM-FORMING COMPOSITION OF INTER-POLYMER LATEX AND COALESCING AGENT

Raymond A. Stone, Fairfield Farms, and Fred Lister and David S. Heller, Dover, Del., assignors to Standard Brands Chemical Industries, Inc., Dover, Del.

No Drawing. Filed Apr. 19, 1968, Ser. No. 722,536
Int. Cl. C08f 19/08, 45/24, 45/34, 45/38, 45/42;
C08g 37/26, 51/24, 51/34, 51/38, 51/42

U.S. Cl. 260-29.4

15 Claims

An improved polymeric film-forming composition comprising (1) a latex of an interpolymer of an aliphatic conjugated diene, a monovinyl aromatic compound or mixtures thereof with other monovinyl compounds and an N-alkylol acrylamide and (2) a minor amount of a volatile organic azeotrope-forming coalescing agent and materials coated therewith.

3,580,877

EMULSION POLYMERS OF STYRENE AND UNSATURATED AMIDES

Alfred Reginald Corry, Dorothy Joyce Guest, and William Ian Williamson, Manchester, England, assignors to Imperial Chemical Industries Limited, London, England
No Drawing. Filed May 18, 1967, Ser. No. 639,302
Claims priority, application Great Britain, May 25, 1966, 23,406/66

Int. Cl. B01j 13/00; C08f 15/02; C09d 5/02

U.S. Cl. 260-29.6RW

16 Claims

Aqueous dispersions of water- and alkali-insoluble solid copolymers of a major proportion by weight of (a) styrene or of a substituted styrene or of mixtures of these, with a minor proportion by weight of (b) a neutral or acidic water-soluble monomer, and optionally with a minor proportion by weight of (c) a different neutral or acidic water-soluble monomer wherein monomer (b) is concentrated at or near the surface of the particles of the copolymer. The dispersions are useful for addition to liquid synthetic detergents to give them the appearance and creamy consistency of a hand lotion.

3,580,878

FLAME-RESISTANT ACRYLONITRILE COPOLYMERS WITH HIGH RECEPTIVITY TO ACID DYES

Iyohiko Nakanome, Kenji Takeya, Hiroshi Suzuki, and Yasuhiro Kitagawa, Saidaiji, Japan, assignors to Japan Exlan Company Limited, Osaka, Japan

No Drawing. Filed June 13, 1968, Ser. No. 737,309
Claims priority, application Japan, July 1, 1967, 42/42,470; Sept. 26, 1967, 42/62,094
Int. Cl. C08f 15/40, 37/00, 45/24

U.S. Cl. 260-29.6

2 Claims

Acrylonitrile copolymers which have high receptivity to acid dyes and are flame resistant, and are thus useful in

making carpeting, curtains, etc. as well as wearing apparel, etc., are ternary polymers composed of acrylonitrile, vinylidene chloride, and a basic monomer of the type of the dimethylaminoethyl and diethylaminoethyl esters of acrylic acid and of methacrylic acid, and the corresponding N-substituted aminopropyl and aminobutyl esters, etc.; or copolymers consisting of acrylonitrile, vinylidene chloride, a basic monomer of the afore-indicated type and one or more neutral ethylenically unsaturated compounds (i.e. methyl acrylate, methyl methacrylate, vinyl acetate, styrene).

3,580,879

GELABLE COMPOSITIONS AND PROCESS OF USING THE SAME

Einosuke Higashimura, Tokyo, Katsumi Tamai, Ohtakeshi, and Eichi Nakamura, Tokyo, Japan, assignors to Mitsubishi Rayon Co., Ltd., Tokyo, Japan

No Drawing. Filed Aug. 29, 1967, Ser. No. 663,992
Claims priority, application Japan, Sept. 8, 1966, 41/59,358


Int. Cl. C08f 15/02; F21b 33/13

U.S. Cl. 260-29.7H

6 Claims

A gelable, non-toxic and odorless composition for construction materials which comprises

- (1) 1-90% by weight of metal methacrylates or acrylates, such as magnesium methacrylate,
- (2) 3-90% by weight of water-soluble ethenoid monomers, such as acrylamide and a compound of



(R is —H or —CH₃, and R' is an alkyl having —OH or —NH₂), and

- (3) 1-30% by weight of water-soluble divinyl monomers such as glyceroldiacrylate.

A process for stabilizing such construction materials as cement and soil, wherein an aqueous solution of the composition and a redox catalyst is added thereto, and high strength and superior impermeability to water can be provided. The period for gelation may be controlled as desired.

In a rapid stabilization process for construction materials adding a gelable composition comprising (1) water-soluble vinyl monomers and (2) water-soluble divinyl monomers and a redox catalyst thereto, the method wherein β -diketone is used as a component of the redox with or without metallic ions. Sodium formaldehyde sulfoxylate, a reducing sugar, a water-soluble amine can also be used as said component.

3,580,880¹

DISPERSIONS OF PARTICULATE SOLIDS IN EITHER LIPOPHILIC OR HYDROPHILIC LIQUIDS STABILIZED WITH A POLYMERIC AMPHIPATHIC STABILISER AND PROCESS FOR PREPARING SAID DISPERSIONS

Michael Raymond Clarke and Leon Filipowicz, Melbourne, Victoria, Australia, assignors to Balm Paints Limited, Melbourne, Victoria, Australia

No Drawing. Filed Nov. 20, 1967, Ser. No. 684,545
Claims priority, application Great Britain, Nov. 25, 1966, 52,826/66

Int. Cl. C08f 45/24; C08g 53/18; C08j 1/46

U.S. Cl. 260-29.6R

16 Claims

A process of preparing stable dispersions of particulate solids in either lipophilic or hydrophilic liquids by dispersing the solids in the liquid in the presence of a polymeric

amphipathic stabiliser which associates with the surface of the particles and provides a solvated steric barrier around them. The stabilisers comprise at least one chain-like component solvatable by a lipophilic liquid and with a chain-length equivalent to at least 12 covalent links together with at least one component solvatable by a hydrophilic liquid, each component being present in the weight proportion of at least 25% of the total weight of stabiliser. The stabilisers may comprise up to 10% by weight of ionizable groups, preferably co-reacted with counter-ions solvatable by a hydrophilic liquid.

3,580,881

POLYURETHANE COATING SYSTEM

Henry J. Lee, 12 Knollwood Drive, Cherry Hill, N.J. 08034

No Drawing. Filed Feb. 27, 1970, Ser. No. 15,227
Int. Cl. C08g 22/06, 51/34, 51/36

U.S. Cl. 260-30.4

10 Claims

Present invention relates to a novel and improved method of protecting a surface with a polyurethane coating that exhibits outstanding chemical and physical properties. The improved process utilizes the ability of aromatic polyisocyanates to dimerize and trimerize and react with a short chain aliphatic glycol under carefully controlled conditions of heat to form a unique prepolymer. The prepolymer, when dissolved in a suitable solvent, has a prolonged stable shelf life and, when applied to the surface to be protected, cures itself on the mere evaporation of the solvent.

3,580,882

MICA-REINFORCED COMPOSITES

Lawrence E. Nielsen, Creve Coeur, and Joseph E. Fields, Ballwin, Mo., assignors to Monsanto Company, St. Louis, Mo.

No Drawing. Continuation-in-part of application Ser. No. 753,857, Aug. 20, 1968. This application Nov. 29, 1968, Ser. No. 780,272

Int. Cl. C08f 45/04

U.S. Cl. 260-41

5 Claims

A shaped composite structure comprising finely comminuted mica as reinforcing filler in a matrix comprising the zinc salt of an acrylic acid polymer, and the method of preparing the same which comprises heating in a mold at a temperature of from about 175° C. to 400° C. and a pressure of from about 5,000 p.s.i. to 50,000 p.s.i. a mixture of zinc oxide and an acrylic acid polymer in contact with the mica.

3,580,883

METHOD OF CHEMICAL GROUT PROCESSING

Shigekazu Kasahara, Yuji Takahashi, Takashi Suzuki, Shinichi Umeda, Kazuo Adachi, and Yasuo Fukuda, Tokyo, Japan, assignors to Tekkoshu Co., Ltd., Tokyo, Japan

No Drawing. Filed Jan. 14, 1969, Ser. No. 791,137
Claims priority, application Japan, Jan. 18, 1968, 43/2,385

Int. Cl. C08f 45/04

U.S. Cl. 260-41

9 Claims

A composition of matter comprising a synthetic resin and a water soluble organic solvent which can dissolve said resin, which composition may also contain cement and/or sodium silicate, is injected into soil. The organic solvent is dissolved away by the ground water which is present in the soil and the remaining solid component fills the spaces in the soil, whereby water paths in the soil are blocked.

3,580,884

TETRAHYDROQUINOXALINE/ALDEHYDE REACTION PRODUCTS AS POLYMER ANTIOZONANTS

Farris H. Wilson, Jr., Cuyahoga Falls, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
No Drawing. Filed Mar. 29, 1968, Ser. No. 717,463

Int. Cl. C08f 11/04; C08g 51/60

U.S. Cl. 260-45.8

7 Claims

Polymers protected against ozone degradation by the incorporation of a reaction product produced by reacting a tetrahydroquinoxaline (1,2,3,4-tetrahydroquinoxaline) with an aldehyde (formaldehyde).

3,580,885

ANTIOZONANTS

Elmer A. Fike, Nitro, W. Va., assignor to Security Chemicals, Inc., Nitro, W. Va.

No Drawing. Filed Sept. 27, 1968, Ser. No. 763,381
Int. Cl. C08c 11/40, 11/54; C08d 9/00

U.S. Cl. 260-45.8

11 Claims

The invention relates to novel N-substituted dimethyl pyrroles for use as antiozonants in rubber.

3,580,886

POLYESTERS STABILIZED WITH AROMATIC ISOCYANATES

Mary J. Stewart, Media, and John A. Price, Swarthmore, Pa., assignors to FMC Corporation, Philadelphia, Pa.
No Drawing. Filed June 5, 1968, Ser. No. 734,534

Int. Cl. C08g 51/60

U.S. Cl. 260-45.9

9 Claims

A thermal stabilized polyester comprising a highly polymeric linear polyester containing a stabilizing amount of an aromatic mono- or polyisocyanate.

3,580,887

ELASTOMERIC PRODUCTS OF EPOXY RESINS AND POLYETHER DISECONDARY AMINES

Allen J. Hubin, White Bear Lake, Minn., assignor to Minnesota Mining & Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Apr. 21, 1969, Ser. No. 818,114

Int. Cl. C08g 30/14

U.S. Cl. 260-47

8 Claims

An elastomeric reaction product of an epoxy resin and at least one amine having a minimum of 2 amino hydrogen atoms per molecule, at least one portion of said amine being a polyether dissecondary amine.

3,580,888

WITHDRAWN

3,580,889

VULCANIZATION ACCELERATORS OF POLYCYCLIC ETHERS FOR FLUORINATED POLYMERS

Arthur Livingston Barney and Wolfgang Honsberg, Wilmington, Del., assignors to E. I. du Pont de Nemours and Company, Wilmington, Del.

No Drawing. Continuation-in-part of abandoned applications Ser. No. 661,230, Aug. 17, 1967, and Ser. No. 731,325, May 22, 1968. This application Feb. 25, 1969, Ser. No. 802,236

Int. Cl. C08f 7/10, 3/20, 19/00

U.S. Cl. 260-47

17 Claims

The acceleration of the vulcanization of saturated, fluorinated polymers by the use of cyclic polyethers. The accelerators enable a more rapid cure with conventional amine-based vulcanization systems and also enable a satisfactory rate and state of cure with weakly basic bis-nucleophiles otherwise incapable of adequately curing fluorinated polymers.

3,580,890

BASIC CATALYSTS CONTAINING AROMATIC NUCLEI AND ARALIPHATICALLY BOUND TERTIARY AMINO GROUPS FOR THE POLYMERIZATION OF NCO GROUPS



Hans Joachim Diehr and Rudolf Merten, Leverkusen, Helmut Piechota, Leverkusen-Mathildenhof, and Konrad Uhlig, Leverkusen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany

No Drawing. Filed Oct. 25, 1968, Ser. No. 770,800
Claims priority, application Germany, Oct. 31, 1967, F 53,928, F 53,929
Int. Cl. C08g 22/00**U.S. Cl. 260—77.5 13 Claims**
A process for the production of polyisocyanurates wherein compounds or mixtures of compounds containing at least two isocyanate groups are reacted in the presence of basic compounds containing at least two aromatic nuclei and at least one araliphatically bound tertiary amino function per molecule.

3,580,891

WATER-INSOLUBLE, CROSS-LINKED POLYMERIC REACTION PRODUCT OF ETHYLENE DIAMINE AND NITRILOTRIACETIC ACID OR DERIVATIVE

Norman B. Rainer, Richmond, Va., assignor to Seekay Chemical Company, Brooklyn, N.Y.

No Drawing. Filed Apr. 16, 1968, Ser. No. 721,585
Int. Cl. C08g 20/32**U.S. Cl. 260—72 4 Claims**
A solute is removed from an aqueous solution by contacting said solution with a cross linked polymer containing recurring nitrogen atoms interconnected at each valence by radicals of the formulawherein a is 1 or 2 and X is a divalent radical selected from the group $-CH_2CH_2-$, $-CH_2CH_2OCH_2CH_2-$ and

3,580,892

PROCESS FOR POLYMERIZING CYCLOPENTENE
Peter Gunther, Opladen, Wolfgang Oberkirch, Cologne-Stammheim, and Gottfried Pampus, Leverkusen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, GermanyNo Drawing. Filed Nov. 5, 1969, Ser. No. 874,399
Claims priority, application Germany, Dec. 3, 1968, P 18 12 338.1
Int. Cl. C08f 5/00**U.S. Cl. 260—93.1 8 Claims**
A catalyst made from (1) a rhenium compound and (2) an aluminum organic compound polymerizes cyclopentene to yield rubber-like products with high content of cis-linkages.

3,580,893

PROCESS FOR THE PREPARATION OF CYCLIC ACID ANHYDRIDESWilliam J. Heilman, Allison Park, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
No Drawing. Continuation-in-part of application Ser. No. 594,347, Oct. 25, 1966. This application May 26, 1969, Ser. No. 828,001

Int. Cl. C08f 27/12

U.S. Cl. 260—78.5T 1 Claim
A process is defined for heating an organic compound containing at least one half-ester of a dicarboxylic acid where the carbonyl groups are directly connected to adjacent internal aliphatic carbon atoms to a temperature in excess of about 80° C. to convert the half-ester groups

to cyclic anhydride groups and a by-product alcohol. The organic compound is a 1:1 copolymer of an aliphatic hydrocarbon having at least three carbon atoms, such as 1-hexene, and maleic anhydride. The organic compound prepared from an olefin having from three to ten carbon atoms can be precipitated as a solid from its homogeneous reaction medium by pouring the reaction solution into a monohydroxy alcohol having one to four carbon atoms, such as methanol. Some methyl half-ester forms can be removed by heating the separated solid product at a temperature in excess of 80° C. while removing the monohydroxy alcohol. Thus, 1-hexene-maleic anhydride copolymers free of half-ester groups can be recovered. If the organic compound contains both half-ester and diester groups, the resulting compound after heating to a temperature in excess of 80° C. will contain anhydride and diester linkages.

3,580,894

UNIQUE POLYMERS AND PROCESSES FOR PRODUCING SAME


Gerd M. Lenke, Dover, Del., assignor to Standard Brands Chemical Industries, Inc., Dover, Del.

No Drawing. Filed Jan. 30, 1968, Ser. No. 701,556
Int. Cl. C08f 27/06**U.S. Cl. 260—79.5 16 Claims**
A unique class of phosphorus and sulfur-containing polymers comprising the reaction products of an unsaturated polymer and a hydrocarbyl phosphinodithioic acid and the processes for making them. These polymers are self-curing and many have superior adhesive properties.

3,580,895

PRODUCTION OF COPOLYMERS IN THE PRESENCE OF AN ORGANOLITHIUM COMPOUND AND AN ORTHOESTER

Akira Onishi, Shiro Anzai, Koichi Irako, Ryota Fujio, Yoshihiro Hayakawa, and Shoji Miyamoto, Tokyo, Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

No Drawing. Filed Dec. 3, 1968, Ser. No. 780,898
Claims priority, application Japan, Dec. 11, 1967, 42/79,057**U.S. Cl. 260—83.7 21 Claims**
Random copolymer is prepared by copolymerizing a conjugated diene, such as 1,3-butadiene and a vinyl-substituted aromatic hydrocarbon, such as styrene at a temperature of -80° to 150° C. in the presence of a substantially anhydrous liquid hydrocarbon by means of a catalyst system consisting essentially of an organolithium compound and an orthoester having the general formulawherein, R^2 is hydrogen or a hydrocarbon radical and R^3 , R^4 and R^5 are hydrocarbon radicals.

3,580,896

AQUEOUS SUSPENSION POLYMERIZATION OF VINYL HALIDE POLYMERS IN THE PRESENCE OF ACRYLIC ACID

Elliott Farber, Trenton, N.J., assignor to Tenneco Chemicals, Inc.

No Drawing. Filed Mar. 6, 1968, Ser. No. 710,758
Int. Cl. C08f 15/30, 15/08, 15/26**U.S. Cl. 260—87.1 8 Claims**
Vinyl halide polymers are prepared in the form of uniform very small particles by incorporating in the monomer component of the polymerization mixture about 0.5

percent to 20 percent and preferably 1 percent to 10 percent by weight of acrylic acid, methacrylic acid, or mixtures thereof. Both the particle size and particle size distribution of vinyl halide homopolymers and copolymers with, for example, vinyl acetate, can be controlled in this way.

3,580,897

PROCESS FOR PRODUCING HYDROGENATED HYDROCARBON POLYMERS

Toshio Yoshimoto, Tsuneaki Narumiya, Seiya Kaneko, Hiroshi Yoshii, and Tetsuya Takamatsu, Tokyo, Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

No Drawing. Filed Nov. 14, 1968, Ser. No. 775,922
Claims priority, application Japan, Nov. 27, 1967, 42/75,633**Int. Cl. C08d 5/02; C08f 27/25 U.S. Cl. 260—85.1 12 Claims**
Hydrogenated hydrocarbon polymers can be obtained in a continuous step comprising polymerizing or copolymerizing conjugated 1,3-diolefin in an inert atmosphere and in an inert solvent by using a catalyst based on an alkali metal or an alkali metal hydrocarbyl to obtain a polymer solution and then mixing homogeneously an organic compound of nickel or cobalt soluble in the inert solvent with the resulting polymer solution without isolating the resulting polymer and catalytically hydrogenating the unsaturated bond of the resulting polymer. In this process the alkali metal or alkali metal hydrocarbyl in the polymerization catalyst, which remains in the resulting polymer after the polymerization acts to effect the reduction of the organic compound of nickel or cobalt to produce the hydrogenation catalyst.

3,580,898

VAPOR PHASE POLYMERIZATION OF BUTENE-1
Milton K. Rosen, Flemington, and Charles D. Mason, Florham Park, N.J., assignors to Allied Chemical Corporation, New York, N.Y.No Drawing. Filed May 28, 1968, Ser. No. 732,528
Int. Cl. C08f 1/42, 3/12**U.S. Cl. 260—93.7 10 Claims**
Vapor phase polymerization of butene-1 using Ziegler-Natta stereoregulating catalyst with diethyl aluminum chloride as co-catalyst. Maintaining initial temperature less than about 26° C. affords powder or granular poly(butene-1) resin of high isotacticity, suitable for powder molding. After initial phase of polymerization (when sufficient polymer has been formed to fill at least about 10% of the reactor volume), temperature and pressure can be raised in order to increase reaction rate without causing agglomeration of product. Molecular weight of poly(butene-1) is controlled without affecting granularity by supplying hydrogen into the reaction medium.

3,580,899

POLYMERIZATION OF ISOPRENE

Jean-Marie Massoubre, Clermont-Ferrand, France, assignor to Compagnie Generale des Etablissements Michelin, raison sociale Michelin & Cie, Clermont-Ferrand, Puy-de-Dome, France

No Drawing. Filed May 10, 1967, Ser. No. 637,327
Claims priority, application France, May 16, 1966, 1,856; Feb. 10, 1967, 94,608
Int. Cl. C08d 3/10**U.S. Cl. 260—94.3 7 Claims**
A polymerization catalyst comprising a mixture of (1) a hydrocarbon solution of a complex of a diaryl ether, such as diphenyl ether, and a tetravalent titanium salt, such as titanium tetrachloride, and (2) a hydrocarbon solution of a trialkyl aluminum compound, such as triisobutyl aluminum; the catalyst desirably further containing a diene compound, such as butadiene or isoprene, and

being useful in a process for the rapid polymerization of isoprene in high yield into high molecular weight polymers which can be free from gel.

3,580,900

WATER-SOLUBLE QUATERNARY AMINE CONTAINING MONOAZO DYESTUFFS


Eberhard Mundlos, Frankfurt am Main, Reinhard Mohr, Offenbach am Main, Gunther Trapp, Frankfurt am Main, and Kurt Hohmann, Offenbach am Main, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany

No Drawing. Filed Oct. 1, 1968, Ser. No. 764,304
Claims priority, application Germany, Oct. 21, 1967, P 16 44 230.1
Int. Cl. C07c 107/06; C09b 45/22, 29/01**U.S. Cl. 260—149 6 Claims**
Water-soluble basic monoazo dyestuffs which are suitable for the dyeing or printing of textile fibrous materials consisting of native or regenerative cellulose, polyamides, polyesters, polyacrylonitrile or polyvinylidene cyanide.

3,580,901

MAROON DISAZO DYES FOR POLYAMIDE FIBERS
James F. Feeman, Wyomissing, Pa., assignor to Crompton & Knowles Corporation, Worcester, Mass.No Drawing. Filed Nov. 14, 1968, Ser. No. 775,950
Int. Cl. C09b 31/04; D06p 1/02**U.S. Cl. 260—191 6 Claims**
Compounds that are useful as neutral dyeing dyes for polyamide fibers and dye such fibers in level, lightfast maroon shades.



The dyes have the structure:

wherein R_1 represents $-H$, $-CH_3$, $-OCH_3$ or $-Cl$; R_2 represents $-H$ or $-CH_3$; R_3 represents lower alkyl having 1 to 4 C atoms and M represents $-H$, $-Na$, $-K$ or $-NH_4$.

3,580,902

WATER-INSOLUBLE MONOAZO DYESTUFFS

Hans-Joerg Angliker, Basel, Switzerland, assignor to Ciba Limited, Basel, Switzerland

No Drawing. Filed Oct. 4, 1967, Ser. No. 672,721
Claims priority, application Switzerland, Oct. 11, 1966, 14,691/66**Int. Cl. C09b 29/08, 29/36, 29/38 U.S. Cl. 260—207 4 Claims**
Water-insoluble mono-azo dyestuff of the formulain which one of the symbols Y represents a phenoxy, phenyl-lower alkoxy, phenylmercapto, phenyl-lower alkylmercapto, phenyl nitrophenyl or phenyl-lower alkyl group and the other represents a hydrogen atom, a lower alkyl, lower alkoxy, phenylmercapto, phenyl-lower alkylmercapto phenyl or phenyl-lower alkyl group and B represents the radical of a coupling component selected from the group consisting of a pyrazolone, barbituric acid, 8-hydroxyquinoline and a compound of the formula

in which R_1 represents hydrogen, halogen, lower alkyl, lower alkoxy, lower alkanoylamino, phenoxy, phenylmercapto phenyl, R_2 represents hydrogen, lower alkyl or lower alkoxy, R_3 and R_4 each represents lower alkyl, cyano-lower alkyl, or lower alkanoyloxy-lower alkyl, dye polyester fibers yellow to red tints of excellent fastness to light and sublimation.

3,580,903

KETODEXTRAN COMPOUNDS


Anthony N. de Belder and Bernt J. Lindberg, Uppsala, Sweden, assignors to Pharmacia AB, Uppsala, Sweden
No Drawing. Filed Apr. 2, 1969, Ser. No. 812,848
Claims priority, application Sweden, Apr. 8, 1968, 4,696/68

Int. Cl. C08b 25/04

U.S. Cl. 260—209D

2 Claims

Derivative of dextran represented by the general formula:



wherein m represents the number of secondary alcohol groups in dextran having the formula $A[CH(OH)]_m$, and wherein n is a number chosen such that the degree of substitution n/m lies between 0.01 and 0.05, and wherein $[CH(OH)]_m$ represents the groups bearing the secondary alcohol groups of the dextran and A represents the remainder of the dextran. The dextran derivatives are very useful in intermediate products and may be reacted with a number of substances to form valuable and useful products. Such can be employed as a carrier for pharmaceuticals containing hydrazine and amino groups.

3,580,904

7-HALO-7-DEOXY-LINCOMYCIN DERIVATIVES

Walter Morozowich and Anthony A. Sinkula, Kalamazoo, Mich., assignors to The Upjohn Company, Kalamazoo, Mich.


No Drawing. Continuation-in-part of application Ser. No. 637,358, May 10, 1967. This application Apr. 3, 1969, Ser. No. 813,341

The portion of the term of the patent subsequent to Feb. 4, 1986, has been disclaimed
Int. Cl. C07c 47/18

U.S. Cl. 260—210

26 Claims

Antibacterial compounds of the formula:



and the salts thereof, and the 3,4-O-arylidene derivatives.

3,580,905

3-(AMINOALKOXYCARBONYLALKYLENE) STEROID DERIVATIVES

Ivor James Stewart Brown, Richard Clarkson, Neville Stanton Crossley, and Bernard Joseph McLoughlin, Macclesfield, England, assignors to Imperial Chemical Industries, Limited, London, England

No Drawing. Filed June 14, 1968, Ser. No. 736,951
Claims priority, application Great Britain, June 22, 1967, 28,824/67

Int. Cl. C07c 169/00, 173/00

U.S. Cl. 260—210.5

3 Claims

The disclosure relates to 3-aminoalkoxycarbonylmethylene derivatives of steroids, processes for their manu-

facture, pharmaceutical compositions containing them and a method of using them to increase the force of contraction of the heart of warm-blooded animals. Representative of the steroid derivatives disclosed are 3-(2-dimethylaminoethoxycarbonylmethylene) - 17β - (β - D - glucopyranosyloxy) - 5α - androstane and the tetra-O-acetate thereof.

3,580,906

STARCH LEVULINATES

Edward Bernasek, Winston-Salem, N.C., and Calley Neil Eaton, New York, N.Y., assignors to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.

No Drawing. Filed Sept. 25, 1968, Ser. No. 762,645

Int. Cl. C08b 19/02

U.S. Cl. 260—233.5

5 Claims

Levulinate esters of starch are prepared by reacting starch with alpha-angelica lactone under controlled conditions of temperature and pH. The resulting starch levulinates may be used in food, cosmetic, adhesive, and paper and textile sizing applications, etc.

3,580,907

MORPHANTHRIDINE DERIVATIVES

Max Thiel and Kurt Stach, Mannheim, Wolfgang Schumann, Mannheim-Waldhof, and Annemarie Ribbentrop, Mannheim, Germany, assignors to Boehringer Mannheim Gesellschaft mit beschränkter Haftung

No Drawing. Filed Jan. 24, 1967, Ser. No. 611,240


B 85,866

Int. Cl. C07d 41/04, 41/06

U.S. Cl. 260—239

16 Claims

Morphanthridine derivatives of the formula



wherein B is H or the group $-A-Am$, wherein Am is a secondary amino group, A is a straight or branched chain alkylene group and X is a methylene or carbonyl group. The pharmacologically acceptable salts of the compounds wherein B is $-A-Am$ are also within the scope of the invention as are the pharmaceutical compositions containing the latter compounds and the method of using the same. The morphanthridine derivatives possess psychodynamic properties, being particularly adapted for use as antidepressive agents.

3,580,908

PROCESS FOR THE CONVERSION OF α -CARBOARYLOXYBENZYL PENICILLINS TO α -CARBOXYBENZYL PENICILLINS

Kenneth Butler, Waterford, Conn., assignor to Pfizer Inc., New York, N.Y.

No Drawing. Filed Oct. 17, 1968, Ser. No. 768,548

Int. Cl. C07d 99/16

U.S. Cl. 260—239.1

6 Claims

The controlled hydrolysis of α -carbobyloxybenzylpenicillin and α -carbobyloxybenzylpenicillins, such as α -carbophenoxybenzylpenicillin, under alkaline conditions to α -carboxybenzylpenicillin salts.

3,580,909

4-STYRYLPYRIDINES


Hanns Hanina Lehr, Montclair, N.J., assignor to Hoffmann-La Roche, Inc., Nutley, N.J.
No Drawing. Filed Dec. 9, 1968, Ser. No. 782,412
Int. Cl. C07d 31/20, 31/24

U.S. Cl. 260—240

12 Claims

4-styrylpyridines, prepared by reacting appropriately substituted pyridines and aromatic aldehydes, are described. The end products are useful as anticonvulsants.

in which R^1 is $-NRalky$,



3,580,910

p-ALKOXY-PIPERIDINE-AMIDES

Max Thiel, Mannheim, Wolfgang Kampe, Heddeshheim, Kurt Stach and Wolfgang Schumann, Mannheim-Waldhof, and Annemarie Ribbentrop, Mannheim, Germany, assignors to Boehringer Mannheim Gesellschaft mit beschränkter Haftung

No Drawing. Filed Jan. 18, 1968, Ser. No. 698,701


Claims priority, application Germany, Jan. 25, 1967, B 90,888

Int. Cl. C07d 29/18

U.S. Cl. 260—240

3 Claims

A series of novel p-alkoxy-piperidine-amides having the formula:



wherein R_1 , R_2 and R_3 are each hydrogen, halogen, hydroxyl, alkoxy, alkyl or trifluoromethyl, R_4 is lower alkyl, and n is 0 or 1, constituting useful chemotherapeutic agents particularly because of their anticonvulsive, tranquilizing and sedative actions.

3,580,911

PHOTOGRAPHIC MATERIALS

John D. Mee and Donald W. Heseltine, Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.
No Drawing. Application July 22, 1968, Ser. No. 746,260, now Patent No. 3,501,312, dated Mar. 17, 1970, which is a continuation-in-part of application Ser. No. 609,792, Jan. 17, 1967. Divided and this application Aug. 5, 1969, Ser. No. 870,922

Int. Cl. C09b 23/06

U.S. Cl. 260—240.65

4 Claims

Trimethine cyanine dyes are provided which contain a 3-indole nucleus which contains either a fused aromatic ring, an alkylene bridge or a 2-heterocyclic substituent.

3,580,912

BIOLOGICALLY ACTIVE SUBSTITUTED-S-TRIAZINES

Werner Heimberger and Hermann Schmitt, Hanau am Main, Germany, assignors to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler, Frankfurt am Main, Germany

No Drawing. Filed Nov. 30, 1967, Ser. No. 686,790


Claims priority, application Germany, Dec. 3, 1966, D 51,705

Int. Cl. C07d 55/22

U.S. Cl. 260—247.5R

5 Claims

Substituted-s-triazines having anti-inflammatory action of the formula



in which X is O or S, Z is alkyl, phenyl, naphthyl or cyclohexyl, Alk is alkylene and the alkyl and alkylene included in R, R^1 to R^3 and Z having up to 6 carbon atoms and their pharmacologically acceptable acid addition salts.

3,580,913

PROCESS FOR PREPARING SUBSTITUTED-6-TRIFLUOROMETHYLURACILS

Albert William Lutz, Princeton, N.J., assignor to American Cyanamid Company, Stamford, Conn.


No Drawing. Filed June 17, 1968, Ser. No. 737,288

Int. Cl. C07d 51/30, 51/32

U.S. Cl. 260—260

7 Claims

Herbicide uracils are prepared in accordance with the following equation:



The single step reaction is carried out in the presence of a solvent and an alkali metal hydride or alkali metal alkoxide.

In the above equation:

R^1 is hydrogen or lower alkyl,
 R^2 is alkyl, alkenyl, cycloalkyl, phenyl, benzyl, or specific mono and disubstituted derivatives thereof,
 R^3 is lower alkyl, and
X is oxygen or sulfur.

3,580,914

DERIVATIVES OF N-METHYLPYPERAZINE

Andrea Pedrazzoli and Leon Dall'Asta, Milan, Italy, assignors to Societe d'Etudes de Recherches et d'Application Scientifiques et Medicales E.R.A.S.M.E., Paris, France

No Drawing. Filed Aug. 14, 1967, Ser. No. 660,227
Claims priority, application Great Britain, Aug. 23, 1966, 37,827/67

Int. Cl. C07d 51/64

U.S. Cl. 260—268

2 Claims

N-methyl-N'-ethyl-piperazines in which the ethyl radical is β,β -disubstituted with (1) a phenyl or phenoxy-methylene radical which is unsubstituted or substituted in the ring with straight or branched aliphatic chains having 4 to 12 carbon atoms or cycloalkyl groups having 5 to 6 carbon atoms or with 2 or 3 chlorine atoms or with 2 chlorine atoms and a nitro group, and (2) a benzyloxy or phenoxyacetyloxy radical which is unsubstituted or substituted in the ring with 1, 2 or 3 chlorine atoms or with 2 chlorine atoms and a nitro group or a benzyloxy radical substituted in the ring with 1, 2 or 3 chlorine atoms; and pharmaceutically acceptable acid addition salts thereof. All of the compounds have antibacterial and antiprotozoan activity.

3,580,915

1,2,3,4-TETRAHYDROBENZO[b][1,6]NAPHTHYRIDINE DERIVATIVES

Milton Wolf, West Chester, and James L. Diebold, Haver-town, Pa., assignors to American Home Products Corporation, New York, N.Y.

No Drawing. Continuation-in-part of applications Ser. No. 533,802, Ser. No. 533,793, both Mar. 14, 1966, and Ser. No. 581,756, Sept. 22, 1966. This application Sept. 16, 1968, Ser. No. 760,063

Int. Cl. C07d 39/00

U.S. Cl. 260—286

6 Claims

This invention concerns 1,2,3,4 - tetrahydrobenzo[b][1,6]naphthyridine, 1,2,3,4,4a,5,10,10a - octahydrobenzo[b][1,6]naphthyridines and the pharmacologically acceptable acid addition salts thereof which are pharmacologically active as central nervous system depressants which are useful in producing a calming effect in warm-blooded animals. Further, this invention concerns a process for the preparation of 10 - amino - 1,2,3,4 - tetrahydrobenzo[b][1,6]naphthyridines.

3,580,916

HYDROXYESTERS OF HEXA- AND OCTAHYDROINDOLOQUINOLINES

William L. Garbrecht, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.

No Drawing. Filed Feb. 20, 1969, Ser. No. 801,144
Int. Cl. C07d 43/20

U.S. Cl. 260—285.5

13 Claims

Esters of lysergic and dihydrolysergic acids, including 4-alkyl, 4-alkenyl and 4-aryl derivatives thereof, in which the esterifying group is derived from a dihydroxy or trihydroxy alkyl alcohol having from two to eight carbon atoms or a C_5 to C_{11} cycloalkyl dihydroxy alcohol, having from 5 to 8 ring carbon atoms, the esters having neurosedative activity in animals.

3,580,917

PROCESS FOR PRODUCING PYRIDINE BASES

Yoshiaki Numa and Akio Nakamachi, Saitama, and Yasukazu Murakami, Kawasaki-shi, Kanagawa, Japan, assignors to Daicel Ltd., Osaka, Japan

No Drawing. Filed June 13, 1968, Ser. No. 736,560
Claims priority, application Japan, June 14, 1967, 42/37,595

Int. Cl. C07d 31/02

U.S. Cl. 260—290

6 Claims

A process for producing β -picoline and pyridine in which a gaseous mixture of acrolein and propylene oxide

are reacted with ammonia in the gas phase at an elevated temperature in the presence of a solid acid catalyst so that β -picoline and pyridine are produced at a high yield and without producing γ -picoline.

3,580,918

METHOD FOR THE PREPARATION OF AMINOALKYL FUMARATES

Frizian Nikolaevich Bodnarjuk and Mikhail Alexeevich Korshunov, Yaroslavl, U.S.S.R., assignors to Nauchno-Issledovatel'skiy Institut Monomeroi Dlya Sinteticheskogo, Yaroslavl, U.S.S.R.


No Drawing. Filed Sept. 3, 1968, Ser. No. 757,122

Int. Cl. C07c 101/00

U.S. Cl. 260—294.3

3 Claims

Aminoalkyl fumarates having the following formula:



wherein:

B is selected from the group consisting of tertiary aliphatic amino groups containing from 2 to 12 carbon atoms and piperidino;

A is H, CH_3 or CH_2-B , and

n is an integer of 1 to 2,

are produced by reacting maleic anhydride and amino alcohols having the general formula



at reflux temperature in the presence of an esterification catalyst and an inert solvent while bubbling nitrogen through the reaction mixture and continuously distilling off the water formed in the course of the reaction in the form of an azeotrope with the solvent. The aminoalkyl fumarates may be copolymerized with other vinyl type monomers to incorporate polar amino groups into polymer molecules to improve the characteristics of colorability, adhesion to various materials, resistance to temperature shocks and antistatic properties.

3,580,919

PROCESS FOR PREPARATION OF NAPHTHYRIDINE DIONE DYESTUFFS

Walter R. Demler, Hamburg, and Arthur F. Jachlewski, Buffalo, N.Y., assignors to Allied Chemical Corporation, New York, N.Y.

No Drawing. Filed Apr. 30, 1968, Ser. No. 725,481

Int. Cl. C07d 31/44

U.S. Cl. 260—295

18 Claims

An improved process for preparing water-insoluble dyes of the naphthyridine dione series by reaction of an indigo with an aryl acetyl halide in the presence of an inorganic acid halide preferably a thionyl halide and an aroyl halide, said indigo, aryl acetyl halide and aroyl halide being free of water-solubilizing substituents. The improved process provides yields of naphthyridine dione dyestuffs which are as much as 60–110% greater than those realized by previously employed processes using an indigo and an aryl acetyl halide as starting materials while at the same time requiring as little as 30–75% of the costly aryl acetyl halide reactant.

3,580,920

CERTAIN PYRIDINIUM HALOETHER SILANES AND DERIVATIVES

Alan L. Culpepper, Midland, Mich., assignor to Dow Corning Corporation, Midland, Mich.


No Drawing. Continuation of application Ser. No. 641,713, Mar. 2, 1967, which is a division of application Ser. No. 314,879, Oct. 9, 1963. This application Apr. 14, 1970, Ser. No. 28,189

Int. Cl. C07d 31/28


U.S. Cl. 260—297

5 Claims

Quaternary ammonium salts of the formula



where Q, Q' and Q'' are hydrogen, halogen, hydroxyl, monovalent hydrocarbon and haloalkyl radicals that are free of aliphatic unsaturation, $RO-$, $RCOO-$, $R_2C=N-O-$, $R-C=N-O-$ or $R'O(CH_2CH_2O)_m-$, R is hydrocarbon or haloalkyl radicals, R' is an alkyl, m is 1 or 2, R is divalent aliphatic or cycloaliphatic hydrocarbon radicals, R' is hydrogen or monovalent hydrocarbon radicals, Z is a tertiary amine radical, and X is a halogen atom as disclosed. An example of a quaternary ammonium salt is



The quaternary ammonium salts are useful as water repellents and as intermediates in making siloxanes which are useful as water repellents especially for cellulosic fabrics.

3,580,921

HETEROCYCLIC MESOIONIC COMPOUNDS

Donald P. Cameron, New London, Conn., assignor to Pfizer Inc., New York, N.Y.

No Drawing. Filed Sept. 20, 1968, Ser. No. 761,319

Int. Cl. C07d 91/54

U.S. Cl. 260—302

12 Claims

A series of novel aryl anhydro 1,2,3-thiadiazolium hydroxide bases and their acid addition salts have been prepared. The anhydro 4-hydroxy-3-(2-substituted phenyl)-1,2,3-thiadiazolium hydroxides produced are all active monoamine oxidase inhibitors and are useful in therapy as non-steroidal anti-inflammatory agents.

3,580,922

PHOSPHORYLATED HETEROCYCLIC COMPOUNDS

Glenn R. Price and Edward N. Walsh, Chicago Heights, Ill., assignors to Stauffer Chemical Company, New York, N.Y.


No Drawing. Filed Dec. 28, 1964, Ser. No. 421,609

Int. Cl. C07f 9/08, 9/16

U.S. Cl. 260—304

6 Claims

Heterocyclic compounds containing thiophosphatoalkyl groups, useful as herbicides, having formula



where R and R' are lower alkyl, X is oxygen or sulfur, R'' is H or lower alkyl, Q is ethylene, propylene, or phenylene.

3,580,923

RESOLUTION PROCESS

Thomas Leigh, Macclesfield, England, assignor to Imperial Chemical Industries Limited, London, England
No Drawing. Filed Jan. 22, 1969, Ser. No. 793,157
Claims priority, application Great Britain, Feb. 14, 1968, 7,321/68

Int. Cl. C07d 99/06

U.S. Cl. 260—306.7

4 Claims

A process for the resolution of racemic tetramisole, a known anthelmintic agent, to produce the (—)-tetramisole, by formation of a salt with an arenesulphonyl-L-pyrogutamic acid or a di-aryl-(+)-tartaric acid.

3,580,924

2-DIPHENYLBENZOXAZOLES

Rudolf Anliker, Binningen, Max Duennenberger, Frenken-dorf, Karl Schmid, Reinach, Basel-Land, and Adolf Emil Siegrist, Basel, Switzerland, assignors to Ciba Limited, Basel, Switzerland

No Drawing. Filed Dec. 27, 1966, Ser. No. 604,584
Claims priority, application Switzerland, Jan. 7, 1966, 196/66

Int. Cl. C07d 85/48

U.S. Cl. 260—307

4 Claims

2-(diphenyl)-benzoxazoles useful as scintillator substances.

3,580,925

IMIDAZOLE PREPARATION

Philip Manos, Wilmington, Del., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
No Drawing. Original application May 23, 1966, Ser. No. 551,872. Divided and this application Dec. 26, 1968, Ser. No. 787,248

Int. Cl. C07d 49/00

U.S. Cl. 260—309

3 Claims

The preparation of benzils from benzoin by reacting the benzoin with a cupric carboxylate catalyst in the presence of a solvent of acetic acid or a water-miscible alcohol at a temperature of 20° to 130° C. while passing oxygen into the reaction mixture. The preparation of imidazoles from benzils by adding, to the reaction mixture in the preceding sentence, ammonia or a weak acid salt thereof and a benzaldehyde.

3,580,926

CARBAZOLE-4-ALKANOIC ACIDS AND TETRAHYDROCARBAZOLE-4-ALKANOIC ACIDS

Franklin W. Short, Saline, Mich., assignor to Parke, Davis & Company, Detroit, Mich.

No Drawing. Filed Nov. 10, 1969, Ser. No. 875,559

Int. Cl. C07d 27/68

U.S. Cl. 260—315

5 Claims

9-phenylcarbazole-4-acetic acid and 5,6,7,8-tetrahydro-9-phenylcarbazole-4-acetic acid; o-fluoro, o-chloro, and α -methyl derivatives; and carboxylate salts of the foregoing compounds. The products are anti-inflammatory agents useful in relieving or preventing inflammation. They can be produced from the corresponding lower alkyl esters by hydrolysis. The intermediates can be produced from hexahydrodibenzofuran-1(2H)-one by reaction with aniline or a substituted aniline, introduction of an alkanolic acid ester side-chain, and dehydrogenation in the ring system.

3,580,927

ULTRAVIOLET LIGHT INHIBITORS

Robert L. Wear, West St. Paul, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

No Drawing. Filed Nov. 24, 1967, Ser. No. 685,329

Int. Cl. C07d 3/00; C07c 49/82

U.S. Cl. 260—333


3 Claims

Ultraviolet light absorbers with extremely low volatility are prepared by reacting 2,4-dihydroxybenzophenone and

siloxane compositions containing the same as cross-linking agents which are storage-stable in the absence of moisture but cure rapidly at ambient temperature in the presence of moisture.

3,580,940 TRISILYLALKANES

James A. Webster, Dayton, Ohio, assignor to Monsanto Research Company, St. Louis, Mo.
No Drawing. Filed Aug. 25, 1969, Ser. No. 852,869
Int. Cl. C07f 7/02; C10m 1/50
U.S. Cl. 260-448.2 2 Claims



where $x=2-6$, useful as functional fluids. The areas of utility are heat-exchange media, gyro fluids, lubricants, anti-corrosive agents and viscosity-index improvers.

3,580,941 AMINOCYCLOTETRASILOZANES

Christopher A. Pearce and Norman C. Lloyd, Glamorgan, Wales, assignors to Midland Silicones Limited, Reading, England
No Drawing. Original application May 21, 1968, Ser. No. 730,940, now Patent No. 3,518,290, dated June 30, 1970. Divided and this application Feb. 19, 1970, Ser. No. 12,836
Claims priority, application Great Britain, May 26, 1967, 24,693/67
Int. Cl. C07f 7/02

U.S. Cl. 260-448.2 3 Claims
Novei compositions of matter and processes for preparing bicyclo- and aminocyclotetrasilazanes. The aminocyclotetrasilazanes are used to form bicyclotetrasilazanes by heating at temperatures above 210° C. under substantially anhydrous conditions.

3,580,942 CHLOROSULFONYL-TERT-BUTYLISOCYANATE AND ITS PREPARATION

Dieter Arlt, Cologne-Buchheim, Germany, assignor to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany
No Drawing. Filed June 18, 1968, Ser. No. 737,859
Claims priority, application Germany, June 21, 1967, F 52,748
Int. Cl. C07c 119/04

U.S. Cl. 260-453 2 Claims
2 - isocyanato - 2,2 - dimethyl-ethane-sulphonic acid chloride is prepared by reacting isobutylene and cyanogen chloride with chlorosulphonic acid or sulphur trioxide. This compound is suitable for the modification of polyurethanes, for reaction with reactive hydrogen containing compounds and it is particularly useful as a cross linking agent for photo lacquers.

3,580,943
DIBENZOCYCLOHEPTENE DERIVATIVES
Donald L. Trepanier, Indianapolis, Ind., assignor to The Dow Chemical Company, Midland, Mich.
No Drawing. Filed Sept. 3, 1968, Ser. No. 757,106
Int. Cl. C07c 121/64, 153/05, 159/00

U.S. Cl. 260-453 6 Claims
Dibenzocycloheptene derivatives such as methylthio 10,11 - dihydro - 5H - dibenzo(a,d)cycloheptene-Δ^{5,7}-butyrimide and the hydrohalide salts thereof such as the hydroiodide and hydrobromide salts. The compounds

are useful in the study of animal behavior and are particularly useful as central nervous system antidepressants and as agents for controlling the appetite of animals.

3,580,944 UNSATURATED ALKYL SULFAMATES AND METHOD OF PREPARATION

Robert W. Hill, Leawood, Kans., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
No Drawing. Filed Aug. 28, 1967, Ser. No. 663,568
Int. Cl. C07c 143/68; C08f 45/46

U.S. Cl. 260-456 4 Claims
Alkenyl sulfamates having 10 to 22 carbon atoms, such as erucyl sulfamate and oleyl sulfamate, are prepared by refluxing the correspond alkenol with sulfamide in a suitable solvent, such as dioxane, until evolution of ammonia ceases. These alkenyl sulfamates are useful as slip additives in mono-olefin polymers, such as polyethylene or polypropylene, when added in amounts from 0.005 to 1 percent by weight.


3,580,945 DERIVATIVES OF 2-OXOCYCLOPENTANE CARBOXYLIC ACID

Real Laliberte, Laval, Quebec, Canada, assignor to Ayerst, McKenna & Harrison, Ltd., St. Laurent, Quebec, Canada
No Drawing. Filed Mar. 21, 1969, Ser. No. 809,412
Int. Cl. C07c 121/46

U.S. Cl. 260-464 3 Claims
Lower alkyl esters of 2-oxocyclopentane carboxylic acid cyanoacethydrazone, prepared from the corresponding lower alkyl ester of 2-oxocyclopentane carboxylic acid and cyanoacethydrazide. The compounds are useful as anti-parasitic agents.

3,580,946
CYANO CONTAINING STYRYL DYESTUFFS
Kenneth Anderton, Manchester, England, assignor to Imperial Chemical Industries Limited, London, England
No Drawing. Filed Dec. 13, 1968, Ser. No. 783,767
Claims priority, application Great Britain, Dec. 29, 1967, 44,095/67; Sept. 17, 1968, 59,093/68
Int. Cl. C07c 121/50

U.S. Cl. 260-465 1 Claim
Water-insoluble styryl dyestuffs of the formula:




wherein R is —OR¹ or —NR²R³, R¹ is an optionally substituted hydrocarbon radical, R² and R³ are independently hydrogen or optionally substituted hydrocarbon, Y is hydrogen or alkyl, the benzene ring B may contain substituents, and m is 2 or 3; and the use of the said dyestuffs for colouring synthetic textile materials.

3,580,947
METHOD OF RETARDING POLYMERIZATION IN THE PROCESS FOR THE PRODUCTION OF METHACRYLIC ACID ESTERS
Masashi Ikeda and Masayoshi Inoue, Ohtake-shi, Japan, assignors to Mitsubishi Rayon Co., Ltd., Tokyo, Japan
No Drawing. Filed Oct. 26, 1967, Ser. No. 678,207
Claims priority, application Japan, Oct. 26, 1966, 41/70,254
Int. Cl. C07c 69/54

U.S. Cl. 260-486R 9 Claims
A method of retarding polymerization in the process for the production of methacrylic acid esters by the re-

action of acetone cyanhydrin or methacrylonitrile with sulfuric acid or fuming sulfuric acid and alcohol, said method being characterized by using as a polymerization-retarder a compound having in its molecular structure an organic ring system represented by





wherein X stands for sulfur, oxygen or nitrogen atom.

3,580,948
1,1-DICHLORO-1-NITROETHANE DERIVATIVES
Leo R. Morris, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.
No Drawing. Filed Aug. 1, 1968, Ser. No. 749,317
Int. Cl. C07c 69/22, 79/12

U.S. Cl. 260-487 4 Claims
Disclosed are, as new compounds, α-(2,2-dichloro-2-nitroethyl)styrene, (1,3,3-trichloro-3-nitropropyl)benzene, and lower alkyl 2,4,4-trichloro-2-methyl-4-nitrobutyrates which are useful as pesticides.

3,580,949
N,N'-BIS-(AMINOALKYL)-BENZYL-AMINES
Vsevolod Gruenman, Montclair, Max Hoffer, Nutley, Jay Philip O'Brien, Irvington, and Albert Israel Rachlin, Verona, N.J., and Gerhard Zbinden, Cambridge, England, assignors to Hoffmann-La Roche Inc., Nutley, N.J.
No Drawing. Original application Mar. 19, 1965, Ser. No. 441,333, now Patent No. 3,382,260, dated May 7, 1968. Divided and this application Nov. 13, 1967, Ser. No. 682,522
Int. Cl. C07c 87/28

U.S. Cl. 260-570.5 2 Claims
N,N¹ - (iminodialkylene)benzenesulfonamides, N,N¹ - (alkylenediiminodialkylene)benzenesulfonamides and derivatives thereof, effective against tachycardia and arrhythmia in both auricular and ventricular tissues, are prepared, for example, from an intermediate of the formula



wherein R₁' and R₄' are hydrogen, lower alkyl, protected amino group or amino group precursor; R₂ and R₃ are hydrogen or lower alkyl; X is chlorine or bromine; n₁ and p₁ are each 2 or 3; N is from 1 to 3, and m₁ is from 2 to 4.

3,580,950
CHELATING COMPOSITIONS BASED ON CHELATING ACIDS AND AMINES
Frederick C. Bersworth, 120 Washington St., East Orange, N.J. 07017

Continuation-in-part of applications Ser. No. 580,829, Sept. 20, 1966, now Patent No. 3,351,758, and Ser. No. 588,224, Oct. 20, 1966, now abandoned, and a continuation of application Ser. No. 468,182, June 4, 1965, now abandoned, which is a continuation of applications Ser. No. 446,120, Apr. 6, 1965, and Ser. No. 466,090, June 24, 1965, now abandoned, which in turn is a continuation-in-part of applications Ser. No. 88,604, Feb. 13, 1961, now abandoned, and Ser. No. 88,606, Feb. 13, 1961, now abandoned. This application Nov. 1, 1967, Ser. No. 679,626

Int. Cl. C07c 101/26 5 Claims
U.S. Cl. 260-534
Chelating acids based on the synthetic polyamino polycarboxylic acids are reacted with amino compounds, such as ethylene diamine, ethanolamine, hexamethylene diamine, and polyamines of such linear structure to form reaction products carrying amino structures in relation to the synthetic amino acid starting material, such that effective chelators for iron and other transition metals are formed.

3,580,951
PREPARATION OF FLUOROANILINES
John W. Churchill and Ehrenfried H. Kober, Hamden, Peter H. Scott, Guilford, and Curtis P. Smith, Cheshire, Conn., assignors to Olin Mathieson Chemical Corporation
No Drawing. Filed Jan. 10, 1969, Ser. No. 790,444
Int. Cl. C07c 85/10

U.S. Cl. 260-580 6 Claims
Fluoroanilines are prepared by the deoxygenation and hydrofluorination of the corresponding nitrobenzenes which are reacted in anhydrous hydrogen fluoride and in an atmosphere of carbon monoxide at 0° to 230° C. under pressures of from 15 to 3000 p.s.i.a. in the presence of certain deoxygenating agents containing phosphorus or sulfur.

3,580,952
PROCESS FOR PURIFYING POLYETHER AMINES
Albrecht Moschel, Kelkheim, Taunus, Germany, assignor to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Filed Jan. 11, 1968, Ser. No. 697,016
Claims priority, application Germany, Jan. 18, 1967, F 51,273
Int. Cl. C07c 89/04

U.S. Cl. 260-584 3 Claims
A process for purification of polyether amines by removing oxides, salts or complex compounds of nickel or cobalt therefrom, which comprises stirring 1 to 500 percent by volume of a lower alkanol and 0.05 to 10 percent by volume of water into the crude product, adding an inert solid drying agent, filtering off the solid substances, removing the alkanol, and heating the product until the weight remains constant.

3,580,953
PREPARATION OF 3 - ENDO-METHYL - 3-EXO(4'-METHYL-5'-HYDROXYPENTYL) NORCAMPHOR FROM 2-METHYL-4-PENTENOL
Wayne I. Fanta and William F. Erman, Springfield Township, Hamilton County, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
No Drawing. Filed Mar. 29, 1968, Ser. No. 717,362
Int. Cl. C07c 49/27

U.S. Cl. 260-586R 14 Claims
Process for preparing 3-endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl)norcamphor from 2-methyl-4-pentenol

comprising the steps of: (1) esterifying 2-methyl-4-pentenol; (2) hydrobrominating the ester in the presence of a free radical catalyst; (3) reducing the hydrobrominated ester to 2-methyl-5-bromopentanol; (4) borating the 2-methyl-5-bromopentanol with boric acid and/or boric anhydride to obtain tri(2-methyl-5-bromopentyl)borate; and (5) alkylating 3-methylnorcamphor with the tri(2-methyl-5-bromopentyl)borate and, subsequently, hydrolyzing the reaction product to obtain 3-endo-methyl-3-exo-(4'-methyl-5'-hydroxypentyl) norcamphor.

3,580,954

PREPARATION OF 3-ENDO-METHYL-3-EXO-(4'-METHYL-5'-HYDROXYPENTYL) NORCAMPHOR FROM 2-METHYL-4-PENTENOL

Wayne I. Fanta and William F. Erman, Springfield Township, Hamilton County, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
No Drawing. Filed Mar. 29, 1968, Ser. No. 717,374
Int. Cl. C07c 49/27

U.S. Cl. 260—586R

14 Claims

Process for preparing 3-endo-methyl-3-exo-(4'-methyl-5'-hydroxypentyl)norcamphor from 2-methyl-4-pentenol comprising the steps of (1) borating 2-methyl-4-pentenol with boric acid and/or boric anhydride to obtain tri(2-methyl-4-pentenyl)borate; (2) hydrobrominating the tri(2-methyl-4-pentenyl)borate in the presence of a free radical catalyst and, subsequently, hydrolyzing the reaction product to obtain 2-methyl-5-bromopentanol; (3) etherifying 2-methyl-5-bromopentanol with dihydropyran to obtain 2-methyl-5-bromopentyl tetrahydropyranyl ether; (4) alkylating 3-methylnorcamphor with the 2-methyl-5-bromopentyl tetrahydropyranyl ether to obtain tetrahydropyranyl ether of 3-endo-methyl-3-exo-(4'-methyl-5'-hydroxypentyl)norcamphor; and (5) treating tetrahydropyranyl ether of 3-endo-methyl-3-exo-(4'-methyl-5'-hydroxypentyl)norcamphor with p-toluenesulfonic acid or hydrochloric acid to obtain 3-endo-methyl-3-exo-(4'-methyl-5'-hydroxypentyl)norcamphor.

3,580,955

AUTO-OXIDATION OF ALDEHYDES IN THE PRESENCE OF ACYLATING AGENTS

Richard Anthony Bafford, Tonawanda, N.Y., assignor to Pennwalt Corporation
No Drawing. Filed Apr. 18, 1968, Ser. No. 722,166
Int. Cl. C07c 73/02

U.S. Cl. 260—610

5 Claims

Peroxy compounds are prepared by reacting free-oxygen, an aldehyde, an organic compound containing active halogen and an acid acceptor, under anhydrous conditions, at a temperature below the decomposition temperature of the desired acylperoxy product.

3,580,956

HYDROXYLATION OF AROMATIC COMPOUNDS

Herman S. Bloch, Skokie, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.
No Drawing. Filed Nov. 3, 1967, Ser. No. 680,311
Int. Cl. C07c 37/00, 39/00, 39/06

U.S. Cl. 260—621

9 Claims

The hydroxylation of an aromatic compound wherein an aromatic compound is reacted with hydrogen peroxide in contact with an acidic crystalline aluminosilicate catalyst at hydroxylation conditions. The aromatic compound is employed in molar excess with respect to hydrogen peroxide, and the catalyst contains a rare-earth metallic component.

3,580,957

PREPARATION OF TETRAFLUOROETHYLENE ETHYLENES

Herman S. Bloch, Skokie, Ill., assignor to Universal Oil Products Company, Des Plaines, Ill.
No Drawing. Filed Aug. 6, 1969, Ser. No. 848,104
Int. Cl. C07c 21/18

U.S. Cl. 260—653.5

10 Claims

Tetrahalo-substituted ethylenes in which all of the halo substituents are identical halogens may be prepared by treating a mixed hexahalo ethane in which at least four of the halogen substituents are identical with a free radical generating catalyst at elevated temperatures in the presence of a hydrocarbon solvent. The tetrahalo-substituted ethylenes are useful as starting materials for the preparation of polymeric substances.

3,580,958

PROCESS FOR THE PRODUCTION OF ACETYLENE

Herbert Baader, Hermulheim, near Cologne, and Kurt Sennwald, Knapsack, near Cologne, Germany, assignors to Knapsack Aktiengesellschaft, Knapsack, near Cologne, Germany
No Drawing. Continuation of application Ser. No. 634,667, Apr. 28, 1967. This application Nov. 3, 1969, Ser. No. 871,595
Claims priority, application Germany, June 1, 1966, K 59,410
Int. Cl. C07c 11/24

U.S. Cl. 260—679

6 Claims

Acetylene is produced by subjecting a dihalogenoethane and/or a vinyl halide to dehydrohalogenation comprising passing the dihalogenoethane and/or the vinyl halide at a temperature between 400 and 850° C. over a catalyst formed of chlorides of the metals comprising lithium, beryllium, magnesium, calcium, strontium, barium, cerium, antimony, copper, silver, gold, zinc, cadmium, mercury, titanium, chromium, manganese, iron, cobalt, nickel, palladium and platinum, the chlorides being used alone or in combination and being deposited on a carrier, if desired.


3,580,959

PROCESS AND APPARATUS FOR PROCESS CONTROL IN CRACKING FURNACES FOR THE THERMAL CRACKING OF HYDROCARBONS

Armin Dörner, Munich, Germany, assignor to Linde Aktiengesellschaft, Wiesbaden, Germany
Filed Oct. 12, 1967, Ser. No. 674,965
Claims priority, application Germany, Oct. 12, 1966, P 15 68 966.4
Int. Cl. C07c 3/30; C07g 9/14, 9/20

U.S. Cl. 260—683

5 Claims



In cracking furnaces for hydrocarbons, having two heating zones—a radiation zone heated by combustion gases, and a convection zone heated by flue gases, the improvements of limiting the extent of preheating of the feed in the convection zone by: (A) water-cooled cooling coils in the convection zone; or (B) by passing a portion of the flue gases around the convection zone; or passing

only a portion of the feed into the convection zone and mixing said portion with cold feed before entering the combustion zone.

3,580,960

DEHYDROGENATION CATALYST

Ian Montgomery Keen, Wealdstone, Harrow, Peter James Craig, Sunbury, and Christopher Patrick Cadman Bradshaw, Hampton, England, assignors to The British Petroleum Company Limited, London, England
No Drawing. Filed June 18, 1969, Ser. No. 834,557
Claims priority, application Great Britain, July 29, 1968, 35,992/68
Int. Cl. B01j 11/08; C07c 5/18

U.S. Cl. 260—683.3

21 Claims

Dehydrogenation catalyst, suitable for the dehydrogenation of alkanes to alkenes, is prepared by ion exchanging a platinum group metal onto a felspar support, preferably albite.


3,580,961

PROCESS FOR PREPARING ISOBUTENE AND THE APPARATUS THEREFOR

Eugene D. Guth, Palos Verdes Estates, Jerry L. Lewis, Cypress, and Leslie J. Van Nice, Manhattan Beach, Calif., assignors to TRW Inc., Redondo Beach, Calif.
Filed July 22, 1969, Ser. No. 843,370
Int. Cl. C07c 5/18, 3/00

U.S. Cl. 260—683.3

35 Claims



This invention relates to a continuous process for preparing an olefin product comprising prevailing amounts of isobutene and the apparatus therefor under substantially adiabatic conditions. Specifically, the process comprises the oxidation of at least one sulfur-containing compound e.g. hydrogen sulfide in the oxidation-reaction zone of a substantially adiabatic reactor, at temperatures ranging up to about 4500° F. and at pressures ranging up to about 1500 p.s.i.a. The oxidation-reaction products passing from the oxidation-reaction zone of said reactor are brought in direct contact and mixed with hydrocarbons containing a substantial amount of isobutane. The isobutane is converted to isobutene in the dehydrogenation-reaction zone of the same reactor. The dehydrogenation of the isobutane is carried out in the presence of the oxidation-reaction products at mixing temperatures which may range up to about 4500° F., at pressures ranging up to about 1400 p.s.i.a. and for a contact or reaction time ranging up to about 60 seconds. The reactor wherein the reactions take place comprises a substantially cylindrical vessel having a plurality of reaction zones. The first of said reaction zones comprises means for receiving combustible materials and is substantially surrounded by a coolant. The second of said reaction zones is insulated and has means for controlling the relative pressures between the first and second zones. The reactor has on its outer periphery means for carrying hydrocarbons into the area of the dehydrogenation zone wherein said hydrocarbons are converted to olefins.


3,580,962

ALKYLATION PROCESS EMPLOYING FLASH VAPORIZATION OF EXTRACTED AND ACID-TREATED ABSORPTION PRODUCT

Henry D. Moorer, Richmond, Va., Ralph M. Lewis, Weston, Conn., and Richard W. Stokeld, Jr., Wappingers Falls, N.Y., assignors to Texaco Inc., New York, N.Y.
Filed June 30, 1969, Ser. No. 837,791
Int. Cl. C07c 3/54

U.S. Cl. 260—683.62

6 Claims



Method for refrigeration of a sulfuric acid alkylation process operated in conjunction with an associated acid recovery process involving reacting used acid with olefin feed in an absorber, extracting resulting dialkyl sulfates, acid treating the extract solution and passing the treated solution to alkylation. The acid treated extract solution is vaporized and passed in indirect exchange with contents of absorber and alkylation reactor. Vaporized isobutane may be separated, recompressed, cooled and returned as a liquid for combination with the acid treated extract stream for additional cooling capacity.

3,580,963

VAPOR DEPOSITED METAL POLYESTER POLYCONDENSATION CATALYSTS

Herbert Kurzke, Bobingen, Wolfgang Goltner, Kriftel, Taunus, and Walter Seifried, Wiesbaden, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Continuation of application Ser. No. 481,396, Aug. 20, 1965. This application Aug. 1, 1969, Ser. No. 849,578
Claims priority, application Germany, Aug. 22, 1964, F 43,809
Int. Cl. C08g 17/015, 39/10

U.S. Cl. 260—860

4 Claims

A process has been provided for dispersing solids in a liquid or a melt by combining a solid to be dispersed with a solid organic carrier which is soluble in the liquid or melt and introducing the combination of the solid and the solid organic carrier material into the liquid or melt whereby the solid organic carrier material is dissolved, and thereby the solid is accordingly dispersed in the liquid or melt.

3,580,964

CURABLE LINEAR POLYESTERS

Gary L. Driscoll, Boothwyn, Pa., assignor to Sun Oil Company, Philadelphia, Pa.
No Drawing. Continuation-in-part of abandoned application Ser. No. 629,376, Apr. 10, 1967. This application Sept. 6, 1967, Ser. No. 665,711
Int. Cl. C08g 17/10, 17/12; C08f 21/02

U.S. Cl. 260—871

21 Claims

Curable polyesters containing an adamantane moiety are prepared in one- or two-stage condensation type reactions. The polyesters are prepared from a hydrocarbon

substituted adamantane diol and anhydride of unsaturated diacids such as maleic acid alone or with a second diol such as ethylene glycol. In addition to the anhydrides of unsaturated diacids, the polyester can contain saturated diacid moieties. The polyesters so prepared can be cross-linked with a conventional crosslinking agent and curable polymer can be cast into sheets or films and cured. The curable blend can be used as a coating and cured in place to give chemical-resistant surfaces. The crosslinked polymers exhibit extremely good hydrolytic and solvent stability with good heat and ultraviolet stability.

3,580,965
THERMOPLASTIC POLYESTER MOLDING COMPOSITIONS CONTAINING OLEFIN-VINYL ESTER COPOLYMERS

Ludwig Brinkmann, Frankfurt am Main, Harald Cherdron, Wiesbaden, and Walter Herwig, Frankfurt am Main, Germany, assignors to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning, Frankfurt am Main, Germany
No Drawing. Filed July 11, 1968, Ser. No. 743,946
Claims priority, application Germany, July 18, 1967, F 52,991

Int. Cl. C08g 39/04

U.S. Cl. 260—873 11 Claims
Molding compositions which can be processed thermoplastically are prepared from a mixture of linear saturated polyesters and α -olefin-vinyl ester copolymers and are distinguished by a high impact strength.

3,580,966
GRAFT COPOLYMERS OF ACRYLONITRILE ONTO A LINEAR POLYETHER HAVING QUATERNISED NITROGEN ATOMS

Helmuth Engelhard, Leverkusen, Francis Bentz, Cologne, and Heinrich Rinkler and Günther Nischk, Dormagen, Germany, assignors to Farbenfabriken Bayer Aktiengesellschaft, Leverkusen, Germany
No Drawing. Filed Dec. 26, 1968, Ser. No. 787,222
Claims priority, application Germany, Jan. 4, 1968, P 17 20 771.5

Int. Cl. C08f 29/56

U.S. Cl. 260—898 6 Claims
The invention relates to an acrylonitrile graft polymer having improved affinity for acid dyes comprising acrylonitrile being graft-polymerised together with other acrylic or vinyl monomers and a linear polyether having quaternised nitrogen atoms as graft base. The graft base has a molecular weight of about 1,000 to about 15,000 and the acrylonitrile graft polymer has a K-value (according to Fikentscher, Cellulose Chemie 13, (1932), page 58) of from 70 to 100. In the process of preparing said acrylonitrile graft polymer acrylonitrile and other copolymerisable comonomers are graft-polymerised in the presence of a graft base consisting of a linear polyether having quaternised nitrogen atoms.

3,580,967
SUBSTITUTED 2-AMINOMALONAMIDES PRODUCTION

John R. Norell, Bartlesville, Okla., assignor to Phillips Petroleum Company
No Drawing. Continuation-in-part of application Ser. No. 560,859, June 27, 1966. This application Jan. 31, 1969, Ser. No. 795,676

Int. Cl. C07c 103/33

U.S. Cl. 260—557 8 Claims
Production of 2-aminomalonamides having hydrocarbyl substituents, which amides are useful as pharmaceutical and agricultural chemicals, antiplasticizers, processing aids and the like, by the reaction of olefins, hydrogen cyanide and anhydrous hydrogen fluoride followed by hydrolysis.

3,580,968
PROCESS FOR PREPARING N,N-DIALKYL-ACRYLAMIDES

Michio Kuraishi, Setunobu Asano, and Nobuo Isogai, Niigata-shi, Japan, assignors to Japan Gas-Chemical Company, Inc., Tokyo, Japan
No Drawing. Filed Apr. 30, 1969, Ser. No. 820,617
Claims priority, application Japan, May 9, 1968, 43/31,096

Int. Cl. C07c 103/00

U.S. Cl. 260—561R 6 Claims
N,N-dimethylacrylamides are prepared with commercial advantages by reacting trimethylamine with lower fatty acids or esters thereof or compounds capable of forming said acids or esters by reaction with carbon monoxide at elevated temperatures and under high pressures and in the presence of metal carbonyls, e.g. aliphatic alcohols and ethers, and with carbon monoxide at elevated temperatures and under high pressures in the presence of metal carbonyls either singly or in combination with halogens or halogen compounds.

3,580,969
DEHYDROGENATION OF OLEFINS

George J. Nolan and Vernon C. F. Holm, Bartlesville, Okla., assignors to Phillips Petroleum Company
No Drawing. Filed Jan. 8, 1968, Ser. No. 696,146

Int. Cl. C07c 5/18

U.S. Cl. 260—666 4 Claims
Improvements in hydrocarbon dehydrogenation are realized by the use of a catalyst comprising tin and/or a tin compound supported on an aluminum phosphate.

3,580,970
DEHYDROGENATION OF CYCLOALIPHATIC KETONES AND ALCOHOLS

Harold E. Swift, Gibsonia, Pa., assignor to Gulf Research & Development Company, Pittsburgh, Pa.
Continuation-in-part of application Ser. No. 506,479, Nov. 5, 1965. This application Nov. 22, 1967, Ser. No. 689,233

Int. Cl. C07c 39/00, 39/02, 39/12

U.S. Cl. 260—621H 9 Claims
Cycloaliphatic ketones and alcohols are dehydrogenated to the corresponding hydroxyaromatic compounds at elevated temperatures in the presence of a novel nickel-tin catalyst.

3,580,971
THIXOTROPIC ORGANOPOLYSILOXANE COMPOSITIONS HAVING PENDANT METHACRYLIC ACID POLYMER

John Charles Getson, Tecumseh, Mich., assignor to Stauffer-Wacker Silicone Corporation, Adrian, Mich.
No Drawing. Filed Aug. 13, 1969, Ser. No. 849,920

Int. Cl. C08g 47/10

U.S. Cl. 260—825 6 Claims
Polymethacrylic acid graft modified siloxanes which exhibit thixotropic properties.

3,580,972
COATING COMPOSITION OF A MIXTURE OF A VINYL ESTER OF AN ALIPHATIC ACID-CARBOXYLIC ACID COPOLYMER AND A TERPOLYMER OF A VINYL ESTER OF AN ALIPHATIC ACID, A CARBOXYLIC ACID ESTER AND A CARBOXYLIC ACID

Robert A. Isaksen, Longmeadow, and Robert V. De Shay, East Longmeadow, Mass., assignors to Monsanto Company, St. Louis, Mo.
No Drawing. Continuation-in-part of application Ser. No. 617,453, Feb. 21, 1967. This application Aug. 7, 1969, Ser. No. 848,354

Int. Cl. C08g 45/04; C08f 29/50

U.S. Cl. 260—836 12 Claims
A first interpolymer of 0.5 to 10 mol percent of an ethylenically unsaturated mono- or poly-carboxylic acid

and 99.5 to 90 mol percent of a vinylidene ester of a saturated aliphatic acid is blended with a second interpolymer which acts as a polymeric plasticizer. Preferably, the first interpolymer is a copolymer of vinyl acetate and crotonic acid. The second interpolymer is comprised of 75 to 95 mol percent of a vinylidene ester of a saturated aliphatic acid (principally vinyl acetate), 5 to 25 mol percent of an ethylenically unsaturated mono- or poly-carboxylic acid having at least 75% of its carboxylic acid groups esterified with an aliphatic alcohol (principally dibutyl maleate), 0.5 to 10 mol percent of an ethylenically unsaturated mono- or poly-carboxylic acid (principally acrylic acid), and, optionally, zero to 3 mol percent of a glycidyl ester of an ethylenically unsaturated mono- or poly-carboxylic acid (principally glycidyl methacrylate). The interpolymer blend is useful for the protection of materials having at least one finished surface. When no longer needed, it may be removed from the substrate by washing with an aqueous alkaline solution.

3,580,973
POLYOXYMETHYLENE-FORMAL-CONTAINING POLYESTER BLOCK POLYMER

Daniel M. Kennedy, Jr., East Brunswick, and Carl Naeher Zellner, Berkeley Heights, N.J., assignors to Celanese Corporation, New York, N.Y.

No Drawing. Filed Dec. 18, 1967, Ser. No. 691,160

Int. Cl. C08g 17/06, 39/10, 51/58

U.S. Cl. 260—860 8 Claims
A novel process for the production of stabilized oxymethylene polymers is presented wherein a polyoxymethylene-polyester block polymer is prepared by reacting a linear, formal-containing polyester with trioxane under trioxane polymerization conditions.

3,580,974
NITRILE POLYMERIC BLENDS
Yoon Chai Lee and Quirino A. Tremontozzi, Springfield, Mass., assignors to Monsanto Company, St. Louis, Mo.
No Drawing. Filed Jan. 3, 1969, Ser. No. 788,963
The portion of the term of the patent subsequent to June 24, 1986, has been disclaimed

Int. Cl. C08f 37/18, 41/12

U.S. Cl. 260—876R 8 Claims
A polymeric blend is prepared from an acrylonitrile/isobutylene copolymer and a methacrylonitrile/isobutylene copolymer. The processing characteristics of the blend are very good, as is the balance of chemical and physical properties exhibited thereby.

3,580,975
VINYL HALIDE GRAFT POLYMERS
Leo E. Rademacher, Springfield, Mass., assignor to Monsanto Company, St. Louis, Mo.
No Drawing. Filed Sept. 21, 1967, Ser. No. 669,372

Int. Cl. C08f 15/00


U.S. Cl. 260—878 13 Claims
There is disclosed a process for preparing novel graft polymers of a vinyl halide and long-chain aliphatic vinyl compound on a rubbery olefin polymer. In accordance with the process, an aqueous dispersion is formed of a rubbery olefin polymer and a monomer formulation containing vinyl halide and a copolymerizable long-chain aliphatic vinyl monomer. Polymerization is effected in the resulting dispersion for a period of time sufficient to polymerize at least a substantial portion of the vinyl halide and aliphatic vinyl monomer present therein and produce grafting of at least a portion of the rubbery olefin polymer after which the copolymeric product is recovered. In the preferred process the faster reacting monomer is continuously added so as to maintain a higher ratio of the slower acting monomer in the dispersion.

ELECTRICAL

3,580,976

DEVICE FOR REGULATING THE TEMPERATURE OF GLASS AT THE OUTLET OF A VERY HIGH TEMPERATURE GLASS MELTING FURNACE
Jacques Marie Yves le Clerc de Bussy, Aumâtres, 80 Oisemont, France

Filed Jan. 26, 1970, Ser. No. 5,569
Claims priority, application France, Jan. 28, 1969, 6901615
Int. Cl. C03b 5/26, 5/30
U.S. Cl. 13—6 12 Claims




The regulating device provides at its outlet a glass whose temperature is adapted to the use of conventional feeders, notwithstanding the very high temperature prevailing in the furnace with which the device is associated. The glass flows through an extension which is surrounded by an enclosure which has, first, a heat-permeable wall for cooling the glass and, then, a heat-impermeable wall. A resistance corrects the temperature of the glass in the outlet by means of a control loop.

3,580,977

QUICK-CHANGE FIELD COIL ASSEMBLY FOR USE IN AN ELECTRODE HAVING A FLUID-COOLED ARCING SURFACE

George A. Kemeny, Export, and Charles B. Wolf, Irwin, Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.
Continuation-in-part of application Ser. No. 777,366, Nov. 20, 1968, now abandoned. This application Feb. 18, 1970, Ser. No. 12,269

Int. Cl. H05b 7/06, 7/10, 7/12
U.S. Cl. 13—18 19 Claims




An electrode has a detachable tip secured to a supporting column. The column includes fluid-channeling and electrically conducting tubes, electrically insulated from each other, extending at least a portion of the way therethrough toward the tip. Within the removable tip is a detachable magnetic field coil assembly including conduit extensions which, when the coil assembly is inserted in the electrode, are aligned with the tubes respectively. Male fittings engage contact finger assemblies and make good electrical connection. The fittings may be on the tubes and the contact finger assemblies may be on the conduit extensions, or the fittings may be on the conduit extensions and the contact finger assemblies may be secured to the ends of the tubes. Means carried by the column, or the conduit extensions including fittings or finger assemblies thereon, or both, provide fluid-tight seals for the cooling fluid flow circuit through the magnetic field coil.

ally conducting tubes, electrically insulated from each other, extending at least a portion of the way therethrough toward the tip. Within the removable tip is a detachable magnetic field coil assembly including conduit extensions which, when the coil assembly is inserted in the electrode, are aligned with the tubes respectively. Male fittings engage contact finger assemblies and make good electrical connection. The fittings may be on the tubes and the contact finger assemblies may be on the conduit extensions, or the fittings may be on the conduit extensions and the contact finger assemblies may be secured to the ends of the tubes. Means carried by the column, or the conduit extensions including fittings or finger assemblies thereon, or both, provide fluid-tight seals for the cooling fluid flow circuit through the magnetic field coil.

3,580,978

VISUAL DISPLAY METHOD AND APPARATUS
William C. Ebeling, Binghamton, N.Y., assignor to Singer-General Precision, Inc., Binghamton, N.Y.

Filed June 6, 1968, Ser. No. 735,109
Int. Cl. G09b 9/02; G06g 7/72
U.S. Cl. 35—10.2 46 Claims



Apparatus for generating a realistic wide-screen visual display for an aircraft simulator with realistic perspective throughout plural widely different phases of simulated flight by scanning a plurality of different successive types of transparencies with a flying spot scanner to derive video signals to drive television display projectors, including the scanning of a pair of transparencies to provide a background terrain elevation image without topographical features, scanning of a second type of transparency to provide an image of an airport or the like to be inset into the background image and distorting the inset image as simulated range and elevation angle from the airport vary, scanning a third type of transparency to provide a different type of inset image during simulated approach and landing and distorting that inset image in accordance with deviation of the simulated aircraft from a reference glideslope, and scanning a fourth type of transparency to provide a panoramic view of the airport during simulated taxiing and parking maneuvers, with means for automatically controlling the successive scanning modes with signals from a flight computer.

3,580,979

ELECTRONIC MUSICAL KEYS WITH TOUCH RESPONSIVE VOLUME CONTROL EMPLOYING A MECHANICAL ELECTRICAL TRANSDUCER

Hiroshi Amano, Hamamatsu-shi, Japan, assignor to Nippon Gakki Seizo Kabushiki Kaisha, Nakazawa-cho, Hamamatsu-shi, Shizuoka-ken, Japan

Filed Aug. 8, 1969, Ser. No. 848,544
Claims priority, application Japan, Aug. 13, 1968, 43/57087
Int. Cl. G10h 3/00; G10c 3/12; G10b 3/12


U.S. Cl. 84—1.1 4 Claims
A keyboard device for an electronic musical instrument comprising a plurality of keys, a lever located under each of

MAY 25, 1971

ELECTRICAL


949

the keys, the lever being swingably supported at one end by a pivot shaft and provided with a weight at the other free end, a mechanical-electrical transducer including a movable magnetic sensor attached to the free end of the lever and a fixed magnet disposed in such position that the magnet applies varied effects on the sensor depending on the relative position thereof, a drive member fixed on the key to transmit the depression of the key to the lever, and a bridge rod fixed to the key to return the lever when the key is released, the lever being provided in relation to the pivot shaft with sufficient friction force to hold the lever in a depressed position in accordance with the key depressing strength.



3,580,980
DIODE KEYING SYSTEM FOR ELECTRONIC ORGAN
Dale M. Uetrecht, Cincinnati, Ohio, assignor to D. H. Baldwin Company, Cincinnati, Ohio

Filed Aug. 26, 1968, Ser. No. 755,043
Int. Cl. G10h 1/06
U.S. Cl. 84—1.22 32 Claims




The keying networks between continuously running square wave tone signal sources and the sound output system of an electronic organ each consist of an isolating diode gate for each source, followed by the parallel combination of at least two keying diode gates of simplified circuitry which either gate-through the square wave signal without change in wave shape (for odd-order-harmonic tones) or gate-through and modify the wave-shape into sawtooths (for full harmonic tones). A keyed activating circuit for the isolating diode gate and the keying diode gates corresponding to a selected key may contain a single key switch connected to a source of direct current and a common R-C attack network for two adjacent footage keying diode gates as well as for the parallel keying diode gates. A common coupler switch for coupling between keyboards is located between the direct current source and auxiliary key switches ganged respectively to the main key switches for a given manual, the auxiliary key switches being connected to a diode to isolate them from the main key switches in the coupled keyboard.

ERRATUM

For Class 174—10 see:
Patent No. 3,579,863

3,580,981
ELECTRICALLY CONDUCTIVE VENTILATING PANEL
Richard W. Lamp, Mendham; Joseph E. Kopf, Cranford; Donald P. Dravis, Roselle, and Robert A. Cuneo, Bergenfield, N.J., assignors to Technical Wire Products, Inc., Cranford, N.J.

Filed Oct. 14, 1969, Ser. No. 866,332
Int. Cl. H05h 9/00
U.S. Cl. 174—35 12 Claims




A framed electrically conductive honeycomb is provided by assembling an electrically conductive honeycomb, an electrically conductive frame for the honeycomb and an electrically conductive textile positioned between the frame and around the periphery of the outer cells of the honeycomb and in contact with both, and then coating the assembly in a metal plating bath to coat the assembly with a coating of an electrically conductive compound thereby assuring continuous mechanical, strong physical and electrical contact between the frame and the honeycomb, as well as a noncorrosion coating.

3,580,982

POLE RISER GUARD—BACK-UP PLATE COMBINATION
Jamshed Behram Havewala, Newark, Del., assignor to Haveg Industries, Inc., Wilmington, Del.


Filed Dec. 22, 1969, Ser. No. 887,135
Int. Cl. H02g 7/20
U.S. Cl. 174—45 8 Claims



A pole riser guard and backup plate combination which is attached to a power pole and surrounds electrical cable. The backup plate is generally channel-shaped and is secured to the pole and the guard extends over the backup plate and receives the backup plate therein whereby the cable is protected by the backup plate from instruments inserted between the guard and the pole.

3,580,983 CONDUCTIVE LINE TUBE


Isaac S. Jackson, Greenwich, N.Y., assignor to National Catheter Corp., Argyle, N.Y.
Filed Dec. 3, 1969, Ser. No. 881,750
Int. Cl. F161 1/12; H051 3/02
U.S. Cl. 174-47 10 Claims



The fabrication of conductive line tubing or electrically conductive medicosurgical tubes by extruding from a mass of flexible plastic material an elongated tube contemporaneous with the extrusion of an elongated electrically conductive plastic filament that is secured to said tube in superimposed relationship piggyback arrangement. The plastic material used to form the conductive line tubes is compounded from dielectric polymers while the filament is formed from a flexible electrically conductive plastic material. The extrusion of the tube and filament is continuous with the filament being secured to the tube subsequent to its withdrawal from an extrusion die.

3,580,984 SURFACE WIRING SYSTEMS

Knut Arnold Oscar Gladh, Sodertalje, Sweden, assignor to Gladol S.A., Geneva, Sweden
Filed Dec. 12, 1968, Ser. No. 783,314
Claims priority, application Sweden, Dec. 13, 1967, 17,105/67
Int. Cl. H02g 3/04
U.S. Cl. 174-48 3 Claims




A prefabricated system for electrical installations in buildings, apartments and the like, wherein at least six aluminum conductors are embedded in a core, said core is covered by a cover means in the form of a conventional floor or ceiling molding or a conventional doorcase and jointed at at least each corner and outlet of the installation, and wherein the material of the core is of substantially uniform thickness around the aluminum conductors embedded in the core.

3,580,985 CABLE CONNECTOR AND MEANS TO MANUFACTURE SAME

Helmut Rothfuss, and Horst Rode, Spahnacher, both of Germany, assignors to The Bunker-Ramo Corporation, Oak Brook, Ill.
Filed Mar. 26, 1969, Ser. No. 810,634
Claims priority, application Germany, Mar. 29, 1968, P 17 65 078.1
Int. Cl. H05k 1/08
U.S. Cl. 174-68.5 12 Claims

A novel cable connector and method of fabricating same is described wherein interconnecting conductor paths are defined on a printed circuit board, the board is perforated, a plug or socket connector is inserted in the perforations, and


the bare ends of feed cables are inserted into perforations adjacent the solder pins of the plug or socket connector. The entire assembly is then batch soldered, thus economically



and conveniently providing complete cable plug assemblies. A technique for rotatably mounting such completed cable plug assemblies is also described.

3,580,986 CORONA FREE COUPLING ASSEMBLY FOR COAXIAL CABLES

Donald O. Misare, Riverside, Ill., assignor to Joslyn Mfg. and Supply Co., Chicago, Ill.
Filed Oct. 22, 1969, Ser. No. 868,548
Int. Cl. H02g 15/08
U.S. Cl. 174-73 4 Claims




A corona free coupling assembly for high voltage coaxial cable comprising an elastomeric body of insulating material having an elongated bore for receiving end portions of the cables, tubular inner shield means embedded in the body in coaxial alignment with the bore and spaced from opposite ends thereof; a tubular connector sleeve is inserted into the bore within said inner shield means for connecting the central conductors in end-to-end relation; conductive spring means is mounted on the connector sleeve including a deflectable free end portion normally biased outwardly for contact against the inner shield means embedded in the elastomeric body. The spring means is deflectable inwardly against the sleeve while being inserted into the elastomeric body with the connected cables. An outer conductive shield means is provided around the insulated elastomeric body for connecting the outer shielding systems of the cables.

3,580,987 ELECTRIC CABLE

Paolo Gazzana Priaroggia, Milan, Italy, assignor to Pirelli Societa per Azioni, Milan, Italy
Filed Mar. 18, 1969, Ser. No. 808,240
Claims priority, application Italy, Mar. 26, 1968, Dec. 23, 1968, 14832A;25510A
Int. Cl. H01b 7/02
U.S. Cl. 174-120 9 Claims


Electric cable and process for its manufacture are disclosed. The electric cable has its electric conductor covered with extruded insulation comprising numerous layers of insu-

lating material, the number of such layers being more than two and preferably ranging between 5 and 100, and the ing against fraudulent subscription-receiver program reception in superior instead of inferior quality rendition; and to



thickness of each of such layers being not greater than 2 mm. and preferably ranging between 0.2 and 2 mm.


3,580,988
GROMMET FOR SPEAKER ENCLOSURE
Donald W. Orlowski, Glenview, and Donald S. Schroeder, Barrington, Ill., assignors to Ampex Corporation, Redwood City, Calif.
Filed Aug. 12, 1969, Ser. No. 849,423
Int. Cl. H01b 17/30; H04r 7/16; F161 5/02
U.S. Cl. 174-153 4 Claims



A resilient grommet for forming an airtight seal in an opening while permitting the airtight passage of an electrical cord through the opening. The grommet provides strain relief for the cord and is provided with a series of ribs to prevent pull-out.


3,580,989
SUBSCRIPTION TELEVISION SYSTEM UTILIZING A TRANSMISSION LINE FOR CONDUCTING EACH AESTHETIC QUALITY TELEVISION PROGRAM
Thomas A. Banning, Jr., Apt. 1408, 5500-5520 S. Shore Drive, Chicago, Ill.
Continuation-in-part of application Ser. No. 559,494, June 22, 1966, which is a continuation-in-part of application Ser. No. 490,402, Sept. 27, 1966, now Patent No. 3,478,162, which is a continuation-in-part of application Ser. No. 459,399, May 27, 1965, now Patent No. 3,365,542. This application May 19, 1967, Ser. No. 645,843
Int. Cl. H04n 1/32, 1/34
U.S. Cl. 178-5.1 13 Claims

A Subscription Television System, including simultaneous coaxial transmission of several different sending station programs through an attended control station, with switching apparatus at each subscription receiver enabling the control station attendant to deliver to the subscription receiver any subscriber-selected one of said programs in subscriber-selected aesthetic rendition quality, including inferior aesthetic quality without subscription charge, or a superior quality with subscription charge; including provisions assur-



assure subscriber-receiver reception of only the selected program, in the quality instructed to the attendant.

3,580,990
RECORDING AND REPRODUCING SYSTEM FOR COLOR VIDEO SIGNALS
Toshihiko Numakura, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan
Filed Nov. 13, 1968, Ser. No. 775,277
Claims priority, application Japan, Nov. 13, 1967, 42/72736
Int. Cl. H04n 9/32
U.S. Cl. 178-5.2 22 Claims




In recording a composite color video signal consisting of a luminance signal and a modulated chrominance signal having its frequency band contained within the luminance signal band, a carrier is frequency modulated with the luminance signal separated from the composite signal, the modulated chrominance signal separated from the composite original is frequency converted to have a frequency band juxtaposed to the lower limit of the bandwidth of the frequency-modulated luminance signal, and the latter is combined with the thus converted chrominance signal and with a pilot signal having a still lower bandwidth to provide a combined signal which is magnetically recorded. Upon magnetic reproduction of the combined signal thus recorded, the pilot signal, frequency-modulated luminance signal and converted chrominance signal are separately extracted from the reproduced signal, amplitude variations of the pilot signal are detected to control the amplitude of the converted chrominance signal which is reconverted to substantially its original frequency band by reference to the pilot signal, and the frequency-modulated luminance signal is demodulated and combined with the reconverted modulated chrominance signal to provide the composite color video signal.

3,580,991

AUTOMATIC TIME CORRECTION CIRCUIT FOR COLOR TV SIGNALS

Gerhard Krause, Darmstadt, Germany, assignor to Fernseh GmbH, Darmstadt, Germany
 Filed Apr. 1, 1969, Ser. No. 811,989
 Claims priority, application Germany, Apr. 3, 1968, P 17 74 082.8
 Int. Cl. H04n 5/21, 5/78, 9/12
 U.S. Cl. 178—5.4




An automatic time correction circuit for color TV signals which are received from a magnetic storage device, such as a tape, in which the delayed color TV signal is compared in phase with a first reference signal, then the compared output signal is again compared with a second reference signal and, the output from the second comparator is superimposed on the output of the first comparator.

3,580,992

MULTI-HEAD MAGNETIC RECORDING AND REPRODUCING DEVICE FOR VIDEO SIGNALS FEATURING HEAD SWITCHING IN THE RECORD MODE

Yasuhito Eguchi, Tokyo; Yoshio Fujiwara, and Takaaki Tohma, Kanagawa-Ken, Japan, assignors to Sony Corporation, Tokyo, Japan
 Filed June 18, 1968, Ser. No. 738,029
 Claims priority, application Japan, June 19, 1967, July 22, 1967, 43/39,158; Utility 43/63,429
 Int. Cl. H04m 5/78
 U.S. Cl. 178—6.6HS




In a magnetic recording and reproducing device having two rotary magnetic heads for recording and reproducing signals, such as video signals, in skew tracks traced across a magnetic tape by the heads, a switching circuit is provided which, during recording, alternately supplies the video signals to the heads in synchronism with the vertical synchronizing pulses included in the video signals. The video signals thus recorded in successive tracks have overlapping portions which either correspond to a very short recording period of the order of one horizontal period of the video signal and are contained in the vertical blanking period of the signal, or one of such overlapping portions is recorded at a substantially lower level than the other. In reproducing the video signals thus recorded, the outputs of the heads are merely combined.

3,580,993

MULTIPLE CAMERA SUPERIMPOSED MESSAGE CLOSED CIRCUIT TELEVISION SYSTEM

Robert E. Sandorf, and Robert A. Hammond, Canton, Ohio, assignors to Diebold, Incorporated, Canton, Ohio
 Filed Sept. 27, 1968, Ser. No. 763,193
 Int. Cl. H04n 5/22, 7/00, 7/18
 U.S. Cl. 178—6

4 Claims



A closed circuit television system advantageously used in conducting television banking services. The system has a plurality of camera viewed teller stations and a plurality of customer stations equipped with monitors. Any teller camera may be connected selectively with one of a plurality of the monitors. A message camera viewing an advertising message from the bank is incorporated in the system so that the same message is superimposed upon any of the teller camera scenes displayed at any of the customer receivers.


3,580,994

SIGNAL EDITING SYSTEM FOR MAGNETIC RECORDING AND REPRODUCING APPARATUS

Yoshiteru Kosaka, Kamakura, Japan, assignor to Victor Company of Japan, Limited, Yokohama, Japan
 Filed Nov. 25, 1968, Ser. No. 778,666
 Claims priority, application Japan, Nov. 27, 1967, 43/75,626; 43/75,627
 Int. Cl. G11b 5/04, 27/02; H04n 5/78

U.S. Cl. 178—6.6A

2 Claims




A signal editing system for magnetic recording and reproducing apparatus which records, on a magnetic tape on which one video signal is already recorded. The recording in either a second video signal from a television camera or video signals other than the second video signal, such as incoming signals of television receivers, for example. The new recording may start at a point on the magnetic tape which is halfway through the one video signal recorded thereon. The signal editing system provides means whereby the synchronizing signals of the two video signals can be brought into phase agreement with each other so that editing of the video signal can be effected without the occurrence of disturbance in synchronism.

3,580,995

CONSTANT SIZED HALFTONE DOT IMAGE GENERATOR

Richard J. Klensch, Trenton, N.J., assignor to RCA Corporation
 Filed Apr. 29, 1968, Ser. No. 725,041
 Int. Cl. H04m 5/84
 U.S. Cl. 178—6.7

8 Claims



A halftone image generator that simulates the continuous tones in an original pattern by producing a plurality of visually subliminal halftone dots of substantially the same size, with the coordinate spacings between the halftone dots being made dependent upon the density of the tones in the original pattern.


3,580,996

VIDEO LANDING AND DEPARTURE SYSTEM

Edward Stanton Maxey, 921 E Ocean Blvd., Stuart, Fla.
 Filed Oct. 17, 1968, Ser. No. 768,256
 Int. Cl. H04n 7/18

U.S. Cl. 178—6.8

20 Claims



A landing and departure system for aircraft, of particular utility in making blind landings at an airport. The system incorporates a closed circuit video system which provides a video display in an aircraft of a detailed model or mockup of the airport for use by the pilot in making the blind landing. In the system, the video camera and model mockup of the airport are moved relative to each other so that the line of sight view of the model airport, as seen by the camera, is the same as the line of sight view which would appear with clear visibility through the cockpit window to the eye of the pilot. The video camera is focused on the model and is movable along a track toward or away from the model in proportion to the approach or departure of the aircraft and simultaneously the model and camera are synchronously moved on tilt and rotating axes to provide a relationship between the camera and model airport in direct proportion to the position and altitude of the aircraft relative to the airport. Means are also provided to manipulate the camera in response to actual roll, pitch and yaw of the aircraft and to vary the video image accordingly. Appropriate ground and airborne electronic control means, such as radar, radio, continuous wave system,


etc. are utilized to sense and move the elements of the system. Also, information, such as actual elevation, distance to the runway and other critical information may be transmitted to the aircraft and displayed on the marginal edges of the video picture.

3,580,997

VIDEO SYSTEM FOR AUTOMATIC PRODUCTION LINE INSPECTION BY X-RAY

Thomas Alan Webb, Milford, and Jay A. Harvey, Fairfield, Conn., assignors to Balteau Electric Corporation, Stamford, Conn.
 Filed July 5, 1968, Ser. No. 742,948
 Int. Cl. H04n 1/38, 7/18
 U.S. Cl. 178—6.8

26 Claims




The disclosed system employs a television camera to convert the radiographic image produced by an irradiated test object to video signals which are processed and interpreted electronically without human interpretation. The video signals are processed to provide an indication of the radiographic density of a test object in relation to that of a reference object. When plural test objects are analyzed in succession and/or are in motion while being irradiated, a radiation mask having synchronizing and coding slots is used to coordinate the video signal processing circuitry to the scan of the TV camera.

3,580,998

VIDEO MULTIPLEXER-SWITCHER WITH SEQUENCE RECYCLING UPON LOSS OF VIDEO

Robert A. Hammond, Canton, and Eugene A. Presta, Louisville, Ohio, assignors to Diebold Incorporated, Canton, Ohio
 Filed Dec. 18, 1968, Ser. No. 784,619
 Int. Cl. H04n 7/02, 7/08, 7/18
 U.S. Cl. 178—6.8

5 Claims



A plurality of television cameras such as in a closed circuit television system for industrial plant security are provided

with a monitoring system including a control module and a plurality of switching modules, one for each camera, and also a single monitoring means such as a television receiver or a video tape recorder or both, at which signals or pictures from the cameras appear sequentially. The monitoring system includes means for enabling the picture from the cameras to be displayed at the monitor successively each for a selected desired length of time; or for enabling any camera to be removed in effect from the system by pressing a button; or for enabling any selected camera to remain connected to the monitor continuously or for any desired period of time merely by the operation of pushbuttons. Flexibility is provided in the system by utilizing monostable regenerative circuits in each video switching module to determine the length of time the corresponding camera remains operatively connected to the monitor and by successively triggering successive switching modules so that a system may be assembled with any desired number of cameras and switching modules. A bistable regenerative circuit is employed in the control module as a clock. Loss of synchronization between the cameras by the monitor is avoided by switching at electronic speeds.


3,580,999

REDUNDANCY REDUCTION DATA COMPRESSOR WITH LUMINANCE WEIGHTING

Frank W. Mounts, Colts Neck, N.Y., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.
Filed Dec. 23, 1968, Ser. No. 786,243
Int. Cl. H04n 7/12

U.S. Cl. 178-7.1

5 Claims



A redundancy reduction data compressor is described for processing a video signal having time subintervals called frames, the amplitude level of which signal is an indication of the luminance level in a scene being viewed. An entire frame of samples from the signal is stored in a frame memory. Each new sample from the signal is compared with its corresponding stored sample having the same time position within the frame. If the new sample is found to differ from the stored sample by more than a threshold level, the new sample is stored in a buffer memory to await transmission over a transmission channel. The threshold level is a function of the luminance level of the new sample and number of samples stored in the buffer memory, such that a sample from the high brightness region of the picture and/or a larger number of samples in the buffer memory result in a larger threshold level.

3,581,000

INCREMENTAL STEPPING PAPER DRIVE


Richard C. Hansen, Penfield; Charles J. Mahler, Fairport; Nicholas M. Soures, Webster, and Thomas L. Stickney, Rochester, all of N.Y., assignors to Xerox Corporation, Rochester, N.Y.

Filed Oct. 7, 1968, Ser. No. 765,538
Int. Cl. H04n 1/22; B65h 5/06

U.S. Cl. 178-7.6

11 Claims

An incremental stepping paper drive assembly for advancing a document or the like past a scanning station in a facsimile communication system. In combination with a binary digit encoder and buffer storage unit, the incremental



stepping paper drive assembly is activated and interrupted in accordance with the amount of information detected, encoded and stored in order to maintain maximum information transmission over a limited bandwidth transmission medium.


3,581,001

FACSIMILE SCANNER ASSEMBLY

Frans Brouwer, Glencoe, and Frank L. Sobchak, Chicago, Ill., assignors to Stewart-Warner Corporation, Chicago, Ill.
Division of Ser. No. 613,545, Feb. 2, 1967. Filed Dec. 1, 1969, Ser. No. 881,056
Int. Cl. H04n 1/24

U.S. Cl. 178-7.6

15 Claims



A scanner assembly for a facsimile transceiver in which three combination optical scanner and printer contact units are mounted on a specially designed timing belt trained about driven and idler pulleys. The belt comprises two narrow steel strips joined together by pin members which register with recesses in the pulleys. Each of the assemblies is detachable from the timing belt and includes means for separately adjusting the operating positions of the optical scanner and the printer contact with respect to the total assembly.

3,581,002


DISPLAY DEVICE FOR PROVIDING GRATICULES OF VARIOUS CONFIGURATIONS

Wellesley Jamison Dodds, Mt. Lakes, N.J., assignor to RCA Corporation

Filed Apr. 1, 1969, Ser. No. 811,861
Int. Cl. H04n 5/72

U.S. Cl. 178-7.84

10 Claims



A novel display device including a means for displaying a visual image to the view of an observer and a means for

providing a changeable graticule in front of the visual image in the view of the observer. The means for providing a changeable graticule includes a plurality of transparent electrode pairs with a liquid crystal material contained therebetween for displaying the graticule. Connection means for electrically energizing selected ones of the electrode pairs are provided.

3,581,003
KEYBOARD


William C. Leone, Palos Verdes Estates, and Robert Lee Malone, Palos Verdes Peninsula, Calif., assignors to Ex Cell-O Corporation, Detroit, Mich.

Filed Mar. 15, 1968, Ser. No. 713,343

Int. Cl. H04l 15/16; 17/02; B41j 5/08

U.S. Cl. 178-17

8 Claims



A keyboard for providing electrical output indications encoded in a preselected code in response to the operation of a key. Each key of the keyboard providing a light signal-transmitting path for transmitting light rays from a light source to an optical encoding element for transmission to a photoelectric means to provide the electrical output indications in accordance with a preselected code representative of an operated key. The keyboard includes gating circuit means for controlling the correct pattern of electrical output indications to be produced from the encoding element.

3,581,004

INVERTED SELECTOR MECHANISM


Arthur A. Hagstrom, Hoffman Estates, Ill., assignor to Teletype Corporation, Skokie, Ill.

Filed Oct. 24, 1968, Ser. No. 770,159

Int. Cl. H04l 17/16

U.S. Cl. 178-33

2 Claims



A selector mechanism including a line relay, a selector magnet, circuitry controlled by the line relay for energizing the selector magnet whenever the line relay is deenergized and vice versa, and means controlled by the selector magnet for producing a marking output whenever the selector magnet is deenergized and for producing a spacing output whenever the selector magnet is energized.

3,581,005

DELAYED ACTION TAPE FAILURE CONTROL FOR HIGH-SPEED TAPE PRINTER


John Fulton, Brookfield, Ill., assignor to Exel Corporation, Chicago, Ill.

Filed June 9, 1969, Ser. No. 831,516

Int. Cl. H04l 13/06

U.S. Cl. 178-42

4 Claims



A delayed action tape failure control for a high-speed tape printer, tape punch, or like machine actuated by recurring pulse signals, comprising a NAND gate and a NOR gate connected to the count and reset inputs, respectively, of a binary counter; the print pulse signals are applied to one input of each gate and a tape presence detector switch, located ahead of the print or punch mechanism, is connected to the other input of each gate. As long as tape is present, the counter is maintained in cleared condition and machine operation continues; when tape is absent, the counter counts print pulses and machine operation is interrupted when a given count is reached.

3,581,006

DUPLEX CONTROL CIRCUIT


Jacob L. Wallace, Jr., Springfield, Va., assignor to The Susquehanna Corporation, Fairfax County, Va.

Filed Mar. 22, 1968, Ser. No. 715,402

Int. Cl. H04l 5/14

U.S. Cl. 178-58


7 Claims



An example of the duplex control circuit is a circuit formed of two logic flip-flops connected between two channels of a half-duplex telegraph circuit. This duplex control circuit functions to prevent reflections or feedback of the transmissions into the inactive channel. Each channel is controlled by one of the flip-flops whereby the flip-flop controlling the inactive channel is set and locks this channel to a marking condition whenever a spacing signal is processed by the active channel and does not become reset until this spacing signal terminates at the input to the inactive channel.


3,581,007
MAGNETIC RECORDING AND REPRODUCING APPARATUS FOR COLOR TELEVISION SIGNALS USING A FREQUENCY MODULATED SUBCARRIER FOR THE TRANSMISSION OF THE COLOR INFORMATION
 Pierre Cassagne, Asnieres, France, assignor to Compagnie Francaise De Television
 Continuation of application Ser. No. 582,013, Sept. 26, 1966, now abandoned. This application Dec. 10, 1969, Ser. No. 880,484

Int. Cl. H04n 9/36
 U.S. Cl. 178—5.4 1 Claim




Magnetic recording and reproducing apparatus for a SECAM-type color television signal comprising a frequency modulated color subcarrier, wherein the color subcarrier is separated, brought to a constant amplitude and recorded together with either an auxiliary carrier frequency modulated by the lower frequency luminance components, or with the attenuated lower frequency luminance components themselves.

3,581,008
PULSE-TRANSMISSION SYSTEM
 Giorgio Dal Monte, Milan, and Nicola Pitidis, Milan, Italy, assignors to Societa Italiana Telecomunicazioni Siemens S.p.A., Milan, Italy
 Filed Sept. 26, 1968, Ser. No. 762,752
 Claims priority, application Italy, Sept. 27, 1967, 20935-A/67
 Int. Cl. H04l 25/02
 U.S. Cl. 178—63 10 Claims




Telecommunication system in which counting pulses or other short input signals are transmitted over a line by respective reversals of polarity which, at the receiving end, are detected and translated into a train of output pulses at a cadence corresponding to that of the train of input pulses giving rise to the polarity reversals.

3,581,009
DISTORTION MEASUREMENT CIRCUIT
 Erwin Schenk, Munich, Germany, assignor to Siemens Aktiengesellschaft, Berlin, Germany
 Filed Sept. 22, 1967, Ser. No. 669,743
 Claims priority, application Germany, Sept. 23, 1966, S106,065
 Int. Cl. H04l 1/00
 U.S. Cl. 178—69 5 Claims



A time distortion measurement circuit for use in conjunction with telegraphy apparatus wherein deviations from the theoretical time duration of steps corresponding to high speed telegraphic information transmission may be displayed on an oscilloscope. The distortion time, if any, of each telegraph information step is determined and stored so that a corresponding distortion indicating signal may be applied to the oscilloscope for a time interval equal to the time duration of the succeeding telegraph step. Thereby a distortion indicating signal of sufficient time duration to effect visual display of step time distortion is applied to the oscilloscope. Counting devices are employed that are responsive to a transition between successive steps and, more particularly, to a change in polarity of the applied telegraph signal, to produce control signals corresponding to their count that are stored and applied to the oscilloscope until the succeeding transition occurs. An indication of the actual time duration of the steps, and consequently of the percentage error between the actual time duration and the theoretical fixed time duration of the steps, is thereby obtained.


3,581,010
FRAME SYNCHRONIZATION SYSTEM FOR SYNCHRONIZING THE FRAME OF A DIGITAL SIGNAL TRANSMISSION
 Toshio Kobayashi, Yokohama-shi, Japan, assignor to Fujitsu Limited, Kawasaki, Japan
 Filed Nov. 14, 1967, Ser. No. 682,807
 Claims priority, application Japan, Nov. 18, 1966, 41-76012
 Int. Cl. H04l 7/08
 U.S. Cl. 178—69.5 6 Claims



A digital signal pulse train is supplied to a detector which detects the synchronous pattern of the pulse train. A pulse


distributor distributes the digital signal pulse train under the control of the detected synchronous pattern by forcibly resetting the frame of the distributed digital signal pulses when the frame of the digital signal pulse train is nonsynchronous and providing a reset pulse for resetting itself independently of the forcible resetting at least once per frame of the digital signal pulse train. A gate circuit connected between the detector and the pulse distributor prohibits further forcible resetting of the pulse distributor until the next succeeding frame of the digital signal pulse train.

3,581,011
TELEVISION BROADCAST SYNCHRONIZING APPARATUS AND METHOD
 Ronald C. Ward, Salt Lake City, and David T. Allen, Provo, Utah, assignors to Telemation, Inc., Salt Lake City, Utah
 Continuation of application Ser. No. 677,286, Oct. 23, 1967, now abandoned. This application July 28, 1969, Ser. No. 848,142
 Int. Cl. H04n 5/04
 U.S. Cl. 178—69.5TV 25 Claims



A high-quality television synchronizing system, including method and apparatus, which uses a high clock or oscillator frequency and causes, solely through division of frequency, each leading and trailing edge of all sync. generator output pulses to be accurately clock-derived. In this way, inter alia, very meaningful improvements in black and white, and color time base stability, including far better color subcarrier phase stability, are attained and need for time adjustment capability is removed. Superior sync. lock characteristics are also provided.


3,581,012
UNIDIRECTIONAL MICROPHONE
 Kanesuke Kishi; Noboru Tsuchiya, Kanagawa-ken, and Kazuo Shimura, Tokyo, Japan, assignors to Sony Corporation, Tokyo, Japan
 Filed July 3, 1968, Ser. No. 742,378
 Claims priority, application Japan, July 13, 1967, 42/45210
 Int. Cl. H04r 1/20
 U.S. Cl. 179—1 6 Claims



A unidirectional microphone in which a second order gradient microphone and a wave-type microphone are combined so as to obtain an improved directional microphone with the low frequency components obtained from the second order gradient microphone and the medium and


higher frequency components being obtained from the wave-type microphone so as to obtain a composite output signal which has a uniform and narrow directive pattern and a smooth frequency response characteristic over a wide frequency range.

3,581,013
MOBILE RADIOTELEPHONE COMMUNICATION SYSTEM
 Jean Jacques Muller, Garches, France, assignor to International Standard Electric Corporation, New York, N.Y.
 Filed Dec. 19, 1968, Ser. No. 785,105
 Claims priority, application France, Dec. 21, 1967, 133,321
 Int. Cl. H04g 7/04
 U.S. Cl. 179—41 10 Claims



A mobile telephone system is provided with radio telephone and paging equipment which is serviced over a group of channels allotted to a fixed radio telephone station. The latter provides automatic communication between the customers of a public telephone ground network and mobile sets. A free channel is marked by a tone, to be taken in a telephone call. Paging call numbers directed to paging mobile sets are transmitted from the station if the required channel is free. If the channel is not free, these paging calls alternate with the radiotelephone communications. In order to more effectively use the equipment, the called paging numbers are stored and then transmitted in limited trains of numbers.

3,581,014
INTEGRATED SYSTEM FOR REPORTING AIRCRAFT DATA
 Alvin R. Vogel, Los Angeles; Douglas A. Moore, Rolling Hills; Martin P. Folan, Long Beach, and John R. Buck, Gardena, Calif., assignors to Northrop Corporation, Beverly Hills, Calif.
 Continuation-in-part of application Ser. No. 656,425, July 27, 1967, now abandoned. This application Feb. 9, 1970, Ser. No. 9,644
 Int. Cl. G08b 3/10; G08g 5/00
 U.S. Cl. 179—100.1 6 Claims



Various aircraft parameters are sensed by function sensors, the outputs of these sensors being fed to a signal conditioner and evaluator where the signals are processed and the mag-

nitudes of these various parameters evaluated. When the magnitude of any of these parameters is above or below certain predetermined limits, an output signal is fed to a transmitter which transmits a voice message indicating the out-of-limits condition. The occurrence of out-of-limit conditions for any of these parameters is also digitally encoded and recorded for future reference. Certain outputs of the signal evaluator and conditioner indicative of selected aircraft flight and operating conditions are continually fed to a digital data encoder where they are placed in suitable condition for recording in digital form and from where they are fed to a continually recycling recorder for recordation.

3,581,015

DYNAMIC MICROPHONE

Takeo Masuda, Tokyo, Japan, assignor to Aiwa Co., Ltd., Tokyo, Japan


Filed Dec. 26, 1967, Ser. No. 693,436

Claims priority, application Japan, Aug. 31, 1967, Aug. 31, 1967, Sept. 6, 1967, Dec. 28, 1966, Dec. 28, 1966, 42/74645; 42/74646; 42/76302; 42/531; 42/532

Int. Cl. H04r 1/34

U.S. Cl. 179-121

9 Claims



This specification discloses a novel dynamic microphone using a flat annular magnet formed of an anisotropic barium ferrite as a permanent magnet to establish a magnetic circuit. The present microphone is extremely flat and of an excellent tone quality, and it can be manufactured at low cost. Various modifications to the microphone of this type become easily possible, and therefore a variety of examples with unidirectional characteristics or other characteristics are disclosed in this specification.

3,581,016

TIME-SHARING TELECOMMUNICATION SYSTEM

Saverio Martinelli, and Giorgio De Varda, both of Milan, Italy, assignors to Societa Italiana Telecomunicazioni Siemens S.p.A., Milan, Italy

Filed Feb. 26, 1969, Ser. No. 802,486

Claims priority, application Italy, Feb. 26, 1968, 13197-A/68

Int. Cl. H04j 3/00

U.S. Cl. 179-15AT

11 Claims

A telephone exchange serving subscriber and trunk lines on a time-sharing basis has three circulating memories operating in synchronism, the operating cycle of each memory representing a frame of 100 phases or time slots serving for the registration of the number of a calling party in a phase of the first memory (100), the number of a called party in a corresponding phase of the second memory (200) and information on the progress of a call between the two parties in the same phase of the third memory (300). The second time slot (phase Φ_2) of the second memory (200) is utilized as a binary counter successively registering, during consecutive frames, the addresses or call numbers of all lines served by the exchange. Each address thus inscribed is entered, one frame later, in a buffer register (800) for the duration of the following frame; concurrently, the line switches of the station identified by that address are briefly closed to sample the line voltage for the presence or absence of loop

current. Special provisions are made for the calling of an outgoing trunk identified by a first digit "O" in its three-digit address. Other phases (Φ_1 , Φ_3 , Φ_4) at the beginning of each frame are utilized for the automatic checking of the equipment, with instant substitution of a standby memory (500) for the monitoring memory (300) or for any one of the three digital sections of either address memory (100, 200), designed as identical modules, if such module is found to be defective.

3,581,017

ELECTRONIC MULTIPLEXER


Roger L. Stevens, Sierra Madre; Peter A. Putnam, Montebello, and Martin Sicon, San Jose, Calif., assignors to Aerojet-General Corporation, El Monte, Calif.

Filed June 13, 1968, Ser. No. 736,835

Int. Cl. H04j 3/04

U.S. Cl. 179-15A

7 Claims



This disclosure involves an all electronic time division multiplexer system designed to sample a large number of millivolt level signal sources at a megacycle sampling rate. [It also includes blanking circuitry which eliminates unwanted transients.] The system comprises three subsystems, a counter and two multiplexer gate subsystem, the first subsystem operating at the basic sampling rate and the second synchronized by the counter at the higher rate. The disclosure illustrates synchronization, blanking and gating circuitry to accomplish the necessary functions. Timing diagrams illustrate the switching sequences to provide accurate multiplexing without loss of data or introduction of unwanted switching transients into the multiplexed signal.

3,581,018

MULTISTAGE TELEPHONE SWITCHING NETWORK

Geoffrey Harland, London, and John P. Ronayne, Edgware, England, assignors to International Standard Electric Corporation, New York, N.Y.

Filed June 12, 1969, Ser. No. 832,678

Claims priority, application England, June 28, 1968, 30935/68

Int. Cl. H04q 3/00


U.S. Cl. 179-22

10 Claims

A telecommunications exchange in which connections are set up through cascaded stages (designated A, B, C & D) of coordinate switching matrices. Certain of the stages are paired in two-stage networks, and a number of these networks (four are disclosed) are used. The intermediate stages (B and C) of a four stage exchange are paired, and certain of the B stage switches handle only calls to and from lines, and

others handle only calls to and from junctions. The third or C stage mixes calls involved in traffic of either type. The

that the load of only one bay is placed on the source at one time. The system provides a period between each one-second



3,581,019

CARD CONTROL OF RADIO TELEPHONE


Donald P. Ryan, Bloomfield, N.J., assignor to Cessna Aircraft Company, Wichita, Kans.

Filed July 30, 1968, Ser. No. 748,813

Int. Cl. H04g 7/04

U.S. Cl. 179-41

3 Claims



Card control of radiotelephone facility. A matrix circuit receives a card, which is apertured, punched or embossed in accordance with the number which the radiotelephone equipment is to respond, the channels in which it is to be operative, to complete transmitter and receiver circuits therefor, and disable channels not used and otherwise control use of the facility by authorized persons. Other features of the invention are disclosed in the specification and drawings.

3,581,020

RINGING TONE DISTRIBUTION CIRCUITS

Morris Ribner, and Alfred M. Hestad, Chicago, Ill., assignors to International Telephone and Telegraph Corporation, New York, N.Y.


Filed Aug. 22, 1969, Ser. No. 852,172

Int. Cl. H04m 1/26

U.S. Cl. 179-84R

7 Claims

A logic system is provided for supplying ringing tone in successive bursts of one-second duration to each of four bays. The system provides the tone in a repetitive cycle so



burst to enable relay contacts to be opened and closed in the absence of ringing tone.

3,581,021

CONDITION RESPONSIVE AUTOMATIC DIALING APPARATUS


Carl S. Pettit, Box 164, Sweethome, Ark.

Filed June 3, 1968, Ser. No. 734,130

Int. Cl. H04m 1/44

U.S. Cl. 179-90

1 Claim



The disclosure relates to an automatic telephone dialing system wherein a driven rotary input member is rotated about a fixed axis adjacent the dial of a conventional telephone to, sequentially, rotate the dial in a clockwise direction and release the same for return to its initial rest position to dial a preselected multiple digit number. The rotation and release of the dial is effected by providing a plurality of spaced driven engaging elements positioned about the periphery of the input member which are rotated, seriatim, into and out of drive engaging relationship with a drive engaging element mounted on the dial. The number, length and spacing of the spaced drive engaging elements correspond to a preselected multiple digit telephone number.

3,581,022

MINIATURE TAPE RECORDER

Sadao Shigetomi, Sagami City, and Shoichi Saito, Tokyo, Japan, assignors to Olympus Optical Company Limited, Tokyo, Japan

Filed Nov. 12, 1968, Ser. No. 774,653

Claims priority, application Japan, June 29, 1968, 43/54791; 43/54792; 43/54793; 43/54794


Int. Cl. G11b 15/02, 23/02

U.S. Cl. 179-100.2Z

6 Claims

A miniature tape recorder having a flat elongated casing capable of being held in one hand of a user. A cassette mounting means is located on the front side of the casing

along a longitudinal edge thereof. An operating means, including a record pushbutton, a record-reproduction pushbutton, a stop pushbutton, and a slidable tape speed control button, is mounted on the opposite longitudinal edge of the casing. A cassette knockout button is located on the back side



of the casing in the proximity of the cassette mounting means, while a volume rotary knob, for actuating a volume control means, is located on the same side edge as the cassette mounting means with spacing from the knockout button.

3,581,023

WAFFER ROTARY SWITCH WITH STATOR PRINTED CIRCUIT CONTACT STRUCTURE AND ROTOR


Walter Meyer, McHenry, Ill., assignor to Oak Electro/Netics Corp.

Division of Ser. No. 798,923, Feb. 13, 1969. Filed Dec. 1, 1969, Ser. No. 881,201

Int. Cl. H01h 19/58

U.S. Cl. 200-11

1 Claim



A printed circuit rotary switch with stator clips soldered thereon and having wiping surfaces spaced from the surface of the switch section. The rotor blade is mounted on a flanged body, in alignment with the wiper contacts and has legs extending through the rotor opening securing the rotor to the stator. The stator has spiral inductors for a tuner printed on one surface, with the beginning terminal of one inductor radially aligned with the ending terminal of the next and joined by a stator contact.

3,581,024

WAFFER DISC ROTARY SWITCH WITH STATOR PRINTED CIRCUIT CONTACT STRUCTURE AND ROTOR

Walter Meyer, McHenry, Ill., assignor to Oak Electro/Netics Corp.

Filed Dec. 1, 1969, Ser. No. 881,202


Int. Cl. H01h 19/58

U.S. Cl. 200-11

7 Claims

A printed circuit rotary switch with stator clips soldered thereon and having wiping surfaces spaced from the surface of the switch section. The rotor blade is mounted on a flanged body, in alignment with the wiper contacts and has legs extending through the rotor opening securing the rotor

to the stator. The stator has spiral inductors for a tuner printed on one surface, with the beginning terminal of one in-



ductor radially aligned with the ending terminal of the next and joined by a stator contact.

3,581,025

ELECTRICAL CONTACT BREAKER MECHANISMS WITH IMPROVED CONTACT GAP ADJUSTMENT MEANS

Roland J. Yeo, 40 Broadlands Road, Avondale, Salisbury, and Jean E. Colley, 18, Coghlan Road, Greendale, Salisbury, Rhodesia


Filed Jan. 2, 1969, Ser. No. 788,564

Claims priority, application Rhodesia, Jan. 15, 1968, 408/67

Int. Cl. H01h 19/00, 19/62, 1/50

U.S. Cl. 200-19

2 Claims



A contact breaker assembly for use with a distributor of a spark ignited internal combustion engine including a first electrical contact point associated with a cam follower and adapted for reciprocatory movement in consonance with the cam follower. A second electrical contact point associated with a bearer member and with hand-operable adjustment means adapted to open or close the gap between the first and second contact points. The hand-operable adjustment means comprises a knurled wheel associated with resiliently biased restraining means and with a screw threaded rod adapted to progress the second electrical contact point towards or away from the first electrical contact point.

3,581,026

TIMER WITH VISUAL INDICATOR FOR PERIOD OF OPERATION


Gerhard K. Losert, Louisville, Ky., assignor to General Electric Company

Filed Nov. 12, 1968, Ser. No. 774,718

Int. Cl. H01h 7/08, 43/10

U.S. Cl. 200-38R

10 Claims



A timer includes a switch and a manually adjustable shaft longitudinally movable between a set and an unset position.

There is a motor-driven gear for releasing the shaft from its set position to provide time-controlled actuation of the switch. A first visual indicator is movable with the gear to show the proper termination time for a desired period of switch actuation. The shaft is movable relative to the gear when the shaft is in its set position to determine the period of switch actuation. A second visual indicator is movable with the shaft. The first and second visual indicators together show when the desired period of switch actuation has been set.

3,581,027

PUSH BUTTON TIME CYCLE CONTROLLER


Herbert F. Lindsay, 12047 Chester Drive, Baton Rouge, La.

Filed Jan. 6, 1969, Ser. No. 789,288

Int. Cl. H01h 43/00

U.S. Cl. 200-38

10 Claims



A pushbutton time cycle controller by virtue of which operations can be programmed, conducted, or carried out according to definitely timed sequences usually arranged over a 12-hour or 24-hour period. The controller comprises the combination of a dial face pushbutton assembly, the pushbuttons of which are arranged in patterns or orbitals for preselected setting in desired timed sequence, for activation of an electrical circuit by physical coaction between the pushbuttons and a displaceable synchronously rotating cam-disc or cam-disc assembly, which is brought into contact with a pressure responsive electrical switch in response to push-button settings. The pressure responsive electrical switch performs a preselected operation by energizing an external electrical circuit, or circuits.

3,581,028

LIQUIDIZER TIMER JOGGER WITH IMPROVED DRIVE MEANS INCLUDING LOST MOTION CONNECTION


Bruno M. Valbona, Avon, Conn., assignor to Dynamics Corporation of America, New York, N.Y.

Filed Nov. 20, 1969, Ser. No. 878,432

Int. Cl. H01h 7/08, 43/10

U.S. Cl. 200-38

15 Claims



An electrically powered liquidizer controlled by a timer-jogger switch means actuated by a lost motion between a manual control and a driven slip clutch member when the control is turned in one direction to energize the liquidizer

and a timer drive member without relative lost motion, and turned in the opposite direction with lost motion to manually energize the liquidizer continuously or intermittently for a period of time which, at will, can be a long or momentary period of time. The control is resiliently held in OFF position against inadvertent movement.

3,581,029

TV ON TIME CONTROL


Douglas G. Noiles, 114 Elm Place, New Canaan, Conn.

Filed Sept. 10, 1968, Ser. No. 758,820

Int. Cl. H01h 7/08

U.S. Cl. 200-38

21 Claims



A control comprising a securable case having an internal outlet into which a TV set may be plugged with the TV set plug secured within the case. ON and OFF pushbuttons are provided. When the ON button is depressed, the TV set may be operated for up to a predetermined total time. During this time, an accumulator wheel driven by a timing motor through a clutch rotates up to a predetermined angular position. When this position is attained, the internal outlet of the device is disconnected from the power line. When the OFF button is depressed, the outlet is not supplied with power and the accumulator wheel is not driven by the timing motor. Each 24 hours a reset wheel upon attaining a predetermined angular position causes the accumulator wheel to be reset to its initial position.

3,581,030

MAGNET ACTUATED MECHANISM FOR USE WITH CARD HAVING MAGNETIC AREAS


Bruce S. Sedley, Glendale, Calif., assignor to H. O. Bohme, Inc., Westbury, N.Y.

Filed Jan. 2, 1969, Ser. No. 788,372

Int. Cl. H01h 43/08

U.S. Cl. 200-46

41 Claims



A magnetic actuated switch for use with a data card having a number of magnetic areas arranged in characteristic pattern. The switch includes a slot into which the card can be in-

serted so that its magnetic elements are in juxtaposition with vertically oriented reed switches which are also arranged in the same characteristic pattern as its elements. One contact of the reed switch is magnetized in accordance with the polarity of the data card's magnetic areas and the other contact is magnetized in accordance with the polarity of a fixed magnetic biasing means included in the switch. The reed switch is closed if the two appropriate polarities are opposite each other. The switches can be connected in any suitable matrix pattern such as for binary coded decimal readout for reading data on the card or for the operation of a device such as a relay or door lock. Alternatively a dual coded card may be used where one code is read by a matrix of switches and the other code performs an unlocking function by means of an associated magnetically operated mechanism.

3,581,031

AN IMPROVED TILT SWITCH


Michael Brian, Birmingham, Mich., assignor to the United States of America as represented by the Secretary of the Navy

Filed Feb. 2, 1970, Ser. No. 7,496

Int. Cl. H01h 35/02

U.S. Cl. 200-61.47

6 Claims



An improved tilt switch having a plurality of mercury switches disposed about a housing and mounted at an angle with respect to the level or horizontal, and having a resilient adjusting means for coupling the housing to a member whose tilt is to be measured.

3,581,032

ENCLOSED SWITCH WITH COVER-CARRIED OPERATOR AND INTERLOCK MECHANISM


Paul M. Christensen, West Orange, N.J., assignor to Arrow-Hart, Inc., Hartford, Conn.

Filed Aug. 11, 1969, Ser. No. 848,948

Int. Cl. H01h 9/20

U.S. Cl. 200-50

27 Claims



An enclosed switch, of the type wherein the switch-operating handle is mounted on a hinged cover of a box, has snap action actuating mechanism and interlocking mechanism

which are also mounted on the cover, the snap action mechanism being operably connected with the switch-operating mechanism at all times so that the contacts can be disengaged while the cover is open and the cover can be closed while the contacts are either engaged or disengaged; but, the switch contacts can not be moved into engagement while the cover is open without disabling the interlock.

A turnable handle operates snap action means having an actuated element operating transversely of the enclosure to actuate the operating mechanism and switch contacts which move in different planes at right angles thereto in the enclosure.

3,581,033

TOGGLE SWITCH


Frank J. Plumb, Prospect, Conn., assignor to J-B-T Instruments, Inc., New Haven, Conn.

Filed May 19, 1969, Ser. No. 825,809

Int. Cl. H01h 13/28

U.S. Cl. 200-67

9 Claims



A toggle switch which has an operating lever extending through and pivoted in a threaded mounting barrel. In a longitudinal bore of the lever there is a compression spring and a plunger the latter being acted on by the spring and engaging a movable switch contact. The pivotal mounting of the lever comprises two ball bearings disposed at opposite sides of the lever and carried respectively in pairs of registered sockets and the lever and barrel, said sockets being external to the longitudinal bore of the lever whereby space is readily available in the bore for the plunger and spring.

3,581,034

FLUID-PRESSURE-ACTUATED SWITCH

Karl Schupp, Pforzheim, and Hans Weismann, Stuttgart-Feuerbach, Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

Filed Mar. 7, 1969, Ser. No. 805,333


Claims priority, application Germany, June 12, 1968,

P 17 65 576.4

Int. Cl. H01h 35/40


U.S. Cl. 200-83

11 Claims



A fluid-pressure-activated switch has a housing provided with an internal annular recess for the marginal portion of an

elastomeric diaphragm whose central portion bulges into the pressure chamber of the housing. The pressure chamber is located opposite a second chamber which receives one or more contacts. The diameter of the annular recess is equal to or smaller than the diameter of the diaphragm and the axial length of the recess is slightly smaller than or at most substantially equal to the thickness of the marginal portion of the diaphragm. The marginal portion includes an axially extending annular bead whose thickness is included in the thickness of the marginal portion and which has a lower resistance to deformation than the material of the remainder of the diaphragm so as to be moved in spite of unevenness on an associated sideface into tight sealing engagement with that face bounding one axial end of the recess when pressure is introduced into the pressure chamber, causing the central portion of the diaphragm to flatten out and to effect radial expansion of the diaphragm which, being resisted by contact of the diaphragm edge with the bottom wall of the recess, results in yielding of the material of the margin of the diaphragm in axial direction and thereby in an increase in the thickness of the margin.



3,581,035

GAS-BLAST CIRCUIT INTERRUPTER WITH MAGNETIC MEANS FOR ACCELERATING MERGER OF SERIES-RELATED ARCS


William H. Rathbun, Pittsfield, Mass., assignor to General Electric Company

Filed Apr. 30, 1969, Ser. No. 820,461

Int. Cl. H01h 33/70

U.S. Cl. 200-148

2 Claims



Discloses a gas-blast circuit breaker comprising two spaced-apart stationary contacts and a movable bridging contact extending therebetween. The bridging contact has an arc-running surface facing the space between the stationary contacts and a centrally located gap that divides the arc-running surface into two spaced-apart sections. Two slots in the bridging contact extend in opposite directions from the gap generally parallel to and behind the arc-running surface. This configuration of the bridging contact is such that the current paths through the two arcs formed upon contact separation are of such configuration that magnetic forces are developed for driving the arcs together and accelerating their merger into a single arc.

3,581,036

PUSH-PULL ELECTRIC SWITCH OPERATOR

William G. Dennison, Milwaukee, Wis., assignor to Cutter-Hammer, Inc., Milwaukee, Wis.

Filed Oct. 13, 1969, Ser. No. 865,726

Int. Cl. H01h 3/12

U.S. Cl. 200-172

6 Claims

A single return spring biases a switch operator against movement to either operating position by being compressed against either an internal shoulder formed in the operator housing or against the inner edge of an inserted ring. A pair of projections on the movable operator nest between a pair of switch actuating levers to bear directly downward upon

one lever in the push direction and to rock the other lever downward in the pull direction. The levers are designed with

3,581,037

EXTENSION DEVICE FOR TOGGLE SWITCHES

Richard A. Schiffler, 226 Freeman, Topeka, Kans.

Filed Oct. 15, 1969, Ser. No. 866,602

Int. Cl. H01h 3/04

U.S. Cl. 200-172A

1 Claim



An extension device for connection to a pivotal toggle of a wall located toggle switch to facilitate operation of the switch by a small child or another who is unable to reach to the toggle of the switch.

3,581,038

MICROWAVE APPLICATOR EMPLOYING A BROADSIDE RADIATOR IN A CONDUCTIVE ENCLOSURE

Norman H. Williams, San Francisco, Calif., assignor to Varian Associates, Palo Alto, Calif.

Filed May 2, 1969, Ser. No. 821,176

Int. Cl. H05b 9/06, 5/00


U.S. Cl. 212-10.55

8 Claims

A microwave applicator for treating material with microwave energy is disclosed. The applicator includes a relatively large conductive enclosure containing a large

broadside microwave radiating antenna disposed for directing the radiated microwave energy onto the load of lossy

a liquid state or being so heated while in the crucible. A coil is positioned adjacent the metal and a current pulse is passed through the coil. The current flow generates an intense mag-



material for treating same. The applicator is particularly useful for treating relatively large amounts of lossy material.

3,581,039

METHOD OF ONE-SIDE ARC WELDING AND BACKING MATERIAL THEREFOR

Fumiaki Kanzaki; Yoshio Kozakura; Kozo Akahide, Chiba-shi, and Tamotu Suzuki, Shimizu-shi, Japan, assignors to Kawasaki Steel Corporation, Kobe-shi, Japan and Nippon Kokan Kabushikikaisha, Tokyo, Japan


Filed Oct. 16, 1968, Ser. No. 767,962

Claims priority, application Japan, Oct. 16, 1967, Dec. 13, 1967, 42/66,420; 42/79,480

Int. Cl. B23k 9/18

U.S. Cl. 219-73

17 Claims



A method for welding steel plates and the like from one side, and a backing material therefor are provided which yields welds of exceptional quality, uniformity, and control. The weld backing material comprises a rigid channeled portion, containing an elastic mineral fiber composite in the channel, where the depth of the channel and the thickness of the fiber composite are determined by the following formula:

$$D = \frac{\rho c \min.}{\rho i} (d + m)$$

where D is the thickness of the composite, d is the depth of the channel, $\rho c \min.$ is the minimum compressed volumetric specific gravity of the composite, ρi is the initial volumetric specific gravity of the composite, and m is the maximum misalignment of the plates to be welded. Welding is accomplished by compressing the backing material along the back of the joint to be welded and welding from the opposed side.

3,581,040

FORMING OF THIN METAL FILAMENTS

James W. Halley, Chesterton, Ind., assignor to Inland Steel Company, Chicago, Ill.

Filed June 11, 1969, Ser. No. 832,201

Int. Cl. H05b 5/00

U.S. Cl. 219-7.5

12 Claims

This disclosure deals with an apparatus and process for forming thin metal filaments from liquid metal. An electrically conductive metal is placed in a crucible having an opening therein, the metal either having been previously heated to

netic field which compresses or squeezes the metal, causing the metal to be forced out of the magnetic field through the opening in the crucible in the form of an elongated filament.

3,581,041

WELD BOX FOR TUBE FORMING MILL


Glenn F. Balfanz, Jr., 3912 Hampton Ave., Western Springs, Ill.

Filed Mar. 28, 1969, Ser. No. 811,496

Int. Cl. B23k 9/02

U.S. Cl. 219-60

10 Claims



A weld box having laterally spaced walls with inlet and outlet ports through which a tube to be welded passes, pre-weld and postweld rollers mounted in the box and adjustable with respect to the welding rod to hold the tube accurately aligned with the rod and prevent the tube from twisting, the rollers rotatable on bearings which are isolated electrically from the rollers to prevent their destruction, the box provided with an inert gas diffuser which is located beneath the weld area and the inlet and outlet having gas outlets to protect the tube from atmospheric contaminants upon entering and exiting the weld box. The box has a tube cooling chamber and a spray trough to cool the tube when it exits the weld box.

3,581,042

UNDERWATER WELDING METHOD

Frank J. Pilia, Short Hills, N.J., assignor to Ocean Systems Incorporated, Reston, Va.

Continuation-in-part of application Ser. No. 664,784, Aug. 31, 1967. This application June 19, 1969, Ser. No. 839,778

Int. Cl. B23k 9/16


U.S. Cl. 219-61

5 Claims

The invention provides a method of welding heavy metal sections located deep under water without having to raise the

sections to the surface. The method consists of lowering a chamber having an open bottom until it encloses the area to be worked upon. Preferably a pressurized gas is introduced into the chamber as it is being lowered in order to prevent the water from rising beyond a certain level which is maintained in a dry condition. After the chamber is set in place, a

switching stages, each responsive to different magnitudes of the electrical signal, the outputs of the circuit arrangement being at least partially coupled with a feed device for the work gap. A particular level of an electrical signal derived from the conditions of the work gap is associated with each of the switching stages. Hence, one switching stage responds to no-load operation, in other words high voltage at the work gap, another stage to approximate short circuit conditions at the work gap, in other words, very low voltage at the work gap, and a further switching stage responds to normal operating conditions at the work gap.



pressurized gas is introduced to displace the remaining water in the chamber. Thereafter the chamber atmosphere is preferably maintained in a substantially inert condition and the weld made with a nonconsumable electrode-inert gas-welding apparatus operating with a 1/64- to 1/4-inch arc length at 85 to 250 amps and at a voltage sufficient to maintain a stable arc.

3,581,043

APPARATUS FOR THE CONTROL AND REGULATION OF THE WORK GAP OF AN ELECTROEROSION MACHINE

Werner Ullmann; Costantino Tadini, and Ehsan Salim, Locarno, Switzerland, assignors to A. G. fur Industrielle Elektronik AGIE, Locarno, Switzerland


Filed July 9, 1968, Ser. No. 743,362

Claims priority, application Switzerland, July 11, 1967, 9820/67

Int. Cl. B23p 1/14

U.S. Cl. 219-69

10 Claims



A circuit arrangement for the control and regulation of the width of a work gap of an electroerosion machine is disclosed. An electrical signal, the magnitude of which is indicative of the condition of the work gap, is fed to the input of a circuit arrangement which comprises a plurality of parallel

3,581,044

CONTINUOUSLY VARIABLE POWER SUPPLY FOR ELECTRIC DISCHARGE MACHINES CAPABLE OF MAINTAINING A CONSTANT RATIO BETWEEN AMPLITUDE AND DURATION OF DISCHARGE CURRENT

Daisaku Watari, and Tosio Morita, Kasuya-gun, Japan, assignors to Seibu Denki Kogyo Kabushiki Kaisha, Kasuya-gun, Japan


Filed Oct. 22, 1968, Ser. No. 769,545

Claims priority, application Japan, Nov. 2, 1967, 42/92847

Int. Cl. B23p 1/08

U.S. Cl. 219-69

9 Claims



Power supply means for applying continuously variable power across the spark electrode-to-workpiece circuit of an electric discharge machine. The spark electrode is connected in one branch of a multivibrator circuit, and control means are provided for continuously varying the amplitude of the current flowing through said branch while maintaining constant the ratio of the amplitude of this current flow to the duration of said flow. The control means comprises a variable resistor the ends of which are connected across the corresponding ends of the two branch circuits of the multivibrator circuit with the sliding piece connected to one terminal of the voltage source.

3,581,045

DIGITALLY CONTROLLED ELECTROEROSION MACHINE

Rudolf Panschow; Herbert Russbuel, Hannover; Volker Suhr, Garbsen, Germany, and Werner Ullmann, Locarno, assignors to A G fur Industrielle Elektronik AGIE, Locarno, Switzerland

Filed Nov. 7, 1968, Ser. No. 774,080

Claims priority, application Switzerland, Nov. 14, 1967, 15863/67


Int. Cl. B23p 1/12

U.S. Cl. 219-69

12 Claims

A program-controlled electroerosion machine is described having a novel numerical control arrangement incorporating a computer interconnected with novel supporting and controlling apparatus. The subject inventive control arrangement operates so as to detect from an information-recording medium a desired travel path of relative movement between the electrode and workpiece and, from such detected information, digital pulses are produced and applied to incremental


drive means such as stepping motors to effect the relative movement. The subject invention incorporates the provision of a reverse storage means incorporated to receive the digital drive pulses and store the same in a sequential manner. In the event of a short circuit or other disturbance at the work gap,



the novel reverse storage means causes relative movement to be effected in a reverse fashion to retrace the desired path of movement until the disturbance is eliminated. Subsequent thereto, normal forward operation of the control apparatus proceeds.

3,581,046
PRESSURE CONTROL FOR TUBE MILL
Charles E. Letsche, 505 Garwood, Prospect Heights, Ill.
Filed Oct. 28, 1968, Ser. No. 808,711
Int. Cl. B23k 11/06, 31/06
U.S. Cl. 219-82

6 Claims



An improved tube mill generally employed in the production of steel tubing by the continuous electric resistance welding of an axially extending seam cleft in a cylindrical tube length formed from a continuous length of metal strips, and directly responsive fluid pressure means to maintain a constant pressure relationship between the welding element and the support means for said tubes to produce uniform welds in said tubing.


3,581,047
SPOT WELDING PROCESS
James W. Mitchell, Jr., Detroit, Mich., assignor to Ford Motor Company, Dearborn, Mich.
Filed May 14, 1969, Ser. No. 824,635
Int. Cl. B23k 11/30

U.S. Cl. 219-91

2 Claims

A process for the production of a hollow, stiff, noncircular fabricated steel structural member in which the assembly is accomplished by spot welding. The critical spot weld in this assembly is accomplished by causing the welding current to

flow along a sheet metal member then through the sheet metal member and supporting the sheet metal member along




which the current flows against columnar collapse by contact with a complementary surface of a welding electrode.

3,581,048
WELDED MEMBER
Stephen V. Leonardo, 1128 Blanchard St., Downers Grove, Ill.
Filed Aug. 8, 1969, Ser. No. 848,584
Int. Cl. B23k 11/14

U.S. Cl. 219-93

1 Claim




My metal crotch weldment is L-shaped and bent to form substantially horizontal and vertical portions, each with nibs adapted to be spot welded to the substantially horizontal and vertical portions of a bent metal tubing. When my L-shaped crotch weldment is positioned with the nibs against the substantially horizontal and vertical portions of a bent tubing and an active electric spot welder is applied to said weldment, the heat therefrom to the nibs causes the nibs to flow into fusion with said portions for retaining the portions of the tubing in fixed spaced position.

3,581,049
SEMI-AUTOMATIC WELD APPARATUS WITH MEANS FOR CHANGING ELECTRODE ANGULAR DISPOSITION
Lou C. Creith, Allentown, Pa., assignor to Olin Corporation
Filed Nov. 12, 1969, Ser. No. 875,991
Int. Cl. B23k 9/12

U.S. Cl. 219-125

12 Claims




A device for varying the angle of inclination between a welding torch and a workpiece. The device is employed in a semi-automatic welding apparatus which includes means for guiding a welding torch along a weld seam at a predetermined rate. The device comprises two cylinders each having

a hole bored through it end to end, with the longitudinal axis of the bore canted with respect to the longitudinal axis of the cylinder. One cylinder fits within the bore of the other and the welding torch is placed in the bore of the inner cylinder. The angle at which the welding torch is inclined to the workpiece can be varied by rotating the cylinders with respect to each other and with respect to the welding torch barrel. After obtaining a desired angle of inclination, both the cylinders and the torch barrel are locked in place.

3,581,050
ELECTRIC ARC-WELDING SYSTEMS
Kenneth William Brown, and Nigel C. Balchin, both of Cambridge, England, assignors to National Research Development Corporation, London, England
Filed July 29, 1968, Ser. No. 748,536
Claims priority, application Great Britain, Aug. 1, 1967, 35204/67
Int. Cl. B23k 9/00

U.S. Cl. 219-130



9 Claims are connected to relays which control the selection of the different parameters.



3,581,052
SHIELDED ARC WELDING CONTROL SYSTEM
Rex W. Milton, Houston, Tex., assignor to Bauer & Associates, Inc.
Continuation-in-part of application Ser. No. 813,436, Apr. 4, 1969, now abandoned. This application June 18, 1969, Ser. No. 834,291
Int. Cl. B23k 9/10

U.S. Cl. 219-131

10 Claims



Different preselected combinations of the values of welding parameters in a consumable electrode arc-welding process are obtained when a selector switch is moved through its different positions. The switch is inserted into the hub of the reel of electrode wire which is to be fed to the welding torch. The reels are coded so that the switch is moved to a position which will select a combination of values appropriate for the wire carried by that reel.

3,581,051
WELDING APPARATUS
Kenneth William Brown, Cambridge, England, assignor to National Research Development Corporation, London, England
Filed July 29, 1968, Ser. No. 748,387
Claims priority, application Great Britain, Aug. 1, 1967, Feb. 29, 1968, Mar. 8, 1968, 35,247/67; 9,906/68; 11,429/68
Int. Cl. B23k 9/10

U.S. Cl. 219-131

10 Claims

In a consumable electrode arc welding process different combinations of the various parameters (open circuit arc voltage, wire feed speed, series inductance, shielding gas) are stored on a plug board by interconnecting each input bus with preselected output buses. The input buses are connected through a selector switch to a voltage source. As the selector

A feedback control system responsive to the ion density in the arc envelope of a welding electrode. The sensing end of a potential gradient probe is positioned in the arc envelope, and a signal is developed in the probe that is proportional to the position of the arc with respect to the workpiece. The induced signal is transmitted to a signal amplifier which responds to signal deviations from a reference signal position of the probe. The output signal from the amplifier controls the degree of field excitation applied to an electrical-welding generator field winding from an exciting source. The amplifier output signal may also be used to control the rate of welding electrode feed as well as the rate of welding head travel. The variable output voltage of the welding generator is connected between the welding electrode and the workpiece to directly control the position of the arc. In this way the output voltage of the welding generator is responsive to the potential gradient of the arc and correctly positions the arc for depositing weld metal on the workpiece.


3,581,053
SYNCHRO-ARC METAL TRANSFER
August F. Manz, Union, N.J., assignor to Union Carbide Corporation
Filed Dec. 5, 1967, Ser. No. 688,157
Int. Cl. B23k 9/00

U.S. Cl. 219-137

7 Claims

Electric arc working apparatus and process for controllably transferring metal from a consumable electrode to a workpiece by applying recurrent power pulses to said elec-

trode while oscillating said electrode at a multiple frequency relative to the power pulse recurrence frequency, and selec-



tively displacing the phase between said power pulses and said electrode oscillations.

3,581,054 WELDING ELECTRODE

Jarl Allan Bjorkroth, Avesta, Sweden, assignor to Avesta Jernverks Aktiebolag, Avesta, Sweden
Filed Sept. 24, 1969, Ser. No. 860,846
Claims priority, application Sweden, July 27, 1965, 9876/65
Int. Cl. B23k 35/22

U.S. Cl. 219-146

7 Claims

A coated electrode for electric arc welding having a core comprising 0.01-0.05 percent carbon, 0.1-0.9 percent silicon, 0.2-2.5 percent manganese, 14.5-18.0 percent chromium, 3.5-6.0 percent nickel, 0.1-2.2 percent molybdenum, 0.02-0.12 percent nitrogen and the remainder iron. The proportion of the constituents are adjusted so that the chromium equivalent (e.g. percent chromium + percent silicon + percent molybdenum) plus the nickel equivalent (e.g. percent nickel + $[0.5 \times \text{percent manganese}] + [30 \times (\text{percent carbon} + \text{percent nitrogen})]$) is between 24.5 and 27, and 1.4 times the chromium equivalent minus the nickel equivalent is between 16 and 19.3. The welding electrode yields a weld metal having a microstructure consisting of ferrite, martensite, and austenite.


3,581,055 CURLING BOBBIN AND HEATER

Tomio Makino, Tokyo, Japan, assignor to Nichel Denki Sangyo K.K.

Filed June 3, 1968, Ser. No. 734,095
Int. Cl. A45d 4/12, 2/36; H05b 1/00

U.S. Cl. 219-222

8 Claims



A curling bobbin and heater assembly includes a bobbin having an outer cylinder with a plurality of radial projections for twining hair, an intermediate cylinder formed of heat storing material, such as paraffin or polycarbonate, and an inner cylinder formed of a material of high thermal conductivity. The inner and outer cylinders are attached by means of an inwardly directed flanged portion on the outer cylinder. The inner cylinder closely fits around and receives a cylindrical

cal electric-heating element is detachable from a base member which includes terminal pins which are received in corresponding sockets on the heating element. The heating element is detachably secured to the inner shell of the bobbin so that, as desired, the heating element and bobbin can be removed from the base member as a unit.

3,581,056 HAIR CURLER HAVING A HIGH HEAT STORAGE CORE TELESCOPICALLY MOUNTED THEREIN

Richard Djenner, Holte, Denmark, assignor to Olaf Bendik Elmer, Copenhagen, Denmark


Filed Apr. 17, 1969, Ser. No. 817,006

Claims priority, application Denmark, Apr. 19, 1968, 1740/68

Int. Cl. A45d 2/24

U.S. Cl. 219-222

4 Claims



Hair curler including a cylindrical wall made of plastic material and a guide tube provided with stop means adjacent each end thereof and mounted within such cylindrical wall so as to form an air space between the cylindrical wall and the guide tube. A central core having substantially the same length as the curler itself and made of a material having a large specific heat is adapted for axial displacement within the guide tube between a first position in which it is completely inserted into the curler and a second position in which one end of the core is projecting from the curler. The core has means cooperating with the above end stops for stopping the core at the above mentioned first and second positions. Pressure means are associated with the core and the guide tube for providing sufficient friction against displacement of the core with respect to the tube.

3,581,057 HOT WATER HEATER


Theodore F. Meyers, Medina, Ohio, assignor to The Hobart Manufacturing Company, Troy, Ohio

Filed Oct. 8, 1969, Ser. No. 864,766

Int. Cl. H05b 1/00

U.S. Cl. 219-312

17 Claims



Air is introduced and retained within a nonpressurized hot water heater tank when water is supplied to the tank and is slowly exhausted after the water supply is shut off to provide space within the tank for expansion of the water when

heated. In the embodiment shown, air is aspirated into the water supply and is accumulated within an inverted cup located within the tank. When the water supply stops, air escapes from the cup thereby providing a space within the tank into which the water can expand.

3,581,058 APPARATUS FOR PROCESSING PHOTOGRAPHIC MATERIALS


Paul Romano, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Jan. 18, 1968, Ser. No. 698,832

Int. Cl. F24h 1/00

U.S. Cl. 219-330

6 Claims



An apparatus for processing photographic liquid including a processing drum which utilizes and discharges successively received unit charges of photographic processing liquid, a container for storing a unit charge of the liquid to be received by the drum, a heating element for heating the container and a fluid pressure temperature sensor in thermal communication with the heating element and the drum for regulating the temperature of the liquid in the container in inverse proportion to the ambient temperature surrounding the drum.

3,581,059 APPARATUS FOR HEATING A STORAGE CORE OF A HEAT STORING FURNACE

Richard Breilmeyer, Winnenden, and Karl Amann, Schmidlen, Germany, assignors to Bauknechte GEA Elektrotechnische Fabriken Gesellschaft mit beschränkter Haftung, Stuttgart, Germany


Filed Sept. 15, 1966, Ser. No. 579,541

Claims priority, application Germany, Sept. 17, 1965, B83772

Int. Cl. F25h 7/00; H05b 1/02

U.S. Cl. 219-378

4 Claims



A heat storage furnace is provided with a storage core enclosed in a thermally insulated housing. Electric heating elements are provided for heating the core. A main thermal switch responsive to temperatures exteriorly of the housing deenergizes the core heating elements when a predetermined maximum temperature is exceeded. An additional thermally responsive switch is connected in series with the main thermal switch and is arranged to respond to the temperature in

the immediate vicinity of an auxiliary heating element connected so as to be energized through the additional thermal switch. The auxiliary heating element is positioned in the housing and is thermally remote from the main thermal switch. The additional thermal switch cyclically opens and closes the circuit to the core heating elements during the charging period before the temperature at the exterior of the housing exceeds the predetermined maximum and the main thermal switch deenergizes the heating elements to terminate the charging period.

3,581,060 TEMPERATURE CONTROL DEVICE IN A HEATED GALETTE

Karl Bauer, and Herbert Turk, Remscheid-Lennep, Germany, assignors to Barmag Barmer Maschinenfabrik Aktiengesellschaft, Wuppertal, Germany


Filed July 12, 1968, Ser. No. 744,550

Claims priority, application Germany, July 14, 1967, Aug. 14, 1967, B93489; B72212

Int. Cl. H05b 1/02

U.S. Cl. 219-469

8 Claims



A rotatable gallette for transporting threads, filaments, tapes and the like capable of being controllably heated, preferably by an internally and concentrically mounted stationary induction coil, in which the roller jacket of the gallette is an outer cylindrical wall having on its inner surface a radially outwardly recessed portion adapted to receive the terminal heat-sensitive end of an elongated temperature measuring feeler gauge.

3,581,061 TEMPERATURE CONTROL SYSTEM PROVIDING FULL- WAVE CONDUCTION INTO TEMPERATURE CHANGE APPARATUS


William W. Chambers, Anaheim, Calif., assignor to Robertshaw Controls Company, Richmond, Va.

Filed Sept. 5, 1968, Ser. No. 757,695

Int. Cl. H05b 1/02

U.S. Cl. 219-499

7 Claims



A temperature control system for connection in series with an alternating current source and an environmental change apparatus, the system including a temperature-sensitive bridge circuit which becomes unbalanced in response to environmental temperature change, the unbalance triggering a controlled rectifier which applies power from the source to the environmental change apparatus, a full-wave bridge rectifier of the system applying positive anode voltage to the controlled rectifier during both negative and positive polarity half-cycles of the source voltage.

3,581,062

ELECTRONIC THERMOSTAT

Keith Aston, England, assignor to The Pavele Corporation, New York, N.Y.

Filed Feb. 18, 1969, Ser. No. 815,511

Claims priority, application Great Britain, Feb. 19, 1968, 8014/68

Int. Cl. H05b 1/02

U.S. Cl. 219—501

3 Claims



A compact, unitary electronic thermostat is formed by encapsulating a temperature sensing element and a solid-state control circuit in a potting compound having good heat transfer characteristics. The unitary thermostat, which includes a solid-state electronic switch having conductive and nonconductive states which are varied in response to the output from the temperature sensing element to control a load power supply may be completely or partially immersed in a fluid environment.

3,581,063

VERIFICATION MEANS FOR CHARACTER GROUPS


Joseph L. Levasseur, St. Louis, Mo., assignor to Simcom Corporation, High Ridge, Mo.

Filed Dec. 30, 1968, Ser. No. 787,648

Int. Cl. G06k 7/00

U.S. Cl. 235—61.7B

31 Claims



Means for verifying that a character group such as a character group that represents an account number such as might be used on a credit card or like device is or is not known to be objectionable for some reason, including means for comparing a particular character group with a plurality of other similar type character groups and indicating the results of the comparison. The invention also includes novel means for storing and moving character groups and other means for reading and/or sensing the stored character groups during movements thereof.

3,581,064

RECORD SCANNER WITH LOADING AND INDEXING MEANS


Ansell W. Palmer, Hampton, N.H., assignor to Honeywell Information Systems Inc.

Filed Apr. 30, 1969, Ser. No. 820,539

Int. Cl. G06k 7/015; G11b 5/82, 25/04

U.S. Cl. 235—61.11D

10 Claims



A record scanner is loaded by an operator placing a record on a locating pin while in an open position. Upon closing, the

record is transferred to a probe which indexes the record for circular scanning by a rotary transducer.

ERRATUM

For Class 235—92 see: Patent No. 3,580,496

3,581,065

ELECTRONIC DISPLAY SYSTEM

Yoshikazu Hatsukano, and Kosei Nomiya, both of Kodaira-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Nov. 22, 1967, Ser. No. 685,047

Claims priority, application Japan, Dec. 2, 1966, 41/78,684

Int. Cl. H03k 21/22

U.S. Cl. 235—92

14 Claims



This specification discloses an electronic display system for an information processing apparatus adapted for visual display of information through the use of indicator tubes. In the present system, a shift register and change over switch means for periodically and sequentially distributing the operating potential to the anode of each indicator tube are provided for the purpose of simultaneously and effectively operating the plurality of indicator tubes by means of a single common control device comprising a single driving circuit, decoder circuit and gate circuit connected with the indicator tubes. Thus, an information signal is periodically and sequentially read out by means of the gate circuit, whereby the control device is operated, and the changeover switch means is operated in synchronism with said information signal to cause the indicator tubes to be periodically glow-discharged.

3,581,066

PROGRAMMABLE COUNTING CIRCUIT


Douglas R. Maure, San Marino, Calif., and Mei Goon Wong, Los Angeles, both of Calif., assignors to Lear Siegler, Inc., Santa Monica, Calif.

Filed Mar. 6, 1968, Ser. No. 711,066

Int. Cl. H03k 21/32

U.S. Cl. 235—92

18 Claims



A programmable counting circuit in which the cycling of a multistage counter is controlled by reset information and

truncation information stored in no more than two registers. A detection circuit generates a "forward carry" signal when the contents of the counter match the contents of a reset register and generates a "reverse carry" signal when the forward carry signal appears in a stage for which a bit is presented in a truncation register. The detection circuit utilizes the "reverse carry" signal to generate reset signals for the counter stage associated with the bit and all prior stages. The detection circuit utilizes subsequent bits in the truncation register to effect the resetting of subsequent groups of stages of the counter whenever the contents of these groups match the corresponding contents of the reset counter. In another embodiment, decoding circuitry utilizes an additional information bit in the reset register to present truncation information sufficient for a single truncation in the absence of a truncation register.

3,581,067

PITCH MATCHING DETECTING AND COUNTING SYSTEM


Samuel P. Willits, and William L. Mohan, both of Barrington, Ill., assignors to Spartans Limited, Palatine, Ill.

Filed Dec. 2, 1968, Ser. No. 780,367

Int. Cl. G06m 9/00

U.S. Cl. 235—92V

23 Claims



An apparatus for counting stacked sheetlike materials having no sheet separation requirements. The active area of the sensor array is matched to the width of a sheet of the stack and the sensor array caused to traverse the stack, the complex signal output of the sensor array being stripped of the unwanted components in a high gain, diode clamped capacitive input operational amplifier whose square wave output is processed and counted in conventional counting circuits.

3,581,068

COUNTER CONTROLLED DIGITAL LIMIT DETECTOR


Robert D. Wyatt, Costa Mesa, Calif., assignor to the United States of America

Filed Jan. 7, 1969, Ser. No. 791,536

Int. Cl. G06m 3/14, 3/02

U.S. Cl. 235—92

6 Claims



A main counter of "n" stages counts in an additive direction and an auxiliary counter of "n" stages counts in an

additive direction to gate $2^n - 1$ pulses into the main counter to effect a subtraction in a digital limit detector system. Alarm generating circuitry is activated when the count in the main counter reaches a preset number representing a limit in a monitored device.

3,581,069

FREQUENCY TO BINARY CONVERTER

Arthur M. Pederson, Mercer Island, Wash.


Filed Nov. 14, 1967, Ser. No. 682,841

Assignor to the United States of America as represented by Secretary of the Navy

Int. Cl. H03k 23/00

U.S. Cl. 235—92

7 Claims



A sound velocity frequency signal to binary signal conversion and storage system. A high frequency crystal controlled oscillator and counter are controlled by a velocimeter counter to supply a binary number to binary storage flip-flops in accordance with the pulse frequency rate input to the velocimeter counter. The number stored is inversely proportional to the average sound velocity for the period of measurement.

3,581,070

APPARATUS FOR OPERATING A SHAFT FURNACE BY DETECTING THE FALLING SPEED OF THE CHARGE

Keiji Tsujihata; Masatoshi Shimada; Hiromi Asai; Yasuhiro Sawada, and Zensaku Ayuha, all of Japan, assignors to Nippon Steel Corporation

Continuation of application Ser. No. 348,631, Mar. 2, 1964, now abandoned. This application Nov. 1, 1968, Ser. No. 774,581

Int. Cl. G06f 15/46

U.S. Cl. 235—151.1

2 Claims



This invention relates to a method and apparatus for always maintaining optimum operating conditions of a blast furnace by measuring the sinking speed of the charge and detecting deviations thereof from a predetermined sinking speed obtained statistically, superposing signals of logical operation obtained by the analysis of various factors representing operating conditions of the furnace on the signal representing the said deviation, and subjecting the blast con-

amplifier responding to changes in the output of the capacitor pump and driving the controlled level amplifier. Each line section analog is a delay line including a nonlinear resistance element, such as a field effect transistor having a resistance proportional to the current passing through it, and a nonlinear voltage variable capacitance diode having a capacitance proportional to the inverse square root of impressed voltage. The regulator analog is a voltage regulator including a control element, such as a field effect transistor, and a differential amplifier responding to changes in regulator analog output voltage to drive the field effect transistor. The transient and load utilization simulator includes a function generator programmed by an opaque tape to simulate fluid withdrawal. The tape controls the amount of light between a light source and a light sensor which produces an output current in response to light. The output current produced is impressed on the electrical analog system by a flow modulator, such as by modulating the regulator station output with this current.

3,581,078

FAST FOURIER ANALYZER

George H. Robertson, Summit, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.
Filed Nov. 24, 1967, Ser. No. 685,648
Int. Cl. G06g 7/19; G01r 23/16
U.S. Cl. 235—193

10 Claims




The recursive equations of the Cooley-Tukey algorithm are implemented in analog form, thereby significantly decreasing the time needed to compute either the Fourier transform or the inverse Fourier transform of a signal segment, relative to the time needed for the same computation by a digital implementation of these equations.

3,581,079

MARINE RUNNING LIGHT CONSTRUCTION

Hugo Magi, Etobicoke, and John Smith, Willowdale, Ontario, Canada, assignors to Aqua-Marine Manufacturing Limited, Toronto, Ontario, Canada
Filed Oct. 2, 1969, Ser. No. 863,089
Int. Cl. B63b 45/04
U.S. Cl. 240—7.5

6 Claims



The combination of a lamp housing and a pivotally mounted lens, the latter being adapted to swing between an

open and a closed position. The lens has a resilient arm extending outwardly from the lens away from the pivot axis, with a bearing edge adapted to sweep through an arc adjacent an inner face of the housing. The face has a cam surface following the arc, such that the bearing arc is biased toward one end or the other of the cam surface, corresponding to the open and closed positions of the lens.

3,581,080


LAMP HOUSING AND ELECTRIC TERMINAL CONSTRUCTION

Hugo Magi, Etobicoke, Ontario, Canada, assignor to Dominion Auto Accessories Limited, Toronto, Ontario, Canada

Filed Apr. 18, 1969, Ser. No. 817,400
Int. Cl. B60q 1/32; H01r 33/48

U.S. Cl. 240—8.2

7 Claims



A lamp housing in which a crook-shaped terminal is looped around a split pin through which the bared end of an electric wire is inserted, so that the terminal contacts the bared end. One projecting part of the terminal is biased toward the center contact of an electric bulb by reason of another projecting part thereof bearing against a portion of the housing.


3,581,081

AUTOMOTIVE LICENSE LAMP ASSEMBLY

Lawrence E. Rieth, Springfield, Ill., assignor to Stewart-Warner Corporation, Chicago, Ill.
Filed Aug. 11, 1969, Ser. No. 849,079
Int. Cl. B60q 1/30

U.S. Cl. 240—8.3

10 Claims



A lamp is removably carried by an open J-slot socket which is concentrically positioned within a cylindrical bushing. The socket is positively locked in place and resiliently sealed against the bushing by a unitary rubber boot which covers the rearward portion of the socket and is compressed between the socket and the bushing.

3,581,082

STREET LIGHTING LUMINAIRE REFRACTOR

Jan Shadwick, Newark, Ohio, assignor to Holophane Company, Inc., New York, N.Y.

Filed Aug. 9, 1968, Ser. No. 751,468
Int. Cl. F21v 5/00

U.S. Cl. 240—106

14 Claims

In a tilted oval street luminaire, a refractor for use with a physically oval, but optically round, reflector provides four

3,581,084

PIEZOELECTRIC WHEEL-AXLE DETECTOR

Saburo Kaneno, Terahata, Kawanishi; Takeshi Yamaguchi, Suita, Osaka, and Shunichi Yoshioka, Takarazuka, all of Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan



Filed Nov. 6, 1968, Ser. No. 773,765

Claims priority, application Japan, Nov. 10, 1967, 42/71965
Int. Cl. B61 13/04

U.S. Cl. 246—249

13 Claims

substantially uniform light beams for intersection lighting. Vertical prisms in the forward beam sections of the refractor and vertical and horizontal prisms in the rear beam sections of the refractor provide the basic four way distribution from a tilted reflected beam which, because of reflector design considerations may be horseshoe-shaped or annular. Some or all of the vertical prisms may have their normally inactive or intermediate surface oriented to receive light to balance the candlepower as between the front and rear beams and horizontal prisms acting in conjunction with the vertical prisms lower the reflected and lateral refracted beams. Front and rear radial prisms redirect incident direct light and reflected plus direct light respectively, into the front and rear



A wheel-axle detector for wheeled vehicles following a track having rails with an I-shaped cross section forming a continuous imperforate web with an opposed overhanging head and foot. A piezoelectric element holder containing a piezoelectric element is inserted directly between the head and the foot of the rail such that a portion of the vehicle wheel load borne on the rail is imparted to the element. A detecting circuit is provided to receive and detect the electrical output of the piezoelectric element.

streets, the latter radial prisms building the below beam component in the rear streets. The bottom of the refractor provides four basic sections of variously oriented prisms on the incident surface, further subdivided into four further sections each to split the direct and reflected light from underneath the unit and uniformly distribute it over the entire intersection. Longitudinal flutes centrally located on the outer surface below the inside bottom sections, and a checkerboard pattern of crossing flutes on the lower portion of street side outer surface coat with the inside prisms to break up the strong component of reflected light while paying due respect to the direct light to confine the down light within the intersection.


3,581,083

WHEEL TRIP

Ivan L. Joy, 1616 W. 29th St., Topeka, Kans.
Division of Ser. No. 665,329, Sept. 5, 1967, Pat. No. 3,461,284.
This application Aug. 11, 1969, Ser. No. 848,922
Int. Cl. B61 11/10

U.S. Cl. 246—246


6 Claims



This disclosure deals with a wheel trip adapted to be mounted adjacent a length of railroad track and to indicate the presence or the passing of the wheels on one side of a train. The wheel trip includes two spaced sensors, means for energizing the two sensors, each of the sensors responding to the presence of a wheel, and means connected in circuit with the sensors for generating a trip signal only when a wheel is adjacent both sensors. A counter and/or a temperature measuring unit may be connected to respond to the trip signal

3,581,085
ULTRAVIOLET FLUORESCENT ANALYZER FOR MONITORING OF OIL IN DISCHARGE BALLAST
Sonja I. Barrett, Middle Farm, Watereaton, Oxford, Oxfordshire, England
Filed May 20, 1968, Ser. No. 730,253
Claims priority, application Great Britain, May 26, 1967, 24592/67
Int. Cl. G01n 21/26
U.S. Cl. 250—43.5

16 Claims



A continuous monitoring system for measuring the oil content of discharged ballast water based on the use of an ultraviolet fluorescence meter. The meter operates by passing ultraviolet light through a sample jet of water, the fluorescent visible light being measured by a filter-photocell combination angled to the incident beam. At elevated oil concentrations, the meter response diminishes as both ultraviolet and visible light are cut off by the increasing amounts of dark oil present, thus giving a false reading. A photocell or fluorescent indicator screen is therefore proposed as a warning device to be used in conjunction with the above monitoring system, to indicate when the emerging ultraviolet light is obscured by excess quantities of oil.

3,581,086

DEVICE FOR THE SUPERVISION OF A TREATMENT IN AN ENCLOSURE AT VERY LOW PRESSURE


Bernard M. Daigne, Malakoff, and Louis Pelletier, Sainte-Genevieve Des Bois, France, assignors to Office National D'Etudes Et De Recherches Aerospatiales (par abreviation O.N.E.R.A.)

Filed Mar. 18, 1968, Ser. No. 713,921

Claims priority, application France, Mar. 21, 1967, 99648
Int. Cl. G01n 23/22

U.S. Cl. 250-49.5

13 Claims



A device for supervising a thermal treatment operation taking place inside a vacuum enclosure by detecting and/or measuring emitted radiation accompanying the operation comprises a compartment maintained at a higher pressure substantially closed at one end by a partition located inside the enclosure and having an opening for passing radiation from the enclosure to a radiation sensitive element closing the compartment at its other end, the size of the opening and the distance between the partition and the radiation sensitive element being such that, for the value of the pressure in the compartment, substantially no vapor molecules originating from the enclosure during the operation reach the sensitive element. The operation may for example comprise an electron gun bombarding a weld region within the enclosure.

3,581,087

X-RAY FLUORESCENCE MEASURING SYSTEM EMPLOYING BALANCED X-RAY FILTERS AND CIRCUIT MEANS TO VARY THE EFFECTIVE RELATIVE TRANSMISSION THEREOF


Joris M. Brinkerhoff, Arlington; Jean Hunerwadel, Hingham, and Francis B. Sellers, Sudbury, all of, Mass., assignors to Panametrics, Inc., Waltham, Mass.

Filed Oct. 25, 1968, Ser. No. 770,615

Int. Cl. H05g 3/00; G01m 23/22

U.S. Cl. 250-51.5

4 Claims



An X-ray fluorescence analysis system for measuring the amount of a specific element in a matrix containing variable amounts of other elements. The system employs a pair of balanced filters and a detector and counting apparatus. One filter has an absorption edge above the characteristic X-ray energy of the specific element and the other has its absorption edge below that energy. The apparatus is arranged so that with one filter in place the number of rays received by the detector for a time τ is accumulated and with the other

filter in place the number of rays detected for a fraction $F\tau$ of that time is subtracted from the first number, the difference representing the quantity of specific element present.

3,581,088

X-RAY TABLE ATTACHMENT


Edward P. Engels, Weiner Memorial Hospital, Marshall, Minn.

Filed Aug. 15, 1968, Ser. No. 752,962

Int. Cl. G01n 23/04

U.S. Cl. 250-55

3 Claims



A body-supporting frame adapted to be removably attached to a vertically oriented X-ray table in a horizontal position for the purpose of obtaining horizontal beam decubitus X-ray films of a patient's chest, abdomen, or extremities. Special bracket detents secured to the footrest of a standard, upright X-ray table may be utilized to slidably and removably support the aforesaid body rest frame on said footrest.

3,581,089

CATADIOPTRIC REFLEX RADIATION DETECTION CONVERSION, LOCATION AND DISPLAY DEVICE


Leonard J. Craig, Carpinteria, Calif., assignor to The United States of America as represented by the Secretary of Air Force

Filed June 25, 1969, Ser. No. 836,395

Int. Cl. G01t 1/00

U.S. Cl. 250-83R

4 Claims



A system for detecting and locating short duration radiant energy pulses occurring in the nonvisible portions of the spectrum by converting each event of pulsed energy within a region of an observer's field of view to a visible pair of distinctive orthogonal lines intersecting over the source of radiation including a pair of apertures, toric reflectors with mutually orthogonal principal axes reflecting the incident radiation on a pair of linear arrays of photosensitive detectors, and detector circuits for illuminating corresponding optoelectric members and an optical system for projecting the visible light before an observer's eyes.

3,581,090

UTILIZING PENETRATING RADIATION


Leonard Carlton Brown, Columbus, Ohio

Filed Oct. 20, 1966, Ser. No. 588,199

Int. Cl. G01t 1/20; G01s 5/16

U.S. Cl. 250-83.3

16 Claims



A system for determining the position of a plurality of objects carrying sources of radiation relative to a detector for said radiation includes means for modulating each of the radiation sources at a different frequency. The modulated radiation is received by an array including a plurality of mutually shielded detectors. Each detector feeds a voltage indicative of the amount of penetrating radiation impinging thereon to a computing network which derives visual signals indicative of the angular location and range of each object carrying a radiation source. Provision is made for eliminating background radiation from the signal derived from each of the detectors.

3,581,091

NEUTRON SPECTROMETER EMPLOYING TWO SEMICONDUCTOR COUNTERS IN COMBINATION WITH A COINCIDENCE CIRCUIT FOR ELIMINATING BACKGROUND

Albertus Cornelis Meijer, Emmasingel, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Sept. 3, 1968, Ser. No. 756,751

Claims priority, application Netherlands, Sept. 15, 1968, 6712684

Int. Cl. G01t 3/00

U.S. Cl. 250-83.1

2 Claims



A hydrogen rich foil is arranged at right angles to a beam of neutrons to be measured and emits protons which are interrupted and counted by a semiconductor barrier layer transmission counter (dE/dx -counter) and a semiconductor absorption or output counter (E -counter which count the protons and measure the energy, background being eliminated by a coincidence counter. Both the transmission counter and absorption counter consists of a checkerboard counter and the scattering foil is arranged substantially immediately against the transmission counter, the scattered protons being measured by means of the coincidence circuit not only according to their number and energy, but also according to their direction.

3,581,092

PYROELECTRIC DETECTOR ARRAY


Denton Pearsall, Stamford, Conn., and Gerald Jankowitz, Hillsdale, N.J., assignors to Barnes Engineering Company, Stamford, Conn.

Filed Apr. 9, 1969, Ser. No. 814,761

Int. Cl. G01t 1/16

U.S. Cl. 250-83.3

5 Claims



An array of thermal detectors for infrared radiation measurement is fabricated on a single piece of pyroelectric material. A common transparent electrode to the infrared radiation is applied thereto and positioned on one side of the layer of pyroelectric material facing the incident radiation, and a plurality of individual field-defining electrodes are mounted on the other side of the pyroelectric material. This structure is simpler and more reliable than an assembly of isolated detectors and is easier to fabricate by using vacuum-deposited leads on the mounting substrate.

3,581,093

DC OPERATED POSITIVE ION ACCELERATOR AND NEUTRON GENERATOR HAVING AN EXTERNALLY AVAILABLE GROUND POTENTIAL TARGET

Barney J. Carr, deceased, late of Colorado Springs, Colo. (by Elisabeth Helen Carr, administratrix), assignor to Kaman Sciences Corporation, Colorado Springs, Colo.


Continuation-in-part of application Ser. No. 363,064, Apr. 23, 1964, now Patent No. 3,393,316, dated July 16, 1968.

This application Apr. 23, 1968, Ser. No. 723,632

Int. Cl. G21g 3/00; G21h

U.S. Cl. 250-84.5

12 Claims



Sealed neutron generator containing an isotope of hydrogen having an ion source, an accelerator and a target containing a substance which reacts with impinging ions to produce neutrons maintained at ground potential and located to be available at the exterior of the generator.

3,581,094

X-RAY APPARATUS

Leonard F. Peyser, Briarcliff Manor, N.Y., and Gordon F. Baror, Norwalk, Conn., assignors to The Machlett Laboratories, Incorporated, Springfield, Conn.

Filed Nov. 7, 1968, Ser. No. 774,106


Int. Cl. G03b 41/16

U.S. Cl. 250-105

10 Claims

X-ray apparatus for preventing overexposure of a subject to X-radiation by limiting the size of the irradiated area to conform substantially to the size of any one of a number of predetermined selected film sizes. This is achieved by an electrical system for compiling and integrating information indicative of the longitudinal and lateral dimensions of the

film area, the distance between the film and the X-ray tube, and the size of the cone of radiation as established by adjusted collimation of the X-ray beam. The electrical system functions to effectively permit operation of the X-ray tube



when integrated information indicates that the various components of the apparatus are properly adjusted so that the size of the cone of radiation and, consequently, of the irradiated area conforms substantially to the size of a film being used.

3,581,095

SOURCE PLAQUE FOR AN IRRADIATION CHAMBER OF CURVILINEAR CROSS SECTION


Jackson A. Ransohoff, Bethesda, and James J. Hairston, Jr., Rockville, Md., assignors to Neutron Products, Inc., Washington, D.C.

Filed July 17, 1967, Ser. No. 653,899

Int. Cl. G21h 5/00

U.S. Cl. 250-106

2 Claims



An elongated tubular source plaque for an irradiation chamber of curvilinear transverse cross section is formed by elongated radiation source members curved to the same curve as the curvilinear section of the irradiation chamber, and the members are spaced apart along the axis of the chamber. Each member is a tube filled with a number of individual sources may be connected end to end to form an annulus, or formed as a helix to provide the tubular source plaque. The members may be of uniform or nonuniform dosage and the spacing of the members may be regular or irregular, and may further be adjustable.

3,581,096

DEVICE FOR CONTROLLING EXPOSURE FROM A RADIOACTIVE SOURCE


George A. Seward, 12 Flaunden Lane, Bovingdon, England

Filed Sept. 3, 1968, Ser. No. 756,970

Int. Cl. G21f 5/02


U.S. Cl. 250-106

9 Claims



A device is disclosed for controlling the exposure from a radioactive source by removably positioning a radiating pellet within a bore in a shielding material in a handle-operated telescoping torch arrangement which can be stored in disassembled form in a protective container.

3,581,097
SOLID-STATE IMAGE PICKUP DEVICE
Masao Hibi, and Takeshi Nishimura, Kodaira-Shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Mar. 13, 1967, Ser. No. 622,773
Claims priority, application Japan, Mar. 16, 1966, 41/15,762
Int. Cl. H01j 39/12; H04n 3/14
U.S. Cl. 250-209 7 Claims



The solid-state image pickup device is equipped with a radiation-sensitive surface formed with a plurality of radiation-sensitive elements disposed in a matrix form, two groups of conductive strips for impressing scanning pulses to said radiation-sensitive elements, first scanning-pulse-distributing means connected to one of said two groups of conductive strips, second scanning-pulse-distributing means connected, via transistors having switching action, to the other of said two groups, and a detector for deriving, as electric signals, the changes in the characteristics of said radiation-sensitive elements.

3,581,098

AUTOMATIC BRIGHTNESS CONTROL


Alan W. Hoover, Hollins, Va., assignor to International Telephone and Telegraph Corporation, Nutley, N.Y.

Filed Feb. 24, 1969, Ser. No. 801,633

Int. Cl. H01j 31/50


U.S. Cl. 250-213

7 Claims



The brightness of a phosphor display screen of an image intensifier tube is automatically controlled by a current-limiting device connected between a direct current source and an oscillator which supplies an alternating voltage to a voltage multiplier, the latter in turn applying a direct accelerating voltage between the input photocathode and output display screen of the tube. The current-limiting device acts to provide a relatively constant current when the input light intensity and corresponding output current of the display screen increase to a predetermined level.

3,581,099
TORIC IMAGING LENS FOR SLOT SENSORS FOR SATELLITES
Georg G. F. Franke, Wetzlar, Germany, assignor to Ernst Leitz GmbH, Wetzlar, Germany
Filed Mar. 7, 1968, Ser. No. 711,314
Claims priority, application Germany, Mar. 10, 1967, L55,966;IXa/42h
Int. Cl. H01j 3/14, 5/16; G02b 3/06, 13/01
U.S. Cl. 250-216 4 Claims



Five embodiments of slot sensors for stabilizing the position of a satellite in space are disclosed. All embodiments comprise a glass body having a refractive circumferential surface of 180° angular aperture. In the image plane of the refractive surface is disposed a slot diaphragm, the slot of which is arranged to coincide with the center plane of said glass body. Behind the slot diaphragm there is provided a photoelectric receiver which is sensitive to the electromagnetic rays which are incident on the sensor.

In the different embodiments the slot diaphragms are shown to be positioned either in front of or behind the center of rotation of the toric glass body (in the direction of light travel) depending on the radius of the toric shape and on the refractive index of the glass.

3,581,100

OPTICAL READING DEVICE


Richard E. Milford, Phoenix, Ariz., assignor to Honeywell Information Systems Inc.

Filed Oct. 3, 1968, Ser. No. 764,890

Int. Cl. G08c 9/06

U.S. Cl. 250-216

4 Claims



An optical read head for record-reading electronic equipment which senses and generates signals in response to marks on documents as the documents are transported along a given path.

3,581,101

PHOTOELECTRIC BUBBLE METER FOR CHECKING GASTIGHT CONTAINERS AND THE LIKE

Teodorico Neeff, 38 Via Gran Sasso 20141, Milan, Italy

Filed July 1, 1969, Ser. No. 838,208

Claims priority, application Italy, July 13, 1968, 18930A/68


Int. Cl. G01h 21/26

U.S. Cl. 250-218

2 Claims

The disclosure relates to a device for checking the gastightness of containers and the like. The device essentially comprises: a transparent jar containing a liquid and provided with an inflow tube dipping in said liquid and an outflow tube terminating above the surface of the liquid, said inflow tube being directly or intermediately with the container to be tested; a projector outside the transparent jar adapted to

transmit a horizontal beam towards the end of the dipping tube; a photocell diametrically opposed to the projector and adapted to reveal the eventual bubbles originated by leaks in



the tested container and issuing from the dipping tube; and an impulse counting device adapted to count the bubbles revealed by the photocell.

3,581,102

PHOTOELECTRIC AND ELECTRIC LIGHT CONVERSION ELEMENT

Kazuyoshi Nagao, Kanagawa-ken, Japan, assignor to Canon Camera Co., Ltd., Tokyo, Japan


Filed Dec. 26, 1968, Ser. No. 787,058

Claims priority, application Japan, Jan. 8, 1968, Jan. 8, 1968, 43/23811;43/985

Int. Cl. G02b 5/16

U.S. Cl. 250-227

10 Claims



In photoelectric transducing apparatus of the type having an electron beam scanning a surface coated with electron activated light emitting material to convert graphic information into electrical output signals, or modulated in accordance with electrical input signals to convert the input signals into graphic information, a light transmitting means comprises a plurality of optical fibers fused together in juxtaposed relation to form a plate having a solid, voidless cross section of the optical fibers. The light transmitting means may comprise a plate severed from the fused fibers and fritted to the surface of a cathode-ray tube, in combination with a light transmitting channel formed of the fused optical fibers. The end faces of the channel may be formed either by cutting perpendicular to the lengths of the fibers or by cutting at an angle to such perpendicular.

3,581,103

ARRANGEMENT FOR THE ADJUSTMENT OF THE POSITION OF MOVABLE MACHINE ELEMENTS

Aarne Olavi Makela, Karhula, Finland, assignor to A. Ahlstrom Osakeyhtio, Noormarkku, Finland

Filed Dec. 30, 1968, Ser. No. 787,870

Claims priority, application Finland, Jan. 3, 1968, 13/68


Int. Cl. G05b 13/02; G01d 5/34

U.S. Cl. 250-231

4 Claims

The invention is particularly applicable for the adjustment of an edge trimming saw by remote control, wherein the number of positions into which the machine element is to be adjusted is small. There is described a nonlinear system comprising a coarse adjustment for transferring the element to

the vicinity of the desired point at a high velocity and a fine adjustment to transfer the body at a low velocity toward its



final position. The fine adjustment is effected by a photocell device and a toothed strip of opaque material.

3,581,104

VOLTAGE SPLITTER CIRCUIT


Donald G. Thew, Milwaukee, Wis., assignor to Hornischfeger Corporation, West Milwaukee, Wis.

Filed Mar. 5, 1970, Ser. No. 16,827

Int. Cl. H02j 1/14, 3/46

U.S. Cl. 307—15

5 Claims



A voltage splitter circuit provides a terminal voltage equal to half the voltage impressed across a pair of voltage busses. The voltage at the intermediate terminal may be used to provide two equal, but opposite, voltages between the intermediate terminal and each of the busses. The intermediate terminal is located between the output circuits of two complementary transistors connected across the busses. The transistors are operated by an amplifier driven by a voltage divider. A feedback circuit exists between the intermediate terminal and the input of the amplifier to stabilize the circuit.

3,581,105

SWITCHING APPARATUS


David B. Gish, Pasadena, Calif., assignor to Bell & Howell Company, Chicago, Ill.

Filed Sept. 23, 1968, Ser. No. 761,698

Int. Cl. H01h 35/00

U.S. Cl. 307—116

13 Claims



A two-terminal switching apparatus which includes a transducer requiring drive energization for producing a sensing capability. The transducer and a switch are parallel con-

nected across the terminals, and one of the terminals is connectable to a source of electrical energy through an external load, while the other terminal is connectable to common. A preset voltage difference appears across the terminals when the switch is conducting, which voltage difference is sufficient to permit transducer drive continuity.

3,581,106

GRADED PLANE, HIGH VOLTAGE DC POWER SUPPLY


Joseph T. Peoples, and Charles C. Landry, Austin, Tex., assignors to Nuclear-Chicago Corp., Des Plaines, Ill.

Filed Apr. 5, 1968, Ser. No. 719,107

Int. Cl. H02j 5/00

U.S. Cl. 307—150

7 Claims



A high voltage electron accelerator system employing a graded plane power supply, a graded plane accelerator, and a single, graded-conductor cable interconnecting the power supply and the accelerator.

3,581,107

DIGITAL LOGIC CLAMP FOR LIMITING POWER CONSUMPTION OF INTERFACE GATE


Einer Dale Nielsen, Los Gatos, Calif., assignor to Signetics Corporation, Sunnyvale, Calif.

Filed Mar. 20, 1968, Ser. No. 714,645

Int. Cl. H03k 19/36, 5/08

U.S. Cl. 307—215

3 Claims



A NAND-type logic gate for interfacing high voltage logic levels with a low level output. Feedback means including a diode are coupled between the base input of an amplifier which is coupled to the input logic terminals and the output. The feedback functions to clamp the input of the amplifier to a relatively low voltage to cause a dropping resistor between the high voltage power supply and the base input of the amplifier to have an increased voltage drop with increased power supply voltage to thus maintain the drive of the amplifier substantially constant. On the other hand, the feedback path is also coupled to ground through an output transistor to thus reflect load current changes to allow the drive voltage to the amplifier to increase in response to increased drive requirements. The diode in the feedback path provides for nonlinearity to thus prevent oscillations.

3,581,108

SINGLE OUTPUT SELECTING CIRCUIT EMPLOYING A PLURALITY OF INTERLOCKED NOR-GATES


Irving V. Eisenmenger, Burlington, N.C., assignor to Western Electric Company, Incorporated, New York, N.Y.

Filed Dec. 5, 1968, Ser. No. 781,359

Int. Cl. H03k 19/34

U.S. Cl. 307—215

3 Claims U.S. Cl. 307—237



A plurality of NOR gates are arranged with the output of each gate connected to an associated output terminal and to an input of every other gate. Energization of a selected output terminal, inhibits the operation of each gate other than the one associated with the selected output terminal thereby latching the one associated with the selected terminal in an energized condition and the nonselected terminals in a nonenergized condition.

3,581,109

CIRCUIT SYSTEM FOR PRODUCING AN OUTPUT SIGNAL FROM A VARIABLE AMPLITUDE SIGNAL WHEN THE AMPLITUDE OF SAID SIGNAL IS WITHIN A SELECTED RANGE

Tore Bertil Reinhold Olsson, and Ake Valentin Nilsson, Karl-skoga, Sweden, assignors to Aktiebolaget Bofors, Bofors, Sweden


Filed Oct. 23, 1967, Ser. No. 677,122

Claims priority, application Sweden, Apr. 3, 1967, 4615/67


Int. Cl. H03k 5/20

U.S. Cl. 307—235

12 Claims



on at least one transformer having at least one transformer secondary which is DC isolated from the aforementioned input and from the supply voltage sources, with means for rectifying the alternating voltage signal and with one output for delivering a DC voltage whose polarity depends on the



state of the input signal, the connections between the transformer secondary and the relay output being provided via the emitter-collector connections of two transistors, which are driven by currents derived from the transformer secondary and applied to the base.

3,581,113

SWITCHING DEVICE FOR DISCONNECTING CABLES
Wilhelm Kafka, Tennenlohe, Germany, assignor to Siemens Aktiengesellschaft, Berlin, Germany


Filed July 25, 1968, Ser. No. 747,684

Claims priority, application Germany, Aug. 4, 1967, S111185 VIII/21c

Int. Cl. H01v 11/10, 11/16

U.S. Cl. 307-245

14 Claims



A switching device for disconnecting superconductive current-carrying cables has a superconductive circuit which provides a high resistance in the normal conducting state. A control mechanism is provided for transferring the superconductive circuit from the superconducting state to the normal conducting state.

3,581,114

SCR SLAVING CIRCUIT


Robert E. Gregson, Scottsdale, Ariz., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Sept. 3, 1968, Ser. No. 756,972

Int. Cl. H03k 17/00

U.S. Cl. 307-252

5 Claims



An SCR slaving circuit wherein first and second controlled rectifiers are connected in parallel with each other and are

further connected in series with a load across an AC line. A control signal is coupled to the gate electrode of the first controlled rectifier to control the slaving action in the circuit, and rectifier control circuitry is coupled between one side of the AC line and the gate electrode of the second controlled rectifier. The rectifier control circuitry blocks gate current to the second controlled rectifier on one-half cycle of the AC line voltage and thereafter provides gate current to turn on the second controlled rectifier. The second controlled rectifier will turn on the following half-cycle of the AC line voltage provided that the first controlled rectifier was conducting the previous half-cycle of the AC line voltage.

3,581,115

PULSE GENERATOR FOR PROVIDING A PLURALITY OF PULSES IN DETERMINED PHASE POSITIONS

Rolf Weber, Munich, Germany, assignor to Siemens Aktiengesellschaft, Berlin, Germany

Filed June 20, 1969, Ser. No. 834,946


Claims priority, application Germany, June 22, 1968,

1,762,470

Int. Cl. H03k 1/12

U.S. Cl. 307-262

7 Claims



A switch is switched to its conductive condition by the output of a bistable multivibrator and transfers pulses produced by a pulse generator to a counter. The counter counts the pulses and supplies an output signal indicating the end of a counting cycle to an AND gate connected in the reset input of the multivibrator. When an auxiliary signal is supplied to the AND gate, the output signal of the counter resets the multivibrator and the switch is switched to its nonconductive condition and prevents the supply of pulses from the pulse generator to the counter.

3,581,116

DIGITAL CONTROLLED STEP VOLTAGE GENERATOR
Joseph Leostic, Le Mesnil Saint-Denis, France, assignor to C.I.T. Compagnie Industrielle Des Telecommunications, Paris, France


Filed Sept. 4, 1968, Ser. No. 757,441

Claims priority, application France, Sept. 4, 1967, 119905

Int. Cl. H03k 25/00

U.S. Cl. 307-264

11 Claims



Digital-controlled generator supplying, during a major cycle, a continuous voltage which is proportional to the fraction i/N of a fixed voltage, with i variable in units from 0 to

N, said major cycle having a duration of K minor cycles, of which each lasts N times an elementary duration t_0 .

3,581,117

THYRISTOR CIRCUIT HAVING IMPROVED TURNOFF CHARACTERISTICS


Lloyd H. Dixon, Jr., Boxford, Mass., assignor to Unitrode Corporation, Watertown, Mass.

Filed July 9, 1968, Ser. No. 743,386

Int. Cl. H03k 17/00

U.S. Cl. 307-252

7 Claims



A thyristor circuit in which self-triggering which may be caused by spurious gate drive is prevented. A thyristor is switched off by interrupting the flow of cathode current while providing a gate circuit path for charging the anode-gate junction capacitor. Upon reapplication of cathode current, self-triggering cannot occur by reason of the fully charged condition of the junction capacitor.

3,581,118

METHOD OF PULSE SHAPING AND RENEWABLE DURATION VARIABLE PULSE-SHAPING CIRCUIT FOR THE APPLICATION OF SAID METHOD

Robert Van Zurk, Meylan, France, assignor to Commissariat A L'Energie Atomique, Paris, France


Filed June 17, 1968, Ser. No. 737,765

Claims priority, application France, June 21, 1967, 111,389

Int. Cl. H03k 1/18

U.S. Cl. 307-267

10 Claims



A method of pulse shaping and an electronic assembly for carrying out said method whereby incident pulses are transmitted to a counter in order to reset said counter to zero, and whereby the resultant signal is recycled, the operation is continued as long as the counter has not recorded a predetermined number and the successive pulses produced by the generator are converted to a single wide pulse. The assembly comprises a counter which has a plurality (n) of flip-flops, an

element for resetting the counter to zero and coupled to the input of the assembly, a logic circuit whose inputs are coupled to each flip-flop of the counter, a pulse generator controlled by the logic circuit as well as a zero-overlap variable shaping device which follows said pulse generator and is coupled to the input of the counter as well as to the output of the assembly.

3,581,119

PHOTO-CURRENT DIVERTER


Gary Grundy, Rosemount, Minn., assignor to The United States of America as represented by the Secretary of the Air Force

Filed Apr. 8, 1969, Ser. No. 814,335

Int. Cl. H03k 17/16

U.S. Cl. 307-288

3 Claims



A transistorized clamping circuit is useful to quickly and efficiently divert radiation induced photocurrents to prevent damage to semiconductor systems. Through the use of a low power, fast turn-on transistor and a high power, slow turn-on transistor, the circuit is able to divert both the initial photocurrent surge and the continuing high photocurrent generated by the radiation.

3,581,120

SCHMITT TRIGGER CIRCUIT WITH VARIABLE HYSTERESIS AND INSENSITIVITY TO TEMPERATURE CHANGE


Hans H. Nord, Little Falls, N.J., assignor to The Western Union Telegraph Company, New York, N.Y.

Filed Feb. 28, 1968, Ser. No. 709,033

Int. Cl. H03k 3/15, 3/295

U.S. Cl. 307-290

3 Claims



A Schmitt trigger circuit is disclosed which employs a complementary pair of transistors in a direct coupled configuration with regenerative feedback. The circuit provides means for controlling hysteresis and is substantially insensitive to temperature changes of its transistors. The circuit employs a single variable resistor in a common emitter circuit to provide symmetrical change in hysteresis.

3,581,121

DELAY LINE ARRANGEMENT

John Thomas Lawrence Sharpe, Harlow, Essex, England, assignor to International Standard Electric Corporation, New York, N.Y.


Filed Mar. 26, 1969, Ser. No. 810,631

Claims priority, application Great Britain, Apr. 16, 1968, 17808/68

Int. Cl. H03k 17/28

U.S. Cl. 307—293

3 Claims



An automatic equalization circuit, e.g. for telephone channels carrying high-speed data, of the kind using a lumped-constant delay line for temporary storage of channel signals, is simplified by substituting for the delay line a chain of capacitive storage elements linked by diode or FET gates.

3,581,122

ALL-PASS FILTER CIRCUIT HAVING NEGATIVE RESISTANCE SHUNTING RESONANT CIRCUIT


Wilmer B. Gaunt, Jr., Boxford, Mass., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, Berkeley Heights, N.J.

Filed Oct. 26, 1967, Ser. No. 678,417

Int. Cl. H04b 3/14

U.S. Cl. 307—295

7 Claims



A transistor circuit having a constant amplitude vs frequency response is described. The required transfer function is obtained by connecting a negative resistance across a resonant network in the transistor circuit. This arrangement provides a pole-zero pattern in the complex plane representation which is symmetrical with respect to the imaginary axis whereby the absolute magnitude of the ratio of output signal to input signal is constant for all frequencies.

3,581,123

CIRCUIT FOR PROVIDING INDUCTIVE IMPEDANCE

Jurgen Pest, Lynchburg, Va., assignor to General Electric Company

Filed Mar. 27, 1969, Ser. No. 811,031


Int. Cl. H01p 1/24

U.S. Cl. 307—304

1 Claim

A field-effect transistor, having a source electrode, a drain electrode, a first insulated gate electrode, and a second insulated gate electrode, is provided with a feedback circuit comprising one or more series resistors and one or more shunt

capacitors connected between the drain electrode and the first insulated gate electrode. This circuit provides an induc-



tive impedance between the source and drain electrodes without inductive coils.

3,581,124

SOLID-STATE TOUCH-RESPONSIVE SWITCH CIRCUIT


Richard A. Flores, 425 S. Reese Place, Burbank, Calif., and Michael Sherman, 17042 Lorillard St., Granada Hills, Calif.

Filed Jan. 17, 1969, Ser. No. 797,719

Int. Cl. H03k 4/48

U.S. Cl. 307—308

8 Claims



A solid-state touch-responsive switch circuit using principally NPN transistors. The base of the first transistor is connected direct to a grounding key adapted preferably to be touched by a finger. The emitter of the transistor is connected to ground through a clock-pulse generator. The collector of this transistor is connected to a power supply through a suitable resistor and to the base of a second transistor through a rectifying diode. This second transistor together with transistors three and four comprise a clamping and amplifying circuit for the output. A feedback line from the outputs of the amplifying transistors back to the base of the first transistor through a diode clamps the output "on" only after the finger has switched the base of the first transistor to "on" and holds it on when the finger has been removed from the key.

3,581,125

OSCILLATOR CIRCUIT FOR ULTRASONIC APPARATUS

John P. Arndt, Cleveland, and Edmond G. Franklin, North Canton, Ohio, assignors to Clevite Corporation

Division of Ser. No. 660,262, Aug. 14, 1967, Pat. No. 3,516,645

Filed Sept. 30, 1969, Ser. No. 862,342

Int. Cl. H01v 7/00


U.S. Cl. 310—8.1

9 Claims

An oscillator circuit is provided for ultrasonic apparatus such as ultrasonic cleaners employing a resonant transducer. The circuit includes a pair of transistors connected in series to a source of power with the transducer connected across one of the transistors in series with the primary winding of a transformer which has secondary windings connected in opposite polarity to the bases of the transistors so that one

transistor is saturated while the other is nonconducting. The circuit accordingly oscillates at substantially the resonant

frequency which provides the flux path. There are field windings fitted between adjacent pole pieces, and pairs of brushes



3,581,126

MOUNTING DEVICE FOR FLEXION VIBRATORS

Luc Omlin, Neuchatel, Switzerland, assignor to Centre Electronique Horloger S. A., Neuchatel, Switzerland


Filed Dec. 29, 1969, Ser. No. 888,513

Claims priority, application Switzerland, Jan. 13, 1969, 402/69

Int. Cl. H01v 7/00

U.S. Cl. 310—9.1

10 Claims



A mounting device for flexion vibrators with two vibration node axes, in particular X-Y flexion quartzes in time-measuring apparatus, which have a hold on the surfaces of the flexion vibrator in the neighborhood of nodes in the points of emergence of the vibration node axes, comprising strips of approximately rectangular cross section in connection members between flexion vibrator and securing points on a support. One end of each strip respectively is directly secured to the flexion vibrator whilst the other end is connected to the support; the long sides of the sections of the strips run practically parallel to the main direction of vibration, and the strips are bent practically perpendicularly to the main direction of vibration and at least partly in a direction perpendicular to the vibration node axes.

3,581,127

LINEAR ELECTRIC MOTOR

Kenneth Warnett, Wyke, Bradford, England, assignor to Electro-Lifts Limited, Leeds, England

Filed Apr. 21, 1969, Ser. No. 817,670


Claims priority, application Great Britain, Apr. 20, 1968, 1877/68

Int. Cl. H02k 41/02

U.S. Cl. 310—13

3 Claims

A linear motor has an armature with an electrical winding and a stator with a plurality of axially spaced pole pieces. These pole pieces are of annular formation surrounding the armature, and are joined together by a cylindrical outer cas-



mounted on the faces of the intermediate pole pieces and urged into contact with the armature winding.

3,581,128

STEPPING WHEEL

Alfred Meisner, and Walter Spitzl, Nurnberg, Germany, assignors to Diehl, Nurnberg, Germany


Filed Oct. 3, 1969, Ser. No. 863,525

Claims priority, application Germany, Oct. 9, 1968, P 18 01 972.2

Int. Cl. H02k 7/02

U.S. Cl. 310—21

12 Claims



A drive for a clockwork in which a magnet is caused to oscillate adjacent a wheel in the radial direction of the wheel. An undulating magnetic path is formed on the wheel in the range of oscillation of the magnet and the configuration of the magnetic path is such that oscillation of the magnet will develop a torque on the wheel to drive it in one direction only.

3,581,129

TUNING FORK DEVICES

Wolfgang Ganter, Schramberg/Sulgen, and Friedrich Assmus, Schramberg/Wurttemberg, Germany, assignors to Messrs. Gebruder Junghans Gesellschaft mit Beschränkter Haftung, Schramberg Wurttemberg, Germany


Division of Ser. No. 816,264, Apr. 15, 1969, Pat. No. 3,529,414

which is a division of application Ser. No. 555,766, now Patent No. 3,456,137. Filed June 5, 1970, Ser. No. 43,702

Int. Cl. H02k 33/00

U.S. Cl. 310—25

2 Claims



A tuning fork for timekeeping devices having two parallel tines with a permanent magnet mounted on each free end thereof and means to mount the tines on a baseplate and a

housinglike magnet-return bracket fixed to the baseplate and surrounding the permanent magnets and bearing the coil assembly.


3,581,130

COUNTERBALANCED RESILIENTLY SUPPORTED TUNING FORK

Boris F. Grib, Huntington, N.Y., assignor to Philamon Incorporated, Westbury, N.Y.
Continuation-in-part of application Ser. No. 743,445, July 9, 1968, now Patent No. 3,480,809. This application Nov. 24, 1969, Ser. No. 879,361
Int. Cl. H02k 33/00

U.S. Cl. 310-25

9 Claims



There is disclosed a tuning fork resonator with electrical drive and pickup coils and a tuning fork having a pair of tines, a common tine-junction section, a supporting portion for securing the fork in place and a pliant section between the common tine-junction portion and the supporting portion of the fork. The fork is provided with a counterbalance which is oppositely disposed from the tines of the fork with respect to the pliant section. The counterbalance counteracts the tendency of the tine ends to rotate in response to lateral acceleration force due to compliance of the pliant section and in some cases also counteracts the response to lateral acceleration force due to bending of the tines themselves. A version is disclosed in which there are two forks laterally spaced with the tine ends physically bridged together by shutters to form an elongated undulating aperture and with the counterbalance and common tine-junction portions of the two forks consisting of a common bridging structure which is relatively rigid so that the two pairs of tines of the respective fork sections are substantially in unison both as to tine vibrations and as to reaction to acceleration forces.

3,581,131

SMALL ELECTRIC MOTORS FOR DENTAL EQUIPMENT OR THE LIKE

Cestmir Richter, Nachod, Czechoslovakia, assignor to Mez Nachod, Narodni podnik, Nachod, Czechoslovakia
Filed Dec. 2, 1969, Ser. No. 881,491

Claims priority, application Czechoslovakia, Dec. 11, 1968, PV8425/61


Int. Cl. H02k 9/10

U.S. Cl. 310-58

8 Claims

A relatively small electric motor adapted to be used for operating dental equipment or the like. The motor includes a rotor and a stator, situated in a motor housing which is formed at its exterior with an inlet passage extending forwardly for directing cooling air to the front of the rotor and stator to flow rearwardly through the gap therebetween. The housing is also formed with an outlet passage having a front end communicating only with the rear of this gap and with the outer atmosphere. In this way cooling air can enter from the rear of the housing into the inlet passage to flow

therealong to the front where the cooling air reverses its direction of flow so as to travel rearwardly through the gap



3,581,132

ROTATING ELECTRICAL MACHINE


Nikolaus Laing, 35-37 Hofener Weg, 7141, Aldingen, Germany

Filed Apr. 3, 1969, Ser. No. 813,096

Int. Cl. H02k 17/00

U.S. Cl. 310-166

17 Claims



In a rotating electrical machine having a pole ring having poles which extend towards the airgap between the stator and the rotor and which are formed with winding slots extending parallel to the rotor axis, the winding extending radially through the winding slots, the pole surfaces near the airgap are larger than the smallest cross sections of the poles. The armatures of such rotating machines can in known manner be formed by spirally coiled strip. A rotating electrical machine of this kind makes a very good pump motor of the kind wherein a partition provides a sealingtight separation between the driven element and the driving element.

3,581,133

GASEOUS DISCHARGE TUBE WITH METALLICALLY COATED, ELECTRODE SUPPORT PORTIONS


Jiro Ushio, Tokyo, Japan, assignor to Ushio Electric Inc., Tokyo, Japan

Filed Dec. 23, 1968, Ser. No. 786,216

Int. Cl. H01j 17/04

U.S. Cl. 313-43

2 Claims



A discharge tube characterized in that a coat of an element selected from the group consisting of rhenium, niobium and

rhodium is applied to a supported portion of an electrode or an electrode supporting member of an electrode which is supported by an electrode supporting portion of a quartz or glass envelope of the discharge tube.

3,581,134

CATHODE RAY TUBE HAVING AN ANNULAR-SHAPED REAR WINDOW


Alfred D. Johnson, Seneca Falls, N.Y., assignor to Sylvania Electric Products Inc.

Filed Dec. 20, 1968, Ser. No. 785,646

Int. Cl. H01j 29/86

U.S. Cl. 313-64

1 Claim



A rear-window cathode ray tube having a longitudinal axis and an envelope of substantially glass construction wherein there is oriented a cathodoluminescent screen and at least one related electron gun. The envelope has a substantially annular-shaped optical access window therein oriented in substantially symmetrical relationship to the longitudinal axis of the tube to provide a substantially annular viewing area for observing the electron impinging side of the screen.

3,581,135

COLOR TUBE ELECTRON SHIELD HAVING OUTWARDLY BOWED EDGES DIRECTED TOWARD VIEWING SCREEN TO MINIMIZE SEAL EDGE INTERFERENCE


Elgie E. Garrett, Chicago; Thomas P. De Franco, Norridge, and Nicholas B. Staples, Chicago, Ill., assignors to Admiral Corporation, Chicago, Ill.

Filed Nov. 18, 1968, Ser. No. 776,338

Int. Cl. H01j 1/53, 29/40

U.S. Cl. 313-85

9 Claims



An electron barrier consisting of two identical shields of semirigid formed aluminum foil having forwardly bowed

edges resiliently contacting the inner wall of a color picture tube panel well below frit seal line. The shadow-mask frame includes a lip cooperating with raised portions on the shields to insure flexure of the bowed edges during installation.

3,581,136

COLOR DOT SCREEN WITH DOT FORM COMPENSATION FOR APPARENT SHIFT OF BEAM DEFLECTION CENTER


Kenneth L. Staunton, Columbus Grove, Ohio, assignor to Sylvania Electric Products, Inc.

Division of Ser. No. 665,563, Sept. 5, 1967, Pat. No. 3,499,372. Filed July 9, 1969, Ser. No. 871,037

Int. Cl. H01j 29/32, 29/30

U.S. Cl. 313-92B

4 Claims



An optical system utilized for providing a tridot patterned color cathode ray tube screen wherein the dot patterns are modified in discrete screen areas to improve the registration of the electron beams with their respective phosphor dots thereby improving color purity of the display. The light source in the optical system used in effecting screen exposure has contiguously oriented light control means with portions formed to provide both symmetrical and unsymmetrical exposure illumination. Thus, by utilizing unsymmetrical exposure, patterns of elongated dots are disposed on different discrete portions of the screen for each of the respective phosphors to achieve improved beam dot registration.

3,581,137

ELECTRIC LAMP HAVING AN ENVELOPE COMPOSED OF PHOTORESISTANT SODA-LIME SILICATE GLASS

Edward G. F. Arnott, Wilkinsburg, and Daniel W. Lewis, Pittsburgh, Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.

Continuation-in-part of application Ser. No. 741,370, July 1, 1968, which is a continuation-in-part of application Ser. No. 657,123, July 31, 1967. This application July 15, 1968, Ser. No. 744,832

Int. Cl. H01j 1/63, 61/30, 61/35


U.S. Cl. 313-109

16 Claims

The light output and lumen maintenance of an electric lamp that generates both visible and ultraviolet radiations (e.g., a fluorescent, an incandescent, or a high-pressure mercury vapor discharge lamp) is enhanced by utilizing an envelope that is composed of a modified soda-lime silicate glass which has a low initial coefficient of absorption in the visible region (below about 0.05 cm.⁻¹), and inhibits the discoloration or "solarization" effect of impinging ultraviolet-radiation. The absorption coefficient in the visible region is maintained below approximately 0.4 cm.⁻¹ after prolonged exposure of the envelope to ultraviolet radiation by controlling the Fe₂O₃ content and adding selected amounts of TiO₂ or MoO₃, or mixtures thereof, to the glass during manufacture. The preferred ranges are between 0.8 percent and about 3

percent by weight TiO_2 , and from about 0.5 percent to 1 percent by weight MoO_3 , when these materials are added as

With 1.25 percent by weight TiO_2 in the glass, the amount of phosphor required per lamp is reduced by 30 percent without decreasing the light output or lumen maintenance. In the case of calcium halophosphate type phosphor, the



separate components. The Fe_2O_3 content does not exceed about 0.07 percent by weight.

3,581,138

GAS DISCHARGE TUBE WITH COLD CATHODE SUITABLE FOR THE SIMULTANEOUS REPRODUCTION OF TWO LEGIBLE CHARACTERS

Adrianus Anthonius Maria Hendriks, Emmasingel, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Jan. 8, 1969, Ser. No. 789,773

Claims priority, application Netherlands, Jan. 12, 1968, 6,800,473

Int. Cl. H01j 61/66

U.S. Cl. 313-109.5

2 Claims



A gas discharge tube for reproducing two independently switchable legible characters which adjoin each other and constitute two groups, the characters being secured to annular frames of equal dimensions but having dimensions which are smaller than the frame and the groups being surrounded by a partially perforated anode. The two groups of characters are associated with a single electrode set. Since the characters are smaller than the associated frame, two characters associated with different groups can be reproduced.

3,581,139

FLUORESCENT LAMP HAVING TITANIUM DIOXIDE-CONTAINING GLASS ENVELOPE AND REDUCED PHOSPHOR WEIGHT

Harry H. Haft, Whippany, and Robert W. Repsher, Kenilston, N.J., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.


Filed Mar. 20, 1969, Ser. No. 808,801

Int. Cl. H01j 61/30, 61/42

U.S. Cl. 313-109

6 Claims

TiO_2 is included as a constituent in the soda-lime silicate glass envelope of a fluorescent lamp in an amount sufficient to chemically stabilize the glass and thus permit the use of a thinner phosphor coating without decreasing the light output of the lamp or impairing its lumen maintenance. Up to 10 percent by weight TiO_2 is employed and less than 2 percent by weight is preferred to minimize lamp cost. The TiO_2 also inhibits solarization and the resultant darkening of the envelope under the influence of the impinging ultraviolet radiations generated within the lamp during operation.



3,581,140

HIGH INTENSITY LIGHT SOURCE WITH INTEGRAL RADIANT-ENERGY-COUPLING APPARATUS


Raymond E. Paquette, Saratoga, Calif., assignor to Varo, Inc., Garland, Tex.

Filed June 11, 1968, Ser. No. 736,082

Int. Cl. H01j 51/16

U.S. Cl. 313-110

6 Claims



An optically efficient light-transmitting rod is formed integral with the envelope of a high intensity illumination producing means such that one end of the rod is positioned proximate the luminant source, and the other is shaped into a suitable utilization form or is adapted so as to provide a means with which to couple the radiant energy to a utilization means.

3,581,141

SURFACE GAP SPARK PLUG


Richard C. Beaubier, Royal Oak, Mich., assignor to Ethyl Corporation, New York, N.Y.

Continuation-in-part of application Ser. No. 776,441, Nov. 18, 1968, now abandoned. This application Apr. 7, 1969, Ser. No. 813,947

Int. Cl. H01t 13/32, 13/52

U.S. Cl. 313-130

17 Claims



A surface gap spark plug having improved resistance to fouling is described. A method of operating an internal combustion engine and other devices, which utilize a fuel containing an organometallic additive is also disclosed.

3,581,142

TRIGGERED VACUUM GAP DEVICE WITH MEANS FOR REDUCING THE DELAY TIME TO ARC-OVER THE MAIN GAP

Raymond L. Boxman, Cambridge, Mass., assignor to General Electric Company


Continuation-in-part of Ser. No. 792,709, Jan. 21, 1969.

Filed Mar. 19, 1969, Ser. No. 808,617

Int. Cl. H01j 1/50

U.S. Cl. 313-162

6 Claims



Discloses a triggered vacuum gap device that comprises a pair of spaced-apart main electrodes defining a main gap therebetween and triggering means adjacent one of the main electrodes but relatively remote from the other for causing arc-over of said main gap upon activation of said triggering means. For reducing the time delay between activation of the triggering means and arc-over of the main gap when the relatively remote electrode is negative, means is provided for developing a magnetic field generally parallel to the electric field between the electrodes in the region of the triggering means.

3,581,143

NONTRACKING WIRE SPARK GAP COMPONENT


John E. Dornfeld, Mequon, Wis., assignor to Sprague Electric Company, North Adams, Mass.

Filed Jan. 16, 1969, Ser. No. 791,683

Int. Cl. H01j 17/00, 21/00

U.S. Cl. 313-325

4 Claims



Each of two noncontacting wire leads has a face of one extremity in registration a predetermined fixed distance from its counterpart to form a spark gap therebetween. Each lead is bent so that the extensions of the leads are oppositely disposed and spaced from each other by a distance substantially greater than the spark gap. A mass of nonconducting material covers both of the bends, and bridges the lead extensions near the bends so as to fix the spacing of the spark gap. The mass is also set back on both sides of the spark gap a distance at least sufficient to assure avoidance of exposure of the mass to carbonizing temperatures during sparking within the voltage rating range of the unit.

3,581,144

METAL-CLAD INSULATED ELECTRICAL HEATER


James E. Beggs, Schenectady, N.Y., assignor to General Electric Company

Filed Mar. 27, 1969, Ser. No. 811,067

Int. Cl. H01j 1/24

U.S. Cl. 313-340

8 Claims



A low mass insulated heater that can be bonded with low thermal drop to an object to be heated consists of a planar arrangement of a heater wire which, after being covered with a thin coating of insulation, is coated with material that is sintered or alloyed to form a metallic sheath. The sheath is brazed directly to a member to be heated to form an integrally bonded structure in which the composite materials all have similar thermal expansion characteristics.

3,581,145

PULSE-FORMING NETWORK FOR A SHORT PULSE LINEAR ACCELERATOR

Dennis E. Morris, Sunnyvale, Calif., assignor to Varian Associates, Palo Alto, Calif.


Continuation-in-part of Ser. No. 792,709, Jan. 21, 1969.

Filed Mar. 3, 1969, Ser. No. 803,921

Int. Cl. H01j 25/36

U.S. Cl. 315-30

4 Claims



A pulse-forming network is disclosed as employed for pulsing the beam of a microwave linear accelerator to provide a train of beam pulses, such pulses being on the order of 2 nanoseconds long. The pulse-forming network includes a pair of open-circuited coaxial cables connected in parallel between a source of potential and an adder. The adder supplies a pulse output to the cathode of the electron gun of the accelerator. One of the parallel branches of the pulse-forming network includes a series connection of one of the coaxial cables, and a delay, and a pulse inverter. The inverted and noninverted pulses obtained by simultaneously shorting the charged coaxial lines to ground are added in the adder to produce a resultant negative pulse applied to the cathode of the gun for turning the gun on for the short 2 nanoseconds. Ferrite-loaded coaxial pulse shapers are disposed in each of the parallel branches for sharpening the leading edge of the resultant negative pulse. One of the distributed coaxial lines is substantially longer than the other to make the positive inverted pulse longer than the negative noninverted pulse, such that the gun is held in the OFF condition for a period following each of the pulses to prevent unwanted dark current. A coupling capacitor is connected between the pulse inverter and ground for holding off a positive quiescent DC bias potential applied to the cathode of the gun. A variable DC current is fed through one of the pulse shapers for varying the pulse width of the resultant pulse.


3,581,146

BALLAST FOR A PLURALITY OF PARALLEL GASEOUS DISCHARGES

Alan E. Hill, 5444 A, Rte. 5, Albuquerque, N. Mex.
Filed July 29, 1969, Ser. No. 845,808
Int. Cl. G05f 1/06

U.S. Cl. 315-180

6 Claims




A plurality of gaseous discharge tubes connected to a common power supply has a vacuum tube connected in series with each gaseous discharge tube to provide ballast for the individual gaseous discharge tubes, a water-cooled, heavy duty anode is provided with a plurality of cathodes positioned adjacent the anode. A discharge tube is connected in each of the cathode circuits. Negative feedback is used to limit the current through each discharge tube. Variable feedback resistors permit balancing of the discharge paths.

3,581,147

ELECTRONIC PULSE COUNTER WITH BISTABLE SWITCHING ELEMENTS

Lev Nickolaevich Korablev, Moscow, U.S.S.R., assignor to Fizicheskoye Institut IM.P.N., Lebedeva, Moscow, U.S.S.R.
Filed Aug. 14, 1967, Ser. No. 660,326
Int. Cl. H01j 17/36; H03k 21/32, 23/18, 23/28
U.S. Cl. 315-84.5

13 Claims




Several different embodiments of the invention in the form of different pulse counters are disclosed involving the use of switching elements and particularly cold-cathode tubes in association with coincidence circuits to provide a pulse counter, there being particularly employed a one-way feedback circuit which has a reduced number of switching elements, smaller than the conversion factor and capacitance of the counter, the input of the first element or stage being directly connected to the counter input, and the combined outputs of at least two last elements or stages of the counter being connected by a unidirectional feedback circuit for returning the preceding elements or stages to the initial zero condition.

DIRECT CURRENT STATIC TRANSFORMER

Roger Raoul Brignet, 98, Rve Saint Spire, Corbeil-Essones, France
Continuation-in-part of application Ser. No. 637,470, May 10, 1967. This application June 4, 1969, Ser. No. 830,312
Int. Cl. H05b 37/00, 39/00, 41/14
U.S. Cl. 315-227

4 Claims



A direct current static transformer for continuous operation comprising a series of successive stages each including a first conductive plate having a multiplicity of thin, needlelike individual electrodes directed toward a second conductive plate, the second conductive plate having a relatively smooth surface facing toward the needle electrodes. Each stage further includes an electrically conductive grid interposed between the first and second plates, the grid being electrically connected to the first plate. The second plate for one stage constitutes the first plate for the next succeeding stage in the transformer. In a preferred construction, there are two such series of successive stages, one series connected to the positive terminal of a DC supply and the other series connected to the negative terminal, with a capacitor connected between the corresponding plates of the two series in each stage.


3,581,149

CORONA DISCHARGING DEVICE FOR ELECTROPHOTOGRAPHIC PROCESS

Hiroshi Tanaka, and Masayoshi Ishihara, both of Tokyo, Japan, assignors to Canon Camera Kabushiki Kaisha, Tokyo, Japan
Filed July 11, 1968, Ser. No. 744,117
Claims priority, application Japan, July 14, 1967, 45-468/67
Int. Cl. H05h 1/00

U.S. Cl. 317-4

8 Claims



Apparatus for use in imparting charge to a member including a conductive element having an end juxtaposed with the surface of the member being charged and a needle-form corona discharge electrode providing a discharge directed principally onto the conductive element. The corona discharge electrode is disposed in a plane substantially non-perpendicular to the member being charged and intersecting the plane containing the conductive element.

3,581,150

OVERVOLTAGE PROTECTION CIRCUIT FOR A GENERATOR REGULATOR SYSTEM

Thomas E. Kirk, and Gerald H. Stenklyft, both of Anderson, Ind., assignors to General Motors Corporation, Detroit, Mich.

Filed Apr. 8, 1970, Ser. No. 26,707

Int. Cl. H02h 3/22; H02j 7/14

U.S. Cl. 317-16

2 Claims



An overvoltage protection circuit for a vehicle electrical generating system provides a plurality of controlled rectifiers connected to the generator output winding for shunting high transient voltages to ground. A control transistor having a time delay biasing circuit is connected to the field winding excitation circuit for holding the field winding deenergized during the high voltage condition. A single overvoltage detecting device is used to render both the plurality of controlled rectifiers and the control transistor conductive.


3,581,151

COLD CATHODE STRUCTURE COMPRISING SEMICONDUCTOR WHISKER ELEMENTS

Willard S. Boyle, Summit, and Jack A. Morton, South Branch, both of N.J., assignors to Bell Telephone Laboratories Incorporated, Murray Hill, N.J.
Filed Sept. 16, 1968, Ser. No. 762,296
Int. Cl. H01l 3/00, 5/00

U.S. Cl. 317-234

9 Claims



Cold cathode structures comprise a plurality of semiconductor whisker elements each including an electronic barrier near the free end. Electron emission is enhanced by a high external field that is concentrated at the tip of each whisker element.

3,581,152

GROUND PROTECTION AND DETECTING FOR HIGH VOLTAGE DC TRANSMISSION SYSTEM

Lloyd F. Hunt, 221 Rocky Point Road, Palos Verdes Estates, Calif.

Filed Mar. 16, 1970, Ser. No. 19,750


Int. Cl. H02h 3/16

U.S. Cl. 317-18D

10 Claims

A grounding system for high voltage DC transmission lines which provides protection for and detection of changes in the


normal operating mode of the high voltage system. The transmission system has a single connection to the earth, at a first point, all other points remote from the first being insulated from their local earth points. Common ground points are provided for all the equipment of the transmission system in

**CONTROL CIRCUITRY TO PREVENT USE OF A SECONDARY CIRCUIT WITHOUT STATIC ELECTRICITY GROUNDS**

John Joyce, 179 Thacher St., Milton, Mass.
Filed Apr. 8, 1969, Ser. No. 814,344
Int. Cl. H02h 1/02

U.S. Cl. 317-18

7 Claims



Control circuits are disclosed to prevent the use of a secondary circuit, each control circuit including first and second grids with the control circuit including a relay in control of the secondary circuit and having a grounded connection with the second grid and parallel leads each including a resistor and having a grounded connection with both grids, the resistors being operative to prevent the closing of the secondary circuit unless all the grounds of the parallel leads are effective.

3,581,154

SURGE-DEFLECTING CABLE TERMINATOR

J. Hebden Willox, 917 Newcastle Ave., Westchester, Ill.

Filed Nov. 18, 1968, Ser. No. 877,716


Int. Cl. H02h 9/06

U.S. Cl. 317-61.5

20 Claims

A weathertight surge-responsive electrical cable terminator, adapted for use in connecting an underground insulated cable to an exposed overhead conductor, includes a housing of insulating material in which the cable end is hermetically sealed alongside a member of magnetic material. Lightning surges transmitted by the exposed overhead conductor to the point of connection are deflected by the electromagnetic

cooperation of the magnetic member with the surge current upon its appearance in the terminator. The terminator is ef-



fective either as a reflector to turn the surge back to the overhead conductor, or as a diverter to direct the surge to an associated lightning arrester.

3,581,155

ELECTROMAGNETIC MAKE-AND-BREAK IGNITION DEVICE FOR A POCKET LIGHTER


Richard Halm, 7061 Battmannsweller Kreis, Schorndorfer Strasse 8, Esslingen Am Neckar, Germany

Filed Mar. 18, 1969, Ser. No. 808,261

Claims priority, application Austria, Mar. 21, 1968, 2,839 Int. Cl. F23g 3/01

U.S. Cl. 317-81

7 Claims



A make-and-break magnet especially for a pocket lighter having a substantially rectangular shape and comprising a permanent magnet forming at least a part of one side of the rectangle, magnetic conductors secured to and carrying the magnet, at least a part of one of the conductors forming a core which forms the opposite side of the rectangle and carries coil windings, and an armature pivotably connected by a bearing to the end of the magnet-carrying side; the upper end of the magnet itself or of one of the magnetic conductors forming an extension of the magnet being bent obliquely upwardly in the direction toward the axis of the core, and the upper ends of the core and of the extensions forming contact surfaces which are obliquely inclined to the axis of the core and extend within a common plane, and the armature having corresponding contact surfaces which are likewise inclined to said axis and extend within a common plane. The armature is pivotably mounted in such a position that, when the magnetic circuit is closed by said armature, the two planes of the associated contact surfaces coincide with each other and these contact surfaces engage fully with each other.

3,581,156 ELECTRONIC ARRANGEMENT FOR CONTROLLING AN ELECTROMAGNETIC CLUTCH


Raymond Dolbachian, Meudon, and Claude Lefevre, Saint Maur, both of France, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Feb. 6, 1969, Ser. No. 797,115

Claims priority, application France, Feb. 16, 1968, 140113 Int. Cl. F16d 67/00; H01h 47/32

U.S. Cl. 317-123

10 Claims



An automatic clutch control system for use in a motor vehicle includes an engine speed transducer that supplies a speed voltage to a control circuit. A power circuit controlled by the control circuit supplies current to the operating coil of the automatic clutch. The control circuit produces control voltages at distinct operating threshold levels for the power circuit that correspond to four engine operating zones, i.e. engine standstill, idling, transmission gear drive, and high speed drive.

ERRATUM

For Class 317-124 see: Patent No. 3,579,703

3,581,157

ELECTRICAL RELAY CIRCUITRY


Frank B. Hall, Chicago, Ill., assignor to Pettibone Corporation

Filed Jan. 17, 1969, Ser. No. 792,102

Int. Cl. H01h 47/16

U.S. Cl. 317-136

5 Claims



Electrical relay circuitry for performing useful work by the selective closing of work circuits. In one form of circuitry, two independent relay magnets with associated contact groups are effective upon selective energization to reverse their respective contact groups, a third contact group being automatically reversed upon energization of either relay magnet. In another form, selective energization of the magnets reverses their respective contact groups, but the third contact group is not reversed unless both magnets are energized.

3,581,158

VARIABLE STACK ELECTRICAL CONDENSER


Jerry Shirek, P.O. Box 1861, Monterey, Calif.

Filed May 19, 1969, Ser. No. 825,584

Int. Cl. H01g 9/08, 1/02

U.S. Cl. 317-230

6 Claims



One or more toroidally shaped electrical condensers are mounted on a standard base unit provided centrally thereof with an externally threaded post that is coaxial of the condensers. A nut threaded on the post holds the condensers on the post and against the base. Metal cases for the condensers form their ground connections and all the cases ground to a peripheral metal band on the base. Contact strips are secured longitudinally of the post and are electrically connected to the base terminals. Each condenser has a spring tab forming its other connection that contacts one of the strips.

3,581,159

SOLID ELECTROLYTE CAPACITOR HAVING IMPROVED COUNTERELECTRODE SYSTEM


John Piper, Greenville, S.C., and Carl F. Leitten, Jr., Indianapolis, Ind., assignors to Union Carbide Corporation, New York, N.Y.

Filed Nov. 12, 1969, Ser. No. 875,790

Int. Cl. H01g 9/05

U.S. Cl. 317-230

24 Claims



A solid electrolytic capacitor and method for the production thereof comprising a body of an anodizable metal, an oxide layer produced by anodization of the body as a dielectric, a solid semiconductive electrolyte layer over the oxide, and an electrically conductive counterelectrode system consisting of a layer of carbon particles on the solid electrolyte, a thin-walled copper lamellar coating over the carbon layer, and an electrical connection to the copper lamellar coating.

3,581,160

SEMICONDUCTOR RECTIFIER ASSEMBLY HAVING HIGH EXPLOSION RATING


Dante E. Piccone, and Daniel B. Rosser, both of Philadelphia, Pa., assignors to General Electric Company

Filed Dec. 23, 1968, Ser. No. 786,251

Int. Cl. H01l 1/08, 1/14

U.S. Cl. 317-234R

10 Claims



The main electrodes of a sealed semiconductor device are clamped between opposing metal members of a pressure assembly, and gaps between opposite ends of the insulating sidewall of the device and the respectively adjacent metal members are closed by resilient O-rings disposed in compression in the gaps and respectively circumscribed by rigid retaining rings.

3,581,161

MOLYBDENUM-GOLD-MOLYBDENUM INTERCONNECTION SYSTEM FOR INTEGRATED CIRCUITS


James A. Cunningham, and Robert S. Clark, both of Dallas, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Continuation of application Ser. No. 606,064, Dec. 30, 1966, now abandoned. This application Jan. 2, 1969, Ser. No. 791,862

Int. Cl. H01l 5/02

U.S. Cl. 317-234R

17 Claims



There is disclosed a multilevel contact and interconnection system for integrated circuits comprising at least three levels. Ohmically connecting to the semiconductor through an opening in its insulating layer is a first layer of molybdenum. The second layer is of gold and the third of molybdenum. This system is virtually alloyless since the molybdenum does not alloy with the semiconductor material or the gold.

3,581,162

OPTICAL SEMICONDUCTOR DEVICE

William Richard Wheatley, Somerville, N.J., assignor to RCA Corporation

Filed July 1, 1969, Ser. No. 838,198


Int. Cl. H01l 1/12, 9/06

U.S. Cl. 317-234

8 Claims

An optical semiconductor device comprises a metal supporting member having a mounting stem, a flat head on one end of the stem and a hub on the head. The hub has an end surface and a peripheral surface. A plurality of electroluminescent semiconductor diodes are mounted in spaced relation on the peripheral surface of the hub so that the supporting member is one terminal of each of the diodes. A terminal


wire extends through and is insulatingly supported on the head of the supporting member. The terminal wire is electrically connected to each of the diodes so as to be the other terminal of the diodes. The diodes are all positioned so that they are adapted to emit light in the same direction away



from the head of the supporting member. An additional electroluminescent semiconductor diode may be mounted on the end surface of the hub and electrically connected to the supporting member and the terminal wire. The additional diode is also adapted to emit light in the same direction as the other diodes.

3,581,163 HIGH-CURRENT SEMICONDUCTOR RECTIFIER ASSEMBLIES

Lars O. Eriksson, West Chester, Pa., assignor to General Electric Company
Filed Apr. 9, 1968, Ser. No. 719,966
Int. Cl. H01L 1/02, 1/14
U.S. Cl. 317-234R 8 Claims



The thermal cycling capability of a high-current semiconductor device is significantly increased by disposed a tungsten strain buffer in compression between a terminal of the device housing and an external pressure applying thrust member.

3,581,164 JUNCTION CAPACITANCE COMPONENT, ESPECIALLY FOR A MONOLITHIC MICROCIRCUIT

Hans Pfander, Freiburg; Harald Schilling, Gundelfingen, and Gerhard Schwabe, Freiburg, all of, Germany, assignors to International Telephone and Telegraph Corporation, Nutley, N.J.

Filed June 18, 1969, Ser. No. 834,428
Claims priority, application Germany, June 26, 1968,
P 17 64 556.6


Int. Cl. H01L 5/00, 7/02

U.S. Cl. 317-234

5 Claims

This is a junction capacitance component which can be simultaneously formed with other planar transistors on a monolithic integrated circuit. The capacitance component achieves an improved specific capacity for the same voltage breakdown by forming an intermediate region between a

wafer and an epitaxial layer, said layer containing a highly doped emitter region base and collector regions, and a highly



doped region which extends from said emitter, through said base and collector to, and within the marginal area of, said intermediate region.

3,581,165 VOLTAGE DISTRIBUTION SYSTEM FOR INTEGRATED CIRCUITS UTILIZING LOW RESISTIVITY SEMICONDUCTIVE PATHS FOR THE TRANSMISSION OF VOLTAGES


Walter C. Seelbach, Scottsdale, Ariz., and Kyriakos E. Lampathakis, Lake Park, Fla., assignors to Motorola, Inc., Franklin Park, Ill.

Continuation-in-part of application Ser. No. 610,915, Jan. 23, 1967, now abandoned. This application Oct. 30, 1967, Ser. No. 683,078

Int. Cl. H01L 19/00

U.S. Cl. 317-235

7 Claims



A voltage distribution system formed in a monolithic integrated circuit structure and a process for making same. Adjacent P-type and N-type conductivity semiconductor layers form respective portions of separate conductive paths for distributing electrical potentials to semiconductor devices or other components within the same integrated structure. P-type and N-type channels are formed within various portions of the semiconductor layers to complete the conductive paths, and reverse biased junctions electrically isolate the conductive paths and prevent electrical interference between same.

3,581,166 GOLD-ALUMINUM LEADOUT STRUCTURE OF A SEMICONDUCTOR DEVICE

Takayuki Suzuoka, Kodaira-shi, Japan, assignor to Hitachi, Ltd., Tokyo, Japan


Filed Jan. 22, 1969, Ser. No. 792,992

Claims priority, application Japan, Jan. 29, 1968, 43/5484

Int. Cl. H01L 5/02

U.S. Cl. 317-235

5 Claims



A semiconductor device, wherein a metal plate having first and second metal layers is fitted on one principal surface of an insulating substrate on which a plurality of leadout leads extend; a semiconductor substrate with a plurality of integrated circuit elements being fitted to said first metal layer; said second metal layer and the first lead being connected by a first connecting wire; and the electrodes of said circuit elements being connected to the remaining leads by the second connecting wires.

3,581,167 REINFORCED CERAMIC CAPACITOR AND METHOD OF MAKING THE SAME


Donald J. Veater; Sumner B. Hill, and Lawrence J. Ruffner, all of State College, Pa., assignors to Erie Technological Products, Inc.

Continuation of application Ser. No. 761,436, Sept. 23, 1968, now abandoned. This application Feb. 19, 1970, Ser. No. 011,929

Int. Cl. H01G 1/13

U.S. Cl. 317-261

7 Claims



A capacitor having an extremely thin central layer (as little as 0.0002 inches) with electrodes sintered on both faces and surrounded by ceramic margins. The central layer is sandwiched between thick outer ceramic layers in face to face engagement with the electrodes and margins with the margins sintered to the outer ceramic layers to provide a unitary ceramic assembly. The outer layers have perforations providing access to the electrodes and have terminal coatings which extend into the perforations to make contact with the electrodes. Leads are soldered to and extend from the terminal coatings.

3,581,168 DYNAMIC BRAKING OF INDUCTION MOTORS


Donald Kirkby, Heckmondwike, England, assignor to BBA Group Limited, Cleckheaton, Yorkshire, England

Filed Mar. 10, 1969, Ser. No. 805,409

Claims priority, application Great Britain, Mar. 19, 1968, 13192/68

Int. Cl. H02p 3/24

U.S. Cl. 318-211



The disclosure of this specification relates to a system for braking an induction motor comprising normally nonconducting switch means operable, when conducting, to connect capacitance means to the primary winding of the motor to effect braking of the motor and means responsive to the interruption of the supply to the motor to render the normally nonconducting switch means conducting for a period of time sufficient to bring the motor to rest.

3,581,169 REVERSING CONTROL FOR AN INDUCTION MOTOR

Romeo T. Calud, Rockford, Ill.; David L. Hansbrough, South Milwaukee, Wis., and Dean R. Zaumseil, Rockford, Ill., assignors to Bucyrus-Erie Company, Milwaukee, Wis.

Filed June 2, 1969, Ser. No. 829,449

Int. Cl. H02k 17/02

U.S. Cl. 318-214

9 Claims



An induction motor with two equal stator segments, one being rotatably adjustable, has an electrical actuator mounted on it and controlled by a feedback control system to position the rotatably adjustable stator segment. A speed control potentiometer is ganged for operation with a master switch, which can energize either of two relays to connect the stator across a powerline for forward or reverse rotation. A limit switch is actuated by the rotationally adjustable stator segment to override the control by the master switch of the relays throughout a predetermined range of stator segment positions.

3,581,170 AUTOMATIC TORQUE CONTROL FOR A DUAL STATOR MOTOR

Donald E. Barber, Oak Creek, Wis., assignor to Bucyrus-Erie Company, South Milwaukee, Wis.

Filed Nov. 19, 1969, Ser. No. 878,032

Int. Cl. H02p 7/36

U.S. Cl. 318-214

5 Claims



A control system for a dual stator induction motor has a rotary actuator which rotates one stator to thereby control the torque produced by the motor. This torque is sensed by a watts transducer connected to measure the electrical power supplied to the motor and which generates a torque feedback signal that is linearly related to the electrical power being supplied. This feedback signal is summed with a manually adjustable reference signal which summed signal is amplified to produce a torque control signal that drives the rotary actuator.

tor. The reference signal is set by the operator for the desired torque and the rotary actuator continuously positions the stator in response to the resulting torque control signal to maintain a relatively constant torque as the motor speed varies.

3,581,171


DEVICE FOR CONTROL OF A RECTIFIER MOTOR
Boris Konstantinovich Baranov, Spusk Gertsena, 11, kv. 26, and Boris Alexandrovich Stromin, ulitsa Sportivnaya 25, kv. 52, both of Novocherkassk Rostovskoi Oblasti, U.S.S.R.

Filed Apr. 23, 1969, Ser. No. 818,617

Int. Cl. H02p 5/40

U.S. Cl. 318—227

4 Claims



A device for control of a rectifier motor with an implicit DC network including output transformers connected to the control electrodes of the rectifying elements in a frequency (and phase) changer, and motor-voltage and supply-voltage transformers, in which the primaries of the output transformers are connected in series with the secondaries of the supply-voltage transformer, while in series with them are connected diodes which, along with said secondaries, form rectifiers producing as many impulses as there are in the output of the rectifier section of the frequency (and phase) changer, the DC circuits of said rectifiers containing commutation switches whose rectifying-element control circuits are connected to the secondaries of the motor-voltage transformer. The device may be used in a variety of electric-drive types where speed control over a broad range is sought.

3,581,172

CONTROL SYSTEM OF ELECTRIC MOTOR
Takashi Tsuboi, and Hiroshi Narita, both of Katsuta-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Apr. 1, 1969, Ser. No. 812,168


Claims priority, application Japan, Apr. 1, 1968,

43/20981;43/25209;43/25214

Int. Cl. H02p 1/20

U.S. Cl. 318—259

13 Claims



A control system for electric motors effecting variation of the electric motor current in a step-by-step operation in successive stages, second impedance control means for controlling the variation of said current by said first means in a linear fashion by providing an impedance varying from a minimum value to a maximum value during each stage of operation and control means for effecting a transition of first

means from one stage to the next in response to detection of said motor current reaching a predetermined value and simultaneously changing the impedance of said second means to said maximum value.

3,581,173


LIGHT ACTUATED BRUSHLESS DC MOTOR
John L. Hood, and Joe H. Mc Gee, both of Charlottesville, Va., assignors to Sperry Rand Corporation

Filed June 9, 1969, Ser. No. 831,340

Int. Cl. H02k 29/00

U.S. Cl. 318—254

8 Claims



A brushless DC motor contains an odd number of stator windings. A cylindrical member is mounted integrally on the rotor and contains a narrow, axially disposed reflecting stripe on its surface corresponding to each stator winding. One of the stripes may have a high degree of light reflectivity, the other stripes may have an intermediate degree of reflectivity, the cylindrical surface between the stripes has a low degree of reflectivity. A stationary light source is arranged to reflect a narrow beam of light from the cylindrical surface onto a sensor. Each burst of light reaching the sensor when a stripe traverses the light beam produces an electrical pulse output from the sensor which switches a sequence steering circuit into a new stable state. The steering circuit has a different stable state for each stator winding and is connected to energize a different individual stator winding for each state. Successive pulses from the sensor switch the steering circuit so as to energize individual stator windings in a cyclical sequence. A burst of light from the high reflectivity stripe further actuates a high level trigger circuit that synchronizes the steering circuit during each revolution of the rotor.

3,581,174


AUTOMATIC REVERSING CIRCUIT FOR A WINDOW REGULATOR MOTOR CONTROL SYSTEM
Dale F. Hammer, Bellbrook, Ohio, assignor to General Motors Corporation, Detroit, Mich.

Filed Dec. 15, 1969, Ser. No. 870,628

Int. Cl. H02p 1/22

U.S. Cl. 318—266

2 Claims



A window regulator motor control system for a drive motor operative to open and close a window includes an automatic reversing circuit incorporating an overload current relay and a reversing relay which function to reverse the motor in response to an overload current condition. The reversing relay is energized through a controlled rectifier gated conductive by a triggering circuit including a re-

sistance-capacitance time delay network connected to the overload current relay. When the window is driven against an obstruction, the time delay network provides a momentary delay before the controlled rectifier is gated conductive and the motor is reversed.

3,581,175

SPEED CONTROL CIRCUIT WITH TWO VOLTAGE SOURCES TO ENABLE PRECISE SPEED CONTROL OVER A LARGE SPEED RANGE

Manfred Merz, Doernigheim am Main, Germany, assignor to Honeywell G.m.b.H., Frankfurt am Main, Germany

Filed Dec. 4, 1969, Ser. No. 882,199


Claims priority, application Germany, Dec. 7, 1968,

P 18 13 384.1

Int. Cl. H02p 5/00

U.S. Cl. 318—305

3 Claims



There is disclosed a control system for controlling the speed of the direct current electric motor over a wide range of speeds, for example, a speed range ratio of 1600:1. The speed of the motor is directly controlled by controlling the firing angle of a thyristor bridge network. In order to accomplish a high order accuracy over the very wide range, a voltage of a first magnitude is applied to the thyristor bridge network over a first portion of a range and a voltage of a second magnitude is applied to the thyristor bridge for a second portion of the range.

3,581,176


SYSTEM FOR DRIVING ELECTRIC MOTORS
Geoffrey James Bigg, Cholsey, and Alistair Michael Heaslett, Reading, both of, England, assignors to Ampex Corporation, Redwood City, Calif.

Filed Aug. 19, 1968, Ser. No. 753,418

Int. Cl. H02p 5/16

U.S. Cl. 318—327

2 Claims



Closed loop servosystem in which an electric motor is driven by or in accordance with signals representing the difference between the actual speed of the motor and a desired nominal speed only if the actual speed is below the nominal speed. The system comprises means for providing trigger signals of a frequency in accord with motor speed, a bistable circuit which when in one state provides an output signal to drive the motor, means responsive to the trigger signals to

put the bistable circuit in said one state after a predetermined time has elapsed from receipt of a trigger signal and to switch the bistable circuit to its other state on receipt of each trigger signal.

3,581,177


MOTOR SPEED CONTROL DEVICE
Louis A. Hausknecht, 4504 State Road, Cleveland, Ohio

Filed Oct. 21, 1968, Ser. No. 769,177

Int. Cl. H02p 7/06

U.S. Cl. 318—330

16 Claims



A system for controlling the speed of a direct current motor. The system employs a pair of breaker points for opening and closing the circuit containing the motor. By varying the frequency of contact between the breaker points and the period of time the points are in contact, different pulsations of current are transmitted to the motor to regulate its speed.

3,581,178


WINDSHIELD WIPER CONTROL DEVICE
Robert W. Kearns, 20524 Rutherford, Detroit, Mich.

Filed Apr. 10, 1969, Ser. No. 815,060

Int. Cl. B60s 1/08

U.S. Cl. 318—443

10 Claims



An electric control device controlling a wiper motor to operate windshield wiper blades intermittently with a dwell period between successive wiping cycles. The wiper motor current is carried by relay contacts and a solid state timing circuit controls the energization of the relay coil.

3,581,179

MULTIPHASE MOTOR CONTROL SYSTEM WITH OVERCURRENT AND UNDERCURRENT PROTECTION
Johnny W. Jones, Tulsa, Okla., assignor to Borg-Warner Corporation, Chicago, Ill.

Filed Sept. 11, 1969, Ser. No. 857,078


Int. Cl. H02p 3/00

U.S. Cl. 318—452

5 Claims

A multiphase motor control system includes an indicator and detector assembly having a meter relay for each phase circuit. Each meter relay has a pair of light-activated silicon

controlled rectifiers (LASCR's) which are normally conductive when illuminated from a pair of lamps indicating the phase current is below a high level setting, and above a low level setting. If any phase current exceeds the high level setting, the meter movement displaces a shutter which blocks the light from the high-current lamp, deenergizing the LASCR and deenergizing a first control relay, which is coupled to all the high-current circuits, to shut down the system.



Correspondingly, decrease of any phase current below the preset low level causes a reduction of illumination on the low level SCR, and drops out a second control relay, also coupled to the other low-current circuits. The control circuit includes the first and second control relays and associated components for regulating, consonant with suitable time delay, energization and deenergization of the motor. A single power supply energizes the meter relays and the control relays in the control circuit.

3,581,180

HIGH SPEED ABSOLUTE POSITION CONTROLS
Alexander Russell; ; and Alastair Gordon Millar, both of National Engineering Lab., East Kilbride, Glasgow, Scotland

Filed Feb. 28, 1969, Ser. No. 803,294

Claims priority, application Great Britain, Feb. 29, 1968, 9955/68

Int. Cl. G05b 1/06

U.S. Cl. 318-608

14 Claims



An arrangement for controlling the positioning of a movable object by power drive means along a defined movement path in accordance with an applied digital position command which comprises power drive means operative to cause movement of said object in either direction along said path, electric waveform generating means for generating at least

two families of electric waveforms related to the absolute position of said object, each of said families comprising a group of different waveforms which each pass through a chosen datum level of amplitude at different positions of said object along its movement path, the unit distance displacement between adjacent waveforms of one group being an integral multiple of the unit distance displacement of the other family or families, position selection means for selecting under said applied digital position command particular position defining waveforms derived one from each of said families of waveforms, datum level detection means operative to provide a control signal in response to passage of an applied waveform signal through said datum level, servo control means for causing operation of said power drive means in one or other direction in response to an applied error signal and cyclically operable step-by-step switch means for successively applying said selected position defining waveforms in turn and in progressively decreasing order of unit displacement distance to said datum level detection means and said servo control means, the control signals from said datum level detection means being operative to control the step-by-step operation of said cyclically operable switch means.

3,581,181


SERVOMOTOR DRIVING AND BRAKING CIRCUIT
Robert H. Wallace, Littleton, Colo., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Sept. 13, 1968, Ser. No. 759,546

Int. Cl. G05f 1/00

U.S. Cl. 318-640

6 Claims



Two AC energized back-to-back silicon-controlled rectifiers power a motor which positions both the projection lens of a projector and a beam of light reflected from a slide in the projector. This beam falls on a pair of photosensitive resistors in an AC bridge circuit which is balanced when the beam is centered on the resistors, and which produces an output voltage for controlling the rectifiers through a transistor when the beam is displaced from center by the shifting of the slide from a focused position. The rectifiers then drive the motor to return the beam to the balance position and deenergize the motor. The concurrent movement of the projection lens refocuses the slide. The contacts of a reed switch, having its coil connected in series with the motor, short circuit the latter to brake its motion whenever the motor is not energized.

3,581,182

DIGITAL INDICATOR STEP MOTOR SYSTEM
David W. Comstock, Milford, and Edwin R. Campbell, Monroe, both of Conn., assignors to United Aircraft Corporation, East Hartford, Conn.

Filed Feb. 8, 1967, Ser. No. 614,679


Int. Cl. G05b 19/40

U.S. Cl. 318-685

7 Claims

A digital indicator system in which a command signal activates a switching network selectively to couple digitally generated, bipolar, phase-displaced signals to the two-phase

internal stator windings of a stepper motor having an outer permanent magnet rotor to cause the rotor always to step in the same direction no matter at what time the switching network is activated by the command signal. The rotor locks magnetically onto the stator poles of one phase when the



input to the motor disappears. Miniature code drums driven by the stepper motor rotors provide feedback signals which are compared with the command signal to deactivate the switching network when the rotors reach the commanded positions.

3,581,183


CHARACTER INDICATOR WITH MEANS FOR MONITORING THE CORRECT POSITIONING
Gian-Franco Piazza; Rudolf Streit, both of Solothurn, Switzerland; Martin Ulrich, Frankfurt am Main; Werner Laber, Mainflingen; Adolf Burkert; Manfred Tron, Wall-dorf, and Wolfgang Waluga, Frankfurt am Main all of, Germany, assignors to Autophon Aktiengesellschaft, Solothurn, Switzerland

Filed Feb. 2, 1970, Ser. No. 7,686

Int. Cl. H02k 37/00


U.S. Cl. 318-696

27 Claims



A character indicator system for sequentially displaying data and having means to monitor the characters indicated to thereby determine the correctness of the display. The character carriers are advanced by a step-by-step motor which advances one step for each alternation of the input energy. The monitor means, as a function of the position of the character carrier or the motor armature, affects at least one alternating current signal whose frequency lies within the order of magnitude of several times the frequency of the energy used for driving the motor. Switch means feed the alternating current signal to the motor input where it can be picked up at the other end of the input and used for monitoring purposes.

ISOLATOR FOR DC SIGNAL TRANSMITTER
Edward T. E. Hurd, III, Burlington County, N.J., assignor to Honeywell Inc., Minneapolis, Minn.
Filed May 19, 1969, Ser. No. 825,873
Int. Cl. H02m 3/32; H03f 3/38; G01r 19/18
U.S. Cl. 321-2 8 Claims



There is disclosed a signal isolator for DC signals which includes a closed-loop, magnetic induction null-balanced output circuit. The DC input signals are chopped and applied as input signals to a first or input winding on a transformer. A sensing winding of the transformer detects the net flux in the transformer core. The signal thereby produced is amplified and converted to a DC output signal. A portion of the output signal is chopped and applied as feedback signal to a third or feedback winding on the transformer. The feedback signal is synchronous with the signal applied to the input winding and is applied to the feedback winding in such a way that the flux produced thereby opposes the flux produced by the signal in the input winding. The sensing winding detects any net flux resultant from the opposed input and feedback signals.

3,581,185

ELECTRIC CIRCUIT FOR GENERATING A PROGRAMMABLE MULTIPHASE ALTERNATING CURRENT

Heinz Hermes; Klaus-Dietrich Thieme, Wedel, Holstein; Willi Gatermann, Hamburg; Peter Koerv, Anzing, and Walter Mehnert, Munich, all of, Germany, assignors to LICENTIA Patent-Verwaltungs-G.m.b.H., Frankfurt am Main, Germany


Filed Dec. 16, 1968, Ser. No. 784,020

Claims priority, application Germany, Dec. 15, 1967, 1,588,510

Int. Cl. H02m 5/14

U.S. Cl. 321-7

9 Claims



A circuit for producing a multiphase alternating current which may be programmed in wave shape, includes a separate oscillator producing an alternating signal for each phase, a ring counter receiving the output of the oscillator whose stages deliver successive outputs which subdivide a given period, an interrogating switching circuit connected to each output of the ring counter and to a separate bar of a

crossbar distribution panel for receiving a characteristic voltage from that bar and switching it to the input of an amplifier upon receiving a pulse from the associated output of the ring counter. Circuit elements for shifting the phase relationship include a bistable circuit means having a first input connected with one stage of one ring counter and a second input connected to a stage of another ring counter, an averaging circuit for averaging the output signals of the bistable circuit means, and means utilizing the said averaged signals for supplying an input signal to one of the oscillators. The frequency of the oscillator signals may be directly varied by the input signal to vary the frequency and, consequently, the phase relationship of the multiphase signal.

3,581,186

REDUCED FORWARD VOLTAGE DROP RECTIFYING CIRCUIT


Aaron David Weinberger, Chicago, Ill., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Mar. 19, 1969, Ser. No. 808,622

Int. Cl. H02m 7/12

U.S. Cl. 321-43

5 Claims



A dynamic rectifying device uses a transistor biased to saturation as the rectifying element. The lower voltage drop between collector and emitter of a saturated transistor (as compared with the diode voltage drop) provides increased rectifying efficiency and better clamping action. The circuit includes a bias network using the input alternating current signal to develop the proper bias voltage for the circuit.

3,581,187

REGULATED DC POWER SUPPLY


Charles B. Grady, Jr., West Orange, N.J., assignor to The Metrodynamics Corporation, Carlstadt, N.J.

Filed June 23, 1969, Ser. No. 835,717

Int. Cl. G05f 1/58, 1/64

U.S. Cl. 323-17

8 Claims



A regulated DC power supply wherein the main pass transistor is connected to an operational amplifier having a positive feedback which rapidly switches the main pass transistor on and off, rather than maintaining transistor continuously on, so as to intermittently supply DC power from a rectified source to the output of the supply while maintaining the voltage of the output within predetermined limits of voltage regulation for various loads and line current fluctuations.

By rapidly switching the main pass transistor, it is possible to significantly reduce its heat dissipation and therefore reduce the size and cost of the power supply.

3,581,188

SWITCHING DEVICE FOR ON-LOAD TAP CHANGERS OF REGULATING TRANSFORMERS

Ryozi Watanabe, and Yutaka Kobayashi, both of Hitachi-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Mar. 10, 1969, Ser. No. 805,487

Claims priority, application Japan, Mar. 13, 1968, 43/15853

Int. Cl. H01f 29/04; H02p 13/06

U.S. Cl. 323-43.5

22 Claims



A switching device for an on-load tap changer of a regulating transformer, in which use is made, instead of contacts, of vacuum switches operable without generating an arc externally, the said vacuum switches being arranged along the sides of a polygonal shape in such a manner that those vacuum switches which are operated in the same switching sequence are located in a group on one and the same side of the said polygonal shape, and operated for opening and closing actions in accordance with the switching sequence from a drive shaft through a link mechanism provided for each group, whereby maintenance of the switching device is facilitated and the operation of the vacuum switches can be controlled easily.

3,581,189

ON-LOAD VOLTAGE REGULATORS

Maurice Sinet, 45 Blvd. Stalingrad 92, Antony, France


Filed July 2, 1969, Ser. No. 838,615

Claims priority, application France, July 3, 1968, 157,661

Int. Cl. H01f 29/04; H02p 13/06

U.S. Cl. 323-43.5R

6 Claims



An on-load voltage regulator comprises a transformer having a magnetic core, a primary winding on the core, and a rotatable secondary winding in the form of a bare wire conductor coiled helically around the core. A brush cooperates with the second winding and is movable axially but not angularly relative to the secondary winding. A slip ring connector at one end of the secondary winding has fixed elements and an element which bridges the fixed elements and which is connected to the end of the secondary winding and is rotatable therewith. An inverse potential is applied between the fixed elements for the purpose of maintaining the potential between the fixed elements at a zero value in use when they are bridged by the rotatable element of the slip ring connector.

3,581,190

MICROWAVE RESONANCE SYSTEMS EMPLOYING A BIMODAL CAVITY


Ian McLaren Brown, St. Louis, Mo., assignor to McDonnell Douglas Corporation, St. Louis, Mo.

Filed Sept. 17, 1968, Ser. No. 760,234

Int. Cl. G01n 27/78

U.S. Cl. 324-0.5

20 Claims



A bimodal microwave cavity structure having separate communicating cavity portions, one of which includes means for positioning a sample or specimen, said cavity structure being able to be resonant in more than one mode such that the sample or specimen when positioned at a suitable location in one of the structure cavities can interact with the fields associated with all modes that are present. The present structure is a relatively simple inexpensive device which can be used to gather information and particularly information from which relatively complex characteristics of specimen substances can be determined. The present structure can also be used in the construction of two level maser devices as well as in other devices.

3,581,191

PHASE CORRELATION FOR AN RF SPECTROMETER EMPLOYING AN RF CARRIER MODULATED BY A PSEUDORANDOM SEQUENCE


Weston A. Anderson, Palo Alto, Calif., assignor to Varian Associates, Palo Alto, Calif.

Filed Aug. 6, 1969, Ser. No. 847,859

Int. Cl. G01n 27/78

U.S. Cl. 324-0.5


11 Claims



pulses commence only at specific, i.e. statistically nonfluctuating, phase values of the HF carrier frequency.

3,581,194
TEMPERATURE RESPONSIVE MEANS FOR
AUTOMATICALLY CORRECTING VARIATIONS IN THE
COMPENSATION OF AN ELECTROMAGNETIC
PROSPECTING DEVICE


Ruben Tegholm, Johanneshov, Sweden, assignor to Atlas Copco Aktiebolag, Nacka, Sweden
Filed Feb. 4, 1969, Ser. No. 796,399
Claims priority, application Sweden, Feb. 6, 1968, 1568/68
Int. Cl. G01v 3/12, 3/16
U.S. Cl. 324—6 6 Claims



In an electromagnetic prospecting device having both a transmitter coil and a receiver coil mounted on the same frame, an auxiliary transmitter coil is provided on the frame intermediate the transmitter and receiver coils for compensation of the influence of the primary field, generated by the transmitter, on the receiver, there also being means for automatically correcting variations in the compensation due to changes in the distance between the transmitter and receiver coils caused by fluctuations in temperature and forces to which the device is exposed.

3,581,195
DETECTION OF VACUUM LEAKS BY GAS IONIZATION
METHOD AND APPARATUS PROVIDING DECREASED
VACUUM RECOVERY TIME

Robert L. Jepsen, Los Altos, Calif., assignor to Varian Associates, Palo Alto, Calif.
Filed June 10, 1968, Ser. No. 735,695
Int. Cl. G01n 27/62
U.S. Cl. 324—33 6 Claims




A vacuum leak detecting method and apparatus is disclosed. An evacuated vacuum envelope structure to be tested for leaks is probed exteriorly with a jet of probe gas, such as helium. A certain fractional proportion of probe gas constituent which leaks through the probed vacuum envelope structure is ionized by a leak detector apparatus connected in gas communication with the structure being tested. The ionized probe gas constituent is collected to produce an ion current signal. The ion current signal is monitored to obtain a measure of the partial pressure of the probe gas constituent for detecting leaks. The fractional proportion of the probe gas which is ionized is varied inversely with the partial pressure of the probe gas constituent, whereby reemission of ionically pumped gas within the pressure measuring system is

minimized, in use, to decrease the recovery time of the leak detector in its high sensitivity range. In one embodiment of the present invention, a comparator circuit is provided for comparing the amplitude of the ion current signal with a reference signal to derive a control signal for controlling the intensity of a ionizing beam of electrons utilized to ionize the probe gas constituent.

3,581,196
DIGITAL CAPACITANCE METER BY MEASURING
CAPACITOR DISCHARGE TIME

William L. Spaid, R.R. #1, South River Road, Cedarville, Ohio
Filed Oct. 28, 1968, Ser. No. 771,026
Int. Cl. G01n 11/52
U.S. Cl. 324—60R 6 Claims



A fully automatic capacitance meter with decimal readout. The meter operates cyclically at a relatively high frequency, acting in an initial small fraction of each cycle to charge the unknown capacitor to a predetermined voltage, discharge the capacitor at a constant rate to zero voltage, measure the time interval required for discharge to produce a time analog of the capacitance, and convert the time analog to a decimal number. The remaining large fraction of each cycle is used to display the decimal number. Automatic range switching is accomplished by changing the discharge rate.

3,581,197
CAPACITANCE MOISTURE METER AND WINGLIKE
PROBE

Dennison H. Morey, Jr., 55 Irwin Lane, Santa Rosa, Calif.; Melvin Silva, P.O. Box 3276, Hayward, Calif., and Gordon D. Browning, 19056 Stanton Ave., Castro Valley, Calif.
Continuation-in-part of application Ser. No. 664,112, Aug. 29, 1967, now abandoned. This application Oct. 3, 1969, Ser. No. 863,665
Int. Cl. G01r 27/26
U.S. Cl. 324—61 5 Claims




Free moisture in yieldable matter (defined to include water, alcohols, and other liquids of relatively high dielectric

constants occurring on the surface of solids or as drops in another liquid) is measured by an instrument which includes a radio frequency oscillator (e.g., 2 MegHz.), preferably voltage-stabilized, connected to an LC circuit that can be made substantially resonant, one of the elements being a capacitance probe, and the potential over one of these elements is measured to indicate the moisture content. The probe preferably includes an outer sheath of metal which partly covers a body of moisture-impermeable dielectric material and leaves a part of the surface of the material exposed, and an inner conductor embedded in the material and thereby completely insulated from the outside of the probe; the capacity between the sheath and conductor varies with the amount of moisture which contacts the exposed surface of the body. When testing material of variable density, such as soil, the probe is placed within the material and the latter is compacted to a predetermined degree if required.

3,581,198
TESTING APPARATUS FOR ELECTRICAL DEVICE
WHERE A STIMULUS IS VARIED BETWEEN TWO
STATES

William E. Shoemaker, Los Altos, and David W. Wilson, Sunnyvale, both of, Calif., assignors to Signetics Corporation, Sunnyvale, Calif.
Filed Jan. 8, 1969, Ser. No. 789,721
Int. Cl. G01r 15/12
U.S. Cl. 324—73 13 Claims




Testing apparatus for testing electrical devices such as operational amplifiers which sequences through a series of tests each test having first and second test halves during which a parameter of the device is varied between two states. The apparatus can be used for pass-fail testing of electrical devices or alternatively for sorting by selective display of the quantitative test information for any desired parameter. This is accomplished by providing a pushbutton for each test; by depressing the pushbutton associated with the test the quantitative information is displayed.

3,581,199
SPECTRUM ANALYZER INCLUDING SAMPLING AND
SCALING MEANS

David A. Spitz, Columbus, Ohio, assignor to Industrial Nucleonics Corporation
Filed Sept. 1, 1967, Ser. No. 665,135
Int. Cl. G01n 23/16
U.S. Cl. 324—77 35 Claims

Disclosed is a digital spectrum analyzer wherein the spectral content at a plurality of frequencies w_m is computed in response to Fourier transforms at each frequency of an analyzed signal at a plurality of discrete time intervals. The Fourier transforms over each interval are combined to indicate the Fourier transform over the entire interval being considered. A further disclosed feature relates to determining with a specific degree of certainty whether a frequency com-


ponent is periodic. The determination is made by multiplying average power spectrum density over all the frequencies by a predetermined factor, dependent upon the degree of certainty desired. If the spectral density at a particular frequency is greater than the product, it can be assumed, with the



predetermined degree of certainty, that the frequency is periodic. Another disclosed feature concerns automatically scaling the amplitudes of the spectral responses at a plurality of predetermined frequencies, whereby no off-scale readings are obtained.

3,581,200
APPARATUS FOR DERIVING THE PROBABILITY
DENSITY FUNCTION OF A SIGNAL WITH RESPECT TO
AMPLITUDE

Ralph W. Mifflin, R. D. 4, Rome, N.Y.
Continuation-in-part of application Ser. No. 531,649, Feb. 25, 1966. This application Feb. 18, 1969, Ser. No. 800,239
Int. Cl. G01r 23/16
U.S. Cl. 324—77R 2 Claims




The probability density function of a signal the amplitude of which is the variate is derived by first producing a constant amplitude FM wave the instantaneous frequency of which is linearly related to the instantaneous amplitude of the signal. A spectrum analyzer and integrator are then used to derive the energy-frequency distribution of the FM wave. This distribution is the probability density function of the signal and is displayed on a suitable X-Y display device synchronized with the spectrum analyzer sweep.

3,581,201
PHASE-SETTING DEVICE

Svyatoslav Anatolevich Kravchenko, Kirovsky Prospekt, 65, kv. 29, and Alexei Alexeevich Kulemin, Kubinskaya ul., 28, kv. 33, both of Leningrad, U.S.S.R.
Filed May 7, 1969, Ser. No. 822,407
Int. Cl. G01r 25/00
U.S. Cl. 324—83 4 Claims

A phase-setting device for very low, low and high frequen-

cies, comprising phase-shifters, scaling circuits, very low frequency and low frequency mixers, and a variable-frequency



cy oscillator, securing high accuracy of phase-shift setting over a broad range of frequencies from very low to high.

3,581,202


DEVICES FOR THE ELECTRO-OPTICAL MEASUREMENT OF AN ELECTRICAL QUANTITY
Yves J. Pelenc, La Tronche, and Georges M. Bernard, Saint Egreve, both of, France, assignors to Merlin Gerin, Societe Anonyme, Grenoble, France

Filed Aug. 15, 1968, Ser. No. 752,927
Claims priority, application France, Sept. 1, 1967, 119,802

Int. Cl. G01r 19/08

U.S. Cl. 324-96

3 Claims



Electro-optical measuring device for high-voltage overhead lines wherein a light beam is directed to the line and reflected to the earth surface and whereby both the upwardly directed light beam and the reflected light beam follow the same path and traverse the same measuring devices.

3,581,203

ANALOG METER HAVING MEANS TO PROVIDE A DIGITAL READING OF THE POINTER POSITION
William Flower, 5127 Estes Ave., Skokie, Ill.


Filed Jan. 2, 1969, Ser. No. 789,099

Int. Cl. G01r 31/00, 19/26

U.S. Cl. 324-96

8 Claims

The invention disclosed within this specification pertains



analogue device by following a meter movement and counting the meter indications from a given point down to zero.

3,581,204

ELECTROMECHANICAL RECORDER AUTOMATIC ZERO APPARATUS


Fred D. Martin, Angleton, Tex., assignor to The Dow Chemical Company, Midland, Mich.

Filed Apr. 14, 1969, Ser. No. 815,865

Int. Cl. G01r 1/02, 13/04

U.S. Cl. 324-130

5 Claims



This invention relates to means for providing an automatic zero to correct periodically for instrument drift to precisely the same point each time after such drift occurred. The automatic zero means of this invention senses the position of a recorder pen and corrects the incoming signal to move the pen to a definite position. Variations that may be encountered in an electronic zero or signal condition feeding the recorder are zeroed out with the signal drift in order to position the recorder pen at a specified point.

3,581,205

APPARATUS FOR TESTING SWITCHING TYPE VOLTAGE REGULATORS BY COUNTING SQUARE WAVE PULSES PRODUCED BY THE REGULATOR

Raymond Michael Christopher Wilson, Birmingham, England, assignor to Joseph Lucas (Industries) Limited, Birmingham, England

Filed Mar. 25, 1969, Ser. No. 810,110

Claims priority, application Great Britain, Jan. 15, 1969, 2396/69


Int. Cl. G01r 31/28, 15/12

U.S. Cl. 324-158

1 Claim

In the testing of a voltage regulator of the kind in which the regulator provides an output voltage of square wave form to a field winding, a signal is injected into the regulator representing the signal which the regulator will receive in use from a generator. The output from the regulator, which will

be of square waveform, is then fed to a counter, and an indication that the regulator is working satisfactorily is given



when a predetermined number of square waves have been counted.

3,581,206

ELECTRONICALLY CONTROLLED SPEEDOMETER WITH MAXIMUM SPEED INDICATOR

Siegfried Strohm, Stuttgart-Stammheim, Germany, assignor to Firma Dr.-Ing. h.c. F. Porsche RG, Stuttgart/Zuffenhausen, Germany


Filed Apr. 3, 1969, Ser. No. 813,036

Claims priority, application Germany, Apr. 6, 1968, P 17 73 152.1

Int. Cl. G01p 3/48

U.S. Cl. 324-169

5 Claims



An electronically controlled speedometer wherein the inductive impulses from the ignition coil whose frequency is proportional to the speed of the motor are shaped and integrated to form a control signal which is applied to a servoamplifier connected to a servomotor forming a servo loop, the servomotor driving the instantaneous speed indicator dial which in turn drags a maximum speed dial therewith in the direction of increasing speed indication, and a critical speed indicator responsive to a critical value of said control signal for interrupting the ignition circuit.

3,581,207

JOINT SETTING OF DEMODULATING CARRIER PHASE, SAMPLING TIME AND EQUALIZER GAIN PARAMETERS IN SYNCHRONOUS DATA TRANSMISSION SYSTEMS

Robert W. Chang, 82 Southview Terrace North, Middletown, N.J.


Filed Aug. 6, 1969, Ser. No. 847,881

Int. Cl. H04b 1/00

U.S. Cl. 325-42

10 Claims

Apparatus and method for the joint setting in synchronous digital data transmission systems of the parameters of demodulating carrier phase, sampling time and transversal equalizer tap gains based on a common mean-square error minimization criterion. Responsive to test pulses traversing a distorting transmission medium and locally generated test pulses traversing an ideal filter simultaneous correlations are made with each equalizer tap output and the error difference between actual and ideal responses to control tap gains, with the derivative of the ideal response and the received



demodulating carrier phase. Optimum control of these critical parameters is thereby guaranteed.

3,581,208

EMERGENCY WARNING AND IDENTIFICATION APPARATUS FOR TWO-WAY RADIO COMMUNICATION SYSTEM


William Buehrle, Jr., 333 Maplewood Road, Huntington Station, N.Y., and Gerald F. Woodard, 8 Lakeside Drive, Centerport, both of, N.Y.

Filed Dec. 16, 1968, Ser. No. 784,034

Int. Cl. H04b 7/00

U.S. Cl. 325-64

5 Claims



Apparatus for audio communications and other such systems are disclosed in which a plurality of portable transceivers each generate a signal having audio components and a unique combination of continuous wave frequency components, for transmission to a remote station. Manual operation of a multiposition switch in each transceiver permits indicating the existence of an emergency or nonemergency transmit condition by controlling the duration of one of the continuous wave frequency components. The transmitted signal is received at the remote station where circuitry filters and detects the unique combination of continuous wave frequency components to identify the transceiver and also determines the duration of the controllable duration component to indicate the particular transceiver's condition. Other embodiments are also covered.

3,581,209

CABLE TELEVISION PROGRAM CAPACITY ENHANCEMENT

Arie Zimmerman, 3511 W. 6th St., Los Angeles, Calif.; James A. Kuksch, 9104 Lantern Lane, and Gerald D. Smith, 6207 Breamore Rd., both of Indianapolis, Ind.

Filed Sept. 17, 1968, Ser. No. 760,158


Int. Cl. H04h 1/04; H04n 7/10

U.S. Cl. 325-308

18 Claims


The invention concerns a system wherein a distribution cable is operable to transmit TV signals to TV receivers each

having a limited number of local channels, the method of the invention enabling selective reception on said channels of cable distributed programs the number of which exceeds the number of said local channels, the method including, processing said signals to derive at least two groups of



resultant signals characterized in that the resultant signals of each group have carrier frequencies corresponding to those characteristic of said local channels, and selectively and individually connecting said resultant groups of signals with the input to a TV receiver.

3,581,210
RF T-PAD LOW IMPEDANCE COUPLING CIRCUIT ATTENUATOR WITH AGC VOLTAGE CONTROL
Warren U. Amfahr, 3100 Brookview Drive, Plano, Tex.
Filed Jan. 23, 1969, Ser. No. 793,438
Int. Cl. H04b 1/18
U.S. Cl. 325-411 9 Claims




An RF signal path variable attenuation circuit with common electrode connected diodes in the signal path and the diode interconnection connected through a transistor to ground. A voltage diode biasing circuit is also so connected in the circuit that the degree of voltage bias to conduction of the diodes is subject to variation through variable DC drain from the diode junction through the transistor along with, simultaneously, variable RF signal diversion to ground as controlled by AGC voltage variations applied at the transistor base.

3,581,211
SYSTEM FOR SIMULTANEOUS RECEPTION OF MULTIPLE SIGNALS
Peter Maitland, and Richard W. Ehrhorn, both of Electronic Communications, Inc. P.O. Box 12248, St. Petersburg, Fla.
Filed Dec. 24, 1968, Ser. No. 786,675
Int. Cl. H04b 1/26
U.S. Cl. 325-451 9 Claims


In this invention, two RF signals of different carrier frequencies and having different amplitude characteristics are received and the information content of each is used

simultaneously. For example, when the RF signals carry different audio signals, this invention allows simultaneous listen-




ing by developing output signals of substantially equal magnitude.

3,581,212
FAST RESPONSE STEPPED-WAVE SWITCHING POWER CONVERTER CIRCUIT
William McMurray, Schenectady, N.Y., assignor to General Electric Company
Filed July 31, 1969, Ser. No. 846,354
Int. Cl. H03b 7/14
U.S. Cl. 328-14 18 Claims



To obtain fast response to a cyclical AC or variable DC input reference signal by a stepped-wave power converter circuit comprising a plurality of equal or unequal inverter modules connected in series or parallel so that the module output voltages add algebraically, the composite instantaneous output stepped-wave voltage is compared with the instantaneous voltage values of the limits of a control band placed about the reference signal. One or more inverter modules are switched to produce a step change whenever the composite output voltage is outside the control band limits. An application is a fast response switching power amplifier for driving sonar transducers.


3,581,213
SYNCHRONIZED BURST GENERATOR
Elmo E. Crump, 63 Grover Lane, West Caldwell, N.J.
Filed May 9, 1968, Ser. No. 727,857
Int. Cl. H03k 19/00
U.S. Cl. 328-25 4 Claims



A burst generator including a continuous wave oscillator, means to synchronize a pulse generator to the oscillator so


that each pulse starts at a corresponding point on a cycle of the continuous wave, and a gating circuit actuated by the pulses to transmit repetitive bursts of oscillations, each starting at a corresponding point of a cycle.

3,581,214
DISCRETELY VARIABLE TIME DELAY SYSTEM HAVING SUBMULTIPLE, ADDITIVE, AND ALTERNATIVE DELAY SELECTION
Ben L. Seegmiller, 2235 E. 21st St., Salt Lake City, Utah
Filed June 19, 1969, Ser. No. 834,817
Int. Cl. H03k 5/159, 5/04
U.S. Cl. 328-55 5 Claims



A time-delay system wherein an input signal triggers the generation of an output signal or pulse that can be accurately controlled as to time delay relative to the input signal, and preferably also as to pulse width. In a preferred form of the invention, the system includes plural circuits the delayed output of a first of which triggers the second, and so forth. Selected time delays of the plural circuits are additive, when desired, and pulse width and polarity are to be predetermined in the final output stage. Switching means are provided to connect in desired fashion one or more selected circuits to the output of the system, and one-shot multivibrators and pulse shaping stages are preferably used in each circuit. Precision resistance-capacitance circuits preferably assist to provide a stepped sequence of time delays as to each respective circuit, and the sequence of respective circuits are preferably related in a submultiple, time-delay relationship.


3,581,215
VARIABLE FREQUENCY DELAY LINE DIFFERENTIATOR
Forrest C. Meyer, San Diego, Calif., assignor to Systems Peripherals Division, San Diego, Calif.
Filed May 22, 1969, Ser. No. 826,839
Int. Cl. H03k 5/159
U.S. Cl. 328-56 10 Claims



A circuit for processing a transducer readout signal is disclosed in which a frequency dependent variable length delay


line is connected across a double ended output of a signal amplifier.

3,581,216
PULSE GENERATOR AND ENCODER
Louis A. Stevenson, Jr., 4010 Overbrook, Houston, Tex.
Filed Nov. 24, 1967, Ser. No. 685,391
Int. Cl. H03m 1/26
U.S. Cl. 328-61 8 Claims



A pulse generating circuit particularly useful as an encoder for automatic electronic dialing equipment including a plurality of serially connected first monostable circuits, a plurality of serially connected second monostable circuits with gate means connected therebetween, means connecting each of said first monostable circuits to the first circuit of said second monostable circuit, means for connecting each said first monostable circuit to a control terminal of said gate means, and means connected with each of said second monostable circuits for receiving a pulse train. Each of the first monostable circuits may correspond to a digit of a plural digit number, and each of the second monostable circuits may correspond to a value of each digit.

3,581,217
FREQUENCY TO DIRECT CURRENT CONVERTER CIRCUIT
Wayne R. Isaacs, 7709 Suburbia St., Houston, Tex.
Filed Nov. 5, 1968, Ser. No. 773,433
Int. Cl. H03b 3/04
U.S. Cl. 328-140 22 Claims




A system is disclosed for converting a periodic signal into a direct current signal that is proportional to and/or a predetermined nonlinear function of the frequency of the periodic signals. The input signals are converted into pulse type signals having a constant amplitude and preset time duration. These pulse type signals are applied to an averaging circuit for providing a direct current output proportional to the frequency and/or to a saturable circuit for providing a direct current signal that is a nonlinear function of the applied frequency. A circuit is included to determine when input frequency has a period shorter than the pulse type signals.

3,581,218
SMOOTHLY ACTING SIGNAL COMPARATOR
Bill J. Ransdell, 1915 24th St., Moline, Ill.
Filed Aug. 26, 1968, Ser. No. 755,319
Int. Cl. G06g 7/14; H03b 3/02; H03k 5/20
U.S. Cl. 328-146 7 Claims


There is provided a signal monitoring circuit, for use with a signal source having a high internal impedance, for providing an output signal when a received input signal attains a predetermined value relative to a comparison signal, including means for developing the comparison signal; and, bistable circuit means having an input circuit for receiving the input signal, and an output circuit. The bistable circuit means being normally in a first condition and being actuated to a second condition when the input signal attains the predeter-

mined value relative to the comparison signal, whereupon the output circuit carries an output signal. The signal monitoring circuit includes an improvement for positively actuating the bistable circuit from the first condition to the second condition so that the output signal is characterized by substantially continuously varying from a first level to a second level,



wherein the improvement comprises circuit means coupling the output circuit to the comparison signal developing means for varying the value of the comparison signal in dependence upon the value of the output signal so as to increase the actuation time required to place the bistable means in the second condition.

3,581,219
SYSTEM FOR DYNAMICALLY ADJUSTING CLIPPING IN EDITING ELECTROCARDIOGRAM WAVES
David C. Alexander, Yorktown Heights, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Oct. 24, 1967, Ser. No. 677,685
Int. Cl. H03k 5/08
U.S. Cl. 328-168
4 Claims




The disclosure sets forth a feedback system for dynamically adjusting the clipping levels in electrocardiogram analyses. The input-analog data is used to control the sampling rate in such a manner that only enough samples, including all significant deviations, are taken to describe the wave adequately. This makes it unnecessary to take a very large number of samples on a noisy record while it avoids missing important points.

3,581,220
FREQUENCY MODULATION SIGNAL DEMODULATOR
Allan J. Bell, 18 Old Post Road, Fairport, N.Y., and Roger B. Stone, 4207 Marble Lane, Fairfax, Va.
Filed Feb. 17, 1969, Ser. No. 799,855
Int. Cl. H04l 27/14
U.S. Cl. 329-126
8 Claims


In a data communication system a demodulator for use in detecting data information carried in a frequency modulated signal. A signal which had been modulated between upper and lower limits of frequency, in addition to other frequencies within or without the said limits for supervisory functions, would be received and by means of equalizers, a limiter, zero crossing detector, Schmitt trigger, and a low pass filter, the original data can be recovered from the

received frequency modulated signal. Further, circuits are provided for providing phasing information and for detecting




the presence or absence of the received carrier frequency signal.

3,581,221
FLEXIBLE AMPLIFICATION SYSTEM
Edward J. Martin, Jr., 219 Ferguson Ave., Newport News, Va.
Filed Apr. 29, 1968, Ser. No. 724,974
Int. Cl. H03f 3/16, 3/18
U.S. Cl. 330-24
10 Claims



A flexible and expandable system comprising a number of modules from which a composite power amplifier of any given output capability can be constructed. An operational amplifier can be constructed from a driver module performing the voltage gain function and a number of booster modules connected to it furnishing the output power capability.


3,581,222
LINEAR VOLTAGE CONTROLLED ATTENUATOR
Duane E. Dunwoodie, Los Altos, Calif., assignor to Wilton Company, Palo Alto, Calif.
Filed Mar. 19, 1969, Ser. No. 808,471
Int. Cl. H03g 3/30
U.S. Cl. 330-29
8 Claims



A voltage controlled attenuator for use in an automatic gain control circuit. The attenuator includes a first transistor having a relatively high output impedance driven by an AC input signal. Its collector output is coupled to the coupled


emitter inputs of two common base connected amplifiers which are differentially driven by a control signal to split the output current of the first transistor between them. The output voltage which is attenuated in proportion to the control signal is then taken from the collector of one of the common base amplifiers.

3,581,223
FAST RESPONSE DYNAMIC GAIN CONTROL CIRCUIT
Merritt S. Armstrong, San Francisco, Calif., assignor to HC Electronics, Inc., Tiburon, Calif.
Filed Apr. 30, 1969, Ser. No. 820,542
Int. Cl. H03g 3/30
U.S. Cl. 330-29
4 Claims




A dynamic gain control circuit for audio frequencies includes an audio amplifier of the operational type having an inverse feedback network including a threshold level sensing network providing a control voltage when the amplified output signal exceeds a predetermined level. The control voltage is coupled to the input of an insulated gate field effect transistor whose impedance is varied to control the amplification of the operational amplifier.

3,581,224
BIPOLAR OPERATIONAL POWER SUPPLY
Sarkis Nercessian, Long Island City, N.Y., assignor to Forbro Design Corp., New York, N.Y.
Filed Dec. 30, 1968, Ser. No. 796,262
Int. Cl. H03f 1/34
U.S. Cl. 330-99
7 Claims




A bipolar operational power supply is constructed to provide stable operation over a wide range of gain settings including zero and with various load conditions in order to provide power output with AC or DC control or combinations of the two and in either voltage or current modes.

3,581,225
TRANSISTORIZED POWER AMPLIFIER
Horst Rothe, Geigersbergstrasse 17, 7500 Karlsruhe-Durlach, Germany
Filed Oct. 3, 1968, Ser. No. 764,755
Claims priority, application Germany, Oct. 4, 1967, P 15 37 653.1
Int. Cl. H03f 1/08
U.S. Cl. 330-28
8 Claims



A transistor power amplifier whose high frequency power conversion efficiency is improved by the application of an input alternating control voltage whose waveform is adjusted to compensate for the voltage drops due to current flow between the transistor base-emitter junction and both the base terminal and the collector terminal of the transistor so as to impart the desired waveform to the output current at the transistor collector terminal.

3,581,226
DIFFERENTIAL AMPLIFIER CIRCUIT USING FIELD EFFECT TRANSISTORS
Carroll R. Perkins, Balboa Island; Everett L. Shaffstall, Fountain Valley; James L. Gunderen, Wilmington, and Robert N. Yoder, Huntington Beach, all of, Calif., assignors to Hughes Aircraft Company, Culver City, Calif.
Filed Dec. 22, 1969, Ser. No. 886,924
Int. Cl. H03f 3/68
U.S. Cl. 330-30
4 Claims




Complementary waveform signals are amplified in respective channels of a dual channel differential amplifier, each channel including a plurality of cascaded field effect transistors. A field effect transistor biased to saturation furnishes an essentially constant current to the first transistor of each channel. A push-pull arrangement including a pair of series connected field effect transistors is provided at the output of each channel. The entire circuit may be fabricated on a single semiconductor substrate using MOS technology.

3,581,227
ADJUSTABLE, THIN MEMBRANE MIRROR FOR USE IN THE STABILIZATION OF RING LASERS
Theodore J. Podgorski, Maplewood, Minn., assignor to Honeywell Inc., Minneapolis, Minn.
Filed Apr. 18, 1968, Ser. No. 722,227
Int. Cl. H01s 3/08
U.S. Cl. 331-94.5
1 Claim

Apparatus to remotely move a mirror in a laser. The driv-

ing means operates against a thin membrane forming a por-




tion of the laser housing so that a mirror fastened to the inside of the membrane may be moved as desired.

3,581,228 SIMULTANEOUS TRANSVERSE AND LONGITUDINAL MODE LOCKING IN A LASER EMPLOYING AN ACTIVE ABSORPTION CELL

Peter W. Smith, Little Silver, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.
Filed June 18, 1968, Ser. No. 737,881
Int. Cl. H01s 3/02

U.S. Cl. 331-94.5

8 Claims




A laser that oscillates in multiple transverse and longitudinal modes is pulsed by a mutual adaptation of an absorption cell having a substantially matching absorption line and the other components of the laser to phase-lock simultaneously the transverse and longitudinal modes of the laser by saturable absorption. Simultaneous locking is accomplished provided that the laser resonator is designed such that the longitudinal mode separation frequency is an integral multiple of the transverse mode separation frequency.

3,581,229 FACE-PUMPED LASER DEVICE WITH OPTICAL PATH FOLDING

William S. Martin, Schenectady, N.Y., assignor to General Electric Company
Filed Aug. 27, 1968, Ser. No. 755,653
Int. Cl. H01s 3/00

U.S. Cl. 331-94.5

10 Claims



A face-pumped laser device employs a prism with an index of refraction at least equal to the square root of two adjacent


and optically contacted to the surface of the active laser medium. The prism provides for refraction and total internal reflection of the pumping radiation which is directed to and is substantially uniformly incident upon the surface of the active laser medium, thus increasing the pumping flux density by the square root of two over conventional techniques. A plurality of prisms positioned on the opposite side of the laser medium are utilized in conjunction with the first mentioned prism to fold the optical path in such a manner that a generated or input laser beam may be made to penetrate a different region of the laser medium on each pass.

3,581,230 PASSIVE Q-SWITCH AND MODULATOR FOR CO₂ LASERS

David C. Smith, Glastonbury, Conn., assignor to United Aircraft Corporation, East Hartford, Conn.
Filed Jan. 27, 1969, Ser. No. 793,945
Int. Cl. H01s 3/10, 3/22, 3/11

U.S. Cl. 331-94.5

5 Claims



A cell containing a gaseous bleachable dye is positioned in the optical feedback cavity of a carbon dioxide laser to Q-switch the laser. An acoustic wave generated through the gas will cause the output of the laser to be modulated at the acoustic frequency.

3,581,231 ULTRA-STABLE LASER CAVITY MIRROR SUPPORT ASSEMBLY


Robert J. Freiberg, Thousand Oaks, Calif., assignor to The United States of America as represented by the Secretary of the Air Force

Filed June 17, 1969, Ser. No. 833,907

Int. Cl. H01s 3/02; F16h 29/20

U.S. Cl. 331-94.5

2 Claims



An ultrastable laser cavity mirror support assembly, for use with laser utilizing external mirrors, which prevents laser output loss caused by mirror misalignment. The assembly includes: a beryllium open-ended tube; two circumferential supports for the tube, each located a predetermined equal distance inward from the nearest end of the tube; first and second counterweighted flat plates affixed, respectively, to each end of the tube and parallel to each other; first and second mirror tuning mechanisms, each mounted on and supported by, respectively, the first and second counterweighted flat plates; and means for rigidly securing the tube, and components mounted and affixed thereto, to a laser housing and an external abutment in the desired orientation.

3,581,232 TUNABLE SEMICONDUCTOR BULK NEGATIVE RESISTANCE MICROWAVE OSCILLATOR

Yoshimasa Murayama, and Hirokazu Kurono, both of Hachioji-shi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed June 27, 1968, Ser. No. 740,635

Claims priority, application Japan, July 14, 1967, 42/45061

Int. Cl. H03b 7/14

U.S. Cl. 331-107

8 Claims



A solid-state oscillator comprising a semiconductor element which has a bulk negative resistance and wherein injected excess carriers are present in operation, said device oscillating with a circuit frequency of a resonator as the space charge limiting current due to the injected carriers becomes unstable owing to the negative resistance.

3,581,233 SOLID-STATE OSCILLATOR ELEMENT


Akio Yamashita, Ikeda-shi, and Takehiro Tuzaki, Toyonaka-shi, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation-in-part of application Ser. No. 651,278, July 5, 1967, now abandoned. This application Aug. 5, 1969, Ser. No. 847,684

Int. Cl. H03b 7/14

U.S. Cl. 331-107

5 Claims



A solid-state oscillator element formed of a thin film of a polycrystalline semiconductor of which the minimum value of the conduction band represents a different energy level depending upon the direction in the wave vector space (usually referred to as "k-space"). Thus, the solid-state oscillator element is capable of producing a microwave oscillation.

3,581,234 BIAS AND TEMPERATURE COMPENSATING CIRCUIT FOR TUNNEL DIODE OSCILLATORS


Milton D. Bloomer, Scotia, N.Y., assignor to General Electric Company

Filed Dec. 10, 1969, Ser. No. 883,750

Int. Cl. H03b 7/08

U.S. Cl. 331-107T

9 Claims



A compensation technique for tunnel diode oscillators is disclosed wherein the peaks in the characteristic curves

(frequency vs. bias) for various operating temperatures are made to coincide in the region of the peak. The effects of bias and temperature are separately compensated and two techniques are disclosed for compensating each.

3,581,235 CRYSTAL STABILIZED HIGH FREQUENCY TRANSISTOR MULTIVIBRATOR


Paul Y. Siu, Los Angeles, Calif., assignor to Burroughs Corporation, Detroit, Mich.

Filed Feb. 19, 1969, Ser. No. 800,411

Int. Cl. H03b 5/36; H03k 3/282

U.S. Cl. 331-113

10 Claims



An astable multivibrator operating in a current mode comprising two transistors with resistive cross-coupling between each collector and the other base and capacitive cross-coupling between emitters. The natural frequency of the multivibrator is determined by the emitter resistors and the cross-coupling capacitance, which is preferably adjustable. A crystal having a parallel resonant overtone mode at the desired frequency of operation of the oscillator is connected between the bases of the transistors. The cross-coupling capacitance is adjusted so that the natural frequency of the multivibrator is slightly higher than the resonant frequency of the crystal.

3,581,236 HIGH STABILITY OSCILLATOR

Leon Berman, Asnieres, France, assignor to C.I.T. Compagnie, Industrielle Des Telecommunications, Paris, France


Filed Jan. 7, 1969, Ser. No. 789,540

Claims priority, application France, Jan. 8, 1968, 135,225

Int. Cl. H03b 5/36

U.S. Cl. 331-116

5 Claims



A high stability oscillator having an amplifying channel including a phase adjusting member and a separate reaction channel including a resonant crystal and a temperature stabilizing circuit, the phase adjusting member being effective to compensate for aging of the crystal without affecting the temperature stabilization of the oscillator.

3,581,237

OSCILLATOR FEEDBACK CIRCUIT FOR USE IN UHF TUNER

Masaharu Nakagawa, Tokyo, Japan, assignor to Alps Electric Company Limited, Tokyo, Japan


Filed Dec. 26, 1968, Ser. No. 787,112

Claims priority, application Japan, Mar. 28, 1968, 43/25002

Int. Cl. H03b 5/18

U.S. Cl. 331-117D

10 Claims



An RF oscillator circuit comprises a capacitance in a feedback circuit connected between the output and input terminals of an amplifier. That capacitance is defined by a pair of overlying conductors respectively operatively connected to the amplifier input and output terminals.

3,581,238

TRANSMISSION TRANSDUCER FOR REMOTE MEASUREMENT

Etsujiro Shimemura, Tokyo, and Masao Iwamiya, Yokohama-shi, both of Japan, assignors to Ltd. The Tsurumi-Seikiosakv-Sho Co., Yokohama-shi, Japan


Filed Sept. 30, 1968, Ser. No. 763,782

Claims priority, application Japan, Sept. 30, 1967, 42/62756

Int. Cl. H03b 5/20

U.S. Cl. 331-135

7 Claims



A transmission transducer for remote measurement is incorporated in the feedback loop of a double integrator type oscillator. The transducer is adapted to control the frequency of the oscillator corresponding to variations of gains of the transducer. The transducer gain is varied in accordance with variations of measured values which are directly sensed by the transducer.

3,581,239

FREQUENCY MODULATED CRYSTAL CONTROLLED OSCILLATOR OPERABLE AT A PLURALITY OF TEMPERATURE COMPENSATED CENTER FREQUENCIES

William J. Knutson, Chicago, Ill., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Mar. 5, 1969, Ser. No. 804,496


Int. Cl. H03c 3/32; H03c 3/20, 3/28

U.S. Cl. 332-18

6 Claims

A frequency modulated, solid state, crystal controlled oscillator, including a voltage variable capacitor, for use in

portable transmitters wherein it is desired to operate at a plurality of center frequencies that are stable with temperature change. Any one of a plurality of center frequency determining circuits, each including a crystal operating in its parallel resonant mode, can be selected to determine a desired center frequency. Each crystal is connected in parallel with a tem-



perature compensating network. The biasing point of the voltage variable capacitor, the net inductance of a circuit which applies the modulating voltage thereto are selected to cause the nonlinear characteristics of the crystal and voltage variable capacitor to counterbalance each other so that linear modulation is attained.

3,581,240

FREQUENCY MODULATED SOLID STATE CRYSTAL OSCILLATOR PROVIDING A PLURALITY OF CENTER FREQUENCIES


Ralph T. Enderby, Bellwood, Ill., assignor to Motorola, Inc., Franklin Park, Ill.

Filed Jan. 13, 1969, Ser. No. 790,726

Int. Cl. H03c 3/28

U.S. Cl. 332-26

8 Claims



Frequency modulated, solid state oscillator which oscillates at any one of a plurality of center frequencies in response to the positioning of a selector switch that connects a selected center frequency determining circuit to the oscillator. Each of the center frequency determining circuits includes a crystal operating in its series resonant mode, an inductor for tuning, and a resistor for suppressing undesirable crystal operation. Frequency modulation is accomplished by impressing a modulating voltage across a varactor included in the frequency control circuit of the oscillator to thereby

change its capacitance and consequently change the frequency of oscillation.

3,581,241

SIDE BAND GENERATOR HAVING STEP CONTROLLED MODULATION

Michel Schilliger, 31, rue des Oisieux 91, Morangis, France


Filed May 24, 1968, Ser. No. 731,868

Claims priority, application France, May 24, 1967, 107,704

Int. Cl. H03c 1/54

U.S. Cl. 332-47

9 Claims



A sideband generator, comprising a high frequency signal generator of frequency f_0 , a circuit for generating low frequency signals of frequency $F=1/T$, characterized in that it comprises a bridge with two inputs and two outputs forming the sum and/or the difference of the signals fed to the inputs, the two inputs of said bridge being connected to the source of high frequency energy by means of numerically controlled distributing and phase-shifting means.

3,581,242

VARIABLE POLARIZER FOR MICROWAVE SYSTEMS


Louis J. Lavedan, Clearwater, Fla., assignor to the United States of America as represented by the Secretary of the Air Force

Filed Oct. 20, 1969, Ser. No. 867,619

Int. Cl. H01p 5/12, 1/16; H03h 7/36

U.S. Cl. 333-1

1 Claim



A dual-channel receiver polarizer microwave system including a pair of waveguide systems each having adjustable phasers mounted in parallel and in series and connected to a source of input signals and a multimode transducer for transmitting and the transducer and a receiver for receiving.

3,581,243

DIRECTIONAL COUPLER WHEREIN DIELECTRIC MEDIA SURROUNDING MAIN LINE IS DIFFERENT FROM DIELECTRIC MEDIA SURROUNDING COUPLED LINE

Andrew Alford, 71 Bacon St., Winchester, Mass.

Filed Mar. 21, 1969, Ser. No. 809,213


Int. Cl. H01p 5/14, 3/08

U.S. Cl. 333-10

7 Claims

In a transmission line device for coupling a wave traveling in a particular direction along a main line to a coupled line,

higher directivity is obtained by utilizing dielectric media of dissimilar dielectric constants in the main line and the cou-



pled line, or by changing the relative propagation velocity along the main line with respect to the propagation velocity along the coupled line.

3,581,244

AUTOMATIC IMPEDANCE MATCHING CIRCUITS FOR VARIABLE FREQUENCY SOURCE


William Irving Smith, Palmyra, N.J., assignor to RCA Corporation

Filed Jan. 28, 1969, Ser. No. 794,665

Int. Cl. H03h 7/40

U.S. Cl. 333-17

3 Claims



An electronically controlled impedance transformer is disclosed in which a tapped inductor is used as the impedance matching coupling means between the source and the load, and in which the inductance of the inductor is changed in accordance with the change of frequency of the current supplied by the source to preserve the impedance match. The coupling means may be tuned and the tuning may be made to track with the change in frequency of the source while the impedance match is substantially preserved, for both high and low Q circuits.

3,581,245

MICROWAVE ABSORBER FOR WAVEGUIDE TERMINATION


Kunio Ohi, Fuchu-shi; Hideaki Inoue, Tokyo; Toshio Nakayama, Tachikawa-shi, and Sosuke Ishii, Kokubunji-shi, all of Japan, assignors to Hitachi Electronics Co., Ltd., Kodaira-shi, Japan

Filed Sept. 27, 1968, Ser. No. 763,255

Int. Cl. H01p 1/26

U.S. Cl. 333-22

6 Claims



A microwave terminator having a microwave absorber in the form of a plate which is fixed bodily to a shortcircuiting

plate of metal disposed at a right angle with the axis of a waveguide. The microwave absorber is made from a composition consisting of a powdery ferromagnetic material, carbon powder and a binder therefor, and is shaped to have a stepwise or continuously varied thickness distribution.

3,581,246

FILTER ARRANGEMENT


Tore Torstensson Fjallbrant, Staborg, Fjaras, Sweden, assignor to Telefonaktiebolaget L. M. Ericsson, Stockholm, Sweden

Filed Nov. 7, 1967, Ser. No. 681,223

Claims priority, application Sweden, Dec. 7, 1966, 16,806/1966

Int. Cl. H03h 13/00; H01p 5/12

U.S. Cl. 333-24.1



There is disclosed a filter comprising a power dividing circuit means including an input port adapted to receive signals, an output port adapted to transmit signals and two signal-transfer ports. Signals received by the input port are power divided and fed to the signal-transfer ports for transmission therefrom to a reactive circuit means which reflects the signals back to the signal-transfer ports. The reflected signals received by the signal-transfer ports pass through the power dividing circuit means to the output port and are geometrically added.

Various power dividing circuit means including differential transformers, magic T devices and 90° hybrid devices are disclosed. The reactive circuit means include, reciprocal and nonreciprocal phase shifters as well as waveguide elements having irises and tuning stubs.

3,581,247

DELAY LINES HAVING NONDISPERSIVE WIDTH-SHEAR MODE PROPAGATION CHARACTERISTICS AND METHOD OF MAKING SAME


John F. Belford, Westport; Donald E. Gibeau, Hazardville, and John Ciriello, Canton, all of, Conn., assignors to Andersen Laboratories, Incorporated, Bloomfield, Conn.

Continuation-in-part of application Ser. No. 736,675, June 13, 1968. This application Sept. 27, 1968, Ser. No. 763,199

Int. Cl. H03h 9/16, 9/30

U.S. Cl. 333-30

9 Claims



Thin guided waveform delay lines of this invention feature a maximum thickness in the order of two 1/2 wavelengths with

full width transducers coextensive with the delay line thickness providing nondispersive width-shear mode propagation characteristics. A low cost mass production method of making a substantially identical series of such delay lines is also disclosed including steps of forming a composite preshaped block of acoustically conductive material with signal transducers affixed thereto and then cutting the composite block with its signal transducers into a plurality of substantially identical delay line segments. Completed delay line segments each can be housed in a casing having associated electrical circuit components of each delay line segment.

3,581,248

ACOUSTIC FILTERS


Adrian J. De Vries, Elmhurst, and Thomas J. Wojcik, Mount Prospect, both of, Ill., assignors to Zenith Radio Corporation, Chicago, Ill.

Filed Mar. 26, 1969, Ser. No. 810,774

Int. Cl. H04r 17/10; H01v 7/00

U.S. Cl. 333-72

1 Claim



A body of piezoelectric material propagates acoustic surface waves. Coupled to a surface of the body is a first transducer that launches the waves. Spaced on the same surface from the first device is a second transducer that responds to the launched waves. In order to reduce interference from reflections and increase efficiency, an end surface of the body is selectively located with respect to the adjacent transducer and is formed to define a particular angle with respect to the wave propagating surface. With the transducer elements in the form of interleaved combs of electrodes, absorption of reflections from an end surface is increased by effectively locating the end surface a precise fraction of an acoustic wavelength from the nearest comb electrode or tooth. Moreover, the response of the combined apparatus to signals being transmitted may be altered by changing either the angle that the end surface forms with respect to the propagating surface or by changing the spacing of the end surface from the transducer. The response also may be altered by depositing a different material on the wave propagating surface.

3,581,249

MINIATURE HELICAL RESONATORS

Frederick E. Spangler, and Henry A. Schaefer, both of Lynchburg, Va., assignors to General Electric Company

Filed Jan. 27, 1969, Ser. No. 794,332

Int. Cl. H03h 1/00, 5/08


U.S. Cl. 333-705

7 Claims

A helical coil resonator is wound on a dielectric form mounted on a dielectric base. Four posts are mounted on the base at the corners of a square, and are threaded on their inner faces to form a threaded receptacle that is concentric about the coil. A cup-shaped dielectric tuning element is threaded in the receptacle for movement toward and away

from the coil, and a metallic can is positioned around the posts. The capacity between the coil and can, and hence the

shaped path, and emerges from the other slanting tubular piece. Axial metal plates in the tubular pieces form an ex-



resonant frequency of the resonator, is varied by adjusting the position of the tuning element relative to the coil.

3,581,250

DELAY LINE HAVING NON PLANAR GROUND PLANE, EACH LOOP BRACKETING TWO RUNS OF MEANDERING SIGNAL LINE


Edwin S. Eichert, Bryn Mawr, and William T. Storey, II, West Chester, both of, Pa., assignors to Technitrol, Inc., Philadelphia, Pa.

Filed Apr. 12, 1968, Ser. No. 720,998

Int. Cl. H01p 5/12, 3/02, 3/08

U.S. Cl. 333-31

9 Claims



An electrical component such as a delay line comprising a first signal conductor and a second signal conductor spatially displaced from and electrically cooperable with said first signal conductor. At least one of said first or second signal conductors extending through an enclosure of nonconductive material having nonplanar upper and lower surfaces to provide increased isolation between an input and an output signal.

A method of making the electrical component also is disclosed.

3,581,251

MICROWAVE TUBE COOLING ASSEMBLY

Friedrich Potzl, Hamburg, Germany, assignor to U.S. Philips Corporation, New York, N.Y.

Filed Feb. 28, 1969, Ser. No. 803,256

Claims priority, application Germany, Mar. 8, 1968, P44196


Int. Cl. H01p 1/16, 7/06

U.S. Cl. 333-83

7 Claims

The invention relates to a connecting flange for a microwave tube arranged in an external resonator space, the connecting flange having two tubular pieces for the inlet and the outlet of the cooling air.

The air enters the resonator space in oblique direction, flows around the microwave tube along an approximately α-



tremely low resistance to the flow of cooling air while exhibiting very high damping for the resonator waves.

3,581,252

POTENTIOMETER CIRCUIT ARRANGEMENT FOR DERIVING A TUNING VOLTAGE

Franz Sacher, Vienna, Austria, assignor to Wiener Schwachstromwerke Gesellschaft m.b.H., Vienna, Austria


Filed Sept. 23, 1968, Ser. No. 761,482

Claims priority, application Austria, Feb. 22, 1968, A1,675/68

Int. Cl. H03j 5/02, 3/18

U.S. Cl. 334-15

6 Claims



A circuit arrangement for deriving a tuning voltage for controlling a tuning capacitance includes a plurality of potentiometers connected to form a voltage divider, each having a resistance path and a tap. The tap is electrically connected to the resistance path, and the resistance paths are connected in series. A selector switch comprises a plurality of contacts, each connected to a respective one of the taps, and a contact arm selectively engageable with the contacts. Each potentiometer corresponds to a respective frequency range, such as a channel or a group of channels.

3,581,253

ARMATURE-CONTACT ROD CONNECTION FOR CURRENT-LIMITING BREAKER


Norman R. Beaudoin, Bristol, and Robert W. Lauben, Farmington, both of, Colo., assignors to General Electric Company

Filed Oct. 15, 1969, Ser. No. 866,533

Int. Cl. H01h 77/10

U.S. Cl. 335-16

9 Claims



A current-limiting circuit breaker is provided with a new and improved contact-operating assembly having a contact

rod operatively joined to a tubular operating shaft by an axially extending stepped connector fixedly received within the rod and slidably retained by the operating shaft to permit limited relative movement between the operating shaft and the contact rod of the assembly. A spring mounted within the tubular shaft acts on the connector and may be adjusted independently of shaft movement.

3,581,254

ADJUSTABLY MOUNTED PLAYER PIANO KEY ACTUATING ASSEMBLY


Richard L. Cannon, and Leonard R. D. Smith, both of Yankton, S. Dak., assignors to Dale Electronics, Inc., Columbus, Nebr.

Filed June 13, 1969, Ser. No. 833,066

Int. Cl. H01t 7/08

U.S. Cl. 335-255

10 Claims



An assembly for actuating piano playing means which includes means for mounting solenoid key actuating units on a metallic channel means. The solenoid units include a laterally extending tab having a groove formed therein which is adapted to receive one flange of the channel means. A screw member extends through the tab and engages the flange to maintain the solenoid unit on the channel means. The units may be arranged in a side-by-side relationship on one channel means or may be arranged on oppositely disposed channels. The metal-to-metal connection between the solenoid units and the channel means permits the channels to serve as a common magnetic path for the individual coils and as a heat sink to dissipate heat directly from the coils. An embodiment of the assembly is also disclosed wherein the solenoid has a tab extending therefrom and which is removably received between a pair of flanges extending from the channel means.

3,581,255

MOUNTING MEANS FOR PLAYER PIANO KEY ACTUATING ASSEMBLY

Richard L. Cannon, and Leonard R. D. Smith, Yankton, both of, S. Dak., assignors to Dale Electronics, Inc., Columbus, Nebr.


Continuation-in-part of Ser. No. 833,066, June 13, 1969

Filed June 24, 1970, Ser. No. 49,349

Int. Cl. H01t 7/08

U.S. Cl. 335-255

7 Claims



An assembly for actuating piano playing means which includes means for mounting solenoid key actuating units on a

metallic support means. The support means includes a pair of spaced apart elongated angle members. Each of the angle members have upper and lower rows of horizontal slots formed therein which are staggered with respect to each other to permit the selective mounting of the solenoid units thereon. Each of the solenoid units have a frame means thereon which may be secured to the angle members by means of screws or the like extending through the slots in the angle members and being threadably received by the frame means.

3,581,256

SHOCK RESISTANT ARMATURE FOR ELECTRO-MAGNETIC DEVICES

Charles Vazquez, Paris, France, assignor to International Standard Electric Corporation, New York, N.Y.

Filed Mar. 21, 1969, Ser. No. 809,270

Claims priority, application France, Mar. 28, 1968, 145,857

Int. Cl. H01f 7/08

U.S. Cl. 335-271

5 Claims



Structure for damping the vibrations in armatures of electromagnets. The shock of operating pieces in electromechanical devices is reduced by making the armature out of several parts. These parts are juxtaposed, but they are not rigidly associated with each other. Each part vibrates at a frequency proper to it. This arrangement enables a great damping of the overall vibration resulting from shocks.

3,581,257

MAGNETIC HOLDING DRUM


Edmund F. Pressnetz, Baldwin, N.Y., assignor to Electronic Transmission Systems, Inc., New York, N.Y.

Filed Oct. 29, 1969, Ser. No. 872,238

Int. Cl. H01f 7/20

U.S. Cl. 335-285

7 Claims



A magnetic holding drum particularly suitable for optical reproduction devices such as facsimile transmitters, which enables the copy to be held substantially flat over the surface of the drum while the drum is either rotated or optically scanned. The drum includes a plurality of spaced-apart, radially disposed elongated magnets on its cylindrical surface. A sliding holder which is slidably retained in grooves at each end of the drum is magnetically affixed at any desired position on the surface of the drum in order to maintain the copy flattened against the drum's surface.

3,581,258

ELECTROMAGNETIC WIRING SYSTEM OF INTERLINKED COILS PARTICULARLY SUITABLE IN A CURRENT TRANSFORMER FOR HIGH VOLTAGES


Friedrich Raupach, Messwandler-Bau GmbH, Nuernberger Strasse 199, D-86 Bamberg, Germany

Filed Feb. 13, 1969, Ser. No. 798,921

Int. Cl. H01f 40/06

U.S. Cl. 336-173

32 Claims



An electromagnetic energy transforming device particularly suitable in a current transformer for high voltages and similarly interlinked coils comprising at least one core; at least one coil threaded through said core; said core having a closed symmetrical geometrical z-y shape of a z-y longitudinal cross section with at least two core legs in parallel and at least one core bar interconnecting said legs; said core having a x-y symmetrical cross section perpendicular to the length of said core substantially elongated, with a longer "x" axis and a shorter "y" axis and a "z" axis perpendicular to said x and y axes; said at least one core bar being symmetrically gradually twisted relative to said core legs with the core "x" axis being parallel to the "z" core axis of said at least two core legs in the center of said core bar between said core legs; the surface of said core bar adjacent the surface of said coil bar being of a shape closely mating with said surface of said coil bar in three dimensions.

3,581,259

QUICKLY-REMOVABLE IGNITION COIL INSTALLATION FOR AUTOMOBILE THEFT PREVENTION


Ernest Brunside, 3843 Rohms Ave., Detroit, Mich.

Filed Nov. 19, 1969, Ser. No. 877,890

Int. Cl. H01f 27/02

U.S. Cl. 336-90

8 Claims



An ignition coil receptacle adapted to be mounted near an automobile engine has a removable cover containing first, second and third low-tension terminals and a single high-tension terminal detachable engageable respectively with first, second and third correspondingly located low-tension electrodes and a single high-tension electrode mounted in the end cap of an automobile ignition induction coil removably mounted in the receptacle. One end of the primary winding of the coil is connected as usual to one end of the secondary winding thereof and their common junction is connected to the first low-tension electrode which in turn is connected directly to the second low-tension electrode. The opposite end of the primary winding is connected to the third low-tension electrode whereas the opposite end of the secondary winding is connected to the single high-tension electrode.

The first, second and third low-tension cover terminals are connected to first, second and third low-tension cables and the single high-tension cover terminal to a high-tension cable, all of these cables being contained within a flexible tubular casing. The first low-tension cable leads to a conventional timer, the opposite pole of which is grounded. The interconnected second low-tension cable is connected to one side of the conventional coil condenser, the opposite side of which is grounded to the engine. The third low-tension cable leads to one terminal of a conventional storage battery, the opposite terminal of which is grounded to the automobile frame. The single high-tension cable is connected to the rotor of the conventional distributor, the fixed poles of which are connected to the central electrode of the spark plug whose casings are grounded to the engine. Upon leaving the automobile, the driver pulls outward upon the receptacle cover, thereby withdrawing the coil and cover as a unit from the receptacle. He then pulls the cover terminals and coil electrodes apart from one another to separate them, replaces the cover upon the receptacle, and carries the ignition coil away with him, thereby preventing theft of the automobile.

3,581,260

FLANGE FOR ELECTROMAGNETIC COIL

Pio Andreis, Milan, Italy, assignor to Societa Italiana Telecomunicazioni Siemens S.P.A., Milan, Italy


Filed Oct. 13, 1969, Ser. No. 865,700

Claims priority, application Italy, Oct. 14, 1968, 22469

Int. Cl. H01f 15/10

U.S. Cl. 336-192

10 Claims



A spool body for a relay coil is formed from a ferromagnetic core bounded by two nonconductive flange plates; at least one of these plates has a pair of notches, tangential to the core, for the ends of each winding to be wound thereon and a pair of depressions adjacent these notches on the outer plate surface remote from the core to receive these wire ends for soldering to respective terminals at locations sheltered from the coil winding or windings.

3,581,261

MOLDED CASE CIRCUIT BREAKER HAVING AN AUXILIARY CONTACT SEPARATING SPRING


John De Torre, and Henry S. Wingard, both of Albemarle, N.C., assignors to Federal Pacific Electric Company

Filed July 28, 1969, Ser. No. 845,275

Int. Cl. H01h 71/16, 71/64, 75/12

U.S. Cl. 337-67

3 Claims



A circuit breaker of the molded case type incorporating a spring that accelerates movement of the movable contact to

the open circuit position. The same spring augments contact pressure between the movable and stationary contacts in the closed circuit condition of the circuit breaker.

3,581,262

SAFETY FUSE WITH GLASS COATING ON FUSIBLE PORTION


Efim Yakovlevich Badinter, ulitsa Fedko, 8, kv. 79; Zinoviy Ieremeevich Zelikovskiy, ulitsa Pushkina, 35, kv. 13, and Irina Georgievna Lazurevskaya, ulitsa Gorkogo, 221a., all of Kishinev, U.S.S.R.

Filed Mar. 6, 1969, Ser. No. 804,797

Int. Cl. H01h 85/14

U.S. Cl. 337-159

4 Claims



A safety fuse provided with a fusible element adapted for protection against overloads, the surface of said fusible element being covered with a continuous glass insulation coating. The fusible element may be a length of a cast microwire provided with a glass insulation.

3,581,263

THERMALLY RESPONSIVE SWITCH


Antonio Moro, Milan, Italy, assignor to Soc. per Azioni Fratelli Borletti, Milan, Italy

Filed July 8, 1968, Ser. No. 743,157

Int. Cl. H01h 37/04, 37/28, 37/54

U.S. Cl. 337-380

12 Claims




A thermally responsive switch comprising a housing including a metal body with a recess therein. A cap of insulating material is secured to the metal body closing the recess. A disc-shaped bimetallic strip is loosely housed in the recess. The fixed contact is carried by a stiff metal bridge which bridges across the recess. The position of the fixed contact is adjustable. Adjustment being made by a tool inserted through an aperture in the cap.

3,581,264
METHOD OF CREATING VARIABLE ELECTRICAL RESISTANCE AND MEANS FOR CREATING THE SAME
Herman R. Person, Columbus, Nebr., assignor to Dale Electronics, Inc., Columbus, Nebr.
Division of Ser. No. 593,998, Nov. 14, 1966, Pat. No. 3,480,832.
Filed Apr. 21, 1969, Ser. No. 817,965
Int. Cl. H01c 7/16

U.S. Cl. 338-20

3 Claims



A variable magnetic resistor comprising a layer of high permeability magnetic alloy formed into a helix with a layer of insulation material in between each convolution of the helix, and an electrical terminal secured to opposite ends of the layer of alloy. The method of creating variable resistance by passing a current of sufficient magnitude through said alloy material that the current passing through the alloy will be forced to the side edges thereof by the magnetic field around each convolution of the helix, whereby the resistance of the alloy will be increased as current moves away from a normal low-voltage path through the broad expanse of the entire cross-sectional area of the coil to a more confined path at the side edges of the coil.

3,581,265

MINIATURIZED POTENTIOMETERS

Eugenio Falco, 13, Avenue Taillebourg, Paris 110, France


Filed Feb. 24, 1969, Ser. No. 801,457

Claims priority, application France, Feb. 27, 1968, Dec. 3, 1968, 141,458; 176,382

Int. Cl. H01c 9/02

U.S. Cl. 338-174

13 Claims



A potentiometer having a cover of conductive material formed by molding in a single piece with a pair of lateral terminals provided to be placed at the ends of a resistance track, a collector, and a base on which the resistance track and the collector are printed. The lateral terminals are separated from the cover during the step of crimping the cover on the base.

3,581,266

HOUSED RESISTOR

Lionel E. Weyenberg, N34 W23575 Capitol Drive Parkway, Pewaukee, Wis.

Filed Dec. 30, 1968, Ser. No. 787,806


Int. Cl. H01c 1/02

U.S. Cl. 338-253

5 Claims

A potted resistor including an outer metal casing, and a re-

sistance element is embedded within an insulating material contained within the casing. Terminal strips are connected to



the resistance element and project outwardly of the insulating material in position to be connected to electrical leads.

3,581,267

ELECTRIC CONDUCTOR BEARINGS


Robert Z. Schreffler, Chester, Va., assignor to Electric Conductor Bearings, Incorporated, Chester, Va.

Continuation-in-part of application Ser. No. 562,956, June 30, 1966. This application Aug. 14, 1968, Ser. No. 752,666

Int. Cl. H01r 39/28

U.S. Cl. 339-8

10 Claims



An electric conductor bearing arrangement includes a fixed outer race, a shaft-mounted rotatable inner race and a plurality of roller bearing devices for completing a current path therebetween. The bearing devices each include a cylindrical coil spring arranged with the longitudinal axis thereof parallel to the shaft axis. The spring bearings which are transversely compressible compensate for any misalignments by assuming a shape compatible with the existing alignment.

3,581,268

ELECTRICAL CONNECTION AND DISTRIBUTION SYSTEM


Harold Akst, West Chester, Pa., assignor to Burroughs Corporation, Detroit, Mich.

Filed Apr. 1, 1969, Ser. No. 812,185

Int. Cl. H01r 29/00

U.S. Cl. 339-18

5 Claims



This invention discloses an electrical connection and distribution system including one or more unique distribution

connectors. Each of said distribution connectors is capable of distributing current or voltage to a plurality of wire connections from an individual connection. The connector shell envisioned, for use in this connector, is of a commercially available configuration. By including one or more unique jumper means in these commercially available connectors, a new and novel connector combination is created wherein a single wire enters a terminal one side of the connector and multiple wires leave corresponding multiple terminals on the same side to provide a distribution system for the current or voltage source which entered the single terminal.

3,581,269

CONNECTOR FOR COAXIAL CABLE


Dean R. Frey, Dover; George L. Hone, Berkeley Heights, and Edward L. Ramsey, Jr., Martinsville, all of N.J., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Mar. 11, 1969, Ser. No. 806,098

Int. Cl. H01r 17/04, 33/34

U.S. Cl. 339-94

4 Claims



This disclosure describes a connector for a communications coaxial cable. The connector structure includes a collapsible bushing which is wedged into a positive grip with the cable jacket, and a separate wedge-type bushing to grip the outer conductor. A resilient seal is afforded around the center conductor. Placement of the cable in the connector and of the latter onto equipment housing requires no special tools.

3,581,270

THERMOPLASTIC LAMP HOLDER


Larry L. Shroyer, Wolcottville, Ind., assignor to Lyall Electric, Inc., Albion, Ind.

Filed Apr. 4, 1969, Ser. No. 813,610

Int. Cl. H01r 13/48

U.S. Cl. 339-160

7 Claims



A multiple lamp holder is disclosed which is characterized by its simplicity of construction. The lamp holder is made up

of four pieces: two conductive terminals, an insulating bushing which holds the two terminals apart and an insulating housing which is molded in a single piece and consists of two complementary halves of the housing joined together in a hinged relationship so that the two halves may be folded together so as to enclose the terminals and bushing and the resulting structure need only to be sealed along a single seam.

3,581,271


CONTACT UNIT HAVING CONTACT PROTECTIVE MEANS

Heinz Knitter, Heilbronn, and Josef Veszelik, Weinsberg, Germany, assignors to The Bunker-Kame Corporation, Oak Brook, Ill.

Filed May 7, 1969, Ser. No.
Int. Cl. H01r 13/42

U.S. Cl. 339-176

8 Claims



Contact unit adapted for insertion in an internal passage of a connector body and including a resilient spring metal contact engageable with a mating contact and substantially enveloped within a protective housing to prevent damage thereto. The housing, contact and terminal means are preferably integral with a metal body and formed from a one-piece sheet metal stamping.

3,581,272


MINIATURE CONNECTOR

Robert S. Yopp, Naperville, and Melvin G. Kraft, Bellwood, Ill., assignors to The Bunker-Romo Corporation, Oak Brook, Ill.

Filed Dec. 23, 1968, Ser. No. 786,189
Int. Cl. H01r 11/22


U.S. Cl. 339-252

5 Claims




Pin contact, of a miniature connector, made as a stamping from a single piece, having a pair of cantilever contact elements together forming a pin member.

3,581,273
MARINE SEISMIC EXPLORATION
Ronald M. Hedberg, 18 Whittier St., Cambridge, Mass.
Continuation of application Ser. No. 645,643, June 13, 1967.
This application Nov. 10, 1969, Ser. No. 875,510
Int. Cl. G01v 1/38
U.S. Cl. 340-7PC 13 Claims



Continuous marine seismic explorations are carried out by providing echo detecting means with control means for maintaining the echo detecting means in fixed or predetermined positions and at spaced points in two dimensions of a horizontal plane, and by generating echo producing impulses at one or more spaced points located in fixed or predetermined relative positions with respect to each other and in said plane. In this way, a set of records may be obtained which define the seismic interfaces of the prospect under survey in two intersecting vertical planes. Thereafter, by producing successive sets of such records, quadratic surfaces in which the true inclinations of interfaces may be determined over an extended area are obtained in a single traverse thereof. At the same time, the accuracy of the records obtained is materially increased.


3,581,274
FREQUENCY-DOMAIN BAND BROADENING OF SEISMIC DATA
William H. Ruehle, Duncanville, Tex., assignor to Mobil Oil Corporation
Filed Mar. 19, 1969, Ser. No. 808,410
Int. Cl. G01v 1/00
U.S. Cl. 340-15.5 9 Claims



The specification, in the preferred embodiment, discloses a technique for removing distortion such as multiples from seismograms by converting the traces of the seismogram by Fourier transformation into their real and imaginary parts. The envelopes of the real and imaginary parts are detected in the frequency domain and operated on to produce inverse operators which are a function of the envelopes of the real and imaginary parts. The product is formed between the real


and imaginary parts of the traces and the inverse operators to remove distortion components from the real and imaginary parts of each trace. The resulting distortion-free data is transformed back into the time domain for further processing and analysis.

3,581,275
MOIRE FRINGE PRODUCING DEVICE USED FOR INTERCEPTION COURSE INDICATION
Paul S. Petersen, Minnetonka, Minn., assignor to Rosemount Engineering Company, Minneapolis, Minn.
Filed Oct. 23, 1965, Ser. No. 503,652
Int. Cl. G08g 5/00; G64f 1/20
U.S. Cl. 340-25 6 Claims




A landing aid utilizing the principle of Moire fringe patterns so that a plurality of wide light and dark bands are observed by a person using the landing aid, and when on proper course, the bands do not move, but when on other than an interception course, the bands appear to move, and such movement will be in relationship to the amount of error in the interception course.

3,581,276
VEHICLE LIGHT CONTROL AND WARNING INDICATOR SYSTEM
LaVerne R. Newman, St. Clair Shores, Mich., assignor to Essex International, Inc., Fort Wayne, Ind.
Filed Mar. 22, 1968, Ser. No. 715,314
Int. Cl. B60q 1/02
U.S. Cl. 340-52 16 Claims




An automatic lamp disconnecting system for vehicle lighting systems having a lamp energizing circuit including a normally open relay switch in series with a manual lamp control switch. Magnetic means for closing the relay switch is energized through the vehicle ignition switch and through a separate holding circuit comprising, in series connection, the relay switch, the lamp control switch, and a normally closed thermal time delay switch which has a heating element responsive to energization of the vehicle lamp only when the ignition switch is opened to effect opening of said time delay switch a predetermined time after opening of the ignition switch.

3,581,277
TIRE INFLATION MONITORY SYSTEM
Robert D. Beatty, Jr., Gates Mills, and Thomas C. Griffiths, Chardon, both of, Ohio, assignors to Eaton Yale & Towne Inc., Cleveland, Ohio
Filed Oct. 20, 1967, Ser. No. 676,891
Int. Cl. B60c 23/00
U.S. Cl. 340-58 18 Claims



Angular movements of wheels or other objects rotating at the same surface speed are sensed as by counting revolutions of the wheels or objects with the angular movements of the wheels or objects being compared with each other or a reference to determine whether or not one wheel or object has a smaller diameter.

3,581,278
WARNING DEVICE FOR MOVING VEHICLE
Bobbie Dale Huffman, R.R. 24, Box 163, Terre Haute, Ind.
Filed Sept. 23, 1968, Ser. No. 761,536
Int. Cl. B60q 1/50 7 Claims




A warning device for a self-propelled vehicle comprising an air-pressure sensitive device normally inactivated by motion of the vehicle against air but becoming activated during deceleration at a speed below a predetermined speed thereby signaling others of the deceleration. The device comprises an air pressure responsive means, a microswitch, and one or a multiple of warning lamps. In a preferred embodiment a manually controlled masking means is provided whereby said air-pressure responsive means can be shielded from air pressure by operator of said vehicle. In another embodiment the warning lamps are the turn signals normally present on a vehicle and a means is provided whereby activation of the turn signals by the turn-signal lever automatically inactivates the warning device.

3,581,279

SIGNAL TRANSMISSION METHOD AND SYSTEM
Timothy Arbuckle, Montclair, N.J., assignor to Computer Modem Corporation, Ft. Lee, N.J.
Filed June 9, 1969, Ser. No. 831,293
Int. Cl. G08c 25/00; H04b 15/00
U.S. Cl. 340-146.1

14 Claims



A signal transmission system enabling exchange of the information content of message signals with substantial reduction of communication channel noise effects thereof. Message signals are converted into other signals actually transmitted. Received signals are reconverted to provide said message signals, the conversion and reversion being of such nature as to effect substantially uniform distribution of channel noise in message signals derived from said received signals.

3,581,280

HOLOGRAPHIC SPATIAL FILTERS AND METHOD OF MAKING SAME
John M. Holeman, Schenectady, N.Y., assignor to General Electric Company
Filed June 27, 1966, Ser. No. 560,418
Int. Cl. G06k 9/00
U.S. Cl. 340-146.3F

9 Claims



This invention relates to holography, and more particularly to a method and apparatus for rapidly making highly efficient spatial filters for holography.

3,581,281


PATTERN RECOGNITION COMPUTER
Francis C. Martin, Williamsville, N.Y., and James P. Nicklas, Woodland Hills, Calif., assignors to Cornell Aeronautical Laboratory, Inc., Buffalo, N.Y.
Filed Mar. 28, 1967, Ser. No. 626,495
Int. Cl. G06k 9/06

U.S. Cl. 340-146.3

5 Claims

A pattern recognition digital computer employing stores for combining the addresses of all points on an input matrix that is exposed to a pattern, the addresses being arbitrarily arranged into discrete areas of the stores, at least one predetermined weight value assigned to each of the discrete areas, threshold units for comparing the activity of each of the discrete areas with a predetermined value, response accumulators for receiving the weight values for each of the dis-

crete areas that are above the threshold; and gates, distributors and arithmetic elements for changing the weight values




for those discrete areas that contribute to incorrect responses.

3,581,282

PALM PRINT IDENTIFICATION SYSTEM
Norman G. Altman, White Plains, N.Y., assignor to Charles H. Lipton and Michael Ebert, New York, N.Y., part interest to each
Filed Dec. 3, 1968, Ser. No. 780,768
Int. Cl. G06k 9/00

U.S. Cl. 340-149

9 Claims



A palm print identification system in which an image of the palm pattern is optically formed and scanned to generate a video signal which is an analog of the pattern, the signal being converted into a numerical code. Because each palm print is unique, an individual is thereby given a singular identifying code number which is an index to the pattern. The code identification may be recorded on an ID card. To verify identification, the hand is placed on a sensing unit and the ID card is inserted in a suitable card reader. The numerical code on the card is sensed and converted into an electrical signal which is compared in a correlator with the video signal derived from the scanned palm of the hand to determine the degree of correspondence therebetween and thereby establish identification.

3,581,283

TONE DECODER RESPONSIVE TO COMBINED TONES
Robert J. Reddel, Fairborn, and Edward J. Brauner, Piqua, both of Ohio, assignors to Ledex, Inc., Dayton, Ohio
Filed Apr. 30, 1968, Ser. No. 725,469
Int. Cl. H04m 11/02

U.S. Cl. 340-171

15 Claims


A tone decoder responsive to predetermined combinations of tones presented for predetermined time intervals comprises plural electromechanical tone detector devices coupled to interrelated switchable devices so arranged that an output function will be initiated only when the combination

3,581,285

KEYBOARD TO MEMORY PERIPHERAL DEVICE
Farid J. Neema, Sudbury, and Robert C. Engelhardt, Watertown, both of Mass., assignors to Honeywell Inc., Minneapolis, Minn.
Filed Nov. 20, 1968, Ser. No. 777,442
Int. Cl. G06f 13/00, 3/10

U.S. Cl. 340-172.5

12 Claims




devices so as to permit application of a voltage through the interrelated switchable devices to an output load device.

3,581,284

RANDOMLY ACCESSED NON-INTERFERING INPUT-OUTPUT DATA ACCUMULATOR
Ronald B. Selden, North Hollywood, Calif., assignor to T R W Inc., Redondo Beach, Calif.
Filed June 3, 1968, Ser. No. 734,091
Int. Cl. G06c 25/02

U.S. Cl. 340-172.5

5 Claims




There is disclosed a data accumulator suitable for use in oil field supervisory control systems or, more generally, in various process control or other data processing systems wherein it is desired to accumulate total at the remote location at any time without destroying or interfering with the accumulating total regardless of when the readout command is received. In order to accomplish this, there is provided a shift register adapted to contain the total count data in the form of a binary word having a predetermined number of bits. The shift register is connected in a feedback loop such that its contents may be serially read out and passed through a specialized adding circuit which either transmits the register content in unchanged form or adds one to the total content depending upon whether the adding circuit has been actuated by receipt of an add command from a bistable input buffer means which receives the input unit event counting pulse. The output of the adding circuit is applied as feedback to the input of the shift register in such a fashion that the register content is continuously circulating. The timing parameters of the circuit are chosen so that the total duration of the input unit event count pulse is greater than the total time duration of the complete work content of the shift register. On this basis, the adding circuit logic can be shown to produce a correct and unambiguous result regardless of when the input pulse arrives or when a readout is desired. The online readout is, of course, taken from the adding circuit.

3,581,286

MODULE SWITCHING APPARATUS WITH STATUS SENSING AND DYNAMIC SHARING OF MODULES
William F. Beausoleil, Poughkeepsie, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.
Filed Jan. 13, 1969, Ser. No. 790,681
Int. Cl. G06f 15/16

U.S. Cl. 340-172.5

17 Claims



An input/output interface switching apparatus for switching I/O interfaces connecting I/O control units between

channels. The I/O interface switching apparatus provides means for attaching one or more strings of control units to one or more channels and provides a means for switching these strings of control units between the channels under configuration control. The switching apparatus is so arranged that a single failure within one interface affects at most only the channel to which the interface is associated. A switching matrix is provided, within the apparatus, which is physically centralized to minimize the number of I/O interface cables and connectors. The switching functions are, however, logically decentralized from a reliability standpoint so that a single component failure will not result in total switching system failure.

3,581,287

APPARATUS FOR ALTERING COMPUTER MEMORY BY BIT, BYTE OR WORD


Lawrence E. Greenspan, Thornton's Ferry, and Earl J. Whitaker, Nashua, both of, N.H., assignors to Sanders Associates, Inc., Nashua, N.H.

Filed Feb. 10, 1969, Ser. No. 798,034

Int. Cl. G11c 15/00

U.S. Cl. 340—172.5

14 Claims



The assembly of individual bits, bytes or words into a 16-bit word is accomplished directly in a computer memory without the use of 16-bit buffer registers in the bit or byte data channels. As a bit, byte or word is received by an input computer channel, that bit, byte or word is stored in the addressed location of the computer memory. In particular, this is accomplished basically by reading the addressed word out of memory into a memory register, gating the new bit or byte into the appropriate stage or stages of the memory register without altering the other stages and writing the new word back into the same memory location.

3,581,288

DATA PROCESSING SYSTEM

Yoshiaki Suzuki, Tokyo, and Toshiharu Inamoto, Yokohama, both of, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Feb. 11, 1969, Ser. No. 798,342

Claims priority, application Japan, Feb. 28, 1968, June 4, 1968, 43/13227; 43/47374


Int. Cl. G06f 3/00, 7/38

U.S. Cl. 340—172.5

4 Claims

A data processing system in which an arithmetic operation and the setting of a decimal point are carried out by a com-

mand entered from entry digit keys to thereby facilitate the setting of the specified decimal point and the starting of com-



3,581,289

DISPLAY TERMINAL FOR COMPUTER MONITORED PLANT VARIABLES


D. F. Wilhelm, Toledo; Peter S. Miller, Toledo; D. L. Bissell, Toledo, and George M. Lambroff, Swanton, all of, Ohio, assignors to Owens-Illinois, Inc.

Filed Apr. 28, 1969, Ser. No. 819,701

Int. Cl. G06f 3/00; G06c 21/00

U.S. Cl. 340—172.5

13 Claims



Input variables are sensed by sensors at various locations in a manufacturing facility and supplied as raw data to a computer which may or may not perform calculations on the data supplied thereto. Data from the computer is presented on a time sharing basis to a plurality of remotely located data display terminals. Each data display terminal is equipped with a plurality of manually actuated data selection units having identifying indicia and a numerical display displaying data from the computer corresponding to the requested indicia of an actuated data selection unit along with data indicating trend of the variable relative to a standard or reference value. The communication link between the computer and the display terminals may be conventional wiring with data lines common to each display terminal and individual lines for achieving connection to the computer and the display terminal being individual to the display terminals. Consult the specification for further features and details.

3,581,290

INFORMATION DISPLAY SYSTEM

Robert Sugarman, New York, N.Y., assignor to Sugarman Laboratories, Inc., Great Neck, N.Y.

Filed June 3, 1969, Ser. No. 830,032


Int. Cl. G06f 3/14

U.S. Cl. 340—172.5

31 Claims

A system for the display of information on a cathode-ray tube or the like wherein the information comprises a plurality of lines of text comprising a number of characters and wherein each text line is formed by a plurality of scans. The system comprises a main memory for storing sets of bits

wherein each set of bits represents a different one of all the characters to be displayed and an auxiliary memory for storing the sets of bits comprising the particular text line being formed on the screen of the cathode-ray tube. The auxiliary memory is operable to sequentially present each set of bits



stored therein at its output during each scan comprising the particular text line. Decoding means responsive to the set of bits of the output of the auxiliary memory is provided to modulate the electron beam to form areas of the character represented by the set of bits during a particular scan.

3,581,291

MEMORY CONTROL SYSTEM IN MULTI-PROCESSING SYSTEM

Shoji Iwamoto, Totsuka-ku, and Hisashi Horikoshi, Tachikawa-shi, both of, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 29, 1969, Ser. No. 872,164

Claims priority, application Japan, Oct. 31, 1968, 43/79555

Int. Cl. G06f 15/16

U.S. Cl. 340—172.5

13 Claims



A multiprocessing system comprises two processors and a main memory to be utilized by the processors in common. Each processor is provided with a buffer memory which stores information read from the main memory, block by block, and the main memory is provided with a key memory which stores an indicator indicating whether or not information in the main memory is read out and stored in each processor at each predetermined amount of its capacity (sector). When one of the processors carries out a writing in a sector of the main memory, whether or not the information of the sector is stored in the other processor is checked. When the information is stored, the address of the information is supplied to the other processor to invalidate the corresponding sector of the buffer memory. In this manner, the coincidence between the stored contents of the main memory and buffer memory is prevented.

3,581,292

READ/WRITE MEMORY CIRCUIT

Robert W. Polkinghorn, Huntington Beach, Calif., assignor to North American Rockwell Corporation

Filed Jan. 7, 1969, Ser. No. 789,455


Int. Cl. G11c 11/24, 7/00

U.S. Cl. 340—173R

11 Claims

Two capacitors of an addressed memory circuit are charged during a write period to a potential representing a logical state. The first capacitor is connected between the

output electrode and the control electrode of the MOS device for turning the MOS device on as a function of the logical state of the capacitor. When the input signal is true, during a read period, the voltage on the output electrode of the MOS device is fed back through the first capacitor for increasing the voltage. As a result, the output voltage is driven to a voltage which overcomes the threshold drop through the device. Another MOS device having a relatively larger control voltage is turned on so that the read signal appearing at



the output electrode of the first MOS device is read out of the address memory circuit without a reduction due to threshold voltages of the MOS devices involved.

The second capacitor connected between the common input/output line and ground is recharged so that it supplies leakage charge to the first capacitor during write periods when the circuit is not addressed. It is conditionally reset to ground between read and write periods to prevent reading of erroneous information.

3,581,293

FORM OF PLATED WIRE MEMORY DEVICE


George A. Fedde, Norristown, and John Presper Eckert, Jr., Gladwyne, both of, Pa., assignors to Sperry Rand Corporation, New York, N.Y.

Continuation of application Ser. No. 241,368, Nov. 30, 1962, now abandoned. This application Nov. 8, 1967, Ser. No. 681,598

Int. Cl. G11c 11/14

U.S. Cl. 340—174

9 Claims



This invention relates to a configuration of a plated wire memory device which permits closer packing of the bits. This is accomplished by using a memory element which has a cross section having a major and minor axis. The forward and return portions of the memory drive which are arranged orthogonally to the plated wire are thereby positioned closer to one another. By reducing the distance (d) between the drive portions, the width (w) thereof can correspondingly be reduced. Reducing (d) and (w) reduces the drive current for a given field strength and for a given amount of interaction between two adjacent drive lines, the distance p can be made smaller.

3,581,294

TUNED PLATED WIRE CONTENT ADDRESSABLE MEMORY

William J. Bartik, Wyncote, Pa., assignor to Sperry Rand Corporation, New York, N.Y.

Filed Mar. 11, 1968, Ser. No. 712,108


Int. Cl. G11c 11/14, 15/00

U.S. Cl. 340—174

4 Claims

A wire element is electrically tuned so that it operates with a low impedance. Bit information is then readily transferred

along the wire from one location (sender) to another location (receiver) by energizing the drive strap adjacent the sending bit with a burst of pulses. When the circulating cur-



rent in the wire builds up to a maximum value, the drive strap adjacent to the receiver bit is energized with a single pulse. The receiver bit will then switch if its binary state is opposite to that of the bit at the transmitter.

3,581,295

MAGNETIC CORE MEMORY ARRAY

Peter A. Denes, 9101 Crestwood Ave. N.E., Albuquerque, N. Mex.


Division of Ser. No. 352,919, Mar. 18, 1964, Pat. No. 3,435,518.

Filed Jan. 29, 1969, Ser. No. 822,337

Int. Cl. G11c 5/06, 11/06

U.S. Cl. 340-174NC

8 Claims



A three-dimensional magnetic core memory system in which the noise effect of partially switched cores on the sensing wires are greatly diminished and the number of connecting points in the system is minimized.

3,581,296

SHIFT REGISTER

William Brooks, 1042 Inverness Way, Sunnyvale, Calif.

Continuation-in-part of application Ser. No. 810,434, Feb. 4, 1969, now Patent No. 3,493,933, which is a division of

application Ser. No. 557,148, June 13, 1966, now Patent No. 3,493,957. This application Nov. 17, 1969, Ser. No. 877,069


Int. Cl. G11c 11/08, 19/00; H03k 23/32

U.S. Cl. 340-174SR

2 Claims

An electronic shift register used with a source of rectified alternating current, having a positive bus and a ground. A series of shift register stages are serially arranged between a first stage and a last stage, each stage having a silicon controlled rectifier and a transfluxor core associated together. Each silicon controlled rectifier has its cathode connected to ground, and a load is connected between its anode and the positive bus. Each transfluxor has a core and a primary connected to an oscillator and actuated thereby, a secondary connected to the gate of its associated silicon controlled rectifier, and first and second windings; each transfluxor except the one at the last stage has a third winding connected to the second winding of the succeeding stage. A shift control

switch is connected in series with each of the first windings, and data input means is connected to the second winding of the first stage for feeding binary data thereto. The connec-



3,581,297

BINARY DATA HANDLING SYSTEM


Michael I. Behr, South Pasadena; Lewis B. Coon, Jr., Pasadena, and Charles E. Bickel, West Covina, all of Calif., assignors to Burroughs Corporation, Detroit, Mich.

Filed Sept. 18, 1967, Ser. No. 668,529

Int. Cl. G11b 5/02, 5/44

U.S. Cl. 340-174.1

9 Claims



A system for reading binary data recorded on a storage medium as magnetic tape in either of several coding techniques. Specifically, the system is capable of reading either phase encoded data or data recorded in the form of nonreturn-to-zero pulses in which one binary value is represented by a flux reversal in a bit cell and the other binary value is represented by the absence of a flux reversal in a bit cell (hereafter called modified NRZ). A positive threshold detector, a negative threshold detector, and a bipolar peak detector are utilized for recovering the NRZ data and part of the preamble of the phase encoded data. The bipolar peak detector is also employed in the recovery of the phase encoded data itself. To recover the NRZ data and the preamble of the phase encoded data, the output of the positive threshold detector and the bipolar peak detector are combined in one AND circuit and the output of the negative threshold detector and the inverse output of the bipolar peak detector are combined in another AND circuit. To recover the phase encoded data, a signal representing the peak-to-peak amplitude of the read head signal is produced by differentiating it and then separately integrating the two half-cycles of the differentiated signal. The maximum amplitude of the differentiated signal is limited to suppress noise. The integrated signals are applied to a positive threshold detector

and a negative threshold detector, respectively. The output of the positive threshold detector is combined with the output of the bipolar peak detector in one AND circuit and the output of the negative threshold detector is combined with the inverse of the output of the bipolar peak detector in another AND circuit to recover the phase encoded data. To check for errors in the phase encoded data, these outputs are switched and applied to two other AND circuits.

3,581,298

SUPPORT DEVICE FOR MAGNETIC HEAD


Shahbuddin A. Billawala, Thousand Oaks, Calif., assignor to Burroughs Corporation, Detroit, Mich.

Filed Apr. 17, 1969, Ser. No. 816,979

Int. Cl. G11b 5/60; F16f 1/02

U.S. Cl. 340-174.1

27 Claims



A support device for floating a magnetic head on a fluid atmosphere adjacent a recording surface has several features in a one piece construction. The support device is a substantially flat, thin body structure of elastic material having perforations therein positioned and shaped to form a platform to which a magnetic head is bonded. A portion of the platform is permanently deformed to lie forward of the remainder of the body structure so the magnetic head is spaced from the remainder of the body structure. A pair of mounting tabs extend inwardly from opposite sides of the outer perimeter of the support device. The portions of the support device adjacent to the tabs are bowed inwardly away from the tabs. A cable support bracket is directly joined to the tabs so forces exerted on the bracket do not effect the position of the magnetic head.

3,581,299

ELECTRIC FENCE CHARGER HAVING GROUND DETECTOR


Willfred W. Schmit, Port Washington, Wis., assignor to Flo-Tronics, Inc., Minneapolis, Minn.

Filed Nov. 19, 1968, Ser. No. 777,040

Int. Cl. G08b 21/00; H05c 1/04; A01b 3/00

U.S. Cl. 340-254

10 Claims



An electric fence charger that is energized from a utility power supply wherein one utility supply line is grounded, said charger having a circuit to provide, in respect to a separate ground connection of said charger, high voltage energy impulses of short duration and a ground detector circuit to provide a visual indication when the fence charger ground does in fact not adequately connect the charger to ground. The ground detector circuit includes a pair of resistors connected in series across the primary winding or a center tapped primary winding of a transformer forming a part of the charger and connected to the utility power supply, and indicating means, such as a neon light, connected between the adjacent ends of said resistors or center tap and the charger ground terminal.

3,581,300

ELECTRONIC ACTUATOR AND TIMER CIRCUIT


Walter G. Eloranta, 1719 Vermont Ave., Fort Wayne, Ind.

Filed July 19, 1968, Ser. No. 746,158

Int. Cl. G08b 23/00

U.S. Cl. 340-309.1

4 Claims



A number of actuator circuits, each having a switch and a capacitor connected in series, are connected to a transformer primary winding. The transformer secondary winding is coupled to a controlled rectifier having a timer capacitor connected to its anode-cathode path. An output circuit is coupled to the timer capacitor. Closing of any one of the switches renders the controlled rectifier conductive to charge the timer capacitor, after which the controlled rectifier is turned off so as to be responsive to closing of another switch. The output circuit produces a signal as long as the timer capacitor has a charge.

3,581,301

DISPLAY ARRANGEMENT FOR SYMBOLS

Theo Stutz, Bassersdorf, and Werner Mueller, Aarau, both of Switzerland, assignors to A. G. Contraves, Zurich, Switzerland


Filed Oct. 24, 1967, Ser. No. 677,801

Claims priority, application Switzerland, Oct. 24, 1966, 15399/66

Int. Cl. G09f 9/30

U.S. Cl. 340-324

12 Claims



A display arrangement for displaying any desired symbol in an arbitrary manner in any desired sequence. The display is in the form of a grid pattern in which the grid areas confined by the lines and columns of the grid are either of one visual surface or another visually contrasting surface. The surfaces are flipped from one to the other through the application of a magnetic actuating device. The actuating device supports the visually contrasting surfaces and includes two permanent magnetic discs mounted in a plane perpendicular to the axis of movement or rotation about which the device moves in flipping from one display surface to the other. The permanent magnets operate in conjunction with an electromagnet which generates a field directed through an airgap. When the direction of the magnetic field is in one sense, one of the two permanent magnetic discs is attracted into the airgap while the other is repelled. When the direction of the magnetic field is reversed, the action upon the permanent magnetic discs is correspondingly reversed and the actuating device is moved so as to display the appropriate visual sur-

face. By energizing the electromagnet with current in the proper direction, a particular area within the grid pattern may be made of one or the other contrasting surface and as a result any desired symbol may be displayed.

3,581,302

APPARATUS AND METHOD FOR PROVIDING GRAPHICAL CONFIGURATIONS BY SEQUENTIALLY DIRECTING A RADIANT ENERGY BEAM TO PRESENT IMAGE POSITIONS


Edwin R. Kolb, University Heights, and Robert M. Horvath, Parma, both of, Ohio, assignors to Harris-Intertype Corporation, Cleveland, Ohio

Filed Mar. 4, 1968, Ser. No. 710,349

Int. Cl. H01J 29/70

U.S. Cl. 340—324

11 Claims



A phototypesetting system employs a cathode-ray tube to present characters of typesetting quality wherein each of the characters displayed is generated by directing the cathode-ray tube beam to a series of locations, each immediately adjacent its previous location, where the beam is energized for a predetermined period of time. A character memory, such as an optically encoded disc, supplies digital information to electronic circuitry which initially locates the beam within a character field and then directs the beam sequentially to additional locations, each of the locations immediately adjacent the previous location, thus forming characters from a series of illuminated spots. Additional deflection signals are supplied to control the cathode-ray tube to move the beam automatically to the next character position after each character has been formed in preparation for the writing of subsequent characters.

3,581,303

DIGITAL TO ANALOG CONVERTER

Franklin G. Kelly, Long Beach, Calif., assignor to TRW Inc., Redondo Beach, Calif.

Filed Oct. 6, 1967, Ser. No. 673,425

Int. Cl. H03k 13/02, 13/04


U.S. Cl. 340—347

3 Claims

A digital to analog converter includes a plurality of parallel connected circuits, each of which has a switching transistor in series with a calibrating or metering resistor. The metering resistors have resistance values that differ from each other by a multiple of two. The switching transistors each have an input terminal for reception of a digital input signal that switches the transistor on. When a transistor is switched on a current is produced that is proportional to the resistance value of the metering resistor in that particular circuit.

The currents are summed in a summing transistor and a summing resistor that are connected in series with the parallel connected circuits. The summing transistor is provided with means for clamping its emitter voltage on the base

thereof. The different currents flowing through the summing transistor and summing resistor produce changes in the voltage across the summing transistor that are compensated by changes in the voltage across the emitter-collector of the



summing transistor, while maintaining constant the voltage across the metering resistors. The voltage across the summing resistor is thereby a function only of the resistance values of the metering resistors.

3,581,304

ANALOG-TO-DIGITAL CYCLIC FORWARD FEED SUCCESSIVE APPROXIMATION CONVERSION EQUIPMENT


Ronald Y. Paradise, Hillsdale; Marvin Masel, W. Englewood; Bob N. Naydan, Oakland, and John D. Brinkman, Pine Brook, all of, N.J., assignors to Singer-General Precision, Inc., Little Falls, N.J.

Filed May 16, 1967, Ser. No. 638,846

Int. Cl. H03k 13/14

U.S. Cl. 340—347

2 Claims



An analog value to be converted to a digital count is first converted into a coarse digital number by applying the analog signal to a ladder network converter which converts the signal into digital form by successive approximation techniques and transfers this digital number to an output register. The value of the number in the register is also reconverted back to analog form by a summing network and subtracted from the original analog signal. The difference between the original and the reconverted values is then amplified by a proper scale factor and again converted to obtain a second digital number in the same converter. The most significant digits of the second digital number are then compared with the corresponding least significant digits of the first number by logic means and the two numbers are then properly consolidated into one number, in a form suitable for use by external equipment, which represents the input analog value with an accuracy higher than that inherent in the analog-to-digital converter being used.

3,581,305

SEQUENTIAL APPROXIMATION PULSE HEIGHT ANALOG-TO-DIGITAL CONVERTER


Donald L. Howlett, Houston, Tex., assignor to Texaco Inc., New York, N.Y.

Filed July 17, 1968, Ser. No. 745,642

Int. Cl. H03k 13/14

U.S. Cl. 340—347

5 Claims



A sequential approximation pulse height analog-to-digital converter including a sample and hold circuit. The converter, including the sample and hold circuit, substantially reduces the "dead time" heretofore required to discharge or step down a capacitor retaining a peak voltage value.

3,581,306

TRIGONOMETRIC ENCODER


Clark E. Johnson, Jr., 60 Pinecroft Road, Weston, Mass.

Continuation-in-part of application Ser. No. 515,895, Dec. 23, 1965, now abandoned. This application Aug. 8, 1969, Ser. No. 848,534

Int. Cl. G08c 9/06

U.S. Cl. 340—347

10 Claims



In a trigonometric encoder for providing a digital indication of a trigonometric function of the angle of rotation of a shaft. A rotatable disc, attached to the shaft, whose rotation is to be measured, has alternate lines of differing flux transmissive ability, which lines are parallel with each other and with the diameter of the disc. There are two sources of flux on one side on the disc and two detectors on the opposite side. Each of the detectors is aligned with its source of flux and is arranged to detect the number of times the lines interrupt the flux from the source during rotation of the disc. The number of detected interruptions along with the number of lines are utilized to provide a trigonometric indication of the angle of rotation of the disc.

3,581,307

DIRECT VIEW HIGH INTENSITY READOUT MODULE HAVING CONICAL LIGHT CONVEYOR TUBE


Jack D. McKim, P. O. Box 149, Del Mar, Calif., and Harold W. Ulmer, 2941 San Luis Rey, Oceanside, Calif.

Filed May 29, 1968, Ser. No. 733,156

Int. Cl. G08b 5/36

U.S. Cl. 340—366

3 Claims



A direct view high intensity readout module primarily designed for seven segment digital readout systems in which seven incandescent bulbs are connected to a different pin of a nine terminal vacuum tube base, one of the terminals being common and one of the terminals preferably being coupled for a period indication. A light conveyor tube surrounds each of the incandescent bulbs on one end, the other end forming a segment of the seven segment numerical readout. A heat sink is in physical contact with each of the seven light conveyor tubes. A nonglare frosted face plate is cemented over the segment end of the light conveyor tubes.

3,581,308

LIGHT GUIDE CHARACTER FORMING MASK AND DISPLAY DEVICE CONTROL ELEMENT


Joseph T. McNaney, 8548 Boulder Drive, La Mesa, Calif.

Filed Apr. 11, 1969, Ser. No. 815,374

Int. Cl. G08b 5/00; G09f 9/30

U.S. Cl. 340—380

7 Claims



The specification discloses a light guide character forming mask assembly, including means for fashioning such assemblies, and means for utilizing the assembly as a character forming and light gate control element in various types of light emitting and light gate display devices.

3,581,309

CLOCK SYNCHRONIZATION WITHOUT ADDRESSING FOR COLLISION AVOIDANCE SYSTEMS

Wayne G. Shear, Pompano Beach, Fla.; Merlin E. Olmstead, Baltimore, Md., and Samuel R. Everett, Fort Lauderdale, Fla., assignors to The Bendix Corporation

Filed Sept. 16, 1968, Ser. No. 759,966

Int. Cl. G01s 9/56


U.S. Cl. 343—6.8

11 Claims

A means of synchronizing clocks without addressing within a cooperative collision avoidance system which utilizes the


time slot of the aircraft requesting synchronization. During its time slot, an aircraft transmitting a collision avoidance message automatically requests clock synchronization. All other aircraft within the collision avoidance network which receive the synchronization request will respond in a random manner with a probability inversely proportional to the number of potential responding aircraft within the collision

frequency output, the two intermediate frequency outputs being mixed to provide a signal dependent only upon the rate



of change of the total path length between the two sites via a target.


3,581,311
LINEARLY POLARIZED MICROWAVE FEED ASSEMBLY FOR PARABOLIC ANTENNAS AND THE LIKE
Alfred Kach, Untersiggenthal, Switzerland, assignor to Patenhold Patentverwertungs & Elektro-Holding AG, Glarus, Switzerland
Filed Nov. 29, 1968, Ser. No. 780,052
Claims priority, application Switzerland, Dec. 1, 1967, 16921
Int. Cl. H01q 19/14
U.S. Cl. 343-781 6 Claims



A first coaxial line, short-circuited at one end and propagating a TEM wave, is surrounded by a concentric sleeve of a length approximately equal to half the operating wave length, to provide a second line with the outer conductor of the first line acting as inner conductor of the second line. The latter has one short-circuited end and an annular radiating aperture at its opposite end. The outer conductor of the first line has a pair of diametrically opposed coupling slots with the intervening segments connected, respectively, inductively and capacitatively with the inner conductor of said first line.

3,581,310
RADAR SYSTEMS
Trevor Buckley, Malvern, England, assignor to Frowds Limited, Teddington, England, a part interest
Filed Apr. 9, 1969, Ser. No. 814,529
Claims priority, application Great Britain, Apr. 24, 1968, 19,399/68
Int. Cl. G01s 9/42
U.S. Cl. 343-7.7 5 Claims

A radar system in which a transmitter and a receiver are located at each of two different sites, the transmitters being operated at different frequencies and some of the power of each transmitter serving as a local oscillator for the receiver which is located on the same site and which receives signals from the other transmitter to provide an intermediate




DESIGNS

MAY 25, 1971


220,792
COMBINED BOTTLE AND STAND THEREFOR
Lee Benson, 5 Horseshoe Lane, Port Chester, N.Y. 10573
Filed Apr. 13, 1970, Ser. No. 22,409
Term of patent 14 years
Int. Cl. D9-01
U.S. Cl. D9-13




220,793
FILM STRIP ADAPTER FOR PHOTOGRAPHIC PROJECTOR
Peter T. Quinn, Littleton, Colo., assignor to Honeywell Inc., Minneapolis, Minn.
Filed June 22, 1970, Ser. No. 23,591
Term of patent 14 years
Int. Cl. D16-04
U.S. Cl. D61-1



220,794
RADIO RECEIVING SET
Eligah R. Rowry, 236 2-chome, Kajino-cho, Koganei-shi, Tokyo, Japan
Filed Nov. 13, 1969, Ser. No. 20,063
Term of patent 14 years
Int. Cl. D14-03
U.S. Cl. D56-4




220,795
SINGLE ELECTRICAL OUTLET
Herbert A. Slater, New York, N.Y., assignor to Slater Electric, Inc., Glen Cove, N.Y.
Filed Apr. 13, 1970, Ser. No. 22,380
Term of patent 14 years
Int. Cl. D13-03
U.S. Cl. D26-1



220,796
EDUCATIONAL DEVICE
Teruo Matsumoto, Tokyo, Japan, assignor to Epoch Company, Ltd., Tokyo, Japan
Filed July 14, 1970, Ser. No. 23,941
Claims priority, application Japan Mar. 30, 1970
Term of patent 14 years
Int. Cl. D19-08
U.S. Cl. D25-1



220,797
TAPE EMBOSING TOOL
William A. Penaluna, Pinole, and Melvin Yee, San Francisco, Calif., assignors to Dymo Industries, Inc., Emeryville, Calif.
Filed Mar. 19, 1970, Ser. No. 21,979
Term of patent 14 years
Int. Cl. D18-99
U.S. Cl. D64-10



**220,798
BOTTLE**

Jacques Leonard, 7 Boulevard Richard Wallace,
Neuilly-sur-Seine, Hauts-de-Seine, France
Filed May 27, 1969, Ser. No. 17,383
Claims priority, application France Nov. 27, 1968
Term of patent 14 years
Int. Cl. D9—01

U.S. Cl. D9—71


**220,799**


PLATE OR SIMILAR ARTICLE
Johann Martin Stangl, Flemington, N.J., assignor to
Stangl Pottery, Trenton, N.J.
Filed Feb. 4, 1970, Ser. No. 21,271
Term of patent 14 years
Int. Cl. D7—01

U.S. Cl. D44—15

**220,800
ICE TRAY**


Johannes Christoffel Krogh, 6 Janie St., Walbutter,
Johannesburg, Transvaal, Republic of South Africa
Filed Apr. 23, 1970, Ser. No. 22,603
Term of patent 14 years
Int. Cl. D15—11

U.S. Cl. D67—3

**220,801
FLASHLIGHT**


Dieter Rams, Koenigstein, Germany, assignor to Braun
Aktiengesellschaft, Frankfurt am Main, Germany
Filed Jan. 15, 1969, Ser. No. 15,368
Claims priority, application Germany July 15, 1968
Term of patent 14 years
Int. Cl. D26—04

U.S. Cl. D48—24

**220,802
WORK BENCH**


James Hedges and Douglas Frank Edwards, Bracknell,
England, assignors to The Barden Corporation (U.K.)
Limited, Bracknell, England
Filed Aug. 29, 1969, Ser. No. 18,928
Claims priority, application Great Britain Mar. 11, 1969
Term of patent 14 years
Int. Cl. D6—01

U.S. Cl. D33—14

**220,803
SALES TERMINAL**

Ronald Segall, Los Angeles, Calif., assignor to Scantlin
Electronics, Inc., Los Angeles, Calif.
Filed Feb. 20, 1970, Ser. No. 21,552
Term of patent 14 years
Int. Cl. D14—02

U.S. Cl. D26—5

**220,804
BUILDING**

Danny W. Evins, Lebanon, Tenn., assignor to Consoli-
dated Oil Company, Inc., Lebanon, Tenn.
Filed Jan. 9, 1970, Ser. No. 20,874
Term of patent 14 years
Int. Cl. D25—04

U.S. Cl. D13—1

**220,805
INHALANT DISPENSER**


John V. Ryden, Summit, N.J., assignor to
Schering Corporation, Bloomfield, N.J.
Filed Dec. 10, 1969, Ser. No. 20,426
Term of patent 14 years
Int. Cl. D24—05

U.S. Cl. D83—1




**220,806
DIFFUSER FOR A LIGHTING FIXTURE**
Richard W. Carroll, Los Angeles, Calif., assignor to
U.S. Industries, Inc., New York, N.Y.
Filed Sept. 4, 1969, Ser. No. 19,017
Term of patent 14 years
Int. Cl. D26—06

U.S. Cl. D48—16

**220,807
REMOTE CONTROL UNIT FOR AN AUTOMATIC
PHONOGRAPH**


Carl W. Sundberg, Bloomfield, Mich., assignor to
Walter E. Heller & Company, Chicago, Ill.
Filed Sept. 4, 1969, Ser. No. 19,008
Term of patent 14 years
Int. Cl. D13—03

U.S. Cl. D26—13




**220,808
TELEVISION RECEIVER ESCUTCHEON**
Richard K. Althaus, Mardian Woods, R.R. 2, Long Grove,
Ill. 60047, and Bernard B. Bluestein, 8816A Dee
Road, Des Plaines, Ill. 60016
Filed May 27, 1969, Ser. No. 17,377
Term of patent 14 years
Int. Cl. D14—03

U.S. Cl. D56—4




**220,809
TOASTER**
Don C. Krammes, Canton, Ohio, assignor to The Hoover
Company, North Canton, Ohio
Filed Mar. 24, 1970, Ser. No. 22,037
Term of patent 14 years
Int. Cl. D7—04

U.S. Cl. D81—10




220,810
MAGNETIC MEASURING TAPE
 Lloyd J. Le Roue, Rte. 2, P.O. Box 2360,
 Wapato, Wash. 98951
 Filed Nov. 24, 1969, Ser. No. 20,254
 Term of patent 14 years
 Int. Cl. D10—08

U.S. Cl. D52—1




220,811
TELEPHONE COUPLER
 Charles Jerabek, Bay Shore, N.Y., assignor to
 Vernitron Corporation, New York, N.Y.
 Filed July 8, 1969, Ser. No. 18,583
 Term of patent 14 years
 Int. Cl. D14—03

U.S. Cl. D26—14




220,812
BILLIARD TABLE OR SIMILAR ARTICLE
 Jeffrey Frank Harrison, Forton, near Preston, England,
 assignor to E. J. Riley Limited, Accrington, England
 Filed Aug. 11, 1969, Ser. No. 18,640
 Claims priority, application Great Britain Dec. 19, 1968
 Term of patent 14 years
 Int. Cl. D21—03

U.S. Cl. D34—3



220,813
ADDING MACHINE
OR THE LIKE
 Carl L. Otto, New York, N.Y., assignor to Litton
 Business Systems, Inc., New York, N.Y.
 Filed Apr. 23, 1970, Ser. No. 22,578
 Term of patent 14 years
 Int. Cl. D18—01

U.S. Cl. D64—11




220,814
ADDING MACHINE
OR THE LIKE
 Carl L. Otto, New York, N.Y., assignor to Litton
 Business Systems, Inc., New York, N.Y.
 Filed Apr. 23, 1970, Ser. No. 22,599
 Term of patent 14 years
 Int. Cl. D18—01

U.S. Cl. D64—11




220,815
TYPEWRITER
 William B. Sklaroff, Narberth, Pa., assignor to Litton
 Business Systems, Inc., New York, N.Y.
 Filed May 4, 1970, Ser. No. 22,789
 Term of patent 14 years
 Int. Cl. D18—02

U.S. Cl. D64—11




220,816
TYPEWRITER
 Joseph L. Morelli, Hartford, Conn., assignor to Litton
 Business Systems, Inc., New York, N.Y.
 Filed Mar. 5, 1970, Ser. No. 21,759
 Term of patent 14 years
 Int. Cl. D18—01

U.S. Cl. D64—11




220,817
REFLEX MEASUREMENT APPARATUS
 Stephens N. Sato, San Diego, Calif., assignor to
 Ivac Corporation, San Diego, Calif.
 Filed Apr. 14, 1970, Ser. No. 22,423
 Term of patent 14 years
 Int. Cl. D24—02; D10—08

U.S. Cl. D83—1




220,818
CASSETTE FOR A SOUND SLIDE PROJECTOR
 William Castedello, Plainville, Conn., assignor to The
 Kalart Company Inc., Plainville, Conn.
 Filed Sept. 30, 1969, Ser. No. 19,347
 Term of patent 14 years
 Int. Cl. D16—99; D14—01

U.S. Cl. D26—14




220,819
LUGGAGE HANDLE
 Joseph N. Laurita, 66—19 Clinton Ave.,
 Maspeth, N.Y. 11378
 Filed May 18, 1970, Ser. No. 23,046
 Term of patent 14 years
 Int. Cl. D8—03

U.S. Cl. D8—154




220,820
ROCKET TOY
 Uwe C. Seefluth, Seestrass, 2409 Klingberg, Germany
 Filed Dec. 29, 1969, Ser. No. 20,672
 Term of patent 14 years
 Int. Cl. D21—02

U.S. Cl. D34—15



220,821
PORTABLE RADIO
 Maurice D. Katz, 35 Broadway, Lawrence, N.Y. 11559
 Filed Dec. 3, 1970, Ser. No. 26,272
 Term of patent 14 years
 Int. Cl. D14—03

U.S. Cl. D56—4



**220,822
JACKET**


Thomas E. De Wan, 9600 N. Lake Drive,
Milwaukee, Wis. 53217
Filed Oct. 6, 1969, Ser. No. 19,439
Term of patent 14 years
Int. Cl. D2—01

U.S. Cl. D2—189

**220,823
CONTOURED PILLOW**


Robert L. Howe and Norma C. Howe, both of 4581 Park-
ridge Road, Sacramento, Calif. 95822
Filed Aug. 4, 1969, Ser. No. 18,525
Term of patent 14 years
Int. Cl. D28—99

U.S. Cl. D83—1

**220,824
COMBINED DATA KEYBOARD ENTRY AND
DISPLAY UNIT**


Gerald M. Adams, Fayetteville, and James H. Frakes, Jr.,
Manlius, N.Y., assignors to SCM Corporation, New
York, N.Y.
Filed May 15, 1970, Ser. No. 22,992
Term of patent 14 years
Int. Cl. D14—02

U.S. Cl. D26—5

**220,825
GAME BOARD**


Frank Kohner, New York, N.Y., and Albert Stubbmann,
Franklin Lakes, N.J., assignors to Kohner Bros., Inc.,
East Paterson, N.J.
Filed May 4, 1970, Ser. No. 22,795
Term of patent 14 years
Int. Cl. D21—01

U.S. Cl. D34—5

**220,826
HAND IRON SAFETY CRADLE**


Raymond R. Vaughn, 6091 Cornell Drive,
Huntington Beach, Calif. 92647
Filed Jan. 6, 1970, Ser. No. 20,775
Term of patent 14 years
Int. Cl. D7—06

U.S. Cl. D49—6

**220,827
SUPPORT FOR A GASOLINE DISPENSER
OR THE LIKE**

Hal C. Hartsell, Jr., Rte. 9, Evergreen Drive, Winston-
Salem, N.C. 27106, and David D. Tompkins, 10350
Olentangy River Road, Worthington, Ohio 43085
Filed Sept. 23, 1969, Ser. No. 19,258
Term of patent 14 years
Int. Cl. D20—99

U.S. Cl. D52—2

**LIST OF PATENTEEES**

TO WHOM

PATENTS WERE ISSUED ON THE 25TH DAY OF MAY, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- Abbott Laboratories: See—
Crites, Nelson A.; and Lyons, Donald H., 3,580,079.
- Abe, Katsuro; Kakinuma, Saburo; and Uno, Masaaki, to Hitachi, Ltd.
Device for controlling pumps for operating hydraulic motors. 3,579,986, Cl. 60-52.
- Abitibi, St. Ann, Paper Ltd.: See—
Hamilton, Douglas D., 3,580,308.
- Abolins, Andrew, to Strick Corporation. Coupling device for container handling system. 3,580,410, Cl. 220-1.5
- Acme Appliance Manufacturing Company: See—
Morgan, Philip R., 3,580,622.
- Adachi, Kazuo: See—
Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
- Adams, Gerald E.: See—
Barnes, Gerald L.; Cichy, Raymond G.; and Adams, Gerald E., 3,580,767.
- Adams, Richard C.; Coombes, William S.; and Lerardo, Domenic, to Schjeldahl, G. T., Company. Multi-purpose punch. 3,580,120, Cl. 83-98.
- Adams, Robert G.: See—
Warren, Robert C.; and Adams, Robert G., 3,580,610.
- Addressograph-Multigraph Corporation: See—
Maul, John A.; Zofchak, James T.; and Anderson, David D., 3,580,169.
- Scholle, Peter T.; and Webb, Samuel L., 3,580,158.
- Seelenbinder, Terrance G., 3,580,677.
- Admiral Corporation: See—
Garrett, Elgie E.; De Franco, Thomas P.; and Staples, Nicholas B., 3,581,135.
- Aerojet-General Corporation: See—
Stevens, Roger L.; Putnam, Peter A.; and Sicon, Martin, 3,581,017.
- Aerovox Corporation: See—
O'Mara, William H.; and Wood, Owen J., 3,579,770.
- AG fur Industrielle Elektronik AGIE: See—
Panschow, Rudolf; Russbucht, Herbert; Suhr, Volker; and Ullmann, Werner, 3,581,045.
- Ullmann, Werner; Tadini, Costantino; and Salim, Ehsan, 3,581,043.
- Agfa-Gevaert Aktiengesellschaft: See—
Ehngelsmann, Dieter; Schroder, Rolf; and Becker, Erwin, 3,580,152.
- Hennig, Fridolin; Kellner, Hans-Jurgen; Potz, Klaus; and Gotze, Christian, 3,580,443.
- Hieber, Fritz; Burger, Erich; and Huber, Hans-Peter, 3,580,675.
- Scholz, Norbert, 3,580,662.
- Agfa-Gevaert Aktiengesellschaft: See—
Zahn, Wolfgang; Nagel, Erlich; and Langer, Reinhold, 3,580,155.
- Aileo, Jackson Anthony, to Gentex Corporation. Protective helmet of adjustable size. 3,579,637, Cl. 2-3.
- Aiwa Co., Ltd.: See—
Masuda, Takeo, 3,581,015.
- Ajinomoto Co., Inc.: See—
Shiio, Isamu; Nakamori, Shigeru; and Sano, Kounosuke, 3,580,810.
- Akahide, Kozo: See—
Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotu, 3,581,039.
- Akermanis, Andreys O. Ladder for fruit picker. 3,580,359, Cl. 182-49.
- Akst, Harold, to Burroughs Corporation. Electrical connection and distribution system. 3,581,268, Cl. 339-18.
- Aktiebolaget Atomenergi: See—
Lofroth, Enar, 3,580,808.
- Aktiebolaget Bofors: See—
Olsson, Tore Bertil Reinhold; and Nilsson, Oake Valentin, 3,581,109.
- Aktiebolaget Electrolux: See—
Kogel, Wilhelm Georg, 3,580,004.
- Aktiebolaget Jonkoping-Vulcan: See—
Eriksson, Birger Sture Erik, 3,580,640.
- Aktiebolaget Stadex: See—
Grundschober, Friedrich; and Sambeth, Joerg, 3,580,218.
- Albertson, Clarence E.; and Krueger, Robert H., to Borg-Warner Corporation. Heat transfer additives for absorbent solutions. 3,580,759, Cl. 252-71.
- Albertson, Orris E.: See—
Logan, Robert P.; and Albertson, Orris E., 3,580,193.
- Alexander, David C., to International Business Machines Corporation. System for dynamically adjusting clipping in editing electrocardiogram waves. 3,581,219, Cl. 328-168.
- Alexander, Donald: See—
Bemiss, Robert P., 3,580,478.
- Alexander, Jerry: See—
Stevens, Irving J.; and Alexander, Jerry, 3,579,831.
- Alfa-Laval AB: See—
Jonsson, Lars-Erik, 3,580,493.
- Schnittger, Jan R.; Nilson, Carl-Goran; and Larsson, Bengt D. R., 3,580,492.
- Alford, Andrew. Directional coupler wherein dielectric media surrounding main line is different from dielectric media surrounding coupled line. 3,581,243, Cl. 333-10.
- Algemene Kunstzijde Unie N.V.: See—
Eshuis, Jannes; and Tjebbes, Horatius, 3,579,765.
- Alkalay, Jorge; and Alkalay, Oton. Container filling device. 3,580,299, Cl. 141-59.
- Alkalay, Oton: See—
Alkalay, Jorge; and Alkalay, Oton, 3,580,299.
- All-Steel Equipment Inc.: See—
Powell, James C., 3,580,122.
- Allen, David T.: See—
Ward, Ronald C.; and Allen, David T., 3,581,011.
- Allen, Howard L.; and De Graff, Charles D., to Hoover Company, The. Motor-pump shaft seal. 3,580,588, Cl. 277-32.
- Allen, Joseph C.; Bednarski, Valery N.; and Hall, Russell W., Jr., to Texaco Inc. Oil recovery by a combination of solution gas drive and water flooding. 3,580,335, Cl. 166-263.
- Allied Chemical Corporation: See—
Cheng, Chao-Shing; and Evans, Francis E., 3,580,857.
- Demler, Walter R.; and Jachlewski, Arthur F., 3,580,919.
- Evans, Francis E.; and Cheng, Chao-Shing, 3,580,858.
- Rosen, Milton K.; and Mason, Charles D., 3,580,898.
- Tyrner, Joseph M., 3,580,111.
- Allina, Stanley F., to Perfection Manufacturing Company, The. Grass catcher assembly. 3,579,966, Cl. 56-202.
- Allison, Robert W., Jr.; Brokloff, Robert W.; and Woodyard, John R., to United States of America, Atomic Energy Commission. Method for producing a chromium activated aluminum oxide scintillator. 3,580,822, Cl. 204-58.
- Alpha Metals Inc.: See—
Boyle, Martin A., 3,579,817.
- Alps Electric Company Limited: See—
Nakagawa, Masaharu, 3,581,237.
- Altman, Norman G., 45% to Lipton, Charles H., and 10% to Ebert, Michael. Palm print identification system. 3,581,282, Cl. 340-149.
- Aluminium Laboratories Limited: See—
Howitt, Fred; and Taylor, Ian, 3,580,747.
- Amann, Karl: See—
Breitmeyer, Richard; and Amann, Karl, 3,581,059.
- Amano, Hiroshi, to Nippon Gakki Seizo Kabushiki Kaisha. Electronic music keyer with touch responsive volume control employing a mechanical-electrical transducer. 3,580,979, Cl. 84-1.1
- Amco International: See—
Terrell, Kyle E.; and Rester, Darryl C., 3,580,341.
- American Can Company: See—
Gerber, Reinhold; Kerrigan, James Edward; and Hawley, Harry Ray, 3,579,737.
- Sarka, Albert J.; and Blake, Trevor H., 3,580,676.
- American Cyanamid Company: See—
Lutz, Albert William, 3,580,913.
- Reddy, Thomas Bradley, 3,580,828.
- American Gage & Machinery Company: See—
Peonski, Edward, 3,579,843.
- American Greetings Corporation: See—
Jordan, Grant H., 3,580,791.
- American Hoist & Derrick Company: See—
Brown, Archer W.; Montgomery, James L.; Beer, Walter A.; and Mero, Thomas J., 3,580,345.
- American Home Products Corporation: See—
Wolf, Milton; and Diebold, James L., 3,580,915.
- American Optical Corporation: See—
Beguin, Fred P.; and Dostourian, Harry, 3,579,640.
- Siegmund, Walter P., 3,580,775.
- American Pulverizer Company: See—
Strom, Sven B., 3,580,518.
- American Standard, Inc.: See—
Mac Kenzie, Douglas James, 3,580,078.
- Martin, George, 3,580,513.
- Amerola Products Corporation: See—
Merola, Anthony, 3,580,576.
- Ameron, Inc.: See—
Pingree, Robert J., 3,580,384.

- AMF Incorporated: *See—*
Gianese, Goffredo, 3,579,953.
Mills, James Claiborne, Jr.; and Hays, Gordon W., 3,579,957.
- Amfahr, Warren U. RF T-pad low impedance coupling circuit attenuator with AGC voltage control. 3,581,210, Cl. 325-411.
- Amoresse, Franklyn J., to Sybron Corporation. Package, liquid flushed, steady bearing assembly. 3,580,547, Cl. 259-23.
- AMP Incorporated: *See—*
Maltais, Frederick Jean, 3,580,619.
- Ampex Corporation: *See—*
Bigg, Geoffrey James; and Heaslett, Alistair Michael, 3,581,176.
Orlowski, Donald W.; and Schroeder, Donald S., 3,580,988.
- Amsted Industries Incorporated: *See—*
Resener, Baird E., 3,580,388.
- Anchor Enterprises Corporation: *See—*
Toth, Louis, 3,579,724.
- Andersen, F. S., ingenior-og maskinforretning I/S: *See—*
Andersen, Ole Stig; and Rathje, Ove, 3,580,694.
- Andersen Laboratories, Incorporated: *See—*
Belford, John F.; Gibeau, Donald E.; and Ciriello, John, 3,581,247.
- Andersen, Ole Stig; and Rathje, Ove, to Andersen, F. S., ingenior-og maskinforretning I/S. Combined fluid impellers and self-sealing closures. 3,580,694, Cl. 416-136.
- Anderson, David D.: *See—*
Maul, John A.; Zofchak, James T.; and Anderson, David D., 3,580,169.
- Anderson, Olavi F.: *See—*
Donadio, Vincent J.; and Anderson, Olavi F., 3,580,031.
- Anderson, Weston A., to Varian Associates. Phase correlation for an RF spectrometer employing an RF carrier modulated by a pseudorandom sequence. 3,581,191, Cl. 324-0.5
- Anderson, William J.: *See—*
Caneer, Ralph A.; Anderson, William J.; Morgan, Bert B.; and Goodman, Jerry M., 3,579,760.
- Andersson, Gustav Mattias; and Granstrom, Ernst Henning Ture, said Granstrom assor. to said Andersson. Pole base providing adjustability for angular axial alignment of the pole. 3,579,936, Cl. 52-297.
- Anderton, Kenneth, to Imperial Chemical Industries Limited. Cyano containing styryl dyestuffs. 3,580,946, Cl. 260-465.
- Ando, Sadanao, to Kabushiki Kaisha Ricoh. Electrostatic photocopying apparatus. 3,580,672, Cl. 355-3.
- Andreas, Ehrhardt, to Hazemag Hartzerkleinerungs- und Zementmaschinenbau-Gesellschaft, m.b.H. Process for dressing asbestos ore waste. 3,580,537, Cl. 251-4.
- Andreassian, Jean-Michel, to Compagnie du Filage des Metaux et des Joints Curt. Extrusion mandrel and method. 3,580,038, Cl. 72-264.
- Andreis, Pio, to Societa Italiana Telecomunicazioni Siemens S.p.A. Flange for electromagnetic coil. 3,581,260, Cl. 336-192.
- Angele, Henry, to Etablissements Valois. Aerosol containers. 3,580,430, Cl. 222-394.
- Angliker, Hans-Joerg, to Ciba Limited. Water-insoluble monoazo dyestuffs. 3,580,902, Cl. 260-207.
- Anliker, Rudolf; Duennenberger, Max; Schmid, Karl; and Siegrist, Adolf Emil, to Ciba Limited. 2-Biphenylbenzoxazoles. 3,580,924, Cl. 260-307.
- Anzai, Shiro: *See—*
Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, 3,580,895.
- Apotheloz, Robert; Bigler, Hans-Ulrich; and Kessler, Rene, to Werkzeugmaschinenfabrik Oerlikon-Buhrle AG. Projectile with hollow explosive charge. 3,580,174, Cl. 102-56.
- Apparel Research Foundation, Inc.: *See—*
Bonton, Ira D.; and Sylvester, Willard G., 3,580,564.
- Aqua-Marine Manufacturing Limited: *See—*
Magi, Hugo; and Smith, John, 3,581,079.
- Aquair Corporation Limited: *See—*
Sloan, Frank Philip, 3,579,650.
- Araki, Shigeru; Takahashi, Shozo; and Muto, Ichiro, to Matsushita Electric Industrial Co., Ltd. High thrust bearing apparatus. 3,580,649, Cl. 308-233.
- Arbuckle, Timothy, to Computer Modem Corporation. Signal transmission method and system. 3,581,279, Cl. 340-146.1
- Ariens Company: *See—*
Mollen, Ignatius J., 3,580,351.
- Arkus-Duntov, Zora, to General Motors Corporation. Vehicle power unit and drive train. 3,580,350, Cl. 180-44.
- Arlt, Dieter, to Farbenfabriken Bayer Aktiengesellschaft. Chlorosulphonyl-tert.-butylisocyanate and its preparation. 3,580,942, Cl. 260-453.
- Armstrong Cork Company: *See—*
Heinzelman, Earl E., 3,579,732.
Spencer, Virgil, 3,580,516.
- Armstrong, George: *See—*
Gossling, Robert C.; and Armstrong, George, 3,580,323.
- Armstrong, Merritt S., to HC Electronics, Inc. Fast response dynamic gain control circuit. 3,581,223, Cl. 330-29.
- Arndt, John P.; and Franklin, Edmond G., to Clevite Corporation, mesne. Oscillator circuit for ultrasonic apparatus. 3,581,125, Cl. 310-8.1
- Arnold, Richard B., to General Electric Company. Coil developing apparatus. 3,579,791, Cl. 29-205.
- Arnold, Richard B.; and Smith, Dallas F., to General Electric Company. Method and apparatus for forming shaped insulators and for developing coils of a magnetic core. 3,579,818, Cl. 29-596.
- Arnott, Edward G. F.; and Lewis, Daniel W., to Westinghouse Electric Corporation. Electric lamp having an envelope composed of photoresistant soda-lime silicate glass. 3,581,137, Cl. 313-109.
- Arnould, Marcel M.; Ward, John C., Jr.; Ray, William Floyd; and Budzyn, Boleslaw L., to Penstar Industries, Inc. Portable elevator for tobacco sticks. 3,580,386, Cl. 198-131.
- Aro Corporation, The: *See—*
Brandenberg, Karl A., 3,580,137.
Brandenberg, Karl A., 3,580,266.
Brandenberg, Karl A., 3,580,285.
- Aronovitz, Manuel. Bath and shower seat. 3,579,668, Cl. 4-185.
- Arrow-Hart, Inc.: *See—*
Christensen, Paul M., 3,581,032.
- Arsdale, Lyle R. Van; and Lathrop, Francis M., II, to M&J Valve Company. Valve operating system. 3,580,282, Cl. 137-608.
- Arvidson, Paul W.; Park, William G.; and Williams, Keith S., to United States of America, Army. Bullet trap attachment for machine guns. 3,580,130, Cl. 89-31.
- Asada, Takeo; and Kamiya, Toshihiro, to Omron Tateisi Electronics Co. Apparatus for checking a ticket. 3,580,121, Cl. 83-107.
- Asahi Kasei Kogyo Kabushiki Kaisha: *See—*
Shimodori, Yutaka; Ootake, Heiichi; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, 3,580,735.
- Asai, Hiromi: *See—*
Tsujihata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuha, Zensaku, 3,581,070.
- Asano, Setunobu: *See—*
Kuraishi, Michio; Asano, Setunobu; and Isogai, Nobuo, 3,580,968.
- Ashenfelter, Richard J.: *See—*
Kenney, James E.; and Ashenfelter, Richard J., 3,580,175.
- Asmuth, James E., to Wisconsin Tissue Mills. Table cover. 3,580,797, Cl. 161-126.
- Assmus, Friedrich: *See—*
Ganter, Wolfgang; and Assmus, Friedrich, 3,581,129.
- Aston, Keith, to Pavelle Corporation, The. Electronic thermostat. 3,581,062, Cl. 219-501.
- Astro Controls, Inc.: *See—*
Korbilas, Christ P.; and Smith, Raymond W., 3,580,276.
- Atkinson, Ross T. Cable-suspended roof structure. 3,579,932, Cl. 52-83.
- Atlantic Richfield Company: *See—*
Moyer, Hallard C.; and Fauber, Eugene M., 3,580,736.
Shalit, Harold, 3,580,823.
- Atlantic Wool Combing Co.: *See—*
Menzies, William C., Jr., 3,579,744.
- Atlas Copco Aktiebolag: *See—*
Bertilsson, Alf Georg, 3,580,435.
Tegholm, Ruben, 3,581,194.
- Atwater-Forbes Corporation: *See—*
Soriano, Charles A., 3,579,837.
- Aurich, Christoph W.: *See—*
Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., 3,579,761.
- Aurich, Peter F.: *See—*
Schuette, Thomas L.; Straub, Melvin J.; Dumas, Pierre; and Aurich, Peter F., 3,579,771.
- Ausnit, Steven. Apparatus for making a web having integral interlocking rib and groove portions. 3,579,730, Cl. 18-12.
- Austin, Eric R.; and Bill, Eric G., to B.S.A. Tools Limited. Presettable tool arrangements for machine tools. 3,580,129, Cl. 82-2.
- Automated Handling Systems, Inc.: *See—*
Nearman, Richard E., 3,580,183.
- Automated Packaging Corporation: *See—*
Lerner, Bernard, 3,579,948.
- Automatic Feed Company: *See—*
Cramer, Donald L.; and Limpach, Paul D., 3,580,021.
- Autophon Aktiengesellschaft: *See—*
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
- Autotelic Industries Limited: *See—*
Speeth, Sheridan D., 3,580,575.
- Autotrol Corporation: *See—*
Posser, David G., 3,580,615.
- Avesta Jernverks Aktiebolag: *See—*
Bjorkroth, Jarl Allan, 3,581,054.
- Aviation Instrument Manufacturing Corporation: *See—*
Winter, John W.; and Harrison, Guy K., Jr., 3,579,847.
- Ayerst, McKenna & Harrison, Ltd.: *See—*
Laliberte, Real, 3,580,945.
- Ayres, Waldemar A., to Becton, Dickinson and Company. Method of thermometer pointing and apparatus therefor. 3,579,838, Cl. 33-19.
- Ayuh, Zensaku: *See—*
Tsujihata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuha, Zensaku, 3,581,070.
- Baader, Herbert; and Sennewald, Kurt, to Knapsack Aktiengesellschaft. Process for the production of acetylene. 3,580,958, Cl. 260-679.
- Babcock & Wilcox Company, The: *See—*
Grams, Richard A., 3,579,990.
- Babcock, John C.: *See—*
Campbell, J. Allen; and Babcock, John C., 3,580,937.
- Babst, Dean V. Fish catching apparatus with snap actuatable hooks. 3,579,897, Cl. 43-35.

- Badinter, Efim Yakovlevich; Zelikovsky, Zinoviy Ieremeevich; and Lazurevskaya, Irina Georgievna. Safety fuse with glass coating on fusible portion. 3,581,262, Cl. 337-159.
- Badische Anilin- & Soda-Fabrik Aktiengesellschaft: *See—*
Fuerst, Ernst; and Weitz, Hans-Martin, 3,580,839.
- Bafford, Richard Anthony, to Pennwalt Corporation. Auto-oxidation of aldehydes in the presence of acylating agents. 3,580,955, Cl. 260-610.
- Baker, Edward D., to National Industrial Manufacturing. Hamburger cooking machine. 3,580,164, Cl. 99-339.
- Baker Oil Tools, Inc.: *See—*
Dean, Michael R.; Castro, Luis F.; and Salerni, John V., 3,580,332.
- Baker, Ralph J. Condensate valve. 3,580,267, Cl. 137-203.
- Balchin, Nigel C.: *See—*
Brown, Kenneth William; and Balchin, Nigel C., 3,581,050.
- Baldwin, D. H., Company: *See—*
Utrecht, Dale M., 3,580,980.
- Baldwin-Lima-Hamilton Corporation: *See—*
Tidball, Robert A.; King, William M.; Bosley, Dewey R.; and Jennings, Charles M., 3,580,816.
- Balfanz, Glenn F., Jr. Weld box for tube forming mill. 3,581,041, Cl. 219-60.
- Ballard, Francis J., Jr., to Brown & Williamson Tobacco Corporation. Pneumatic feed system for uniform supply of tobacco to cigarette making machines. 3,580,644, Cl. 302-59.
- Ballard, Gary W., to Carrier Corporation. Absorption refrigeration machine with generator level control. 3,580,013, Cl. 62-148.
- Balle, Walter; and Pommer, Gunter, to Leonhard Herbert Maschinenfabrik. Tire vulcanising press. 3,579,736, Cl. 18-17.
- Ballen, Sue. Set a table puzzle. 3,579,862, Cl. 35-8.
- Balm Paints Limited: *See—*
Clarke, Michael Raymond; and Filipowicz, Leon, 3,580,880.
- Balteau Electric Corporation: *See—*
Webb, Thomas Alan; and Harvey, Jay A., 3,580,997.
- Baltimore and Ohio Railroad Company, The: *See—*
Payseure, Lawrence A., 3,581,071.
- Balzer, Jerry L., to Hoover Company, The. Suction cleaner nozzle adjustment. 3,579,699, Cl. 15-361.
- Bang, Mogens W., to Stackpole Carbon Company. Apparatus for making stators for rotary electric switches. 3,579,743, Cl. 18-36.
- Banister, Ronald A.: *See—*
Wrabetz, Voyta E.; and Banister, Ronald A., 3,580,102.
- Banks, Peter Baldwin, to English Electric Valve Company Limited. Glass treatment with discrete areas. 3,580,709, Cl. 65-30.
- Banning, Thomas A., Jr. Subscription television system utilizing a transmission line for conducting each aesthetic quality television program. 3,580,989, Cl. 178-5.1
- Bar-On, Ari; and Emslie, Norman M., to Philco-Ford Corporation. Radial runout recorder. 3,580,064, Cl. 73-146.
- Barabashkin, Vladimir Pavlovich: *See—*
Zayats, Iosif Lvovich; Barabashkin, Vladimir Pavlovich; Matveev, Boris Nikolaevich; and Shevakin, Yuri Fedorovich, 3,580,036.
- Baranov, Boris Konstantinovich; and Stromin, Boris Alexandrovich. Device for control of a rectifier motor. 3,581,171, Cl. 318-227.
- Barber, Donald E., to Bucyrus-Erie Company. Automatic torque control for a dual stator motor. 3,581,170, Cl. 318-214.
- Barber-Greene Company: *See—*
Smith, Fred T., 3,580,407.
- Barclays Bank Limited: *See—*
Bell, John, 3,580,205.
- Barden, Wayne A.: *See—*
Rozema, Arthur L.; Brady, Lynn J.; and Barden, Wayne A., 3,579,819.
- Bardsley, Donald E.: *See—*
Vore, Herbert G.; and Bardsley, Donald E., 3,579,726.
- Barker, Layle B., to Reynolds Metals Company. Swimming pool structure. 3,579,665, Cl. 4-172.19
- Barmag Barmer Maschinenfabrik Aktiengesellschaft: *See—*
Bauer, Karl; and Turk, Herbert, 3,581,060.
- Barnard, Walter C.; and Hodapp, Donald C., to Whirlpool Corporation. Ice maker with water distributor. 3,580,008, Cl. 62-347.
- Barnes Engineering Company: *See—*
Pearsall, Denton; and Jankowitz, Gerald, 3,581,092.
- Barnes, Gerald L.; Cichy, Raymond G.; and Adams, Gerald E., to Uniroyal, Inc. Method of making a toothed drive belt with an abrasion resistant urethane coating on the transmission surface. 3,580,767, Cl. 156-138.
- Barney, Arthur Livingston; and Honsberg, Wolfgang, to Du Pont de Nemours, E. I., and Company. Vulcanization accelerators of polycyclic ethers for fluorinated polymers. 3,580,889, Cl. 260-47.
- Barney, Ronald N.: *See—*
Herbert, David B.; and Barney, Ronald N., 3,580,322.
- Barnhard, Philip, IV, to Du Pont de Nemours, E. I., and Company. Process for preparation of pentolite. 3,580,754, Cl. 149-93.
- Barrett, George M. Pressure intensifier. 3,579,985, Cl. 60-52.
- Barrett, Sonja I. Ultraviolet fluorescent analyzer for monitoring of oil in discharge ballast. 3,581,085, Cl. 250-43.5
- Barsby, Alan, to Marshall Sons & Company Limited. Air heater. 3,580,237, Cl. 126-110.
- Bartik, William J., to Sperry Rand Corporation. Tuned plated wire content addressable memory. 3,581,294, Cl. 340-174.
- Bash, Sidney D., to Stewart-Warner Corporation. Spool valve. 3,580,286, Cl. 137-625.68
- Bassett, Ernest D. Collating machine feeding into or out of racks. 3,580,563, Cl. 270-58.
- Bates, Tex., to Finn Industries, Inc., The. Carton sealing apparatus with rotation control. 3,579,954, Cl. 53-76.
- Batista, Roy I.: *See—*
Hagan, Melvin A.; and Batista, Roy I., 3,579,808.
- Batlas, George X., 1/4 to Longo, Vincent, 1/4 to Pearl, Curtis F., and 1/4 to Genantonio, Anthony. All-direction atomizers. 3,580,510, Cl. 239-327.
- Battelle Development Corporation: *See—*
Leith, Emmett N.; and Upitnieks, Juris, 3,580,655.
- Battelle Development Corporation, The: *See—*
Ramseier, Serge, 3,580,089.
- Battelle Memorial Institute: *See—*
Bouladon, Gabriel; and Zuppiger, Paul, 3,580,182.
- Bauer & Associates, Inc.: *See—*
Milton, Rex W., 3,581,052.
- Bauer, Karl; and Turk, Herbert, to Barmag Barmer Maschinenfabrik Aktiengesellschaft. Temperature control device in a heated gallette. 3,581,060, Cl. 219-469.
- Bauer, Peter; and Mentzer, William R., Jr., to Bowles Fluidics Corporation. Fluidic slip-resolver system. 3,580,499, Cl. 235-201.
- Bauerlein, Carl C., to Eaton Yale & Towne, Inc. Belt driven ice maker. 3,580,007, Cl. 62-345.
- Bauger, Louis: *See—*
Caruel, Jacques Emile Jules; Quillevere, Herve Alain; and Bauger, Louis, 3,579,983.
- Bauknechte GEA Electrotechnische Fabriken Gesellschaft mit beschränkter Haftung: *See—*
Breitmeyer, Richard; and Amann, Karl, 3,581,059.
- Baumann, Ludwig. Bubble bath device. 3,579,659, Cl. 4-180.
- Baunach, Waldemar: *See—*
Schunck, Kurt; and Baunach, Waldemar, 3,580,674.
- Bausch & Lomb Incorporated: *See—*
Clark, James A., 3,580,088.
- Bavor, Gordon F.: *See—*
Peyser, Leonard F.; and Bavor, Gordon F., 3,581,094.
- BBA Group Limited: *See—*
Kirkby, Donald, 3,581,168.
- Beamer, John D., to Rain Bird Sprinkler Mfg. Corporation. Drive mechanism for large volume rotary sprinklers. 3,580,507, Cl. 239-233.
- Bean, Dennis P.; and Parks, John C., to Solatron Enterprises, Co. Coil former. 3,580,030, Cl. 72-130.
- Beattie, John O. Apparatus for casting and thermally curing plastic sheets. 3,579,738, Cl. 18-26.
- Beatty, Robert D., Jr.; and Griffiths, Thomas C., to Eaton Yale & Towne, Inc. Tire inflation monitoring system. 3,581,277, Cl. 340-58.
- Beaubier, Richard C., to Ethyl Corporation. Surface gap spark plug. 3,581,141, Cl. 313-130.
- Beaudoin, Norman R.; and Lauben, Robert W., to General Electric Company. Armature-contact rod connection for current-limiting breaker. 3,581,253, Cl. 335-16.
- Beaunit Corporation: *See—*
Dessauer, Hans J., 3,579,961.
- Beausoleil, William F., to International Business Machines Corporation. Module switching apparatus with status sensing and dynamic sharing of modules. 3,581,286, Cl. 340-172.5
- Becker, Erwin: *See—*
Ehngelsmann, Dieter; Schroder, Rolf; and Becker, Erwin, 3,580,152.
- Beckman Instruments, Inc.: *See—*
Watanabe, Hideo; and Leonard, John E., 3,580,239.
- Beckwith, Robert C.: *See—*
Hecker, Robert W., Jr.; and Beckwith, Robert C., 3,579,696.
- Becton, Dickinson and Company: *See—*
Ayres, Waldemar A., 3,579,838.
Stawski, Theodore H., 3,580,472.
- Bednarski, Valery N.: *See—*
Allen, Joseph C.; Bednarski, Valery N.; and Hall, Russell W., Jr., 3,580,335.
- Beeler, Robert S., to Eastman Kodak Company. Film-sound synchronizing system. 3,580,669, Cl. 353-15.
- Beer, Walter A.: *See—*
Brown, Archer W.; Montgomery, James L.; Beer, Walter A.; and Mero, Thomas J., 3,580,345.
- Beggs, James E., to General Electric Company. Metal clad insulated electrical heater. 3,581,144, Cl. 313-340.
- Beguine, Fred P.; and Dostourian, Harry, to American Optical Corporation. Hearing protector headsets. 3,579,640, Cl. 2-209.
- Behar, Isaac, to Trefleries & Cableries de Bourg et du Havre. Process for the modification of the mechanical characteristics of carbon steel wire. 3,580,746, Cl. 148-12.
- Behnke, Edward: *See—*
Kron, Harold O.; Liu, John K.; and Behnke, Edward, 3,580,371.
- Behnke, John M., to Bristol-Myers Company. Polishing composition. 3,580,875, Cl. 260-23.
- Behr, Michael I.; Coon, Lewis B., Jr.; and Bickel, Charles E., to Burroughs Corporation. Binary data handling system. 3,581,297, Cl. 340-174.1
- Belcastro, Richard J., to GTE Automatic Electric Laboratories, Incorporated. Apparatus for evaluating signals read from magnetic medium. 3,581,110, Cl. 307-237.

- Belford, John F.; Gibeau, Donald E.; and Ciriello, John, to Andersen Laboratories, Incorporated. Delay lines having nondispersive width-shear mode propagation characteristics and method of making same. 3,581,247, Cl. 333-30.
- Bell & Howell Company: *See—*
- Cooper, Dester P., Jr., 3,580,661.
- Gish, David B., 3,581,105.
- Bell, Allan J.; and Stone, Roger B. Frequency modulation signal demodulator. 3,581,220, Cl. 329-126.
- Bell, Bella: *See—*
- Bell, John, 3,580,205.
- Bell, John, deceased (by Barclays Bank Limited) Bell, Bella; executors), to Muirhead Limited. Ship stabilizers. 3,580,205, Cl. 114-125.
- Bell, Robert P., Jr.: *See—*
- Carter, Ernest P.; Bell, Robert P., Jr.; and Carroll, Alton P., Jr., 3,580,296.
- Bell Telephone Laboratories, Incorporated: *See—*
- Boyle, Willard S.; and Morton, Jack A., 3,581,151.
- Frey, Dean R.; Hone, George L.; and Ramsey, Edward L., Jr., 3,581,269.
- Gaunt, Wilmer B., Jr., 3,581,122.
- Gressitt, Tillman J., 3,579,823.
- Kretzmer, Ernest R., 3,581,111.
- Mounts, Frank W., 3,580,999.
- Robertson, George H., 3,581,078.
- Smith, Peter W., 3,581,228.
- Bellart, Jean-Pierre B., to Societe Anonyme Poclair. Earthworking machine. 3,580,406, Cl. 214-137.
- Bellasio, Elvio: *See—*
- Cavalleri, Bruno; Bellasio, Elvio; and Testa, Emilio, 3,580,932.
- Bemiss, Robert P., 1/2 to Alexander, Donald. Packaging. 3,580,478, Cl. 229-43.
- Ben Bassett, Marvin, to Technicolor, Inc. Method for removing film from a film cartridge. 3,580,665, Cl. 352-78.
- Bender, Carl M.: *See—*
- Hogue, Dean M.; and Bender, Carl M., 3,580,343.
- Bender, Charles E.; and Fraser, Douglas S., to Cenco Medical/Health Supply Corporation, mesne. Fermenter having a magnetically driven agitator. 3,580,812, Cl. 195-143.
- Bendix Corporation, The: *See—*
- Strack, Richard R., 3,580,082.
- Bendix Corporation, The: *See—*
- Shear, Wayne G.; Everett, Samuel R.; and Olmstead, Merlin E., 3,581,309.
- Bendix-Westinghouse Automotive Air Brake Company: *See—*
- Ternent, George E., 3,580,646.
- Benham, Ralph E., to Purex Corporation, Ltd. Irrigation control apparatus. 3,580,504, Cl. 239-70.
- Bennett Enterprises, Inc.: *See—*
- Bennett, Lewis D., 3,580,278.
- Bennett, George K.; and Buchanan, Richard G., to Psychological Corporation, The. Test administering apparatus. 3,579,870, Cl. 35-48.
- Bennett, Lewis D., to Bennett Enterprises, Inc. Fluid actuated transmission control. 3,580,278, Cl. 137-554.
- Bentov, Itzhak E., to Medi-Tech Incorporated. Anatomical model. 3,579,858, Cl. 35-17.
- Bentz, Francis: *See—*
- Engelhard, Helmut; Bentz, Francis; Rinkler, Heinrich; and Nischk, Gunther, 3,580,966.
- Berardinelli, Frank M.: *See—*
- McAndrew, Francis B.; Price, Martin B.; and Berardinelli, Frank M., 3,580,928.
- Beresnev, Boris Ivanovich; Bulychev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich. Method of manufacturing rod, shaped and tubular products from difficult-to-work metals and alloys, preferably high melting-point and chemically active ones. 3,580,019, Cl. 72-47.
- Berliner Maschinenbau AG vorm. L. Schwartzkopff: *See—*
- Trinks, Walter; Netzer, Theodor Karl; Victoria, Hans T.; Saurer, Hermann; and von Paulgerg, Heinrich, 3,580,048.
- Berman, Leon, to C. I. T. Compagnie Industrielle des Telecommunications. High stability oscillator. 3,581,236, Cl. 331-116.
- Bernard, Georges M.: *See—*
- Pelenc, Yves J.; and Bernard, Georges M., 3,581,202.
- Bernardin, Leo J., to Kimberly-Clark Corporation. Sanitary napkin and flushable wrapper therefor. 3,580,253, Cl. 128-290.
- Bernasek, Edward; and Eaton, Calley Neil, to Reynolds, R. J., Tobacco Company, Starch levulinates. 3,580,906, Cl. 260-233.5
- Berryman, Charles O.: *See—*
- Chute, Richard; and Berryman, Charles O., 3,580,603.
- Bersworth, Frederick C. Chelating compositions based on chelating acids and amines. 3,580,950, Cl. 260-534.
- Bertelli, Guido: *See—*
- Torti, Luigi; and Bertelli, Guido, 3,580,800.
- Berthiez, Charles William. Balance compensating device. 3,580,133, Cl. 90-11.
- Bertilsson, Alf Georg, to Atlas Copco Aktiebolag. Spray gun with pressure operated valve. 3,580,435, Cl. 222-504.
- Bertin & Cie: *See—*
- Bertin, Jean Henri; and Croix-Marie, Francis Marie Jean, 3,580,181.
- Bertin, Jean Henri; and Croix-Marie, Francis Marie Jean, to Bertin & Cie. Surface-effect transport support systems. 3,580,181, Cl. 104-23.
- Besora, Juan E. Juice extractor. 3,580,314, Cl. 146-3.
- Besson, Rene; and Chopard, Remy, to Ebauches S.A. Flexure-type symmetrical oscillator. 3,579,975, Cl. 58-23.
- Bethlehem Steel Corporation: *See—*
- Merrill, Neal W.; and Nippert, Charles R., 3,580,023.
- Roscoe, John D., 3,580,556.
- Bexford Limited: *See—*
- Clachan, Margaret L.; McGrail, Patrick T.; and Shephard, Basil R., 3,580,734.
- Beyl, Jean Joseph Alfred. Heel downholder for safety ski bindings. 3,580,597, Cl. 280-11.
- Bhagat, Gopal C., to Xerox Corporation. Apparatus for duplexing. 3,580,670, Cl. 355-3.
- Bialkowski, Ludwik S., to Goodrich, B. F., Company, The. Automatic adjustment mechanism particularly for brakes. 3,580,365, Cl. 188-196.
- Bianca, Dominick, to Du Pont de Nemours, E. I., and Company. Non-yellowing polyurethane. 3,580,873, Cl. 260-18.
- Biancamaria, Joseph, to L'homme (Societe Anonyme). Method of making accurately dimensioned smooth-surface multi-layer cardboard tubes. 3,580,146, Cl. 93-94.
- Bickel, Charles E.: *See—*
- Behr, Michael I.; Coon, Lewis B., Jr.; and Bickel, Charles E., 3,581,297.
- Bickford, John H., to Veeder Industries Inc. Fluid dispensing apparatus indicator system. 3,580,421, Cl. 222-27.
- Big Drum, Inc.: *See—*
- Lutsey, Thomas H., 3,580,188.
- Bigg, Geoffrey James; and Heaslett, Alistair Michael, to Ampex Corporation. System for driving electric motors. 3,581,176, Cl. 318-327.
- Bigler, Hans-Ulrich: *See—*
- Apotheloz, Robert; Bigler, Hans-Ulrich; and Kessler, Rene, 3,580,174.
- Bill, Eric G.: *See—*
- Austin, Eric R.; and Bill, Eric G., 3,580,129.
- Billawala, Shahbuddin A., to Burroughs Corporation. Support device for magnetic head. 3,581,298, Cl. 340-174.1
- Billenstein, Siegfried: *See—*
- Geymayer, Peter; Billenstein, Siegfried; and Renz, Werner, 3,580,849.
- Bindernagel, Ali; Kost, Erwin; and Staat, Karl-Hans, to Kocks, Friedrich, Firma. Apparatus for calibrating pipes. 3,580,020, Cl. 72-58.
- Bini, Giancarlo; and Tamoni, Gianfranco, to Carlo Gavazzi S.p.A. Regulating valve for water mixing in air conditioning systems. 3,580,284, Cl. 137-625.18
- Bio-Medical Sciences, Inc.: *See—*
- Weinstein, Berel, 3,580,241.
- Birchall, William R.: *See—*
- Watson, Lloyd M.; and Birchall, William R., 3,580,862.
- Bissell, D. L.: *See—*
- Wilhelm, D. F.; Miller, Peter S.; Bissell, D. L.; and Lambroff, George M., 3,581,289.
- Bjorkroth, Jarl Allan, to Avesta Jernverks Aktiebolag. Welding electrode. 3,581,054, Cl. 219-146.
- Blachez, Loic: *See—*
- de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignet, Paul, 3,580,818.
- Black Clawson Company, The: *See—*
- Zink, Stanley C.; and Slane, Joseph J., 3,580,648.
- Blackburn, Samuel S., Jr.; and Rickard, Earl K., to Combustion Engineering, Inc. Steam generator using gas recirculation. 3,580,226, Cl. 122-235.
- Blackburn, William A.: *See—*
- Criner, Gaspard X.; and Blackburn, William A., 3,580,763.
- Blackman, Seymour N. Clinical thermometer storage and sterilizing apparatus. 3,580,077, Cl. 73-343.
- Blais, Zoel W.; and Shaw, Harold F., to Thayer, Inc. Infant's safety car bed. 3,579,674, Cl. 5-94.
- Blake, Trevor H.: *See—*
- Sarka, Albert J.; and Blake, Trevor H., 3,580,676.
- Blakeslee, A. Eugene; Gukelberger, Thomas F., Jr.; and Lyons, Vincent J., to International Business Machines Corporation. Method of growing single crystals. 3,580,732, Cl. 117-106.
- Blankenhorn, Gerhard; and Muller, Gunter. Slinger apparatus for lining the interior of a vessel. 3,579,755, Cl. 25-1.
- Blaser, Wayne W.: *See—*
- Mandrell, Melford E.; and Blaser, Wayne W., 3,580,067.
- Blazon, Inc.: *See—*
- Green, Martin, 3,580,571.
- Blevins, William V., to United States of America, Army. Method for leak testing masks. 3,580,051, Cl. 73-40.
- Bliss, E. W., Company: *See—*
- Helrigel, Robert A.; Brownell, James R.; Ward, Roderick K.; and Keithley, Harry E., 3,580,558.
- Blitz, Saul: *See—*
- Hansen, Benth Preben; and Blitz, Saul, 3,579,725.
- Bloch, Herman S., to Universal Oil Products Company. Hydroxylation of aromatic compounds. 3,580,956, Cl. 260-621.
- Bloch, Herman S., to Universal Oil Products Company. Preparation of tetrafluoroethylene ethylenes. 3,580,957, Cl. 260-653.5

- Bloomer, Milton D., to General Electric Company. Bias and temperature compensating circuit for tunnel diode oscillators. 3,581,234, Cl. 331-107.
- Bloomer-Fiske, Inc.: *See—*
- Foldenauer, Ralph M., 3,580,165.
- Blosse, Jean Charles Joseph; and Blosse, Michel Jean Joseph. Mechanically-actuated warning device. 3,580,217, Cl. 116-169.
- Blosse, Michel Jean Joseph: *See—*
- Blosse, Jean Charles Joseph; and Blosse, Michel Jean Joseph, 3,580,217.
- Blumenschein, Gordon L. Pail having mop wringing grill. 3,579,705, Cl. 15-260.
- Bobo, Donald J. Rock polishing rumble. 3,579,921, Cl. 51-164.
- Bock, Gerhard; Riccius, Rolf; Weitkamp, Gunter; and Wolf, Bernhard, to Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung fruher 'Weser' Flugzeugbau/ Fock-Wulf Heinkel-Flugzeugbau Hunefeldstrasse. Retractable main carriage for vertically staring airplanes and airplanes starting on a short runway. 3,580,531, Cl. 244-102.
- Bock, John T. Tilttable drummer's seat. 3,580,634, Cl. 297-313.
- Bodenhoff, Max, A/S: *See—*
- Nielsen, Erik Christian Valeur, 3,580,652.
- Bodine, Albert G. Sonic energy in machining operations. 3,580,136, Cl. 90-64.
- Bodnarjuk, Frizian Nikolaevich; and Korshunov, Mikhail Alexeevich, to Nauchno-Issledovatel'skiy Institut Monomero Dlya Sinteticheskogo. Method for the preparation of aminoalkyl fumarates. 3,580,918, Cl. 260-294.3
- Boehmer, Matthew A.; and Maxwell, Jerrold F. Hydraulic fluid. 3,580,847, Cl. 252-75.
- Boehringer Mannheim Gesellschaft mit beschränkter Haftung: *See—*
- Thiel, Max; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,907.
- Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,910.
- Boeing Company, The: *See—*
- Lancashire, Thomas, 3,580,403.
- Boettcher, Stephen A.; and Simonetti, Louis F., to Speedfam Corporation. Polishing machine. 3,579,916, Cl. 51-131.
- Boettcher, Stephen A.; and Simonetti, Louis F., to Speedfam Corporation. Polishing machine. 3,579,917, Cl. 51-131.
- Bohme, H. O., Inc.: *See—*
- Sedley, Bruce S., 3,581,030.
- Boissin, Jean-Claude: *See—*
- Thibault, Jean-Jacques; and Boissin, Jean-Claude, 3,579,998.
- Bokros, Jack C., to Gulf Energy & Environmental Systems, Inc. Cardiac valve occluder having a density approximately equal to blood. 3,579,645, Cl. 3-1.
- Bond, Harry Laurence Fred; Stubbs, Dennis; and Maltby, Todwick, to Davy and United Engineering Company, Limited. Rolling mills. 3,580,035, Cl. 72-243.
- Bondarenko, Alexandr Andreevich; and Klevanov, Fedor Grigorievich. Winding pitch changer of a stator-winding machine. 3,580,090, Cl. 74-96.
- Bongers, Piet Frans; and Zanmarchi, Giulio, to U.S. Philips Corporation, mesne. Transmission element for magneto-optical applications, particularly for the modulation of infrared radiation in the wavelength range between 1 and 20 microns. 3,580,664, Cl. 350-320.
- Bonner, Barrie: *See—*
- Tilly, Lorenz; and Bonner, Barrie, 3,580,041.
- Bonton, Ira D.; and Sylvester, Willard G., to Apparel Research Foundation, Inc., mesne. Feeding apparatus for nonrigid sheet. 3,580,564, Cl. 271-33.
- Boot, Herbert W.; Parr, Leslie R.; and Fudger, Shirley L. W., to USM Corporation. Shoe supports. 3,579,695, Cl. 12-127.
- Booth, Edwin F. Attachment for a tined fork. 3,580,625, Cl. 294-59.
- Borden, Inc.: *See—*
- Davis, Glenn V., 3,579,950.
- Borg Warner Corporation: *See—*
- Mac Phee, Colin A. A.; and Haene, Antonio C. P., 3,580,743.
- Borg-Warner Corporation: *See—*
- Albertson, Clarence E.; and Krueger, Robert H., 3,580,759.
- Grabowski, Thomas S., 3,580,730.
- Jones, Johnny W., 3,581,179.
- Mieras, Spencer H., 3,580,108.
- Born, Dieter; Stech, Peter; and Huebner, Werner, to Klein Schanzlin & Becker A. G. Contact-free hydrostatic seal. 3,580,587, Cl. 277-3.
- Bosch, Paul; and Kobald, Walter, to Bosch, Robert, G.m.b.H. Regulated hydraulic drive control apparatus. 3,579,979, Cl. 60-19.
- Bosch, Robert, G.m.b.H.: *See—*
- Bosch, Paul; and Kobald, Walter, 3,579,979.
- Busse, Herbert, 3,579,987.
- Schupp, Karl; and Weismann, Hans, 3,581,034.
- Stams, Dietrich, 3,579,978.
- Bosley, Dewey R.: *See—*
- Tidball, Robert A.; King, William M.; Bosley, Dewey R.; and Jennings, Charles M., 3,580,816.
- Bossetta, Gaspar Robert. Automatic grocery bag filling apparatus with inner and outer tray. 3,579,959, Cl. 53-260.
- Boswell, George T., to Susquehanna Corporation, The. Fuze with impact switch. 3,580,176, Cl. 102-75.
- Bouhot, Marcel. Cock. 3,580,541, Cl. 251-174.
- Bouladon, Gabriel; and Zuppiger, Paul, to Battelle Memorial Institute. Variable speed transport apparatus. 3,580,182, Cl. 104-25.
- Boultinghouse, Harold D., to Phillips Petroleum Company. Method of forming nonwoven articles by fusing strands to a base. 3,580,761, Cl. 156-72.
- Bourdon, Claude: *See—*
- Robert, Andre; Bourdon, Claude; and Le Goer, Jean Luc, 3,580,681.
- Bowie, Philip A.: *See—*
- Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., 3,579,761.
- Bowles Fluidics Corporation: *See—*
- Bauer, Peter; and Mentzer, William R., Jr., 3,580,499.
- Boxman, Raymond L., to General Electric Company. Triggered vacuum gap device with means for reducing the delay time to arc-over the main gap. 3,581,142, Cl. 313-162.
- Boyce, William C.; and Matza, Edward C., to LTV Aerospace Corporation. Maneuvering unit. 3,580,528, Cl. 244-1.
- Boyle, Martin A., to Alpha Metals Inc. Cover for coplanar walls of an open top circuit package. 3,579,817, Cl. 29-588.
- Boyle, Willard S.; and Morton, Jack A., to Bell Telephone Laboratories, Incorporated. Cold cathode structure comprising semiconductor whisker elements. 3,581,151, Cl. 317-234.
- Bradbury, Cyril Henry, to Simms Group Research and Development Limited. Valve mechanisms for use with internal combustion engines. 3,580,231, Cl. 123-32.
- Bradshaw, Christopher Patrick Cadman: *See—*
- Keen, Ian Montgomery; Craig, Peter James; and Bradshaw, Christopher Patrick Cadman, 3,580,960.
- Brady, Lynn J.: *See—*
- Rozema, Arthur L.; Brady, Lynn J.; and Barden, Wayne A., 3,579,819.
- Brandenberg, Karl A., to Aro Corporation, The. Fluid proximity sensor and drive mechanism to control distance of an object from the sensor. 3,580,137, Cl. 91-50.
- Brandenberg, Karl A., to Aro Corporation, The. Comparator circuit for digital positioning control. 3,580,266, Cl. 137-81.5
- Brandenberg, Karl A., to Aro Corporation, The. Work control device for fluid driven apparatus. 3,580,285, Cl. 137-624.2
- Brandts, Theodor G.: *See—*
- Pickup, John; Brandts, Theodor G.; and Lichtenberger, Joseph A., 3,580,704.
- Braun Aktiengesellschaft: *See—*
- Scheibel, Josef, 3,580,096.
- Brauner, Edward J.: *See—*
- Reddel, Robert J.; and Brauner, Edward J., 3,581,283.
- Bray, Aaron C., Jr. Device for holding pleated material. 3,579,877, Cl. 38-12.
- Bray, Nicholas P. Forward planning apparatus. 3,579,884, Cl. 40-110.
- BRD, Inc.: *See—*
- Hallett, Thomas E., 3,579,861.
- Breitmeyer, Richard; and Amann, Karl, to Bauknechte GEA Elektrotechnische Fabriken Gesellschaft mit beschränkter Haftung. Apparatus for heating a storage core of a heat storing furnace. 3,581,059, Cl. 219-378.
- Brennan, Brian L.: *See—*
- Brennan, Edward N.; and Brennan, Brian L., 3,580,349.
- Brennan, Edward N.; and Brennan, Brian L. Portable motorized cart. 3,580,349, Cl. 180-27.
- Brian, Michael, to United States of America, Navy. An improved tilt switch. 3,581,031, Cl. 200-61.47
- Bridge, John. System and apparatus for holding freight containers to vehicles and the like. 3,580,185, Cl. 105-366.
- Bridgestone Tire Company Limited: *See—*
- Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, 3,580,895.
- Yoshimoto, Toshio; Narumiya, Tsuneaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, 3,580,897.
- Brignet, Roger Raoul. Direct current static transformer. 3,581,148, Cl. 315-227.
- Brinckman, Eric Maria, to Gevaert-Agfa N.V. Thermographic recording process. 3,580,719, Cl. 96-27.
- Brinkerhoff, Joris M.; Hunerwadel, Jean L.; and Sellers, Francis B., to Panametrics, Inc. X-ray fluorescence measuring system employing balanced X-ray filters and circuit means to vary the effective relative transmission thereof. 3,581,087, Cl. 250-51.5
- Brinkman, John D.: *See—*
- Paradise, Ronald Y.; Masel, Marvin; Naydan, Bob N.; and Brinkman, John D., 3,581,304.
- Brinkmann, Ludwig; Cherdron, Harald; and Herwig, Walter, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Thermoplastic polyester molding compositions containing olefin-vinyl ester copolymers. 3,580,965, Cl. 260-873.
- Bristol-Myers Company: *See—*
- Behnke, John M., 3,580,875.
- British Cast Iron Research Association: *See—*
- Edwards, Albert, 3,580,326.
- British Petroleum Company Limited, The: *See—*
- Keen, Ian Montgomery; Craig, Peter James; and Bradshaw, Christopher Patrick Cadman, 3,580,960.
- Britnev, Georgy Pavlovich: *See—*
- Beresnev, Boris Ivanovich; Bulychev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich;

- Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
- Britt, Richard G.; and Loughridge, Frederick A., to Sylvania Electric Products, Inc. Particle tube fusion furnace. 3,580,710, Cl. 65-144.
- Brokloff, Robert W.: See—
Allison, Robert W., Jr.; Brokloff, Robert W.; and Woodyard, John R., 3,580,822.
- Brooks, Ray G. Actuating mechanism for pressurized fluid dispenser. 3,580,432, Cl. 222-402.13
- Brooks, William. Shift register. 3,581,296, Cl. 340-174.5
- Broussard, Leo P.; Dickson, Leon L., Jr.; and Gardener, Wilhelmus J. G., to Shell Oil Company. Method for preventing deformation in a well casing. 3,580,334, Cl. 166-250.
- Brouwer, Charles W., to Leesona Corporation. Bobbin orienting. 3,580,374, Cl. 193-43.
- Brouwer, Frans; and Sobchak, Frank L., to Stewart-Warner Corporation. Two speed drive mechanism for facsimile recording system of the like. 3,580,110, Cl. 74-812.
- Brouwer, Frans; and Sobchak, Frank L., to Stewart-Warner Corporation. Facsimile scanner assembly. 3,581,001, Cl. 178-7.6
- Brown & Williamson Tobacco Corporation: See—
Ballard, Francis J., Jr., 3,580,644.
- Brown, Archer W.; Montgomery, James L.; Beer, Walter A.; and Mero, Thomas J., to American Hoist & Derrick Company. Disc brake for track driven machine. 3,580,345, Cl. 180-9.2
- Brown, Cicero C. Automatic rotary slips. 3,579,752, Cl. 24-263.
- Brown, David Argent. Toy watercraft. 3,579,900, Cl. 46-93.
- Brown, David N. Electronic marker actuator. 3,580,340, Cl. 172-126.
- Brown, Fred P., Jr.: See—
Rohdin, Howard A.; and Brown, Fred P., Jr., 3,580,442.
- Brown, Gaylord W., to Koehring Company. Extruder-molder. 3,579,723, Cl. 18-4.
- Brown, Ian McLaren, to McDonnell Douglas Corporation. Microwave resonance systems employing a bimodal cavity. 3,581,190, Cl. 324-0.5
- Brown, Ivor James Stewart; Clarkson, Richard; Crossley, Neville Stanton; and McLoughlin, Bernard Joseph, to Imperial Chemical Industries, Limited. 3(Aminoalkoxycarbonylalkylene)steroid derivatives. 3,580,905, Cl. 260-210.5
- Brown, Kenneth William, to National Research Development Corporation. Welding apparatus. 3,581,051, Cl. 219-131.
- Brown, Kenneth William; and Balchin, Nigel C., to National Research Development Corporation. Electric arc welding systems. 3,581,050, Cl. 219-130.
- Brown, Leonard Carlton, to United States of America, Atomic Energy Commission, mesne. Utilizing penetrating radiation. 3,581,090, Cl. 250-83.3
- Brown, Richard L.: See—
Shuster, Joseph; and Brown, Richard L., 3,580,379.
- Brownell, James R.: See—
Helrigel, Robert A.; Brownell, James R.; Ward, Roderick K.; and Keithley, Harry E., 3,580,558.
- Browning, Gordon D.: See—
Morey, Dennison H., Jr.; Silva, Melvin; and Browning, Gordon D., 3,581,197.
- Browning, Stanley Albert Charles: See—
Gonyou, John Christie; and Browning, Stanley Albert Charles, 3,579,955.
- Bruckner-Maschinenbau Gernot Bruckner: See—
Frailzi, Raimund, 3,580,451.
- Bryan Donkin Company Limited, The: See—
Farrell, Sydney, 3,580,271.
- B.S.A. Tools Limited: See—
Austin, Eric R.; and Bill, Eric G., 3,580,129.
- Buchanan, Richard G.: See—
Bennett, George K.; and Buchanan, Richard G., 3,579,870.
- Buchner, Norbert; and Domke, Klaus, to Fr. Hesser Maschinenfabrik Aktiengesellschaft. Apparatus for reducing the atmospheric oxygen content of fluent solid pourable materials by gas exchange. 3,579,945, Cl. 53-112.
- Buck, Jack B. Dental X-ray film holder. 3,580,159, Cl. 95-100.
- Buck, John R.: See—
Vogel, Alvin R.; Moore, Douglas A.; Folan, Martin P.; and Buck, John R., 3,581,014.
- Buckley, Trevor, 1/2 to Frowds Limited. Radar systems. 3,581,310, Cl. 343-7.7
- Bucyrus-Erie Company: See—
Barber, Donald E., 3,581,170.
- Calud, Romeo T.; Hansbrough, David L.; and Zaumseil, Dean R., 3,581,169.
- Budd Company, The: See—
Dean, Albert G., 3,580,557.
- Budzyn, Boleslaw L.: See—
Arnould, Marcel M.; Ward, John C., Jr.; Ray, William Floyd; and Budzyn, Boleslaw L., 3,580,386.
- Buege, Dennis R.: See—
Stouffer, James R.; Buege, Dennis R.; and Gillis, Wayne A., 3,579,716.
- Buehrle, William E., Jr.; and Woodard, Gerald F. Emergency warning and identification apparatus for two-way radio communication system. 3,581,208, Cl. 325-64.
- Bulychev, Dmitry Konstantinovich: See—
Beresnev, Boris Ivanovich; Bulychev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
- Bunker-Ramo Corporation, The: See—
Knitter, Heinz; and Veszelik, Josef, 3,581,271.
- Rothfuss, Helmut; and Rode, Horst, 3,580,985.
- Yopp, Robert S.; and Kraft, Melvin G., 3,581,272.
- Burdick, Glen A., to Sylvania Electric Products, Inc. Method of fabricating cathode ray tube screen. 3,579,768, Cl. 29-25.13
- Burger, Erich: See—
Hieber, Fritz; Burger, Erich; and Huber, Hans-Peter, 3,580,675.
- Burke, William R.; and McCall, Frank S., to Union Camp Corporation. Collapsible cellular box partitions. 3,580,471, Cl. 229-15.
- Burkert, Adolf: See—
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
- Burman, Per Aron, to Burrough Corporation. Component removing tool. 3,579,795, Cl. 29-252.
- Burmeister, Fred; Enkvist, Ernst; Johansson, Bengt; and Kostilainen, Valtter, to Oy Wartsila AB. Arrangement in ships. 3,580,204, Cl. 114-67.
- Burnham, Clifford Henry. Copy holder. 3,579,888, Cl. 40-356.
- Burns, Alvin G.; and Miller, Sheldon M. Inflatable packing for stuffing boxes. 3,580,586, Cl. 277-3.
- Burnside, Ernest. Quickly-removable ignition coil installation for automobile theft prevention. 3,581,259, Cl. 336-90.
- Burrough Corporation: See—
Burman, Per Aron, 3,579,795.
- Burroughs Corporation: See—
Akst, Harold, 3,581,268.
- Burroughs Corporation: See—
Behr, Michael I.; Coon, Lewis B., Jr.; and Bickel, Charles E., 3,581,297.
- Billawala, Shahbuddin A., 3,581,298.
- Di Paolo, Peter T., Jr.; and Carbine, Joseph C., 3,579,778.
- Kupsky, George A., 3,580,654.
- Siu, Paul Y., 3,581,235.
- Waltz, Richard B., 3,581,074.
- Bushey, Donald H.: See—
Heywood, Vincent E.; Bushey, Donald H.; and Chapman, William A., Jr., 3,579,944.
- Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich. Appliance for supplying gas into a predetermined zone. 3,580,554, Cl. 263-33.
- Busse, Ewald A. Device for mixing combustible components recovered from exhaust gases with fuel charge of carburetor. 3,580,233, Cl. 123-119.
- Busse, Herbert, to Bosch, Robert, G.m.b.H. Adjustable hydraulic operation arrangement. 3,579,987, Cl. 60-52.
- Butler, Kenneth, to Pfizer Inc. Process for the conversion of α -carboxybenzylpenicillins to α -carboxybenzylpenicillins. 3,580,908, Cl. 260-239.1
- Butler National Corporation: See—
Perkins, Earl Stuart, 3,580,080.
- Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkina, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich. Active material for lasers. 3,580,859, Cl. 252-301.1
- Bykov, Leonid Alexandrovich: See—
Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.
- Byrne Doors, Inc.: See—
Wetter, Allan E., 3,579,910.
- Cadotte, John E.; and Francis, Peter S., to United States of America, Interior. Ultrathin semipermeable membrane. 3,580,841, Cl. 210-23.
- Cagle, Buddy L., Sr. Cable feed device. 3,580,448, Cl. 226-127.
- Calamvotsakis, Constantine P. Box game. 3,580,582, Cl. 273-139.
- California Car Wash Systems, Inc.: See—
Haley, David Merl, 3,579,700.
- Calmece Extrudorm Limited: See—
Schneider, Jack Marvin, 3,580,773.
- Calud, Romeo T.; Hansbrough, David L.; and Zaumseil, Dean R., to Bucyrus-Erie Company. Reversing control for an induction motor. 3,581,169, Cl. 318-214.
- Camdex, Inc.: See—
Leich, Robert A., 3,580,128.
- Cameron, Donald P., to Pfizer Inc. Heterocyclic mesoionic compounds. 3,580,921, Cl. 260-302.
- Campbell, Albert B., to Royal Products Company. Lather machine. 3,580,863, Cl. 252-359.
- Campbell, Edwin R.: See—
Comstock, David W.; and Campbell, Edwin R., 3,581,182.
- Campbell, J. Allen; and Babcock, John C., to Upjohn Company, The. 7α - and 7β -Methyl-3 α , 5 α -cycloandrostenes, 6-methyl derivatives thereof and the 19-nor analogues of the foregoing. 3,580,937, Cl. 260-397.4

- Campbell, Ray J. Mailbox. 3,580,491, Cl. 232-35.
- Campbell, Thomas A.: See—
Underwood, Ray L.; and Campbell, Thomas A., 3,580,627.
- Canadian Cedar Inc.: See—
Fox, Edward L., Jr., 3,580,311.
- Canadian International Paper Company: See—
Hamilton, Douglas D., 3,580,308.
- Hoffmann, Wolfgang; and Wick, Paul, 3,579,956.
- Cancer, Ralph A.; Anderson, William J.; Morgan, Bert B.; and Goodman, Jerry M., to Northrop Carolina, Inc. Texturizing apparatus. 3,579,760, Cl. 28-1.7
- Cannon, Lester E.; Tindall, John M.; and Taylor, Howard N., to Folding Cartons, Inc. Carton for use with packaging apparatus. 3,580,476, Cl. 229-37.
- Cannon, Richard L.; and Smith, Leonard R. D., to Dale Electronics, Inc. Adjustably mounted player piano key actuating assembly. 3,581,254, Cl. 335-255.
- Cannon, Richard L.; and Smith, Leonard R. D., to Dale Electronics, Inc. Mounting means for player piano key actuating assembly. 3,581,255, Cl. 335-255.
- Cano, Serafin: See—
Rocha, Octavio; and Cano, Serafin, 3,580,228.
- Canon Camera Co., Ltd.: See—
Nagao, Kazuyoshi, 3,581,102.
- Canon Camera Kabushiki Kaisha: See—
Tanaka, Hiroshi; and Ishihara, Masayoshi, 3,581,149.
- Caplin, Harry B. Collapsible hand truck. 3,580,600, Cl. 280-36.
- Carbine, Joseph C.: See—
Di Paolo, Peter T., Jr.; and Carbine, Joseph C., 3,579,778.
- Carbon, Erich; and Wagner, Wolfgang, to Volkswagen Aktiengesellschaft. Lock for safety belts. 3,579,750, Cl. 24-230.
- Cardwell, Lonnie D.; Esenwein, Fred T.; and Pierard, Arthur E., to United States of America, Navy, mesne. Rocket burn rate testing device. 3,580,049, Cl. 73-35.
- Caretta, Renato: See—
Pacciari, Antonio; and Caretta, Renato, 3,580,766.
- Caribbean Holdings Ltd.: See—
Dobell, Curzon; and Wilson, Leslie P., 3,580,461.
- Carlo Gavazzi S.p.A.: See—
Bini, Giancarlo; and Tamoni, Gianfranco, 3,580,284.
- Carlson, Gerald J., to General Electric Company. Tool surface temperature measuring apparatus. 3,579,775, Cl. 29-96.
- Carr, Barney J., deceased (by Carr, Elisabeth Helen; administratrix), to Kaman Sciences Corporation, mesne. DC operated positive ion accelerator and neutron generator having an externally available ground potential target. 3,581,093, Cl. 250-84.5
- Carr, Elisabeth Helen: See—
Carr, Barney J., 3,581,093.
- Carraher, Delbert V.: See—
Issott, John W.; Honkala, Harold E.; and Carraher, Delbert V., 3,580,037.
- Carrier Corporation: See—
Ballard, Gary W., 3,580,013.
- Czuszak, Charles C., 3,580,691.
- Eisberg, Keith V., 3,580,001.
- Fisher, John T., 3,580,002.
- Hale, Harry T., 3,580,005.
- Smith, Donald R.; and Cavestany, Adrian V., 3,580,512.
- Walters, Frank F., 3,580,028.
- Carroll, Alton P., Jr.: See—
Carter, Ernest P.; Bell, Robert P., Jr.; and Carroll, Alton P., Jr., 3,580,296.
- Carroll Plastics Corporation: See—
Pieszak, Franklin B.; and Knaggs, Marvin G., 3,580,467.
- Carson, Arthur N., to Carson Laboratories, Inc. Hologram apparatus and method. 3,580,656, Cl. 350-3.5
- Carson Laboratories, Inc.: See—
Carson, Arthur N., 3,580,656.
- Carter, Clarence F., to Carter Engineering Company. Method and apparatus for feeding and compacting finely divided particulate material. 3,580,419, Cl. 222-1.
- Carter Engineering Company: See—
Carter, Clarence F., 3,580,419.
- Carter, Ernest P.; Bell, Robert P., Jr.; and Carroll, Alton P., Jr., to Monsanto Company. Articles woven from non-extensible materials. 3,580,296, Cl. 139-425.
- Caruel, Jacques Emile Jules; Quillevere, Herve Alain; and Bauger, Louis, to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation. Improvements in or relating to combustion chambers. 3,579,983, Cl. 60-39.71
- Casebeer, Oran T., to Eastman Kodak Company. Automatic exposure control device. 3,580,157, Cl. 95-64.
- Cassagne, Pierre, to Compagnie Francaise de Television. Magnetic recording and reproducing apparatus for color television signals using a frequency modulated subcarrier for the transmission of the color information. 3,581,007, Cl. 178-5.4
- Cassella Farbwerke Mainkur Aktiengesellschaft: See—
Heid, Christian; and Keil, Karl-Heinz, 3,580,851.
- Cassill, William Guy, to Mead Corporation, The. Alignment system for arrays of a noncontacting printer. 3,580,515, Cl. 239-536.
- Cast, Adolf; and Schwarz, Heinz, to Reich, Karl M., Maschinenfabrik. Fastener driving device operating means. 3,580,455, Cl. 227-8.
- Castro, Luis F.: See—
Dean, Michael R.; Castro, Luis F.; and Salerni, John V., 3,580,332.
- Catherin, Jean-Michel, to Compagnie General d'Electricite. Laser gyrometer system. 3,579,846, Cl. 33-204.
- C.A.V. Limited: See—
Hazel, Jack A., 3,580,118.
- Cavalleri, Bruno; Bellasio, Elvio; and Testa, Emilio, to Lepetit S.p.A.-Gruppo per la Ricerca Scientifica e la Produzione Chimica Farmaceutica. Pharmacologically active diethyl-(2-dibenzofuramyl)-malonate. 3,580,932, Cl. 260-346.2
- Cavestany, Adrian V.: See—
Smith, Donald R.; and Cavestany, Adrian V., 3,580,512.
- Celanese Corporation: See—
Kennedy, Daniel M., Jr.; and Zellner, Carl Nacher, 3,580,973.
- McAndrew, Francis B.; Price, Martin B.; and Berardinelli, Frank M., 3,580,928.
- Cenco Medical/Health Supply Corporation: See—
Bender, Charles E.; and Fraser, Douglas S., 3,580,812.
- Centre Electronique Horloger S.A.: See—
Omlin, Luc, 3,581,126.
- Centre Technique Industriel dit: Institut Textile de France: See—
Voisin, Eugene; Raisin, Jean-Pierre; and Delair, Jean-Paul, 3,580,012.
- Cer Preduzece Termo-Tehnickih Uredajaja I Montaza: See—
Ivackovic, Nikola; and Urosec, Milija, 3,579,852.
- Cerrito, Michael: See—
McClure, Arthur A., 3,580,690.
- Cervenka, Joseph J.; and Hetzel, Marvin E. Machine for applying lugs or the like to bobbins or the like. 3,579,787, Cl. 29-203.
- Cessna Aircraft Company: See—
Ryan, Donald P., 3,581,019.
- Ceyzeriat, Louis; Gaignon, Maurice; and Lefort, Marcel, to Rhone-Poulenc S.A. Aminosilanes and compositions containing them. 3,580,939, Cl. 260-448.2
- Chaban, Michael J., Jr., to Standrad International Corporation. Stock feed apparatus. 3,580,449, Cl. 226-150.
- Challenge Machinery Company, The: See—
Westra, Dan P.; and Siewert, John J., 3,580,123.
- Chambers, Robert F. Eyelet and lug assembly. 3,580,621, Cl. 287-101.
- Chambers, William W., to Robertshaw Controls Company. Temperature control system providing full wave conduction into temperature change apparatus. 3,581,061, Cl. 219-499.
- Chang, Robert W. Joint setting of demodulating carrier phase, sampling time and equalizer gain parameters in synchronous data transmission systems. 3,581,207, Cl. 325-42.
- Chapman, William A., Jr.: See—
Heywood, Vincent E.; Bushey, Donald H.; and Chapman, William A., Jr., 3,579,944.
- Cheeseman, Ian Clifford; and Smith, Michael Charles George, to United Kingdom of Great Britain and Northern Ireland, Minister of Technology in Her Britannic Majesty's Government of the. Boundary layer control devices. 3,580,693, Cl. 416-90.
- Chemical Separation Corporation: See—
Higgins, Irwin R., 3,580,842.
- Cheney, Oliver F., to Delaware Valley Armaments, Inc. Method and apparatus for testing rotation-responsive delay devices. 3,580,046, Cl. 73-5.
- Cheng, Chao-Shing; and Evans, Francis E., to Allied Chemical Corporation. Stable liquid dicarboxylic acid anhydride composition. 3,580,857, Cl. 252-182.
- Cheng, Chao-Shing: See—
Evans, Francis E.; and Cheng, Chao-Shing, 3,580,858.
- Cherdron, Harald: See—
Brinkmann, Ludwig; Cherdron, Harald; and Herwig, Walter, 3,580,965.
- Chermack, Robert W. Glass filler. 3,580,304, Cl. 141-244.
- Cherry, Gene F. Military ribbon holder. 3,579,881, Cl. 40-1.5
- Chery, Walter V., to Textron Inc. Slide fastener device and method of making the same. 3,579,748, Cl. 24-205.1
- Chesapeake and Ohio Railway Company, The: See—
Payseure, Lawrence A., 3,581,071.
- Cheslin, Sigmund: See—
Schriever, Fred G.; and Cheslin, Sigmund, 3,580,779.
- Chetwynd, Earl G.: See—
Griffin, Anthony L.; and Chetwynd, Earl G., 3,579,878.
- Chevron Research Company: See—
Furby, Neal W.; Godfrey, Douglas; and Peeler, Robert L., 3,580,848.
- Hughes, Walter D., 3,580,263.
- Parker, Phillip H., 3,580,769.
- Rhodes, David R., 3,580,832.
- Wyrick, Leon M., 3,580,538.
- Chicago Lock Co.: See—
Kerr, William J., 3,580,016.
- Chicago Roller Skate Company, The: See—
Keltz, Lawrence W.; and Marek, Charles, 3,579,688.
- Ware, Gordon K., 3,580,594.
- Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.
- Child Guidance Toys Inc.: See—
Genin, Robert, 3,579,904.
- Chopard, Remy: See—
Besson, Rene; and Chopard, Remy, 3,579,975.
- Choquette, Rita Marie. Bath tub for invalids. 3,579,658, Cl. 4-173.
- Christensen, Paul M., to Arrow-Hart, Inc. Enclosed switch with over-carried operator and interlock mechanism. 3,581,032, Cl. 200-50.

- Chrysler Corporation: *See—*
 Gau, Leonard P., 3,579,981.
 Sarto, Jorma O., 3,580,232.
 Verdoodt, Marcel E.; and Michalke, Klaus A., 3,579,698.
- Chuhita, Thomas A., to Eastman Kodak Company. Web transport apparatus. 3,580,452, Cl. 226-191.
- Churchill, John W.; Kober, Ehrenfried H.; Scott, Peter H.; and Smith, Curtis P., to Olin Mathieson Chemical Corporation. Preparation of fluoroanilines. 3,580,951, Cl. 260-580.
- Chute, Richard; and Berryman, Charles O., to Eaton Yale & Towne, Inc. Inflatable safety apparatus. 3,580,603, Cl. 280-150.
- Ciba Limited: *See—*
 Angliker, Hans-Joerg, 3,580,902.
 Anliker, Rudolf; Duennenberger, Max; Schmid, Karl; and Siegrist, Adolf Emil, 3,580,924.
- Cichy, Raymond G.: *See—*
 Barnes, Gerald L.; Cichy, Raymond G.; and Adams, Gerald E., 3,580,767.
- Cimber, Hugo S. Aspirator. 3,580,255, Cl. 128-276.
- Cincinnati Butchers' Supply Company, The: *See—*
 Schmidt, Carl Oscar, Jr., 3,579,715.
- Cincinnati Milacron Inc.: *See—*
 Pfister, Stanley A., 3,579,812.
- Ciriack, Gunter; Eckert, Georg; and Hofmann, Horst, to Siemens Aktiengesellschaft. Grid electrode for electronic tubes. 3,580,739, Cl. 117-217.
- Ciriello, John: *See—*
 Belford, John F.; Gibeau, Donald E.; and Ciriello, John, 3,581,247.
- C.I.T.-Compagnie Industrielle des Telecommunications: *See—*
 Leostic, Joseph, 3,581,116.
- C.I.T. Compagnie Industrielle des Telecommunications: *See—*
 Berman, Leon, 3,581,236.
- Cities Service Company: *See—*
 Harris, Dale K., 3,580,279.
 Huskey, Joseph E., 3,580,060.
- Clair, Hermann, to Eastman Kodak Company. Control mechanism for motion picture projector. 3,580,668, Cl. 352-194.
- Clachan, Margaret L.; McGrail, Patrick T.; and Shephard, Basil R., to Bexford Limited. Antistatic film base material and process for preparing same. 3,580,734, Cl. 117-138.8
- Clark Equipment Company: *See—*
 Stickle, Stanley A., 3,580,373.
- Clark, James A., to Bausch & Lomb Incorporated. Curve generating linkage. 3,580,088, Cl. 74-1.
- Clark, Robert S.: *See—*
 Cunningham, James A.; and Clark, Robert S., 3,581,161.
- Clarke, Michael Raymond; and Filipowicz, Leon, to Balm Paints Limited. Dispersions of particulate solids in either lipophilic or hydrophilic liquids stabilized with a polymeric amphoteric stabiliser and process for preparing said dispersions. 3,580,880, Cl. 260-29.6
- Clarke, Robert E. Cream dispenser with pleated walls and lip type opening. 3,580,427, Cl. 222-215.
- Clarke, Terence J.L.; and Evans, Ivor, deceased (by Evans, Josie V.; administratrix), to United Shoe Machinery Corporation. Method for coating work pieces with thermoplastic material. 3,580,774, Cl. 156-247.
- Clarkson, Richard: *See—*
 Brown, Ivor James Stewart; Clarkson, Richard; Crossley, Neville Stanton; and McLoughlin, Bernard Joseph, 3,580,905.
- Clevite Corporation: *See—*
 Arndt, John P.; and Franklin, Edmond G., 3,581,125.
- Clopay Corporation: *See—*
 Gossling, Robert C.; and Armstrong, George, 3,580,323.
- Coad, Brian C., to Texas Instruments, Incorporated. Manufacture of interiorly coated tubing. 3,579,772, Cl. 29-33.
- Coes, Loring, Jr., to Norton Company. Vibratory grinding method. 3,579,927, Cl. 51-281.
- Coffey, H. Franklin; and Powers, Samuel T., to Lovelace Foundation for Medical Education and Research. Wheelchair attachment. 3,580,591, Cl. 280-532.
- Colbert, William V.: *See—*
 Hill, Fredrick L.; Gates, Lauren W.; and Colbert, William V., 3,579,968.
- Cole, John M., to Thomas & Betts Corporation. Fastener anchored in honeycomb panel. 3,579,942, Cl. 52-615.
- Coleman, Charles; and Weaver, Boyd S., to United States of America, Atomic Energy Commission. Selective stripping of plutonium from organic extracts. 3,580,705, Cl. 23-341.
- Colley, Jean E.: *See—*
 Yeo, Roland J.; and Colley, Jean E., 3,581,025.
- Colombo, Americo; and Ronchetti, Ugo. Odontological instrument. 3,579,833, Cl. 32-27.
- Combustion Engineering, Inc.: *See—*
 Blackburn, Samuel S., Jr.; and Rickard, Earl K., 3,580,226.
- Commercial Solvents Corporation: *See—*
 Griffith, George L., 3,580,750.
 Griffith, George L., 3,580,751.
 Griffith, George L., 3,580,752.
 Griffith, George L., 3,580,753.
 Hidy, Phil, 3,580,811.
- Hidy, Phil H.; and Young, Vernon V., 3,580,929.
- Commissariat a l'Energie Atomique: *See—*
 de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignot, Paul, 3,580,818.
- Van Zurk, Robert, 3,581,118.
- Compagnie des Ateliers et Forges de La Loire (St. Chamond, Firminy, St. Etienne, Jacob-Holtzes): *See—*
 Gay, Pierre, 3,580,033.
- Compagnie du Filage des Metaux et des Joints Curty: *See—*
 Andreassian, Jean-Michel, 3,580,038.
- Compagnie Francaise de Television: *See—*
 Cassagne, Pierre, 3,581,007.
- Compagnie General d'Electricite: *See—*
 Catherin, Jean-Michel, 3,579,846.
- Compagnie Generale des Etablissements Michelin raison sociale Michelin & Cie: *See—*
 Massoubre, Jean-Marie, 3,580,899.
- Computer Modem Corporation: *See—*
 Arbuckle, Timothy, 3,581,279.
- Comstock, David W.; and Campbell, Edwin R., to United Aircraft Corporation. Digital indicator step motor system. 3,581,182, Cl. 318-685.
- Consolidated Packaging Machinery Corporation: *See—*
 Riesenbergh, James H., 3,580,302.
- Consolidated Paper (Bahamas) Limited: *See—*
 Pickup, John; Brandts, Theodor G.; and Lichtenberger, Joseph A., 3,580,704.
- Construction Machinery Company: *See—*
 Fry, William H.; and Zerba, Lawrence G., 3,580,440.
- Container Corporation of America: *See—*
 Koboldt, Melvin A., 3,580,481.
- Continental Can Company: *See—*
 Vercillo, Peter A., 3,580,201.
- Continental Can Company, Inc.: *See—*
 French, Richard P., 3,580,480.
 McDewitt, James A., 3,580,468.
 Weiss, Arthur J., 3,580,479.
- Continental Carbon Company: *See—*
 Middlebrooks, Ollie, 3,579,717.
- Continental Gummi-Werke Aktiengesellschaft: *See—*
 Menell, Hans; and Scheithauer, Walter, 3,580,318.
- Continental Industries, Inc.: *See—*
 Morain, Eldon W., 3,579,826.
- Continental Oil Company: *See—*
 Sparlin, Derry D., 3,580,338.
 Whitfill, Donald L., 3,580,826.
- Contraves AG: *See—*
 Stutz, Theo; and Mueller, Werner, 3,581,301.
- Convex Limited: *See—*
 Zysman, Milton, 3,579,773.
- Conwed Corporation: *See—*
 Shreve, Robert N., 3,579,774.
- Cook, Allen D.; and Szabo, Kalman T., to Smith Kline & French Laboratories. Small animal milking apparatus. 3,580,220, Cl. 119-14.01
- Cook, Edward H., Jr.: *See—*
 Curry, John E.; Grotheer, Morris P.; and Cook, Edward H., Jr., 3,580,824.
- Cook, Richard E.: *See—*
 Orn, Vernon B.; and Cook, Richard E., 3,579,895.
- Coombes, William S.: *See—*
 Adams, Richard C.; Coombes, William S.; and Lerardo, Domenic, 3,580,120.
- Coon, Lewis B., Jr.: *See—*
 Behr, Michael I.; Coon, Lewis B., Jr.; and Bickel, Charles E., 3,581,297.
- Cooper, Beresford B., to Entwistle Company, The. Extrusion head. 3,579,731, Cl. 18-13.
- Cooper, Dester P., Jr., to Bell & Howell Company. Rear projection viewing screen for close viewing. 3,580,661, Cl. 350-128.
- Cooper, Hugh, Jr. Anatomy relating device for dentists. 3,579,832, Cl. 32-17.
- Cooper, Roy M., to Olin Mathieson Chemical Corporation. Mercury cell having rotating anode. 3,580,833, Cl. 204-212.
- Copley, Stephen M.; Giamei, Anthony F.; Hornbecker, Merton F.; and Kear, Bernard H., to United Aircraft Corporation. Double-oriented single crystal castings. 3,580,324, Cl. 164-60.
- Corken Pump Company: *See—*
 Kennedy, Garth P.; and Nelson, William E., 3,580,420.
- Cornell Aeronautical Laboratory, Inc.: *See—*
 Martin, Francis C.; and Nicklas, James P., 3,581,281.
- Cornell Research Foundation, Inc.: *See—*
 Stouffer, James R.; Buege, Dennis R.; and Gillis, Wayne A., 3,579,716.
- Corning Glass Works: *See—*
 Samuels, Walter E. D., 3,579,879.
 Steinberg, David R., 3,580,075.
- Corry, Alfred Reginald; Guest, Dorothy Joyce; and Williamson, William Ian, to Imperial Chemical Industries Limited. Emulsion polymers of styrene and unsaturated amides. 3,580,877, Cl. 260-29.6
- Cory Corporation: *See—*
 Farrell, Claude S., Jr., 3,580,163.
- Cosentino, Louis Ciro, to Hoffmann-La Roche Inc. Disposable electrode with self-sealing plug outlet. 3,580,240, Cl. 127-2.06
- Cosier, James Edwin Henry, to Postmaster General, Her Majesty's. Apparatus for forming moulding components. 3,579,739, Cl. 18-30.
- Costa, Robert B., to Rain Bird Sprinkler Mfg. Corporation. Bearing for impact motor driven sprinkler. 3,580,506, Cl. 239-230.

- Coulter Electronics, Inc.: *See—*
 Coulter, Wallace H., 3,580,686.
- Coulter, Wallace H., to Coulter Electronics, Inc. Vessel having inter-sample anti-contamination construction. 3,580,686, Cl. 356-246.
- Cox, John B.; and Stoltz, Jacques R., to Mobil Oil Corporation. Time averaging method and apparatus for obtaining fluid measurements. 3,580,072, Cl. 73-205.
- Coy, John W., to Coy Oil Co., Inc. Economizer. 3,580,225, Cl. 122-20.
- Coy Oil Co., Inc.: *See—*
 Coy, John W., 3,580,225.
- Cragstan Industries, Inc.: *See—*
 Perhacs, Leslie, Jr., 3,579,901.
- Craig, Leonard J., to United States of America, Air Force. Catadioptric reflex radiation detection conversion, location and display device. 3,581,089, Cl. 250-83.
- Craig, Peter James: *See—*
 Keen, Ian Montgomery; Craig, Peter James; and Bradshaw, Christopher Patrick Cadman, 3,580,960.
- Cramer, Donald L.; and Limpach, Paul D., to Automatic Feed Company. Strip stocking handling equipment. 3,580,021, Cl. 72-5.
- Crane Co.: *See—*
 Lien, Millard H., 3,579,661.
- Craver, Edward H., to Western Electric Company, Incorporated. Apparatus for assembling pieceparts into cup-shaped adapters. 3,579,792, Cl. 29-208.
- Creith, Lou C., to Olin Corporation. Semi-automatic weld apparatus with means for changing electrode angular disposition. 3,581,049, Cl. 219-125.
- Crick, Stephen E.: *See—*
 Hayes, Edward J.; and Crick, Stephen E., 3,579,783.
- Crider, Walter Leslie, to United States of America, Health, Education and Welfare. Flame emission instrument for selectively monitoring metal aerosols. 3,580,680, Cl. 356-87.
- Criner, Gaspard X.; and Blackburn, William A., to Monsanto Company. Method of producing fiber reinforced foam products. 3,580,763, Cl. 156-78.
- Crisp, Clair R., Jr. Automatic car washer. 3,579,701, Cl. 15-21.
- Crites, Nelson A.; and Lyons, Donald H., to Abbott Laboratories. Thermometer indicator. 3,580,079, Cl. 73-358.
- Croix-Marie, Francis Marie Jean: *See—*
 Bertin, Jean Henri; and Croix-Marie, Francis Marie Jean, 3,580,181.
- Crompton & Knowles Corporation: *See—*
 Feeman, James F., 3,580,901.
- Crook, Walter, Jr.: *See—*
 Koll, Laurel A.; and Crook, Walter, Jr., 3,579,672.
- Cross Electronics, Inc.: *See—*
 Roman, Terrance S., 3,580,678.
- Crossley, Neville Stanton: *See—*
 Brown, Ivor James Stewart; Clarkson, Richard; Crossley, Neville Stanton; and McLoughlin, Bernard Joseph, 3,580,905.
- Crown Zellerbach Corporation: *See—*
 Metz, Peter J., Jr., 3,579,735.
- Crump, Elmo E. Synchronized burst generator. 3,581,213, Cl. 328-25.
- CTS Corporation: *See—*
 Rozema, Arthur L.; Brady, Lynn J.; and Barden, Wayne A., 3,579,819.
- Culpepper, Alan L., to Dow Corning Corporation. Certain pyridinium haloether silanes and derivatives. 3,580,920, Cl. 260-297.
- Cumpston, Edward H., Jr. Heat meter. 3,580,070, Cl. 73-193.
- Cuneo, Robert A.: *See—*
 Lamp, Richard W.; Kopf, Joseph E.; Dravis, Donald P.; and Cuneo, Robert A., 3,580,981.
- Cunningham, James A.; and Clark, Robert S., to Texas Instruments, Incorporated. Molybdenum-gold-molybdenum interconnection system for integrated circuits. 3,581,161, Cl. 317-234.
- Currey, John E.; Grotheer, Morris P.; and Cook, Edward H., Jr., to Hooker Chemical Corporation. Impregnated graphite. 3,580,824, Cl. 204-95.
- Cutter-Hammer, Inc.: *See—*
 Dennison, William G., 3,581,036.
- Cvacho, Daniel S.; and Fritchey, Edward H., to Reynolds Metals Company. Apparatus for and method of forming a sheet-like workpiece. 3,580,200, Cl. 113-1.
- Cynober, Simon, to Saunier Duval. Articulated cartridges for pneumatic conveyance. 3,580,527, Cl. 243-38.
- Czuszak, Charles C., to Carrier Corporation. Vibration absorbing throttle lift bar. 3,580,691, Cl. 415-155.
- Dach, Hansjorg, to Zahnradfabrik Friedrichshafen Aktiengesellschaft. Automatic gear-shift control for automotive transmission system. 3,580,112, Cl. 74-868.
- Dahle, Hildegard, to U.S. Philips Corporation. Acid containing electrolytic liquid for an electrolytic capacitor. 3,580,845, Cl. 252-62.2
- Dahms, Wolfgang: *See—*
 Todt, Hans-Gunther; and Dahms, Wolfgang, 3,580,821.
- Daicel Ltd.: *See—*
 Numa, Yoshiaki; Nakamachi, Akio; and Murakami, Yasukazu, 3,580,917.
- Daigne, Bernard M.; and Pelletier, Louis, to Office National d'Etudes et de Recherches Aeronautiques (par abbreviation O.N.E.R.A.). Device for the supervision of a treatment in an enclosure at very low pressure. 3,581,086, Cl. 250-49.5
- Daimler-Benz Aktiengesellschaft: *See—*
 Gmeiner, Gunter; and Grabner, Christian, 3,580,624.
- Heim, Gerhard, 3,580,629.
- Hoffmann, Heinrich; and Wagner, Wilhelm, 3,580,230.
- Dal Monte, Giorgio; and Pitidis, Nicola, to Societa Italiana Telecomunicazioni Siemens S.p.A. Pulse-transmission system. 3,581,008, Cl. 178-63.
- Dale Electronics, Inc.: *See—*
 Cannon, Richard L.; and Smith, Leonard R. D., 3,581,254.
 Cannon, Richard L.; and Smith, Leonard R. D., 3,581,255.
 Person, Herman R., 3,581,264.
- Dall'Asta, Leone: *See—*
 Pedrazzoli, Andrea; and Dall'Asta, Leone, 3,580,914.
- Dalton, Robert Barry, to United Aircraft Corporation. Spherical bearing tester. 3,580,059, Cl. 73-71.5
- Dame, Charles, Jr., to General Foods Corporation. Method of increasing solubility of food acidulents. 3,580,726, Cl. 99-78.
- Damewood, Glenn; Sparks, Cecil R.; and King, James D., to Southern Gas Association, mesne. Electrical analog model for fluid flow transmission system. 3,581,077, Cl. 235-184.
- D'Amico, Paul M. Devices and accessories for electric armored cables and stuffing tubes. 3,579,790, Cl. 29-203.
- Damon Corporation: *See—*
 Neame, Samuel, Jr.; Kondel, George C.; and De Santis, Italo J., 3,580,301.
- Daniel, David W.; and McNabb, Warren C., to Lear, Siegler, Inc. Gear rolling. 3,580,027, Cl. 72-98.
- Daniel, David W.; Verschaeve, Henry O.; and McNabb, Warren C., to Lear, Siegler, Inc. Rolling chamfers on gear teeth. 3,580,029, Cl. 72-108.
- Darragh, Richard T.; and Succo, John A., to Procter & Gamble Company, The. Protein-supplemented peanut spread. 3,580,729, Cl. 99-128.
- David Manufacturing Co.: *See—*
 Murphy, David M., 3,580,549.
- Davidson, Louis, Composite mantle system. 3,580,192, Cl. 108-152.
- Davidson Rubber Company, Inc.: *See—*
 Rhodes, Richard D., Jr.; and Flanagan, Kirby E. L., 3,580,869.
- Davies, Kenneth Knapton, to Metal Box Company Limited, The. Cartons. 3,580,465, Cl. 229-14.
- Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, to Molins Machines Company Limited. Packing machines. 3,579,952, Cl. 53-37.
- Davis, Frank J.; and Edwards, George Zahnor, to Kedman Company. Eye-shield operating system for welding helmets. 3,579,638, Cl. 2-8.
- Davis, Glenn V., to Borden, Inc. Method of and apparatus for obviating spillage in moving containers. 3,579,950, Cl. 53-37.
- Davis, William J.: *See—*
 Strafford, Richard A.; and Davis, William J., 3,580,572.
- Davy and United Engineering Company, Limited: *See—*
 Bond, Harry Laurence Fred; Stubbs, Dennis; and Maltby, Todwick, 3,580,035.
- Dawson, John M.: *See—*
 Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., 3,580,802.
- Dayton Reliable Tool & Mfg. Company: *See—*
 Eickenhorst, Franklin C., 3,580,264.
- Dean, Albert G., to Budd Company, The. Railway spring suspension. 3,580,557, Cl. 267-3.
- Dean, Michael R.; Castro, Luis F.; and Salerni, John V., to Baker Oil Tools, Inc. Apparatus for controlling fluid flow from gas storage wells and reservoirs. 3,580,332, Cl. 166-184.
- De Belder, Anthony N.; and Lindberg, Bernt J., to Pharmacia AB. Keto dextran compounds. 3,580,903, Cl. 260-209.
- Decker, Eugene J.: *See—*
 Zueger, Karl J.; and Decker, Eugene J., 3,580,456.
- De Claire, Alton G., Jr.: *See—*
 Hestad, Erling; Ritter, Thomas E.; and De Claire, Alton G., Jr., 3,580,352.
- De Franco, Thomas P.: *See—*
 Garrett, Elgie E.; De Franco, Thomas P.; and Staples, Nicholas B., 3,581,135.
- De Graff, Charles D.: *See—*
 Allen, Howard L.; and De Graff, Charles D., 3,580,588.
- Delair, Jean-Paul: *See—*
 Voisin, Eugene; Raisin, Jean-Pierre; and Delair, Jean-Paul, 3,580,012.
- Delaware Valley Armaments, Inc.: *See—*
 Cheney, Oliver F., 3,580,046.
- Delong, William T., to McKay Company, The. Welding flux component. 3,580,748, Cl. 148-26.
- Delort, Pierre A. Sanitary towel. 3,580,252, Cl. 128-290.
- DeMan, Heiko T., to Electronic Dispensers International. Beverage dispenser. 3,580,425, Cl. 222-129.1
- Demler, Walter R.; and Jachlewski, Arthur F., to Allied Chemical Corporation. Process for preparation of naphthyridine dione dyestuffs. 3,580,919, Cl. 260-295.
- Denes, Peter A. Magnetic core memory array. 3,581,295, Cl. 340-174.
- Dennison, William G., to Cutter-Hammer, Inc. Push-pull electric switch operator. 3,581,036, Cl. 200-172.
- Densmore, William P., to Norton Company. Abrasive wheel. 3,579,925, Cl. 51-330.
- De Pauw, Robert C. Toboggan. 3,580,598, Cl. 280-18.
- De Pentti, Kenneth L., to Midland-Ross Corporation. Rotary uncoupling devices. 3,580,400, Cl. 213-166.

Depenti, Kenneth L.: *See—*
Willison, Donald; and Depenti, Kenneth L., 3,580,399.

De Santis, Italo J.: *See—*
Nejame, Samuel, Jr.; Kondel, George C.; and De Santis, Italo J., 3,580,301.

De Shay, Robert V.: *See—*
Isaksen, Robert A.; and De Shay, Robert V., 3,580,972.

Dessauer, Hans J., to Beaunit Corporation. Cake wrapping device. 3,579,961, Cl. 53-390.

De Torre, John; and Wingard, Henry S., to Federal Pacific Electric Company. Molded case circuit breaker having an auxiliary contact separating spring. 3,581,261, Cl. 337-67.

Deussner, Herbert; and Langmaack, Jurgen, to Klockner-Humboldt-Deutz Aktiengesellschaft. Device for feeding pulverulent materials. 3,579,850, Cl. 34-57.

Deutsche Gold- und Silber-Scheideanstalt vormals Roessler: *See—*
Fratzcher, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, 3,580,844.

Heimberger, Werner; and Schmitt, Hermann, 3,580,912.

Klein, Kurt; Lumbeck, Gerd; and Maluzi, Joachim, 3,580,519.

De Varda, Giorgio: *See—*
Martinelli, Saverio; and De Varda, Giorgio, 3,581,016.

de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignet, Paul, to Commissariat a l'Energie Atomique. Sea water multistage distillation process with common reheating means. 3,580,818, Cl. 203-11.

De Voss, Edwin A.; and Guerreiro, Antone M. Tube bending mandrel. 3,580,044, Cl. 72-466.

De Vries, Adrian J.; and Wojcik, Thomas J., to Zenith Radio Corporation. Acoustic filters. 3,581,248, Cl. 333-72.

De Vries, Robert W., to Wolverine Brass Works. Single lever valve for automatic washers. 3,580,283, Cl. 137-625.18.

Diamond Alkali Company: *See—*
Lasco, Ralph H., 3,580,854.

Diamondhead Properties, Inc.: *See—*
Koll, Laurel A.; and Crook, Walter, Jr., 3,579,672.

Di Bartolo, Ernest A.: *See—*
Stark, Donald A.; Di Bartolo, Ernest A.; Feather, Harry A.; and Sundin, Charles H., 3,579,989.

DiBlasi, Rosario. Wheel collapsible frame. 3,580,348, Cl. 180-25.

Dick, Werner: *See—*
Hammann, Heinz; and Dick, Werner, 3,580,551.

Dickson, Leon L., Jr.: *See—*
Broussard, Leo P.; Dickson, Leon L., Jr.; and Gardenier, Wilhelmus J. G., 3,580,334.

Diebold Incorporated: *See—*
Hammond, Robert A.; and Presta, Eugene A., 3,580,998.

Sandorf, Robert E.; and Hammond, Robert A., 3,580,993.

Diebold, James L.: *See—*
Wolf, Milton; and Diebold, James L., 3,580,915.

Diehl: *See—*
Meisner, Alfred; and Spitzl, Walter, 3,581,128.

Diehl, Charles G., to Save Fuel Corporation. Automatic damper means. 3,580,238, Cl. 126-295.

Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, to Farbenfabriken Bayer Aktiengesellschaft. Polyisocyanurate resin and foam formation catalyzed by Mannich bases. 3,580,868, Cl. 260-2.5.

Diehr, Hans Joachim: *See—*
Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.

Dieterich, Frank L. Method and blank for making potentiometer contact springs. 3,579,822, Cl. 29-630.

Dietz, Johannes. Silent butler. 3,580,396, Cl. 211-88.

Dilday, Joseph T., to Olin Corporation. Coated fertilizer. 3,580,715, Cl. 71-28.

Dill, Frederick H., Jr., to International Business Machines Corporation. Method for fabricating a semi-conductor device having an epitaxially grown region. 3,579,814, Cl. 29-578.

Dill, Onnie R. Vibratory massaging device. 3,580,245, Cl. 128-33.

Di Luco, Eugene W. Demountable wig stand. 3,580,436, Cl. 223-66.

Dinorwic Slate Quarries Company Limited: *See—*
Lombos, Lazlo; and Hughes, Michael Robert, 3,580,235.

Di Paolo, Peter T., Jr.; and Carbine, Joseph C., to Burroughs Corporation. Unitary bi-stable code wheel for mechanical conveyors and sorting apparatus. 3,579,778, Cl. 29-110.

Dixon, Lloyd H., Jr., to Unitrode Corporation. Thyristor circuit having improved turn-off characteristics. 3,581,117, Cl. 307-252.

Djenner, Richard, to Olaf Bendik Elmer. Hair curler having a high heat storage core telescopically mounted therein. 3,581,056, Cl. 219-222.

Dmitrenko, Viktor Makarovich: *See—*
Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich, 3,580,554.

D'Muha, Thomas F. Electronic timepiece. 3,579,976, Cl. 58-50.

Doane, James E.; and Sheriff, Robert C. Banding apparatus for stacked articles. 3,580,786, Cl. 156-475.

Dobell, Curzon; and Wilson, Leslie P., to Caribbean Holdings Ltd., mesne. Method and apparatus for making elongated vessels, containers and tubular members. 3,580,461, Cl. 228-15.

Dodds, Wellesley Jamison, to RCA Corporation. Display device for providing gratitudes of various configurations. 3,581,002, Cl. 178-7.84.

Dodgen Industries, Inc.: *See—*
Dodgen, John N.; and Johnson, Kenneth R., 3,580,599.

Dodgen, John N.; and Johnson, Kenneth R., to Dodgen Industries, Inc. Jack and tie-down system for a vehicle mounted camper. 3,580,599, Cl. 280-34.

Doherty, Martin C., to General Electric Company. Fluidic speed governor. 3,580,086, Cl. 73-506.

Dolan, Jose P., to Institute of Gas Technology, The. Cooling apparatus and process for heat-actuated compressors. 3,580,003, Cl. 62-115.

Dolbachian, Raymond; and Lefevre, Claude, to U.S. Philips Corporation. Electronic arrangement for controlling an electromagnetic clutch. 3,581,156, Cl. 317-123.

Dominion Auto Accessories Limited: *See—*
Magi, Hugo, 3,581,080.

Dominion Luggage Co., Limited: *See—*
Slam, Jack, 3,579,804.

Domke, Klaus: *See—*
Buchner, Norbert; and Domke, Klaus, 3,579,945.

Donadio, Vincent J.; and Anderson, Olavi F., to United States of America, Army. Manufacturing apparatus. 3,580,031, Cl. 72-186.

Dopner, Horst, to Telefunken Patentverwertungsgesellschaft m.b.H. Arrangement maintaining constant tape tension in magnetic tape recorders. 3,580,525, Cl. 242-189.

Dorner, Armin, to Linde Aktiengesellschaft. Process and apparatus for process control in cracking furnaces for the thermal cracking of hydrocarbons. 3,580,959, Cl. 260-683.

Dornfeld, John E., to Sprague Electric Company. Non-tracking wire spark gap component. 3,581,143, Cl. 313-325.

Dorr-Oliver Incorporated: *See—*
Logan, Robert P.; and Albertson, Orris E., 3,580,193.

Dostourian, Harry: *See—*
Beguin, Fred P.; and Dostourian, Harry, 3,579,640.

Douglas, Bobby L., to Dresser Industries Inc. Well liquid removal device. 3,580,333, Cl. 166-224.

Dow Badische Company: *See—*
Nishimura, Akihiro, 3,580,874.

Dow Chemical Company, The: *See—*
Mandrell, Melford E.; and Blaser, Wayne W., 3,580,067.

Martin, Fred D., 3,581,204.

Mintz, Michael J., 3,580,831.

Morris, Leo R., 3,580,948.

Mussell, Dorsey R.; and Schwartzbeck, Richard A., 3,580,716.

Spence, Thomas C., 3,580,801.

Trepanier, Donald L., 3,580,943.

West, Walter H., 3,579,733.

Dow Corning Corporation: *See—*
Culpepper, Alan L., 3,580,920.

Dragos, Ion: *See—*
Iliescu, Liviu; and Dragos, Ion, 3,580,682.

Drake, Lewis A.: *See—*
Waltz, Marion D.; and Drake, Lewis A., 3,580,022.

Dravis, Donald P.: *See—*
Lamp, Richard W.; Kopf, Joseph E.; Dravis, Donald P.; and Cueno, Robert A., 3,580,981.

Dresser Industries Inc.: *See—*
Douglas, Bobby L., 3,580,333.

Dreyer, Heinz: *See—*
Perthen, Johannes; Gerighausen, Werner; Kunzmann, Konrad; and Dreyer, Heinz, 3,580,062.

Driscoll, Gary L., to Sun Oil Company. Curable linear polyesters. 3,580,964, Cl. 260-871.

Dubost, Pierre J.; and Perret, Henri. Apparatus for the systematic correction and selective appreciation of teaching tests. 3,579,875, Cl. 35-48.

Duchek, Ernest J., to Powers Regulator Company. Thermostatic pressure transmitter. 3,580,502, Cl. 236-102.

Duennenberger, Max: *See—*
Anliker, Rudolf; Duennenberger, Max; Schmid, Karl; and Siegrist, Adolf Emil, 3,580,924.

Duerink, Steven; and Steenvoort, Leendert. Package for solid pieces of foodstuffs or the like and method for manufacturing such packages. 3,580,463, Cl. 229-2.5.

Duffy, Richard J., to USM Corporation. Methods of making self-locking threaded elements. 3,579,684, Cl. 10-10.

Dumas, Pierre: *See—*
Schuette, Thomas L.; Straub, Melvin J.; Dumas, Pierre; and Aurich, Peter F., 3,579,771.

Duncan, William R. Automatic pilot. 3,580,206, Cl. 114-144.

Dunn, Jane M. Apparatus for holding pets. 3,580,222, Cl. 119-102.

Dunn, William H., Jr., to Grace, W. R., & Co. Vacuum apparatus and snorkel nozzle. 3,580,300, Cl. 141-65.

Dunwoodie, Duane E., to Wilton Company. Linear voltage controlled attenuator. 3,581,222, Cl. 330-29.

Du Pont de Nemours, E. I., and Company: *See—*
Barney, Arthur Livingston; and Honsberg, Wolfgang, 3,580,889.

Barnhard, Philip, IV, 3,580,754.

Bianca, Dominick, 3,580,873.

Hick, Robert M., Jr.; and Gould, Joseph C., 3,580,796.

Hyde, Thomas J.; and Targonski, Leonard A., 3,580,577.

Lang, Frederic A., 3,579,931.

Manos, Philp, 3,580,925.

Dupre, Jean, to Rohm and Haas Company. Stabilized nonionic surfactants in solid formulations containing active chlorine compounds. 3,580,850, Cl. 252-99.

Du Priest, Florence. Stadium foot bag and seat. 3,580,633, Cl. 297-184.

Dura Corporation: *See—*
Mc Gee, Donald J., 3,580,347.

Duthoit, Jean: *See—*
Plumat, Emile; and Duthoit, Jean, 3,579,720.

Dyal, Gilford E., to Tripco, Inc. Method for producing laminated structures. 3,580,770, Cl. 156-216.

Dyer, Arthur M. Toilet tank and guide for flush control valve. 3,579,649, Cl. 4-56.

Dynamics Corporation of America: *See—*
Valbona, Bruno M., 3,581,028.

Dynamit Nobel Aktiengesellschaft: *See—*
Gawlick, Heinz; Stahlmann, Rudolf; and Umbach, Hans, 3,580,179.

Gawlick, Heinz; and Marondel, Gunther, 3,580,180.

Eastburn, Francis J.: *See—*
Gulstad, Clayton O.; and Eastburn, Francis J., 3,580,728.

Eastman Kodak Company: *See—*
Beeler, Robert S., 3,580,669.

Casebeer, Oran T., 3,580,157.

Chuhua, Thomas A., 3,580,452.

Claar, Hermann, 3,580,668.

Ettischer, Helmut, 3,580,154.

Harvey, Donald M., 3,580,148.

Mee, John D.; and Heseltine, Donald W., 3,580,911.

Moore, Robert B., Jr., 3,580,445.

Romano, Paul, 3,581,058.

Eaton, Calley Neil: *See—*
Bernasek, Edward; and Eaton, Calley Neil, 3,580,906.

Eaton Yale & Towne, Inc.: *See—*
Bauerlein, Carl C., 3,580,007.

Beatty, Robert D., Jr.; and Griffiths, Thomas C., 3,581,277.

Chute, Richard; and Berryman, Charles O., 3,580,603.

Nearman, Richard E., 3,580,382.

Ebauches S.A.: *See—*
Besson, Rene; and Chopard, Remy, 3,579,975.

Ebeling, William C., to Singer-General Precision, Inc. Visual display method and apparatus. 3,580,978, Cl. 35-10.2.

Ebert, Michael: *See—*
Altman, Norman G., 3,581,282.

Eckert, George: *See—*
Ciriack, Gunter; Eckert, Georg; and Hofmann, Horst, 3,580,739.

Eckert, John Presper, Jr.: *See—*
Fedde, George A.; and Eckert, John Presper, Jr., 3,581,293.

Eddington, Lloyd H. Record book. 3,579,871, Cl. 35-66.

Edson, Jerry W. Portable boat ramp. 3,579,996, Cl. 61-66.

Edwards, Albert, to British Cast Iron Research Association. Apparatus for making foundry cores and moulds. 3,580,326, Cl. 164-200.

Edwards, George Zahnor: *See—*
Davis, Frank J.; and Edwards, George Zahnor, 3,579,638.

Edwards, John C., Sr. Gizzard processing device. 3,579,714, Cl. 17-11.

Eggstein, Giorgio; and Ungerer, Heinz, to Heinkel, Ernst Aktiengesellschaft. Disk brake construction. 3,580,361, Cl. 188-72.4.

Eguchi, Yasuhito; Fujiwara, Yoshio; and Tohma, Takaaki, to Sony Corporation. Multi-head magnetic recording and reproducing device for video signals featuring head switching in the record mode. 3,580,992, Cl. 178-6.6.

Ehngelsmann, Dieter; Schroder, Rolf; and Becker, Erwin, to Agfa-Gevaert Aktiengesellschaft. Photographic apparatus. 3,580,152, Cl. 95-31.

Ehrenberg, Hermann, to Fouquet-Werk Frauz & Planck. Pipe union. 3,580,617, Cl. 285-340.

Ehrens, Henry; and Weiner, Sidney. Sealed Unit Parts Co., Inc. Debrisless tap valve with backraked piercing element. 3,580,269, Cl. 137-318.

Ehrhorn, Richard W.: *See—*
Maitland, Peter; and Ehrhorn, Richard W., 3,581,211.

Ehrlich, Stanley V., to Western Manufacturing, Inc. Apparatus for chipping scrap materials. 3,580,517, Cl. 241-186.

Eichenlaub, John E. Apparatus for welding heat sealable sheet material. 3,580,795, Cl. 156-583.

Eichert, Edwin S.; and Storey, William T., II, to Technitrol, Inc. Delay line having non planar ground plane, each loop bracketing two runs of meandering signal line. 3,581,250, Cl. 333-31.

Eichman, Ellis V. Frame structure for glass or solid panel walls. 3,579,939, Cl. 52-397.

Eickenhorst, Franklin C., to Dayton Reliable Tool & Mfg. Company. Fluidic device. 3,580,264, Cl. 137-81.5.

EIS Automotive Corporation, The: *See—*
Schwarz, Ernest I., 3,580,273.

Eisberg, Keith V., to Carrier Corporation. Absorption refrigeration machine with concentration control tank. 3,580,001, Cl. 62-101.

Eisenberg, Edith Brown. Tables having positions of use and non-use. 3,580,189, Cl. 108-3.

Eisenmenger, Irving V., to Western Electric Company, Incorporated. Single output selecting circuit employing a plurality of interlocked nor-gates. 3,581,108, Cl. 307-215.

Electric Conductor Bearings, Incorporated: *See—*
Schreffler, Robert Z., 3,581,267.

Electro-Lifts Limited: *See—*
Warnett, Kenneth, 3,581,127.

Electronic Dispensers International: *See—*
DeMan, Heiko T., 3,580,425.

Electronic Transmission Systems, Inc.: *See—*
Priessnetz, Edmund F., 3,581,257.

Elitex, Zavody textilnih strojarenstvi: *See—*
Rambousek, Zdenek, 3,580,292.

Ellert, Georgy Vladimirovich: *See—*
Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkina, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich, 3,580,859.

Elliot Laboratories, Inc.: *See—*
Ericson, Richard E., 3,579,652.

Elliot, Michael. Article holder. 3,580,394, Cl. 211-60.

Elmy, Richard A., to Westinghouse Electric Corporation. Pop-out lint trap and door interlock for laundry apparatus. 3,579,851, Cl. 34-82.

Eloranta, Walter G. Electronic actuator and timer circuit. 3,581,300, Cl. 340-309.1.

Emhart Corporation: *See—*
Mc Intyre, Daniel, 3,580,143.

Emslie, Norman M.: *See—*
Bar-On, Ari; and Emslie, Norman M., 3,580,064.

Enderby, Ralph T., to Motorola, Inc. Frequency modulated solid state crystal oscillator providing a plurality of center frequencies. 3,581,240, Cl. 332-26.

Endle, Joseph, to Polymer Corporation, The. Method of electrolytic tinning sheet steel. 3,580,289, Cl. 204-34.

Engel, Jean-Pierre: *See—*
Wichoud, Michel; and Engel, Jean-Pierre, 3,580,526.

Engelhard, Helmut; Bentz, Francis; Rinkler, Heinrich; and Nischk, Gunther, to Farbenfabriken Bayer Aktiengesellschaft. Graft copolymers of acrylonitrile onto a linear polyether having quaternized nitrogen atoms. 3,580,966, Cl. 260-898.

Engelhardt, Robert C.: *See—*
Neema, Farid J.; and Engelhardt, Robert C., 3,581,285.

Engels, Edward P. X-ray table attachment. 3,581,088, Cl. 250-55.

Engineered Products Company, The: *See—*
Pietsch, Raymond L., 3,579,934.

Engis Equipment Company: *See—*
Panko, Walter B.; and Steindler, Julius P., 3,579,912.

English Electric Valve Company Limited: *See—*
Banks, Peter Baldwin, 3,580,709.

Enkvist, Ernst: *See—*
Burmeister, Fred; Enkvist, Ernst; Johansson, Bengt; and Kostilainen, Valter, 3,580,204.

Entwistle Company, The: *See—*
Cooper, Beresford B., 3,579,731.

Eppich, Robert E.; and Webber, Fred J., to General Motors Corporation. Mold for improved control of heat transfer in casting plate or strip products. 3,580,328, Cl. 164-283.

E. P. S. (Research & Development) Limited: *See—*
Hawley, Edwin L., 3,579,747.

Ericson, Richard E., to Elliot Laboratories, Inc. Sanitary urine collector. 3,579,652, Cl. 4-110.

Erie Technological Products, Inc.: *See—*
Veater, Donald J.; Hill, Sumner B.; and Ruffner, Lawrence J., 3,581,167.

Eriksson, Birger Sture Erik, to Aktiebolaget Jonkoping-Vulcan. System for distributing and advancing objects. 3,580,640, Cl. 302-2.

Eriksson, Gustave Ragnar, to Saab Aktiebolag. Means for exposing normally covered plate while moving it to exposure situation. 3,580,685, Cl. 356-244.

Eriksson, Lars O., to General Electric Company. High-current semiconductor rectifier assemblies. 3,581,163, Cl. 317-234.

Erman, William F.: *See—*
Fanta, Wayne I.; and Erman, William F., 3,580,953.

Fanta, Wayne I.; and Erman, William F., 3,580,954.

ESB Incorporated: *See—*
Hills, Stanley, 3,580,825.

James, Herbert I., 3,580,740.

Esenwein, Fred T.: *See—*
Cardwell, Lonnie D.; Esenwein, Fred T.; and Picard, Arthur E., 3,580,049.

Eshuis, Jannes; and Tjebbes, Horatius, to Algemene Kunstzijde Unie N.V. Method of opening crimped yarn. 3,579,765, Cl. 28-72.16.

Eskimo Pie Corporation: *See—*
Leonard, Edwin Clifton, 3,580,470.

Esmond, William G. Artificial heart. 3,579,644, Cl. 3-1.

Essex International, Inc.: *See—*
Newman, La Verne R., 3,581,276.

Esso Research and Engineering Company: *See—*
Kroll, Wolfram R., 3,580,938.

Pfrehm, Raymond H., 3,580,045.

Spenadel, Lawrence, 3,580,867.

Etablissements MACHET: *See—*
Machet, Adrien, 3,580,173.

Etablissements Valois: *See—*
Angele, Henry, 3,580,430.

Etat Francais represente par le Ministre des Armees, Delegation Ministerielle pour l'Armement: *See—*
Robert, Andre; Bourdon, Claude; and Le Goer, Jean Luc, 3,580,681.

Ethyl Corporation: *See—*
Beaubier, Richard C., 3,581,141.

Perilstein, Warren L., 3,580,707.

Yang, Meiling T., 3,580,852.

- Ettischer, Helmut, to Eastman Kodak Company. Operating mechanism for mirror reflex camera. 3,580,154, Cl. 95-42.
- Evans, Francis E.: See—
Cheng, Chao-Shing; and Evans, Francis E., 3,580,857.
- Evans, Francis E.; and Cheng, Chao-Shing, to Allied Chemical Corporation. Stable liquid anhydride compositions. 3,580,858, Cl. 252-182.
- Evans, Ivor: See—
Clarke, Terence J.L.; and Evans, Ivor, 3,580,774.
- Evans, Josie V.: See—
Clarke, Terence J.L.; and Evans, Ivor, 3,580,774.
- Evans, Raymond Victor, to Singer-Cobble Limited. Yarn guide. 3,580,454, Cl. 226-198.
- Eveleth Taconite Company: See—
Urich, Daniel M., 3,580,553.
- Everett, Samuel R.: See—
Shear, Wayne G.; Everett, Samuel R.; and Olmstead, Merlin E., 3,581,309.
- Everson, Ivor; and George, Maurice William, to United Kingdom Atomic Energy Authority. Nuclear reactors. 3,580,803, Cl. 176-28.
- EVG Entwicklungs und Verwertungs-Gesellschaft m.b.H.: See—
Gott, Hans; and Ritter, Josef, 3,580,018.
- Ex-Cell-O Corporation: See—
Leone, William C.; and Malone, Robert Lee, 3,581,003.
- Excelmatic, Inc.: See—
Kraus, Charles E., 3,580,094.
- Expando Products Company: See—
Triplett, Lee, 3,580,397.
- Explosives Corporation of America: See—
Maes, Michael E., 3,580,171.
- Extel Corporation: See—
Fulton, John, 3,581,005.
- Fairbanks, John P.: See—
Trindle, John P., 3,580,429.
- Fairbanks, Theodore H., to FMC Corporation. Apparatus for extruding net-like structures. 3,579,729, Cl. 18-12.
- Falco, Eugenio. Improvement in miniaturized potentiometers. 3,581,265, Cl. 338-174.
- Falk, Edward J., to Wagner Electric Corporation. Disc brake. 3,580,362, Cl. 188-73-4.
- Fanta, Wayne I.; and Erman, William F., to Procter & Gamble Company. The. Preparation of 3-endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl) norcamphor from 2-methyl-4-pentenol. 3,580,953, Cl. 260-586.
- Fanta, Wayne I.; and Erman, William F., to Procter & Gamble Company. The. Preparation of 3-endo-methyl-3-exo(4'-methyl-5'-hydroxypentyl)norcamphor from 2-methyl-4-pentenol. 3,580,954, Cl. 260-586.
- Farbenfabriken Bayer Aktiengesellschaft: See—
Arlt, Dieter, 3,580,942.
- Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,868.
- Engelhard, Helmut; Bentz, Francis; Rinkler, Heinrich; and Nischk, Gunther, 3,580,966.
- Gunther, Peter; Oberkirch, Wolfgang; and Pampus, Gottfried, 3,580,892.
- Schmidt, Wolfgang; Kraft, Karl-Josef; and Kurth, Willi, 3,579,722.
- Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.
- Farber, Elliott, to Tenneco Chemicals, Inc. Aqueous suspension polymerization of vinyl halide polymers in the presence of acrylic acid. 3,580,896, Cl. 260-87.1
- Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning: See—
Brinkmann, Ludwig; Cherdron, Harald; and Herwig, Walter, 3,580,965.
- Geymayer, Peter; Billenstein, Siegfried; and Renz, Werner, 3,580,849.
- Kurzke, Herbert; Goltner, Wolfgang; and Seifried, Walter, 3,580,963.
- Moschel, Albrecht, 3,580,952.
- Mundlos, Eberhard; Mohr, Reinhard; Trapp, Gunther; and Hohmann, Kurt, 3,580,900.
- Rauterkus, Karl Josef; and Vollmann, Hansjorg, 3,580,871.
- Wenzel, Gunter, 3,580,789.
- Farmhand, Inc.: See—
Moore, Carroll E., 3,580,548.
- Farrand Optical Co., Inc.: See—
La Russa, Joseph, 3,580,660.
- Farrell, Claude S., Jr., to Cory Corporation. Variable capacity coffee percolator. 3,580,163, Cl. 99-310.
- Farrer, Sydney, to Bryan Donkin Company Limited, The. Gas pressure regulators. 3,580,271, Cl. 137-458.
- Fauber, Eugene M.: See—
Moyer, Hallard C.; and Fauber, Eugene M., 3,580,736.
- Faukner, Kenneth F.: See—
Moore, Robert D., 3,580,667.
- Faulkner, James M. Suspending device for garments. 3,579,639, Cl. 2-117.
- Favreau, Ernest: See—
Fraser, Colin Kenneth Glenn; Favreau, Ernest; and March, Willis Paul, 3,580,546.
- Feather, Harry A.: See—
Stark, Donald A.; Di Bartolo, Ernest A.; Feather, Harry A.; and Sundin, Charles H., 3,579,989.
- Fedde, George A.; and Eckert, John Presper, Jr., to Sperry Rand Corporation. Form of plated wire memory device. 3,581,293, Cl. 340-174.
- Federal Auto Products Co., Inc.: See—
Phillips, Virgil, 3,580,424.
- Federal Pacific Electric Company: See—
De Torre, John; and Wingard, Henry S., 3,581,261.
- Federal-Mogul Corporation: See—
Nueman, William H.; and Repella, James A., 3,580,061.
- Feeman, James F., to Crompton & Knowles Corporation. Maroon diazo dyes for polyamide fibers. 3,580,901, Cl. 260-191.
- Feinberg, Emanuel M. Process for manufacturing press-free, resinated, double-face, interlock knit fabric. 3,579,766, Cl. 28-74.
- Fenner, Robert M.; and Hamilton, Donald E. Foldable trampoline. 3,580,570, Cl. 272-65.
- Ferag, Fehr & Reist AG: See—
Reist, Walter, 3,580,562.
- Ferguson, James L.: See—
Goldberg, Newton N.; and Ferguson, James L., 3,580,864.
- Ferkovich, Edward F. Thread conditioning and restoring tool. 3,579,689, Cl. 10-140.
- Fernseh GmbH: See—
Krause, Gerhard, 3,580,991.
- Fetter, Paul E. Utility hump seat and double tray. 3,580,630, Cl. 297-125.
- Fetzer, Gustav; and Freytag, Gerhard, to Zinser-Textilmaschinen Gesellschaft mit beschränkter Haftung. Stop mechanism for a rotary textile spindle. 3,579,973, Cl. 57-88.
- Fichtel & Saahs AG: See—
May, Michael, 3,580,229.
- Fichtner, Rudi; Ober, Horgern; and Klein, Wilhelm, to USM Corporation. Shoe lasting machines. 3,579,691, Cl. 12-12.4
- Field, Joseph H.: See—
Myers, John G.; and Field, Joseph H., 3,580,702.
- Fields, Joseph E.: See—
Nielsen, Lawrence E.; and Fields, Joseph E., 3,580,882.
- Fike, Elmer A., to Security Chemicals, Inc. Antiozonants. 3,580,885, Cl. 260-45.8
- Filipowicz, Leon: See—
Clarke, Michael Raymond; and Filipowicz, Leon, 3,580,880.
- Fillion, Walter A. Puller device for generally cylindrical stem assemblies or valves. 3,579,796, Cl. 29-263.
- Filper Corporation: See—
Kilner, George E., 3,580,381.
- Finn Industries, Inc., The: See—
Bates, Tex, 3,579,954.
- Firestone Tire & Rubber Company, The: See—
Hollis, Jack Lyndon; and Shockey, Ray Douglas, 3,580,781.
- Firth, Donald; Hancock, Roger Harvey Yorke; and McCallum, James, to National Research Development Corporation. Hydrostatic transmission control system. 3,579,988, Cl. 60-53.
- Fisher Governor Company: See—
Schuder, Charles B.; Skov, Victor E.; and Lytle, Richard F., 3,580,288.
- Fisher, James J.: See—
Noonan, Michael F.; and Fisher, James J., 3,580,573.
- Fisher, John T., to Carrier Corporation. Freeze limiting absorption refrigeration machine. 3,580,002, Cl. 62-101.
- Fisher, Sidney L., to Spider Staging, Inc. Universal joint. 3,580,010, Cl. 64-9.
- Fizicheskoy Institute IM. P. N. Lebedeva: See—
Korablev, Lev Nickolaevich, 3,581,147.
- Fjallbrant, Tore Torstensson, to Telefonaktiebolaget L M Ericsson. Filter arrangement. 3,581,246, Cl. 333-24.1
- Flanagan, Kirby E. L.: See—
Rhodes, Richard D., Jr.; and Flanagan, Kirby E. L., 3,580,869.
- Fleco Corporation: See—
Frankenberg, Edward V.; and Griffith, Norman N., 3,580,310.
- Flo-Tronics, Inc.: See—
Schmit, Wilfred W., 3,581,299.
- Flores, Richard A.; and Sherman, Michael. Solid state touch responsive switch circuit. 3,581,124, Cl. 307-308.
- Flottorp, Thomas. Spring operated fishing rod device. 3,579,896, Cl. 43-19.
- Flower, William. Analog meter having means to provide a digital reading of the pointer position. 3,581,203, Cl. 324-96.
- Floyd, Johnnie E. Stair negotiating wheel chair or an irregular terrain negotiating vehicle. 3,580,344, Cl. 180-8.
- Fluid Controls, Inc.: See—
Stark, Donald A.; Di Bartolo, Ernest A.; Feather, Harry A.; and Sundin, Charles H., 3,579,989.
- Flynn, John F. Vented leaching channel. 3,579,995, Cl. 61-13.
- FMC Corporation: See—
Fairbanks, Theodore H., 3,579,729.
- Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
- Stewart, Mary J.; and Price, John A., 3,580,886.
- Stock, David K.; and Wech, Robert J., 3,580,142.
- Folan, Martin P.: See—
Vogel, Alvin R.; Moore, Douglas A.; Folan, Martin P.; and Buck, John R., 3,581,014.

- Foldenauer, Ralph M., to Bloomer-Fiske, Inc. Meat mold. 3,580,165, Cl. 99-351.
- Folding Cartons, Inc.: See—
Cannon, Lester E.; Tindall, John M.; and Taylor, Howard N., 3,580,476.
- Forbro Design Corporation: See—
Nercessian, Sarkis, 3,581,224.
- Ford Motor Company: See—
Mitchell, James W., Jr., 3,581,047.
- Wargo, William, 3,580,331.
- Fordyce, David B.: See—
Mickus, James C.; Fordyce, David B.; and Mansfield, Richard C., 3,580,855.
- Foreman, Dave O. Motor operated vibrator having solar type motion. 3,580,246, Cl. 128-36.
- Forkner, John F. Light display instrument. 3,580,126, Cl. 84-464.
- Fort Wayne Metals, Inc.: See—
Glaze, Ardelle, 3,580,783.
- Fortson, Warren D. Control and mounting system for electric trolling motor. 3,580,212, Cl. 115-18.
- Fosindus Company: See—
Pavonet, Engelhard, 3,580,703.
- Foundry Suppliers Inc.: See—
Klempner, George R.; and Rosenberg, Sam, 3,579,784.
- Fouquet-Werk Frau & Planck: See—
Ehrenberg, Hermann, 3,580,617.
- Fowler, Timothy J., to Monsanto Company. Pallet construction. 3,580,190, Cl. 108-58.
- Fox, Edward L., Jr., to Canadian Cedar Inc. Process for treating wood. 3,580,311, Cl. 144-309.
- Fr. Hesser Maschinenfabrik Aktiengesellschaft: See—
Buchner, Norbert; and Domke, Klaus, 3,579,945.
- Fraitzl, Raimund, to Bruckner-Maschinenbau Gernot Bruckner. Clamp block chain for holding one edge of a web of material. 3,580,451, Cl. 226-173.
- Francis, Peter S.: See—
Cadotte, John E.; and Francis, Peter S., 3,580,841.
- Frank, Emil A., 50% to Frank, Ronald L. Pipe connector. 3,579,670, Cl. 4-252.
- Frank, Ronald L.: See—
Frank, Emil A., 3,579,670.
- Frank, George G. F., to Leitz, Ernest, G.m.b.H. Toric imaging lens for slot sensors for satellites. 3,581,099, Cl. 250-216.
- Frankenberg, Edward V.; and Griffith, Norman N., to Fleco Corporation. Tree shear device with blade. 3,580,310, Cl. 144-34.
- Franklin, Edmond G.: See—
Arndt, John P.; and Franklin, Edmond G., 3,581,125.
- Fransen, Theodor, to N.V. Machinefabriek L. Te Strake. Weaving machine. 3,580,293, Cl. 139-303.
- Frantz Manufacturing Company: See—
Wolf, Cecil R.; and Holland, John P., 3,579,809.
- Fraser, Colin Kenneth Glenn; Favreau, Ernest; and March, Willis Paul, to Kaydon Technical Enterprises Ltd. Device for mixing and proportioning liquids. 3,580,546, Cl. 259-4.
- Fraser, Douglas S.: See—
Bender, Charles E.; and Fraser, Douglas S., 3,580,812.
- Fratzscher, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler. Method of processing oil emulsions used in metal machining. 3,580,844, Cl. 210-40.
- Freeman, Alfred. Heat setting of footwear. 3,579,849, Cl. 34-48.
- Freermann, Hans, to Schmale, Carl, Firma. Apparatus for folding, feeding and pressing pieces of fabric material. 3,579,876, Cl. 38-2.
- Freiberg, Robert J., to United States of America, Air Force. Ultra-stable laser cavity mirror support assembly. 3,581,231, Cl. 331-94.5
- French, Richard P., to Continental Can Company, Inc. Lock for egg carton cover. 3,580,480, Cl. 229-45.
- French State, represented by the Minister of Armed Forces Ministerial Delegation of Weapons, Technical Delegation of Land Weapons Manufacturing Workshops of Tarbes: See—
Huberdeau, Gerard, 3,579,806.
- Frey, Dean R.; Hone, George L.; and Ramsey, Edward L., Jr., to Bell Telephone Laboratories, Incorporated. Connector for coaxial cable. 3,581,269, Cl. 339-94.
- Freytag, Gerhard: See—
Fetzer, Gustav; and Freytag, Gerhard, 3,579,973.
- Frieling, Gerald H., Jr., to Texas Instruments, Incorporated. Metal strand having a chromium steel core and corrosion-resistant cladding. 3,580,706, Cl. 29-196.3
- Fritchey, Edward H.: See—
Cvacho, Daniel S.; and Fritchey, Edward H., 3,580,200.
- Fritzche, Harold L., to General Electric Company. Apparatus for compressing laminated cores. 3,579,788, Cl. 29-205.
- Frowds Limited: See—
Buckley, Trevor, 3,581,310.
- Fry, William H.; and Zerba, Lawrence G., to Construction Machinery Company. Auxiliary chute hold-down means for a truck mounted concrete mixer. 3,580,440, Cl. 224-42.31
- Fudger, Shirley L. W.: See—
Boot, Herbert W.; Parr, Leslie R.; and Fudger, Shirley L. W., 3,579,695.
- Fuerst, Ernst; and Weitz, Hans-Martin, to Badische Anilin- & Soda-Fabrik Aktiengesellschaft. Recovery of aromatic hydrocarbons from mixtures of hydrocarbons by selective extraction with a substituted piperazine solvent. 3,580,839, Cl. 208-326.
- Fuji Denki Kogyo Co., Ltd.: See—
Moriya, Nobuharu, 3,579,719.
- Fuji Motors Corporation: See—
Itoh, Yoshishige; Kawamura, Masatada; and Kasai, Yoshio, 3,580,637.
- Fuji Shashin Film Kabushiki Kaisha: See—
Fujisawa, Shin, 3,580,149.
- Fujio, Ryota: See—
Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, 3,580,895.
- Fujisawa, Shin, to Fuji Shashin Film Kabushiki Kaisha. Filter correction device. 3,580,149, Cl. 95-11.
- Fujita, Kozo: See—
Kitano, Yasushi; and Fujita, Kozo, 3,580,355.
- Fujitsu Limited: See—
Kobayashi, Toshio, 3,581,010.
- Fujiwara, Mitsuo: See—
Sakamoto, Kenro; Takahashi, Takao; Koitabashi, Takeo; and Fujiwara, Mitsuo, 3,580,722.
- Fujiwara, Yoshio: See—
Eguchi, Yasuhito; Fujiwara, Yoshio; and Tohma, Takaaki, 3,580,992.
- Fujui Seiren Kako Kabushiki Kaisha: See—
Horie, Hajime; Hirano, Tadao; and Suzuki, Tokihide, 3,580,015.
- Fukuda, Yasuo: See—
Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
- Fukushima, Yoshio, to Kabushiki Kaisha Ricoh. Aperture position selecting system for use with multi-photographic device. 3,580,153, Cl. 95-36.
- Fukushima, Yoshio, to Kabushiki Kaisha Ricoh. Portable traffic sign. 3,580,659, Cl. 350-98.
- Fulton, John, to Extel Corporation. Delayed action tape-failure control for high speed tape printer. 3,581,005, Cl. 178-42.
- Furbeck, Warren R.: See—
Lee, Charles A.; and Furbeck, Warren R., 3,580,784.
- Furby, Neal W.; Godfrey, Douglas; and Peeler, Robert L., to Chevron Research Company. Functional fluids containing carbon dioxide for preventing cavitation damage. 3,580,848, Cl. 252-78.
- Furman, George R., to Texaco Inc. Support assembly for a travel cylinder having rolling contact with the bed of a printing machine. 3,580,170, Cl. 101-269.
- Furstenburg, Alvin J.; and Kujawa, Edmund J. Felt Products Mfg. Co. Method of making a ground mold. 3,579,799, Cl. 29-416.
- Gage, Arthur F.; and Stamm, Alex F., to Rockwell-Standard Company, mesne. Variable position means for holding a non-rotating work-piece in friction welding apparatus. 3,580,459, Cl. 228-2.
- Gaignon, Maurice: See—
Ceyzeriat, Louis; Gaignon, Maurice; and Lefort, Marcel, 3,580,939.
- Gajovski, Frank R. Method for insulating boiler or like housing wall. 3,579,802, Cl. 29-432.2
- Gallasch, Ernst: See—
Schwenk, Kurt; Gallasch, Ernst; Hablitzel, Hermann; and Jacob, Friedrich, 3,579,727.
- Game Innovations, Inc.: See—
McCarthy, James B., 3,580,578.
- Ganter, Wolfgang; and Assmus, Friedrich, to Messrs. Gebruder Junghons Gesellschaft mit Beschränkter Haftung. Tuning fork devices. 3,581,129, Cl. 310-25.
- Garber, Howard A. Ice dispensing machine. 3,580,428, Cl. 222-241.
- Garbrecht, William L., to Lilly, Eli, and Company. Hydroxycesters of hexa- and octahydroindolizines. 3,580,916, Cl. 260-285.5
- Gardenier, Wilhelmus J. G.: See—
Broussard, Leo P.; Dickson, Leon L., Jr.; and Gardenier, Wilhelmus J. G., 3,580,334.
- Garlock Inc.: See—
Merkwacz, Joseph, 3,580,616.
- Garnhart, David L.: See—
Regan, James L.; and Garnhart, David L., 3,579,935.
- Garrett Corporation, The: See—
Horacek, Herbert P., 3,580,265.
- Garrett, Elgie E.; De Franco, Thomas P.; and Staples, Nicholas B., to Admiral Corporation. Color tube electron shield having outwardly bowed edges directed toward viewing screen to minimize seal edge interference. 3,581,135, Cl. 313-85.
- Garrett, Howard R.: See—
Hentges, Ronald L.; and Garrett, Howard R., 3,579,958.
- Garrod, Norman John. Gramophone record sleeves. 3,580,487, Cl. 229-68.
- Gartzke, Rudolf E., to Gartzke's Refrigeration, Inc. Traversable hardware in guideway for shelf or drapery use. 3,579,710, Cl. 16-93.
- Gartzke's Refrigeration, Inc.: See—
Gartzke, Rudolf E., 3,579,710.
- Gaspari, Anthony Mario, to Pall (Canada) Ltd. Sandblasting stencil and method of making same. 3,579,926, Cl. 51-262.
- Gatermann, Willi: See—
Hermes, Heinz; Thieme, Klaus-Dietrich; Gatermann, Willi; Koerv, Peter; and Mehnert, Walter, 3,581,185.
- Gates, Lauren W.: See—
Hill, Fredrick L.; Gates, Lauren W.; and Colbert, William V., 3,579,968.
- Gau, Leonard P., to Chrysler Corporation. Anti-pollution exhaust valve combination with fluidic control and valve cooling features. 3,579,981, Cl. 60-29.

- Gaunt, Wilmer B., Jr., to Bell Telephone Laboratories, Incorporated. All-pass filter circuit having negative resistance shunting resonant circuit. 3,581,122, Cl. 307-295.
- Gauper, Morris S. Toilet tissue holding and dispensing apparatus. 3,580,651, Cl. 312-39.
- Gawlick, Heinz; and Marondel, Gunther, to Dynamit Nobel Aktiengesellschaft. Consumable industrial propellant cartridge. 3,580,180, Cl. 102-101.
- Gawlick, Heinz; Stahlmann, Rudolf; and Umbach, Hans, to Dynamit Nobel Aktiengesellschaft. Ammunition for target practice or other short-range purposes. 3,580,179, Cl. 102-92.7
- Gawrych, Robert I.: See—
Kuzma, John J.; and Gawrych, Robert I., 3,579,891.
- Gay, Pierre, to Compagnie des Ateliers et Forges de La Loire (St. Chamond, Firminy, St. Etienne, Jacob-Holtz). Rolling mill for producing thin strip stock. 3,580,033, Cl. 72-205.
- Gearhart, Harlan G., to VSI Corporation. Method and device for heat treatment of metals. 3,580,555, Cl. 266-4.
- Gebler, Horst: See—
Kegelmann, Gunter; Gebler, Horst; and Seifried, Walter, 3,580,798.
- Gebrüder Boehringer Gesellschaft mit beschränkter Haftung: See—
Weber, Lorenz, 3,580,216.
- GEHAP Gesellschaft fuer Handel und Patentverwertung mbH & Co., K.G., Firma: See—
Schmidt, Karl, 3,579,974.
- Geigy Chemical Corporation: See—
Zergenyi, Janos; and Habicht, Ernst, 3,580,931.
- Gelfenbein, Evgeny Jukhimovich: See—
Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.
- Gellman Industries, Inc.: See—
Provost, Emil L.; and Tomasello, Antonio, 3,580,474.
- Genantonio, Anthony: See—
Batlas, George X., 3,580,510.
- General Electric Company: See—
Arnold, Richard B., 3,579,791.
Arnold, Richard B.; and Smith, Dallas F., 3,579,818.
Beaudoin, Norman R.; and Lauben, Robert W., 3,581,253.
Beggs, James E., 3,581,144.
Bloomer, Milton D., 3,581,234.
Boxman, Raymond L., 3,581,142.
Carlson, Gerald J., 3,579,775.
Doherty, Martin C., 3,580,086.
Eriksson, Lars O., 3,581,163.
Fritzsche, Harold L., 3,579,788.
Gentry, Finis E., 3,579,815.
Hewitt, Terry L., 3,579,869.
Holeman, John M., 3,581,280.
Holtherrichs, Philip D.; and Wanger, Robert P., 3,579,929.
Hovious, Thomas C.; and Torkildsen, Robert A., 3,580,741.
Kast, Howard Berdolt, 3,579,805.
Kidd, Thomas L., Jr.; and McClain, Albert D., Jr., 3,580,755.
Littlefield, Derwood F., 3,580,391.
Loser, Gerhard K., 3,581,026.
Lucek, John R., 3,580,714.
Martin, William S., 3,581,229.
McMurray, William, 3,581,212.
Mosher, Ralph S., 3,580,099.
Pest, Jurgen, 3,581,123.
Piccone, Dante E.; and Rosser, Daniel B., 3,581,160.
Rathbun, William H., 3,581,035.
Sarver, James F.; and Hewes, Ralph A., 3,580,860.
Spangler, Fredrick E.; and Schaefer, Henry A., 3,581,249.
Stahl, Laddie L., 3,580,401.
Young, James Roger, 3,580,052.
Zubler, Edward G., 3,580,856.
- General Electric Company Limited, The: See—
Neild, Donald William, 3,580,496.
- General Foods Corporation: See—
Dame, Charles, Jr., 3,580,726.
Tolf, Ingvar L.; Herzing, Vernon J.; Miller, Everett L.; and Lightfoot, George L., 3,580,402.
- General Impact Extrusions (Manufacturing) Ltd.: See—
Rieder, Otto E., 3,579,767.
- General Mills, Inc.: See—
Gulstad, Clayton O., 3,580,727.
Gulstad, Clayton O.; and Eastburn, Francis J., 3,580,728.
- General Motors Corporation: See—
Arkus-Duntov, Zora, 3,580,350.
Eppich, Robert E.; and Webber, Fred J., 3,580,328.
Hammer, Dale F., 3,581,174.
Heck, Burnette, 3,580,368.
Heck, Burnette, 3,580,369.
Hestad, Erling; Ritter, Thomas E.; and De Claire, Alton G., Jr., 3,580,352.
Hitzelberger, Alan L., 3,580,085.
Kirk, Thomas E.; and Stenkyft, Gerald H., 3,581,150.
Peters, Theodore F., 3,580,623.
Rantala, Charles W., 3,580,628.
Rohde, Robert P., 3,579,984.
Whitney, Donald R., 3,580,357.
- General Technologies Corporation: See—
Milewski, John V.; and Shyne, James J., 3,580,731.
- General Tire & Rubber Company, The: See—
Uelzmann, Heinz; and Hiding, David C., 3,580,799.
- Genie Grape Harvester, Inc.: See—
Sagouspe, Jean; and Riley, Eugene D., 3,579,971.
- Genin, Robert, to Child Guidance Toys Inc. Toy railroad assembly. 3,579,904, Cl. 46-216.
- Gentex Corporation: See—
Aileo, Jackson Anthony, 3,579,637.
- Gentiluomo, Joseph A. Putting green including means for sequentially returning holed-out ball to peripherally spaced ball dispensers. 3,580,583, Cl. 273-176.
- Gentry, Finis E., to General Electric Company. Process for wafer fabrication of high blocking voltage silicon elements. 3,579,815, Cl. 29-580.
- George, Maurice William: See—
Everson, Ivor; and George, Maurice William, 3,580,803.
- Georgia-Pacific Corporation: See—
King, Jonathan W., Jr., 3,580,387.
- Gerber, Reinhold; Kerrigan, James Edward; and Hawley, Harry Ray, to American Can Company. Brim curling apparatus. 3,579,737, Cl. 18-19.
- Gerek, Gene: See—
Hartzell, Rowland S.; and Gerek, Gene, 3,580,777.
- Gerighausen, Werner: See—
Perthen, Johannes; Gerighausen, Werner; Kunzmann, Konrad; and Dreyer, Heinz, 3,580,062.
- Gerity-Schultz Corporation: See—
Kenney, James E.; and Ashenfelter, Richard J., 3,580,175.
- Gerlach, Fritz; Hauskrecht, Toni; and Holch, Hermann, to Lonza Werke GmbH. Manufacture of bodies from a bundle of bonded resin tubes. 3,580,764, Cl. 156-83.
- Gesellschaft für Kernforschung mbH: See—
Handel, Karlheinz, 3,580,805.
- Getson, John Charles, to Stauffer-Wacker Silicone Corporation. Thixotropic organopolysiloxane compositions having pendant methacrylic acid polymer. 3,580,971, Cl. 260-825.
- Gettel, Roger W., to Sperry Rand Corporation. Relief valves with controlled pressure override. 3,580,277, Cl. 137-525.5
- Gevaert-Agfa N.V.: See—
Brinckman, Eric Maria, 3,580,719.
- Geymayer, Peter; Billenstein, Siegfried; and Renz, Werner, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Lubricant. 3,580,849, Cl. 252-78.
- Giamei, Anthony F.: See—
Copley, Stephen M.; Giamei, Anthony F.; Hornbecker, Merton F.; and Kear, Bernard H., 3,580,324.
- Gianese, Goffredo, to AMF Incorporated. Cigarette packers. 3,579,953, Cl. 53-59.
- Gibeau, Donald E.: See—
Belford, John F.; Gibeau, Donald E.; and Ciriello, John, 3,581,247.
- Giddings & Lewis, Inc.: See—
Jones, Gordon H., 3,580,135.
- Giglio, Gino. Bathtub construction. 3,579,667, Cl. 4-181.
- Gilbert, Edward L., deceased (by Graff, Edith M., administratrix); and Rogers, William A. Adjustable support for tree shaking apparatus. 3,579,970, Cl. 56-328.
- Gill, Lester D. Paper board container with platform style bottom. 3,580,473, Cl. 229-21.
- Gillis, Wayne A.: See—
Stouffer, James R.; Buege, Dennis R.; and Gillis, Wayne A., 3,579,716.
- Gilman, John M., to Realistic Company. The. Container closure and apparatus for opening same. 3,580,423, Cl. 222-81.
- Gilson, Warren E. Program control apparatus. 3,580,105, Cl. 74-568.
- Ginsburgh, Irwin; and Nebelsiek, Hilbert J., to Standard Oil Company (Indiana). Fueling device for automobiles and the like. 3,580,414, Cl. 220-86.
- Giraud, Francois Louis, to Societe de L'Aerortrain. Transportation systems. 3,580,184, Cl. 104-165.
- Girling Limited: See—
Payne, Arthur Albert, 3,580,544.
- Gish, David B., to Bell & Howell Company, mesne. Switching apparatus. 3,581,105, Cl. 307-116.
- Gladh, Knut Arnold Oscar, to Gladol S.A. Surface wiring systems. 3,580,984, Cl. 174-48.
- Gladol S.A.: See—
Gladh, Knut Arnold Oscar, 3,580,984.
- Glaverbel, S.A.: See—
Plumat, Emile; and Duthoit, Jean, 3,579,720.
- Glaze, Ardelle, to Fort Wayne Metals, Inc. Method of producing multitudinous straight cut-to-length filaments in oriented form. 3,580,783, Cl. 156-426.
- Globotex AG: See—
Vorberg, Fritz, 3,580,437.
- Gmeiner, Gunter; and Grabner, Christian, to Daimler-Benz Aktiengesellschaft. Installation for controlling the closing condition of parts adapted to be mutually locked, especially in motor vehicles. 3,580,624, Cl. 292-216.
- Goad, Albert, to Rotax Limited. Ball screw and nut mechanism. 3,580,098, Cl. 74-459.

- Godfrey, Douglas: See—
Furby, Neal W.; Godfrey, Douglas; and Peeler, Robert L., 3,580,848.
- Gogarty, William B.; and Mc Atee, Richard W., to Marathon Oil Company. Method for stabilizing the mobility of polyacrylamide solutions flowing through porous media. 3,580,337, Cl. 166-273.
- Goldberg, Newton N., to Westinghouse Electric Corporation. Stabilization of cholesteric-phase liquid crystal compositions against true solid formation using cholesteryl p-nonylphenyl carbonate. 3,580,865, Cl. 252-408.
- Goldberg, Newton N.; and Ferguson, James L., to Westinghouse Electric Corporation. Cholesteric-phase liquid-crystal compositions stabilized against true-solid formation, using cholesteryl erucyl carbonate. 3,580,864, Cl. 252-408.
- Gollwitzer, George E., to Kelsey-Hayes Company. Wheel rounding machine. 3,580,043, Cl. 72-402.
- Goltner, Wolfgang: See—
Kurzke, Herbert; Goltner, Wolfgang; and Seifried, Walter, 3,580,963.
- Goodman, Jerry M.: See—
Caner, Ralph A.; Anderson, William J.; Morgan, Bert B.; and Goodman, Jerry M., 3,579,760.
- Goodnow, Daniel M. Synchronous spark timer. 3,580,063, Cl. 73-118.
- Goodrich, B. F., Company, The: See—
Bialkowski, Ludwik S., 3,580,365.
Plaat, C. Lucas; and Linn, Donald F., 3,580,366.
Siebert, Alan R., 3,580,830.
- Goodway Inc.: See—
Kalman, Mario, 3,579,947.
- Goodyear Tire & Rubber Company, The: See—
Wilson, Farris H., Jr., 3,580,884.
- Gordon, Abraham: See—
Plawner, Moshe L.; Vento, Vincent R.; and Gordon, Abraham, 3,580,363.
- Gordon, Ernest S. Optical density calibrated photometer. 3,580,684, Cl. 356-226.
- Gorter, Werner; and Hauser, Johann, to SEMPERIT Österreichisch-Amerikanische Gummiwerke Aktiengesellschaft. Pneumatic tyre. 3,580,319, Cl. 152-361.
- Goss, John B. Control apparatus for high pressure water system. 3,580,509, Cl. 239-302.
- Gossling, Robert C.; and Armstrong, George, said Gossling assor. to Clapay Corporation. Window shade. 3,580,323, Cl. 160-263.
- Goto, Kenjiro, to Mansei Kogyo Kabushiki Kaisha. Liquefied gas-fueled smoking lighter utilizing piezo-electric elements as the voltage generation source. 3,580,698, Cl. 431-255.
- Gott, Hans; and Ritter, Josef, to EVG Entwicklungs und Verwertungs-Gesellschaft m.b.H. Machine for coiling elongated strip-like material. 3,580,018, Cl. 72-12.
- Gotze, Christian: See—
Hennig, Fridolin; Kellner, Hans-Jurgen; Potz, Klaus; and Gotze, Christian, 3,580,443.
- Gould, Joseph C.: See—
Hick, Robert M., Jr.; and Gould, Joseph C., 3,580,796.
- Grabner, Christian: See—
Gmeiner, Gunter; and Grabner, Christian, 3,580,624.
- Grabowski, Thomas S., to Borg-Warner Corporation. Discontinuous polycarbonate coatings. 3,580,730, Cl. 117-8.
- Grace, W. R., & Co.: See—
Dunn, William H., Jr., 3,580,300.
- Grady, Charles B., Jr., to Metrodynamics Corporation, The. Regulated DC power supply. 3,581,187, Cl. 323-17.
- Grahn, Robert D., to Sunbeam Corporation. Hedge trimmer. 3,579,827, Cl. 30-144.
- Grams, Richard A., to Babcock & Wilcox Company, The. Vapor generator. 3,579,990, Cl. 60-73.
- Granberg, Mauritz L.; and Mueller, Hubert W., Jr., to Sperry Rand Corporation. Digital to analog current distribution circuit. 3,581,076, Cl. 235-154.
- Granstrom, Ernst Henning Ture: See—
Andersson, Gustav Mattias; and Granstrom, Ernst Henning Ture, 3,579,936.
- Grant, Charles Clark Simpson, to Ibbett Engineering Company Limited. Trailer towing arrangement. 3,580,608, Cl. 280-405.
- Graves, Mary E. Therapeutic device oscillating device. 3,580,244, Cl. 128-25.
- Graves, Rodney J. Automated controlled environment for continuous production of plant life. 3,579,907, Cl. 47-17.
- Graving, Robert S. Method of producing a rolled bundle of preformed valley flashing. 3,579,946, Cl. 53-21.
- Green, Harry S. Floating, sea water distillation apparatus using a recirculating, directly contacting fluent heating medium. 3,580,814, Cl. 202-234.
- Green, Martin, to Blazon, Inc. Chain swing. 3,580,571, Cl. 272-85.
- Greenberg, Sol; Rosen, Heinz; Weinberger, Richard; and Mongodin, Guy, to Veeco Instruments, Incorporated. Vacuum gauge. 3,580,081, Cl. 73-399.
- Greenleaf, James O., to Stepan Chemical Company, mesne. Roofing tile. 3,579,940, Cl. 52-542.
- Greenspan, Lawrence E.; and Whitaker, Earl J., to Sanders Associates, Inc. Apparatus for altering computer memory by bit, byte or word. 3,581,287, Cl. 340-172.5
- Gregson, Robert E., to Motorola, Inc. SCR-slaving circuit. 3,581,114, Cl. 307-252.
- Grete, Lucien Ernest; and Leveque, Roger, to International Standard Electric Corporation. Machine for the manufacture of relay coil bobbins. 3,579,789, Cl. 29-203.
- Gressitt, Tillman J., to Bell Telephone Laboratories, Incorporated. Apparatus and method for applying indexing strips to cable pair groups. 3,579,823, Cl. 29-630.
- Grib, Boris F., to Philamon Incorporated. Counterbalanced resiliently supported tuning fork. 3,581,130, Cl. 310-25.
- Griffin, Anthony L.; and Chetwynd, Earl G. Card retainer. 3,579,878, Cl. 40-10.
- Griffith, Edwin D., to Owens-Illinois, Inc. Hermetically-sealed composite container. 3,580,464, Cl. 229-5.6
- Griffith, George L., to Commercial Solvents Corporation. TMETN-inorganic nitrate explosives blended with petroleum oil. 3,580,750, Cl. 149-38.
- Griffith, George L., to Commercial Solvents Corporation. TMETN-inorganic nitrate explosives blended with hot inorganic nitrate. 3,580,751, Cl. 149-38.
- Griffith, George L., to Commercial Solvents Corporation. TMETN-inorganic nitrate explosives blended with water. 3,580,752, Cl. 149-38.
- Griffith, George L., to Commercial Solvents Corporation. TMETN-inorganic nitrate explosives blended with aluminum. 3,580,753, Cl. 149-39.
- Griffith Laboratories, Inc., The: See—
Schnell, Carl, 3,580,315.
- Griffith, Norman N.: See—
Frankenberg, Edward V.; and Griffith, Norman N., 3,580,310.
- Griffiths, Thomas C.: See—
Beatty, Robert D., Jr.; and Griffiths, Thomas C., 3,581,277.
- Grotheer, Morris P.: See—
Curry, John E.; Grotheer, Morris P.; and Cook, Edward H., Jr., 3,580,824.
- Grove, Marvin H., to M&J Valve Company, and M&J Development Company. Resilient O-ring and method of manufacture. 3,580,765, Cl. 156-110.
- Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, to Hoffmann-La Roche Inc. N,N'-bis-(aminoalkyl)-benzyl-amines. 3,580,949, Cl. 260-570.5
- Grundschober, Friedrich; and Sambeth, Joerg, to Aktiebolaget Stadex. Apparatus for applying a coating of adhesive material on to a support. 3,580,218, Cl. 118-621.
- Grundt, Gary, to United States of America, Air Force, mesne. Photocurrent diverter. 3,581,119, Cl. 307-288.
- GTE Automatic Electric Laboratories, Incorporated: See—
Belcastro, Richard J., 3,581,110.
- Gualdipex S.A.: See—
Heiberger, Ernst, 3,579,920.
- Guarasi, Joseph S. Portable hair wash sink. 3,579,656, Cl. 4-159.
- Gubin, Georgy Viktorovich: See—
Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich, 3,580,554.
- Guenthard, Jacques, to Sandoz Ltd., a/k/a Sandoz A.G. Anthraquinone dyes, their production and use. 3,580,933, Cl. 260-372.
- Guerreiro, Antone M.: See—
De Voss, Edwin A.; and Guerreiro, Antone M., 3,580,044.
- Guest, Dorothy Joyce: See—
Corry, Alfred Reginald; Guest, Dorothy Joyce; and Williamson, William Ian, 3,580,877.
- Guirice, Raymond, to Societe a Responsabilite Limitee Laboraver. Self-injectable ampoule. 3,580,251, Cl. 128-220.
- Gukelberger, Thomas F., Jr.: See—
Blakeslee, A. Eugene; Gukelberger, Thomas F., Jr.; and Lyons, Vincent J., 3,580,732.
- Gul, Valentin Evgenievich: See—
Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Mariya Konstantinovna; and Kuzina, Alexandra Nikitichna, 3,580,776.
- Gulf Energy & Environmental Systems, Inc.: See—
Bokros, Jack C., 3,579,645.
- Gulf Research & Development Company: See—
Heilmann, William J., 3,580,893.
Hill, Robert W., 3,580,944.
Swift, Harold E., 3,580,970.
- Gulstad, Clayton O., to General Mills, Inc. Process for making expanded snack product. 3,580,727, Cl. 99-81.
- Gulstad, Clayton O.; and Eastburn, Francis J., to General Mills, Inc. Process for making expanded snack product. 3,580,728, Cl. 99-81.
- Gundersen, James L.: See—
Perkins, Carroll R.; Shaffstall, Everett L.; Gundersen, James L.; and Yoder, Robert N., 3,581,226.
- Gunter, Peter; Oberkirch, Wolfgang; and Pampus, Gottfried, to Farbenfabriken Bayer Aktiengesellschaft. Process for polymerizing cyclopentene. 3,580,892, Cl. 260-93.1
- Gunyou, John Christie; and Browning, Stanley Albert Charles, to Hybride Turkeys Limited. Applicator for bag closures. 3,579,955, Cl. 53-138.
- Gurevich, Leonid Mikhailovich. Device to facilitate removal of asbestos-cement pipes from the mandrel in a plant for manufacture of such pipes. 3,579,756, Cl. 25-30.
- Gurrieri, Salvatore J., to Pilarski, Anthony J. Swimming pool cover drain. 3,579,657, Cl. 4-172.12

- Gustafson, Ake, to Tetra Pak AG. Apparatus for forming a tube from a travelling web. 3,580,788, Cl. 156-497.
- Guth, Eugene D.; Lewis, Jerry L.; and Van Nice, Leslie J., to TRW Inc. Process for preparing isobutene and the apparatus therefor. 3,580,961, Cl. 260-683.3
- Guyer, Reynolds W., Jr.; and Kruse, Wilbert A., said Krause assor to said Guyer, d/b/a Winsor Concepts. Toy gun with stretchable diaphragm. 3,580,234, Cl. 124-21.
- Habicht, Ernst: *See—*
- Zergenyi, Janos; and Habicht, Ernst, 3,580,931.
- Hablitzel, Hermann: *See—*
- Schwenk, Kurt; Gallasch, Ernst; Hablitzel, Hermann; and Jacob, Friedrich, 3,579,727.
- Haene, Antonio C. P.: *See—*
- Mac Phee, Colin A. A.; and Haene, Antonio C. P., 3,580,743.
- Hafeli, Otto F. Trailer jack. 3,580,543, Cl. 254-100.
- Haft, Harry H.; and Repsher, Robert W., to Westinghouse Electric Corporation. Fluorescent lamp having tio-containing glass envelope and reduced phosphor weight. 3,581,139, Cl. 313-109.
- Hagan, Melvin A.; and Batista, Roy I., to TRW Inc. Tantalum clad niobium. 3,579,808, Cl. 29-497.5
- Hagemeister, Per Juel: *See—*
- Hansen, Viggo Rasmus; and Hagemeister, Per Juel, 3,580,522.
- Hagenah, Klaus, to Hauni-Werke Korber & Co. K.G. Apparatus for transporting and collecting shredded tobacco or the like. 3,580,645, Cl. 302-59.
- Hagstrom, Arthur A., to Teletype Corporation. Inverted selector mechanism. 3,581,004, Cl. 178-33.
- Hairston, James J., Jr.: *See—*
- Ransohoff, Jackson A.; and Hairston, James J., Jr., 3,581,095.
- Hale, Harry T., to Carrier Corporation. Refrigeration system. 3,580,005, Cl. 62-149.
- Haley, David Merl, to California Car Wash Systems, Inc. Car washing apparatus. 3,579,700, Cl. 15-21.
- Hall, Charles Thomas: *See—*
- Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, 3,579,952.
- Hall, Frank B., to Pettibone Corporation. Electrical relay circuitry. 3,581,157, Cl. 317-136.
- Hall, Robert Leonard, to Monsanto Chemicals Limited. Containers. 3,580,485, Cl. 229-51.
- Hall, Russell W., Jr.: *See—*
- Allen, Joseph C.; Bednarski, Valery N.; and Hall, Russell W., Jr., 3,580,335.
- Hallerback, Stig Lennart. Method of manufacturing rolling bearing components. 3,579,782, Cl. 29-148.4
- Hallett, Thomas E., to BRD, Inc. Single-channel electronic question-response system. 3,579,861, Cl. 35-48.
- Halley, James W., to Inland Steel Company. Forming of thin metal filaments. 3,581,040, Cl. 219-7.5
- Hallock, Robert Lay. Magnetic hammer. 3,580,312, Cl. 145-30.
- Halm, Richard. Electromagnetic make-and-break ignition device for a pocket lighter. 3,581,155, Cl. 317-81.
- Hamilton, Donald E.: *See—*
- Fenner, Robert M.; and Hamilton, Donald E., 3,580,570.
- Hamilton, Douglas D., 1/3 to Canadian International Paper Company, 1/3 to Quebec North Shore Paper Company, and 1/3 to Abitibi, St. Ann, Paper Ltd. Tree processing apparatus with feed rolls. 3,580,308, Cl. 144-3.
- Hamilton, Joseph R., to Lynch Corporation. Spraying mechanism for glassware forming machines. 3,580,711, Cl. 65-169.
- Hammann, Heinz; and Dick, Werner, to Lico AG. Concrete and the like mixer. 3,580,551, Cl. 259-152.
- Hammelmann, Paul; and Lettmann, Heinz. Submersible cleaning gun. 3,580,511, Cl. 239-419.5
- Hammer, Dale F., to General Motors Corporation. Automatic reversing circuit for a window regulator motor control system. 3,581,174, Cl. 318-266.
- Hammond, Robert A.; and Presta, Eugene A., to Diebold Incorporated. Video multiplexer-switcher with sequence recycling upon loss of video. 3,580,998, Cl. 178-6.8
- Hammond, Robert A.: *See—*
- Sandorf, Robert E.; and Hammond, Robert A., 3,580,993.
- Hancock, Roger Harvey Yorke: *See—*
- Firth, Donald; Hancock, Roger Harvey Yorke; and McCallum, James, 3,579,988.
- Handel, Karlheinz, to Gesellschaft fur Kernforschung mbH. Safety device for nuclear reactors with means for preventing control rod ejection. 3,580,805, Cl. 176-36.
- Hannah, Amos F. Toy hay baler. 3,579,899, Cl. 46-39.
- Hannah, John: *See—*
- Patchett, Arthur A.; and Hannah, John, 3,580,936.
- Hansbrough, David L.: *See—*
- Calud, Romeo T.; Hansbrough, David L.; and Zaumseil, Dean R., 3,581,169.
- Hansen, Arne, to Kidde, Walter & Company, Inc. Combined pressurizing and relief valve for fire extinguishers. 3,580,274, Cl. 137-493.
- Hansen, Benth Preben; and Blitz, Saul, to T. W. Manufacturing Company, Inc. Machine for producing hollow articles. 3,579,725, Cl. 18-5.
- Hansen, Dan Sigurd, to Smidth, F. L., & Co. Stack preheater. 3,580,552, Cl. 263-32.
- Hansen, Peter: *See—*
- Fratzsch, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, 3,580,844.
- Hansen, Richard C.; Mahler, Charles J.; Soares, Nicholas M.; and Stickney, Thomas L., to Xerox Corporation. Incremental stepping paper drive. 3,581,000, Cl. 178-7.6
- Hansen, Siegfried, to Hughes Aircraft Company. Survey level. 3,580,687, Cl. 356-248.
- Hansen, Viggo Rasmus; and Hagemeister, Per Juel, to Harnden, C. A., Limited. Method and arrangement for winding a continuous web. 3,580,522, Cl. 242-56.
- Hanson, Iner O. Screenshot holding device. 3,579,938, Cl. 52-365.
- Hanson, John R.; and Pierson, Karl B., to Tiona-Betts, Inc. Valve. 3,580,275, Cl. 137-516.29
- Hanzawa, Teruo: *See—*
- Iwama, Masakuni; Inoue, Isaburo; and Hanzawa, Teruo, 3,580,721.
- Harland, Geoffrey; and Ronayne, John P., to International Standard Electric Corporation. Multi-stage telephone switching network. 3,581,018, Cl. 179-22.
- Harnden, C. A., Limited: *See—*
- Hansen, Viggo Rasmus; and Hagemeister, Per Juel, 3,580,522.
- Harnischfeger Corporation: *See—*
- Siegel, Charles R.; and Schneider, Karl, 3,580,405.
- Thew, Donald G., 3,581,104.
- Harrington, Edwin C., Jr., to Monsanto Company. Machining method. 3,580,134, Cl. 90-13.
- Harris, Dale K., to Cities Service Company. Lock and seal means for longitudinally movable member inserted into a vessel. 3,580,279, Cl. 137-590.
- Harris-Intertype Corporation: *See—*
- Kolb, Edwin R.; and Horvath, Robert M., 3,581,302.
- Sarka, Albert J.; and Blake, Trevor H., 3,580,676.
- Harrison, Guy K., Jr.: *See—*
- Winter, John W.; and Harrison, Guy K., Jr., 3,579,847.
- Hartley Controls Corporation: *See—*
- Hartley, Nelson, 3,580,422.
- Hartley, Nelson, to Hartley Controls Corporation. Apparatus for adding finely divided solid material to a mixture. 3,580,422, Cl. 222-57.
- Hartzell, Rowland S.; and Gere, Gene, to PPG Industries, Inc. Method of bonding asbestos sheet material to concrete. 3,580,777, Cl. 156-278.
- Harvey, Donald M., to Eastman Kodak Company. Photochromic exposure control. 3,580,148, Cl. 95-10.
- Harvey, Jay A.: *See—*
- Webb, Thomas Alan; and Harvey, Jay A., 3,580,997.
- Hashimoto, Hideo, to Kabushiki Kaisha Ricoh. Automatic elevating mechanism for a paper feed platform of an automatic paper feed device for use with a photocopying machine, printing press, or the like. 3,580,567, Cl. 271-62.
- Haskon Incorporated: *See—*
- Hentges, Ronald L.; and Garrett, Howard R., 3,579,958.
- Hasler, A. G.: *See—*
- Laderach, Peter, 3,581,112.
- Hatsukano, Yoshikazu; and Nomiya, Kosei, to Hitachi, Ltd. Electronic display system. 3,581,065, Cl. 235-92.
- Hauni-Werke Korber & Co. K.G.: *See—*
- Hagenah, Klaus, 3,580,645.
- Hauser, Johann: *See—*
- Gorter, Werner; and Hauser, Johann, 3,580,319.
- Hausknecht, Louis A. Motor speed control device. 3,581,177, Cl. 318-330.
- Hauskrecht, Toni: *See—*
- Gerlach, Fritz; Hauskrecht, Toni; and Holch, Hermann, 3,580,764.
- Havé Industries, Inc.: *See—*
- Havewala, Jamshed Behram, 3,580,982.
- Havewala, Jamshed Behram, to Havé Industries, Inc. Pole riser guard-back-up plate combination. 3,580,982, Cl. 174-45.
- Hawk Oil Field Equipment Corporation: *See—*
- Maasshoff, Gunter, 3,580,138.
- Hawley, Edwin L., to E. P. S. (Research & Development) Limited. Strip fasteners. 3,579,747, Cl. 24-201.
- Hawley, Harry Ray: *See—*
- Gerber, Reinhold; Kerrigan, James Edward; and Hawley, Harry Ray, 3,579,737.
- Haws Drinking Faucet Company: *See—*
- Wright, Allen C., 3,580,542.
- Hayakawa, Yoshihiro: *See—*
- Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, 3,580,895.
- Hayashi, Shinichi: *See—*
- Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.
- Hayashi, Yasutoshii. End plate forming apparatus. 3,580,025, Cl. 72-84.
- Hayes Albion Corporation: *See—*
- Warner, Robert F., 3,580,056.
- Hayes, Edward J.; and Crick, Stephen E., to Kelsey-Hayes Company. Method for manufacturing wheels. 3,579,783, Cl. 29-159.
- Hayes, Thomas H., to Lilly, Eli, and Company. Pill dispenser with indicating means. 3,579,883, Cl. 40-107.
- Hays, Gordon W.: *See—*
- Mills, James Claiborne, Jr.; and Hays, Gordon W., 3,579,957.

- Hazel, Jack A., to C.A.V. Limited. Machine tool cut-off slide. 3,580,118, Cl. 82-46.
- Hazemag Hartzkerleinerungs- und Zementmaschinenbau-Gesellschaft, m.b.H.: *See—*
- Andreas, Ehrhardt, 3,580,537.
- HC Electronics, Inc.: *See—*
- Armstrong, Merritt S., 3,581,223.
- Heaslett, Alistair Michael: *See—*
- Bigg, Geoffrey James; and Heaslett, Alistair Michael, 3,581,176.
- Heatwole, Oliver W. Key-adjustable harmonica. 3,580,125, Cl. 84-377.
- Hebert, Gerard E., to Lockhart Manufacturing Corporation. Storage rack. 3,580,602, Cl. 280-79.3
- Heck, Burnette, to General Motors Corporation. Disc brake cooling means and pump drive mechanism. 3,580,368, Cl. 188-264.
- Heck, Burnette, to General Motors Corporation. Liquid-cooled disc brake assembly. 3,580,369, Cl. 188-264.
- Hecker, Robert W., Jr.; and Beckwith, Robert C., to Loomis Machine Company. Dockboard. 3,579,696, Cl. 14-71.
- Hedberg, Ronald M. Marine seismic exploration. 3,581,273, Cl. 340-7.
- Heffernan, Bart T.; and Ostrowsky, Efrim M. Heart valve assembly and method of implanting in the body. 3,579,642, Cl. 3-1.
- Heiberger, Ernst, to Gualdipex S.A. Polishing machine for workpieces. 3,579,920, Cl. 51-164.
- Heid, Christian; and Keil, Karl-Heinz, to Cassella Farbwerke Mainkur Aktiengesellschaft. Stable alkali chlorite mixtures. 3,580,851, Cl. 252-99.
- Heidenhain, Johannes, Dr.: *See—*
- Kraus, Heinz; and Holstein, Siegfried, 3,579,836.
- Heilmann, William J., to Gulf Research & Development Company. Process for the preparation of cyclic acid anhydrides. 3,580,893, Cl. 260-78.5
- Heim, Gerhard, to Daimler-Benz Aktiengesellschaft. Installation for closing or opening apertures in vehicles. 3,580,629, Cl. 296-137.
- Heimberger, Werner; and Schmitt, Hermann, to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler. Biologically active substituted-s-triazines. 3,580,912, Cl. 260-247.5
- Hein, Rolf. Bubble blowing device. 3,579,898, Cl. 46-7.
- Heinen, Irving Joseph. Rotatable multi-port valve with fluid pressure controlled valve means. 3,580,540, Cl. 251-159.
- Heinkel, Ernst Aktiengesellschaft: *See—*
- Eggstein, Giorgio; and Ungerer, Heinz, 3,580,361.
- Heinonen, Martti, to Valmet Oy. Device for manufacturing blades for the blade wheel of an axial flow machine. 3,580,039, Cl. 72-316.
- Heinzel, Joseph A., to Olin Corporation. Snap off telescope mount. 3,579,840, Cl. 33-50.
- Heinzelman, Earl E., to Armstrong Cork Company. Dry lubricant coating of extruded tubing. 3,579,732, Cl. 18-14.
- Held, Gerhard R. Self-air cooling abrading wheel. 3,579,928, Cl. 51-356.
- Hellborg, Lars Ingvar, to Sobrafina S.A., mesne. Apparatus for uniting a plurality of first objects with a corresponding number of second objects. 3,579,785, Cl. 29-200.
- Heller, David S.: *See—*
- Stone, Raymond A.; Lister, Fred; and Heller, David S., 3,580,876.
- Helmerich & Payne, Inc.: *See—*
- Van Scoy, Davis A., 3,580,539.
- Heirigel, Robert A.; Brownell, James R.; Ward, Roderick K.; and Keithley, Harry E., to Bliss, E. W., Company. Cushion mounting in punch press. 3,580,558, Cl. 267-114.
- Henderson, William P. Method of verifying the replacement of a damaged windshield. 3,579,798, Cl. 29-401.
- Hendricks, Grover E. Underwater projectile for firing a cartridge upon impact. 3,580,172, Cl. 102-48.
- Hendriks, Adrianus Anthonius Maria, to U.S. Philips Corporation, mesne. Gas discharge tube with cold cathode suitable for the simultaneous reproduction of two legible characters. 3,581,138, Cl. 313-109.5
- Hennig, Fridolin; Kellner, Hans-Jurgen; Potz, Klaus; and Gotze, Christian, to Agfa-Gevaert Aktiengesellschaft. Apparatus for opening film cassettes. 3,580,443, Cl. 225-96.5
- Henry, Colonel. Animal halters. 3,579,963, Cl. 54-24.
- Henshaw, James N., to USM Corporation. Fastener inserting machines. 3,580,457, Cl. 227-116.
- Hensley, Loyd D.: *See—*
- Prasse, Herbert F.; and Hensley, Loyd D., 3,580,589.
- Hentges, Ronald L.; and Garrett, Howard R., to Haskon Incorporated. Machine for forming, filling, and sealing containers. 3,579,958, Cl. 53-183.
- Herbert, David B.; and Barney, Ronald N., to Norton Company. Flexible refractory curtain. 3,580,322, Cl. 160-231.
- Hermes, Heinz; Thieme, Klaus-Dietrich; Gatermann, Willi; Koerv, Peter; and Mehnert, Walter, to LICENTIA Patent-Verwaltungs-G.m.b.H. Electric circuit for generating a programmable multi-phase alternating current. 3,581,185, Cl. 321-7.
- Hernandez, Tomas; and Lorenzo, Valentin E. Method of controlling humidity contamination of hygroscopic-material handling machines. 3,579,848, Cl. 34-15.
- Herr, John Addison: *See—*
- Klawunn, Herbert G.; and Herr, John Addison, 3,580,780.
- Herwig, Walter: *See—*
- Brinkmann, Ludwig; Cherdron, Harald; and Herwig, Walter, 3,580,965.
- Herzing, Vernon J.: *See—*
- Tolf, Ingvar L.; Herzing, Vernon J.; Miller, Everett L.; and Lightfoot, George L., 3,580,402.
- Heseltine, Donald W.: *See—*
- Mee, John D.; and Heseltine, Donald W., 3,580,911.
- Hestad, Alfred M.: *See—*
- Ribner, Morris; and Hestad, Alfred M., 3,581,020.
- Hestad, Erling; Ritter, Thomas E.; and De Claire, Alton G., Jr., to General Motors Corporation. Steering torque servo. 3,580,352, Cl. 180-79.2
- Hetland, Thomas E., to Whirlpool Corporation. Vacuum cleaner motor control. 3,579,706, Cl. 15-327.
- Hetzel, Marvin E.: *See—*
- Cervenka, Joseph J.; and Hetzel, Marvin E., 3,579,787.
- Hewes, Ralph A.: *See—*
- Salver, James F.; and Hewes, Ralph A., 3,580,860.
- Hewitt, Eugene E., to Uniroyal, Inc. Apparatus for welding thermoplastic sheet material. 3,580,793, Cl. 156-579.
- Hewitt, Harlan Douglas. Vehicle tilt compensator. 3,580,354, Cl. 180-104.
- Hewitt, Terry L., to General Electric Company. Automatic answer confirmation system. 3,579,869, Cl. 35-48.
- Hexdall, Andrew M. Heavy duty metal snips. 3,579,828, Cl. 30-251.
- Heywood, Vincent E.; Bushey, Donald H.; and Chapman, William A., Jr., to United States Envelope Company. Apparatus and method for banding groups of envelopes. 3,579,944, Cl. 53-3.
- Hibi, Masao; and Nishimura, Takeshi, to Hitachi, Ltd. Solid state image pick-up device. 3,581,097, Cl. 250-209.
- Hick, Robert M., Jr.; and Gould, Joseph C., to Du Pont de Nemours, E. I., and Company. Glass laminated by an adhesive comprising the polyurethane resulting from the reaction of bis(2-isocyanatoethyl) fumarate with polyols without other isocyanate. 3,580,796, Cl. 161-190.
- Hickman, Norman A., to Statham Instruments Inc. Flowmeter probe. 3,580,071, Cl. 73-194.
- Hicks, Harris Vernon, to Lucas, Joseph, (Industries) Limited. Composite lenses. 3,580,663, Cl. 350-189.
- Hidinger, David C.: *See—*
- Uelzmann, Heinz; and Hidinger, David C., 3,580,799.
- Hidy, Phil H.; and Young, Vernon V., to Commercial Solvents Corporation. Process for recovering fermentation estrogenic substance. 3,580,929, Cl. 260-343.2
- Hidy, Phil, to Commercial Solvents Corporation. Synthetic fermentation medium and process using same for cultivating *Gibberella zeae*. 3,580,811, Cl. 195-100.
- Hieber, Fritz; Burger, Erich; and Huber, Hans-Peter, to Agfa-Gevaert Aktiengesellschaft. Strip scanning copying apparatus. 3,580,675, Cl. 355-50.
- Higashimura, Einosuke; Tamai, Katsumi; and Nakamura, Eiichi, to Mitsubishi Rayon Co., Ltd. Gelable compositions and process of using the same. 3,580,879, Cl. 260-29.7
- Higgason, Frank G., Jr.; and Sehnert, Robert J., to Ludlow Typograph Company. Apparatus for the production of coded intelligence on a record medium. 3,580,494, Cl. 234-6.
- Higgins, Irwin R., to Chemical Separation Corporation. Down flow ion exchange. 3,580,842, Cl. 210-25.
- Hilburn, Luell. Clamping fixture for use in a hoisting and lifting device. 3,580,626, Cl. 294-67.
- Hill, Alan E. Ballast for a plurality of parallel gaseous discharges. 3,581,146, Cl. 315-180.
- Hill, Franz, to Zahnradfabrik Friedrichshafen Aktiengesellschaft. Planetary-gear transmission with interconnected sun gears and ring gears. 3,580,109, Cl. 74-763.
- Hill, Fredrick L.; Gates, Lauren W.; and Colbert, William V., to University of California, The Regents of the. Crop harvester adjustable for different row spacings and for different types of final operation. 3,579,968, Cl. 56-327.
- Hill, Robert W., to Gulf Research & Development Company. Unsaturated alkyl sulfamates and method of preparation. 3,580,944, Cl. 1.
- Hill, Sumner B.: *See—*
- Veater, Donald J.; Hill, Sumner B.; and Ruffner, Lawrence J., 3,581,167.
- Hille Engineering Company Limited, The: *See—*
- Wilson, Alexander Ian, 3,580,034.
- Hills, Stanley, to ESB Incorporated. Electrolytic process for purifying iron dissolved from scrap steel. 3,580,825, Cl. 204-112.
- Hinchcliffe, Dennis: *See—*
- Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, 3,579,952.
- Hinchcliffe, Basil W., to Koppers Company, Inc. Condition responsive water quench in a closed coke cooling system. 3,580,813, Cl. 201-39.
- Hinckley, Henry R., & Company: *See—*
- Hinckley, Henry R., 3,580,208.
- Hinckley, Henry R., to Hinckley, Henry R., & Company. Rudder control for a sail boat. 3,580,208, Cl. 114-163.
- Hinckley, Thayer C. Burner for cigarette lighter. 3,580,700, Cl. 431-344.
- Hini, Paul, to Siemens Aktiengesellschaft. Method of making galvanomagnetic resistor utilizing grid for short-circuiting hall voltage. 3,579,820, Cl. 29-610.
- Hirano, Tadao: *See—*
- Horie, Hajime; Hirano, Tadao; and Suzuki, Tokihide, 3,580,015.
- Hirschey, Kenneth A. Combination car seat and crib. 3,579,673, Cl. 5-94.

- Hitachi Electronics Co., Ltd.: *See—*
Ohi, Kunio; Inoue, Hideaki; Nakayama, Toshio; and Ishii, Sosuke, 3,581,245.
- Hitachi, Ltd.: *See—*
Abe, Katsuro; Kakinuma, Saburo; and Uno, Masaaki, 3,579,986.
Hatsukano, Yoshikazu; and Nomiya, Kosei, 3,581,065.
Hibi, Masao; and Nishimura, Takeshi, 3,581,097.
Iwamoto, Shoji; and Horikoshi, Hisashi, 3,581,291.
Miura, Tanetoshi; Koshikawa, Tsuneji; Nakano, Yasuaki; and Nakayama, Takeshi, 3,581,192.
Murayama, Yoshimasa; and Kuroko, Hirokazu, 3,581,232.
Suzuoka, Takayuki, 3,581,166.
Tsuboi, Takashi; and Narita, Hiroshi, 3,581,172.
Watanabe, Ryozi; and Kobayashi, Yutaka, 3,581,188.
Yaegashi, Toshio, 3,579,781.
- Hitzelberger, Alan L., to General Motors Corporation. Pointer stabilizer. 3,580,085, Cl. 73-496.
- Hobart Manufacturing Company, The: *See—*
Meyers, Theodore F., 3,581,057.
- Hobbs, Peter Alfred, to National Research Development Corporation. Machines for planting tubers and the like. 3,580,417, Cl. 221-224.
- Hochstetler, Eli. Machine for processing wheelbarrow handles. 3,580,309, Cl. 144-11.
- Hodapp, Donald C.: *See—*
Barnard, Walter C.; and Hodapp, Donald C., 3,580,008.
- Hoenisch, Walter H., to King-Seely Thermos Co. Method and apparatus for dispensing ice cubes and the like. 3,580,416, Cl. 221-203.
- Hoerner Waldorf Corporation: *See—*
Mobley, Odess V., 3,580,475.
- Hoffer, Max: *See—*
Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, 3,580,949.
- Hoffman, Ernest G.: *See—*
La Pointe, Lloyd J.; Voegelin, Howard J.; and Hoffman, Ernest G., 3,580,498.
- Hoffmann, Heinrich; and Wagner, Wilhelm, to Daimler-Benz Aktiengesellschaft. Air-compressing injection-type internal combustion engine with externally controlled ignition and quality regulation. 3,580,230, Cl. 123-32.
- Hoffmann, Wolfgang; and Wick, Paul, to Canadian International Paper Company. Packaging apparatus. 3,579,956, Cl. 53-159.
- Hoffmann-La Roche Inc.: *See—*
Cosentino, Louis Ciro, 3,580,240.
Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, 3,580,949.
Lehr, Hanns Hanina, 3,580,909.
- Hofmann, Horst: *See—*
Ciriack, Gunter; Eckert, Georg; and Hofmann, Horst, 3,580,739.
- Hogue, Dean M.; and Bender, Carl M. Truck with built-in weighing mechanism and load hold-down device. 3,580,343, Cl. 177-136.
- Hohmann, Kurt: *See—*
Mundlos, Eberhard; Mohr, Reinhard; Trapp, Gunther; and Hohmann, Kurt, 3,580,900.
- Holch, Hermann: *See—*
Gerlach, Fritz; Hausrecht, Toni; and Holch, Hermann, 3,580,764.
- Holeman, John M., to General Electric Company. Holographic spatial filters and method of making same. 3,581,280, Cl. 340-146.3
- Holland, John P.: *See—*
Wolf, Cecil R.; and Holland, John P., 3,579,809.
- Hollinger, Harvey T. Decal dispensing apparatus. 3,580,415, Cl. 221-74.
- Hollis, Jack Lyndon; and Shockey, Ray Douglas, to Firestone Tire & Rubber Company, The. Apparatus for building up tread material on a tire carcass. 3,580,781, Cl. 156-397.
- Holm, Vernon C. F.: *See—*
Nolan, George J.; and Holm, Vernon C. F., 3,580,969.
- Holman, Elmer. Zipper safety fastener. 3,579,749, Cl. 24-205.14
- Holophone Company, Inc.: *See—*
Shadwick, Jan, 3,581,082.
- Holstein, Siegfert: *See—*
Kraus, Heinz; and Holstein, Siegfert, 3,579,836.
- Holthenrichs, Philip D.; and Wanger, Robert P., to General Electric Company. Flexible structure orientation control. 3,579,929, Cl. 52-1.
- Holzl, Hans, to Kunststoffe Hans Holz KG. Articulated floor mat. 3,579,704, Cl. 15-215.
- Hone, George L.: *See—*
Frey, Dean R.; Hone, George L.; and Ramsey, Edward L., Jr., 3,581,269.
- Honeywell G.m.b.H.: *See—*
Merz, Manfred, 3,581,175.
- Honeywell Inc.: *See—*
Hurd, Edward T. E., III, 3,581,184.
Neema, Farid J.; and Engelhardt, Robert C., 3,581,285.
Podgorski, Theodore J., 3,581,227.
Rasmussen, Robert F., 3,580,139.
Sampson, Richard L., 3,580,087.
Wallace, Robert H., 3,581,181.
- Honeywell Information Systems Inc.: *See—*
Milford, Richard E., 3,581,100.
Palmer, Ansell W., 3,581,064.
- Honkala, Harold E.: *See—*
Issott, John W.; Honkala, Harold E.; and Carraher, Delbert V., 3,580,037.
- Honsberg, Wolfgang: *See—*
Barney, Arthur Livingston; and Honsberg, Wolfgang, 3,580,889.
- Hood, John L.; and McGee, Joe H., to Sperry Rand Corporation. Light actuated brushless D.C. motor. 3,581,173, Cl. 318-254.
- Hoodwin, Louis S. Apparatus for testing rotary power transmitting components. 3,580,068, Cl. 73-162
- Hooker Chemical Corporation: *See—*
Currey, John E.; Grotheer, Morris P.; and Cook, Edward H., Jr., 3,580,824.
- Hoory, Sadok E.; Newman, Stanley F.; and Vincent, Robert E., to Shell Oil Company. Recovery of propylene and propylene oxide by selective separation with plural stage distillation, propylene oxide absorption and subsequent distillation. 3,580,819, Cl. 203-42.
- Hoover, Alan W., to International Telephone and Telegraph Corporation. Automatic brightness control. 3,581,098, Cl. 250-213.
- Hoover Company, The: *See—*
Allen, Howard L.; and De Graff, Charles D., 3,580,588.
Balzer, Jerry L., 3,579,699.
- Horacek, Herbert P., to Garrett Corporation, The. Bistable fluidic amplifier. 3,580,265, Cl. 137-81.5
- Horie, Hajime; Hirano, Tadao; and Suzuki, Tokihide, to Fujii Seiren Kako Kabushiki Kaisha. Device for treating textile fabric. 3,580,015, Cl. 68-53.
- Horikoshi, Hisashi: *See—*
Iwamoto, Shoji; and Horikoshi, Hisashi, 3,581,291.
- Hornak, John C.; and Thompson, Douglas F. Football blocking sled. 3,580,574, Cl. 273-55.
- Hornbecker, Merton F.: *See—*
Copley, Stephen M.; Giamei, Anthony F.; Hornbecker, Merton F.; and Kear, Bernard H., 3,580,324.
- Horvath, Robert M.: *See—*
Kolb, Edwin R.; and Horvath, Robert M., 3,581,302.
- Hosea, Joel C.: *See—*
Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., 3,580,802.
- Hoshi, Hideo; Washi, Masao; and Yoshiki, Hiroshi. Tapping apparatus. 3,579,687, Cl. 10-129.
- Hoshino, Fumiro: *See—*
Miya, Bunji; Hoshino, Fumiro; and Matuda, Morio, 3,580,930.
- Hovious, Thomas C.; and Torkildsen, Robert A., to General Electric Company. Universal automatic sensing and actuating control system for fluid consuming power sources and the like. 3,580,741, Cl. 136-86.
- Howitt, Fred; and Taylor, Ian, to Aluminium Laboratories Limited. Production of aluminum zinc magnesium alloy articles. 3,580,747, Cl. 148-12.7
- Howlett, Donald L., to Texaco Inc. Sequential approximation pulse height analog-to-digital converter. 3,581,305, Cl. 340-347.
- Huber, Hans-Peter: *See—*
Hieber, Fritz; Burger, Erich; and Huber, Hans-Peter, 3,580,675.
- Huberdeau, Gerard, to French State, represented by the Minister of Armed Forces Ministerial Delegation of Weapons, Technical Delegation of Land Weapons Manufacturing Workshops of Tarbes. Method of producing toroidal bodies from hard, brittle steels. 3,579,806, Cl. 29-463.
- Hubin, Allen J., to Minnesota Mining & Manufacturing Company. Elastomeric products of epoxy resins and polyether disocyanate amines. 3,580,887, Cl. 260-47.
- Hudson, Kenneth C.; and Shashoua, Fred E., to United States of America, Air Force, mesne. Low light level color photography. 3,580,151, Cl. 95-12.20
- Huebner, Werner: *See—*
Born, Dieter; Stech, Peter; and Huebner, Werner, 3,580,587.
- Huffman, Bobbie Dale. Warning device for moving vehicle. 3,581,278, Cl. 340-9062.
- Hughes Aircraft Company: *See—*
Hansen, Siegfried, 3,580,687.
Perkins, Carroll R.; Shaffstall, Everett L.; Gundersen, James L.; and Yoder, Robert N., 3,581,226.
- Hughes, George T., to Ovitrone Corporation. Picture frame mounting construction. 3,579,886, Cl. 40-152.
- Hughes, Michael Robert: *See—*
Lombos, Lazlo; and Hughes, Michael Robert, 3,580,235.
- Hughes, Walter D., to Chevron Research Company. Pressure liquid level indicator. 3,580,263, Cl. 137-2.
- Hunerwadel, Jean L.: *See—*
Brinkerhoff, Joris M.; Hunerwadel, Jean L.; and Sellers, Francis B., 3,581,087.
- Hunnicutt, Roy. Mixing apparatus. 3,580,550, Cl. 259-107.
- Hunt, Lloyd F. Ground protection and detection for high voltage D.C. transmission system. 3,581,152, Cl. 317-18.
- Hunter Engineering Company: *See—*
Hunter, Lee; Senften, David A.; and Logan, Edwin W., 3,579,845.
- Hunter, Lee; Senften, David A.; and Logan, Edwin W., to Hunter Engineering Company. Dynamic wheel toe and tire pull testing apparatus. 3,579,845, Cl. 33-203.13
- Hurd, Edward T. E., III, to Honeywell Inc. Isolator for D.C. signal transmitter. 3,581,184, Cl. 321-2.
- Huskey, Joseph E., to Cities Service Company. Hardness tester. 3,580,060, Cl. 73-78.

- Husky Manufacturing and Tool Works Ltd.: *See—*
Rees, Herbert, 3,579,740.
- Huyghe, Jean: *See—*
de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignet, Paul, 3,580,818.
- Hybride Turkeys Limited: *See—*
Gunyou, John Christie; and Browning, Stanley Albert Charles, 3,579,955.
- Hyde, Thomas J.; and Targonski, Leonard A., to Du Pont de Nemours, E. I., and Company. Copolylactam bowling pin. 3,580,577, Cl. 273-82.
- Ibbett Engineering Company Limited: *See—*
Grant, Charles Clark Simpson, 3,580,608.
- Icore Industries: *See—*
Shuster, Joseph; and Brown, Richard L., 3,580,379.
- Ideal Security Hardware Corporation: *See—*
Waldo, Russell W., 3,580,017.
- Ikeda, Masashi; and Inoue, Masayoshi, to Mitsubishi Rayon Co., Ltd. Method of retarding polymerization in the process for the production of methacrylic acid esters. 3,580,947, Cl. 260-486.
- Ikuta, Yoshiharu: *See—*
Kurashiki, Hajime; and Ikuta, Yoshiharu, 3,580,211.
- Iliescu, Liviu; and Dragos, Ion, to Ministerul Industriei Constructiilor de Masini. Method and stereoscopic optical apparatus for determining the roughness of the surfaces of machined parts. 3,580,682, Cl. 356-168.
- Imhof, Herman A., to USM Corporation. Automatic shoe machinery and operation of the same. 3,579,694, Cl. 12-17.
- Imperial Chemical Industries Limited: *See—*
Anderton, Kenneth, 3,580,946.
Brown, Ivor James Stewart; Clarkson, Richard; Crossley, Neville Stanton; and McLoughlin, Bernard Joseph, 3,580,905.
Corry, Alfred Reginald; Guest, Dorothy Joyce; and Williamson, William Ian, 3,580,877.
Leigh, Thomas, 3,580,923.
- Imprimerie Chaix-Desfosses-Neogravure: *See—*
Lannegrace, Jean-Paul, 3,580,827.
- Improved Machinery Inc.: *See—*
Vore, Herbert G.; and Bardsley, Donald E., 3,579,726.
- Inamoto, Toshiharu: *See—*
Suzuki, Yoshiaki; and Inamoto, Toshiharu, 3,581,288.
- Indian Head Inc.: *See—*
Kieffer, William H., 3,579,764.
- Industrial Nucleonics Corporation: *See—*
Spitz, David A., 3,581,199.
- Industrie A. Zanussi S.p.A.: *See—*
Mazza, Lamberto, 3,580,014.
- Ingraham, Robert C.; and Ramsey, Hubert J., to Sylvania Electric Products, Inc. Method of producing semiconductor devices. 3,579,816, Cl. 29-583.
- Inland Steel Company: *See—*
Halley, James W., 3,581,040.
- Inoue, Hideaki: *See—*
Ohi, Kunio; Inoue, Hideaki; Nakayama, Toshio; and Ishii, Sosuke, 3,581,245.
- Inoue, Isaburo: *See—*
Iwama, Masakuni; Inoue, Isaburo; and Hanzawa, Teruo, 3,580,721.
- Inoue, Masayoshi: *See—*
Ikeda, Masashi; and Inoue, Masayoshi, 3,580,947.
- Inouye, Shingo; and Saul, George, to United States of America, Air Force. Immersion thermocouple for atmospheric and vacuum environments. 3,580,744, Cl. 136-234.
- Institutul de Cercetari Tehnologice Pentru Constructii de Masini: *See—*
Luca, Ioan, 3,580,026.
- Institute of Gas Technology, The: *See—*
Dolan, Jose P., 3,580,003.
- Institutul de Cercetari Stiintifice Pentru Protectia Muncii: *See—*
Minetos, Nicolae, 3,580,307.
- Integral Process Systems, Inc.: *See—*
Wagner, Richard C., 3,580,000.
- International Business Machines Corporation: *See—*
Alexander, David C., 3,581,219.
Beausoleil, William F., 3,581,286.
Blakeslee, A. Eugene; Gukelberger, Thomas F., Jr.; and Lyons, Vincent J., 3,580,732.
Dill, Frederick H., Jr., 3,579,814.
Lipschutz, Lewis D., 3,580,460.
Pliskin, William A.; and Taylor, James E., 3,580,066.
- International Dynetics Corporation: *See—*
Long, Joseph F., 3,580,166.
- International Paper Company: *See—*
Lee, Charles A.; and Furbeck, Warren R., 3,580,784.
- International Standard Electric Corporation: *See—*
Grente, Lucien Ernest; and Leveque, Roger, 3,579,789.
Harland, Geoffrey; and Ronayne, John P., 3,581,018.
Muller, Jean Jacques, 3,581,013.
Sharpe, John Thomas Lawrence, 3,581,121.
Vazquez, Charles, 3,581,256.
- International Telephone and Telegraph Corporation: *See—*
Hoover, Alan W., 3,581,098.
Pfander, Hans; Schilling, Harald; and Schwabe, Gerhard, 3,581,164.
Ribner, Morris; and Hestad, Alfred M., 3,581,020.
- Irako, Koichi: *See—*
Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, 3,580,895.
- Isaacs, Wayne R. Frequency to direct current converter circuit. 3,581,217, Cl. 328-140.
- Isaksen, Robert A.; and De Shay, Robert V., to Monsanto Company. Coating composition of a mixture of a vinyl ester of an aliphatic acid-carboxylic acid copolymer and a terpolymer of a vinyl ester of an aliphatic acid, a carboxylic acid ester and a carboxylic acid. 3,580,972, Cl. 260-836.
- Ishihara, Frank Y., 50% to Tall, Leonard H. Opener for a film pack. 3,579,801, Cl. 29-427.
- Ishihara, Masayoshi: *See—*
Tanaka, Hiroshi; and Ishihara, Masayoshi, 3,581,149.
- Ishii, Sosuke: *See—*
Ohi, Kunio; Inoue, Hideaki; Nakayama, Toshio; and Ishii, Sosuke, 3,581,245.
- Isogai, Nobuo: *See—*
Kuraishi, Michio; Asano, Setunobu; and Isogai, Nobuo, 3,580,968.
- Issott, John W.; Honkala, Harold E.; and Carraher, Delbert V., to Universal Oil Products Company, mesne. Tube extrusion apparatus including separable arrested mandrel tip tube cutoff. 3,580,037, Cl. 72-255.
- Itek Corporation: *See—*
Watson, John Thaxter; and Robinson, Kenneth, 3,580,150.
- Ito, Teruhiko; Mitsui, Naoshi; Maeda, Seiichiro; and Kato, Takeshi, to Seitetsu Kagaku Co., Ltd. Process for producing high molecular weight polymers of alkylene oxides. 3,580,866, Cl. 260-2.
- Itoh, Yoshishige; Kawamura, Masatada; and Kasai, Yoshio, to Fuji Motors Corporation. Method of destroying ferroconcrete, rock or the like. 3,580,637, Cl. 299-14.
- Ivackovic, Nikola; and Urosevic, Milija, to Cer Produzece Termo-Tehnickih Uredajaja I Montaza. Vertical grain drying device. 3,579,852, Cl. 34-167.
- Iverson, Peter B., to Postmark Corporation. Advertising display support. 3,579,885, Cl. 40-145.
- Iwama, Masakuni; Inoue, Isaburo; and Hanzawa, Teruo, to Konishiroku Photo Industry Co., Ltd. Light-sensitive color-photographic material. 3,580,721, Cl. 96-100.
- Iwamiya, Masao: *See—*
Shimemura, Etsujiro; and Iwamiya, Masao, 3,581,238.
- Iwamoto, Shoji; and Horikoshi, Hisashi, to Hitachi, Ltd. Memory control system in multi-processing system. 3,581,291, Cl. 340-172.5
- Iytaka, Tateshi: *See—*
Sato, Shui; Sakazume, Kaichiro; and Iytaka, Tateshi, 3,580,724.
- J-B-T Instruments, Inc.: *See—*
Plumb, Frank J., 3,581,033.
- Jachlewski, Arthur F.: *See—*
Demler, Walter R.; and Jachlewski, Arthur F., 3,580,919.
- Jackson, Isaac S., to National Catheter Corporation. Conductive line tube. 3,580,983, Cl. 174-47
- Jacob, Friedrich: *See—*
Schwenk, Kurt; Gallasch, Ernst; Hablitzel, Hermann; and Jacob, Friedrich, 3,579,727.
- James, Herbert I., to ESB Incorporated. Zinc electrode containing lead sulfide to reduce gassing at the zinc electrode in heat sterilized silver zinc alkaline battery. 3,580,740, Cl. 136-30.
- Jankowitz, Gerald: *See—*
Pearsall, Denton; and Jankowitz, Gerald, 3,581,092.
- Jantzen, Robert J., to Ocean Science and Engineering, Inc. Dredging apparatus with surge compensating means. 3,579,872, Cl. 37-66.
- Japan Aircraft Manufacturing Co., Ltd.: *See—*
Wada, Misao; and Soda, Kiyoshi, 3,580,530.
- Japan Exlan Company Limited: *See—*
Nakanome, Iyohiko; Takeya, Kenji; Suzuki, Hiroshi; and Kitagawa, Yasuhiro, 3,580,878.
- Japan Gas-Chemical Company, Inc.: *See—*
Kuraishi, Michio; Asano, Setunobu; and Isogai, Nobuo, 3,580,968.
- Jarret, Jacques; and Jarret, Jean, to Societe d'Exploitation des Ressources Auto-Amortisseuses Jarret. Improvements in resilient devices. 3,580,560, Cl. 267-153.
- Jarret, Jean: *See—*
Jarret, Jacques; and Jarret, Jean, 3,580,560.
- Jeddeloh Bros. Sweed Mills, Inc.: *See—*
Larson, Charles L., 3,580,778.
- Jefferson Robert T.: *See—*
Salyer, Ival O.; Jefferson Robert T.; and Ross, William D., 3,580,843.
- Jegou, Francois: *See—*
de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignet, Paul, 3,580,818.
- Jennings, Charles M.: *See—*
Tidball, Robert A.; King, William M.; Bosley, Dewey R.; and Jennings, Charles M., 3,580,816.
- Jepsen, Robert L., to Varian Associates. Detection of by gas ionization method and apparatus providing decreased vacuum recovery time. 3,581,195, Cl. 324-33.
- Jewett, Lawrence A.; and Jewett, Walter C. Vehicle luggage carrier. 3,580,439, Cl. 224-42.1
- Jewett, Walter C.: *See—*
Jewett, Lawrence A.; and Jewett, Walter C., 3,580,439.
- Jisa, Miloslav; Zmatlik, Josef; Mohelnicky, Josef; and Milichovsky, Bohumil, to Stantni Vyzkumny Ustav Textilni. Partly woven and partly knitted fabric and apparatus for making the same. 3,580,295, Cl. 139-383.

- Johansson, Bengt: *See*—
Burmeister, Fred; Enkvist, Ernst; Johansson, Bengt; and Kostilainen, Valter, 3,580,204.
- Johnson, Alfred D., to Sylvania Electric Products, Inc. Cathode ray tube having an annular shaped rear window. 3,581,134, Cl. 313-64.
- Johnson, Clark E., Jr. Trigonometric encoder. 3,581,306, Cl. 340-347.
- Johnson, Evar C. Toilet flushing attachment. 3,579,664, Cl. 4-250.
- Johnson, Gilbert A., to Marquette Electronics, Inc. Means and method for subtracting D.C. noise from electrocardiographic signals. 3,580,243, Cl. 128-206.
- Johnson, Janet M.: *See*—
Wray, Dennis; and Johnson, Janet M., 3,580,701.
- Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., to United States of America, Atomic Energy Commission. Device for determining the shape of magnetic surfaces in toroidal configurations containing plasma. 3,580,802, Cl. 176-1.
- Johnson, Joseph E.: *See*—
Simon, Alan J.; Johnson, Joseph E.; and O'Keeffe, Trencé W., 3,580,749.
- Johnson, Kenneth R.: *See*—
Dodgen, John N.; and Johnson, Kenneth R., 3,580,599.
- Johnson, Theodore C. Hose straightening device. 3,579,786, Cl. 29-200.
- Jonckheere, Lucien Julianne Arthur. Clips useful in the medical field. 3,579,751, Cl. 24-252.
- Jones, Charles E., to Sabin Machine Co. Vibrating machine. 3,579,919, Cl. 51-163.
- Jones, Gordon H., to Giddings & Lewis, Inc. Clamping apparatus for a machine tool. 3,580,135, Cl. 90-11.
- Jones, John Paul, Jr., to Navcor, Inc., a division of KDI Corporation. Coded punch electromagnetic interposer assembly. 3,580,495, Cl. 234-115.
- Jones, Johnny W., to Borg-Warner Corporation. Multi-phase motor control system with over-current and under-current protection. 3,581,179, Cl. 318-452.
- Jonsson, Lars-Erik, to Alfa-Laval AB. Method and apparatus for detecting sludge level in a centrifuge. 3,580,493, Cl. 233-19.
- Jordan, Grant H., to American Greetings Corporation. Device for applying a band of thermosetting material onto a label and for sealing the label onto an article. 3,580,791, Cl. 156-540.
- Jorgensen, Anker E.; and Oxley, Gerald K., to TRW Inc. Telescoping section in a steering column. 3,580,101, Cl. 74-493.
- Joslyn Mfg. and Supply Co.: *See*—
Misare, Donald O., 3,580,986.
- Joy, Ivan L. Wheel trip. 3,581,083, Cl. 246-246.
- Joyce, John. Control circuitry to prevent use of a secondary circuit without static electricity grounds. 3,581,153, Cl. 317-18.
- Kabushiki Kaisha Ricoh: *See*—
Ando, Sadanao, 3,580,672.
- Fukushima, Yoshio, 3,580,153.
- Fukushima, Yoshio, 3,580,659.
- Hashimoto, Hideo, 3,580,567.
- Kabushiki Kaisha Suwa Seikosha: *See*—
Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.
- Kach, Alfred, to Pathehold Patentverwertungs- & Elektro-Holding AG. Linearly polarized microwave feed assembly for parabolic antennas and the like. 3,581,311, Cl. 343-781.
- Kafka, Wilhelm, to Siemens Aktiengesellschaft. Switching device for disconnecting cables. 3,581,113, Cl. 307-245.
- Kaiser Aluminum & Chemical Corporation: *See*—
Peterson, John R., 3,580,835.
- Kakinuma, Saburo: *See*—
Abe, Katsuro; Kakinuma, Saburo; and Uno, Masaaki, 3,579,986.
- Kalle Aktiengesellschaft: *See*—
Kegelman, Gunter; Gebler, Horst; and Seifried, Walter, 3,580,798.
- Maar, Herbert; Steppan, Hartmut; Messwarb, Gunter; and Luders, Walter, 3,580,888.
- Kalman, Mario, to Goodway Inc. Method of printing and folding a mailing piece. 3,579,947, Cl. 53-23.
- Kaltenbach, Roger Max. Apparatus for obtaining uniform droplets. 3,579,721, Cl. 18-27.
- Kaltenegger, Benno. Vibratory road roller. 3,580,147, Cl. 94-50.
- Kaman Sciences Corporation: *See*—
Carr, Barney J., 3,581,093.
- Kamborian, Jacob S.: *See*—
Robinson, Charles A., 3,579,693.
- Kamborian, Jacob S. Toe lasting machine. 3,579,690, Cl. 12-12.4.
- Kamiya, Toshihiro: *See*—
Asada, Takeo; and Kamiya, Toshihiro, 3,580,121.
- Kampe, Wolfgang: *See*—
Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,910.
- Kaneko, Seiya: *See*—
Yoshimoto, Toshio; Narumiya, Tsuneaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, 3,580,897.
- Kaneno, Saburo; Yamaguchi, Takeshi; and Yoshioka, Shunichi, to Sumitomo Electric Industries, Ltd. Piezoelectric wheel-axle detector. 3,581,084, Cl. 246-249.
- Kang, Katherine K. H.; and Kang, Young Ok. Skewer meat device. 3,579,713, Cl. 17-1.
- Kang, Young Ok: *See*—
Kang, Katherine K. H.; and Kang, Young Ok, 3,579,713.
- Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotu, to Kawasaki Steel Corporation, and Nippon Kokan Kabushikikaisha. Method of one-side arc welding and backing material therefor. 3,581,039, Cl. 219-73.
- Kao Soap Co., Ltd.: *See*—
Miya, Bunji; Hoshino, Fumiro; and Matuda, Morio, 3,580,930.
- Kappel, Thomas Inc.: *See*—
Wagner, Millard C., 3,580,606.
- Karasman, Paul G. Burglar alarm. 3,580,215, Cl. 116-87.
- Karlinsky, Stanislav Evgenievich: *See*—
Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.
- Kashahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, to Tekkosa Co., Ltd. Method of chemical grout processing. 3,580,883, Cl. 260-41.
- Kasai, Yoshio: *See*—
Itoh, Yoshishige; Kawamura, Masatada; and Kasai, Yoshio, 3,580,637.
- Kashahara, Toshio; and Numao, Mitsuru. Method of jointing sheaths of aluminum sheathed cables. 3,580,756, Cl. 156-49.
- Kast, Howard Berdolt, to General Electric Company. Method of forming interference fits by heat treatment. 3,579,805, Cl. 29-447.
- Kastner, Arnold. Cigarette tube packaging apparatus. 3,580,433, Cl. 222-440.
- Kato, Takeshi: *See*—
Ito, Teruhiko; Mitsui, Naoshi; Maeda, Seiichi; and Kato, Takeshi, 3,580,866.
- Kawamura, Masatada: *See*—
Itoh, Yoshishige; Kawamura, Masatada; and Kasai, Yoshio, 3,580,637.
- Kawasaki Steel Corporation: *See*—
Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotu, 3,581,039.
- Kaydon Technical Enterprises Ltd.: *See*—
Fraser, Colin Kenneth Glenn; Favreau, Ernest; and March, Willis Paul, 3,580,546.
- KDI Corporation: *See*—
Jones, John Paul, Jr., 3,580,495.
- Kear, Bernard H.: *See*—
Copley, Stephen M.; Giamei, Anthony F.; Hornbecker, Merton F.; and Kear, Bernard H., 3,580,324.
- Kearney & Trecker Corporation: *See*—
Sedgwick, Robert K., 3,580,834.
- Kearns, Robert W. Windshield wiper control device. 3,581,178, Cl. 318-443.
- Kedman Company: *See*—
Davis, Frank J.; and Edwards, George Zahnor, 3,579,638.
- Keen, Ian Montgomery; Craig, Peter James; and Bradshaw, Christopher Patrick Cadman, to British Petroleum Company Limited, The. Dehydrogenation catalyst. 3,580,960, Cl. 260-683.3.
- Kegelman, Gunter; Gebler, Horst; and Seifried, Walter, to Kalle Aktiengesellschaft. Biaxially stretched trioxane copolymer film and process for the preparation thereof. 3,580,798, Cl. 161-165.
- Keil, Karl-Heinz: *See*—
Heid, Christian; and Keil, Karl-Heinz, 3,580,851.
- Keiper, Phillip C. Elevator systems. 3,580,360, Cl. 187-29.
- Keithley, Harry E.: *See*—
Helrigel, Robert A.; Brownell, James R.; Ward, Roderick K.; and Keithley, Harry E., 3,580,558.
- Kellner, Hans-Jürgen: *See*—
Hennig, Fridolin; Kellner, Hans-Jürgen; Potz, Klaus; and Gotze, Christian, 3,580,443.
- Kelly, Donald A. Uniflow stirling engine and frictional heating system. 3,579,980, Cl. 60-42.
- Kelly, Franklin G., to TRW Inc. Digital to analog converter. 3,581,303, Cl. 340-347.
- Kelsey-Hayes Company: *See*—
Gollwitzer, George E., 3,580,043.
- Hayes, Edward J.; and Crick, Stephen E., 3,579,783.
- Taccone, Russell W., 3,580,329.
- Keltz, Lawrence W.; and Marek, Charles, to Chicago Roller Skate Company, The. Tap holder. 3,579,688, Cl. 10-134.
- Kemeny, George A.; and Wolf, Charles B., to Westinghouse Electric Corporation. Quick-change field coil assembly for use in an electrode having a fluid-cooled arcing surface. 3,580,977, Cl. 13-18.
- Kennedy, Daniel M., Jr.; and Zellner, Carl Naehner, to Celanese Corporation. Polyoxymethylene-formal-containing polyester block polymer. 3,580,973, Cl. 260-860.
- Kennedy, Garth P.; and Nelson, William E., to Corken Pump Company. Evacuation system for pipeline discharging pump. 3,580,420, Cl. 222-1.
- Kenney, James E.; and Ashenfelter, Richard J., to Gerity-Schultz Corporation. Fragmentation explosive device. 3,580,175, Cl. 102-67.
- Kent-Moore Corporation: *See*—
White, Richard B., 3,580,055.
- Kerr, William J., to Chicago Lock Co. Keeper lock for a slide fastener. 3,580,016, Cl. 70-68.
- Kerrigan, James Edward: *See*—
Gerber, Reinhold; Kerrigan, James Edward; and Hawley, Harry Ray, 3,579,737.
- Kershaw, John Knox, to Marmon Groups, Inc., The, mesne. Railway ballast working apparatus. 3,579,873, Cl. 37-105.

- Kessler, Rene: *See*—
Apotheloz, Robert; Bigler, Hans-Ulrich; and Kessler, Rene, 3,580,174.
- Key, John W. Printing screen cleaner. 3,580,261, Cl. 134-104.
- Keyes Fibre Company: *See*—
Lowery, Louie R., 3,579,951.
- Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich. Continuous casting mold. 3,580,327, Cl. 164-280.
- Kidd, Thomas L., Jr.; and McClain, Albert D., Jr., to General Electric Company. Non-flammable, thin, integrally illuminated control panel overlay. 3,580,755, Cl. 156-3.
- Kidde, Walter & Company, Inc.: *See*—
Hansen, Arne, 3,580,274.
- Kidder, Ephraim Henry. Fish impaling and grappling implement. 3,579,894, Cl. 43-6.
- Kieffer, William H., to Indian Head Inc. Process for producing textured yarns. 3,579,764, Cl. 28-72.11.
- Kiehl, Arthur H. Conveyor article transfer apparatus. 3,580,377, Cl. 198-20.
- Kilner, George E., to Filper Corporation. Apparatus and method for levelling drupe halves and the like. 3,580,381, Cl. 198-33.
- Kimberly-Clark Corporation: *See*—
Bernardin, Leo J., 3,580,253.
- King, Arthur S. Treatment system with cooling means. 3,580,836, Cl. 204-308.
- King, James D.: *See*—
Damewood, Glenn; Sparks, Cecil R.; and King, James D., 3,581,077.
- King, Jonathan W., Jr., to Georgia-Pacific Corporation. Conveyor article support apparatus. 3,580,387, Cl. 198-178.
- King of Prussia Research and Development Corporation: *See*—
Kron, Harold O.; Liu, John K.; and Behnke, Edward, 3,580,371.
- King, Robert H.: *See*—
Thelen, Edmund J.; and King, Robert H., 3,580,466.
- King, William M.: *See*—
Tidball, Robert A.; King, William M.; Bosley, Dewey R.; and Jennings, Charles M., 3,580,816.
- King-Seely Thermos Co.: *See*—
Hoenisch, Walter H., 3,580,416.
- Zumstein, Fred R., 3,580,762.
- Kirk, Thomas E.; and Stenkiyft, Gerald H., to General Motors Corporation. Overvoltage protection circuit for a generator regulator system. 3,581,150, Cl. 317-16.
- Kirkby, Donald, to BBA Group Limited. Dynamic braking of induction motors. 3,581,168, Cl. 318-211.
- Kishi, Kanesuke; Tsuchiya, Noboru; and Shimura, Kazuo, to Sony Corporation. Unidirectional microphone. 3,581,012, Cl. 179-1.
- Kitagawa, Yasuhiro: *See*—
Nakanome, Iyohiko; Takeya, Kenji; Suzuki, Hiroshi; and Kitagawa, Yasuhiro, 3,580,878.
- Kitano, Yasushi; and Fujita, Kozo, to Matsushita Electric Industrial Co., Ltd. Automatic speed control apparatus for automotive vehicles. 3,580,355, Cl. 180-105.
- Klawunn, Herbert G.; and Herr, John Addison, to Singer Company, The. Method and apparatus for bar sealing of girdle panels. 3,580,780, Cl. 156-380.
- Kleban, Michael P.: *See*—
Spadoni, Frank G., Jr.; and Kleban, Michael P., 3,580,297.
- Klebetchnik GmbH: *See*—
Pollmeier, Heinz; and Witthuhn, Johann, 3,580,790.
- Klein, Kurt: *See*—
Fratzcher, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, 3,580,844.
- Klein, Kurt; Lumbeck, Gerd; and Maluzi, Joachim, to Deutsche Gold- und Silber-Scheideanstalt vormals Roessler. Process for hindering the agglomeration or reagglomeration of ground finely divided powdered substances. 3,580,519, Cl. 241-22.
- Klein Schanzlin & Becker A. G.: *See*—
Born, Dieter; Stech, Peter; and Huebner, Werner, 3,580,587.
- Klein, Wilhelm: *See*—
Fichtner, Rudi; Ober, Horgern; and Klein, Wilhelm, 3,579,691.
- Klempner, George R.; and Rosenberg, Sam, to Foundry Suppliers Inc. Engine block stripping apparatus. 3,579,784, Cl. 29-200.
- Klensch, Richard J., to RCA Corporation. Constant sized halftone dot image generator. 3,580,995, Cl. 178-6.7.
- Klevanov, Fedor Grigorievich: *See*—
Bondarenko, Alexandr Andreevich; and Klevanov, Fedor Grigorievich, 3,580,090.
- Klimsch & Co.: *See*—
Schunck, Kurt; and Baunach, Waldemar, 3,580,674.
- Klockner-Humboldt-Deutz Aktiengesellschaft: *See*—
Deussner, Herbert; and Langmaack, Jürgen, 3,579,850.
- Klose, Karl W.: *See*—
Teed, Richard K.; and Klose, Karl W., 3,580,198.
- Knaggs, Marvin G.: *See*—
Pieszak, Franklin B.; and Knaggs, Marvin G., 3,580,467.
- Knapsack Aktiengesellschaft: *See*—
Baader, Herbert; and Sennwald, Kurt, 3,580,958.
- Knitter, Heinz; and Veszelik, Josef, to Bunker-Ramo Corporation, The. Contact unit having contact protective means. 3,581,271, Cl. 339-176.
- Knizia, Klaus, to L. & C. Steinmüller G.m.b.H. Method and apparatus for operation of a positively driven steam generator with rolled overlap and gas-tight welded vaporizer walls. 3,580,223, Cl. 122-1.
- Knutson, William J., to Motorola, Inc. Frequency modulated crystal controlled oscillator operable at a plurality of temperature compensated center frequencies. 3,581,239, Cl. 332-18.
- Knyazev, Vladimir Fedorovich: *See*—
Kononov, Mikhail Ivanovich; Krashennnikov, Evgeny Anatolevich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaevich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich, 3,580,717.
- Kobald, Walter: *See*—
Bosch, Paul; and Kobald, Walter, 3,579,979.
- Kobayashi, Toshio, to Fujitsu Limited. Frame synchronization system for synchronizing the frame of a digital signal transmission. 3,581,010, Cl. 178-69.5.
- Kobayashi, Yutaka: *See*—
Watanabe, Ryozi; and Kobayashi, Yutaka, 3,581,188.
- Kober, Ehrenfreid H.: *See*—
Churchill, John W.; Kober, Ehrenfreid H.; Scott, Peter H.; and Smith, Curtis P., 3,580,951.
- Koboldt, Melvin A., to Container Corporation of America. Easy opening arrangement for reclosable can. 3,580,481, Cl. 229-51.
- Koch, Peter, to United States of America, Agriculture. Process of making laminated wood product utilizing modulus of elasticity measurement. 3,580,760, Cl. 156-64.
- Kocherov, Anatoly Vasilievich: *See*—
Beresnev, Boris Ivanovich; Bulychov, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
- Kocks, Friedrich, Firma: *See*—
Bindernagel, Ali; Kost, Erwin; and Staat, Karl-Hans, 3,580,020.
- Koehler-Dayton, Inc.: *See*—
Russo, Ronald D., 3,579,651.
- Koehring Company: *See*—
Brown, Gaylord W., 3,579,723.
- Koenig, Robert P.: *See*—
Sherman, Russell G.; and Koenig, Robert P., 3,580,272.
- Koerv, Peter: *See*—
Hermes, Heinz; Thieme, Klaus-Dietrich; Gatermann, Willi; Koerv, Peter; and Mehnert, Walter, 3,581,185.
- Koestel, Alfred, to United States of America, Air Force. Boiler inlet plug insert with heat dam. 3,580,227, Cl. 122-406.
- Kogel, Wilhelm Georg, to Aktiebolaget Electrolux. Apparatus for defrosting cooling units of absorption refrigeration systems. 3,580,004, Cl. 62-148.
- Koitaibashi, Takeo: *See*—
Sakamoto, Kenro; Takahashi, Takao; Koitaibashi, Takeo; and Fujiwara, Mitsuto, 3,580,722.
- Kolb, Edwin R.; and Horvath, Robert M., to Harris-Intertype Corporation. Apparatus and method for providing graphical configurations by sequentially directing a radiant energy beam to present image positions. 3,581,302, Cl. 340-324.
- Koll, Laurel A.; and Crook, Walter, Jr., to Diamondhead Properties, Inc., mesne. Method and apparatus for moving objects. 3,579,672, Cl. 5-81.
- Komen, Stanley. Continuous envelope. 3,580,488, Cl. 229-69.
- Kondel, George C.: *See*—
Nejame, Samuel, Jr.; Kondel, George C.; and De Santis, Italo J., 3,580,301.
- Konishiroku Photo Industry Co., Ltd.: *See*—
Iwama, Masakuni; Inoue, Isaburo; and Hanzawa, Teruo, 3,580,721.
- Sakamoto, Kenro; Takahashi, Takao; Koitaibashi, Takeo; and Fujiwara, Mitsuto, 3,580,722.
- Sato, Shui; Sakazume, Kaichiro; and Sakamoto, Eiichi, 3,580,723.
- Sato, Shui; Sakazume, Kaichiro; and Iyaka, Tateshi, 3,580,724.
- Kononov, Mikhail Ivanovich; Krashennnikov, Evgeny Anatolevich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaevich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich. Method of obtaining a spongy metal ingot in a shaft furnace. 3,580,717, Cl. 75-37.
- Kooi, Else; and Van Der Meer, Aant Bouwe Daniel, to U.S. Philips Corporation, mesne. Semiconductor device. 3,580,745, Cl. 148-1.5.
- Kopf, Joseph E.: *See*—
Lamp, Richard W.; Kopf, Joseph E.; Dravis, Donald P.; and Cuneo, Robert A., 3,580,981.
- Koppers Company: *See*—
Tucker, Linwood G., 3,580,815.
- Koppers Company, Inc.: *See*—
Hinchliffe, Basil W., 3,580,813.
- Kopsch, Paul J.; Turcus, Daniel, Jr.; and Ward, Donald F. Externally lubricated projectile and method of making same. 3,580,178, Cl. 102-92.2.
- Korablev, Lev Nickolaevich, to Fizicheskoy Institute IM. P. N. Lebedeva. Electronic pulse counter with bistable switching elements. 3,581,147, Cl. 315-84.5.
- Korbilas, Christ P.; and Smikh, Raymond W., to Astro Controls, Inc., mesne. Multi-purpose liquid transfer valve. 3,580,276, Cl. 137-517.

Korshunov, Mikhail Alexeevich: *See—*
Bodnarjuk, Frizian Nikolaevich; and Korshunov, Mikhail Alexeevich, 3,580,918.

Kosaka, Yoshiteru, to Victor Company of Japan, Limited. Signal editing system for magnetic recording and reproducing apparatus. 3,580,994, Cl. 178-6.6.

Koshikawa, Tsuneji: *See—*
Miura, Tanetoshi; Koshikawa, Tsuneji; Nakano, Yasuaki; and Nakayama, Takeshi, 3,581,192.

Kost, Erwin: *See—*
Bindernagel, Ali; Kost, Erwin; and Staat, Karl-Hans, 3,580,020.

Kostilainen, Valter: *See—*
Burmeister, Fred; Enkvist, Ernst; Johansson, Bengt; and Kostilainen, Valter, 3,580,204.

Kotter, Helmut, to Stiegemeyer, Joh., & Co. G.m.b.H. Adjustable bed. 3,579,671, Cl. 5-62.

Kowalski, Robert J. Archery bow sight. 3,579,839, Cl. 33-46.

Kozakura, Yoshio: *See—*
Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotzu, 3,581,039.

Kraft, Karl-Josef: *See—*
Schmidt, Wolfgang; Kraft, Karl-Josef; and Kurth, Willi, 3,579,722.

Kraft, Melvin G.: *See—*
Yopp, Robert S.; and Kraft, Melvin G., 3,581,272.

Krahulec, Fred, to Motorola, Inc. Rotationally responsive device. 3,580,177, Cl. 102-79.

Kramer, Harold A., to United States of America, Agriculture. Pneumatic probe sampler. 3,580,084, Cl. 73-421.

Krascheninnikov, Evgeny Anatolievich: *See—*
Kononov, Mikhail Ivanovich; Krascheninnikov, Evgeny Anatolievich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaevich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich, 3,580,717.

Kraus, Charles E., to Exceleumatic, Inc. Motion transmission drive. 3,580,094, Cl. 74-242.11.

Kraus, Heinz; and Holstein, Siegfert, to Heidenhain, Johannes, Dr. Arrangement for measuring of lengths. 3,579,836, Cl. 33-1.

Krause, Gerhard, to Fernseh GmbH. Automatic time correction circuit for color TV signals. 3,580,991, Cl. 178-5.4.

Kravchenko, Svyatoslav Anatolievich; and Kulemin, Alexei Alexeevich. Phase-setting device. 3,581,201, Cl. 324-83.

Krein, Reuben J., to Stitchcraft Corporation. Article holding apparatus. 3,580,561, Cl. 267-81.

Kretzmer, Ernest R., to Bell Telephone Laboratories, Incorporated. Adaptive integrator for digital signals. 3,581,111, Cl. 307-236.

Kroll, Wolfram R., to Esso Research and Engineering Company. Preparation of dialkyl Group IIIa metal-diacylmethane. 3,580,938, Cl. 260-448.

Kron, Harold O.; Liu, John K.; and Behnke, Edward, to King of Prussia Research and Development Corporation. Self-synchronizing clutch. 3,580,371, Cl. 192-18.

Krueger, Robert H.: *See—*
Albertson, Clarence E.; and Krueger, Robert H., 3,580,759.

Kruger, Max: *See—*
Kusters, Eduard; and Kruger, Max, 3,580,447.

Kruse, Wilbert A.: *See—*
Guyer, Reynolds W., Jr.; and Kruse, Wilbert A., 3,580,234.

Kuffer, Clarence O.; and McAvoy, Thomas. Valve Corporation of America Aerosol valve tip and stem assembly and method of assembling same. 3,580,431, Cl. 222-42.1.

Kugler, Emanuel. Plastic bag with integral handle. 3,580,486, Cl. 229-54.

Kuhn, Henry S. Disposable urinal. 3,579,653, Cl. 4-110.

Kuhn, Henry S. Disposable self-inflatable bed pan. 3,579,654, Cl. 4-113.

Kuhn, Henry S. Writing guide for training purposes and use by the blind. 3,579,867, Cl. 35-38.

Kujawa, Edmund J.: *See—*
Furstenburg, Alvin J.; and Kujawa, Edmund J., 3,579,799.

Kukla, Stanley. Method of forming decorative three dimensional effect designs and coatings. 3,580,768, Cl. 156-156.

Kulemin, Alexei Alexeevich: *See—*
Kravchenko, Svyatoslav Anatolievich; and Kulemin, Alexei Alexeevich, 3,581,201.

Kumpf, Hermann, to Siemens Aktiengesellschaft. Steam generating assembly for use in the interior of a pressure vessel of a pressurized water nuclear reactor. 3,580,807, Cl. 176-55.

Kunststoffe Hans Holz KG: *See—*
Holzl, Hans, 3,579,704.

Kunzmann, Konrad: *See—*
Perthen, Johannes; Gerighausen, Werner; Kunzmann, Konrad; and Dreyer, Heinz, 3,580,062.

Kupersmit, Julius B. Combination cleat and clip means for assembling collapsible containers. 3,580,618, Cl. 287-20.924.

Kupsky, George A., to Burroughs Corporation. Method of making display devices. 3,580,654, Cl. 316-20.

Kuraishi, Michio; Asano, Setunobu; and Isogai, Nobuo, to Japan Gas-Chemical Company, Inc. Process for preparing N,N-dialkylacrylamides. 3,580,968, Cl. 260-561.

Kurashiki, Hajime; and Ikuta, Yoshiharu, to Mitsui Shipbuilding and Engineering Co., Ltd. Method of shaft alignment of a main engine shaft in shipbuilding. 3,580,211, Cl. 115-0.5.

Kurisu, Albert G., to United States of America, Navy. Method of making conformal blocks for evaporatively cooling circuit assemblies. 3,579,821, Cl. 29-627.

Kurono, Hirokazu: *See—*
Murayama, Yoshimasa; and Kurono, Hirokazu, 3,581,232.

Kurth, Willi: *See—*
Schmidt, Wolfgang; Kraft, Karl-Josef; and Kurth, Willi, 3,579,722.

Kurzke, Herbert; Goltner, Wolfgang; and Seifried, Walter, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Vapor deposited metal polyester polycondensation catalysts. 3,580,963, Cl. 260-860.

Kuster, William. Process for separating and recovering bone and collagen from animal by-products. 3,580,725, Cl. 99-7.

Kusters, Eduard, Maschinenfabrik: *See—*
Kusters, Eduard; and Kruger, Max, 3,580,447.

Kusters, Eduard; and Kruger, Max, to Kusters, Eduard, Maschinenfabrik. Textile treating apparatus. 3,580,447, Cl. 226-119.

Kuzina, Alexandra Nikitichna: *See—*
Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Maiya Konstantinovna; and Kuzina, Alexandra Nikitichna, 3,580,776.

Kuzma, John J.; and Gawrych, Robert I., to Olin Mathieson Chemical Corporation. Single selective trigger system for double barrel firearms. 3,579,891, Cl. 42-42.

Kvalheim, Andrew M.; and McEvers, Boh L. Lumber and veneer jointer. 3,580,792, Cl. 156-546.

Laber, Werner: *See—*
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.

La Croix, George E. Fetal scalp electrode unit. 3,580,242, Cl. 128-2.06.

Laderach, Peter, to Hasler A. G. Electronic relay. 3,581,112, Cl. 307-241.

La Forge, David H. Miniature steerable vehicle and track system therefor. 3,579,906, Cl. 46-244.

Laing, Nikolaus. Rotating electrical machine. 3,581,132, Cl. 310-166.

L'Air Liquide, Societe Anonyme pour l'Etude et L'Exploitation des Procédes George Claude: *See—*
Rapinat, Michel, 3,579,997.

L'Air Liquide Societe Anonyme pour l'Etude et L'Exploitation des Procédes Georges Claude: *See—*
Thibault, Jean-Jacques; and Boissin, Jean-Claude, 3,579,998.

Laliberte, Real, to Ayerst, McKenna & Harrison, Ltd. Derivatives of 2-oxocyclopentane carboxylic acid. 3,580,945, Cl. 260-464.

Lamberson, Jack L. Electric teaching device. 3,579,857, Cl. 35-9.

Lambroff, George M.: *See—*
Wilhelm, D. F.; Miller, Peter S.; Bissell, D. L.; and Lambroff, George M., 3,581,289.

Lambuth, Alan L., to Monsanto Company. Ready-to-use phenolic adhesives. 3,580,872, Cl. 260-17.2.

Lamp, Richard W.; Kopf, Joseph E.; Dravis, Donald P.; and Cunco, Robert A., to Technical Wire Products, Inc. Electrically conductive ventilating panel. 3,580,981, Cl. 174-35.

Lampathakis, Kyriakos E.: *See—*
Seelbach, Walter C.; and Lampathakis, Kyriakos E., 3,581,165.

Lancashire, Thomas, to Boeing Company, The. Materials handling apparatus. 3,580,403, Cl. 214-38.

Landis Tool Company: *See—*
Price, Ralph E., 3,579,914.

Landry, Charles C.: *See—*
Peoples, Joseph T.; and Landry, Charles C., 3,581,106.

Lang, David L.: *See—*
Ligon, James T.; and Lang, David L., 3,580,503.

Lang, Felix C.: *See—*
Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., 3,579,761.

Lang, Frederic A., to Du Pont de Nemours, E. I., and Company. Method for post-tensioning tendons. 3,579,931, Cl. 52-741.

Lang, Gunther. Process and tool for forming holes in profiled members with a predetermined spacing. 3,580,040, Cl. 72-324.

Langer, Reinhold: *See—*
Zahn, Wolfgang; Nagel, Erlich; and Langer, Reinhold, 3,580,155.

Langmaack, Jurgen: *See—*
Deussner, Herbert; and Langmaack, Jurgen, 3,579,850.

Lannegrace, Jean-Paul, to Imprimerie Chaix-Desfosses-Neogravure. Etching method and apparatus. 3,580,827, Cl. 204-143.

Lanza, Vincent L., to Raychem Corporation. Process for irradiating polyvinylidene fluoride and a compatible polyfunctional monomer and product thereof. 3,580,829, Cl. 204-159.17.

La Pointe, Lloyd J.; Voegelin, Howard J.; and Hoffman, Ernest G., to Veeder Industries, Inc. Electromagnetic counting mechanism. 3,580,498, Cl. 235-117.

Larson, Charles L., to Jeddell Bros. Sweed Mills, Inc. Method and apparatus for plywood panel lay-up. 3,580,778, Cl. 156-299.

Larson, Leighton W. Bi-valved cast. 3,580,248, Cl. 128-89.

Larson, Wesley S., to United States of America, Army, mesne. End clip for load carrying belt. 3,579,641, Cl. 2-325.

Larsson, Bengt D. R.: *See—*
Schnittger, Jan R.; Nilson, Carl-Goran; and Larsson, Bengt D. R., 3,580,492.

La Russa, Joseph, to Farrand Optical Co., Inc. Image-forming apparatus. 3,580,660, Cl. 353-122.

Lasco, Ralph H., to Diamond Alkali Company. Sequestering agents for metal ion contamination in side-chain halogenation of alkyl-aromatic hydrocarbons comprising phosphorous halide and organic phosphate. 3,580,854, Cl. 252-181.

Lathrop, Francis M., II: *See—*
Arsdale, Lyle R. Van; and Lathrop, Francis M., II, 3,580,282.

Lauben, Robert W.: *See—*
Beaudoin, Norman R.; and Lauben, Robert W., 3,581,253.

Lauckhardt, Gerhard: *See—*
Muhlbach, Anton; and Lauckhardt, Gerhard, 3,579,692.

Laukien, Gunther R. Pulse spectrometer employing sequences of synchronized modulated pulses. 3,581,193, Cl. 324-0.5.

Lautenschlager, Alfred Johann, to Oerlikon-Buhrie Holding AG. Method for bringing two stationary gearwheels into engagement with one another on a lapping or testing machine. 3,579,803, Cl. 29-434.

Lavander, Edward J., to Xerox Corporation. Exposure apparatus. 3,580,671, Cl. 355-3.

Lavedan, Louis J., to United States of America, Air Force. Variable polarizer for microwave systems. 3,581,242, Cl. 333-1.

Lazurevskaya, Irina Georgievna: *See—*
Badinter, Efim Yakovlevich; Zelkovsky, Zinoviy Ieremeevich; and Lazurevskaya, Irina Georgievna, 3,581,262.

L. & C. Steinmuller G.m.b.H.: *See—*
Knizia, Klaus, 3,580,223.

Lear, Siegler, Inc.: *See—*
Daniel, David W.; and McNabb, Warren C., 3,580,027.

Daniel, David W.; Verschaeve, Henry O.; and McNabb, Warren C., 3,580,029.

Maure, Douglas R.; and Wong, Mei Goon, 3,581,066.

Push, Raymond C., 3,580,635.

Leblond, Jean, to Uniroyal Englebert France S.A. Apparatus for shaping tires. 3,580,782, Cl. 156-415.

le Clerc de Bussy, Jacques Marie Yves. Device for regulating the temperature of glass at the outlet of a very high temperature glass melting furnace. 3,580,976, Cl. 13-6.

Ledex, Inc.: *See—*
Reddel, Robert J.; and Brauner, Edward J., 3,581,283.

Lee, Charles A.; and Furbeck, Warren R., to International Paper Company, mesne. Apparatus for making a bias laid ribbon. 3,580,784, Cl. 156-429.

Lee, Henry J. Polyurethane coating system. 3,580,881, Cl. 260-30.4.

Lee, James O. Spring check. 3,579,708, Cl. 16-52.

Lee, Richard J. Cartridge case reloading. 3,580,127, Cl. 86-24.

Lee, Yoon Chai; and Tremontozzi, Quirino A., to Monsanto Company. Nitrile polymeric blends. 3,580,974, Cl. 260-876.

Leesona Corporation: *See—*
Brouwer, Charles W., 3,580,374.

Settanni, Richard, 3,580,521.

Lefevre, Claude: *See—*
Dolbachian, Raymond; and Lefevre, Claude, 3,581,156.

Lefort, Marcel: *See—*
Ceyzeriat, Louis; Gagnon, Maurice; and Lefort, Marcel, 3,580,939.

Le Goer, Jean Luc: *See—*
Robert, Andre; Bourdon, Claude; and Le Goer, Jean Luc, 3,580,681.

Lehr, Hanns Hanina, to Hoffmann-La Roche Inc. 4-Styrylpyridines. 3,580,909, Cl. 260-240.

Leich, Robert A., to Camdex, Inc. Ammunition reloader. 3,580,128, Cl. 86-31.

Leigh, Thomas, to Imperial Chemical Industries Limited. Resolution process. 3,580,923, Cl. 260-306.7.

Leiner, P., & Sons (Encapsulations) Limited: *See—*
Mehta, Maharaj K., 3,579,734.

Mehta, Maharaj Krishen, 3,579,960.

Leiter, Robert Paul; and Ware, Thomas G. Toilet seat cover. 3,579,663, Cl. 4-230.

Leith, Emmett N.; and Upitnieks, Juris, to Battelle Development Corporation, mesne. Wavefront reconstruction. 3,580,655, Cl. 350-3.5.

Leitten, Carl F., Jr.: *See—*
Piper, John; and Leitten, Carl F., Jr., 3,581,159.

Leitz, Ernest, G.m.b.H.: *See—*
Franke, Georg G. F., 3,581,099.

Leitz, Ernst, G.m.b.H.: *See—*
Loseries, Peter, 3,580,156.

Lekberg, Robert D. Shipboard recirculation sewage system. 3,579,646, Cl. 4-10.

Lenke, Gerd M., to Standard Brands Chemical Industries, Inc. Unique polymers and processes for producing same. 3,580,894, Cl. 260-79.5.

Leonard, Edwin Clifton, to Eskimo Pie Corporation. Container for packing bags. 3,580,470, Cl. 229-15.

Leonard, John E.: *See—*
Watanabe, Hideo; and Leonard, John E., 3,580,239.

Leonardo, Stephen V. Welded member. 3,581,048, Cl. 219-93.

Leone, William C.; and Malone, Robert Lee, to Ex-Cell-O Corporation. Keyboard. 3,581,003, Cl. 178-17.

Leonhard Herbert Maschinenfabrik: *See—*
Balle, Walter; and Pommer, Gunter, 3,579,736.

Leopold, Wilbur R., Jr.; and Smith, John J., to Mueller Co. Wrench. 3,580,270, Cl. 137-318.

Leostic, Joseph, to C.I.T.-Compagnie Industrielle des Telecommunications. Digital controlled step voltage generator. 3,581,116, Cl. 307-264.

Lepetit S.p.A.-Gruppo per la Ricerca Scientifica e la Produzione Chimica Farmaceutica: *See—*
Cavalleri, Bruno; Bellasio, Elvio; and Testa, Emilio, 3,580,932.

L'Equipement par l'Acier Inoxydable (Equipinox): *See—*
Nicolin, Andre J., 3,579,711.

Lerardo, Domenic: *See—*
Adams, Richard C.; Coombes, William S.; and Lerardo, Domenic, 3,580,120.

Lerner, Bernard, to Automated Packaging Corporation. Bag handling apparatus and method. 3,579,948, Cl. 53-29.

Lester Engineering Company: *See—*
Schwartz, William H., 3,579,741.

Letsche, Charles E. Pressure control for tube mill. 3,581,046, Cl. 219-82.

Lettmann, Heinz: *See—*
Hammelmann, Paul; and Lettmann, Heinz, 3,580,511.

Levasseur, Joseph L., to Simcom Corporation. Verification means for character groups. 3,581,063, Cl. 235-61.7.

Levenson, Myron F. Dental paste dispensing tool. 3,579,835, Cl. 32-58.

Leveque, Roger: *See—*
Grente, Lucien Ernest; and Leveque, Roger, 3,579,789.

Lewis, Daniel W.: *See—*
Arnott, Edward G. F.; and Lewis, Daniel W., 3,581,137.

Lewis, Jerry L.: *See—*
Guth, Eugene D.; Lewis, Jerry L.; and Van Nice, Leslie J., 3,580,961.

Lewis, Ralph M.: *See—*
Moorer, Henry D.; Lewis, Ralph M.; and Stokeld, Richard W., Jr., 3,580,962.

L'homme (Societe Anonyme): *See—*
Biancamaria, Joseph, 3,580,146.

LICENTIA Patent-Verwaltungs-G.m.b.H.: *See—*
Hermes, Heinz; Thieme, Klaus-Dietrich; Gattermann, Willi; Koerv, Peter; and Mehnert, Walter, 3,581,185.

Lichtenberger, Joseph A.: *See—*
Pickup, John; Brandts, Theodor G.; and Lichtenberger, Joseph A., 3,580,704.

Lico AG: *See—*
Hammann, Heinz; and Dick, Werner, 3,580,551.

Lien, Millard H., to Crane Co. Sink. 3,579,661, Cl. 4-187.

Lightfoot, George L.: *See—*
Tolf, Ingvar L.; Herzing, Vernon J.; Miller, Everett L.; and Lightfoot, George L., 3,580,402.

Ligon, James T.; and Lang, David L. Aerator and fountain attachments for faucets. 3,580,503, Cl. 239-25.

Lilley, Arthur W.: *See—*
Ramsay, Marcus; and Lilley, Arthur W., 3,580,113.

Lilly, Eli, and Company: *See—*
Garbrecht, William L., 3,580,916.

Hayes, Thomas H., 3,579,883.

Limpach, Paul D.: *See—*
Cramer, Donald L.; and Limpach, Paul D., 3,580,021.

Lindberg, Bernt J.: *See—*
De Belder, Anthony N.; and Lindberg, Bernt J., 3,580,903.

Linde Aktiengesellschaft: *See—*
Dorner, Armin, 3,580,959.

Lindsay, Herbert F. Push button time cycle controller. 3,581,027, Cl. 200-38.

Lindsey, L. E. Suspension bracket for conductor insulator. 3,580,534, Cl. 248-221.

Linkinson, William Simpson: *See—*
Williams, Albert Etheridge; and Linkinson, William Simpson, 3,580,809.

Linn, Donald F.: *See—*
Piaat, C. Lucas; and Linn, Donald F., 3,580,366.

Lipschutz, Lewis D., to International Business Machines Corporation. Thermocompression bonding apparatus. 3,580,460, Cl. 228-4.

Lipton, Charles H.: *See—*
Altman, Norman G., 3,581,282.

Liquid Controls Corporation: *See—*
Siebold, Howard E., 3,580,073.

Lister, Fred: *See—*
Stone, Raymond A.; Lister, Fred; and Heller, David S., 3,580,876.

Littlefield, Derwood F., to General Electric Company. Solid state pulsed electronic control for high speed conveyor sorting device. 3,580,391, Cl. 209-73.

Litton Precision Products, Inc.: *See—*
Spadoni, Frank G., Jr.; and Kleban, Michael P., 3,580,297.

Litton Systems, Inc.: *See—*
Maffitt, Kent N., 3,580,771.

Uridil, Joseph E., 3,580,840.

Littwin, Sheldon; and Schure, Alexander. Teaching device. 3,579,864, Cl. 35-9.

Litvinov, Anatoly Ivanovich: *See—*
Khimich, Georgiy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.

Liu, John K.: *See—*
Kron, Harold O.; Liu, John K.; and Behnke, Edward, 3,580,371.

Lloyd, Norman C.: *See—*
Pearce, Christopher A.; and Lloyd, Norman C., 3,580,941.

Lockhart Manufacturing Corporation: *See—*
Hebert, Gerard E., 3,580,602.
Loeffler, Herbert V. Sprayer boom assembly. 3,580,505, Cl. 239-168.
Loewenstein, Gideon. Sanitary single use toilet seat covers. 3,579,669, Cl. 4-245.
Lofgreen, Earston Arthur, to Occidental Petroleum Corporation. Plastic mulch. 3,580,196, Cl. 111-1.
Lofroth, Enar, to Aktiebolaget Atomenergi. Nuclear reactor fuel element with non-aligned channeling. 3,580,808, Cl. 176-74.
Logan, Edwin W.: *See—*
Hunter, Lee; Senften, David A.; and Logan, Edwin W., 3,579,845.
Logan, Jonathan, Inc.: *See—*
Willis, David M., 3,579,679.
Logan, Robert P.; and Albertson, Orris E., to Dorr-Oliver Incorporated. Heat treated waste sludge disposal. 3,580,193, Cl. 110-8.
Logistics Industries Corporation: *See—*
Reese, Larrie S., 3,580,469.
Lombos, Lazo; and Hughes, Michael Robert, to Dinorwic Slate Quarries Company Limited. Manufacture of slates. 3,580,235, Cl. 125-3.
Long, Joseph F., to International Dynetics Corporation. Compaction apparatus. 3,580,166, Cl. 100-49.
Longo, Vincent.: *See—*
Batlas, George X., 3,580,510.
Lanza-Werke GmbH: *See—*
Gerlach, Fritz; Hauskrecht, Toni; and Holch, Hermann, 3,580,764.
Loomis Machine Company: *See—*
Hecker, Robert W., Jr.; and Beckwith, Robert C., 3,579,696.
Lord Corporation: *See—*
Schmitt, Regis V., 3,580,532.
Lorenzo, Valentin E.: *See—*
Hernandez, Tomas; and Lorenzo, Valentin E., 3,579,848.
Loseries, Peter, to Leitz, Ernst, G.m.b.H. Swinging sector shutter for photographic cameras. 3,580,156, Cl. 95-60.
Loser, Gerhard K., to General Electric Company. Timer with visual indicator for period of operation. 3,581,026, Cl. 200-38.
Loshbough, Richard C., to Reliance Electric Company. Escalator system having fault indicator. 3,580,376, Cl. 198-16.
Loughridge, Frederick A.: *See—*
Britt, Richard G.; and Loughridge, Frederick A., 3,580,710.
Lovelace Foundation for Medical Education and Research: *See—*
Coffey, H. Franklin; and Powers, Samuel T., 3,580,591.
Lowery, Louie R., to Keyes Fibre Company. Arrangement for bagging articles. 3,579,951, Cl. 53-55.
Lowry Development Corporation: *See—*
Lowry, Robert D.; and Strout, Russell B., 3,579,662.
Lowry, Robert D.; and Strout, Russell B., to Lowry Development Corporation. Freeze protected waste trap. 3,579,662, Cl. 4-206.
Loy, George W., to Scio Cabinet Company, Inc. Plastic laminating apparatus. 3,580,787, Cl. 156-477.
LTV Aerospace Corporation: *See—*
Boyce, William C.; and Matza, Edward C., 3,580,528.
Mills, Oscar F., 3,580,411.
Luca, Ioan, to Institutul de Cercetari Tehnologice Pentru Constructii de Masini. Method and apparatus for manufacturing finned pipes. 3,580,026, Cl. 72-96.
Lucas, Joseph, (Industries) Limited: *See—*
Hicks, Harris Vernon, 3,580,663.
Snell, John, 3,579,933.
Wilson, Raymond Michael Christopher, 3,581,205.
Lueck, John R., to General Electric Company. Discharge control element for glass-melting furnaces. 3,580,714, Cl. 65-330.
Luders, Walter: *See—*
Maar, Herbert; Steppan, Hartmut; Messwarb, Gunter; and Luders, Walter, 3,580,888.
Ludlow Typograph Company: *See—*
Higgason, Frank G., Jr.; and Sehnert, Robert J., 3,580,494.
Lukens, Edward E. Foam plastic panel without truss members. 3,579,937, Cl. 52-309.
Luksch, James A.: *See—*
Zimmerman, Arie; Luksch, James A.; and Smith, Gerald D., 3,581,209.
Lumbeck, Gerd: *See—*
Klein, Kurt; Lumbeck, Gerd; and Maluzi, Joachim, 3,580,519.
Lumex, Inc.: *See—*
Murcott, Charles E., 3,580,631.
Lummus Company, The: *See—*
Lutz, Irvin H., 3,580,838.
Lutsey, Thomas H., to Big Drum, Inc. Apparatus for producing frozen coated ice-cream cones. 3,580,188, Cl. 107-1.
Luttich, Werner Richard Gotthard. Tobacco flavoring. 3,580,259, Cl. 131-144.
Lutz, Albert William, to American Cyanamid Company. Process for preparing substituted-6 trifluoromethyluracils. 3,580,913, Cl. 260-260.
Lutz, Irvin H., to Lummus Company, The. Hydrocarbon pyrolysis process. 3,580,838, Cl. 208-100.
Lyall Electric, Inc.: *See—*
Shroyer, Larry L., 3,581,270.
Lynch Corporation: *See—*
Hamilton, Joseph R., 3,580,711.
Lynworth, Lawrence C., to Panametrics, Inc., mesne. Dual ultrasonic sensors employing a single mode of ultrasonic transmission. 3,580,058, Cl. 73-67.7.

Lyons, Donald H.: *See—*
Crites, Nelson A.; and Lyons, Donald H., 3,580,079.
Lyons, Vincent J.: *See—*
Blakeslee, A. Eugene; Gukelberger, Thomas F., Jr.; and Lyons, Vincent J., 3,580,732.
Lytle, Richard F.: *See—*
Schuder, Charles B.; Skov, Victor E.; and Lytle, Richard F., 3,580,288.
Maar, Herbert; Steppan, Hartmut; Messwarb, Gunter; and Luders, Walter, to Kalle Aktiengesellschaft. Polyethers capable of being cross-linked under the action of light and process for their manufacture. 3,580,888, Cl. 260-47.
Maasshoff, Gunter, to Hawk Oil Field Equipment Corporation. Valve operating mechanism. 3,580,138, Cl. 91-277.
Machet, Adrien, to Etablissements MACHET. Explosive table decoration. 3,580,173, Cl. 102-37.2.
Machlett Laboratories, Incorporated, The: *See—*
Peysier, Leonard F.; and Bavor, Gordon F., 3,581,094.
Mac Kenzie, Douglas James, to American Standard, Inc. Thermocouple failure indicating device. 3,580,078, Cl. 73-344.
Mac Key, Donald I.; and Mac Key, Terance Donald. Cold drawing of nylon filaments. 3,579,762, Cl. 28-71.3.
Mac Key, Terance Donald: *See—*
Mac Key, Donald I.; and Mac Key, Terance Donald, 3,579,762.
Mac Phee, Colin A. A.; and Haene, Antonio C. P., to Borg Warner Corporation, mesne. Thermoelectric module with diagonal construction and method of manufacturing. 3,580,743, Cl. 136-212.
Maeda, Seiichiro: *See—*
Ito, Teruhiko; Mitsui, Naoshi; Maeda, Seiichiro; and Kato, Takeshi, 3,580,866.
Maes, Michael E., to Explosives Corporation of America. Field sensitized explosive devices and sensitizing method. 3,580,171, Cl. 102-28.
Maffitt, Kent N., to Litton Systems, Inc. Method for rendering an irregular surface smooth utilizing direct contact transfer. 3,580,771, Cl. 156-235.
Magi, Hugo, to Dominion Auto Accessories Limited. Lamp housing and electric terminal construction. 3,581,080, Cl. 240-8.2.
Magi, Hugo; and Smith, John, to Aqua-Marine Manufacturing Limited. Marine running light construction. 3,581,079, Cl. 240-7.5.
Mahler, Charles J.: *See—*
Hansen, Richard C.; Mahler, Charles J.; Soures, Nicholas M.; and Stickney, Thomas L., 3,581,000.
Maitland, Peter; and Ehrhorn, Richard W. System for simultaneous reception of multiple signals. 3,581,211, Cl. 325-451.
Makela, Aarne Olavi, to Osakeyhtio, A. Ahlstrom. Arrangement for the adjustment of the position of movable machine elements. 3,581,103, Cl. 250-231.
Makino, Tomio, to Nichiel Denki Sangyo K.K. Curling bobbin and heater. 3,581,055, Cl. 219-222.
Malenge, Pierre. Design grid with variable guide. 3,579,859, Cl. 35-27.
Mallory, Donald G.; and Turner, Lyman H., to Xerox Corporation. Sheet feeding apparatus. 3,580,565, Cl. 271-39.
Malone, Robert Lee: *See—*
Leone, William C.; and Malone, Robert Lee, 3,581,003.
Maltis, Frederick Jean, to AMP Incorporated. Spring clip. 3,580,619, Cl. 287-53.
Maltby, Todwick: *See—*
Bond, Harry Laurence Fred; Stubbs, Dennis; and Maltby, Todwick, 3,580,035.
Maltsev, Mikhail Vasilievich: *See—*
Beresnev, Boris Ivanovich; Bulychev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
Maluzi, Joachim: *See—*
Fratzsch, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, 3,580,844.
Klein, Kurt; Lumbeck, Gerd; and Maluzi, Joachim, 3,580,519.
Mancini, John. Novel pitch adjustment means for stringed instruments. 3,580,124, Cl. 84-313.
Mandil, Harry: *See—*
Weems, Sterling J.; and Mandil, Harry, 3,580,806.
Mandonas, Nicholas J.; and Ryll, Paul A., to Western Electric Company. Apparatus for abrading articles. 3,579,922, Cl. 51-165.
Mandrell, Melford E.; and Blaser, Wayne W., to Dow Chemical Company, The. Method of determining the rate of vapor transmission through sheet materials. 3,580,067, Cl. 73-159.
Mannesmann Aktiengesellschaft: *See—*
Schrewe, Hans, 3,580,325.
Manning, Peter R. J., to Tri-Ang Toys Limited. Fertilizer distributor. 3,580,426, Cl. 222-177.
Manos, Philp, to Du Pont de Nemours, E. I., and Company. Imidazole preparation. 3,580,925, Cl. 260-309.
Mansci Kogyo Kabushiki Kaisha: *See—*
Goto, Kenjiro, 3,580,698.
Mansfield, Richard C.: *See—*
Mickus, James C.; Fordyce, David B.; and Mansfield, Richard C., 3,580,855.
Manz, August F., to Union Carbide Corporation. Synchro-arc metal transfer. 3,581,053, Cl. 219-137.
Marandi, Ali; and Solomon, Kenneth H., to Rain Bird Sprinkler Mfg. Corporation. Motor for rotating jet sprinkler. 3,580,508, Cl. 239-241.

Marathon Oil Company: *See—*
Gogarty, William B.; and Mc Atee, Richard W., 3,580,337.
March, Willis Paul: *See—*
Fraser, Colin Kenneth Glenn; Favreau, Ernest; and March, Willis Paul, 3,580,546.
Marek, Charles: *See—*
Keltz, Lawrence W.; and Marek, Charles, 3,579,688.
Maremont Corporation: *See—*
Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., 3,579,761.
Marik, James, to Marik Spring, Inc. Tie-down clip. 3,579,746, Cl. 24-131.
Marik Spring, Inc.: *See—*
Marik, James, 3,579,746.
Markow, Demeter: *See—*
Rasworschegg, Heinrich; Markow, Demeter; and Sandri, Alfred, 3,580,718.
Marks, Lawrence P., to Smith, A. O., Corporation. Load tie down tensioner. 3,580,187, Cl. 105-369.
Marmon Groups, Inc., The: *See—*
Kershaw, John Knox, 3,579,873.
Marondel, Gunther: *See—*
Gawlick, Heinz; and Marondel, Gunther, 3,580,180.
Marquette Electronics, Inc.: *See—*
Johnson, Gilbert A., 3,580,243.
Marshall Sons & Company Limited: *See—*
Barsby, Alan, 3,580,237.
Martin, Benjamin P. Sailboat. 3,580,203, Cl. 114-39.
Martin, Edward J., Jr. Flexible amplification system. 3,581,221, Cl. 330-24.
Martin, Francis C.; and Nicklas, James P., to Cornell Aeronautical Laboratory, Inc. Pattern recognition computer. 3,581,281, Cl. 340-146.3.
Martin, Fred D., to Dow Chemical Company, The. Electromechanical recorder automatic zero apparatus. 3,581,204, Cl. 324-130.
Martin, George, to American Standard, Inc. Shower head. 3,580,513, Cl. 239-460.
Martin, Johannes Josef. Grate for industrial furnaces. 3,580,195, Cl. 110-35.
Martin, William S., to General Electric Company. Face-pumped laser device with optical path folding. 3,581,229, Cl. 331-94.5.
Martinelli, Saverio; and De Varda, Giorgio, to Societa Italiana Telecomunicazioni Siemens S.p.A. Time-sharing telecommunication system. 3,581,016, Cl. 179-15.
Martino, Joseph J. Circuit board drier. 3,579,853, Cl. 34-218.
Martynov, Evgeny Dmitrievich: *See—*
Beresnev, Boris Ivanovich; Bulychev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
Mascaro, Angelo. Switch for sewing machine control and thread cutoff. 3,580,197, Cl. 112-11.
Maschinenfabrik Fr. Niepmann & Co.: *See—*
Niepmann, Otto, 3,580,757.
Masel, Marvin: *See—*
Paradise, Ronald Y.; Masel, Marvin; Naydan, Bob N.; and Brinkman, John D., 3,581,304.
Mason, Charles D.: *See—*
Rosen, Milton K.; and Mason, Charles D., 3,580,898.
Massoubre, Jean-Marie, to Compagnie Generale des Etablissements Michelin raison sociale Michelin & Cie. Polymerization of isoprene. 3,580,899, Cl. 260-94.3.
Mastrapas, George V. Reinforced tire. 3,580,316, Cl. 152-200.
Masuda, Takeo, to Aiwa Co., Ltd. Dynamic microphone. 3,581,015, Cl. 179-121.
Matsubara, Yukio: *See—*
Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.
Matsuda, Shogo: *See—*
Shimodoi, Yutaka; Ootake, Heiichi; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, 3,580,735.
Matsumoto, Masamiki; Nishino, Motohisa; and Tanaka, Yoshimasa, to Matsushita Denko Kabashiki Kaisha. Electric dry shaver. 3,579,824, Cl. 30-43.92.
Matsuo Electric Company, Limited: *See—*
Matsuo, Masao; and Tomiwa, Hiroshi, 3,579,811.
Tomiwa, Hiroshi, 3,579,813.
Matsuo, Masao; and Tomiwa, Hiroshi, to Matsuo Electric Company, Limited. Method of making passive electronic components including laminating terminals. 3,579,811, Cl. 29-570.
Matsushita, Akira. Capacitors and production thereof. 3,579,769, Cl. 29-25.42.
Matsushita Denko Kabashiki Kaisha: *See—*
Matsumoto, Masamiki; Nishino, Motohisa; and Tanaka, Yoshimasa, 3,579,824.
Matsushita Electric Industrial Co., Ltd.: *See—*
Araki, Shigeru; Takahashi, Shozo; and Muto, Ichiro, 3,580,649.
Kitano, Yasushi; and Fujita, Kozo, 3,580,355.
Suzuki, Yoshiaki; and Inamoto, Toshiharu, 3,581,288.
Yamashita, Akio; and Tuzaki, Takehiro, 3,581,233.
Matt, Richard J.; and Restelli, Ronald E., to Tectron Incorporated. Method of making a bearing having a full complement of balls. 3,579,780, Cl. 29-148.4.

Mattel, Inc.: *See—*
Osborne, Brian G., 3,579,902.
Stastny, Edwin O.; Stormon, Lester T.; and Sims, Anson, 3,580,585.
Matthews, William F. Rotary tool attachment for chain saw motor. 3,580,342, Cl. 173-29.
Mattil, Howard F., to Phelps Dodge Copper Products Corporation. Method and apparatus for corrugating tubes. 3,580,024, Cl. 72-77.
Mattsson, Orjan Mats; and Widl, Walter Herbert Ewin, to Telefonaktiebolaget L M Ericsson. Arrangement for disconnecting a defective local concentrator in a data transmission system. 3,581,075, Cl. 235-153.
Matuda, Morio: *See—*
Miya, Bunji; Hoshino, Fumiro; and Matuda, Morio, 3,580,930.
Matulewicz, Leonard A. Method and apparatus for producing a stream feeder. 3,579,807, Cl. 29-471.3.
Matveev, Boris Nikolaevich: *See—*
Zayats, Iosif Lvovich; Barabashkin, Vladimir Pavlovich; Matveev, Boris Nikolaevich; and Shevakin, Jury Fedorovich, 3,580,036.
Matza, Edward C.: *See—*
Boyce, William C.; and Matza, Edward C., 3,580,528.
Maugis, Pierre Marcel, to Societe Technique de Geothermic. Geothermal system. 3,580,330, Cl. 165-45.
Maul, John A.; Zofchak, James T.; and Anderson, David D., to Addressograph-Multigraph Corporation. Settable drum series printing wheel arrangement. 3,580,169, Cl. 101-110.
Maure, Douglas R.; and Wong, Mei Goon, to Lear Siegler, Inc. Programmable counting circuit. 3,581,066, Cl. 235-92.
Maxey, Edward Stanton. Video landing and departure system. 3,580,996, Cl. 178-6.8.
Maxwell, James D. Collapsible fish net. 3,579,890, Cl. 43-12.
Maxwell, Jerrold F.: *See—*
Boehmer, Matthew A.; and Maxwell, Jerrold F., 3,580,847.
May, Michael, to Fichtel & Saahs AG. Method and means for switching on and off the fan wheel of a regulating fan. 3,580,229, Cl. 123-41.12.
Mazza, Lamberto, to Industrie A. Zanussi S.p.A. Machine having a rotary motion, especially washing machine, furnished with ballast. 3,580,014, Cl. 68-23.1.
McAndrew, Francis B.; Price, Martin B.; and Berardinelli, Frank M., to Celanese Corporation. Process for purifying acetals. 3,580,928, Cl. 260-340.
Mc Atee, Richard W.: *See—*
Gogarty, William B.; and Mc Atee, Richard W., 3,580,337.
Mc Avoy, Thomas: *See—*
Kuffer, Clarence O.; and Mc Avoy, Thomas, 3,580,431.
McCabe, Francis J. Fabricated ventilator and method of producing same. 3,580,160, Cl. 98-121.
Mc Call, Frank S.: *See—*
Burke, William R.; and Mc Call, Frank S., 3,580,471.
McCallum, James: *See—*
Firth, Donald; Hancock, Roger Harvey Yorke; and McCallum, James, 3,579,988.
McCammon, James Elvin. Brake operated accelerator disconnect device. 3,580,370, Cl. 192-3.
McCarthy, James B., to Game Innovations, Inc. Bouncing ball game method. 3,580,578, Cl. 273-95.
McCarthy, Richard H., to Stearns Electric Corporation. Universal mounting plate and construction method. 3,580,367, Cl. 188-206.
McClain, Albert D., Jr.: *See—*
Kidd, Thomas L., Jr.; and McClain, Albert D., Jr., 3,580,755.
McClure, Arthur A., to Cerrito, Michael. Insert chaser die head. 3,580,690, Cl. 408-178.
McCombie, Alan Keith: *See—*
Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, 3,579,952.
Mc Dermott, Louis W. Driver training car throttle disconnect. 3,580,100, Cl. 74-482.
McDevitt, James A., to Continental Can Company, Inc. Nestable double-walled disposable container. 3,580,468, Cl. 229-14.
McDonnell Douglas Corporation: *See—*
Brown, Ian McLaren, 3,581,190.
Rosner, Robert E., 3,580,870.
McDonnell, Thomas M. Removable shelf. 3,580,191, Cl. 108-152.
Mc Evers, Bob L.: *See—*
Kvalheim, Andrew M.; and Mc Evers, Bob L., 3,580,792.
McFarland, James D., Jr.: *See—*
Schiefer, Paul J.; and McFarland, James D., Jr., 3,580,372.
Mc Gee, Donald J., to Dura Corporation. Tapered spring leaf suspension for driver tandem axle assembly. 3,580,347, Cl. 180-22.
McGee, Joe H.: *See—*
Hood, John L.; and McGee, Joe H., 3,581,173.
McGrail, Patrick T.: *See—*
Clachan, Margaret L.; McGrail, Patrick T.; and Shephard, Basil R., 3,580,734.
McGrath, Martin H. Vip jacket under skid wire of paper power cables. 3,579,863, Cl. 174-10.
McHargue, Clifford. Device for extracting a mired motor vehicle. 3,580,317, Cl. 152-208.
Mc Intyre, Daniel, to Emhart Corporation. Magazine construction for packing case erecting machine. 3,580,143, Cl. 93-53.
McKay Company, The: *See—*
Delong, William T., 3,580,748.

McKim, Jack D.; and Ulmer, Harold W. Direct view high intensity readout module having conical light conveyor tube. 3,581,307, Cl. 340-366.

McKnight, Charles Allen. Surgical instrument. 3,580,313, Cl. 145-46.

McLaren, Terrence F. Truck. 3,580,346, Cl. 180-19.

McLaughlin, William L., to Morgren, C. A., Co. Directional control valve. 3,580,287, Cl. 137-625.69

McLean, Leslie R. Motorized float. 3,579,680, Cl. 9-1.

McLoughlin, Bernard Joseph: *See—*
Brown, Ivor James Stewart; Clarkson, Richard; Crossley, Neville Stanton; and McLoughlin, Bernard Joseph, 3,580,905.

McMullen, John J., Associates, Inc.: *See—*
Pangalila, Frans V. A., 3,580,207.

McMurray, William, to General Electric Company. Fast response stepped-wave switching power converter circuit. 3,581,212, Cl. 328-14.

McNabb, Warren C.: *See—*
Daniel, David W.; and McNabb, Warren C., 3,580,027.

McNabb, Warren C.: *See—*
Daniel, David W.; Verschaeve, Henry O.; and McNabb, Warren C., 3,580,029.

McNaney, Joseph T. Light guide character forming mask and display device control element. 3,581,308, Cl. 340-380.

McNitt, Lewis F., to Midland-Ross Corporation. Fifth wheel support system. 3,580,611, Cl. 280-433.

Mead Corporation, The: *See—*
Cassill, William Guy, 3,580,515.

Medi-Tech Incorporated: *See—*
Bentov, Itzhak E., 3,579,858.

Mee, John D.; and Heseltine, Donald W., to Eastman Kodak Company. Photographic materials. 3,580,911, Cl. 260-240.65

Mehnert, Walter: *See—*
Hermes, Heinz; Thieme, Klaus-Dietrich; Gattermann, Willi; Koerv, Peter; and Mehnert, Walter, 3,581,185.

Mehta, Maharaj K., to Leiner, P., & Sons (Encapsulations) Limited. Float-operated level control. 3,579,734, Cl. 18-15.

Mehta, Maharaj Krishen, to Leiner, P., & Sons (Encapsulations) Limited. Powder-encapsulation machine. 3,579,960, Cl. 53-184.

Meijer, Albertus Cornelis, to U.S. Philips Corporation, mesne. Neutron spectrometer employing two semi-conductor counters in combination with a coincidence circuit for eliminating background. 3,581,091, Cl. 250-83.1

Meisner, Alfred; and Spitzl, Walter, to Diehl. Stepping wheel. 3,581,128, Cl. 310-21.

Meldau, Robert F., to Phillips Petroleum Company. Production of oil from a pumping well and a flowing well. 3,580,336, Cl. 166-267.

Melnikova, Galina Konstantinovna: *See—*
Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Mariya Konstantinovna; and Kuzina, Alexandra Nikitichna, 3,580,776.

Menell, Hans; and Scheithauer, Walter, to Continental Gummi-Werke Aktiengesellschaft. Pneumatic vehicle tire. 3,580,318, Cl. 152-354.

Mentzer, William R., Jr.: *See—*
Bauer, Peter; and Mentzer, William R., Jr., 3,580,499.

Menzies, William C., Jr., to Atlantic Wool Combing Co. Apparatus for separating fibers. 3,579,744, Cl. 19-97.5

Merck & Co., Inc.: *See—*
Patchett, Arthur A.; and Hannah, John, 3,580,936.

Merkwacz, Joseph, to Garlock Inc. Reinforced expansion. 3,580,616, Cl. 285-229.

Merlin Gerin, Societe Anonyme: *See—*
Pelenc, Yves J.; and Bernard, Georges M., 3,581,202.

Mero, Thomas J.: *See—*
Brown, Archer W.; Montgomery, James L.; Beer, Walter A.; and Mero, Thomas J., 3,580,345.

Merola, Anthony, to Amerola Products Corporation, mesne. Billiard cue and replaceable cue tip assembly. 3,580,576, Cl. 273-70.

Merrill, Neal W.; and Nippert, Charles R., to Bethlehem Steel Corporation. Automated stops for bar bending machine. 3,580,023, Cl. 72-22.

Merten, Rudolf: *See—*
Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,868.

Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.

Merz, Manfred, to Honeywell G.m.b.H. Speed control circuit with two voltage sourced to enable precise speed control over a large speed range. 3,581,175, Cl. 318-305.

Messrs. Gebrüder Junghons Gesellschaft mit Beschränkter Haftung: *See—*
Ganter, Wolfgang; and Assmus, Friedrich, 3,581,129.

Messrs. Volkswagenwerk A. G.: *See—*
Schwenk, Kurt; Gallasch, Ernst; Hablitzel, Hermann; and Jacob, Friedrich, 3,579,727.

Messwarb, Gunter: *See—*
Maar, Herbert; Steppan, Hartmut; Messwarb, Gunter; and Luders, Walter, 3,580,888.

Metal Box Company Limited, The: *See—*
Davies, Kenneth Knapton, 3,580,465.

Metallgesellschaft Aktiengesellschaft: *See—*
Nonnenmacher, Friedrich Karl, 3,580,389.

Metrodynamics Corporation, The: *See—*
Grady, Charles B., Jr., 3,581,187.

Metz, Peter J., Jr., to Crown Zellerbach Corporation. Apparatus for balancing pressure applied to film-forming material in the deposition thereof onto a casting surface. 3,579,735, Cl. 18-15.

Meyer, Forrest C., to Systems Peripherals Division, mesne. Variable frequency delay line differentiator. 3,581,215, Cl. 328-56.

Meyer, Walter, to Oak Electro/netics Corporation. Disc wafer rotary switch with stator printed circuit contact structure and rotor. 3,581,023, Cl. 200-11.

Meyer, Walter, to Oak Electro/netics Corporation. Wafer rotary switch with stator printed circuit contact structure and rotor. 3,581,024, Cl. 200-11.

Meyers, Theodore F., to Hobart Manufacturing Company, The. Hot water heater. 3,581,057, Cl. 219-312.

Meylan-Rochat, Andre, to Parechoc S.A. Regulator-assembly for timepiece. 3,579,977, Cl. 58-112.

Mez Machod, Narodni Podnik: *See—*
Richter, Cestmir, 3,581,131.

Michalke, Klaus A.: *See—*
Verdoort, Marcel E.; and Michalke, Klaus A., 3,579,698.

Michels, Charles E., to Wrapping Machinery Company, Inc. Wrapping method and apparatus. 3,579,949, Cl. 53-33.

Mickus, James C.; Fordyce, David B.; and Mansfield, Richard C., to Rohm and Haas Company. Process for inhibition of scale and corrosion using a polyfunctional phosphate polyol ester having at least 75% primary phosphate ester groups. 3,580,855, Cl. 252-181.

Microdot Inc.: *See—*
Williams, Charles A.; and Waller, Richard E., 3,579,793.

Middlebrooks, Ollie, to Continental Carbon Company. Apparatus for pelletizing carbon black. 3,579,717, Cl. 18-1.

Midland Silicones Limited: *See—*
Pearce, Christopher A.; and Lloyd, Norman C., 3,580,941.

Midland-Ross Corporation: *See—*
De Penti, Kenneth L., 3,580,400.

McNitt, Lewis F., 3,580,611.

Willison, Donald; and Depenti, Kenneth L., 3,580,399.

Mieras, Spencer H., to Borg-Warner Corporation. Differential mechanism. 3,580,108, Cl. 74-711.

Mifflin, Ralph W. Apparatus for deriving the probability density function of a signal with respect to amplitude. 3,581,200, Cl. 324-77.

Mihalkanin, Peter. Tape wrapping apparatus with traveling wheel gear. 3,580,785, Cl. 156-468.

Mihara, Kouichi: *See—*
Shimodoi, Yutaka; Ootake, Heiichiro; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, 3,580,735.

Mihic, Wlajko. Tool holder assemblies. 3,579,776, Cl. 29-96.

Mikolajczak, Alojzy A., to United Aircraft Corporation. Seal construction. 3,580,692, Cl. 415-174.

Miles, Ray P. Skate device for transporting large objects. 3,580,601, Cl. 280-47.13

Milewski, John V.; and Shyne, James J., to General Technologies Corporation. Method of treating the surface of a filament. 3,580,731, Cl. 117-66.

Milewski, Victor, to Valeron Corporation, The. Helical end mill. 3,579,777, Cl. 29-105.

Milford, Richard E., to Honeywell Information Systems Inc., mesne. Optical reading device. 3,581,100, Cl. 250-216.

Milichovsky, Bohumil: *See—*
Jisa, Miloslav; Zmatlik, Josef; Mohelnicky, Josef; and Milichovsky, Bohumil, 3,580,295.

Millar, Alastair Gordon: *See—*
Russell, Alexander; and Millar, Alastair Gordon, 3,581,180.

Miller, Everett L.: *See—*
Tolf, Ingvar L.; Herzing, Vernon J.; Miller, Everett L.; and Lightfoot, George L., 3,580,402.

Miller, Harold A.; Nider, William K.; and Zavialoff, Igor P., to Sicracin Corporation, The. Apparatus for stretching sheet material. 3,579,718, Cl. 18-1.

Miller, John Everett. Polybase counter. 3,579,866, Cl. 35-32.

Miller, Peter S.: *See—*
Wilhelm, D. F.; Miller, Peter S.; Bissell, D. L.; and Lambroff, George M., 3,581,289.

Miller, Sheldon M.: *See—*
Burns, Alvin G.; and Miller, Sheldon M., 3,580,586.

Mills, James Claiborne, Jr.; and Hays, Gordon W., to AMF Incorporated. Bagging apparatus. 3,579,957, Cl. 53-190.

Mills, Oscar F., to LTV Aerospace Corporation. Container having moveable wall. 3,580,411, Cl. 220-4.

Milton, Rex W., to Bauer & Associates, Inc. Shielded arc welding control system. 3,581,052, Cl. 219-131.

Minetos, Nicolae, to Institutul de Cercetari Stiintifice Pentru Protectia Muncii. Protection device for a circular cutting saw. 3,580,307, Cl. 143-159.

Mingotti, Aurelio, to S. A. C. M. I. Cooperativa Meccanici Imola Soc. Coop. A. R. L. Fly press for producing ceramic tiles. 3,579,757, Cl. 25-45.

Ministerul Industriei Constructiilor de Masini: *See—*
Ilescu, Liviu; and Dragos, Ion, 3,580,682.

Minnesota Mining & Manufacturing Company: *See—*
Hubin, Allen J., 3,580,887.

Minnesota Mining and Manufacturing Company: *See—*
Wear, Robert L., 3,580,927.

Mintz, Leonard A. Stamping press with linearly applied force. 3,580,794, Cl. 156-581.

Mintz, Michael J., to Dow Chemical Company, The. Photochlorination of monoh and Di-chloroethane. 3,580,831, Cl. 204-163.

Misarc, Donald O., to Joslyn Mfg. and Supply Co. Corona free coupling assembly for coaxial cables. 3,580,986, Cl. 174-73.

Mitchell, James W., Jr., to Ford Motor Company. Spot welding process. 3,581,047, Cl. 219-91.

Mitchell, Ralph W. Cutter chain. 3,580,639, Cl. 299-84.

Mitsubishi Paper Mills, Ltd.: *See—*
Ohyama, Yasushi; and Miyazawa, Sadayuki, 3,580,720.

Mitsubishi Rayon Co., Ltd.: *See—*
Higashimura, Einosuke; Tamai, Katsumi; and Nakamura, Eiichi, 3,580,879.

Ikeda, Masashi; and Inoue, Masayoshi, 3,580,947.

Mitsui, Naoshi: *See—*
Ito, Teruhiko; Mitsui, Naoshi; Maeda, Seiichiro; and Kato, Takeshi, 3,580,866.

Mitsui Shipbuilding and Engineering Co., Ltd.: *See—*
Kurashiki, Hajime; and Ikuta, Yoshiharu, 3,580,211.

Mitten, Frank P. Combined wrapping and taping work table. 3,579,962, Cl. 53-390.

Miura, Tanetoshi; Koshikawa, Tsuneji; Nakano, Yasuaki; and Nakayama, Takeshi, to Hitachi, Ltd. Frequency spectrum analyzer with displayable colored shiftable frequency spectrogram. 3,581,192, Cl. 324-77.

Miya, Bunji; Hoshino, Fumiro; and Matuda, Morio, to Kao Soap Co., Ltd. Process for producing gamma-butyrolactone. 3,580,930, Cl. 260-343.6

Miyahara, Michito: *See—*
Ogawa, Kazuki; and Miyahara, Michito, 3,580,708.

Miyahune, Yoshio. Perpetual calendar. 3,579,882, Cl. 40-107.

Miyamoto, Shoji: *See—*
Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro, and Miyamoto, Shoji, 3,580,895.

Miyasaka, Tsugumitsu: *See—*
Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.

Miyazawa, Sadayuki: *See—*
Ohyama, Yasushi; and Miyazawa, Sadayuki, 3,580,720.

Mizrany, Ronald A.: *See—*
Radford, James T.; and Mizrany, Ronald A., 3,579,905.

M&J Development Company: *See—*
Grove, Marvin H., 3,580,765.

M&J Valve Company: *See—*
Arsdale, Lyle R. Van; and Lathrop, Francis M., II, 3,580,282.

Grove, Marvin H., 3,580,765.

Mobil Oil Corporation: *See—*
Cox, John B.; and Stoltz, Jacques R., 3,580,072.

Ruchle, William H., 3,581,274.

Mobley, Odess V., to Hoerner Waldorf Corporation. Stacking trays. 3,580,475, Cl. 229-34.

Mobsby, Eric George Herbert, to United Kingdom Atomic Energy Authority. Acoustic thermometers. 3,580,076, Cl. 73-339.

Mohan, William L.: *See—*
Willits, Samuel P.; and Mohan, William L., 3,581,067.

Mohelnicky, Josef: *See—*
Jisa, Miloslav; Zmatlik, Josef; Mohelnicky, Josef; and Milichovsky, Bohumil, 3,580,295.

Mohr, Reinhard: *See—*
Mundlos, Eberhard; Mohr, Reinhard; Trapp, Gunther; and Hohmann, Kurt, 3,580,900.

Molins, Desmond Walter, to Molins Machine Company Limited. Cigarettes testing. 3,580,053, Cl. 73-41.

Molins Machine Company Limited: *See—*
Molins, Desmond Walter, 3,580,053.

Molins Machines Company Limited: *See—*
Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, 3,579,952.

Mollen, Ignatius J., to Ariens Company. Self-propelled garden tractor vehicle. 3,580,351, Cl. 180-53.

Mon, George, to United States of America, Army. Method of making capillary assemblies for oxygenators and the like. 3,579,810, Cl. 29-527.1

Monacelli, Umberto. Compressed air stapling machine for metallic staples with control of the anvil for bending the staple ends. 3,580,458, Cl. 227-124.

Mongodin, Guy: *See—*
Greenberg, Sol; Rosen, Heinz; Weinberger, Richard; and Mongodin, Guy, 3,580,081.

Monsanto Chemicals Limited: *See—*
Hall, Robert Leonard, 3,580,485.

Monsanto Company: *See—*
Carter, Ernest P.; Bell, Robert P., Jr.; and Carroll, Alton P., Jr., 3,580,296.

Criner, Gaspard X.; and Blackburn, William A., 3,580,763.

Fowler, Timothy J., 3,580,190.

Harrington, Edwin C., Jr., 3,580,134.

Isaksen, Robert A.; and De Shay, Robert V., 3,580,972.

Lambuth, Alan L., 3,580,872.

Lee, Yoon Chai; and Tremontozzi, Quirino A., 3,580,974.

Nielsen, Lawrence E.; and Fields, Joseph E., 3,580,882.

Rademacher, Leo E., 3,580,975.

Monsanto Research Company: *See—*
Webster, James A., 3,580,940.

Monsanto Research Corporation: *See—*
Salzer, Ival O.; Jefferson Robert T.; and Ross, William D., 3,580,843.

Monterey Mills, Inc.: *See—*
Nielsen, William L., 3,579,647.

Montgomery, James L.: *See—*
Brown, Archer W.; Montgomery, James L.; Beer, Walter A.; and Mero, Thomas J., 3,580,345.

Moore Business Forms Inc.: *See—*
Winston, Rodney W.; and Witham, Peter M., 3,580,614.

Moore, Carroll E., to Farmhand, Inc. Conveyor attachment for portable feed mill. 3,580,548, Cl. 259-95.

Moore, Douglas A.: *See—*
Vogel, Alvin R.; Moore, Douglas A.; Folan, Martin P.; and Buck, John R., 3,581,014.

Moore, Robert B., Jr., to Eastman Kodak Company. Guiding apparatus for eliminating entanglement and twist in puddled multifilament yarn. 3,580,445, Cl. 226-97.

Moore, Robert D. Ashtray structures. 3,580,260, Cl. 131-242.

Moore, Robert D., 1/2 to Faulkner, Kenneth F. Entertainment system. 3,580,667, Cl. 352-124.

Moorer, Henry D.; Lewis, Ralph M.; and Stokeld, Richard W., Jr., to Texaco Inc. Alkylation process employing flash vaporization of extracted and acid-treated absorption product. 3,580,962, Cl. 260-683.62

Morain, Eldon W., to Continental Industries, Inc. Tool for simultaneously beveling mating pipes. 3,579,826, Cl. 30-93.

Morel, Joseph. Bone implant. 3,579,830, Cl. 32-10.

Morey, Dennison H., Jr.; Silva, Melvin; and Browning, Gordon D. Capacitance moisture meter and wing-like probe. 3,581,197, Cl. 324-61.

Morey, Thomas H.: *See—*
Pope, Karl D., III; Morey, Thomas H.; and Tierney, Robert R., 3,579,681.

Morgan, Bert B.: *See—*
Caneer, Ralph A.; Anderson, William J.; Morgan, Bert B.; and Goodman, Jerry M., 3,579,760.

Morgan, Douglas H. Artificial articular eminence for the mandibular joint. 3,579,643, Cl. 3-1.

Morgan, John Robert. Support for growing plants. 3,579,908, Cl. 47-45.

Morgan, Philip R., to Acme Appliance Manufacturing Company. Door latch. 3,580,622, Cl. 292-169.

Morgren, C. A., Co.: *See—*
McLaughlin, William L., 3,580,287.

Morioka, Isao. Method for reproducing three-dimensional image. 3,580,758, Cl. 156-58.

Morita, Tosio: *See—*
Watari, Daisaku; and Morita, Tosio, 3,581,044.

Moriya, Nobuharu, to Fuji Denki Kogyo Co., Ltd. Apparatus and method for making spherical granules. 3,579,719, Cl. 18-1.

Moro, Antonio, to Soc. per Azioni Fratelli Borletti. Thermally responsive switch. 3,581,263, Cl. 337-380.

Morozowich, Walter; and Sinkula, Anthony A., to Upjohn Company. The 7-Halo-7-deoxy-lincosamin derivatives. 3,580,904, Cl. 260-210.

Morris, Dennis E., to Varian Associates. Pulse forming network for a short pulse linear accelerator. 3,581,145, Cl. 315-30.

Morris, Leo R., to Dow Chemical Company, The. 1,1-Dichloro-1-nitroethane derivatives. 3,580,948, Cl. 260-487.

Morris, William J., to Philco-Ford Corporation. Cabinet structure. 3,580,650, Cl. 312-7.

Morton, Jack A.: *See—*
Boyle, Willard S.; and Morton, Jack A., 3,581,151.

Moschel, Albrecht, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Process for purifying polyether amines. 3,580,952, Cl. 260-584.

Moser, William J. Loading ramps for trailers. 3,580,404, Cl. 214-85.

Mosher, Ralph S., to General Electric Company. Articulating mechanism. 3,580,099, Cl. 74-469.

Motorola, Inc.: *See—*
Enderby, Ralph T., 3,581,240.

Gregson, Robert E., 3,581,114.

Knutson, William J., 3,581,239.

Krahulec, Fred, 3,580,177.

Seelbach, Walter C.; and Lampathakis, Kyriakos E., 3,581,165.

Weinberger, Aaron David, 3,581,186.

Mounts, Frank W., to Bell Telephone Laboratories, Incorporated. Redundancy reduction data compressor with luminance weighting. 3,580,999, Cl. 178-71.

Moyer, Hallard C.; and Fauber, Eugene M., to Atlantic Richfield Company. Paperboard impregnated with a petroleum wax-polyurethane blend. 3,580,736, Cl. 117-155.

Mueller Co.: *See—*
Leopold, Wilbur R., Jr.; and Smith, John J., 3,580,270.

Mueller, Hubert W., Jr.: *See—*
Granberg, Mauritz L.; and Mueller, Hubert W., Jr., 3,581,076.

Mueller, Werner: *See—*
Stutz, Theo; and Mueller, Werner, 3,581,301.

Muhlbach, Anton; and Lauckhardt, Gerhard, to USM Corporation. Shoe machines. 3,579,692, Cl. 12-8.3

Muirhead Limited: *See—*
Bell, John, 3,580,205.

Muller, Ernest. Marine propeller shafts bearing arrangements. 3,580,214, Cl. 115-34.

- Muller, Gunter: See—
Blankenhorn, Gerhard; and Muller, Gunter, 3,579,755.
- Muller, Jakob. Method and apparatus for detecting an undesired condition of a shuttle-carried weft yarn. 3,580,294, Cl. 139-371.
- Muller, Jean Jacques, to International Standard Electric Corporation. Mobile radiotelephone communication system. 3,581,013, Cl. 179-41.
- Mumford, Eustace H., to Owens-Illinois, Inc. Glass forming mold elements with yielding supports. 3,580,712, Cl. 65-307.
- Mundlos, Eberhard; Mohr, Reinhard; Trapp, Gunther; and Hohmann, Kurt, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Water-soluble quaternary amine containing monoazo dyestuffs. 3,580,900, Cl. 260-149.
- Murakami, Yasukazu: See—
Numa, Yoshiaki; Nakamachi, Akio; and Murakami, Yasukazu, 3,580,917.
- Murayama, Yoshimasa; and Kurono, Hirokazu, to Hitachi, Ltd. Tunable semiconductor bulk negative resistance microwave oscillator. 3,581,232, Cl. 331-107.
- Murcott, Charles E., to Lumex, Inc. Invalid chair. 3,580,631, Cl. 297-155.
- Murphy, David M., to David Manufacturing Co. Grain stirring device. 3,580,549, Cl. 259-102.
- Murphy, Edward L. Carousel sign. 3,579,880, Cl. 40-33.
- Murphy, Herman G. Snow deflector unit. 3,579,930, Cl. 52-24.
- Murray, William Bruce; and Wright, Roy E., to Philadelphia Quartz Company of California. Corrosion prevention with sodium silicate and soluble zinc salts. 3,580,934, Cl. 252-389.
- Musgrove, Johnnie J. Mowing machine. 3,579,965, Cl. 56-7.
- Mussell, Dorsey R.; and Schwartzbeck, Richard A., to Dow Chemical Company, The. Method for plant growth regulation. 3,580,716, Cl. 71-76.
- Muto, Ichiro: See—
Araki, Shigeru; Takahashi, Shozo; and Muto, Ichiro, 3,580,649.
- Muttart, Vincent H. Clamping mechanism for molding machine. 3,579,742, Cl. 18-30.
- Myers, John G., and Field, Joseph H., to United States of America, Interior. Method of removing sulfur oxides from gases. 3,580,702, Cl. 23-25.
- Myers, Thomas Leroy, to Stedman Foundry and Machine Company, Incorporated. Breaker plate assembly for a disintegrator. 3,580,520, Cl. 241-299.
- Myrice, Frank D.: See—
Weaver, Robert L.; and Myrice, Frank D., 3,580,395.
- Nagao, Kazuyoshi, to Canon Camera Co., Ltd. Photo-electric and electric light conversion element. 3,581,102, Cl. 250-227.
- Nagel, Erlich: See—
Zahn, Wolfgang; Nagel, Erlich; and Langer, Reinhold, 3,580,155.
- Nagy, Ernest J., to Pullman Incorporated. Combination gravity and pneumatic gate arrangement for hoppers. 3,580,642, Cl. 302-52.
- Naito, Hiroshi: See—
Yashiro, Katsuji; and Naito, Hiroshi, 3,580,104.
- Nakagawa, Masaharu, to Alps Electric Company Limited. Oscillator feedback circuit for use in UHF tuner. 3,581,237, Cl. 331-117.
- Nakamachi, Akio: See—
Numa, Yoshiaki; Nakamachi, Akio; and Murakami, Yasukazu, 3,580,917.
- Nakamori, Shigeru: See—
Shio, Isamu; Nakamori, Shigeru; and Sano, Kou-nosuke, 3,580,810.
- Nakamura, Eiichi: See—
Higashimura, Einosuke; Tamai, Katsumi; and Nakamura, Eiichi, 3,580,879.
- Nakano, Yasuaki: See—
Miura, Tanetoshi; Koshikawa, Tsuneji; Nakano, Yasuaki; and Nakayama, Takeshi, 3,581,192.
- Nakanome, Iyohiko; Takeya, Kenji; Suzuki, Hiroshi; and Kitagawa, Yasuhiko, to Japan Exlan Company Limited. Flame-resistant acrylonitrile copolymers with high receptivity to acid dyes. 3,580,878, Cl. 260-29.6.
- Nakayama, Takeshi: See—
Miura, Tanetoshi; Koshikawa, Tsuneji; Nakano, Yasuaki; and Nakayama, Takeshi, 3,581,192.
- Nakayama, Toshio: See—
Ohi, Kunio; Inoue, Hideaki; Nakayama, Toshio; and Ishii, Sosuke, 3,581,245.
- Nance, David. Method and apparatus for combatting aircraft fires. 3,580,339, Cl. 169-2.
- Narco Scientific Industries, Inc.: See—
Visher, Wilbur A., 3,581,073.
- Narita, Hiroshi: See—
Tsuboi, Takashi; and Narita, Hiroshi, 3,581,172.
- Narumiya, Tsuneaki: See—
Yoshimoto, Toshio; Narumiya, Tsuneaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, 3,580,897.
- Naske, Christoph, to WHB-Anbaumobil von Poschinger K.G. Connecting fixture. 3,580,535, Cl. 248-239.
- Nasonov, Petr Yakovlevich: See—
Kononov, Mikhail Ivanovich; Krashennnikov, Evgeny Anatolievich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaeovich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich, 3,580,717.
- National Catheter Corporation: See—
Jackson, Isaac S., 3,580,983.
- National Distillers and Chemical Corporation: See—
Quackenbush, John J., 3,580,413.
- Watson, Lloyd M.; and Birchall, William R., 3,580,862.
- National Gypsum Company: See—
Shull, John D., Jr., 3,580,390.
- National Industrial Manufacturing: See—
Baker, Edward D., 3,580,164.
- National Research Development Corporation: See—
Brown, Kenneth William; and Balchin, Nigel C., 3,581,050.
- Brown, Kenneth William, 3,581,051.
- Firth, Donald; Hancock, Roger Harvey Yorke; and McCallum, James, 3,579,988.
- National Research Development Corporation: See—
Hobbs, Peter Alfred, 3,580,417.
- Nauchno-Issledovatel'skiy Institut Monomernov Dlya Sinteticheskogo: See—
Bodnarjuk, Frizian Nikolaevich; and Korshunov, Mikhail Alexeevich, 3,580,918.
- Naumenko, Viktor Arsenievich; Torortseva, Tatiana Nikolaevna; Penkova, Lidia Fedorovna; Vyselkov, Andrei Akimovich; and Rogova, Galina Ivanovna. Separator-electrolyte carrier for primary cells. 3,580,742, Cl. 136-155.
- Navcor, Inc.: See—
Jones, John Paul, Jr., 3,580,495.
- Naydan, Bob N.: See—
Paradise, Ronald Y.; Masel, Marvin; Naydan, Bob N.; and Brinkman, John D., 3,581,304.
- Nearman, Richard E., to Automated Handling Systems, Inc. Trolley and hanger apparatus. 3,580,183, Cl. 104-111.
- Nearman, Richard E., to Eaton Yale & Towne Inc. Signal disabling device. 3,580,382, Cl. 198-38.
- Nebelsiek, Hilbert J.: See—
Ginsburgh, Irwin; and Nebelsiek, Hilbert J., 3,580,414.
- Nederlandse Organisatie voor Toegepost-Natuurwetenschappelijk Onderzoek ten behoeve van Nijverheid, Handel en Verkeer: See—
Van Staveren, Pieter, 3,580,356.
- Nedschroef Octrooi Maatschappij N.V.: See—
Van de Meerendonk, Gerardus Cornelis, 3,579,685.
- Neff, Teodorico. Photoelectric bubble meter for checking gas-tight containers and the like. 3,581,101, Cl. 250-218.
- Necma, Farid J.; and Engelhardt, Robert C., to Honeywell Inc. Keyboard to memory peripheral device. 3,581,285, Cl. 340-172.5.
- Neild, Donald William, to General Electric Company Limited, The. Counting device including an escapement with no automatic return bias. 3,580,496, Cl. 235-92.
- Nejame, Samuel, Jr.; Kondel, George C.; and De Santis, Italo J., to Damon Corporation, mesne. Continuous flow liquid distributing system. 3,580,301, Cl. 141-131.
- Nelson, Harold E., Jr., to Rohr Corporation. Thrust reversing apparatus for jet-propelled aircraft. 3,579,991, Cl. 60-232.
- Nelson, William E.: See—
Kennedy, Garth P.; and Nelson, William E., 3,580,420.
- Nercessian, Sarkis, to Forbro Design Corporation. Bipolar operational power supply. 3,581,224, Cl. 330-99.
- Netzer, Theodor Karl: See—
Trinks, Walter; Netzer, Theodor Karl; Victoria, Hans T.; Saurer, Hermann; and von Paulger, Heinrich, 3,580,048.
- Neutron Products, Inc.: See—
Ransohoff, Jackson A.; and Hairston, James J., Jr., 3,581,095.
- Newman, La Verne R., to Essex International, Inc. Vehicle light control and warning indicator system. 3,581,276, Cl. 340-52.
- Newman, Stanley F.: See—
Hoory, Sadok E.; Newman, Stanley F.; and Vincent, Robert E., 3,580,819.
- Newton, Augustus L. Receptacle disposal container adapter. 3,580,408, Cl. 214-302.
- Nichiel Denki Sangyo K.K.: See—
Makino, Tomio, 3,581,055.
- Nichols, Gordon E., to Winthrop-Atkins Co., Inc. Slant front easel. 3,580,536, Cl. 248-459.
- Nicklas, James P.: See—
Martin, Francis C.; and Nicklas, James P., 3,581,281.
- Nicolin, Andre J., to L'Equipment par l'Acier Inoxydable (Equipinox). Means for attaching a detachable handle for kitchen utensil vessels. 3,579,711, Cl. 16-114.
- Nider, William K.: See—
Miller, Harold A.; Nider, William K.; and Zavialoff, Igor P., 3,579,718.
- Nielsen, Einer Dale, to Signetics Corporation. Digital logic clamp for limiting power consumption of interface gate. 3,581,107, Cl. 307-215.
- Nielsen, Erik Christian Valeur, to Bodenhoff, Max, A/S. Typewriter table. 3,580,652, Cl. 312-208.
- Nielsen, Lawrence E.; and Fields, Joseph E., to Monsanto Company. Mica-reinforced composites. 3,580,882, Cl. 260-41.
- Nielson, William L., to Monterey Mills, Inc. Toilet tank cover. 3,579,647, Cl. 4-1.
- Niepmann, Otto, to Maschinenfabrik Fr. Niepmann & Co. Web wind-up machines. 3,580,757, Cl. 156-504.
- Nilson, Carl-Goran: See—
Schnittger, Jan R.; Nilson, Carl-Goran; and Larsson, Bengt D. R., 3,580,492.

- Nilsson, Oake Valentin: See—
Olsson, Tore Bertil Reinhold; and Nilsson, Oake Valentin, 3,581,109.
- Nippert, Charles R.: See—
Merrill, Neal W.; and Nippert, Charles R., 3,580,023.
- Nippon Gakki Seizo Kabushiki Kaisha: See—
Amano, Hiroshi, 3,580,979.
- Nippon Kokan Kabushiki Kaisha: See—
Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotu, 3,581,039.
- Nippon Steel Corporation: See—
Tsujiata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuha, Zensaku, 3,581,070.
- Nippon Tungsten Company, Ltd.: See—
Ogawa, Kazuki; and Miyahara, Michito, 3,580,708.
- Nischk, Gunther: See—
Engelhard, Helmut; Bentz, Francis; Rinkler, Heinrich; and Nischk, Gunther, 3,580,966.
- Nishimura, Akihiro, to Dow Badische Company. Dyeable pill-resistant polyesters. 3,580,874, Cl. 260-22.
- Nishimura, Takeshi: See—
Hibi, Masao; and Nishimura, Takeshi, 3,581,097.
- Nishino, Motohisa: See—
Matsumoto, Masamiki; Nishino, Motohisa; and Tanaka, Yoshimasa, 3,579,824.
- Niskovskikh, Vitaly Maximovich: See—
Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.
- Nisshin Kasai Kabushiki Kaisha: See—
Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.
- Nittai Lease Company Ltd.: See—
Tomizawa, Kazuhiro, 3,580,093.
- Noiles, Douglas G. TV on time control. 3,581,029, Cl. 200-38.
- Nolan, George J.; and Holm, Vernon C. F., to Phillips Petroleum Company. Dehydrogenation of olefins. 3,580,969, Cl. 260-666.
- Nomiya, Kosei: See—
Hatsukano, Yoshikazu; and Nomiya, Kosei, 3,581,065.
- Nonnenmacher, Friedrich Karl, to Metallgesellschaft Aktiengesellschaft. Screw conveyor. 3,580,389, Cl. 198-213.
- Noonan, Michael F.; and Fisher, James J. Football field area identification means. 3,580,573, Cl. 273-55.
- Nord, Hans H., to Western Union Telegraph Company, The. Schmitt trigger circuit with variable hysteresis and insensitivity to temperature change. 3,581,120, Cl. 307-290.
- Nordland, George W. Golf cart bag securement apparatus. 3,580,533, Cl. 248-96.
- Norell, John R., to Phillips Petroleum Company. Substituted 2-aminomalonamides production. 3,580,967, Cl. 260-557.
- North American Rockwell Corporation: See—
Polkinghorn, Robert W., 3,581,292.
- Northrop Carolina, Inc.: See—
Caneer, Ralph A.; Anderson, William J.; Morgan, Bert B.; and Goodman, Jerry M., 3,579,760.
- Northrop Corporation: See—
Vogel, Alvin R.; Moore, Douglas A.; Folan, Martin P.; and Buck, John R., 3,581,014.
- Northrop, Walter A. Bumper combining hitch and step. 3,580,613, Cl. 280-500.
- Northwood, John Lenard: See—
Ranby, Peter Whitten; and Northwood, John Lenard, 3,580,738.
- Norton Company: See—
Coes, Loring, Jr., 3,579,927.
- Densmore, William P., 3,579,925.
- Herbert, David B.; and Barney, Ronald N., 3,580,322.
- Noyes, Theodore A. Vacuum support for animals. 3,580,221, Cl. 119-96.
- Nuclear-Chicago Corporation: See—
Peoples, Joseph T.; and Landry, Charles C., 3,581,106.
- Nueman, William H.; and Repella, James A., to Federal-Mogul Corporation. Seal testing device. 3,580,061, Cl. 73-88.
- Numa, Yoshiaki; Nakamachi, Akio; and Murakami, Yasukazu, to Daciel Ltd. Process for producing pyridine bases. 3,580,917, Cl. 260-290.
- Numakura, Toshihiko, to Sony Corporation. Recording and reproducing system for color video signals. 3,580,990, Cl. 178-5.2.
- Numao, Mitsuru: See—
Kashahara, Toshio; and Numao, Mitsuru, 3,580,756.
- Nunes, John F., Jr. Sod handling machine. 3,580,375, Cl. 198-8.
- N.V. Machinefabriek L. Te Strake: See—
Fransen, Theodorus, 3,580,293.
- Van Mullekom, Hubert P., 3,580,444.
- Nymeyer, Frederick. Auction market computation system. 3,581,022, Cl. 235-152.
- Oak Electro/netics Corporation: See—
Meyer, Walter, 3,581,023.
- Meyer, Walter, 3,581,024.
- Ober, Horgern: See—
Fichtner, Rudi; Ober, Horgern; and Klein, Wilhelm, 3,579,691.
- Oberkirch, Wolfgang: See—
Gunther, Peter; Oberkirch, Wolfgang; and Pampus, Gottfried, 3,580,892.
- O'Brien, Edward D., to Stauffer Chemical Company. Apparatus for agglomerating dusts and the like. 3,580,545, Cl. 259-3.
- O'Brien, Jay Philip: See—
Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, 3,580,949.
- Occidental Petroleum Corporation: See—
Lofgreen, Earston Arthur, 3,580,196.
- Ocean Science and Engineering, Inc.: See—
Jantzen, Robert J., 3,579,872.
- Ocean Systems Incorporated: See—
Pilia, Frank J., 3,581,042.
- Oerlikon-Buhrle Holding AG: See—
Lautenschlager, Alfred Johann, 3,579,803.
- Oetiker, Hans. Compression band. 3,579,754, Cl. 24-279.
- Oettinger, Joseph S. Shipping envelope. 3,580,489, Cl. 229-70.
- Offenbroich, Adrian Gottfried. Fastening devices. 3,580,620, Cl. 287-54.
- Office National d'Etudes et de Recherches Aerospatiales (par abreviation O.N.E.R.A.): See—
Daigne, Bernard M.; and Pelletier, Louis, 3,581,086.
- Ogawa, Kazuki; and Miyahara, Michito, to Nippon Tungsten Company, Ltd. Method of forming cutting tool materials consisting of alumina and titanium carbide. 3,580,708, Cl. 51-307.
- Ohi, Kunio; Inoue, Hideaki; Nakayama, Toshio; and Ishii, Sosuke, to Hitachi Electronics Co., Ltd. Microwave absorber for waveguide termination. 3,581,245, Cl. 333-22.
- Ohlstein, Paul E., to United States of America, Navy. Squib-powered automatic inflation device. 3,579,964, Cl. 222-5.
- Ohyama, Yasushi; and Miyazawa, Sadayuki, to Mitsubishi Paper Mills, Ltd. Photographic sensitized papers excellent in fluorescent brightening effect and process for preparing the same. 3,580,720, Cl. 96-82.
- O'Keeffe, Trencé W.: See—
Simon, Alan J.; Johnson, Joseph E.; and O'Keeffe, Trencé W., 3,580,749.
- Okuyama, Chiyoshi; and Osumi, Syuzo. Ferroelectric ceramic materials. 3,580,846, Cl. 252-62.9.
- Olaf Bendik Elmer: See—
Djenner, Richard, 3,581,056.
- Olin Corporation: See—
Creith, Lou C., 3,581,049.
- Dilday, Joseph T., 3,580,715.
- Heinzel, Joseph A., 3,579,840.
- Ramsay, Marcus; and Lilley, Arthur W., 3,580,113.
- Olin Mathieson Chemical Corporation: See—
Churchill, John W.; Kober, Ehrenfreid H.; Scott, Peter H.; and Smith, Curtis P., 3,580,951.
- Cooper, Roy M., 3,580,833.
- Kuzma, John J.; and Gawrych, Robert L., 3,579,891.
- Vartanian, Edwin S., 3,580,132.
- Olmstead, Merlin E.: See—
Shear, Wayne G.; Everett, Samuel R.; and Olmstead, Merlin E., 3,581,309.
- Olofson, Arne K. Backing ring centering device. 3,579,844, Cl. 33-180.
- Olson, Birger H. Controlled release safety cleat. 3,580,209, Cl. 114-218.
- Olsson, Tore Bertil Reinhold; and Nilsson, Oake Valentin, to Aktiebolaget Bofors. Circuit system for producing an output signal from a variable amplitude signal when the amplitude of said signal is within a selected range. 3,581,109, Cl. 307-235.
- Olvey, James O., Sr. Bead-head fly with dangling spinner. 3,579,892, Cl. 43-42.11.
- Olympus Optical Company Limited: See—
Shigetomi, Sadao; and Saito, Shoichi, 3,581,022.
- O'Mara, William H.; and Wood, Owen J., to Aerovox Corporation. Method of forming tubular mica capacitor. 3,579,770, Cl. 29-25.42.
- Omlin, Luc, to Centre Electronique Horloger S. A. Mounting device for flexion vibrators. 3,581,126, Cl. 310-9.1.
- Omron Tateisi Electronics Co.: See—
Asada, Takeo; and Kamiya, Toshihiro, 3,580,121.
- Onishi, Akira; Anzai, Shiro; Irako, Koichi; Fujio, Ryota; Hayakawa, Yoshihiro; and Miyamoto, Shoji, to Bridgestone Tire Company Limited. Production of copolymers in the presence of an organolithium compound and an orthoester. 3,580,895, Cl. 260-83.7.
- Ootake, Heiichiro: See—
Shimodoi, Yutaka; Ootake, Heiichiro; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, 3,580,735.
- Orlowski, Donald W.; and Schroeder, Donald S., to Ampex Corporation. Grommet for speaker enclosure. 3,580,988, Cl. 174-153.
- Orn, Vernon B.; and Cook, Richard E. Artificial fish lure and method of making same. 3,579,895, Cl. 43-17.6.
- Oroza, August, to U.S. Divers. Oxygen generators. 3,580,250, Cl. 128-203.
- Orshansky, Elias, Jr., to URS Systems Corporation. Transmission. 3,580,107, Cl. 74-687.
- Osakeyhtio, A. Ahlstrom: See—
Makela, Aarne Olavi, 3,581,103.
- Osborne, Brian G., to Mattel, Inc. Doll structure including appendage with fastener trapped therein for connecting to torso. 3,579,902, Cl. 46-149.
- Ostrowsky, Efrem M.: See—
Heffernan, Bart T.; and Ostrowsky, Efrem M., 3,579,642.
- Osumi, Syuzo: See—
Okuyama, Chiyoshi; and Osumi, Syuzo, 3,580,846.

Otsukakoki Kabushiki Kaisha: *See—*
Yashiro, Katsuji; and Naito, Hiroshi, 3,580,104.
Ott, Robert E., to SCM Corporation. Food cooking apparatus having continuous cleaning properties and process for producing same. 3,580,733, Cl. 117-129.
Otto, Gunter: *See—*
Spieth, Rudolf; and Otto, Gunter, 3,580,559.
Overend, Thomas F. Mud flaps for dump trucks. 3,580,604, Cl. 280-154.5
Ovitron Corporation: *See—*
Hughes, George T., 3,579,886.
Owens, Walter K. Commode flushing mechanism. 3,579,648, Cl. 4-52.
Owens-Illinois, Inc.: *See—*
Griffith, Edwin D., 3,580,464.
Mumford, Eustace H., 3,580,712.
Schirm, Helmut T.; and Zeigler, Robert O., 3,580,713.
Wilhelm, D. F.; Miller, Peter S.; Bissell, D. L.; and Lambroff, George M., 3,581,289.
Oxley, Gerald K.: *See—*
Jorgensen, Anker E.; and Oxley, Gerald K., 3,580,101.
Oy Wartsila AB: *See—*
Burmeister, Fred; Enkvist, Ernst; Johansson, Bengt; and Kostilainen, Valter, 3,580,204.
P'osser, David G., to Autotrol Corporation. Softener control assembly. 3,580,615, Cl. 285-81.
Pacciarini, Antonio; and Caretta, Renato, to Pirelli S.p.A. Method for manufacturing pneumatic tires. 3,580,766, Cl. 156-123.
Packaging Corporation of America: *See—*
Thelen, Edmund J.; and King, Robert H., 3,580,466.
Packaging Industries, Inc.: *See—*
Rohdin, Howard A.; and Brown, Fred P., Jr., 3,580,442.
Packard, Robert F., to Technical Metals, Inc. Production of elongated extrusions composed of titanium base metal. 3,579,800, Cl. 29-423.
Paget, John A., to United States of America, Atomic Energy Commission. Lifting mechanism and refueling machine. 3,580,804, Cl. 176-30.
Paielli, Michael F. Fifth wheel with load transferring device. 3,580,609, Cl. 280-405.
Palamarchuk, Vladimir Ivanovich: *See—*
Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich, 3,580,554.
Pall (Canada) Ltd.: *See—*
Gaspari, Anthony Mario, 3,579,926.
Pallich, Adolf, to Zbrojovka, narodni podnik. Anesthetizing gun for use in slaughtering animals. 3,579,889, Cl. 42-1.
Palmer, Ansell W., to Honeywell Information Systems Inc. Record scanner with loading and indexing means. 3,581,064, Cl. 235-61.11
Pampus, Gottfried: *See—*
Gunther, Peter; Oberkirch, Wolfgang; and Pampus, Gottfried, 3,580,892.
Panametrics, Inc.: *See—*
Brinkerhoff, Joris M.; Hunerwadel, Jean L.; and Sellers, Francis B., 3,581,087.
Lynnworth, Lawrence C., 3,580,058.
Pangalila, Frans V. A., to McMullen, John J., Associates, Inc. Method and means for mooring. 3,580,207, Cl. 114-144.
Panko, Walter B.; and Steindler, Julius P., to Engis Equipment Company. Universal clamp for abrasive tool. 3,579,912, Cl. 51-59.
Panschow, Rudolf; Russbult, Herbert; Suhr, Volker; and Ullmann, Werner, to AG fur Industrielle Elektronik AGIE. Digitally controlled electro-erosion machine. 3,581,045, Cl. 219-69.
Paquette, Raymond E., to Varo, Inc., mesne. High intensity light source with integral radiant energy coupling apparatus. 3,581,140, Cl. 313-110.
Paradise, Ronald Y.; Masel, Marvin; Naydan, Bob N.; and Brinkman, John D., to Singer-General Precision, Inc. Analog-to-digital cyclic forward feed successive approximation conversion equipment. 3,581,304, Cl. 340-347.
Parechoc S.A.: *See—*
Meylan-Rochat, Andre, 3,579,977.
Park, William G.: *See—*
Arvidson, Paul W.; Park, William G.; and Williams, Keith S., 3,580,130.
Parke, Davis & Company: *See—*
Short, Franklin W., 3,580,926.
Parker, Phillip H., to Chevron Research Company. Method for making corrugated thermoplastic articles. 3,580,769, Cl. 156-206.
Parks, John C.: *See—*
Bean, Dennis P.; and Parks, John C., 3,580,030.
Parr, Leslie R.: *See—*
Boot, Herbert W.; Parr, Leslie R.; and Fudger, Shirley L. W., 3,579,695.
Parran, John J., Jr., to Procter & Gamble Company. The Detergent compositions containing particle deposition enhancing agents. 3,580,853, Cl. 252-152.
Patchett, Arthur A.; and Hannah, John, to Merck & Co., Inc. 5 β -Taurocholic acids and 5 β -taurocholic acids. 3,580,936, Cl. 260-397.
Patelhold Patentverwertungs- & Elektro-Holding AG: *See—*
Kach, Alfred, 3,581,311.
Pavelle Corporation, The: *See—*
Aston, Keith, 3,581,062.

Pavonet, Engelhard, to Fosindus Company. Process for the purification of residual gypsum formed in the manufacture of phosphoric acid by the action of sulphuric acid on natural phosphates. 3,580,703, Cl. 23-122.
Payne, Arthur Albert, to Girling Limited. Tool for use with disc brakes. 3,580,544, Cl. 254-131.
Payseure, Lawrence A., to Chesapeake and Ohio Railway Company, The, and Baltimore and Ohio, Railroad Company, The. Train length measuring device. 3,581,071, Cl. 235-151.32
Pearce, Christopher A.; and Lloyd, Norman C., to Midland Silicones Limited. Aminocyclotetrasiloxanes. 3,580,941, Cl. 260-448.2
Pearl, Curtis F.: *See—*
Batlas, George X., 3,580,510.
Pearsall, Denton; and Jankowitz, Gerald, to Barnes Engineering Company. Pyroelectric detector array. 3,581,092, Cl. 250-83.3
Pearson, Arthur W. Trailer hitch. 3,580,612, Cl. 280-492.
Pedersen, Erik J. Automatic hanger discharge. 3,580,378, Cl. 198-25.
Pederson, Arthur M., to United States of America, Navy, mesne. Frequency to binary converter. 3,581,069, Cl. 235-92.
Pedrazzoli, Andrea; and Dall'Asta, Leone, to Societe d'Etudes de Recherches et d'Application Scientifiques et Medicales E.R.A.S.M.E. Derivatives of N-methylpiperazine. 3,580,914, Cl. 260-268.
Peeler, Robert L.: *See—*
Furby, Neal W.; Godfrey, Douglas; and Peeler, Robert L., 3,580,848.
Pelenc, Yves J.; and Bernard, Georges M., to Merlin Gerin, Societe Anonyme. Devices for the electro-optical measurement of an electrical quantity. 3,581,202, Cl. 324-96.
Pelletier, Louis: *See—*
Daigne, Bernard M.; and Pelletier, Louis, 3,581,086.
Penkova, Lidia Fedorovna: *See—*
Naumenko, Viktor Arsenievich; Torortseva, Tatiana Nikolaevna; Penkova, Lidia Fedorovna; Vyselkov, Andrei Akimovich; and Rogova, Galina Ivanovna, 3,580,742.
Pennwalt Corporation: *See—*
Bafford, Richard Anthony, 3,580,955.
Penstar Industries, Inc.: *See—*
Arnould, Marcel M.; Ward, John C., Jr.; Ray, William Floyd; and Budzyn, Boleslaw L., 3,580,386.
Peonski, Edward, to American Gage & Machinery Company. Gage with variable response amplifier. 3,579,843, Cl. 33-147.
Peoples, Joseph T.; and Landry, Charles C., to Nuclear-Chicago Corporation. Graded plane, high voltage DC power supply. 3,581,106, Cl. 307-150.
Pepe, Frank W. Tool for removing concentric knockouts. 3,579,797, Cl. 29-267.
Perfection Manufacturing Company, The: *See—*
Allina, Stanley F., 3,579,966.
Perhaas, Leslie, Jr., to Cragstan Industries, Inc. Kaleidoscope pull-toy construction. 3,579,901, Cl. 46-103.
Perilstein, Warren L., to Ethyl Corporation. Process for preparing overbased barium sulfonates, products therefrom and use in distillate fuel oils. 3,580,707, Cl. 44-51.
Perkin, Richard S., to Perkin-Elmer Corporation, The. Solar spectrographs. 3,580,679, Cl. 356-76.
Perkin-Elmer Corporation, The: *See—*
Perkin, Richard S., 3,580,679.
Perkins, Carroll R.; Shaffstall, Everett L.; Gundersen, James L.; and Yoder, Robert N., to Hughes Aircraft Company. Differential amplifier circuit using field effect transistors. 3,581,226, Cl. 330-30.
Perkins, Earl Stuart, to Butler National Corporation. Full data altimeter display. 3,580,080, Cl. 73-384.
Perret, Henri: *See—*
Dubost, Pierre J.; and Perret, Henri, 3,579,875.
Person, Herman R., to Dale Electronics, Inc. Method of creating variable electrical resistance and means for creating the same. 3,581,264, Cl. 338-20.
Perthen, Johannes; Gerighausen, Werner; Kunzmann, Konrad; and Dreyer, Heinz, said Gerighausen, said Kunzmann and said Dreyer assors to said Perthen. Surface measuring device. 3,580,062, Cl. 73-105.
Pest, Jurgen, to General Electric Company. Circuit for providing inductive impedance. 3,581,123, Cl. 307-304.
Peters, Theodore F., to General Motors Corporation. Latch mechanism. 3,580,623, Cl. 292-201.
Petersen, Paul S., to Rosemount Engineering Company. Moire fringe producing device used for interception course indication. 3,581,275, Cl. 340-25.
Petersen, Rudolph S., to Sanders Associates, Inc. Control valve. 3,580,281, Cl. 137-596.16
Peterson, Dana. Protractor. 3,579,841, Cl. 33-75.
Peterson, John R., to Kaiser Aluminum & Chemical Corporation. Electrolytic reduction cell. 3,580,835, Cl. 204-243.
Pettersson, Tor: *See—*
Spencer, Lloyd; and Pettersson, Tor, 3,580,091.
Pettersson, Karl-Olof: *See—*
Regebro, Ebbe Torsten Leonard; and Pettersson, Karl-Olof, 3,579,666.
Pettibone Corporation: *See—*
Hall, Frank B., 3,581,157.
Pettit, Carl S. Condition responsive automatic dialing apparatus. 3,581,021, Cl. 179-90.
Peyser, Leonard F.; and Bavor, Gordon F., to Machlett Laboratories, Incorporated, The. X-ray apparatus. 3,581,094, Cl. 250-105.

Pfander, Hans; Schilling, Harald; and Schwabe, Gerhard, to International Telephone and Telegraph Corporation. Junction capacitance component, especially for a monolithic microcircuit. 3,581,164, Cl. 317-234.
Pfarrwaller, Erwin, to Sulzer Brothers Limited. Coupling. 3,580,011, Cl. 64-27.
Pfister, Stanley A., to Cincinnati Milacron Inc. Machine tool. 3,579,812, Cl. 29-568.
Pfizer Inc.: *See—*
Butler, Kenneth, 3,580,908.
Cameron, Donald P., 3,580,921.
Pfrehm, Raymond H., to Esso Research and Engineering Company. Meter prover. 3,580,045, Cl. 73-3.
Pharmacia AB: *See—*
De Belder, Anthony N.; and Lindberg, Bernt J., 3,580,903.
PHELPS Dodge Copper Products Corporation: *See—*
Mattil, Howard F., 3,580,024.
Philadelphia Quartz Company of California: *See—*
Murray, William Bruce; and Wright, Roy E., 3,580,934.
Philamon Incorporated: *See—*
Grib, Boris F., 3,581,130.
Philco-Ford Corporation: *See—*
Bar-On, Ari; and Emslie, Norman M., 3,580,064.
Morris, William J., 3,580,650.
Phillips, Virgil, to Federal Auto Products Co., Inc. Dispensing valve for a sealed pressurized container. 3,580,424, Cl. 222-89.
Phillips, Bryce W., to Reynolds Metals Company. Method of and apparatus for orienting indicia bearing cylindrical objects. 3,580,380, Cl. 198-33.
Phillips Petroleum Company: *See—*
Boultinghouse, Harold D., 3,580,761.
Meldau, Robert F., 3,580,336.
Nolan, George J.; and Holm, Vernon C. F., 3,580,969.
Norell, John R., 3,580,967.
Reid, Richard K.; and Welty, Richard O., 3,579,728.
Photovolt Corporation: *See—*
Schulkind, Herbert, 3,580,683.
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, to Autophon Aktiengesellschaft. Character indicator with means for monitoring the correct positioning. 3,581,183, Cl. 318-696.
Piccoli, Mario, to Somet S.p.A. Societa Meccanica Tessile. Filling carrier for use in shuttleless looms. 3,580,291, Cl. 139-122.
Piccone, Dante E.; and Rosser, Daniel B., to General Electric Company. Semiconductor rectifier assembly having high explosion rating. 3,581,160, Cl. 317-234.
Pickup, John; Brandts, Theodor G.; and Lichtenberger, Joseph A., to Consolidated Paper (Bahamas) Limited. Colorimetric indicators for determining pH of motor oil. 3,580,704, Cl. 23-230.
Piechota, Helmut: *See—*
Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,868.
Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.
Pierard, Arthur E.: *See—*
Cardwell, Lonnie D.; Esenwein, Fred T.; and Pierard, Arthur E., 3,580,049.
Pierce, Harold C. Carloading box spacers. 3,580,186, Cl. 105-369.
Pierce, Paul W. Beehive. 3,579,676, Cl. 6-2.
Pierie, Charles G. Door return and check mechanism. 3,579,709, Cl. 16-65.
Pierson, Karl B.: *See—*
Hanson, John R.; and Pierson, Karl B., 3,580,275.
Pieszak, Franklin B.; and Knaggs, Marvin G., to Carroll Plastics Corporation. Carburator package. 3,580,467, Cl. 229-14.
Pietsch, Raymond L., to Engineered Products Company, The. Magnetic door catch with riser. 3,579,934, Cl. 49-394.
Pilarski, Anthony J.: *See—*
Gurrieri, Salvatore J., 3,579,657.
Pilia, Frank J., to Ocean Systems Incorporated. Underwater welding method. 3,581,042, Cl. 219-61.
Pingree, Robert J., to Ameron, Inc., mesne. Material feeding apparatus. 3,580,384, Cl. 198-64.
Piper, John; and Leitten, Carl F., Jr., to Union Carbide Corporation. Solid electrolyte capacitor having improved counterelectrode system. 3,581,159, Cl. 317-230.
Pirelli Societa per Azioni: *See—*
Priaroggia, Paolo Gazzana, 3,580,987.
Pirelli S.p.A.: *See—*
Pacciarini, Antonio; and Caretta, Renato, 3,580,766.
Pitidis, Nicola: *See—*
Dal Monte, Giorgio; and Pitidis, Nicola, 3,581,008.
Plaat, C. Lucas; and Linn, Donald F., to Goodrich, B. F., Company, The. Brake retractor resetting mechanism. 3,580,366, Cl. 188-196.
Placements Jean Paul Tanguay Ltce: *See—*
Tanguay, Jean Paul, 3,580,306.
Plawner, Moshe L.; Vento, Vincent R.; and Gordon, Abraham, to United States of America, Air Force. Hydraulic gimbal lock. 3,580,363, Cl. 188-74.
Pletscher, Theodor. Gebruder Pletscher Bicycle support. 3,580,607, Cl. 280-301.
Pliskin, William A.; and Taylor, James E., to International Business Machines Corporation. Method for detecting exposure of a base material through an overlying coating. 3,580,066, Cl. 73-150.

Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., to Maremont Corporation. Apparatus for yarn removal. 3,579,761, Cl. 28-19.
Plumat, Emile; and Duthoit, Jean, to Glaverbel, S.A. Apparatus for subdividing fluid mass into grains. 3,579,720, Cl. 18-2.5
Plumb, Frank J., to J-B-T Instruments, Inc. toggle switch. 3,581,033, Cl. 200-67.
Plummer, Calvin C. Heat radiator and burner with adjustable connection to gas supply line. 3,580,236, Cl. 126-59.5
Pneumatic Scale Corporation: *See—*
Trusselle, William H., 3,580,298.
Podgorski, Theodore J., to Honeywell Inc. Adjustable, thin membrane mirror for use in the stabilization of ring lasers. 3,581,227, Cl. 331-94.5
Polkinghorn, Robert W., to North American Rockwell Corporation. Read/write memory circuit. 3,581,292, Cl. 340-173.
Pollitzer, Ernest L., to Universal Oil Products Company. Hydrorefining of coke-forming hydrocarbon distillates. 3,580,837, Cl. 208-57.
Pollmeier, Heinz; and Witthuhn, Johann, to Klebetechnik GmbH. Apparatus for the automatic wrapping of rotatable bodies. 3,580,790, Cl. 156-521.
Polymer Corporation, The: *See—*
Endle, Joseph, 3,580,289.
Polytronic S. A.: *See—*
Scharz, Armin; and Scharz, Oskar, 3,580,579.
Pommer, Gunter: *See—*
Balle, Walter; and Pommer, Gunter, 3,579,736.
Pontecorvo, Nicholas E. Apparatus for processing cheese curd into homogenous cheese. 3,580,161, Cl. 99-243.
Pontecorvo, Nicholas E. Cheese kneading apparatus. 3,580,162, Cl. 99-243.
Pope, Karl D., III; Morey, Thomas H.; and Tierney, Robert R. Sectional and longitudinally adjustable surfboard fin assembly. 3,579,681, Cl. 9-310.
Porsche, Dr.-Ing. H.c.F., K.G., Firma: *See—*
Strohm, Siegfried, 3,581,206.
Posey, John T.: *See—*
Preston, Walter George, 3,580,523.
Possis Machine Corporation: *See—*
Schuette, Thomas L.; Straub, Melvin J.; Dumas, Pierre; and Aurich, Peter F., 3,579,771.
Postmark Corporation: *See—*
Iverson, Peter B., 3,579,885.
Postmaster General, Her Majesty's: *See—*
Cosier, James Edwin Henry, 3,579,739.
Potter Instrument Company, Inc.: *See—*
Schoeneman, Robert E., 3,580,453.
Pötz, Klaus: *See—*
Hennig, Fridolin; Kellner, Hans-Jurgen; Potz, Klaus; and Gotze, Christian, 3,580,443.
Potzl, Friedrich, to U.S. Philips Corporation. Micro-wave tube cooling assembly. 3,581,251, Cl. 333-83.
Powell, Alfred, H. Electrician's tool for longitudinally and circumferentially cutting insulation on wire. 3,579,825, Cl. 30-90.7
Powell, James C., to All-Steel Equipment Inc. Apparatus for making knock-outs in electrical boxes formed of plastic material. 3,580,122, Cl. 83-108.
Powell, Jonathan S. Means for securing couplings to pipe. 3,579,794, Cl. 29-237.
Powell, Patrick L., to Stewart-Warner Corporation. Tamper prevention apparatus for odometer. 3,580,497, Cl. 235-96.
Power Industries Limited: *See—*
Sparks, Derick A., 3,580,450.
Powers Regulator Company: *See—*
Duchek, Ernest J., 3,580,502.
Sherman, Russell G.; and Koenig, Robert P., 3,580,272.
Powers, Samuel T.: *See—*
Coffey, H. Franklin; and Powers, Samuel T., 3,580,591.
PPG Industries, Inc.: *See—*
Hartzell, Rowland S.; and Gere, Gene, 3,580,777.
Prasse, Herbert F.; and Hensley, Loyd D., to Ramsey Corporation. Circumferentially expanding oil control ring. 3,580,589, Cl. 277-140.
Precision Processes (Textiles) Limited: *See—*
Wray, Dennis; and Johnson, Janet M., 3,580,701.
Presta, Eugene A.: *See—*
Hammond, Robert A.; and Presta, Eugene A., 3,580,998.
Preston, Walter George, to Posey, John T. Retractable safety belt for hospital gurneys and the like. 3,580,523, Cl. 242-107.1
Preus, Paul; and Rosendahl, Charles E. Barrier for control of substances in bodies of water. 3,579,994, Cl. 61-1.
Priaroggia, Paolo Gazzana, to Pirelli Societa per Azioni. Electric cable. 3,580,987, Cl. 174-120.
Price, Glenn R.; and Walsh, Edward N., to Stauffer Chemical Company. Phosphorylated heterocyclic compounds. 3,580,922, Cl. 260-304.
Price, John A.: *See—*
Stewart, Mary J.; and Price, John A., 3,580,886.
Price, Martin B.: *See—*
McAndrew, Francis B.; Price, Martin B.; and Berardinelli, Frank M., 3,580,928.
Price, Ralph E., to Landis Tool Company. Work driving device. 3,579,914, Cl. 51-101.
Priessnitz, Edmund F., to Electronic Transmission Systems, Inc. Magnetic holding drum. 3,581,257, Cl. 335-285.

- Procter & Gamble Company, The: See—
Darragh, Richard T.; and Succo, John A., 3,580,729.
Fanta, Wayne I.; and Erman, William F., 3,580,953.
Fanta, Wayne I.; and Erman, William F., 3,580,954.
Parran, John J., Jr., 3,580,853.
- Provost, Emile L.; and Tomasello, Antonio, to Gellman Industries, Inc. Container magazine for dispensing labels. 3,580,474, Cl. 229-20.
- Pryor, Dale H., to Youngstown Sheet and Tube Company. Pipe-gripping apparatus. 3,579,753, Cl. 24-263.
- Psychological Corporation, The: See—
Bennett, George K.; and Buchanan, Richard G., 3,579,870.
- Pullen, Robert K. Packed snow and ice remover for highways and the like. 3,580,638, Cl. 299-25.
- Pullman Incorporated: See—
Nagy, Ernest J., 3,580,642.
- Purex Corporation, Ltd.: See—
Benham, Ralph E., 3,580,504.
- Push, Raymond C., to Lear Siegler, Inc. Reclining forward folding seat. 3,580,635, Cl. 297-355.
- Putnam, Peter A.: See—
Stevens, Roger L.; Putnam, Peter A.; and Sicon, Martin, 3,581,017.
- Quackenbush, John J., to National Distillers and Chemical Corporation. Clear thermoplastic multi-ply meat tray and absorbent strips. 3,580,413, Cl. 220-83.
- Quebec North Shore Paper Company: See—
Hamilton, Douglas D., 3,580,308.
- Quick, Lester K. Central refrigeration system with automatic standby compressor capacity. 3,580,006, Cl. 62-196.
- Quillevre, Herve Alain: See—
Caruel, Jacques Emile Jules; Quillevre, Herve Alain; and Bauger, Louis, 3,579,983.
- Quinn, Frederic R., to Zyrotron Industries, Inc. Modulating valve construction. 3,580,500, Cl. 236-12.
- Rachlin, Albert Israel: See—
Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, 3,580,949.
- Radecki, Tony, to Rain Bird Sprinkler Mfg. Corporation. Distance selector for sprinklers. 3,580,514, Cl. 239-521.
- Rademacher, Leo E., to Monsanto Company. Vinyl halide graft polymers. 3,580,975, Cl. 260-878.
- Radford, James T.; and Mizrany, Ronald A. Aircraft, battery and battery-carrying means, wherein the conductive wires serve as manipulating wires. 3,579,905, Cl. 46-244.
- Rain Bird Sprinkler Mfg. Corporation: See—
Beamer, John D., 3,580,507.
Costa, Robert B., 3,580,506.
Marandi, Ali; and Solomon, Kenneth H., 3,580,508.
Radecki, Tony, 3,580,514.
- Rainer, Norman B., to Seekay Chemical Company. Water-insoluble, cross-linked polymeric reaction product of ethylene diamine and nitrilotriacetic acid or derivative. 3,580,891, Cl. 260-72.
- Raisin, Jean-Pierre: See—
Voisin, Eugene; Raisin, Jean-Pierre; and Delair, Jean-Paul, 3,580,012.
- Rambousek, Zdenek, to Elitex, Zavody textilniho strojirenstvi. Apparatus and method for positioning warp sheds. 3,580,292, Cl. 139-190.
- Ramsay, Marcus; and Lilley, Arthur W., to Olin Corporation. Electrical ignition firearm with a forwardly sliding barrel. 3,580,113, Cl. 42-84.
- Ramseier, Serge, to Battelle Development Corporation, The. Motion converting mechanism. 3,580,089, Cl. 74-49.
- Ramsey Corporation: See—
Prasse, Herbert F.; and Hensley, Loyd D., 3,580,589.
- Ramsey, Edward L., Jr.: See—
Frey, Dean R.; Hone, George L.; and Ramsey, Edward L., Jr., 3,581,269.
- Ramsey, Hubert J.: See—
Ingraham, Robert C.; and Ramsey, Hubert J., 3,579,816.
- Ranby, Peter Whitten; and Northwood, John Lenard, to Thorn Electrical Industries Limited. Plastics materials with conductive surfaces. 3,580,738, Cl. 117-215.
- Ransdell, Bill J. Smoothly acting signal comparator. 3,581,218, Cl. 328-146.
- Ransohoff, Jackson A.; and Hairston, James J., Jr., to Neutron Products, Inc. Source plaque for an irradiation chamber of curvilinear cross section. 3,581,095, Cl. 250-106.
- Rantala, Charles W., to General Motors Corporation. Rocker molding installation. 3,580,628, Cl. 296-1.
- Rapidograph, Inc.: See—
Riepe, Helmut, 3,580,689.
- Rapinat, Michel, to L'Air Liquide, Societe Anonyme pour l'Etude et l'Exploitation des Procédes George Claude. Cryopumping installations with high flow-rates. 3,579,997, Cl. 62-55.5.
- Rasmussen, Robert F., to Honeywell Inc. Control apparatus. 3,580,139, Cl. 91-411.
- Rasworschegg, Heinrich; Markow, Demeter; and Sandri, Alfred, to Waagner-Biro Aktiengesellschaft. Method for the utilization of hot waste gases from furnaces of metallurgical works. 3,580,718, Cl. 75-60.
- Rathbun, William H., to General Electric Company. Gas-blast circuit interrupter with magnetic means for accelerating merger of series-related arcs. 3,581,035, Cl. 200-148.
- Rathje, Ove: See—
Andersen, Ole Stig; and Rathje, Ove, 3,580,694.
- Raupach, Friedrich. Electro-magnetic wiring system of interlinked coils particularly suitable in a current transformer for high voltages. 3,581,258, Cl. 336-173.
- Rauterkus, Karl Josef; and Vollmann, Hansjorg, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Process for the manufacture of polymer dispersions with positive zeta potential. 3,580,871, Cl. 260-17.
- Raval, Jean Ernest Paul. Wrist band. 3,580,438, Cl. 224-4.
- Raven Electronics Corporation: See—
Raven, Richard C., 3,580,581.
- Raven, Richard C., to Raven Electronics Corporation. Probability generating system and game for use therewith. 3,580,581, Cl. 273-138.
- Ray, William Floyd: See—
Arnould, Marcel M.; Ward, John C., Jr.; Ray, William Floyd; and Budzyn, Boleslaw L., 3,580,386.
- Raychem Corporation: See—
Lanza, Vincent L., 3,580,829.
- RCA Corporation: See—
Dodds, Wellesley Jamison, 3,581,002.
Klensch, Richard J., 3,580,995.
Smith, William Irving, 3,581,244.
Wheatley, William Richard, 3,581,162.
- Realistic Company, The: See—
Gilman, John M., 3,580,423.
- Reddel, Robert J.; and Brauner, Edward J., to Ledex, Inc. Tone decoder responsive to combined tones. 3,581,283, Cl. 340-171.
- Reddy, Thomas Bradley, to American Cyanamid Company. Electrodeposition of lithium. 3,580,828, Cl. 204-14.
- Redeco, Inc.: See—
Schwartz, Ralph E., 3,579,999.
- Reed, Charles C., Jr. Crown and bridge remover. 3,579,834, Cl. 32-43.
- Rees, Herbert, to Husky Manufacturing and Tool Works Ltd. Mechanism for closing and opening injection molds. 3,579,740, Cl. 18-30.
- Reese, Larrie S., to Logistics Industries Corporation. Corner pad. 3,580,469, Cl. 229-14.
- Regan, James L. Paint can rim piercer. 3,579,678, Cl. 7-14.1.
- Regan, James L. Explosive tendon tensioning means. 3,579,758, Cl. 25-118.
- Regan, James L.; and Garnhart, David L., said Garnhart assor. to said Regan. System for erecting multi-storey buildings. 3,579,935, Cl. 52-126.
- Regebro, Ebbe Torsten Leonard; and Pettersson, Karl-Olof. Swimming pool. 3,579,666, Cl. 4-172.19.
- Reich, Karl M., Maschinenfabrik: See—
Cast, Adolf; and Schwarz, Heinz, 3,580,455.
- Reid, Richard K.; and Welty, Richard O., to Phillips Petroleum Company. Polymer separation. 3,579,728, Cl. 18-12.
- Reis, Robert D., to United Electric Controls Company. Piston valve. 3,580,280, Cl. 137-596.14.
- Reist, Walter, to Ferag, Fehr & Reist AG. Apparatus for opening folded articles, such as newspapers. 3,580,562, Cl. 270-54.
- Reliance Electric and Engineering Company, The: See—
Seed, Aniese E., 3,580,095.
- Reliance Electric Company: See—
Loshbough, Richard C., 3,580,376.
- Renard, John J. Apparatus for erecting and forming initially collapsed cartons into containers. 3,580,144, Cl. 93-53.
- Rental Equipment Manufacturing Corporation: See—
Thompson, David R., 3,579,702.
- Renz, Werner: See—
Geymayer, Peter; Billenstein, Siegfried; and Renz, Werner, 3,580,849.
- Repella, James A.: See—
Nueman, William H.; and Repella, James A., 3,580,061.
- Repsher, Robert W.: See—
Haft, Harry H.; and Repsher, Robert W., 3,581,139.
- Resener, Baird E., to Amsted Industries Incorporated. Attachments for a flexible belt. 3,580,388, Cl. 198-198.
- Restelli, Ronald E.: See—
Matt, Richard J.; and Restelli, Ronald E., 3,579,780.
- Rester, Darryl C.: See—
Terrell, Kyle E.; and Rester, Darryl C., 3,580,341.
- Revco Inc.: See—
Vermes, Roy E., 3,580,145.
- Reynolds Metals Company: See—
Barker, Layle B., 3,579,665.
Cvacho, Daniel S.; and Fritchey, Edward H., 3,580,200.
Phillips, Bryce W., 3,580,380.
Witte, Richard F., 3,580,482.
- Reynolds, R. J., Tobacco Company: See—
Bernasek, Edward; and Eaton, Calley Neil, 3,580,906.
- Rhodes, David R., to Chevron Research Company. Electrolytic coulometer titration system. 3,580,832, Cl. 204-195.
- Rhodes, Richard D., Jr.; and Flanagan, Kirby E. L., to Davidson Rubber Company, Inc. Microcellular polyurethane foams based on aromatic polyamines and propoxylated aniline. 3,580,869, Cl. 260-2.5.
- Rhone-Poulenc S.A.: See—
Ceyzeriat, Louis; Gaignon, Maurice; and Lefort, Marcel, 3,580,939.

- Ribbentrop, Annemarie: See—
Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,910.
- Thiel, Max; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,907.
- Ribner, Morris; and Hestad, Alfred M., to International Telephone and Telegraph Corporation. Ringing tone distribution circuits. 3,581,020, Cl. 179-84.
- Riccus, Rolf: See—
Bock, Gerhard; Riccius, Rolf; Weitkamp, Gunter; and Wolf, Bernhard, 3,580,531.
- Richards, William R., to Textron Inc., mesne. Snowmobile track. 3,580,647, Cl. 305-35.
- Richter, Cestmir, to Mez Machod, Narodni Podnik. Small electric motors for dental equipment or the like. 3,581,131, Cl. 310-58.
- Richter, Eugene P., Jr. Nut harvester. 3,579,969, Cl. 56-328.
- Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., to Windmoller & Holscher FMC Corporation. Apparatus for paper sacks manufacture Bag stack accumulating conveyor. 3,580,141, Cl. 93-33.
- Rickard, Earl K.: See—
Blackburn, Samuel S., Jr.; and Rickard, Earl K., 3,580,226.
- Rieder, Otto E., to General Impact Extrusions (Manufacturing) Ltd. Method for forming flash holes in cartridge cases. 3,579,767, Cl. 29-1.3.
- Riegel Paper Corporation: See—
Young, Chauncey, 3,580,483.
- Riegel Textile Corporation: See—
Teed, Richard K.; and Klose, Karl W., 3,580,198.
- Riepe, Helmut, to Rapidograph, Inc., mesne. Tubular writing head for a tubular writing pen. 3,580,689, Cl. 401-258.
- Riesenberg, James H., to Consolidated Packaging Machinery Corporation. Container filling machine. 3,580,302, Cl. 141-141.
- Rieth, Lawrence E., to Stewart-Warner Corporation. Automotive license lamp assembly. 3,581,081, Cl. 240-8.3.
- Riley, Eugene D.: See—
Sagouspe, Jean; and Riley, Eugene D., 3,579,971.
- Rinkler, Heinrich: See—
Engelhard, Helmut; Bentz, Francis; Rinkler, Heinrich; and Nischk, Gunther, 3,580,966.
- Ritter, Josef: See—
Gott, Hans; and Ritter, Josef, 3,580,018.
- Ritter, Thomas E.: See—
Hestad, Erling; Ritter, Thomas E.; and De Claire, Alton G., Jr., 3,580,352.
- Roberge, Robert A. Inflatable toy dispenser. 3,580,303, Cl. 141-173.
- Robert, Andre; Bourdon, Claude; and Le Goer, Jean Luc, to Etat Francais representant par le Ministre des Armees, Delegation Ministerielle pour l'Armement. Apparatus for automatically measuring the properties of elliptically polarized light. 3,580,681, Cl. 356-114.
- Roberts, Warren A. Adaptors for use in tire changing and wheel balancing. 3,580,320, Cl. 157-1.24.
- Robertshaw Controls Company: See—
Chambers, William W., 3,581,061.
- Robertson, George H., to Bell Telephone Laboratories, Incorporated. Fourier analyzer. 3,581,078, Cl. 235-193.
- Robertson, James H. Horseshoe-shaped lifebuoy and method of making the same. 3,579,683, Cl. 9-340.
- Robinson, Charles A., to Kamborian, Jacob S. Pincers assembly. 3,579,693, Cl. 12-14.5.
- Robinson, Kenneth: See—
Watson, John Thaxter; and Robinson, Kenneth, 3,580,150.
- Rocha, Octavio; and Cano, Serafin. Oscillating internal combustion engine. 3,580,228, Cl. 123-18.
- Rochelt, Gunter. Desk frame. 3,579,887, Cl. 40-152.1.
- Rockwell-Standard Company: See—
Gage, Arthur F.; and Stamm, Alex F., 3,580,459.
- Rode, Horst: See—
Rothfuss, Helmut; and Rode, Horst, 3,580,985.
- Rodionov, Kuzma Petrovich: See—
Beresnev, Boris Ivanovich; Bulychiev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
- Rogers, William A.: See—
Gilbert, Edward I.; and Rogers, William A., 3,579,970.
- Rogova, Galina Ivanovna: See—
Naumenko, Viktor Arsenievich; Torortseva, Tatiana Nikolaevna; Penkova, Lidia Fedorovna; Vyselkov, Andrei Akimovich; and Rogova, Galina Ivanovna, 3,580,742.
- Rohde, Robert P., to General Motors Corporation. Fluid power steering system with fluid pressure reserve. 3,579,984, Cl. 60-51.
- Rohdin, Howard A.; and Brown, Fred P., Jr., to Packaging Industries, Inc. Method and apparatus for transferring articles and the like. 3,580,442, Cl. 225-2.
- Rohm and Haas Company: See—
Dupre, Jean, 3,580,850.
- Mickus, James C.; Fordyce, David B.; and Mansfield, Richard C., 3,580,855.
- Rohr Corporation: See—
Nelson, Harold E., Jr., 3,579,991.
Tanner, Carole S.; and Tontini, Remo, 3,579,993.
- Roman, Terrance S., to Cross Electronics, Inc., mesne. Optical pyrometers. 3,580,678, Cl. 356-43.
- Romano, Paul, to Eastman Kodak Company. Apparatus for processing photographic materials. 3,581,058, Cl. 219-330.
- Ronayne, John P.: See—
Harland, Geoffrey; and Ronayne, John P., 3,581,018.
- Ronchetti, Ugo: See—
Colombo, Americo; and Ronchetti, Ugo, 3,579,833.
- Root, James R., to Ruskin Manufacturing Company. Smoke damper. 3,580,321, Cl. 160-1.
- Ropp, Richard C., to Westinghouse Electric Corporation. Method of preparing rare-earth metal orthovanadate phosphors by precipitation. 3,580,861, Cl. 252-301.4.
- Roscoe, John D., to Bethlehem Steel Corporation. Safety shield for a fume-collecting apparatus. 3,580,556, Cl. 266-16.
- Rosemount Engineering Company: See—
Petersen, Paul S., 3,581,275.
- Rosen, Heinz: See—
Greenberg, Sol; Rosen, Heinz; Weinberger, Richard; and Mongodin, Guy, 3,580,081.
- Rosen, Milton K.; and Mason, Charles D., to Allied Chemical Corporation. Vapor phase polymerization of butene-1. 3,580,898, Cl. 260-93.7.
- Rosenberg, Sam: See—
Klempner, George R.; and Rosenberg, Sam, 3,579,784.
- Rosendahl, Charles E.: See—
Preus, Paul; and Rosendahl, Charles E., 3,579,994.
- Rosner, Robert E., to McDonnell Douglas Corporation. Beaded injectable sealing composition. 3,580,870, Cl. 260-2.5.
- Ross, William D.: See—
Salyer, Ival O.; Jefferson, Robert T.; and Ross, William D., 3,580,843.
- Rosser, Daniel B.: See—
Piccone, Dante E.; and Rosser, Daniel B., 3,581,160.
- Rotax Limited: See—
Goad, Albert, 3,580,098.
- Roth, Albert L. Rectangular carton having sift-proof and squaring closure. 3,580,477, Cl. 229-39.
- Rothe, Horst. Transistorized power amplifier. 3,581,225, Cl. 330-28.
- Rothfuss, Helmut, and Rode, Horst, to Bunker-Ramo Corporation. The. Cable connector and means to manufacture same. 3,580,985, Cl. 174-68.5.
- Rouet, James; and Vignes, Roger, to Service National dit. Gaz de France. Gas operated water heater. 3,580,224, Cl. 122-16.
- Royal Products Company: See—
Campbell, Albert B., 3,580,863.
- Rozema, Arthur L.; Brady, Lynn J.; and Barden, Wayne A., to CTS Corporation. Method of making a resistor. 3,579,819, Cl. 29-610.
- Rozhdestvenskaya, Maiya Konstantinovna: See—
Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Maiya Konstantinovna; and Kuzina, Alexandra Nikitichna, 3,580,776.
- Rozmus, Walter J., to Utica Tool Company, Inc. Wire stripping apparatus. 3,580,114, Cl. 81-9.5.
- Rudnitsky, Jury Petrovich: See—
Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkin, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich, 3,580,859.
- Ruegg, Ernst, to Wyss, Escher, Limited. Device for collecting solids in a centrifuge. 3,580,393, Cl. 210-369.
- Ruehle, William H., to Mobil Oil Corporation. Frequency-domain band broadening of seismic data. 3,581,274, Cl. 340-15.5.
- Ruffner, Lawrence J.: See—
Veater, Donald J.; Hill, Sumner B.; and Ruffner, Lawrence J., 3,581,167.
- Ruskin Manufacturing Company: See—
Root, James R., 3,580,321.
- Russbult, Herbert: See—
Panschow, Rudolf; Russbult, Herbert; Suhr, Volker; and Ullmann, Werner, 3,581,045.
- Russell, Alexander; and Millar, Alastair Gordon. High speed absolute position controls. 3,581,180, Cl. 318-608.
- Russo, Ronald D., to Koehler-Dayton, Inc. Self-contained sewerage system. 3,579,651, Cl. 4-78.
- Ryabinin, Jury Nikolaevich: See—
Beresnev, Boris Ivanovich; Bulychiev, Dmitry Konstantinovich; Martynov, Evgeny Dmitrievich; Ryabinin, Jury Nikolaevich; Rodionov, Kuzma Petrovich; Maltsev, Mikhail Vasilievich; Britnev, Georgy Pavlovich; and Kocherov, Anatoly Vasilievich, 3,580,019.
- Ryan, Donald P., to Cessna Aircraft Company, mesne. Card control of radio telephone. 3,581,019, Cl. 179-41.
- Ryll, Paul A.: See—
Mandonas, Nicholas J.; and Ryll, Paul A., 3,579,922.
- Saab Aktiebolag: See—
Eriksson, Gustave Ragnar, 3,580,685.
- Sabin Machine Co.: See—
Jones, Charles E., 3,579,919.
- Sacher, Franz, to Wiener Schwachstromwerke Gesellschaft m.b.H. Potentiometer circuit arrangement for deriving a tuning voltage. 3,581,252, Cl. 334-15.
- S. A. C. M. I. Cooperativa Meccanici Imola Soc. Coop. A. R. L.: See—
Mingotti, Aurelio, 3,579,757.
- Sagouspe, Jean; and Riley, Eugene D., to Genie Grape Harvester, Inc. Catch floor for grape harvesters. 3,579,971, Cl. 56-330.

- Saito, Mataichi. Method for continuously grinding a drill tip end into a normal shape and into a split point. 3,579,924, Cl. 51-288.
- Saito, Shoichi. *See—*
Shigetomi, Sadao; and Saito, Shoichi, 3,581,022.
- Sakamoto, Eiichi. *See—*
Sato, Shui; Sakazume, Kaichiro; and Sakamoto, Eiichi, 3,580,723.
- Sakamoto, Kenro; Takahashi, Takao; Koitabashi, Takeo; and Fujiwara, Mitsuo, to Konishiroku Photo Industry Co., Ltd. Light-sensitive silver halide color photographic emulsion. 3,580,722, Cl. 96-100.
- Sakazume, Kaichiro. *See—*
Sato, Shui; Sakazume, Kaichiro; and Sakamoto, Eiichi, 3,580,723.
- Sato, Shui; Sakazume, Kaichiro; and Iytaka, Tateshi, 3,580,724.
- Salerni, John V. *See—*
Dean, Michael R.; Castro, Luis F.; and Salerni, John V., 3,580,332.
- Salim, Ehsan. *See—*
Ullmann, Werner; Tadini, Costantino; and Salim, Ehsan, 3,581,043.
- Salyer, Ival O.; Jefferson Robert T.; and Ross, William D., to Monsanto Research Corporation. Chromatographic medium and method. 3,580,843, Cl. 210-31.
- Sambeth, Joerg. *See—*
Grundschober, Friedrich; and Sambeth, Joerg, 3,580,218.
- Sampson, Arnold, to Sampson Corporation, The. Pericortical dental implant and inserter therefor. 3,579,829, Cl. 32-10.
- Sampson Corporation, The. *See—*
Sampson, Arnold, 3,579,829.
- Sampson, Richard L., to Honeywell Inc. Fluid actuated instrument sensitive to density temperature or linear acceleration. 3,580,087, Cl. 73-515.
- Samuels, Walter E. D., to Corning Glass Works. Fluidic character display device. 3,579,879, Cl. 40-28.
- Sanders Associates, Inc. *See—*
Greenspan, Lawrence E.; and Whitaker, Earl J., 3,581,287.
- Petersen, Rudolph S., 3,580,281.
- Sandorf, Robert E.; and Hammond, Robert A., to Diebold, Incorporated. Multiple camera superimposed message closed circuit television system. 3,580,993, Cl. 178-6.
- Sandoz A.G. *See—*
Guenthard, Jacques, 3,580,933.
- Sandoz Ltd. *See—*
Guenthard, Jacques, 3,580,933.
- Sandri, Alfred. *See—*
Rasworschegg, Heinrich; Markow, Demeter; and Sandri, Alfred, 3,580,718.
- Sano, Kounosuke. *See—*
Shiio, Isamu; Nakamori, Shigeru; and Sano, Kounosuke, 3,580,810.
- Sansei Manufacturing Co., Ltd. *See—*
Suzuki, Kinichiro, 3,579,913.
- Sarka, Albert J.; and Blake, Trevor H., said Sarka assor. to Harris-Intertype Corporation, and said Blake assor. to American Can Company. Art of plate making. 3,580,676, Cl. 355-86.
- Sarto, Jorma O., to Chrysler Corporation. Engine exhaust recirculation. 3,580,232, Cl. 123-119.
- Sarver, James F.; and Hewes, Ralph A., to General Electric Company. Infrared-excitable alkaline earth thorium fluoride luminescent materials. 3,580,860, Cl. 252-301.1
- Sarzinski, Stefan. 'Zrak'-Preduzec Precizne mehanike i Optike. Tool carrier assembly for a lathe or other machine tool. 3,580,117, Cl. 82-36.
- Sato, Shui; Sakazume, Kaichiro; and Iytaka, Tateshi, to Konishiroku Photo Industry Co., Ltd. Light-sensitive supersensitized silver halide color photographic emulsions. 3,580,724, Cl. 96-124.
- Sato, Shui; Sakazume, Kaichiro; and Sakamoto, Eiichi, to Konishiroku Photo Industry Co., Ltd. Light-sensitive silver halide photographic emulsion. 3,580,723, Cl. 96-122.
- Satterthwaite, James Glenn; and Wilcox, Waverly Hope. Free orbital surface treating tool. 3,579,915, Cl. 51-120.
- Saul, George. *See—*
Inouye, Shingo; and Saul, George, 3,580,744.
- Saunier Duval. *See—*
Cynober, Simon, 3,580,527.
- Saurer, Hermann. *See—*
Trinks, Walter; Netzer, Theodor Karl; Vitoria, Hans T.; Saurer, Hermann; and von Paulgerg, Heinrich, 3,580,048.
- Save Fuel Corporation. *See—*
Diehl, Charles G., 3,580,238.
- Sawada, Yasuhiro. *See—*
Tsujihata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuha, Zensaku, 3,581,070.
- Scarpa Laboratories, Inc. *See—*
Scarpa, Thomas J., 3,580,092.
- Scarpa, Thomas J., to Scarpa Laboratories, Inc. Acoustic flowmeter. 3,580,092, Cl. 73-194.
- Schacht Associates, Inc. *See—*
Schacht, Louis L.; and Turner, Ralph, 3,579,909.
- Schacht, Louis L.; and Turner, Ralph, to Schacht Associates, Inc. Balanced door. 3,579,909, Cl. 49-252.
- Schaefer, Henry A. *See—*
Spangler, Fredrick E.; and Schaefer, Henry A., 3,581,249.
- Schafer, Fritz, K.G. *See—*
Schafer, Manfred, 3,580,398.
- Schafer, Manfred, to Schafer, Fritz, K.G. Shelving system. 3,580,398, Cl. 211-148.
- Schaller, Robert L., to Sundstrand-Engelberg Inc. Platen type belt grinder. 3,579,918, Cl. 51-148.
- Scharz, Armin; and Scharz, Oskar, to Polytronic S. A. Electric target apparatus for indicating hit points. 3,580,579, Cl. 273-102.2
- Scharz, Oskar. *See—*
Scharz, Armin; and Scharz, Oskar, 3,580,579.
- Schaumann, Wolfgang. *See—*
Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,910.
- Thiel, Max; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,907.
- Scheer, Leila C. Child's sleeping bag. 3,579,675, Cl. 5-343.
- Scheibel, Josef, to Braun Aktiengesellschaft. Driving mechanism for slide changers or the like. 3,580,096, Cl. 74-411.5
- Scheithauer, Walter. *See—*
Menell, Hans; and Scheithauer, Walter, 3,580,318.
- Scheler, Holger. *See—*
Werkmeister, Johannes; and Scheler, Holger, 3,580,418.
- Schenk, Erwin, to Siemens Aktiengesellschaft. Distortion measurement circuit. 3,581,009, Cl. 178-69.
- Scher, Joseph William, to Weber & Scher Mfg. Co., Inc. Cable-measuring machine. 3,579,842, Cl. 33-133.
- Schering AB. *See—*
Todt, Hans-Gunther; and Dahms, Wolfgang, 3,580,821.
- Schiefer Manufacturing Company. *See—*
Schiefer, Paul J.; and McFarland, James D., Jr., 3,580,372.
- Schiefer, Paul J.; and McFarland, James D., Jr., to Schiefer Manufacturing Company. Clutch with adjustable centrifugal pressure assist levers. 3,580,372, Cl. 192-105.
- Schiffelbein, Richard A. Extension device for toggle switches. 3,581,037, Cl. 200-172.
- Schilliger, Michel. Side band generator having step controlled modulation. 3,581,241, Cl. 332-47.
- Schilling, Harald. *See—*
Pfander, Hans; Schilling, Harald; and Schwabe, Gerhard, 3,581,164.
- Schirm, Helmut T.; and Zeigler, Robert O., to Owens-Illinois, Inc. Apparatus for feeding glass. 3,580,713, Cl. 65-327.
- Schjeldahl, G. T., Company. *See—*
Adams, Richard C.; Coombes, William S.; and Lerardo, Domenic, 3,580,120.
- Schladermundt, Peter. *See—*
Wark, John D.; and Schladermundt, Peter, 3,580,580.
- Schloss, Charles M., Jr. Method of and apparatus for increasing the capacity of bucket elevators. 3,580,641, Cl. 302-12.
- Schlumbaum, Hermann, to Stephan-Werke GmbH & Co. Apparatus for detecting leaks in hollow bodies. 3,580,054, Cl. 73-49.2
- Schmale, Carl. *See—*
Freermann, Hans, 3,579,876.
- Schmermund, Alfred. Arrangements for creating delayed electric control effects in response to the reception of electric impulses. 3,579,703, Cl. 317-124.
- Schmid, Karl. *See—*
Anliker, Rudolf; Duennenberger, Max; Schmid, Karl; and Siegrist, Adolf Emil, 3,580,924.
- Schmidt, Carl Oscar, Jr., to Cincinnati Butchers' Supply Company, The. Stuffer with a resilient cushioning means for piston. 3,579,715, Cl. 17-39.
- Schmidt, Karl, to GEHAP Gesellschaft fuer Handel und Patentverwertung mbH & Co., K.G., Firma. Electronically-controlled drive mechanism particularly for clocks. 3,579,974, Cl. 58-23.
- Schmidt, Wolfgang; Kraft, Karl-Josef; and Kurth, Willi, to Farbenfabriken Bayer Aktiengesellschaft. Apparatus for continuous production of foam plastic sections. 3,579,722, Cl. 18-4.
- Schmitt, Wilfred W., to Flo-Tronics, Inc. Electric fence charger having ground detector. 3,581,299, Cl. 340-254.
- Schmitt, Hermann. *See—*
Heimberger, Werner; and Schmitt, Hermann, 3,580,912.
- Schmitt, Regis V., to Lord Corporation. Trunnion mounting. 3,580,532, Cl. 248-9.
- Schmitz, Werner. *See—*
Fratzscher, Helmut; Klein, Kurt; Maluzi, Joachim; Hansen, Peter; and Schmitz, Werner, 3,580,844.
- Schneider, Irwin. Information storage with optic materials. 3,580,688, Cl. 356-256.
- Schneider, Jack Marvin, to Calmec Extrufirm Limited. Apparatus for moulding articles from plastics material. 3,580,773, Cl. 156-244.
- Schneider, Karl. *See—*
Siegel, Charles R.; and Schneider, Karl, 3,580,405.
- Schneider, Michael S. Portion access pie plate. 3,580,484, Cl. 229-51.
- Schneider, Richard C. Hydrotherapeutic device. 3,580,247, Cl. 128-66.
- Schnell, Carl, 1/2 to Griffith Laboratories, Inc., The. Comminuting machine. 3,580,315, Cl. 146-79.
- Schnittger, Jan R.; Nilson, Carl-Goran; and Larsson, Bengt D. R., to Alfa-Laval AB. Centrifugal separator with adjustable outlet means. 3,580,492, Cl. 233-7.
- Schnur, Nicholas Joseph. Method and apparatus for the centrifugal distillation of a liquid. 3,580,817, Cl. 203-11.
- Schoeneman, Robert E., to Potter Instrument Company, Inc. Tension arm. 3,580,453, Cl. 226-195.
- Scholle, Peter T.; and Webb, Samuel L., to Addressograph-Multigraph Corporation. Liquid level sensing device. 3,580,158, Cl. 95-89.

- Scholz, Norbert, to Agfa-Gevaert Aktiengesellschaft. Variable focal length objective having four lens groups. 3,580,662, Cl. 350-184.
- Schrecengost, Eugene E. Combination deer-carass sled and chaise lounge. 3,580,592, Cl. 280-8.
- Schreffler, Robert Z., to Electric Conductor Bearings, Incorporated. Electric conductor bearings. 3,581,267, Cl. 339-8.
- Schrewe, Hans, to Mannesmann Aktiengesellschaft. Continuous casting machine for slabs. 3,580,325, Cl. 164-82.
- Schriever, Fred G.; and Cheslin, Sigmund. Hand operated tool for marking wire. 3,580,779, Cl. 156-384.
- Schroder, Rolf. *See—*
Ehngelsmann, Dieter; Schroder, Rolf; and Becker, Erwin, 3,580,152.
- Schroeder, Donald S. *See—*
Orlowski, Donald W.; and Schroeder, Donald S., 3,580,988.
- Schuder, Charles B.; Skov, Victor E.; and Lytle, Richard F., to Fisher Governor Company. Flow control device including a pressure-balanced single-seated valve plug. 3,580,288, Cl. 137-630.13
- Schuette, Thomas L.; Straub, Melvin J.; Dumas, Pierre; and Aurich, Peter F., to Possis Machine Corporation. Machine for automatically assembling armature cores and commutators therefor. 3,579,771, Cl. 29-33.
- Schulkind, Herbert, to Photovolt Corporation. Computing colorimeter. 3,580,683, Cl. 356-184.
- Schumacher, Gustav. Grain-lifter for grain-cutting assemblies. 3,579,967, Cl. 56-313.
- Schunck, Kurt; and Baunach, Waldemar, to Klimsch & Co. Device for fast removal of exposed film from the suction board of process cameras and delivery to a subsequent process station. 3,580,674, Cl. 355-28.
- Schupp, Karl; and Weismann, Hans, to Bosch, Robert, G.m.b.H. Fluid-pressure actuated switch. 3,581,034, Cl. 200-83.
- Schure, Alexander. *See—*
Littwin, Sheldon; and Schure, Alexander, 3,579,864.
- Schwabe, Gerhard. *See—*
Pfander, Hans; Schilling, Harald; and Schwabe, Gerhard, 3,581,164.
- Schwartz, Ralph E., to Redeco, Inc., mesne. Method and apparatus for the preservation of biological substances. 3,579,999, Cl. 62-56.
- Schwartz, William H., to Lester Engineering Company. Machine and clamp force control system therefor. 3,579,741, Cl. 18-30.
- Schwartzbeck, Richard A. *See—*
Mussell, Dorsey R.; and Schwartzbeck, Richard A., 3,580,716.
- Schwarz, Ernest I., to EIS Automotive Corporation, The. Two-way check valve. 3,580,273, Cl. 137-493.2
- Schwarz, Heinz. *See—*
Cast, Adolf; and Schwarz, Heinz, 3,580,455.
- Schwenk, Kurt; Gallasch, Ernst; Hablitzel, Hermann; and Jacob, Friedrich, to Messrs. Volkswagenwerk A. G. Foam mould. 3,579,727, Cl. 18-5.
- Schwing, Friedrich. Concrete pump assembly. 3,580,696, Cl. 417-515.
- Scio Cabinet Company, Inc. *See—*
Loy, George W., 3,580,787.
- SCM Corporation. *See—*
Ott, Robert E., 3,580,733.
- Scott, Peter H. *See—*
Churchill, John W.; Kober, Ehrenfreid H.; Scott, Peter H.; and Smith, Curtis P., 3,580,951.
- Scripto, Inc. *See—*
Vaughan, Harry L., 3,580,699.
- Seaboard Fabricators, Inc. *See—*
Van Dalen, Leonard, 3,580,097.
- Scars, Levi L.; and Sommer, Richard N., to SSP Industries. Agricultural implement. 3,579,972, Cl. 56-370.
- Security Chemicals, Inc. *See—*
Fike, Elmer A., 3,580,885.
- Sedgwick, Robert K., to Kearney & Trecker Corporation. Apparatus for machining metals electrochemically. 3,580,834, Cl. 204-224.
- Sedley, Bruce S., to Bohme, H. O., Inc. Magnet actuated mechanism for use with card having magnetic arcs. 3,581,030, Cl. 200-46.
- Seed, Aniese E., to Reliance Electric and Engineering Company, The. Constant meshing force rack and pinion. 3,580,095, Cl. 74-409.
- Seegmiller, Ben L., to University of Utah, The. Probe device usable in measuring stress. 3,580,057, Cl. 73-67.6
- Seegmiller, Ben L. Discretely variable time delay system having submultiple, additive, and alternative delay selection. 3,581,214, Cl. 328-55.
- Seekay Chemical Company. *See—*
Rainer, Norman B., 3,580,891.
- Seelbach, Walter C.; and Lampathakis, Kyriakos E., to Motorola, Inc. Voltage distribution system for integrated circuits utilizing low resistivity semiconductive paths for the transmission of voltages. 3,581,165, Cl. 317-235.
- Seelenbinder, Terrance G., to Addressograph-Multigraph Corporation. Exposure apparatus for copy making machines equipped with light reflective conveyor. 3,580,677, Cl. 355-110.
- Sehnert, Robert J. *See—*
Higgason, Frank G., Jr.; and Sehnert, Robert J., 3,580,494.
- Seibu Denki Kogyo Kabushiki Kaisha. *See—*
Watari, Daisaku; and Morita, Tosio, 3,581,044.
- Seifried, Walter. *See—*
Kegelmann, Gunter; Gebler, Horst; and Seifried, Walter, 3,580,798.
- Kurkze, Herbert; Goltner, Wolfgang; and Seifried, Walter, 3,580,963.
- Seitetsu Kagaku Co., Ltd. *See—*
Ito, Teruhiko; Mitsui, Naoshi; Maeda, Seiichiro; and Kato, Takeshi, 3,580,866.
- Selden, Ronald B., to TRW Inc. Randomly accessed non-interfering input-output data accumulator. 3,581,284, Cl. 340-172.5
- Sellers, Francis B. *See—*
Brinkerhoff, Joris M.; Hunerwadel, Jean L.; and Sellers, Francis B., 3,581,087.
- SEMPERIT Österreichisch-Amerikanische Gummiwerke Aktiengesellschaft. *See—*
Gorter, Werner; and Hauser, Johann, 3,580,319.
- Senften, David A. *See—*
Hunter, Lee; Senften, David A.; and Logan, Edwin W., 3,579,845.
- Sennewald, Kurt. *See—*
Baader, Herbert; and Sennewald, Kurt, 3,580,958.
- Service National dit: Gaz de France. *See—*
Rouet, James; and Vignes, Roger, 3,580,224.
- Settanni, Richard, to Leeson Corporation. Coil winder automatically sequencing multiple preset winding selections. 3,580,521, Cl. 242-4.
- Setto, Joseph B., to United States of America, Air Force. Dual side-arm controller. 3,580,636, Cl. 297-417.
- Seward, George A. Device for controlling exposure from a radioactive source. 3,581,096, Cl. 250-106.
- Seymour, Paul Maurice. Folding table and seat support structure. 3,580,632, Cl. 297-157.
- Shaad, Robert B. Easy opening flat object mailer. 3,580,490, Cl. 229-92.9
- Shadwick, Jan, to Holophane Company, Inc. Street lighting luminaire refractor. 3,581,082, Cl. 240-106.
- Shafer, Homer J. Lubricant seal for rotary valve. 3,580,268, Cl. 137-246.22
- Shaffstall, Everett L. *See—*
Perkins, Carroll R.; Shaffstall, Everett L.; Gundersen, James L.; and Yoder, Robert N., 3,581,226.
- Shalit, Harold, to Atlantic Richfield Company. Hydrogen production. 3,580,823, Cl. 204-60.
- Sharpe, John Thomas Lawrence, to International Standard Electric Corporation. Delay line arrangement. 3,581,121, Cl. 307-293.
- Shashoua, Fred E. *See—*
Hudson, Kenneth C.; and Shashoua, Fred E., 3,580,151.
- Shaw, Harold F. *See—*
Blais, Zoel W.; and Shaw, Harold F., 3,579,674.
- Shear, Wayne G.; Everett, Samuel R.; and Olmstead, Merlin E., to Bendix Corporation, The. Clock synchronization without addressing for collision avoidance systems. 3,581,309, Cl. 343-6.8
- Shell Oil Company. *See—*
Broussard, Leo P.; Dickson, Leon L., Jr.; and Gardenier, Wilhelmus J. G., 3,580,334.
- Hoory, Sadok E.; Newman, Stanley F.; and Vincent, Robert E., 3,580,819.
- Simpson, Samuel W., 3,580,047.
- Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Maiya Konstantinovna; and Kuzina, Alexandra Nikitichna. Method of producing electric contact between two cemented parts. 3,580,776, Cl. 156-275.
- Shepherd, Basil R. *See—*
Clachan, Margaret L.; McGrail, Patrick T.; and Shephard, Basil R., 3,580,734.
- Sheridon, Nicholas K., to Xerox Corporation. Blazed surface hologram. 3,580,657, Cl. 350-3.5
- Sheriff, Robert C. *See—*
Doane, James E.; and Sheriff, Robert C., 3,580,786.
- Sherman, Michael. *See—*
Flores, Richard A.; and Sherman, Michael, 3,581,124.
- Sherman, Russell G.; and Koenig, Robert P., to Powers Regulator Company. Automatic air flow regulator. 3,580,272, Cl. 137-486.
- Shevakin, Jury Fedorovich. *See—*
Zayats, Iosif Lvovich; Barabashkin, Vladimir Pavlovich; Matveev, Boris Nikolaevich; and Shevakin, Jury Fedorovich, 3,580,036.
- Shigetomi, Sadao; and Saito, Shoichi, to Olympus Optical Company Limited. Miniature tape recorder. 3,581,022, Cl. 179-100.22
- Shiio, Isamu; Nakamori, Shigeru; and Sano, Kounosuke, to Ajinomoto Co., Inc. Fermentative production of L-threonine. 3,580,810, Cl. 195-29.
- Shimada, Masatoshi. *See—*
Tsujihata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuha, Zensaku, 3,581,070.
- Shimemura, Etsujiro; and Iwamiya, Masao, to Tsurumi-Seikikosaku-Sho Co., Ltd., The. Transmission transducer for remote measurement. 3,581,238, Cl. 331-135.
- Shimodoi, Yutaka; Ootake, Heiichiro; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, to Asahi Kasei Kogyo Kabushiki Kaisha. Polyolefin-molded article having good antistatic property and preparation of the same. 3,580,735, Cl. 117-138.8
- Shimura, Kazuo. *See—*
Kishi, Kanesuke; Tsuchiya, Noboru; and Shimura, Kazuo, 3,581,012.
- Shirek, Jerry. Variable stack electrical condenser. 3,581,158, Cl. 317-230.
- Shockey, Ray Douglas. *See—*
Hollis, Jack Lyndon; and Shockey, Ray Douglas, 3,580,781.

- Shoemaker, William E.; and Wilson, David W., to Signetics Corporation. Testing apparatus for electrical device where a stimulus is varied between two states. 3,581,198, Cl. 324-73.
- Short, Franklin W., to Parke, Davis & Company. Carbazole-4-alkanoic acids and tetrahydrocarbazole-4-alkanoic acids. 3,580,926, Cl. 260-315.
- Shreve, Robert N., to Conwed Corporation. Method of constructing a mattress. 3,579,774, Cl. 29-91.1
- Shreve, Russell L., to Teleflex Incorporated, mesne. Remote flexible cable. 3,580,103, Cl. 74-501.
- Shroyer, Larry L., to Lyall Electric, Inc. Thermoplastic lamp holder. 3,581,270, Cl. 339-160.
- Shull, John D., Jr., to National Gypsum Company. Plaster colorant system. 3,580,390, Cl. 206-46.
- Shuster, Joseph; and Brown, Richard L., to Icore Industries. Package turning device. 3,580,379, Cl. 198-31.
- Shyne, James J.: See—
Milewski, John V.; and Shyne, James J., 3,580,731.
- Sicona, Martin: See—
Stevens, Roger L.; Putnam, Peter A.; and Sicona, Martin, 3,581,017.
- Siebert, Alan R., to Goodrich, B. F., Company, The. Preparation of xanthate terminated polymers. 3,580,830, Cl. 204-159.24
- Siebold, Howard E., to Liquid Controls Corporation. Temperature compensator. 3,580,073, Cl. 73-233.
- Siegel, Charles R.; and Schneider, Karl, to Harnischfeger Corporation. Multiple V-belt drive for a crowd mechanism of a power shovel. 3,580,405, Cl. 214-135.
- Siegmund, Walter P., to American Optical Corporation. Method of making fiberoptic tips with trimmed tips. 3,580,775, Cl. 156-247.
- Siegrist, Adolf Emil: See—
Anliker, Rudolf; Duennenberger, Max; Schmid, Karl; and Siegrist, Adolf Emil, 3,580,924.
- Siemens Aktiengesellschaft: See—
Ciriack, Gunter; Eckert, Georg; and Hofmann, Horst, 3,580,739.
- Hini, Paul, 3,579,820.
- Kafka, Wilhelm, 3,581,113.
- Kumpf, Hermann, 3,580,807.
- Schenk, Erwin, 3,581,009.
- Weber, Rolf, 3,581,115.
- Sieracin Corporation, The: See—
Miller, Harold A.; Nider, William K.; and Zavialoff, Igor P., 3,579,718.
- Siewert, John J.: See—
Westra, Dan P.; and Siewert, John J., 3,580,123.
- Signetics Corporation: See—
Nielsen, Einer Dale, 3,581,107.
- Shoemaker, William E.; and Wilson, David W., 3,581,198.
- Silva, Melvin: See—
Morey, Dennison H., Jr.; Silva, Melvin; and Browning, Gordon D., 3,581,197.
- Simcom Corporation: See—
Levasseur, Joseph L., 3,581,063.
- Simms Group Research and Development Limited: See—
Bradbury, Cyril Henry, 3,580,231.
- Simon, Alan J.; Johnson, Joseph E.; and O'Keeffe, Trence W., to Westinghouse Electric Corporation. Method and apparatus for selective etching of insulating layers. 3,580,749, Cl. 148-187.
- Simonetti, Louis F.: See—
Boettcher, Stephen A.; and Simonetti, Louis F., 3,579,916.
- Boettcher, Stephen A.; and Simonetti, Louis F., 3,579,917.
- Simpson, Samuel W., to Shell Oil Company. Pour and cloud point analyzer. 3,580,047, Cl. 73-17.
- Sims, Anson: See—
Stastny, Edwin O.; Stormon, Lester T.; and Sims, Anson, 3,580,585.
- Simshauser, Herbert H. Can crushing apparatus. 3,580,167, Cl. 100-52.
- Sinclair, Rolf M.: See—
Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., 3,580,802.
- Sinet, Maurice. On-load voltage regulators. 3,581,189, Cl. 323-43.5
- Singer Company, The: See—
Klawunn, Herbert G.; and Herr, John Addison, 3,580,780.
- Wiehl, Frederick R.; and Wilson, Edmund B., III, 3,580,106.
- Singer-Cobble Limited: See—
Evans, Raymond Victor, 3,580,454.
- Singer-General Precision, Inc.: See—
Ebeling, William C., 3,580,978.
- Paradise, Ronald Y.; Masel, Marvin; Naydan, Bob N.; and Brinkman, John D., 3,581,304.
- Sinkula, Anthony A.: See—
Morozowich, Walter; and Sinkula, Anthony A., 3,580,904.
- Siprikova, Nina Isidorovna: See—
Shenfil, Leonid Zalmanovich; Gul, Valentin Evgenievich; Melnikova, Galina Konstantinovna; Siprikova, Nina Isidorovna; Rozhdestvenskaya, Maiya Konstantinovna; and Kuzina, Alexandra Nikitichna, 3,580,776.
- Siu, Paul Y., to Burroughs Corporation. Crystal stabilized high frequency transistor multivibrator. 3,581,235, Cl. 331-113.
- Skov, Victor E.: See—
Schuder, Charles B.; Skov, Victor E.; and Lytle, Richard F., 3,580,288.
- Slan, Jack, to Dominion Luggage Co., Limited. Method of making luggage cases. 3,579,804, Cl. 29-434.
- Slane, Joseph J.: See—
Zink, Stanley C.; and Slane, Joseph J., 3,580,648.
- Sloan, Frank Philip, to Aquair Corporation Limited. Venting device for toilets. 3,579,650, Cl. 4-72.
- Smith, F. L., & Co.: See—
Hansen, Dan Sigurd, 3,580,552.
- Smith, A. O., Corporation: See—
Marks, Lawrence P., 3,580,187.
- Smith, Cecil R. Door hinge with spaced automatic latching positions for selective degrees of door opening. 3,579,712, Cl. 16-141.
- Smith, Curtis P.: See—
Churchill, John W.; Kober, Ehrenfreid H.; Scott, Peter H.; and Smith, Curtis P., 3,580,951.
- Smith, Dallas F.: See—
Arnold, Richard B.; and Smith, Dallas F., 3,579,818.
- Smith, David C., to United Aircraft Corporation. Passive Q-switch and modulator for lasers. 3,581,230, Cl. 331-94.5
- Smith, Donald R.; and Cavestany, Adrian V., to Carrier Corporation. Gas burner. 3,580,512, Cl. 239-432.
- Smith, Fred T., to Barber-Greene Company. Method of reclaiming bulk material. 3,580,407, Cl. 214-152.
- Smith, Gerald D.: See—
Zimmerman, Arie; Luksch, James A.; and Smith, Gerald D., 3,581,209.
- Smith, Gilbert L. Meat cleaning brush. 3,579,697, Cl. 15-3.1
- Smith, John J.: See—
Leopold, Wilbur R., Jr.; and Smith, John J., 3,580,270.
- Magi, Hugo; and Smith, John, 3,581,079.
- Smith Kline & French Laboratories: See—
Cook, Allen D.; and Szabo, Kalman T., 3,580,220.
- Smith, Leonard R. D.: See—
Cannon, Richard L.; and Smith, Leonard R. D., 3,581,254.
- Cannon, Richard L.; and Smith, Leonard R. D., 3,581,255.
- Smith, Michael Charles George: See—
Cheeseman, Ian Clifford; and Smith, Michael Charles George, 3,580,693.
- Smith, Peter W., to Bell Telephone Laboratories, Incorporated. Simultaneous transverse and longitudinal mode locking in a laser employing an active absorption cell. 3,581,228, Cl. 331-94.5
- Smith, Raymond W.: See—
Korbilas, Christ P.; and Smith, Raymond W., 3,580,276.
- Smith, Thomas B.; and Swassing, Raymond H., Jr. Educational device for training in mathematics. 3,579,874, Cl. 35-32.
- Smith, William Irving, to RCA Corporation. Automatic impedance matching circuits for variable frequency source. 3,581,244, Cl. 333-17.
- Snell, John, to Lucas, Joseph, (Industries) Limited. Method of manufacturing a cam for use in an ignition distributor. 3,579,933, Cl. 51-315.
- Snow, Lawrence E., to White Consolidated Industries, Inc. Ice maker. 3,580,009, Cl. 62-353.
- Snyder, David W., to Snyder Specialty, Inc. Wire grooving method and machine. 3,580,042, Cl. 72-339.
- Snyder Specialty, Inc.: See—
Snyder, David W., 3,580,042.
- Sobchak, Frank L.: See—
Brouwer, Frans; and Sobchak, Frank L., 3,580,110.
- Brouwer, Frans; and Sobchak, Frank L., 3,581,001.
- Soboleski, Henry J. Fruit and vegetable jar suppressor device. 3,580,409, Cl. 215-81.
- Sobrafina S.A.: See—
Hellborg, Lars Ingvar, 3,579,785.
- Soc. per Azioni Fratelli Borletti: See—
Moro, Antonio, 3,581,263.
- Societa Italiana Telecomunicazioni Siemens S.p.A.: See—
Martinelli, Saverio; and De Varda, Giorgio, 3,581,016.
- Societa Italiana Telecomunicazioni Siemens S.p.A.: See—
Andreis, Pio, 3,581,260.
- Dal Monte, Giorgio; and Pitidis, Nicola, 3,581,008.
- Societe a Responsabilite Limitee Laboraver: See—
Guiriec, Raymond, 3,580,251.
- Societe Anonyme Poclair: See—
Bellart, Jean-Pierre B., 3,580,406.
- Societe de L'Aerotrain: See—
Giraud, Francois Louis, 3,580,184.
- Societe d'Etudes de Recherches et d'Application Scientifiques et Medicales E.R.A.S.M.E.: See—
Pedrazzoli, Andrea; and Dall'Asta, Leone, 3,580,914.
- Societe d'Exploitation des Ressorts Auto-Amortisseurs Jarret: See—
Jarret, Jacques; and Jarret, Jean, 3,580,560.
- Societe Industrielle Bull-General Electric (Societe Anonyme): See—
Vasse, Jacques, 3,580,566.
- Societe Nationale d'Etude et de Construction de Moteurs d'Aviation: See—
Caruel, Jacques Emile Jules; Quillevere, Herve Alain; and Bauge, Louis, 3,579,983.
- Societe Technique de Geothermie: See—
Maugis, Pierre Marcel, 3,580,330.
- Soda, Kiyoshi: See—
Wada, Misao; and Soda, Kiyoshi, 3,580,530.
- Solatron Enterprises: See—
Bean, Dennis P.; and Parks, John C., 3,580,030.
- Solomon, Kenneth H.: See—
Marandi, Ali; and Solomon, Kenneth H., 3,580,508.

- Somet S.p.A. Societa Meccanica Tessile: See—
Piccoli, Mario, 3,580,291.
- Sommer, Francis Noel, to Sommer S. A. Method of non-woven cloth manufacture. 3,579,763, Cl. 28-72.2
- Sommer, Richard N.: See—
Sears, Levi L.; and Sommer, Richard N., 3,579,972.
- Sommer S. A.: See—
Sommer, Francis Noel, 3,579,763.
- Sony Corporation: See—
Eguchi, Yasuhito; Fujiwara, Yoshio; and Tohma, Takaaki, 3,580,992.
- Kishi, Kanesuke; Tsuchiya, Noboru; and Shimura, Kazuo, 3,581,012.
- Numakura, Toshihiko, 3,580,990.
- Sorenson Engineering, Inc.: See—
Sorenson, Jess Frank, 3,579,686.
- Sorenson, Jess Frank, to Sorenson Engineering, Inc. Automatic screw machine. 3,579,686, Cl. 10-87.
- Soriano, Charles A., to Atwater-Forbes Corporation. Foot measuring apparatus. 3,579,837, Cl. 33-3.
- Sorokin, Vladimir Andreevich: See—
Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich, 3,580,554.
- Soures, Nicholas M.: See—
Hansen, Richard C.; Mahler, Charles J.; Soures, Nicholas M.; and Stickney, Thomas L., 3,581,000.
- Southern Gas Association: See—
Damewood, Glenn; Sparks, Cecil R.; and King, James D., 3,581,077.
- Spadoni, Frank G., Jr.; and Kleban, Michael P., to Litton Precision Products, Inc. Device for twisting and aligning terminal posts of an electrical connector. 3,580,297, Cl. 140-149.
- Spaid, William L. Digital capacitance meter by measuring capacitor discharge time. 3,581,196, Cl. 324-60.
- Spangler, Fredrick E.; and Schaefer, Henry A., to General Electric Company. Miniature helical resonators. 3,581,249, Cl. 333-705.
- Sparks, Cecil R.: See—
Damewood, Glenn; Sparks, Cecil R.; and King, James D., 3,581,077.
- Sparks, Derick A., to Power Industries Limited. Gripping means for binding materials. 3,580,450, Cl. 226-171.
- Sparlin, Derry D., to Continental Oil Company. Method for injecting fluids into underground formations having differing permeabilities. 3,580,338, Cl. 166-276.
- Spartanics Limited: See—
Willits, Samuel P.; and Mohan, William L., 3,581,067.
- Speedfam Corporation: See—
Boettcher, Stephen A.; and Simonetti, Louis F., 3,579,916.
- Boettcher, Stephen A.; and Simonetti, Louis F., 3,579,917.
- Speeth, Sheridan D., to Autotelic Industries Limited, mesne. Game device including selectively impact operable lights. 3,580,575, Cl. 273-58.
- Speizman Industries, Inc.: See—
Starbuck, Leslie; and Whymark, Arthur F., 3,580,392.
- Spenadel, Lawrence, to Ezzo Research and Engineering Company. Process for preparing a closed cell EPDM sponge composition. 3,580,867, Cl. 260-2.5
- Spence, Thomas C., to Dow Chemical Company, The. Method for manufacturing nonwoven fibrous products from gel fibers. 3,580,801, Cl. 162-157.
- Spencer, Lloyd; and Petterson, Tor. Actuator for mixing valve. 3,580,091, Cl. 74-107.
- Spencer, Virgil, to Armstrong Cork Company. Method of separating a sheet into chips. 3,580,516, Cl. 241-25.
- Sperry Rand Corporation: See—
Bartik, William J., 3,581,294.
- Fedde, George A.; and Eckert, John Presper, Jr., 3,581,293.
- Gettel, Roger W., 3,580,277.
- Granberg, Mauritz L.; and Mueller, Hubert W., Jr., 3,581,076.
- Hood, John L.; and McGee, Joe H., 3,581,173.
- Spider Staging, Inc.: See—
Fisher, Sidney L., 3,580,010.
- Spieth, Rudolf; and Otto, Gunter. Hydropneumatic piston-cylinder arrangement. 3,580,559, Cl. 267-126.
- Spitler, Nathan Shreve. Hydraulic steering and braking system for snow skis. 3,580,605, Cl. 280-11.13
- Spitz, David A., to Industrial Nucleonics Corporation. Spectrum analyzer including sampling and scaling means. 3,581,199, Cl. 324-77.
- Spitzer, Artur, to Spitzer, Ludwig Sen. KG (Kommanditgesellschaft). Convertible transport container with plural funnel type outlets. 3,580,434, Cl. 222-461.
- Spitzer, Artur, to Spitzer, Ludwig, Sen. KG (Kommanditgesellschaft). Transport container for flowable material. 3,580,643, Cl. 302-53.
- Spitzer, Ludwig Sen. KG (Kommanditgesellschaft): See—
Spitzer, Artur, 3,580,434.
- Spitzer, Artur, 3,580,643.
- Spitzl, Walter: See—
Meisner, Alfred; and Spitzl, Walter, 3,581,128.
- Sprague Electric Company: See—
Dornfeld, John E., 3,581,143.
- Sprunger, Lynn H. Anti-sway suspension system for an axled vehicle. 3,580,593, Cl. 280-124.
- Square D Company: See—
Wrabetz, Voyta E.; and Banister, Ronald A., 3,580,102.
- SSP Industries: See—
Sears, Levi L.; and Sommer, Richard N., 3,579,972.
- Staat, Karl-Hans: See—
Bindernagel, Ali; Kost, Erwin; and Staat, Karl-Hans, 3,580,020.
- Stach, Kurt: See—
Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,910.
- Thiel, Max; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, 3,580,907.
- Stackpole Carbon Company: See—
Bang, Mogens W., 3,579,743.
- Stahl, Laddie L., to General Electric Company. Multipurpose air supply system. 3,580,401, Cl. 214-1.
- Stahlmann, Rudolf: See—
Gawlick, Heinz; Stahlmann, Rudolf; and Umbach, Hans, 3,580,179.
- Stamm, Alex F.: See—
Gage, Arthur F.; and Stamm, Alex F., 3,580,459.
- Stams, Dietrich, to Bosch, Robert, G.m.b.H. Hydraulic drive control arrangement. 3,579,978, Cl. 60-19.
- Standard Brands Chemical Industries, Inc.: See—
Lenke, Gerd M., 3,580,894.
- Stone, Raymond A.; Lister, Fred; and Heller, David S., 3,580,876.
- Standard Oil Company (Indiana): See—
Ginsburgh, Irwin; and Nebelsiek, Hilbert J., 3,580,414.
- Standrad International Corporation: See—
Chaban, Michael J., Jr., 3,580,449.
- Stantini Vyzkumny Ustav Textilni: See—
Jisa, Miloslav; Zmatlik, Josef; Mohelnicky, Josef; and Milichovsky, Bohumil, 3,580,256.
- Staples, Nicholas B.: See—
Garrett, Elgie E.; De Franco, Thomas P.; and Staples, Nicholas B., 3,581,135.
- Starbuck, Leslie; and Whymark, Arthur F., to Speizman Industries, Inc. Method and apparatus for removing a flaccid article from a support surface. 3,580,392, Cl. 209-74.
- Stark, Donald A.; Di Bartolo, Ernest A.; Feather, Harry A.; and Sundin, Charles H., to Fluid Controls, Inc. Linear self-synchronizing master-slave hydraulic remote control device. 3,579,989, Cl. 60-54.5
- Stastny, Edwin O.; Stormon, Lester T.; and Sims, Anson, to Mattel, Inc. Device for reproducing sounds in toys. 3,580,585, Cl. 274-1.
- Statham Instruments Inc.: See—
Hickman, Norman A., 3,580,071.
- Stauffer Chemical Company: See—
O'Brien, Edward D., 3,580,545.
- Price, Glenn R.; and Walsh, Edward N., 3,580,922.
- Stauffer-Wacker Silicone Corporation: See—
Getson, John Charles, 3,580,971.
- Staunton, Kenneth L., to Sylvania Electric Products, Inc. Color dot screen with dot form compensation for apparent shift of beam deflection center. 3,581,136, Cl. 313-92.
- Stawski, Theodore H., to Becton, Dickinson and Company. Swab dispenser and package therefor. 3,580,472, Cl. 229-17.
- Stearns, Charles F.: See—
Urban, Louis A.; and Stearns, Charles F., 3,579,992.
- Stearns Electric Corporation: See—
McCarthy, Richard H., 3,580,367.
- Stebbins, Robert C. Insect inspection cage. 3,580,219, Cl. 119-1.
- Stech, Peter: See—
Born, Dieter; Stech, Peter; and Huebner, Werner, 3,580,587.
- Stedman Foundry and Machine Company, Incorporated: See—
Myers, Thomas Leroy, 3,580,520.
- Stein, Marcel. Top roller for textile drafting devices. 3,579,779, Cl. 29-113.
- Steinberg, David R., to Corning Glass Works. Pressure transducer for ionizable fluids. 3,580,075, Cl. 73-339.
- Steindler, Julius P.: See—
Panko, Walter B.; and Steindler, Julius P., 3,579,912.
- Steinmetz, Floyd. Ball bearing lapping machine. 3,579,911, Cl. 51-3.
- Steinvoort, Leendert: See—
Duerink, Steven; and Steinvoort, Leendert, 3,580,463.
- Stenklyft, Gerald H.: See—
Kirk, Thomas E.; and Stenklyft, Gerald H., 3,581,150.
- Stepan Chemical Company: See—
Greenleaf, James O., 3,579,940.
- Stephan-Werke GmbH & Co.: See—
Schlumbaum, Hermann, 3,580,054.
- Steppan, Hartmut: See—
Maar, Herbert; Steppan, Hartmut; Messwarb, Gunter; and Luders, Walter, 3,580,888.
- Stevens, Irving J.; and Alexander, Jerry. Bone implant. 3,579,831, Cl. 32-10.
- Stevens, Roger L.; Putnam, Peter A.; and Sicona, Martin, to Aerojet-General Corporation. Electronic multiplexer. 3,581,017, Cl. 179-15.
- Stevenson, Louis A., Jr. Pulse generator and encoder. 3,581,216, Cl. 328-61.
- Stewart, Johnny E. Animal call. 3,579,903, Cl. 46-180.
- Stewart, Mary J.; and Price, John A., to FMC Corporation. Polyesters stabilized with aromatic isocyanates. 3,580,886, Cl. 260-45.9

Stewart-Warner Corporation: *See*—
 Bash, Sidney D., 3,580,286.
 Brouwer, Frans; and Sobchak, Frank L., 3,580,110.
 Brouwer, Frans; and Sobchak, Frank L., 3,581,001.
 Powell, Patrick L., 3,580,497.
 Rieth, Lawrence E., 3,581,081.
 Stickle, Stanley A., to Clark Equipment Company. Portable ramp. 3,580,373, Cl. 193-5.
 Stickney, Thomas L.: *See*—
 Hansen, Richard C.; Mahler, Charles J.; Soures, Nicholas M.; and Stickney, Thomas L., 3,581,000.
 Stieglmeyer, John, & Co. G.m.b.H.: *See*—
 Kotter, Helmut, 3,579,671.
 Stitchcraft Corporation: *See*—
 Krein, Reuben J., 3,580,561.
 Stock, David K.; and Wech, Robert J., to FMC Corporation. Bag stack accumulating conveyor. 3,580,142, Cl. 93-33.
 Stock, David K.: *See*—
 Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
 Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
 Stokeld, Richard W., Jr.: *See*—
 Moorer, Henry D.; Lewis, Ralph M.; and Stokeld, Richard W., Jr., 3,580,962.
 Stoltz, Jacques R.: *See*—
 Cox, John B.; and Stoltz, Jacques R., 3,580,072.
 Stone, Guthrie B. Tightrope device. 3,580,568, Cl. 272-60.
 Stone, Morris Denor; and Talbot, Howard Hubbell, to United Engineering and Foundry Company. Apparatus for reducing the width of metallic slabs. 3,580,032, Cl. 72-199.
 Stone, Raymond A.; Lister, Fred; and Heller, David S., to Standard Brands Chemical Industries, Inc. Film-forming composition of interpolymer latex and coalescing agent. 3,580,876, Cl. 260-29.4
 Stone, Roger B.: *See*—
 Bell, Allan J.; and Stone, Roger B., 3,581,220.
 Storey, William T., II: *See*—
 Eichert, Edwin S.; and Storey, William T., II, 3,581,250.
 Stormon, Lester T.: *See*—
 Stastny, Edwin O.; Stormon, Lester T.; and Sims, Anson, 3,580,585.
 Stouffer, James R.; Buege, Dennis R.; and Gillis, Wayne A., to Cornell Research Foundation, Inc. Meat tenderizing method. 3,579,716, Cl. 17-45.
 Strack, Richard R., to Bendix Corporation. The. Pressure transducer. 3,580,082, Cl. 73-406.
 Strafford, Richard A.; and Davis, William J. Bowler's equalizing weight. 3,580,572, Cl. 273-54.
 Straub, Melvin J.: *See*—
 Schuette, Thomas L.; Straub, Melvin J.; Dumas, Pierre; and Aurich, Peter F., 3,579,771.
 Streed, Donovan P. Humidity and temperature sensing and control circuit. 3,580,501, Cl. 236-44.
 Streit, Rudolf: *See*—
 Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
 Strem, Lawrence F. Visual aid for teaching and testing the sight reading of the fractional divisions of an inch. 3,579,860, Cl. 35-31.
 Strick Corporation: *See*—
 Abolins, Andrew, 3,580,410.
 Strittmater, David J.; and Voelker, Nicholas W., to Universal Oil Products Company. Laminate bond peeling strength tester. 3,580,065, Cl. 73-150.
 Stroborg, Clark E.; and Stroborg, Eldon L. Combine. 3,580,258, Cl. 130-27.
 Stroborg, Eldon L.: *See*—
 Stroborg, Clark E.; and Stroborg, Eldon L., 3,580,258.
 Strohm, Siegfried, to Porsche, Dr.-Ing. H.c.F., K.G., Firma. Electronically controlled speedometer with maximum speed indicator. 3,581,206, Cl. 324-169.
 Strom, Sven B., to American Pulverizer Company. Ring hammers. 3,580,518, Cl. 241-193.
 Stromin, Boris Alexandrovich: *See*—
 Baranov, Boris Konstantinovich; and Stromin, Boris Alexandrovich, 3,581,171.
 Strout, Russell B.: *See*—
 Lowry, Robert D.; and Strout, Russell B., 3,579,662.
 Strub, Rene, to Sulzer Brothers Limited. Gas turbine power plant including a nuclear reactor as heat source. 3,579,982, Cl. 60-36.
 Stuart, Henry P. Bandage containing a medicinal material and method of using. 3,580,254, Cl. 128-268.
 Stubbs, Dennis: *See*—
 Bond, Harry Laurence Fred; Stubbs, Dennis; and Maltby, Todwick, 3,580,035.
 Stutz, Theo; and Mueller, Werner, to Contraves AG. Display arrangement for symbols. 3,581,301, Cl. 340-324.
 Succo, John A.: *See*—
 Darragh, Richard T.; and Succo, John A., 3,580,729.
 Sugarman Laboratories, Inc.: *See*—
 Sugarman, Robert, 3,581,290.
 Sugarman, Robert, to Sugarman Laboratories, Inc. Information display system. 3,581,290, Cl. 340-172.5
 Sugimura, Kazuo; and Sugimura, Nobuyuki. Accumulator. 3,580,290, Cl. 138-121.
 Sugimura, Nobuyuki: *See*—
 Sugimura, Kazuo; and Sugimura, Nobuyuki, 3,580,290.
 Suhr, Volker: *See*—
 Panschow, Rudolf; Russbuel, Herbert; Suhr, Volker; and Ullmann, Werner, 3,581,045.
 Sulzer Brothers Limited: *See*—
 Pfarrer, Erwin, 3,580,011.
 Strub, Rene, 3,579,982.
 Sumitomo Electric Industries, Ltd.: *See*—
 Kaneno, Saburo; Yamaguchi, Takeshi; and Yoshioka, Shunichi, 3,581,084.
 Sun Oil Company: *See*—
 Driscoll, Gary L., 3,580,964.
 Sunbeam Corporation: *See*—
 Grahn, Robert D., 3,579,827.
 Sundberg, Alan F. Portable toilet and sink structures and the like. 3,579,655, Cl. 4-116.
 Sundin, Charles H.: *See*—
 Stark, Donald A.; Di Bartolo, Ernest A.; Feather, Harry A.; and Sundin, Charles H., 3,579,989.
 Sundstrand-Engelberg Inc.: *See*—
 Schaller, Robert L., 3,579,918.
 Susquehanna Corporation, The: *See*—
 Boswell, George T., 3,580,176.
 Wallace, Jacob L., Jr., 3,581,006.
 Suter, Xaver, to Werkzeugmaschinenfabrik Oerlikon-Buhle AG. Rocket with spreadable empennage. 3,580,529, Cl. 244-3.29
 Suzuki, Hiroshi: *See*—
 Nakanome, Iyohiko; Takeya, Kenji; Suzuki, Hiroshi; and Kitagawa, Yasuhiro, 3,580,878.
 Suzuki, Kinichiro, to Sansei Manufacturing Co., Ltd. Hydro-electrical control for a rotary surface grinder. 3,579,913, Cl. 51-95.
 Suzuki, Takashi: *See*—
 Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
 Suzuki, Tamotsu: *See*—
 Kanzaki, Fumiaki; Kozakura, Yoshio; Akahide, Kozo; and Suzuki, Tamotsu, 3,581,039.
 Suzuki, Tokihide: *See*—
 Horie, Hajime; Hirano, Tadao; and Suzuki, Tokihide, 3,580,015.
 Suzuki, Yoshiaki; and Inamoto, Toshiharu, to Matsushita Electric Industrial Co., Ltd. Data processing system. 3,581,288, Cl. 340-172.5
 Suzuoka, Takayuki, to Hitachi, Ltd. Gold-aluminum lead-out structure of a semiconductor device. 3,581,166, Cl. 317-235.
 Svensen, Niels Alf, to United Aircraft Corporation. Non-clogging marine grille with unpowered weed cutting provisions. 3,580,210, Cl. 115-075.
 Swanson, Percy L. Gas cooled microscope slide. 3,580,658, Cl. 350-93.
 Swartz, Elmer L.: *See*—
 Warren, Raymond W.; and Swartz, Elmer L., 3,580,069.
 Swassing, Raymond H., Jr.: *See*—
 Smith, Thomas B.; and Swassing, Raymond H., Jr., 3,579,874.
 Swift, Harold E., to Gulf Research & Development Company. Dehydrogenation of cycloaliphatic ketones and alcohols. 3,580,970, Cl. 260-621.
 Sybron Corporation: *See*—
 Amorese, Franklyn J., 3,580,547.
 Sylvania Electric Products, Inc.: *See*—
 Britt, Richard G.; and Loughridge, Frederick A., 3,580,710.
 Burdick, Glen A., 3,579,768.
 Ingraham, Robert C.; and Ramsey, Hubert J., 3,579,816.
 Johnson, Alfred D., 3,581,134.
 Staunton, Kenneth L., 3,581,136.
 Sylvester, Willard G.: *See*—
 Bonton, Ira D.; and Sylvester, Willard G., 3,580,564.
 Systems Peripherals Division: *See*—
 Meyer, Forrest C., 3,581,215.
 Szabo, Kalman T.: *See*—
 Cook, Allen D.; and Szabo, Kalman T., 3,580,220.
 Taccone, Russell W., to Kelsey-Hayes Company. Plural mold casting apparatus. 3,580,329, Cl. 164-366.
 Tadini, Costantino: *See*—
 Ullmann, Werner; Tadini, Costantino; and Salim, Ehsan, 3,581,043.
 Tahan, Victor G.: *See*—
 Wilkinson, Jack E.; and Tahan, Victor G., 3,580,256.
 Takahashi, Shozo: *See*—
 Araki, Shigeru; Takahashi, Shozo; and Muto, Ichiro, 3,580,649.
 Takahashi, Takao: *See*—
 Sakamoto, Kenro; Takahashi, Takao; Koitabashi, Takeo; and Fujiwara, Mitsuo, 3,580,722.
 Takahashi, Yuji: *See*—
 Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
 Takamatsu, Tetsuya: *See*—
 Yoshimoto, Toshio; Narumiya, Tsunekaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, 3,580,897.
 Takao, Kiyoshi: *See*—
 Shimodoi, Yutaka; Ootake, Heiichiro; Mihara, Kouichi; Takao, Kiyoshi; and Matsuda, Shogo, 3,580,735.
 Takao, Kentaro. Aerosol nebulizers. 3,580,249, Cl. 128-194.
 Takeya, Kenji: *See*—
 Nakanome, Iyohiko; Takeya, Kenji; Suzuki, Hiroshi; and Kitagawa, Yasuhiro, 3,580,878.

Talbot, Howard Hubbell: *See*—
 Stone, Morris Denor; and Talbot, Howard Hubbell, 3,580,032.
 Tall, Leonard H.: *See*—
 Ishihara, Frank Y., 3,579,801.
 Tam, Wayne C. Panel frame assembly. 3,579,943, Cl. 52-656.
 Tamai, Katsumi: *See*—
 Higashimura, Einosuke; Tamai, Katsumi; and Nakamura, Eiichi, 3,580,879.
 Tamoni, Gianfranco: *See*—
 Bini, Giancarlo; and Tamoni, Gianfranco, 3,580,284.
 Tanaka, Hiroshi; and Ishihara, Masayoshi, to Canon Camera Kabushiki Kaisha. Corona discharging device for electrophotographic process. 3,581,149, Cl. 317-4.
 Tanaka, Yoshimasa: *See*—
 Matsumoto, Masamiki; Nishino, Motohisa; and Tanaka, Yoshimasa, 3,579,824.
 Tanguay, Jean Paul, to Placements Jean Paul Tanguay Ltée, mesne. Mobile tree slasher. 3,580,306, Cl. 143-46.
 Tanner, Carole S.; and Tontini, Remo, to Rohr Corporation. Sound suppression system. 3,579,993, Cl. 60-262.
 Targonski, Leonard A.: *See*—
 Hyde, Thomas J.; and Targonski, Leonard A., 3,580,577.
 Taylor, Howard N.: *See*—
 Cannon, Lester E.; Tindall, John M.; and Taylor, Howard N., 3,580,476.
 Taylor, Ian: *See*—
 Howitt, Fred; and Taylor, Ian, 3,580,747.
 Taylor, James E.: *See*—
 Pliskin, William A.; and Taylor, James E., 3,580,066.
 Teague, Earl E. Weed seed collector for a thresher combine. 3,580,257, Cl. 130-24.
 Technical Metals, Inc.: *See*—
 Packard, Robert F., 3,579,800.
 Technical Wire Products, Inc.: *See*—
 Lamp, Richard W.; Kopf, Joseph E.; Dravis, Donald P.; and Cuneo, Robert A., 3,580,981.
 Technicolor, Inc.: *See*—
 Ben Bassett, Marvin, 3,580,665.
 Technitrol, Inc.: *See*—
 Eichert, Edwin S.; and Storey, William T., II, 3,581,250.
 Tecumseh Products Company: *See*—
 Tenisons, Janis, 3,580,116.
 Teed, Richard K.; and Klose, Karl W., to Riegel Textile Corporation. Apparatus for automatically fabricating individual articles. 3,580,198, Cl. 112-121.11
 Tegholm, Ruben, to Atlas Copco Aktiebolag. Temperature responsive means for automatically correcting variations in the compensation of an electromagnetic prospecting device. 3,581,194, Cl. 324-6.
 Tekkosha Co., Ltd.: *See*—
 Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
 Teleflex Incorporated: *See*—
 Shreve, Russell L., 3,580,103.
 Telefonaktiebolaget L M Ericsson: *See*—
 Fjallbrant, Tor Torstensson, 3,581,246.
 Mattsson, Orjan Mats; and Widl, Walter Herbert Ewin, 3,581,075.
 Telefunken Patentverwertungsgesellschaft m.b.H.: *See*—
 Dopner, Horst, 3,580,525.
 Telemation, Inc.: *See*—
 Ward, Ronald C.; and Allen, David T., 3,581,011.
 Telesco Brophy Limited: *See*—
 Weber, Heinz, 3,580,262.
 Teletype Corporation: *See*—
 Hagstrom, Arthur A., 3,581,004.
 Tenisons, Janis, to Tecumseh Products Company. Clutch adjustment tool. 3,580,116, Cl. 81-302.
 Tenneco Chemicals, Inc.: *See*—
 Farber, Elliott, 3,580,896.
 Terao, Yoshikazu: *See*—
 Wada, Yoshiyo; Yasutake, Katsuya; and Terao, Yoshikazu, 3,580,446.
 Ternent, George E., to Bendix-Westinghouse Automotive Air Brake Company. Dual circuit brake valve. 3,580,646, Cl. 303-52.
 Terrell, Kyle E.; and Rester, Darryl C., to Amco International. Dozer for a farm tractor. 3,580,341, Cl. 172-805.
 Testa, Emilio: *See*—
 Cavalleri, Bruno; Bellasio, Elvio; and Testa, Emilio, 3,580,932.
 Tetra Pak AG: *See*—
 Gustafson, Ake, 3,580,788.
 Texaco Inc.: *See*—
 Allen, Joseph C.; Bednarski, Valery N.; and Hall, Russell W., Jr., 3,580,335.
 Furman, George R., 3,580,170.
 Howlett, Donald L., 3,581,305.
 Moorer, Henry D.; Lewis, Ralph M.; and Stokeld, Richard W., Jr., 3,580,962.
 Texas Instruments Incorporated: *See*—
 Coad, Brian C., 3,579,772.
 Cunningham, James A.; and Clark, Robert S., 3,581,161.
 Frieling, Gerald H., Jr., 3,580,706.
 Textron Inc.: *See*—
 Chery, Walter V., 3,579,748.
 Richards, William R., 3,580,647.
 Zotter, John F., 3,580,590.
 Textron Incorporated: *See*—
 Matt, Richard J.; and Restelli, Ronald E., 3,579,780.
 Thayer, Inc.: *See*—
 Blais, Zoel W.; and Shaw, Harold F., 3,579,674.
 Thelen, Edmund J.; and King, Robert H., to Packaging Corporation of America. Sanitary package. 3,580,466, Cl. 229-14.
 Thew, Donald G., to Harnischfeger Corporation. Voltage splitter circuit. 3,581,104, Cl. 307-15.
 Thibault, Jean-Jacques; and Boissin, Jean-Claude, to L'Air Liquide Societe Anonyme pour l'Etude et l'Exploitation des Procédes Georges Claude. Cryogenic pumping device for the creation of very high vacua. 3,579,998, Cl. 62-55.5
 Thiel, Max; Kampe, Wolfgang; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, to Boehringer Mannheim Gesellschaft mit beschränkter Haftung. P-alkoxy-piperidine-amides. 3,580,910, Cl. 260-240.
 Thiel, Max; Stach, Kurt; Schaumann, Wolfgang; and Ribbentrop, Annemarie, to Boehringer Mannheim Gesellschaft mit beschränkter Haftung. Morphanthridine derivatives. 3,580,907, Cl. 260-239
 Thieme, Klaus-Dietrich: *See*—
 Hermes, Heinz; Thieme, Klaus-Dietrich; Gatermann, Willi; Koerv, Peter; and Mehnert, Walter, 3,581,185.
 Thomas & Betts Corporation: *See*—
 Cole, John M., 3,579,942.
 Thomas, Carroll E. Artist's painting kit and tripod adapter therefor. 3,580,653, Cl. 312-231.
 Thompson, Daniel T. Dough feeding apparatus. 3,580,385, Cl. 198-103.
 Thompson, David R., to Rental Equipment Manufacturing Corporation. Sweeper. 3,579,702, Cl. 15-79.
 Thompson, Douglas F.: *See*—
 Hornak, John C.; and Thompson, Douglas F., 3,580,574.
 Thompson, Harry W. Wrench having a locked adjustable position. 3,580,115, Cl. 81-165.
 Thompson, Kenneth L., to Ye Dock Master, Inc. Floating wharf structure. 3,580,202, Cl. 114-0.5
 Thompson, Kermith R. Remote control for fuel line shut-off. 3,580,353, Cl. 180-98.
 Thorn Electrical Industries Limited: *See*—
 Ranby, Peter Whitten; and Northwood, John Lenard, 3,580,738.
 Tibbals, Howard C. Wood parquet block flooring unit. 3,579,941, Cl. 52-384.
 Tidball, Robert A.; King, William M.; Bosley, Dewey R.; and Jennings, Charles M., to Baldwin-Lima-Hamilton Corporation. Apparatus for making large distillation plants. 3,580,816, Cl. 202-173.
 Tierney, Robert R.: *See*—
 Pope, Karl D., III; Morey, Thomas H.; and Tierney, Robert R., 3,579,681.
 Tilly, Lorenz; and Bonner, Barrie, to Universal Alufolien Verfahren A.G., mesne. Die assembly. 3,580,041, Cl. 72-336.
 Timofeev, Evgeny Petrovich: *See*—
 Kononov, Mikhail Ivanovich; Krashenninnikov, Evgeny Anatolievich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaevich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich, 3,580,717.
 Tindall, John M.: *See*—
 Cannon, Lester E.; Tindall, John M.; and Taylor, Howard N., 3,580,476.
 Tiona-Betts, Inc.: *See*—
 Hanson, John R.; and Pierson, Karl B., 3,580,275.
 Tjebbes, Horatius: *See*—
 Eshuis, Jannes; and Tjebbes, Horatius, 3,579,765.
 Todt, Hans-Gunther; and Dahms, Wolfgang, to Schering AB. Bright silver electroplating. 3,580,821, Cl. 204-46.
 Tohma, Takaaki: *See*—
 Eguchi, Yasuhiro; Fujiwara, Yoshio; and Tohma, Takaaki, 3,580,992.
 Tolf, Ingvar L.; Herzing, Vernon J.; Miller, Everett L.; and Lightfoot, George L., to General Foods Corporation. Apparatus for automatically stacking and inverting stacked units of sheet material. 3,580,402, Cl. 214-6.
 Tomasello, Antonio: *See*—
 Provost, Emile L.; and Tomasello, Antonio, 3,580,474.
 Tomiwa, Hiroshi, to Matsuo Electric Company, Limited. Method of making electronic components on comb like metal fingers and severing the fingers. 3,579,813, Cl. 29-570.
 Tomiwa, Hiroshi: *See*—
 Matsuo, Masao; and Tomiwa, Hiroshi, 3,579,811.
 Tomizawa, Kazuhiro, to Nittai Lease Company Ltd. Lower roller for endless tread for vehicle. 3,580,093, Cl. 74-230.3
 Tontini, Remo: *See*—
 Tanner, Carole S.; and Tontini, Remo, 3,579,993.
 Torkildsen, Robert A.: *See*—
 Hovius, Thomas C.; and Torkildsen, Robert A., 3,580,741.
 Torortseva, Tatiana Nikolaevna: *See*—
 Naumenko, Viktor Arsenievich; Torortseva, Tatiana Nikolaevna; Penkova, Lidia Fedorovna; Vyselkov, Andrei Akimovich; and Rogova, Galina Ivanovna, 3,580,742.
 Torti, Luigi; and Bertelli, Guido. Method for bonding olefinic terpolymers to natural rubber and vulcanizates obtained thereby. 3,580,800, Cl. 161-243.
 Toth, Louis, to Anchor Enterprises Corporation. Apparatus for the manufacture of composite structural elements. 3,579,724, Cl. 18-4.

- Trans-Sonics, Inc.: See—
Westcott, Vernon C.; and Williams, Sidney B., 3,580,074.
- Trapp, Gunther: See—
Mundlos, Eberhard; Mohr, Reinhard; Trapp, Gunther; and Hohmann, Kurt, 3,580,900.
- Traub, Hermann, Firma: See—
Werkmeister, Johannes; and Scheler, Holger, 3,580,418.
- Traynor, Edward J., Jr., to Westinghouse Electric Corporation. Chemical radiating conductor edges of flat cable, 3,580,737, Cl. 117-212.
- Trefleries & Cables de Bourg et du Havre: See—
Behar, Isaac, 3,580,746.
- Trementozzi, Quirino A.: See—
Lee, Yoon Chai; and Trementozzi, Quirino A., 3,580,974.
- Trepanier, Donald L., to Dow Chemical Company. The Dibenzo-cycloheptene derivatives, 3,580,943, Cl. 260-453.
- Tri-Ang Toys Limited: See—
Manning, Peter R. J., 3,580,426.
- Trindle, John P., to Fairbanks, John P. Paste dispenser with interchangeable bagged cartridges, 3,580,429, Cl. 222-327.
- Trinks, Walter; Netzer, Theodor Karl; Victoria, Hans T.; Saurer, Hermann; and von Paulgerg, Heinrich, to Berliner Maschinenbau AG vorm. L. Schwartzkopff. Simulator for simulating the action of the pressure of a shock wave of a nuclear explosion, 3,580,048, Cl. 73-35.
- Triplett, Lee, to Expando Products Company. Utility rod and mounting construction therefor, 3,580,397, Cl. 211-105.4.
- Triplex Safety Glass Company Limited: See—
Witherington-Perkins, Geoffrey Frank, 3,580,119.
- Triprio, Inc.: See—
Dyal, Gilford E., 3,580,770.
- Tron, Manfred: See—
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
- Trosko, David P. Golf practice device, 3,580,584, Cl. 273-186.
- Trusselle, William H., to Pneumatic Scale Corporation. Container filling machine, 3,580,298, Cl. 141-40.
- TRW Inc.: See—
Guth, Eugene D.; Lewis, Jerry L.; and Van Nice, Leslie J., 3,580,961.
- Hagan, Melvin A.; and Batista, Roy I., 3,580,808.
- Jorgensen, Anker E.; and Oxley, Gerald K., 3,580,101.
- Kelly, Franklin G., 3,581,303.
- Selden, Ronald B., 3,581,284.
- Tsapkin, Vadim Vasilievich: See—
Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkina, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich, 3,580,859.
- Tsapkina, Irma Vyacheslavovna: See—
Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkina, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich, 3,580,859.
- Tsuboi, Takashi; and Narita, Hiroshi, to Hitachi, Ltd. Control system of electric motor, 3,581,172, Cl. 318-259.
- Tsuchiya, Noboru: See—
Kishi, Kanesuke; Tsuchiya, Noboru; and Shimura, Kazuo, 3,581,012.
- Tsujihata, Keiji; Shimada, Masatoshi; Asai, Hiromi; Sawada, Yasuhiro; and Ayuba, Zensaku, to Nippon Steel Corporation. Apparatus for operating a shaft furnace by detecting the falling speed of the charge, 3,581,070, Cl. 235-151.1.
- Tsurumi-Seikikosaku-Sho Co., Ltd., The: See—
Shimemura, Etsujiro; and Iwamiya, Masao, 3,581,238.
- Tucker, Linwood G., to Koppers Company. Apparatus for simultaneously actuating standpipe lid, damper valve and steam valve, 3,580,815, Cl. 202-258.
- Tumba, Sven O. G. Bilge pump for boats, 3,580,695, Cl. 417-330.
- Tureus, Daniel, Jr.: See—
Kopsch, Paul J.; Tureus, Daniel, Jr.; and Ward, Donald F., 3,580,178.
- Turk, Herbert: See—
Bauer, Karl; and Turk, Herbert, 3,581,060.
- Turner, Lyman H.: See—
Mallory, Donald G.; and Turner, Lyman H., 3,580,565.
- Turner, Ralph: See—
Schacht, Louis L.; and Turner, Ralph, 3,579,909.
- Tusson, John R. Isolation of information, 3,579,854, Cl. 35-8.
- Tuzaki, Takehiro: See—
Yamashita, Akio; and Tuzaki, Takehiro, 3,581,233.
- T. W. Manufacturing Company, Inc.: See—
Hansen, Benth Preben; and Blitz, Saul, 3,579,725.
- Tyrner, Joseph M., to Allied Chemical Corporation. Cam-controlled indexing device, 3,580,111, Cl. 74-817.
- Uelzmann, Heinz; and Hiding, David C., to General Tire & Rubber Company. The Laminated products, 3,580,799, Cl. 161-186.
- Uetrecht, Dale M., to Baldwin, D. H., Company. Diode keying system for electronic organ, 3,580,980, Cl. 84-122.
- Uhlig, Konrad: See—
Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,868.
- Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, 3,580,890.
- Ullman Devices Corporation: See—
Ullman, Robert, 3,579,677.
- Ullman, Robert, to Ullman Devices Corporation. Flexible rotary compound tool, 3,579,677, Cl. 7-1.
- Ullmann, Werner: See—
Panschow, Rudolf; Russbuel, Herbert; Suhr, Volker; and Ullmann, Werner, 3,581,045.
- Ullmann, Werner; Tadini, Costantino; and Salim, Ehsan, to A.G. fur Industrielle Elektronik AGIE. Apparatus for the control and regulation of the work gap of an electroerosion machine, 3,581,043, Cl. 219-69.
- Ulmer, Harold W.: See—
McKim, Jack D.; and Ulmer, Harold W., 3,581,307.
- Ulrich, Martin: See—
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
- Umbach, Hans: See—
Gawlick, Heinz; Stahlmann, Rudolf; and Umbach, Hans, 3,580,179.
- Umeda, Shinichi: See—
Kasahara, Shigekazu; Takahashi, Yuji; Suzuki, Takashi; Umeda, Shinichi; Adachi, Kazuo; and Fukuda, Yasuo, 3,580,883.
- Underwood, Ray L.; and Campbell, Thomas A. Motor vehicle loading and transporting device, 3,580,627, Cl. 296-1.
- Ungerer, Heinz: See—
Eggstein, Giorgio; and Ungerer, Heinz, 3,580,361.
- Union Camp Corporation: See—
Burke, William R.; and Mc Call, Frank S., 3,580,471.
- Union Carbide Corporation: See—
Manz, August F., 3,581,053.
- Piper, John; and Leitten, Carl F., Jr., 3,581,159.
- Uniroyal Englebert France S.A.: See—
Leblond, Jean, 3,580,782.
- Uniroyal, Inc.: See—
Barnes, Gerald L.; Cichy, Raymond G.; and Adams, Gerald E., 3,580,767.
- Hewitt, Eugene E., 3,580,793.
- United Aircraft Corporation: See—
Comstock, David W.; and Campbell, Edwin R., 3,581,182.
- Copley, Stephen M.; Giamei, Anthony F.; Hornbecker, Merton F.; and Kear, Bernard H., 3,580,324.
- Dalton, Robert Barry, 3,580,059.
- Mikolajczak, Alojzy A., 3,580,692.
- Smith, David C., 3,581,230.
- Svensen, Niels Alf, 3,580,210.
- Urban, Louis A.; and Stearns, Charles F., 3,579,992.
- United Electric Controls Company: See—
Reis, Robert D., 3,580,280.
- United Engineering and Foundry Company: See—
Stone, Morris Denor; and Talbot, Howard Hubbell, 3,580,032.
- United Kingdom Atomic Energy Authority: See—
Everson, Ivor; and George, Maurice William, 3,580,803.
- Mobbsy, Eric George Herbert, 3,580,076.
- Williams, Albert Etheridge; and Linkison, William Simpson, 3,580,809.
- United Kingdom of Great Britain and Northern Ireland, Minister of Technology in Her Britannic Majesty's Government of the: See—
Cheeseman, Ian Clifford; and Smith, Michael Charles George, 3,580,693.
- United Shoe Machinery Corporation: See—
Clarke, Terence J.L.; and Evans, Ivor, 3,580,774.
- United States Envelope Company: See—
Heywood, Vincent E.; Bushey, Donald H.; and Chapman, William A., Jr., 3,579,944.
- United States of America
Agriculture: See—
Koch, Peter, 3,580,760.
- Kramer, Harold A., 3,580,084.
- Air Force: See—
Craig, Leonard J., 3,581,089.
- Freiberg, Robert J., 3,581,231.
- Grundy, Gary, 3,581,119.
- Hudson, Kenneth C.; and Shashoua, Fred E., 3,580,151.
- Inouye, Shingo; and Saul, George, 3,580,744.
- Koestel, Alfred, 3,580,227.
- Lavedan, Louis J., 3,581,242.
- Plawner, Moshe L.; Vento, Vincent R.; and Gordon, Abraham, 3,580,363.
- Setto, Joseph B., 3,580,636.
- Army: See—
Arvidson, Paul W.; Park, William G.; and Williams, Keith S., 3,580,130.
- Blevins, William V., 3,580,051.
- Donadio, Vincent J.; and Anderson, Olavi F., 3,580,031.
- Larson, Wesley S., 3,579,641.
- Mon, George, 3,579,810.
- Warren, Raymond W.; and Swartz, Elmer L., 3,580,069.
- Zimmerman, John R., 3,580,131.
- Atomic Energy Commission: See—
Allison, Robert W., Jr.; Brokloff, Robert W.; and Woodyard, John R., 3,580,822.
- Brown, Leonard Carlton, 3,581,090.
- Coleman, Charles; and Weaver, Boyd S., 3,580,705.

- Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., 3,580,802.
- Paget, John A., 3,580,804.
- Health, Education and Welfare: See—
Crider, Walter Leslie, 3,580,680.
- Interior: See—
Cadotte, John E.; and Francis, Peter S., 3,580,841.
- Myers, John G.; and Field, Joseph H., 3,580,702.
- Navy: See—
Brian, Michael, 3,581,031.
- Cardwell, Lonnie D.; Esenwein, Fred T.; and Pierard, Arthur E., 3,580,049.
- Kurisu, Albert G., 3,579,821.
- Ohlstein, Paul E., 3,579,964.
- Pederson, Arthur M., 3,581,069.
- Wyatt, Robert D., 3,581,068.
- Unitrode Corporation: See—
Dixon, Lloyd H., Jr., 3,581,117.
- Universal Alufolien Verfahren A.G.: See—
Tilly, Lorenz; and Bonner, Barrie, 3,580,041.
- Universal Oil Products Company: See—
Bloch, Herman S., 3,580,956.
- Bloch, Herman S., 3,580,957.
- Issott, John W.; Honkala, Harold E.; and Carraher, Delbert V., 3,580,037.
- Pollitzer, Ernest L., 3,580,837.
- Strittmater, David J.; and Voelker, Nicholas W., 3,580,065.
- University of California, The Regents of the: See—
Hill, Fredrick L.; Gates, Lauren W.; and Colbert, William V., 3,579,968.
- University of Utah, The: See—
Seegmiller, Ben L., 3,580,057.
- Uno, Masaaki: See—
Abe, Katsuro; Kakinuma, Saburo; and Uno, Masaaki, 3,579,986.
- Upitnieks, Juris: See—
Leith, Emmett N.; and Upitnieks, Juris, 3,580,655.
- Upjohn Company, The: See—
Campbell, J. Allen; and Babcock, John C., 3,580,937.
- Morozowich, Walter; and Sinkula, Anthony A., 3,580,904.
- VanRheenen, Verlan H., 3,580,935.
- Urban, Louis A.; and Stearns, Charles F., to United Aircraft Corporation. Power plant variable geometry control, 3,579,992, Cl. 60-239.
- Urich, Daniel M., to Eveleth Taconite Company. Grate stripper for pelletizing machine, 3,580,553, Cl. 263-32.
- Uridil, Joseph E., to Litton Systems, Inc. Process for treating sewage and other contaminated waters, 3,580,840, Cl. 210-11.
- Urosevic, Milija: See—
Ivackovic, Nikola; and Urosevic, Milija, 3,579,852.
- URS Systems Corporation: See—
Orshansky, Elias, Jr., 3,580,107.
- U.S. Divers: See—
Oroza, August, 3,580,250.
- U.S. Philips Corporation: See—
Bongers, Piet Frans; and Zanmarchi, Giulio, 3,580,664.
- Dahle, Hildegard, 3,580,845.
- Dolbachian, Raymond; and Lefevre, Claude, 3,581,156.
- Hendriks, Adrianus Anthonius Maria, 3,581,138.
- Kooi, Else; and Van Der Meer, Aant Bouwe Daniel, 3,580,745.
- Meijer, Albertus Cornelis, 3,581,091.
- Potzl, Friedrich, 3,581,251.
- Ushio Electric Inc.: See—
Ushio, Jiro, 3,581,133.
- Ushio, Jiro, to Ushio Electric Inc. Gaseous discharge tube with metallized coated, electrode support portions, 3,581,133, Cl. 313-43.
- USM Corporation: See—
Boot, Herbert W.; Parr, Leslie R.; and Fudger, Shirley L. W., 3,579,695.
- Duffy, Richard J., 3,579,684.
- Fichtner, Rudi; Ober, Horgern; and Klein, Wilhelm, 3,579,691.
- Henshaw, James N., 3,580,457.
- Imhof, Herman A., 3,579,694.
- Muhlbach, Anton; and Lauckhardt, Gerhard, 3,579,692.
- Utica Tool Company, Inc.: See—
Rozmus, Walter, 3,580,114.
- Valbona, Bruno M., to Dynamics Corporation of America. Liquidizer timer jogger with improved drive means including lost motion connection, 3,581,028, Cl. 200-38.
- Valeron Corporation, The: See—
Milewski, Victor, 3,579,777.
- Valmet Oy: See—
Heinonen, Martti, 3,580,632.
- Vance, Robert G. Optical printer for motion picture film, 3,580,666, Cl. 352-90.
- Van Dalen, Leonard, to Seaboard Fabricators, Inc., mesne. Screw and nut driver, 3,580,097, Cl. 74-421.
- Van de Meerendonk, Gerardus Cornelis, to Nedschroef Octrooi Maatschappij N.V. Mechanism for ejecting workpieces from the matrices of upsetting machines, 3,579,685, Cl. 10-12.
- Van Der Meer, Aant Bouwe Daniel: See—
Kooi, Else; and Van Der Meer, Aant Bouwe Daniel, 3,580,745.
- Van Der Wal, Jurjen. Variable pitch chain assembly, 3,580,383, Cl. 198-16.
- Van Mullekom, Hubert P., to N.V. Machinefabriek L. te Strake. Device for localizing an excess in length in a thread, 3,580,444, Cl. 226-97.
- Van Nice, Leslie J.: See—
Guth, Eugene D.; Lewis, Jerry L.; and Van Nice, Leslie J., 3,580,961.
- VanRheenen, Verlan H., to Upjohn Company, The. Process for the preparation of 3-nol ethers, of 3- keto-3'-6-(N-disubstituted)aminomethyl steroids, 3,580,935, Cl. 260-397.1.
- Van Scoy, Davis A., to Helmerich & Payne, Inc. Valve seal and system, 3,580,539, Cl. 251-159.
- Van Staveren, Pieter, to Nederlandse Organisatie voor Toegepost-Natuurwetenschappelijk Onderzoek ten behoeve van Nijverheid, Handle en Verkeer. Pressure wave sustained vehicle, 3,580,356, Cl. 180-116.
- Vanyi, Louis. Soldering apparatus, 3,580,462, Cl. 228-51.
- Van Zurk, Robert, to Commissariat a l'Energie Atomique. Method of pulse-shaping and renewable-duration variable pulse-shaping circuit for the application of said method, 3,581,118, Cl. 307-267.
- Varaxin, Alexei Ivanovich: See—
Khimich, Georgy Lukich; Niskovskikh, Vitaly Maximovich; Varaxin, Alexei Ivanovich; Gelfenbein, Evgeny Jukhimovich; Bykov, Leonid Alexandrovich; Litvinov, Anatoly Ivanovich; and Karlinsky, Stanislav Evgenievich, 3,580,327.
- Varian Associates: See—
Anderson, Weston A., 3,581,191.
- Jepsen, Robert L., 3,581,195.
- Morris, Dennis E., 3,581,145.
- Williams, Norman H., 3,581,038.
- Varo, Inc.: See—
Paquette, Raymond E., 3,581,140.
- Vartanian, Edwin S., to Olin Mathieson Chemical Corporation. Buffer and delay mechanism for a firearm, 3,580,132, Cl. 89-130.
- Vasiliev, Evgeny Nikolaevich: See—
Kononov, Mikhail Ivanovich; Krashenninnikov, Evgeny Anatolievich; Knyazev, Vladimir Fedorovich; Vasiliev, Evgeny Nikolaevich; Nasonov, Petr Yakovlevich; and Timofeev, Evgeny Petrovich, 3,580,717.
- Vasse, Jacques, to Societe Industrielle Bull-General Electric (Societe Anonyme). Asynchronously controlled arrangement for feeding record cards, 3,580,566, Cl. 271-41.
- Vaughan, Harry L., to Scripto, Inc. Fuel transfer system for cigarette lighters, 3,580,699, Cl. 431-321.
- Vaughn, Reuben F.: See—
Plonsker, Harvey R.; Vaughn, Reuben F.; Lang, Felix C.; Aurich, Christoph W.; and Bowie, Philip A., 3,579,761.
- Vazquez, Charles, to International Standard Electric Corporation. Shock resistant armature for electro-magnetic devices, 3,581,256, Cl. 335-271.
- Veater, Donald J.; Hill, Sumner B.; and Ruffner, Lawrence J., to Erie Technological Products, Inc. Reinforced ceramic capacitor and method of making the same, 3,581,167, Cl. 317-261.
- Veeco Instruments, Incorporated: See—
Greenberg, Sol; Rosen, Heinz; Weinberger, Richard; and Mongodin, Guy, 3,580,081.
- Veeder-Industries Inc.: See—
Bickford, John H., 3,580,421.
- La Pointe, Lloyd J.; Voegelin, Howard J.; and Hoffman, Ernest G., 3,580,498.
- Vento, Vincent R.: See—
Plawner, Moshe L.; Vento, Vincent R.; and Gordon, Abraham, 3,580,363.
- Vercillo, Peter A., to Continental Can Company. Closure, 3,580,201, Cl. 113-121.
- Verdoordt, Marcel E.; and Michalke, Klaus A., to Chrysler Corporation. Tailgate window washer, 3,579,698, Cl. 15-250.1.
- Vereinigte Flugtechnische Werke Gesellschaft mit beschränkter Haftung fruher 'Weser' Flugzeugbau/ Fock-Wulf Heinkel-Flugzeugbau Hunefeldstrasse: See—
Bock, Gerhard; Riccius, Rolf; Weitkamp, Gunter; and Wolf, Bernhard, 3,580,531.
- Vergara Ochoa, Alfonso. Method and apparatus for the transfer of images onto surfaces of hollow elastomeric articles, 3,580,772, Cl. 156-240.
- Verhagen, Cornelis M. Stabilization pendulum system, 3,580,364, Cl. 188-87.
- Vermes, Roy E., to Revco Inc. Counting apparatus, 3,580,145, Cl. 93-93.
- Verschaeve, Henry O.: See—
Daniel, David W.; Verschaeve, Henry O.; and Mc Nabb, Warren C., 3,580,024.
- Veszelik, Josef: See—
Knitter, Heinz; and Veszelik, Josef, 3,581,271.
- Victor Company of Japan, Limited: See—
Kosaka, Yoshiteru, 3,580,994.
- Wada, Yoshiyo; Yasutake, Katsuya; and Terao, Yoshikazu, 3,580,446.
- Victoria, Hans T.: See—
Trinks, Walter; Netzer, Theodor Karl; Victoria, Hans T.; Saurer, Hermann; and von Paulgerg, Heinrich, 3,580,048.
- Vignes, Roger: See—
Rouet, James; and Vignes, Roger, 3,580,224.

- Vignet, Paul: *See—*
de Villiers, Rocco Catoggio; Blachez, Loic; Jegou, Francois; Huyghe, Jean; and Vignet, Paul, 3,580,818.
- Vigorelli, Luigi. Embroidery stitching sewing machine. 3,580,199, Cl. 112-158.
- Vincent, Robert E.: *See—*
Hoory, Sadok E.; Newman, Stanley F.; and Vincent, Robert E., 3,580,819.
- Visher, Wilbur A., to Narco Scientific Industries, Inc. Electronic course line computer. 3,581,073, Cl. 235-150.26
- Voegelin, Howard J.: *See—*
La Pointe, Lloyd J.; Voegelin, Howard J.; and Hoffman, Ernest G., 3,580,498.
- Voelker, Nicholas W.: *See—*
Strittmater, David J.; and Voelker, Nicholas W., 3,580,065.
- Vogel, Alvin R.; Moore, Douglas A.; Folan, Martin P.; and Buck, John R., to Northrop Corporation. Integrated system for reporting aircraft data. 3,581,014, Cl. 179-100.1
- Voisin, Eugene; Raisin, Jean-Pierre; and Delair, Jean-Paul, to Centre Technique Industriel dit: Institut Textile de France. Device for controlling the delivery of thread to a knitting machine. 3,580,012, Cl. 66-55.
- Volkl, Franz, OHG.: *See—*
Volkl, Franz, 3,580,596.
- Volkl, Franz, to Volkl, Franz, OHG. Ski construction. 3,580,596, Cl. 280-11.13
- Volkswagen Aktiengesellschaft: *See—*
Carbon, Erich; and Wagner, Wolfgang, 3,579,750.
- Vollmann, Hansjorg: *See—*
Rauterkus, Karl Josef; and Vollmann, Hansjorg, 3,580,871.
- von Paulberg, Heinrich: *See—*
Trinks, Walter; Netzer, Theodor Karl; Victora, Hans T.; Saurer, Hermann; and von Paulberg, Heinrich, 3,580,048.
- Vorberg, Fritz, to Globotex AG. Method and apparatus for making hip stockings for panty hose and the like. 3,580,437, Cl. 223-75.
- Vore, Herbert G.; and Bardsley, Donald E., to Improved Machinery Inc. Template assembly. 3,579,726, Cl. 18-5.
- VSI Corporation: *See—*
Gearhart, Harlan G., 3,580,555.
- Vyselkov, Andrei Akimovich: *See—*
Naumenko, Viktor Arsenievich; Torotseva, Tatiana Nikolaevna; Penkova, Lidia Fedorovna; Vyselkov, Andrei Akimovich; and Rogova, Galina Ivanovna, 3,580,742.
- Waagener-Biro Aktiengesellschaft: *See—*
Rasworschegg, Heinrich; Markow, Demeter; and Sandri, Alfred, 3,580,718.
- Wada, Misao; and Soda, Kiyoshi, to Japan Aircraft Manufacturing Co., Ltd. Lift fan installation of vertical or short take-off and landing aircraft. 3,580,530, Cl. 244-54.
- Wada, Yoshiyo; Yasutake, Katsuya; and Terao, Yoshikazu, to Victor Company of Japan, Limited. Magnetic tape movement initiation system. 3,580,446, Cl. 226-108.
- Wagner Electric Corporation: *See—*
Falk, Edward J., 3,580,362.
- Wagner, Millard C., to Kappel, Thomas Inc. Cargo loading and support system. 3,580,606, Cl. 280-179.
- Wagner, Richard C., to Integral Process Systems, Inc. Chamber for food treating apparatus. 3,580,000, Cl. 62-77.
- Wagner, Wilhelm: *See—*
Hoffmann, Heinrich; and Wagner, Wilhelm, 3,580,230.
- Wagner, Wolfgang: *See—*
Carbon, Erich; and Wagner, Wolfgang, 3,579,750.
- Waldo, Russell W., to Ideal Security Hardware Corporation. Lock with means concealing mounting fasteners. 3,580,017, Cl. 70-81.
- Waldron, Paul H. R. Testing device for stretchable sheet materials under simultaneous distortion in three dimensions. 3,580,050, Cl. 73-37.
- Walker, Norman Kenneth. Method for measuring the effects of stress on a man's performance of primary and secondary task. 3,579,865, Cl. 35-22.
- Walker, William H. Locking mechanism for fluid type actuators. 3,580,140, Cl. 92-25.
- Wallace, Jacob L., Jr., to Susquehanna Corporation, The. Duplex control circuit. 3,581,006, Cl. 178-58.
- Wallace, Robert H., to Honeywell Inc. Servo motor driving and braking circuit. 3,581,181, Cl. 318-640.
- Waller, Richard E.: *See—*
Williams, Charles A.; and Waller, Richard E., 3,579,793.
- Walsh, Edward N.: *See—*
Price, Glenn R.; and Walsh, Edward N., 3,580,922.
- Walters, Frank F., to Carrier Corporation. Apparatus for producing external integral fins for tubing. 3,580,028, Cl. 72-98.
- Waltz, Marion D.; and Drake, Lewis A., to Youngstown Sheet and Tube Company, The. Rolling mill including gauge control. 3,580,022, Cl. 72-8.
- Waltz, Richard B., to Burroughs Corporation. Automatic checkout apparatus. 3,581,074, Cl. 235-153.
- Waluga, Wolfgang: *See—*
Piazza, Gian-Franco; Streit, Rudolf; Ulrich, Martin; Laber, Werner; Burkert, Adolf; Tron, Manfred; and Waluga, Wolfgang, 3,581,183.
- Wanger, Robert P.: *See—*
Holtzheirichs, Philip D.; and Wanger, Robert P., 3,579,929.
- Ward, Donald F.: *See—*
Kopsch, Paul J.; Turcus, Daniel, Jr.; and Ward, Donald F., 3,580,178.
- Ward, John C., Jr.: *See—*
Arnould, Marcel M.; Ward, John C., Jr.; Ray, William Floyd; and Budzyn, Boleslaw L., 3,580,386.
- Ward, Roderick K.: *See—*
Helrigel, Robert A.; Brownell, James R.; Ward, Roderick K.; and Keithley, Harry E., 3,580,558.
- Ward, Ronald C.; and Allen, David T., to Telemation, Inc. Television broadcast synchronizing apparatus and method. 3,581,011, Cl. 178-69.5
- Ware, Gordon K., to Chicago Roller Skate Company, The. Toe stop mounting for roller skates. 3,580,594, Cl. 280-11.2
- Ware, Gordon K.; Diehr, Hans Joachim; Merten, Rudolf; Piechota, Helmut; and Uhlig, Konrad, to Chicago Roller Skate Company, The. Farbenfabriken Bayer Aktiengesellschaft. Toe stop mounting for street roller skates. Basic catalysts containing aromatic nuclei and araliphatically bound tertiary amino groups for the polymerization of NCO groups. 3,580,890, Cl. 260-77.5
- Ware, Thomas G.: *See—*
Leiter, Robert Paul; and Ware, Thomas G., 3,579,663.
- Wargo, William, to Ford Motor Company. Apparatus for annealing with accelerated cooling. 3,580,331, Cl. 165-48.
- Wark, John D.; and Schladermundt, Peter. Aerial spinning disc. 3,580,580, Cl. 273-106.
- Warner, Robert F., to Hayes Albion Corporation. Nondestructive, resonant testing apparatus with magnetic pickup. 3,580,056, Cl. 73-67.2
- Warnett, Kenneth, to Electro-Lifts Limited. Linear electric motor. 3,581,127, Cl. 310-13.
- Warren, Raymond W.; and Swartz, Elmer L., to United States of America, Army. Subsonic fluidic angle-of-attack sensor. 3,580,069, Cl. 73-180.
- Warren, Robert C.; and Adams, Robert G. Automatic anti-jackknifing control for articulated vehicles. 3,580,610, Cl. 280-432.
- Washi, Masao: *See—*
Hoshi, Hideo; Washi, Masao; and Yoshiki, Hiroshi, 3,579,687.
- Watanabe, Hideo; and Leonard, John E., to Beckman Instruments, Inc. Method and apparatus for in vivo potentiometric measurements. 3,580,239, Cl. 128-2.1
- Watanabe, Ryozi; and Kobayashi, Yutaka, to Hitachi, Ltd. Switching device for on-load tap changers or regulating transformers. 3,581,188, Cl. 323-43.5
- Watari, Daisaku; and Morita, Tosio, to Seibu Denki Kogyo Kabushiki Kaisha. Continuously variable power supply for electric discharge machines capable of maintaining a constant ratio between amplitude and duration of discharge current. 3,581,044, Cl. 219-69.
- Watson, John Thaxter; and Robinson, Kenneth, to Itek Corporation. Panoramic camera with forward image motion compensation by optical rotation of image. 3,580,150, Cl. 95-12.5
- Watson, Lloyd M.; and Birchall, William R., to National Distillers and Chemical Corporation. Continuous process for preparing alkali metal dispersions and apparatus. 3,580,862, Cl. 252-309.
- Way, Frederick L. Auto-chess apparatus and punched card therefor. 3,579,856, Cl. 35-8.
- Wear, Robert L., to Minnesota Mining and Manufacturing Company. Ultraviolet light inhibitors. 3,580,927, Cl. 260-333.
- Weaver, Boyd S.: *See—*
Coleman, Charles; and Weaver, Boyd S., 3,580,705.
- Weaver, Eugene E. Universal yarn spool holder. 3,580,524, Cl. 242-129.7
- Weaver, Robert L.; and Myrice, Frank D. Intensive care apparatus. 3,580,395, Cl. 211-87.
- Webb, Samuel L.: *See—*
Scholle, Peter T.; and Webb, Samuel L., 3,580,158.
- Webb, Thomas Alan; and Harvey, Jay A., to Balteau Electric Corporation. Video system for automatic production line inspection by X-ray. 3,580,997, Cl. 178-6.8
- Webbere, Fred J.: *See—*
Eppich, Robert E.; and Webbere, Fred J., 3,580,328.
- Weber & Scher Mfg. Co., Inc.: *See—*
Scher, Joseph William, 3,579,842.
- Weber, Heinz, to Telesco Brophrey Limited. Umbrella handle carrying strap assembly. 3,580,262, Cl. 135-20.
- Weber, Lorenz, to Gebruder Boehringer Gesellschaft mit beschränkter Haftung. Apparatus in a machine tool for indicating displacement effected by a feed spindle. 3,580,216, Cl. 116-115.5
- Weber, Rolf, to Siemens Aktiengesellschaft. Pulse generator for providing a plurality of pulses in determined phase positions. 3,581,115, Cl. 307-262.
- Webster, James A., to Monsanto Research Company. Trisilylalkanes. 3,580,940, Cl. 260-448.2
- Wech, Robert J.: *See—*
Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
- Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
- Stock, David K.; and Wech, Robert J., 3,580,142.
- Weems, Sterling J.; and Mandil, Harry, to Westinghouse Electric Corporation. Pressure suppressing arrangement. 3,580,806, Cl. 176-37.
- Weinberger, Aaron David, to Motorola, Inc. Reduced forward voltage drop rectifying circuit. 3,581,186, Cl. 321-43.

- Weinberger, Richard: *See—*
Greenberg, Sol; Rosen, Heinz; Weinberger, Richard; and Mon-godin, Guy, 3,580,081.
- Weiner, Sidney: *See—*
Ehrens, Henry; and Weiner, Sidney, 3,580,269.
- Weinstein, Berel, to Bio-Medical Sciences, Inc. Cardiographic apparatus with stylus control means. 3,580,241, Cl. 128-2.06
- Weismann, Hans: *See—*
Schupp, Karl; and Weismann, Hans, 3,581,034.
- Weiss, Arthur J., to Continental Can Company, Inc. Molded pulp egg carton. 3,580,479, Cl. 229-44.
- Weiss, Hubert L. Hinge structure for electric power distribution box or the like. 3,580,412, Cl. 220-35.
- Weitkamp, Gunter: *See—*
Bock, Gerhard; Riccius, Rolf; Weitkamp, Gunter; and Wolf, Bernhard, 3,580,531.
- Weitz, Hans-Martin: *See—*
Fuerst, Ernst; and Weitz, Hans-Martin, 3,580,839.
- Welty, Richard O.: *See—*
Reid, Richard K.; and Welty, Richard O., 3,579,728.
- Wenzel, Gunter, to Farbwerke Hoechst Aktiengesellschaft vormals Meister Lucius & Bruning. Welding gear for objects of thermoplastic material. 3,580,789, Cl. 156-497.
- Werkmeister, Johannes; and Scheler, Holger, to Traub, Hermann, Firma. Apparatus for feeding rod stock and the like. 3,580,418, Cl. 221-275.
- Werkzeugmaschinenfabrik Oerlikon-Bührle AG: *See—*
Apotheloz, Robert; Bigler, Hans-Ulrich; and Kessler, Rene, 3,580,174.
- Suter, Xaver, 3,580,529.
- West, Walter H., to Dow Chemical Company, The. Apparatus for variable parison forming. 3,579,733, Cl. 18-14.
- Westcott, Vernon C.; and Williams, Sidney B., to Trans-Sonics, Inc. Temperature compensated liquid quantity gage. 3,580,074, Cl. 73-304.
- Western Electric Company: *See—*
Mandonas, Nicholas J.; and Ryll, Paul A., 3,579,922.
- Western Electric Company, Incorporated: *See—*
Craver, Edward H., 3,579,792.
- Eisenmenger, Irving V., 3,581,108.
- Western Manufacturing, Inc.: *See—*
Ehrlich, Stanley V., 3,580,517.
- Western Union Telegraph Company, The: *See—*
Nord, Hans H., 3,581,120.
- Westinghouse Electric Corporation: *See—*
Arnott, Edward G. F.; and Lewis, Daniel W., 3,581,137.
- Elmy, Richard A., 3,579,851.
- Goldberg, Newton N.; and Ferguson, James L., 3,580,864.
- Goldberg, Newton N., 3,580,865.
- Haft, Harry H.; and Repsher, Robert W., 3,581,139.
- Kemeny, George A.; and Wolf, Charles B., 3,580,977.
- Ropp, Richard C., 3,580,861.
- Simon, Alan J.; Johnson, Joseph E.; and O'Keeffe, Trencé W., 3,580,749.
- Traynor, Edward J., Jr., 3,580,737.
- Weems, Sterling J.; and Mandil, Harry, 3,580,806.
- Westra, Dan P.; and Siewert, John J., to Challenge Machinery Company, The. Cutter. 3,580,123, Cl. 83-380.
- Wetter, Allan E., to Byrne Doors, Inc. Locking means for a vertically movable door. 3,579,910, Cl. 49-322.
- Weyenberg, Lionel E. Housed resistor. 3,581,266, Cl. 338-253.
- WHB-Anbaumobel von Poschinger K.G.: *See—*
Naske, Christoph, 3,580,535.
- Wheatley, William Richard, to RCA Corporation. Optical semiconductor device. 3,581,162, Cl. 317-234.
- Whirlpool Corporation: *See—*
Barnard, Walter C.; and Hodapp, Donald C., 3,580,008.
- Hetland, Thomas E., 3,579,706.
- Whistler Green Engineering Products Limited: *See—*
Whistler, Sidney, 3,579,707.
- Whistler, Sidney, to Whistler Green Engineering Products Limited. Fastening devices for carpets. 3,579,707, Cl. 16-8.
- Whitaker, Earl J.: *See—*
Greenspan, Lawrence E.; and Whitaker, Earl J., 3,581,287.
- Whitaker, Willard H. Bath tub hoist device. 3,579,660, Cl. 4-185.
- White Consolidated Industries, Inc.: *See—*
Snow, Lawrence E., 3,580,009.
- White, Richard B., to Kent-Moore Corporation. Tank system tightness tester. 3,580,055, Cl. 73-49.2
- Whited, Prentiss. Dressing tool method and means. 3,579,923, Cl. 51-209.
- Whitfill, Donald L., to Continental Oil Company. Electrolytic decoloring of fertilizer solutions. 3,580,826, Cl. 204-131.
- Whitney, Donald R., to General Motors Corporation. Wave interference silencing system. 3,580,357, Cl. 181-44.
- Whymark, Arthur F.: *See—*
Starbuck, Leslie; and Whymark, Arthur F., 3,580,392.
- Wichoud, Michel; and Engel, Jean-Pierre. Apparatus for storing and winding discontinuously and reversibly moving tape. 3,580,526, Cl. 242-190.
- Wick, Paul: *See—*
Hoffmann, Wolfgang; and Wick, Paul, 3,579,956.
- Widl, Walter Herbert Ewin: *See—*
Mattsson, Orjan Mats; and Widl, Walter Herbert Ewin, 3,581,075.
- Wiehl, Frederick R.; and Wilson, Edmund B., III, to Singer Company, The. Aluminum pressed metal link for 600 class sewing machines. 3,580,106, Cl. 74-579.
- Wiener Schwachstromwerke Gesellschaft m.b.H.: *See—*
Sacher, Franz, 3,581,252.
- Wilcox, Waverly Hope: *See—*
Satterthwaite, James Glenn; and Wilcox, Waverly Hope, 3,579,915.
- Wilhelm, D. F.; Müller, Peter S.; Bissell, D. L.; and Lambroff, George M., to Owens-Illinois, Inc. Display terminal for computer monitored plant variables. 3,581,289, Cl. 340-172.5
- Wilkinson, Jack E.; and Tahan, Victor G. Pre-tied suture and method of suturing. 3,580,256, Cl. 128-335.5
- Williams, Albert Etheridge; and Linkison, William Simpson, to United Kingdom Atomic Energy Authority. Nuclear reactor fuel element with spaced reductions of diameter. 3,580,809, Cl. 176-76.
- Williams, Charles A.; and Waller, Richard E., to Microdot Inc., mesne. Power tool for thread inserts. 3,579,793, Cl. 29-240.5
- Williams, Keith S.: *See—*
Arvidson, Paul W.; Park, William G.; and Williams, Keith S., 3,580,130.
- Williams, Norman H., to Varian Associates. Microwave applicator employing a broadside radiator in a conductive enclosure. 3,581,038, Cl. 219-10.
- Williams, Sidney B.: *See—*
Westcott, Vernon C.; and Williams, Sidney B., 3,580,074.
- Williamson, William Ian: *See—*
Corry, Alfred Reginald; Guest, Dorothy Joyce; and Williamson, William Ian, 3,580,877.
- Willis, David M., to Logan, Jonathan, Inc. Tensionless liquid treating apparatus and method. 3,579,679, Cl. 8-151.
- Willison, Donald; and Depenti, Kenneth L., to Midland-Ross Corporation. Automatic trainline connector. 3,580,399, Cl. 213-76.
- Willits, Samuel P.; and Mohan, William L., to Spartans Limited. Pitch matching detecting and counting system. 3,581,067, Cl. 235-92.
- Willox, J. Hebdon. Surge-deflecting cable terminator. 3,581,154, Cl. 317-61.5
- Wilson, Alexander Ian, to Hille Engineering Company Limited, The. Rolling mills. 3,580,034, Cl. 72-237.
- Wilson, David W.: *See—*
Shoemaker, William E.; and Wilson, David W., 3,581,198.
- Wilson, Edmund B., III: *See—*
Wiehl, Frederick R.; and Wilson, Edmund B., III, 3,580,106.
- Wilson, Farris H., Jr., to Goodyear Tire & Rubber Company, The. Tetrahydroquinoline/aldehyde reaction process as polymer antiozonants. 3,580,884, Cl. 260-45.8
- Wilson, Henry Allen. Training frame for use in learning how to ride a unicycle or walk on the hands. 3,580,569, Cl. 272-60.
- Wilson, Leslie P.: *See—*
Dobell, Curzon; and Wilson, Leslie P., 3,580,461.
- Wilson, Porter C. Flag football belt device. 3,579,745, Cl. 24-73.
- Wilson, Raymond Michael Christopher, to Lucas, Joseph, (Industries) Limited. Apparatus for testing switching type voltage regulators by counting square wave pulses produced by the regulator. 3,581,205, Cl. 324-158.
- Wilton Company: *See—*
Dunwoody, Duane E., 3,581,222.
- Windmoller & Holscher: *See—*
Richter, Herbert; Stock, David K.; Wech, Robert J.; Stock, David K.; and Wech, Robert J., 3,580,141.
- Wingard, Henry S.: *See—*
De Torre, John; and Wingard, Henry S., 3,581,261.
- Winsor Concepts: *See—*
Guyer, Reynolds W., Jr.; and Kruse, Wilbert A., 3,580,234.
- Winsor, Niels K.: *See—*
Johnson, John L.; Winsor, Niels K.; Dawson, John M.; Sinclair, Rolf M.; and Hosea, Joel C., 3,580,802.
- Winston, Rodney W.; and Witham, Peter M., to Moore Business Forms Inc. Pocket register. 3,580,614, Cl. 282-3.
- Winter, John W.; and Harrison, Guy K., Jr., to Aviation Instrument Manufacturing Corporation, mesne. Attitude indicator. 3,579,847, Cl. 33-204.
- Winthrop-Atkins Co., Inc.: *See—*
Nichols, Gordon E., 3,580,536.
- Wisconsin Tissue Mills: *See—*
Asmuth, James E., 3,580,797.
- Witham, Peter M.: *See—*
Winston, Rodney W.; and Witham, Peter M., 3,580,614.
- Witherington-Perkins, Geoffrey Frank, to Triplex Safety Glass Company Limited. Maintaining sheets of glass in mutually spaced relationship when stacked together for transport or storage. 3,580,119, Cl. 83-23.
- Withers, Harold. Leaf burner attachment for lawn mowers. 3,580,194, Cl. 110-18.
- Witte, Richard F., to Reynolds Metals Company. Latch for reclosable carton and blank therefor. 3,580,482, Cl. 229-51.
- Witthuhn, Johann: *See—*
Pollmeier, Heinz; and Witthuhn, Johann, 3,580,790.
- Wojcik, Thomas J.: *See—*
De Vries, Adrian J.; and Wojcik, Thomas J., 3,581,248.
- Wolf, Bernhard: *See—*
Bock, Gerhard; Riccius, Rolf; Weitkamp, Gunter; and Wolf, Bernhard, 3,580,531.

- Wolf, Cecil R.; and Holland, John P., to Frantz Manufacturing Company. Method of joining sheets of rigid deformable material. 3,579,809, Cl. 29-509.
- Wolf, Charles B.: *See—*
- Kemeny, George A.; and Wolf, Charles B., 3,580,977.
- Wolf, Milton; and Diebold, James L., to American Home Products Corporation. 1,2,3,4-Tetrahydrobenzo[b] [1,6] naphthyridine derivatives. 3,580,915, Cl. 260-286.
- Wolfe, Henry S. Reflecting fishing float. 3,579,893, Cl. 43-17.5
- Wolverine Brass Works: *See—*
- De Vries, Robert W., 3,580,283.
- Wong, Mei Goon: *See—*
- Maure, Douglas R.; and Wong, Mei Goon, 3,581,066.
- Wood, Craig A. Ski-board. 3,579,682, Cl. 9-310.
- Wood, Owen J.: *See—*
- O'Mara, William H.; and Wood, Owen J., 3,579,770.
- Woodard, Gerald F.: *See—*
- Buehrle, William E., Jr.; and Woodard, Gerald F., 3,581,208.
- Woodyard, John R.: *See—*
- Allison, Robert W., Jr.; Brokloff, Robert W.; and Woodyard, John R., 3,580,822.
- Worthy, Clive Reginald: *See—*
- Worthy, Maurice Reginald; and Worthy, Clive Reginald, 3,579,855.
- Worthy, Maurice Reginald; and Worthy, Clive Reginald. Teaching machines. 3,579,855, Cl. 35-8.
- Wrabetz, Voyta E.; and Banister, Ronald A., to Square D Company. Adjustable flexible cable force transmitting assembly. 3,580,102, Cl. 74-501.
- Wrapping Machinery Company, Inc.: *See—*
- Michels, Charles E., 3,579,949.
- Wray, Dennis; and Johnson, Janet M., to Precision Processes (Textiles) Limited. Process for producing shrink-resistant wool by treatment with hypochlorous acid and cationic hydrophilic resinous condensation product. 3,580,701, Cl. 8-127.6
- Wright, Allen C., to Haws Drinking Faucet Company. Push button valve. 3,580,542, Cl. 251-282.
- Wright, Herbert Leslie. Sawing machine. 3,580,305, Cl. 143-37.
- Wright, Roy E.: *See—*
- Murray, William Bruce; and Wright, Roy E., 3,580,934.
- Wyatt, Robert D., to United States of America, Navy, mesne. Counter controlled digital limit detector. 3,581,068, Cl. 235-92.
- Wyrick, Leon M., to Chevron Research Company. Pneumatic system for air motor control. 3,580,538, Cl. 251-29.
- Wyss, Escher, Limited: *See—*
- Ruegg, Ernst, 3,580,393.
- Xerox Corporation: *See—*
- Bhagat, Gopal C., 3,580,670.
- Hansen, Richard C.; Mahler, Charles J.; Soures, Nicholas M.; and Stickney, Thomas L., 3,581,000.
- Lavander, Edward J., 3,580,671.
- Mallory, Donald G.; and Turner, Lyman H., 3,580,565.
- Sheridan, Nicholas K., 3,580,657.
- Yang, Frank Y., 3,580,673.
- Yaegashi, Toshio, to Hitachi, Ltd. Sleeved roll and method of making the same. 3,579,781, Cl. 29-148.4
- Yamaguchi, Takeshi: *See—*
- Kaneno, Saburo; Yamaguchi, Takeshi; and Yoshioka, Shunichi, 3,581,084.
- Yamamoto, Masao: *See—*
- Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, 3,580,820.
- Yamamoto, Masatada. Safety escape bag. 3,580,358, Cl. 182-48.
- Yamamura, Katsumi; Miyasaka, Tsugumitsu; Hayashi, Shinichi; Yamamoto, Masao; and Matsubara, Yukio, to Kabushiki Kaisha Suwa Seikosha, and Nishin Kasai Kabushiki Kaisha. Palladium-nickel alloy plating bath. 3,580,820, Cl. 204-43.
- Yamashita, Akio; and Tuzaki, Takehiro, to Matsushita Electric Industrial Co., Ltd. Solid state oscillator element. 3,581,233, Cl. 331-107.
- Yang, Frank Y., to Xerox Corporation. Cleaning apparatus. 3,580,673, Cl. 355-15.
- Yang, Meiling T., to Ethyl Corporation. Detergent formulations containing tetrahydrofuran 2,3,4,5-tetracarboxylic acid salts as builders. 3,580,852, Cl. 252-135.
- Yashiro, Katsuji; and Naito, Hiroshi, to Otsukakoki Kabushiki Kaisha. Control lever for parking brake systems. 3,580,104, Cl. 74-535.
- Yasutake, Katsuya: *See—*
- Wada, Yoshiyo; Yasutake, Katsuya; and Terao, Yoshikazu, 3,580,446.
- Ye Dock Master, Inc.: *See—*
- Thompson, Kenneth L., 3,580,202.
- Yeo, Roland J.; and Colley, Jean E. Electrical contact breaker mechanisms with improved contact gap adjustment means. 3,581,025, Cl. 200-19.
- Yoder, Robert N.: *See—*
- Perkins, Carroll R.; Shaffstall, Everett L.; Gundersen, James L.; and Yoder, Robert N., 3,581,226.
- Yopp, Robert S.; and Kraft, Melvin G., to Bunker-Ramo Corporation. The Miniature connector. 3,581,272, Cl. 339-252.
- Yoshii, Hiroshi: *See—*
- Yoshimoto, Toshio; Narumiya, Tsuneaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, 3,580,897.
- Yoshiki, Hiroshi: *See—*
- Hoshi, Hideo; Washi, Masao; and Yoshiki, Hiroshi, 3,579,687.
- Yoshimoto, Toshio; Narumiya, Tsuneaki; Kaneko, Seiya; Yoshii, Hiroshi; and Takamatsu, Tetsuya, to Bridgestone Tire Company Limited. Process for producing hydrogenated hydrocarbon polymers. 3,580,897, Cl. 260-85.1
- Yoshioka, Shunichi: *See—*
- Kaneno, Saburo; Yamaguchi, Takeshi; and Yoshioka, Shunichi, 3,581,084.
- Young, Chauncey, to Riegel Paper Corporation. Membrane sealed carton. 3,580,483, Cl. 229-51.
- Young, James Roger, to General Electric Company. Discharge gage for helium leak detector use. 3,580,052, Cl. 73-40.7
- Young, Vernon V.: *See—*
- Hidy, Phil H.; and Young, Vernon V., 3,580,929.
- Youngblood, John O. Pump. 3,580,697, Cl. 417-557.
- Youngman, Derek Henry: *See—*
- Davies, Robert William; Hall, Charles Thomas; Hinchcliffe, Dennis; McCombie, Alan Keith; and Youngman, Derek Henry, 3,579,952.
- Youngstown Sheet and Tube Company: *See—*
- Pryor, Dale H., 3,579,753.
- Youngstown Sheet and Tube Company, The: *See—*
- Waltz, Marion D.; and Drake, Lewis A., 3,580,022.
- Yuen, Melville J. G. Swimming paddles. 3,580,213, Cl. 115-2.3
- Zahn, Wolfgang; Nagel, Erlich; and Langer, Reinhold, to Agfa-Gevaert Aktiengesellschaft. Driving arrangement for single blade shutter for photographic apparatus. 3,580,155, Cl. 95-53.
- Zahnradfabrik Friedrichshafen Aktiengesellschaft: *See—*
- Dach, Hansjorg, 3,580,112.
- Hill, Franz, 3,580,109.
- Zanmarchi, Giulio: *See—*
- Bongers, Piet Frans; and Zanmarchi, Giulio, 3,580,664.
- Zaumseil, Dean R.: *See—*
- Calud, Romeo T.; Hansbrough, David L.; and Zaumseil, Dean R., 3,581,169.
- Zavialoff, Igor P.: *See—*
- Miller, Harold A.; Nider, William K.; and Zavialoff, Igor P., 3,579,718.
- Zayats, Iosif Lvovich; Barabashkin, Vladimir Pavlovich; Matveev, Boris Nikolaevich; and Shevakin, Jury Fedorovich. Method of rolling on a pilger mill. 3,580,036, Cl. 72-249.
- Zbinden, Gerhard: *See—*
- Gruenman, Vsevolod; Hoffer, Max; O'Brien, Jay Philip; Rachlin, Albert Israel; and Zbinden, Gerhard, 3,580,949.
- Zbrojovka, narodni podnik: *See—*
- Pallich, Adolf, 3,579,889.
- Zeigler, Robert O.: *See—*
- Schirm, Helmut T.; and Zeigler, Robert O., 3,580,713.
- Zelikovsky, Zinovy Ieremeevich: *See—*
- Badinter, Efim Yakovlevich; Zelikovsky, Zinovy Ieremeevich; and Lazurevskaya, Irina Georgievna, 3,581,262.
- Zellner, Carl Naehrer: *See—*
- Kennedy, Daniel M., Jr.; and Zellner, Carl Naehrer, 3,580,973.
- Zenith Radio Corporation: *See—*
- De Vries, Adrian J.; and Wojcik, Thomas J., 3,581,248.
- Zerba, Lawrence G.: *See—*
- Fry, William H.; and Zerba, Lawrence G., 3,580,440.
- Zercher, Richard C. Clampless fender mounted bracket. 3,580,441, Cl. 224-42.31
- Zergenyi, Janos; and Habicht, Ernst, to Geigy Chemical Corporation. 5-(2-Methylenecarboxyl)-benzofuran 2-carboxylic acids. 3,580,931, Cl. 260-346.2
- Zhabotinsky, Mark Efremovich: *See—*
- Buzhinsky, Igor Mikhailovich; Zhabotinsky, Mark Efremovich; Rudnitsky, Jury Petrovich; Tsapkin, Vadim Vasilievich; Tsapkina, Irma Vyacheslavovna; and Ellert, Georgy Vladimirovich, 3,580,859.
- Zimmerman, Arie; Luksch, James A.; and Smith, Gerald D. Cable television program capacity enhancement. 3,581,209, Cl. 325-308.
- Zimmerman, John R., to United States of America, Army, mesne. Anti-feed back device. 3,580,131, Cl. 89-34.
- Zink, Stanley C.; and Slane, Joseph J., to Black Clawson Company. The. Roll and anti-friction bearing assembly. 3,580,648, Cl. 308-207.
- Zinser-Textilmaschinen Gesellschaft mit beschränkter Haftung: *See—*
- Fetzer, Gustav; and Freytag, Gerhard, 3,579,973.
- Zipser, Frederick S. Speed measuring device. 3,580,083, Cl. 73-432.
- Zmatlik, Josef: *See—*
- Jisa, Miloslav; Zmatlik, Josef; Mohelnicky, Josef; and Milichovsky, Bohumil, 3,580,295.
- Zofchak, James T.: *See—*
- Maul, John A.; Zofchak, James T.; and Anderson, David D., 3,580,169.
- Zolotarev, Petr Semenovich: *See—*
- Bushuev, Vladimir Pavlovich; Gubin, Georgy Viktorovich; Zolotarev, Petr Semenovich; Sorokin, Vladimir Andreevich; Palamarchuk, Vladimir Ivanovich; and Dmitrenko, Viktor Makarovich, 3,580,554.
- Zotter, John F., to Textron Inc. Bearing seal construction. 3,580,590, Cl. 277-277.
- Zrak "P" Produkcije Precizne mehanike i Optike: *See—*
- Sarzynski, Stefan, 3,580,117.
- Zubler, Edward G., to General Electric Company. Getter composition for electric lamps and similar devices. 3,580,856, Cl. 252-181.6
- Zuccolo, Giorgio. Trellis unit for making of beams. 3,579,759, Cl. 25-131.6

- Zueger, Karl J.; and Decker, Eugene J. Apparatus for inserting stick-like objects into comestible articles. 3,580,456, Cl. 227-100.
- Zumstein, Fred R., to King-Seeley Thermos Co. Method of making double-walled plastic articles. 3,580,762, Cl. 156-73.
- Zuppiger, Paul: *See—*
- Bouladon, Gabriel; and Zuppiger, Paul, 3,580,182.
- Zytron Industries, Inc.: *See—*
- Quinn, Frederic R., 3,580,500.
- Zysman, Milton, to Convex Limited. Handle attaching apparatus and method. 3,579,773, Cl. 29-91.
- Zysset, Karl. Hand squeezer for fruits and vegetables. 3,580,168, Cl. 100-234.

LIST OF REISSUE PATENTEES

TO WHOM
MAY 25, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Gingery, Wayne P., to Super-Drive Products, Inc. Dual splined shaft assembly for a clutch. Re. 27,126, 5-25-71, Cl. 240—46.11.
192—70.13.

LIST OF DESIGN PATENTEES

Adams, Gerald M., and J. H. Frakes, Jr., to SCM Corp. Combined data keyboard entry and display unit. 220,824, 5-25-71, Cl. D26—5.
Althaus, Richard K., and B. B. Gluestein. Television receiver escutcheon. 220,808, 5-25-71, Cl. D56—4.
Barden Corp., The: See—
Hedges, James E. 220,802.
Benson, Lee. Combined bottle and stand therefor. 220,792, 5-25-71, Cl. D9—13.
Bluestein, Bernard B.: See—
Althaus, Richard K., and Bluestein. 220,808.
Braun Aktiengesellschaft: See—
Rams, Dieter. 220,801.
Carroll, Richard W., to U.S. Industries, Inc. Diffuser for a lighting fixture. 220,806, 5-25-71, Cl. D48—16.
Castedello, William, to The Kalart Co., Inc. Cassette for a sound slide projector. 220,818, 5-25-71, Cl. D26—14.
Consolidated Oil Co.: See—
Evins, Danny W. 220,804.
De Wan, Thomas E. Jacket. 220,822, 5-25-71, Cl. D2—189.
Dymo Industries, Inc.: See—
Penaluna, William A., and Yee. 220,797.
Edwards, Douglas F.: See—
Hedges, James, and Edwards. 220,802.
Epoch Co., Ltd.: See—
Matsumoto, Teruo. 220,796.
Evins, Danny W., to Consolidated Oil Co., Inc. Building. 220,804, 5-25-71, Cl. D13—1.
Frakes, James H., Jr.: See—
Adams, Gerald M., and Frakes. 220,824.
Harrison, Jeffrey F., to E. J. Riley Ltd. Billiard table or similar article. 220,812, 5-25-71, Cl. D34—3.
Hartsell, Hal C., Jr., and D. D. Tompkins. Support for a gasoline dispenser or the like. 220,827, 5-25-71, Cl. D52—2.
Hedges, James, and D. F. Edwards, to The Barden Corp. Work bench. 220,802, 5-25-71, Cl. D33—14.
Heller, Walter E., and Co.: See—
Sundberg, Carl W. 220,807.
Honeywell Inc.: See—
Quinn, Peter T. 220,793.
Hoover Co., The: See—
Krammes, Don C. 220,809.
Howe, Robert L., and N. C. Howe. Contoured pillow. 220,823, 5-25-71, Cl. D83—1.
Ivac Corp.: See—
Sato, Stephens N. 220,817.
Jerabek, Charles, to Vernitron Corp. Telephone coupler. 220,811, 5-25-71, Cl. D26—14.
Kalart Co., Inc.: See—
Castedello, William. 220,818.
Katz, Maurice D. Portable radio. 220,821, 5-25-71, Cl. D56—4.
Kohner Bros., Inc.: See—
Kohner, Frank, and Stubbmann. 220,825.
Kohner, Frank, and A. Stubbmann, to Kohner Bros., Inc. Game board. 220,825, 5-25-71, Cl. D34—5.
Krammes, Don C., to The Hoover Co. Toaster. 220,809, 5-25-71, Cl. D81—10.
Krogh, Johannes C. Ice tray. 220,800, 5-25-71, Cl. D6—3.
Laurita, Joseph N. Luggage handle. 220,819, 5-25-71, Cl. D8—154.
Leonard, Jacques. Bottle. 220,798, 5-25-71, Cl. D9—71.
Le Roue, Lloyd J. Measuring tape. 220,810, 5-25-71, Cl. D52—1.
Litton Business Systems, Inc.: See—
Otto, Carl L. 220,813.
Morelli, Joseph L. 220,815.
Misumoto, Teruo, to Epoch Co., Ltd. Educational device. 220,796, 5-25-71, Cl. D25—1.
Morelli, Joseph L., to Litton Business Systems, Inc. Type-writer. 220,816, 5-25-71, Cl. D64—11.
Otto, Carl L., to Litton Business Systems, Inc. Adding machine or the like. 220,813, 5-25-71, Cl. D64—11.
Otto, Carl L., to Litton Business Systems, Inc. Adding machine or the like. 220,814, 5-25-71, Cl. D64—11.
Penaluna, William A., and M. Yee, to Dymo Industries, Inc. 220,797, 5-25-71, Cl. D64—10.
Quinn, Peter T., to Honeywell, Inc. Film strip adapter for photographic projector. 220,793, 5-25-71, Cl. D61—1.
Rams, Dieter, to Braun Aktiengesellschaft. Flashlight. 220,801, 5-25-71, Cl. D48—24.
Riley, E. J., Ltd.: See—
Harrison, Jeffrey F. 220,812.
Rowry, Eligah R. Radio receiving set. 220,794, 5-25-71, Cl. D56—4.
Ryden, John V., to Schering Corp. Inhalant dispenser. 220,805, 5-25-71, Cl. D83—1.
SCM Corp.: See—
Adams, Gerald M., and Frakes. 220,824.
Sato, Stephens N., to Ivac Corp. Reflex measurement apparatus. 220,817, 5-25-71, Cl. R83—1.
Seefuth, Uwe C. Rocket toy. 220,820, 5-25-71, Cl. D34—15.
Scantlin Electronics, Inc.: See—
Segall, Ronald. 220,803.
Schering Corp.: See—
Ryden, John V. 220,805.
Segall, Ronald, to Scantlin Electronics, Inc. Sales terminal. 220,803, 5-25-71, Cl. D26—5.
Sklaroff, William B., to Litton Business Systems, Inc. Type-writer. 220,815, 5-25-71, Cl. D64—11.
Stangl, Johann M., to Stangl Pottery. Plate or similar article. 220,799, 5-25-71, Cl. D44—15.
Stangl Pottery: See—
Stangl, Johann M. 220,799.
Slater Electric, Inc.: See—
Slater, Herbert A. 220,795.
Slater, Herbert A., to Slater Electric, Inc. Single electrical outlet. 220,795, 5-25-71, Cl. D26—1.
Stubbmann, Albert: See—
Kohner, Frank, and Stubbmann. 220,825.
Sundberg, Carl W., to Walter E. Heller & Co. Remote control unit for an automatic phonograph. 220,807, 5-25-71, Cl. D26—13.
Tompkins, David D.: See—
Hartsell, Hal C., Jr., and Tompkins. 220,827.
U.S. Industries, Inc.: See—
Carroll, Richard W. 220,806.
Vaughn, Raymond R. Hand iron safety cradle. 220,826, 5-25-71, Cl. D49—6.
Vernitron Corp.: See—
Jerabek, Charles. 220,811.
Yee, Melvin: See—
Penaluna, William A., and Yee. 220,797.

PI 46

CLASSIFICATION OF PATENTS

ISSUED MAY 25, 1971

NOTE.—First number, class; second number, subclass; third number, patent number

2- 3 : 3,579,637	18- 5 : 3,579,725	29- 527.1 : 3,579,810	46- 7 : 3,579,898	60- 53 : 3,579,988	73-194 : 3,580,071
8 : 3,579,638	568 : 3,579,812	568 : 3,579,812	39 : 3,579,899	54.5 : 3,579,989	205 : 3,580,072
117 : 3,579,639	3,579,727	570 : 3,579,811	93 : 3,579,900	73 : 3,579,990	233 : 3,580,073
209 : 3,579,640	12 : 3,579,728	578 : 3,579,814	103 : 3,579,901	232 : 3,579,991	304 : 3,580,074
325 : 3,579,641	3,579,729	580 : 3,579,815	149 : 3,579,902	239 : 3,579,992	339 : 3,580,075
3- 1 : 3,579,642	13 : 3,579,731	583 : 3,579,816	180 : 3,579,903	262 : 3,579,993	358 : 3,580,076
3,579,643	14 : 3,579,732	588 : 3,579,817	216 : 3,579,904	61- 1 : 3,579,994	343 : 3,580,077
3,579,645	15 : 3,579,733	596 : 3,579,818	244 : 3,579,905	13 : 3,579,995	344 : 3,580,078
4- 1 : 3,579,647	3,579,734	610 : 3,579,819	47- 17 : 3,579,907	66 : 3,579,996	358 : 3,580,079
10 : 3,579,648	17 : 3,579,736	627 : 3,579,821	45 : 3,579,908	62- 55.5 : 3,579,997	384 : 3,580,080
52 : 3,579,649	19 : 3,579,737	630 : 3,579,822	49- 252 : 3,579,909	56 : 3,579,999	399 : 3,580,081
72 : 3,579,650	26 : 3,579,738	3,579,823	322 : 3,579,910	77 : 3,580,000	406 : 3,580,082
78 : 3,579,651	30 : 3,579,739	3,579,824	394 : 3,579,934	101 : 3,580,001	421 : 3,580,084
110 : 3,579,652	3,579,740	90.7 : 3,579,825	51- 3 : 3,579,911	115 : 3,580,003	432 : 3,580,083
3,579,653	3,579,741	93 : 3,579,826	59 : 3,579,912	148 : 3,580,004	496 : 3,580,085
113 : 3,579,654	3,579,742	144 : 3,579,827	95 : 3,579,913	148 : 3,580,004	506 : 3,580,086
116 : 3,579,655	36 : 3,579,743	251 : 3,579,828	101 : 3,579,914	3,580,013	515 : 3,580,087
159 : 3,579,656	19- 97.5 : 3,579,744	32- 10 : 3,579,829	120 : 3,579,915	149 : 3,580,005	74- 1 : 3,580,088
172.12 : 3,579,657	23- 2 : 3,580,702	3,579,830	131 : 3,579,916	196 : 3,580,006	49 : 3,580,089
19 : 3,579,665	122 : 3,580,703	3,579,831	148 : 3,579,918	345 : 3,580,007	96 : 3,580,090
173 : 3,579,666	230 : 3,580,704	17 : 3,579,832	163 : 3,579,919	347 : 3,580,008	107 : 3,580,091
180 : 3,579,669	341 : 3,580,705	27 : 3,579,833	164 : 3,579,920	353 : 3,580,009	230.3 : 3,580,093
181 : 3,579,667	24- 73 : 3,579,745	43 : 3,579,834	3,579,921	64- 9 : 3,580,010	242.11 : 3,580,094
185 : 3,579,660	131 : 3,579,746	58 : 3,579,835	165 : 3,579,922	27 : 3,580,011	409 : 3,580,095
187 : 3,579,661	201 : 3,579,747	33- 1 : 3,579,836	209 : 3,579,923	65- 30 : 3,580,709	411.5 : 3,580,096
206 : 3,579,662	205.1 : 3,579,748	3 : 3,579,837	262 : 3,579,926	144 : 3,580,710	421 : 3,580,097
230 : 3,579,663	14 : 3,579,749	19 : 3,579,838	281 : 3,579,927	169 : 3,580,711	459 : 3,580,098
245 : 3,579,669	230 : 3,579,750	46 : 3,579,839	288 : 3,579,924	307 : 3,580,712	469 : 3,580,099
250 : 3,579,664	252 : 3,579,751	50 : 3,579,840	307 : 3,580,708	330 : 3,580,714	482 : 3,580,100
252 : 3,579,670	263 : 3,579,752	75 : 3,579,841	315 : 3,579,933	66- 55 : 3,580,012	493 : 3,580,101
5- 62 : 3,579,671	3,579,753	133 : 3,579,842	330 : 3,579,925	68- 23.1 : 3,580,014	501 : 3,580,102
81 : 3,579,672	279 : 3,579,754	147 : 3,579,843	356 : 3,579,928	53 : 3,580,015	535 : 3,580,103
94 : 3,579,673	25- 1 : 3,579,755	180 : 3,579,844	52- 1 : 3,579,929	70- 68 : 3,580,016	535 : 3,580,104
343 : 3,579,675	30 : 3,579,756	203.13 : 3,579,845	24 : 3,579,930	81 : 3,580,017	568 : 3,580,105
6- 2 : 3,579,676	45 : 3,579,757	204 : 3,579,846	83 : 3,579,932	71- 28 : 3,580,715	579 : 3,580,106
7- 1 : 3,579,677	118 : 3,579,758	3,579,847	126 : 3,579,935	76 : 3,580,716	687 : 3,580,107
14.1 : 3,579,678	131.6 : 3,579,759	34- 15 : 3,579,848	297 : 3,579,936	72- 5 : 3,580,021	711 : 3,580,108
8- 127.6 : 3,580,701	28- 1.7 : 3,579,760	48 : 3,579,849	309 : 3,579,937	8 : 3,580,022	763 : 3,580,109
151 : 3,579,679	19 : 3,579,761	57 : 3,579,850	365 : 3,579,938	12 : 3,580,018	812 : 3,580,110
9- 1 : 3,579,680	71.3 : 3,579,762	82 : 3,579,851	384 : 3,579,941	22 : 3,580,023	817 : 3,580,111
310 : 3,579,681	72.11 : 3,579,764	167 : 3,579,852	397 : 3,579,939	47 : 3,580,019	868 : 3,580,112
340 : 3,579,682	16 : 3,579,765	218 : 3,579,853	542 : 3,579,940	58 : 3,580,020	75- 37 : 3,580,717
10- 10 : 3,579,684	2 : 3,579,766	35- 8 : 3,579,854	615 : 3,579,942	77 : 3,580,024	60 : 3,580,718
12 : 3,579,685	74 : 3,579,766	3,579,855	656 : 3,579,943	84 : 3,580,025	81- 9.5 : 3,580,114
87 : 3,579,686	29- 1.3 : 3,579,767	3,579,856	741 : 3,579,931	96 : 3,580,026	165 : 3,580,115
129 : 3,579,687	25.13 : 3,579,768	3,579,862	53- 3 : 3,579,944	98 : 3,580,027	302 : 3,580,116
134 : 3,579,688	42 : 3,579,769	9 : 3,579,857	21 : 3,579,946	3,580,028	82- 2 : 3,580,129
140 : 3,579,689	33 : 3,579,771	10.2 : 3,580,978	23 : 3,579,947	108 : 3,580,029	36 : 3,580,117
12- 8.3 : 3,579,692	91 : 3,579,773	17 : 3,579,858	29 : 3,579,948	130 : 3,580,030	46 : 3,580,118
12.4 : 3,579,690	1 : 3,579,774	22 : 3,579,865	37 : 3,579,950	186 : 3,580,031	83- 23 : 3,580,119
14.5 : 3,579,693	96 : 3,579,775	27 : 3,579,859	55 : 3,579,952	199 : 3,580,032	107 : 3,580,121
17 : 3,579,694	105 : 3,579,777	31 : 3,579,860	59 : 3,579,953	205 : 3,580,033	108 : 3,580,122
127 : 3,579,695	110 : 3,579,778	32 : 3,579,866	76 : 3,579,954	237 : 3,580,034	380 : 3,580,123
13- 6 : 3,580,976	113 : 3,579,779	38 : 3,579,867	112 : 3,579,945	243 : 3,580,035	84- 1.1 : 3,580,979
18 : 3,580,977	148.4 : 3,579,780	48 : 3,579,861	138 : 3,579,955	249 : 3,580,036	22 : 3,580,980
14- 71 : 3,579,696	159 : 3,579,783	3,579,868	159 : 3,579,956	255 : 3,580,037	313 : 3,580,124
15- 3.1 : 3,579,697	196.3 : 3,580,706	3,579,870	183 : 3,579,958	264 : 3,580,038	377 : 3,580,125
21 : 3,579,700	200 : 3,579,784	3,579,875	184 : 3,579,960	324 : 3,580,040	464 : 3,580,126
79 : 3,579,702	3,579,785	3,579,876	190 : 3,579,957	336 : 3,580,041	86- 24 : 3,580,127
215 : 3,579,704	203 : 3,579,787	3,579,877	260 : 3,579,959	339 : 3,580,042	31 : 3,580,128
250.1 : 3,579,698	3,579,788	40- 1.5 : 3,579,881	390 : 3,579,961	402 : 3,580,043	89- 31 : 3,580,130
260 : 3,579,705	3,579,790	10 : 3,579,878	5 : 3,580,046	466 : 3,580,044	34 : 3,580,131
327 : 3,579,706	205 : 3,579,788	28 : 3,579,879	17 : 3,580,047	73- 3 : 3,580,045	130 : 3,580,132
361 : 3,579,699	3,579,791	33 : 3,579,880	35 : 3,580,048	5 : 3,580,046	90- 11 : 3,580,133
16- 8 : 3,579,707	208 : 3,579,792	107 : 3,579,882	35 : 3,580,049	17 : 3,580,047	13 : 3,580,134
52 : 3,579,708	237 : 3,579,794	110 : 3,579,884	56- 7 : 3,579,965	35 : 3,580,048	64 : 3,580,136
65 : 3,579,709	240.5 : 3,579,793	145 : 3,579,885	202 : 3,579,966	37 : 3,580,050	91- 50 : 3,580,137
93 : 3,579,710	252 : 3,579,795	152 : 3,579,886	313 : 3,579,967	40 : 3,580,051	277 : 3,580,138
114 : 3,579,711	263 : 3,579,796	1 : 3,579,887	327 : 3,579,968	7 : 3,580,052	411 : 3,580,139
141 : 3,579,712	267 : 3,579,797	356 : 3,579,888	328 : 3,579,969	41 : 3,580,053	92- 25 : 3,580,140
17- 1 : 3,579,713	401 : 3,579,798	42- 1 : 3,579,889	330 : 3,579,970	49.2 : 3,580,054	93- 8 : 3,580,141
39 : 3,579,715	416 : 3,579,799	42 : 3,579,891	370 : 3,579,972	67.2 : 3,580,056	53 : 3,580,143
45 : 3,579,716	423 : 3,579,800	84 : 3,580,113	50 : 3,579,976	6 : 3,580,057	93 : 3,580,145
18- 1 : 3,579,717	427 : 3,579,801	43- 6 : 3,579,894	112 : 3,579,977	7 : 3,580,058	94 : 3,580,146
3,579,718	432.2 : 3,579,802	12 : 3,579,890	60- 19 : 3,579,978	71.5 : 3,580,059	94- 50 : 3,580,147
2.5 : 3,579,720	434 : 3,579,803	17.5 : 3,579,893	24 : 3,579,980	88 : 3,580,061	95- 10 : 3,580,148
7 : 3,579,721	447 : 3,579,805	6 : 3,579,895	29 : 3,579,981	105 : 3,580,062	11 : 3,580,149
4 : 3,579,722	463 : 3,579,806	19 : 3,579,896	36 : 3,579,982	118 : 3,580,063	12.20 : 3,580,151
3,579,723	471.3 : 3,579,807	35 : 3,579,897	39.71 : 3,579,983	146 : 3,580,064	31 : 3,580,152

LIST OF REISSUE PATENTEES

TO WHOM
MAY 25, 1971

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Gingery, Wayne P., to Super-Drive Products, Inc. Dual splined shaft assembly for a clutch. Re. 27,126, 5-25-71, Cl. 20—192—70.13.

LIST OF DESIGN PATENTEES

Adams, Gerald M., and J. H. Frakes, Jr., to SCM Corp. Combined data keyboard entry and display unit. 220,824, 5-25-71, Cl. D26—5.
Althaus, Richard K., and B. B. Gluestein. Television receiver escutcheon. 220,808, 5-25-71, Cl. D56—4.
Barden Corp., The: See—
Hedges, James E. 220,802.
Benson, Lee. Combined bottle and stand therefor. 220,792, 5-25-71, Cl. D9—18.
Bluestein, Bernard B.: See—
Althaus, Richard K., and Bluestein. 220,808.
Braun Aktiengesellschaft: See—
Rams, Dieter. 220,801.
Carroll, Richard W., to U.S. Industries, Inc. Diffuser for a lighting fixture. 220,806, 5-25-71, Cl. D48—16.
Castedello, William, to The Kalart Co., Inc. Cassette for a sound slide projector. 220,818, 5-25-71, Cl. D26—14.
Consolidated Oil Co.: See—
Evins, Danny W. 220,804.
De Wan, Thomas E. Jacket. 220,822, 5-25-71, Cl. D2—189.
Dymo Industries, Inc.: See—
Penaluna, William A., and Yee. 220,797.
Edwards, Douglas F.: See—
Hedges, James, and Edwards. 220,802.
Epoch Co., Ltd.: See—
Matsumoto, Teruo. 220,796.
Evins, Danny W., to Consolidated Oil Co., Inc. Building. 220,804, 5-25-71, Cl. D13—1.
Frakes, James H., Jr.: See—
Adams, Gerald M., and Frakes. 220,824.
Harrison, Jeffrey F., to E. J. Riley Ltd. Billiard table or similar article. 220,812, 5-25-71, Cl. D34—3.
Hartsell, Hal C., Jr., and D. D. Tompkins. Support for a gasoline dispenser or the like. 220,827, 5-25-71, Cl. D52—2.
Hedges, James, and D. F. Edwards, to The Barden Corp. Work bench. 220,802, 5-25-71, Cl. D33—14.
Heller, Walter E., and Co.: See—
Sundberg, Carl W. 220,807.
Honeywell Inc.: See—
Quinn, Peter T. 220,793.
Hoover Co., The: See—
Krammes, Don C. 220,809.
Howe, Robert L., and N. C. Howe. Contoured pillow. 220,823, 5-25-71, Cl. D83—1.
Ivac Corp.: See—
Sato, Stephens N. 220,817.
Jerabek, Charles, to Vernitron Corp. Telephone coupler. 220,811, 5-25-71, Cl. D26—14.
Kalart Co., Inc.: See—
Castedello, William. 220,818.
Katz, Maurice D. Portable radio. 220,821, 5-25-71, Cl. D56—4.
Kohner Bros., Inc.: See—
Kohner, Frank, and Stubbmann. 220,825.
Kohner, Frank, and A. Stubbmann, to Kohner Bros., Inc. Game board. 220,825, 5-25-71, Cl. D34—5.
Krammes, Don C., to The Hoover Co. Toaster. 220,809, 5-25-71, Cl. D81—10.
Krogh, Johannes C. Ice tray. 220,800, 5-25-71, Cl. D6—3.
Laurita, Joseph N. Luggage handle. 220,819, 5-25-71, Cl. D8—154.
Leonard, Jacques. Bottle. 220,798, 5-25-71, Cl. D9—71.
Le Roue, Lloyd J. Magnetic measuring tape. 220,810, 5-25-71, Cl. D52—1.

PI 46

CLASSIFICATION OF PATENTS

ISSUED MAY 25, 1971

NOTE.—First number, class; second number, subclass; third number, patent number

2- 3 : 3,579,637	18- 5 : 3,579,725	29- 527.1 : 3,579,810	46- 7 : 3,579,898	60- 53 : 3,579,988	73- 194 : 3,580,071
8 : 3,579,638	3,579,726	568 : 3,579,812	39 : 3,579,899	54.5 : 3,579,989	205 : 3,580,092
117 : 3,579,639	3,579,727	570 : 3,579,811	93 : 3,579,900	73 : 3,579,990	233 : 3,580,072
209 : 3,579,640	12 : 3,579,728	3,579,813	103 : 3,579,901	232 : 3,579,991	233 : 3,580,073
325 : 3,579,641	3,579,729	578 : 3,579,814	149 : 3,579,902	239 : 3,579,992	304 : 3,580,074
3- 1 : 3,579,642	3,579,730	580 : 3,579,815	180 : 3,579,903	262 : 3,579,993	339 : 3,580,075
3,579,643	13 : 3,579,731	583 : 3,579,816	216 : 3,579,904	61- 1 : 3,579,994	3,580,076
3,579,644	14 : 3,579,732	588 : 3,579,817	244 : 3,579,905	13 : 3,579,995	343 : 3,580,077
3,579,645	3,579,733	596 : 3,579,818	3,579,906	66 : 3,579,996	344 : 3,580,078
4- 1 : 3,579,647	15 : 3,579,734	610 : 3,579,819	47- 17 : 3,579,907	62- 55.5 : 3,579,997	358 : 3,580,079
10 : 3,579,646	3,579,735	627 : 3,579,821	45 : 3,579,908	56 : 3,579,999	384 : 3,580,080
52 : 3,579,648	17 : 3,579,736	630 : 3,579,822	49- 252 : 3,579,909	77 : 3,580,000	399 : 3,580,081
56 : 3,579,649	19 : 3,579,737	3,579,823	322 : 3,579,910	101 : 3,580,001	421 : 3,580,084
72 : 3,579,650	26 : 3,579,738	3,579,824	394 : 3,579,934	115 : 3,580,002	432 : 3,580,083
78 : 3,579,651	30 : 3,579,739	90.7 : 3,579,825	51- 3 : 3,579,911	148 : 3,580,003	496 : 3,580,085
110 : 3,579,652	3,579,740	93 : 3,579,826	59 : 3,579,912	115 : 3,580,004	506 : 3,580,086
113 : 3,579,654	3,579,741	144 : 3,579,827	95 : 3,579,913	148 : 3,580,005	515 : 3,580,087
116 : 3,579,655	3,579,742	251 : 3,579,828	101 : 3,579,914	149 : 3,580,015	74- 1 : 3,580,088
159 : 3,579,656	36 : 3,579,743	32- 10 : 3,579,829	120 : 3,579,915	196 : 3,580,006	49 : 3,580,089
172.12 : 3,579,657	19- 97.5 : 3,579,744	3,579,830	131 : 3,579,916	345 : 3,580,007	96 : 3,580,090
19 : 3,579,665	23- 2 : 3,580,702	3,579,831	148 : 3,579,918	347 : 3,580,008	107 : 3,580,091
173 : 3,579,666	122 : 3,580,703	3,579,832	163 : 3,579,919	353 : 3,580,009	230.3 : 3,580,093
180 : 3,579,667	230 : 3,580,704	3,579,833	164 : 3,579,920	37 : 3,580,010	242.11 : 3,580,094
181 : 3,579,668	341 : 3,580,705	27 : 3,579,834	165 : 3,579,922	64- 9 : 3,580,011	409 : 3,580,095
185 : 3,579,669	24- 73 : 3,579,745	43 : 3,579,835	209 : 3,579,923	65- 30 : 3,580,012	411.5 : 3,580,096
187 : 3,579,670	131 : 3,579,746	58 : 3,579,836	281 : 3,579,927	144 : 3,580,013	421 : 3,580,097
206 : 3,579,671	201 : 3,579,747	33- 1 : 3,579,837	288 : 3,579,928	169 : 3,580,014	459 : 3,580,098
230 : 3,579,672	205.1 : 3,579,748	3 : 3,579,838	307 : 3,580,029	307 : 3,580,015	469 : 3,580,099
245 : 3,579,673	14 : 3,579,749	19 : 3,579,839	307 : 3,580,030	330 : 3,580,016	482 : 3,580,100
250 : 3,579,674	252 : 3,579,750	46 : 3,579,840	315 : 3,579,933	66- 55 : 3,580,017	493 : 3,580,101
252 : 3,579,675	263 : 3,579,751	50 : 3,579,841	330 : 3,579,934	68- 23.1 : 3,580,018	501 : 3,580,102
5- 62 : 3,579,676	279 : 3,579,752	133 : 3,579,842	356 : 3,579,935	53 : 3,580,019	535 : 3,580,103
81 : 3,579,677	25- 1 : 3,579,753	147 : 3,579,843	52- 1 : 3,579,936	81 : 3,580,020	568 : 3,580,104
94 : 3,579,678	30 : 3,579,754	180 : 3,579,844	24 : 3,579,937	71- 28 : 3,580,021	579 : 3,580,105
343 : 3,579,679	45 : 3,579,755	203.13 : 3,579,845	83 : 3,579,938	76 : 3,580,022	687 : 3,580,106
6- 2 : 3,579,680	118 : 3,579,756	204 : 3,579,846	126 : 3,579,939	72- 5 : 3,580,023	711 : 3,580,107
7- 1 : 3,579,681	131.6 : 3,579,757	34- 15 : 3,579,847	297 : 3,579,940	8 : 3,580,024	763 : 3,580,108
14.1 : 3,579,682	28- 1.7 : 3,579,758	48 : 3,579,848	309 : 3,579,941	12 : 3,580,025	812 : 3,580,109
8- 127.6 : 3,580,701	19 : 3,579,759	57 : 3,579,849	365 : 3,579,942	22 : 3,580,026	817 : 3,580,110
151 : 3,579,683	71.3 : 3,579,760	82 : 3,579,850	384 : 3,579,943	47 : 3,580,027	868 : 3,580,111
9- 1 : 3,579,684	72.11 : 3,579,761	167 : 3,579,851	397 : 3,579,944	58 : 3,580,028	875 : 3,580,112
310 : 3,579,685	16 : 3,579,762	218 : 3,579,852	542 : 3,579,945	77 : 3,580,029	886 : 3,580,113
340 : 3,579,686	2 : 3,579,763	35- 8 : 3,579,853	615 : 3,579,946	84 : 3,580,030	897 : 3,580,114
10- 10 : 3,579,687	74 : 3,579,764	3,579,854	656 : 3,579,947	96 : 3,580,031	915 : 3,580,115
12 : 3,579,688	29- 1.3 : 3,579,765	3,579,855	741 : 3,579,948	98 : 3,580,032	932 : 3,580,116
87 : 3,579,689	42 : 3,579,766	3,579,856	53- 3 : 3,579,949	108 : 3,580,033	949 : 3,580,117
129 : 3,579,690	33 : 3,579,767	3,579,857	21 : 3,579,950	130 : 3,580,034	966 : 3,580,118
134 : 3,579,691	33 : 3,579,768	3,579,858	23 : 3,579,951	186 : 3,580,035	983 : 3,580,119
140 : 3,579,692	42 : 3,579,769	3,579,859	29 : 3,579,952	199 : 3,580,036	998 : 3,580,120
12- 8.3 : 3,579,693	33 : 3,579,770	3,579,860	33 : 3,579,953	205 : 3,580,037	107 : 3,580,121
12.4 : 3,579,694	33 : 3,579,771	3,579,861	55 : 3,579,954	237 : 3,580,038	108 : 3,580,122
14.5 : 3,579,695	33 : 3,579,772	3,579,862	59 : 3,579,955	243 : 3,580,039	130 : 3,580,123
17 : 3,579,696	91 : 3,579,773	3,579,863	76 : 3,579,956	249 : 3,580,040	84- 1.1 : 3,580,124
127 : 3,579,697	96 : 3,579,774	3,579,864	112 : 3,579,957	255 : 3,580,041	22 : 3,580,125
17 : 3,579,698	105 : 3,579,775	3,579,865	138 : 3,579,958	264 : 3,580,042	313 : 3,580,126
113 : 3,579,699	110 : 3,579,776	3,579,866	159 : 3,579,959	316 : 3,580,043	377 : 3,580,127
127 : 3,579,700	113 : 3,579,777	3,579,867	183 : 3,579,960	324 : 3,580,044	464 : 3,580,128
13- 6 : 3,580,976	148.4 : 3,579,778	3,579,868	190 : 3,579,961	336 : 3,580,045	86- 24 : 3,580,129
18 : 3,580,977	159 : 3,579,779	3,579,869	260 : 3,579,962	339 : 3,580,046	31 : 3,580,130
14- 71 : 3,579,696	196.3 : 3,580,706	3,579,870	390 : 3,579,963	402 : 3,580,047	89- 31 : 3,580,131
15- 3.1 : 3,579,697	200 : 3,579,784	3,579,871	54- 24 : 3,579,964	466 : 3,580,048	34 : 3,580,132
21 : 3,579,700	79 : 3,579,785	3,579,872	56- 7 : 3,579,965	5 : 3,580,049	130 : 3,580,133
3,579,701	203 : 3,579,786	3,579,873	38- 2 : 3,579,966	17 : 3,580,050	90- 11 : 3,580,134
215 : 3,579,702	203 : 3,579,787	3,579,874	12 : 3,579,967	35 : 3,580,051	13 : 3,580,135
250.1 : 3,579,698	205 : 3,579,788	3,579,875	40- 1.5 : 3,579,968	202 : 3,579,968	64 : 3,580,136
260 : 3,579,705	3,579,789	3,579,876	10 : 3,579,969	313 : 3,579,969	91- 50 : 3,580,137
327 : 3,579,706	208 : 3,579,792	3,579,877	28 : 3,579,970	327 : 3,579,970	277 : 3,580,138
361 : 3,579,699	237 : 3,579,793	3,579,878	33 : 3,579,971	328 : 3,579,971	411 : 3,580,139
16- 8 : 3,579,707	240.5 : 3,579,794	3,579,879	107 : 3,579,972	330 : 3,579,972	92- 25 : 3,580,140
52 : 3,579,708	252 : 3,579,795	3,579,880	110 : 3,579,973	370 : 3,579,973	93- 8 : 3,580,141
65 : 3,579,709	263 : 3,579,796	3,579,881	145 : 3,579,974	370 : 3,579,974	33 : 3,580,142
93 : 3,579,710	267 : 3,579,797	3,579,882	152 : 3,579,975	67.2 : 3,580,056	53 : 3,580,143
114 : 3,579,711	401 : 3,579,798	3,579,883	356 : 3,579,976	6 : 3,580,057	3,580,144
141 : 3,579,712	416 : 3,579,799	3,579,884	42- 1 : 3,579,977	7 : 3,580,058	93 : 3,580,145
17- 1 : 3,579,713	423 : 3,579,800	3,579,885	42 : 3,579,978	112 : 3,579,978	94 : 3,580,146
11 : 3,579,714	427 : 3,579,801	3,579,886	43- 6 : 3,579,979	88 : 3,580,061	94- 50 : 3,580,147
39 : 3,579,715	432.2 : 3,579,802	3,579,887	17.5 : 3,579,980	105 : 3,580,062	95- 10 : 3,580,148
45 : 3,579,716	434 : 3,579,803	3,579,888	29 : 3,579,981	118 : 3,580,063	12.20 : 3,580,149
18- 1 : 3,579,717	447 : 3,579,804	3,579,889	36 : 3,579,982	146 : 3,580,064	5 : 3,580,150
3,579,718	463 : 3,579,805	3,579,890	39.71 : 3,579,983	150 : 3,580,065	31 : 3,580,151
2.5 : 3,579,720	471.3 : 3,579,806	3,579,891	51 : 3,579,984	159 : 3,580,066	36 : 3,580,152
7 : 3,579,721	497.5 : 3,579,807	3,579,892	52 : 3,579,985	162 : 3,580,067	42 : 3,580,153
4 : 3,579,722	509 : 3,579,808	3,579,893	44- 51 : 3,580,707	180 : 3,580,068	53 : 3,580,154
3,579,723	3,579,724	3,579,894		193 : 3,580,069	60 : 3,580,155
		3,579,895			64 : 3,580,156

PI 47

95-89 : 3,580,158	128-21 : 3,580,239	156-235 : 3,580,771	179-121 : 3,581,015	211-148 : 3,580,398	229-43 : 3,580,478
100 : 3,580,159	25 : 3,580,244	240 : 3,580,772	180-8 : 3,580,344	213-76 : 3,580,399	44 : 3,580,479
96-27 : 3,580,719	33 : 3,580,245	244 : 3,580,773	9.2 : 3,580,345	166 : 3,580,400	45 : 3,580,480
82 : 3,580,720	36 : 3,580,246	247 : 3,580,774	19 : 3,580,346	214-1 : 3,580,401	51 : 3,580,481
100 : 3,580,721	66 : 3,580,247	250 : 3,580,775	22 : 3,580,347	6 : 3,580,402	52 : 3,580,482
3,580,722	89 : 3,580,248	275 : 3,580,776	25 : 3,580,348	38 : 3,580,403	53 : 3,580,483
122 : 3,580,723	194 : 3,580,249	278 : 3,580,777	27 : 3,580,349	85 : 3,580,404	54 : 3,580,484
124 : 3,580,724	203 : 3,580,250	299 : 3,580,778	44 : 3,580,350	135 : 3,580,405	55 : 3,580,485
98-121 : 3,580,160	220 : 3,580,251	380 : 3,580,780	53 : 3,580,351	137 : 3,580,406	56 : 3,580,486
99-7 : 3,580,161	268 : 3,580,252	384 : 3,580,779	79.2 : 3,580,352	152 : 3,580,407	57 : 3,580,487
78 : 3,580,726	276 : 3,580,253	397 : 3,580,781	98 : 3,580,353	302 : 3,580,408	58 : 3,580,488
81 : 3,580,727	290 : 3,580,252	415 : 3,580,782	104 : 3,580,354	215-81 : 3,580,409	59 : 3,580,489
3,580,728	3,580,253	426 : 3,580,783	105 : 3,580,355	219-7.5 : 3,581,040	92.9 : 3,580,490
128 : 3,580,729	335.5 : 3,580,256	429 : 3,580,784	116 : 3,580,356	10.55 : 3,581,038	232-35 : 3,580,491
243 : 3,580,161	130-24 : 3,580,257	468 : 3,580,785	181-44 : 3,580,357	60 : 3,581,041	233-7 : 3,580,492
339 : 3,580,162	27 : 3,580,258	475 : 3,580,786	182-44 : 3,580,358	61 : 3,581,042	19 : 3,580,493
310 : 3,580,163	131-144 : 3,580,259	477 : 3,580,787	49 : 3,580,359	69 : 3,581,043	234-6 : 3,580,494
339 : 3,580,164	242 : 3,580,260	497 : 3,580,788	187-29 : 3,580,360	69 : 3,581,044	115 : 3,580,495
351 : 3,580,165	134-104 : 3,580,261	504 : 3,580,789	188-72.4 : 3,580,361	73 : 3,581,045	235-61.11 : 3,581,064
100-49 : 3,580,166	135-20 : 3,580,262	521 : 3,580,790	73.4 : 3,580,362	82 : 3,581,046	92 : 3,580,496
52 : 3,580,167	136-30 : 3,580,263	540 : 3,580,791	74 : 3,580,363	91 : 3,581,047	359 : 3,580,863
234 : 3,580,168	86 : 3,580,264	546 : 3,580,792	87 : 3,580,364	93 : 3,581,048	389 : 3,580,934
101-110 : 3,580,169	155 : 3,580,265	579 : 3,580,793	196 : 3,580,365	125 : 3,581,049	408 : 3,580,864
269 : 3,580,170	212 : 3,580,266	581 : 3,580,794	206 : 3,580,366	130 : 3,581,050	3,580,865
102-28 : 3,580,171	234 : 3,580,267	583 : 3,580,795	264 : 3,580,367	131 : 3,581,051	3,580,866
37.2 : 3,580,172	81.5 : 3,580,268	157-124 : 3,580,320	192-3 : 3,580,370	137 : 3,581,052	96 : 3,580,497
48 : 3,580,173	3,580,269	160-1 : 3,580,321	18 : 3,580,371	146 : 3,581,053	117 : 3,580,498
56 : 3,580,174	203 : 3,580,270	231 : 3,580,322	70.13 : 3,580,372	146 : 3,581,054	150.26 : 3,581,073
67 : 3,580,175	246.22 : 3,580,271	263 : 3,580,323	105 : 3,580,373	222 : 3,581,055	151.1 : 3,581,070
75 : 3,580,176	318 : 3,580,272	161-126 : 3,580,324	193-5 : 3,580,374	312 : 3,581,056	32 : 3,581,071
79 : 3,580,177	3,580,273	186 : 3,580,325	43 : 3,580,375	330 : 3,581,057	152 : 3,581,072
92.2 : 3,580,178	458 : 3,580,274	190 : 3,580,326	195-29 : 3,580,376	378 : 3,581,058	153 : 3,581,073
7 : 3,580,179	486 : 3,580,275	243 : 3,580,327	100 : 3,580,377	469 : 3,581,059	154 : 3,581,074
101 : 3,580,180	493 : 3,580,276	162-157 : 3,580,328	143 : 3,580,378	499 : 3,581,061	184 : 3,581,075
104-23 : 3,580,181	516.29 : 3,580,277	164-60 : 3,580,329	16 : 3,580,379	501 : 3,581,062	193 : 3,581,076
25 : 3,580,182	554 : 3,580,278	190 : 3,580,330	20 : 3,580,380	501 : 3,581,063	201 : 3,580,499
111 : 3,580,183	590 : 3,580,279	283 : 3,580,331	25 : 3,580,381	501 : 3,581,064	236-12 : 3,580,500
165 : 3,580,184	596.14 : 3,580,280	365 : 3,580,332	33 : 3,580,382	501 : 3,581,065	44 : 3,580,501
105-366 : 3,580,185	608 : 3,580,281	448 : 3,580,333	38 : 3,580,383	501 : 3,581,066	102 : 3,580,502
369 : 3,580,186	624.2 : 3,580,282	224 : 3,580,334	64 : 3,580,384	501 : 3,581,067	239-25 : 3,580,503
107-1 : 3,580,187	625.18 : 3,580,283	250 : 3,580,335	103 : 3,580,385	501 : 3,581,068	70 : 3,580,504
108-3 : 3,580,188	3,580,284	263 : 3,580,336	131 : 3,580,386	501 : 3,581,069	168 : 3,580,505
58 : 3,580,189	3,580,285	267 : 3,580,337	178 : 3,580,387	501 : 3,581,070	230 : 3,580,506
152 : 3,580,190	68 : 3,580,286	273 : 3,580,338	198 : 3,580,388	501 : 3,581,071	233 : 3,580,507
110-8 : 3,580,191	69 : 3,580,287	276 : 3,580,339	213 : 3,580,389	501 : 3,581,072	241 : 3,580,508
18 : 3,580,192	630.13 : 3,580,288	276 : 3,580,340	200-11 : 3,581,023	501 : 3,581,073	302 : 3,580,509
35 : 3,580,193	138-31 : 3,580,289	303 : 3,580,341	19 : 3,581,024	501 : 3,581,074	327 : 3,580,510
111-1 : 3,580,194	139-122 : 3,580,290	371 : 3,580,342	33 : 3,581,025	501 : 3,581,075	419.5 : 3,580,511
112-11 : 3,580,195	121 : 3,580,291	383 : 3,580,343	89 : 3,581,026	501 : 3,581,076	432 : 3,580,512
121.18 : 3,580,196	121 : 3,580,292	425 : 3,580,344	129.1 : 3,581,027	501 : 3,581,077	460 : 3,580,513
158 : 3,580,197	121 : 3,580,293	445 : 3,580,345	177 : 3,581,028	501 : 3,581,078	521 : 3,580,514
113-1 : 3,580,198	121 : 3,580,294	465 : 3,580,346	241 : 3,581,029	501 : 3,581,079	536 : 3,580,515
121 : 3,580,199	121 : 3,580,295	477 : 3,580,347	394 : 3,581,030	501 : 3,581,080	546 : 3,580,516
114-5 : 3,580,200	121 : 3,580,296	488 : 3,580,348	402.1 : 3,581,031	501 : 3,581,081	556 : 3,580,517
121 : 3,580,201	121 : 3,580,297	499 : 3,580,349	413 : 3,581,032	501 : 3,581,082	566 : 3,580,518
67 : 3,580,202	121 : 3,580,298	500 : 3,580,350	424 : 3,581,033	501 : 3,581,083	576 : 3,580,519
39 : 3,580,203	121 : 3,580,299	501 : 3,580,351	434 : 3,581,034	501 : 3,581,084	586 : 3,580,520
67 : 3,580,204	121 : 3,580,300	502 : 3,580,352	444 : 3,581,035	501 : 3,581,085	596 : 3,580,521
125 : 3,580,205	121 : 3,580,301	503 : 3,580,353	454 : 3,581,036	501 : 3,581,086	606 : 3,580,522
144 : 3,580,206	121 : 3,580,302	504 : 3,580,354	464 : 3,581,037	501 : 3,581,087	616 : 3,580,523
163 : 3,580,207	121 : 3,580,303	505 : 3,580,355	474 : 3,581,038	501 : 3,581,088	626 : 3,580,524
218 : 3,580,208	121 : 3,580,304	506 : 3,580,356	484 : 3,581,039	501 : 3,581,089	636 : 3,580,525
115-5 : 3,580,209	121 : 3,580,305	507 : 3,580,357	494 : 3,581,040	501 : 3,581,090	646 : 3,580,526
3,580,210	121 : 3,580,306	508 : 3,580,358	504 : 3,581,041	501 : 3,581,091	656 : 3,580,527
18 : 3,580,211	121 : 3,580,307	509 : 3,580,359	514 : 3,581,042	501 : 3,581,092	666 : 3,580,528
22.3 : 3,580,212	121 : 3,580,308	510 : 3,580,360	524 : 3,581,043	501 : 3,581,093	676 : 3,580,529
34 : 3,580,213	121 : 3,580,309	511 : 3,580,361	534 : 3,581,044	501 : 3,581,094	686 : 3,580,530
116-87 : 3,580,214	121 : 3,580,310	512 : 3,580,362	544 : 3,581,045	501 : 3,581,095	696 : 3,580,531
115.5 : 3,580,215	121 : 3,580,311	513 : 3,580,363	554 : 3,581,046	501 : 3,581,096	706 : 3,580,532
169 : 3,580,216	121 : 3,580,312	514 : 3,580,364	564 : 3,581,047	501 : 3,581,097	716 : 3,580,533
117-8 : 3,580,217	121 : 3,580,313	515 : 3,580,365	574 : 3,581,048	501 : 3,581,098	726 : 3,580,534
66 : 3,580,218	121 : 3,580,314	516 : 3,580,366	584 : 3,581,049	501 : 3,581,099	736 : 3,580,535
106 : 3,580,219	121 : 3,580,315	517 : 3,580,367	594 : 3,581,050	501 : 3,581,100	746 : 3,580,536
129 : 3,580,220	121 : 3,580,316	518 : 3,580,368	604 : 3,581,051	501 : 3,581,101	756 : 3,580,537
138.8 : 3,580,221	121 : 3,580,317	519 : 3,580,369	614 : 3,581,052	501 : 3,581,102	766 : 3,580,538
155 : 3,580,222	121 : 3,580,318	520 : 3,580,370	624 : 3,581,053	501 : 3,581,103	776 : 3,580,539
212 : 3,580,223	121 : 3,580,319	521 : 3,580,371	634 : 3,581,054	501 : 3,581,104	786 : 3,580,540
215 : 3,580,224	121 : 3,580,320	522 : 3,580,372	644 : 3,581,055	501 : 3,581,105	796 : 3,580,541
217 : 3,580,225	121 : 3,580,321	523 : 3,580,373	654 : 3,581,056	501 : 3,581,106	806 : 3,580,542
118-621 : 3,580,226	121 : 3,580,322	524 : 3,580,374	664 : 3,581,057	501 : 3,581,107	816 : 3,580,543
119-1 : 3,580,227	121 : 3,580,323	525 : 3,580,375	674 : 3,581,058	501 : 3,581,108	826 : 3,580,544
14.01 : 3,580,228	121 : 3,580,324	526 : 3,580,376	684 : 3,581,059	501 : 3,581,109	836 : 3,580,545
96 : 3,580,229	121 : 3,580,325	527 : 3,580,377	694 : 3,581,060	501 : 3,581,110	846 : 3,580,546
102 : 3,580,230	121 : 3,580,326	528 : 3,580,378	704 : 3,581,061	501 : 3,581,111	856 : 3,580,547
122-1 : 3,580,231	121 : 3,580,327	529 : 3,580,379	714 : 3,581,062	501 : 3,581,112	866 : 3,580,548
16 : 3,580,232	121 : 3,580,328	530 : 3,580,380	724 : 3,581,063	501 : 3,581,113	876 : 3,580,549
20 : 3,580,233	121 : 3,580,329	531 : 3,580,381	734 : 3,581,064	501 : 3,581,114	886 : 3,580,550
235 : 3,580,234	121 : 3,580,330	532 : 3,580,382	744 : 3,581,065	501 : 3,581,115	896 : 3,580,551
406 : 3,580,235	121 : 3,580,331	533 : 3,580,383	754 : 3,581,066	501 : 3,581,116	906 : 3,580,552
123-18 : 3,580,236	121 : 3,580,332	534 : 3,580,384	764 : 3,581,067	501 : 3,581,117	916 : 3,580,553
32 : 3,580,237	121 : 3,580,333	535 : 3,580,385	774 : 3,581,068	501 : 3,581,118	926 : 3,580,554
41.12 : 3,580,238	121 : 3,580,334	536 : 3,580,386	784 : 3,581,069	501 : 3,581,119	936 : 3,580,555
119 : 3,580,239	121 : 3,580,335	537 : 3,580,387	794 : 3,581,070	501 : 3,581,120	946 : 3,580,556
124-21 : 3,580,240	121 : 3,580,336	538 : 3,580,388	804 : 3,581,071	501 : 3,581,121	956 : 3,580,557
125-3 : 3,580,241	121 : 3,580,337	539 : 3,580,389	814 : 3,581,072	501 : 3,581,122	966 : 3,580,558
126-59.5 : 3,580,242	121 : 3,580,338	540 : 3,580,390	824 : 3,581,073	501 : 3,581,123	976 : 3,580,559
110 : 3,580,243	121 : 3,580,339	541 : 3,580,391	834 : 3,581,074	501 : 3,581,124	986 : 3,580,560
295 : 3,580,244	121 : 3,580,340	542 : 3,580,392	844 : 3,581,075	501 : 3,581,125	996 : 3,580,561
128-2.06 : 3,580,245	121 : 3,580,341	543 : 3,580,393	854 : 3,581,076	501 : 3,581,126	1006 : 3,580,562
3,580,246	121 : 3,580,342	544 : 3,580,394	864 : 3,581,077	501 : 3,581,127	1016 : 3,580,563
3,580,247	121 : 3,580,343	545 : 3,580,395	874 : 3,581,078	501 : 3,581,128	1026 : 3,580,564
3,580,248	121 : 3,580,344	546 : 3,580,396	884 : 3,581,0		

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

1 : 3,579,961	6 : 3,579,940	6 : 3,580,504	6 : 3,581,145	9 : 3,580,413	12 : 3,580,996
3,580,475	3,579,943	3,580,506	3,581,152	3,580,421	3,581,211
4 : 3,579,745	3,579,954	3,580,507	3,581,158	3,580,498	3,581,242
3,579,907	3,579,971	3,580,508	3,581,191	3,580,521	3,581,309
3,580,177	3,579,972	3,580,512	3,581,195	3,580,590	3,579,663
3,580,196	3,579,991	3,580,514	3,581,197	3,580,656	3,579,969
3,580,227	3,579,993	3,580,523	3,581,198	3,580,679	3,580,471
3,580,265	3,580,030	3,580,534	3,581,209	3,580,690	3,580,699
3,581,100	3,580,044	3,580,538	3,581,215	3,580,692	3,579,906
3,581,114	3,580,071	3,580,540	3,581,222	3,580,775	3,580,213
5 : 3,580,238	3,580,091	3,580,542	3,581,223	3,580,833	3,579,819
3,580,257	3,580,107	3,580,545	3,581,226	3,580,908	3,579,646
3,580,313	3,580,126	3,580,555	3,581,235	3,580,921	3,579,883
3,580,370	3,580,136	3,580,563	3,581,284	3,580,951	3,579,654
3,580,570	3,580,137	3,580,572	3,581,292	3,580,997	3,579,664
3,580,715	3,580,161	3,580,584	3,581,296	3,581,028	3,579,688
3,581,021	3,580,162	3,580,585	3,581,297	3,581,029	3,579,697
6 : 3,579,643	3,580,164	3,580,622	3,581,298	3,581,033	3,579,705
3,579,645	3,580,186	3,580,626	3,581,303	3,581,092	3,579,737
3,579,649	3,580,202	3,580,636	3,581,307	3,581,182	3,579,787
3,579,657	3,580,203	3,580,653	3,581,308	3,581,230	3,579,799
3,579,670	3,580,219	3,580,661	3,579,702	3,581,247	3,579,809
3,579,675	3,580,222	3,580,684	3,580,287	3,581,253	3,579,827
3,579,676	3,580,233	3,580,687	3,580,337	3,579,639	3,579,828
3,579,678	3,580,239	3,580,700	3,580,625	3,580,621	3,579,843
3,579,681	3,580,250	3,580,725	3,580,641	3,580,873	3,579,867
3,579,682	3,580,256	3,580,769	3,581,093	3,580,876	3,579,912
3,579,683	3,580,263	3,580,792	3,581,181	3,580,889	3,579,916
3,579,686	3,580,266	3,580,804	9 : 3,579,641	3,580,890	3,579,917
3,579,700	3,580,272	3,580,819	3,579,651	3,580,894	3,580,000
3,579,708	3,580,285	3,580,822	3,579,677	3,580,925	3,580,003
3,579,718	3,580,305	3,580,829	3,579,724	3,580,982	3,580,016
3,579,735	3,580,320	3,580,832	3,579,731	3,580,125	3,580,073
3,579,742	3,580,343	3,580,835	3,579,738	3,581,110	3,580,078
3,579,758	3,580,364	3,580,848	3,579,780	11 : 3,580,125	3,580,080
3,579,794	3,580,372	3,580,934	3,579,797	12 : Re.27,125	3,580,110
3,579,795	3,580,373	3,580,961	3,579,797	3,579,648	3,580,115
3,579,808	3,580,375	3,581,003	3,579,837	3,579,668	3,580,138
3,579,821	3,580,377	3,581,014	3,579,891	3,579,798	3,580,163
3,579,822	3,580,379	3,581,017	3,579,848	3,579,857	3,580,165
3,579,841	3,580,381	3,581,030	3,580,050	3,579,989	3,580,185
3,579,853	3,580,383	3,581,038	3,580,059	3,580,007	3,580,191
3,579,868	3,580,384	3,581,061	3,580,113	3,580,158	3,580,201
3,579,871	3,580,385	3,581,066	3,580,132	3,580,247	3,580,215
3,579,881	3,580,412	3,581,068	3,580,143	3,580,261	3,580,270
3,579,899	3,580,425	3,581,089	3,580,166	3,580,310	3,580,276
3,579,901	3,580,456	3,581,105	3,580,193	3,580,311	3,580,340
3,579,902	3,580,462	3,581,107	3,580,210	3,580,359	3,580,346
3,579,935	3,580,478	3,581,124	3,580,226	3,580,569	3,580,354
	3,580,484	3,581,140	3,580,273	3,580,686	
			3,580,324	3,580,786	

17 : 3,580,407	21 : 3,580,644	26 : 3,580,043	29 : 3,579,712	36 : 3,579,655	36 : 3,581,234
3,580,414	3,581,026	3,580,055	3,579,845	3,579,656	3,581,257
3,580,419	22 : 3,579,854	3,580,056	3,579,874	3,579,667	3,581,280
3,580,424	3,579,959	3,580,067	3,579,966	3,579,669	3,581,281
3,580,431	3,580,279	3,580,068	3,580,047	3,579,716	3,581,282
3,580,466	3,580,334	3,580,085	3,580,321	3,579,730	3,581,286
3,580,476	3,580,760	3,580,103	3,580,339	3,579,766	3,581,290
3,580,480	3,580,852	3,580,116	3,580,362	3,579,768	
3,580,488	3,581,027	3,580,123	3,580,481	3,579,775	37 : 3,579,714
3,580,494	23 : 3,580,208	3,580,128	3,580,483	3,579,779	3,579,760
3,580,497	24 : 3,579,644	3,580,131	3,580,505	3,579,814	3,579,792
3,580,502	3,579,810	3,580,172	3,580,518	3,579,815	3,580,075
3,580,533	3,579,823	3,580,209	3,580,582	3,579,831	3,580,244
3,580,565	3,579,860	3,580,232	3,580,589	3,579,856	3,580,296
3,580,594	3,579,865	3,580,236	3,580,870	3,579,863	3,580,763
3,580,595	3,579,872	3,580,242	3,580,882	3,579,869	3,580,906
3,580,598	3,579,911	3,580,267	3,581,063	3,579,870	3,581,108
3,580,677	3,580,051	3,580,277	3,581,190	3,579,878	3,581,261
3,580,726	3,580,063	3,580,283	3,579,938	3,579,886	3,579,699
3,580,736	3,580,084	3,580,316	3,579,661	3,579,904	3,579,713
3,580,759	3,580,124	3,580,328	3,580,638	3,579,909	3,579,715
3,580,767	3,580,183	3,580,331	3,581,264	3,579,918	3,579,741
3,580,785	3,580,378	3,580,347	3,580,581	3,579,950	3,579,746
3,580,814	3,580,382	3,580,350	3,579,652	3,579,962	3,579,786
3,580,837	3,580,408	3,580,352	3,579,726	3,579,964	3,579,802
3,580,863	3,580,422	3,580,353	3,579,930	3,579,980	3,579,805
3,580,922	3,580,427	3,580,357	3,580,281	3,579,999	3,579,807
3,580,956	3,580,499	3,580,368	3,580,297	3,580,005	3,579,812
3,580,957	3,580,556	3,580,369	3,580,869	3,580,013	3,579,834
3,580,986	3,580,733	3,580,402	3,581,064	3,580,024	3,579,835
3,580,988	3,580,806	3,580,457	3,581,287	3,580,028	3,579,851
3,580,989	3,581,071	3,580,459	3,579,764	3,580,042	3,579,879
3,581,001	3,581,095	3,580,467	3,579,817	3,580,052	3,579,908
3,581,004	25 : 3,579,640	3,580,468	3,579,838	3,580,081	3,579,919
3,581,005	3,579,662	3,580,503	3,579,842	3,580,083	3,579,948
3,581,020	3,579,674	3,580,558	3,579,864	3,580,086	3,579,990
3,581,023	3,579,684	3,580,602	3,579,897	3,580,088	3,580,021
3,581,024	3,579,690	3,580,603	3,579,951	3,580,099	3,580,022
3,581,041	3,579,693	3,580,609	3,579,994	3,580,114	3,580,079
3,581,046	3,579,694	3,580,623	3,580,031	3,580,148	3,580,095
3,581,048	3,579,770	3,580,627	3,580,064	3,580,157	3,580,167
3,581,067	3,579,800	3,580,628	3,580,066	3,580,170	3,580,169
3,581,072	3,579,816	3,580,635	3,580,077	3,580,189	3,580,175
3,581,081	3,579,858	3,580,655	3,580,092	3,580,192	3,580,178
3,581,135	3,579,877	3,580,707	3,580,094	3,580,241	3,580,190
3,581,154	3,579,922	3,580,712	3,580,097	3,580,255	3,580,194
3,581,157	3,579,925	3,580,716	3,580,106	3,580,269	3,580,264
3,581,169	3,579,927	3,580,762	3,580,111	3,580,274	3,580,268
3,581,186	3,579,944	3,580,779	3,580,207	3,580,302	3,580,309
3,581,203	3,579,992	3,580,831	3,580,240	3,580,312	3,580,336
3,581,218	3,579,995	3,580,847	3,580,360	3,580,390	3,580,365
3,581,239	3,580,058	3,580,904	3,580,363	3,580,391	3,580,366
3,581,240	3,580,074	3,580,920	3,580,386	3,580,394	3,580,376
3,581,248	3,580,082	3,580,926	3,580,436	3,580,401	3,580,387
3,581,272	3,580,134	3,580,935	3,580,472	3,580,452	3,580,395
18 : 3,579,788	3,580,145	3,580,937	3,580,473	3,580,453	3,580,399
3,579,791	3,580,150	3,580,948	3,580,479	3,580,460	3,580,400
3,579,818	3,580,280	3,580,971	3,580,571	3,580,474	3,580,423
3,579,819	3,580,298	3,581,031	3,580,577	3,580,477	3,580,439
3,579,873	3,580,301	3,581,047	3,580,650	3,580,486	3,580,464
3,579,883	3,580,303	3,581,141	3,580,654	3,580,489	3,580,491
3,580,001	3,580,322	3,581,178	3,580,731	3,580,490	3,580,515
3,580,002	3,580,442	3,581,231	3,580,768	3,580,500	3,580,574
3,580,108	3,580,449	3,581,259	3,580,780	3,580,510	3,580,588
3,580,122	3,580,536	3,581,276	3,580,802	3,580,547	3,580,601
3,580,286	3,580,564	27 : 3,579,673	3,580,825	3,580,568	3,580,606
3,580,388	3,580,600	3,579,706	3,580,861	3,580,575	3,580,611
3,580,409	3,580,632	3,579,771	3,580,867	3,580,580	3,580,646
3,580,520	3,580,665	3,579,796	3,580,875	3,580,583	3,580,676
3,580,593	3,580,710	3,579,885	3,580,881	3,580,614	3,580,680
3,580,642	3,580,714	3,579,946	3,580,896	3,580,616	3,580,729
3,580,711	3,580,737	3,579,958	3,580,898	3,580,618	3,580,744
3,580,783	3,580,741	3,580,008	3,580,909	3,580,631	3,580,787
3,580,793	3,580,794	3,580,017	3,580,913	3,580,634	3,580,791
3,580,811	3,580,972	3,580,087	3,580,928	3,580,648	3,580,799
3,580,916	3,580,974	3,580,139	3,580,936	3,580,657	3,580,830
3,580,929	3,580,975	3,580,234	3,580,938	3,580,660	3,580,843
3,580,943	3,581,035	3,580,248	3,580,950	3,580,669	3,580,853
3,581,040	3,581,087	3,580,304	3,580,973	3,580,670	3,580,854
3,581,150	3,581,117	3,580,345	3,580,981	3,580,671	3,580,856
3,581,270	3,581,122	3,580,416	3,580,995	3,580,673	3,580,860
3,581,278	3,581,142	3,580,469	3,581,002	3,580,683	3,580,862
3,581,300	3,581,153	3,580,501	3,581,019	3,580,732	3,580,864
19 : Re.27,126	3,581,243	3,580,548	3,581,032	3,580,812	3,580,884
3,579,963	3,581,273	3,580,553	3,581,042	3,580,824	3,580,897
3,580,061	3,581,285	3,580,604	3,581,053	3,580,828	3,580,940
3,580,100	3,581,306	3,580,647	3,581,078	3,580,857	3,580,953
3,580,130	26 : 3,579,696	3,580,651	3,581,111	3,580,858	3,580,954
3,580,197	3,579,698	3,580,727	3,581,120	3,580,911	3,580,980
3,580,258	3,579,723	3,580,728	3,581,134	3,580,919	3,580,993
3,580,288	3,579,733	3,580,771	3,581,139	3,580,955	3,580,998
3,580,440	3,579,774	3,580,795	3,581,151	3,580,978	3,581,057
3,580,549	3,579,777	3,580,840	3,581,162	3,580,983	3,581,082
3,580,561	3,579,783	3,580,841	3,581,184	3,580,999	3,581,090
3,580,599	3,579,793	3,580,855	3,581,187	3,581,000	3,581,125
20 : 3,579,923	3,579,832	3,580,887	3,581,207	3,581,058	3,581,136
3,579,996	3,579,894	3,580,927	3,581,213	3,581,094	3,581,174
3,580,415	3,579,910	3,581,076	3,581,228	3,581,130	3,581,177
3,580,836	3,579,928	3,581,088	3,581,244	3,581,144	3,581,196
3,580,944	3,579,934	3,581,119	3,581,269	3,581,200	3,581,199
3,581,037	3,579,981	3,581,227	3,581,279	3,581,208	3,581,277
3,581,083	3,579,984	3,581,275	3,581,304	3,581,212	3,581,283
21 : 3,579,784	3,580,009	28 : 3,579,660	3,579,689	3,581,219	3,581,289
3,579,880	3,580,027	3,579,672	3,580,591	3,581,220	3,581,302
3,580,317	3,580,029	3,580,212	3,581,146	3,581,224	3,579,828
3,580,513	3,580,037	3,580,341	3,581,295	3,581,229	

40 : 3,579,866	42 : 3,580,046	42 : 3,580,813	47 : 3,580,705	48 : 3,581,305	53 : 3,579,932
3,580,245	3,580,072	3,580,815	3,580,784	49 : 3,579,638	3,580,010
3,580,338	3,580,151	3,580,816	3,580,842	3,580,057	3,580,140
3,580,420	3,580,160	3,580,817	48 : 3,579,717	3,580,397	3,580,171
3,580,429	3,580,220	3,580,850	3,579,752	3,581,011	3,580,206
3,580,448	3,580,225	3,580,865	3,579,753	3,581,214	3,580,254
3,580,586	3,580,275	3,580,886	3,579,840	50 : 3,580,070	3,580,349
3,580,612	3,580,289	3,580,893	3,579,847	3,580,482	3,580,543
3,580,697	3,580,329	3,580,901	3,579,903	51 : 3,579,665	3,580,613
3,580,761	3,580,371	3,580,915	3,579,905	3,579,900	3,580,872
3,580,826	3,580,403	3,580,964	3,579,939	3,579,915	3,581,069
3,580,967	3,580,410	3,580,970	3,579,970	3,579,957	3,580,730
3,580,969	3,580,441	3,580,977	3,580,045	3,580,069	55 : 3,579,647
3,581,179	3,580,495	3,581,049	3,580,049	3,580,176	3,579,710
41 : 3,579,749	3,580,516	3,581,073	3,580,221	3,580,200	3,579,949
3,579,844	3,580,532	3,581,074	3,580,246	3,580,380	3,580,065
3,580,101	3,580,539	3,581,137	3,580,260	3,580,428	3,580,102
3,580,342	3,580,557	3,581,160	3,580,278	3,580,470	3,580,105
3,580,404	3,580,573	3,581,163	3,580,282	3,580,605	3,580,127
3,580,517	3,580,576	3,581,167	3,580,332	3,580,666	3,580,135
3,580,658	3,580,578	3,581,250	3,580,333	3,580,688	3,580,142
3,580,778	3,580,592	3,581,268	3,580,335	3,580,801	3,580,144
42 : 3,579,637	3,580,610	3,581,293	3,580,344	3,580,874	3,580,187
3,579,709	3,580,619	3,581,294	3,580,411	3,580,885	3,580,188
3,579,729	3,580,630	43 : 3,580,823	3,580,432	3,580,891	3,580,243
3,579,732	3,580,639	44 : 3,580,120	3,580,509	3,580,962	3,580,253
3,579,743	3,580,678	3,580,374	3,580,550	3,581,006	3,580,351
3,579,748	3,580,691	3,580,706	3,580,633	3,581,098	3,580,367
3,579,778	3,580,702	45 : 3,579,679	3,580,667	3,581,123	3,580,405
3,579,790	3,580,740	3,579,761	3,580,765	3,581,173	3,580,615
3,579,829	3,580,748	3,579,965	3,580,770	3,581,221	3,580,797
3,579,839	3,580,749	3,580,198	3,580,838	3,581,249	3,580,834
3,579,893	3,580,750	3,580,300	3,581,052	3,581,267	3,581,036
3,579,914	3,580,751	3,581,159	3,581,077	52 : 3,579,862	3,581,104
3,579,929	3,580,752	46 : 3,581,254	3,581,106	53 : 3,579,701	3,581,143
3,579,931	3,580,753	3,581,255	3,581,161	3,579,801	3,581,170
3,579,937	3,580,754	47 : 3,579,892	3,581,204	3,579,825	3,581,266
3,579,942	3,580,755	3,579,941	3,581,210	3,579,861	3,581,299
3,579,947	3,580,777	3,580,060	3,581,216	3,579,890	58 : 3,580,159
3,580,023	3,580,781	3,580,445	3,581,217	3,579,895	3,580,528
3,580,032	3,580,796	3,580,524	3,581,274	3,579,921	

Design Patents

6 : 220,803	8 : 220,793	34 : 220,799	36 : 220,813	36 : 220,824	42 : 220,815
220,806	9 : 220,816	220,805	220,814	220,825	47 : 220,804
220,817	17 : 220,818	36 : 220,792	220,819	37 : 220,827	53 : 220,810
220,823	26 : 220,808	220,795	220,821	39 : 220,809	55 : 220,822
220,826		220,811			


**U. S.
OFFICIAL GAZETTE
UNITED STATES
PATENT OFFICE**

VOL 886

MAY

1971

MICRO PHOTO DIVISION



BELL & HOWELL

J